This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

+ *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.

+ *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.

+ *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.

+ *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at `http://books.google.com/`

LANE MEDICAL LIBRARY STANFORD
F34 .L25a 1889 STOR
Textbook of human physiology --
24503384628



LANE

MEDICAL LIBRARY

LEVI COOPER LANE FUND



LANE

MEDICAL LIBRARY

LEVI COOPER LANE FUND

A TEXT-BOOK

OF

HUMAN PHYSIOLOGY.

STANDARD MEDICAL WORKS.

ANDERSON (Prof. T. McCall). A Treatise on Diseases of the Skin; with Special Reference to Diagnosis and Treatment. With several full-page Plates, two of which are colored, and numerous Wood Engravings. Octavo.
Cloth, $4.50; Leather, $5.50.

BYFORD (Prof. W. H.). The Diseases of Women. Fourth Edition. Revised and rewritten. With 306 Illustrations, over 100 of which are original with this work. Octavo. Cloth, $5.00; Leather, $6.00.

CAZEAUX AND TARNIER'S Midwifery, with Appendix by PAUL F. MUNDÉ. Eighth American, from the Eighth French and First Italian Editions. Elegantly Illustrated with seven beautifully colored and five other full-page Plates, and many Wood Engravings. Octavo. *Students' Edition.*
Cloth, $5.00; Leather, $6.00.

FAGGE (Chas. Hilton, M. D.). The Principles and Practice of Medicine. Edited by P. H. PYE-SMITH, M. D. Including a Section on Skin Diseases by the Editor, and a Chapter on Cardiac Diseases by SAMUEL WILKES, M. D. 2 Vols. Octavo. Cloth, $8.00; Leather, $10.00; Half Russia, $12.00.

GOWERS (Prof. Wm. R.). Manual of Diseases of the Nervous System. A Complete Text-book. 341 Illustrations. Octavo.
Cloth, $6.50; Leather, $7.50.

HOLDEN (Luther, F.R.C.S.). A Manual of Anatomy. Fifth Edition. Carefully revised and enlarged. 208 Illustrations. Octavo.
Oilcloth, $4.50; Cloth, $5.00; Leather, $6.00.

JACOBSON (W. H. A., F.R.C.S.). The Operations of Surgery. A Systematic Handbook for Practitioners, Students and Hospital Surgeons. 199 Illustrations (describing over 230 operations as performed at Guy's Hospital, London). Octavo. 1000 pages. Cloth, $5.00; Leather, $6.00.

MEYER (Dr. Edouard). A Manual of Diseases of the Eye. Translated from the Third Edition by A. FREEDLAND FERGUS, M. B. (Glasgow). 270 Illustrations and two Colored Plates (by LIEBREICH). Octavo.
Cloth, $4.50; Leather, $5.50.

ROBERTS (Prof. Fred.). The Theory and Practice of Medicine. Seventh Edition. Thoroughly revised and Enlarged. Illustrated. Octavo.
Cloth, $5.50; Leather, $6.50.

WINCKEL (Prof. F.). Text-book on Midwifery, including the Diseases of Childbed. Authorized Translation by J. CLIFTON EDGAR, M. D., Lecturer on Obstetrics, University Medical College, New York. With 190 Illustrations, the majority of which are original with this work. Octavo. *Nearly Ready.*

*** These books may be obtained through any bookseller, or upon receipt of the price any book will be sent, postage prepaid. Complete Catalogues upon application.

P. BLAKISTON, SON & CO., Medical Publishers and Booksellers,
1012 WALNUT STREET, PHILADELPHIA.

A TEXT-BOOK

OF

HUMAN PHYSIOLOGY

INCLUDING

HISTOLOGY AND MICROSCOPICAL ANATOMY;

WITH

SPECIAL REFERENCE TO THE REQUIREMENTS OF

PRACTICAL MEDICINE.

BY

DR. L. LANDOIS,

PROFESSOR OF PHYSIOLOGY AND DIRECTOR OF THE PHYSIOLOGICAL INSTITUTE, UNIVERSITY OF GREIFSWALD.

THIRD AMERICAN,

TRANSLATED FROM THE SIXTH GERMAN EDITION.

WITH ADDITIONS BY

WILLIAM STIRLING, M.D., Sc.D.,

BRACKENBURY PROFESSOR OF PHYSIOLOGY AND HISTOLOGY IN THE OWENS COLLEGE, AND PROFESSOR IN THE VICTORIA UNIVERSITY, MANCHESTER; EXAMINER IN PHYSIOLOGY, UNIVERSITY OF OXFORD.

WITH SIX HUNDRED AND NINETY-TWO ILLUSTRATIONS.

PHILADELPHIA:

P. BLAKISTON, SON & CO.,

1012 WALNUT STREET.

1889.

[*All Rights Reserved.*]

PRESS OF WM. F. FELL & CO.,
1220-24 SANSOM ST.,
PHILADELPHIA.

LANE LIBRARY

L25s
1889

TO

SIR JOSEPH LISTER, BARONET,

M.D., D.C.L., LL.D., F.R.SS. (LOND. AND EDIN.),

PROFESSOR OF CLINICAL SURGERY IN KING'S COLLEGE, LONDON, SURGEON-EXTRAORDINARY TO THE QUEEN;

FORMERLY REGIUS PROFESSOR OF CLINICAL SURGERY IN THE UNIVERSITY OF EDINBURGH,

IN ADMIRATION OF

The Man of Science,

WHOSE BRILLIANT DISCOVERIES HAVE REVOLUTIONIZED

MEDICAL PRACTICE, AND CONTRIBUTED INCALCULABLY TO THE

WELL-BEING OF MANKIND;

AND IN GRATITUDE TO

The Teacher,

WHOSE NOBLE EARNESTNESS IN INCULCATING

THE SACREDNESS OF HUMAN LIFE

STIRRED THE HEARTS OF ALL WHO HEARD HIM:

This Work is respectfully Dedicated

BY HIS FORMER PUPIL,

THE TRANSLATOR.

54790

PREFATORY NOTE TO THE THIRD EDITION.

In offering to the Profession this Third English Edition, I would only say that the whole work has again been thoroughly revised and in many parts extended. In all respects I have endeavored to keep it abreast of the latest investigations in Physiology and their bearing on Practical Medicine and Surgery.

I have again to thank my publishers for enabling me to enhance the usefulness of the work by very numerous additions to the Illustrations, which now number 692 as compared with the 494 of the First Edition. Many of these new engravings are original; others are derived from the Sixth German Edition of the work, from Stöhr's *Lehrbuch der Histologie*, Quain's *Anatomy*, Ferrier's *Functions of the Brain* (Second Edition), H. Obersteiner's *Anleitung beim Studium des Baues der nervösen Centralorgane*, Rollett's Article on "Muscle" in the *Real-Encyclopædie*, Gowers' *Diseases of the Nervous System*, and most of those for the chapter on Reproduction from Haddon's *Introduction to Embryology*.

In addition, I have to tender special acknowledgments to my colleagues and friends, Professors A. H. Young, James Ross, A. W. Hare and Dr. Aug. D. Waller; as well as to Messrs. Carl Reichert, of Vienna; W. Petzold, of Leipzic; Rothe, of Prague; Maw, Cassella, Krohne and Sesemann, Evans & Wormall, of London, and Ferries & Co., of Bristol.

For the first time the work appears here in one volume—an arrangement adopted both to meet the wishes of Students and to facilitate easy reference. I can but express a hope that the present Edition, in its new form, will meet with the same very kind reception accorded to its predecessors.

WILLIAM STIRLING.

The Owens College,
Manchester.

PREFACE TO THE FIRST EDITION.

THE fact that Professor LANDOIS' "*Lehrbuch der Physiologie des Menschen*" has already passed through four large Editions since its first appearance in 1880, shows that in some special way it has met the wants of Students and Practitioners in Germany. The characteristic which has thus commended the work will be found mainly to lie in its eminent *practicality;* and it is this consideration which has induced me to undertake the task of putting it into an English dress for English readers.

Landois' work, in fact, forms a *Bridge* between Physiology and the Practice of Medicine. It never loses sight of the fact that the Student of to-day is the practicing Physician of to-morrow. Thus, to every Section is appended—after a full description of the normal processes—a short *résumé* of the pathological variations, the object of this being to direct the attention of the Student, from the outset, to the field of his future practice, and to show him to what extent pathological processes are a disturbance of the normal activities.

In the same way, the work offers to the busy physician in practice a ready means of refreshing his memory on the theoretical aspects of Medicine. He can pass *backward* from the examination of pathological phenomena to the normal processes, and, in the study of these, find new indications and new lights for the appreciation and treatment of the cases under consideration.

With this object in view, all the methods of investigation which may with advantage be used by the Practitioner, are carefully and fully described; and Histology, also, occupies a larger place than is usually assigned to it in Text-books of Physiology.

A word as to my own share in the present version:—

(1) In the task of translating, I have endeavored throughout to convey the author's meaning accurately, without a too rigid adherence to the original. Those who from experience know something of the difficulties of such an undertaking will be most ready to pardon any shortcomings they may detect.

(2) Very considerable additions have been made to the Histological, and also (where it has seemed necessary) to the Physiological sections. All such additions are enclosed within square brackets [ ]. I have to acknowledge my indebtedness to many valuable Papers in the various Medical Journals—British

and Foreign—and also to the Histological Treatises of Cadiat, Ranvier, and Klein; Quain's *Anatomy*, Vol. II, Ninth Edition; Hermann's *Handbuch der Physiologie;* and the Text-books on Physiology, by Rutherford, Foster, and Kirkes; Gamgee's *Physiological Chemistry;* Ewald's *Digestion;* and Roberts' *Digestive Ferments.*

(3) The Illustrations have been greatly increased in number, viz., from 275 in the Fourth German Edition to 494 in the English version. These additional Diagrams, with the sources whence derived, are distinguished in the List of Woodcuts by an asterisk.

There only remains for me now to express my thanks to all who have kindly helped in the progress of the work, either by furnishing Illustrations or otherwise —especially to Drs. Byrom Bramwell, Dudgeon, Lauder Brunton, and Knott; Mr. Hawksley; Professors Hamilton and McKendrick; to my esteemed teacher and friend, Professor Ludwig, of Leipzic; and, finally, to my friend, Mr. A. W. Robertson, M.A., formerly Assistant Librarian in the University, and now Librarian of the Aberdeen Public Library, for much valuable assistance while the work was passing through the press.

In conclusion—and forgetting for the moment my own connection with it—I heartily commend the work *per se* to the attention of Medical men, and can wish for it no better fate than that it may speedily become as popular in this country as it is in its Fatherland.

WILLIAM STIRLING.

ABERDEEN UNIVERSITY.

GENERAL CONTENTS.

INTRODUCTION.

PAGE

The Scope of Physiology and its Relations to other Branches of Natural Science, ... 33
Matter, ... 34
Forces, ... 35
Law of the Conservation of Energy, ... 38
Animals and Plants, ... 39
Vital Energy and Life, ... 41

I. PHYSIOLOGY OF THE BLOOD.

SECTION

1. Physical Properties of the Blood, ... 42
2. Microscopic Examination of the Blood, ... 44
3. Histology of the Human Red Blood Corpuscles, ... 46
4. Effects of Reagents on the Blood Corpuscles, ... 47
5. Preparation of the Stroma—Making Blood "Lake Colored," 49
6. Form and Size of the Blood Corpuscles of Different Animals, ... 50
7. Origin of the Red Blood Corpuscles, ... 51
8. Decay of the Red Blood Corpuscles, ... 53
9. The Colorless Corpuscles—Leucocytes—Blood Plates—Granules, ... 53
10. Abnormal Changes of the Blood Corpuscles, ... 58
11. Chemical Constituents of the Red Blood Corpuscles, ... 59
12. Preparation of Hæmoglobin Crystals, ... 59
13. Quantitative Estimation of Hæmoglobin, ... 60
14. Use of Spectroscope, ... 61
15. Compounds of Hæmoglobin—Methæmoglobin, ... 62
16. Carbonic Oxide Hæmoglobin—Poisoning with Carbonic Oxide, ... 65
17. Other Compounds of Hæmoglobin, ... 66
18. Decomposition of Hæmoglobin, ... 66
19. Hæmin and Blood Tests, ... 67
20. Hæmatoidin, ... 68
21. The Colorless Proteid of Hæmoglobin, ... 68
22. Proteids of the Stroma, ... 69
23. The other Constituents of Red Blood Corpuscles, ... 69
24. Chemical Composition of the Colorless Corpuscles, ... 69
25. Blood Plasma, and its Relation to Serum, ... 70
26. Preparation of Plasma, ... 70
27. Fibrin—Coagulation of the Blood, ... 71
28. General Phenomena of Coagulation, ... 72
29. Cause of Coagulation of the Blood, ... 74
30. Source of the Fibrin Factors, ... 77
31. Relation of the Red Blood Corpuscles to the Formation of Fibrin, ... 77
32. Chemical Composition of the Plasma and Serum, ... 78
33. The Gases of the Blood, ... 80
34. Extraction of the Blood Gases, ... 81
35. Quantitative Estimation of the Blood Gases, ... 82
36. The Blood Gases, ... 83
37. Is Ozone (O_3) present in Blood? 84
38. Carbon dioxide and Nitrogen in Blood, ... 85
39. Arterial and Venous Blood, ... 86
40. Quantity of Blood, ... 86
41. Variations from the Normal Conditions of the Blood, ... 87

II. PHYSIOLOGY OF THE CIRCULATION.

SECTION		PAGE
42.	General View of the Circulation,	91
43.	The Heart,	92
44.	Arrangement of the Cardiac Muscular Fibres,	92
45.	Arrangement of the Ventricular Fibres,	94
46.	Pericardium, Endocardium, Valves,	95
47.	Automatic Regulation of the Heart,	96
48.	The Movements of the Heart,	98
49.	Pathological Disturbances of Cardiac Action,	101
50.	The Apex Beat—The Cardiogram,	102
51.	The Time Occupied by the Cardiac Movements,	107
52.	Pathological Disturbance of the Cardiac Impulse,	110
53.	The Heart Sounds,	112
54.	Variations of the Heart Sounds,	114
55.	The Duration of the Movements of the Heart,	116
56.	Physical Examination of the Heart,	117
57.	Innervation of Heart—Cardiac Nerves,	117
58.	The Automatic Motor Centres of the Heart,	119
59.	The Cardio-pneumatic Movements,	128
60.	Influence of the Respiratory Pressure on the Heart,	129

THE CIRCULATION.

61.	The Flow of Fluids through Tubes,	132
62.	Propelling Force, Velocity of Current, Lateral Pressure,	132
63.	Currents through Capillary Tubes,	134
64.	Movements of Fluids and Wave Motion in Elastic Tubes,	134
65.	Structure and Properties of the Blood Vessels,	134
66.	Investigation of the Pulse,	139
67.	Pulse Tracing, or Sphygmogram,	144
68.	Origin of the Dicrotic Wave,	145
69.	Dicrotic Pulse,	148
70.	Characters of the Pulse,	149
71.	Variations in the Strength, Tension, and Volume of the Pulse,	150
72.	The Pulse Curves of various Arteries,	151
73.	Anacrotism,	151
74.	Influence of the Respiratory Movements on the Pulse Curve,	153
75.	Influence of Pressure upon the Form of the Pulse Wave,	155
76.	Rapidity of Transmission of Pulse Waves,	156
77.	Propagation of the Pulse Wave in Elastic Tubes,	156
78.	Velocity of the Pulse Wave in Man,	156
79.	Other Pulsatile Phenomena,	157
80.	Vibrations communicated to the Body by the Action of the Heart,	158
81.	The Blood Current,	159
82.	Schemata of the Circulation,	161
83.	Capacity of the Ventricles,	161
84.	Estimation of the Blood Pressure,	161
85.	Blood Pressure in the Arteries,	165
86.	Blood Pressure in the Capillaries,	171
87.	Blood Pressure in the Veins,	171
88.	Blood Pressure in the Pulmonary Artery,	173
89.	Measurement of the Velocity of the Blood Stream,	175
90.	Velocity of the Blood in Arteries, Capillaries, and Veins,	177
91.	Estimation of the Capacity of the Ventricles,	179
92.	The Duration of the Circulation,	179
93.	Work of the Heart,	180
94.	Blood Current in the Smallest Vessels,	180
95.	Passage of the Blood Corpuscles out of the Vessels [Diapedesis],	182
96.	Movement of the Blood in the Veins,	183
97.	Sounds or Bruits within Arteries,	184
98.	Venous Murmurs,	185
99.	The Venous Pulse—Phlebogram,	185
100.	Distribution of the Blood,	187
101.	Plethysmography,	187
102.	Transfusion of Blood,	189

THE BLOOD GLANDS.

SECTION PAGE
103. The Spleen—Thymus—Thyroid—Suprarenal Capsules—Hypophysis Cerebri—Coccygeal and Carotid Glands, ... 192
104. Comparative, ... 201
105. Historical Retrospect, ... 202

III. PHYSIOLOGY OF RESPIRATION.

106. Structure of the Air Passages and Lungs, ... 203
107. Mechanism of Respiration, ... 209
108. Quantity of Gases Respired, ... 210
109. Number of Respirations, ... 211
110. Time occupied by the Respiratory Movements, ... 212
111. Pathological Variations of the Respiratory Movements, ... 215
112. General View of the Respiratory Muscles, ... 216
113. Action of the Individual Respiratory Muscles, ... 217
114. Relative Size of the Chest, ... 220
115. Pathological Variations of the Percussion Sounds, ... 222
116. The Normal Respiratory Sounds, ... 223
117. Pathological Respiratory Sounds, ... 224
118. Pressure in the Air Passages during Respiration, ... 225
119. Appendix to Respiration, ... 226
120. Peculiarly Modified Respiratory Sounds, ... 226
121. Quantitative Estimation of CO_2, O, and Watery Vapor, ... 227
122. Methods of Investigation, ... 228
123. Composition and Properties of Atmospheric Air, ... 230
124. Composition of Expired Air, ... 231
125. Daily Quantity of Gases Exchanged, ... 232
126. Review of the Daily Gaseous Income and Expenditure, ... 232
127. Conditions Influencing the Gaseous Exchanges, ... 232
128. Diffusion of Gases within the Lungs, ... 234
129. Exchange of Gases between the Blood and Air, ... 235
130. Dissociation of Gases, ... 237
131. Cutaneous Respiration, ... 238
132. Internal Respiration, ... 238
133. Respiration in a Closed Space, ... 240
134. Dyspnœa and Asphyxia, ... 241
135. Respiration of Foreign Gases, ... 244
136. Accidental Impurities of the Air, ... 244
137. Ventilation of Rooms, ... 245
138. Formation of Mucus, ... 245
139. Action of the Atmospheric Pressure, ... 247
140. Comparative and Historical, ... 249

IV. PHYSIOLOGY OF DIGESTION.

141. The Mouth and its Glands, ... 250
142. The Salivary Glands, ... 252
143. Histological Changes in Salivary Glands, ... 253
144. The Nerves of the Salivary Glands, ... 255
145. Action of Nerves on the Salivary Secretion, ... 256
146. The Saliva of the Individual Glands, ... 260
147. The Mixed Saliva in the Mouth, ... 261
148. Physiological Action of Saliva, ... 262
149. Tests for Sugar, ... 264
150. Quantitative Estimation of Sugar, ... 265
151. Mechanism of the Digestive Apparatus, ... 266
152. Introduction of the Food, ... 267
153. The Movements of Mastication, ... 267
154. Structure and Development of the Teeth, ... 268
155. Movements of the Tongue, ... 271
156. Deglutition, ... 272
157. Movements of the Stomach, ... 275
158. Vomiting, ... 276
159. Movements of the Intestine, ... 277

SECTION PAGE
160. Excretion of Fecal Matter, . . . 278
161. Conditions influencing the Movements of the Intestine, . . . 280
162. Structure of the Stomach, . . . 284
163. The Gastric Juice, . . . 287
164. Secretion of Gastric Juice, . . . 288
165. Methods of obtaining Gastric Juice, . . . 291
166. Process of Gastric Digestion, . . . 292
167. Gases in the Stomach, . . . 297
168. Structure of the Pancreas, . . . 297
169. The Pancreatic Juice, . . . 298
170. Digestive Action of the Pancreatic Juice, . . . 299
171. The Secretion of the Pancreatic Juice, . . . 302
172. Preparation of Peptonized Food, . . . 303
173. Structure of the Liver, . . . 303
174. Chemical Composition of the Liver Cells, . . . 307
175. Diabetes Mellitus, or Glycosuria, . . . 310
176. The Functions of the Liver, . . . 311
177. Constituents of the Bile, . . . 312
178. Secretion of Bile, . . . 315
179. Excretion of Bile, . . . 316
180. Reabsorption of Bile—Jaundice, . . . 317
181. Functions of the Bile, . . . 319
182. Fate of the Bile in the Intestine, . . . 320
183. The Intestinal Juice, . . . 321
184. Fermentation Processes in the Intestine, . . . 324
185. Processes in the Large Intestine, . . . 328
186. Pathological Variations, . . . 331
187. Comparative Physiology, . . . 333
188. Historical Retrospect, . . . 334

V. PHYSIOLOGY OF ABSORPTION.

189. The Organs of Absorption, . . . 336
190. Structure of the Small and Large Intestines, . . . 336
191. Absorption of the Digested Food, . . . 342
192. Absorptive Activity of the Wall of the Intestine, . . . 344
193. Influence of the Nervous System, . . . 347
194. Feeding with "Nutrient Enemata" . . . 347
195. Chyle Vessels and Lymphatics, . . . 348
196. Origin of the Lymphatics, . . . 348
197. The Lymph Glands, . . . 351
198. Properties of Chyle and Lymph, . . . 353
199. Quantity of Lymph and Chyle, . . . 354
200. Origin of Lymph, . . . 355
201. Movement of Chyle and Lymph, . . . 356
202. Absorption of Parenchymatous Effusions, . . . 359
203. Dropsy, Œdema, Serous Effusions, . . . 359
204. Comparative Physiology, . . . 360
205. Historical Retrospect, . . . 361

VI. PHYSIOLOGY OF ANIMAL HEAT.

206. Sources of Heat, . . . 362
207. Homoiothermal and Poikilothermal Animals, . . . 365
208. Methods of Estimating Temperature—Thermometry . . . 366
209. Temperature Topography, . . . 369
210. Conditions Influencing the Temperature of Organs, . . . 370
211. Estimation of the Amount of Heat—Calorimetry . . . 371
212. Thermal Conductivity of Animal Tissues, . . . 373
213. Variations of the Mean Temperature, . . . 373
214. Regulation of the Temperature, . . . 376
215. Income and Expenditure of Heat, . . . 379
216. Variations in Heat Production, . . . 380
217. Relation of Heat Production to Bodily Work, . . . 381
218. Accommodations for Different Temperatures, . . . 381
219. Storage of Heat in the Body, . . . 382

SECTION PAGE
220. Fever, . . . 383
221. Artificial Increase of the Temperature, . . . 384
222. Employment of Heat, . . . 384
223. Increase of Temperature *post-mortem*, . . . 385
224. Action of Cold on the Body, . . . 385
225. Artificial Lowering of Temperature, . . . 386
226. Employment of Cold, . . . 387
227. Heat of Inflamed Parts, . . . 387
228. Historical and Comparative, . . . 387

VII. PHYSIOLOGY OF THE METABOLIC PHENOMENA OF THE BODY.

229. General View of Food Stuffs, . . . 388
230. Structure and Secretion of the Mammary Glands, . . . 390
231. Milk and its Preparations, . . . 392
232. Eggs, . . . 395
233. Flesh and its Preparations, . . . 396
234. Vegetable Foods, . . . 397
235. Condiments—Coffee, Tea, and Alcohol, . . . 400
236. Equilibrium of the Metabolism, . . . 402
237. Metabolism during Hunger and Starvation, . . . 408
238. Metabolism during a purely Flesh Diet, . . . 409
239. A Diet of Fat or of Carbohydrates, . . . 410
240. Mixture of Flesh and Fat, . . . 411
241. Origin of Fat in the Body, . . . 411
242. Corpulence, . . . 413
243. The Metabolism of the Tissues, . . . 414
244. Regeneration of Organs and Tissues, . . . 416
245. Transplantation of the Tissues, . . . 419
246. Increase in Size and Weight during Growth, . . . 419

GENERAL VIEW OF THE CHEMICAL CONSTITUENTS OF THE ORGANISM.

247. Inorganic Constituents, . . . 421
248. Organic Compounds—Proteids, . . . 423
249. The Animal and Vegetable Proteids and their Properties, . . . 424
250. The Albuminoids, . . . 426
251. The Fats, . . . 429
252. The Carbohydrates, . . . 430
253. Historical Retrospect, . . . 433

VIII. THE SECRETION OF URINE.

254. Structure of the Kidney, . . . 434
255. The Urine, . . . 440
256. Organic Constituents of Urine—Urea, . . . 443
257. Qualitative and Quantitative Estimation of Urea, . . . 446
258. Uric Acid, . . . 447
259. Qualitative and Quantitative Estimation of Uric Acid, . . . 449
260. Kreatinin and other Substances, . . . 449
261. Coloring Matters of the Urine, . . . 452
262. Indigo, Phenol, Kresol, Pyrokatechin, . . . 453
263. Spontaneous Changes in Urine, Fermentations, . . . 456
264. Albumin in Urine, . . . 457
265. Blood in Urine, . . . 460
266. Bile in Urine, . . . 462
267. Sugar in Urine, . . . 462
268. Cystin, . . . 465
269. Leucin, Tyrosin, . . . 465
270. Deposits in Urine, . . . 465
271. General Scheme for Detecting Urinary Deposits, . . . 467
272. Urinary Calculi, . . . 468
273. The Secretion of Urine, . . . 469

SECTION PAGE
274. The Formation of Urinary Constituents, . . . 473
275. Passage of Various Substances into the Urine, . . . 475
276. Influence of Nerves on the Renal Secretion, . . . 476
277. Uræmia, Ammoniæmia, . . . 479
278. Structure and Functions of the Ureter, . . . 480
279. Urinary Bladder and Urethra, . . . 481
280. Accumulation and Retention of Urine, . . . 483
281. Retention and Incontinence of Urine, . . . 486
282. Comparative and Historical, . . . 486

IX. FUNCTIONS OF THE SKIN.

283. Structure of the Skin, Nails, and Hair, . . . 487
284. The Glands of the Skin, . . . 492
285. The Skin as a Protective Covering, . . . 493
286. Cutaneous Respiration and Secretion—Sweat, . . . 493
287. Conditions Influencing the Secretion of Sweat, . . . 495
288. Pathological Variations, . . . 497
289. Cutaneous Absorption—Galvanic Conduction, . . . 498
290. Comparative—Historical, . . . 499

X. PHYSIOLOGY OF THE MOTOR APPARATUS.

291. Ciliary Motion, Pigment Cells, . . . 500
292. Structure and Arrangement of the Muscles, . . . 502
293. Physical and Chemical Properties of Muscle, . . . 511
294. Metabolism in Muscle, . . . 513
295. Rigor mortis, . . . 515
296. Muscular Excitability, . . . 519
297. Changes in a Muscle during Contraction, . . . 524
298. Muscular Contraction, . . . 526
299. Rapidity of Transmission of a Muscular Contraction, . . . 537
300. Muscular Work, . . . 538
301. The Elasticity of Muscle, . . . 541
302. Formation of Heat in an Active Muscle, . . . 543
303. The Muscle Sound, . . . 545
304. Fatigue and Recovery of Muscle, . . . 545
305. The Mechanism of the Joints, . . . 547
306. Arrangement and Uses of the Muscles of the Body, . . . 549
307. Gymnastics—Pathological Motor Variations, . . . 553
308. Standing, . . . 554
309. Sitting, . . . 555
310. Walking, Running, and Leaping, . . . 555
311. Comparative, . . . 558

XI. VOICE AND SPEECH.

312. Voice and Speech, . . . 559
313. Arrangement of the Larynx, . . . 560
314. Organs of Voice—Laryngoscopy, . . . 565
315. Conditions Modifying the Laryngeal Sounds, . . . 568
316. Range of the Voice, . . . 569
317. Speech—The Vowels, . . . 569
318. The Consonants, . . . 572
319. Pathological Variations of Voice and Speech, . . . 573
320. Comparative—Historical, . . . 573

XII. GENERAL PHYSIOLOGY OF THE NERVES AND ELECTRO-PHYSIOLOGY.

321. Structure and Arrangement of the Nerve Elements, . . . 575
322. Chemical and Mechanical Properties of Nerve Substance, . . . 581
323. Metabolism of Nerves, . . . 582
324. Excitability of Nerves—Stimuli, . . . 583
325. Diminution of Excitability—Degeneration and Regeneration of Nerves, . . . 587

SECTION PAGE
326. The Galvanic Current, . . . 591
327. Action of the Galvanic Current—Galvanometer, . . . 593
328. Electrolysis, . . . 594
329. Induction—Extra-Current—Magneto-Induction, . . . 599
330. Du Bois-Reymond's Inductorium, . . . 601
331. Electrical Currents in Passive Muscle and Nerve, . . . 603
332. Currents of Stimulated Muscle and Nerve, . . . 607
333. Currents in Nerve and Muscle during Electrotonus, . . . 611
334. Theories of Muscle and Nerve Currents, . . . 613
335. Electrotonic Alteration of the Excitability, . . . 615
336. Electrotonus—Law of Contraction, . . . 617
337. Rapidity of Transmission of Nervous Impulses, . . . 620
338. Double Conduction in Nerves, . . . 623
339. Therapeutical Uses of Electricity—Reaction of Degeneration, . . . 624
340. Electrical Charging of the Body, . . . 629
341. Comparative —Historical, . . . 629

XIII. PHYSIOLOGY OF THE PERIPHERAL NERVES.

342. Classification of Nerve Fibres, . . . 631
343. Nervus Olfactorius, . . . 634
344. Nervus Opticus, . . . 634
345. Nervus Oculomotorius, . . . 637
346. Nervus Trochlearis, . . . 639
347. Nervus Trigeminus, . . . 640
348. Nervus Abducens, . . . 649
349. Nervus Facialis, . . . 649
350. Nervus Acusticus, . . . 653
351. Nervus Glosso-pharyngeus, . . . 655
352. Nervus Vagus, . . . 656
353. Nervus Accessorius, . . . 664
354. Nervus Hypoglossus, . . . 664
355. The Spinal Nerves, . . . 665
356. The Sympathetic Nerve, . . . 670
357. Comparative—Historical, . . . 673

XIV. PHYSIOLOGY OF THE NERVE CENTRES.

358. General, . . . 675
359. Structure of the Spinal Cord, . . . 676
360. Spinal Reflexes, . . . 686
361. Inhibition of the Reflexes, . . . 689
362. Centres in the Spinal Cord, . . . 693
363. Excitability of the Spinal Cord, . . . 695
364. The Conducting Paths in the Spinal Cord, . . . 696
365. General Schema of the Brain, . . . 700
366. The Medulla Oblongata, . . . 705
367. Reflex Centres of the Medulla Oblongata, . . . 710
368. The Respiratory Centre, . . . 712
369. The Cardio-Inhibitory Centre, . . . 718
370. The Accelerans Cordis Centre, . . . 720
371. Vasomotor Centre and Vasomotor Nerves, . . . 722
372. Vaso-dilator Centre and Vaso-dilator Nerves, . . . 729
373. The Spasm Centre—The Sweat Centre, . . . 730
374. Psychical Functions of the Cerebrum, . . . 731
375. Structure of the Cerebrum—Motor Cortical Centres, . . . 737
376. The Sensory Cortical Centres, . . . 751
377. The Thermal Cortical Centres, . . . 755
378. Topography of the Cortex Cerebri, . . . 756
379. The Basal Ganglia—The Mid-brain, . . . 765
380. The Structure and Functions of the Cerebellum, . . . 772
381. The Protective Apparatus of the Brain, . . . 776
382. Comparative—Historical, . . . 779

XV. PHYSIOLOGY OF THE SENSE ORGANS.

1. SIGHT.

SECTION		PAGE
383.	Introductory Observations,	781
384.	Histology of the Eye,	783
385.	Dioptric Observations,	792
386.	Formation of a Retinal Image,	796
387.	Accommodation of the Eye,	799
388.	Normal and Abnormal Refraction,	803
389.	The Power of Accommodation,	805
390.	Spectacles,	806
391.	Chromatic Aberration and Astigmatism,	807
392.	The Iris,	808
393.	Entoptical Phenomena,	812
394.	Illumination of the Eye—The Ophthalmoscope,	814
395.	Activity of the Retina in Vision,	818
396.	Perception of Colors,	823
397.	Color Blindness,	828
398.	Stimulation of the Retina,	829
399.	Movements of the Eyeballs,	833
400.	Binocular Vision,	837
401.	Single Vision—Identical Points,	837
402.	Stereoscopic Vision,	839
403.	Estimation of Size and Distance,	841
404.	Protective Organs of the Eye,	843
405.	Comparative—Historical,	845

2. HEARING.

406.	Structure of the Organ of Hearing,	847
407.	Physical Introduction,	848
408.	Ear Muscles,	849
409.	Tympanic Membrane,	849
410.	The Auditory Ossicles and their Muscles,	851
411.	Eustachian Tube—Tympanum,	855
412.	Conduction of Sound in the Labyrinth,	856
413.	Structure of the Labyrinth,	857
414.	Auditory Perceptions of Pitch,	860
415.	Perception of Quality—Vowels,	863
416.	Action of the Labyrinth,	867
417.	Harmony—Discords—Beats,	868
418.	Perception of Sound,	869
419.	Comparative—Historical,	870

3. SMELL.

420.	Structure of the Organ of Smell,	871
421.	Olfactory Sensations,	872

4. TASTE.

422.	Position and Structure of the Organs of Taste,	874
423.	Gustatory Sensations,	876

5. TOUCH.

424.	Terminations of Sensory Nerves,	878
425.	Sensory and Tactile Sensations,	881
426.	The Sense of Locality,	882
427.	The Pressure Sense,	885
428.	The Temperature Sense,	887
429.	Common Sensation—Pain,	889
430.	The Muscular Sense,	891

XVI. PHYSIOLOGY OF REPRODUCTION AND DEVELOPMENT.

SECTION		PAGE
431.	Forms of Reproduction,	893
432.	Testis—Seminal Fluid,	896
433.	The Ovary—Ovum—Uterus,	901
434.	Puberty,	906
435.	Menstruation,	907
436.	Penis—Erection,	909
437.	Ejaculation—Reception of the Semen,	911
438.	Fertilization of the Ovum,	912
439.	Impregnation and Cleavage of the Ovum,	913
440.	Structures formed from the Epiblast,	917
441.	Structures formed from the Mesoblast and the Hypoblast,	919
442.	Formation of the Heart and Embryo,	921
443.	Further formation of the Body,	922
444.	Formation of the Amnion and Allantois,	923
445.	Human Fœtal Membranes—Placenta,	925
446.	Chronology of Human Development,	929
447.	Formation of the Osseous System,	930
448.	Development of the Vascular System,	934
449.	Formation of the Intestinal Canal,	938
450.	Development of Genito-Urinary Organs,	940
451.	Formation of the Central Nervous System,	943
452.	Development of the Sense Organs,	944
453.	Birth,	946
454.	Comparative—Historical,	947
	Appendix A.; Bibliography,	950
	Appendix B.; Tables of Measure (Metric and Ordinary) and of Temperature,	954
	Index,	955

LIST OF ILLUSTRATIONS.

FIGURE		PAGE
1.	Human colored blood corpuscles,	44
2.	Apparatus of Abbé and Zeiss for estimating the blood corpuscles,	45
3.	Mixer,	45
*4.	Gower's hæmacytometer (*Hawksley*),	46
*5.	Crenation of human blood corpuscles,	47
6.	Red blood corpuscles showing various changes of shape,	48
*7.	Effect of reagents on blood corpuscles (*Stirling*),	49
8.	Vaso-formative cells,	52
9.	White blood corpuscles and fibrin,	54
*10.	White blood corpuscles (*Klein*),	55
11.	Amœboid movements of colorless corpuscles,	56
12.	Blood plates and their derivatives,	57
13.	Hæmoglobin crystals,	59
*14.	Gowers' hæmoglobinometer (*Hawksley*),	60
*15.	Fleischl's hæmometer (*Reichert*),	61
16.	Scheme of a spectroscope,	62
17.	Various spectra of hæmoglobin and its compounds,	63
18.	Hæmin crystals,	67
19.	Hæmin crystals prepared from traces of blood,	67
20.	Hæmatoidin crystals,	68
*21.	Hewson's experiment,	74
22.	Scheme of Pflüger's gas pump,	82
*23.	Micrococcus, bacterium, vibrio,	90
*24.	Bacillus anthracis,	90
25.	Scheme of the circulation,	91
26.	Muscular fibres from the heart,	92
27.	Muscular fibres in the left auricle,	93
28.	Muscular fibres in the ventricles,	94
*29.	Lymphatic from the pericardium (*Cadiat*),	95
*30.	Section of the endocardium (*Cadiat*),	95
*31.	Purkinje's fibres (*Ranvier*),	96
32.	Cast of the ventricles of the human heart,	99
33.	The closed semilunar valves,	100
*34.	Gaule's maximum and minimum manometer (*Gscheidlen*),	100
*35.	Manometer of Gaule (*Gscheidlen*),	100
*36.	Various cardiographs (*Hermann*),	103
*37.	Cardiogram,	103
*38.	Arteriogram and Cardiogram,	104
39.	Curves of the apex beat,	104
40.	Changes of the heart during systole, and sections of thorax,	105
*41.	Dog's heart, posterior surface (*Ludwig and Hesse*),	106
*42.	Left lateral surface (*Ludwig and Hesse*),	106
*43.	Anterior surface (*Ludwig and Hesse*),	106
*44.	Base of heart (*Ludwig and Hesse*),	107
*45.	Base of heart in systole and diastole (*Ludwig and Hesse*),	107
46.	Curves from a rabbit's ventricle,	108
*47.	Marey's registering tambour (*Hermann*),	109
48.	Curves obtained with a cardiac sound,	110
49.	Curves from the cardiac impulse,	111, 112
*50.	Scheme of cardiac cycle,	112
*51.	Position of the heart in the chest (*Luschka and Gairdner*),	115
*52.	Curves of excised rabbits' hearts (*Stirling, after Waller*),	116
*53.	Heart of frog from the front (*Ecker*),	118

FIGURE PAGE
*54. Heart of frog from behind (*Ecker*), . . . 118
*55. Auricular septum (*Ecker*), . . . 119
*56. Bipolar nerve cells from a frog's heart, . . . 119
*57. Scheme of frog's heart (*Brunton*), . . . 119
*58. Stannius's experiment (*Brunton*), . . . 119
*59. Luciani's groups of cardiac pulsations (*Hermann*), . . . 123
*60. Scheme of a frog manometer (*Stirling*), . . . 123
*61. Perfusion cannula (*Kronecker and Stirling*), . . . 124
*62. Roy's tonometer (*Stirling*), . . . 124
*63. Curves of a frog's heart at different temperatures (*Hermann*), . . . 125
64. Cardio-pneumograph of Landois, . . . 128
65. Apparatus for showing the effect of respiration, . . . 130
66. Cylindrical vessel filled with water, . . . 133
67. Cylindrical vessel with manometers, . . . 133
68. Small artery with its various coats, . . . 135
69. Capillaries injected with silver nitrate, . . . 135
*70. Longitudinal section of a vein at a valve (*Cadiat*), . . . 136
71. Sphygmometer of Herisson, . . . 139
72. Scheme of Marey's sphygmograph, . . . 140
*73. Marey's improved sphygmograph (*B. Bramwell*), . . . 140
*74. Ludwig's sphygmograph, . . . 141
*75. Dudgeon's sphygmograph (*Dudgeon*), . . . 141
76. Scheme of Brondgeest's pansphygmograph, . . . 142
77. Scheme of Landois' angiograph, . . . 142
78. Pulse curves of the carotid, radial, and posterior tibial arteries, . . . 143
*79. S. Mayer's gas sphygmoscope, . . . 143
80. Hæmautographic curve, . . . 143
*81. Sphygmogram of radial artery (*Dudgeon*), . . . 144
*82. Irregular pulse, mitral regurgitation, . . . 145
83. Sphygmograms of various arteries, . . . 146
*84. Pulse tracings after amyl nitrite (*Stirling, after Murrell*), . . . 147
*85. Aortic regurgitation, . . . 147
86. Pulsus dicrotus, P. caprizans, P. monocrotus, . . . 148
*87. Hyperdicrotic pulse, . . . 149
88. Pulsus alternans, . . . 150
89. Curves of the posterior tibial artery, . . . 151
90. Anacrotic pulse curves, . . . 152
91. Anacrotic pulse curves, . . . 152
92. Influence of the respiration on the sphygmogram, . . . 153
93. Pulse curves during Müller's and Valsalva's experiments, . . . 154
94. Pulsus paradoxus, . . . 155
95. Various radial curves altered by pressure, . . . 155
96. Pulse tracings of the radial artery, . . . 157
97. Tracings from the posterior tibial, and carotid arteries, . . . 157
98. Apparatus for registering the molar motions of the body, . . . 158
99. Vibration and heart curves, . . . 159
100. Ludwig and Fick's kymographs, . . . 162
*101. Ludwig's improved revolving cylinder (*Hermann*), . . . 162
*102. Blood-pressure tracing of the carotid of a dog (*Hermann*), . . . 163
*103. Fick's spring manometer, by Hering (*Hermann*), . . . 164
104. Fick's flat-spring kymograph, . . . 165
*105. Scheme of height of blood pressure, . . . 166
*106. Depressor curve (*Stirling*). . . . 167
*107. Blood pressure and respiration tracings taken simultaneously (*Stirling*), . . . 168
*108. Blood-pressure tracing during stimulation of the vagus (*Stirling*), . . . 170
*109. Apparatus of v. Kries for capillary pressure (*C. Ludwig*), . . . 171
*110. Scheme of the blood pressure, . . . 172
111. Volkmann's hæmadromometer, . . . 175
112. Ludwig and Dogiel's rheometer, . . . 175
113. Vierordt's hæmatachometer—Dromograph, . . . 176
114. Photohæmatachometer, . . . 177
*115. Scheme of sectional area (after *Yeo*), . . . 178
116. Diapedesis, . . . 182
117. Various forms of venous pulse, . . . 186
118. Mosso's plethysmograph, . . . 188

FIGURE PAGE
*119. Section of spleen (*Stöhr*), . . . 192
*120. Trabeculæ of the spleen (*Cadiat*), . . . 193
*121. Adenoid tissue of spleen (*Cadiat*), . . . 193
*122. Malpighian corpuscle of the spleen (*Cadiat*), . . . 193
*123. Elements of splenic pulp (*Stöhr*), . . . 194
*124. Tracing of the splenic curve (*Roy*), . . . 196
*125. Thymus gland (*Cadiat*), . . . 197
*126. Elements of the thymus gland (*Cadiat*), . . . 197
*127. Thyroid gland (*Cadiat*), . . . 198
*128. Supra-renal capsule (*Cadiat*), . . . 200
129. Schemata of the circulation, . . . 201
*130. Human bronchus (*Hamilton*), . . . 204
*131. Air vesicles injected with silver nitrate (*Hamilton*), . . . 206
132. Scheme of the air vesicles of lung, . . . 207
*133. Interlobular septa of lung (*Hamilton*), . . . 208
134. Scheme of Hutchinson's spirometer, . . . 211
135. Brondgeest's tambour and curve, . . . 212
136. Marey's stethograph (*M'Kendrick*), . . . 213
137. Pneumatograms, . . . 214
138. Section through diaphragm (*Hermann*), . . . 217
139. Action of intercostal muscles, . . . 218
140. Cyrtometer curve, . . . 221
141. Sibson's thoracometer, . . . 221
142. Topography of the lungs and heart, . . . 222
143. Andral and Gavarret's respiration apparatus, . . . 228
144. Scharling's apparatus, . . . 229
145. Regnault and Reiset's apparatus, . . . 229
146. v. Pettenkofer's apparatus, . . . 230
147. Valentin and Brunner's apparatus, . . . 231
148. Ciliated epithelium, . . . 244
149. Objects found in sputum, . . . 246
*150. Squamous epithelium from the mouth (*Stirling*), . . . 250
151. Mucous follicle and salivary corpuscles (*Schenk*), . . . 250
*152. Section of tonsil (*Stöhr*), . . . 251
*153. Scheme of glands, . . . 252
154. Rodded epithelium of a salivary duct, . . . 252
155. Histology of the salivary glands, . . . 252
*156. Human submaxillary gland (*Heidenhain*), . . . 253
*157. Parotid gland of rabbit at rest (*Heidenhain*), . . . 254
*158. Parotid gland of rabbit, active phase *Heidenhain*), . . . 254
*159. Scheme of the nerves of the salivary glands (*Stirling*), . . . 255
*160. Diagram of a salivary gland (*Stirling*), . . . 259
161. Apparatus for estimation of sugar, . . . 265
162. Polarization apparatus, . . . 266
163. Vertical section of a tooth, . . . 268
164. Dentine, . . . 269
165. Interglobular spaces, . . . 269
166. Dentine and enamel, . . . 269
167. Dentine and crusta petrosa, . . . 269
168. } Development of a tooth, . . . 270
169. }
170. }
171. Section of œsophagus (*Schenk*), . . . 274
172. Perinæum and its muscles, . . . 278
173. Levator ani externus and internus, . . . 279
*174. Vertical section of Auerbach's plexus (*Cadiat*), . . . 280
*175. Auerbach's plexus (*Cadiat*), . . . 281
*176. Meissner's plexus (*Cadiat*), . . . 282
*177. Vertical section of stomach (*Stöhr*), . . . 284
178. Goblet cells, . . . 284
179. Surface section of gastric mucous membrane, . . . 284
180. Fundus gland of the stomach, . . . 285
181. Pyloric gland, . . . 285
182. Scheme of the gastric mucous membrane, . . . 286
*183. Pyloric mucous membrane (*Hermann*), . . . 287

FIGURE PAGE
*184. Pyloric glands during digestion (*Hermann*), . . . 287
*185. Scheme of pyloric fistula (*Stirling*), . . . 289
*186. Section of the acini of the pancreas (*Hermann*), . . . 297
187. Changes of the pancreatic cells during activity, . . . 297
*188. Section of human liver (*Stöhr*), . . . 303
189. Scheme of a liver lobule, . . . 304
*190. Human liver cells (*Cadiat*), . . . 305
*191. Liver cells during fasting (*Hermann*), . . . 305
192. Bile ducts, . . . 305
*193. Liver cells (*Stirling, after Stolnikoff*), . . . 306
194. Various appearances of the liver cells, . . . 306
195. Interlobular bile duct, . . . 307
*196. Cholesterin (*Stirling*), . . . 314
*197. Biliary fistula (*Stirling*), . . . 316
*198. Section of duodenum (*Stöhr*), . . . 321
*199. Lieberkühn's gland (*Hermann*), . . . 322
200. Transverse section of Lieberkühn's follicles (*Schenk*), . . . 322
*201. Schemata of intestinal fistulæ (*Stirling*), . . . 322
*202. Moreau's fistula (*after Brunton*), . . . 323
203. Bacterium aceti and B. butyricus, . . . 325
204. Bacillus subtilis, . . . 326
205. Bacteria of fæces, . . . 330
*206. Scheme of intestinal absorption (*Beaunis*), . . . 336
*207. Longitudinal section of small intestine (*Schenk*), . . . 337
208. Scheme of an intestinal villus, . . . 338
209. Injected villus (*Schenk*), . . . 338
*210. Villi of small intestine injected (*Cadiat*), . . . 339
*211. Duodenum injected (*Stöhr*), . . . 340
*212. Section of a solitary follicle (*Cadiat*), . . . 340
*213. Section of a Peyer's patch (*Cadiat*), . . . 341
214. Section of large intestine (*Schenk*), . . . 341
215. Endosmometer, . . . 342
216. Origin of lymphatics in the tendon of diaphragm, . . . 349
*217. Lymphatics of diaphragm silvered (*Ranvier*), . . . 349
218. Perivascular lymphatics, . . . 350
219. Stomata from lymph sac of frog, . . . 350
220. Section of two lymph follicles, . . . 351
*221. Scheme of a lymphatic gland (*Sharpey*), . . . 351
222. Part of a lymphatic gland, . . . 352
*223. Section of the central tendon of diaphragm (*Brunton*), . . . 357
*224. Section of fascia lata of a dog (*Brunton*), . . . 357
*225. Lymph hearts (*Ecker*), . . . 358
226. Water calorimeter of Favre and Silbermann, . . . 362
*227. Water calorimeter of Dulong (*Rosenthal*), . . . 363
*228. Clinical Thermometers, . . . 367
229. Walferdin's metastatic thermometer, . . . 367
230. Scheme of thermo-electric arrangements, . . . 368
231. Kopp's apparatus for specific heat, . . . 372
232. Daily variations of temperature, . . . 374
*233. Acini of the mammary gland of a sheep (*Cadiat*), . . . 390
234. Milk glands during inaction and secretion, . . . 391
*235. Milk and colostrum (*Stirling*), . . . 392
*236. Section of a grain of wheat (*Blyth*), . . . 398
237. Yeast-cells growing, . . . 401
238. Composition of animal and vegetable foods, . . . 404
*239. Starch grains, . . . 432
*240. Longitudinal section of the kidney (*Henle*), . . . 434
*241. Malpighian pyramid (*Tyson, after Ludwig*), . . . 435
*242. Scheme of the uriniferous tubules (*Klein and Noble Smith*), . . . 436
243. Scheme of the structure of the kidney, . . . 437
244. Glomerulus and renal tubules, . . . 438
*245. Convoluted renal tubule (*Heidenhain*), . . . 438
*246. Irregular tubule (*Tyson, after Klein*), . . . 438
*247. Transverse section of the apex of a Malpighian pyramid (*Cadiat*), . . . 439
*248. Development of a glomerulus (*Cadiat*), . . . 441

FIGURE		PAGE
249.	Graduated urinary flask,	441
250.	Urinometer,	441
251.	Graduated burette,	443
252.	Urea and urea nitrate,	444
*253.	Oxalate of urea (*after Beale*),	446
*254.	Ureameter (*Charteris*),	446
255.	Graduated pipette,	447
256.	Uric acid,	448
257.	Kreatinin zinc chloride,	450
*258.	Oxalate of lime,	450
259.	Hippuric acid,	451
260.	Deposit in urine during the "acid fermentation,"	456
261.	Deposit in ammoniacal urine,	456
262.	Micrococcus ureæ,	457
263.	Esbach's albumimeter,	459
264.	Blood corpuscles in urine,	460
265.	Peculiar forms of blood corpuscles,	460
266.	Colored and colorless corpuscles in urine,	460
267.	Blood corpuscles and triple phosphate,	460
268.	Spectroscopic examination of urine,	461
*269.	Picro-saccharimeter (*G. Johnson*),	464
*270.	Inosit (*Beale, after Funke*),	464
271.	Cystin and oxalate of lime,	465
272.	Leucin, tyrosin, and ammonium urate,	465
273.	Fungi in urine,	466
274.	Epithelial casts,	466
275.	Blood casts,	466
276.	Leucocyte cast,	466
277.	Cast of urate of soda,	466
278.	Finely granular casts,	466
279.	Coarsely granular casts,	467
280.	Hyaline casts,	467
281.	Calcic carbonate and phosphate,	467
282.	Triple phosphate,	467
283.	Imperfect forms of triple phosphate,	467
284.	Acid ammonium urate,	468
285.	Basic magnesic phosphate,	468
*286.	Oncometer (*Stirling, after Roy*),	477
*287.	Oncograph (*Stirling, after Roy*),	477
*288.	Renal oncograph curve (*Stirling, after Roy*),	478
*289.	Section of ureter (*Stöhr*),	480
*290.	Transitional epithelium (*Beale*),	481
291.	View of the trigone of the bladder,	482
*292.	Nervous mechanism of micturition (*Stirling, after Gowers*),	485
*293.	Section of epidermis and its nerves (*Ranvier*),	487
294.	Scheme of the structure of the skin,	488
*295.	Papillæ of the skin injected,	489
296.	Transverse section of a nail,	489
297.	Transverse section of a hair follicle,	490
298.	Longitudinal section of a hair follicle,	491
299.	Sebaceous gland,	492
300.	Ciliated epithelium,	500
*301.	Pigment and guanin cells of frog (*Stirling*),	502
302.	Histology of muscular tissue,	503
*303.	Muscular fibre (*Quain*),	504
*304.	Insect's muscle (*Rollett*),	505
*305.	Insect's muscle (*Rollett*),	505
*306.	Network in muscle (*Melland*),	506
307.	Tendon attached to a muscle,	506
*308.	Injected blood vessels of muscle (*Kölliker*),	506
309.	Motorial end plates,	507
*310.	Termination of a nerve in a frog's muscle (*Kühne*),	508
*311.	Scheme of nerve ending in muscle (*Rollett, after Kühne*),	508
*312.	Smooth muscle,	510
*313.	Non-striped muscle cell (*Stirling*),	510

FIGURE PAGE
*314. Nerve ending in smooth muscle (*Cadiat*), . . . 510
*315. Frog with its sciatic artery ligatured (*Stirling*), . . . 521
*316. Scheme of the curara experiment (*after Rutherford*), . . . 521
*317. Excitability in a frog's sartorius (*Stirling, after Pollitzer*), . . . 522
*318. Excitability in a curarized sartorius (*Stirling, after Pollitzer*), . . . 522
319. Microscopic appearances in contracting muscle, . . . 525
320. Helmholtz's myograph, . . . 526
*321. Pendulum myograph, . . . 527
*322. Scheme of the pendulum myograph (*Stirling*), . . . 528
*323. Du Bois-Reymond's spring myograph, . . . 529
324. Muscle curve, . . . 529
*325. Muscle curve of pendulum myograph (*Stirling*), . . . 530
*326. Method of studying a muscular contraction (*after Rutherford*), . . . 531
*327. Effect of make and break induction shocks (*Stirling*), . . . 531
328. Muscle curves, . . . 531
329. Muscle curve, opening and closing shocks, . . . 532
*330. Veratrin curve (*Stirling*), . . . 533
331. Muscle curves, tetanus, . . . 534
*332. Staircase contractions (*Buckmaster*), . . . 535
333. Curves of voluntary impulses, . . . 535
*334. Curves of a red and pale muscle (*Kronecker and Stirling*), . . . 536
*335. Muscle curves (*Kronecker and Stirling*), . . . 536
*336. Tone inductorium (*Kronecker and Stirling*), . . . 537
*337. Muscle curves (*Marey*), . . . 538
*338. Height of the lift by a muscle, . . . 539
*339. Dynamometer, . . . 540
*340. Curve of elasticity (*after Marey*), . . . 541
*341. Curve of elasticity of a muscle (*after Marey*), . . . 541
*342. Curve of elasticity (*Marey*), . . . 541
*343. Fatigue curve (*Stirling*), . . . 546
*344. Fatigue curve (*Waller*), . . . 547
*345. Vertical section of articular cartilage (*Stirling*), . . . 548
*346. Orders of levers, . . . 551
*347. Scheme of the action of muscles on bones, . . . 551
348. Phases of walking, . . . 556
349. Instantaneous photograph of a person walking, . . . 556
350. Instantaneous photograph of a runner, . . . 557
351. Instantaneous photograph of a person jumping, . . . 558
352. Larynx from the front, . . . 561
353. Larynx from behind, . . . 561
354. Larynx from behind, . . . 562
355. Nerves of the larynx, . . . 562
356. Action of the posterior crico-arytenoid muscles, . . . 563
357. Action of the arytenoid muscles, . . . 563
358. Action of the lateral crico-arytenoid muscles, . . . 563
359. Vertical section of the head and neck, . . . 565
360. Examination of the larynx, . . . 566
361. Laryngoscopic view of the larynx, . . . 566
362. View of the larynx during a high note, . . . 567
363. View of the larynx during a deep inspiration, . . . 567
364. Rhinoscopy, . . . 567
365. View of the posterior nares, . . . 568
366. Parts concerned in phonation, . . . 571
367. Tumors on the vocal cords, . . . 573
368. Histology of nervous tissues, . . . 576
*369. Transverse section of nerve fibres (*Cadiat*), . . . 578
*370. Sympathetic nerve fibre (*Ranvier*), . . . 578
*371. Medullated nerve fibre (*Stirling*), . . . 578
372. Medullated nerve fibre, . . . 578
*373. Medullated nerve fibres (*Schwalbe*), . . . 578
*374. Ranvier's crosses (*Ranvier*), . . . 579
375. Transverse section of a nerve, . . . 579
*376. Cell from the Gasserian ganglion (*Schwalbe*), . . . 580
377. Degeneration and regeneration of nerve fibres, . . . 588
*378. Waller's experiments (*after Dalton*), . . . 588

FIGURE		PAGE
379.	Rheocord of du Bois-Reymond,	593
380.	Scheme of a galvanometer,	594
*381.	Large Grove's battery (*Gscheidlen*),	595
*382.	Daniell's cell (*Stirling*),	596
*383.	Grennet's battery (*Gscheidlen*),	596
*384.	Leclanché's element (*Gscheidlen*),	596
*385.	Non-polarizable electrodes (*Elliott Brothers*),	597
*386.	Fleischl's non-polarizable electrodes (*Petzoldt*),	597
*387.	Thomson's galvanometer (*Elliott Brothers*),	597
*388.	Lamp and scale (*Elliott Brothers*),	598
*389.	Galvanometer shunt (*Elliott Brothers*),	598
*390.	Scheme of the induced currents (*Hermann*),	600
*391.	Helmholtz's modification (*Hermann*),	600
392.	Scheme of an induction machine,	601
*393.	Inductorium (*Elliott Brothers*),	602
*394.	Inductorium (*Petzoldt*),	602
395.	Stöhrer's apparatus,	603
*396.	Friction key (*Elliott Brothers*),	603
*397.	Plug key (*Elliott Brothers*),	603
*398.	Capillary contact (*Kronecker and Stirling*),	603
399.	Scheme of the muscle current,	604
400.	Capillary electrometer,	604
*401.	Nerve-muscle preparation,	606
*402.	Kühne's experiment (*Stirling*),	606
*403.	Electrometer curve, frog's muscle (*Waller*),	608
*404.	Electrometer curve, frog's heart (*Waller*),	608
*405.	Secondary contraction,	609
406.	Bernstein's differential rheotome,	610
407.	Nerve current in electrotonus,	611
408.	Scheme of electrotonic excitability,	616
409.	Method of testing electrotonic excitability,	616
410.	Distribution of an electrical current,	617
411.	Velocity of nerve energy,	621
*412.	Scheme for testing velocity of a nerve impulse,	621
*413.	Curves of a nerve impulse (*Marey*),	622
*414.	Kühne's gracilis experiment,	624
*415.	Sponge rheophores *Weiss*),	624
*416.	Disk rheophore (*Weiss*),	624
*417.	Metallic brush (*Weiss*),	624
418.	Motor points of the arm,	625
419.	Motor points of the arm,	625
420.	Motor points of the leg,	626
421.	Motor points of the leg,	627
*422.	Scheme of a reflex act (*Stirling*),	633
423.	Optic chiasma,	635
*424.	Relation of field of vision, retina, and optic tracts (*Gowers*),	635
*425.	Decussation of the optic tracts (*Charcot*),	636
*426.	Scheme of images in squinting (*Bristowe*),	638
427.	Medulla oblongata,	639
*428.	Under surface of the brain,	640
429.	Connections of the cranial nerves,	642
430.	Sensory nerves of the face,	647
431.	Motor points of the face and neck,	651
*432.	Disposition of the semicircular canals (*Stirling*),	654
433.	Scheme of the branches of vagus and accessorius,	658
*434.	Cardiac nerves of the rabbit (*Stirling*),	660
*435.	Diagram of a spinal nerve (*Ross*),	666
*436.	Spinal ganglion (*Cadiat*),	666
437.	Cutaneous nerves of the arm,	668
438.	Cutaneous nerves of the leg (*Henle*),	668
*439.	Visceral nerves of the dog (*Gaskell*),	671
440.	Transverse section of the spinal cord,	676
*441.	Transverse section of the white matter (*Obersteiner*),	677
*442.	Multipolar nerve cells of the cord (*Cadiat*),	677
*443.	Relation of white and gray matter of the cord (*Schäfer*),	677

FIGURE		PAGE
*444.	Transverse sections of the spinal cord,	678
*445.	Cell from Clarke's column (*Obersteiner*),	679
*446.	Transverse section of the cord (*Cadiat*),	679
*447.	Longitudinal section of the cord (*Cadiat*),	680
*448.	Multipolar nerve cell,	680
*449.	Scheme of fibres in cord (*Obersteiner*),	680
*450.	Glia cell (*Obersteiner*),	681
*451.	Glia cells of cord (*Obersteiner*),	681
*452.	Spinal cord injected (*Obersteiner*),	682
*453.	Injected blood vessels of the cord (*Kölliker*),	682
454.	Conducting paths in the cord,	683
*455.	Degeneration paths in the cord (*Bramwell*),	685
*456.	Scheme of a reflex act (*Stirling*),	686
*457.	Section of a spinal segment (*Stirling*),	686
*458.	Propagation of reflex movements (*Beaunis*),	687
*459.	Effect of section of half of the cord (*Erb*),	699
*460.	Brain, ventricles, and basal ganglia,	700
461.	Scheme of the brain,	701
*462.	Connections of the cerebellum,	702
*463.	Diagram of a spinal segment (*Bramwell*),	706
*464.	Section across the pyramids (*Schwalbe*),	707
*465.	Section of the medulla oblongata (*Schwalbe*),	708
*466.	Section of the olivary body (*Schwalbe*),	708
*467.	Scheme of the respiratory centres (*Rutherford*),	713
*468.	Action of vagus on frog's heart (*Stirling*),	719
*469.	Scheme of the accelerans fibres (*Stirling*),	721
*470.	Cardiac plexus of a cat (*Böhm*),	721
*471.	Frog without its cerebrum (*Stirling, after Goltz*),	733
*472.	Frog without its cerebrum (*Stirling, after Goltz*),	733
*473.	Pigeon with its cerebrum removed (*after Dalton*),	734
*474.	Motor area of cerebral convolution (*Ferrier and B. Lewis*),	738
*475.	Cerebral convolution; sensory area (*Ferrier and B. Lewis*),	738
*476.	Perivascular lymph spaces (*Obersteiner*),	738
*477.	Frontal convolution by Weigert's method (*Obersteiner*),	738
*478.	Cerebral convolution injected,	739
*479.	Left side of the human brain (*Ecker*),	740
*480.	Inner aspect of right hemisphere (*Ecker*),	741
*481.	Left frontal lobe and island of Reil (*Turner*),	742
*482.	Brain from above (*Ecker*),	743
483.	Cerebrum of dog, carp, frog, pigeon, and rabbit,	745
484.	Relation of the cerebral convolutions to the skull,	747
*485.	Motor areas of a monkey's brain (*Horsley and Schäfer*),	748
*486.	Motor areas of the marginal convolution (*Horsley and Schäfer*),	748
*487.	Psycho-optic fibres (*Munk*),	752
*488.	Motor areas (*after Gowers*),	756
*489.	Motor centres (*after Schäfer and Horsley*),	756
*490.	Section of a cerebral hemisphere (*Horsley*),	757
*491.	Innervation of associated muscles (*Ross*),	757
*492.	Secondary degeneration in a crus (*Charcot*),	759
*493.	Transverse section of the crus cerebri (*Charcot*),	759
*494.	Scheme of aphasia (*Lichtheim*),	761
*495.	Scheme of aphasia (*Lichtheim*),	761
*496.	Scheme of aphasia (*Ross*),	762
*497.	Relation of the convolutions to the skull (*R. W. Reid*),	764
*498.	Relation of motor centres to skull (*Hare*),	765
*499.	Outline markings on skull (*Hare*),	765
*500.	Basal ganglia and the ventricles,	767
*501.	Transverse section of the right hemisphere (*Gegenbaur*),	768
*502.	Transverse section of the crura (*Wernicke and Gowers*),	769
*503.	Transverse section of the pons (*Wernicke*),	769
*504.	Course of the fibres in pons (*Erb*),	769
*505.	Longitudinal section of a human brain (*Wiedersheim*),	772
*506.	Section of the cerebellum (*Sankey*),	773
*507.	Purkinje's cell (*Obersteiner*),	773
*508.	Pigeon with its cerebellum removed (*Dalton*),	774

FIGURE		PAGE
*509.	Cortex cerebri and its membranes (*Schwalbe*),	776
*510.	Circle of Willis (*Charcot*),	778
*511.	Ganglionic arteries (*Charcot*),	779
*512.	Corneal corpuscles (*Ranvier*),	783
*513.	Corneal spaces (*Ranvier*),	783
514.	Junction of the cornea and sclerotic,	478
*515.	Vertical section of cornea with nerve fibuli (*Ranvier*),	785
*516.	Horizontal section of cornea with nerve fibuli (*Ranvier*),	786
*517.	Vertical section of choroid and sclerotic (*Stöhr*),	786
518.	Blood vessels of the eyeball,	787
*519.	Vertical section human retina (*Cadiat*),	788
520.	Layers of the retina,	788
*521.	Vertical section of the fovea centralis (*Cadiat*),	789
*522.	Fibres of the lens (*Kölliker*),	790
523.	Section of the optic nerve,	791
524.	Action of lenses on light,	793
525.	Refraction of light,	794
526.	Construction of the refracted ray,	794
527.	Optical cardinal points,	795
528.	Construction of the refracted ray,	796
529.	Construction of the image,	796
530.	Refracted ray in several media.	797
531.	Visual angle and retinal image,	797
532.	Scheme of the ophthalmometer,	798
533.	Horizontal section of the eyeball,	800
534.	Scheme of accommodation,	801
535.	Sanson-Purkinje's images,	801
*536.	Phakoscope (*M'Kendrick*),	802
537.	Scheiner's experiment,	803
538.	Refraction of the eye,	804
539.	Myopic eye,	804
540.	Hypermetropic eye,	804
541.	Power of accommodation,	805
*542.	Diagram of astigmatism (*Frost*),	808
543.	Cylindrical glasses,	808
*544.	Scheme of the nerves of the iris (*Erb*),	810
*545.	Pupilometer (*Gorham*),	811
*546.	Pupilometer (*Gorham*),	811
547.	Entoptical shadows,	812
548.	Scheme of the original ophthalmoscope,	814
549.	Scheme of the indirect method,	815
550.	Action of a divergent lens,	815
551.	Action of a divergent lens,	815
552.	View of the fundus oculi,	816
*553.	Morton's ophthalmoscope (*Pickard and Curry*),	816
*554.	Frost's artificial eye (*Frost*),	817
*555.	Action of the orthoscope,	817
*556.	Mariotte's experiment,	818
*557.	Horizontal section of the right eye,	820
*558.	M'Hardy's perimeter (*Pickard and Curry*),	821
*559.	Priestley Smith's perimeter (*Pickard and Curry*),	821
560.	Perimetric chart,	822
561.	Geometrical color zone,	825
562.	Action of light rays on the retina,	826
*563.	Cones of the retina (*Stirling after Engelmann*),	829
*564.	Irradiation,	831
*565.	Irradiation,	831
566.	Scheme of the action of the ocular muscles,	835
567.	Identical points of the retina,	838
568.	The horopter,	838
569.	Two stereoscopic drawings,	839
570.	Wheatstone's stereoscope,	840
571.	Brewster's stereoscope,	840
572.	Telestereoscope,	841
573.	Wheatstone's pseudoscope,	841

FIGURE		PAGE
574.	Kollett's apparatus,	842
*575.	Zöllner's lines,	843
576.	Section of an eyelid,	844
577.	Scheme of the organ of hearing,	847
578.	External auditory meatus,	849
579.	Left tympanic membrane and ossicles,	850
580.	Membrana tympani and ossicles,	850
581.	Tympanic membrane from within,	850
*582.	Ear specula (*Krohne and Sesemann*),	850
*583.	Toynbee's artificial membrana tympani (*Krohne and Sesemann*),	851
584.	Right auditory ossicles,	851
585.	Tympanum and auditory ossicles,	852
586.	Tensor tympani and Eustachian tube,	853
587.	Right stapedius muscle,	854
*588.	Eustachian catheter,	856
*589.	Politzer's ear bag (*Krohne and Sesemann*),	856
590.	Right labyrinth,	856
591.	Scheme of the cochlea,	858
*592.	Interior of the right labyrinth,	858
*593.	Semicircular canals,	858
*594.	Section of the macula acustica (*Ranvier*),	859
595.	Scheme of the canalis cochlearis,	860
*596.	Galton's whistle (*Krohne and Sesemann*),	862
597.	Curve of a muscle note and its overtones,	864
*598.	Kœnig's manometric capsule (*Kœnig*),	865
*599.	Flame pictures of vowels (*Kœnig*),	865
*600.	Kœnig's analyzing apparatus (*Kœnig*),	866
601.	Nasal and pharyngo-nasal cavities,	871
*602.	Section of the olfactory region (*Stöhr*),	871
603.	Olfactory cells,	872
*604.	Filiform papillæ (*Stöhr*),	874
*605.	Fungiform papillæ (*Stöhr*),	874
606.	Circumvallate papilla and taste bulbs,	875
*607.	Papillæ foliatæ (*Stöhr*),	875
608.	Vertical section of skin,	878
609.	Wagner's touch corpuscle (*Ranvier*),	878
610.	Pacini's corpuscle,	879
*611.	End bulb from conjunctiva (*Quain*),	879
*612.	Tactile corpuscle from clitoris, (*Quain*),	879
*613.	Tactile corpuscles from a duck's bill (*Quain*),	880
*614.	Bouchon epidermique (*Ranvier*),	880
615.	Æsthesiometer,	882
*616.	Æsthesiometer of Sieveking,	883
*617.	Aristotle's experiment,	884
618.	Pressure spots,	885
619.	Landois' pressure mercurial balance,	886
620.	Cold and hot spots,	887
621.	Cold and hot spots,	887
622.	Topography of temperature spots,	889
*623.	Karyokinesis (*Gegenbaur*),	893
*624.	Typical nucleated cell (*Carnoy*),	893
*625.	Mitosis or nuclear division (*Flemming*),	894
626.	Ovum of Tænia solium,	895
627.	Cysticercus,	895
628.	Cysticerci of Tænia solium,	896
629.	Scolex,	896
630.	Echinococcus,	896
631.	Tænia solium,	896
*632.	Section of testis (*Schenk*),	897
*633.	Tubule of testis (*Schenk*),	898
*634.	Section of epididymis, (*Schenk*),	898
635.	Spermatic crystals,	899
636.	Spermatozoa,	900
637.	Spermatogenesis,	900
*638.	A cat's ovary (*Hart and Barbour, after Schrön*),	901

FIGURE		PAGE
*639.	Section of an ovary (*Turner*),	901
640.	Ripe ovum of rabbit,	902
641.	Ovary and polar globules,	903
642.	Scheme of a meroblastic ovum,	904
643.	White and yellow yelk,	904
*644.	Hen's egg (*Kölliker*),	905
*645.	Mucous membrane of the uterus (*Hart and Barbour, after Turner*),	905
*646.	Fallopian tube and its annexes (*Henle*),	905
*647.	Section of Fallopian tube (*Schenk*),	906
*648.	Uterus before menstruation (*J. Williams*),	907
*649.	Uterus after menstruation (*J. Williams*),	907
650.	Fresh corpus luteum,	908
651.	Corpus luteum of a cow,	908
652.	Lutein cells,	908
*653.	Erectile tissue (*Cadiat*),	909
654.	The urethra and adjoining muscles,	910
*655.	Formation of polar globules,	913
656.	Extrusion of a polar globule,	913
657.	Polar globules, male and female pronucleus,	914
*658.	Segmentation of a rabbit's ovum (*Quain, after v. Beneden*),	914
659.	Cleavage of the yelk,	914
*660.	Blastodermic vesicle of rabbit *Quain, after v. Beneden*),	915
661.	The blastoderm,	915
*662.	Primitive streak (*Balfour*),	916
*663.	Transverse section of an embryo newt (*Hertwig*),	916
*664.	Vertical section of a blastoderm (*Klein*),	917
665.	Schemata of development,	918
*666.	Embryo fowl, 2d day (*Kölliker*),	919
*667.	Transverse section of an embryo duck (*Balfour*),	920
*668.	Uterine mucous membrane (*Coste*),	925
*669.	Placental villi (*Cadiat*),	926
*670.	Fœtal circulation (*Clelana*),	928
*671.	Head of embryo rabbit (*Kölliker*),	931
672.	Hare lip,	931
*673.	Meckel's cartilage (*W. K. Parker*),	931
674.	Centres of ossification in the innominate bone,	933
675.	Development of the heart,	935
676.	The aortic arches,	936
677.	Veins of the embryo,	936
678.	Development of the veins and portal system,	937
679.	Development of the intestine,	938
680.	Development of the lungs,	938
681.	Formation of the omentum,	938
682.	Development of the internal generative organs,	939
*683.	Development of ova (*Wiedersheim*),	940
684.	Development of the external genitals,	942
*685. *686. *687. *688.	Changes in the external organs of generation in the female (*after Schroeder*),	942 942 942 942
*689.	Transverse section of an embryo brain (*Kölliker*),	943
*690.	Embryo brain of fowl (*Quain, after Mihalkowics*),	944
691.	Development of the eye,	945
*692.	Development of the vertebrate ear (*Haddon*),	945

[The illustrations indicated by the word *Hermann*, are from Hermann's *Handbuch der Physiologie;* by *Cadiat*, from Cadiat's *Traité d'Anatomie Générale*; by *Ranvier*, from Ranvier's *Traité Technique d'Histologie;* by *Brunton*, from Brunton's *Text-book of Pharmacology, Therapeutics, and Materia Medica;* by *Schenk*, from Schenk's *Grundriss der normalen Histologie;* by *Ecker*, from Ecker's *Anatomie des Frosches*, 2d ed.; by *Quain*, from *Quain's Anatomy;* by *Stöhr*, from Stöhr's *Lehrbuch der Histologie*, Jena, 1887; by *Obersteiner*, from H. Obersteiner's *Anleitung beim Studium des Baues der nervösen Centralorgane*, Wien, 1888.]

INTRODUCTION.

THE SCOPE OF PHYSIOLOGY AND ITS RELATIONS TO OTHER BRANCHES OF NATURAL SCIENCE.

PHYSIOLOGY is the science of the vital phenomena of organisms, or, broadly, it is the Doctrine of Life. Correspondingly to the divisions of organisms, we distinguish—(1) *Animal Physiology;* (2) *Vegetable Physiology;* and (3) the *Physiology of the Lowest Living Organisms*, which stand on the border line of animals and plants, *i. e.*, the so-called *Protistæ* of Haeckel, micro-organisms, and those elementary organisms or *cells* which exist on the same level.

The object of Physiology is to establish these phenomena, to determine their regularity and causes, and to refer them to the general fundamental laws of Natural Science, viz., the Laws of Physics and of Chemistry.

The following Scheme shows the relation of Physiology to the allied branches of Natural Science:—

BIOLOGY.

The science of organized beings or organisms (animals, plants, protistæ, and elementary organisms).

I. Morphology.

The doctrine of the **form** of organisms.

General Morphology.	Special Morphology.
The doctrine of the formed elementary constituents of organisms.	The doctrine of the *parts* and *organs* of organisms.
(**Histology**)—	(**Organology—Anatomy**)—
(*a*) Histology of Plants.	(*a*) **Phytotomy.**
(*b*) Histology of Animals.	(*b*) **Zootomy.**

II. Physiology.

The doctrine of the **vital phenomena** of organisms.

General Physiology.	Special Physiology.
The doctrine of vital phenomena in general—	The doctrine of the activities of the individual organs—
(*a*) Of Plants.	(*a*) Of Plants.
(*b*) Of Animals.	(*b*) Of Animals.

III. Embryology.

The doctrine of the **generation** and **development** of organisms.

Morphological part of the doctrine of development, *i. e.*, the doctrine of *form* in its stages of development—
(*a*) General.
(*b*) Special.

1. History of the development of *single* beings, of the individual (*e. g.*, of man) from the ovum onward (**Ontogeny**)—
   (*a*) In Plants.
   (*b*) In Animals.
2. History of the development of a *whole stock* of organisms from the lowest forms of the series upward (**Phylogeny**)—
   (*a*) In Plants.
   (*b*) In Animals.

Physiological part of the doctrine of development, *i. e.*, the doctrine of the *activity* during development—
(*a*) General.
(*b*) Special.

Morphology and **Physiology** are of equal rank in biological science, and a previous acquaintance with Morphology is assumed as a basis for the comprehen-

sion of Physiology, since the work of an organ can only be properly understood when its external form and its internal arrangements are known. **Development** occupies a middle place between Morphology and Physiology; it is a morphological discipline in so far as it is concerned with the description of the parts of the developing organism; it is a physiological doctrine in so far as it studies the *activities* and *vital phenomena* during the course of development.

MATTER.—The entire visible world, including all organisms, consists of matter, *i. e.*, of substance which occupies space.

We distinguish *ponderable* matter which has weight, and *imponderable* matter which cannot be weighed in a balance. The latter is generally termed *ether*.

In ponderable materials, again, we distinguish their *form, i.e.*, the nature of their limiting surfaces; further, their *volume, i. e.*, the amount of space which they occupy; and lastly, their *aggregate condition, i. e.*, whether they are solid, fluid, or gaseous bodies.

Ether.—The ether fills the space of the universe, certainly as far as the most distant visible stars. This ether, notwithstanding its imponderability, possesses distinct mechanical properties; it is infinitely more attenuated than any known kind of gas, and behaves more like a solid body than a gas, resembling a gelatinous mass rather than the air. It participates in the luminous phenomena due to the vibrations of the atoms of the fixed stars, and hence it is the transmitter of light, which is conducted by means of its vibrations, with inconceivable rapidity (42,220 geographical miles per second), to our visual organs (*Tyndall*).

Imponderable matter (ether) and ponderable matter are not separated sharply from each other; rather does the ether penetrate into all the spaces existing between the smallest particles of ponderable matter.

Particles.—Supposing that ponderable matter were to be subdivided continuously into smaller and smaller portions, until we reach the last stage of division in which it is possible to recognize the *aggregate* condition of the matter operated upon, we should call the finely-divided portions of matter in this state *particles*. Particles of iron would still be recognized as *solid*, particles of water as *fluid*, particles of oxygen as *gaseous*.

Molecules.—Supposing, however, the process of division of the particles to be carried further still, we should at last reach a limit, beyond which, neither by mechanical nor by physical means, could any further division be effected. We should have arrived at the *molecules*. A molecule, therefore, is the smallest amount of matter which can still exist in a free condition, and which as a unit no longer exhibits the *aggregate* condition.

Atoms.—But even molecules are not the final units of matter, since every molecule consists of a group of smaller units, called *atoms*. An atom cannot exist by itself in a free condition, but the atoms unite with other similar or dissimilar atoms to form groups, which are called molecules. Atoms are incapable of further subdivision, hence their name. We assume that the atoms are invariably of the same size, and that they are solid. From a chemical point of view, the atom of an elementary body (element) is the smallest amount of the element which can enter into a chemical combination. Just as ponderable matter consists in its ultimate parts of ponderable atoms, so does the ether consist of analogous small ether-atoms.

Ponderable and Imponderable Atoms.—The ponderable atoms within ponderable matter are arranged in a definite relation to the ether-atoms. The ponderable atoms mutually attract each other, and similarly they attract the imponderable ether-atoms; but the ether-atoms repel each other. Hence, in ponderable masses, ether-atoms surround every ponderable atom. These masses, in virtue of the attraction of the ponderable atoms, tend to come together, but only to the extent permitted by the surrounding ether-atoms. Thus the ponderable atoms can never come so close as not to leave interspaces. All matter must,

therefore, be regarded as more or less loose and open in texture, a condition due to the interpenetrating ether-atoms, which resist the direct contact of the ponderable atoms.

Aggregate Condition of Atoms.—The relative arrangement of the molecules, *i. e.*, the smallest particles of matter which can be isolated in a free condition, determines the aggregate condition of the body.

Within a **solid** body, characterized by the permanence of its volume as well as by the independence of its form, the molecules are so arranged that they cannot readily be displaced from their relative positions.

Fluid bodies, although their volume is permanent, readily change their shape, and their molecules are in a condition of continual movement.

When this movement of the molecules takes so wide a range that the individual molecules fly apart, the body becomes **gaseous,** and as such is characterized by the instability of its form as well as by the changeableness of its volume.

Physics is the study of these molecules and their motions.

FORCES.

1. Gravitation—Work done.—All phenomena appertain to matter. These phenomena are the appreciable expression of the forces inherent in matter. The forces themselves are not appreciable, they are the causes of the phenomena.

Gravitation.—The law of gravitation postulates that every particle of ponderable matter in the universe attracts every other particle with a certain force. This force is inversely as the square of the distance. Further, the attractive force is directly proportional to the amount of the attracting matter, without any reference to the quality of the body. We may estimate the intensity of gravitation by the extent of the movement which it communicates to a body allowed to fall, for one second, through a given distance, in a space free from air. Such a body will fall *in vacuo* 9.809 metres per second. This fact has been arrived at experimentally.

Let us represent $g = 9.809$ metres, the final velocity of the freely falling body at the end of one second. The velocity, V, of the freely falling body is proportional to the time, t, so that

$$V = gt \quad \ldots\ldots\ldots\ldots\ldots\ldots (1);$$

i. e., at the end of the 1st sec., and $V = g$, $1 = g = 9.809$ M—the distance traversed—

$$s = \frac{g}{2} t^2 \quad \ldots\ldots\ldots\ldots\ldots\ldots (2):$$

i. e., the distances are as the square of the times. Hence, from (1) and (2) it follows (by eliminating t) that—

$$V = \sqrt{2gs} \quad \ldots\ldots\ldots\ldots\ldots\ldots (3).$$

The velocities are as the square roots of the distances traversed—

Therefore

$$\frac{V^2}{2g} = s \quad \ldots\ldots\ldots\ldots\ldots\ldots (4).$$

The freely falling body, and in fact every freely moving body, possesses **kinetic energy,** and is in a certain sense a magazine of energy. The kinetic energy of any moving body is always equal to the product of its weight (estimated by the balance), and the height to which it would rise from the earth, if it were thrown from the earth with its own velocity.

Let W represent the kinetic energy of the moving body, and P its weight, then $W = P.\ s$, so that from (4) it follows that—

$$W = P \frac{V}{2g} \quad \ldots\ldots\ldots\ldots\ldots\ldots (5).$$

Hence, the kinetic energy of a body is proportional to the square of its velocity.

Work.—If a force (pressure, strain, tension) be so applied to a body as to move it, a certain amount of *work* is performed. The amount of work is equal

to the product of the amount of the pressure or strain which moves the body, and of the distance through which it is moved.

Let K represent the force acting on the body, and S the distance, then the work W = KS. The attraction between the earth and any body raised above it is a source of work.

It is usual to express the value of K in kilogrammes, and S in metres, so that the "**unit of work**" is the **kilogramme-metre**, *i. e.*, the force which is required to raise 1 kilo. to the height of 1 metre.

2. Potential Energy.—*The transformation of Potential into Kinetic Energy, and conversely:* Besides kinetic energy, there is also "potential energy," or energy of position. By this term are meant various forms of energy, which are suspended in their action, and which, although they may *cause* motion, are not in themselves motion. A coiled watch-spring kept in this position, a stone resting upon a tower, are instances of bodies possessing potential energy, or the energy of position. It requires merely a push to develop kinetic from the potential energy, or to transform potential into kinetic energy.

Work, w, was performed in raising the stone to rest upon the tower.

$w = p, s$, where p = the weight and s = the height,
$p = m. g$, is = the product of the mass (m), and the force of gravity (g), so that $w = m\,g\,s$.

This is at the same time the expression for the potential energy of the stone. This potential energy may readily be transformed into kinetic energy by merely pushing the stone so that it falls from the tower. The kinetic energy of the stone is equal to the final velocity with which it impinges upon the earth.

$$\begin{aligned} V &= \sqrt{2g\,s} \text{ (see above (3)).} \\ V^2 &= 2g\,s. \\ mV^2 &= 2m\,g\,s. \\ \frac{m}{2}V^2 &= m\,g\,s. \end{aligned}$$

$m\,g\,s$ was the expression for the potential energy of the stone while it was still resting on the height; $\frac{m}{2}V_2$ is the kinetic energy corresponding to this potential energy (*Brücke*).

Potential energy may be transformed into mechanical energy under the most varied conditions; it may also be transferred from one body to another.

The movement of a pendulum is a striking example of the former. When the pendulum is at the highest point of its excursion, it must be regarded as absolutely at rest for an instant, and as endowed with potential energy, thus corresponding with the raised stone in the previous instance. During the swing of the pendulum this potential energy is changed into kinetic energy, which is greatest when the pendulum is moving most rapidly toward the vertical. As it rises again from the vertical position, it moves more slowly, and the kinetic energy is changed into potential energy, which once more reaches its maximum when the pendulum comes to rest at the utmost limit of its excursion. Were it not for the resistances continually opposed to its movements, such as the resistance of the air and friction, the movement of the pendulum, due to the alternating change of kinetic into potential energy and *vice versâ*, would continue uninterruptedly, as with a mathematical pendulum. Suppose the swinging ball of the pendulum, when exactly in a vertical position, impinged upon a resting but movable sphere, the potential energy of the ball of the pendulum would be transferred directly to the sphere, provided that the elasticity of the ball of the pendulum and the sphere were complete; the pendulum would come to rest, while the sphere would move onward with an equal amount of kinetic energy, provided there were no resistance to its movement. This is an example of the transference of kinetic energy from one body to another. Lastly, suppose that a stretched watch-spring on uncoiling causes another spring to become coiled; and we have another example of the transference of kinetic energy from one body to another.

The following general statement is deducible from the foregoing examples: If, in a system, the individual moving masses approach the final position of equilibrium, then in this system the sum of the *kinetic* energies increases; if, on the other hand, the particles move away from the final position of equilibrium, then

the sum of the *potential* energies is increased at the expense of the kinetic energies, *i. e.*, the *kinetic* energies diminish (*Brücke*).

The pendulum, which, after swinging from the highest point of its excursion, approaches the vertical position, *i. e.*, the position of equilibrium of a passive pendulum, has in this position the largest amount of potential energy; as it again ascends to the highest point of its excursion on the other side, it again gradually receives the maximum of potential energy at the expense of the gradually diminishing movement, and therefore of the kinetic energy.

3. **Heat.**—*Its Relation to Potential and Kinetic Energy.*—If a lead weight be thrown from a high tower to the earth, and if it strike an unyielding substance, the movement of the mass of lead is not only arrested, but the kinetic energy (which to the eye appears to be lost) is transformed into a lively vibratory movement of the atoms. When the lead meets the earth, heat is produced. The amount of heat produced is proportional to the kinetic energy which is transformed through the concussion. At the moment when the lead weight reaches the earth, the atoms are thrown into vibrations; they impinge upon each other; then rebound again from each other in consequence of their elasticity, which opposes their direct juxtaposition; they fly asunder to the maximum extent permitted by the attractive force of the ponderable atoms, and thus oscillate to and fro. All the atoms vibrate like a pendulum, until their movement is communicated to the ethereal atoms surrounding them on every side, *i. e.*, until the heat of the heated mass is "*radiated.*" *Heat is thus a vibratory movement of the atoms.*

As the amount of heat produced is proportional to the kinetic energy which is transformed through the concussion, we must find an adequate measure for both forces.

Heat-Unit.—As a standard of measure of heat, we have the "heat-unit" or **calorie.** The "heat-unit" or calorie is the amount of energy required to raise the temperature of 1 gramme of water 1° Centigrade. The "heat-unit" corresponds to 425.5 gramme-metres, *i. e.*, the same energy required to heat 1 gramme of water 1° C. would raise a weight of 425.5 grammes to the height of 1 metre; or, a weight of 425.5 grammes, if allowed to fall from the height of 1 metre, would by its concussion produce as much heat as would raise the temperature of 1 gramme of water 1° C. The "**mechanical equivalent**" of the heat-unit is, therefore, 425.5 gramme-metres.

It is evident that from the collision of moving masses an immeasurable amount of heat can be produced. Let us apply what has already been said to the earth. Suppose the earth to be disturbed in its orbit, and suppose further that, owing to the attraction of the sun, it were to impinge on the latter (whereby, according to J. R. Mayer, its final velocity would be 85 geographical miles per second), the amount of heat produced by the collision would be equal to that produced by the combustion of a mass of pure charcoal more than 5000 times as heavy (*Julius Robert Mayer, Helmholtz*).

Thus, the heat of the sun itself can be produced by the collision of masses of cold matter. If the cold matter of the universe were thrown into space, and there left to the attraction of its particles, the collision of these particles would ultimately produce the light of the stars. At the present time, numerous cosmic bodies collide in space, while innumerable small meteors (94,000 to 188,000 billions of kilos. per minute) fall into the sun. The force of gravity is perhaps, in fact, the only source of all heat (*J. R. Mayer, Tyndall*).

We have a homely example of the transformation of kinetic energy into heat in the fact that a blacksmith may make a piece of iron red hot by hammering it. Of the conversion of heat into kinetic energy we have an example in the hot watery vapor (steam) of the steam engine raising the piston. An example of the conversion of potential energy into heat occurs in a metallic spring, when it uncoils and is so placed as to rub against a rough surface, producing heat by friction.

4. **Chemical Affinity: Relation to Heat.**—While gravity acts upon the particles of matter without reference to the composition of the body, there is another atomic force which acts between atoms of a chemically different nature; this is **chemical affinity.** This is the force in virtue of which the atoms of chemically different bodies unite to form a **chemical compound.** The force itself varies greatly between the atoms of different chemical bodies; thus we speak

of strong chemical affinities and weak affinities. Just as we were able to estimate the potential energy of a body in motion from the amount of heat which was produced when it collided with an unyielding body, so we can measure the amount of heat which is formed when the atoms of chemically different bodies unite to form a chemical compound. As a rule, heat is formed when separate chemically-different atoms form a compound body. When, in virtue of chemical affinity, the atoms of 1 kilo. of hydrogen and 8 kilos. of oxygen unite to form the chemical compound *water*, an amount of heat is thereby evolved which is equal to that produced by a weight of 47,000 kilos. falling and colliding with the earth from a height of 1000 feet above the surface of the earth. If 1 gramme of H be burned along with the requisite amount of O to form water, it yields 34,460 heat-units or calories: and 1 gramme carbon burned to carbonic acid (carbon dioxide) yields 8080 heat-units. *Wherever, in chemical processes, strong chemical affinities are satisfied, heat is set free, i. e.*, chemical affinity is changed into heat. Chemical affinity is a form of potential energy obtaining between the most different atoms, which during chemical processes is changed into heat. Conversely, in those chemical processes where strong affinities are dissolved, and chemically-united atoms thereby pulled asunder, there must be a diminution of temperature, or, as it is said, *heat becomes latent*—that is, the energy of the heat which has become latent is changed into chemical energy, and this, after decomposition of the compound chemical body, is again represented by the chemical affinity between its isolated different atoms.

LAW OF THE CONSERVATION OF ENERGY.—Julius Robert Mayer and Helmholtz have established the important law that, in a system which does not receive any influence and impression from without, the sum of all the forces acting within it is always the same. *The various forms of energy can be transformed one into the other, so that kinetic energy may be transformed into potential energy and vice versâ, but there is never any part of the energy lost.* The transformation takes place in such measure that, from a certain definite amount of one form of energy a definite amount of another can be obtained.

The various **forms of energy** acting in organisms occur in the following modifications:—

1. **Molar motion** (ordinary movements), as in the movements of the whole body, of the limbs, or of the intestines, and even those observable microscopically in connection with cells.

2. **Movements of Atoms as Heat.**—We know, in connection with the vibration of atoms, that the number of vibrations in the unit of time determines whether the oscillations appear as heat, light, or chemically-active vibrations. Heat-vibrations have the smallest number, while chemically-active vibrations have the largest number, light-vibrations standing between the two. In the human body we only observe heat-vibrations, but some of the lower animals are capable of exhibiting the phenomena of light.

In the human organism the molar movements in the individual organs are constantly being transformed into heat, *e.g.*, the kinetic energy in the organs of the circulation is transformed by friction into heat. The measure of this is the "**unit of work**" = 1 gramme-metre, and the "**unit of heat**" = 425.5 gramme-metres.

3. **Potential Energy.**—The organism contains many chemical compounds which are characterized by the great complexity of their constitution, by the imperfect saturation of their affinities, and hence by their great tendency to split up into simpler bodies.

The body can transform the potential energy into heat as well as into kinetic energy, the latter always in conjunction with the former, but the former always by itself alone. *The simplest measure of the potential energy is the amount of heat* which can be obtained by complete combustion of the chemical compounds

representing the potential energy. The number of work-units can then be calculated from the amount of heat produced.

4. The phenomena of **electricity, magnetism,** and **diamagnetism** may be recognized in two directions, as movements of the smallest particles, which are recognized in the glowing of a thin wire when it is traversed by strong electrical currents (against considerable resistance), and also as molar movement, as in the attraction or repulsion of the magnetic needle. Electrical phenomena are manifested in our bodies by muscle, nerve, and glands, but these phenomena are relatively small in amount when compared with the other forms of energy. It is not improbable that the electrical phenomena of our bodies become almost completely transformed into heat. As yet experiment has not determined with accuracy "a unit of electricity" directly comparable with the "heat-unit" and the "work-unit."

It is quite certain that within the organism one form of energy can be transformed into another form, and that a certain amount of one form will yield a definite amount of another form; further, that new energy never arises spontaneously, nor is energy already present ever destroyed, so that in the organism the law of the conservation of energy is continually in action.

ANIMALS AND PLANTS.—The animal body contains a quantity of chemically-potential energy stored up in its constituents. The total amount of the energy present in the human body might be measured by burning completely an entire human body in a *calorimeter*, and thereby determining how many heat-units are produced when it is reduced to ashes (see *Animal Heat*).

The chemical compounds containing the potential energy are characterized by the complicated relative position of their atoms, by a comparatively imperfect saturation of the affinities of their atoms, by the relatively small amount of oxygen which they contain, by their great tendency to decomposition, and the facility with which they undergo decomposition.

If a man were not supplied with food he would lose 50 grammes of his body weight every hour; the material part of his body, which contains the potential energy, is used up, oxygen is absorbed, and a continual process of combustion takes place; by the process of combustion simpler substances are formed from the more complex compounds, whereby potential is converted into kinetic energy. It is immaterial whether the combustion is rapid or slow; the same amount of the same chemical substances always produces the same amonnt of kinetic energy, *i.e.*, of heat.

A person, when fasting, experiences after a certain time the disagreeable feeling of exhaustion of his reserve of potential energy, hunger sets in, and he takes food. *All food for the animal kingdom is obtained, either directly or indirectly, from the vegetable kingdom.* Even carnivora, which eat the flesh of other animals, only eat organized matter which has been formed from vegetable food. The existence of the animal kingdom presupposes the existence of the vegetable kingdom.

All substances, therefore, necessary for the food of animals occur in vegetables. Besides **water** and the **inorganic constituents,** plants contain, among other organic compounds, the following *three chief representatives of food-stuffs*—**fats, carbohydrates,** and **proteids.**

All these contain stores of potential energy, in virtue of their complex chemical constitution.

The **fats** contain:— $\left\{\begin{array}{l} C_nH_{2n-1}O(OH) = \text{fatty acids} \\ + C_3H_5(OH)_3 = \text{glycerin} \end{array}\right\}$ (§ 251).

The **carbohydrates** contain:—$C_6H_{10}O_5$ . . (§ 252).

The **proteids** contain per cent.:— $\left\{\begin{array}{l} \text{C. } 51.5\text{–}54.5 \\ \text{H. } 6.9\text{–} 7.3 \\ \text{N. } 15.2\text{–}17.0 \\ \text{O. } 20.9\text{–}23.5 \\ \text{S. } 0.3\text{–} 2.0 \end{array}\right\}$ (§§ 248 and 249).

A man who takes a certain amount of this food adds thereto **oxygen** from the air in the process of respiration. Combustion or oxidation then takes place, whereby chemically-potential energy is transformed into heat.

It is evident that the products of this combustion must be bodies of simpler constitution—bodies with less complex arrangement of their atoms, with the greatest possible saturation of the affinities of their atoms, of greater stability, partly rich in O, and possessing either no potential energy, or only very little. These bodies are **carbon dioxide**, CO_2; **water**, H_2O; and as the chief representative of the nitrogenous excreta, **urea** ($CO(NH_2)_2$), which has still a small amount of potential energy, but which outside the body readily splits into CO_2 and ammonia (NH_3).

The human body is an organism in which, by the phenomena of oxidation, the complex nutritive materials of the vegetable kingdom, which are highly charged with potential energy, are transformed into simple chemical bodies, whereby the potential energy is transformed into the equivalent amount of kinetic energy (heat, work, electrical phenomena).

But how do plants form these complex food-stuffs so rich in potential energy? It is plain that the potential energy of plants must be obtained from some other form of energy. This potential energy is supplied to plants by the **rays of the sun**, whose chemical light-rays are absorbed by plants. Without the rays of the sun there could be no plants. Plants absorb from the air and the soil CO_2, H_2O, NH_3, and N, of which carbon dioxide, water, and ammonia (from urea) are also produced by the excreta of animals. *Plants absorb the kinetic energy of light from the sun's rays and transform it into potential energy*, which is accumulated during the growth of the plant in its tissues, and in the food-stuffs produced in them during their growth. This formation of complex chemical compounds is accompanied by the simultaneous excretion of O.

Occasionally, kinetic energy, such as we universally meet with in animals, is liberated in plants. Many plants develop considerable quantities of heat in their flowers, *e.g.*, the arum tribe. We must also remember that during the formation of the solid parts of plants, when fluid juices are changed into solid masses, heat is set free. In plants, under certain circumstances, O is absorbed, and CO_2 is excreted, but these processes are so trivial as compared with the typical condition in the vegetable kingdom, that they may be regarded as of small moment.

Plants, therefore, are organisms which, by a reduction process, transform simple stable combinations into complex compounds, whereby potential solar energy is transformed into the chemically-potential energy of vegetable tissues. **Animals** are living beings, which by oxidation decompose or break up the complex grouping of atoms manufactured by plants, whereby potential is transformed into kinetic energy. Thus, there is a constant circulation of matter and a constant exchange of energy between plants and animals. All the energy of animals is derived from plants. All the energy of plants arises from the sun. Thus the sun is the cause, the original source of all energy in the organism, *i. e.*, of the whole of life.

As the formation of solar heat and solar light is explicable by the gravitation of masses, gravity is *perhaps* the original form of energy of all life.

We may thus represent the formation of kinetic energy in the animal body from the potential energy of plants. Let us suppose the atoms of the substances formed in organisms, as simple small bodies, balls, or blocks. As long as these lie in a single layer, or in a few layers, upon the surface, there is a stable arrangement, and they continue to remain at rest. If, however, an artificial tower be built of these blocks, so that an unstable erection is produced, and the same tower be afterward knocked down, then for this purpose we require (1) the motor power of the workman who lifts and carries the blocks; (2) a blow or other impulse from without applied to the unstable structure—when the atoms will fall together, and as they fall collide with each other and produce heat. Thus, the

energy employed by the workman is again transformed into the last-named form of energy.

In plants the complex unstable building of the groups of atoms is carried on, the constructer being the sun. In animals, which eat plants, the complex groups of the atoms are tumbled down, with the liberation of kinetic energy.

Vital Energy and Life.—The forces which act in organisms, in plants, and animals are exactly the same as are recognizable as acting in dead matter. A so-called "vital force," as a special force of a peculiar kind, causing and governing the vital phenomena of living beings, does not exist. The forces of all matter, of organized as well as unorganized, exist in connection with their smallest particles or atoms. As, however, the smallest particles of organized matter are, for the most part, arranged in a very complicated way, compared with the much simpler composition of inorganic bodies, so the forces of the organism connected with the smallest particles yield more complicated phenomena and combinations, whereby it is excessively difficult to ascribe the vital phenomena in organisms to the simple fundamental laws of physics and chemistry.

The Exchange of Material, or Metabolism (*"Stoffwechsel"*) *as a Sign of Life.*—Nevertheless, there appears to be a special exchange of matter and energy peculiar to living beings. This consists in the capacity of organisms to assimilate the matter of their surroundings, and to work it up into their own constitution, so that it forms for a time an integral part of the living being, to be given off again. The whole series of phenomena is called **metabolism** or **"Stoffwechsel,"** which consists in the introduction, assimilation, integration, and excretion of matter.

We have already shown that the metabolism of plants and that of animals are quite different. The processes, as already described, actually occur in the typical higher plants and animals.

But there is a large group of organisms which, throughout their entire organization, exhibit so low a degree of development, that by some observers they are considered as undifferentiated "ground-forms." They are regarded as neither plants nor animals, and are the most simple forms of animated matter. Haeckel has called these organisms **Protistæ**, as being the original and primitive forms.

We must assume that, corresponding with their simpler vital conditions, their metabolism is also simpler, but on this point we still require further observations and experiments.

PHYSIOLOGY OF THE BLOOD.

[THE blood is aptly described by Claude Bernard as an **internal medium** which acts as a "go-between" or **medium of exchange** for the outer world and the tissues. Into it are poured those substances which have been subjected to the action of the digestive fluids, and in the lungs or other respiratory organs it receives oxygen. It thus contains *new* substances, but in its passage through the tissues it gives up some of these new substances, and receives in exchange certain **waste products** which have to be got rid of. Its composition is thus highly complex. Besides carrying the *new* nutrient fluids *to* the tissues, it is also the great **oxygen carrier,** as well as the medium by which some of the waste products, *e. g.*, CO_2, urea, are removed *from* the tissues, and brought to the organs, *e. g.*, the lungs, kidneys, skin, which eliminate them from the body. It is at once a great pabulum-supplying medium and a channel for getting rid of useless materials. As the composition of the organs through which the blood flows varies, it is evident that its composition must vary in different parts of the circulatory system; and it also varies in the same individual under different conditions. Still, with slight variations, there are certain general physical, histological, and chemical properties which characterize blood *as a whole.*]

1. **PHYSICAL PROPERTIES.**—(1) **Color.**—The color of blood varies from a bright scarlet-red in the arteries to a deep, dark, bluish-red in the veins. Oxygen (and, therefore, the air) makes the blood bright red; want of oxygen makes it dark. Blood free from oxygen (and also venous blood) is *dichroic—i. e.*, by reflected light it appears dark red, while by transmitted light it is green. [Arterial blood is monochroic.]

In thin layers blood is **opaque,** as is easily shown by shaking blood so as to form bubbles, or by allowing blood to fall upon a plate with a pattern on it, and pouring it off again. [Printed matter cannot be read through a thin layer of blood spread on a glass slide.] Blood behaves, therefore, like an "opaque color," as its coloring matter is suspended in the form of fine particles—the blood corpuscles.

Hence, it is possible to separate the coloring matter from the fluid part of the blood by filtration. This is accomplished by mixing the blood with fluids which render the blood corpuscles sticky or rough. If mammalian blood be treated with one-seventh of its volume of solution of sodic sulphate, or if frog's blood be mixed with a 2 per cent. solution of sugar (*Joh. Müller*) and filtered, the shriveled corpuscles, now robbed of part of their water, remain upon the filter.

(2) **Reaction.**—The reaction is alkaline, owing to the presence of disodic phosphate, Na_2HPO_4, and bicarbonate of soda. After blood is shed, its alkalinity rapidly diminishes, and this occurs more rapidly the greater the alkalinity of the blood. This is due to the formation of an acid, in which, perhaps, the colored corpuscles take part, owing to the decomposition of their coloring matter. A high temperature and the addition of an alkali favor the formation of the acid (*N. Zuntz*).

The alkaline reaction of blood is diminished: (*a*) by great muscular exertion, owing to the [illegible] of a large amount of acid in the muscles; (*β*) during coagulation; (*γ*) in old blood, or [illegible]ved by water from old blood stains, such blood being usually acid; fresh cruor has a

stronger alkaline reaction than serum; (δ) after the prolonged use of soda the alkalinity is increased, after the use of acids it is decreased.

Methods.—Owing to the color of the blood we cannot employ ordinary litmus paper to test its reaction. One of the following methods may be used: (1) Moisten a strip of glazed red litmus paper with solution of common salt, and allow a drop of blood to fall on the paper; then rapidly wipe it off before its coloring matter has time to penetrate and tinge the paper (*Zuntz*). (2) Liebreich used thin plates of plaster-of-Paris of a perfectly neutral reaction. These are dried, and afterward moistened with a neutral solution of litmus. When a drop of blood is placed upon the porous plate, the fluid part of the blood passes into it, while the corpuscles are washed off with water, and the altered color of the litmus-stained slab is apparent. [(3) Schäfer uses dry, faintly-reddened, glazed litmus paper, and on it is placed a drop of blood, which is wiped off after a few seconds. The place where the blood rested is indicated by a blue patch upon a red or violet ground.]

Estimation of the Alkalinity.—A very dilute solution of tartaric acid (1 cubic centimetre combines with 3.1 milligrams of soda, *i. e.*, 1 litre of water contains 7.5 grams of crystallized tartartic acid) is added to blood until a blue litmus paper is turned red (by Zuntz's method). 100 grams of rabbit's blood have an alkalinity corresponding to 150 milligrams of soda; the blood of carnivora to about 180 milligrams (*Lassar*), while 100 c.c. of normal human blood have an alkalinity equal to 260–300 milligrams of soda (*v. Jaksch*).

The following method can be used with a few drops of blood: To neutralize the blood, tartaric acid in the above concentration is used. Prepare the following mixture by mixing it with a concentrated solution of sodic sulphate, and then adding sodic sulphate until the mixture is completely saturated. I, 10 parts of solution of tartaric acid to 100 parts of concentrated sodic sulphate solution; II, 20 parts tartaric acid solution to 90 sodic sulphate solution; III contains these substances in the proportion of 30 to 80; IV, 40 to 70; V, 50 to 60; VI, 60 to 50; VII, 70 to 40; VIII, 80 to 30; IX, 90 to 20; and X, 100 to 10. Excess of sodic sulphate is present in all the flasks.

A known volume of the blood to be investigated is mixed with an equal volume of each of the mixtures, in a small tube, which is made by drawing out a glass tube 1 millimetre in diameter to a fine point. To calibrate this tube, suck up water, say, to the height of 8 mm., make a mark on the tube with a fine file, then suck up the water until its lower level corresponds with the mark. Again mark the upper limit of the water. To test the blood, suck a drop of the mixture I up to the level of the first mark on the glass pipette, and, after wiping its point, suck up an equal quantity of blood. Again clean the point of the pipette, and blow its contents into a watch glass; then mix, and test the reaction with sensitive violet-colored litmus paper. Proceed in the same way with the several mixtures, II to X, until the alkaline reaction disappears or the acid appears. The narrow strips of litmus paper are dipped into each of the mixtures, the corpuscles remain in the wetted part of the paper, while the fluid permeates further and shows the reaction. As a rule, the degree of alkalinity in human blood corresponds to VI. Human blood can be sucked directly from a small wound made by a needle, either by attaching an elastic tube or a small hypodermic syringe to the pipette (*Landois*).

Pathological.—The alkalinity is increased during persistent vomiting, and decreased in pronounced anæmia, cachexia, uræmia, rheumatism, high fever, diabetes, and cholera. [Immediately before death by cholera it may be acid (*Cantani*).]

(3) **Odor.**—Blood emits a peculiar odor, the halitus sanguinis, which differs in animals and man.

It depends upon the presence of volatile fatty acids. If concentrated sulphuric acid be added to blood, whereby the volatile fatty acids are set free from their combinations with alkalies, the characteristic odor, somewhat similar to that of butyric acid, becomes much more perceptible.

(4) **Taste.**—Blood has a saline taste, depending upon the salts dissolved in the fluid of the blood.

(5) **Specific Gravity.**—The specific gravity is 1056–1059 in man, 1051–1055 in woman; in children less. The specific gravity of the blood corpuscles is 1105, that of the plasma 1027. Hence the corpuscles tend to sink.

Clinical Method.—A thin glass tube is drawn out till it is of small calibre, and then bent at a right angle, and closed above with a caoutchouc cap. Press slightly on the caoutchouc cap, and suck up a drop of the freshly-drawn blood obtained by pricking the finger. The fine capillary tube is at once immersed in a solution of sodic sulphate, and a drop of the blood expressed into the saline solution. It is necessary to prepare several solutions of sodic sulphate with specific gravities varying from 1050–1070. The solution in which the corpuscles remain suspended indicates the specific gravity of the blood (*Roy, Landois*).

The drinking of water and hunger diminish the specific gravity temporarily, while thirst and the digestion of dry food raise it. If blood be passed through an organ artificially, its specific gravity

rises in consequence of the absorption of dissolved matters and the giving off of water. It falls after hemorrhage, and is diminished in badly-nourished individuals. [By working with solutions of glycerine, Jones finds that it is highest at birth, is at a minimum between the second week and the second year; it rises gradually until the 35th–45th year. It is usually higher in the male than the female, is diminished by pregnancy, the ingestion of solid or liquid food, and gentle exercise.]

[(6) **Temperature.**—Blood is viscid, and its temperature varies from 36.5° C. (97.7° F.) to 37.8° C. (100° F.). The warmest blood in the body is that of the hepatic vein (§ 210).]

2. MICROSCOPIC EXAMINATION.—[Blood, when examined by the microscope, is seen to consist of an enormous number of **corpuscles**—colored and colorless—floating in a transparent fluid, the **plasma**, or **liquor sanguinis.**

Human Red Blood Corpuscles.—(*a*) **Form.**—They are circular, coin-shaped, homogeneous disks, with saucer-like depressions on both surfaces, and with rounded margins; in other words, they are bi-concave, circular, non-nucleated disks.

FIG. 1.



A, human colored blood corpuscles—1, on the flat; 2, on edge; 3, rouleau of colored corpuscles. B, amphibian colored blood corpuscles—1, on the flat; 2, on edge. C, ideal transverse section of a human colored blood corpuscle magnified 5000 times linear—*ab*, diameter; *cd*, thickness.

(*b*) **Size.**—The diameter (*ab*) is 7.7μ,* (6.7–9.3μ) the greatest thickness (*cd*) 1.9μ (Fig. 1, C), [*i.e.*, it is $\frac{1}{3500}$ to $\frac{1}{3200}$ of an inch in diameter, and about one-fourth of that in thickness].

They are slightly **diminished** in size by septic fever, inanition, morphia, increased bodily temperature, and CO_2; and **increased** by O, watery condition of the blood, cold, consumption of alcohol, quinine, and hydrocyanic acid. *Compare* § 10, 3.

If the total amount of blood in a man be taken at 4400 cubic centimetres, the corpuscles therein contained have a surface of 2816 square metres, which is equal to a square surface with a side of 80 paces; 176 cubic centimetres of blood pass through the lungs in a second, and the blood corpuscles in this amount of blood have a superficies of 81 square metres, equal to a square surface with a side of 13 paces (*Welcker*).

(*c*) **The weight** of a blood corpuscle is 0·00008 milligramme.

(*d*) **The number** exceeds 5,000,000 per cubic millimetre in the male, and 4,500,000 in the female; so that, in 10 lbs. of blood, there are 25 billions of corpuscles. The number is in inverse ratio to the amount of plasma; hence, the number must vary with the state of contraction of the blood vessels, the pressure, diffusion currents, and other conditions.

* The Greek letter μ represents one-thousandth of a millimetre ($\mu = 0{\cdot}001$ mm.), and is the sign of a *micro-millimetre*, or a *micron*.

The number of red corpuscles is **increased**; in venous blood (especially in the small cutaneous veins), after the use of solid food, after much sweating, and the excretion of much water by the bowel and kidneys; during inanition, because the blood plasma undergoes decomposition sooner than the blood corpuscles themselves; in the blood of the newly-born child, especially when the umbilical cord is long in being tied (§ 40), from the 4th day onward the number is diminished; in persons of robust constitution, and in those who live in the country. The number is **diminished**, during pregnancy, after copious draughts of water. In the earlier period of fœtal life the number is only ½–1 million in 1 cubic millimetre. (For the **pathological conditions** see § 10.)

Methods of Counting the Blood Corpuscles.—The pointed end of a glass pipette (Fig. 3), the **mixer**, is dipped into the blood, and by sucking the elastic tube *f*, blood is drawn into the tube until it reaches the mark ½, on the stem of the pipette, or until the mark 1 is reached. The carefully-cleaned point of the pipette is dipped into the **artificial serum**, and this is sucked into the pipette

FIG. 2.



Apparatus of Abbé and Zeiss for counting the corpuscles. A, in section; C, surface view without cover-glass; B, microscopic appearance with the blood corpuscles.

FIG. 3.



The *Melangeur*, pipette or mixer.

until it reaches the mark, 101. The artificial serum consists of 1 vol. of solution of gum arabic (sp. gr. 1020) and 3 vols. of a solution of equal parts of sodic sulphate and sodic chloride (sp. gr. 1020). The process of mixing the two fluids is aided by the presence of a little glass ball (*a*) in the bulb of the pipette. If blood is sucked up to the mark ½, the strength of the mixture is 1 : 200; if to the mark 1, it is 1 : 100; a small drop of the mixture is allowed to run into the **counting chamber** of Abbé and Zeiss (Fig. 2). The first portions are not used, in order to obtain a uniform sample from the bulb of the pipette. This chamber consists of a glass receptacle 0.1 mm. deep, with its base divided into squares and cemented to a glass slide, the whole being covered with a thin covering glass. The space over each square $= \frac{1}{4000}$ cubic millimetre. Count, with the aid of a microscope, the number of blood corpuscles in each square, and the number found, multiplied by 4000, will give the number of blood corpuscles in 1 c.mm. This number, again, must be multiplied by 100 or 200, according as the blood was diluted 100 or 200 times. To ensure greater accuracy, it is well to count the number in *several* squares, and to take the mean of these.

[**Gowers' Method.**—"The **Hæmacytometer** (Fig. 4) consists of (1) a small pipette, which, when filled to the mark on its stem, holds exactly 995 cubic millimetres. It is furnished with an india-rubber tube and mouthpiece to facilitate filling and emptying. (2) A capillary tube marked to contain exactly 5 cubic millimetres, with india-rubber tube for filling, etc. (3) A small glass jar in which the dilution is made. (4) A glass stirrer for mixing the blood and solution in the glass jar. (5) A brass stage plate, carrying a glass slip, on which is a cell, $\frac{1}{5}$ of a millimetre deep. The bottom of this is divided into $\frac{1}{10}$ millimetre squares. Upon the top of the cell rests the cover-glass, which is kept in its place by the pressure of two springs proceeding from the ends of the stage plate." The diluting solution used is a solution of sodic sulphate in distilled water, sp. gr. 1025, or the following—sodic sulphate, 104 grains; acetic acid, 1 drachm; distilled water, 4 oz.

"995 cubic millimetres of the solution are placed in the mixing jar; 5 cubic millimetres of blood are drawn into the capillary tube from the puncture in the finger, and then blown into the solution. The two fluids are well mixed by rotating the stirrer between the thumb and finger, and a small drop of this dilution is placed in the centre of the cell, the covering glass gently put upon the cell, and secured by the two springs, and the plate placed upon the stage of the microscope. The lens is then focused for the squares. In a few minutes the corpuscles have sunk to the bottom of the cell, and are seen at rest on the squares. The number in ten squares is then counted, and this, multiplied by 10,000, gives the number in a cubic millimetre of blood."

FIG. 4.



Gowers' apparatus. A, pipette for measuring the diluting solution; B, capillary tube for measuring the blood; C, cell with divisions on the floor, mounted on a slide; D, vessel in which the dilution is made; E, glass stirrer; F, guarded spear-pointed needle.

To estimate the **colorless** corpuscles only, mix the blood with 10 parts 0·5 per cent. solution of acetic acid, which destroys all the red corpuscles. (*Thoma*).

(*e*) Red blood corpuscles are characterized by their great **elasticity, flexibility,** and **softness.** [The elastic property is shown by the extent to which red corpuscles while circulating may be distorted, and yet resume their original form as soon as the pressure is removed.]

3. HISTOLOGY OF THE HUMAN RED BLOOD CORPUSCLES.—When observed singly, human red blood corpuscles are bi-concave circular disks of a yellow color with a slight tinge of green; they seem to be devoid of an envelope, are certainly non-nucleated, and appear to be homogeneous throughout. Each corpuscle consists (1) of a framework, an exceedingly pale, transparent, soft protoplasm—the **stroma;** and (2) of the **red pigment,** or hæmoglobin, which impregnates the stroma, much as fluid passes into and is retained in the interstices of a bath sponge.

4. EFFECT OF REAGENTS.—(A) **On their Vital Phenomena.**—The blood corpuscles present in shed blood—or even in defibrinated blood, when it is reintroduced into the circulation—retain their vitality and functions undiminished. **Heat** acts powerfully on their vitality, for if blood be heated to 52° C., the vitality of the red corpuscles is destroyed. Mammalian blood may be kept for four or five days in a vessel under iced water, and still retain its functions; but if it be kept longer, and reintroduced into the circulation, the corpuscles rapidly break up—a proof that they have lost their vitality. The red corpuscles in freshly shed blood sometimes exhibit a peculiar mulberry-like appearance (Figs. 5, 6, *g*, *h*). [This is called **crenation** of the colored corpuscles. It occurs in cases of poisoning with Calabar bean; and also by the addition of a 2 per cent. solution of common salt.] The blood of many persons crenates spontaneously—a condition ascribed to an active contraction of the stroma, but it is doubtful if this is the cause. The red corpuscles of the embryo chick undergo active contraction.

FIG. 5.



Crenation of human red blood corpuscles.

(B) **On their external characters.**—(*a*) The **color** is changed by many gases. O makes blood scarlet, want of O renders it dark bluish-red, CO makes it cherry-red, NO violet-red. There is no difference between the shape of the corpuscles in arterial and venous blood. All reagents (*e. g.*, a concentrated solution of sodic sulphate), which cause great shrinking of the colored corpuscles, produce a very bright scarlet or brick-red color. The red color so produced is quite different from the scarlet-red of arterial blood. Reagents which render blood corpuscles globular darken the blood, *e.g.*, water.

[The contrast is very striking, if we compare blood to which a 10 per cent. solution of common salt has been added with blood to which water has been added. With reflected light the one is bright red, and the other a very dark, deep crimson, almost black.

(*b*) **Formation of Rouleaux.**—A very common phenomenon in shed blood is the tendency of the corpuscles to run into rouleaux (Fig. 1, A, 3).

Conditions that increase the coagulability of the blood favor this phenomenon, which is ascribed by Dogiel to the attraction of the disks and the formation of a sticky substance. [The cause of the formation of rouleaux is by no means clear. The corpuscles may be detached from each other by gently touching the cover-glass, but the rouleaux may re-form. Lister suggested that the surfaces of the corpuscles were so altered that they became adhesive. Norris made experiments with corks weighted with tacks or pins, so as to produce partial submersion of the cork disks. These disks rapidly cohere, owing to capillarity, and form rouleaux. If the disks be completely submerged they remain apart, as occurs with unaltered blood corpuscles within the blood vessels. If, however, the corpuscles be dipped in petroleum, and then placed in water, rouleaux are formed.] If reagents which cause the corpuscles to swell up be added to the blood, the corpuscles become globular and the rouleaux break up. According to E. Weber and Suchard, the uniting medium is not fibrin (although it may sometimes assume a fibrous form), but belongs to the peripheral layer of the corpuscles.

(*c*) **Changes of Form.**—The **discharge of a Leyden jar** causes the corpuscles to crenate, so that their surfaces are beset with coarse or fine projections (Fig. 6, *c*, *d*, *e*, *g*, *h*); it also causes the corpuscles to assume a spherical form (*i*, *i'*),

and they become smaller than normal. The corpuscles so altered are sticky, and run together like drops of oil, forming larger spheres. The prolonged action of the electrical spark causes the hæmoglobin to separate from the stroma (*k*), whereby the fluid part of the blood is reddened, while the stroma is recognizable only as a faint shadow (*l*). Similar forms are to be found in decomposing blood, as well as after the action of many other reagents. **Heat.**—When blood is heated,

FIG. 6.

Red blood corpuscles. *a*, *b*, normal human red corpuscles, the central depression more or less in focus; *c*, *d*, *e*, mulberry, and *g*, *h*, crenated forms; *k*, pale corpuscles decolorized by water; *l*, stroma; *f*, frog's blood corpuscle acted on by a strong saline solution.

on a warm stage, to 52° C. the corpuscles exhibit remarkable changes. Some of them become spherical, others biscuit-shaped; some are perforated, while in others small portions become detached and swim about in the surrounding fluid, a proof that heat destroys the histological individuality of the corpuscles. If the heat be continued, the corpuscles are ultimately dissolved (§ 10, 3).

Heat acts like the addition of a concentrated solution of **urea** to blood. If strong pressure be exerted upon a microscopic preparation, the blood corpuscles may break in pieces. The latter process is called **hæmocytotrypsis**, in contradistinction to that of solution of the corpuscles or **hæmocytolysis**.

If a finger moistened with blood be rapidly drawn across a warm slip of glass, so that the fluid dries rapidly, the corpuscles exhibit very remarkable shapes, showing their great ductility and softness.

Cytozoon—Gaule's Experiment.—A few drops of freshly-shed frog's blood are mixed with 5 c.c. of 0.6 per cent. solution of common salt, and the mixture defibrinated by shaking it along with a few c.c. of mercury. A drop of the defibrinated blood is examined on a hot stage (30°–32° C.) under a microscope, when a protoplasmic mass, the so-called "*Würmchen*," escapes with a lively movement from many corpuscles, and ultimately dissolves. Similar "cytozoa" were discovered by Gaule in the epithelium of the cornea, of the stomach and intestine, in connective tissue, in most of the large glands, and in the retina (frog, triton). In mammals also he found similar but smaller structures. Most probably these structures are parasitic in their nature, as suggested by Ray Lankester, who called the parasite **Drepanidium ranarum.**

[**Staining Reagents.**—Such reagents as magenta, picro-carmine, carmine, and many of the aniline dyes, stain the nucleus deeply when such is present, and although they must traverse the hæmoglobin to reach the nucleus, the hæmoglobin itself is not stained. When no nucleus is present, therefore, the corpuscles are not stained. Magenta causes one or more small spots or maculæ to appear on the edge of the corpuscles (Fig. 7, *a*). What its significance is, is entirely unknown. Normal saline solution (0.6 per cent. NaCl), tinged with methyl violet, is a good staining and preservative agent.]

[**Agitation with Mercury.**—If ox blood be shaken up with mercury for 7 or 8 hours, the corpuscles completely disappear, no trace of stroma or corpuscles being found in the fluid (*Meltzer and Welch*). The addition of pyrogallic acid (20 per cent.) potassic chlorate (6 per cent.), and silver nitrate (3 per cent.), completely prevents dissolution of the corpuscles, even though the shaking be kept up for fourteen days.]

If blood be mixed with concentrated gum solution, and if concentrated salt solution be added to it under the microscope, the corpuscles assume elongated forms. Similar forms are obtained by

mixing blood with an equal volume of gelatine at 36° C., allowing it to cool, and then making sections of the coagulated mass. The corpuscles may be broken up by pressing firmly on the cover-glass. In all these experiments no trace of an envelope around the corpuscles is observed. [An excellent reagent for "fixing" the blood corpuscles is either a dilute solution or the vapor of osmic acid.]

Conservation of the Corpuscles.—In investigating blood with the microscope for **forensic purposes**, it is necessary to have a solvent for the blood when it occurs as stains on a garment or instrument. Dried stains are dissolved by a concentrated, or a 30 per cent. solution of caustic

FIG. 7.

a, *b*, human red blood corpuscles; *a*, acted on by magenta; *b*, by tannic acid. The others are amphibian red blood corpuscles; *c*, *d*, *e*, effect of tannic acid; *f*, of dilute acetic acid; *g*, of dilute alcohol; *d*, by boracic acid.—*Stirling*.

potash, or with one of the preserving fluids. If the stain be softened with concentrated tartaric acid, colorless corpuscles are specially distinct (*Struwe*). Nevertheless, corpuscles are often *not* found in such stains. If the corpuscles have become very pale, their color may be improved by adding a solution of iodide of potassium, a saturated solution of picric acid, 20 per cent. pyrogallic acid, or 3 per cent. solution of silver nitrate.

5. STROMA—LAKE-COLORED BLOOD.—Many reagents cause the hæmoglobin to separate from the stroma. The hæmoglobin dissolves in the serum; the blood becomes dark red and **transparent**, as it contains its coloring matter in solution, and hence it is called "**lake-colored**" (*Rollett*). The aggregate condition of the hæmoglobin is not altered when the corpuscles are dissolved—it only changes its place, leaving the stroma and passing into the serum. Hence, the temperature of the blood is not lowered thereby.

Methods.—To obtain a large quantity of the **stroma for chemical purposes**, add 10 vols. of a solution of common salt (1 vol. concentrated solution, and 15 to 20 vols. of water) to 1 vol. of defibrinated blood, when the stromata are thrown down as a whitish precipitate.

For **microscopical purposes**, mix blood with an equal volume of a concentrated solution of sodic sulphate, and cautiously add a 1 per cent. solution of tartaric acid.

The following reagents cause a separation of the stroma from the hæmoglobin, and thus make blood transparent:—

(*a*) **Physical Agents.**—1. Heating the blood to 60° C. (*Schultze*); the temperature, however, varies for the blood of different animals. 2. Repeated freezing and thawing of the blood (*Rollett*). 3. Sparks from an electrical machine (but not after the addition of salts to the blood) (*Rollett*); the constant and induced currents (*Neumann*).

(*b*) **Chemically active Substances produced within the Body.**—4. Bile (*Hünefeld*), or bile salts (*Plattner, v. Dusch*). 5. Serum of other species or animals (*Landois*); thus dog's serum and frog's serum dissolve the blood corpuscles of the rabbit in a few minutes. 6. The addition of lake-colored blood of many species of animals (*Landois*).

(*c*) **Other Chemical Reagents.**—7. Water. 8. The vapor of chloroform (*Böttcher*); ether (*v. Wittich*); amyls, small quantities of alcohol (*Rollett*); thymol (*Marchand*); nitrobenzol, ethylic ether, aceton, petroleum ether, etc. (*L. Lewin*). 9. Antimoniuretted hydrogen, arseniuretted hydrogen; carbon bisulphide; boracic acid (2 per cent.) added to amphibian blood, causes the red mass (which also encloses the nucleus when such is present), the so-called **zooid**, to separate from the **œcoid** (Fig. 7, *d*). The zooid may shrink from the periphery of the corpuscle, or it may pass out of the corpuscle altogether (*Brücke*); Brücke regards the stroma in a certain sense as a house, in which the remainder of the substance of the corpuscle, the chief part endowed with vital phenomena, lives. 11. Strong solutions of acids dissolve the corpuscles; more dilute solutions cause precipitates in the hæmoglobin. This is easily seen with carbolic acid (*Hüls and Landois, Stirling and Rannie*). 12. Alkalies of moderate strength cause sudden solution. A ten per cent. solution of potash, placed at the edge of a cover-glass, shows the process of solution going on under the microscope. At first the corpuscles become globular, and so appear smaller, but afterward they burst like soda bubbles. [13. NH_4Cl injected into the blood causes vacuolation of the red corpuscles (*Bobritzky*). 14. Sodic salicylate, benzoate and colchicin, dissolve the red corpuscles (*N. Paton*).]

[**Tannic Acid.**—A freshly prepared solution of tannic acid has a remarkable effect on the colored blood corpuscles of man and animals—causing a separation of the hæmoglobin from the stroma (*W. Roberts*). The usual effect is to produce one or more granular buds of hæmoglobin on the side of the corpuscles (Fig. 7, *b*, *c*); more rarely the hæmoglobin collects around the nucleus, if such be present (Fig. 7, *d*), or is extruded, as shown in Fig. 7, *e*.]

[**Ammonium or Potassium Sulpho-cyanide** removes the hæmoglobin, and reveals a reticular structure—*intra-nuclear* plexus of fibrils (*Stirling and Rannie*).]

The **Amount of Gases** in the blood exercises an important influence on their solubility. The corpuscles of venous blood, which contains much CO_2, are more easily dissolved than those of arterial blood; while between both stands blood containing CO. When the gases are completely removed from the blood, it becomes lake-colored.

Salts increase the resistance of the corpuscles to physical means of solution, while they facilitate the action of chemical solvents.

If certain salts be added in substance to blood, they make blood lake-colored; potassic sulphocyanide, sodic chloride, etc. (*Kowalewsky*).

Resistance to Solvents.—The red blood corpuscles offer a certain degree of resistance to the action of solvents.

Method.—Mix a small drop of blood with an equal volume of a 3 per cent. solution of sodic chloride, and then add distilled water until all the colored corpuscles are dissolved. Fill the mixer (Fig. 3) up to the mark 1 with blood obtained by picking the finger, and blow this blood into an equal volume of a 3 per cent. solution of NaCl previously placed in a hollow in a glass slide. Mix the fluids, and the corpuscles will remain undissolved. By means of the pipette add distilled water, and go on doing so until all the corpuscles are dissolved; which is ascertained with the microscope. In normal blood, solution of the corpuscles occurs after 30 volumes of distilled water have been added to the blood (*Landois*).

There are some individuals whose blood is more soluble than that of others; their corpuscles are soft, and readily undergo changes. Many conditions, such as cholæmia, poisoning with substances which dissolve the corpuscles, and a markedly venous condition of the blood, affect the corpuscles. Interesting observations may be made on the blood in infectious diseases, hæmoglobinuria, and in cases of burning. In anæmia and fever, the capacity for resistance seems to be diminished.

6. FORM AND SIZE OF THE BLOOD CORPUSCLES OF ANIMALS.—All mammals (with the exception of the camel, llama, alpaca, and their allies), and the cyclostomata among fishes, *e.g.*, Petromyzon, possess circular, bi-concave, *non-nucleated*, disk-shaped corpuscles. Elliptical corpuscles without a nucleus are found in the above-named mammals, while all birds, reptiles, amphibians (Fig. 1, B, 1, 2), and fishes (except cyclostomata) have *nucleated*, elliptical, bi-convex corpuscles.

Size (μ = 0.001 Millimetre)

Of the Disk-shaped Corpuscles.	Of the Elliptical Corpuscles.	
	Short Diameter.	Long Diameter.
Elephant, ... 9.4 μ	Llama, ... 4.0 μ	8.0 μ
Man, ... 7.7 "	Dove, ... 6.5 "	14.7 "
Dog, ... 7.3 "	Frog, ... 15.7 "	22.3 "
Rabbit, ... 6.9 "	Triton, ... 19.5 "	29.3 "
Cat, ... 6.5 "	Proteus, ... 35.0 "	58.0 "
Sheep, ... 5.0 "		
Goat, ... 4.1 "		
Musk-deer, ... 2.5 "		

The corpuscles of Amphiuma are nearly one-third larger than those of Proteus (*Riddel*).

Among **vertebrates**, amphioxus has colorless blood. The large blood corpuscles of many **amphibia**, *e.g.*, amphiuma, are visible to the naked eye. The blood corpuscles of the frog contain, in addition to a nucleus, a nucleolus (*Auerbach*, *Ranvier*), [and the same is true of the colored corpuscles of the newt (*Stirling*). The nucleolus is revealed by acting on the corpuscles with dilute alcohol (1, alcohol; 2, water; Ranvier's "*alcool au tiers*" (Fig. 7, *g*.).] It is evident that the larger the blood corpuscles are, the smaller must be the number and total superficies of the corpuscles in a given volume of blood. In **birds**, however, the number is relatively larger than in

other classes of vertebrates, notwithstanding the larger size of their corpuscles; this, doubtless, has a relation to the very energetic metabolism that takes place in birds (*Malassez*). Among **mammals**, carnivora have more blood corpuscles than herbivora. Goat's blood contains 9,720,000 corpuscles per cubic millimetre; llama's, 13,000,000; bullfinches, 3,600,000; lizard's, 1,420,000; frog's, 404,000; and that of proteus, 36,000 (*Welcker*). In **hibernating** animals, the number diminishes from 7,000,000 to 2,000,000 per cubic millimetre. No relation exists between the size of the animal and that of its blood corpuscles.

The **invertebrata** generally have colorless blood, with colorless corpuscles; but the earth-worm, and the larva of the large gnats, etc., have red blood whose plasma contains hæmoglobin, while the blood corpuscles themselves are colorless. Many invertebrates possess red, violet, brown or green opalescent blood with colorless corpuscles (amœboid cells). In cephalopods, and some crabs, the blood is blue, owing to the presence of a coloring matter (**hæmocyanin**), which contains copper, and combines with O.

7. ORIGIN OF THE RED BLOOD CORPUSCLES.—(A) **During Embryonic Life.**—Blood corpuscles are developed in the fowl during the first days of embryonic life. [They appear in groups within the large branched cells of the mesoblast, in the vascular area of the blastoderm, outside the developing body of the chick, where they form the "**blood-islands**" of Pander. The mother-cells form an irregular network by the union of the processes of adjoining cells, and meantime the central masses split up, and the nuclei multiply. The small nucleated masses of protoplasm, which represent the blood corpuscles, acquire a reddish hue, while the surrounding protoplasm, and also that of the processes, becomes vacuolated or hollowed out, constituting a branching system of canals; the outer part of the cells remaining with their nuclei to form the walls of the future blood vessels. A fluid appears within this system of branched canals in which the corpuscles lie, and gradually a communication is established with the blood vessels developed in connection with the heart. According to Klein, the nuclei of the protoplasmic wall also proliferate, and give rise to new cells, which are washed away to form blood corpuscles.] At first the corpuscles exhibit amœboid movements, are devoid of pigment, nucleated, globular, larger and more irregular than the permanent corpuscles. They become colored, retain their nucleus, and are capable of undergoing multiplication by division; Remak observed all the stages of the process of *division*, which is best seen from the third to the fifth day of incubation. Increase by division also takes place in the larvæ of the salamander, triton and toad (*Flemming*); and during the intra-uterine life of a mammal, in the spleen, bone-marrow, the liver, and the circulating blood (*Bizzozero*).

Neumann found in the **liver** of the embryo protoplasmic cells containing red blood corpuscles. Cells, some with, others without, hæmoglobin, but with large nuclei, have been found. These cells increase by division, their nucleus shrivels, and they ultimately form blood corpuscles (*Löwit*) The **spleen** is also regarded as a centre of their formation, but this seems to be the case only during embryonic life (*Neumann*). Here the red corpuscles are said to arise from yellow, round, nucleated cells, which represent transition forms. Foa and Salvioli found red corpuscles forming endogenously within large, protoplasmic cells in **lymphatic glands.** In the later period of embryonic life, the characteristic non-nucleated corpuscles seem to be developed from the nucleated corpuscles. The nucleus becomes smaller and smaller, breaks up, and gradually disappears. In the human embryo at the fourth week, only nucleated corpuscles are found; at the third month their number is still $\frac{1}{4}$–$\frac{1}{8}$ of the total corpuscles, while at the end of fœtal life nucleated blood corpuscles are very rarely found. Of course, in animals with nucleated blood corpuscles, the nucleus of the embryonic blood corpuscles remains.

(B) **During Post-Embryonic Life.**—Kölliker assumed that in the tail of the tadpole capillaries are formed by the anastomoses of the processes of branched and radiating connective-tissue corpuscles. These corpuscles lose their nuclei and protoplasm, become hollowed out, join with neighboring capillaries, and thus

form new blood channels. J. Arnold and Golubew oppose this view, asserting that the blood capillaries in the tail of the tadpole give off solid buds at different places, which grow more and more into the surrounding tissues, and anastomose with each other; after their protoplasm and contents disappear they become hollow, and a branched system of capillaries is formed in the tissues. Ranvier noticed the same mode of growth in the omentum of newly-born kittens.

Young rabbits, a week old, have, in their omentum, small white or milk spots (*Ranvier*), in which lie "**vaso-formative cells**," *i. e.*, highly refractive cells of variable shape, with long cylindrical protoplasmic processes (Fig. 8). In its refractive power the protoplasm of these cells resembles that of lymph corpuscles. Long rod-like nuclei lie within these cells (K, K), and also *red blood corpuscles* (*r*, *r*), and both are surrounded with protoplasm. These vaso-formative cells give off protoplasmic processes (*a*, *a*), some of which end free, while others form a network. Here and there elongated connective-tissue corpuscles lie on the branches, and ultimately form the adventitia of the blood vessel. The vaso-formative cells have many forms: they may be elongated cylinders ending in points, or more round and oval, resembling lymph cells, or modified connective-tissue corpuscles. *These cells are always the seat of origin of non-nucleated red blood corpuscles*, which arise in the protoplasm of vaso-formative cells, as chlorophyll grains or starch granules arise within the cells of plants. The corpuscles escape, and are washed into the circulation when the cells, by means of their processes, form connections with the circulatory system. Probably the vessels so formed in the omentum are only temporary. May it not be that there are many other situations in the body where blood is regenerated?

FIG. 8.

Formation of red blood corpuscles within "vaso-formative cells," from the omentum of a rabbit seven days old. *r*, *r*, the formed corpuscles; K, K, nuclei of the vaso-formative cell; *a*, *a*, processes which ultimately unite to form capillaries.

[The observations of Schäfer also prove the **intra-cellular origin** of red blood corpuscles, and although this mode usually ceases before birth, still it is found in the rat at birth. The protoplasm of the subcutaneous **connective-tissue corpuscles**, which are derived from the mesoblast, has in it small colored globules about the size of a colored corpuscle. The mother cells elongate, become pointed at their ends, and unite with processes from adjoining cells. The cells become vacuolated; fluid or plasma, in which the liberated corpuscles float, appears in their interior, and ultimately a communication is established with the general circulation.]

Neumann observed similar formations in the embryonic liver; Wissotzky in the rabbit's amnion; Klein in the embryo chick; and Bayerl in ossifying cartilage. All these observations go to show that at a certain early period of development blood corpuscles are formed within other large cells of the mesoblast, and that part of the protoplasm of these blood-forming cells remains to form the wall of the future blood vessel.

(C) **Later Formation.**—Most observers agree that the red blood corpuscles are formed from special nucleated cells, which gradually assume the form and color of the perfect red corpuscle. According to Neumann, however, these corpuscles are pigmented from the first. In the tailed amphibians and fishes, the **spleen,** in all other vertebrates the **red marrow of bone,** are the seats of formation of these corpuscles, which subsequently increase by division (*Neumann, Rindfleisch, Bizzozero*). In the red marrow of bone we can study all the stages

of the transformation; especially pale contractile cells similar to colorless corpuscles, and also red nucleated corpuscles, which are similar to the nucleated corpuscles of the embryo, and the progenitors of the red corpuscles. These transition cells are said by Erb to be more numerous after severe hemorrhage, the number of them occurring in the blood corresponding with the energy of the formative process. After copious hemorrhage, these transition forms appear in numbers in the blood stream. The small veins, and, perhaps, the capillaries of the red marrow of bone and the spleen have no proper walls, so that the red corpuscles when formed can pass into the circulation.

Red or **blood-forming marrow** occurs in the bones of the skull, and in most of the bones of the trunk, while the bones of the extremities either contain yellow marrow (which is essentially fatty in its nature), or, at most, it is only the heads of the long bones that contain red marrow. Where the blood-regeneration process is very active, however, the yellow marrow may be changed into red, even throughout all the bones of the extremities (*Neumann*).

8. DECAY OF THE RED BLOOD CORPUSCLES.—The blood corpuscles undergo decay within a limited time, and the **liver** is regarded as one of the chief places in which their disintegration occurs, because bile pigments are formed from hæmoglobin, and the blood of the hepatic vein contains fewer red corpuscles than the portal vein.

The **splenic pulp** contains cells which indicate that colored corpuscles are broken up within it. These are the so-called "blood-corpuscle-containing cells" (§ 102). Quincke's observations go to show that the red corpuscles—which may live from three to four weeks—when about to disintegrate, are taken up by the white blood corpuscles in the hepatic capillaries, by the cells of the spleen and the bone marrow, and are stored up chiefly in the **capillaries of the liver**, in the **spleen**, and in the **marrow of bone.** They are transformed, partly into colored, and partly into colorless proteids which contain iron, and are either deposited in a granular form, or are dissolved. Part of the products of decomposition is used for the formation of new blood corpuscles in the marrow and in the spleen, and also perhaps in the liver, while a portion of the iron is excreted by the liver in the bile.

That the normal red blood corpuscles and other particles suspended in the blood stream are not taken up in this way, may be due to their being smooth and polished. As the corpuscles grow older and become more rigid, they, as it were, are caught by the amœboid cells. As cells containing blood corpuscles are very rarely found in the general circulation, one may assume that the occurrence of these cells within the spleen, liver, and marrow of bone is favored by the slowness of the circulation in these organs (*Quincke*).

Pathological.—In certain pathological conditions, ferruginous substances derived from the red blood corpuscles are found in masses in the spleen, the marrow of bone, and the capillaries of the liver: (1) When the disintegration of blood corpuscles is increased, as in anæmia (*Stahel*). (2) When the formation of red blood corpuscles from the old material is diminished. If the excretion from the liver cells be prevented, iron accumulates within them; it is also more abundant in the blood serum, and it may even accumulate in the secretory cells of the cortex of the kidney and pancreas, in gland cells, and in the tissue elements of other organs. When the amount of blood in dogs is greatly increased, after four weeks an enormous number of granules containing iron occur in the leucocytes of the liver capillaries, the cells of the spleen, bone-marrow, lymph glands, liver cells, and the epithelium of the cortex of the kidney. The iron reaction in the last two situations occurs after the introduction of hæmoglobin, or of salts of iron into the blood (*Glaevecke, v. Stark*).

When we reflect how rapidly large quantities of blood are replaced after hemorrhage and after menstruation, it is evident that there must be a brisk manufactory somewhere. As to the number of corpuscles which daily decay, we have in some measure an index in the amount of bile pigment and urine pigment resulting from the transformation of the liberated hæmoglobin (§ 20).

9. COLORLESS CORPUSCLES, BLOOD PLATES AND GRANULES.—White Blood Corpuscles.—Blood, like many other tissues, contains a number of cells or corpuscles which reach it from without; the corpuscles

vary somewhat in form, and are called **colorless or white blood corpuscles**, or "**leucocytes**" (*Hewson*, 1770). Similar corpuscles are found in lymph, adenoid tissue, marrow of bone, and as wandering cells or leucocytes in connective tissue, and also between glandular and epithelial cells. So that these corpuscles are by no means peculiar to blood alone. They all consist of more or less spherical masses of protoplasm, which is sticky, highly refractile, soft, capable of movement, and devoid of an envelope (Fig. 9). When they are quite fresh (A) it is difficult to detect the nucleus, but after they have been shed for some time, or after the addition of water (B), or acetic acid, the nucleus (which is usually a compound one) appears; acetic acid clears up the perinuclear protoplasm, and reveals the presence of the nuclei, of which the number varies from one to four, although generally three are found. The subsequent addition of magenta solution causes the nuclei to stain deeply. Water makes the contents more turbid, and causes the corpuscles to swell up. One or more nucleoli may be present in the nucleus. The **size** of the corpuscles varies from 4–13 μ, and as a rule they are about $\frac{1}{2500}$ of an inch in diameter; in the smallest forms the layer of the protoplasm is extremely thin. They all exhibit **amœboid movements** which are very apparent in the larger corpuscles, and were discovered by Wharton Jones in the skate (1846), and by Davine in the corpuscles of man (1850). Max Schultze describes three different forms in **human blood**:—

FIG. 9.



A, human white blood corpuscles, without any reagent; B, after the action of water; C, after acetic acid; D, frog's corpuscles, changes of shape due to amœboid movement; E, fibrils of fibrin from coagulated blood; F, elementary granules.

(1) The smallest, spherical forms, less than the red corpuscles, with one or two nuclei, and a very small amount of protoplasm.

(2) Spherical forms, the same size as the colored blood corpuscles.

(3) The large amœboid corpuscles, with much protoplasm and distinctly evident movements.

[On examining human blood microscopically, more especially after the colored blood corpuscles have run into rouleaux, the colorless corpuscles may readily be detected, there being usually three or four of them visible in the field at once. They adhere to the glass slide, for if the cover-glass be moved, the colored corpuscles readily glide over each other, while the colorless can be seen still adhering to the slide.]

[**White Corpuscles of Newt's Blood.**—The characters of the colorless corpuscles are best studied in a drop of newt's blood, which contains the following varieties:—

(1) **The large, finely granular corpuscle**, which is about $\frac{1}{100}$ of an inch in diameter, irregular in outline, with fine processes or pseudopodia projecting from its surface. It rapidly changes its shape at the ordinary temperature, and in its interior a bi- or tri-partite nucleus may be seen, surrounded with fine granular protoplasm, whose outline is continually changing. Sometimes *vacuoles* are seen in the protoplasm.

(2) **The coarsely granular variety** is less common than the first-mentioned, but when detected its characters are distinct. The protoplasm contains, besides a nucleus, a large number of highly refractive granules, and the corpuscle usually exhibits active amœboid movements; suddenly the granules may be seen to rush from one side of the corpuscle to the other. The processes are

usually more blunt than those emitted by (1). The relation between these two kinds of corpuscles has not been ascertained.

(3) **The small colorless corpuscles** are more like the ordinary human colorless corpuscle, and they, too, exhibit amœboid movements.]

Two kinds of colorless corpuscles like (1) and (2) exist in **frog's blood**. In the coarsely granular corpuscles the glancing granules may be of a fatty nature, since they dissolve in alcohol and ether, but other granules exist which are insoluble in these fluids. The nature of the latter is unknown. Very large colorless corpuscles exist in the axolotl's blood.

[**Action of Reagents.**—(*a*) **Water,** when added slowly, causes the colorless corpuscles to become globular, and the granules within them to exhibit Brownian movements. (*b*) **Pigments,** such as magenta or carmine, stain the nuclei very deeply, and the protoplasm to a less extent. (*c*) **Dilute Acetic Acid** clears up the surrounding protoplasm and brings clearly into view the composite nucleus, which may be stained thereafter with magenta. (*d*) **Iodine** gives a faint port-wine color, especially in horse's blood, indicating the presence of glycogen. (*e*) **Dilute Alcohol** causes the formation of clear blebs on the surface of the corpuscles, and brings the nuclei into view (*Ranvier, Stirling*).]

FIG. 10.

Plexus of fibrils in a colorless blood corpuscle.

[A delicate plexus of the fibrils—**intra-nuclear plexus**—exists within the nucleus, just as in other cells. It is very probable that the protoplasm itself is pervaded by a similar plexus of fibrils, and that it is continuous with the intra-nuclear plexus (Fig. 10).] The colorless corpuscles divide, and in this way reproduce themselves.

The Number of Colorless Corpuscles is very much less than that of the red corpuscles, and is subject to considerable variations. It is certain that the colorless corpuscles are *very much fewer in shed blood* than in blood still within the circulation. Immediately after blood is shed, an enormous number of white corpuscles disappear (§ 31).

Al. Schmidt estimates the number that remain at $\frac{1}{10}$ of the whole originally present in the circulating blood. The proportion is greater in children than in adults. The following table gives the number in shed blood:—

Number of White in Proportion to Red Blood Corpuscles:—		
In Normal Conditions.	In Different Places.	In Different Conditions.
1 : 335 (*Welcker*). 1 : 357 (*Moleschott*).	Splenic Vein, 1 : 60 Splenic Artery, 1 : 2260 Hepatic Vein, 1 : 170 Portal Vein, 1 : 740 Generally more numerous in Veins than Arteries.	*Increased* by Digestion, Loss of Blood, Prolonged Suppuration, Parturition, Leukæmia, Quinine, Bitters. *Diminished* by Hunger, Bad Nourishment.

[The number also varies with the **Age** and **Sex**:—

Age. Sex.	White. Red.	General Conditions.	White. Red.
Girls, ...	1 : 405	While fasting, ...	1 : 716
Boys, ...	1 : 226	After a meal, ...	1 : 347
Adults, ...	1 : 335	During pregnancy, . . .	1 : 281]
Old Age, ...	1 : 381		

II. **The amœboid movements** of the white corpuscles (so called because they resemble the movements of amœba) consist in an alternate contraction and relax-

ation of the protoplasm surrounding the nucleus. Processes are given off from the surface, and are retracted again. There is an *internal current* in the protoplasm, and the nucleus has also been observed to change its form [and exhibit contractions without the corpuscle dividing. The karyokinetic aster, and convolution of the intranuclear plexus have been seen.] Two series of phenomena result from these movements: (1) The "**wandering**" or locomotion of the corpuscles due to the extension and retraction of their processes; (2) the **absorption of small particles** into their interior (fat, pigment, foreign bodies). The particles adhere to the sticky external surface, are carried into the interior by the internal currents, and may eventually be excreted, just as particles are taken up by amœba and the effete particles excreted. [Max Schultze observed that colored particles were readily taken up by these corpuscles. **Conditions for movement.**—In order that the amœboid movements of the leucocytes may take place, it is necessary that there be—(1) a certain temperature and normal atmospheric pressure; (2) the surrounding medium, within certain limits, must be "indifferent," and contain a sufficient amount of water and oxygen; (3) there must be a basis or support to move on.]

FIG 11.

Human leucocytes, showing amœboid movements.

Struggle between Microbes and the Organism.—Metschnikoff emphasizes the activity of the leucocytes in retrogressive processes, whereby the parts to be removed are taken up by them in fine granules, and, as it were, are "*eaten*." Hence, he calls such cells "**phagocytes.**" They may be found in the atrophied tails of batrachians, the cells containing in their interior whole pieces of nerve fibre and primitive muscular bundles. Schizomycetes which have found their way into the blood (§ 183) have been found to be partly taken up by the colorless corpuscles. [The spores of a kind of yeast are similarly attacked in the transparent tissues of the water flea by the leucocytes, and the connective-tissue cells also destroy microbes.]

Effect of Reagents.—On a hot stage (35°–40° C.) the colorless corpuscles of **warm-blooded animals** retain their movements for a long time; at 40° C. for two to three hours; at 50° C. the proteids are coagulated and cause "**heat rigor**" and death [when their movements no longer recur on lowering the temperature]. In **cold-blooded animals** (frogs), colorless corpuscles may be seen to crawl out of small coagula, in a moist chamber, and move about in the serum. [Draw a drop of newt's blood into a capillary tube, seal up the ends of the latter and allow the blood to coagulate. After a time, examine the tube in clove oil, when some of the colorless corpuscles will be found to have made their way out of the clot.] **Induction shocks** cause them to withdraw their processes and become spherical, and, if the shocks be not too strong, their movements recommence. Strong and continued shocks kill them, causing them to swell up, and completely disintegrating them.

Diapedesis.—These amœboid movements are of special interest on account of the "wandering out" (diapedesis) of colorless blood corpuscles through the walls of the blood vessels (§ 95).

[**Effect of Drugs.**—**Acids** and **Alkalies**, if very dilute, at first increase, but afterward arrest their movements. **Sodic chloride** in a 1 per cent. solution at first accelerates their movements, but afterward produces a tetanic contraction, and, it may be, expulsion of any food particles they contain. The **Cinchona alkaloids**—quinine, quinidine, cinchonidine (1 : 1500)—quickly arrest the locomotive movements, as well as the protrusion of pseudopodia, although the leucocytes of different animals vary somewhat in their resistance to the action of drugs. Quinine not only arrests the movements of the leucocytes when applied to them directly, but when injected into the circulation of a frog the leucocytes no longer pass through the walls of the capillaries (*Binz*).

The chyle contains leucocytes, which are more resistant than those of the blood, but less so than those of the coagulable transudations. The leucocytes of the lymphatic glands may also be dissolved (*Rauschenbach*).

Relation to Aniline Pigments.—Ehrlich has observed a remarkable relation of the white corpuscles to *acid* (eosin, picric acid, aurantia), *basic* (dahlia, acetate of rosanilin), or *neutral* (picrate of rosanilin) reactions. The smallest protoplasmic granules of the cells have different chemical affinities for these pigments. Thus Ehrlich distinguishes "eosinophile," "basophile," and "neutrophile" granules within the cells. Eosinophile granules occur in the leucocytes which come from bone marrow, the myelogenic leucocytes. The small leucocytes, *i. e.*, those about the size of a colored blood corpuscle or slightly larger, are formed in the lymphatic glands, the lymphogenic. The large amœboid multi-nucleated cells, which are found outside the vessels in inflammations, exhibit a neutrophile reaction. Their origin is unknown, and so is that of the large uni-nucleated cells, and the large cells with constricted nuclei. The eosinophile corpuscles are considerably increased in leukæmia. The *basophile* granules occur also in connective-tissue corpuscles, especially in the neighborhood of epithelium; they are always greatly increased where chronic inflammation occurs.

III. **Blood Plates.**—Special attention has recently been directed to a *third* element of the blood, the "**blood plates**" or "**blood tablets**" of Bizzozero; pale, colorless, oval, round, or lenticular disks of variable size (mean, 3 μ). In

FIG. 12.

"Blood plates" and their derivatives. 1, a red blood corpuscle on the flat; 2, on the side; 3, unchanged blood plates; 4, lymph corpuscle, surrounded by blood plates; 5, altered blood plates; 6, lymph corpuscle with two heads of fused blood plates and threads of fibrin; 7, group of fused blood plates; 8, small group of partially dissolved blood plates with fibrils of fibrin.

a healthy man Fusari found 18,000 to 250,000 in 1 cubic millimetre of blood. These blood plates may be recognized in the circulating blood of the mesentery of a chloralized guinea-pig and the wing of the bat. They are precipitated in enormous numbers upon threads suspended in fresh shed blood. They may be obtained from blood flowing directly from a blood vessel, on mixing it with 1 per cent. solution of osmic acid. They rapidly change in shed blood (Fig. 12, 5), disintegrating, forming small particles, and ultimately dissolving. When several occur together they rapidly unite, form small groups (7), and collect into finely granular masses. These masses may be associated in coagulated blood with fibrils of fibrin (Fig. 12).

[These blood plates are best seen in the shed blood of the guinea-pig, especially if it be mixed with a solution of sodic sulphate (sp. gr. 1022) or ¾ per cent. NaCl tinged with methyl-violet. Bizzozero regards them as the agents which immediately induce coagulation and take part in the formation of fibrin during coagulation of the blood; Eberth and Schimmelbusch ascribe the initial formation of white thrombi to them. According to Löwit they are formed from partially disintegrated leucocytes, as a consequence of alteration of the blood. Along with the leucocytes they are concerned in the formation of fibrin (*Hlava*). These structures were known to earlier observers; but their significance has been variously interpreted. Hayem called them **hæmatoblasts.** Halla

found that they increased in pregnancy, Afanassiew in conditions of regeneration of the blood, and Fusari in febrile anæmia; they are diminished in fever.

[As to the **hæmatoblasts**, or, as they have also been called, the "globules of Donné" by Pouchet, there seems to be some confusion, for both colored and colorless granules are described under these names. As Gibson suggests, the former are, perhaps, parts of disintegrated colored corpuscles, while the latter are the blood plates. The "invisible blood corpuscles" described by Norris seem to be simply decolorized red corpuscles (*Hart, Gibson*).]

IV. **Elementary Granules.**—Blood contains **elementary granules** (Fig. 9, F), [*i.e.*, the elementary particles of Zimmermann and Beale. They are irregular bodies, much smaller than the ordinary corpuscles, and appear to consist of masses of protoplasm detached from the surface of leucocytes, or derived from the disintegration of these corpuscles, or of the blood plates. Others, again, are completely spherical granules, either consisting of some proteid substance or fatty in their nature. The protoplasmic and the proteid granules disappear on the addition of acetic acid, while the fatty granules (which are most numerous after a diet rich in fats) dissolve in ether].

V. In **coagulated blood**, delicate threads of **fibrin** (Figs. 9, E, and 12, 6, 7, 8) are seen, more especially after the corpuscles have run into rouleaux. At the nodes of these fibres are found granules which closely resemble those described under III.

[When the blood-forming process is particularly active, "**nucleated colored corpuscles**" or the "corpuscles of Neumann," are sometimes found in the blood. They are identical with the nucleated colored blood corpuscles of the fœtus, being somewhat larger than the non-nucleated colored corpuscle (§ 7).]

10. **ABNORMAL CHANGES OF THE BLOOD CORPUSCLES.**—(1) **Hemorrhages diminish the number** of red corpuscles (at most one-half), and so does **menstruation.** The loss is partly covered by the absorption of fluid from the tissues. Menstruation shows us that a moderate loss of red corpuscles is replaced within twenty-eight days. When a large amount of blood is lost, so that all the vital processes are lowered, the time may be extended to five weeks. In **acute fevers**, as the temperature increases, the number of *red* corpuscles *diminishes*, while the *white* corpuscles *increase* in number. By greatly cooling peripheral parts of the body, as by keeping the hands in iced water, in some individuals possessing red blood corpuscles of low resisting power, these corpuscles are dissolved, the blood plasma is reddened, and even hæmoglobinuria may occur (§ 265).

Diminished production of new red corpuscles causes a decrease, since blood corpuscles are continually being used up. In **chlorotic females** there seems to be a congenital weakness in the blood-forming and blood-propelling apparatus, the cause of which is to be sought for in some faulty condition of the mesoblast. In them the heart and the blood vessels are small, and the absolute number of corpuscles may be diminished one-half, although the *relative* number may be retained, while in the corpuscles themselves the hæmoglobin is diminished almost one-third; but it rises again after the administration of iron (*Hayem*). The administration of iron increases the amount of hæmoglobin in the blood. [The action of iron in anæmic persons has been known since the time of Sydenham. Hayem also finds in certain forms of anæmia that there is considerable variation in the *size* of the red corpuscles, and that in chronic anæmia the mean diameter of the corpuscles is always less than normal (7 μ to 6 μ). There is, moreover, a persistent alteration in the *volume*, *coloring power*, and *consistence* of the corpuscles, consequently a want of accord between the *number* of the corpuscles and their coloring power, *i.e.*, the amount of hæmoglobin which they contain. In **pernicious anæmia**, in which the continued decrease in the red corpuscles may ultimately produce death, there is undoubtedly a severe affection of the blood-forming apparatus. The corpuscles assume many *abnormal* and bizarre forms, often being oval or tailed, irregularly shaped, and sometimes very pale; while numerous cells containing blood-corpuscles are found in the marrow of bone. In this disease, although the red blood corpuscles are diminished in number, some may be larger and contain more hæmoglobin than normal corpuscles. The number of colored corpuscles is also diminished in chronic poisoning by lead or miasmata, and also by the poison of syphilis.

(2) The **size** of the corpuscles varies in **disease** from 2.9–12.9 μ (mean 6–8 μ); "dwarf corpuscles" or **microcytes** (6 μ and less) are regarded as young forms, and occur plentifully in nearly all cases of anæmia. "Giant blood corpuscles" or **macrocytes** (10 μ and more) are constant in pernicious anæmia, and sometimes in leukæmia, chlorosis, and liver cirrhosis (*Gram*).

(3) **Abnormal forms** of the red corpuscles have been observed after severe **burns** (*Lesser*); the corpuscles are much smaller, and under the influence of the heat, particles seem to be detached from them just as can be seen happening under the microscope as the effect of heat. **Disintegra-**

tion of the corpuscles into fine droplets has been observed in various diseases, as in severe malarial fevers. The dark granules of a pigment closely related to hæmatin are derived from the granules arising from the disintegration of the blood corpuscles, and these particles float in the blood (**melanæmia**). This condition can be produced artificially by injecting bisulphide of carbon (7 to 70 of oil) subcutaneously into rabbits (*Schwalbe*). They are partly absorbed by the colorless corpuscles, but they are also deposited in the spleen, liver, brain, and bone marrow.

(4) Sometimes the red corpuscles are abnormally **soft**, and readily yield to pressure.

Parasites of Blood Corpuscles.—Within the red blood corpuscles of birds, fishes, and tortoises, parasites are occasionally developed in the form of round "pseudo-vacuoles" from which free parasites are subsequently discharged (*Danilewsky*). In malarial conditions in man, protozoon-like organisms have been seen within the red corpuscles, the plasmodium malariæ (*Marchiafava*).

The white corpuscles are enormously increased in number in **leukæmia** (*J. H. Bennett, Virchow*). In some cases the blood looks as if it were mixed with milk. The colorless corpuscles seem to be formed chiefly in bone-marrow (*E. Neumann*), and also in the spleen and lymphatic glands (myelogenic, splenic, and lymphatic leukæmia).

11. CHEMICAL CONSTITUENTS OF THE RED BLOOD CORPUSCLES.—(1) **The coloring matter or hæmoglobin** (Hb) is the cause of the red color of blood; it also occurs in muscle, and in traces in the fluid part of blood, but in the last case only as the result of the solution of some red corpuscles. Its **percentage composition** is: C 53.85, H 7.32, N 16.17, Fe 0.42, S 0.39, O 21.84 (dog). Its rational formula is unknown, but Preyer gives the empirical formula C_{600}, H_{960}, N_{154}, Fe, S_3, O_{179}. Although it is a colloid substance it **crystallizes** in all classes of vertebrates, according to the rhombic system, and chiefly in rhombic plates or prisms; in the guinea-pig in rhombic tetrahedra; in the squirrel, however, it yields hexagonal plates. The varying forms, perhaps, correspond to slight differences in the chemical composition in different cases. Crystals separate from the blood of all classes of vertebrata during the slow evaporation of lake-colored blood, but with varying facility (Fig 13).

FIG. 13.

Hæmoglobin crystals from blood. *a*, *b*, human; *c*, cat; *d*, guinea-pig; *e*, hamster; *f*, squirrel.

The coloring matter crystallizes very readily from the blood of man, dog, mouse, guinea-pig, rat, cat, hedgehog, horse, rabbit, birds, fishes; with difficulty from that of the sheep, ox, and pig. Colored crystals are not obtained from the blood of the frog. More rarely a crystal is formed from a single corpuscle enclosing the stroma. Crystals have been found near the nucleus of the large corpuscles of fishes, and in this class of vertebrates colorless crystals have been observed.

Dichroism.—Hæmoglobin crystals are **doubly refractive** and **pleo-chromatic**; they are bluish-red with transmitted light, scarlet-red by reflected light. They contain from 3 to 9 per cent. water of crystallization, and are soluble in water, but more so in dilute alkalies. They are insoluble in alcohol, ether, chloroform, and fats. The solutions are dichroic: red in reflected light, and green in transmitted light.

In the act of crystallization the hæmoglobin seems to undergo some internal change. Before it crystallizes it does not diffuse like a true colloid, and it also rapidly decomposes hydric peroxide. If it be redissolved after crystallization, it diffuses, although only to a small extent, but it no longer decomposes hydric peroxide, and is decolorized by it. [The presence of O favors crystallization.]

12. PREPARATION OF HÆMOGLOBIN CRYSTALS.—Method of Rollett.—Put defibrinated blood in a platinum capsule placed on a freezing mixture, freeze the blood, and then thaw it; pour the lake-colored blood into a plate, until it forms a stratum not more than 1½ mm. in thickness, and allow it to evaporate slowly in a cool place, when crystals will separate.

Method of Hoppe-Seyler.—Mix defibrinated blood with 10 volumes of a 20 per cent. salt solution, and allow it to stand for two days. Remove the clear upper fluid with a pipette, wash

the thick deposit of blood corpuscles with water, and afterward shake it for a long time with an equal volume of ether, which dissolves the blood corpuscles. Remove the ether, filter the lake-colored blood, add to it ¼ of its volume of cold alcohol (0°), and allow the mixture to stand in the cold for several days. The numerous crystals can be collected on a filter and pressed between folds of blotting paper.

Method of Gscheidlen.—Take defibrinated blood, which has been exposed for twenty-four hours to the air, and keep in a closed tube of narrow calibre for several days at 37° C. When the blood is spread on glass, the crystals form rapidly. [Vaccine tubes answer very well.]

[**Method of Stirling and Brito.**—It is in many cases sufficient to mix a drop of blood with a few drops of water on a glass slide, and to seal up the preparation. After a few days beautiful crystals are developed. The addition of water to the blood of some animals, such as the rat and the guinea-pig, is rapidly followed by the formation of crystals of hæmoglobin. Very large crystals may be obtained from the stomach of the leech several days after it has sucked blood.]

13. QUANTITATIVE ESTIMATION OF HÆMOGLOBIN.—(*a*) **From the Amount of Iron.**—As dry (100° C.) hæmoglobin contains 0.42 per cent. of iron, the amount of hæmoglobin may be calculated from the amount of iron. If m represents the percentage amount of metallic iron, then the percentage of hæmoglobin in blood is $= \frac{100\,m}{0.42}$. The procedure is the following: Calcine a weighed quantity of blood, and exhaust the ash with HCl to obtain ferric chloride, which is transformed into ferrous chloride. The solution is then titrated with potassic permanganate.

(*b*) **Colorimetric Method.**—Prepare a dilute watery solution of hæmoglobin crystals of a known strength. With this compare an aqueous dilution of the blood to be investigated, by adding water to it until the color of the test solution is obtained. Of course, the solutions must be compared in vessels with parallel sides and of exactly the same width, so as to give the same thickness of fluid (*Hoppe-Seyler*). [In the vessel with parallel sides, or **hæmatinometer**, the sides are exactly 1 centimetre apart. Instead of using a standard solution of oxyhæmoglobin, a solution of picro-carminate of ammonia may be used (*Rajewsky*, *Malassez*).]

(*c*) **By the Spectroscope.**—Preyer found that an 0.8 per cent. watery solution (1 cm. thick), allowed the red, the yellow, and the first strip of green to be seen (Fig. 17, 1). Take the blood to be investigated (about 0.5 c.cm.), and dilute it with water until it shows exactly the same optical effects in the spectroscope. If k is the percentage of Hb, which allows green to pass through (0.8 per cent.), b, the volume of blood investigated (about 0.5 c.cm.), w, the necessary amount of water added to dilute it, then x = the percentage of Hb in the blood to be investigated—

$$x = \frac{k(w + b)}{b}.$$

FIG. 14.



Gowers' hæmoglobinometer. A, pipette bottle for distilled water; B, capillary pipette; C, graduated tube; D, tube with standard dilution; F, lancet for pricking the finger.

It is very convenient to add a drop of caustic potash to blood and then to saturate it with CO.

[(*d*) The **Hæmoglobinometer** of Gowers is used for the clinical estimation of hæmoglobin (Fig. 14). "The tint of the dilution of a given volume of blood with distilled water is taken as the index of the amount of hæmoglobin. The distilled water rapidly dissolves out all the hæmoglobin, as is shown by the fact that the tint of the dilution undergoes no change on standing. The color of a dilution of average normal blood one hundred times is taken as the standard. The quantity of hæmoglobin is indicated by the amount of distilled water needed to obtain the tint with the same volume of blood under examination as was taken of the standard. On account of the instability of a standard dilution of blood, tinted glycerine jelly is employed instead. This is perfectly stable, and by means of carmine and picro-carmine the exact tint of diluted blood can be obtained. The apparatus consists of two glass tubes of exactly the same size. One contains (D) a standard of the tint of a dilution of 20 cubic mm. of blood, in cubic centimetres of water (1 in 100). The second tube (C) is graduated, 100 degrees = 2

centimetres (100 times 20 cubic millimetres). The 20 cubic millimetres of blood are measured by a capillary pipette (B). This quantity of the blood to be tested is ejected into the bottom of the tube, a few drops of distilled water being first placed in the latter. The mixture is rapidly agitated to prevent the coagulation of the blood. The distilled water is then added drop by drop (from the pipette stopper of a bottle (A) supplied for that purpose), until the tint of the dilution is the same as that of the standard, and the amount of water which has been added (*i. e.*, the degree of dilution) indicates the amount of hæmoglobin."

"Since average normal blood yields the tint of the standard at 100 degrees of dilution, the number of degrees of dilution necessary to obtain the same tint with a given specimen of blood is the percentage proportion of the hæmoglobin contained in it, compared to the normal. For instance, the 20 cubic millimetres of blood from a patient with anæmia gave the standard tint of 30 degrees of dilution. Hence it contained only 30 per cent. of the normal quantity of hæmoglobin. By ascertaining with the hæmacytometer the corpuscular richness of the blood, we are able to compare the two. A fraction, of which the numerator is the percentage of hæmoglobin, and the denominator the percentage of corpuscles, gives at once the average value per corpuscle. Thus the blood mentioned above containing 30 per cent. of hæmoglobin, contained 60 per cent. of corpuscles; hence the average value of each corpuscle was $\frac{30}{60}$ or $\frac{1}{2}$ of the normal. Variations in the amount of hæmoglobin may be recorded on the same chart as that employed for the corpuscles. The instrument is only expected to yield approximate results, accurate within 2 or 3 per cent. It has, however, been found of much utility in clinical observation."]

(*e*) **Fleischl's Hæmometer.**—For **clinical purposes** this instrument (Fig. 15) is useful. A cylinder G, of two compartments *a* and *a'*, rests on a metallic table. Both compartments are filled with water, but in one (*a*) is placed a known quantity of blood measured in a measuring tube of known capacity. The red color of the solution of hæmoglobin thus obtained is compared with a red wedge of glass (K), which is moved by means of a wheel (R and T) under the other compartment (*a'*) until the two colors are identical. The illumination of the dilute blood solution and the red glass wedge is done from below by lamp light reflected from the white reflecting surface (S). The frame in which the red glass wedge is fixed bears numbers, and when the color is identical in the two compartments *a* and *a'*, the percentage of hæmoglobin as compared with normal blood can be read off directly. Suppose it to be 80 on the scale, then the blood examined contains 80 per cent. of the hæmoglobin of normal blood.

FIG. 15.



V. Fleischl's hæmometer. K, red colored wedge of glass moved by R; G, mixing vessel with two compartments *a* and *a'*; M, table with hole to read off the percentage of hæmoglobin on the scale P; T, to move K; S, mirror of plaster-of-Paris.

The **amount** of hæmoglobin in man is 13.77 per cent., in the woman 12.59 per cent., during pregnancy 9 to 12 per cent. (*Preyer*). According to Leichtenstern, Hb is in greatest amount in the blood of a newly-born infant, but after ten weeks the excess disappears. Between six months and five years it is smallest in amount; it reaches its second highest maximum between twenty-one and forty-five, and then sinks again. From the tenth year onward, the blood of the female is poorer in Hb. The taking of food causes a temporary decrease of the Hb, owing to the dilution of the blood.

In Animals.—In the dog, 9.7; ox, 9.9; sheep, 10.3; pig, 12.7; horse, 13.1; birds, 16–17 per cent.
Pathological.—A decrease is observable during recovery from febrile conditions, and also during phthisis, cancer, ulcer of the stomach, cardiac disease, chronic diseases, chlorosis, leukæmia, pernicious anæmia, and during the rapid mercurial treatment of syphilitic persons.

14. **THE SPECTROSCOPE.**—As the spectroscope is frequently used in the investigation of blood and other substances, a short description of the instrument is given here (Fig. 16). It

consists of—(1) a tube, A, which has at its peripheral end a **slit**, S (that can be narrowed or widened). At the other end a collecting lens, C (called a **collimator**), is placed, so that its focus is in exact line with the slit. Light (from the sun or a lamp) passes through the slit, and thus goes parallel through C to (2) the **prism**, P, which decomposes the parallel rays into a colored spectrum, *r*, *v*. (3) An astronomical **telescope** is directed to the spectrum *r*, *v*, and the observer, B, with the aid of the telescope, sees the spectrum magnified from six to eight times. (4) A third tube, D, contains a delicate **scale**, M, on glass, whose image, when illuminated, is reflected from the prism to the eye of the observer, so that he sees the spectrum, and over or above it the scale. To keep out other rays of light the inner ends of the three tubes are covered by metal or by a dark cloth (see also § 265).

[The **micro-spectroscope**, *e.g.*, as made by Browning or Zeiss, may be used when small quantities of a solution are to be examined. Every spectroscope ought to give two spectra, so that the position of any absorption band may be definitely ascertained. The spectroscope is fitted into the ocular end of the tube of a microscope instead of the eye-piece. Small cells for containing the fluid to be examined are made from short pieces of barometer tubes cemented to a plate of glass.]

Absorption Spectra.—If a colored medium (*e.g.*, a solution of blood) be placed between the slit and a source of light, all the rays of colored light do not pass through it—some are absorbed; many yellow rays are absorbed by blood, hence that part of the spectrum appears dark to the observer. On account of this absorption, such a spectrum is called an "*absorption spectrum*."

FIG. 16.



Scheme of a spectroscope for observing the spectrum of blood. A, tube; S, slit; *m*, *m*, layer of blood with flame in front of it; P, prism; M, scale; B, eye of observer looking through a telescope; *r*, *v*, spectrum.

Flame Spectra.—If mineral substances be burned on a platinum wire in a *non-luminous* flame or Bunsen's burner in front of the slit, the elements present in the mineral or ash give special colored band or bands, which have a definite position. Sodium gives a yellow, potassium a red and violet line. These substances are found on burning the ashes of almost all organs.

If **sunlight** be allowed to fall upon the slit, the spectrum shows a large number of lines (**Fraunhofer's lines**) which occupy definite positions in the colored spectrum. These lines are indicated by the letters A, B, C, D, etc., *a*, *b*, *c*, etc. (Fig. 17).

15. COMPOUNDS OF Hb WITH O; OXYHÆMOGLOBIN AND METHÆMOGLOBIN.—1. **Oxyhæmoglobin** (O_2Hb) behaves as a weak acid, and occurs to the extent of 86.78 to 94.30 per cent. in dry human red corpuscles (*Jüdell*). It is formed very readily whenever Hb comes into contact with O or atmospheric air. According to Bohr, 1 gramme Hb unites with 1.56 cubic centimetre of O at 0° and 760 mm. Hg pressure, the union being stronger in weak than in concentrated solutions. Oxyhæmoglobin is a very **loose chemical compound**, and is slightly less soluble than Hb; its **spectrum** shows in the *yellow* and the *green* **two dark absorption-bands**, whose length and breadth in an 0.18 per cent. solution are given in Fig. 17 (2).

It occurs in the blood corpuscles circulating in arteries and capillaries, as can be shown by the spectroscopic examination of the ear of a rabbit, of the prepuce, and the web of the fingers (*Vierordt*).

[**Spectrum of Oxyhæmoglobin.**—In the spectrum of a dilute solution of hæmoglobin crystals or arterial blood, part of the red and violet rays are absorbed, but **two** well-marked **absorption-bands** exist between D and E. The line nearest D, *i.e.*, next the red end of the spectrum, sometimes designated by the letter (α) is narrow, sharply defined, and black at its centre, and its position cor-

FIG. 17.



Spectra of hæmoglobin and its compounds.

responds to the wave-length 579. The other absorption-band near E, conveniently designated by (β), is broader, not so dark, and its edges are less sharply defined. Its centre corresponds to the wave-length 553.8. In very dilute solutions the α band is the only one visible. In a strong solution, as shown in Fig. 17, the two bands fuse, but are again made visible as two on dilution of the blood.]

Reduction of Oxyhæmoglobin.—It gives its O very readily, however, even when means which set free absorbed gases are used. It is **reduced** by the removal of the gases by the *air-pump*, by the *conduction* through its solution of *other gases*

(CO), and by *heating* to the boiling point. In the circulating blood its O is very rapidly given up to the tissues, so that in suffocated animals only *reduced hæmoglobin* is found in the arteries. Some constituents of the serum and sugar remove its O. By adding a solution of oxyhæmoglobin **reducing substances**—*e.g.*, ammonium sulphide, iron filings, or Stokes's fluid [tartaric acid, iron proto-sulphate, and excess of ammonia]—the two absorption-bands of the spectrum disappear, and *reduced hæmoglobin* (gas-free), with **one absorption-band,** is formed. The color changes from a bright red to a purplish or claret tint. The two bands are reproduced by shaking the reduced hæmoglobin with air, whereby O_2Hb is again formed. Solutions of oxyhæmoglobin are readily distinguished, by their scarlet color, from the purplish tint of reduced hæmoglobin.

[The single absorption-band (Fig. 17, 4) designated by the letter (γ), lying about midway between the position of the two previous bands, is broader, fainter, less deeply shaded, and its centre is about, but not quite, intermediate between D and E. It extends between the wave-lengths 595 and 538, and is blackest opposite the wave-length 550, so that it lies nearer D than E. At the same time more of the blue rays are transmitted. On dilution the band is not resolved into two, but simply becomes fainter and disappears.]

[Hæmoglobin has certain remarkable characters: (1) Although it is a crystalloid body it diffuses with difficulty through an animal membrane, owing to the large size of its molecule. (2) It readily combines with O to form an unstable and *loose* chemical compound, oxyhæmoglobin. (3) This O it gives up readily to the tissues or other deoxidizing reagents. (4) Its composition is very complex, for, in addition to the ordinary elements present in proteids, it contains a remarkable amount of iron (0.4 per cent).]

If a string be tied round the base of two fingers so as to intetrrupt the circulation, spectroscopic examination shows that the oxyhæmoglobin rapidly passes into reduced Hb (*Vierordt*). Cold delays this reduction; it is accelerated in youth, during muscular activity, or by suppressed respiration, and usually also during fever.

The spectroscopic examination of small **blood-stains** is often of the utmost forensic importance. A minimal drop is sufficient. Dissolve the stain in a few drops of distilled water, and place the solution in a thin glass tube in front of the slit of the spectroscope.

Para-hæmoglobin.—If O_2Hb be preserved under alcohol it passes into a modified form, which is insoluble in water (*Nencki and Sieber.*)

2. **Methæmoglobin** is a more stable, crystalline compound (*Hoppe-Seyler.*) It contains the same amount of O as O_2Hb, but in a different chemical union, while the O is also more firmly united with it. It shows **four absorption-bands** like hæmatin in acid solution (Fig. 17, 5), of which that between C and D is distinct; the second is very indistinct, while the third and fourth readily fuse, so that these last two bands are only well seen with good apparatus.

It is produced spontaneously in old brown blood stains, in the crusts of bloody wounds, in blood cysts, and in bloody urine. Chemically, it can be prepared from a solution of Hb, by the action of potassic ferri-cyanide (*Jäderholm*) or potassic chlorate (*Marchand*), [or by adding to a solution of Hb a freshly prepared solution of potassic permanganate], and in non-laky blood by alloxantin (*Kowalewsky*). It crystallizes if defibrinated blood is shaken with amyl nitrite and the mahogany-brown laky fluid be allowed to evaporate slowly (*Halliburton*).

If a trace of ammonia be added to a solution of methæmogoblin, it gives an alkaline solution of methæmogoblin, which shows two bands like oxyhæmoglobin, of which the first one is the broader, and extends more toward the red. If ammonium sulphide be added to the methæmoglobin solution, reduced Hb is formed.

[**Action of Nitrites.**—The addition of amyl nitrite dissolved in alcohol, or sodic potassic nitrite to defibrinated blood causes the latter to assume a chocolate color, which, on the addition of ammonia, changes to red. The chocolate-colored fluid shows one well-defined band in the red, and less distinctly other three bands like methæmoglobin (*Gamgee*).]

[The nitrites therefore form a compound with its oxygen more firmly fixed than the O in HbO_2, so that large doses of nitrites arrest the internal respiration and are poisonous. It is, however,

affected by the products formed in the blood during asphyxia, while CO-Hb is not, the methæmoglobin formed by the nitrites is reduced by these products to Hb, which as it passes through the lungs takes up O.]

16. **CARBONIC OXIDE HÆMOGLOBIN, POISONING WITH CO.**—3. **CO-Hæmoglobin** is a more stable chemical compound than the foregoing, and is produced at once when carbonic oxide is brought into contact with the pure Hb or O_2Hb (*Cl. Bernard*, 1857). It has an intensely florid or *cherry-red* color, is not dichroic, and its spectrum shows **two absorption-bands**, very like those of O_2Hb, but they are slightly closer together and lie more toward the violet (Fig. 17, 3). Reducing substances which act upon HbO_2, *e.g.*, ammonium sulphide or Stokes's fluid, do not affect these bands, *i.e.*, they cannot convert the CO-Hb into reduced Hb. If a 10 per cent. solution of caustic soda be added to a solution of CO-Hb, and heated, it gives a *cinnabar-red color;* while, with an HbO_2 solution, it gives a dark brown, greenish, greasy mass. Oxidizing substances [solutions of potassic permanganate (0.025 per cent.), potassic chlorate (5 per cent.), and dilute chlorine solution] make solutions of CO-Hb cherry-red in color, while they turn solutions of O_2Hb pale yellow. After this treatment both solutions show the absorption-bands of methæmogoblin, but those of the CO-Hb appear considerably later. If ammonium sulphide be added, O_2Hb and CO-Hb are re-formed.

On account of its **stability**, CO-Hb resists external influences and even putrefaction for a long time, and the two bands of the spectrum may be visible after many months. Landois obtained the soda test and spectroscopic bands in the blood of a woman poisoned eighteen months previously by CO, and after great putrefaction of the body had taken place. [Stirling has kept CO-Hb in a stoppered bottle for five years without putrefaction taking place.]

If CO or air containing it be inspired, it gradually displaces the O, volume for volume, out of the red blood corpuscles, and death soon occurs; 1000 c.cm. inspired at once will kill a man. A very small quantity in the air ($\frac{1}{400}$–$\frac{1}{1000}$) suffices, in a relatively short time, to form a large quantity of CO-Hb. As continued contact with other gases (such as the passing of O through it for a very long time) gradually separates the CO from the Hb, with the formation of O_2Hb, it happens that, in very partial poisoning with CO, the blood gradually gets rid of the CO by the respiratory organs. It is uncertain if any part is excreted as CO_2. [CO-Hæmoglobin, being a stable compound when once formed, circulates in the blood vessels; but it neither gives up oxygen to the tissues, nor takes up oxygen in the lungs, hence its very poisonous properties. The real cause of death in animals poisoned with it is, that the internal respiration is arrested.]

Poisoning with Carbonic Oxide.—Carbonic oxide is formed during the incomplete combustion of coal or coke, and passes into the air of the room, provided there is not a free outlet for the products of combustion. It occurs to the extent of 12–28 per cent. in ordinary gas, which largely owes its poisonous properties to the presence of CO. If the O be gradually displaced from the blood by the respiration of air containing CO, life can only be maintained as long as sufficient O can be obtained from the blood to support the oxidations necessary for life. Death occurs before all the O is displaced from the blood. CO has no effect when directly applied to muscle and nerve. When it is mixed with air, as in **coal-gas poisoning**, and inhaled, there is first stimulation and afterward paralysis of the nervous system, as shown by the symptoms induced, *e.g.*, violent headache, great restlessness, excitement, increased activity of the heart and respiration, salivation, tremors, and spasms. Later, unconsciousness, weakness, and paralysis occur, labored respiration, diminished heart-beat, and lastly, complete loss of sensibility, cessation of the respiration and heart-beat, and death. At first the temperature rises several tenths of a degree, but it soon falls 1° or more. The pulse is also increased at first, but afterward it becomes very small and frequent. In poisoning with **pure CO** there is no dyspnœa, but sometimes muscular spasms occur, the coma not being very marked. There is also temporary but pronounced paralysis of the limbs, followed by violent spasms. After death the heart and brain are congested with intensely florid blood. In poisoning with the **vapor of charcoal**, where CO and CO_2 both occur, there is a varying degree of coma; pronounced dyspnœa, muscular spasms which may last several minutes, gradual paralysis and asphyxia, moniliform contractions and subsequent dilatation of the blood vessels, with congestion of various organs, occur, accompanied by a fall of the blood pressure (*Klebs*), indicating initial stimulation and subsequent paralysis of the vaso-motor centre. This also explains the variations in

the temperature and the occasional occurrence of sugar in the urine after poisoning with CO. After death, the blood vessels are found to be filled with fluid blood of an exquisitely bright cherry-red color, while all the muscles and viscera and exposed parts of the body (such as the lips) have the same color. The brain is soft and friable; there is catarrh of the respiratory organs and degeneration of the muscles, and great congestion and degeneration of the liver, kidneys, and spleen. The spots of lividity, *post-mortem*, are bright red. After recovery from poisoning with CO there may be paraplegia and (although more rarely) disturbances of the cerebral activity.

17. OTHER COMPOUNDS OF HÆMOGLOBIN.—4. **Nitric Oxide Hæmoglobin** (NO-Hb) is formed when NO is brought into contact with Hb (*L. Hermann*).

As NO has a great affinity for O, red fumes of nitrogen peroxide (NO_2) being formed whenever the two gases meet, it is clear that, in order to prepare NO-Hb, the O must first be removed. This may be done by passing H through it [or ammonia may be added to the blood, and a stream of NO passed through it; the ammonia combines with all the acid formed by the union of the NO with the O of the blood]. NO-Hb is a *more stable chemical compound* than CO-Hb, which, as we have seen, is again more stable than O_2Hb. It has a *bluish-violet* tint, and also gives two absorption-bands in the spectrum similar to those of the other two compounds, but not so intense. These bands are *not* abolished by the action of reducing agents. As NO-Hb cannot be formed in the body, it has no practical significance.

The three compounds of Hb, with O, CO, and NO are **crystalline**, like reduced Hb; they are **isomorphous**, and their solutions are **not dichroic.** All three gases unite in equal volumes with Hb. If O be conducted through a concentrated solution of Hb devoid of gases, a crystalline mass of O_2Hb is thereby readily formed.

5. **Cyanogen**, CNH (*Hoppe-Seyler*), and **acetylene**, C_2H_4 (*Bistrow and Liebreich*), form easily decomposable compounds with Hb. The former occurs in poisoning with hydrocyanic acid, and has a spectrum nearly identical with that of O_2Hb, and, like O_2Hb, it is reduced, but very slowly, by special reagents. [The existence of these compounds is, however, highly doubtful (*Gamgee*).]

18. DECOMPOSITION OF HÆMOGLOBIN.—In solution and in the dry state Hb gradually becomes decomposed, whereby the iron-containing pigment hæmatin (along with certain bye-products, formic, lactic, and butyric acids) is formed. Hæmoglobin, however, may be decomposed at once into (1) **Hæmatin**, a body containing iron, and (2) a colorless proteid closely related to **globulin**; by (*a*) the addition of all acids, even by CO_2 in the presence of plenty of water; (*b*) strong alkalies; (*c*) all reagents which coagulate albumin, and by heat at 70°–80° C.; (*d*) by ozone.

(A) **Hæmatin**, $C_{32}H_{32}N_4FeO_4$ (*Nencki and Sieber*), is a bluish-black amorphous body, which forms about 4 per cent. of hæmoglobin (dog). It is *insoluble* in water, alcohol, and ether; *soluble* in dilute alkalies and acids, and in acidulated ether and alcohol.

(1) **Acid Hæmatin.**—Lecanu extracted it from dry blood corpuscles by using alcohol containing sulphuric and tartaric acids. [If acetic acid be added to a solution of Hb and slightly heated, a mahogany-brown fluid is obtained, containing *hæmatin in acid solution*, which gives a spectrum with **one absorption-band** to the red side of D near C (Fig. 17, 5). There is at the same time a considerable absorption of the blue end of the spectrum. If an **ethereal extract** of the acid hæmatin be made, the ether is colored brown and shows **four absorption-bands**, as in Fig. 17, 5.]

(2) **Alkali Hæmatin.**—[If to the above solution ammonia or caustic soda be added, on heating gently, the color changes, and the fluid becomes dichroic, showing a greenish tinge. On mixing the solution thoroughly with air the spectrum of oxy-alkali hæmatin is obtained, *i. e.*, **one absorption-band** just to the red side of D (Fig. 17, 6), so that it is much nearer D than the corresponding band of acid hæmatin. Much of the blue end of the spectrum is absorbed as well.]

[(3) **Reduced Alkali Hæmatin** or **Hæmochromogen.**—If the solution of alkali hæmatin be reduced by ammonium sulphide, the spectrum of hæmochro-

mogen is obtained, viz., **two absorption-bands** between D and E, but they are nearer the violet end than in the case of HbO_2 and Hb-CO (Fig. 17, 7).]

[(4) **Hæmatoporphyrin** or **Iron-free Hæmatin.**—On adding blood to concentrated sulphuric acid a clear purplish-red solution is obtained, which shows **two absorption-bands,** one close to and on the red side of D, and a second half-way between D and E. If water be added a brown precipitate is thrown down. When this precipitate is dissolved in caustic soda, it gives a fluid which shows *four* absorption-bands.]

Action of CO_2.—If CO_2 be passed through a solution of oxyhæmoglobin for a considerable time, reduced Hb is first formed; but if the process be prolonged the Hb is decomposed, a precipitate of globulin is thrown down, and an absorption-band, similar to that obtained when Hb is decomposed with acids, is observed (p. 66).

An alkaline solution of hæmatin, when reduced by tin and hydrochloric acid, yields **urobilin** (compare § 261).

When hæmoglobin is extravasated into the subcutaneous tissue, it becomes so altered that at first hæmatoidin (§ 20), and ultimately hydrated oxide of iron, appear in its place.

19. HÆMIN AND BLOOD TESTS.—In 1853 Teichmann prepared crystals of **hæmin** from blood, which Hoppe-Seyler showed to be **chloride of**

FIG. 18.

Hæmin crystals. 1, human; 2, seal; 3, calf; 4, pig; 5, lamb; 6, pike; 7, rabbit.

FIG. 19.

Hæmin crystals prepared from traces of blood.

hæmatin (Hæmatin, + 2HCl), with the formula $C_{32}H_{31}ClN_4FeO_3$ (*Nencki and Sieber*). The presence of these crystals is used as a test for blood stains or blood in solution. They (Fig. 18) are prepared by adding a small crystal of common salt to dry blood on a glass slide, and then an excess of *glacial* acetic acid; the whole is gently heated until bubbles of gas are given off. On allowing the preparation to cool, the characteristic hæmin crystals are obtained.

Characters.—When well formed, the crystals are small microscopic rhombic plates, or rods; sometimes they are single—at other times they are aggregated in groups, often crossing each other. Some kinds of blood (ox and pig) yield very irregular, scarcely crystalline, masses. The crystalline forms of hæmin are identical in all the different kinds of blood that have been examined. They are **doubly refractive**; under the polarization microscope they are a glancing yellow, appearing raised on the dark field, with a strong absorption of the light parallel to the long axis of the crystals (*Falk and Morache*). They are **pleochromatic**; by transmitted light they are mahogany-brown, and by reflected light bluish-black, glancing like steel.

(1) **Preparation from Dry Blood Stains.**—Place a few particles of the blood stain on a glass slide, add 2 to 3 drops of *glacial* acetic acid and a small crystal of common salt; cover with a cover-glass, and heat gently over the flame of a spirit lamp until bubbles of gas are given off. On cooling, the crystals appear in the preparation (Fig. 19).

(2) **From Stains on Porous Bodies.**—The stained object (cloth, wood, blotting paper, earth) is extracted with a small quantity of dilute caustic potash, and afterwards with water in a watch-glass. Both solutions are carefully filtered, and tannic acid and glacial acetic acid are added until an acid reaction is obtained. The dark precipitate which is formed is collected on a filter and washed. A small part of it is placed on a microscope slide, a granule of common salt is added, and the whole dried; the dry stain is treated as in (1) (*Struwe*).

(3) **From Fluid Blood.**—Dry the blood slowly at a low temperature, and proceed as in (1).

(4) **From Dilute Solutions of Hæmoglobin.**—(*a*) *Struwe's Method.*—Add to the fluid, ammonia, tannic acid, and afterwards glacial acetic acid, until it is acid; a black precipitate of tannate of hæmatin is thrown down. This is isolated, washed, dried, and treated as in (1), but instead of NaCl a granule of ammonium chloride is added.

Hæmin crystals may sometimes be prepared from putrefying or lake-colored blood, but they are very small, and the test often fails. When mixed with iron-rust, as on iron weapons, the blood crystals are generally not formed. In such cases, scrape off the stains and boil them with dilute caustic potash. If blood be present, the dissolved hæmatin forms a fluid, which in a thin layer is green, in a thick layer red (*H. Rose*).

Hæmin crystals have been prepared from all classes of vertebrates and from the blood of the earth-worm. From the blood of the ox and pig they may be almost amorphous.

Chemical Characters.—They are insoluble in water, alcohol, ether, chloroform; but concentrated H_2SO_4 dissolves them, expelling the HCl, and giving a violet-red color. Ammonia also dissolves them, and if the resulting solution be evaporated, heated to 130° C., and treated with boiling water (which extracts the ammonium chloride), **hæmatoporphyrin**—identical with Mulder's **iron-free hæmatoin**, and with Preyer's **hæmatoin**, is obtained (*Hoppe-Seyler*). It is a bluish-black substance, which on being pounded forms a brown and amorphous powder. Its solutions in caustic alkalies are dichroic; in reflected light, brownish-red; in transmitted light, in a thick stratum, red—in a thin one, olive-green. The acid solutions are monochromatic and brown.

Preparation in Bulk.—To obtain it in quantity, heat dried horse's blood with 10 parts of formic acid. If the crystals be suspended in methyl alcohol, on adding iodine and heating them they dissolve with a purple color; after adding bromine, brown; and after passing chlorine gas, green; all these give a characteristic spectrum (*Axenfeld*).

The glacial acetic acid may be replaced by oxalic or tartaric acid, the common salt by salts of iodine or bromine; in the latter case similar bromine- or iodine-hæmatin is formed (*Bikfalvi*).

FIG. 20.



Hæmatoidin crystals.

20. HÆMATOIDIN.—Virchow discovered this important derivative of hæmoglobin. It occurs in the body wherever blood stagnates outside the circulation, and becomes decomposed—as when blood is extravasated into the tissues—*e.g.*, the brain—in solidified blood plugs or thrombi; especially in veins; invariably in the Graafian follicles. It contains no iron ($C_{32}H_{36}N_4O_6$), and crystallizes in clino-rhombic prisms (Fig. 20) of a yellowish-brown color. It is soluble in warm alkalies and chloroform. Very probably it is *identical* with the bile-pigment—**bilirubin.** [When acted upon by impure nitric acid (Gmelin's reaction), it gives the same play of colors as bile.]

Pathological.—In cases where a large amount of blood has undergone solution within the blood vessels (as by injecting foreign blood) hæmatoidin crystals have been found in the urine. For their occurrence in the urine in jaundice (§ 180), and in the sputum (§ 138).

21. (B.) **THE COLORLESS PROTEID OF HÆMOGLOBIN.**—It is closely related to **globulin**; but, while the latter is precipitated by all acids, even by CO_2, and re-dissolved on passing O through it, the proteid of hæmoglobin, on the other hand, is not dissolved after precipitation on passing through it a stream of O.

As crystals of hæmoglobin can be decolorized under special circumstances, it is probable that these owe their crystalline form to the proteid which they contain. Landois placed crystals of hæmoglobin along with alcohol in a dialyser, putting ether acidulated with sulphuric acid outside, and thereby obtained colorless crystals. [If frogs' blood be sealed up on a microscopic slide along

with a few drops of water for several days, long, colorless, acicular crystals are developed in it (*Stirling and Brito*).]

22. II. **PROTEIDS OF THE STROMA.**—**Dry** red human blood corpuscles contain from 5.10–12.24 per cent. of these proteids, but little is known about them (*Füdell*). One of them is **globulin**, which is combined with a body resembling nuclein (*Wooldridge*), and traces of a **diastatic ferment** (*v. Wittich*). The stroma tends to form masses which resemble fibrin.

L. Brunton found a body resembling mucin in the nuclei of red blood corpuscles, and Miescher detected **nuclein** (§ 250, 2).

23. **OTHER CONSTITUENTS OF RED BLOOD CORPUSCLES.**—III. **Lecithin** (0.35–0.72 per cent.) in dry blood corpuscles (§ 250, 2). **Cholesterin** (0.25 per cent.) (§ 250, III.), **no Fats.**

Lecithin is regarded as a **glycero-phosphate of neurin**, in which, in the radical of glycero-phosphoric acid, two atoms of H are replaced by two of the radical of stearic acid. By gentle heat glycero-phosphoric acid is split up into glycerine and phosphoric acid (§ 250).

These substances are obtained by extracting old stromata or isolated blood corpuscles with ether. When the ether evaporates, the characteristic globular forms ("myelin-forms") of lecithin, and crystals of cholesterin are recognized. The amount of lecithin may be determined from the amount of phosphorus in the ethereal extract.

IV. **Water** (681.63 per 1000—*C. Schmidt*).

V. **Salts** (7.28 per 1000), chiefly compounds of *potash and phosphoric acid;* the phosphoric acid is derived only from the burned lecithin; while the greater part of the sulphuric acid is derived from the burning of the hæmoglobin in the analysis.

Analysis of Blood.—1000 parts, by weight, of **horse's blood** contain—
344.18 blood corpuscles (containing about 128 per cent. of solids).
655.82 plasma (containing about 10 per cent. of solids).

1000 parts, by weight, of **moist blood corpuscles** contain—

Solids,	367.9 (pig);	400.1 (ox).
Water,	632.1 "	599.9 "

The solids are—

	Pig.	Ox.
Hæmoglobin,	261	280.5
Proteids,	86.1	107
Lecithin, Cholesterin, and other Organic Bodies,	12.0	7.5
Inorganic salts,	8.09	4.8
Including **Potash,**	5.543	0.747
Including Magnesia,	0.158	0.017
Including Chlorine,	1.504	1.635
Including **Phosphoric Acid,**	2.067	0.703
Including Soda,	0	2.093 (*Bunge*).

[An approximate estimate of the composition of **human blood** is given in the following table:—

Composition of Human Blood as a Whole.

Water,		780
Solids—of these—		
Corpuscles,	134	
Serum-albumin, Serum-globulin,	70	
Fibrin of Clot (? Fibrinogen),	2.2	220
Inorganic Salts (of serum),	6.0	
Extractives,	6.2	
Fatty matters,	1.4	
Gases, O, CO_2, N.]		

24. **CHEMICAL COMPOSITION OF THE WHITE CORPUSCLES.**—Investigations have been made on pus cells, which closely resemble colorless blood corpuscles. They contain several **proteids**; alkali-albuminate, a

proteid which coagulates at 48° C., an albuminate resembling myosin, paraglobulin, peptone, and a coagulating ferment; **nuclein** in the nuclei (§ 250, 2), glycogen (§ 252), lecithin, cerebrin, cholesterin, and fat.

100 parts, by weight, of dry pus, contain the following **Salts**:—

Earthy Phosphates,	0.416	Potash,	0.201
Sodic Phosphate,	0.606	Sodic Chloride,	0.143

25. BLOOD PLASMA AND ITS RELATION TO SERUM.—The unaltered fluid in which the blood corpuscles float is called **blood plasma,** or **liquor sanguinis.** This fluid, however, after blood is withdrawn from the vessels, rapidly undergoes a change, owing to the formation of a solid fibrous substance—**fibrin**. After this occurs, the new fluid which remains, no longer coagulates spontaneously (it is plasma, *minus* the fibrin factors), and is called **serum.** Apart from the presence of the fibrin factors, the chemical composition of plasma and serum is the same.

[When blood coagulates, Table I shows what takes place, while Table II shows what occurs when it is beaten: —



Plasma is a clear, transparent, slightly thickish fluid, which, in most animals (rabbit, ox, cat, dog), is almost colorless; in man it is yellow, and in the horse citron yellow.

26. PREPARATION OF PLASMA.—(A) **Without Admixture.**—Taking advantage of the fact that plasma, when cooled to 0° outside the body, does not coagulate for a considerable time, Brücke prepares the plasma thus: The blood of the horse (because it coagulates slowly, and its corpuscles sink rapidly to the bottom) is received, as it flows from an artery, into a tall, narrow glass, placed in a freezing mixture, and cooled to 0°. The blood remains fluid, the colored corpuscles subside in a few hours, while the plasma remains above as a clear layer, which can be removed with a cooled pipette. If this plasma be then passed through a cooled filter, it is robbed of all its colorless corpuscles. [Burdon-Sanderson uses a vessel consisting of three compartments—the outer and inner contain ice, while the blood is caught in the central compartment, which does not exceed half an inch in diameter.] The *quantity* of plasma may be roughly (but only roughly) estimated by using a tall, graduated measuring glass. If the plasma be warmed, it soon coagulates (owing to the formation of the fibrin), and passes into a trembling jelly. If, however, it be beaten with a glass rod, the fibrin is obtained as a white, stringy mass, adhering to the rod. The quantity of fibrin in a given volume of plasma is very small (p. 71), although it varies much in different cases.

(B) **With Admixture.**—Blood flowing from an artery is caught in a tall vessel containing $\frac{1}{7}$ of its volume of a concentrated solution of sodic sulphate (*Hewson*) —or in a 25 per cent. solution of magnesic sulphate (1 vol. to 4 vols. blood—*Simmer*)—or 1 vol. blood with 2 vols. of a 4 per cent. solution of monophosphate of potash (*Masia*). When the blood is mixed with these fluids and put in a cool place, the corpuscles subside, and the clear stratum of plasma mixed with the salts

may be removed with a pipette. [The plasma so obtained is called "**salted plasma.**"] If the salts be removed by dialysis, coagulation occurs; or it may be caused by the addition of water (*Joh. Müller*). Blood which is mixed with a 4 per cent. solution of common salt does not coagulate, so that it also may be used for the preparation of plasma. [For frogs' blood Johannes Müller used a ½ per cent. solution of cane sugar, which permits the corpuscles to be separated from the plasma by filtration. The plasma mixed with the sugar coagulates in a short time.]

27. **FIBRIN—COAGULATION OF THE BLOOD—General Characters.—Fibrin** is that substance which, becoming solid in shed blood, in plasma and in lymph causes **coagulation** of these fluids. In these fluids, when left to themselves, fibrin is formed, consisting of innumerable, excessively delicate, closely packed, microscopic, doubly refractive fibrils (Fig. 7, E). These fibrils entangle the blood corpuscles as in a spider's web, and form with them a jelly-like solid mass called the **blood clot** or **placenta sanguinis**. At first the clot is very soft, and after the first 2 to 15 minutes a few fibres may be found on its surface; these may be removed with a needle, while the interior of the clot is still fluid. The fibres ultimately extend throughout the entire mass, which, in this stage, has been called *cruor*. After from 12 to 15 hours the fibrin contracts, or, at least, shrinks more and more closely round the corpuscles, and a fairly solid, trembling, jelly-like clot, which can be cut with a knife, is formed. During this time the clot takes the shape of the vessel in which the blood coagulates, and expresses from its substance a fluid—the **blood serum.** Fibrin may be obtained by washing away the corpuscles from the clot with a stream of water.

Crusta Phlogistica.—If the corpuscles subside very rapidly, and if the blood coagulates slowly, the upper stratum of the clot is not red, but only yellowish, on account of the absence of colored corpuscles. This is regularly the case in horse's blood, and in human blood it is observed especially in inflammations; hence this layer has been called **crusta phlogistica.** Such blood contains more fibrin, and so coagulates more slowly.

The crusta is formed under other circumstances, *e.g.*, with increased sp. gr. of the corpuscles, or diminished sp. gr. of the plasma (as in hydræmia and chlorosis), whereby the corpuscles sink more rapidly, and also during pregnancy. The taller and narrower the glass, the thicker is the crusta (compare § 41). The upper end of the clot, where there are few corpuscles, shrinks more, and is therefore smaller than the rest of the clot. This upper, lighter-colored layer is called the "**buffy coat;**" but it gradually passes, both in size and color, into the normal dark-colored clot. [Sometimes the upper surface of the clot is concave or "**cupped.**" The older physicians attached great importance to this condition, and also to the occurrence of the buffy coat.]

Defibrinated Blood.—If freshly-shed blood be beaten or whipped with a glass rod, or with a bundle of twigs, fibrin is deposited on the rod or twigs in the form of a solid, fibrous, yellowish-white, elastic mass, and the blood which remains is called "*defibrinated blood*" (p. 70). [The twigs and fibrin must be washed in a stream of water to remove adhering corpuscles.]

Coagulation of Plasma.—Plasma shows phenomena exactly analogous, save that the clot is not so well marked, owing to the absence of the resisting corpuscles; there is, however, always a soft trembling jelly formed when plasma coagulates. [In Hewson's experiment on the blood of a horse tied in a vein, he found that the plasma coagulated—fibrin being formed, so that he showed coagulation to be due to changes in the plasma itself (§ 29).]

Properties of Fibrin.—Although the fibrin appears voluminous, it only occurs to the extent of 0.2 per cent. (0.1 to 0.3 per cent.) in the blood. The amount varies considerably in two samples of the same blood. It is insoluble in water and ether; alcohol shrivels it by extracting water; dilute hydrochloric acid (0.1 per cent.) causes it to swell up and become clear, and changes it into syntonin

or acid albumin (§ 249, III). When fresh, it has a grayish-yellow, fibrous appearance, and is elastic; when dried, it is horny, transparent, brittle, and friable.

When fresh it dissolves in 6–8 per cent. solutions of sodium nitrate or sulphate, in dilute alkalies, and in ammonia, thus forming alkali-albuminate. Heat does not coagulate these solutions. [It is also soluble in, or rather decomposed by, 5–10 per cent. solutions of neutral salts, *e.g.*, NaCl, yielding two fibro-globulins (*Green*).] Hydric peroxide is rapidly decomposed by fibrin into water and O (*Thénard*). Fibrin which has been exposed to the air for a long time is no longer soluble in solution of potassic nitrate, but in neurin (*Mauthner*). During putrefaction it passes into solution, albumin being formed. Fibrin contains, entangled in it, ferric, calcic, and magnesic phosphates, and calcium sulphate whose origin is unknown.

Time for Coagulation.—The first appearance of a coagulum occurs in man's blood after 3 minutes 45 seconds, in woman's blood after 2 min. 20 sec. (*H. Nasse*). Age has no effect; withdrawal of food accelerates coagulation (*H. Vierordt*).

28. GENERAL PHENOMENA OF COAGULATION.—I. Blood in direct contact with living unaltered blood vessels does not coagulate. [Hewson (1772) found that when he tied the jugular vein of a horse in two places, and excised it, the blood did not coagulate for a long time.] Brücke filled the heart of a tortoise with blood which had stood 15 minutes exposed to the air at 0°, and kept it in a moist chamber; at 0° C. the blood was still uncoagulated in the contracting heart after eight days. Blood in a contracting frog's heart preserved under mercury does not coagulate. If the wall of the vessel be altered by **pathological processes** (*e.g.*, if the intima becomes rough and uneven, or undergoes inflammatory change), coagulation is apt to occur at these places. Blood rapidly coagulates in a *dead* heart, or in blood vessels (but not in capillaries) or other canals (*e.g.*, the ureter). If blood stagnates in a living vessel, coagulation begins in the central axis, because here there is no contact with the wall of the living blood vessel.

II. **Conditions which Hinder or Delay Coagulation.**—(*a*) The addition of small quantities of *alkalies*, *ammonia*, or concentrated solutions of *neutral salts of the alkalies and earths* (alkaline chlorides, sulphates, phosphates, nitrates, carbonates). Magnesic sulphate acts most favorably in delaying coagulation (1 vol. solution of 28 per cent. to 3½ vols. blood of the horse).

(*b*) Precipitation of the fibrino-plastin by adding weak acids, or CO_2.

By the addition of *acetic acid* until the reaction is acid, coagulation is completely arrested. A large amount of CO_2 delays it, hence venous blood coagulates more slowly than arterial, and the blood of *suffocated* persons remains fluid for the same reason.

(*c*) The addition of *egg-albumin*, *syrup*, *glycerine*, and much *water*. If uncoagulated blood be brought into contact with a layer of already-formed fibrin, coagulation occurs later.

(*d*) By *cold* (0° C.) coagulation may be delayed for one hour. If blood is frozen at once, after thawing it is still fluid, and then coagulates (*Hewson*). When shed blood is under *high pressure* it coagulates slowly.

(*e*) Blood of *embryo fowls* does not coagulate before the twelfth or fourteenth day of incubation (*Boll*); that of the *hepatic vein* very slightly; *menstrual blood* shows little tendency to coagulate when alkaline mucus from the vagina is mixed with it. If it be rapidly discharged, it coagulates in masses. Fœtal blood at the moment of birth coagulates soon.

(*f*) *Blood rich in fibrin* from inflamed parts coagulates slowly, but the clot so formed is firm.

(*g*) [Blood coagulates more slowly in a smooth than a rough vessel, and also in a shallow vessel than in a deep one.]

Hæmophilia.—A very slight scratch in some persons may cause very free bleeding. These persons are called colloquially "**bleeders**," and are said to have **hæmophilia** or the **hemorrhagic diathesis**. In "bleeders" coagulation seems not to take place, owing to a want of the substances producing fibrin; hence, in these cases, wounds of vessels are not plugged with fibrin. [A tendency to hemorrhage occurs in scurvy, purpura, in some infectious diseases, such as typhus, plague, yellow fever, and in poisoning with phosphorus.]

Injection of Peptones.—Albertoni observed that if tryptic pancreas ferment (dissolved in glycerine) be injected into the blood of an animal, the blood does not coagulate. Schmidt-Mülheim found that after the injection of *pure peptone* into the blood (0.5 gram per kilo.) of a dog, the blood lost its power of coagulating. [This occurs in the dog, but not in the rabbit. Peptonized blood coagulates when it is treated with CO_2 or water. It appears, however, that it is not the peptone which prevents the coagulation, but the albumoses adhering to it which do so.] A substance is formed in the plasma, which prevents coagulation, but which is precipitated by CO_2. Lymph behaves similarly (*Fano*). After peptones are injected, there is a great solution of leucocytes in the blood (*v. Samson-Himmelstjerna*). The secretion of the mouth of the medicinal leech [although its action is not due to a ferment (*Haycraft*)] and snake poison also prevent coagulation (*Wall*). [Diastatic ferment also prevents coagulation (*Salvioli*).]

III. **Coagulation is accelerated**—(*a*) **By contact with foreign Substances of all kinds**, but only when the blood adheres to them, hence, threads or needles introduced into arteries are rapidly covered with fibrin. Blood does not coagulate in contact with bodies covered with fat or vaseline (*Freund*). Even the introduction of air bubbles into the circulation or the passage of indifferent gases, N or H, through blood, accelerates it. The pathologically altered wall of a vessel acts like a foreign body. Blood shed from an artery rapidly coagulates on the walls of vessels, on the surfaces exposed freely to air, and on the rods or twigs used to beat it.

(*b*) The products of the retrogressive metabolism of proteids (uric acid, glycin, leucin, taurin, kreatin, sarkin, but not urea) favor coagulation by increased ferment formation; but if they are added in excess, they retard the process.

From a watery extract of the testis or thymus, on the addition of acetic acid, is precipitated a substance which is soluble in sodic carbonate. It is a mixture of **lecithin** and albumin, and when it is injected into the blood stream it causes almost instantaneous death by intravascular coagulation (*Wooldridge*).

(*c*) During rapid hemorrhage, the last portions of blood coagulate most rapidly (*Holzmann*).

(*d*) Heating the blood from 39° to 55° C. (*Hewson*).

(*e*) Agitation of the blood (*Hewson and Hunter*).

[(*f*) The addition of a small quantity of water.

(*g*) A *watery* condition of the blood. The clot is small and soft.

(*h*) Contact with oxygen.]

IV. **Rapidity of Coagulation.**—Among vertebrates, the blood of birds (especially of the pigeon) coagulates almost momentarily; in cold-blooded animals coagulation occurs much more slowly, while mammals stand midway between the two.

[The blood of a fowl begins to coagulate in ½ to 1½ minute; pig, sheep, rabbit, in ½ to 1½ minute; dog, 1 to 3 minutes; horse and ox, 5 to 13 minutes; man, 3 to 4 minutes; solidification is completed in 9 to 11 minutes (*Nasse*).] The blood of invertebrates, which is usually colorless when it is oxidized (§ 32), forms a soft, whitish clot of fibrin. Even in *lymph* and *chyle*, a small soft clot is formed.

V. When coagulation occurs, the aggregate condition of the fibrin factors is altered, so that **heat must be set free** (*Valentin*, 1844).

VI. In blood shed from an artery, the degree of **alkalinity diminishes** from the time of its being shed until coagulation is completed (*Pflüger and Zuntz*). This is probably due to a decomposition in the blood, whereby an acid is developed, which diminishes the alkalinity (p. 72).

VII. During coagulation there is a **diminution of the O** in the blood, although a similar decrease also occurs in non-coagulated blood. Traces of *ammonia* are also given off, which Richardson erroneously supposed to be the cause of the coagulation of the blood.

[This is refuted—(1) by the fact that blood, when collected under mercury (whereby no escape of ammonia is possible), also coagulates; and (2) by the following experiment of Lister: He placed two ligatures on a vein containing blood, moistening one-half of the outer surface of the

vein with ammonia, leaving the other half intact. The blood coagulated in the first half, and not in the other, owing to the properties of the wall of the vein of the former being altered. Neither the decrease of O nor the evolution of ammonia seems to have any causal connection with the formation of fibrin.]

Pathological.—When the blood coagulates within the vessels during life, the process is called **thrombosis**, and the coagulum or plug so formed is termed a **thrombus.** When a clot of blood or other body is carried by the blood stream to another part of the vascular system where it blocks up a vessel, the plug is called an **embolus**, and the result **embolism.**

29. **CAUSE OF THE COAGULATION OF BLOOD.**—[**Hewson's Experiments** (1772.)—Hewson tied the jugular vein of a horse between two ligatures, removed it, and then suspended it by one end (Fig. 21). He found that the blood remained fluid for a long time (48 hours), the red corpuscles sank (R C) and left a clear layer of plasma on the surface (P). On drawing off some of this clear plasma it coagulated, thus proving coagulation to be due to changes in the plasma. Lister repeated this experiment, and found that, even if the upper end of the tube be opened and the blood freely exposed to the air, coagulation is but slightly hastened. He showed that the blood might be poured from one vein into another, just as one might pour fluid from one test tube into another. In this case there were two test tubes, *i. e.*, the veins—and although the blood, on being poured from the one to the other, came into contact with the air, it did not coagulate. Hewson, however, found that blood poured from the vein into a glass vessel coagulated, so that, in his opinion, the blood vessels exerted a restraining influence on coagulation. By cooling the blood and preventing it from coagulating, he proved that coagulation was not due to the loss of heat. Nor could it be a vital act, as sodic sulphate or other neutral salt prevented coagulation indefinitely, but coagulation took place when the blood was diluted with water.]

FIG. 21.



Vein of horse tied between two ligatures. P, plasma; W C, white, and R C, red corpuscles.

[**Buchanan's Researches.**—The serous sacs of the body contain a fluid which in some respects closely resembles lymph. The pericardial fluid of some animals coagulates spontaneously (*e. g.*, in the rabbit, ox, horse, and sheep) if the fluid be removed *immediately after death.* If this be not done till *several hours after death* the fluid does not coagulate spontaneously. The fluid of the tunica vaginalis of the testis sometimes accumulates to a great extent, and constitutes *hydrocele*, but this fluid shows no tendency to coagulate spontaneously. Andrew Buchanan found, however, that if to the fluid of ascites, pleuritic fluid, or hydrocele fluid, there be added clear blood serum, then coagulation takes place, *i. e.* two fluids—neither of which shows any tendency *by itself* to coagulate—form a clot when they are mixed (1831). He also found, that if "washed blood clot" (which consists of a mixture of fibrin and colorless corpuscles) be added to hydrocele fluid, coagulation occurred. He compared the action of washed blood clot to the action of rennet in coagulating milk, and he imagined *the agents which determined the coagulation to be colorless corpuscles.* Thus, the buffy coat of horses' blood is a powerful agent, and it contains numerous colorless corpuscles. He finally concluded that some constituent in the plasma, to which he gave the name of a "soluble fibrin," is acted upon by the colorless corpuscles and converted into fibrin. The soluble fibrin of Buchanan is comparable to the fibrinogen in Hammarsten's theory. Buchanan, however, did not separate the substance.]

[**Denis's Plasmine** (1859).—Denis mixed uncoagulated blood with a saturated solution of sodic sulphate, and allowed the corpuscles to subside. The salted plasma thus obtained he precipitated with sodic chloride. The precipitate, when washed with a saturated solution of sodic chloride, he called **plasmine.** If plasmine be mixed with water, it coagulates spontaneously, resulting in the formation of fibrin, while another proteid remains in solution. According to the view of Denis, fibrin is produced by the splitting up of plasmine into two bodies—fibrin and a soluble proteid.]

[**A. Schmidt's Researches** (1861).—This observer re-discovered the chief facts already known to Buchanan, viz., that some fluids which do not coagulate spontaneously, clot when mixed with other fluids which show no tendency to coagulate spontaneously, *e. g.*, hydrocele fluid and blood serum. He isolated from these fluids the bodies described as fibrinogen and fibrino-plastin. The bodies so obtained were not pure, but Schmidt supposed that the formation of fibrin was due to the interaction of these two proteids. The reason hydrocele fluid does not coagulate, he says, is that it contains fibrinogen and no fibrino plastin, while blood serum contains the latter, but not the former. Schmidt afterwards discovered that these two substances may be present in a fluid, and yet coagulation may not occur (*e.g.*, occasionally in hydrocele fluid). He supposed, therefore, that blood or blood serum contained some other constituent necessary for coagulation. This he afterwards isolated in an impure condition and called *fibrin-ferment.*]

A. Schmidt's theory is that fibrin is formed by the coming together of *two proteid substances* which occur dissolved in the plasma, viz.: (1) **fibrinogen,**

i. e., the substance which yields the chief mass of the fibrin, and (2) **fibrino-plastic substance** or fibrino-plastin (serum-globulin or paraglobulin, § 32). In order to determine the coagulation a ferment seems to be necessary, and this is supplied by (3) the **fibrin-ferment.**

1. **Properties.**—Fibrinogen and fibrino-plastin belong to the group of proteids called **globulins**, *i. e.*, they are insoluble in pure water, but are soluble in dilute solutions of common salt (§ 249), and are not distinguished from each other by well-marked chemical characters. Still they differ, as follows:—

Fibrino-plastin is more easily precipitated from its solutions than fibrinogen. It is more readily redissolved when once it is precipitated. It forms when precipitated a very light granular powder.

Fibrinogen adheres as a sticky deposit to the side of the vessel. It coagulates at 56° C.

On account of their great similarity, both substances are not usually prepared from blood plasma. *Fibrinogen* is prepared from *serous* transudations (pericardial, abdominal, or pleuritic fluid, or the fluid of hydrocele), which contain no fibrino-plastin. *Fibrino-plastin* is most readily prepared from *serum*, in which there is still plenty of fibrino-plastin, but no fibrinogen.

2. **Preparation of Fibrino-plastin, Serum-globulin, or Paraglobulin.**—(*a*) Dilute **blood serum** with twelve times its volume of ice-cold water, and almost neutralize it with acetic acid [add 4 drops of a 25 per cent. solution of acetic acid to every 120 c. c. of diluted serum]; or (*b*) pass a stream of carbon dioxide through the diluted serum, which soon becomes turbid; after a time a fine white powder, copious and granular, is precipitated.

[(*c*) **Method of Hammarsten.**—All the fibrino-plastin in serum is not precipitated either by adding acetic acid or by CO_2. Hammarsten found, however, that if crystals of magnesium sulphate be added to complete saturation, it precipitates the whole of the serum-globulin, but does not precipitate serum-albumin; serum-globulin is more abundant than serum-albumin in the serum of the ox and horse, while in man and the rabbit the reverse obtains; (compare § 32).]

Schmidt found that 100 c.c. of the serum of ox blood yielded 0.7 to 0.8 grm.; horse's serum, 0.3 to 0.56 grm. of dry fibrino-plastin. Fibrino-plastin occurs not only in serum, but also in red blood corpuscles, in the fluids of connective tissue, and in the juices of the cornea.

3. **Preparation of Fibrinogen.**—This is best prepared from **hydrocele fluid**, although it may also be obtained from the fluids of serous cavities, *e.g.*, the pleura, pericardium, or peritoneum. It does not exist in blood serum, although it does exist in blood plasma, lymph, and chyle, from which it may be obtained by a stream of CO_2, after the paraglobulin is precipitated. (*a*) Dilute hydrocele fluid with ten to fifteen times its volume of water, and pass a stream of CO_2 through it for a long time. (*b*) Add powdered *common salt* to saturation to a serous transudation, when a sticky, glutinous (not very abundant) precipitate of fibrinogen is obtained.

[Hammarsten and Eichwald find that, although paraglobulin and fibrinogen are soluble in solutions of common salt (containing 5 to 8 per cent. of the salt), a saline solution of 12 to 16 per cent. is required to precipitate the fibrinogen, leaving still in solution paraglobulin, which is not precipitated until the amount of salt exceeds 20 per cent.]

Properties of the Fibrin Factors.— They are insoluble in pure water, but dissolve in water containing O in solution. Both are soluble in very dilute alkalies, *e. g.*, caustic soda, and are precipitated from this solution by CO_2. They are soluble in dilute common salt—like all globulins—but if a certain amount of common salt be added in excess, they are precipitated. Very dilute hydrochloric acid dissolves them, but after several hours they become changed into a body resembling syntonin or acid albumin (§ 249, III.). Fibrinogen held in solution by common salt coagulates at 52° to 55° C. [Frédéricq finds that fibrinogen

exists *as such* in the plasma; it coagulates at 56° C., and the plasma thereafter is uncoagulable.]

4. Preparation of the Fibrin-Ferment.—(*a*) Mix blood serum (ox) with twenty times its volume of strong alcohol, and after one month filter off the deposit thereby produced. The deposit on the filter consists of coagulated insoluble albumin and the ferment; dry it carefully over sulphuric acid, and reduce to a powder. Triturate 1 gram of the powder with 65 c.c. of water for ten minutes, and filter. The ferment is dissolved by the water, and passes through the filter, while the coagulated albumin remains behind (*Schmidt*).

[(*b*) **Gamgee's Method.**—Buchanan's "washed blood clot" (p. 74) is digested in an 8 per cent. solution of common salt. The solution so obtained possesses in an intense degree the properties of Schmidt's fibrin-ferment.]

In the preparation of fibrino-plastin, the ferment is carried down with it mechanically. The ferment seems to be formed first in fluids outside the body, very probably by the solution of the colorless corpuscles. More ferment is formed in the blood the longer the interval between its being shed and its coagulation. It is destroyed at 70° C. Blood flowing directly from an artery into alcohol contains no ferment. It is also formed in other protoplasmic parts (*Rauschenbach*), *e.g.*, in dead muscle, brain, suprarenal capsule, spermatozoa, testicle (*Foa and Pellacani*), and in vegetable micro organisms [*e.g.*, yeast] and protozoa (*Grohmann*) [so that it would seem to be a general product of protoplasm. As the ferment does not pre-exist in colorless blood corpuscles, it seems to be formed from some mother substance in them, the blood plasma itself decomposing this substance.]

Coagulation Experiments.—According to A. Schmidt, if pure solutions of (1) fibrinogen, (2) fibrino-plastin, and (3) fibrin-ferment be mixed, fibrin is formed. The process goes on best at the temperature of the body; it is delayed at 0°; and the ferment is destroyed at the boiling point. The presence of O seems necessary for coagulation. The amount of the ferment appears to be immaterial; large quantities produce more rapid coagulation, but the amount of fibrin formed is not greater.

[Foa and Pellacani find that a filtered watery extract of fresh brain, capsule of the kidneys, testes, and some other tissues, when injected into the blood vessels of a rabbit, causes coagulation of the blood in the pulmonary circulation and the heart, death being caused by the action of a substance identical with the fibrin-ferment.]

The **amount of salts** present has a remarkable relation to coagulation. Solutions of the fibrin factors deprived of salts, and redissolved in very dilute caustic soda, when mixed, do not coagulate until sufficient NaCl be added to make a 1 per cent. solution of this salt (*Schmidt*). [Green finds that calcium sulphate brings about coagulation in plasma which shows little or no tendency to clot, while coagulation in its absence is almost or quite prevented.]

When blood or blood plasma coagulates, all the fibrinogen is used up, so that the serum contains only fibrino-plastin and fibrin-ferment; hence, the addition of hydrocele fluid (which contains fibrinogen) to serum causes coagulation.

[**Hammarsten's Theory.**—Hammarsten's researches led him to believe that fibrino-plastin is quite unnecessary for coagulation. According to him, fibrin is formed from *one* body, viz., *fibrinogen*, which is present in plasma when it is acted upon by the *fibrin-ferment;* the latter, however, has not been obtained in a pure state. Neither he nor Schmidt asserts that this body is of the nature of a ferment, although they use the term for convenience. It is quite certain that fibrin may be formed when no fibrino-plastin is present, coagulation being caused by the addition of calcic chloride or casein prepared in a special way. But, whether *one* or *two* proteids be required, in all cases it is clear that a certain quantity of salts, especially of NaCl, is necessary.]

[The main drift of the foregoing evidence points to the presence of one proteid —*fibrinogen*—in the plasma, which under certain circumstances yields fibrin. In shed blood this act seems to be determined by a ferment, perhaps derived from the disintegration of colorless corpuscles.]

[**Theory of Wooldridge.**—Wooldridge attributes great importance to **lecithin.** In shed blood the coagulation is brought about by the interaction of the plasma and the colorless corpuscles. If lecithin (which is present in considerable amount in the colorless corpuscles) diffuses into the blood, coagulation takes place. When peptone is injected into the blood of the dog, the blood does not clot; this is due, according to Wooldridge, to the peptone "preventing the interaction of leucocytes and plasma." If, however, the corpuscular elements are removed by the centrifugal machine, the peptone plasma can be made to clot. He also believes that fibrin-ferment does not pre-exist in normal plasma, but that "it may make its appearance in that plasma in the absence of all cellular elements, and must therefore come from some constituent or constituents of the plasma itself."]

30. **SOURCE OF THE FIBRIN FACTORS.**—Al. Schmidt maintains that all the three substances out of which fibrin is said to be formed, arise from the breaking up of colorless blood corpuscles. In the blood of man and mammals, fibrinogen exists dissolved in the circulating blood as a dissolution product of the retrogressive changes of the white corpuscles. Plasma contains dissolved fibrinogen and serum-albumin. The circulating blood is very rich in colorless blood corpuscles, much richer, indeed, than was formerly supposed. As soon as blood is shed from an artery, enormous numbers of the colorless corpuscles are dissolved —according to Al. Schmidt 71.7 per cent. (horse). First the body of the cell disappears, and then the nucleus. The products of their dissolution are dissolved in the plasma, and one of these products is *fibrino-plastin.* At the same time the fibrin-ferment is also produced, so that it would seem not to exist in the intact blood corpuscles. Fibrino-plastin and fibrin-ferment are also produced by the "*transition forms*" of blood corpuscles, *i. e.*, those forms which are intermediate between the red and the white corpuscles. They seem to break up immediately after blood is shed. The *blood plates* (p. 57) are also probably sources of these substances.

In amphibians and birds the *red* nucleated corpuscles rapidly break up after blood is shed, and yield the substance or substances which form fibrin. Al. Schmidt convinced himself that in these animals fibrinogen is originally a constituent of the blood corpuscles.

It is clear, therefore, according to Schmidt's view, that as soon as the blood corpuscles, white or red, are dissolved, the fibrin factors pass into solution, and the formation of fibrin by the interaction of the three substances will ensue.

If a large number of leucocytes be introduced into the circulation of an animal, the leucocytes are dissolved in great numbers in the blood, so that death takes place by diffuse coagulation. Should the animal survive the immediate danger of death, the blood, owing to the want of leucocytes, is completely incapable of coagulating (*Groth*).

[And. Buchanan thought that the potential element of his "washed blood clot" resided in the colorless corpuscles, "primary cells or vesicles." He, like Schmidt, found that the buffy coat of horses' blood, which is very rich in white corpuscles, produced coagulation rapidly. Buchanan compared the action of his washed clot to that of rennet in coagulating milk.]

Pathological.—Al. Schmidt and his pupils have shown that *some* ferment, probably derived from the dissolution of colorless corpuscles, is found in circulating blood, and that it is more abundant in venous than in arterial blood, while it is most abundant in shed blood. It is specially remarkable that in *septic fever* the amount of ferment in blood may increase to such an extent as to permit the occurrence of spontaneous coagulation (thrombosis), which may even produce death (*Arn. Köhler*). In febrile cases generally, the amount of ferment is somewhat more abundant (*Edelberg and Birk*). After the injection of ichor into the blood an enormous number of colorless corpuscles are dissolved (*F. Hoffmann*). The injection of peptone, Hb, and to a less degree of distilled water, is followed by dissolution of numerous leucocytes.

There are changes in the blood, constituting true blood diseases, in which the physiological metabolism of the colorless corpuscles is enormously increased, so that the metabolic products accumulate in the blood (*Alex. Schmidt*). The result of this is spontaneous coagulation within the circulatory system, and death even may occur; there is always an increase of temperature. After such a condition, the coagulability of the blood is diminished.

31. **FORMATION OF FIBRIN.**—After several observers had shown that the red blood corpuscles (bird, horse, frog) participate in the production of fibrin, Landois observed, in 1874, under the microscope, that the stromata of the red blood corpuscles of mammals passed into fibrin. If a

drop of defibrinated rabbit's blood be placed in serum of frog's blood, without mixing them, the red corpuscles can be seen collecting together; their surfaces are sticky, and they can only be separated by a certain pressure on the cover-glass, whereby some of the now spherical corpuscles are drawn out into threads. The corpuscles soon become spherical, and those at the margin allow the hæmoglobin to escape, the decolorization progresses, from the margin inward, until at last there remain masses of stroma adhering together. The stroma substance is very sticky, but soon the cell contours disappear, and the stromata adhere and form fine fibres. Thus (according to Landois) the formation of fibrin from red blood corpuscles can be traced step by step. The red corpuscles of man and animals, when dissolved in the serum of other animals, show much the same phenomena.

Stroma-Fibrin and Plasma-Fibrin.—Landois calls fibrin formed direct from stroma, *stroma-fibrin*; fibrin formed in the usual way *plasma-fibrin*. The stroma-fibrin is closely related chemically to stroma itself; as yet, however, the two kinds of fibrin have not been sharply distinguished chemically. Substances which rapidly dissolve red corpuscles cause extensive coagulation, *e. g.*, injection of bile or bile salts, or lake-colored blood, into arteries. After the injection of foreign blood the newly-injected blood often breaks up in the blood vessels of the recipient, while the finer vessels are frequently found plugged with small thrombi (§ 102).

Coagulable Fluids.—With regard to coagulability, fluids containing proteids may be classified thus:—

(1) Those that *coagulate spontaneously*, *i. e.*, blood, lymph, chyle.
(2) Those *capable of coagulating*, *e. g.*, fluids secreted pathologically in serous cavities; for example, hydrocele fluid, which, as usually containing fibrinogen only, does not coagulate spontaneously, but it coagulates on the addition of fibrino-plastin and ferment (or of blood serum in which both occur).
(3) Those which *do not coagulate*, *e. g.*, milk or seminal fluid, which do not seem to contain fibrinogen.

32. CHEMICAL COMPOSITION OF PLASMA AND SERUM.—I. **Proteids** occur to the amount of 8 to 10 per cent. in the plasma. Only 0.2 per cent. of these go to form fibrin. After the formation of the fibrin the plasma is converted into serum. The sp. gr. of human serum is 1027 to 1029. It contains several proteids. [According to Hammarsten, *human* serum contains 9.207 per cent. of solids,—of these, 3.103 = serum-globulin, and 4.516 = serum-albumin, *i. e.*, in the ratio of 1 : 1.511. In horse serum the proportion is 4.5 : 2.6, in ox serum 4.16 : 3.29, and rabbit serum 6.22 : 1.78. The total amount of proteids in blood seems to be much more constant than are the relative proportions of serum-albumin and serum-globulin (*Salvioli*).]

(*a*) **Serum-globulin** or **Paraglobulin** (2 to 4 per cent.). If crystals of magnesium sulphate be added to saturation to serum at 35° C., serum-globulin is precipitated, but not serum-albumin. It is soluble in 10 per cent. solution of common salt, and coagulates at 69–75° C. Its specific rotatory power is — 47.8° (*Frédéricq*).

[Serum-globulin was described by Panum under the name of "serum-casein"; by Al. Schmidt, as "fibrino-plastic substance"; and by Kühne, as "paraglobulin."] During hunger the globulin increases and the albumin diminishes.

(*b*) **Serum-albumin** (3–4 per cent.). Its solutions begin to be turbid at 60° C., and coagulation occurs at 73° C., the fluid becoming slightly more alkaline at the same time. If sodium chloride be cautiously added to serum, the coagulating temperature may be lowered to 50° C. Its specific rotatory power is from — 62.6 to 64.5° (*Starke*). It is changed into syntonin or acid albumin by the action of dilute HCl, and by dilute alkalies into alkali-albuminate.

Serum-albumin is absent from the blood of starving snakes; and reappears after they are fed (*Tiegel*).

[**Serum-Albumin** *v.* **Egg-Albumin**—Although serum-albumin is closely related to egg-albumin they differ—(*a*) as regards their action upon polarized light; (*b*) the precipitate produced by adding HCl or HNO_3 is readily soluble in 4 c.c. of the reagent in the case of serum-albumin, while the precipitate in egg-albumin is dissolved with very great difficulty; (*c*) egg-albumin, injected into the veins, is excreted in the urine as a foreign body, while serum-albumin is not; (*d*) serum-albumin is not coagulated by ether, while egg-albumin is, if the solution

is not alkaline (§ 249). Serum-albumin has never been obtained free from salts, even when it is dialysed for a very long time.]

After all the serum-globulin in serum is precipitated by magnesium sulphate, serum-albumin still remains in solution. If this solution is heated to 40 or 50° C. a copious precipitate of non-coagulated serum-albumin is obtained, which is soluble in water. If the serum-albumin be filtered from the fluid, and if the clear fluid be heated to over 60° C., Frédéricq found that it becomes turbid from the precipitation of other proteids; the amount of these other bodies, however, is small.

[**Proteids of the Serum.**—Halliburton has shown by the method of "**fractional heat coagulation**" (*i. e.*, ascertaining the temperature at which a proteid is coagulated, filtering the fluid and again heating the filtrate to a higher temperature), that from the same fluid perhaps two or more proteids, all with different temperatures of coagulation, may be obtained. Care must be taken to keep the reaction constant. He finds that serum-globulin coagulates at 75° C., while serum-albumin in reality consists of three proteids, which coagulate at different temperatures; (α) at 73°, (β) at 77°, and (γ) at 84° C.]

[**Precipitation by Salts.**—Sulphate of magnesia not only precipitates serum-globulin but also fibrinogen. The fluid must be shaken for several hours to get complete saturation. Sodic sulphate, when added to serum deprived of its globulin by $MgSO_4$, precipitates serum-albumin, but it produces no precipitate with pure serum. In this way serum-albumin may be obtained in a pure, uncoagulated, and still soluble condition. Serum-globulin is thrown down by sodic nitrate, acetate, or carbonate; while *all* the proteids of the serum are precipitated by potassic acetate or phosphate, and the same result is brought about by adding two salts, *e.g.*, $MgSO_4$ and Na_2SO_4 (in this case sodio-magnesic sulphate is formed); $MgSO_4$ and $NaNO_3$; $MgSO_4$ and KI; NaCl and Na_2SO_4. After serum-globulin is thrown down by $MgSO_4$, the addition of $MgSO_4$ and Na_2SO_4 or the double-salt, precipitates the serum-albumin, which is still soluble in water. As sulphate of ammonia precipitates all the proteids except peptones, it may be used (*Halliburton*).]

[**The plasma of Invertebrata** (decapod crustaceans, some gasteropods, cephalopods, etc.) clots like vertebrate blood, and contains fibrinogen, but, in addition, there is found in it a substance corresponding to hæmoglobin, and called by Frédéricq, **hæmocyanin.** It exists like Hb in two conditions, one reduced and the other oxy-hæmocyanin, the former being colorless, the latter blue. In its general characters it resembles Hb, although it contains *copper* instead of iron, and gives no absorption-bands (*Halliburton*). In the blood of some decapod crustaceans there is a reddish pigment, **tetronerythrin,** which is identical with that in the exoskeleton and hypoderm. It belongs to the group of lipochromes, like some of the pigments of the retina. The hæmocyanin is respiratory in function, and it is remarkable that it is contained in the plasma, and not in the formed elements like the Hb of vertebrates. So that, stated broadly, in these invertebrates the plasma is both nutritive and respiratory in its functions, while in vertebrates the red blood corpuscles chiefly are respiratory and the plasma nutritive.]

II. **Fats** (0.1 to 0.2 per cent.).—**Neutral fats** (tristearin, tripalmitin, triolein) occur in the blood in the form of small microscopic granules, which, after a meal rich in fat (or milk) render the serum quite milky.

[The amount of fat in the serum of fasting animals is about 0.2 per cent.; during digestion 0.4 to 0.6 per cent.; and in dogs fed on a diet rich in fat it may be 1.25 per cent. There are also minute traces of *fatty acids* (succinic). Röhrig showed that *soluble soaps*, *i.e.*, alkaline salts of the fatty acids, cannot exist in the blood. **Cholesterin** may be considered along with the fats. It occurs in considerable amount in nerve tissues, and, like fats, is extracted by ether from the dry residue of blood serum. Hoppe-Seyler found 0.019 to 0.314 per cent. in the serum of the blood of fattened geese. There is no fat in the red blood corpuscles. **Lecithin** (its decomposition products, glycerin-phosphoric acid and protagon) occur in serum and also in the blood corpuscles.]

III. Traces of **Grape Sugar** [0.1 to 0.15 per cent. (more in the hepatic vein, 0.23 per cent.)] derived from the liver and muscles, and increased after hemorrhage (§ 175); some **glycogen,** and another reducing fermentative substance also increased by hemorrhage.

The amount of grape sugar in the blood increases with the absorption of sugar from the intestine, and this increase is most obvious in the blood of the portal and hepatic veins; there is also a slight increase in the arterial blood, but there it is rapidly changed. The presence of sugar is ascertained by coagulating blood by boiling it with sodium sulphate, pressing out the

fluid and testing it for sugar with Fehling's solution (*Cl. Bernard*). Pavy coagulates the blood with alcohol.

IV. **Extractives.**—Kreatin, urea (0.016 per cent., increased after nitrogenous food), succinic acid, and uric acid (more abundant in gouty conditions), guanin (?), carbamic acid, sarcolactic acid; all occur in very small amounts.

V. **Salts** (0.85 per cent.), especially *sodic chloride* (0.5 per cent.) and *sodic carbonate*. [It is most important to note that the *soda* salts are far more abundant in the serum than the potassium salts. The ratio may be as high as 10 : 1.] Animal diet increases the amount of salts, vegetable food diminishes it temporarily.

Salts in human blood serum (*Hoppe-Seyler*).

Sodic Chloride, ...	4.92 per 1000	Sodic Phosphate, . . .	0.15 per 1000
" Sulphate, ...	0.44 "	Calcic Phosphate, . . . }	0.73 "
" Carbonate, ...	0.21 "	Magnesic " . . . }	

If large quantities of salts are introduced into the blood, they almost entirely disappear from the blood stream within a few minutes, chiefly by diffusion into the tissues. They are gradually eliminated by the kidneys. The same is true of sugar and peptones (*Ludwig and Klicowicz*).

VI. **Water** about 90 per cent.

VII. A yellow **pigment.**

The pigment may be extracted with methylic alcohol. It shows two absorption-bands of a lipochrome like lutein (*Krukenberg*). Thudichum regards the pigment of the serum as lutein; Maly, as hydrobilirubin; and MacMunn as choletelin.

33. **THE GASES OF THE BLOOD.—Absorption by Solid Bodies.**—A considerable attraction exists between the particles of solid porous bodies and gases, whereby the latter are attracted and condensed within the pores of solid bodies, *i. e.*, the gases are *absorbed*. Thus, 1 volume of boxwood charcoal (at 12° C. and ordinary barometric pressure) absorbs 35 volumes CO_2, 9.4 vol. O, 7.5 vol. N, 1.75 vol. H. *Heat* is always formed when gases are absorbed, and the amount of heat evolved bears a relation to the energy with which the absorption takes place. Non-porous bodies are similarly invested by a layer of condensed gases *on their surface*.

By Fluids.—*Fluids* can also absorb gases. *A known quantity of fluid at different pressures* always absorbs the *same volume of gas*. Whether the pressure be great or small, the *volume* of the gas absorbed is equally great (*W. Henry*). But according to Boyle (1662) and Mariotte's law (1679) on the compression of gases, when the pressure within the same *volume* of gas is increased, the *volume varies inversely as the pressure*. Hence it follows that, with *varying pressure*, the *volume* of gas absorbed remains the same, but the *quantity of gas* (*weight*) *is directly proportional to the pressure*. If the pressure = 0, the weight of the gas absorbed must also = 0. As a necessary result of this, we see that (1) *fluids can be freed of their absorbed gases in a vacuum under an air-pump*.

Coefficient of Absorption means the *volume* of a gas (0° C.) which is absorbed by a unit of volume of a liquid (at 760 mm. Hg) at a given temperature. The *volume* of a gas absorbed, and therefore the coefficient of absorption, is quite independent of the pressure, while the *weight* of the gas is proportional to it. *Temperature* has an important influence on the coefficient of absorption. With a low temperature it is greatest; it diminishes as the temperature increases; and at the *boiling point* it = 0. Hence, it follows that (2) *absorbed gases may be expelled from fluids simply by causing the fluids to boil*. The coefficient of absorption diminishes for different fluids and gases, with increasing temperature, in a *special*, and by no means uniform, manner, which must be determined empirically for each liquid and gas. Thus the coefficient of absorption for CO_2 in water diminishes with an increasing temperature, while that for H in water remains unchanged between 0° and 20° C.

Diffusion of Gases.—Gases which do not enter into chemical combinations with each other mix with each other in definite proportions. If the necks of two flasks be placed in communication by means of a glass or other tube, and if the lower flask contain CO_2, and the upper one H, the gases mix *quite independently of their different specific gravities*, both gases forming in each flask a perfectly uniform mixture. The phenomenon is called the *diffusion of gases*. If a *porous membrane* be previously inserted between the gases, the exchange of gases still goes on through the membrane. But (as with endosmosis in fluids) the gases pass with unequal rapidity through the pores, so that at the beginning of the experiment a larger amount of gas is found on one side of the membrane than on the other. According to Graham, the rapidity of the diffusion of the gases through the pores is inversely proportional to the square root of their specific gravities. (According to Bunsen, however, this is not quite correct.)

Different Gases in a Gaseous Mixture do not Exert Pressure upon one another.—Gases, therefore, pass into a space filled with another gas, as they would pass into a vacuum. If the surface of a fluid containing absorbed gases be placed in contact with a very large quantity of another gas, the absorbed gases diffuse into the latter. Hence, absorbed gases can be removed by (3) *passing a stream of another gas through the fluid, or by merely shaking up the fluid with another gas.*

Partial Pressure.—If *two or more gases are mixed* in a closed space over a fluid, as the different gases existing in a gaseous mixture exert no pressure upon each other, the several gases are absorbed. The weight of each absorbed is proportional to the pressure under which each gas would be, were it the only gas in the space. This pressure is called the *partial pressure* of a gas (*Bunsen*). The absorption of gases from their mixtures, therefore, is *proportional to the partial pressure.* The partial pressure of a gas in a space is at the same time the expression for the tension of the gas absorbed by a fluid.

The air contains 0.2096 volume of O, and 0.7904 volume N. If 1 volume of the air be placed under a pressure, P, over water, the partial pressure under which O is absorbed = 0.2096 P; that for N = 0.7904 P. At 0° C., and 760 mm. pressure, 1 volume of water absorbs 0.02477 volume of air, consisting of 0.00862 volume O, and 0.01615 volume N. It contains, therefore, 34 per cent. O and 66 per cent. N. *Therefore, water absorbs from the air a mixture of gases containing a larger percentage of O than the air itself.*

34. EXTRACTION OF THE BLOOD GASES.—[The blood to be analyzed must be collected over mercury so as to avoid contact with air. This is done by means of a special apparatus, consisting of a graduated tube filled with mercury and communicating with a glass globe also filled with mercury, which can be lowered as the blood flows into the graduated tube.] The extraction of the gases from the blood, and their collection for chemical analysis, are carried out by means of the mercurial pump (*C. Ludwig*). Fig. 22 shows in a diagrammatic form the arrangement of Pflüger's gas pump.

It consists of a receptacle for the blood, or "**blood-bulb**" (A), a *glass globe* capable of containing 250 to 300 c.c., connected above and below with tubes, each of which is provided with a stop-cock, *a* and *b*; *b* is an ordinary stop-cock, while *a* has through its long axis a perforation which opens at *x*, and is so arranged that, according to the position of the handle, it leads up into the blood-bulb (position *x*, *a*), or downward through the lower tube (position *x'*, *a'*). This blood-bulb is first completely emptied of air (by means of a mercurial air pump), and then carefully weighed. One end (*x'*) of it is tied into an artery or a vein of an animal, and when the lower stop-cock is placed in the position *x*, *a*, blood flows into the receptacle. When the necessary amount of blood is collected, the lower stop-cock is put into the position *x'*, *a'*, and the blood-bulb, after being cleaned most carefully, is weighed to ascertain the weight of the amount of blood collected. The second part of the apparatus consists of the **froth-chamber**, B, leading upward and downward into tubes, each of which is provided with an ordinary stop-cock, *c* and *d*. The froth-chamber, as its name denotes, is to catch the froth which is formed during the energetic evolution of the gases from the blood. The lower aperture of the froth-chamber is connected by means of a well-ground tube with the blood-bulb, while above it communicates with the third part of the apparatus, the **drying-chamber**, G. This consists of a U-shaped tube, provided below with a small glass bulb, which is half filled with sulphuric acid, while in its limbs are placed pieces of pumice-stone also moistened with sulphuric acid. As the blood gases pass through this apparatus (which may be shut off by the stop-cocks *e* and *f*), they are freed from their *watery vapor* by the sulphuric acid, so that they pass quite dry through the stop-cock, *f*. The short, well-ground tube, D, is fixed to *f*, and to the former is attached the small *barometric tube* or *manometer*, *y*, which indicates the extent of the vacuum. From D we pass to the pump proper. This consists of two large glass bulbs, which are continued above and below into open tubes; the lower tubes, Z and *w*, being united by a caoutchouc tube, G. Both the bulbs and the caoutchouc tube contain mercury—the bulbs being about half full, and F being larger than E. The bulb, E, is fixed; but F can be raised or lowered by means of a pulley with a rack and pinion motion. If F be raised, E is filled; if F be lowered, E is emptied. The upper end of E divides into two tubes, *g* and *h*, of which *g* is united to D. The ascending tube, *h* (gas-delivery tube), is very narrow, and is bent so that its free end dips into a vessel containing mercury, *v* (a pneumatic trough), and the opening is placed exactly under the tube for collecting the gases, the **eudiometer**, J, which is also filled with mercury. Where *g* and H unite, there is a two-way stop-cock, which in one position, H, places E in communication with A, B, G, D, the chambers to be exhausted, and in the position K shuts off A, B, G, D, and places the bulb, E, in communication with the gas-delivery tube, *h*, and the eudiometer, J. B, G, D are completely emptied of air, thus: The stop-cock is placed in the position, K; raise F until drops of mercury issue from the fine tube, *i* (not yet placed under J); place the stop-cock in the position H, lower F; stop-cock in position, K, and so on until the barometer, *y*, indicates a complete vacuum. J is now placed over *i*. Open the cocks, *c* and *b*, so that the blood-bulb, A, communicates with the rest of the apparatus, and the blood gases froth up in B, and after being dried in G pass toward E. Lower F, and they pass into E; stop-cock in position, K, raise F, and the gases are collected in J under mercury. The repeated lowering and raising of F with the corresponding position of the stop-cocks ultimately drives all the

gases into J. The removal of the gases is greatly facilitated by placing the blood-bulb, A, in a vessel containing water at 60° C.

It is well to remove the gases from the blood immediately after it is collected from a blood vessel, because the O undergoes a diminution if the blood be kept. Of course, in making several analyses, it is difficult to do this, and the best plan to pursue in that case is to keep the receptacles containing the blood on ice.

Mayow (1670) observed that gases were given off from blood *in vacuo*. Magnus (1837) investi-

FIG. 22.



Scheme of Pflüger's gas-pump. A, blood-bulb; *a*, stop-cock, with a longitudinal perforation opening upward; *a'*, the same opening downward; *b* and *c*, stop-cocks; B, froth-chamber; *d*, *e*, *f*, stop-cocks; G, drying-chambers, containing sulphuric acid and pumice-stone; D, tube, with manometer, *y*.

gated the percentage composition of the blood gases. The more important recent investigations have been made by Lothar Meyer (1857), and by the pupils of C. Ludwig and E. Pflüger.

35. QUANTITATIVE ESTIMATION OF THE BLOOD GASES.—The gases obtained from blood consist of O, CO_2, and N. Pflüger obtained (at 0° C. and 1 metre Hg pressure) 47.3 volumes per cent., consisting of—

O, 16.9 per cent.; **CO_2**, 29 per cent.; **N**, 1.4 per cent.

As is shown in Fig. 22, J, the gases are obtained in an **eudiometer**, *i.e.*, in a narrow tube, closed at one end, and with a very exact scale marked on it, and having two fine platinum wires melted into its upper end, with their free ends projecting into the tube (*p* and *n*).

(1) **Estimation of the CO_2.**—A small ball of *fused caustic potash*, fixed on a platinum wire, is introduced into the mixture of gases through the lower end of the eudiometer under cover of the mercury. The surface of the potash ball is moistened before it is introduced. The CO_2 unites with the potash to form potassium carbonate. The potash bulb is withdrawn after 24 hours. The diminution in volume indicates the amount of CO_2 absorbed.

(2) **Estimation of the O.**—(*a*) Just as in estimating the CO_2, a ball of *phosphorus* on a platinum wire is introduced into the eudiometer; it absorbs the O and forms phosphoric acid. Another plan is to employ a small papier-maché ball saturated with *pyrogallic acid in caustic potash*, which rapidly absorbs O. After the ball is removed, the diminution in volume indicates the quantity of O.

(*b*) The O is most easily and accurately estimated by *exploding it in the eudiometer.* Introduce a sufficient quantity of H into the eudiometer, and accurately ascertain its volume; an electrical spark is now passed between the wires, *p* and *n*, through the mixture of gases; the O and H unite to form water, which causes a diminution in the volume of the gases in the eudiometer, of which ⅓ is due to the O used to form water (H_2O).

(*c*) **Estimation of the N.**—When the CO_2 and O are estimated by the above method, the *remainder* is pure N.

36. **THE BLOOD GASES**—[In human blood, the average total gases are estimated to be, at 0° C. and 1 metre pressure,

	O	CO_2	N
Arterial blood,	17	30	1 to 2 per cent.
Venous blood,	6 to 10	35	1 to 2 "

or, calculated at 0° C. and 760 mm. pressure,

Arterial blood,	20	39	1.4 per cent.
Venous blood,	8 to 12	46	1.4 "]

1. **Oxygen** exists in **arterial** blood (dog) on an average to the extent of 17 volumes per cent. (at 0° C. and 1 metre Hg pressure) (*Pflüger*). According to Pflüger, arterial blood (dog) is saturated to $\frac{9}{10}$ with O, while, according to Hüfner, it is saturated to the extent of $\frac{14}{15}$. In **venous** blood the quantity varies very greatly; in the blood of a passive muscle 6 volumes per cent. have been found; while in the blood after asphyxia it is absent, or occurs only in traces. It is certainly more abundant in the comparatively red blood of active glands (salivary glands, kidney), than in ordinary dark venous blood.

[**Modifying Conditions.**—The amount of O obtainable from the blood depends upon the organ from which the blood comes, or whether the organ be active or at rest. Thus the O present in the

Carotid artery is . .	21 per cent.	Renal vein (kidney active),	17 per cent.
Renal artery, . .	19 "	Renal vein (kidney at rest),	6 "

Bert finds that increase of the *atmospheric pressure* from 1 to 10 atmospheres raises the amount of O in arterial blood from 20 to over 24 per cent., and the N from 1.8 to over 9 per cent., while the CO_2 is but slightly affected.]

The O in Blood occurs—(*a*) *simply absorbed* in the plasma. This is only a minimal amount, and does not exceed what distilled water at the temperature of the body would take up at the partial pressure of the O in the air of the lungs (*Lothar Meyer*).

(*b*) *Almost the total O of the blood is* **chemically united,** and therefore not subject to the law of absorption. It is *loosely* united to the hæmoglobin of the red corpuscles, with which it forms *oxyhæmoglobin* (§ 15). With regard to the taking up of O, the total quantity of blood behaves exactly like a solution of hæmoglobin free from O (*Preyer*). The absorption of O is more rapid in blood than in a solution of Hb.

The absorption of this quantity of O is completely **independent of pressure**; hence, animals confined in a closed space, until they are nearly asphyxiated, can use up almost all the O from the

surrounding atmosphere. The fact of the union being independent of pressure is proved by the following: The blood only gives off copiously its chemically united O when the atmospheric pressure is lowered to 20 millimetres, Hg (*Worm Müller*); and, conversely, blood only takes up a little more O when the pressure is increased to 6 atmospheres (*Bert*).

Physical Methods of Obtaining O from Blood.—Notwithstanding the chemical union between the Hb and O, all the O of the blood can be expelled from its state of combination by those means which set free absorbed gases—(*a*) by introducing blood into a Torricellian vacuum; (*b*) by boiling; (*c*) by the conduction of other gases [H, N, CO, or NO] through the blood, because the oxyhæmaglobin compound is so loose that it is decomposed even by these physical means.

Reducing Reagents.—Among *chemical* reagents the following *reducing* substances—ammonium sulphide, sulphuretted hydrogen, alkaline solutions of sub-salts or Stokes's fluid, iron filings, etc., rob blood of its O (§ 15).

Relation to Fe.—The amount of **iron in the blood** (0.55 in 1000 parts) stands in direct relation to the amount of Hb; this to the quantity of blood corpuscles; and this, in turn, to the specific gravity of the blood. The amount of O in the blood, therefore, is nearly proportional to the specific gravity of the blood, and it is also in proportion to the amount of iron in the blood. Picard affirms that 2.36 grams of iron in the blood can fix chemically 1 gram O; while, according to Hoppe-Seyler, the proportion is 1 atom iron to 2 atoms O.

During morphia narcosis the amount of O in the blood is diminished (*Ewald*); after hemorrhage the arterial blood is saturated with O (*J. G. Ott*).

Disappearance of O in Shed Blood.—Even immediately after blood is shed, there is a slight disappearance of O, as a physiological index of respiration of the tissues within the living blood itself (§ 132). When blood is kept long outside of the blood vessels, the quantity of O gradually diminishes, and if it be kept for a length of time at a high temperature it may disappear altogether. This depends upon decomposition occurring in the blood, whereby reducing substances are formed which consume the O. All kinds of blood, however, do not act with equal energy in consuming O, *e.g.*, venous blood from active muscles acts most energetically, while that from the hepatic vein has very little effect. CO_2 appears in the blood in place of the O, and the color darkens. The amount of CO_2 produced is sometimes greater than that of the O consumed.

Relation to Acids.—If blood (or a solution of oxyhæmoglobin) be acted upon by *acids* (*e.g.*, tartaric acid) until it is strongly acid, O can be pumped out in considerably less amount, while the formation of CO_2 is not increased. We must, therefore, assume that, during the decomposition of the Hb caused by the acids (§ 18), a decomposition product becomes more highly oxidized by the intense chemical union of the O at the moment of its origin (*Lothar Meyer, Zuntz, Strassburg*). The same phenomenon occurs when oxyhæmoglobin is decomposed by *boiling*.

37. IS OZONE PRESENT IN BLOOD?—On account of the numerous and energetic oxidations which occur in connection with the blood, the question has often been raised as to whether the O of the blood exists in the form of ozone (O_3). Ozone, however, is contained neither in the blood itself (*Schönbein*) nor in the blood gases obtained from it. Nevertheless, the red corpuscles (and Hb) have a distinct relation to ozone.

(1) **Tests for Ozone.**—Hæmoglobin acts as a *conveyer of ozone*, *i.e.*, it is able to remove the active O of other bodies and to *convey* or transfer it at once to other easily oxidizable substances. (*a*) Turpentine which has been exposed to the air for a long time always contains ozone. The tests for the latter are starch and potassium iodide, the ozone decomposing the iodide, when the iodine strikes a blue with the starch. (*b*) Freshly-prepared tincture of guaiacum is also rendered blue by ozone. If some tincture of guaiacum be added to turpentine there is no reaction, but on adding a drop of blood a deep blue color is immediately produced, *i.e.*, blood takes the ozone from the turpentine and *conveys* it at once to the dissolved guaiacum, which becomes blue. It is immaterial whether the Hb contains O or not.

(2) It is also asserted that hæmoglobin acts as an *ozone-producer*, *i.e.*, that it can convert the ordinary O of the air into ozone. Hence the reason why red blood corpuscles alone render guaiacum blue. This reaction succeeds best when the guaiacum solution is allowed to dry on blotting-paper, and a few drops of blood (diluted 5 to 10 times) are poured on it. That the Hb forms ozone from the surrounding O, is shown by the fact that red blood corpuscles containing carbonic oxide cause the blue color (*Kühne and Scholz*). According to Pflüger, however, these reactions only occur from decomposition of the Hb, so that on this view the blood corpuscles cannot be regarded as producers of ozone.

Sulphuretted hydrogen is decomposed by blood (as by ozone itself) into sulphur and water.

Hydric peroxide is decomposed by blood into O and water [but this reaction is prevented by the addition of a small amount of hydrocyanic acid (*Schönbein*)]. Crystallized Hb does not do this, and H_2O_2 may be cautiously injected into the blood vessels of animals. This would show that *unchanged* Hb does *not* produce ozone.

Various Forms of Oxygen.—There are three forms of oxygen: (1) The ordinary oxygen(O_2) in the air. (2) Active or nascent oxygen (O), which never can occur in the free state, but the moment it is formed acts as a powerful oxidizing agent and produces chemical compounds. It converts water into hydric peroxide—the N of the air into nitrous and nitric acids, and even CO into CO_2, which ozone does not. It certainly plays an important part in the organism. (3) Ozone (O_3), which is formed by the decomposition of several molecules of ordinary oxygen (O_2) into two atoms of O, and the appropriation of each of these atoms by a molecule of undecomposed oxygen. It is oxygen condensed to $\frac{3}{2}$ of its volume.

38. CO_2 AND N IN BLOOD.—II. **Carbon Dioxide.**—In **arterial** blood there are about 30 volumes per cent. of CO_2 at 0° C. and 1 metre pressure (*Setschenow*); but in **venous** blood the amount is very variable, *e.g.*, in the venous blood of passive muscles there are 35 volumes per cent. (*Sczelkow*), while in the blood of asphyxia there may be 52.6 volumes per cent. The CO_2 in the *lymph* of asphyxia is less than that in the blood (*Buchner, Gaule*). The CO_2 of the blood may be extracted from it or *completely pumped out*, but during the process of evacuation, or removal of the gas, a new property of the red blood corpuscles is produced, whereby they assume the function of an acid, and thus aid in the *chemical* expulsion of the CO_2. This acid-like property of the red corpuscles occurs especially in the presence of O and heat.

(A) **The CO_2 in the Plasma.**—*The largest portion of the CO_2 belongs to the plasma* (or serum), and it all appears to be in a state of **chemical** combination. Serum takes up CO_2 quite independently of pressure, hence it cannot be merely absorbed. A certain part of the CO_2 can be removed from the serum (plasma) by the Torricellian vacuum, while another part is obtained only after the addition of an acid. [The latter is called the "fixed" CO_2, while the former is known as the "loose" CO_2.] The CO_2 in the serum exists in the following conditions:—

(1) CO_2 is united to the soda of the plasma in the form of "*neutral sodic carbonate.*" This portion of the CO_2 can only be displaced from its combination by the addition of an acid, (In depriving blood of its gases the red corpuscles play the rôle of an acid.)

(2) A portion of the CO_2 is *loosely* united to sodic carbonate in the form of *sodic bicarbonate;* the carbonate takes up 1 equivalent of CO_2; $Na_2CO_3 + CO_2 + H_2O = 2NaHCO_3$. This CO_2 may be pumped out, as in the process the bicarbonate splits up again into the neutral carbonate and CO_2.

Preyer has objected to this view on the ground that blood is alkaline in reaction, while all solutions that contain CO_2 in a state of absorption, or loose chemical combinations, are always acid. Pflüger and Zuntz showed that blood, after being completely saturated with CO_2, still remains alkaline.

As the bicarbonate only gives up its CO_2 very slowly *in vacuo*, while blood gives off its CO_2 very energetically, perhaps the soda, united with an albuminous body, combines with the CO_2 and forms a complex compound, from which the CO_2 is rapidly given off *in vacuo*.

(3) A minimal portion of the CO_2 may be chemically united with *neutral sodic phosphate* in the plasma (*Fernet*). One equivalent of this salt can fix one equivalent of CO_2, so *acid* sodium phosphate and *acid* sodium carbonate are formed, $Na_2HPO_4 + CO_2 + H_2O = NaH_2PO_4 + NaH, CO_3$ (*Hermannn*). When the gases are removed the CO_2 escapes, and *neutral* sodic phosphate remains.

It is probable, however, that *almost all* the sodic phosphate found in the blood-ash arises from the burning of lecithin; we have, therefore, to consider only the very small amount of this salt which occurs in the plasma (*Hoppe-Seyler and Sertoli*).

(B) **The CO_2 in the Blood Corpuscles.**—The red corpuscles contain CO_2 in loose chemical combination; for (1) a volume of blood can fix nearly as much CO_2 as an equal volume of serum (*Ludwig, Al. Schmidt*); and (2) with increasing

pressure the absorption of CO_2 by blood takes place in a different ratio from what occurs with serum (*Pflüger, Zuntz*). The red corpuscles can fix more CO_2 than their own volume, and the union of the CO_2 seems to depend upon the Hb, for Setschenow found that, when Hb was acted on by CO_2, its power of fixing the latter was increased, which is perhaps due to the formation of some substance more suited for fixing CO_2. The colorless corpuscles, after the manner of the serum constituents, also fix CO_2 to the extent of $\frac{1}{8}$ to $\frac{1}{12}$ of the absorbing power of serum.

After the use of I, Hg, sodic oxalate, and nitrite, there is a diminution of CO_2 in arterial blood (*Feitelberg*), and also in fever (*Geppert, Minkowski*). [In the last case it is perhaps due to the diminished alkalinity, and this is in part owing to the acid products formed during the decomposition of the tissues.]

III. **Nitrogen** exists in the blood to the extent of 1.4 to 1.6 vol. per cent., and it appears to be simply *absorbed*.

It is doubtful if any part of the N exists chemically united in the red corpuscles. Blood warmed outside the body, and with a free supply of oxygen, gives off a minute quantity of ammonia, which is perhaps derived from the decomposition of some salt of ammonia as yet unknown (*Kühne and Strauch*).

39. ARTERIAL AND VENOUS BLOOD.—Arterial blood contains in solution all those substances which are necessary for the nutrition of the tissues, those which are employed in secretion, and it also contains a rich supply of O. **Venous blood** must contain less of all these, but in addition it holds the used-up or effete substances derived from the tissues, and the products of their retrogressive metabolism are more numerous; there is in venous blood a larger amount of CO_2. It is evident, also, that the blood of certain veins, the portal and hepatic, must have special characters.

The following are the most important points of difference between arterial blood and venous blood:—

Arterial Blood contains—

more O,	more extractives,	less urea.
less CO_2,	more salts,	It is bright red and not dichroic.
more water,	more sugar,	
more fibrin,	fewer blood corpuscles,	As a rule it is 1° C. warmer.

The **bright-red** color of arterial blood depends on the presence of oxyhæmoglobin, while the dark color of venous blood is due to its smaller proportion of oxyhæmoglobin, and the quantity of reduced hæmoglobin which it contains. The dark change of color is not to be attributed to the larger quantity of CO_2 in venous blood (*Marchand*); for if equal quantities of O be added to two portions of blood, and if CO_2 be added to one of them, the color is not changed (*Pflüger*).

[According to C. Schmidt, the blood of the **portal vein** contains more water, plasma, salts, and fats, but less extractives and corpuscles than the blood of the hepatic vein; while (when an animal is not digesting) sugar is absent or at least only in traces in the portal vein, and in considerable amount in the hepatic vein (§ 175)]

40. QUANTITY OF BLOOD.—In the adult the quantity of blood is equal to $\frac{1}{18}$ part of the body weight (*Bischoff*), in newly-born children $\frac{1}{19}$ (*Welcker*).

According to Schücking, the amount of blood in a newly-born child depends to some extent upon the time at which the umbilical cord is ligatured. The amount = $\frac{1}{15}$ of the body weight when the cord is tied at once, while if it is tied somewhat later it may be $\frac{1}{9}$. Immediate ligature of the cord may, therefore, deprive a newly-born child of 100 grams of blood. Further, the number of corpuscles is less in a child after immediate ligature of the umbilical cord than when it is tied somewhat later (*Helot*).

The methods of Valentin (1838), and Ed. Weber (1850), are not now used, as the results obtained are not sufficiently accurate.

Method of Welcker (1854).—Begin by taking the weight of the animal to be experimented on; place a cannula in the carotid, and allow the blood to run into a flask previously weighed, and in which small pebbles (or Hg) have been placed in order to defibrinate the blood by shaking.

Take a part of this defibrinated blood, and make it cherry-red in color by passing through it a stream of CO (because ordinary blood varies in color according to the amount of O contained in it—*Gscheidlen, Heidenhain*). Tie a ⊢ shaped cannula in the two cut ends of the carotid, and allow a 0.6 per cent. solution of common salt to flow into the vessel from a pressure bottle; collect the colored fluid issuing from the jugular veins and inferior vena cava until the fluid is quite clear. The entire body is then chopped up (with the exception of the contents of the stomach and intestines, which are weighed, and their weight deducted from the body weight), and extracted with water, and after twenty-four hours the fluid is expressed. This water, as well as the washings with salt solution, are collected and weighed, and part of the mixture is saturated with CO. A sample of this dilute blood is placed in a vessel with parallel sides (1 cm. apart) opposite the light (the so-called hæmatinometer), and in a second vessel of the same dimensions a sample of the undiluted CO blood is diluted with water from a burette, until both fluids give the *same intensity of color*. From the quantity of water required to dilute the blood to the tint of the washings of the blood vessels, the quantity of blood in the washings is calculated. On chopping up the muscles alone, we obtain the amount of Hb present in them, which is not taken into calculation.

Quantity of Blood in Various Animals.—The quantity of blood in the mouse $= \frac{1}{12}$ to $\frac{1}{18}$; guinea-pig $= \frac{1}{19.7}$ ($\frac{1}{17}$ to $\frac{1}{22}$); rabbit $= \frac{1}{20.1}$ ($\frac{1}{15}$ to $\frac{1}{27}$); dog $= \frac{1}{18}$ ($\frac{1}{11}$ to $\frac{1}{18}$); cat $= \frac{1}{21.5}$; birds $= \frac{1}{10}$ to $\frac{1}{18}$; frog $= \frac{1}{15}$ to $\frac{1}{20}$; fishes $= \frac{1}{14}$ to $\frac{1}{19}$ of the body weight (without the contents of the stomach and intestines).

The specific gravity of the blood ought always to be taken when estimating the amount of blood. The amount of blood is diminished during inanition; fat persons have relatively less blood; after hemorrhage the loss is at first replaced by a watery fluid, while the blood corpuscles are gradually regenerated.

Blood in Organs.—The estimation of the *quantity of blood in different organs* is done by suddenly ligaturing their blood vessels *intra vitam*. A watery extract of the chopped-up organ is prepared, and the quantity of blood estimated as described above. [Roughly it may be said that the lungs, heart, large arteries, and veins contain ¼; the muscles of the skeleton, ¼; the liver, ¼; and other organs, ¼ (*Ranke*).]

41. **ABNORMAL CONDITIONS OF THE BLOOD.**—(A) 1 **Polyæmia.**—(1) An increase in the entire mass of the blood, *uniformly in all organs*, constitutes *polyæmia* or *plethora*, and in over-nourished individuals it may approach a pathological condition. A bluish-red color of the skin, swollen veins, large arteries, hard, full pulse, injection of the capillaries and smaller vessels of the visible mucous membranes are signs of this state, and, when accompanied by congestion of the brain, there is vertigo, congestion of the lungs, and breathlessness. After major amputations with little loss of blood a relative but transient increase of blood has been found (?) (*plethora apocoptica*).

Transfusion.—Polyæmia may be produced artificially by the *injection of blood* of the same species. If the normal quantity of blood be increased 83 per cent. no abnormal condition occurs, because the blood pressure is not permanently raised. The excess of blood is accommodated in the greatly distended capillaries, which may be stretched beyond their normal elasticity. If it be increased to 150 per cent. there are variations in the blood pressure, life is endangered, and there may be sudden rupture of blood vessels (*Worm Müller*).

Fate of Transfused Blood.—After the transfusion of blood the formation of lymph is greatly increased; but in one or two days the serum is used up, the water is excreted chiefly by the urine, and the albumin is partly changed into urea. Hence, the blood at this time appears to be relatively richer in blood corpuscles (*Panum, Lesser, Worm Müller*). The red corpuscles break up much more slowly, and the products thereof are partly excreted as urea and partly (but not constantly) as bile pigments. Even after a month an increase of colored blood corpuscles has been observed (*Tschirjew*). That the blood corpuscles are broken up *slowly* in the economy is proved by the fact, that the amount of urea is much larger when the same quantity of blood is swallowed by the animal than when an equal amount is transfused (*Tschirjew, Landois*). In the latter case there is a moderate increase of the urea, lasting for days, a proof of the slow decomposition of the red corpuscles. Pronounced over-filling of the vessels causes loss of appetite and a tendency to hemorrhage of the mucous membranes.

(2) **Polyæmia serosa** is that condition in which the amount of serum, *i.e.*, the amount of water in the blood, is increased. This may be produced artificially by the transfusion of blood serum from the same species. The water is soon given off in the urine, and the albumin is decomposed into urea, without, however, passing into the urine. An animal forms more urea in a short time from a quantity of transfused serum than from the same quantity of blood, a proof that the blood corpuscles remain longer undecomposed than the serum (*Forster, Landois*). If serum from another species of animal be used (*e.g.*, dog's serum transfused into a rabbit), the blood corpuscles of the

recipient are dissolved; hæmoglobinuria is produced (*Ponfick*); and if there be general dissolution of the corpuscles, death may occur (*Landois*).

(3) **Polyæmia aquosa** is a simple increase of the water of the blood, and occurs temporarily after copious drinking, but increased diuresis soon restores the normal condition. Diseases of the kidneys, which destroy their secreting parenchyma, produces this condition, and often general dropsy, owing to the passage of water into the tissues. Ligature of the ureter produces a watery condition of the blood.

(4) **Plethora polycythæmica, Hyperglobulie.**—An increase of the red corpuscles has been assumed to occur when periodically recurring hemorrhages are interrupted, *e.g.*, menstruation, bleeding from the nose, etc.; but the increase of corpuscles has not been definitely proved. There is a proved case of temporary polycythæmia, viz., when similar blood is transfused, a part of the fluid being used up, while the corpuscles remain unchanged for a considerable time. There is a remakable increase in the number of blood corpuscles (to 8.82 millions per cubic millimetre) in certain severe cardiac affections where there is great congestion, and much water transudes through the vessels. In cases of hemiplegia, for the same reason, the number of corpuscles is greater on the paralyzed congested side (*Pensoldt*). After diarrhœa, which diminishes the water of the blood, there is also an increase (*Brouardel*), and the same is the case after profuse sweating and polyuria. Drugs (alcohol, chloral, amyl nitrite) which act on the blood vessels affect the number of corpuscles; during contraction of the blood vessels their number increases, during dilatation they diminish in number (*Andreesen*). There is a temporary increase in the hæmatoblasts as a reparative process after severe hemorrhage (§ 7), or after acute diseases. In cachectic conditions this increase continues, owing to the diminished non-conversion of these corpuscles into red corpuscles. In the last stages of cachexia the number diminishes more and more until the formation of hæmatoblasts ceases (*Hayen*).

(5) **Plethora hyperalbuminosa** is a term applied to the increase of albumins in the plasma, such as occurs after taking a large amount of food. A similar condition is produced by transfusing the serum of the same species, whereby, at the same time, the urea is increased. Injection of egg-albumin produces albuminuria (*Stokvis, Lehmann*).

[The **subcutaneous injection** of human blood has been practiced with good results in anæmia (*v. Ziemssen*). When defibrinated *human* blood is injected subcutaneously, while its passage into the circulation is aided by massage, it causes neither pain nor inflammation, but the blood of *animals*, and a solution of hæmoglobin, always induce abscess (*Benczur*). Blood is also rapidly absorbed when injected in small amount into the respiratory passages.]

Mellitæmia.—The sugar in the blood is partly given off by the *urine*, and in "**diabetes mellitus**" 1 kilo. (2.2 lbs.) may be given off daily, when the quantity of urine may rise to 25 kilos. To replace this loss of grape sugar a large amount of food and drink is required, whereby the urea may be increased threefold. The increased production of sugar causes an increased decomposition of albuminous tissues; hence the urea is always increased, even though the supply of albumin be insufficient. The patient loses flesh; all the glands, and even the testicles, atrophy or degenerate (pulmonary phthisis is common); the skin and bones become thinner; the nervous system holds out longest. The teeth become carious on account of the acid saliva, the crystalline lens becomes turbid from the amount of sugar in the fluid of the eye which extracts water from the lens, and wounds heal badly because of the abnormal condition of the blood. Absence of all carbohydrates in the food causes a diminution of the sugar in the blood, but does not cause it to disappear entirely. [The sugar in the blood is also increased after the inhalation of chloroform or amyl nitrite, and after the use of curara, nitro-benzole, and chloral (§ 175).] An excessive amount of inosite has been found in the blood and urine (§ 267), constituting **mellituria inosita** (*Vohl*).

Lipæmia, or an Increase of the Fat in the Blood, occurs after every meal rich in fat (*e.g.*, in sucking kittens), so that the serum may become turbid like milk. Pathologically, this occurs in a high degree in drunkards and in corpulent individuals. When there is great decomposition of albumin in the body (and therefore in very severe diseases), the fat in the blood increases, and this also takes place after a liberal supply of easily decomposable carbohydrates and much fat.

After injuries to bones affecting the marrow, not unfrequently fatty granules pass from the marrow through the imperfect walls of the blood vessels into the blood stream. These fatty particles may form fat emboli, *e.g.*, in the liver or lungs, or they may appear in the urine.

If granules of cinnabar or indigo are injected into the blood, they are taken up by the leucocytes, and by them are carried outside the blood stream. The cells of the splenic pulp, marrow of bone, and the liver also take up these particles (*Siebel*).

The **salts** remain very persistently in the blood. The withdrawal of common salt produces albuminuria, and, if all salts be withheld, paralytic phenomena occur (*Forster*). Over-feeding with salted food, such as salt meat, has caused death through fatty degeneration of the tissues, especially of the glands. Withdrawal of lime and phosphoric acid produces atrophy and softening of the bones. In infectious diseases and dropsies the salts of the blood are often increased, and diminished in inflammation and cholera. [Na Cl is absent from the urine in certain stages of pneumonia, and it is a good sign when the chlorides begin to return to the urine.] [In **scurvy** the

corpuscular elements are diminished in amount, but we have not precise information as to the salts, although this disease is prevented, in persons forced to live upon preserved and salted food, by a liberal use of the salts—especially potash salts—of the organic acids, as contained in lime-juice. In **gout** the blood, during an acute attack, and also in chronic gout, contains an excess of uric acid (*Garrod*).]

The **amount of fibrin** is increased in inflammations of the lung and pleura [croupous pneumonia, erysipelas], hence such blood forms a *crusta phlogistica* (§ 27). In other diseases, where decomposition of the blood corpuscles occurs, the fibrin is increased, perhaps because the dissolved red corpuscles yield material for the formation of fibrin. After repeated hemorrhages, Sigm. Mayer found an increase of fibrin. Blood rich in fibrin is said to coagulate *more slowly* than when less fibrin is present—still there are many exceptions.

(B) (I.) Diminution of the Quantity of Blood, or its Individual Constituents.—(1) **Oligæmia vera, Anæmia,** or diminution of the quantity of blood as a whole, occurs whenever there is hemorrhage. Life is endangered in newly-born children when they lose a few ounces of blood; in children a year old, on losing half a pound; and in adults, when one-half of the total blood is lost. Women bear loss of blood much better than men. The periodical formation of blood after each menstruation seems to enable blood to be renewed more rapidly in their case. Stout persons, old people, and children do not bear the loss of blood well. The more rapidly blood is lost, the more dangerous it is. [A moderate loss of blood is soon made up, but the fluid part is more quickly restored than are the corpuscles.]

Symptoms of Loss of Blood.—Great loss of blood is accompanied by general paleness and coldness of the cutaneous surface, increased oppression, twitching of the eyeballs, noises in the ears and vertigo, loss of voice, great breathlessness, stoppage of secretions, coma; dilatation of the pupils, involuntary evacuations of urine and fæces, and lastly, general convulsions, are sure signs of **death by hemorrhage.** In the gravest cases recovery is only possible by means of transfusion. Animals can bear the loss of one-fourth of their entire blood without the blood pressure in the arteries permanently falling, because the blood vessels contract and accommodate themselves to the smaller quantity of blood (in consequence of the stimulation of the vasomotor centre in the medulla). The loss of one-third of the total blood diminishes the blood pressure considerably (one-fourth in the carotid of the dog). If the hemorrhage is not such as to cause death, the fluid part of the blood and the dissolved salts are restored by absorption from the tissues, the blood pressure gradually rises, and then the albumin is restored, though a longer time is required for the formation of red corpuscles. At first, therefore, the blood is abnormally rich in water (**hydræmia**), and at last abnormally poor in corpuscles (**oligocythæmia, hypoglobulie**). With the increased lymph stream which pours into the blood, the colorless corpuscles are considerably increased above normal, and during the period of restitution fewer red corpuscles seem to be used up (*e.g.*, for bile).

After moderate bleeding from an artery in animals, Buntzen observed that the *volume* of the blood was restored in several hours; after more severe hemorrhage in 24 to 48 hours. The red blood corpuscles, after a loss of blood equal to 1.1 to 4.4 per cent. of the body weight, are restored only after 7 to 34 days. The regeneration *begins* after 24 hours. During the period of regeneration the number of the blood corpuscles in an early stage of development is increased. The newly-formed corpuscles contain less Hb than normal (*Jac. G. Ott*). Even in man the duration of the period of regeneration depends upon the amount of blood lost (*Lyon*). The amount of hæmoglobin is diminished nearly in proportion to the amount of the hemorrhage (*Bizzozero and Salvioli*).

Metabolism in Anæmia.—The *condition of the metabolism* within the bodies of anæmic persons is important. The decomposition of proteids is increased (the same is the case in hunger), hence the excretion of urea is increased (*Bauer*). The decomposition of fats, on the contrary, is diminished, which stands in relation with the diminution of CO_2 given off. Anæmic and chlorotic persons put on fat easily. The fattening of cattle is aided by occasional bleedings and by intercurrent periods of hunger (*Aristotle*).

(2) An excessive thickening of the blood through loss of water is called **Oligæmia sicca.** This occurs in man after copious watery evacuations, as in cholera, so that the thick tarry blood stagnates in the vessels. Perhaps a similar condition—though to a less degree—may exist after very copious perspiration.

(3) If the proteids in blood be abnormally diminished the condition is called **Oligæmia hypalbuminosa;** they may be diminished about one-half. They are usually replaced by an excess of water in the blood [so that the blood is watery, constituting **hydræmia**]. Loss of albumin from the blood is caused directly by albuminuria (25 grams of albumin may be given off by the urine daily), persistent suppuration, great loss of milk, extensive cutaneous ulceration, albuminous diarrhœa (dysentery). Frequent and copious hemorrhages, however, by increasing the absorption of water into the vessels, at first produce oligæmia hypalbuminosa.

For the **abnormal changes** of the red and white blood corpuscles, see § 10; for **Hæmophilia,** § 28.

[**Organisms in the Blood.**—The presence of animal and vegetable parasites in the blood gives rise to certain diseases. Some of these, and especially the vegetable organisms, have the power of multiplying in the blood. The vegetable forms belonging to the **schizomycetes** are frequently spoken of collectively under the title **bacteria.** They are classified by Cohn into

I. Sphærobacteria.
II. Microbacteria, exhibit movements.
III. Desmobacteria } exhibit movements.
IV. Spirobacteria }

These forms are shown in Fig. 23. The micrococci (A) are examples of I; while Bacterium termo (B) is an example of II. In III the members are short cylindrical rods, straight (Bacillus,

FIG. 23.

A, micrococcus; B, bacterium; C, vibrios; D, bacilli; E, spirillum.

FIG. 24.

Bacillus anthracis from the blood (ox) in splenic fever.

D) or wavy (Vibrio, C). Splenic fever of cattle is due to the presence of Bacillus anthracis (Fig. 24). These rod-shaped bodies under proper conditions divide transversely and elongate, but they also form spores in their interior, which in turn under appropriate conditions may germinate (Fig. 24). Class IV is represented by two genera, Spirochæta and Spirillum (Fig. 23), the former with close, and the later with open spirals. The Spirochæta Obermeieri (often spoken of as "Spirillum") is present in the blood during the paroxysms in persons suffering from relapsing fever. Among animal parasites are Filaria sanguinis, and Bilharzia Hæmatobia, which occurs in the portal vein and in the veins of the urinary apparatus.]

PHYSIOLOGY OF THE CIRCULATION.

42. GENERAL VIEW.—The blood within the vessels is in a state of continual motion, being carried *from* the ventricles by the large arteries (aorta and pulmonary) and their branches *to* the system of *capillary* vessels, *from* which again it passes into the *veins* that end in the atria of the auricles (*W. Harvey*, 1628).

FIG. 25.



Scheme of the circulation.—*a*, right, *b*, left auricle; A, right, B, left ventricle; 1, pulmonary artery; 2, aorta; *l*, area of pulmonary, K, area of systemic circulation; *o*, the superior vena cava; G, area supplying the inferior vena cava, *u*; *d*, *d*, intestine; *m*, mesenteric artery; *q*, portal vein; L, liver; *h*, hepatic vein.

The **cause of the circulation** is the *difference of pressure* which exists between the blood in the aorta and pulmonary artery on the one hand, and the two venæ cavæ and the four pulmonary veins on the other. The blood, of course, moves continually in its closed tubular system in the direction of least resistance. The greater the difference of pressure, the more rapid the movement will be. The cessation of the difference of pressure (as after death) naturally brings the movement to a standstill (§ 81). The circulation is usually divided into—

(1) **The greater, or systemic circulation,** which includes the course of the blood from the left auricle and left ventricle, through the aorta and all its branches, the capillaries of the body and the veins, until the two venæ cavæ terminate in the right auricle.

(2) **The lesser, or pulmonic circulation,** which includes the course from the right auricle and right ventricle, the pulmonary artery, the pulmonary capillaries, and the four pulmonary veins springing from them, until these open into the left auricle.

(3) **The portal circulation** is sometimes spoken of as a special circulatory system, although it represents only a second set of capillaries (within the liver) introduced into the course of a venous trunk. It consists of the vena portarum—formed by the union of the intestinal or mesenteric and splenic veins, and it passes into the liver, where it divides into capillaries, from which the hepatic veins arise. The hepatic vein joins the inferior vena cava.

Strictly speaking, however, there is no special portal circulation. Similar arrangements occur in other animals in different organs, *e. g.*, snakes have such a system in their supra-renal capsules, and the frog in its kidneys. When an *artery* splits up into fine branches during its course, and these branches do not form capillaries, but reunite into an arterial trunk, a **rete mirabile** is formed, such as occurs in apes and the edentata. Microscopic retia mirabilia exist in the human mesentery (*Schöbl*). Similar arrangements may exist in connection with veins, giving rise to *venous retia mirabilia*.

43. **THE HEART.—The muscular fibres** of the mammalian heart consist of short (50 to 70 μ in man), very fine, transversely striated fibres, which are actual unicellular elements, devoid of a sarcolemma (15 to 25 μ broad), and usually divided at their blunt ends, by which means they anastomose and form a network (Fig. 26, A, B). The individual muscle cells contain in their centre an oval nucleus, and are held together by a cement which is blackened by silver nitrate, and dissolved by a 33 per cent. solution of caustic potash. This cement is also dissolved by a 40 per cent. solution of nitric acid. The transverse striæ are not very distinct, and not unfrequently there is an appearance of longitudinal striation, produced by a number of very small granules arranged in rows within the fibres. The fibres are gathered lengthwise in bundles, or fasciculi, surrounded and separated from each other by delicate processes of the **perimysium.** When the connective tissue is dissolved by prolonged boiling, these bundles can be isolated, and constitute the so-called "fibres" of the heart. The transverse sections of the bundles in the auricles are polygonal or rounded, while in the ventricles they are somewhat flattened. [The muscular mass of the heart is called the **myocardium,** and is invested by fibrous tissue. It is important to notice that the connective tissue of the visceral pericardium (**epicardium**) is continuous with that of the endocardium by means of the perimysium surrounding the bundles of muscular fibres.] The fine spaces which exist between these bundles form narrow lacunæ, lined with epithelium, and constituting part of the lymphatic system of the heart.

[The cardiac muscular fibres occupy an intermediate position between striped and plain muscular fibres. Although they are striped, they are involuntary, not being directly under the influence of the will, while they contract more slowly than a voluntary muscle of the skeleton.] In the **frog's** heart

FIG. 26.

A, muscular fibres from the heart of a mammal, and C from a frog; B, transverse section of the cardiac fibres; *b*, connective-tissue corpuscles; *c*, capillaries.

the muscular fibres are in shape elongated spindles, or fusiform, in this respect resembling the plain muscle cells, but they are transversely striped (Fig. 26, C). They are easily isolated by means of a 33 per cent. solution of potash or dilute alcohol.

44. **ARRANGEMENT OF THE CARDIAC MUSCULAR FIBRES.**—The study of the embryonic heart is the key to a proper understanding of the complicated arrangement of the fibres in the adult heart. The simple tubular heart of the embryo has an *outer circular* and an *inner longitudinal* layer of fibres. The septum is formed later; hence, it is clear that a part, at least, of the fibres must be common to the two auricles, and a part also to the two ventricles, since there is, originally, but one chamber in the heart. The muscular fibres of the auricles are, however, *completely separated* from those of the ventricles by the fibro-cartilaginous rings. In the auricles the fundamental arrangement of the embryonic fibres partly remains, while in the ventricles it becomes obscured as the cavities undergo a sac-like dilatation, and also become twisted in a spiral manner.

(1) **The muscular fibres in the auricles** are completely separated from the fibres of the ventricles by the *fibrous* rings which surround the auriculo-ventricular orifices, and which serve as an attachment for the auriculo-ventricular valves (Fig. 27, I). The auricles are much thinner than the ventricles, and their fibres are generally arranged in two layers; the outer *transverse* layer is continuous over

both auricles, while the inner one is directed *longitudinally*. The outer transverse fibres may be traced from the openings of the venous trunks anteriorly and posteriorly over the auricular walls. The longitudinal fibres are specially well marked where they are inserted into the fibro-cartilaginous rings, while in some parts of the anterior auricular wall they are not continuous. In the *auricular septum*, some fibres, circularly disposed around the *fossa ovalis* (formerly the embryonic opening of the foramen ovale), are well marked. *Circular bands* of striped muscle exist around the *veins* where they open into the heart; these are least marked on the inferior vena cava, and are stronger and reach higher (2.5 cm.) on the superior vena cava (Fig. 27, II). Similar fibres exist around the pulmonary veins, where they join the left auricle, and these fibres (which are arranged as an inner circular and an outer longitudinal layer) can be traced to the hilus of the lung in man and some mammals; in the ape and rat they extend on the pulmonary veins right into the lung. In the mouse and bat, again, the striped muscular fibres pass so far into the lungs that the walls of the smaller veins are largely composed of striped muscle (*Stieda*).

FIG. 27.



I. Course of the muscular fibres on the left auricle with the outer transverse and inner longitudinal fibres, the circular fibres on the pulmonary veins (*v. p.*); V, the left ventricle (*John Reid*). II. Arrangement of the striped muscular fibres on the superior vena cava (*Elischer*)—*a*, opening of vena azygos; *v*, auricle.

Circular muscular fibres are found where the vena magna cordis enters the heart, and in the *Valvula Thebesii* which guards it.

Physiological Significance. — (1) The auricles contract *independently* of the ventricles. This is seen when the heart is about to die; when there may be several auricular contractions for one ventricular, and at last only the auricles pulsate. The auricular portion of the right auricle beats longest; hence it is called the "ultimum moriens." Independent rhythmical contractions of the venæ cavæ and pulmonary veins are often noticed after the heart has ceased to beat. [This beating can also be observed in those veins in a rabbit after the heart is cut out of the body.]

(2) The double arrangement of the fibres (transverse and longitudinal) produces a simultaneous and uniform diminution of the auricular cavity (such as occurs in most of the hollow viscera).

(3) The contraction of the circular muscular fibres around the venous orifices, and the subsequent contraction of the auricle, cause these veins to empty themselves into the auricle; and by their presence and action they prevent any large quantity of blood from passing backward into the veins when the auricle contracts. [No valves are present in the superior and inferior vena cava in the adult heart, or in the pulmonary veins; hence the contraction of these circular muscular fibres plays an important part in preventing any reflux of blood during the contraction of the auricles.]

45. ARRANGEMENT OF THE VENTRICULAR FIBRES.—(2) **The muscular fibres** in the thick wall of the **ventricles** are arranged in several layers (Fig. 28, A) under the pericardium. First, there is an *outer longitudinal* layer (A) which is in the form of single bundles on the right ventricle, but forms a complete layer on the left ventricle, where it measures about one-eighth of the thickness of the ventricular wall. A *second longitudinal* layer of fibres lies on the *inner surface* of the ventricles, distinctly visible at the orifices, and within the vertically placed papillary muscles, while elsewhere it is replaced by the irregularly arranged trabeculæ carneæ. Between these two layers there lies the thickest layer, consisting of *more or less transversely* arranged bundles, which may be broken up into single layers more or less circularly disposed. The deep *lymphatic vessels* run between the layers, while the *blood vessels* lie within the substance of the layers, and are surrounded by the primitive bundles of muscular fibres. All three layers are not completely independent of each other; on

FIG. 28.



Course of the ventricular muscular fibres. A, on the anterior surface; B, view of the apex with the vortex; C, course of the fibres within the ventricular wall; D, fibres passing into a papillary muscle.

the contrary, the fibres which run *obliquely* form a gradual *transition* between the transverse layers and the inner and outer longitudinal layers. It is not, however, quite correct to assume that the outer longitudinal layer gradually passes into the transverse, and this again into the inner longitudinal layer (as is shown schematically in C); because, as Henle pointed out, the transverse fibres are relatively far greater in amount. In general, the *outer* longitudinal fibres are so arranged as to cross the *inner* longitudinal layer at an acute angle. The transverse layers lying between these two form gradual transitions between these directions. At the apex of the left ventricle, the outer longitudinal fibres bend or curve so as to meet at the so-called vortex B, where they enter the muscular substance, and, taking an upward and inward direction, reach the papillary muscles, P, D; although it is a mistake to say that all the bundles which ascend to the papillary muscles arise from the vertical fibres of the outer surface: many seem to arise independently within the ventricular wall. According to Henle, all the external longitudinal

fibres do not arise from the fibrous rings or the roots of the arteries. The mitral orifice is surrounded by circular fibres which act like a sphincter (*Henle*).

[The assumption that the muscles of the ventricle are arranged so as to form a figure of 8, or in loops, seems to be incorrect; thus, fibres are said to arise at the base of the ventricle, to pass over it, and to reach the vortex, where they pass into the interior of the muscular substance, to end either in the papillary muscles or high up on the inner surface of the heart at its base. Figs. C and D give a schematic representation of this view.]

Only the general arrangement of the ventricular muscular fibres has been indicated. According to Pettigrew, there are seven layers in the ventricle, viz., three external, a fourth or central layer, and three internal. These internal layers are continuous with the corresponding external layers at the apex, thus—one and seven, two and six.

46. PERICARDIUM, ENDOCARDIUM, VALVES.—The **pericardium** encloses within its two layers [visceral and parietal] a lymph space—the pericardial space—which contains a small quantity of lymph—the **pericardial fluid**. It has the structure of a serous membrane, *i. e.*, it consists of *connective tissue* mixed with *fine elastic fibres* arranged in the form of a thin delicate membrane, and covered on its free surfaces with a single layer of epithelium or *endothelium*, composed of irregular, polygonal, flat cells. A rich *lymphatic network* lies under the pericardium (Fig. 29) and endocardium; also in the deeper layers of the visceral pericardium next the heart and between muscular bundles (*Salvioli*). No stomata exist either on its visceral or parietal layers. Around the coronary arteries of the heart exist lymph vessels and deposits of fat, which lie in the furrows and grooves in the *tuberosa* of the *epicardium* (visceral layer).

FIG. 29.



Lymphatic of the pericardium, epithelium stained with nitrate of silver.

The **endocardium**, next the cavity of the heart, consists of a *single* layer of polygonal, flat, nucleated *endothelial* cells. [Under this there is a nearly homogeneous hyaline layer (Fig. 30, *a*), slightly thicker on the left side, which gives the endocardium its polished appearance.] Then follows, as the *basis of the membrane*, a layer of *fine elastic fibres*—stronger in the auricles, and in some places thereof assuming the characters of a fenestrated membrane. Between these fibres a small quantity of connective tissue exists, which is in larger amount and more areolar in its characters next the myocardium. Bundles of *non-striped muscular* fibres (few in the auricles) are scattered and arranged for the most part longitudinally between the elastic fibres. These seem evidently meant to resist the distention which is apt to occur when the heart contracts and great pressure is put upon the endocardium. In all cases where high pressure is put upon walls composed of soft parts, we always find muscular fibres present, and never elastic fibres alone. No *blood vessels* occur in the endocardium (*Langer*).

FIG. 30.



Section of the endocardium. *a*, hyaline layer; *b*, network of fine elastic fibres; *c*, network of stronger elastic fibres; *d*, myocardium with blood vessels, which do not pass into the endocardium.

The **valves** also belong to the endocardium—both the *semilunar valves* of the aorta and pulmonary artery, which prevent the blood from passing back into the ventricles, and the tricuspid (*right* auriculo-ventricular) and mitral (*left* auriculo-ventricular), which protect the auricles from the same result. The lower vertebrata have valves in the orifices of the venæ cavæ, which prevent regurgitation into them; while in birds and some mammals these valves exist in a rudimentary condition. The valves are fixed by their base to resistant *fibrous*

rings, consisting of elastic and fibrous tissue. They are formed of two layers—(1) the *fibrous*, which is a direct continuation of the fibrous rings, and (2) a layer of *elastic* elements. The elastic layer of the auriculo-ventricular valves is an immediate prolongation of the endocardium of the auricles, and is directed toward the auricles. The semilunar valves have a thin elastic layer directed toward the arteries, which is thickest at their base. The connective-tissue layer directed toward the ventricle is about half the thickness of the valve itself.

The auriculo-ventricular valves also contain **striped muscular fibres.** Radiating fibres proceed from the auricles and pass into the valves, which, when the atria contract, retract the valves toward their base, and thus make a larger opening for the passage of the blood into the ventricles; according to Paladino, they raise the valves after they have been pressed down by the blood current. This observer also described some longitudinal fibres which proceed from the ventricles to enter these valves. There is also a concentric layer of fibres arranged near their point of attachment, and directed more toward their ventricular surface. These fibres seem to contract sphincter-like when the ventricle contracts, and thus approximate the base of the valves, and so prevent too great tension being put upon them. The larger chordæ tendineæ also contain striped muscle, while a delicate muscular network exists in the valvula Thebesii and valvula Eustachii.

Purkinje's Fibres consist of an anastomosing system of grayish fibres which exist in the subendocardial tissue of the ventricles, especially in the heart of the sheep and ox. The fibres are made up of polyhedral clear cells, containing some granular protoplasm, and usually two nuclei (Fig. 31). The margins of the cells are striated. Transition forms are found between these cells and the ordinary cardiac fibres; in fact, these cells become continuous with the true fully developed cardiac fibres. They represent cells which have been arrested in their development. They are absent in man and the lower vertebrates, but in birds and some mammals they are well marked (*Schweigger-Seidel, Ranvier*).

FIG. 31.



Purkinje's fibres isolated with dilute alcohol. *c*, cell; *f*, striated substance; *n*, nucleus. × 300.

Blood Vessels occur in the auriculo-ventricular valves only where muscular fibres are present, while the semilunar valves are usually devoid of vessels except at their base. The best figures of the blood vessels of the valves are given by Langer. The network of **lymphatics** in the endocardium reaches toward the middle of the valves.

Weight of the Heart.—According to W. Müller the proportion between the weight of the body and the heart in the child, and until the body reaches 40 kilos., is 5 grms. of heart substance to 1 kilo. of body weight; when the body weight is from 50 to 90 kilos. the ratio is 1 kilo. to 4 grms. of heart substance; at 100 kilos. 3.5 grms. As age advances, the auricles become stronger. The right ventricle is half the weight of the left. The weight of the heart of an adult man is about 309 grms.; female, 274 grms. [According to Laennec the heart is about the size of the closed fist of the individual.] Blosfeld and Dieberg give 346 grms. for the male, and 310 to 340 grms. for the female heart. The *specific gravity* of the heart muscle is 1.069. The thickness of the left ventricle in the middle in man is 11.4 mm., and in woman 11.15; that of the right is 4.1 and 3.6 mm. respectively.

47. AUTOMATIC REGULATION OF THE HEART.—Anatomical Investigations.—The two coronary arteries arise from the first part of the aorta *in the region* of the sinus of Valsalva. The position of origin varies—(1) either the orifices lie within the sinus, or (2) their openings are only partially reached by the margins of the semilunar valves (which is *usually* the case in the *left* coronary artery of man and the ox), or (3) their orifices lie clear above the margins of the valves. Post-mortem observations seem to show that during contraction of the ventricle it is very improbable that the semilunar valves constantly cover the origin of the coronary arteries.

Automatic Regulation of the Heart.—Brücke attempted to show that during the systole, or contraction of the ventricle, the semilunar valves covered the openings of the coronary arteries, so that these vessels could be filled with blood only during the diastole or relaxation of the ventricle. To him it seemed that (*a*) the diastolic filling of the coronary arteries would help to dilate the ventricles; (*b*) on the contrary, a systolic filling of these arteries would oppose the contraction, because the systolic filling and expulsion of the blood from the coronary arteries would diminish the force of the ventricular contraction. [To this supposed arrangement Brücke gave the name "Selbststeuerung," which may be rendered as above, or as "self-controlling" action of the heart by the aortic valves.]

Arguments against Brücke's View.—The following considerations militate against this theory: (1) Filling the coronary vessels under a high pressure in a dead heart causes a *diminution* of the ventricular cavity (*v. Wittich*). (2) The chief trunks of the coronary arteries lie in loose sub-pericardial fatty tissue in the cardiac sulci, hence a dilatation of the ventricle through this agency is most unlikely (*Landois*). (3) Experiments on animals have shown that a coronary artery spouts, like all arteries, during the systole of the ventricle. Von Ziemssen found that in the case of a woman who had a large part of the anterior wall of the thorax removed by an operation, the heart being covered only by a thin membrane, the pulse in the coronary arteries was synchronous with the pulse in the pulmonary artery. H. N. Martin and Sedgwick placed a manometer in connection with the coronary artery, and another with the carotid in a large dog, and they found that the pulsations occurred *simultaneously*. When a coronary artery is divided, the blood flows out continuously, but undergoes acceleration during the systole of the ventricles (*Endemann, Perls*). (4) If a strong intermittent current of water be allowed to flow through a sufficiently wide tube into the left auricle of a fresh pig's heart, so that the water passes into the aorta, and if the aorta be provided with a vertical tube, the water flows continuously from the coronary arteries, and is accelerated during the systole. (5) It is exceedingly improbable that the coronary arteries should be filled during the diastole, while all the other arteries are filled during systole of the ventricle. (6) There is always a sufficient quantity of blood in the sinus of Valsalva to fill the arteries during the first part of the systole. (7) The valves, when raised, are not applied directly to the aortic wall (*Hamberger, Rüdinger*) even by the most energetic pressure from the ventricle (*Sandborg and Worm Müller*). (8) Observations on voluntary muscles have shown that the small arteries dilate during contraction of the muscle, and the blood stream is accelerated. (9) By the systolic filling of the aorta the arterial path is elongated—this elastic distention is compensated before the diastole occurs. By the recoil of the aortic walls the layer of blood in them is driven backward and closes the valves (*Ceradini*). According to Sandborg and Worm Müller, the semilunar valves close just after the ventricles have begun to relax, which agrees with the curve obtained from the cardiac impulse (Fig. 39, A).

During the systole, the small arterial trunks lying next the ventricular cavities have to bear a higher pressure than that borne by the aorta, and their lumen must be compressed during the systole so that their contents are propelled toward the veins.

Peculiarities of the Cardiac Blood Vessels.—The *capillary vessels* of the myocardium are very numerous, corresponding to the energetic activity of the heart. Where they pass into veins, several unite at once to form a wide venous trunk, whereby an easy passage is offered to the blood. The *veins* are provided with valves so that (1) during systole of the right auricle the venous stream is interrupted; (2) during contraction of the ventricles, the blood in the coronary veins is similarly accelerated as in the veins of muscles. The coronary arteries are characterized by their very thick connective tissue and elastic intima, which perhaps accounts for the frequent occurrence of atheroma of these vessels (*Henle*). Some observers maintain that the coronary arteries do not anastomose, but this is denied by Langer and Krause. [West has injected the one artery from the other.] Many of the small lower vertebrates have no blood vessels in their heart muscle, *e. g.*, frog (*Hyrtl*).

Ligature of the Coronary Arteries.—The phenomena produced by partial obliteration or ligature of the coronary arteries are most important. In man analogous conditions occur, as in atheroma or calcification of these arteries. Sée and others have ligatured the coronary arteries in dogs, and found that after two minutes the cardiac contractions gave place to twitchings of the muscular fibres, and ultimately the heart ceased to beat. Ligature of the anterior coronary artery alone, or of both its branches, is sufficient to produce this result. If the coro-

nary arteries be compressed or tied in a rabbit in the angle between the bulbus aortæ and the ventricle, the heart's action is soon weakened, owing to the sudden anæmia and to the retention of the decomposition products of the metabolism in the heart muscle. Ligature of one artery first affects the corresponding ventricle, then the other ventricle, and, last of all, the auricles. Hence, compression of the *left* coronary artery (with simultaneous artificial respiration in a curarized animal) causes slowing of the contractions, especially of the left ventricle, while the right one at first contracts more quickly, and then, gradually, its rhythm is slowed. The contractions of the left ventricle are not only slowed but also weakened, while the right pulsates with undiminished force. Hence it follows that, as the left half of the heart cannot expel the blood in sufficient quantity, the left auricle becomes filled, while the right ventricle, not being affected, pumps blood into the lungs. Œdema of the lungs is produced by the high pressure in the pulmonary circulation, which is propagated from the right heart through the pulmonary vessels into the left auricle (*Samuelson and Grünhagen*). According to Sig. Mayer, protracted dyspnœa causes the left ventricle to beat more feebly sooner than the right, so that the left side of the heart becomes congested. Perhaps this may explain the occurrence of pulmonary œdema during the death agony.

Cohnheim and v. Schulthess-Rechberg found, after ligature of one of the large branches of a coronary artery in a dog, that at the end of a minute the pulsations become intermittent. This intermittence becomes more pronounced, the two sides of the heart do not contract simultaneously (**arhythmia**), the heart beats more slowly, and the blood pressure falls. Suddenly, about 105 seconds after the ligature is applied, both ventricles cease to beat, and there is a great fall of the blood pressure. After an arrest lasting for 10 to 20 seconds, twitching movements occur in the ventricles, while the auricles pulsate regularly, and may continue to do so for many minutes, but the ventricles cease to beat altogether after 50 seconds. According to Lukjanow, there is a peristaltic condition which operates upward and downward, and occurs in the period between the regular contraction and the twitching vibratory movement. Stimulation of the vagus does not arrest these peristaltic movements.

Pathological.—In so-called sclerosis of the coronary arteries in old age, there are attacks of diminished cardiac activity, weakness of the heart, an altered rhythm and frequency, with consequent breathlessness; there may also be loss of consciousness, congestions, and attacks of pulmonary œdema. Death may take place unexpectedly from sudden arrest of the heart's action.

48. MOVEMENTS OF THE HEART.—Cardiac Revolution.—The movement of the heart is characterized by an alternate contraction and relaxation of its walls. The total cardiac movement is called a "**cardiac revolution**" or a "**cardiac cycle,**" and consists of three acts—the contraction or *systole of the auricles*, the contraction or *systole of the ventricles*, and the *pause* (Fig. 50). During the pause, the auricles and ventricles are relaxed; during the contraction of the auricles the ventricles are at rest; while during the contraction of the ventricles the auricles are relaxed. The rest during the phase of relaxation is called the *diastole*. The following is the sequence of events in the heart during a cardiac revolution:—

(**A**) **The blood flows into the auricles,** and thus distends them and the auricular appendices. This is caused by—

(1) The *pressure* of the blood in the venæ cavæ (right side) and the pulmonary veins (left side) being greater than the pressure in the auricles. (2) The *elastic traction of the lungs* (§ 68), which, after complete systole of the auricles, pulls asunder the now relaxed and yielding auricular walls. The auricular appendages are also filled at the same time, and they act to a certain extent as accessory reservoirs for the large supply of blood streaming into the auricles.

(**B**) **The auricles contract,** and we observe in rapid succession—

(1) The contraction and emptying of the auricular appendix toward the atrium. Simultaneously the mouths of the veins become narrowed, owing to the contraction of their circular muscular fibres (more especially the superior vena cava and the pulmonary veins); (2) the auricular walls contract simultaneously toward the

auriculo-ventricular valves and the venous orifices, whereby (3) the blood is driven into the relaxed ventricles, which are considerably distended thereby.

The contraction of the auricles is followed by

(*a*) A slight stagnation of the blood in the large venous trunks, as can be observed in a rabbit after division of the pectoral muscles so as to expose the junction of the jugular with the subclavian vein. There is no actual regurgitation of the blood, but only a partial interruption of the inflow into the auricles, because the mouths of the veins are contracted, and the pressure in the superior vena cava and pulmonary veins soon holds in equilibrium any reflux of blood; and lastly,

FIG. 32.



Cast of the ventricles of the human heart viewed from *behind* and above; the walls have been removed, and only the fibrous rings and the auriculo-ventricular valves are retained. L, left, R, right ventricle; S, septum; F, left fibrous ring, with mitral valve closed; D, right fibrous ring, with tricuspid closed; A, aorta, with the left (C_1) and right (C) coronary arteries; S, sinus of Valsalva; P, pulmonary artery.

because any reflux into the cardiac veins is prevented by valves. The movement of the heart causes a regular pulsatile phenomenon in the blood of the venæ cavæ, which under abnormal circumstances may produce a venous pulse (see § 99).

(*b*) The chief motor effect of the contraction of the auricles is the *dilatation of the relaxed ventricle*, which has already been dilated to a slight extent by the *elastic traction* of the lungs.

Aspiration of the Ventricles.—The dilatation of the ventricles has been ascribed to the elasticity of the muscular walls—the strongly contracted ventricular walls (like a compressed india-rubber bag), in virtue of their elasticity, are supposed, in returning to their normal resting form, to

suck in or aspirate the blood under a negative pressure; this power on the part of the ventricle is not great (see below).

(*c*) When the ventricles are distended by the inflowing blood, the auriculo-ventricular valves are floated up, partly by the recoil or reflexion of the blood from the ventricular wall, and partly owing to their lighter specific gravity, whereby they easily float into a more or less horizontal position. The valves are also raised to a slight extent by the longitudinal muscular fibres, which pass from the auricles into the cusps of the valve.

(**C**) **The ventricles now contract,** and simultaneously the auricles relax, whereby—

(1) The muscular walls contract forcibly from all sides, and thus diminish the ventricular cavity. (2) The blood is at once pressed against the under surface of the auriculo-ventricular valves, whose curved margins are opposed to each other like teeth, and are pressed hermetically against each other (Fig. 32). It is impossible for the blood to push the cusps backward into the auricle, as the **chordæ tendineæ** hold fast their margins and surfaces like a taut sail. The margins of the neighboring cusps are also kept in apposition, as the chordæ tendineæ from one papillary muscle always pass to the adjoining edges of two cusps. The extent to which the ventricular wall is shortened is compensated by the contraction of the papillary muscle, and also of the large muscular chordæ, so that the cusps cannot be pushed into the auricle. When the valves are closed, their surfaces are horizontal, so that, even when the ventricles are contracted to their greatest extent, there remains in the *supra-papillary space* a small amount of blood which is not expelled (*Sandborg and Worm Müller*). (3) When the pressure within the ventricles exceeds that in the arteries, the semilunar valves are forced open and stretched like a sail across the pocket-like sinus, without, however, being directly applied to the wall of the arteries (pulmonary and aorta), and thus the blood enters the arteries.

(**D**) **Pause.**—As soon as the ventricular contraction ends, and the ventricles begin to relax, the *semilunar valves close* (Fig. 33). The diastole of the ventricles is followed by the **pause.** Under normal circumstances, the right and left halves of the heart always contract or relax uniformly and simultaneously.

FIG. 33.

The closed semilunar valve of the pulmonary artery seen from below.

Negative Pressure in the Ventricle.—Goltz and Gaule found that there was a *negative pressure* of 23.5 mm. Hg (dog) in the interior of the ventricle during a certain phase of the heart's action. This they determined by a maximal and minimal manometer. They surmised that this phase coincided with the *diastolic dilatation*, for which they assumed a considerable power of aspiration. Moens is of opinion that this negative pressure within the ventricle obtains *shortly before the systole has reached its height, i. e.*, just before the inner surface of the ventricles and the valves, after the blood is expelled, are nearly in apposition. He explains this aspiration as being due to the formation of an empty space in the ventricle caused by the energetic expulsion of the blood through the aorta and pulmonary artery.

FIG. 34.

FIG. 35.

Gaule's maximum and minimum manometer.

[**Maximum and Minimum Manometer.**—Into the tube connecting the interior of the ventricle of the heart with the ordinary **U**-shaped mercury manometer, is introduced the maximum manome-

ter, which is constructed on the principle of a ball and cup valve (Fig. 34), the ball A being kept closed in B by a spring C. To make it a maximum manometer, the end A is connected with the heart, and B with the mercurial manometer (Fig. 35). When a clamp is placed on the upper limb the valve is acted on only at each systole of the heart, blood is driven beyond it, but during diastole it closes and no blood can return. This goes on until the pressure beyond the valve in the mercury manometer is the same as in the heart. If the valve be reversed, it is converted into a minimum manometer.]

49. **PATHOLOGICAL CARDIAC ACTION.—Cardiac Hypertrophy.**—All resistances to the movement of the blood through the various chambers of the heart, and through the vessels communicating with it, cause a greater amount of work to be thrown upon the portion of the heart specially related to this part of the circulatory system; consequently, there is produced an increase in the thickness of the muscular walls and dilatation of the heart. If the resistance or obstacle does not act upon *one* part of the heart alone, but on parts lying in the *onward* direction of the blood stream, these parts also subsequently undergo hypertrophy. If, in addition to the muscular thickening of a part of the heart, the cavity is simultaneously dilated, it is spoken of as **eccentric hypertrophy** or **hypertrophy with dilatation.** The obstacles most likely to occur in the *blood vessels* are narrowing of the lumen or want of elasticity in their walls; in the *heart*, narrowing of the arterial or venous orifices or insufficiency or incompetency of the valves. Incompetency of the valves forms an obstruction to the movement of the blood, by allowing part of the blood to flow back or regurgitate, thus throwing extra work upon the heart.

Thus arise—(1) **Hypertrophy of the left ventricle,** owing to resistance in the area of the systemic circulation, especially in the arteries and capillaries—not in the veins. Among the causes are—constriction of the orifice or other parts of the aorta, calcification, atheroma, and want of elasticity of the large arteries and irregular dilatations or aneurisms in their course; insufficiency of the aortic valves, in which case the same pressure always obtains within the ventricle and in the aorta; and, lastly, cirrhosis of the kidneys, whereby the excretion of water by these organs is diminished. Even in mitral insufficiency, compensatory hypertrophy of the left ventricle must occur, owing to the hypertrophy of the left atrium in consequence of the increased blood pressure in the pulmonary circuit.

(2) **Hypertrophy of the left auricle** occurs in stenosis or constriction of the left auriculo-ventricular orifice, or in insufficiency of the mitral valve, and it occurs also as a result of aortic insufficiency, because the auricle has to overcome the continual aortic pressure within the ventricle.

(3) **Hypertrophy of the right ventricle** occurs (*a*) when there is resistance to the blood stream through the pulmonary circuit. The resistance may be due to (*α*) obliteration of large vascular areas in consequence of destruction, shrinking or compression of the lungs, and the disappearance of numerous capillaries in emphysematous lungs; (*β*) overfilling of the pulmonary circuit with blood in consequence of stenosis of the left auriculo-ventricular orifice, or mitral insufficiency—consequent upon hypertrophy of the left auricle resulting from aortic insufficiency. (*b*) When the valves of the pulmonary artery are insufficient, thus permitting the blood to flow back into the ventricle, so that the pressure within the pulmonary artery prevails within the right ventricle (very rare).

(4) **Hypertrophy of the right auricle** occurs in consequence of the last-named condition, and also from stenosis of the tricuspid orifice, or insufficiency of the tricuspid valve (rare).

Artificial Injury to the Valves.—If the aortic valves are perforated, with or without simultaneous injury to the mitral or tricuspid valves, the heart does more work; thus the physical defect is overcome for a time, so that the blood pressure does not fall. The heart seems to have a store of reserve energy which is called into play. Soon, however, dilatation takes place, on account of the regurgitation of the blood into the heart. Hypertrophy then occurs, but the compensation meanwhile must be obtained through the reserve energy of the heart (*O. Rosenbach*).

Impeded Diastole.—Among causes which hinder the diastole of the heart are—copious effusion into the pericardium, or the pressure of tumors upon the heart. The systole is greatly interfered with when the heart is united to the pericardium and to the connective tissue in the mediastinum. As a consequence the connective tissue, and even the thoracic wall, are drawn in during contraction of the heart, so that there is a retraction of the region of the apex beat during systole, and a protrusion of this part during the diastole.

[**Palpitation** is a symptom indicating generally very rapid and quick action of the heart, the pulsations often being unequal in time and intensity, while the person is generally conscious of the irregularity of the cardiac action. It may be due to some *organic* condition of the heart itself, especially where the cardiac muscles are weak, in cases of dilatation and hypertrophy of the left ventricle, where the heart is gradually becoming unable to overcome the resistances offered to its work, and especially during exertion when the heart is taxed above its strength. It may also occur where the blood pressure is low, as in anæmia, so that the heart contracts quickly, there being little resistance opposed to its action. The excitability of the cardiac muscle may be increased, as in fatty heart,

when very slight exertion may excite it often in a paroxysmal way. In other cases, it is *nervous* in its origin, being either diect or reflex. In very emotional and excitable people (especially in women) it is easily set up, and in some people it may be produced reflexly by gastric or intestinal irritation or dyspepsia. It also frequently results from excesses of all kinds and the over-use of tobacco. The **remedies** to be used obviously depend on the cause. Where the blood pressure is low, as in anæmia, digitalis and iron will do good; the former by increasing the blood pressure, and the latter by improving the general nutrition of the body and the blood in particular. In neurotic cases cardiac sedatives are indicated, while in cases due to indigestion hydrocyanic acid is useful (*Brunton*).]

[**Fainting or Syncope.**—In fainting, the person loses consciousness, owing to a sudden arrest of the blood supply to the brain, the face is pallid, the respiration is feeble or ceases, while the heart beats but feebly or not at all. The defective supply of blood to the brain may depend upon sudden arrest of the heart's action, caused, it may be, by a fright, or the heart's action may be arrested reflexly. Any cause which suddenly diminishes the blood pressure may produce it, or when pressure is suddenly removed from the large vessels, as in tapping the abdomen in ascites, without at the same time giving sufficient support to the abdominal viscera. When a person has been long in the recumbent position, on being rapidly set up in bed he may faint. In some forms of heart disease, sudden exertion or change of posture may produce it.]

[**Treatment.**—The object is to restore consciousness and the action of the heart. Place the person in the horizontal position, keep the head low, even lower than the body, and do not support it with pillows. Dashing cold water on the face, so as to stimulate the fifth nerve, usually succeeds in causing the person to take a deep inspiration. In other cases a sniff of smelling salts or ammonia, acting through the nasal branch of the fifth nerve, will excite the cardiac and respiratory functions (§ 368).]

50. **THE APEX BEAT, CARDIOGRAM.—Cardiac Impulse.**—By the term "**apex beat**" or "**cardiac impulse**" is understood, under normal circumstances, an elevation (perceptible to touch and sight) in a circumscribed area of the *fifth left* intercostal space, and caused by the movement of the heart. [The apex beat is felt in the fifth left intercostal space, 2 inches below the nipple, and 1 inch to its sternal side, or at a point 2 inches to the left of the sternum.] The impulse is more rarely felt in the fourth intercostal space, and it is much less distinct when the heart beats against the fifth rib itself. The position and force of the cardiac impulse vary with changes in the position of the body.

[The cardiac impulse is synchronous with the systole of the heart, but although this name and apex beat are frequently used as synonymous terms, it is to be remembered that the impulse may be caused by different parts of the heart being in contact with the chest wall. The cardiac impulse is usually higher than normal in children, while it is lower during inspiration than expiration.]

[**Methods.**—To obtain a curve of the apex beat or a **cardiogram**, we may use one or other of the following cardiographs (Fig. 36). Fig. 36, A, is the first form used by Marey, and it consists of an oval wooden capsule applied in an air-tight manner over the apex beat. The disk, *p*, capable of being regulated by the screw, *s*, presses upon the region of the apex beat, while *t* is a tube which may be connected with a recording tambour (Fig. 47). B is an improved form of the instrument, consisting essentially of a tambour, while attached to the membrane is a button, *p*, to be applied over the apex beat. The movements of the air within the capsule are communicated by the tube, *t*, to a recording tambour. Fig. 36, C, is the **pansphygmograph** of Brondgeest, which consists of a Marey's tambour, in an iron horse-shoe frame, and adjustable by means of a screw, *s*. Burdon-Sanderson's cardiograph is shown in D. The button, *p*, carried by the spring, *e*, does not rest upon the caoutchouc membrane, but on an aluminium plate attached to it. The apparatus is adjusted to the chest by three supports. Fig. 36, E, shows a modified instrument on the same principle, by Grummach and v. Knoll. In all these figures the *t* indicates the exit tube communicating with a recording tambour (Fig. 47). D and E may be used for other purposes, *e. g.*, for the pulse, so that they are **polygraphs**. See also Fig. 76.]

Fig. 39, A, shows the **cardiogram** or the impulse curve of the heart of a healthy man; B, that of a dog, obtained by means of a sphygmograph. In both the following points are to be noticed: *ab*, corresponds to the time of the pause and *the contraction of the auricles*. As the atria contract in the direction of the axis of the heart from the right and above toward the left and below, the apex of the heart moves toward the intercostal space. The two or three smaller elevations are perhaps caused by the contractions of the ends of the veins, the auricular appendices, and the atria themselves.

The portion *bc*, which communicates the greatest impulse to the instrument, and also to one's hand when it is placed on the apex beat, is caused by *the contraction of the ventricles*, and during it the first sound of the heart occurs. Fre-

FIG. 36.



Cardiographs. A, Marey's original form; B, Marey's improved form; C, pansphygmograph (Brondgeest); D, cardiograph (Burdon-Sanderson); E, that of v. Knoll.

quently, but erroneously, the cardiac impulse has been ascribed to the contraction of the ventricles alone. It, however, is due to all those conditions which cause an elevation in the region of the cardiac impulse.

[Edgren recorded a human cardiogram, and listened at the same time to the heart sounds, recording the latter by means of an electric signal. The curve rises at *a*, with the beginning of

FIG. 37.

Cardiogram. *a-f*: 1, beginning of 1st, and 2, 2d sound.

the first sound, *i. e.*, with the contraction of the ventricles, and reaches the abscissa at *f* with the beginning of the second sound, *i.e.*, when the semilunar valves are closed. The relation between *a* and the points intermediate between it and *f*, and to the pulse curve of the carotid, is shown in Fig. 38. The letters with the dash correspond to the unmarked letters in the cardiogram.]

The **cause of the ventricular impulse** has been much discussed. It depends upon the following:—

FIG. 38.



The upper curve from the human carotid; the lower a cardiogram taken simultaneously.

(1) The base of the heart (auriculo-ventricular groove) represents during diastole a *transversely-placed ellipse* (Fig. 40, I, FG), while during contraction it has a more *circular* figure, *ab*. Thus, the long diameter of the ellipse (FG) is diminished, the small diameter *dc* is increased, while the base is brought nearer to the chest wall *e*. This alone does not cause the impulse, but the basis of the heart, being hardened during the systole and brought nearer to the chest wall, allows the apex to execute the movement which causes the impulse (p. 102).

(2) During relaxation, the ventricle lies with its apex (Fig. 40, II, *i*) obliquely

FIG. 39.



Curves from the apex beat. A, normal curve (man); B, from a dog; C, very rapid curve (dog); D and E, normal curves (man) registered on a vibrating glass plate where each indentation = 0.01613 sec. In all the curves *ab* means contraction of the auricles, and *bc* of the ventricles; *d*, closure of the aortic, and *e*, of the pulmonary valves; *ef*, diastole of the ventricle.

downward, and with its long axis in an oblique direction—so that the angles (*bci*, *aci*) formed by the axis of the ventricles with the diameter of the base are unequal

—during systole it represents a regular cone, with its axis at right angles to its base. Hence, the apex (*i*) must be erected from below and behind (*p*), forward and upward (*Harvey*—"cor sese erigere"), and when hardened during systole presses itself into the intercostal space (Fig. 40, II).

(3) The ventricles undergo during systole a slight spiral twisting on their long axis ("lateralem inclinationem"—*Harvey*), so that the apex is brought from behind more forward, and thus a greater portion of the left ventricle is turned to the front. This rotation is caused by the muscular fibres of the ventricles, which proceed from that part of the fibrous rings between the auricles and ventricles which lies next the anterior thoracic wall. The fibres pass from above obliquely downward, and to the left, and also run in part upon the posterior surface of the ventricles. When they contract in the axis of their direction, they tend to

FIG. 40.



I. II.

I. Schematic horizontal section through the heart, lungs, and thorax, to show the change of shape which the base of the heart undergoes during contraction of the ventricle—F, G, transverse diameter of the ventricle during diastole; *e*, position of the thoracic wall: *a*, *b*, transverse diameter of the heart during systole, with *e*, position of the anterior thoracic wall during systole. II. Side view of the heart—*i*, apex during diastole; *p*, during systole.

raise the apex, and also to bring more of the posterior surface of the heart in relation with the anterior thoracic wall. It is favored by the slightly spiral arrangement of the aorta and pulmonary artery.

These are the most important causes, but the minor causes are—

(4) The "*reaction impulse*" or "*recoil*," or that movement which the ventricles are said to undergo (like an exploded gun or rocket), at the moment when the blood is discharged into the aorta and pulmonary artery, whereby the apex goes in the opposite direction, *i. e.*, downward and slightly outward. Landois, however, has shown that the mass of blood is discharged into the vessels 0.08 of a second after the beginning of the systole, while the cardiac impulse occurs with the first sound.

(5) When the blood is discharged into the aorta and pulmonary artery, these

vessels are slightly *elongated*, owing to the increased blood pressure. As the heart is suspended from above by these vessels, the apex is pressed slightly downward and forward toward the intercostal space (?).

As the cardiac impulse is observed in the empty hearts of dead animals, (4) and (5) are certainly of only second-rate importance. Filehne and Pentzoldt maintain that the apex during systole does not move to the left and downward, as must be the case in (4) and (5), but that it moves upward and to the right—a result corroborated by v. Ziemssen. [Barr attributes the cause of the impulse to the rigidity or hardening of the ventricle during systole, to the rotatory movement and lengthening downward of the blood column in the aorta and pulmonary artery, while toward the end of the systole the maximum of recoil takes place and also contributes to cause it.]

It is to be remembered that as the apex is *always* applied to the chest wall, separated from it merely by the thin margin of the lung, it only presses against the intercostal space during systole (*Kiwisch*).

After the apex of the curve, *c*, has been reached at the end of the systole, the curve falls rapidly, as the ventricles quickly become relaxed. In the descending part of the curve, at *d* and *e*, are two elevations, which occur *simultaneously with the second sound.* These are caused by the sudden closure of the semilunar valves, whereby an impulse is propagated through the axis of the ventricle to its apex, and thus causes a vibration of the intercostal space; *d* corresponds to the closure of the aortic valves, and *e* to the closure of the pulmonary valves. The closure of the valves in these two vessels is not simultaneous, but is separated by an interval of 0.05 to 0.09 sec. The aortic valves close sooner on account of the greater blood pressure there. Complete diastolic relaxation of the ventricle occurs from *e* to *f* in the curve.

It is clear, then, that the cardiac impulse is caused chiefly by the contraction of the ventricles, while the auricular systole and the vibration caused by the closure of the semilunar valves are also concerned in its production.

[**Change in Shape of Heart.**—The experiments of Ludwig and Hesse on the heart of the dog show that the shape of the ventricles varies remarkably in systole and diastole, and that the shape of the heart as found post-mortem is not its natural shape.]

[**Method.**—Bleed a dog rapidly from the carotids, defibrinate the blood, expose the heart, tie graduated straight tubes into the pulmonary artery and aorta, and ligature the auricular vessels. Pour the blood into the heart until it is dilated under a pressure equal to the mean arterial pressure

FIG. 41. FIG. 42. FIG. 43.

Projection of a dog's heart. Posterior surface. Anterior surface. Left lateral surface.

(150 mm.). The ventricles are in the diastolic phase, the auricles still pulsate. A plaster cast is now rapidly made of the ventricles. This represents the diastolic phase. To obtain what may be regarded as the systolic phase, a heart, similarly prepared but emptied of blood, is suddenly plunged into a hot (50° C.) saturated solution of potassic bichromate, when the heart gives one rapid and final contraction and remains permanently contracted, owing to the heat rigor, its proteids being coagulated (§ 295). This is the systolic phase. Little pins with twisted points are previously inserted in the organ to mark certain parts of both hearts for comparison.]

[In diastole, the shape of the ventricle is hemispheroidal, the apex being rounded, while the posterior surface is flatter than the anterior (Fig. 41). In the plane of

the ventricular base, the greatest diameter is from right to left, and the shortest from base to apex. The conus arteriosus is above the plane of the base. During *systole*, the apex is more pointed, the ventricle more conical, while all the diameters in the plane of the base are equally diminished, hence the vertical measurement from base to apex is longer now than either of the diameters at the base (Fig. 43). The conus arteriosus sinks toward the plane of the base, while the base of the ventricle becomes more circular, so that the difference of the curvatures of the anterior and posterior surfaces vanishes (Fig. 42). In all these figures the shaded part represents diastole and the clear part systole. The most remarkable point is that the vertical measurement remains unchanged. This refers to the left ventricle, which of course forms the apex; the right is shortened. The plane of the ventricular base in systole is about one-half of what it is in diastole, as is shown in Fig. 44. Thus the heart is diminished in all its diameters except one, the arterial orifices are scarcely affected, while the area of the auriculo-ventricular orifices (M, T) is diminished about one-half (Fig. 45). This is most important in connection with the closure of the auriculo-ventricular valves; as it shows that the muscular fibres of the heart, by diminishing these orifices during systole, greatly aid in the perfect closure of these valves. Thus we explain why defective nutrition of the cardiac muscle may give rise to incompetency of these valves, without the valves themselves being diseased (*Macalister*).]

FIG. 44.

Projection of the base in systole and diastole. RV, right, and LV, left ventricle.

FIG. 45.

A, aorta; PA, pulmonary artery; M, mitral, and T, tricuspid orifice.

[In order to account for the vertical diameter remaining unchanged, we may represent the ventricular fibres as consisting of three layers, viz., an inner and outer set, more or less longitudinal, and a middle set, circular. Both sets will tend, when they contract, to diminish the cavity, but the shortening of the longitudinal layers is compensated for by the contraction, *i. e.*, the elongation produced by the circular set.]

[In order to obtain the **shape of the cavities**, dogs were taken of the same litter and as nearly alike as possible. One heart was filled with blood, as already described, and placed in a cool solution of potassic bichromate, whereby it was slowly hardened in the diastolic form, while the other was plunged, as before, into a hot solution. Casts were then made of the cavities.]

51. THE TIME OF THE CARDIAC MOVEMENTS.—Methods.—The time occupied by the various *phases of the movements* of the heart may be determined by studying the apex beat curve.

(1) If we know at what rate the plate on which the curve was obtained moved during the experiment, of course all that is necessary is to measure the distance, and so calculate the time occupied by any event (see Pulse, § 67).

(2) It is preferable, however, to cause a tuning fork, whose rate of vibration is known, to write its vibrations under the curve of the apex beat, or the curve may be written upon a plate attached to a vibrating tuning fork (Fig. 39, D, E). Such a curve contains fine teeth caused by the vibrations of the tuning fork. D and E are curves obtained from the cardiac impulse in this way from healthy students. In D the notch *d* is not indicated. Each complete vibration of the tuning fork, reckoned from apex to apex of the teeth = 0.01613 second, so that it is simply necessary to count the number of teeth and multiply to obtain the time. The values obtained vary within certain limits even in health.

The value of *a b* = **pause + contraction of the auricles,** is subject to the greatest variation, and depends chiefly upon the number of heart beats per minute. The more quickly the heart beats, the shorter is the pause, and conversely. In some curves, even when the heart beats slowly, it is scarcely possible to distinguish

the auricular contraction (indicated by a rise) from the part of the curve corresponding to the pause (indicated by a horizontal line). In one case (heart beats 55 per minute) the pause = 0.4 second, the auricular contraction = 0.177 second. In Fig. 39, A, the time occupied by the pause + the auricular contraction (74 beats per minute) = 0.5 second. In D, *a b* = 19 to 20 vibrations = 0.32 second; in E = 26 vibrations = 0.42 second.

The **ventricular systole** is calculated from the beginning of the contraction *b*, to *e* when the semilunar valves are closed; it lasts from the first to the second sound. It also varies somewhat, but is more constant. When the heart beats rapidly, it is somewhat shorter—during slow action longer. In E = 0.32 second; in D = 0.29 second; with 55 beats per minute Landois found it = 0.34, with a very high rate of beating = 0.199 second.

When the ventricles beat feebly, they contract more slowly, as can be shown by applying the registering apparatus to the heart of an animal just killed. In Fig. 46, from the ventricle of a rabbit just killed, the slow heart beats, B, are seen to last longest. In cases of enormous hypertrophy and dilatation of the left ventricle, the duration of the ventricular systole is not longer than normal (*Landois*).

In calculating the time occupied by the ventricular systole we must remember—(1) *The time between the two sounds* of the heart, *i. e.*, from the beginning of the first to the end of the second sound (*b* to *e*). (2) *The time the blood flows into the aorta*, which comes to an end at the depression between *c* and *d* (in Fig. 39, E). Its commencement, however, does not coincide with *b*, as the aortic valves open 0.085 to 0.073 second after the beginning of the ventricular systole. Hence the aortic current lasts 0.08 to 0.09 second. This is calculated in the following way: The time between

FIG. 46.



Curves recorded by the ventricle of a rabbit, upon a vibrating plate attached to a tuning fork (vibration = 0.01613 sec.). A, soon after death; B, from the dying ventricle.

the first sound of the heart and the pulse in the axillary artery is 0.137 second, and of this time 0.052 second is occupied in the propagation of the pulse wave along the 30 cm. of artery lying between the root of the aorta and the axilla. Thus the pulse wave in the aorta occurs 0.137 minus 0.052 = 0.085 second after the beginning of the first sound. The current in the pulmonary artery is interrupted in the depression between *d* and *e*. (3) *Lastly, the time occupied by the muscular contraction of the ventricle*, which begins at *b*, reaches its greatest extent at *c*, and is completely relaxed at *f*. The apex of the curve, *c*, may be higher or lower according to the flexibility of the intercostal space, hence the position of *c* varies. In hypertrophy with dilatation of the left ventricle, the duration of the ventricular contraction does not greatly exceed the normal.

The time which elapses between *d* and *e*, *i.e.*, between the complete closure of the aortic and pulmonary valves, is greater the more the pressure in the aorta exceeds that in the pulmonary artery, as the valves are closed by the pressure from above, and the difference in time may be 0.05 second, or even double that time, in which case the second sound appears double (compare § 54). If the aortic pressure diminishes while that in the pulmonary artery rises, *d* and *e* may be so near each other that they are no longer marked as distinct elements in the curve.

The time, *ef*, during which the ventricles relax varies somewhat: 0.1 second may be taken as a mean.

Accelerated Cardiac Action.—When the action of the heart is greatly accelerated, the pause is considerably shortened in the first instance (*Donders*), and to a less extent the time of contraction of the auricles and ventricles. When the pulse rate is very rapid, the systole of the atria coincides with the closure of the arterial valves of the preceding contraction, as is shown in Fig. 39, C (dog).

In registering the cardiac impulse, the apparatus is separated by a greater or less depth of soft parts from the heart itself, so that in all cases the intercostal tissues do not follow exactly the movements of the heart, and thus the curve obtained may not coincide mathematically with the movements of the heart. It is desirable that curves be obtained from persons whose hearts are exposed, *i.e.*, in cases of **ectopia cordis.**

Cleft Sternum.—Gibson inscribed cardiograms from the heart of a man with cleft sternum. The following were the results obtained: Auricular contraction = 0.115; ventricular contraction $(b, d) = 0.28$; difference between closure of valves $(d, e) = 0.09$; ventricular diastole $(e, f) = 0.11$; pause = 0.45 second.

FIG. 47.



Marey's registering tambour. T, metallic capsule, with thin india-rubber stretched over it, and bearing an aluminium disk, which acts upon the writing lever, H. By means of a thick-walled caoutchouc tube, it may be connected with any system containing air, so as to record variations of pressure.

Endocardial Pressure.—In large mammals, such as the horse, Chauveau and Marey (1861) determined the duration of the events that occur within the heart, and also the endocardial pressure by means of a **cardiac sound.** Small elastic bags attached to tubes were introduced through the jugular vein into the right auricle and ventricle. Each of these tubes was connected with a registering tambour (Fig. 47), and simultaneous tracings of the variations of pressure within the cavities of the heart were obtained by causing the writing points of the levers of the tambours to write upon a revolving cylinder.

Fig. 48, A, gives the result obtained when one elastic bag was placed in the right auricle, being introduced through the jugular vein and superior vena cava; B, when the other bag pushed through the tricuspid orifice was in the right ventricle; D, in the root of the aorta, pushed in through the carotid; C, pushed past the semilunar valves into the left ventricle; while at E a similar bag has been placed externally between the heart's apex and the inner wall of the chest. In all cases v = auricular contraction; V, that of the ventricle; s, closure of semilunar valves, sooner in C than B; P = pause.

Methods.—(1) The **cardiac sound** consists of a tube containing two separate air passages, and in connection with each of these there is a small elastic bag or ampulla. One of the bags is fixed to the free end of the sound, and communicates with one of the air passages. The other bag is placed in connection with the second air passage in the sound, and at such a distance that, when the former bag lies within the ventricle, the latter is in the auricle. Each bag and air tube communicating with it is connected with a Marey's tambour (Fig. 47), provided with a lever which inscribes its movements upon a revolving cylinder. Any variation of pressure within the auricle or ventricle will affect the elastic ampullæ, and thus raise or depress the lever. Care must be taken that the writing points of the levers are placed exactly above each other. A tracing of the cardiac impulse is taken simultaneously by means of a cardiograph attached to a separate tambour.

It has still to be determined whether the auricles and ventricles act alternately, so that at the moment of the beginning of the ventricular contraction the auricles relax, or whether the ventricles are contracted while the auricles still remain slightly contracted, so that the whole heart is contracted for a short time at least. The latter view was supported by Harvey, Donders, and others, while Haller and many of the more recent observers support the view that the action of the auricles and ventricles alternates. In the case of Frau Serafin, whose heart was exposed, v. Ziemssen obtained curves from the auricles, which showed that the contraction of the auricles continued even after the commencement of the ventricular systole. In Marey's curve the contraction of the ventricle is represented as following that of the auricle (Fig. 48).

[(2) Rolleston used a special apparatus which was connected with the interior of the heart, and he finds that there is no distinct rise of pressure in the dog within the ventricles corresponding to the auricular systole such as was obtained by Marey in the horse. During the ventricular diastole in certain cases the pressure falls below the atmospheric pressure, and may be equal to —20 mm. mercury or more in the left ventricle (*cf.* 48). It is probably caused by the elastic expansion of the

ventricle continuing after the blood in the auricle at the moment of the cessation of the ventricular systole has entered the ventricle, *i.e.*, the quantity of blood in the auricle is not sufficient in all cases to distend the left ventricle to the point at which its suction action ceases. Magini, operating on dogs with a trocar which perforated the cavities of the heart, found none of the secondary elevations obtained by Marey with his sound.]

A. Fick regards the alternating contraction as a means whereby the pressure in the large venous trunks is kept nearly constant. At the moment of ventricular systole the auricles relax, and the venous blood flows freely into the latter, while if the auricles remained contracted, the blood in the veins would be kept back. Further, at the moment of ventricular diastole the auricles contract, so that there is not an abnormal diminution of the pressure in the veins. Thus the pressure in the auricle is more equable, while the current in the terminal parts of the veins is kept more constant.

FIG. 48.



Curves obtained from the heart of a horse by the cardiac sound.

52. **PATHOLOGICAL CARDIAC IMPULSES.—Change in the Position of the Apex Beat.**—The position of the cardiac impulse is changed—(1) by the accumulation of fluids (serum, pus, blood) or gas in one pleural cavity. A copious effusion into the left pleural cavity compresses the lung, and may displace the heart toward the right side, while effusion on the right side may push the heart more to the left. As the right heart must make a greater effort to propel the blood through the compressed lung, the cardiac impulse is usually increased. Advanced emphysema of the lung, causing the diaphragm to be pressed downward, displaces the heart downward and inward, while pushing or pulling up of the diaphragm (by contraction of the lung, or through pressure from below) causes the apex beat to be displaced upward, and also slightly to the left. Thickening of the muscular walls with dilatation of the cavities of the left ventricle makes that ventricle longer and broader, while the increased cardiac impulse may be felt in the axillary line in the sixth, seventh, or even eighth intercostal space to the left of the mammary line. Hyper-

trophy, with dilatation of the right side, increases the breadth of the heart, so that the cardiac impulse is felt more to the right, even to the right of the sternum. In the rare cases where the heart is transposed, the apex beat is felt on the right side. When the cardiac impulse goes to the left of the left mammary line, or to the right of the parasternal line, the heart is increased in breadth, and there is hypertrophy of the heart. A greatly increased cardiac impulse may extend to several intercostal spaces.

The cardiac impulse is abnormally **weakened** in cases of atrophy and degeneration of the cardiac muscle, or by weakening of the innervation of the cardiac ganglia. It is also weakened when the heart is separated from the chest wall owing to the collection of fluids or air in the pericardium, or by a greatly distended left lung; and, indeed, when the left side of the chest is filled with fluid, the cardiac impulse may be extinguished. The same occurs when the left ventricle is very imperfectly filled during its contraction (in consequence of marked narrowing of the mitral orifice), or when it can only empty itself very slowly and gradually, as during marked narrowing of the aortic orifice.

An **increase** of the cardiac impulse occurs during hypertrophy of the walls, as well as under the influence of various stimuli (psychical, inflammatory, febrile, toxic) which affect the cardiac ganglia. Great hypertrophy of the left ventricle causes the heart to *heave*, so that a part of the chest wall may be raised and also vibrate during systole.

A **pulling in** of the anterior wall of the chest during the cardiac systole occurs in the third and fourth interspaces, not unfrequently under normal circumstances, sometimes during increased cardiac action, and in eccentric hypertrophy of the ventricles. As the heart's apex is slightly displaced, and the ventricle becomes slightly smaller during its systole, the empty space is filled by the

FIG. 49, A.



yielding soft parts of the intercostal space. When the heart is united with the pericardium and the surrounding connective tissue, which renders systolic locomotion of the heart impossible, retraction of the chest wall during systole takes the place of the cardiac impulse (*Skoda*). During the diastole, a diastolic cardiac impulse of the corresponding part of the chest wall may be said to occur.

Clinically, changes in the cardiac impulse are best ascertained by taking graphic representations of the cardiac impulse, and studying the curves so obtained (Figs. 49 A and 49 B).

In curve P (much reduced), from a case of marked **hypertrophy with dilatation,** the ventricular contraction, *bc*, is usually very great, while the time occupied by the contraction is not much increased. P and Q were obtained from a case of marked eccentric hypertrophy of the left ventricle, due to insufficiency of the aortic valves. Curve Q was taken intentionally over the auriculo-ventricular groove, where retraction of the chest wall occurred during systole; nevertheless the individual events occurring in the heart are indicated.

Fig. E is from a case of **aortic stenosis.** The auricular contraction (*ab*) lasts only a short time; the ventricular systole is obviously lengthened, and after a short elevation (*bc*) shows a series of fine indentations (*c*, *e*) caused by the blood being pressed through the narrow and roughened aorta.

Fig. F, from a case of **insufficiency of the mitral valve,** shows (*ab*) well marked on account of the increased activity of the left auricle, while the shock (*d*) from the closure of the aortic valves is small, on account of the diminished arterial tension. On the other hand, the shock from the accentuated pulmonary sound (*e*) is very great, and is in the apex of the curve. On account of the great tension in the pulmonary artery, the second pulmonary tone may be so strong, and

succeed the second aortic sound (*d*) so rapidly, that both almost merge completely into each other (H and K).

The curve of **stenosis of the mitral orifice** (G) shows a long, irregular, notched, auricular contraction (*ab*), caused by the blood being forced through an irregular narrow orifice. The ventricular contraction (*bc*) is feeble because the ventricle is imperfectly filled. The closures of the two valves, *d* and *e*, are relatively far apart, and one can hear distinctly a reduplicated second sound. The aortic valves close rapidly, because the aorta is imperfectly supplied with blood, while the more copious inflow of blood into the pulmonary artery causes its valves to close later.

If the heart beats rapidly and feebly—if the blood pressure in the aorta and pulmonary artery be low, the signs of closure of the pulmonary valves may be absent—as in curve L—taken from a girl suffering from nervous palpitation and morbus Basedowii.

In very rare cases of insufficiency of the mitral valve, it has been observed that at certain times both ventricles contract simultaneously, as in a normal heart, but that this alternates with a condition where the right ventricle alone seems to contract. Curve M is such a curve obtained by Malbranc, who called this condition **intermittent hemisystole.** The first curve (I) is like a normal curve, during which the whole heart acted as usual. The curve II, however, is caused by the right side of the heart alone; it wants the closure of the aortic valves, *d*, and there was no pulse in the arteries. Owing to insufficiency of the tricuspid valve, the same person had a venous pulse with every cardiac impulse, so that the arterial and venous pulses first occurred together, and then the venous pulse alone occurred. In these cases the mitral insufficiency leads to the right ventricle

FIG. 49, B.



FIGS. 49 A AND 49 B.—Curves of the cardiac impulses. *ab*, contraction of auricles; *bc*, ventricular systole: *d*, closure of aortic, and *e*, of pulmonary valves; *ef*, diastole of ventricle: P, Q, hypertrophy and dilatation of the left ventricle; E, stenosis of the aortic orifice; F, mitral insufficiency; G, mitral stenosis; L, nervous palpitation in Basedow's disease; M, so-called hemisystole.

being overdistended, while the left is nearly empty, so that the right side requires to contract more energetically than the left. It does not seem that the right ventricle alone contracts in these cases, but rather that the action of the left side is very feeble.

53. THE HEART SOUNDS.—On listening over the region of the heart in a healthy man, either with the ear applied directly to the chest wall (*Harvey*), or by means of a stethoscope (*Laennec*, 1819), we hear two characteristic sounds, the so-called "**heart sounds.**" The two sounds are called first and second, and together they correspond to a single cardiac cycle. These sounds are separated by silences. [Fig. 50 shows the relation of the events occurring in the heart during a cardiac cycle to the sounds and silences.]

FIG. 50.

Scheme of a cardiac cycle. The inner circle shows what events occur in the heart, and the outer, the relation of the sounds and silences to these events.

1. The first sound.
2. The first or short silence.
3. The second sound.
4. The second or long silence.

[**Relative Duration.**—There is no absolute duration of each phase of a cardiac cycle, but we may take the aver-

age duration calculated from the measurements of Gibson, in a case of fissure of the sternum, to be as follows:—

Auricular systole,	.112 sec.
Ventricular systole,	.368 "
Ventricular diastole,	.578 "
Cardiac cycle,	1.058 sec.

Suppose we divide the cycle into tenths (*Walshe*), then the first sound will last $\frac{4}{10}$, the first silence $\frac{1}{10}$, the second sound $\frac{2}{10}$, and the long silence $\frac{3}{10}$ of the entire period.]

The **first sound** [long or systolic] is twice as long as, somewhat duller, and one-third or one-fourth deeper than, the second sound; it is less sharply defined at first, and is *synchronous with the systole of the ventricles.*

The **second sound** [short or diastolic] is clearer, sharper, shorter, more sudden, and is one-third to one-fourth higher; it is sharply defined and *synchronous with the closure of the semilunar valves.* The sounds emitted during each cardiac cycle have been compared to the pronunciation of the syllables *lŭbb, dŭp.* Or the result may be expressed thus—



[It is to be remembered that in reality *four* sounds are produced in the heart, but the two first sounds occur together and the two second, so that only a single first and a single second sound are heard.]

The **causes of the first sound** are due to two conditions. As the sound is heard, although enfeebled, in an excised heart in which the movements of the valves are arrested, and also when the finger is introduced into the auriculo-ventricular orifices so as to prevent the closure of the valves (*C. Ludwig and Dogiel*), one of the chief factors lies in the "*muscle sound*" produced by the contracting muscular fibres of the ventricles. This sound is supported and increased by the sound produced by the tension and vibration of the auriculo-ventricular valves and their chordæ tendineæ, at the moment of the ventricular systole. Wintrich, by means of proper resonators, has analyzed the first sound and distinguished the clear, short, valvular part from the deep, long, muscular sound.

The muscle sound produced by *transversly striped muscle* does not occur with a *simple* contraction (p. 127), but only when several contractions are superposed to produce tetanus (§ 303). The ventricular contraction is only a *simple* contraction, but it lasts considerably longer than the contraction of other muscles, and herein lies the cause of the occurrence of the muscle sound during the ventricular contraction.

Defective Heart Sounds.—In certain conditions (typhus, fatty degeneration of the heart), where the muscular substance of the heart is much weakened, the first sound may be completely inaudible. In aortic insufficiency, in consequence of the reflux of blood from the aorta into the ventricle, the mitral valve is gradually stretched, and sometimes even before the beginning of the ventricular systole, the first sound may be absent. Such pathological conditions seem to show that, for the production of the first sound, muscle sound and valve sound must eventually work together, and that the tone is altered, or may even disappear, when one of these causes is absent. [Yeo and Barrett state that the sound is purely muscular (?).]

The cause of the second sound is undoubtedly due to the prompt closure, and therefore sudden stretching or tension, of the semilunar valves of the aorta and pulmonary artery, so that it is purely a valvular sound. Perhaps it is augmented by the sudden vibration of the fluid particles in the large arterial trunks. [The second sound has all the characters of a valvular sound. That the aortic

valves are concerned in its production, is proved by introducing a curved wire through the left carotid artery and hooking up one or more segments of the valve, when the sound is modified, and it may disappear or be replaced by an abnormal sound or "murmur." Again, when these valves are diseased, the sound is altered, and it may be accompanied or even displaced by murmurs.] Although the aortic and pulmonary valves do not close simultaneously, usually the difference in time is so small that *both* valves make *one* sound, but the second sound may be double or divided when, through increase of the difference of pressure in the aorta and pulmonary artery, the interval becomes longer. Even in health this may be the case, as occurs at the end of inspiration or the beginning of expiration (*v. Dusch*).

Where the Sounds are Heard Loudest.—The sound produced by the *tricuspid valve* is heard loudest at the junction of the lower right costal cartilages with the sternum; as the *mitral valve* lies more to the left and deeper in the chest, and is covered in front by the arterial orifice, the mitral sound is best heard at the apex beat, or immediately above it, where a strip of the left ventricle lies next the chest wall. [The sound is conducted to the part nearest the ear of the listener by the muscular substance of the heart.] The aortic and pulmonary orifices lie so close together that it is convenient to listen for the second (*aortic*) sound in the direction of the aorta, where it comes nearest to the surface, *i. e.*, over the second right costal cartilage or aortic cartilage close to its junction with the sternum. The sound, although produced at the semilunar valves, is carried upward by the column of blood and by the walls of the aorta. The sound produced by the *pulmonary artery* is heard most distinctly over the third left costal cartilage, somewhat to the left and external to the margin of the sternum (Fig. 51).

54. **VARIATIONS OF THE HEART SOUNDS.**—**Increase** of the first sound of both ventricles indicates a more energetic contraction of the ventricles and a simultaneously greater and more sudden tension of the auriculo-ventricular valves. Increase of the second sound is a sign of increased tension in the interior of the corresponding large arteries. Hence increase of the second (pulmonary) sound indicates overfilling and excessive tension in the pulmonary circuit. *A feeble* action of the heart, as well as abnormal want of blood in the heart, causes weak heart sounds, which is the case in degenerations of the heart muscle.

Irregularities in structure of the individual valves may cause the heart sounds to become "**impure.**" If a pathological cavity, filled with air, be so placed, and of such a form as to act as a resonator to the heart sounds, they may assume a "metallic" character. The first and second sounds may be "**reduplicated**" or [although "duplication" is a more accurate term (*Barr*)] doubled. The reduplication of the first sound is explained by the tension of the tricuspid and that of the mitral valves not occurring simultaneously. Sometimes in disease a sound is produced by a hypertrophied auricle producing an audible **presystolic sound**, *i. e.*, a sound or "murmur" preceding the first sound. [This has been questioned quite recently.] As the aortic and pulmonary valves do not close quite simultaneously, a *reduplicated second sound* is only an increase of a physiological condition. All conditions which cause the aortic valves to close rapidly (diminished amount of blood in the left ventricle) and the pulmonary valves to close later (congestion of the right ventricle—both conditions together in mitral stenosis), favor the production of a reduplicated second sound.

Cardiac Murmurs.—If irregularities occur in the valves, either in cases of stenosis or in insufficiency, so that the blood is subjected to vibratory oscillations and friction, then, instead of the heart sounds, other sounds—**murmurs** or **bruits**—arise or accompany these. A combination of these sounds is always accompanied by disturbances of the circulation. [These murmurs may be produced within the heart, when they are termed **endocardial**; or outside it, when they are called **exocardial** murmurs. But other murmurs are due to changes in the quality or amount of the blood, when they are spoken of as **hæmic** murmurs. In the study of all murmurs, note their *rhythm* or exact relation to the normal sounds, their *point of maximum intensity*, and the *direction in which the murmur is propagated.*] It is rare that tumors or other deposits projecting into the ventricles cause murmurs, unless there be present at the same time lesions of the valves and disturbances of the circulation. The cardiac murmurs are always related to the systole or diastole, and usually the systolic are more accentuated and louder. Sometimes they are so loud that the thorax trembles under their irregular oscillations (*fremitus*, frémissement cataire).

In cases where **diastolic murmurs** are heard, there are always anatomical changes in the car-

diac mechanism. These are insufficiency of the arterial valves, or stenosis of the auriculo-ventricular orifice (usually the left). **Systolic murmurs** do not always necessitate a disturbance in the cardiac mechanism. They may occur on the left side, owing to insufficiency of the mitral valve, stenosis of the aorta, and in the calcification and dilatation of the ascending part of the aorta. These murmurs occur very much less frequently on the right side, and are due to insufficiency of the tricuspid and stenosis of the pulmonary orifice.

FIG. 51.



The heart—its several parts and great vessels in relation to the front of the thorax. The lungs are collapsed to their normal extent, as after death, exposing the heart. The outlines of the several parts of the heart are indicated by very fine dotted lines. The area of propagation of valvular murmurs is marked out by more visible dotted lines. A, the circle of mitral murmur, corresponds to the left apex. The broad and somewhat *diffused area*, roughly triangular, is the region of tricuspid murmurs, and corresponds generally with the right ventricle, where it is least covered by lung. The letter C is in its centre. The circumscribed *circular area*, D, is the part over which the pulmonic arterial murmurs are commonly heard loudest. In many cases it is an inch, or even more, lower down, corresponding to the *conus arteriosus* of the right ventricle, where it touches the wall of the thorax. The internal organs and parts of organs are indicated by letters as follows:—*r. au*, right auricle, traced in fine dotting; *ao*, arch of aorta, seen in the first intercostal space, and traced in fine dotting on the sternum; *v. i.*, the two innominate veins; *r. v.*, right ventricle; *l. v.*, left ventricle.

Functional Murmurs.—Systolic murmurs often occur without any valvular lesion, although they are always less loud, and are caused by abnormal vibrations of the valves or arterial walls. They occur most frequently at the orifice of the pulmonary artery [and are generally heard at the base], less frequently at the mitral, and still less frequently at the aortic or the tricuspid orifice. Anæmia, general malnutrition, acute febrile affections, are the causes of these murmurs. [Some of

these are due to an altered condition of the blood, and are called **hæmic**, and others to defective cardiac muscular nutrition, and are called **dynamic** (*Walshe*).]

Sounds may also occur during a certain stage of inflammation of the pericardium (pericarditis) from the roughened surfaces of this membrane rubbing upon each other. Audible friction sounds are thus produced, and the vibration may even be perceptible to touch. [These are "**friction sounds**," and quite distinct from sounds produced within the heart itself.]

55. DURATION OF THE MOVEMENTS OF THE HEART.—

FIG. 52.



Curves of excised rabbit's heart. 1, 6 mins. after excision; 2, 10 mins.; 3, 20 mins.; 4, 70 mins. (After *Waller and Reid.*)

The heart continues to beat for some time after it is cut out of the body. The movement lasts longer in cold-blooded animals (frog, turtle)—extending even to days—than in mammals. A rabbit's heart beats from 3 minutes up to 36 minutes after it is cut out of the body. The average of many experiments is about 11 minutes. [Waller and Reid recorded the ventricular contractions of a rabbit's heart 72 minutes after its excision. Fig. 52 shows the prolongation of the ventricular systole in an excised rabbit's heart, the movements being recorded by a lever resting on the heart.] Panum found the last trace of contraction to occur in the right auricle (rabbit) 15 hours after death; in a mouse's heart, 46 hours; in a dog's, 96 hours. An excised frog's heart beats, at the longest, 2½ days (*Valentin*). In a human embryo (third month) the heart was found beating after 4 hours. In this condition stimulation causes an increase and acceleration of the action. The ventricular contraction weakens, and soon each auricular contraction is not followed by a ventricular contraction, two or more of the former being succeeded by only one of the latter. At the same time the ventricles contract more slowly (Fig. 46), and soon stop altogether, while the auricles continue to beat. If the ventricles be stimulated directly, as by pricking them with a pin, they may execute a contraction. The left auricle soon ceases to beat, while the right auricle still continues to contract. The right auricular appendix continues to beat longest, as was observed by Galen and Cardanus (1550), and it is termed "ultimum moriens." Similar observations have been made upon the hearts of persons who have been executed.

If the heart has ceased to beat, it may be excited to contract for a short time by direct stimulation, more especially by heat (*Harvey*); even under these circumstances the auricles and their appendices are the last parts to cease contracting. As a general rule, direct stimulation, although it may cause the heart to act more vigorously for a short time, brings it to rest sooner. In such cases, therefore, the regular sequence of events ceases, and there is usually a twitching movement of the muscular fibres of the heart. C. Ludwig found that, even after the excitability is extinguished in the mammalian heart, it may be restored by injecting arterial blood into the coronary arteries; conversely lesion of these vessels is followed by enfeebled action of the heart (§ 47). Hammer found that in a man whose left coronary artery was plugged the pulse fell from 80 to 8 beats per minute.

[The beats of the excised heart of a rabbit gradually decline in force and frequency, the latent period and contraction become longer and the excitability more obtuse. The duration of a contraction may be 6 sec., the normal being .3 sec. The beats have often a bigeminal character. An excised heart may be frozen quite hard, yet on being thawed it contracts spontaneously. The contraction proceeds in a wave from the spot stimulated in the frog's heart at 8° to 12° C. at 30 to 90 mm. per sec.; in the mammalian excised heart about 8 metres per sec. (*Waller and Reid*).]

Action of Gases on the Heart.—During its activity the heart uses O, and produces CO_2, so that it beats longest in pure O (12 hours), and not so long in N,—H (1 hour)—CO_2 (10 minutes)

—CO (42 minutes)—Cl (2 minutes), or in a vacuum (20 to 30 minutes), even when there is watery vapor present to prevent evaporation. If the heart be reintroduced into O it begins to beat again. [A frog's heart ceases to beat in compressed O (10 to 12 atmospheres) in about one-third of the time it would do were it simply excised and left to itself. An excised heart suspended in ordinary air beats three to four times as long as a heart which is placed upon a glass plate.]

[56. **PHYSICAL EXAMINATION OF THE HEART.**—The **physical methods** of diagnosis enable us to obtain precise knowledge regarding the actual state of the heart. The methods available are:—

1. Inspection.
2. Palpation.
3. Percussion.
4. Auscultation.

To arrive at a correct diagnosis all the methods must be employed.]

[**Inspection.**—The person is supposed to have his chest exposed and to be in the recumbent position. It is important to remember the **limits of the heart.** The *base* corresponds to a line joining the upper margins of the third costal cartilages, the apex to the fifth interspace, while transversely it extends from a little to the right of the sternum to within a little of the left nipple; this area occupied by the heart being called the **deep cardiac region.** By the eye we can detect any alteration in the configuration of the præcordia, bulging or retraction of the region as a whole or of the intercostal spaces, and we may detect variations in the position, character, extent of the cardiac impulse, or the presence of other visible pulsations.]

[**Palpation.**—By placing the whole hand flat upon the præcordia, we can ascertain the presence or absence, the situation and extent, and any alterations in the characters of the apex beat; or we may detect the existence of abnormal pulsations, vibrations, thrills, or friction in this region. In feeling for the apex beat, if it be at all feeble, it is well to make the patient lean forward. Of course, it must be remembered that the whole heart may be displaced by tumors or accumulations of fluids pressing upon it, *i. e.*, conditions external to itself, or the apex beat may be displaced from causes within the heart itself, as in hypertrophy of the left ventricle.]

[**Percussion.**—As the heart is a solid organ, and is surrounded by the lungs which contain air, it is evident that the sound emitted by striking the chest over the region of the former must be different from that produced over the latter. Not only is there a difference in the sound or note emitted, but the "sensation of resistance" which one feels on percussing the two organs is different. We may ascertain—

1. The superficial or absolute cardiac dullness.
2. The deep or relative dullness.

[**Superficial Cardiac Dullness.**—This theoretically is the part of the heart in direct contact with the chest wall and uncovered by lung, but obviously as the lungs vary in size during respiration, it must be smaller during inspiration and larger during expiration. It forms a roughly triangular space, whose base cannot be accurately determined, as the heart dullness merges into that of the liver, situate below it, but it corresponds to a horizontal line 2½ inches long, extending from the apex beat to the middle of the sternum. The internal side corresponding to the left edge of the sternum is 2 inches long, and reaches from the junction of the fourth costal cartilage with the sternum—apex of the triangle—to the sternal end of the base line. The superior, outer, or oblique line, 3 inches in length, is somewhat curved, and passes downward and outward from the apex of the triangle to the apex of the heart.]

[**Deep Cardiac Dullness.**—By this method theoretically we seek to define the exact limits of the heart as a whole, and thus to ascertain its absolute size, and of course percussion has to be done through a certain thickness of lung tissue, and hence one must strike the pleximeter forcibly. It extends vertically from the third rib and ends at the sixth, but owing to the cardiac merging in the hepatic dullness, this lower limit cannot be accurately ascertained; while *transversely* at the fourth rib it extends from just within the nipple line to slightly beyond the right of the sternum. By these means we may detect increase in the size of the heart or alterations in the relation of the lungs to the heart, fluid in pericardium, etc.]

[**Auscultation.**—This is one of the most valuable methods, for by it we can detect variations and modifications in the healthy sounds of the heart, the rhythm and frequency of the heart beat, the existence of abnormal sounds, and their exact relation to the normal sounds, also their characters and relation to the cardiac cycle, and the direction in which these sounds are propagated (§ 54).]

57. **INNERVATION OF THE HEART.**—[**Intra- and Extra-Cardiac Nervous Mechanism.**—When the heart is removed from the body, or when all the nerves which pass to it are divided, it still beats for some time, so that its movements must depend upon some mechanism situated within itself. The ordinary rhythmical movements of the heart are undoubtedly *associated with* the presence of nerve ganglia, which exist in the substance of the heart—the

intra-cardiac ganglia. But the movements of the heart are influenced by nervous impulses which reach it from without, so that there falls to be studied an *intra-cardiac* and an *extra-cardiac* nervous mechanism.]

The **cardiac plexus** is composed of the following nerves: (1) The cardiac branches of the vagus, the branch of the same name from the external branch of the superior laryngeal, a branch from the inferior laryngeal, and sometimes branches from the pulmonary plexus of the vagus (more numerous on the right side); (2) the superior, middle, inferior, and lowest cardiac branches of the three cervical ganglia and the first thoracic ganglia of the sympathetic; (3) the inconstant twig of the descending branch of the hypoglossal nerve, which, according to Luschka, arises from the upper cervical ganglion. From the plexus there proceed—the *deep* and the *superficial* nerves (the latter usually at the division of the pulmonary artery under the arch of the aorta, and containing the ganglion of Wrisberg) (§ 370). The following nerves may be separately traced from the plexus:—

(*a*) The **plexus coronarius dexter and sinister,** which contains the *vaso-motor nerves* for the coronary vessels (physiological proof still wanting) as well as the nerves (sensory?) proceeding from them (to the pericardium?).

(*b*) **Intra-cardiac nerves and ganglia.**—The nerves lying in the *grooves of the heart* and in *its substance* contain numerous ganglia (*Remak*), and are regarded as the automatic motor centres of the heart. A nervous ring containing numerous ganglia corresponds to the margin of the septum atriorum; there is another in the auriculo-ventricular groove. Where the two meet, they exchange fibres. The ganglia usually lie near the pericardium. In *mammals*, the two largest ganglia lie near the orifice of the superior vena cava—in *birds*, the largest ganglion (containing thousands of ganglionic cells) lies posteriorly where the longitudinal and transverse sulci cross each other. Fine branches, also provided with small ganglia, proceed from these ganglia, and penetrate the muscular walls of the auricles and ventricles.

[**Frog's Heart.**—The frog's heart consists of the *sinus venosus*, into which open the single inferior and the two superior venæ cavæ (Fig. 54). There are *two auricles;* the right one communicates with the sinus venosus, and opens into the single ventricle; the left auricle also

FIG. 53.

Heart of frog from the front. V, single ventricle; *Ad*, *As*, right and left auricles; B, bulbus arteriosus; 1, carotid, 2, aorta, and 3, pulmo-cutaneous arteries; C, carotid gland.

FIG. 54.



Heart of frog from behind. *s.v.*, sinus venosus opened; *ci*, inferior; *csd*, *css*, right and left superior venæ cavæ; *vp.*, pulmonary vein; *Ad*, and *As*, right and left auricles; *Ap*, communication between the right and left auricle.

opens into the *single ventricle* (Fig. 53, *v*), and in the latter are mixed the venous blood returned by the right auricle and the arterial blood from the left auricle. The aorta with its *bulbus arteriosus* conducts the blood from the ventricle. The various orifices are guarded by projections of tissue, which act like valves. The two auricles are completely separated by a septum. This septum ends posteriorly in a free concave margin so as to divide the auriculo-ventricular orifice into a right and a left orifice. Each orifice is guarded by two thick, fleshy valves, which close it.]

[**Nerves.**—The two cardiac branches of the vagi—the **nervi cardiaci**—proceed to the posterior surface of the sinus venosus, and where the latter joins the auricle they interlace, and are mixed with a number of ganglion cells (Fig. 57). This spot is called **Remak's ganglion,** is sometimes single, at others double, and it can be seen as a white "crescent" when the heart is lifted up and looked at from behind (Fig. 54). The cardiac nerves proceed downward on the auricular septum,

FIG. 55.

Auricular septum of a frog's heart. *a*, anterior, and *p*, posterior branch of the cardiac vagus; B, Bidder's ganglion.

FIG. 56.

Pyriform ganglionic bi-polar nerve cell from the heart of a frog. *m*, sheath; *n*, straight process; *o*, spiral process.

exchanging fibres in their course to join two ganglia at the auriculo-ventricular groove, and known as **Bidder's ganglia** (Fig. 57). It has been stated by one observer that the bulbus arteriosus contains ganglionic cells, but this is denied by others.]

According to Openchowsky, every part of the heart (frog, triton, tortoise) contains nerve fibres which are connected with every muscular fibre. In the auricles, at the end of the non-medullated fibre, a tri-radiate nucleus exists which gives off fibrils to the muscular bundles. There is a

FIG. 57.



Scheme of nerves of frog's heart. R. Remak's, and B. Bidder's ganglia; S.V., sinus venosus; A, auricles; V, ventricle; B.A., bulbus arteriosus; *vag*, vagi.

FIG. 58.



Stannius's experiment. A, auricle; V, ventricle; S.V., sinus venosus. The zig-zag lines indicate which parts continue to beat; in 2 the ventricle beats at a different rate.

network of fine nerve fibres distributed immediately under the endocardium—these fibres act partly *in a centripetal direction* on the cardiac ganglia, and are partly *motor* for the endocardial muscles. The parietal layer of the pericardium contains (sensory) nerve fibres. The following kinds of nerve cells are found—*unipolar cells*, the single processes of which afterward divide; **bipolar pyriform cells** (Fig. 56), which in the frog possess a straight (*n*) and usually also a spiral process (*o*).

58. THE AUTOMATIC MOTOR CENTRES OF THE HEART.—(1) It is generally assumed that the nervous centres which excite the cardiac movements, and maintain the rhythm of these movements, lie within the heart, and that they are probably represented by the *ganglia*.

(2) There are—not one, but several of these centres in the heart, which are connected with each other by conducting paths. As long as the heart is intact,

all its parts move in rhythmical sequence from a principal central point, an impulse being conducted from this centre through the conducting paths. What the "discharging forces" of these regular progressive movements are, is unknown. If, however, the heart be subjected to the action of diffuse stimuli (*e.g.*, strong electrical currents), all the centres are thrown into action, and a spasm-like action of the heart occurs. The *dominating centre lies in the auricles*, hence the regular progressive movement usually starts from them. If the excitability is diminished, as by touching the septum with opium, other centres seem to undertake this function, in which case the movement may extent from the ventricles to the auricles. According to Kronecker and Schmey, in the *dog's* heart there is a spot above the lower limit of the upper third of the ventricular septum, which, when it is injured, *e.g.*, by destroying it with a stout needle, brings the heart to a standstill; this has been called a coördinating centre.

(3) All stimuli of moderate strength applied directly to the heart cause at first an increase of the rhythmical heart beats; stronger stimuli cause a diminution, and it may be paralysis, which is often preceded by a convulsive movement. Increased activity exhausts the energy of the heart sooner.

(4) Single very weak stimuli, which have no effect on the heart when applied singly, if repeated sufficiently often, may become active, owing to "summation of the stimuli" (*v. Basch*).

(5) Even the weakest stimulus which can excite a contraction always causes an energetic contraction, *i. e.*, "the minimal stimulus causes a maximal effect" (*Bowditch, Kronecker and Stirling*).

(6) After every contraction of the heart there is a short period of "diminished excitability" or Marey's "refractory period," during which the heart is less susceptible to further stimulation.

(7) The non-ganglionic apex of the heart, when it is not stimulated, no longer beats spontaneously, but it responds each time by a single contraction to a single direct stimulus. If, however, a continuous stimulus, *e. g.*, a continuous current of electricity, be applied to it, it executes a series of beats. Such continuous stimuli are obtained through a continuous pressure of fluid, exerted on the interior of the heart or by moistening the heart with chemical substances.

(8) The auricular centres seem to be more excitable than those of the ventricle; hence, in a heart left to itself the auricles pulsate longest.

(9) The heart may be excited (reflexly) from its inner surface. Weak stimuli applied to the inner surface of the heart greatly accelerate the heart's action, the stimulus required being much feebler than that applied to the external surface of the heart. Strong stimuli, which bring the heart to rest, also act more easily when applied to the inner surface than when they are applied to its outer surface. The ventricle is always the first part to be paralyzed.

(10) In order that the heart may continue to contract, it is necessary that it be supplied with a fluid which, in addition to O, must contain the *necessary nutritive materials*. The most perfect fluid, of course, is blood. Hence the heart after a time ceases to beat in an indifferent fluid (0.6 per cent. sodium chloride), but its activity may be revived by supplying it with a proper nutritive fluid.

Cardiac Nutritive Fluids.—These nutritive fluids are such as contain serum-albumin, *e.g.*, blood, serum, or lymph. Serum retains its nutritive properties even after it has been subjected to diffusion (*Martius and Kronecker*). Milk and whey (*v. Ott*), normal saline solution mixed with blood, albumin, or peptone, and 0.3 per cent. solution carbonate (*Kronecker, Merunowicz and Stiénon*), a trace of caustic soda (*Gaule*), or a solution of the salts of serum, are suitable. Alkaline solution of soda revives a feebly beating heart by neutralizing the acid formed in the cardiac muscle, or normal saline containing calcic phosphate and potassic chloride (*S. Ringer*).

(11) The independent pulsations of parts of the heart which are devoid of ganglia, show that the presence of ganglia is not absolutely necessary in order to have

rhythmical pulsation. Direct stimulation of the heart may cause these movements. But the ganglia are more excitable than the heart muscle itself, and they conduct the impulses which lead to the regular alternating action of the various parts of the heart, so that, under normal circumstances, we must assume that the action of the heart is governed by the ganglia.

(12) If a heart be cut into pieces, so that the individual pieces still remain connected with each other, the regular peristaltic or wave-like movements proceeding from the auricles to the ventricle may continue for a long time (*Donders, Engelmann*). If the heart, however, be completely divided into two distinct pieces (auricle and ventricle), the movements of both parts continue, but not in the same sequence—they beat at different rates.

The chief experiments upon which the above statements are based are as follows:—

I. Experiments by **cutting** and **ligaturing** the heart. These experiments have been made chiefly upon the heart of the frog. The **ligature** experiments are performed by tightening and then relaxing a ligature placed around the heart, so that the physiological connection is destroyed, while the anatomical or mechanical connections (continuity of the cardiac wall, intact condition of its cavities) still exist. The most important of these experiments are—

(1) **Stannius's Experiment.**—If the sinus venosus of a frog's heart be separated from the auricles, either by an incision or by a ligature, the auricles and ventricle stand still in diastole, while the veins and the remainder of the sinus continue to beat (Fig. 58, 1). If a second incision be made at the auriculo-ventricular groove, as a rule the ventricle begins at once to beat again, while the auricles remain in the condition of diastolic rest. [Thus the sinus venosus and ventricle continue to beat, while the auricle stands still, but the two former no longer beat with the same rhythm, the ventricle usually beats more slowly, as is shown in Fig. 58, 2, by the large zig-zags.] According to the position of the second ligature or incision, the auricles may also beat along with the ventricles, or the auricles alone may beat, while the ventricles remain at rest.

Theoretical.—Various explanations of these experiments have been given: (*a*) Remak's ganglion in the sinus venosus is distinguished by its great excitability, while Bidder's ganglion in the auriculo-ventricular groove is less excitable; in the normal condition of the heart the motor impulse is carried from the former to the latter. If the sinus venosus be separated from the heart, Remak's ganglion has no action on the heart. The heart stops for two reasons—first, because Bidder's ganglion alone has not sufficient energy to excite it to action, and because the inhibitory fibres of the vagus going to the heart have been stimulated by being divided at this point (*Heidenhain*). [That stimulation of the inhibitory fibres of the vagus is not the cause of the standstill, is proved by the fact that the standstill occurs even after the administration of atropine, which paralyzes the cardiac inhibitory mechanism.] The passive heart, however, may be made to contract by mechanically stimulating Bidder's ganglion, *e. g.*, by a slight prick with a needle in the auriculo-ventricular groove, or by the action of a constant current of moderate strength (*Eckhard*), the ventricular pulsation at the same time preceding the auricular (*v. Bezold, Bernstein*). If the auriculo-ventricular groove be divided, the ventricle pulsates again, because Bidder's ganglion has been stimulated by the act of dividing it; while, at the same time, the ventricle is withdrawn from the inhibitory influence of the vagus produced by the first division at the sinus venosus. If the line of separation is so made that Bidder's ganglion remains attached to the auricles, these pulsate, and the ventricle rests; if it be divided into halves, the auricles and ventricles pulsate, each half being excited by the portion of the ganglion in relation with it. (*b*) According to another view, both Remak's (*a*) and Bidder's ganglia (*b*) are motor centres, but in the auricles there is in addition an *inhibitory ganglionic system* (*c*) (*Bezold, Traube*). Under normal circumstances $a + b$ is stronger than c, while c is stronger than a or b separately. If the sinus venosus be separated, it beats in virtue of a; on the other hand, the heart rests because c is stronger than b. If the section be made at the level of the auriculo-ventricular groove, the auricles stand still, owing to c, while the ventricle beats, owing to b.

(2) If the ventricle of a frog's heart be separated from the rest of the heart by means of a **ligature**, or by an **incision** carried through it at the level of the

auriculo-ventricular groove, the sinus and atria pulsate undisturbed as before (*Descartes*, 1644), but the ventricle stands still in diastole. A single local stimulus applied to the ventricle is responded to by a *single* contraction. If the incision be so made that the lower margin of the auricular septum remains attached to the ventricle, the latter pulsates. Even the ventricles of a rabbit's heart, when separated with a part of the auricles in connection with them, pulsate (*Tigerstedt*).

[**Gaskell's Clamp.**—Gaskell uses a clamp, regulated by a millimetre screw, to compress the heart, and thus to obstruct the passage of impulses from one part of the heart to the other, or to "block" the way, the pulsations of the auricles and ventricles being separately registered. By compressing the heart at the auriculo-ventricular groove, the ratio of auricular and ventricular beats alters, and instead of being 1 : 1, there may be 2, 3, or more auricular beats for each beat of the ventricle, expressed thus: $\frac{A}{V}, \frac{II}{I}, \frac{III}{I}, \frac{IV}{I}$. After the heart is fixed by the clamp, levers are placed horizontally above and below the heart. These levers are fixed to part of the auricles and to the apex by means of threads. Each part of the heart attached to a lever, as it contracts, pulls upon its own lever, so that the extent and duration of each contraction may be registered. This method is applicable for studying the effect of the vagus and other nerves upon the heart.]

(3) **Section.**—A. Fick showed that the process of excitement in the contractile tissue of the frog's heart is propagated in all directions (1874), so that to a certain extent the whole frog's heart behaves like *one* continuous muscular fibre; thus one transverse cut into the ventricle does not prevent contraction from taking place in the separated parts. Engelmann's experiments also show that if the ventricle of a frog's heart be cut up into two or more strips in a zig-zag way, so that the individual parts still remain connected with each other by muscular tissue, the strips still beat in a regularly progressive rhythmical manner, provided one strip is caused to contract. The rapidity of the transmission is about 10 to 15 mm. per sec. Hence, it appears that the conducting paths for the impulse causing the contraction are not nervous, but must be the contractile mass itself. It has not been proved that nerve fibres proceed from the ganglia to all the muscles.

[According to Marchand's experiments, it takes a very long time for the excitement to pass from the auricles to the ventricle—a much longer time, in fact, than it would require to conduct the excitement through muscle—so that it is probable that the propagation of the impulse from the auricles to the ventricle is conducted by nervous channels to the auriculo-ventricular nervous apparatus. In fact, in the mammalian heart the muscular fibres of the auricles are quite distinct from those of the ventricles.]

(4) When the apex of a frog's heart is ligatured off from the rest of the heart, it no longer pulsates (*Heidenhain, Goltz*), but such an apex, if stimulated directly, *e. g.*, by a prick of a pin, responds with a single contraction. If the "heart apex" be filled with normal saline solution under pressure, which acts as a stimulus, the heart begins to pulsate, and the same is the case with a solution of delphinin or quinine. If a cannula be tied into the heart over the auriculo-ventricular groove, the ventricle does not beat, but if the ventricle be filled through the cannula with blood containing oxygen, under a constant and sufficient pressure, it also pulsates (*Ludwig and Merunowicz*).

(5) Luciani found that a heart ligatured above the auriculo-ventricular groove, when filled with pure serum, produced *groups of pulsations* with a long diastolic pause between every two groups (Fig. 59). The successive beats in each group assume a "staircase" character (p. 126). These periodic groups undergo many changes; they occur when the heart is filled with pure serum free from blood corpuscles, and they disappear and give place to regular pulsations when defibrinated blood or serum containing hæmoglobin or normal saline solution is used (*Rossbach*). They also occur when the blood within the heart has become dark-colored, *i, e.*, when it has been deprived of certain of its constituents, and if a trace of *veratrin* be added to bright red blood they occur.]

(6) An apex preparation, when stimulated with even a weak induction shock, always gives its maximal contraction, and when a tetanizing current is applied, tetanus does not occur (*Kronecker and Stirling*). When the opening and closing shocks of a sufficiently strong constant current are applied to the heart apex, it contracts with each closing or opening shock. [When a *constant* current is applied to the lower two-thirds of the ventricle (heart apex), under certain conditions the apex contracts *rhythmically*. This is an important fact in connection with any theory of the cardiac beat.]

FIG. 59.



Four groups of pulsations with intervening pauses, with their "staircase" character. The points on the abscissa were marked every 10 seconds.

(7) If the bulbus aortæ (frog) be ligatured, it still pulsates, provided the internal pressure be moderate. Should it cease to beat, a single stimulus makes it respond by a series of contractions. Increase of temperature to 35° C., and raising the pressure within it, increase the number of pulsations (*Engelmann*).

Action of Fluids.—Haller was of opinion that the venous blood was the natural stimulus which caused the heart to contract. That this is not so, is proved at once by the fact that the heart beats rhythmically when it contains no blood. Blood and other fluids which are supplied to an excised heart are not the cause of its rhythmical movements, but only the conditions on which these movements depend.

[**Methods.**—The study of the action of fluids upon the excised frog's heart has been rendered possible by the invention of Ludwig's "**frog manometer.**" The apparatus (Fig. 60) consists of (1) a double-way cannula, *c*, which is tied into the heart, *h*; (2) a manometer, *m*, connected with *c*, and registering the movements of its mercury on a revolving cylinder, *cyl*; (3) two Mariotte's flasks, *a* and *b*, which are connected with the other limb of the cannula. Either *a* or *b* can be placed in communication with the interior of the heart by means of the stop-cock, *s*. The fluid in one graduated tube may be poisoned, and the other not; *d* is a glass vessel for fluid, in which the heart pulsates, *e'* and *e* are electrodes, *e* is inserted into the fluid in *d*, *e'* is attached to the German silver cannula which is shown in Fig. 61.]

FIG. 60.



Scheme of a frog manometer. *a*, *b*, Mariotte's flasks for the nutrient fluids; *s*, stop-cock; *c*, cannula; *m*, manometer; *h*, heart; *d*, glass cup for *h*; *e'*, *e*, electrodes; *cyl*, revolving cylinder.

[In the **tonometer** of Roy (Fig. 62) the ventricle, *h*, or the whole heart, is placed in an air-tight chamber, *o*, filled with oil. As before, a "perfusion" cannula is tied into the heart. A piston, *p*, works up and down in a cylinder, and is adjusted by means of a thin flexible animal membrane, such as is used by perfumers. Attached to the piston by means of a thread is a writing lever, *l*, which records the variations of pressure within the chamber, *o*. When the ventricle contracts, it becomes smaller, diminishes the pressure within *o*, and hence the piston and lever rise; conversely, when the heart dilates, the lever and piston descend. Variations in the volume of the ventricle may be registered, without in any way interfering with the flow of fluids through it.]

[Two preparations of the frog's heart have been used—(1) The "**heart,**" in which case the cannula is introduced into the heart through the sinus venosus, and a ligature is tied over it *around the auricle*, *i. e.*, *above* the auriculo-ventricular groove. Thus the auriculo-ventricular ganglia and other nervous structures remain in the preparation. This was the heart

preparation employed by Luciani and Rossbach. (2) In the "**heart apex,**" or **apex** preparation, the cannula is introduced as before, but the ligature is tied on it over the ventricle, several millimetres *below* the auriculo-ventricular groove, so that this preparation contains none of the auriculo-ventricular ganglia, and, according to the usual statement, this part of the heart is devoid of nerve ganglia. This is the preparation which was used by Bowditch, Kronecker and Stirling, Merunowicz, and others. The first effect of the application of the ligature in both cases is, that both preparations cease to beat, but the "heart" usually resumes its rhythmical contractions within several minutes, while the "heart apex" does not contract spontaneously until after a much longer time (10 to 90 mins.).]

[If the "**heart apex**" be filled with a 0.6 per cent. solution of common salt, the contractions are at first of greater extent, but they afterward cease, and the preparation passes into a condition of "apparent death," lasting 30–90 mins.; while, if the action of the fluid be prolonged, the heart may not contract at all, even when it is stimulated electrically or mechanically. It may be made, however, to pulsate again, if it be supplied with saline solution containing blood (1 to 10 per cent.). If the ventricle be nipped with wire forceps at the junction of the upper with its middle third, so as to separate the lower two-thirds of the ventricle, physiologically but not anatomically, from the rest of the heart, then the apex will cease to contract, although it is still supplied with the frog's own blood (*Bernstein, Bowditch*). The physiologically isolated apex may be made to beat by clamping the aortic branches so as to prevent blood passing out of the heart, and thus raising the intra-cardiac

FIG. 61.

Perfusion cannula for a frog's heart. *c*, for fixing an electrode; *d*, the heart is tied over the flanges, preventing it from slipping out; *e*, section of *d*.

FIG. 62.



Roy's heart tonometer. *h*, heart; *o*, air-tight chamber; *p*, piston; *l*, writing lever; *e*, outflow tube.

pressure. The rate of the beat of the apex is independent of and slower than that of the rest of the heart. This experiment proves that the amount of **pressure** within the apex cavity is an important factor in the causation of the spontaneous beats of the apex. If blood serum, to which a trace of delphinin is added, be transfused or "*perfused*" through the heart, it begins to beat within a minute, continues to beat for several seconds, and then stands still in diastole (*Bowditch*). Quinine and a mixture of atropine and muscarin have a similar action. These experiments show that, *provided no nervous apparatus exists within the heart apex*, the cause of the varying contraction is to be sought for in the musculature of the heart, and that the stimulus necessary for the systole of the heart's apex may arise within itself. If there is no nervous apparatus of any kind present, then we must assume that the heart muscle may execute rhythmical movements independently of the presence of any nervous mechanism, although it is usually assumed that the ganglia excite the heart muscle to pulsate rhythmically. It is by no means *definitely proved* that the heart apex is devoid of all nervous structures, which may act as originators of these rhythmical impulses.]

[**Action of Drugs.**—If the heart apex contains no nervous structures, it must form a good object for the study of the action of drugs on the cardiac muscle. Some of these have been mentioned already. Ringer finds that a calcium salt makes the contractions higher and longer. *Dilute acids* added to saline solution, *e.g.*, lactic, cause complete relaxation of the cardiac musculature, while *dilute alkalies* produce an opposite effect or tonic contraction, even though the apex be not pulsating. The action of a dilute acid may be set aside by a dilute alkali, and *vice versâ*. Digitalin, antiarin,

barium, and veratria act like alkalies, while saponin, muscarin, and pilocarpin have the effect of acids (§ 65). An isolated frog's heart, fatigued after being supplied with a solution of blood, is caused to beat more vigorously by a solution of kreatinin, or extract of meat (*Mays*).]

[The "**heart**" preparation in many respects behaves like the foregoing, *i.e.*, it is exhausted after a time by the continued application of normal saline solution (0.6 per cent. NaCl), while its activity may be restored by supplying it with albuminous and other fluids (p. 120).]

II. Direct Stimulation of the Heart.—All direct cardiac stimuli act more energetically on the inner than on the outer surface of the heart. If strong stimuli are applied for too long a time, the ventricle is the part first paralyzed.

(*a*) **Thermal Stimuli.**—[**Heat** affects the *number* or *frequency* and the *amplitude* of the pulsations, as well as the *duration* of the systole and diastole and the *excitability* of the heart.] Descartes (1644) observed that heat increases the number of pulsations of an eel's heart. As the temperature increases, the number of beats is at first considerably increased, but afterward the beats again become fewer, and if the temperature is raised above a certain limit the heart stands still, the myosin of which its fibres consist is coagulated, and "**heat rigor**" occurs. Even before this stage is reached, however, the heart may stand still, the muscular fibres appearing to remain contracted. The ventricles usually cease to beat before the auricles (*Schelske*). The *size* and *extent* of the contractions increase up to about 20° C., but above this point they diminish (Fig. 63). The *time* occupied by any single contraction at 20° C. is only about $\frac{1}{10}$ of the time occupied by a contraction occurring at 5° C. A heart which has been warmed is capable of reacting pretty rapidly to intermittent stimuli, while a heart at a low temperature reacts only to stimuli occurring at a considerable interval (*Gaule*).

FIG. 63.



A, contractions of a frog's heart at 19° C.; B, at 34° C.; C, at 3° C.

Cold.—When the temperature of the blood is diminished, the heart beats more slowly. A frog's heart, placed between two watch glasses and laid on ice, beats very much more slowly. The pulsations of a frog's heart stop when the heart is exposed to a temperature of 4° C. to 0°. If a frog's heart be taken out of warm water, and suddenly placed upon ice, it beats more rapidly, and conversely, if it be taken from ice and placed over warm water, it beats more slowly at first and more rapidly afterward (*Aristow*).

[**Methods.**—The effect of heat on a heart may be studied by the aid of the frog manometer, the fluid in which the heart is placed being raised to any temperature required. For demonstration purposes, the heart of a pithed frog is excised and placed on a glass slide under a light lever, such as a straw. The slide is warmed by means of a spirit lamp. In this way the frequency and amplitude of the contractions are readily made visible at a distance.]

(*b*) **Mechanical Stimuli.**—Pressure applied to the heart from without accelerates its action. In the case of Frau Serafin, v. Ziemssen found that slight pressure on the auriculo-ventricular groove caused a second short contraction of both ventricles after the heart beat. Strong pressure causes a very irregular action of the cardiac muscle. This may readily be produced by compressing the freshly-excised heart of a dog between the fingers. The **intra-cardiac pressure** also affects the heart beat (p. 124). If the pressure within the heart be increased, the heart beats are gradually increased, if it be diminished the number of beats diminishes (*Ludwig and Thiry*). If the intra-cardiac pressure be very greatly increased, the heart's action becomes very irregular and slower. A heart which has ceased to beat may, under certain circumstances, be caused to execute a *single* contraction if it be stimulated mechanically.

(*c*) **Electrical Stimuli.**—A **constant** electrical current of moderate strength increases the number of heart beats. V. Ziemssen found, in the case of Frau Serafin (§ 47, 3), that the number

of beats was doubled when a constant uninterrupted strong current was passed through the ventricles. If the constant current be very strong, or if tetanizing induction currents be used, the cardiac muscle assumes a condition resembling, but not identical with, tetanus (*Ludwig and Hoffa*), and, of course, this results in a fall of the blood pressure. If the auriculo-ventricular groove be compressed so as to cause the ventricle of a frog's heart to cease to beat, on placing one electrode of a constant current on the ventricular wall and the other electrode on an indifferent part of the body, we obtain, on making the current, a systolic contraction of the ventricle only when the cathode touches the ventricle; and conversely on breaking, only when the anode is on the heart (*Biedermann*).

When a **single induction shock** is applied to the ventricle of a frog's heart during systole, it has no apparent effect; but if it is applied during diastole, the succeeding contraction takes place sooner. The auricles and also the apex behave in a similar manner. While they are contracted, an induction shock has no effect; if, however, the stimulus is applied during diastole, it causes a contraction, which is followed by systole of the ventricle. Even when strong tetanizing induction shocks are applied to the heart, they do not produce *tetanus* of the entire cardiac musculature, or as it is said, "the heart knows no tetanus" (*Kronecker and Stirling*). Small, white, local, wheal-like elevations—such as occur when the intestinal musculature is stimulated—appear between the electrodes. They may last several minutes. A frog's heart, which yields weak and irregular contractions, may be made to execute regular rhythmical contractions synchronous with the stimuli, if electrical stimuli are used (*Bowditch*).

[Break induction shocks, if of sufficient strength, cause the heart to contract, while weak stimuli have no effect; on the other hand, moderate stimuli, when they do cause the heart to contract, always cause a maximal contraction, so that a minimal stimulus acts at the same time like a maximal stimulus. The heart either contracts or it does not contract, and when it contracts, the result is always a "maximal" contraction (*Kronecker and Stirling*). Bowditch found that the excitability of the heart was increased by its own movements, so that after a heart had once contracted, the strength of the stimulus required to excite the next contraction may be greatly diminished, and yet the stimulus be effectual. Usually the amplitude of the first beat so produced is not so great as the second beat, and the second is less than the third, so that a "**staircase**" ("Treppe") of beats of successively greater extent was produced (Fig. 59). Under certain circumstances, however, a skeletal muscle gives contractions of a "staircase" character. This staircase arrangement occurs even when the strength of the stimulus is kept constant, so that the production of one contraction facilitates the occurrence of the succeeding one. A staircase arrangement of the pulsations is also seen in Luciani's groups (p. 122). The question, whether a stimulus will cause a contraction, depends upon what particular phase the heart is in when the shock is applied. Even comparatively weak stimuli will cause a heart to contract, provided the stimuli are applied at the proper moment and in the proper tempo, *i.e.*, to say, they become what are called "infallible." If stimuli are applied to the heart, at intervals which are longer than the time the heart takes to execute its contraction, they are effectual or "adequate," but if they are applied before the period of pulsation comes to an end, then they are ineffectual (*Kronecker*). It is quite clear, therefore, that the relation of the strength of the stimulus to the extent of the contraction of the cardiac muscle, is quite different from what occurs in a muscle of the skeleton, where within certain limits the amplitude of the contraction bears a relation to the stimulus, while in the heart the contraction is always *maximal.*]

Human Heart.—V. Ziemssen found that he could not alter the heart beats of the human heart (*Frau Serafin*, § 47, 3), even with strong induction currents. The ventricular diastole seemed to be less complete, and there were irregularities in its contraction. By opening and closing, or by reversing a strong *constant* current applied to the heart, the number of beats was increased, and the increase corresponded with the number of electrical stimuli; thus, when the electrical stimuli were 120, 140, 180, the number of heart beats was the same, the pulse beforehand being 80. The normal pulse rate of 80 was reduced to 60 and 50 when the number of shocks was reduced in the same ratio. [In Frau Serafin's case the electrodes were applied to the heart, separated from it merely by the pericardium. Ziemssen found that the Faradic current did not modify the heart's action when the thorax was intact, but that the constant current did, if of sufficient strength. Herbst and Dixon Mann obtained negative results with both kinds of electricity in the normal thorax.]

(*d*) **Chemical Stimuli.**—Many chemical substances, when applied in a dilute solution to the inner surface of the heart, increase the heart beats, while if they are concentrated, or allowed to act too long, they diminish the heart beats, and paralyze it. Bile and bile salts diminish the heart beats (also when they are absorbed into the blood, as in jaundice); in very dilute solutions both increase the heart beats. A similar result is produced by acetic, tartaric, citric, and phosphoric acids. Chloroform and ether, applied to the inner surface, rapidly diminish the heart beats, and then paralyze it; but very small quantities of ether (1 per cent.) accelerate the heart beat of the frog (*Kronecker and M'Gregor-Robertson*), while a solution of 1½ to 2 per cent, passed through the heart arrests it temporarily or completely. Dilute solutions of opium, strychnia, or alcohol applied to the endocardium, increase the heart beats; if concentrated they rapidly arrest its action. Chloral hydrate paralyzes the heart.

Action of Gases.—When blood containing different gases was passed through a frog's heart, Klug found that blood containing sulphurous acid rapidly and completely killed the heart; chlorine stimulated the heart at first, and ultimately killed it; and laughing gas rapidly killed it also. Blood containing sulphuretted hydrogen paralyzed the heart without stimulating it. Carbonic oxide also paralyzed it, but if fresh blood was transfused the heart recovered. [Blood containing O excites the heart (*Castell*), while the presence of much CO_2 paralyzes it, and the presence of CO_2 is more injurious than the want of O. Blood or serum completely saturated with CO_2 exhausts the heart (*Saltet and Kronecker*), but it recovers itself when the CO_2 is removed. H and N have no effect.]

Cardiac Poisons are those substances whose action is characterized by special effects upon the movements of the heart. Among these are **neutral potash salts**, which cause the heart to stand still in diastole. An excised frog's heart ceases to beat after one-half to one minute when it is placed in a 2 per cent. solution of potassic chloride.] Even a very dilute solution of yellow prussiate of potash injected into the heart of a frog causes the ventricle to stand still in systole. **Antiar** (Java arrow poison) causes the ventricle to stand still in systole and the auricles in diastole. Some heart poisons, in small doses, diminish the heart's action, and in large doses not unfrequently accelerate it, *e. g.*, digitalis, morphia, nicotin. Others, when given in small doses, accelerate its action, and in large doses slow it—veratria, aconitin, camphor.

Special Actions of Cardiac Poisons.—The complicated actions of various poisons upon the heart have led observers to suppose that there are various intra-cardiac mechanisms on which these substances may act. Besides the *muscular fibres* of the heart and its *automatic ganglia*, some toxicologists assume that there are *inhibitory ganglia* into which the inhibitory fibres of the vagus pass, and *accelerator ganglia*, which are connected with the accelerating nerve fibres of the heart. *Both the inhibitory and accelerator ganglia are connected with the automatic ganglia* by conducting channels.

Muscarin and all other trimethylammonium bases stimulate permanently the inhibitory ganglia, so that the heart stands still (*Schmiedeberg and Koppe*). [According to Gaskell, however, when the action of the sinus is arrested by muscarin, there is no deflection of the galvanometer similar to that produced by the excitation of the vagus. He infers that muscarin does not cause arrest of the beat by acting as an excitant of inhibitory mechanisms, but as a depressant to motor activity.] As atropin and daturin paralyze these ganglia, the standstill of the heart brought about by muscarin may be set aside by atropin. [If a frog's heart be excised and placed in a watch glass, and a few drops of a very dilute solution of muscarin be placed on it with a pipette, it ceases to beat within a few minutes, and will not beat again. If, however, the muscarin be removed, and a solution of atropine applied to the heart, it will resume its contractions after a short time.] Physostigmin or Calabar bean excites the energy of the cardiac muscle to such an extent, that stimulation of the vagus no longer causes the heart to stand still. Iodine-aldehyd, chloroform, and chloral hydrate paralyze the automatic ganglia. The heart stands still, and it cannot be made to contract again by atropine. The cardiac muscle itself remains excitable after the action of muscarin and iodine-aldehyd, so that if it be stimulated it contracts. [According to Gaskell, antiarin and digitalin solutions produce an alteration in the condition of the muscular tissue of the apex of the heart of the same nature as that produced by the action of a very dilute alkali solution, while the action of a blood solution containing muscarin closely resembles that of a dilute acid solution (p. 138, § 65).]

[**Nature of a Cardiac Contraction.**—The question as to whether this is a simple contraction or a compound tetanic contraction has been much discussed. So much is certain, that the systolic contraction of the heart is of very much longer duration (8 to 10 times) than the contraction of a skeletal muscle produced by stimulation of its motor nerve. When the sciatic nerve of a nerve-muscle preparation is adjusted upon a contracting heart, a *simple* secondary twitch of the limb, and not a tetanic spasm, is produced when the heart (auricle or ventricle) contracts. This of itself is not sufficient proof that the systole is a simple spasm, for tetanus of a muscle does not in all cases give rise to secondary tetanus in the leg of a rheoscopic limb. Thus, a simple "initial" contraction occurs when the nerve is applied to a muscle tetanized by the action of strychnia, and the contracted diaphragm gives a similar result. The question whether the heart can be tetanized has been answered in the negative, and as yet it has not been shown that the heart can be tetanized in the same way that a skeletal muscle is tetanized.]

[MacWilliam finds, when the quadriceps extensor cruris contracts to cause the knee jerk, that a sound similar to the first sound of the heart is heard. As the former is regarded as a simple contraction, it is argued that a simple contraction can produce a muscle sound. Frédéricq regards the ventricular systole not as a simple contraction, but as composed of three or more fused contractions corresponding to tetanus. This he concludes from a study of cardiograms as well as from the electro-motive phenomena of the heart.]

The **peripheral** or **extra-cardiac** nerves (§§ 369 and 370).

59. CARDIO-PNEUMATIC MOVEMENT.—As the heart within the thorax occupies a smaller space during the systole than during the diastole, it follows that, when the glottis is open, air must be drawn into the chest when the heart contracts; whenever the heart relaxes, *i. e.*, during diastole, air must be expelled through the open glottis. But we must also take into account the degree to which the larger intra-thoracic vessels are filled with blood. These movements of the air within the lungs, although slight, seem to be of importance in hibernating animals. In animals in this condition, the agitation of the gases in the lungs favors the exchange of CO_2 and O in the lungs, and this slow current of air is sufficient to aerate the blood passing through the lungs. [Ceradini called the diminution of the volume of the entire heart which occurs during systole **meiocardia,** and the subsequent increase of volume, when the heart is distended to its maximum, **auxocardia.**]

Method.—*A manometric flame* may be used. Insert one limb of a Y-tube into the opened trachea of an animal, while the other limb passes to a small gas jet, and connect the other tube with the gas supply. The movements of the heart affect the column of gas, and thus affect the flame. It may also be done in man by inserting the tube into one nostril, while the other nostril and the mouth are closed. [A simpler and less irritating plan is to fill a wide curved glass tube with tobacco smoke, and insert one end of the tube into one nostril while the other nostril and the mouth are closed. If the glottis be kept open, and respiration be stopped, then the movements of the column of smoke within the tube are obvious. Or a manometer containing a drop of a colored fluid may be used under the same conditions.]

FIG. 64.



Landois' cardio-pneumograph, and the curves obtained therewith. A and B, from man, 1 and 2 correspond to the periods of the first and second heart sounds; C, from dog; D, method of using the apparatus.

The cardiac pneumograph (Fig. 64) consists of a tube (D), about 1 inch in diameter and 6 to 8 inches in length; the tube is bent at a right angle, and communicates with a small metal capsule about the size of a saucer (T), over which a membrane composed of collodion and castor oil is loosely stretched. To this membrane is attached a glass rod (H) used as a writing style, which records its movements on a glass plate (S) moved by clock work. A small valve (K) is placed on the side of the tube (D), which enables the experimenter to breathe when necessary. The tube (D) is held in an air-tight manner between the lips, the nostrils being closed, the glottis open, and respiration stopped. In the curves (Fig. 64, A, B) we observe that—

(1) At the moment of the first sound (1) the respiratory gases undergo a sharp *expiratory* movement, because at the moment of the first part of the ventricular systole the blood of the ventricle has not left the thorax, while venous blood is streaming into the right auricle through the venæ cavæ, and because the dilating branches of the pulmonary artery compress the accompanying bronchi. The blood of the right ventricle has not yet left the thorax, it passes merely into the pulmonary circuit. The expiratory movement is diminished somewhat (*a*) by the muscular mass of the ven-

tricle occupying slightly less bulk during the contraction, and (β) owing to the thoracic cavity being slightly increased by the fifth intercostal space being pushed forward by the cardiac impulse.

(2) Immediately after (1) there follows a strong inspiratory current of the respiratory gases. As soon as the blood from the root of the aorta reaches that part of the aorta lying outside the thorax, more blood leaves the chest than passes into it simultaneously through the venæ cavæ.

(3) After the second sound (at 2), indicated sometimes by a slight depression in the apex of the curve, the arterial blood accumulates, and hence there is another expiratory movement in the curve.

(4) The peripheral wave movements of the blood from the thorax cause another inspiratory movement of the gases.

(5) More blood flows into the chest through the veins, and the next heart beat occurs.

60. INFLUENCE OF THE RESPIRATORY PRESSURE ON THE HEART.—The variation in pressure to which all the intra-thoracic organs are subjected, owing to the increase and decrease in the size of the chest caused by the respiratory movements, exerts an influence on the movements of the heart. Examine first the relations in different *passive conditions of the thorax, when the glottis is open.*

The diastolic dilatation of the cavities of the heart, besides the pressure of the venous blood and the elastic stretching of the relaxed muscle wall, is fundamentally due to the **elastic traction of the lungs.** This is stronger the more the lungs are distended (inspiration), and is less active the more the lungs are contracted (expiration). Hence it follows—

(1) When the greatest possible **expiratory effort** is made (of course, with the glottis open, only a small amount of blood flows into the heart; the heart in diastole is small and contains a small amount of blood. Hence the systole must also be small, thus causing a small pulse beat.

(2) On taking the greatest possible **inspiration** (with the glottis open), and therefore causing the greatest stretching of the elastic tissue of the lungs, the elastic traction of the lungs is, of course, greatest = 30 mm. Hg (*Donders*), and may interfere with the contraction of the thin-walled atria and appendices, in consequence of which these cavities do not completely empty themselves into the ventricles. The heart is in a state of great diastolic distention, and filled with blood; nevertheless, in consequence of the limited action of the auricles, only small pulse beats are observed. In several individuals Donders found the pulse to be smaller and slower; afterward it became larger and faster.

(3) When the chest is in a position of **moderate rest,** whereby the elastic traction is moderate = 7.5 mm. Hg, we have the condition most favorable to the action of the heart—sufficient diastolic dilatation of the cavities of the heart, as well as unhindered emptying of them during systole.

Voluntary increase or diminution of the intra-thoracic pressure affects the action of the heart.

(1) **Valsalva's Experiment** (1740).—If the thorax is fixed in the position of deepest inspiration, and the glottis be then closed, and if a powerful expiratory effort be made by bringing into action all the expiratory muscles, so as to contract the chest, the cavities of the heart are so compressed that the circulation of the blood is temporarily interrupted. In this expiratory phase the elastic traction is very limited, and the air in the lungs being under a high pressure also acts upon the heart and the intra-thoracic great vessels. No blood can pass into the thorax from without; hence the visible veins swell up and become congested, the blood in the lungs is rapidly forced into the left ventricle by the compressed air in the lungs, and the blood soon passes out of the chest, so that the heart and lungs contain little blood, thus leading to a greater supply of blood in the systemic than in the pulmonary circulation and the heart. The heart sounds disappear, and the pulse is absent (*E. H. Weber, Donders*).

(2) **J. Müller's Experiment** (1838).—Conversely, if after the deepest possible expiration the glottis be closed, and the chest be now dilated with a great inspiratory effort, the heart is powerfully dilated, the elastic traction of the lungs,

and the very attenuated air in these organs, act so as to dilate the cavities of the heart. More blood flows into the right heart, and, in proportion as the right auricle and ventricle can overcome the traction outward, the blood vessels of the lungs become filled with blood, and thus partly occupy the lung space. Much less blood is driven out of the left heart, so that the pulse may disappear. Hence the heart is distended with blood and the lungs are congested, while the aortic system contains a small amount of blood, *i. e.*, the systemic circulation is comparatively empty, while the heart and the pulmonary vessels are engorged with blood.

In normal respiration, the air in the lungs during inspiration is under slight pressure, while during expiration the pressure is higher, so that these conditions

FIG. 65.



Apparatus for demonstrating the action of inspiration, II, and expiration, I, on the heart and blood stream. P, *p*, lungs; H, *h*, heart; L, *l*, closed glottis; M, *m*, manometers; E, *e*, ingoing blood stream, vein; A, *a*, outgoing blood stream, artery; D, diaphragm during expiration; *d*, during inspiration.

favor the circulation; inspiration favors the occurrence of diastole, the supply of blood (and lymph) through the venæ cavæ. In operations where the axillary or jugular vein is cut, air may be sucked into the circulation during inspiration, and cause death. Expiration favors the flow of blood in the aorta and its branches, and aids the systolic emptying of the heart.

The elastic traction of the lungs aids the **lesser circulation** through the lungs; the blood of the pulmonary capillaries is exposed to the pressure of the air in the lungs, while the blood in the pulmonary veins is exposed to a less pressure, as the elastic traction of the lungs, by dilating the left auricle, favors the outflow from the capillaries into the left auricle. The elastic traction of the lungs acts slightly as a disturbing agent on the right ventricle, and, therefore, on the movement of

blood through the pulmonary artery, owing to the overpowering force of the blood stream through the pulmonary artery, as against the elastic traction of the lungs (*Donders*).

The above apparatus (Fig. 65) shows the effect of the inspiratory and expiratory movements on the dilatation of the heart, and on the blood stream in the large blood vessels. The large glass vessel represents the thorax; the elastic membrane, D, the diaphragm; P, *p*, the lungs; L, the trachea supplied with a stop-cock to represent the glottis; H, the heart; E, the venæ cavæ; A, the aorta. If the glottis be *closed*, and the expiratory phase imitated by pushing up D as in I, the air in P, P and the heart H are compressed, the venous valve closes, the arterial is opened, and the fluid is driven out through A. The manometer, M, indicates the intra-thoracic pressure. If the glottis be closed, and the inspiratory phase imitated, as in II, *p*, *p* and *h* are dilated, the venous valve opens, the arterial valve closes; hence, venous blood flows from *e* into the heart, Thus, inspiration always favors the venous stream, and hinders the arterial; while expiration hinders the venous, and favors the arterial stream. If the glottis L and *l* be open, the air in P, P, *p*, *p* will be changed during the respiratory movements D and *d*, so that the action on the heart and blood vessels will be diminished, but it will still persist, although to a much less extent.

THE CIRCULATION OF THE BLOOD.

61. FLOW OF FLUIDS THROUGH TUBES.—Toricelli's Theorem states that the velocity of efflux (v) of a fluid—through an opening at the bottom of a cylindrical vessel—is exactly the same as the velocity which a body falling freely would acquire, were it to fall from the surface of the fluid to the base of the orifice of the outflow. If h be the height of the propelling force, the velocity of efflux is given by the formula—

$$v = \sqrt{2gh} \text{ (where } g = 9.8 \text{ metres).}$$

The rapidity of outflow increases with increase in the height of the propelling force, h. The former occurs in the ratio 1, 2, 3, when h increases in the ratio 1, 4, 9, *i.e.*, the velocity of efflux is as the square root of the height of the propelling force. Hence, it follows that the velocity of efflux depends upon the height of the liquid above the orifice of outflow, and not upon the nature of the fluid.

Resistance.—Toricelli's theorem, however, is only valid when all resistance to the outflow is absent; but in every physical experiment such resistance exists. Hence, the propelling force, h, has not only to cause the *efflux* of the fluid, but has also to *overcome resistance.* These two forces may be expressed by the heights of two columns of water placed over each other, viz., by the height of the column of water causing the outflow, F, and the height of the column, D, which overcomes the resistance opposed to the outflow of the fluid. So that

$$h = F + D.$$

62. VELOCITY OF THE CURRENT. RESISTANCE.—In the case of a fluid flowing through a tube, which it fills completely, we have to consider the propelling force, h, causing the fluid to flow through the various sections of the tube. The amount of the propelling force depends upon two factors:—

(1) On the *velocity of the current, v;* (2) on the pressure (amount of *resistance*) to which the fluid is subjected at the various parts of the tube, D.

(1) The **velocity** of the current, v, is estimated—(a) from the lumen, l, of the tube; and (b) from the quantity of fluid, q, which flows through the tube in the unit of time. So that $v = q : l$. Both values, q as well as l, can be accurately measured. (The circumference of a circular tube, whose diameter $= d$ is $3.14.d$. The sectional area (lumen of the tube) is $l = \frac{3.14}{4}.d^2$). Having in this way determined v, from it we may calculate the height of the column of fluid, F, which will give this velocity, *i.e.*, the height from which a body must fall in vacuo, in order to attain the velocity v. In this case $F = \frac{v^2}{4g}$ (where g = the distance traversed by a falling body in 1 sec. = 4.9 metre).

(2) The pressure, D (amount of resistance), is measured directly by placing manometers at different parts of the tube (Fig. 67).

The **propelling force** at any part of the tube is $h = F + D$; or, $h = \frac{v^2}{4g} + D$ (*Donders*). This is proved experimentally by taking a tall cylindrical vessel, A, of sufficient size, which is kept filled with water at a constant level, h. The rigid outflow tube, ab, has in connection with it a number of tubes placed vertically, 1, 2, 3, constituting a **piezometer.** At the end of the tube, b, there is an opening with a short tube fixed in it, from which the water issues to a constant height, provided the level of h is kept constant. The height to which it rises depends on the height of the column of fluid causing the velocity, F. As the pressure in the manometric tubes, D^1, D^2, D^3, can be read off directly, the propelling force of the water at the sections of the tubes, I, II, III, is—

$$h = F + D^1;\ F + D^2;\ F + D^3.$$

At the end of the tube, b, where $D^4 = O$, $h = F + O$, *i.e.*, $h = F$. In the cylinder itself it is the constant pressure, h, which causes the movement of the fluid. It is clear that the propelling force of the water gradually diminishes as we pass from the inflow toward the outflow of the tube, b. The water in the pressure cylinder, falling from the height, h, only rises as high as F at b. This diminution of the propelling power is due to the presence of **resistances,** which oppose the current in the tube, *i.e.*, part of the energy is transformed into heat. As the propelling force at b is represented only by F, while in the vessel it is h, the difference must be due to the sum of the resistances, $D = h - F$; hence it follows that $h = F + D$.

Estimation of the Resistance.—When a fluid flows through a tube of uniform calibre, the propelling force, *h*, diminishes from point to point on account of the uniformly acting resistance, hence the sum of the resistance in the whole tube is directly proportional to its length. In a uniformly wide tube, fluid flows through each sectional area with equal velocity, hence *v* and also F are equal in all parts of the tube. The diminution which *h* (propelling force) undergoes can only occur from a diminution of pressure D, as F remains the same throughout (and $h = F + D$) Experiment with the pressure cylinder shows that the pressure toward the outflow end of the tube gradually diminishes. *In a uniformly wide tube, the height of the pressure in the manometers expresses the resistances opposed to the current of fluid which it has to overcome in its course from the point investigated to the free orifice of efflux.*

Nature of the Resistance.—The resistance opposed to the flow of a fluid depends upon the *cohesion of the particles* of the fluid among themselves. During the current, the outer layer of fluid which is next the wall of the tube, and which moistens it, is at rest. All the other layers of fluid, which may be represented as so many cylindrical layers, one inside the other, move more rapidly as we proceed toward the axis of the tube, the axial thread or stream being the most rapidly moving part of the liquid. On account of the movement of the cylindrical layers, one within the other, a part of the propelling energy must be used up. The amount of the resistance greatly depends upon the *amount of the cohesive force* which the particles of the fluid have for each other; the more firmly the particles cohere the greater will be the resistance, and *vice versâ*. Hence, the sticky blood current experiences greater resistance than water or ether.

Heat diminishes the cohesion of the particles, hence it also diminishes the resistance to the onflow. These resistances are first developed by, and result from, the movement of the particles

FIG. 66.



Cylindrical vessel filled with water. *h*, height of the column of fluid; D, height required to overcome the resistance; F, height causing the efflux.

FIG. 67.



A, cylindrical vessel filled with water. *ab*, outflow tube, along which are placed at intervals vertical tubes, 1, 2, 3, to estimate the pressure.

of the fluid, they being, as it were, torn from each other. The *more rapid the current*, therefore, *i. e.*, the larger the number of particles of fluid which are pulled asunder in the unit of time, the *greater will be the sum of the resistance.* As the layer of fluid lying next the tube, and moistening it, is at rest, the material which composes the tube exerts no influence on the resistance.

Tubes of Unequal Diameter.—When the velocity of the current is uniform, the resistance depends upon the diameter of the tube—the smaller the diameter the greater the resistance; the greater the diameter the less the resistance. The resistance in narrow tubes, however, increases more rapidly than the diameter of the tube decreases, as has been proved experimentally. In tubes of unequal calibre, at different parts of their course, the velocity of the current varies—it is slower in the wide part of the tube, and more rapid in the narrow parts. As a general rule, in tubes of unequal diameter the velocity of the current is inversely proportional to the diameter of the corresponding section of the tube; *i. e.*, if the tube be cylindrical, it is inversely proportional to the square of the diameter of the circular transverse section. In tubes of uniform diameter, the propelling force of the moving fluid diminishes *uniformly* from point to point, but in tubes of *unequal* calibre it does *not* diminish *uniformly*. As the resistance is greater in narrow tubes, of course the propelling force must diminish more rapidly in them than in wide tubes. Hence, within the wide parts of the tube the pressure is greater than the sum of the resistances still to be overcome, while in the narrow portions it is less than these.

Tortuosities and bending of the vessels add new resistance, and the fluid presses more solely on the convex side than on the concave side of the bend, and there the resistance to the flow than on the convex side.

Division of a tube into two or more branches is a source of resistance, and diminishes the propelling power. When a tube divides into two smaller tubes, of course some of the particles of the fluid are retarded, while others are accelerated on account of the unequal velocities of the different layers of the fluid. Many particles which had the greatest velocity in the axial layer come to lie more toward the side of the tube, where they move more slowly; and conversely many of those lying in the outer layers reach the centre, where they move more rapidly. Hence, some of the propelling force is used up in this process, and the pulling asunder of the particles where the tube divides acts in a similar manner. If two tubes *join* to form *one* tube, new resistance is thereby caused, which must diminish the propelling force. The sum of the mean velocities in both branches is independent of the *angle* at which the division takes place (*Jacobson*). If a branch be opened from a tube, the principal current is accelerated to a considerable extent, no matter at what angle the branch may be given off.

63. FLOW IN CAPILLARY TUBES.—Poiseuille proved experimentally that the flow in the capillaries is subject to special conditions:—

(1) The quantity of fluid which flows out of the *same* capillary tube is proportional to the pressure.

(2) The time necessary for a given quantity of fluid to flow out (with the like pressure, diameter of tube and temperature), is proportional to the length of the tubes.

(3) The product of the outflow (other things being equal) is as the fourth power of the diameter.

(4) The velocity of the current is proportional to the pressure and to the square of the diameter, and inversely proportional to the length of the tube.

(5) The resistance in the capillaries is proportional to the velocity of the current.

64. FLOW IN ELASTIC TUBES.—(1) When an uninterrupted *uniform* current flows through an elastic tube, it follows exactly the *same laws* as if the tube had *rigid walls*. If the propelling power increases or diminishes, the elastic tubes become wider or narrower, and they behave, as far as the movement of the fluid is concerned, as wider or narrower rigid tubes.

(2) **Wave Motion.**—If, however, more fluid be forced *in jerks* into an elastic tube, *i. e.*, *interruptedly*, the first part of the tube dilates suddenly, corresponding to the quantity of fluid propelled into it. The jerk communicates an *oscillatory* movement to the particles of the fluid, which is communicated to all the fluid particles from the beginning to the end of the tube; *a positive wave is thus rapidly propagated throughout the whole length of the tube.* If we imagine the elastic tube to be closed at its peripheral end, the positive wave will be reflected from the point of occlusion, and it may be propagated to and fro through the tube until it finally disappears. In such a closed tube a sudden jet of fluid produces only a *wave movement*, *i. e.*, only a vibratory movement, or an alteration in the shape of the liquid, there being no actual translation of the particles along the tube.

(3) If, however, fluid be pumped interruptedly or by jerks into an elastic tube filled with fluid, in which there is already a continuous current, the movement of the current is combined with the wave movement. We must carefully distinguish the *movement of the current of the fluid*, *i. e.*, the translation of a mass of fluid through the tube, from the *wave movement*, the oscillatory movement, or movement of change of form in the column of fluid. In the former, the particles are actually translated, while in the latter they merely vibrate. The current in elastic tubes is slower than the wave movement, which is propagated with great rapidity. This last case obtains in the arterial system. The blood in the arteries is already in a state of continual movement, directed from the aorta to the capillaries; by means of the systole of the left ventricle a quantity of fluid is suddenly pumped into the aorta, and causes a *positive wave*, the **pulse wave**, which is propagated with great rapidity to the terminations of the arteries, while the current of the blood itself moves much more slowly.

Rigid and Elastic Tubes.—If a quantity of fluid be forced into a *rigid tube* under a certain pressure, the same quantity of fluid will flow out at once at the other end of the tube, provided there be no special resistance. In an *elastic tube*, immediately after the forcing in of a quantity of fluid, at first only a small quantity flows out, and the remainder flows out only after the propelling force has ceased to act. If an equal quantity of fluid be **periodically** injected into a **rigid tube**, with each jerk an equal quantity is forced out at the other end of the tube, and the outflow lasts exactly as long as the jerk or the contraction, and the pause between two periods of outflow is exactly the same as between the two jerks or contractions. In an **elastic tube** it is different, as the outflow continues for a time after the jerk; hence, it follows that a continuous outflow current will be produced in elastic tubes, when the time between two jerks is made shorter than the duration of the outflow after the jerk has been completed. When fluid is pumped periodically into rigid tubes, it causes a sharp abrupt outflow synchronous with the inflow, and the outflow becomes continuous only when the inflow is continuous and uninterrupted. In elastic tubes, an intermittent current under the above conditions causes a continuous outflow, which is increased with the systole or contraction.

65. STRUCTURE AND PROPERTIES OF THE BLOOD VESSELS.—In the body the large vessels carry the blood to and from the various tissues and organs, while the thin-walled capillaries bring the blood into intimate relation with the tissues. Through the excessively thin walls of the capillaries the fluid part of the blood transudes, to nourish the tissues outside the capillaries.

[At the same time fluids pass from the tissues into the blood. Thus there is an exchange between the blood and the fluids of the tissues. The fluid after it passes into the tissues constitutes the *lymph*, and acts like a stream *irrigating* the tissue elements.]

I. **The arteries** are distinguished from veins by their *thicker walls*, due to the greater development of smooth muscular and elastic tissues—the middle coat (tunica media) of the arteries is specially thick, while the outer coat (t. adventitia) is relatively thin. [The absence of valves is by no means a characteristic feature.]

A **typical artery** consists of *three* coats (Fig. 68). (1) The **tunica intima**, or **inner coat**, consists of a layer of (*a*) irregular, long, fusiform, nucleated, squamous cells forming the excessively thin, transparent endothelium, immediately in contact with the blood stream. [Like other endothelial cells, these cells are held together by a cement substance, which is blackened by the action of silver nitrate.] Outside this lies a very thin, more or less fibrous, layer—*sub-epithelial layer*—in which numerous spindle or branched protoplasmic cells lie embedded within a corresponding system of plasma canals. Outside this is an *elastic lamina* (*b*), which in the *smallest arteries* is a structure-

FIG. 68.



Coats of a small artery. *a*, endothelium; *b*, internal elastic lamina; *c*, circular muscular fibres of the middle coat; *d*, the outer coat.

FIG. 69.

Capillaries. The outlines of the nucleated endothelial cells with the cement blackened by the action of silver nitrate.

less or fibrous elastic membrane—in arteries of *medium size* it is a fenestrated membrane (*Henle*), while in the *largest* arteries there may be several layers of elastic laminæ or fenestrated elastic membrane mixed with connective tissue. [In some arteries the elastic membrane is distinctly fibrous, the fibres being chiefly arranged longitudinally. It can be stripped off, when it forms a brittle elastic membrane, which has a great tendency to curl up at its margins. In a transverse section of a middle-sized artery it appears as a bright wavy line, but the curves are probably produced by the partial collapse of the vessel. It forms an important guide to the pathologist, in enabling him to determine which coat of the artery is diseased.] In middle-sized and large arteries a few non-striped muscular fibres are disposed *longitudinally* between the elastic plates or laminæ. Along with the circular muscular fibres of the middle coat, they may act so as to narrow the artery, and they may also aid in keeping the lumen of the vessel open and of uniform calibre.

(2) The **tunica media**, or **middle coat**, contains much non-striped muscle (*c*), which in the *smallest* arteries consists of transversely disposed non-striped muscular fibres lying between the endothelium and the T. adventitia, while a finely granular tissue with few elastic fibres forms the bond of union between them. As we proceed from the very smallest to the small arteries, the

number of muscular fibres becomes so great as to form a well-marked fibrous *ring of non-striped muscle*, in which there is comparatively little connective tissue. In the *large* arteries the amount of connective tissue is considerably increased, and between the layers of fine connective tissue numerous (as many as fifty) thick, elastic, fibrous or fenestrated laminæ are concentrically arranged. A few non-striped fibres lie scattered among these, and some of them are arranged transversely, while a few have an oblique or longitudinal direction.

The first part of the aorta and pulmonary artery, and the retinal arteries, are devoid of muscle. The descending aorta, common iliac, and popliteal have longitudinal fibres between the transverse ones. Longitudinal bundles lying inside the media occur in the renal, splenic, and internal spermatic arteries. Longitudinal bundles occur both on the outer and inner surfaces of the umbilical arteries, which are very muscular.

(3) The **tunica adventitia**, or **outer coat**, in the *smallest* arteries consists of a structureless membrane with a few connective-tissue corpuscles attached to it; in *somewhat larger* arteries there is a layer of fine fibrous elastic tissue mixed with bundles of fibrillar connective tissue (*a*). In arteries of *middle size*, and in the *largest* arteries, the chief mass consists of bundles of fibrillar connective tissue containing connective-tissue corpuscles. The bundles cross each other in a variety of directions, and fat cells often lie between them. Next the media there are numerous fibrous or fenestrated elastic lamellæ. In medium-sized and small arteries the elastic tissue next the media takes the form of an independent elastic membrane (Henle's external elastic membrane). Bundles of non-striped muscle, arranged longitudinally, occur in the adventitia of the arteries of the penis, and in the renal, splenic, spermatic, iliac, hypogastric, and superior mesenteric arteries.

II. **The capillaries**, while retaining their diameter, divide and reunite so as to form networks, whose shape and arrangement differ considerably in different tissues. The diameter of the capillaries varies considerably, but as a general rule it is such as to admit freely a single row of blood corpuscles. In the retina and the muscles the diameter is 5–6 μ, and in bone marrow, liver, and choroid 10–20 μ. The tubes consist of a single layer of transparent, excessively thin, nucleated, endothelial cells joined to each other by their margins. [The nuclei contain a well marked intra-nuclear plexus of fibrils, like other nuclei.] The cells are more fusiform in the smaller capillaries and more polygonal in the larger. The body of the cells presents the characters of very faintly refractive protoplasm, but it is doubtful whether the body of the cell is endowed with the property of contractility (p. 138).

FIG. 70.

Longitudinal section of a vein at the level of a valve. *a*, hyaline layer of the internal coat; *b*, elastic lamina; *c*, groups of smooth muscular fibres divided transversely; *d*, longitudinal muscular fibres in the adventitia.

If a dilute solution (¼ per cent.) of **silver nitrate** be injected into the blood vessels, the cement substance of the endothelium [and of the muscular fibres as well] is revealed by the presence of the black "**silver lines.**" The blackened cement substance shows little specks and large black slits at different points. It is not certain whether these are actual holes through which colorless corpuscles may pass out of the vessels, or are merely larger accumulations of the cement substance. [If a capillary is examined in a perfectly fresh condition (while living) and without the addition of any reagent, it is impossible to make out any line of demarcation between adjacent cells, owing to the uniform refractive index of the entire wall of the tube.]

[Arnold called these small areas in the black silver lines, when they are large, **stomata**, and when small, **stigmata**. They are most numerous after venous congestion, and after the disturbances which follow inflammation of a part. They are not always present. The existence of cement substance between the cells may also be inferred from the fact that indigo-sulphate of soda is deposited in it (*Thoma*), and particles of cinnabar and China ink are fixed in it, when these substances are injected into the blood (*Foa*).]

Fine anastomosing fibrils derived from non-medullated **nerves** terminate in small end-buds in relation with the capillary wall; ganglia in connection with the nerves of capillaries occur only in the region of the sympathetic.

The small vessels next in size to the capillaries, and continuous with them, have a completely structureless covering in addition to the endothelium.

III. **The veins** are generally distinguished from the arteries by their *lumen* being *wider* than the lumen of the corresponding arteries; their

walls are thinner on account of the smaller amount of non-striped muscle and elastic tissue (the non-striped muscle is not unfrequently arranged longitudinally in veins). They are also more *extensile* (with the same strain). The adventitia is usually the thickest coat. The occurrence of **valves** is limited to the veins of certain areas.

Structure.—(1) The **tunica intima** consists of a layer of *shorter* and broader endothelial cells, under which in the smallest veins there is a structureless elastic membrane, *sub-epithelial layer*, which is fibrous in veins somewhat larger in size, but in all cases is thinner than in the arteries. In large veins it may assume the characters of a fenestrated membrane, which is double in some parts of the crural and iliac veins. Isolated muscular fibres exist in the intima of the femoral and popliteal veins.

(2) The **t. media** of the larger veins consists of alternate layers of elastic and muscular tissue united to each other by a considerable amount of connective tissue, but this coat is always thinner than in the corresponding arteries. This coat diminishes in the following order in the following vessels: popliteal, veins of the lower extremity, veins of the upper extremity, superior mesenteric, other abdominal veins, hepatic, pulmonary, and coronary veins. The following veins contain no muscle: veins of bone, central nervous system and its membranes, retina, the superior cava, with the large trunks that open into it, the upper part of the inferior cava. Of course, in these cases the media is very thin. In the smallest veins the media is formed of fine connective tissue, with very few muscular fibres scattered in the inner part.

(3) The **t. adventitia** is thicker than that of the corresponding arteries; it contains *much connective tissue*, usually arranged longitudinally, and not much elastic tissue. Longitudinally arranged *muscular fibres* occur in some veins (renal, portal, inferior cava near the liver, veins of the lower extremities). The **valves** consist of fine fibrillar connective tissue with branched cells. An elastic network exists on their convex surface, and both surfaces are covered by endothelium. The valves contain many muscular fibres (Fig. 70). [Ranvier has shown that the shape of the epithelial cells on the side over which the blood passes is more elongated than on the cardiac side of the valve, where the long axes of the cells are placed transversely.]

The **sinuses** of the dura mater are spaces covered with endothelium. The spaces are either duplicatures of the membrane, or channels in the substance of the tissue itself.

Cavernous spaces we may imagine to arise by numerous divisions and anastomoses of tolerably large veins of unequal calibre. The vascular wall appears to be much perforated and like a sponge, the internal space being traversed by threads and strands of tissue, which are covered with endothelium on their surfaces, that are in contact with the blood. The surrounding wall consists of connective tissue, which is often very tough, as in the corpus cavernosum, and it not unfrequently contains non-striped muscle.

Cavernous formations of an analogous nature on *arteries* are the *carotid gland* of the frog, and a similar structure on the pulmonary arteries and aorta of the turtle, and the *coccygeal gland* of man. The last structure is richly supplied with sympathetic nerve fibres, and is a convoluted mass of ampullated or fusiform dilatations of the middle sacral artery, surrounded and permeated by non-striped muscle.

Vasa Vasorum.—[These are small vessels which nourish the coats of the arteries and veins. They arise from one part of a vessel and enter the walls of the same, or another vessel at a lower level. They break up chiefly in the outer coat, and none enter the inner coat.] In structure they resemble other small blood vessels. The blood circulating in the arterial or venous wall is returned by small veins.

[**Lymphatics.**—There are no lymphatics on the inner surface of the muscular coat, or under the intima in large arteries. They are numerous in a gelatinous layer immediately outside the muscular coat, and the same relation obtains in large muscular veins and lymphatic trunks (*Heggan*).]

Intercellular Blood Channels.—Intercellular blood channels of narrow calibre, and without walls, occur in the granulation tissue of healing wounds. At first blood plasma alone is found between the formative cells, but afterwards the blood current forces blood corpuscles through the channels. The first blood vessels in the developing chick are formed in a similar way, from the formative cells of the mesoblast.

Properties of the Blood Vessels.—The larger blood vessels are cylindrical tubes composed of several layers of various tissues, more especially *elastic tissue* and *smooth muscular fibres*, and the whole is lined by a smooth polished layer of endothelium. One of the most important properties is the **contractility** of the vascular wall, in virtue of which the calibre of the vessel can be varied, and therefore the supply of blood to a part is altered. The contractility is due to the plain muscular fibres, which are, for the most part, arranged circularly. It is most marked in the small arteries, and of course is absent where no muscular

tissue occurs. The amount and intensity of the contraction depend upon the development of the muscular tissue; in fact, the two go hand in hand. [If an artery be exposed in the living body it soon contracts under the stimulus of the atmosphere acting upon the muscular fibres.]

[**Action of Drugs on the Vascular System.**—Gaskell finds that a very dilute solution of lactic **acid** (1 : 10,000 parts of saline solution), passed through the **blood vessels** of a frog, always enlarges the calibre of the blood vessels, while an **alkaline solution** (1 part sodium hydrate to 10,000 saline solution) always diminishes their size, usually to absolute closure, and indeed the artificial constriction of the blood vessels may be almost complete. These fluids are antagonistic to each other as far as regards their action on the calibre of the arteries. Dilute alkaline solutions act on the **heart** in the same way. After a series of beats the ventricle stops beating, the standstill being in a state of contraction. Very dilute lactic acid causes the ventricle to stand still in the phase of complete relaxation. The acid and alkaline saline solutions are antagonistic in their action on the ventricle. Cash and Brunton find that dilute acids have a tendency to increase the transudation through the vessels and produce *œdema* of the surrounding tissues. They also observed that barium, calcium, strontium, copper, iron, and tin produce contraction of the blood vessels when solutions of their salts are driven through them, while the same effect is produced by very dilute solutions of potassium. Nicotin, atropin, and chloral differ in their action according to the dose. In these experiments the effect was ascertained by the amount of fluid which flowed out of the vessels in a given time.] If blood containing certain drugs be perfused through the blood vessels of a freshly excised organ, the blood vessels are *dilated; e. g.*, by amyl nitrite, chloral hydrate, morphia, CO, paraldehyde, kairin, quinine, atropin, ferricyanide of potassium, (urea and sodic chloride in the renal vessels),—they are contracted by digitalin, veratria, helleborin (*Kobert*). Heat causes contraction of the blood vessels of the frog's mesentery (*Gärtner*). According to Roy the blood vessels shorten when heated.

That the **capillaries** undergo dilatation and contraction, owing to variations in the size of the protoplasmic elements of their walls, must be admitted.

Stricker has described capillaries as "protoplasm in tubes," and observed that in the tadpole they exhibited movements when stimulated. Golubew described an active state of contraction of the capillary wall, but he regarded the nuclei as the parts which underwent change. Rouget observed the same result in the capillaries of new-born mammals. Tarchanoff found that mechanical or electrical stimulation caused a change in the shape and size of the nuclei, so that he regards these as the actively contractile parts. [Severini also attaches great importance to the contractility of the capillaries and especially of their nuclei as influencing the blood stream. Oxygen acts on the nuclei of the capillary wall (membrana nictitans of frog) and causes them to swell, while CO_2 has an opposite effect. The circulation through a lung suddenly filled with O or atmospheric air is at first very rapid, but soon diminishes, while with CO_2 the circulation remains constant.] As the capillaries are excessively thin, soft, and delicate, it is obvious that the form of the individual cells must depend to a considerable extent upon the degree to which the vessels are filled with blood. In vessels which are distended with blood the endothelial cells are flattened, but when the capillaries are collapsed they project more or less into the lumen of the vessel (*Renaut*).

[It is well known that the capillaries present great variations in their diameter at different times. As these variations are usually accompanied by a corresponding contraction or dilatation of the arterioles, it is usually assumed that the variations in the diameter of the capillaries are due to differences of the pressure within the capillaries themselves, viz., to the elasticity of their walls. Every one is agreed that the capillaries are very elastic, but the experiments of Roy and Graham Brown show that they are contractile as well as elastic, and these observers conclude that, under normal conditions, it is by the contractility of the capillary wall as a whole that the diameter of these vessels is changed, and to all appearance their contractility is constantly in action. "The individual capillaries (in all probability) contract or expand in accordance with the requirements of the tissues through which they pass. The regulation of the vascular blood flow is thus more complete than is usually imagined."]

Physical Properties.—Among the physical properties of the blood vessels, **elasticity** is the most important; their elasticity is *small in amount, i. e.*, they offer little resistance to any force applied to them so as to distend or elongate them, but it is *perfect in quality, i.e.*, the blood vessels rapidly regain their original size and form after the force distending them is removed.

[**Uses of Elasticity.**—The elasticity of the arteries is of the utmost importance in aiding the conversion of the unequal movement of the blood in the large arteries into a uniform flow in the capillaries. E. H. Weber compared the elastic wall of the arteries with the air in the air chamber of a fire engine. In both cases an elastic medium is acted upon—the air in the one case and the elastic tissue in the other—which in turn presses upon the fluid, propelling it onward continually,

while the action of the pump or the heart, as the case may be, is intermittent. The ordinary spray producer acts on this principle. A uniform spray or jet is obtained by pumping intermittently, but only when the resistance is such as to bring into action the elasticity of the bag between the pump and the spray orifice.]

According to E. H. Weber, Volkmann, and Wertheim, the elongation of a blood vessel and *moist* tissues generally is not proportional to the weight used to extend it, the elongation being relatively less with a large weight than with a small one, so that the curve of extension is nearly [or, at least bears a certain relation to] a *hyperbola*. According to Wundt, we have not only to consider the extension produced at *first* by the weight, but also the subsequent **"elastic after-effect,"** which occurs gradually. The elongation which takes place during the last few moments occurs so slowly and so gradually that it is well to observe the effect by means of a magnifying lens. Variations from the general law occur to this extent, that if a certain weight is exceeded, less extension, and, it may be, permanent elongation of the artery not unfrequently occur. K. Bardeleben found, especially in veins elongated to 40 or 50 per cent. of their original length, that when the weight employed increased by an equal amount each time, the elongation was proportional to the square root of the weight. This is apart from any elastic after-effect. Veins may be extended to at least 50 per cent. of their length without passing the limit of their elasticity.

[Roy experimented upon the elastic properties of the *arterial wall*. A portion of an artery, so that it could be distended by any desired internal pressure, was enclosed in a small vessel containing olive oil arranged in the same way as in Fig. 62, for the heart. The variations of the contents were recorded by means of a lever writing on a revolving cylinder. The instrument is termed a **sphygmotonometer.** The *aorta and other large arteries* are most elastic and most distensible at pressures corresponding more or less exactly to their normal blood pressure, while in *veins* the relation between internal pressure and the cubic capacity is very different. In them the maximum of distensibility occurs with pressures immediately above zero. Speaking generally, the cubic capacity of an *artery* is greatly increased by raising the intra-arterial tension, say from zero to about the normal internal pressure which the artery sustains during life. Thus in the *rabbit*, the capacity of the aorta was *quadrupled* by raising the intra-arterial pressure from zero to 200 mm. Hg., while that of the carotid was more than *six times* greater at that pressure than it was in the undistended condition. The pulmonary artery is distinguished by its excessive elastic distensibility. Its capacity (rabbit) was increased more than twelve times on raising the internal pressure from zero to about 36 mm. Hg. Veins, on the other hand, are distinguished by the relatively small increase in their cubic capacity produced by greatly raising the internal pressure, so that the enormous changes in the capacity of the veins during life are due less to differences in the pressure than to the great differences in the *quantity* of blood which they contain.]

FIG. 71.

Sphygmometer of Hérisson and Chelius.

Pathological.—Interference with the nutrition of an artery alters its elasticity, [and that in cases where no structural changes can be found]. Marasmus preceding death causes the arteries to become wider than normal. In some old people they become atheromatous and even calcified.

Cohesion.—The cohesion of blood vessels is very great, and in virtue of this they are able to resist even considerable internal pressure without giving way. The carotid of a sheep is ruptured only when fourteen times the usual pressure it is called upon to bear is put upon it (*Volkmann*). Given a vein and an artery of the same thickness, a greater pressure is required to rupture the former than the latter. The human carotid or iliac artery resists a pressure of 8 atmospheres, the veins about the half of this.

66. INVESTIGATION OF THE PULSE.—[The characters of the pulse may be investigated by—(1) the eye (*inspection*); (2) the finger (*palpation*); (3) instruments.

Two or three fingers are placed over the course of the radial artery, and the various phenomena in connection with the pulse are noted. It takes much practice for the physician to acquire the tactus eruditus, and notwithstanding the value of instruments, every physician should make a careful study of the pulse beat with his finger. In order to feel the pulse beat or to take a pulse tracing, there must be some resistant body, *e.g.*, a bone behind the artery, and a certain degree of pressure must be exerted on the artery.]

The individual phases of the movement of the pulse can only be accurately investigated by the application of *instruments* to the arteries.

(1) **Poiseuille's Box Pulse Measurer** (1829).—An artery is exposed and placed in an oblong box filled with an indifferent fluid. A vertical tube with a scale attached communicates with the interior of the box. The column of fluid undergoes a variation with every pulse beat.

(2) **Hérisson's Tubular Sphygmometer** consists of a glass tube whose lower end is covered with an elastic membrane (Fig. 71). The tube is partly filled with Hg. The membrane is placed over the position of a pulsating artery, so that its beat causes a movement in the Hg. Chelius used a similar instrument, and he succeeded with this instrument in showing the existence of the double beat (dicrotism) in the normal pulse (1850).

(3) **Vierordt's Sphygmograph** (1855).—In this, one of the earliest sphygmographs, Vierordt departed from the principle of a fluctuating fluid column, and adopted the principle of the *lever*.

FIG. 72.



Scheme of Marey's sphygmograph. A, spring with ivory pad, *y*, which rests on the artery; *e*, weak spring pressing *k* into *t*; *v*, writing lever; P, piece of smoked glass or paper moved by clockwork, U; H, screw to limit excursion of A; S, arrangement for fixing the instrument to the arm of the patient.

Upon the artery rested a small pad, which moved a complicated system of levers. At first he used a straw 6 inches long, which rested on the artery. The point of one of the levers inscribed its movements upon a revolving cylinder. This instrument was soon discarded.

(4) **Marey's Sphygmograph** consists of a combination of a lever with an elastic spring. The elastic spring (Fig. 72, A) is fixed at one end, *z*, free at the other end, and provided with an ivory pad, *y*, which is pressed by the spring upon the radial artery. On the upper surface of the pad there is a vertically placed fine-toothed rod, *k*, which is pressed upon by a weak spring, *e*, so that its teeth dovetail with similar teeth in the small wheel, *t*, from whose axis there projects a long, light,

FIG. 73.



Marey's improved sphygmograph. A, steel spring; B, first lever; C, writing lever; C', its free writing end; D, screw for bringing B in contact with C; G, slide with smoked paper; H, clockwork; L, screw for increasing the pressure; M, dial indicating the pressure; K, K, straps for fixing the instrument to the arm, and the arm to the double inclined plane or support.

wooden lever, *v*, running nearly parallel with the elastic spring. This lever has a fine style at its free end, *s*, which writes upon a smoked plate, P, moved by clockwork, U, in front of the style. Marey's instrument, as improved by Mahomed and others, has been very largely used.

[Its more complete form, as in Fig. 73, where it is shown applied to the arm, consists of (1) a steel spring, A, which is provided with a pad resting on the artery, and moves with each movement of the artery; (2) the lever, C, which records the movement of the artery and spring in a magnified form on the smoked paper, G; (3) an arrangement, L, whereby the exact pressure exerted upon the artery is indicated on the dial, M; (4) the clockwork, H, which moves the smoked paper, G, at a uniform rate; (5) a framework to which the various parts of the instrument are attached, and by means of which the instrument is fastened to the arm by straps K, K (*Byrom Bramwell*).]

[**Application.**—In applying the sphygmograph, cause the patient to seat himself beside a low table, and place his arm on the double inclined plane (Fig. 73). In the newer form of instrument, the lid of the box is so arranged as to unfold to make this support. The fingers ought to be semi-flexed. Mark the position of the radial artery with ink. See that the clockwork is wound up,

FIG. 74.



Ludwig's Sphygmograph.

and apply the ivory pad exactly over the radial artery where it lies upon the radius, fixing it to the arm by the non-elastic straps, K, K. Fix the slide holding the smoked paper in position. The best paper to use is that with a very smooth surface, or an enameled card smoked over the flame of a turpentine lamp, over a piece of burning camphor, or over a fan-tailed gas burner. The writing

FIG. 75.



Dudgeon's Sphygmograph.

style is so arranged as to write upon the smoked paper with the least possible friction. It is most important to regulate the pressure exerted upon the artery by means of the milled head, L. This must be determined for each pulse, but the rule is to graduate the pressure until the greatest amplitude of movement of the lever is obtained. Set the clockwork going, and a tracing is obtained,

which must be "fixed" by dipping it in a rapidly drying varnish, *e. g.*, photographic. In every case scratch on the tracing, with a needle, the name, date, and amount of pressure employed.]

[(5) **Dudgeon's Sphygmograph.**—This is a convenient form of sphygmograph, although Broadbent regards its results as untrustworthy. The instrument after being carefully adjusted upon the radial artery is kept in position by an inelastic strap. The pressure of the spring is regulated,

FIG. 76.



Scheme of Brondgeest's sphygmograph. S, S', receiving and recording (S, S') tambours with writing levers, Z and Z'; K, K', conducting tubes: *p*, over heart, *p'*, over a distant artery.

by the eccentric wheel, to any amount from 1 to 5 ounces. As in other instruments the tracing paper is moved in front of the writing needle by means of clockwork. The writing levers are so adjusted that the movements of the artery are magnified fifty times (Fig. 75).]

(6) [**Ludwig's** improved form is a very serviceable instrument (Fig. 74).]

FIG. 77.



Scheme of Landois' Angiograph.

(7) **Marey's tambours** are also employed for registering the movements of the pulse. They are used in the same way as the **pansphygmograph.** Two pairs of metallic cups (Fig. 76, S, S, and S', S', Upham's capsules) are pierced in the middle by thin metal tubes, whose free ends are connected with caoutchouc tubes, K and K'. All the four metallic vessels are covered with an elastic membrane. On S and S' are fixed two knob-like pads, *p* and *p'*, which are applied to the

pulsating arteries, and the metal arcs, B and B′, retain them in position. On the other tambours are arranged the writing levers, Z and Z′. Pressure on the one tambour necessarily compresses the air, and makes the other, with which it is connected, expand, so as to move the writing lever. This arrangement does not give absolutely exact results; still, it is very easily used, and is convenient. In Fig. 76 a double arrangement is shown, whereby one instrument, B, may be placed over the heart and the other, B′, on a distant artery.

(8) **Landois' Angiograph.**—To a basal plate, G, G, are fixed two upright supports, *p*, which carry between them at their upper part the movable lever, *d*, *r*, carrying a rod bearing a pad, *e*, directed downward, which rests on the pulse. The short arm carries a counterpoise, *d*, so as exactly to balance the long arm. The long arm has fixed to it at *r* a vertical rod provided with teeth, *h*, which is pressed against a toothed wheel firmly fixed on the axis of the very light writing lever, *e*, *f*, which is supported between two uprights, *q*, fixed to the opposite end of the basal plate, G, G. The writing lever is equilibrated by means of a light weight. The writing needle, *k*, is fixed by a joint to *e*, and it writes on the plate, *t*. The first mentioned lever, *d*, *r*, carries a shallow cup, Q, just above the pad, into which weights may be put to press on the pulse. In this instrument the weight can be measured and varied; the writing lever moves vertically, and not in a curve as in Marey's apparatus, which greatly facilitates the measuring of the curves (Fig. 77).

Other sphygmographs are used, both in this country and abroad, including that of Sommerbrodt, which is a complicated form of Marey's sphygmograph, and those of Pond and Mach.

FIG. 78.

Normal pulse curve of the radial artery, obtained by the angiograph writing upon a plate attached to a vibrating tuning-fork. Each double vibration = 0.01613 sec.

In every **pulse curve—sphygmogram** or **arteriogram**—we can distinguish the *ascending part* (ascent) of the curve, the *apex*, and the *descending part* (descent). Secondary elevations scarcely ever occur in the ascent, which is usually represented by a straight line, while they are always present in the descent. Such elevations occurring in the descent are called **catacrotic**, and those in the ascent, **anacrotic**. When the recoil elevation or dicrotic wave occurs in a well-marked form in the descent, the pulse is said to be **dicrotic**, and when it occurs twice, **tricrotic**.

FIG. 79.

Gas Sphygmoscope of S. Mayer.

FIG. 80.

Hæmautographic curve of the posterior tibial artery of a dog. P, primary pulse wave; R, dicrotic wave; *e*, *e*, elevations due to elasticity.

Measuring Pulse Curves.—If the smoked surface on which the tracing is inscribed is moved at a uniform rate by means of the clockwork, then the height and length of the curve are measured by means of an ordinary rule. If we know the rate at which the paper was moved, then it is easy to calculate the duration of any event in the curve.

The curve may be recorded on a plate of glass fixed to a tuning-fork kept in vibration. Every part of the curve shows little elevations (whose rate of vibration is known beforehand). All that is required is to count the number of vibrations in order to ascertain the duration of any part of the curve (Fig. 78).

Gas Sphygmoscope.—A small metallic or glass capsule (Fig. 79), provided with an inlet and an outlet tube, and closed below by a fine membrane, is placed over an artery. The inlet tube is connected to a gas supply, and the outlet to a rat-tail gas burner (*b*). The gas jet responds to every pulse beat. Czermac *photographed* a beam of light set in motion by the movements of the pulse.

Hæmautography.—Expose a large artery of an animal, and divide it so that the stream of blood issuing from it strikes against a piece of paper drawn in front of the blood stream. The curve so obtained (Fig. 80) shows, in addition to the primary wave, P, a distinct dicrotic wave, R, and slight vibrations, *e*, *e*, due to the variations in the elasticity of the arterial wall, which shows that the movements occur in the blood itself, and are communicated as waves to the arterial wall. By estimating the amount of blood in the various parts of the curve, we obtain a knowledge of the amount of blood discharged by the divided artery during the systole and diastole (*i.e.*, the narrowing and dilatation) of the artery—the ratio is 7 : 10. Thus in the *unit of time*, during arterial dilatation, rather more than *twice* as much blood flows out as compared with what occurs during arterial contraction.

67. PULSE TRACING OR SPHYGMOGRAM.—[The Pulse.—With each systole of the heart, a certain quantity of blood is forced into the already filled and partially distended arteries, the resistance in the vessels is lowest between the pulsations, and at this time the arterial tubes are somewhat flattened, but with each systole of the left ventricle the pulse wave, or rather the liquid pressure within the vessel, is increased, thus forcing the artery back into the circular form. "The change of shape, from the flattened condition impressed upon the vessel by the finger or the sphygmograph lever, to the round cylindrical shape which it assumes under the distending force of the blood within it, constitutes the pulse" and it indicates the degree and duration of the increased pressure in the arterial system caused by the ventricular systole (*Broadbent*).]

FIG. 81.

Sphygmogram of radial artery: pressure 2 oz. Each part of the curve between the base of one up-stroke and the base of the next up-stroke corresponds to a beat of the heart, so that this figure shows five heart beats and part of a sixth.

Analysis.—A **sphygmogram** or **pulse tracing** consists of a series of curves (Fig. 81) each of which corresponds with one beat of the heart. Each pulse curve consists of—

1. The line of ascent (*a* to *b* in Fig. 81).
2. The apex (P in Fig. 83, and *b* in Fig. 81).
3. The line of descent (*b* to *h*).

(1) The **line of ascent**, up-stroke, or percussion stroke, is nearly vertical, and occurs during the dilatation of the artery produced by the systole of the left ventricle, when the aortic valves are forced open and the ventricular contents are projected into the arterial system. [The ascent is nearly vertical, but in some cases, where the ventricle contracts very suddenly, as occasionally happens in aortic regurgitation, it is quite vertical (Fig. 85).]

(2) The **apex** or **percussion wave** in a normal pulse is pointed.

(3) The **line of descent** is gradual, and corresponds to the diminution of diameter or contraction of the artery. It is interrupted by *two completely distinct elevations* or secondary waves. Such elevations are called "catacrotic." The more distinct of the two occurs as a well-marked elevation about the middle of the descent (R in Fig. 83 and *f* in Fig. 81); it is called the **dicrotic wave**, or,

with reference to its mode of origin, the "*recoil wave.*" [As the descent corresponds to the time when blood is flowing out of the arteries at the periphery into the capillaries, its direction will depend on the rapidity of the outflow. Thus it will be more rapid in paralysis of the arterioles and very rapid in aortic regurgitation, where, of course, much of the blood flows backward into the left ventricle (Fig. 85). In this case, the artery will recoil suddenly from under the finger or pad of the instrument, and this constitutes the "pulse of empty arteries."]

The **dicrotic wave**, or recoil wave, corresponds to the time following the closure of the aortic valves, and is preceded in the descent by a slight depression, the **aortic notch**.

[The **tidal wave**, or pre-dicrotic, occurs between the apex and the dicrotic wave (Fig. 81, *d'*). It occurs on the descent, and during the contraction of the ventricle. The tidal wave is best marked in a *hard* pulse, *i.e.*, where the blood pressure is high, so that it is usually well marked in cirrhotic disease of the kidney, accompanied by hypertrophy of the left ventricle.]

[In some cases, *e.g.*, **mitral regurgitation**, the pre-dicrotic wave may be present in some pulse beats and absent in others (Fig. 82), where the tidal wave is present in the largest pulse, and absent in the others, while the base line is uneven. In mitral stenosis the amount of blood discharged into the left ventricle frequently varies, hence the variations in the characters of the arterial pulse.]

There may be other **secondary** waves in the lower part of the descent.

[**Respiratory or Base Line.**—If a line be drawn so as to touch the bases of

FIG. 82.

Irregular pulse of mitral regurgitation.

all the up-strokes, we obtain a straight line, hence called by this name. The base line is altered in disease and during forced respiration (§ 74).]

The pulse curve indicates the variations of pressure which the blood exerts on the arterial walls, for the lever rises and falls with the pressure, hence v. Kries calls it the "**pressure pulse.**"

68. **ORIGIN OF THE DICROTIC WAVE.**—The **dicrotic** or **recoil wave**, which is always present in a normal pulse, is caused thus: During the ventricular systole a mass of blood is propelled into the already full aorta, whereby a positive wave is rapidly transmitted from the aorta throughout the arterial system, even to the smallest arterioles, *in which this primary wave is extinguished.* As soon as the semilunar valves are closed, and no more blood flows into the arterial system, the arteries, which were previously distended by the mass of blood suddenly thrown into them, recoil or contract, so that in virtue of the elasticity (and contractility) of their walls, they exert a counter-pressure upon the column of blood, and thus the blood is forced onward. There is a free passage for it toward the periphery, but toward the centre (heart) it impinges upon the already closed semilunar valves. This develops a new positive wave, which is propagated peripherally through the arteries, where it disappears in their finest branches. In those cases where there is sufficient time for the complete development of the pulse curve (as in the short course of the carotids, and in the arteries of the upper arm, but not in those of the lower extremity, on account of their length), a second reflected wave may be caused in exactly the same way as the first. Just as the pulse occurs later in the more peripherally placed arteries than in those near the heart, so the secondary wave reflected from the closed aortic valves

must appear later in the peripheral arteries. Both kinds of waves, the primary pulse wave, the secondary, and eventually even the tertiary reflected wave, arise in the same place, and take the same course, and the longer the course they have to travel to any part of the arterial system, the later they arrive at their destination.

FIG. 83.



I, II, III, sphygmograms of carotid artery; IV, axillary; V to IX, radial; X, dicrotic radial pulse; XI, XII, crural; XIII, posterior tibial; XIV, XV, pedal. In all the curves P indicates apex; R, dicrotic wave; *e*, *e*, elevations due to elasticity; K, elevation caused by the closure of the semilunar valves of the aorta.

[The conditions which favor dicrotism are low blood pressure and a rapid, sharp cardiac contraction. When the blood pressure is low, there is less resistance to the inflow of blood at the aorta from the left ventricle, so that its systole occurs sharply, forcing on the blood and distending the arterial walls. The elastic coats rebound on the contained blood, and thus start a wave from the closed semilunar valves.]

The following points regarding the dicrotic wave have been ascertained experimentally, chiefly by Landois:—

1. The dicrotic wave occurs later in the descending part of the curve, the further the artery experimented upon is distant from the heart. Compare the curves, Fig. 83.

The shortest accessible course is that of the carotid; where the dicrotic wave reaches its maximum 0.35 to 0.37 sec. after the beginning of the pulse. In the upper extremity the apex of the dicrotic wave is 0.36 to 0.38, to 0.40 sec. after the beginning of the pulse beat. The longest course is that of the arteries of the lower extremity. The apex of the dicrotic wave occurs 0.45 to 0.52 to 0.59 sec. after the beginning of the curve. It varies with the height of the individual.

2. The dicrotic elevation in the descent is lower, and is less distinct, the further the artery is situated from the heart, so that the longer the distance which the wave has to travel the less distinct it becomes.

3. It is best marked in a pulse where the primary pulse wave is short and energetic. It is greatest relatively when the systole of the heart is short and energetic.

4. It is better marked *the lower the tension* of the blood within the arteries [and is best developed in a *soft* pulse]. In Fig. 83, IX and X were obtained when the tension of the arterial was *low;* V and VI, *medium;* and VII with *high* tension.

Conditions influencing Arterial Tension.—It is **diminished** at the beginning of inspiration (§ 74), by hemorrhage, stoppage of the heart, heat, an elevated position of parts of the body, **amyl nitrite**, nitro-glycerine, and the **nitrites** generally. [Both drugs accelerate the pulse beats and

FIG. 84.



Pulse tracings. A, normal; A', one minute after inhalation of amyl nitrite; B, normal; B', after a dose of nitro-glycerine (*Stirling, after Murrell*).

produce marked dicrotism; with amyl nitrite the full effect is obtained in from 15 to 20 sec. after the inhalation of the dose (Fig. 84, A, A'), but with nitro-glycerine not until 6 or 7 min. (Fig. 84, B, B') and in the latter case the effects last longer.] It is **increased** at the beginning of expiration, by accelerated action of the heart, stimulation of vaso-motor nerves, diminished outflow of blood at the periphery, and by inflammatory congestion by certain poisons, as lead; compression of other large arterial trunks, action of cold and electricity on the small cutaneous vessels, and by impeded outflow of venous blood. When a large arterial trunk is exposed, the stimulation of the air causes it to contract, resulting in an increased tension within the vessel. In many diseased conditions the arterial tension is greatly increased—[*e.g.*, in Bright's disease, where the kidney is contracted ("**granular**"), and where the left ventricle is hypertrophied].

FIG. 85.



Aortic Regurgitation.

In all these conditions increased arterial tension is indicated by the dicrotic wave being less high and less distinct, while with diminished arterial tension it is a larger and apparently more independent elevation. Moens has shown that the time between the primary elevation and dicrotic wave increases with increase in the diameter of the tube, with diminution of its thickness, and when its coefficient of elasticity diminishes.

[The dicrotic wave is absent or but slightly marked in cases of atheroma and in aortic regurgitation (Fig. 85). In this figure observe also the vertical character of the up-stroke.]

Elastic Elevations.—Besides the dicrotic wave, a number of small less-marked elevations occur in the course of the descent in a sphygmogram (Fig.

83, *e*, *e*). These elevations are caused by the elastic tube being thrown into vibrations by the rapid, energetic pulse wave, just as an elastic membrane vibrates when it is suddenly stretched. The artery also executes vibratory movements when it passes suddenly from the distended to the relaxed condition. These small elevations in the pulse curve, caused by the elastic vibrations of the arterial wall, are called "**elastic elevations**" by Landois.

(1) The elastic vibrations increase in number in one and the same artery with the degree of tension of the elastic arterial wall. A very high tension occurs in the cold stage of intermittent fever, in which case these elevations are well marked.

(2) If the tension of the arterial wall be greatly diminished, these elevations may disappear, so that, while diminished tension favors the production of the dicrotic wave, it acts in the opposite way with reference to the "elastic elevations." (3) In diseases of the arterial walls affecting their elasticity, these elevations are either greatly diminished or entirely abolished. (4) The further the arteries are distant from the heart, the higher are the elastic elevations. (5) When the mean pressure within the arteries is increased by preventing the outflow of blood from them, the elastic vibrations are higher and nearer the apex of the curve. (6) They vary in number and length in the pulse curves obtained from different arteries of the body.

When the arm is held in an upright position, after five minutes the blood vessels empty themselves and collapse, while the elasticity of the arteries is diminished.

69. **DICROTIC PULSE.**—Sometimes during fever, especially when the temperature is high, a dicrotic pulse may be felt, each pulse beat, as it were, being composed of two beats (Fig. 83, X), one beat being large and the other small, and more like an after beat. Both beats correspond to *one* beat of the heart. The two beats are quite distinguishable by the touch. The phenomenon is only an exaggerated condition of what occurs in a normal pulse. *The sensible second beat is nothing*

FIG. 86.



Development of the Pulsus dicrotus—P. caprizans; P. monocrotus.

more than the greatly increased dicrotic elevation, which, under ordinary conditions, is not felt by the finger.

Conditions.—The occurrence of a dicrotic pulse is **favored** (1) by a short primary pulse wave, as in fevers, where the heart beats rapidly.

(2) By *diminished arterial tension*. A short systole and diminished arterial blood pressure are the most favorable conditions for causing a dicrotic pulse. [So that dicrotism is best marked in a soft pulse.] The double beat may be felt only at certain parts of the arterial system, while at other parts only a single beat is felt. A favorite site is the radial artery of one or other side, where conditions favorable to its occurrence appear to exist. This seems to be due to a local diminution of the blood pressure in this area, owing to the paralysis of its vasomotor nerves (*Landois*). If the tension be increased by compressing other large arterial trunks or the veins of the part, the double beat becomes a simple pulse beat. The dicrotic pulse in fever seems to be due to the increased temperature (39° to 40° C.), whereby the artery is more distended, and the heart beat is shorter and more prompt.

(3) It is absolutely necessary that the *elasticity of the arterial wall be normal.* The dicrotic pulse does not occur in old persons with atheromatous arteries.

Monocrotic Pulse.—In Fig. 86, A, B, C, we observe a gradual passage of the normal radial curve, A, into the dicrotic beat, B, and C, where the dicrotic wave, *r*, appears as an independent

elevation. If the frequency of the pulse increases more and more in fever, the next following pulse beat may occur in the ascending part of the dicrotic wave, D, E, F, and it may even occur close to the apex, G (**P. caprizans**). If the next following beat occurs in the depression, *i*, between the primary elevation, *p*, and the dicrotic elevation, *r*, the latter entirely disappears, and the curve, H, assumes what Landois calls the "monocrotic type."

FIG. 87.



Hyperdicrotic Pulse.

[**Degrees of Dicrotism.**—When the aortic notch reaches the respiratory or base line, the tidal wave having disappeared, the pulse is said to be **fully dicrotic.** When the aortic notch falls below the base line, *i. e.*, below where the up-stroke begins, the pulse is said to be **hyperdicrotic** (Fig. 87). This form occurs during high fever (104° F.), and is usually a grave sign, indicating exhaustion and the need for stimulants.]

70. CHARACTERS OF THE PULSE.—[The three factors concerned in the production of the pulse are, (1) the action of the heart, (2) the elasticity of the large vessels, (3) the resistance in the small arteries and capillaries. Any or all or several of these factors may be modified.] (1) **Frequency.**—According as a greater or less *number of beats* occurs in a given time, *e. g.*, per minute, the pulse is said to be frequent or infrequent. The **normal rate, in man** = 71 per minute, and somewhat more in the female; in fever it may exceed 120 (250 have been counted by Bowles), while in other diseases it may fall to 40, and even 10 to 15; but such cases are rare, and are probably due to an affection of the cardiac nerves (§ 41). The frequency of the pulse is usually increased when the respirations are *deeper*, but not more numerous, *i. e.*, rapid shallow respirations do not affect the frequency of the pulse, but deep respirations do. [The frequency may be regular or irregular with regard to time.]

(2) **Celerity or Rapidity.**—If the pulse wave is developed, so that the distention of the artery slowly reaches its height, and the relaxation also takes place gradually, we have the p. tardus or *slow* or *long* pulse; the opposite condition gives rise to the p. celer or *quick* or *short* pulse. The rapidity of the pulse is increased by quick action of the heart, power of expansion of the arterial walls, easy efflux of blood owing to the dilatation of the small arteries, and by nearness to the heart. [The *quickness* has reference to a *single* pulse beat, the *frequency* to a *number* of beats.] In a quick pulse, the curve is high and the angle at the apex is acute, while in a slow pulse the ascent is low and the angle at the apex is large.

(3) **Conditions Affecting the Pulse Rate.—Frequency in Health.**—In man the **normal pulse rate** = 71 to 72 beats per minute, in the female about 80. In some individuals the pulse rate may be higher (90 to 100), in others lower (50), and such a fact must be borne in mind.

(*a*) **Age**:—

	Beats per Minute.		Beats per Minute.		Beats per Minute
Newly born,	130 to 140	5 years,	94 to 90	25 to 50 years,	70
1 year,	120 to 130	10 "	about 90	60 years,	74
2 years,	105	10 to 15 years,	78	80 "	79
3 "	100	15 to 20 "	70	80 to 90 years,	over 80
4 "	97	20 to 25 "	70		

(*b*) The **length of the body** has a certain relation to the frequency of the pulse. The following results have been obtained by Czarnecki from the formulæ of Volkmann and Rameaux:—

Length of Body in 10 cm.	Pulse. Calculated.	Observed.	Length of Body in 10 cm.	Pulse. Calculated.	Observed.
80 to 90,	90	103	140 to 150,	69	74
90 to 100,	86	91	150 to 160,	67	68
100 to 110,	81	87	160 to 170,	65	65
110 to 120,	78	84	170 to 180,	63	64
120 to 130,	75	78	Above 180,	60	60
130 to 140,	72	86			

(*c*) The **pulse rate is increased** *by muscular activity, by every increase of the arterial blood pressure, by taking of food, increased temperature, painful sensations, by psychical disturbances, and* [*in extreme debility*]. *Increased heat,* **fever,** or pyrexia increases the frequency, and as a rule the increase varies with the height of the temperature. [Dr. Aitken states that an increase of the temperature of 1° F. above 98° F. corresponds with an increase of ten pulse beats per minute; thus—

Temp. F.	Pulse Rate.	Temp. F.	Pulse Rate.	Temp. F.	Pulse Rate.
98°	60	101°	90	104°	120
99°	70	102°	100	105°	130
100°	80	103°	110	106°	140

This is merely an approximate estimate.] It is more frequent when a person is *standing* than when he lies down. *Music* accelerates the pulse and increases the blood pressure in dogs and men. Increased barometric pressure diminishes the frequency.

The Variation of the Pulse Rate during the Day.—3 to 6 A.M. = 61 beats; 8 to 11½ A.M. = 74. It then falls toward 2 P.M.; toward 3 (at dinner time) another increase takes place and goes on until 6 to 8 P.M. = 70; and it falls until midnight = 54. It then rises again toward 2 A.M., when it soon falls again, and afterward rises as before toward 3 to 6 A.M.

[**Pulse Rate in Animals.**—(*Colin.*)]

	Per Min.		Per Min.		Per Min.
Elephant,	25–28	Lioness,	68	Rabbit,	120–150
Camel,	28–32	Tiger,	74	Mouse,	120
Giraffe,	66	Sheep,	70–80	Goose,	110
Horse,	36–40	Goat,	70–80	Pigeon,	136
Ox,	45–50	Leopard,	60	Hen,	140
Tapir,	44	Wolf (female),	96	Snake,	24
Ass,	46–50	Hyæna,	55	Carp,	20
Pig,	70–80	Dog,	90–100	Frog,	80
Lion,	40	Cat,	120–140	Salamander,	77

(4) **Variations in the Pulse Rhythm (Allorhythmia).**—On applying the fingers to the normal pulse, we feel beat after beat occurring at apparently equal intervals. Sometimes in a normal series a beat is omitted = pulsus intermittens, or **intermittent pulse.** [In feeling an intermittent pulse, we imagine or have the impression that a beat is omitted. This may be due to a reflex arrest of the ventricular contraction, caused by digestive derangement, in which case it has no great significance; but if it be due to failure of the ventricular action, intermittent pulse is a serious symptom, being frequently present when the muscular walls are degenerated.] At other times the beats become smaller and smaller, and after a certain time begin as large as before = **p. myurus.** When an extra beat is intercalated in a normal series = **p. intercurrens.** The regular alternation of a high and a low beat = **p. alternans** (Fig. 88). In the **p. bigeminus** of Traube the beats occur in

FIG. 88.



Pulsus alternans.

pairs, so that there is a longer pause after every two beats. Traube found that he could produce this form of pulse in curarized dogs by stopping the artificial respiration for a long time. The **p. trigeminus** and **quadrigeminus** occur in the same way, but the irregularities occur after every third and fourth beat. Knoll found that in animals such irregularities of the pulse were apt to occur, as well as great irregularity in the rhythm generally, when there is much resistance to the circulation, and consequently the heart has great demands upon its energy. The same occurs in man when an improper relation exists between the force of the cardiac muscle and the work it has to do (*Riegel*). Complete irregularity of the heart's action is called **arhythmia cordis.**

71. VARIATIONS IN THE CHARACTERS OF THE PULSE.—Compressibility.—The relative **strength** or **compressibility** of the pulse (p. fortis and debilis), *i. e.*, whether the pulse is *strong* or *weak*, is estimated by the weight which the pulse is able to raise. A sphygmograph, provided with an index indicating the amount of pressure exerted upon the spring pressing upon the artery, may be used (Fig. 73). In this case, as soon as the pressure exerted upon the artery overcomes the pulse beat, the lever ceases to move. *The weight employed indicates the strength of the pulse.* [The finger may be, and generally is used. The finger is pressed upon the artery until the pulse beat in the artery *beyond* the point of pressure is obliterated. In health it requires a pressure of several ounces to do this. Handfield Jones uses a **sphygmometer** for this purpose. It is constructed like a cylindrical letter weight, and the pressure is exerted by means of a spiral spring which has been carefully graduated.] The pulse is *hard* or *soft* when the artery, according to the mean blood pressure, gives a feeling of greater or less resistance to the finger, and this quite independent of the energy of the individual pulse beats (p. durus and mollis). In estimating the **tension** of the artery and the pulse, *i. e.*, whether it is *hard* or *soft*, it is important to observe whether the artery has this quality only during the pulse wave, *i. e.*, if it is hard during diastole, or whether it is hard or soft during the period of rest of the arterial wall. All arteries are harder and less compressible during the pulse beat than during the period of rest, but an artery which is very hard during the pulse beat may be hard also during the pause between the pulse beats, or it may be very soft, as in insufficiency of the aortic valves. In this case, after the systole of the left ventricle, owing to the

incompetency of the aortic semilunar valves, a large amount of blood flows back into the ventricle, so that the arteries are thereby suddenly rendered partially empty. [The sudden collapse of the artery gives rise to the characteristic "pulse of unfilled arteries" (Fig. 85).]

Under similar conditions, the **volume** of the pulse is obvious from the size of the sphygmogram, so that we speak of a *large* and a *small* pulse (p. magnus and parvus). Sometimes the pulse is so thready and of such diminished volume that it can scarcely be felt. A *large* pulse occurs in disease when, owing to hypertrophy of the left ventricle, a large amount of blood is forced into the aorta. A *small* pulse occurs under the opposite condition, when a small amount of blood is forced into the aorta, either from a diminution of the total amount of the blood, or from the aortic orifice being narrowed [aortic stenosis], or from disease of the mitral valve; again, where the ventricle contracts feebly, the pulse becomes small and thready.

Compare the **two radials.** Sometimes the pulse differs on the two sides, or it may be absent on one side. [The pulse wave in the two radials is often different when an aneurism is present on one side.]

Angiometer.—Waldenburg constructed a "pulse clock," to register the tension, the diameter of the artery, and the volume of the pulse upon a dial. It does not give a graphic tracing, the results being marked by the position of an indicator.

72. THE PULSE CURVES OF VARIOUS ARTERIES.—1. Carotid (Fig 83, I, II, III; Fig. 93, C and C_1). The ascending part is very steep—the apex of the curve (Fig. 83, P) is sharp and high. Below the apex there is a small notch—the "**aortic notch**" (Fig. 83, K)—which depends on a positive wave formed in the root of the aorta, owing to the closure of the aortic valves, and propagated with almost wholly undiminished energy into the carotid artery. Quite close to this notch, if the curve be obtained with minimal friction, the first elastic vibration occurs (Fig. 83, II, *e*). Above the middle of the descending part of the curve is the dicrotic elevation, R, produced by the reflection of a positive wave from the already closed semilunar valves. The dicrotic wave is relatively small on account of the high tension in the carotid artery. After this the curve falls rapidly, but in its lowest third two small elevations may be seen. Of these the former is due to elastic vibration. The latter represents a *second* dicrotic wave (Fig. 83, III, R). Here there is a *true tricrotism*, which is more easily obtained from the carotid on account of the shortness of the arterial channel.

2. Axillary Artery (Fig. 83, IV). In this curve the ascent is very steep, while in the descent near the apex there is a small (aortic) elevation, K, caused by a positive wave, produced by the closure of the aortic valves. Below the middle there is a tolerably high dicrotic elevation, R, higher than in the carotid curve; because in the axillary artery the arterial tension is less, and permits a greater development of the dicrotic wave. Further on, two or three small elastic vibrations occur, *e*, *e*.

3. Radial Artery (Fig. 78; Fig. 83, V to X; Fig. 93, R and R_1). The line of ascent (Fig. 83) is tolerably high and sudden—somewhat in the form of a long *f*. The apex, P, is well marked. Below this, if the tension be high, two elastic vibrations may occur (V, *e*, *e*), but if it be low, only one (VI to IX, *e*). About the middle of the curve is the well-marked dicrotic elevation, R. This wave is least pronounced in a small hard pulse, and when the artery is much distended (Fig. 83, VII, R_1); it is larger when the tension is low (Fig. 83, IX, R), and is greatest of all when the pulse is dicrotic (X, R). Two or three small elastic elevations occur in the lowest part of the curve.

FIG. 89.



Curve of posterior tibial. Written by the angiograph upon a vibrating plate.

4. Femoral Artery (Fig. 83, XI, XII). The ascent is steep and high—the apex of the curve is not unfrequently broad, and in it the closure of the aortic valves (K) is indicated. The curve falls rapidly toward its lowest third. The dicrotic elevation, R, occurs late after the beginning of the curve, and there are also small elastic elevations (*e*, *e*).

5. Pedal Artery (Fig. 83, XIV, XV), and **Posterior Tibial** (Fig. 89 and Fig. 83, XIII). In pulse curves obtained from these arteries, there are well-marked indications that the apparatus (heart) producing the waves is placed at a considerable distance. The ascent is oblique and low—the dicrotic elevation occurs late. Two elastic vibrations (Fig. 83, XIV, *e*, *e*) occur in the descent, but they are very close to the apex, while the elastic vibrations at the lower part of the curve are feebly marked. Fig. 89 is from the posterior tibial. When measured it gives the following result:—

1 to 2 . . . . . 9.5	1 vibration is = 0.01613 sec.
1 to 3 20	
1 to 4 . . . . . 30.5	
1 to 6 61	

73. ANACROTISM.—As a general rule, the line of ascent of a pulse curve has the form of an *f*, and is nearly vertical. The arterial walls are thrown into elastic vibration by the pulse beat, and the number of vibrations depends greatly upon the tension of the arterial walls. The disten-

tion of the artery, or what is the same thing, the ascent of the sphygmogram usually occurs so rapidly that it is equal to *one* elastic vibration. The elongated *f*-shape of the ascent is fundamentally just a prolonged elastic vibration. When the number of vibrations causing the elastic variation is small, and when the line of ascent is prolonged, two elevations occasionally occur in the line of ascent. Such a condition may occur normally (Fig. 83, VIII, at 1 and 2; X, at 1 and 2). When a series of closely-placed elastic vibrations occur in the upper part of the line of ascent, so that the apex appears dentate and forms an angle with the line of ascent, then the condition becomes one of **anacrotism** (Fig. 90, *a*, *a*), which, when it is so marked, may be characterized as pathological. Anacrotism of the pulse occurs when the time of the influx of the blood is longer than the time occupied by an elastic vibration. Hence it takes place—

(1) In **dilatation** and **hypertrophy of the left ventricle**, *e*, *g*., Fig. 90, A, a tracing from the

FIG. 90.



Anacrotic radial curves. *a*, *a*, the anacrotic parts.

radial artery of a man suffering from contracted kidney. The large volume of blood expelled with each systole requires a long time to dilate the tense arteries.

(2) When the **extensibility** of the arterial wall is **diminished**, even the normal amount of blood expelled from the heart at every systole requires a long time to dilate the artery. This occurs in old people where the arteries tend to become rigid, *e. g.*, in atheroma. Cold also stimulates the arteries, so that they become less extensile. Within one hour after a tepid bath, the pulse assumes the anacrotic form (Fig 90, D) *G. v. Liebig*).

(3) When the blood stagnates in consequence of great diminution in the velocity of the blood stream, as occurs in **paralyzed limbs**, the volume of blood propelled into the artery at every sys-

FIG. 91.



I. II. III.

I, II, III, curves with anacrotic elevations *a*, in insufficiency of the aortic valves.

tole no longer produces the normal distention of the arterial coats, and anacrotic notches occur (Fig. 90. B).

(4) After **ligature** of an artery, when blood slowly reaches the peripheral part of the vessel through a relatively small collateral circulation, it also occurs. If the brachial artery be compressed so that the blood slowly reaches the radial, the radial pulse may become anacrotic. It often occurs in stenosis of the aorta, as the blood has difficulty in getting into the aorta (Fig. 90, C).

Recurrent Pulse.—If the radial artery be compressed at the wrist, the pulse beat reappears on the distal side of the point of pressure through the arteries of the palm of the hand (*Janaud, Neidert*). The curve is **anacrotic**, and the dicrotic wave is diminished, while the elastic elevations are increased.

(5) A special form of anacrotism occurs in cases of well-marked **insufficiency of the aortic valves.** Practically, in these cases, the aorta remains permanently open. The contraction of the left auricle causes in the blood a wave motion, which is at once propagated through the open mouth of the aorta into the large blood vessels. This wave is followed by the wave caused by the contraction of the hypertrophied left ventricle, but of course the former wave is not so large as the latter. In insufficiency of the aortic valves, the auricular wave occurs before the ventricular wave in the ascending part of the curve. The auricular is well marked only in the large vessels, for it soon becomes lost in the peripheral vessels. Fig. 91, I, was obtained from the carotid of a man suffering from *well-marked* insufficiency of the aortic valves, with considerable hypertrophy of the left ventricle and left auricle. The ascent is steep, caused by the force of the contracting heart. In the apex of the curve are two projections; A is the anacrotic auricular wave, and V is the ventricular wave. Fig. 91, II, is a curve obtained from the *subclavian artery* of the same individual. In the femoral artery the auricular projection is only obtained when the friction of the writing style is reduced to the minimum, and when it occurs it immediately precedes the beginning of the ascent (Fig. 86, III, *a*). The pulse curve, in cases of aortic insufficiency, is also characterized by (1) its considerable height; (2) the rapid fall of the lever from the apex of the curve, because a large part of the blood which is forced into the aorta regurgitates into the left ventricle when the ventricle relaxes; (3) not unfrequently a projection occurs at the apex, due to the elastic vibration of the tense arterial wall; (4) the dicrotic wave (R) is small compared with the size of the curve itself, because the pulse wave, owing to the lesion of the aortic valves, has not a sufficiently large surface to be reflected from (Fig. 85). The great height of the curve is explained by the large amount of blood projected into the aortic system by the greatly hypertrophied and dilated ventricle.

74. INFLUENCE OF RESPIRATION ON THE PULSE CURVE.—The **respiratory movements** influence the pulse (1) in a purely **physical** way. Stated broadly, the blood pressure rises during inspiration and falls during expiration, but when we consider the effect on the pulse curve, it is found that it varies with the depth, rapidity, and ease of respiration; (2) the res-

FIG. 92.



Influence of the respiration upon the pulse. J, inspiration; E, expiration.

piratory movements are accompanied by stimulation of the **vasomotor centre,** which produces variations of the blood pressure.

1. **Normal Respiration.**—Fig. 92 shows what sometimes, but by no means always, happens. During **inspiration,** owing to the dilatation of the thorax, more arterial blood is retained within the chest, while at the same time venous blood is sucked into the right auricle by the aspiration of the thorax; as a consequence of this, the tension in the arteries during inspiration must be less. The diminution of the chest during **expiration** favors the flow in the arteries, while it retards the flow of the venous blood in the venæ cavæ, two factors which raise the tension in the arterial system. The difference of pressure explains the difference in the form of the pulse curve obtained during inspiration and expiration, as in Fig. 92 and Fig. 83, I, III, IV, in which J indicates the part of the curve which occurred during inspiration, and E the expiratory portion. The following are the points of difference: (1) The greater distention of the arteries during expiration causes all the parts of the curve occurring during this phase to be higher; (2) the line of the ascent is lengthened during expiration, because the expiratory thoracic movement helps to increase the force of the expiratory wave; (3) owing to the increase of the pressure, the dicrotic wave must be less during expiration; (4) for the same reason the elastic elevations are more distinct and occur higher in the curve near its apex. The **frequency of the pulse** is slightly greater during expiration than during inspiration.

2. This purely mechanical effect of the respiratory movements is modified by the simultaneous stimulation of the **vasomotor centre** which accompanies these

movements. At the beginning of inspiration the blood pressure in the arteries is lowest, but it begins to rise during inspiration, and increases until the end of the inspiratory act, reaching its maximum at the beginning of expiration ; during the remainder of the expiration the blood pressure falls until it reaches its lowest level again at the beginning of inspiration (compare § 85, *f*); the pulse curves are similarly modified, and exhibit the signs of greater or less tension of the arteries corresponding to the phases of the respiratory movements. [There is, as it were, a displacement of the blood-pressure curve relative to the respiratory curve.]

Forced Respiration.—With regard to the effect produced on the pulse curve by a powerful expiration and a forced inspiration, observers are by no means agreed.

Valsalva's Experiment.—Strong expiratory pressure is best produced by closing the mouth and nose, and then making a great expiratory effort (§ 60); *at first* there is increase of blood pressure, while the form of the pulse waves resembles that which occurs in ordinary expiration, the dicrotic wave being less developed; but, when the forced pressure is long continued, the pulse curves have all the signs of diminished tension. This effect is due to the action of the vasomotor centre, which is affected reflexly from the pulmonary nerves. We must assume

FIG. 93.



C, curve from the carotid, and R, radial, during Müller's experiment; C_1 and R_1, during Valsalva's experiment. Curves written on a vibrating surface.

that forced expiration, such as occurs in Valsalva's experiment, acts by *depressing* the activity of the vasomotor centre (§ 371, II). Coughing, singing, and declaiming act like Valsalva's experiment, while the frequency of the pulse is increased at the same time. *After* the cessation of Valsalva's experiment, the blood pressure *rises* above the normal state (*Sommerbrodt*), almost as much as it fell below it; the normal condition being restored within a few minutes (*Lenzmann*).

Müller's Experiment.—When the thorax is in the expiratory phase, close the mouth and nose, and take a deep inspiration so as forcibly to expand the chest (§ 60). At first the pulse curves have the characteristic signs of diminished tension, viz., a higher and more distinct dicrotic wave; then the tension can, by nervous influences, be increased, just as in Fig. 93, where C and R are tracings taken from the carotid and radial arteries respectively, during Müller's experiment, in which the dicrotic waves, *r*, *r*, indicate the diminished tension in the vessels. In C_1 and R_1, taken from the same person during Valsalva's experiment, the opposite condition occurs.

Compressed Air.—On *expiring* into a vessel resembling a spirometer (see Respiration), (Waldenburg's respiration apparatus), and filled with compressed air, the same result is obtained as in

Valsalva's experiment—the blood pressure falls and the pulse beats increase; conversely, the *inspiration* from this apparatus of air under less pressure acts like Müller's experiment, *i. e.*, it increases the effect of the inspiration, and afterward increases the blood pressure, which may either remain increased on continuing the experiment, or may fall (*Lenzmann*).

The *inspiration* of compressed air diminishes the mean blood pressure (*Zuntz*), and the after-effect continues for some time. The pulse is more frequent both during and after the experiment. *Expiration* in rarefied air increases the blood pressure. The effects which depend upon the action of the nervous system do not occur to the same extent in all cases. Exposure to compressed air in a **pneumatic cabinet** lowers the pulse curve, the elastic vibrations become indistinct, and the dicrotic wave diminishes and may disappear (*v. Vivenot*). The heart's beat is slowed and the blood pressure raised (*Bert*). Exposure to rarefied air causes the opposite result, which is a sign of diminished arterial tension.

Pulsus Paradoxus.—Under pathological conditions, especially when there is union of the heart or its large vessels with the surrounding parts, the pulse during inspiration may be extremely

FIG. 94.



Pulsus paradoxus (after *Kussmaul*). E, expiration; J, inspiration.

small and changed, or may even be absent (Fig. 94). This condition has been called **pulsus paradoxus** (*Griesinger, Kussmaul*). It depends upon a diminution of the arterial lumen during the inspiratory movement. Even in health, it is possible by a change of the inspiratory movement to produce the p. paradoxus (*Riegel, Sommerbrodt*).

75. **INFLUENCE OF PRESSURE ON THE PULSE CURVE.**—It is most important to know the **actual pressure** which is applied to an artery while a sphygmogram is being taken. The changes affect the *form* of the curve as well as the relation of individual parts thereof. In Fig. 95, *a*, *b*, *c*, *d*, *e* are radial curves; *a* was taken with a minimal pressure, *b* with 100, *c* 200, *d* 250, and *e* 450 grams pressure, while A, B, C, D show the relations as to the time of occurrence of the individual phenomena where the weight was successively increased. The study of these curves yields the following results: (1) When the weight is small, the dicrotic wave is relatively less; the whole curve is high; (2) with a moderate weight (100 to 200 grams) the

FIG. 95.



Various forms of curves (radial) obtained by gradually increasing the pressure.

dicrotic wave is best marked, the whole curve is somewhat lower; (3) on increasing the weight the size of the dicrotic wave again diminishes; (4) the fine elastic vibrations preceding the dicrotic wave appear first when a weight of 220 to 300 grams is used; (5) the rapidity of the pulse changes with increasing weight, the time occupied by the ascent becoming shorter, the descent becoming longer; (6) the height of the entire curve decreases as the weight increases. In every sphygmogram the pressure under which it was obtained ought always to be stated. In Fig. 95, A, B are curves obtained from the radial artery of a healthy student. The pressure exerted upon the artery for A was 100; B, 220 grms. (1 vibration = 0.01613 sec.).

If pressure be exerted upon an artery for a long time, the strength of the pulse is gradually increased. If, after subjecting an artery to considerable pressure, a lighter weight be used, not unfrequently the pulse curve assumes the form of a dicrotic pulse, owing to the greater development of the dicrotic elevation. When strong pressure is applied, the blood is forced to find its way through collateral channels. When the chief artery ceases to be compressed, the total area is, of course, considerably and suddenly enlarged, which results in the production of a dicrotic elevation. Fig. 83, X, is such a dicrotic curve obtained after considerable pressure had been applied to the artery.

76. TRANSMISSION OF PULSE WAVES.—The pulse wave proceeds throughout the arterial system from the root of the aorta, so that the pulse is felt sooner in parts lying near the heart than in the peripheral arteries. E. H. Weber calculated the **velocity of the pulse wave** as 9.240 metres [28½ feet] per second, from the difference in time between the pulse in the external maxillary artery and the dorsal artery of the foot. Czermak showed that the elasticity was not equal in all the arteries, so that the velocity of the pulse wave cannot be the same in all. The pulse wave is propagated more slowly in the arteries with soft extensile walls than in arteries with resistant and thick walls, so that it is transmitted more rapidly in the arteries of the lower extremities than in those of the upper. It is still slower in children.

77. PULSE WAVE IN ELASTIC TUBES.—Waves similar to the pulse may be produced in elastic tubes. (1) According to E. H. Weber the velocity of propagation of the waves is 11.205 metres per sec.; according to Donders, 11–13 metres (34–42 feet). (2) According to E. H. Weber increased internal tension causes only an inconsiderable decrease; Rive found a great decrease; Donders found no obvious difference; while Marey found an increased velocity. (3) Donders found the velocity to be the same in tubes 2 mm. in diameter as in wider tubes, but Marey believes that the velocity varies when the diameter of the tube changes. (4) The velocity is less, the smaller the elastic coefficient. (5) The velocity increases with increased thickness of the wall, while it diminishes when the specific gravity of the fluid increases.

Moens has recently formulated the following **laws** as to the velocity of propagation of waves in elastic tubes: (1) It is inversely proportional to the square root of the specific gravity of the fluid; (2) it is as the square root of the thickness of the wall, the lateral pressure being the same; (3) it is inversely as the square root of the diameter of the tube, the lateral pressure being the same; (4) it is as the square root of the elastic coefficient of the wall of the tube, the lateral pressure being the same (*Valentin*).

(A) The velocity of the wave is 11.809 metres per second.

(B) The *intra-vascular pressure* has a decided influence on the velocity: thus, in the tube, A, with 18 cm. (Hg.) pressure, the velocity per metre = 0.093 second, while with 21 cm. pressure (Hg.) = 0.095 second per metre.

(C) The *specific gravity of the liquid* influences the velocity of the pulse wave. In *mercury* the wave is propagated four times more slowly than in water.

(D) The velocity in a tube which is more rigid and not so extensile is greater than in a tube which is easily distended.

78. VELOCITY OF THE PULSE WAVE IN MAN.—Landois obtained the following results in a student: Difference between carotid and radial = 0.074 second (the distance being taken as 62 centimetres); carotid and femoral = 0.068 second; femoral (inguinal region) and posterior tibial = 0.097 second (distance estimated at 91 centimetres). [Waller obtained between the heart and carotid 0.10 second; heart and femoral, 0.18 sec.; heart and dorsalis pedis, 0.22.]

The **velocity of the pulse wave** in the arteries of the upper extremities = 8.43 metres per second, and in those of the lower extremity 9.40 metres per second, [*i.e.*, about 30 feet per second]. The velocity is greater in the less extensile arteries of the lower extremities than in those of the upper limb. For the same reason it is less in the peripheral arteries and in the yielding arteries of children (*Czermak*).

E. H. Weber estimated the velocity at 9.24 metres per second; Garrod, 9–10.8 metres; Grashey, 8.5 metres; Moens, 8.3 metres, and with diminished pressure during Valsalva's experiment 7.3 metres (§ 60, § 74).

Influencing Conditions.—In animals, hemorrhage, slowing of the heart produced by stimulation of the vagus (*Moens*), section of the spinal cord, deep morphia narcosis, and dilatation of the blood vessels by heat, produce *slowing* of the velocity, while stimulation of the spinal cord *accelerates* it (*Grunmach*).

The **wave length of the pulse wave** is obtained by multiplying the duration of the inflow of blood into the aorta = 0.08 to 0.09 second (§ 51), by the velocity of the pulse wave.

Method.—Place the knobs of two tambours (Fig. 76) upon the two arteries to be investigated, or place one over the apex beat and the other upon an artery. These receiving tambours are connected with two registering tambours, as in Brondgeest's pansphygmograph (§ 67, Fig. 76), so that their writing levers are directly over each other, and so arranged as to write simultaneously on *one* vibrating plate attached to a tuning-fork. [Or they may be made to write upon a revolving cylinder, whose rate of movement is ascertained by causing a tuning-fork of a known rate of vibration to write under them.] The apparatus is improved by using rigid tubes and filling them with water, in which all impulses are rapidly communicated. In arteries which are distant from each

FIG. 96.



A, curve of radial artery on a vibrating surface (1 vib. = 0.01613 sec.); P, apex of curve; *e*, *e*, elastic vibrations; R, dicrotic wave. B, curve of same radial taken along with the heart beat; *v*, H, P, contraction of the ventricle.

other, or in the case of the heart and an artery, the two knobs of the receiving tambours may be connected by means of a **Y**-tube with *one* writing lever. In Fig 96, B is a curve from the radial artery taken in this way. In it *v* H P indicates contraction of the ventricle; H, the apex of the ventricular contraction; P, the primary apex of the radial curve; *v*, the beginning of the ventricular contraction; *p*, of the radial pulse. A is the curve of the radial artery alone. From these curves it is evident that in this instance nine vibrations occur between the beginning of the ventricular contraction and the beginning of the pulse in the radial artery = 0.15 sec.

In Fig. 97 the difference between the carotid and the posterior tibial pulse = 0.137 sec.

Pathological.—In cases of *diminished extensibility* of the arteries, *e. g.*, in atheroma (§ 77, D), the pulse wave is propagated more rapidly. Local dilatations of the arteries, as in **aneurisms**, cause a retardation of the wave, and a similar result arises from local constrictions. Relaxation of the walls of the vessels in high fever retards the movement (*Hamernik*).

FIG. 97.

Curves of the carotid and posterior tibial taken simultaneously with Brondgeest's pansphygmograph writing upon a vibrating plate attached to a tuning-fork. The arrows indicate the identical moment of time in each curve.

79. **OTHER PULSATILE PHENOMENA.**—1. In the **mouth and nose**, when they are filled with air, and the glottis closed, pulsatile phenomena (due to the arteries in their soft parts) may be found communicating a movement to the contained air. The curves obtained are relatively small, and closely resemble the curve of the carotid. A similar pulse is obtained in the tympanum with intact membrana tympani, and when the soft parts of the tympanum are congested (*Schwartze*, *Tröltsch*).

2. **Entoptical Pulse.**—After violent exercise, an illumination, corresponding to each pulse beat, occurs on a dark optical field. When the optical field is bright, an analogous darkening occurs. The ophthalmoscope occasionally reveals pulsation of the retinal arteries (*Jäger*), which becomes marked in insufficiency of the aortic valves.

3. **Pulsatile Muscular Contraction.**—The *orbicularis palpebrarum muscle* contracts under similar conditions synchronously with the pulse; and it is perhaps due to the pulse beat exciting the sensory nerves reflexly. The Brothers Weber found that not unfrequently, while walking, the step and pulse gradually and involuntarily coincide.

4. When the legs are crossed as one sits in a chair, the leg which is supported is raised with each pulse beat, and it gives also a second or dicrotic elevation.

5. If, while a person is quite quiet, the incisor teeth of the lower jaw be made just to touch the upper incisors very lightly, we detect a double beat of the lower against the upper teeth, owing to the pulse beat in the external maxillary artery raising the lower jaw. The second elevation is due to the closure of the semilunar valves, and not to a dicrotic wave.

6. **Brain and Fontanelles.**—The large arteries at the base of the *brain* communicate a movement to it, while similar movements occur with respiration—rising during expiration and falling during inspiration. These movements are visible in the *fontanelles of infants*. The respiratory movements depend upon variations in the amount of blood in the veins of the cranial cavity, and also upon the respiratory variations of the blood pressure.

7. Among **pathological** phenomena are (*a*) the beating in the epigastrium, *e. g.*, in the hypertrophy of the right or left ventricle, caused, it may be, by deep insertion of the diaphragm, and it may be, partly, by the beating of a dilated abdominal aorta or cœliac axis.

(*b*) **Aneurisms** or *abnormal dilatations* of the arteries cause an abnormal pulsation, while they

FIG. 98.



I. Elastic support for registering the molar motions of the body—K, wooden box; B, feet of patient; *p*, cardiograph; *a b*, elastic tubing. II. Vibration curves of a healthy person. III. Curve obtained from a patient with insufficiency of the aortic valves and great hypertrophy of the heart.

produce a *slowing in the velocity of the pulse wave* in the corresponding artery. Hence the pulse appears later in such an artery than in the artery on the healthy side. *Hypertrophy and dilatation of the left ventricle* cause the arteries near the heart to pulsate strongly. In the analogous condition of the right ventricle, the beat of the pulmonary artery may be seen and felt in the second left intercostal space.

80. **VIBRATIONS OF THE BODY DUE TO THE HEART.**—The beating of the heart and large arteries communicates vibrations to the body as a whole; the vibration being not simple but compound. Gordon was the first to represent this pulsatory vibration graphically. If a person be placed in an erect attitude in the scale-pan of a large balance, the index oscillates, and its movements coincide with the heart's movements.

Method.—Take a long four-sided box, K, open at the top, and arrange several coils, *a*, *b*, of stout caoutchouc tubing round one end (Fig. 98). A wooden board, B, is so placed that it rests with one end on the caoutchouc tubing, and with the other on the narrow end of the box. The person to be experimented upon, A, stands vertically and firmly on this board. A receiving tambour, *p*, is placed against the surface of the board next the elastic tube, which registers the vibrations of the foot support. Fig. III is a curve showing such vibrations, each heart beat being followed in this case by four oscillations. To ascertain the relations and causes of these vibrations, it is necessary to obtain, simultaneously, a tracing of the heart and the vibratory curve. For this purpose use the

two tambours of Brondgeest's pansphygmograph (§ 67, 76), placing one knob or pad over the heart and the other on the foot support, and allow the writing tambours to inscribe their vibrations on a glass plate attached to a tuning-fork.

In the *lower* or *cardiac impulse curve* (Fig. 99), the rapidly rising part is due to the ventricular systole. It contains eight vibrations (1 vib. = 0.01613 sec.). The beginning of the ventricular systole is indicated in the figure by -36, -3, -17.

If the corresponding numbers in the upper or *vibratory curve* are studied, it is obvious that *at the moment of ventricular systole the body makes a downward vibration, i. e.*, it exercises greater pressure upon the foot support. Gordon interprets his curve as giving exactly the opposite result. This downward motion, however, lasted only during five vibrations of the tuning-fork; during the last

FIG. 99.



The upper curve is the vibration curve of a healthy person, and the lower one a tracing of the apex beat.

three vibrations, corresponding to the systole, there is an ascent of the body corresponding to a less pressure upon the foot plate. When the ventricle empties itself, it undergoes a movement in a downward and outward direction—Gutbrodt's "reaction impulse."

In the *upper curve* analogous numbers are employed to indicate the vibrations occurring simultaneously, viz., -28, -11, -10. The closure of the semilunar valves is well marked in the three heart beats at 20, -20. This closure is indicated in analogous points in both curves, after which there is a descent of the foot support, and this corresponds to the downward propagation of the pulse wave through the aorta to the vessels of the feet.

Pathological.—In insufficiency of the aortic valves, as shown in Fig. 98, III, the vibration communicated to the body is very considerable.

81. THE BLOOD CURRENT.—Cause.—The closed and much-branched vascular system, whose walls are endowed with elasticity and contractility, is not only completely filled with blood, but it is **over-filled**. The total volume of the blood is somewhat greater than the capacity of the entire vascular system. Hence it follows that the mass of blood must exert **pressure** on the walls of the entire system, thus causing a corresponding dilatation of the elastic vascular walls (*Brunner*). This occurs during life; after death the muscles of the vessels relax, and fluid passes into the tissues, so that the blood vessels come to contain less fluid, and some of them may be empty.

If the blood were uniformly distributed throughout the vascular system and under the same pressure, it would remain in a position of equilibrium (as after death). If, however, the pressure be raised in one section of the tube, the blood will move from the part where the pressure is higher to where it is lower; so that the **blood current is a result of the difference of pressure** within the vascular system. If either the aorta or the venæ cavæ be suddenly ligatured in a living animal, the blood continues to flow, but gradually more slowly, until the difference of pressure is equalized throughout the entire vascular system.

The **velocity** of the current will be greater the greater the difference of pressure, and the less the resistance opposed to the blood stream.

The **difference of pressure which causes the current is produced by the heart.** Both in the systemic and pulmonary circulation the point of greatest pressure is in the root or beginning of the arterial system, while the point of

lowest pressure is in the terminal portion of the venous orifices at the heart. Hence the blood flows continually from the arteries through the capillaries into the venous trunks. The heart keeps up the difference of pressure required to produce this result; with each systole of the ventricles a certain quantity of blood is forced into the beginning of the arteries, while at the same time an equal amount flows from the venous orifices into the auricles during their diastole (*E. H. Weber*).

Donders showed that the action of the heart not only causes the difference of pressure necessary to establish a blood current, but also **raises the mean pressure** within the vascular system. The terminations of the veins at the heart are wider and more extensible than the arteries where they arise from the heart (Fig. 133). As the heart propels a volume of blood into the arteries equal to that which it receives from the veins, it follows that the arterial pressure must rise more rapidly than the venous pressure diminishes, since the arteries are not so wide nor so extensible as the veins. Thus the total pressure must also increase.

Cause of Continuous Flow.—The volume of blood expelled from the ventricles at every systole would give rise to a *jerky* or intermittent movement of the blood stream (1) if the tubes had rigid walls, as in such tubes any pressure exerted upon their contents is propagated momentarily throughout the length of the tube, and the motion of the fluid ceases when the propelling force ceases; (2) the flow would also be intermittent in character in elastic tubes if the time between two successive systoles were longer than the duration of the current necessary for the compensation of the difference of pressure caused by the systole. If the time between two successive systoles be shorter than the time necessary to equilibrate the pressure, the current will become **continuous**, provided the resistance at the periphery of the tube be sufficiently great to bring the elasticity of the tube into action. The more rapidly systole follows systole, the greater the difference of pressure becomes, and the more distended the elastic walls. Although the current thus produced is continuous, a sudden rise of pressure is caused by the forcing in of a mass of blood at every systole, so that with every systole there is a sudden jerk and *acceleration of the blood stream* corresponding to the pulse (compare § 64).

The sudden jerk-like acceleration of the blood current is propagated throughout the arterial system with the velocity of the pulse wave; both phenomena are due to the same fundamental cause. Every pulse beat causes a temporary rapid progressive acceleration of the particles of the fluid. But just as the form movement of the pulse is not a simple movement, neither is the pulsatile acceleration a simple acceleration. It follows the course of the development of the pulse wave. The pulse curve is the graphic representation of the pulsatory acceleration of the blood stream. Every rise in the curve corresponds to an acceleration, every depression to a retardation of the current.

[**Method: Rigid and Elastic Tubes.**—These facts are easily demonstrated. Tie a Higginson's syringe to a piece of an ordinary gas pipe. On forcing water through the tube, by compressing the elastic pump, the water will flow out at the other end of the tube in jets, while during the intervals of pulsation no water will flow out. As the walls of the tube are rigid, just as much fluid flows out as is forced into the tube. If a similar arrangement be made, and a long elastic tube be used, a **continuous** outflow is obtained, provided the pulsations occur with sufficient rapidity and the length of the tube, or the resistance at its periphery, be sufficient to bring the elasticity of the tube into action. This can be done by putting a narrow cannula in the outflow end of the tube, or by placing a clamp on it so as to diminish the exit aperture. This apparatus converts the intermittent flow into a continuous current.] The fire-engine is a good example of the conversion of an intermittent inflow into a uniform outflow. The air in the reservoir is in a state of elastic tension, and it represents the elasticity of the vascular walls. When the pump is worked slowly, the outflow of the water occurs in jets, and is interrupted. If the pumping movement be sufficiently rapid, the compressed air in the reservoir causes a continuous outflow, which is distinctly accelerated at every movement of the pump. [The ordinary spray-producer is another good example.]

[Thus, there are two factors—a **central** one, the **heart**,—and a **peripheral**

one, the amount of **resistance** in the arterioles. Either or both may be varied, and as this is done, so will the pressure and velocity vary.]

Current in the Capillaries.—In the *capillaries* the pulsatile acceleration of the current ceases with the extinction of the pulse wave. The great resistance which is offered to the current toward the capillary area causes both to disappear. It is only when the capillaries are greatly dilated, and when the arterial blood pressure is high, that the pulse is propagated through the capillaries into the beginning of the veins. A **venous pulse** is observed in the veins of the sub-maxillary gland after stimulation of the chorda tympani nerve, which contains the vaso-dilator nerves for the blood vessels of this gland. If the finger be constricted with an elastic band, so as to hinder the return of the venous blood, and to increase the arterial blood pressure, while at the same time dilating the capillaries, an intermittent increased redness occurs, which corresponds with the well-known throbbing sensation in the swollen finger. This is due to the **capillary pulse.** [Roy and Graham Brown found that pulsatile phenomena were produced in the capillaries by increasing the extra-vascular pressure (§ 86). Quincke called attention to the capillary pulse, which can often be seen under the finger nails. Extend the fingers completely, when a whitish area appears under the nails. A red area near the free margin of the nail advances and retires with each pulse beat. It is well marked in some diseased conditions of the heart, especially in incompetence of the aortic valves, and is probably produced by increased extra-vascular pressure.]

82. **SCHEMATA OF THE CIRCULATION.**—E. H. Weber constructed a scheme of the circulation. It consisted of a force pump with properly arranged valves to represent the heart, portions of gut for the arteries and veins, and a piece of glass tubing containing a piece of sponge to represent the capillaries. Various schemes have been invented, including the very complicated one of Marey [the extremely ingenious one of v. Thanhoffer, and the thoroughly practical one of Rutherford].

83. CAPACITY OF THE VENTRICLES.—Since the right and left ventricles contract simultaneously, and just the same volume of blood passes through the pulmonary as through the systemic circulation, it follows that the right ventricle must be just as capacious as the left. The capacity of the ventricles has been estimated in the following ways:—

Methods.—(1) **Directly,** by filling the *dead* relaxed ventricle with blood or an injection mass. This method is unsatisfactory and inaccurate.

(2) **Indirectly.** Volkmann (1850) estimated it thus: Estimate the sectional area of the aorta, and the velocity of the blood stream in it (§ 1). From this calculate the amount of blood passing through the aorta in the unit of time. As the total quantity of blood in the body is known ($= \frac{1}{13}$ of the body weight), we can easily calculate how long this takes to flow through the aorta. We must also know the number of beats during the time of the circulation. From these data, and from experiments on animals, Volkmann estimated the volume of blood discharged at each systole by the ventricle to be $\frac{1}{400}$ of the body weight. For a man weighing 75 kilos. this is 187.5 grams. This estimate still leaves much to be desired.

Place calculates it in the following manner: A man uses about 500 litres of O in 24 hours. To absorb this into the venous blood (which contains about 7 vols. per cent. less O than arterial), about 7000 litres of blood must pass through the lungs in 24 hours. If one calculates 100,000 heart beats in 24 hours, then at each systole only 70 cubic centimetres are discharged.

84. ESTIMATION OF THE BLOOD PRESSURE.—(A) In Animals: (1) Methods of Hales.—The Rev. Stephen Hales (1727) was the first to introduce a long glass tube into a blood vessel in order to estimate the blood pressure by measuring the height of the column of blood.

The tube was provided at its lower end with a copper tube bent at a right angle (Pitot's tube). [The tube he used was one-sixth of an inch bore and about 9 feet long, and was inserted into the femoral artery of a horse. The height to which the blood rose in the tube was noted, as well as the oscillations that occurred with every pulsation. From the height of the column of fluid he calculated the force of the heart.]

(2) **The Hæmadynamometer of Poiseuille** (1828).—This observer used a **U**-shaped tube partially filled with mercury—a **manometer**—which was brought into connection with a blood vessel by means of a *rigid* tube. [The mercury oscillated with every pulsation, and the extent of

the oscillations was read off by means of a scale attached to the bent tube. He called the instrument a *hæmädynamometer*.]

[(3) **Vierordt** used a tube 5 or 6 feet long, and filled it with a solution of sodium carbonate, thus preventing much blood from entering the tube, while at the same time the soda solution prevented the coagulation of the blood.]

FIG. 100.



I. Scheme of C. Ludwig's kymograph. II. Fick's spring kymograph.

FIG. 101.



Ludwig's improved revolving cylinder, *R*, moved by the clockwork in the box *A*, and regulated by a Foucault's regulator placed on the top of the box. The disk, D, moved by the clockwork, presses upon the wheel, *n*, which can be raised or lowered by the screw, *L*, thus altering the position of *n* on *D*, so as to cause the cylinder to rotate at different rates. The cylinder itself can be raised by the handle, *U*. On the left side of the figure is a mercurial manometer. When the cylinder is used, it is covered with smoked smooth paper.

(4) **C. Ludwig's Kymograph.**—C. Ludwig employed a **U**-shaped manometer, but he placed a light float (Fig. 100, *d*, *s*) upon the surface of the mercury in the open limb of the tube. A writing style, *f*, placed transversely on the free end of the float, inscribed the movements of the float—and, therefore, of the mercury—upon a cylinder, *c*, caused to revolve at a uniform rate. This apparatus *registered* the height of the blood pressure, as well as the pulsatile and other oscillations occurring in the mercury. Volkmann called this instrument a **kymograph** or "wave writer." The difference of the height of the column of mercury, *c*, *d*, in both limbs of the tube indicates the pressure within the vessel. If the height of the column of mercury be multiplied by 13.5, this gives the height of the corresponding column of blood. Setschenow placed a stop-cock in the lower bend, *h*, of the tube. If this be closed so as just to permit a small aperture of communication to remain, the pulsatile vibrations no longer appear, and the apparatus indicates the *mean pressure*.

By the term *mean pressure* is meant the limit of pressure, above and below which the oscillations occurring in an ordinary blood-pressure tracing range. [Briefly, it is the *average* elevation of the mercurial column.]

In a **blood-pressure tracing**, such as Fig. 102, each of the **smaller waves** corresponds to a **heart beat**, the ascent corresponds to the systole and the descent to the diastole. The **large undulations** are due to the **respiratory movements**. It is clear that the heart beat is expressed as a simple rise and fall (Fig. 102), so that the curve of the heart beat obtained with a mercurial kymograph differs from a sphygmographic curve.

Faults of a Mercurial Manometer.—A perfect recording instrument ought to indicate the height of the blood pressure, and also the size, form, and duration of any wave motion communicated to it. The mercurial manometer does not give the true form of the pulse wave, as the mercury, when once set in motion, executes vibrations of its own, owing to its great inertia, and thus the finer movements of the pulse wave are lost. Hence a mercurial kymograph is used for registering the blood pressure, and not for obtaining the *exact* form of the pulse wave. Instruments with less inertia, and with no vibrations peculiar to themselves, are required for this purpose.

FIG. 102.



Blood-pressure curve of the carotid of a dog obtained with a mercurial manometer. $O-x$ = line of no pressure, zero line, or abscissa; $y-y'$ is the blood-pressure tracing with small waves, each one caused by a heart beat, and the large waves due to the respiration. A millimetre scale shows the height of the pressure in millimetres of mercury.

[**Method.**—Expose the carotid of a chloralized rabbit, and isolate a portion of the vessel between two ligatures, or two spring clamps. With a pair of scissors make an oblique slit in the artery, and into it tie a straight glass **cannula**, directing the pointed end of the cannula toward the heart. Fill the cannula with a saturated solution of sodium carbonate, taking care that no air bubbles enter, and connect it with the **lead tube** which goes to the ascending limb of the manometer. The tube which connects the artery with the manometer must be flexible and yet inelastic, and a lead tube is best. It is usual to connect a **pressure bottle**, containing a saturated solution of sodium carbonate, by means of an elastic tube, with the tube attached to the manometer. This bottle can be raised or lowered. Before beginning the experiment, raise the pressure bottle until there is a *positive* pressure of mercury in the manometer about equal to the estimated blood pressure, and then clamp the tube of the pressure bottle where it joins the lead tube. This positive pressure prevents the escape of blood from the artery into the solution of sodium carbonate. When all is ready, the ligature on the *cardiac* side of the cannula is removed, and immediately the float begins to oscillate and inscribe its movements upon the recording surface. The fluid within the artery exerts pressure latterly upon the sodium carbonate solution, and this in turn transmits it to the mercury. Peptones,

or rather the albumoses, when injected into the blood keep it from coagulating (p. 73). Roy finds that oil may take the place of sodic carbonate.]

[**Precautions.**—In taking a blood-pressure tracing, after seeing that the apparatus is perfect, care must be taken that the animal is perfectly quiescent, as every movement causes a rise of blood pressure. This may be secured by giving curara and keeping up artificial respiration, or by the carefully regulated inhalation of ether. When a drug is to be injected to test its action, if it be introduced into the jugular vein it is apt to affect the heart directly. This may be avoided by injecting it into a vein of the leg, or under the skin. The solution of the drug must not contain particles which will block up the capillaries. Care should also be taken that the carbonate of soda does not flow back into the artery.]

[**Continuous Tracing.**—When we have occasion to take a tracing for any length of time, it must be written upon a strip of paper which is moved at a uniform rate in front of the writing style on the float (Fig. 100). Various arrangements are employed for this purpose, but it is usual to cause a cylinder to revolve, so as to unfold a roll or riband of paper placed on a movable bobbin. As the cylinder revolves, it gradually winds off the strip of paper, which is kept applied to the revolving surface by ivory friction wheels. In Hering's complicated kymograph a long strip of smoked paper is used. The writing style may consist of a sable brush, or a fine glass pen filled with aniline blue dissolved in water, to which a little alcohol and glycerine are added.]

[In order to measure the height of the pressure, we must know the position of the **abscissa** or line of no pressure, and it may be recorded at the same time as the blood pressure, or afterward. In Fig. 102 $O-x$ is the zero line or the abscissa, and the height of the vertical lines or **ordinates** may be measured by the millimetre scale on the left of the figure. The height of the blood pressure is obtained by drawing ordinates from the curve to the abscissa, measuring their length, and **multiplying by two.**]

(5) **Spring Kymograph.—A. Fick** (1864) uses a "hollow spring kymograph" on the principle of Bourdon's manometer (Fig. 100, II).

A hollow **C**-shaped metallic spring, F, is filled with alcohol. One end of the hollow spring is closed, and the other end, covered by a membrane, is brought into connection with a blood vessel by a junction piece filled with a solution of sodium carbonate. As soon as the communication with the artery is opened, the pressure rises, and the spring, of course, tends to straighten itself. To the closed end, *b*, there is fixed a vertical rod attached to a series of levers, *h*, *i*, *k*, *e*, one of which writes its movements upon a surface moving at a uniform rate. The blood pressure and the periodic variations of the pulse are both recorded, although the latter is not done with absolute accuracy.

[**Hering** improved Fick's instrument (Fig. 103). *a*, *b*, *c*, is the hollow spring filled with alcohol, and communicating at *a* with the lead tube, *d*, passing to the cannula in the artery. To *c* is attached a series of light wooden levers with a writing style, *s*. The lower part of 4 dips into a vessel, *e*, filled with oil or glycerine, which serves to damp the vibrations of the levers. At *f* is a syringe communicating with the tube, *d*, filled with solution of sodic carbonate, and used for regulating the amount of fluid in the tube connecting the manometer with the blood vessel. The whole apparatus can be raised or lowered on the toothed rod, *h*, by means of the mill-head opposite, *g*, to which all the parts of the apparatus are attached.]

FIG. 103.



Fick's spring manometer, as improved by Hering.

(6) **Fick's Flat Spring Kymograph.**—The narrow tube *a*, *a* (1 mm. diam.) is placed in connection with a blood vessel by means of the cannula, *c*, and over its vertical expanded end, A, is fixed a caoutchouc membrane, with a projecting point, *s*, which presses against a horizontal spring, F, joined to a writing lever, H, by an intermediate piece, *b*. The whole is held in the metallic frame, R R (Fig. 104). In order to estimate the absolute pressure, the instrument must be compared previously with a mercurial manometer.

(B) **In man** the blood pressure may be estimated by means of (1) a properly

graduated sphygmograph (§ 67). The pressure required to abolish the movement of the lever indicates approximately the vascular tension. The mean blood pressure in the radial artery is equal to 550 grams.

(2) **Sphygmomanometer of v. Basch.**—A capsule containing fluid was placed upon a pulsating artery, while the capsule itself communicated with a mercurial manometer. As soon as the pressure within the manometer *slightly exceeded* that within the artery, the artery was compressed so that a sphygmograph placed on a peripheral portion of the vessel ceased to beat. Both arrangements do not give the exact pressure within the artery; they only indicate the pressure which is required to compress the artery and the overlying soft parts. The pressure required to compress the arterial walls, however, is very small compared with the blood pressure. It is only 4 mm. Hg. V. Basch estimated the pressure in the radial artery of a healthy man to be 135 to 165 millimetres of mercury.

Variations.—**In children** the blood pressure increases with age, height and weight. In the superficial temporal artery, at 2 to 3 years, it is = 97 mm.; 12 to 13 years, 113 mm. Hg. (*A. Eckert*, c. § 100). The blood pressure is raised immediately after **bodily movements**; it is higher when a person is in the horizontal position than when sitting, and in sitting than in standing. After a cold as well as after a warm bath, the first effect is an increase of blood pressure and of the quantity of urine.

FIG. 104.

Fick's flat spring kymograph.

85. BLOOD PRESSURE IN THE ARTERIES.—The following results have been obtained by experiment on **systemic arteries**:—

(*a*) **Mean Blood Pressure.**—The blood pressure is very considerable, varying within pretty wide limits; in the large arteries of large mammals, and perhaps in man, it = 140 to 160 millimetres [5.4 to 6.4 inches] of a mercurial column.

The following results have been obtained, those marked thus * by Poiseuille, and those + by Volkmann:—

* Carotid, Horse, 161 mm.
\+ " " 122 to 214 mm.
* " Dog, 151 mm.
" " 130 to 190 mm. (*Ludwig*).
\+ " Goat, 118 to 135 mm.
\+ " Rabbit, 90 mm.
\+ Carotid, Fowl, 88 to 171 mm.
\+ Aorta of Frog, 22 to 29 mm.
\+ Gill artery of Pike, 35 to 84 mm.
Brachial artery of Man during an operation, 110 to 120 mm. (*Faivre*). Perhaps too low, owing to the injury.

E. Albert estimated the blood pressure by means of a manometer, placed in connection with the anterior tibial artery of a boy whose leg was to be amputated, to be 100 to 160 mm. Hg. The elevation with each pulse beat was 17 to 20 mm.; coughing raised it to 20 or 30 mm.; tight bandaging of the healthy leg, 15 mm.; while passive elevation of the body, whereby the hydrostastic action of the column of blood was brought into play, raised it 40 mm.

The pressure in the aorta of mammals varies from 200 to 250 mm. Hg. As a general rule, the blood pressure in large animals is higher than in small animals, because in the former the blood channel is considerably longer, and there is greater resistance to be overcome. In very young and in very old animals the pressure is lower than in individuals in the prime of life.

The arterial pressure in the **fœtus** is scarcely half that of the newly-born, while the venous pressure is higher, the difference of pressure between arterial and venous blood being scarcely half so great as in adult animals (*Cohnstein and Zuntz*).

The **arterial blood pressure is highest** in the aorta, and falls toward the smaller vessels, but the fall is very gradual, as shown in Fig. 105. A great fall takes place on passing from the area of the arterioles into the capillary area (C), while it is less in the venous area, and negative near the heart, as indicated in the dotted line passing below the abscissa, so that the pressure is **lowest** in the cardiac ends of the venæ cavæ (compare Fig. 111).

(*b*) **Branching of the Blood Vessels.**—Within the large arteries the blood pressure diminishes relatively little as we pass toward the periphery, because the difference of the resistance in the different sections of large tubes is very small. As soon, however, as the arteries begin to divide frequently, and undergo a considerable diminution in their lumen, the blood pressure in them rapidly diminishes, because the propelling energy of the blood is much weakened, owing to the resistance which it has to overcome (§ 99).

FIG. 105.



Scheme of the blood pressure, in A, the arteries; C, capillaries, and V, veins; O–O, is the abscissa or line of no pressure; L. V., left ventricle, and R. A. right auricle; B. P., the height of the blood pressure.

(*c*) **Amount of Blood.**—The blood pressure is increased with *greater filling of the arteries*, and *vice versâ*; hence it—

Increases.	*Decreases.*
1. With increased and accelerated action of the heart;	1. During diminished and enfeebled action of the heart;
2. In plethoric persons;	2. In anæmic persons;
3. After considerable increase of the quantity of blood by direct transfusion, or after a copious meal.	3. After hemorrhage or considerable excretions from the blood by sweating, the urine, severe diarrhœa.

The blood pressure does not vary in the same proportion as the variations in the amount of blood. The vascular system, in virtue of its muscular tissue, has the property, within liberally wide limits, of accommodating itself to larger or smaller quantities of blood (*C. Ludwig and Worm Müller*, § 102, *d*). [In fact, a large amount of blood may be transfused without materially raising the blood pressure.] Small and moderate hemorrhages (in the dog to 2.8 per cent. of the body weight) have no obvious effect on the blood pressure. After a slight loss of blood the pressure may even rise (*Worm Müller*). If a large amount of blood be withdrawn, it causes a great fall of the blood pressure, and when hemorrhage occurs to 4–6 per cent. of the body weight, the blood pressure = 0. The transfusion of a *moderate* amount of blood does not raise the mean arterial blood pressure. There are important practical deductions from these experiments, viz., that the arterial blood pressure cannot be diminished directly by moderate bloodletting, and that the blood pressure is not necessarily high in plethoric persons.]

(*d*) **Capacity of the Vessels.**—The arterial pressure rises when the capacity of the arterial system is diminished, and conversely. The circularly-disposed smooth muscular fibres of the arteries are the chief agents concerned in this process. When they relax, the arterial blood pressure falls, and when they contract, it rises. These actions of muscular fibres are controlled and regulated by the action of the vasomotor nerves (§ 371).

(*e*) **Collateral Vessels.**—The arterial pressure within a *given area* of the vascular system must rise or fall according as the neighboring areas are diminished, whether by the application of pressure, or a ligature, or are rendered impervious, or as these areas dilate. The application of cold or warmth to limited areas of the body—increasing or diminishing the atmospheric pressure on a part—the paralysis or stimulation of certain vasomotor areas (§ 371), all produce remarkable variations in the blood pressure. [The effect of dilatation of a large vascular area on the arterial pressure is well shown by what happens when the blood vessels of the abdomen are dilated. Divide both vagi in the neck of a

rabbit and stimulate the **central end** of the **superior cardiac** or **depressor nerve**; after a few seconds, the blood vessels of the abdomen dilate, and gradually there is a steady fall of the blood pressure in the systemic arteries. Fig. 106 is a blood-pressure tracing showing the height of the blood pressure before stimulation, *a*. The stimulation was continued from *a* to *b*, and after a certain *latent* period there is a steady fall of the blood pressure.]

(*f*) **Respiratory Undulations.**—The arterial pressure also undergoes regular variations or undulations owing to the respiratory movements. These undulations are called *respiratory undulations* (Figs. 102 and 107). Stated broadly, during every strong inspiration the blood pressure rises, and during expiration it falls (§ 74). This is not quite correct. These undulations may be explained by the fact that, with every expiration, the blood in the aorta is subjected to an increase of pressure through the compressed air in the chest; with every inspiration, on the other hand, it is diminished, owing to the rarefaction of the air in the lungs acting

FIG. 106.



Kymographic tracing showing the effect on the blood pressure of stimulation of the central end of the depressor nerve in the rabbit after section of both vagi in the neck. Stimulation began at *a* and ended at *b*; *o* – *x*, the abscissa.

upon the aorta. Besides, the inspiratory movements of the chest aspirate blood from the venæ cavæ toward the heart, while expiration retards it, and thus influences the blood pressure. The undulations are most marked in the arteries lying nearest to the heart. The respiratory undulations are due in part to a stimulation or condition of excitement of the vasomotor centre, which runs parallel with the respiratory movements. This stimulation of the vasomotor centre causes the arteries to contract, and thus the blood pressure is raised. The variations in the pressure which depend upon a varying activity of the vasomotor centre are known as the "curves of Traube and Hering." Fig. 107 shows the carotid blood-pressure tracing of a dog. In this curve, when inspiration begins (I) the blood pressure is still falling slightly, but gradually rises until it reaches its maximum shortly after the beginning of expiration (E). [The maxima and minima of the respiratory and blood-pressure curves do not coincide exactly, but in addition the *number* of pulse beats is greater in the ascent than in the descent.

This is well marked in a blood-pressure tracing from a dog's carotid (Fig. 107), while in a rabbit this difference of the pulse rate is but slightly marked (Fig. 106). The smaller number of pulse beats during the descent, *i.e.*, during the greater part of expiration—is due to the activity of the cardio-inhibitory centre in the medulla oblongata. This is proved by the fact that section of both vagi in the dog causes the difference of pulse rate to disappear, while other conditions remain the same as before, except that the heart beats more rapidly. It would seem that, during the ascent, the cardio-inhibitory centre is comparatively inactive. It is clear, therefore, that the **respiratory** and **cardio-inhibitory centres** in the medulla oblongata act to a certain extent in unison, so that it is reasonable to suppose that other centres situated in close proximity to these may also act in unison with them, or, as it were, "in sympathy." As already stated, the **vaso-motor centre** is also in action during a particular part of the time.]

[If a dog be curarized and **artificial respiration** established, the respiratory undulations still occur, although in a modified form. In artificial respiration, the mechanical conditions, as regards the intra-thoracic pressure, are exactly the reverse of those which obtain during ordinary respiration. Air is forced into the chest during artificial respiration, so that the pressure within the chest is increased during inspiration, while in ordinary inspiration the pressure is diminished. Thus, the same mechanical explanation will not suffice for both cases.]

FIG. 107.



Carotid blood-pressure tracing of dog; vagi not divided; I = inspiration, E = expiration (*Stirling*).

If the artificial respiration be suddenly interrupted in a curarized animal, the blood pressure rises steadily and rapidly. This rise is due to the stimulation of the vasomotor centre in the medulla oblongata by the impure blood. This causes contraction of the small arteries throughout the body, which retards the outflow from the large arteries, and thus the pressure within them is raised. [Stated broadly, the arterial pressure depends on the **central** organ—the heart, and on the condition of the **peripheral** organs—the small arteries. Both are influenced by the nervous system. If the action of the vasomotor centre be eliminated by dividing the spinal cord in the cervical region, arrest of the respiration causes a very slight rise of the blood pressure; hence, it is evident that venous blood acts but slightly on the heart, or on any local peripheral nervous mechanism, or on the muscular fibres of the arteries. This experiment shows that it is the vasomotor centre which is specially acted upon by the venous blood.]

[**Traube-Hering Curves.**—The following experiment proves that the varying activity of the vasomotor centre suffices to produce undulations in the blood-pressure tracing. Take a dog, curarize it, expose both vagi and establish artificial respiration; then estimate the blood pressure in the carotid. After section of the vagi, the heart will continue to beat more rapidly, but it will be undisturbed by the cardio-inhibitory centre. Thus the central factor in the causation of the blood pressure remains constant. Suddenly interrupt the respiration, and, as already stated, the blood pressure will rise steadily and uniformly, owing to the stimu-

lation of the vasomotor centre by the venous blood. In this case the *peripheral* factor, or state of tension of the small arteries throughout the body, is influenced by the condition of the nerve centre, which controls their action. After a time, the blood-pressure tracing shows a series of bold curves higher than the original tracing. These can only be due to an alteration in the state of the small arteries, brought about by a condition of rythmical activity of the vasomotor centre. These curves were described and figured by Traube, and are called the Traube or Traube-Hering curves. As in other conditions, stimulation causes exhaustion, and soon the venous blood paralyzes the vasomotor centre and the small arteries relax, blood flows freely out of the larger arteries, and the blood pressure rapidly sinks. Variations in the blood pressure have been observed after a mechanical pump has been substituted for the heart, *i.e.*, after all respiratory movements have been set aside, so that the only factor which would account for the phenomena of the Traube-Hering curves is the variation in the peripheral resistance in the small arteries, determined by the condition of the vasomotor centre.]

Variations.—The respiratory undulations of the blood pressure become more pronounced the greater the force of the respirations, which produce greater variations of the intra-thoracic pressure. In man, the diminution of the pressure within the trachea is 1 mm. Hg. during tranquil inspiration]; while during forced respiration, when the respiratory passage is closed, it may be 57 mm. Conversely, during ordinary expiration, the pressure is increased within the trachea 2–3 mm. Hg., while during forced expiration, owing to the compression of the abdominal muscles, it may reach 87 mm. Hg.

Other Factors.—The increase of the blood pressure during inspiration, as well as the fall during expiration, must in part depend upon the pressure within the abdomen. As the diaphragm descends during inspiration, it presses upon the abdominal contents, including the abdominal vessels, whereby the blood pressure must be increased. The reverse effect occurs during expiration (*Schweinburg*). [Section of both phrenic nerves and opening of the abdominal cavity cause the respiratory undulations almost entirely to disappear. The respiratory undulations, therefore, depend in great part upon the changes of the abdominal pressure and the effect of these changes on the amount of blood in the abdominal vessels. When making a blood-pressure experiment, pressure upon the abdomen of the animal with the hand causes the blood pressure to rise rapidly.]

(*g*) **Variations with each Pulse Beat.**—The mean arterial pressure undergoes a variation with each heart beat or *pulse beat*, causing the so-called **pulsatory undulations** (Fig. 107). The mass of blood forced into the arteries with each ventricular systole causes a positive wave and an increase of the pressure corresponding with it, which, of course, corresponds in its development and in its form with the pulse curve.

In the large arteries, Volkmann found the increase during the heart beat to be $= \frac{1}{16}$ (horse) and $\frac{1}{17}$ (dog) of the total pressure.

None of the apparatus described in § 84 gives an exact representation of the pulse curve. They all show simply a rise and fall, a simple curve. The sphygmograph alone gives a true expression of the undulations in the blood pressure which are due to the heart beat.

(*h*) **Arrest of the Heart's Action.**— If the heart's action be arrested or interrupted by continued **stimulation of the vagus**, or by high positive respiratory pressure, the arterial blood pressure falls enormously, while it rises in the veins as the blood flows into them from the arteries to equilibrate the difference of pressure in the two sets of vessels. This experiment shows that, even when the difference of pressure is almost entirely set aside, the passive blood presses upon the arterial walls, *i.e.*, on account of the overfilling of the blood vessels a slight pressure is exerted upon the walls, even when there is no circulation. [As already stated, the arterial pressure depends on the condition of the central organ—the heart—and on the peripheral organs—the small arteries. If the action of the heart be arrested, then the blood pressure rapidly falls. Fig. 108 shows the effect on the blood pressure of arresting the action of the heart by stimulation of the **peripheral end of the vagus.** There is a sudden fall of the arterial pressure, as shown by the rapid fall of the curve from *a*.]

[**Variations in Animals.**—The pressure in the arterial system depends upon the balance between the inflow and outflow, *i. e.*, upon the heart and the state of the arterioles. But it is to be noted that the central factor, the heart, varies in different animals. In the rabbit, the heart normally beats rapidly, so that section of the vagi does not cause any great increase in the number of beats, nor is the blood pressure much raised thereby. In the dog, on the other hand, the beats are considerably increased by section of the vagi, while the blood pressure rises considerably. Atropin paralyzes the cardiac terminations of the vagus, and thereby trebles the number of heart beats in the dog, while it only raises it 25 per cent. in the rabbit; in man, again, the number may be doubled. As Brunton has shown, this difference of the initial number of heart beats and the action of the vagus have important relations to the action of drugs on the blood pressure. For example, if an intact rabbit be caused to inhale **amyl nitrite**, the blood pressure falls at once and rapidly, while in the dog the fall may be slight. The pulse of the dog, however, is greatly accelerated, so much so as to be nearly as rapid as that of the rabbit. In both, the vessels are dilated, but in the dog, notwithstanding this dilatation, which *per se* would cause the pressure to fall, the heart of the dog beats now so rapidly as to compensate for this, and thus keeps the blood pressure nearly normal; while the increased rate of beating in the rabbit is not sufficient for this purpose. If the vagi in the dog be divided, the subsequent inhalation of amyl nitrite causes a fall of blood pressure like that in the rabbit (*Brunton*).]

FIG. 108.



Blood-pressure tracing taken with a mercurial kymograph from the carotid of a rabbit. $o-x$, abscissa; stimulation of vagus begun at a and stopped at b.

[**Relation of Blood Pressure to Pulse Rate.**—When the blood pressure rises in an intact animal, as a rule the pulse rate falls, owing to stimulation of the vagus centre increasing the cardio-inhibitory action, while a fall of blood pressure is accompanied by an increase of the number of pulse beats for the opposite reason, the action of the medullary cardio-inhibitory centre being increased. But the blood pressure may be increased either by the action of the heart or the arterioles. If we divide the vagi the pulse beats more quickly, and in some animals the blood pressure rises; in this case, the rise in the two curves occurs together, and if the vagi be stimulated there is a sudden fall of the blood pressure, due to arrest of the heart's action, so that again the two curves are parallel. If the arterioles contract the blood pressure rises, but by and by the pulse rate falls, owing to the cardio-inhibitory action of the vagus; while, on the other hand, if the arterioles are dilated, the blood pressure falls, and the heart beats faster.

Thus, in both of these cases the pulse curve and blood-pressure curve run in opposite directions. These results only obtain when the vagi are intact (*Brunton*).]

[The increase in the pulse rate and blood pressure following section of the vagi do not run parallel. Both sooner or later reach a maximum, but the blood pressure gradually falls to or below the normal, while the pulse rate remains above the normal (*Münzel*).]

For the **effects of the nervous system** upon the blood pressure see § 371.

Pathological.—In persons suffering from granular or contracted kidney and sclerosis of the arteries, in lead poisoning, and after the injection of ergotin, which causes contraction of the small arteries, it is found, on employing the method of v. Basch, that the blood pressure is raised. It is also increased in cases of cardiac hypertrophy with dilatation, and by digitalis in cardiac affections, while it falls after the injection of morphia. The blood pressure falls in fever, a fact also indicated in the sphygmogram (§ 69), and it is low in chlorosis and phthisis.

86. BLOOD PRESSURE IN THE CAPILLARIES.—Methods.—Direct estimation of the capillary pressure is not possible, on account of the smallness of the capillary tubes. If a glass plate of known dimensions be placed on a portion of the skin rich in blood vessels, and if it be weighted until the capillaries become pale, we obtain approximately the pressure necessary to overcome the capillary pressure. N. v. Kries placed a small glass plate (Fig. 109) 2.5–5 sq. mm., on a suitable part of the skin, *e. g.*, the skin at the root of the nail on the terminal phalanx, or on the ear in man, and on the gum in rabbits. Into a scale pan attached to this, weights were placed until the skin became pale. The pressure in the capillaries of the hand, when the hand is raised, Kries found to be 24 mm. Hg.; when the hand hangs down, 54 mm. Hg.: in the ear, 20 mm., and in the gum of a rabbit, 32 mm.

Roy and Graham Brown compressed from below transparent vascular membranes against a glass plate by means of an elastic bag connected with a manometer, while the variations in the capillaries were observed from above by a microscope.

FIG. 109



V. Kries's apparatus for capillary pressure. *a*, square of glass.

Conditions influencing Capillary Pressure.—The capillary blood pressure in a given area **increases** (1) When the afferent small arteries dilate, so that the blood-pressure within the large arteries is propagated more easily into them. (2) By increasing the pressure in the small afferent arteries. (3) By narrowing the diameter of the veins leading from the capillary area. Closure of the veins may quadruple the pressure. (4) By increasing the pressure in the veins (*e. g.*, by altering the position of a limb). A **diminution** of the capillary pressure is caused by the opposite conditions.

Changes in the **diameter of the capillaries** influence the internal pressure. We have to consider the movements of the capillary wall itself as well as the pressure, swelling, and consistence of the surrounding tissues. The resistance to the blood stream is greatest in the capillary area, and it is evident that the blood in a long capillary must exert more pressure at the commencement than at the end of the capillary; in the middle of the capillary area the blood pressure is just about one-half of the pressure within the large arteries (*Donders*). The capillary pressure must also vary in different regions of the body. Thus, the pressure within the intestinal capillaries, in those constituting the glomeruli of the kidney, and in those of lower limbs when the person is in the erect posture, must be greater than in other regions, depending in the former cases partly upon the double resistance caused by two sets of capillaries, and in the latter case partly on purely hydrostatic causes.

87. BLOOD PRESSURE IN THE VEINS.—In the **large venous trunks** near the heart (innominate, subclavian, jugular) a mean **negative pressure** of about —0.1 mm. Hg. prevails (*H. Jacobson*). Hence, the lymph stream can flow unhindered. As the distance of the veins from the heart increases, there is a *gradual* increase of the lateral pressure; in the external facial vein (sheep) = + 3 mm.; brachial, 4.1 mm., and in its branches 9 mm.; crural, 11.4 mm. [The pressure is said to be *negative* when it is less than that of the atmosphere. The gradual fall of the blood pressure from the capillary area (C) to the venous area (V) is shown in Fig. 108, while within the thorax, where the veins terminate in the right auricle, the pressure is negative.]

Modifying Conditions.—(1) All conditions which *diminish the difference of pressure* between the arterial and venous systems *increase the venous pressure*, and *vice versâ*.

(2) General plethora of blood increases it; anæmia diminishes it.

(3) Respiration, or the **aspiration of the thorax**, affects specially the pressure in the veins near the heart; during inspiration, owing to the diminished tension, blood flows toward the chest, while during expiration it is retarded. The effects are greater, the deeper the respiratory movement, and these may be very great when the respiratory passages are closed (§ 60).

[When a vein is exposed at the root of the neck, it collapses during inspiration, and fills during expiration. The respiratory movements do not affect the venous stream in peripheral veins. The veins of the neck and face become distended with blood during crying, and on making violent expiratory efforts, as in blowing upon a wind instrument. Every surgeon is acquainted with the fact that air is particularly liable to be sucked into the veins, especially in operations near the root of the neck. This is due to the negative intra-thoracic pressure occurring during inspiration.]

(4) **Aspiration of the Heart.**—Blood is sucked or aspirated into the auricles when they dilate (p. 100), so that there is a double aspiration—one synchronous with inspiration, and the other, which is but slight, synchronous with the heart beat. There is a corresponding retardation of the blood stream in the venæ cavæ, caused by the contraction of the auricle (p. 99, *a*). The respiratory and cardiac undulations are occasionally observable in the jugular vein of a healthy person (§ 99).

FIG. 110.



Scheme of the blood pressure. H, heart; *a*, auricle; *v*, ventricle; A, arterial; C, capillary; and V, venous areas. The circle indicates the parts within the thorax; B. P., pressure in the aorta.

(5) Change in the *position* of the limbs or of the body, for hydrostatic reasons, greatly alters the venous pressure. The veins of the lower extremity bear the greatest pressure, while at the same time they contain most muscle (*K. Bardeleben*, § 65). Hence, when these muscles from any cause become insufficient, dilatations occur in the veins, giving rise to the production of **varicose veins.**

[Braune showed that the femoral vein under Poupart's ligament collapsed when the lower limb was rotated outward and backward, but filled again when the limb was restored to its former position. All the veins which open into the femoral vein have valves, which permit blood to pass into the femoral vein, but prevent its reflux. This mechanism acts to a slight degree as a kind of suction and pressure apparatus when a person walks, and thus favors the onward movement of the blood.]

[(6) **Muscular Movements.**—Veins which lie between muscles are compressed when these muscles contract, and as valves exist in the veins, the flow of blood is accelerated toward the heart; if the outflow of the blood be obstructed in any way, then the venous pressure on the distal side of the obstruction may be greatly increased. When a fillet is tied on the upper arm, and the person moves the muscles of the forearm, the superficial veins become turgid, and can be distinctly traced on the surface of the limb.]

(7) **Gravity** exercises a greater effect upon the blood stream in the extensile veins than upon the stream in the arteries. It acts on the distribution of the blood, and thus indirectly on the motion of the blood stream. It favors the emptying of descending veins, and retards the emptying of ascending veins, so that the pressure becomes less in the former and greater in the latter. If the position of the limb be changed, the conditions of pressure are also altered. If a person be suspended with the head hanging downward, the face soon becomes turgid, the position of the body favoring the inflow of blood through the arteries, and retarding the outflow through the veins. If the hand hangs down it contains more blood in the veins than if it is held for a short time over the head, when it becomes pale and bloodless. [As Lister has shown, the condition of the vessels

in the limb is influenced not only by the position of the limb, but also by the fact that a nervous mechanism is called into play.]

[**Ligature of the portal vein** causes congestion of the rootlets and dilatation of all the blood vessels in the abdomen; gradually nearly all the blood of the animal accumulates within its belly, so that, paradoxical as it may seem, an animal may be bled into its own belly. As a consequence of *sudden* and *complete* ligature of this vein, the arterial blood pressure gradually and rapidly falls, and the animal dies very quickly. If the ligature be removed before the blood pressure falls too much, the animal may recover. Schiff and Lautenbach regard the symptoms as due chiefly to the action of a poison, for when the blood of the portal vein in an animal treated in this way is injected into a frog, it causes death within a few hours, while the ordinary blood of the portal vein has no effect.]

[**Ligature of the Veins of a Limb.**—The effect of ligaturing or compressing *all* the veins of a limb is well seen in cases where a bandage has been applied too tightly. It leads to congestion and increase of pressure within the veins and capillaries, increased transudation of fluid through the capillaries, and consequent *œdema* of the parts beyond the obstruction. Ligature of *one* vein does not always produce œdema, but if several veins of a limb be ligatured, and the vasomotor nerves be divided at the same time, the rapid production of œdema is ensured. In pathological cases the pressure of a tumor upon a large vein may produce similar results (§ 203).]

88. BLOOD PRESSURE IN THE PULMONARY ARTERY.—Methods.—(1) **Direct estimation** of the blood pressure in the pulmonary artery by opening the chest was made by C. Ludwig and Beutner (1850). Artificial respiration was kept up, and the manometer was placed in connection with the left branch of the pulmonary artery. The circulation through the left lung of cats and rabbits was thereby completely cut off, and in dogs to a great extent interrupted. There was an additional disturbing element, viz., the removal of the elastic force of the lungs, owing to the opening of the chest, whereby the venous blood no longer flowed normally into the right heart, while the heart itself was under the full pressure of the atmosphere. The estimated pressure in the dog = 29.6; in the cat = 17.7; in the rabbit, 12 mm. Hg., *i. e.*, in the dog 3 times, the rabbit 4 times, and the cat 5 times less than the carotid pressure.

(2) Hering (1850) experimented upon a calf with ectopia cordis. He introduced glass tubes directly into the heart, by pushing them through the muscular walls of the ventricles. The blood rose to the height of 21 inches in the right tube, and 33.4 inches in the left.

(3) Faivre (1856) introduced a catheter through the jugular vein into the right ventricle, and placed it in connection with a recording tambour.

Indirect measurements have been made by comparing the relative thickness of the walls of the right and left ventricles, or the walls of the pulmonary artery and aorta.

Beutner and Marey estimated the relation of the pulmonary artery to the aortic pressure as 1 to 3; Goltz and Gaule as 2 to 5; Fick and Badoud found a pressure of 60 mm. in the pulmonary artery of the dog, and in the carotid 111 mm. Hg. The blood pressure within the pulmonary artery of a child is relatively higher than in the adult.

Elastic Tension of Lungs.—The lungs within the chest are kept in a state of distention, owing to the fact that a negative pressure exists on their outer pleural surface. When the glottis is open, the inner surface of the lung and the walls of the capillaries in the pulmonary air vesicles are exposed to the full pressure of the air. The heart and large blood vessels within the chest are not exposed to the full pressure of the atmosphere, but only to the pressure which corresponds to the atmospheric pressure *minus* the pressure exerted by the elastic traction of the lungs (§ 60). The trunks of the pulmonary artery and veins are subjected to the same conditions of pressure. The elastic traction of the lungs is greater the more they are distended. The blood of the pulmonary capillaries will, therefore, tend to flow toward the large blood vessels. As the elastic traction of the lungs acts chiefly on the thin-walled pulmonary veins, while the semilunar valves of the pulmonary artery, as well as the systole of the right ventricle, prevent the blood from flowing backward, it follows that *the blood in the capillaries of the lesser circulation must flow toward the pulmonary veins.*

If tubes with thin walls be placed in the walls of an elastic distensible bag, the lumen of these tubes changes according to the manner in which the bag enclosing them is distended. If the bag be directly inflated so as to increase the pressure within it, the lumen of the tubes is diminished (*Funke and Latschenberger*). If

the bag be placed within a closed space, and the tension within this space be diminished so that the bag thereby becomes distended, the tubes in its wall dilate. In the latter case—viz., by negative aspiration—the lungs are kept distended within the thorax, hence the blood vessels of the lungs containing air are wider than those of collapsed lungs (*Quincke and Pfeiffer, Bowditch and Garland, De Jäger*). Hence also, more blood flows through the lungs distended within the thorax than through collapsed lungs. The *dilatation* which takes place during *inspiration* acts in a similar manner. The negative pressure that obtains within the lungs during inspiration causes a considerable dilatation of the pulmonary veins, into which the blood of the lungs flows readily, while the blood under high pressure in the thick-walled pulmonary artery scarcely undergoes any alteration. The velocity of the blood stream in the pulmonary vessels is accelerated during inspiration (*De Jäger, Lalesque*). The blood pressure in the pulmonary circuit is raised when the lungs are inflated. Contraction of small arteries, which causes an increase of the blood pressure in the systemic circulation, also raises the pressure in the pulmonary circuit, because more blood flows to the right side of the heart.

The vessels of the pulmonary circulation are very distensible and their **tonus** is slight. [Occlusion of one branch of the pulmonary artery does not raise the pressure within the aorta. Even when one pulmonary artery is plugged with an embolon of paraffin, the pressure within the aortic system is not raised (*Lichtheim*). When a large branch of the pulmonary artery becomes impervious, the obstruction is rapidly compensated for, and this is not due to the action of the nervous system. The vasomotor system has much less effect upon the pulmonary blood vessels than upon those of the systemic circulation. The compensation seems to be due chiefly to the great distensibility and dilatation of the pulmonary vessels (*Lichtheim*).] We know little of the effect of physiological conditions upon the pulmonary artery. According to Lichtheim *suspension of the respiration* causes an increase of the pressure. [In one experiment he found that the pressure within the pulmonary artery was increased, while it was not increased in the carotid, and he regards this experiment as proving the existence of vasomotor nerves in the lung.]

During the act of great **straining**, the blood at first flows rapidly out of the pulmonary veins, and afterward ceases to flow, because the inflow of blood into the pulmonary vessels is interfered with. As soon as the straining ceases, blood flows rapidly into the pulmonary vessels (*Lalesque*).

Severini found that the blood stream through the lungs is greater and more rapid when the lungs are filled with air rich in CO_2 than when the air within them is rich in O. He supposes that these gases act upon the vascular ganglia within the lung, and thus affect the diameter of the vessels.

Pathological.—Increase of the pressure within the area of the pulmonary artery occurs frequently in man, in certain cases of heart disease. In these cases the second pulmonary sound is always accentuated, while the elevation caused thereby in the cardiogram is always more marked and occurs earlier (§ 52). Electrical and mechanical stimulation of abdominal organs raises the blood pressure in the pulmonary artery (*Morel*).

[**The action of drugs** on the pulmonary circulation may be tested by Holmgren's apparatus (§ 94), which permits of distention of the lung and retention of the normal circulation in the frog. Cold contracts the pulmonary capillaries to one-third of their diameter, and anæsthetics arrest the pulmonary circulation, chloroform being most and ether least active, while ethidene is intermediate in its effect.]

[**Influence of the Nervous System.**—The pulmonary circulation is much less dependent on the nervous system than the systemic circulation. Very considerable variations of the blood pressure within the other parts of the body may occur, while the pressure within the right heart and pulmonary artery is but slightly affected thereby. The pressure is increased by electrical stimulation of the medulla oblongata, and it falls when the medulla is destroyed. Section and stimulation of the central or peripheral ends of the vagi, stimulation of the

splanchnics, and of the central end of the sciatic, have but a minimal influence on the pressure of the pulmonary artery (*Aubert*).]

89. VELOCITY OF THE BLOOD STREAM.—Methods: (1) A. W. Volkmann's Hæmadromometer (1850).—A glass tube of the shape of a hair-pin, 60–130 cm. long and 2 or 3 mm. broad, with a scale etched on it, or attached to it, is fixed to a metallic basal plate, B, so

FIG. 111.



Volkmann's hæmadromometer (B). I, blood flows from artery to artery; II, blood must pass through the glass tube of B; *c*, *c*, cannulæ for the divided artery.

FIG. 112.



Ludwig and Dogiel's rheometer. X, Y, axis of rotation; A, B, glass bulbs; *h*, *k*, cannulæ inserted in the divided artery; *e*, e_1, rotates on *g*, *f*; *c*, *d*, tubes.

that each limb passes to a stop-cock with three channels. The basal plate is perforated along its length, and carries at each end short cannulæ, *c*, *c*, which are tied into the ends of a divided artery. The whole apparatus is first filled with water [or, better, with salt solution]. The stop-cocks are moved simultaneously, as they are attached to a toothed wheel, and have at first the position given in Fig. 111, I, so that the blood simply flows through the hole in the basal piece, *i. e.*, directly from one end of the artery to the other. If at a given moment the stop-cock is turned in the direc-

tion indicated in Fig. 111, II, the blood has to pass through the glass tube, and the time it takes to make the circuit is noted; and as the length of the tube is known, we can easily calculate the velocity of the blood. The method has very obvious defects arising from the narrowness of the tube; the introduction of such a tube offers new resistance, while there are no respiratory or pulse variations observable in the stream in the glass tube.

Volkmann found the **velocity** to be in the carotid (dog) = 205 to 357 mm.; carotid (horse) = 306; maxillary (horse) = 232; metatarsal = 56 mm. per second.

(2) C. Ludwig and Dogiel (1867) devised a "**stromuhr**" or **rheometer** for measuring the amount of blood which passed through an artery in a given time (Fig. 112).

It consists of two glass bulbs, A and B, of exactly the same capacity. These bulbs communicate with each other above, their lower ends being fixed by means of the tubes, *c* and *d*, to the metal disk, *e*, e_1. This disk rotates round the axis, X, Y, so that, after a complete revolution, the tube *c* communicates with *f*, and *d* with *g*; *f* and *g* are provided with horizontally placed cannulæ, *h* and *k*, which are tied into the ends of the divided artery. The cannula *h* is fixed in the central

FIG. 113.



I. Vierordt's hæmatachometer. A, glass; *e*, entrance; *a*, exit cannula; *p*, pendulum. II. Dromograph. A, B, tube inserted in artery; C, lateral tube connected with a manometer; *b*, index moving in a caoutchouc membrane, *a*; G, handle. III. Curve obtained by dromograph.

end, and *k* in the peripheral end of the artery (*e. g.*, carotid); the bulb, A, is filled with oil, and B with defibrinated blood; at a certain moment the communication through *h* is opened, the blood flows in, driving the oil before it, and passes into B, while the defibrinated blood flows through *k* into the peripheral part of the artery. As soon as the oil reaches *m*—a moment which is instantly noted, or, what is better, inscribed upon a revolving cylinder—the bulbs, A, B, are rotated upon the axis, X, Y, so that B comes to occupy the position of A. The same experiment is repeated, and can be continued for a long time. The quantity of blood which passes in the unit of time (1 sec.) is calculated from the time necessary to fill the bulb with blood. Important results are obtained by means of this instrument.

[Suppose 50 c.cm. of blood are delivered in 100 secs., then 1 c.cm. flows through in 2 secs. Suppose the sectional area of the artery to be 3¼ mm. As the velocity is measured by the ratio of the quantity to the sectional area, then $\frac{5000}{3.14} = 159$ mm. per second.]

[As peptone injected into the blood prevents it from coagulating (dog), this fact has been turned to account in using the rheometer.]

(3) **Vierordt's Hæmatachometer** (1858) consists of a small metal box (Fig. 113, I) with parallel glass sides. To the narrow sides of the box are fitted an inlet, *e*, and an exit cannula, *a*. In its interior is suspended, against the entrance opening, a pendulum, *p*, whose vibrations may be

read off on a curved scale. [This instrument, as well as Volkmann's apparatus, has only an historical interest.]

(4) **Chauveau** and **Lortet's Dromograph** (1860) is constructed on the same principle. A tube A, B (Fig. 113), of sufficient diameter, with a side tube fixed to it, C, which can be placed in connection with a manometer, is introduced into the carotid artery of a horse. At *a* a small piece is cut out and provided with a covering of gutta-percha which has a small hole in it; through this a light pendulum, *a*, *b*, with a long index, *b*, projects into the tube, *i. e.*, into the blood current, which causes the pendulum to vibrate, and the extent of the vibrations can be read off on a scale, S, S. G is an arrangement to permit the instrument to be held. Both this and the former instrument are tested beforehand with a stream of water sent through them with varying velocities.

(5) **Cybulski's Photohæmatachometer.**—When fluid flows into a tube (Fig. 114, II, *de*) in the direction of the arrow, the fluid stands higher in the manometer *p* than in *m*. The tube *my* indicates the lateral pressure, but *px* gives this *plus* the velocity of the fluid (p. 132). The velocity of the current may be estimated from the difference in the level in the two tubes.

Pitot's tube as used by *Cybulski* is bent at a right angle (I, *cp*), the end *c* being inserted and tied into the central, and *p* into the peripheral, part of a divided artery. As the blood flows through the tube, the blood rises higher in *a* than *b*.

To avoid having the manometers *a* and *b* too long, they are connected with each other by a capillary tube filled with air and provided above with a stop-cock *i*. The blood is allowed to rise to the height of 1 and 2, the stop-cock *i* is closed, and practically an air manometer is made, which shows a marked difference in the level of the blood of the two tubes. The level of the blood in 1 and 2 is continually changed by the movements of the heart and those of respiration, and these variations are photographed by means of a camera *n* with a rapidly moving plate *k*.

FIG. 114.



I. Scheme of the photohæmatachometer; II. Pitot's tube.

Fig. 114, C, shows a curve obtained from the carotid of a dog. The velocity of the current at $1_1 - 1 = 238$ mm., in the phase $2_1 - 2 = 225$ mm., and at $3_1 - 3 = 177$ mm. The velocity is greatest at the end of inspiration and the beginning of expiration. Asphyxia increases it at first. Paralysis of the sympathetic increases it, while stimulation of this nerve diminishes it. Section of the vagi increases the velocity, while stimulation diminishes it.

The curve of the velocity may be written off on a smoked glass plate, moving parallel with the index *b*. The dromograph curve, Fig. 113, III, shows the primary elevation, P, and the dicrotic elevation R.

90. **VELOCITY OF THE BLOOD.—Division of Vessels—Arteries.**—In estimating the velocity of the blood, it is important to remember that the sectional area of all the branches of the aorta becomes greater as we proceed from the aorta toward the capillaries, so that the capillary area is 700 times greater than the sectional area of the aorta. As the veins join and form larger trunks, the venous area gradually becomes smaller, but the sectional area of the venous orifices at the heart is greater than that of the corresponding arterial orifices. [We may represent the result as two cones placed base to base (Fig. 115), the bases meeting in the capillary area. The sectional

area of the venous orifice (V) is represented larger than that of the arterial (A). The **increased sectional area** influences the **velocity** of the blood current, while the resistance affects the pressure.]

The common iliacs are an exception; the sum of their sectional areas is less than that of the aorta; the sections of the four pulmonary veins are together less than that of the pulmonary artery.

(2) **Sectional Area.**—*An equal quantity of blood* must pass through every section of the circulatory system, through the pulmonic as well as through the systemic circulation, so that the same amount of blood must pass through the pulmonary artery and aorta, notwithstanding the very unequal blood pressure in these two vessels.

FIG. 115.



Scheme of the sectional area. A, arterial, and V, venous orifice.

(3) **Lumen.**—The velocity of the current, therefore, in various sections of the vessels, must be inversely as their lumen.

(4) **Capillaries.**—Hence, the velocity must diminish very considerably as we pass from the root of the aorta and the pulmonary artery toward the capillaries, so that the **velocity in the capillaries** of mammals = 0.8 millimetre per sec.; frog = 0.53 mm. (*E. H. Weber*); man = 0.6 to 0.9 (*C. Vierordt*). According to A. W. Volkmann, the blood in mammalian capillaries flows 500 times slower than the blood in the aorta, so that the total sectional area of all the capillaries must be 500 times greater than that of the aorta. Donders found the velocity of the stream in the small afferent arteries to be 10 times faster than in the capillaries.

Veins.—The current becomes accelerated in the veins, but in the larger trunks it is 0.5 to 0.75 times less than in the corresponding arteries.

(5) **Mean Blood Pressure.**—The velocity of the blood does not depend upon the *mean* blood pressure, so that it may be the same in congested and in anæmic parts (*Volkmann, Hering*).

(6) **Difference of Pressure.**—On the other hand, the velocity in any section of a vessel is dependent on the difference of the pressure which exists at the commencement and at the end of that particular section of a blood vessel; it depends, therefore, on (1) the *vis a tergo* (*i.e.*, the action of the heart), and (2) on the amount of the resistance at the periphery (dilatation or contraction of the small vessels).

Corresponding to the smaller difference in the arterial and venous pressure in the fœtus (§ 85), the velocity of the blood is less in this case (*Cohnstein and Zuntz*).

(7) **Pulsatory Acceleration.**—With *every pulse beat* a corresponding acceleration of the blood current (as well as of the blood pressure) takes place in the arteries (pp. 169, 176). In large vessels, Vierordt found the increase of the velocity during the systole to be greater by ¼ to ½ than the velocity during the diastole. The variations in the velocity caused by the heart beat are recorded in Fig. 113, obtained by Chauveau's dromograph from the carotid of a horse. The velocity curve corresponds with a sphygmogram—P represents the primary elevation and R the dicrotic wave. This acceleration, as well as the pulse, disappears in the capillaries. A pulsatory acceleration, more rapid during its first phase, is observable in the small arteries, although the arteries themselves are not distended thereby.

(8) **Respiratory Effect.**—Every *inspiration retards* the velocity in the arteries, every *expiration aids* it somewhat; but the value of these agencies is very small.

If we compare what has already been said regarding the effect of the respiration on the contraction and dilatation of the heart and on the blood stream (§ 60), it is clear that **respiration favors the blood stream**, and so does artificial respiration. When artificial respiration is interrupted, the blood stream becomes slower (*Dogiel*). If the suspension of respiration lasts somewhat longer, the current is again accelerated on account of the dyspnœic stimulation of the vasomotor centre (*Heidenhain*) (§ 371, I).

(9) **Modifying Conditions.**—Many circumstances affect the velocity of the blood in the veins. (1) There are *regular* variations in the large veins near the heart due to the *respiration and the movements of the heart* (§§ 50 and 60). (2) *Irregular* variations due to *pressure*, *e. g.*, from contracting muscles (§ 87), *friction* on the skin in the direction or against the direction of the venous current; the *position* of a limb or of the body. The pump-like action of the veins of the groin on moving the leg has been referred to (§ 87). When the lower limb is extended and rotated outward, the femoral vein in the iliac fossa collapses, owing to an internal negative pressure; when the thigh is flexed and raised, it fills under a positive pressure (*Braune*). A similar condition obtains in walking.

91. **CAPACITY OF THE VENTRICLES.**—Vierordt calculated the capacity of the left ventricle from the velocity of the blood stream, and the amount of blood discharged per second by the right carotid, right subclavian, the two coronary arteries, and the aorta below the origin of the innominate artery. He estimated that with every systole of the heart, 172 cubic centimetres (equal to 180 grammes) of blood were discharged into the aorta; this, therefore, must be the capacity of the left ventricle (compare § 83).

92. **THE DURATION OF THE CIRCULATION.**—The time required by the blood to make a **complete circuit** through the course of the circulation was first determined by Hering (1829), in the horse. He injected a 2 per cent. solution of potassium ferrocyanide into a special vein, and ascertained (by means of ferric chloride) when this substance appeared in the blood taken from the corresponding vein on the *opposite* side of the body. The ferrocyanide may also be injected into the central or cardiac end of the jugular vein, and the time noted at which its presence is detected in the blood of the peripheral end of the same vein. Vierordt (1858) improved this method by placing under the corresponding vein of the opposite side a rotating disk, on which was fixed a number of cups at regular intervals. The first appearance of the potassium ferrocyanide is detected by adding ferric chloride to the serum which separates from the samples of blood after they have stood for a time. The duration of the circulation is as follows:—

Horse, ... 31.5 seconds.	Hedgehog, . . . 7.61 seconds.	Duck, ... 10.64 seconds.
Dog, ... 16.7 "	Cat, ... 6.69 "	Buzzard, . . 6.73 "
Rabbit, ... 7.79 "	Goose, ... 10.86 "	Fowl, ... 5.17 "

Results.—When these numbers are compared with the frequency of the normal pulse beat in the corresponding animals, the following deductions are obtained:—

(1) The mean time required for the circulation is accomplished during 27 heart beats, *i. e.*, for man = 32.2 seconds, supposing the heart to beat 72 times per minute.

(2) Generally, the mean time for the circulation in two warm-blooded animals is inversely as the frequency of the pulse beats.

Modifying Conditions.—The time is influenced by the following factors:—

1. **Long vascular channels** (*e. g.*, from the metatarsal vein of one foot to the other foot) require a longer time than short channels (as between the jugulars). The difference may be equal to 10 per cent. of the time required to complete the entire circuit.

2. In **young animals** (with shorter vascular channels and higher pulse rate) the time is shorter than in old animals.

3. **Rapid and energetic** cardiac contractions (as during muscular exercise) diminish the time. Hence rapid and at the same time less energetic contractions (as after section of both vagi), and slow but vigorous systoles (*e. g.*, after slight stimulation of the vagus), have no effect.

C. Vierordt estimated the **quantity of blood** in a man, in the following manner: In all warm-blooded animals, 27 systoles correspond to the time for completing the circulation. Hence, the

total mass of the blood must be equal to 27 times the capacity of the ventricle, *i. e.*, in man, 187.5 grms. × 27 = 5062.5 grms. This is equal to $\frac{1}{13}$ of the body weight in a person weighing 65.8 kilos. (compare § 49.)

It is not to be forgotten that the salt used is to some extent poisonous, but Hermann uses the corresponding innocuous soda salt (25 per cent.).

Pathological.—The duration of the circulation seems to be increased during septic fever (*E. Wolff*).

93. WORK OF THE HEART.—The **left ventricle** expels 0.188 kilo. of blood with each systole, and in doing so it overcomes the pressure in the aorta, which is equal to a column of blood 3.21 metres in height. [The amount of blood expelled from each ventricle during the systole is about 180 grms. (6 oz.). It is forced out against a pressure of 250 mm. Hg. = 3.21 metres of blood.] The work of the heart at each systole is 0.188 × 3.21 = 0.604 kilogramme-metre. If the number of beats = 75 per minute, then the work of the left ventricle in 24 hours = (0.604 × 75 × 60 × 24) = 65,230 kilogramme-metres; while the "work" done by the *right* ventricle is about one-third that of the left, and therefore = 21,740 kilogramme-metres. Both ventricles do work equal to 86,970 kilogramme-metres. A workman during eight hours produces 300,000 kilogramme-metres, *i. e.*, about four times as much as the heart. As the whole of the work of the heart is consumed in overcoming the resistance within the circulation, or rather is converted into heat, the body must be partly warmed thereby—(425.5 gramme-metres are equal to 1 heat unit, *i. e.*, the force required to raise 425.5 grammes to the height of 1 metre may be made to raise the temperature of 1 cubic centimetre of water 1° C.). So that 204,000 "heat units" are obtained from the transformation of the kinetic energy of the heart.

One gramme of coal when burned yields 8080 heat units, so that the heart yields as much energy for heating the body as if about 25 grammes of coal were burned within it to produce heat.

§ 94. BLOOD CURRENT IN THE SMALLER VESSELS.—Methods.—The most important observations for this purpose are made by means of the **microscope** on transparent parts of living animals. Malpighi was the first to observe the circulation in this way in the lung of a frog (1661).

The following parts have been employed: The tails of tadpoles and small fishes; the web, tongue, mesentery, and lungs of curarized frogs; the wing of the bat; the third eyelid of the pigeon or fowl; the mesentery; the vessels of the liver of frogs and newts, pia mater of rabbits, the skin on the belly of the frog, the mucous membrane of the inner surface of the human lip (*Hüter's* Cheilangioscope, 1879); the conjunctiva of the eyeball and eyelids. All these may be examined by *reflected* light.

[**Holmgren's Method.**—In studying the circulation in the frog's lung, it must be inflated. A cannula with a bulge on its free end is placed in the larynx, while to the other end is fixed a piece of caoutchouc tubing. The lung is inflated and then the caoutchouc tube is closed, after which the lung is placed in a chamber with glass above and below, and examined microscopically.]

[**Entoptical appearances** of the circulation (*Purkinje*, 1815). Under certain conditions a person may detect the movement of the blood corpuscles within the blood vessels of his own eye. The best method is that of Rood, viz., to look at the sky through a dark blue glass, or through several pieces of cobalt glass placed over each other (*Helmholtz*).]

Form and Arrangement of Capillaries.—Regarding the form and arrangement of the capillaries, we find that—

1. The *diameter* which, in the finest, permits only the passage of single corpuscles in a row—one behind the other—may vary from 5 μ to 2 μ, so that 2 or more corpuscles may move abreast when the capillary is at its widest.

2. The *length* is about 0.5 mm. They terminate in small veins.

3. The *number* is very variable, and the capillaries are most numerous in those tissues where the metabolism is most active, as in lungs, liver, muscles—less numerous in the sclerotic and in the nerve trunks.

4. They form numerous *anastomoses*, and give rise to **networks**, whose form and arrangement are largely determined by the arrangement of the tissue elements themselves. They form *simple loops* in the skin, and polygonal networks in the serous membranes, and on the surface of many gland tubes; they occur in the form of elongated networks, with short connecting branches in

muscle and nerve, as well as between the straight tubules of the kidney; they converge *radially* toward a central point in the lobules of the liver, and form *arches* in the free margins of the iris, and on the limit of the sclerotic and cornea.

[**Direct Termination of Arteries in Veins.**—Arteries sometimes terminate directly in veins, without the intervention of capillaries, *e.g.*, in the ear of the rabbit, in the terminal phalanges of the fingers and toes in man and some animals, in the cavernous tissue of the penis. They may be regarded as secondary channels which protect the circulation of adjacent parts, and they may also be related to the heat-regulating mechanisms of peripheral parts (*Hoyer*).]

In connection with the termination of arteries in capillaries, it is important to ascertain if the arterioles are **terminal arteries**, *i.e.*, if they do not form any further anastomoses with other similar arterioles, but terminate directly in capillaries, and thus only communicate by capillaries with neighboring arterioles—or the arteries may anastomose with other arteries just before they break up into capillaries. This distinction is important in connection with the nutrition of parts supplied by such arteries (*Cohnheim*).

Capillary Circulation.—On observing the capillary circulation, we notice that the **red corpuscles** move only in the axis of the current (axial current), while the lateral transparent plasma current flowing on each side of this central thread is free from these corpuscles. [The axial current is the more rapid.] This plasma layer or "**Poiseuille's space**" is seen in the smallest arteries and veins, where $\frac{3}{5}$ are taken up with the axial current, and the plasma layer occupies $\frac{1}{5}$ on each side of it (Fig. 116). A great many, but not all, of the colorless corpuscles move in this layer. It is much less distinct in the capillaries. Rud. Wagner stated that it is absent in the finest vessels of the lung and gills [although Gunning was unable to confirm this statement]. The colored corpuscles move in the smallest capillaries in *single file*, one after the other; in the larger vessels, several corpuscles may move abreast, with a *gliding* motion, and in their course they may turn over and even be twisted if any obstruction is offered to the blood stream. As a general rule, in these vessels the movement is uniform, but at a sharp bend of the vessel it may partly be retarded and partly accelerated. Where a vessel divides, not unfrequently a corpuscle remains upon the projecting angle of the division, and is doubled over it so that its ends project into the two branches of the tube. There it may remain for a time, until it is dislodged, when it soon regains its original form on account of its elasticity. Not unfrequently we see a red corpuscle becoming bent where two vessels meet, but on all occasions it rapidly regains its original form. This is a good proof of the elasticity of the colored corpuscles. The motion of the **colorless corpuscles** is quite different in character; they *roll* directly on the *vascular wall*, moistened on their peripheral zone by the plasma in Poiseuille's space, their other surface being in contact with the thread of colored corpuscles in the centre of the stream. Schklarewsky (1868) has shown by physical experiments, that the particles of least specific gravity in all capillaries (*e.g.*, of glass) are pressed toward the wall, while those of greater specific gravity remain in the middle of the stream. [Graphite and particles of carmine were supended in water, and caused to circulate through capillary tubes placed under a microscope, when the graphite kept the centre of the stream, and the carmine moved in the layer next the wall of the tube.]

When the colorless corpuscles reach the wall of the vessel, they must roll along, partly on account of their surface being *sticky*, whereby they readily adhere to the vessel, and partly because one surface is directed toward the axis of the vessel where the movement is most rapid, and where they receive impulses directly from the rapidly moving colored blood corpuscles (*Donders*). The rolling motion is not always uniform, not unfrequently it is retrograde in direction, which seems to be due to an irregular adhesion to the vascular wall. Their *slower* movement (10 to 12 times slower than the red corpuscles) is partly due to their stickiness, and partly to the fact that, as they are placed near the wall, a large part of their surface lies in the peripheral threads of the fluid, which, of course, move more slowly (in fact the layer of fluid next the wall is passive—p. 133).

[D. J. Hamilton finds that, when a frog's web is examined in a vertical position, by far the

greater proportion of leucocytes float on the *upper* surface, and only a few on the lower surface, of a small blood vessel. In experiments to determine why the colored corpuscles float or glide exclusively in the axial stream, while a great many, but not all, of the leucocytes roll in the peripheral layers, Hamilton ascertained that the nearer the suspended body approaches to the specific gravity of the liquid in which it is immersed, the more it tends to occupy the centre of the stream. He is of opinion that the phenomenon of the separation of the blood corpuscles in the circulating fluid is due to the colorless corpuscles being specifically lighter, and the colored either of the same or of very slightly greater specific gravity, than the blood plasma. Hamilton controverts the statement of Schklarewsky, and he finds that it is the relative specific gravity of a body which ultimately determines its position in a tube. These experiments point to the immense importance of a due relation subsisting between the specific gravity of the blood plasma and that of the corpuscles.]

In the vessels first formed in the incubated egg, as well as in young tadpoles, the movement of the blood from the heart occurs in jerks (*Spallanzani*, 1768).

The velocity of the blood stream is influenced by the *diameter of the vessels*, which undergo periodic changes of calibre. This change occurs not only in vessels provided with muscular fibres, but also in the capillaries, which vary in diameter, owing to the contraction of the cells composing their walls (p. 138).

The amount of *water in the blood* is of importance; when it is increased, the circulation is facilitated and accelerated (§ 62).

The velocity of the blood is greater in the **pulmonary** than in the systemic capillaries; so that the total sectional area of the pulmonary capillaries is less than that of all the systemic capillaries.

95. **DIAPEDESIS.**—If the circulation be studied in the vessels of the mesentery, we may observe **colorless corpuscles** passing out of the vessels in greater or less numbers (Fig. 116). The mere contact with the air suffices to excite slight inflammation. At first, the colorless corpuscles in the plasma space move more slowly; several accumulate near each other, and adhere to the walls—soon they bore into the wall, ultimately they pass quite through it, and may wander for a distance into the perivascular tissues. It is doubtful whether they pass through the so-called "**stomata**" which exist between the endothelial cells, or whether they simply pass through the cement substance between the endothelial cells (p. 136). This process is called **diapedesis**, and consists of several acts: (*a*) The adhesion of lymph cells or colorless corpuscles to the inner surface of the vessel (after moving more slowly along the wall up to this point). (*b*) They send processes into and through the vascular wall. (*c*) The body of the cell is drawn after or follows the processes, whereby the corpuscle appears constricted in the centre (Fig. 116, *c*). (*d*) The complete passage of the corpuscle through the wall, and its further motion in virtue of its own amœboid movements. Hering observed that in large vessels with perivascular lymph spaces, the corpuscles passed into the spaces, hence cells are found in lymph before it has passed through lymphatic glands. The **cause** of the diapedesis is partly due to the independent locomotion of the corpuscles, and it is partly a physical act, viz., a filtration of the colloid mass of the cell under the force of the blood pressure (*Hering*)—in the latter respect depending upon the intravascular pressure and the velocity of the blood stream. Hering regards this process, and even the passage of the colored corpuscles through the vascular wall, as a normal process. The **red corpuscles** pass out of the vessels when the venous outflow is obstructed, which also causes the transudation of plasma through the vascular wall. The plasma carries the colored corpuscles along with it, and at the moment of their passage through the wall they assume extraordinary shapes, owing to the tension put upon them, regaining their shape as soon as they pass out (*Cohnheim*). This remarkable phenomenon was described by Waller in 1846. It was re-described by Cohnheim, and according to him the out-wandering is a sign of inflammation, and the colorless corpuscles which accumulate in the tissues are to be regarded as true **pus corpuscles**, which may undergo further increase by division.

FIG. 116.



Small vessel of a frog's mesentery showing diapedesis. *w*, *w*, vascular walls; *a*, *a*, Poiseuille's space; *r*, *r*, red corpuscles; *l*, *l*, colorless corpuscles adhering to the wall, and *c*, *c*, in various stages of extrusion; *f*, *f*, extruded corpuscles.

Stasis.—When a strong stimulus acts on a vascular part, hyperæmic *redness* and *swelling* occur.

Microscopic observation shows that the capillaries and the small vessels are dilated and *overfilled* with blood corpuscles; in some cases, a temporary narrowing precedes the dilatation; simultaneously the velocity of the stream changes, rarely there is a temporary acceleration, *more frequently it becomes slower*. If the action of the stimulus or irritant be continued, the retardation becomes considerable, the stream moves in jerks, then follows a **to-and-fro movement** of the blood column—a sign that stagnation has taken place in other vascular areas. At last the blood stream comes completely to a stand-still—**stasis**—and the blood vessels are plugged with blood corpuscles. Numerous colorless blood corpuscles are found in the stationary blood. While these various processes are taking place, the colorless corpuscles—more rarely the red—pass out of the vessels. Under favorable circumstances the stasis may disappear. The swelling which occurs in the neighborhood of inflamed parts is chiefly due to the **exudation** of plasma into the surrounding tissues.

96. MOVEMENT OF THE BLOOD IN THE VEINS.—In the smallest veins coming from the capillaries, the blood stream is more rapid than in the capillaries themselves, but less so than in the corresponding arteries. The stream is uniform, and if no other conditions interfered with it, the venous stream toward the heart ought to be uniform, but many circumstances affect the stream in different parts of its course. Among these are: (1) The relative *laxness*, great *distensibility*, and the ready *compressibility* of the walls, even of the thickest veins. (2) The *incomplete filling* of the veins, which does not amount to any considerable distention of their walls. (3) The numerous and free *anastomoses* between adjoining veins, not only between veins lying in the same plane, but also between superficial and deep veins. Hence, if the course of the blood be obstructed in one direction, it readily finds another outlet. (4) The presence of numerous **valves** which permit the blood stream to move only in a centripetal direction. They are absent from the smallest veins, and are most numerous in those of middle size.

Position of Valves.—The venous valves always have two pouches, and are placed at definite intervals, which correspond to the 1, 2, 3, or n^{th} power of a certain "fundamental distance," which is = 7 mm. for the lower extremity and 5.5 mm. for the upper. Many of the original valves disappear. On the proximal side of every valve a lateral branch opens into the vein, while on the distal side of each branch lies a valve. The same is true for the lymphatics (*K. Bardeleben*).

Effect of Pressure.—As soon as pressure is applied to the veins, the next lowest valves close, and those immediately above the seat of pressure open and allow the blood to move freely toward the heart. The *pressure* may be exerted from *without*, as by anything placed against the body; the thickened, *contracted* muscles, especially the muscles of the limbs, compress the veins. That the blood flows out of a divided vein more rapidly when the muscles contract, is shown during venesection. If the muscles are kept contracted, the venous blood passing out of the muscles collects in the passive parts, *e.g.*, in the cutaneous veins. The pulsatile pressure of the arteries accompanying the veins favors the venous current. From a hydrostatic point of view the valves are of considerable importance, as they serve to divide the column of blood into segments (*e.g.*, in the crural vein in the erect attitude), so that the fine blood vessels in the foot are not subjected to the whole amount of the hydrostatic pressure in the veins.

The **velocity** of the venous blood has been measured directly (with the hæmadromometer and the rheometer—§ 89). Volkmann found it to be 225 mm. per sec. in the jugular vein. Reil observed that 2½ times more blood flowed from an arterial orifice than from a venous orifice of the same size. The velocity of the venous current obviously depends upon the sectional area of the vessel. Borelli estimated the capacity of the venous system to be 4 times greater than that of the arterial; while, according to Haller, the ratio is 9 to 4.

Large Veins.—As we proceed from the small veins toward the venæ cavæ, the sectional area of the veins, taken as a whole, becomes less, so that the *velocity of the current increases* in the same ratio. The velocity of the current in the venæ cavæ may be about half of that in the aorta (*Haller*). As the **pulmonary veins** are narrower than the pulmonary artery, the blood moves more rapidly in the former.

97. **SOUNDS WITHIN ARTERIES.**—The sounds produced within arteries are, speaking strictly from a physical point of view, only noises or bruits. Still, following Skoda's lead, they are spoken of by physicians as "tones." Clinically, there is no sharp distinction between "tones," sounds, noises, or bruits. In four-fifths of all healthy men two sounds—corresponding in duration and other characters to the two heart sounds—are heard in the carotid (*Conrad, Weil*). Sometimes only the second heart sound is distinguishable, as its place of origin is near to the carotid. They are not true arterial sounds, but are simply "**propagated heart sounds.**" Sometimes the sound of the pulmonary artery can be heard in this way (*Weil, Bettelheim*). These murmurs, sounds, or bruits occur either *spontaneously*, or are produced by the *application of external pressure*, whereby the lumen of the vessel is diminished. Hence one distinguishes: (1) **Spontaneous Murmurs**, and (2) **Pressure Murmurs.**

Arterial Sounds or murmurs are readily produced by pressing upon a strong artery, *e.g.*, the crural in the inguinal region, so as to leave only a narrow passage for the blood ("**stenosal murmur**"). A fine blood stream passes with great rapidity and force through this narrow part, into a wider portion of the artery lying behind the point of compression. Thus arises the "pressure stream" (*P. Niemeyer*), or the "**fluid vein**" ("veine fluide" of Chauveau). The particles of the fluid are thrown into rapid *oscillation*, and undergo *vibratory* movements, and by their movements produce the sound within the peripheral dilated portion of the tube. A sound is produced in the fluid by pressure (*Corrigan*). The sounds are not caused by vibrations of the vascular wall, as supposed by Bouillaud.

A murmur of this sort is the "**sub-clavicular murmur**" (*Roser*), occasionally heard during systole in the subclavian artery; it occurs when the two layers of the pleura adhere to the apex of the lung (especially in tubercular diseases of the lungs), whereby the subclavian artery undergoes a local constriction due to its being made tense and slightly curved (*Friedreich*). This result is indicated in a diminution or absence of the pulse wave in the radial artery (*Weil*).

It is obvious that arterial murmurs will occur in the human body—(*a*) When, owing to pathological conditions, the arterial tube is *dilated at one part*, into which the blood current is forcibly poured from the normal narrow tube. Dilatations of this sort are called **aneurisms**, in which murmurs are generally audible. (*b*) When **pressure** is exerted *upon an artery*, *e.g.*, by the pressure of the greatly enlarged arteries during pregnancy, or by a large tumor pressing upon a large artery.

Spontaneous Murmurs.—In cases where no source of external pressure is discoverable, and when no aneurism is present, the spontaneously occurring sounds are favored, when at the moment of arterial rest (cardiac systole) the arterial walls are distended to the slightest extent, and when during the movement of the pulse (cardiac diastole) the tension is most rapid (*Traube, Weil*), *i. e.*, when the low systolic minimum tension of the arterial wall passes rapidly into the high maximum tension. This is especially the case in insufficiency of the aortic valves, in which case the sounds in the arteries are audible over a wide area. If the minimum tension of the arterial wall is relatively great, even during diastole, the sounds in the arteries are greatly diminished.

Arterial murmurs are **favored** by (1) Sufficient delicacy and elasticity of the arterial walls. (2) Diminished peripheral resistance, *e. g.*, an easy outflow of the fluid at the end of the stream. (3) Accelerated current in the vascular system generally. (4) A considerable difference of the pressure in the narrow and wide portions of the tube. (5) Large calibre of the arteries.

In normal pulsating arteries, sounds may be heard especially at an acute bend of the artery. Murmurs of this sort are loudest where several large arteries lie together; hence, during pregnancy, we hear the *uterine murmur*, or **placental bruit**, or *souffle* in the greatly dilated uterine arteries. It is much less distinct in the umbilical arteries of the cord (umbilical murmurs). Similar sounds are heard through the thin walls of the head of infants, and a murmur is sometimes heard in the enlarged spleen in ague (*Maissurianz*).

Auscultation of the Normal Pulse.—On auscultating the radial artery under favorable circumstances, and especially in old, thin persons with wide arteries and dicrotic pulse, one may hear two sounds corresponding to the primary and dicrotic waves.

In **insufficiency of the aortic valves**, characteristic sounds may be heard in the crural artery. If pressure be exerted upon the artery, a double blowing murmur is heard; the first one is due to a large mass of blood being propelled into the artery synchronously with the heart beat, the second to the fact that a large quantity of blood flows back into the heart during diastole. If no pressure be exercised two sounds are heard, and these seem to be due to a wave propagated into the arteries by the auricles and ventricles respectively—compare § 73, Fig. 86, III. In atheroma a double sound may sometimes be heard (§ 73, 2).

98. VENOUS MURMURS.—I. **Bruit de Diable.**—This sound is heard above the clavicles in the furrow between the two heads of the sterno-mastoid, most frequently on the right side, and in 40 per cent. of all persons examined. It is either a continuous or a rhythmical murmur, occurring during the diastole of the heart or during inspiration; it has a whistling or rushing character, or even a musical quality, and arises within the bulb of the common jugular vein. When this sound is heard without pressure being exerted by the stethoscope, it is a pathological phenomenon. If, however, pressure be exerted, and if, at the same time, the person examined turn his head to the opposite side, a similar sound is heard in nearly all cases. The pathological *bruit de diable* occurs especially in anæmic persons, in lead poisoning, in syphilitic and scrofulous persons, sometimes in young persons, and less frequently in elderly people. Sometimes a *thrill* of the vascular wall may be felt.

Causes.—It is due to the vibration of the blood flowing in from the relatively narrow part of the common jugular vein into the wide bulbous portion of the vessel, and seems to occur chiefly when the walls of a thin part of the vein lie close to each other, so that the current must purl through it. It is clear that pressure from without, or lateral pressure, as by turning the head to the opposite side, must favor its occurrence. Its *intensity* will be increased when the velocity of the stream is increased, hence *inspiration* and the *diastolic* action of the heart (both of which assist the venous current) increase it. The erect attitude acts in a similar manner. A similar bruit is sometimes, though rarely, heard in the subclavian, axillary, thyroid, facial, innominate and crural veins, and superior cava.

II. Regurgitant Murmurs.—On making a sudden effort, a murmur may be heard in the crural vein during expiration, which is caused by a centrifugal current of blood, owing to the incompetence or absence of the valves in this region. If the valves at the jugular bulb are not tight, there may be a bruit with expiration (*expiratory* jugular vein bruit—*Hamernjk*), or during the cardiac systole (*systolic* jugular vein bruit—*v. Bamberger*).

III. Valvular Sounds in Veins.—When the tricuspid valve is incompetent, during the ventricular systole, a large volume of blood is propelled backward into the venæ cavæ. The venous valves are closed suddenly thereby and a sound produced. This occurs at the bulb or dilatation on the jugular vein (*v. Bamberger*), and in the crural vein at the groin (*N. Friedreich*), *i. e.*, only as long as the valves are competent. Forced expiration may cause a valvular sound in the crural vein. No sound is heard in the veins under perfectly normal circumstances.

99. THE VENOUS PULSE—PHLEBOGRAM.—Methods.—A tracing of the movements of a vein, taken with a lightly weighted sphygmograph, has a characteristic form, and is called a **phlebogram** (Fig. 117). In order to interpret the various events of the phlebogram, it is most important to record simultaneously the events that take place in the heart. The auricular contraction (compare Fig. 39) is synchronous with *a b*; *b c*, with the ventricular systole, during which time the first sound occurs, while *a b* is a presystolic movement. The carotid pulse coincides nearly with the apex of the cardiogram, *i. e.*, almost simultaneously with the descending limb of the phlebogram (*Riegel*).

Occasionally in healthy individuals a pulsatile movement, synchronous with the action of the heart, may be observed in the common jugular vein. It is either confined to the lower part of the vein, the so-called bulb, or extends further up along the trunk of the vein. In the latter case, the valves above the bulb are insufficient, which is by no means rare, even in health. The wave motion passes from below upward, and is most obvious when the person is in the passive horizontal position, and it is more frequent on the right side, because the right vein lies nearer the heart than the left. It is propagated more slowly than the arterial pulse wave. The venous pulse resembles very closely the tracing of the cardiac impulse. Compare Fig. 117, 1, with Fig. 39.

It is obvious that, as the jugular vein is in direct communication with the right auricle, and as the pressure within it is low, the systole of the right auricle must cause a positive wave to be propagated toward the peripheral end of the jugular vein. Fig. 117, 9 and 10, are venous pulse tracings of a healthy person with insufficiency of the valves of the jugular vein. In these curves, the part *a b* cor-

responds to the contraction of the auricle. Occasionally this part consists of two elevations, corresponding to the contraction of the atrium and auricle respectively. As the blood in the right auricle receives an impulse from the sudden tension of the tricuspid valve, *synchronous with the systole of the right ventricle*, there is a positive wave in the jugular vein in Fig. 117, 9 and 10, indicated by *b*, *c*. Lastly, the sudden closure of the pulmonary valves may even be indicated (*e*). As the aorta lies in direct relation with the pulmonary artery, the sudden closure of its valves may also be indicated (Fig. 91, 9, at *d*). During the diastole of the auricle and ventricle, blood flows into the heart, so that the vein partly collapses and the lever of the recording instrument descends.

Sinus and Retinal Pulse.—The blood in the sinuses of the *brain* also undergoes a pulsatile movement, owing to the fact that during cardiac diastole much blood flows into the veins (*Mosso*). Under favorable circumstances, this movement may be propagated into the veins of the *retina*, constituting the *venous retinal pulse* of the older observers (*Helfreich*).

FIG. 117.



Venous pulses (*Friedreich*). 1–8, from insufficiency of the tricuspid; 9, 10, pulse of the jugular vein of a healthy person. In all the curves, *a b* = contraction of the right auricle; *b c*, of the right ventricle; *d*, closure of the aortic valves; *e*, closure of the pulmonary valves; *e*, *f*, diastole of the right ventricle.

Pathological Jugular Vein Pulse.—The venous pulse in the jugular vein is far better marked in *insufficiency of the tricuspid valve*, and the vein may pulsate violently, but if its valves be perfect, the pulse is not propagated along the vein, so that *a pulse in the jugular vein is not necessarily a sign of insufficiency of the tricuspid valve*, but only of insufficiency of the valve of the jugular vein (*Friedreich*).

Liver Pulse.—The ventricular systole is propagated into the valveless inferior vena cava, and causes the *liver pulse*. With each systole blood passes into the hepatic veins, so that the liver undergoes a *systolic swelling and injection*.

Fig. 117, 2–8, are curves of the pulse in the common jugular vein. Although at first sight the curves appear to be very different, they all agree in this, that the various events occurring in the heart during a cardiac revolution are indicated more or less completely. In all the curves, *a b* = auricular contraction. The auricle, when it contracts, excites a positive wave in the veins. The elevation, *b c*, is caused by the large blood wave produced in the veins, owing to the emptying of the ventricle. It is always greater, of course, in insufficiency of the tricuspid valves than under normal circumstances (Fig. 117, 9 and 10). In the latter case, the closure of the tricuspid valve causes only a slight wave motion in the auricle. The apex, *c*, of this wave may be higher or lower, accord-

ing to the tension in the vein and the pressure exerted by the sphygmograph. As a general rule, at least one notch (4, 5, 6, *e*) follows the apex, due to the prompt closure of the valves of the pulmonary artery. The closure of the closely adjacent aortic valves may cause a small secondary wave near to *e* (as in 1 and 2, *d'*). The curve falls toward *f*, corresponding to the diastole of the heart.

A well-marked venous pulse occurs when the *right auricle is greatly congested*, as in cases of insufficiency of the mitral valve or stenosis of the same orifice. In rare cases, in addition to the pulse in the common jugular vein, the external jugular, the facial, thyroid, external thoracic veins, or even the veins of the upper and lower extremities may pulsate. A similar pulsation must occur in the pulmonary veins in mitral insufficiency, but of course the result is not visible.

On rare occasions, a pulse occurs in the **veins** on the back of the **hand** and **foot**, owing to the arterial pulse being propagated through the capillaries into the veins. This may occur under normal circumstances, when the peripheral ends of the arteries become dilated and relaxed (*Quincke*), or when the blood pressure within these vessels rises rapidly and falls as suddenly, as in **insufficiency of the aortic valves.**

In progressive effusion into the pericardium the carotid pulse at first becomes smaller and the venous pulse larger; beyond a certain stage of pressure the latter ceases (*Riegel*).

100. DISTRIBUTION OF THE BLOOD.—In the rabbit, one-fourth of the total amount of the blood is found in each of the following: *a*, in the passive muscles; *b*, in the liver; *c*, in the organs of the circulation (heart and vessels); *d*, in all other parts together.

Methods.—The methods adopted do not give exact results. J. Ranke ligatured the parts during life, removed them, and investigated the amount of blood while the tissues were still warm.

Influencing Conditions.—The amount of blood is influenced by (1) the anatomical distribution of the vessels (vascularity or the reverse) as a whole; (2) the diameter of the vessels, which depends upon physiological causes (*a*) on the blood pressure within the vessels; (*b*) on the condition of the vasomotor or vaso-dilator nerves; (*c*) on the condition of the tissues themselves, *e.g.*, the vessels of the intestine during absorption; by the vessels of muscle during muscular contraction; of vessels in inflamed parts.

The most important factor, however, is the state of **activity of the organ** itself; hence, the saying, "ubi irritatio, ibi affluxus." We may instance the congestion of the salivary glands and the gastric mucous membrane during digestion, and the increased vascularity of muscles during contraction. As the activity of organs varies at different times, the *amount of blood in the part or organ goes hand in hand with the variations in its states of activity*. When some organs are congested, others are at rest; during digestion, there is muscular relaxation and less mental activity: violent muscular exertion retards digestion—during great congestion of the cutaneous vessels the activity of the kidneys diminishes. Many organs (heart, muscles of respiration, certain nerve centres) seem always to be in a nearly uniform state of activity and vascularity. During the *activity of an organ*, the amount of blood in it may be increased 30 per cent., nay, even 47 per cent. The motor organs of young muscular persons are relatively more vascular than those of old and feeble persons (*J. Ranke*). In the condition of increased activity a *more rapid renewal* of the blood seems to occur; after muscular exertion the duration of the circulation diminishes (*Vierordt*).

During a condition of mental activity, the carotid is dilated, the dicrotic wave in the carotid curve is increased (the radial shows the opposite condition), and the pulse is increased in frequency (*Gley*).

Age.—The *development of the heart and large vessels* determines a different distribution of the blood in the child from that which obtains in the adult. The heart is relatively small from infancy up to puberty, the vessels are relatively large; while after puberty the heart is large, and the vessels are relatively smaller. Hence it follows that the blood pressure in the arteries of the systemic circulation must be lower in the child than in the adult. The pulmonary artery is relatively wide in the child, while the aorta is relatively small; after puberty both vessels have nearly the same size. Hence, it follows that the blood pressure in the pulmonary vessels of the child is relatively higher than that in the adult (*Beneke*).

101. PLETHYSMOGRAPHY.—In order to estimate and register the amount of blood in a limb Mosso devised an instrument (Fig. 118), which he termed a **plethysmograph.**

It consists of a long cylindrical glass vessel, G, suited to accommodate a limb. The opening through which the limb is introduced is closed with caoutchouc, and the vessel is filled with water. There is an opening in the side of the vessel in which a manometer tube, filled to a certain height with water, is fixed. As the arm is enlarged owing to the increased supply of arterial blood passing into it at each pulse beat, of course the water column in the manometer is raised. Fick placed a float upon the surface of the water, and thus enabled the variations in the volume of the fluid to be inscribed on a revolving cylinder. The curve obtained resembled the pulse curve; it was even dicrotic. In Fig. 118 the movement of the fluid is represented as conveyed to a Marey's tambour, T, similar to the recording apparatus employed in Brondgeest's pansphygmograph (Fig. 76).

The cylinder C may be filled with air. Kries fills it with gas and connects the tube leading to T to a gas burner. The variations in the gas flame are then photographed.

Results.—(1) Pulsatile Variations in the Volume.—As the venous current is regarded as uniform in the passive limb, every increase of the volume curve indicates a greater velocity of the arterial current toward the periphery, and *vice versâ* (*Fick*). The curves registered by the apparatus are **volume pulses**, and they resemble the curve of the dromograph (Fig. 113, III). The ascent of the curve indicates a greater, the descent a diminished inflow of arterial blood.

At first sight the plethysmograph curve (volume pulse, § 90, 7) is very like the pulse curve (pressure pulse); both are dicrotic. But there are differences; the volume pulse curve beyond the apex falls more rapidly. This rapid fall, which is not accompanied by a corresponding fall of the pressure, is attributed by v. Kries to peripheral reflexion. The dicrotic wave occurs sooner in the volume pulse than in the pulse curve.

FIG. 118.



Mosso's plethysmograph. G, glass vessel for holding a limb; F, flask for varying the water pressure in G; T, recording apparatus.

(2) The **respiratory undulations** correspond to similar variations in the blood pressure tracing (§ 85, *f*). Vigorous respiration and cessation of the respiration cause a diminution of the volume. The limb swells during straining and coughing, but diminishes during sighing. (3) Certain **periodic undulations** occur, due to the regular periodic contractions of the small arteries. (4) Other undulations, due to various accidental causes, affect the blood pressure: changes of the position of a limb acting hydrostatically, and dilatation or contraction of the vessels in other vascular regions. (5) Movement of the muscles of the limb under observation causes diminution of volume, as the venous current is accelerated, the musculature is also very slightly diminished in volume, even when the intra-muscular vessels are dilated. (6) *Mental exercise* causes a diminution in the volume of the limb, and so does sleep (*Mosso*). *Music* influences the blood pressure in dogs, the pressure rising or falling under different conditions. The stimulation of the auditory nerve is transmitted to the medulla oblongata, where it acts so as to cause acceleration of the action of the heart (*Dogiel*). (7) *Compression of the afferent artery* causes a decrease, and *compression of the vein* an increase in the volume of the limb (*Mosso*). (8) Stimulation of the vasomotor nerves causes a decrease, that of the vaso-dilators an increase in the volume (*Bowditch and Warren*).

102. TRANSFUSION OF BLOOD.—Transfusion is the introduction of blood from one animal into the vascular system of another animal.

(*a*) The **red corpuscles** are the most important elements in connection with the restorative powers of the blood. They seem to preserve their functions even in blood which has been defibrinated outside the body (§ 4, A).

(*b*) With regard to the **gases** present in the blood, arterial blood never acts injuriously; but venous blood overcharged with carbonic acid ought only to be transfused when the respiration is sufficient to oxygenate the blood as it passes through the pulmonary capillaries, whereby venous is transformed into arterial blood. If the respiratory movements have ceased, or are imperfectly performed, the blood becomes rapidly richer in carbonic acid, and in this condition reaches the heart; thence it is propelled into the blood vessels of the medulla oblongata, where it acts as a powerful stimulus of the respiratory centre, causing dyspnœa, convulsions, and death.

(*c*) The **fibrin**, and the substances from which it is formed, do not seem to play any part in connection with the restorative powers of the blood; hence defibrinated blood performs all the functions of non-defibrinated blood within the body (*Panum, Landois*).

(*d*) The investigations of Worm Müller showed that an **excess** of 83 per cent. of blood may be transfused into the vascular system of an animal (dog) without producing any injurious effects. Hence it follows that the vascular system has the power of accommodating large quantities of blood within it. That the vascular system can accommodate itself to a diminished amount of blood has been known for a long time (§ 85, *c*). [It is very important to observe that the transfusion of a large quantity of blood does not materially or permanently raise the blood pressure.]

When Employed.—The transfusion of blood is used (1) in **acute anæmia** (§ 41, I), *e.g.*, after copious hemorrhage. New blood (150 to 500 c. c.), from the *same species* of animal, is introduced directly into the vessels, to supply the place of the blood lost by the hemorrhage.

(2) In cases of **poisoning**, where the blood has been rendered useless by being mixed with a poisonous substance, and hence is unable to support life. In such cases remove a considerable quantity of the blood, and replace it by fresh blood. Carbonic oxide is a poison of this kind, and its effects on the body have already been described (§ 16). A similar practice is indicated in poisoning with ether, chloral, chloroform, opium, morphia, strychnine, cobra poison, and such substances as dissolve the blood corpuscles, *e.g.*, potassic chlorate.

(3) Under certain **pathological conditions**, the blood may become so altered in quality as to be unable to support life. The morphological elements of the blood may be altered, and so may the relative proportion of its other constituents. Among these conditions may be cited the pathological condition of uræmia, due, it may be, to the accumulation of urea or the products of its decomposition within the blood; accumulation of the biliary constituents in the blood, and great increase of the carbonic acid. All these three conditions, when very pronounced, may cause death. In these cases, part of the impure blood may be replaced by normal human blood.

Among conditions where the *morphological constituents* of the blood are altered qualitatively or quantitatively are: hydræmia (excessive amount of water in the blood, § 41, 1); oligocythæmia (abnormal diminution of red blood corpuscles). When these conditions are highly developed, more especially in pernicious anæmia (§ 10, 2), healthy blood may be substituted. Transfusion is not suited for persons suffering from leukæmia (compare p. 59).

After-Effects.—A quarter or half an hour after normal blood has been injected into the blood vessels of a man, there is a greater or less *febrile reaction*, according to the amount of blood transfused (Fever, § 220).

Operation.—The operative procedure to be adopted in the process of transfusion varies according as defibrinated or non-defibrinated blood is used. In order to defibrinate blood, some blood is withdrawn from a vein of a healthy man in the ordinary way, collected in an open vessel, and whipped or beaten with a glass rod until all the fibrin is completely removed from it. It is then filtered through an atlas filter, heated to the temperature of the body (by placing it in a vessel in warm water), and injected by means of a syringe into an artery opened for the purpose. A vein (*e.g.*, basilic or great saphenous) may be selected for the transfusion, in which case the blood is driven inward in the direction of the heart; if an artery is selected (radial or posterior tibial) the blood is injected toward the periphery (*Hüter*), or toward the heart (*Landois, Schäfer*).

If **non-defibrinated** human blood is used, the blood may be passed *directly* from the arm of the giver to the arm of the receiver by means of a flexible tube. The tube used must be filled with normal saline solution to prevent the entrance of air. [J. Duncan collects the blood shed during an operation in a 5 per cent. solution of sodic phosphate (*Pavy*), and injects the mixture especially where much blood has been lost previously.]

Dangers.—It is most important that **no air** be allowed to pass into the circulation, for if it be introduced in sufficient quantity it may cause death. When air enters the circulation it reaches the right side of the heart, where, owing to the movement of the blood, it forms air bubbles and makes a froth. The air-bubbles are pumped into the branches of the pulmonary artery, in which they become impacted, arrest the pulmonary circulation, and rapidly cause death.

Peritoneal Transfusion.—Recently, the injection of defibrinated blood into the *peritoneal cavity* has been recommended. The blood so injected is absorbed (*Ponfick*). Even after twenty minutes the number of blood corpuscles in the blood of the recipient (rabbit) is increased, and the number is greatest on the first or second day. The operation, however, may cause death, and one fatal case, owing to peritonitis, is recorded (*Mosler*). It is evident that this method of transfusion is not applicable in cases where blood must be introduced into the circulation as rapidly as possible (*e.g.*, after severe hemorrhage or in certain cases of poisoning). [Blood has been injected into the subcutaneous cellular tissue of the abdomen in cases of great debility.]

Heterogeneous Blood.—*The blood of animals ought never to be transfused into the blood vessels of man.* It is to be remembered, however, that the blood corpuscles of the sheep are rapidly dissolved by human blood, so that the active constituents of the blood are rendered useless (*Landois*). As a general rule, the blood serum of some mammals dissolves the blood corpuscles of other mammals (§ 5, 5).

Solution of the Blood Corpuscles.—The serum of dog's blood is a powerful solvent, while that of the blood of the horse and rabbit dissolves corpuscles relatively slowly. The blood corpuscles of mammals vary very greatly with reference to their power to resist the solvent action of the serum of other animals. The red blood corpuscles of rabbits' blood are rapidly dissolved by the blood serum of other animals, while those of the cat and dog resist the solvent action much longer. Solution of the corpuscles occurs in defibrinated as well as in ordinary blood. When the blood of a rabbit or lamb is injected into the blood vessels of a dog, the red blood corpuscles are dissolved in a few minutes. If blood be withdrawn by pricking the skin with a needle, the partially dissolved corpuscles may be detected.

Liberation of Hæmoglobin and Hæmoglobinuria.—As a result of the solution of the colored corpuscles, the blood plasma is reddened by the liberated hæmoglobin. Part of the dissolved material may be used up in the body of the recipient, some of it for the formation of bile, but if the solution of the corpuscles has been extensive, the hæmoglobin *is excreted in the urine* (hæmoglobinuria), in less amount in the intestine, the bronchi, and the serous cavities. Bloody urine has been observed in man after the injection of 100 grammes of lamb's blood. Even some of the recipient's blood corpuscles are dissolved by the serum of the transfused blood, *e. g.*, on transfusing dog's blood into man. In the rabbit, whose corpuscles are readily dissolved, the transfusion of the *blood serum* of the dog, man, pig, sheep, or cat produces serious symptoms, and even death. The dog, whose corpuscles are more resistant, bears transfusion of other kinds of blood well.

Dangers.—When *foreign* or *heterogeneous* blood (*i. e.*, blood from a different species) is transfused, two phenomena which may be dangerous to life occur:—

(1) Before the corpuscles are dissolved, they usually run together and form sticky masses, consisting of 10 or 12 corpuscles, which are apt to occlude the capillaries. After a time they give up their hæmoglobin, leaving the stroma, which yields a sticky, fibrin-like mass that may occlude fine vessels (§ 31).

(2) The presence of a large quantity of dissolved hæmoglobin may cause extensive coagulation within the blood vessels. The injection of dissolved hæmoglobin causes extensive coagulations (*Naunyn and Francken*).

The coagulation occurs usually in the venous system and in the larger vessels, and may cause death either suddenly or after a considerable time.

Dissolved hæmoglobin seems greatly to increase the activity of the fibrin-ferment (§ 30), perhaps by accelerating the disintegration of the colorless corpuscles. Hæmoglobin exposed to the air

gradually loses this property; and the fibrin-ferment, when in contact with hæmoglobin, is either destroyed or rendered less active (*Sachssendahl*).

Vascular Symptoms.—As a result of the above-named causes of occlusion of the vessels, there are often signs of the circulation being impeded in various organs. In man, after transfusion of lambs' blood, the skin is bluish-red, in consequence of the stagnation of blood in the cutaneous vessels. Difficulty of breathing occurs from obstruction in the capillaries of the lung; while there may be rupture of small bronchial vessels, causing sanguineous expectoration. The dyspnœa may increase, especially when the circulation through the medulla oblongata—the seat of the respiratory centre—is interfered with. In the digestive tract, for the same reason, *increased peristalsis*, evacuation of the contents of the rectum, vomiting, and abdominal pain may occur. These phenomena are explained by the fact that disturbances of the circulation in the intestinal vessels cause increased peristaltic movements. Degeneration of the parenchyma of the *kidney* occurs as a result of the occlusion of some of the renal vessels. The uriniferous tubules become plugged with cylinders of coagulated albumin (*Ponfick*). Owing to the occlusion of numerous small muscular branches, the *muscles* may become stiff, or coagulation of their myosin may occur. Other symptoms, referable to the *nervous system*, *sense organs*, and *heart*, are all due to the interference with the circulation through them. An important symptom is the occurrence of a considerable amount of *fever* half an hour or so after the transfusion of heterogeneous blood (§ 200). When many vessels are occluded, rupture of some small blood vessels may take place. This explains the occurrence of slight, yet persistent hemorrhages, which occur on the free surfaces of the mucous and serous membranes, and in the parenchyma of organs, as well as in wounds. The blood coagulates with difficulty, and imperfectly.

Transfusion of other Fluids.—Other substances have been transfused. **Normal saline solution** (0.6 per cent. NaCl), or **serum** from the same species, aids the circulation in a purely mechanical way (*Goltz*), and it even excites the circulation (*Kronecker*). In severe anæmia this fluid cannot maintain life (*Eulenburg and Landois*). The injection of **peptone**, even in moderate amount, is dangerous to life, as it causes paralysis of the vessels (p. 73).

THE BLOOD GLANDS.

103.—**I. THE SPLEEN.—Structure.**—The spleen is covered by the peritoneum, except at the hilum. Under this **serous** covering there is a tough, thick, elastic, fibrous **capsule**, which closely invests the organ and gives a covering to the vessels which enter or leave it at the hilum, so that fibrous tissue is carried into the organ along the course of the vessels (Fig. 119). [The capsule cannot be separated without tearing the splenic pulp.] Numerous **trabeculæ** pass into the spleen from the deep surface of the capsule, where they branch and anastomose so as to produce a network of sustentacular tissue, which is continuous with the connective tissue, prolonged inward and surrounding the blood vessels (Fig. 120). Thus, the connective tissue in the spleen, as in other viscera, is continuous throughout the organ. In this way an irregular dense network is formed, comparable to the meshes of a bath sponge. [This network is easily demonstrated by washing out the pulp lying in its meshes by means of a stream of water, when a beautiful, soft, semi-elastic network or **framework** of rounded and flattened threads is obtained.] The **capsule** (Fig. 119) is composed of interlacing bundles of connective tissue mixed with numerous fine fibres of elastic tissue and some non-striped muscular fibres.

FIG. 119.



Section of human spleen × 10 times.

Reticulum.—Within the meshes of the trabecular framework there is disposed a very delicate network or reticulum of adenoid tissue, which, with the other colored elements that fill up the meshes, constitutes the splenic pulp (Fig. 121). The reticulum is continuous with the fibres of the trabeculæ. [If a fine section of the spleen be "penciled" in water, so as to remove the cellular elements, the preparation presents much the same characters as a section of a lymph gland similarly treated, viz., a very fine network of adenoid tissue, continuous with, and surrounding the walls of, the blood vessels. The spaces of this tissue are filled with lymph and blood corpuscles.]

The **pulp** is a dark, reddish-colored, semi-fluid material, which may be squeezed or washed out of the meshes in which it lies. It contains a large number of colored blood corpuscles, and becomes brighter when it is exposed to the action of the oxygen of the air.

Blood Vessels and Malpighian Corpuscles.—The large splenic artery, accompanied by a vein, splits up into several branches before it enters the spleen. Both vessels and their branches are enclosed in a fibrous sheath, which becomes continuous with the trabeculæ. The smaller branches of the artery gradually lose this fibrous investment, and each one ultimately divides into a group or pencil of arterioles or **penicilli**, *which do not anastomose with each other.* [Thus each branch is **terminal**—a condition which is of great importance in connection with the pathology of embolism or infarction of the vessels of the spleen.] At the points of division of the branches of the artery, or scattered along their course, are small oval or globular masses of adenoid tissue ($\frac{1}{15}$ to $\frac{1}{10}$ inch in diameter), the **Malpighian corpuscles.** [These bodies are visible to the naked eye as small, round, or oval white structures, about the size of millet seed, in a section of a fresh spleen. They are very numerous—[70,000 in man]—and are readily detected in the dark reddish pulp. One must be careful not to mistake sections of the trabeculæ for them. These corpuscles consist of adenoid tissue, whose meshes are filled with lymph corpuscles, and they present exactly the same structure as the solitary follicles of the intestine (§ 197). They are small lymphatic

accumulations around the arteries—**periarterial** masses of adenoid tissue similar to those masses that occur in a slightly different form in other organs, *e. g.*, the lungs. In a section of the spleen the artery may pass through the centre of the mass or through one side of it, and in some cases the tissue is collected unequally on opposite sides of the vessel, so that it is lop-sided. They are not surrounded by any special envelope. In some animals the lymphatic tissue is continued for some distance along the small arteries, so that to some extent it resembles a perivascular sheath of ade-

FIG. 120.

Trabeculæ of the spleen of a cat with the splenic pulp washed out. *a*, trabecula; *b*, vein.

FIG. 121.



Adenoid reticulum of spleen of cat.

noid tissue. In a well-injected spleen, a few fine capillaries are to be found within these corpuscles. The capillaries distributed in the substance of the Malpighian corpuscle (Fig. 122) form a network, and ultimately pour their blood into the spaces in the pulp. According to Cadiat, the corpuscles are separated from the splenic pulp by a lymphatic sinus, which is traversed by efferent capillaries passing to the pulp (Fig. 122).]

Connection of Arteries and Veins.—It is very difficult to determine what is the exact mode of termination of the arteries within the spleen, more especially as it is extremely difficult to inject the blood vessels of the spleen. According to Stieda and others, the fine "capillary arteries" formed by the division of the small arteries do not open directly into the capillary veins, but the connection between the arteries and veins is by means of the "**intermediary intercellular spaces**" of the reticulum of the spleen, so that, according to this view, there is no continuous channel lined throughout by epithelium connecting these vessels one with another. Thus the blood of the spleen flows into the spaces of the adenoid reticulum just as the lymph stream flows through the spaces in a lymph gland. According to Billroth and Kölliker, a closed blood channel actually does exist between the capillary arteries and the veins, consisting of dilated spaces (similar to those of erectile tissue). These intermediary spaces are said to be completely lined by spindle-shaped epithelium, which abuts externally on the reticulum of the pulp. [According to Frey, owing to the walls of the terminal vessels being incomplete, there being clefts or spaces between the cells composing them, the blood passes freely into spaces of the adenoid tissue of the pulp "in the same way as the water of a river finds its way among the pebbles of its bed," these "**intermediary passages**" being bounded directly by the cells and fibres of the network of the pulp. From these passages the venous radicals arise. At first, their walls are imperfect and cribriform, and they often present peculiar transverse markings, due to the circular disposition of the elastic fibres of the reticulum. The small veins have at first a different course from the arteries. They anastomose freely, but they soon become ensheathed, and accompany the arteries in their course.]

FIG. 122.

Malpighian corpuscle of a cat's spleen injected. *a*, artery; *b*, meshes of the pulp injected; *c*, the artery of the corpuscle ramifying in the lymphatic tissue composing it.

Elements of the Pulp (Fig. 123.)—The morphological elements are very various—(1) Lymph corpuscles of various sizes, sometimes partly swollen, and at other times with granular contents. (2) Red blood corpuscles. (3) Transition forms between 1 and 2 [although this is denied by some observers (§ 7, C)]. (4) Cells containing red blood corpuscles and pigment granules. [These cells exhibit amœboid movements.] (Compare § 8.)

[**Lymphatics** undoubtedly arise within the spleen, but they are not numerous. There are two systems—a superficial or capsular, and trabecular system; and a perivascular set. The **superficial** lymphatics in the capsule are rather more numerous. Some of them seem to communicate with the lymphatics within the organ (*Tomsa Kölliker*). In the horse's spleen they communicate with the lymphatics in the trabeculæ, and with the perivascular lymphatics. The exact mode of origin of the **perivascular** system is unknown, but in part at least it begins in the spaces of the adenoid tissue of the Malpighian corpuscles and perivascular adenoid tissue, and runs along the arteries toward the hilum. There seem to be no afferent lymphatics in the spleen such as exist in a lymphatic gland.

The **nerves** of the spleen are composed for the most part of non-medullated nerve fibres, and run along with the artery. Their exact mode of termination is unknown, but they probably go to the blood vessels and to the muscular tissue in the capsule and trabeculæ. [They are well seen in the spleen of the ox, and in their course very small ganglia, placed wide apart, have been found by Remak and W. Stirling.]

FIG. 123.

Elements of human splenic pulp. 1, colorless cells; 2, endothelium; 3, colored blood corpuscles; 4, cells containing granules, the upper one with a colorless blood corpuscle, *b*, enclosed.

Chemical Composition.—Several of the more highly oxidized stages of albuminous bodies exist in the spleen. Besides the ordinary constituents of the blood, there exist leucin, tyrosin, xanthin, hypoxanthin; lactic, butyric, acetic, formic, succinic, and uric acids, and perhaps glycero-phosphoric acid (*Salkowski*); cholesterin, a gluten-like body, inosit, a pigment containing iron, and even free iron oxide (*Nasse*). The ash is rich in phosphoric acid and iron (p. 195)—poor in chlorine compounds. The splenic juice is alkaline in reaction; the specific gravity of the spleen = 1059–1066.

The **functions** of the spleen are obscure, but we know some facts on which to form a theory. [The spleen differs from other organs in that no very apparent effect is produced by it, so that we must determine its uses in the economy from a consideration of such facts as the following: (1) The effects of its removal or extirpation. (2) The changes which the blood undergoes as it passes through it. (3) Its chemical composition. (4) The results of experiments upon it. (5) The effects of diseases.]

(1) **Extirpation.**—The spleen may be removed from an animal—old or young—without the organism suffering any very obvious change (*Galen*). The human spleen has been successfully removed by *Köberle*, *Péan*, and others. As a result (compensatory?) the lymphatic glands enlarge, but not constantly, while the blood-forming activity of the red marrow of bone is increased. Small brownish-red patches were observed in the intestines of frogs after extirpation of the spleen. These new formations are regarded by some observers as compensatory organs. Tizzoni asserts that new splenic structures are formed in the omentum (horse, dog) after the destruction of the parenchyma and blood vessels of the spleen. The spleen is absent extremely seldom.

[The weight of the animal (dog) diminishes after the operation, but afterward increases. The number of red blood corpuscles is lessened, reaching its minimum about the 150th to the 200th day, while the colorless corpuscles are increased in number. The lymphatic glands (especially the internal, and those in the neck, mesentery, and groin) enlarge, while on section the cortical substance of these structures is redder, owing to the great number of red corpuscles, many of them are nucleated in the lymph spaces (*Gibson*). The marrow of all the long bones (those of the foot excepted), becomes very red and soft, with the characters of embryonic bone-marrow. Such animals withstand hemorrhage (to ⅓ of the total amount of blood) without any specially bad results (*Tizzoni, Winogradow*). Schindeler observed that animals after extirpation of the spleen became very ravenous.]

[**Regeneration.**—After entire removal of the spleen, nodules of splenic tissue are reproduced (fox); while new adenoid tissue is formed in the lymphatic glands, and in Peyer's patches, the parenchyma of the former coming to resemble splenic tissue (*Tizzoni, Eternod.*)]

(2) According to Gerlach and Funke the spleen is a **blood-forming gland.** The blood of the splenic vein contains far more colorless corpuscles than the blood of the splenic artery (p. 55). Many of these corpuscles undergo fatty degeneration, and disappear in the blood stream. That colorless blood corpuscles are formed within the spleen seems to be proved by the enormous number of these corpuscles which are found in the blood in cases of leukæmia (*Bennett* (1852), *Virchow*). Bizzozero and Salvioli found that, several days after severe hemorrhage, the spleen became enlarged, and its parenchyma contained numerous red nucleated hæmatoblasts.

(3) Other observers (*Kölliker and Ecker*) regard the spleen as an organ in which **colored blood corpuscles are destroyed,** and they consider the large protoplasmic cells containing pigment granules as a proof of this (p. 53). According to the observations of Kusnetzow, these structures are merely lymph corpuscles, which, in virtue of their amœboid movements, have entangled colored blood corpuscles. [Such corpuscles exhibit similar properties when placed upon a warm stage.] Similar cells occur in extravasations of blood. The colored blood corpuscles within the lymph cells gradually become disintegrated, and give rise to the production of granules of hæmatin and other derivatives of hæmoglobin. [The spleen contains so much free iron that a section of this organ, especially from a young animal, when treated with Tizzoni's fluid, *i. e.*, with potassic ferrocyanide and hydrochloric acid, gives a distinct blue color (§ 174, 4).] Hence, the spleen contains more *iron* than corresponds to the amount of blood present in it. When we consider that the spleen contains a large number of extractives derived from the decomposition of proteids, it is very probable that colored blood corpuscles are destroyed in the spleen. Further, the juice of the spleen contains salts similar to those that occur in the red blood corpuscles.

The blood from the spleen is said to have undergone other changes, but the following statement must be accepted with caution: The blood of the **splenic vein** contains more water and fibrin, its red blood corpuscles are smaller, brighter, less flattened, more resistant, and do not form rouleaux; its hæmoglobin crystallizes more easily, and there is a large proportion of O during digestion.

[The spleen has therefore very direct relations to the blood; in it colored blood corpuscles undergo disintegration, it produces colorless corpuscles, and it is said to transform white corpuscles into red.]

(4) **Contraction.**—In virtue of the plain muscular fibres in its capsule and trabeculæ, the spleen undergoes variations in its volume. Stimulation of the spleen or its nerves, by cold, electricity, quinine, eucalyptus, ergot of rye, and other "**splenic reagents**" causes it to contract, whereby it becomes paler, and its surface may even appear granular. *After a meal*, the spleen increases in size, and it is usually largest about five hours after digestion has begun, *i. e.*, at a time when the digestive organs have almost finished their work, and have again become less vascular. After a time it regains its original volume. For this reason the spleen was formerly regarded as an apparatus for regulating the amount of blood in the digestive organs. [The congestion of the spleen after a meal is more probably related to the formation of new colorless corpuscles than to the destruction of red corpuscles. It may be, however, that some of the products of digestion are partially acted upon in the spleen, and undergo further change in the liver.] There is a relation between the size of the spleen and that of the liver, for it is found that when the spleen contracts—*e. g.*, by stimulation of its nerves—the liver becomes enlarged, as if it were injected with more blood than usual (*Drosdow and Botschetschkarow*).

[**Oncograph.**—Botkin, and more recently Roy, have studied various conditions which affect the size of the spleen. Roy enclosed the spleen of a dog in a box with rigid walls, the oncograph (ὄγκος, volume), and filled with oil after the manner of the plethysmograph (§§ 101, 276). Any variations in the size of the organ caused a variation in the amount of oil within the box, and these variations were

recorded. The blood pressure was recorded at the same time. The circulation through the spleen is peculiar, and is not due to the blood pressure within the arteries, but is carried on chiefly by a rhythmical contraction of the muscular fibres of the capsule and trabeculæ. The spleen undergoes very regular rhythmical contractions (**systole**) and dilatations (**diastole**). This alternation of systole and diastole may last for hours, and the two events together occupy about one minute (Fig. 124). Changes in the arterial blood pressure have comparatively little influence on the volume of the spleen. The rhythmical contractions, although modified, still go on after section of the splenic nerves. This would seem to indicate that the spleen has an independent (nervous) mechanism within itself, causing its movements.]

[**Influence of Nerves.**—Section of the splenic nerves is followed by an increase in the size of the spleen. The nerves have their centre in the medulla oblongata. Stimulation of the medulla oblongata, either directly or by means of asphyxiated blood, causes contraction of the spleen, hence the spleen is "small and contracted" in death from asphyxia. The fibres proceed down the cord,

FIG. 124.



Tracing of a splenic curve, reduced one-half, taken with the oncograph. The upper line with large waves is the splenic curve; each ascent corresponds to an increase, and each descent to a diminution in the volume of the spleen. The curve beneath is a blood-pressure tracing from the carotid artery. The lowest line indicates the time, the interruptions of the marker occurring every two seconds. The vertical lines, *a* and *b*, give the relative positions of the lever point of the oncograph, and of the point of the recording style of the kymograph respectively (*Roy*).

and leaving it in the dorsal region, enter the left splanchnic, pass through the semilunar ganglion, and thus reach the splenic plexus. Stimulation of the peripheral ends of these nerves causes contraction of the spleen, and so does cold applied to the spleen directly or over the region of the organ. In the last case the result is brought about reflexly. Botkin found that the application of the induced current to the skin over the spleen, in a case of leukæmia, caused well-marked contraction of the spleen in all its dimensions, and the result lasted some time. After every stimulation the number of colorless corpuscles in the blood increased, and the condition of the patient improved.]

[There is a popular notion that the spleen is influenced by the condition of the nervous system. Botkin found that depressing emotions increased its size, while exhilarating ideas diminished it. The **causes** of these changes are referable not only to changes in the amount of blood in the spleen, but also to the greater or less degree of contraction of its muscular tissue. And it would appear that, like the small arteries, the muscular tissue of the spleen is in a state of **tonic con-**

traction. The size of the spleen may be influenced **reflexly.** Thus, Tarchanoff found that stimulation of the *central* end of the vagus, when the splanchnics were intact, caused contraction of the spleen, while stimulation of the *central* end of the sciatic also caused contraction, but to a less degree. It is quite certain that all the phenomena are not due to the action of vasomotor nerves on the splenic blood vessels. There is a certain amount of independent action of the muscular fibres of the organ, and it is not improbable that the innervation of the spleen is similar to the innervation of arteries, and that it has a motor centre in the cord capable of being influenced reflexly by afferent nerves, while it also sends out efferent impulses.]

[Stimulation of (1) the central end of a sensory nerve; (2) of the peripheral ends of both splanchnics; (3) of the peripheral ends of both vagi, causes contraction of the spleen. But even after section of the splanchnics and vagi, stimulation of a sensory nerve still causes contraction, so that there must be some other channel as yet unknown (*Roy*). Bochefontaine found that electrical stimulation of certain parts of the cortex cerebri produced contraction of the spleen.] *Sensory* nerves seem to occur only in the peritoneum covering the spleen.

Pressure on the splenic vein causes enlargement of the spleen, hence, increased pressure in this vein (congestion of the portal vein, cessation of hæmorrhoidal and menstrual discharges) also causes its enlargement. With regard to the action of "**splenic reagents,**" such as **quinine,** on the contraction of the spleen, Binz is of opinion that this drug retards the formation of the colorless blood corpuscles, so that its chief function is interfered with and the organ becomes less vascular. It is not definitely decided, however, whether it is contraction or dilatation of the spleen that alters the proportion of red and white corpuscles in the blood.

Splenic Tumors.—The increase in size of the spleen in various diseases early attracted the attention of physicians. The healthy spleen undergoes several variations in volume during the course of a day, corresponding with the varying activity of the digestive organs. In this respect the spleen resembles the arteries. In many fevers the spleen becomes greatly enlarged, probably due to paralysis of its nerves. It is greatly increased in intermittent fever or ague, and often during the course of typhus. When it becomes abnormally enlarged, and remains so after repeated attacks of the ague, it is greatly hypertrophied, and constitutes "**ague cake.**" In cases of splenic leukæmia it is greatly enlarged, and at the same time there is a great increase in the number of colorless corpuscles in the blood and also a decrease of the colored ones (§ 10).

FIG. 125.

Section of the thymus gland of a cat, with one complete lobule with a cortical part *a*, and a centre, *b*. *a*, lymphoid tissue; *c*, blood vessels injected; *d*, connective tissue.

II. The Thymus.—During fœtal life this gland is largely developed, and it increases during the first two or three years of life, remaining stationary until the tenth or fourteenth year, when it

FIG. 126.

Elements of the thymus (× 300). *a*, lymph corpuscles; *b*, concentric corpuscle of Hassall.

begins to atrophy and undergo fatty degeneration. [The degeneration begins at the outer part of each lobule and progresses inward (*His*).]

Structure.—"It consists of an aggregation of lymph follicles (resembling the glands of Peyer) or masses of adenoid tissue held together by a framework of connective tissue which contains blood vessels, lymphatics, and a few nerves (Fig. 125). The **framework** of connective tissue gives off septa which divide the gland into **lobes,** these being further subdivided by finer septa into **lobules,** the lobules being separated by fine intra-lobular lamellæ of connective tissue into **follicles** (0.5–1.5

mm.). These follicles make up the gland substance, and they are usually polygonal when seen in a section. Each follicle consists of a **cortical** and a **medullary** part, and the matrix or framework of both consists of a fine adeniod reticulum whose meshes are filled with lymph corpuscles" (Fig. 126, *a*).] Many of these corpuscles exhibit various stages of disintegration. In the medulla are found the **concentric corpuscles of Hassall.** ["They consist of a central granular part, around which are disposed layers of flattened, nucleated, endothelial cells arranged concentrically. When seen in a section they resemble the 'cell nests' of epithelioma (Fig. 126, *b*). They have also been compared to similar bodies which occur in the prostate. They are most numerous when the gland undergoes its retrograde metamorphosis." Sig. Mayer finds that the thymus of the frog contains structures, with transverse markings, identical with the stripes of striped muscular fibres. The structures are identical with those called "**sarcoplasts**" by Margo and Paneth, and "**sarcolytes**" by Sig. Mayer. They also occur in large numbers in the tail of the larvæ of batrachians, when the tail is undergoing a retrograde metamorphosis.]

Simon, His, and others described a convoluted blind canal, the "**central canal,**" as occurring within the gland, and on it the follicles were said to be placed. Other observers, Jendrassik and Klein, either deny its existence or regard it merely as a lymphatic or an artificial product. Numerous fine **lymphatics** penetrate into the interior of the organ, and many are distributed over its surface, but their mode of origin is unknown. [They seem to be channels through which the lymph corpuscles are conveyed away from the gland.] Numerous **blood vessels** are also distributed to the septa and follicles (Fig. 125, *c*).

Chemical Composition.—Besides gelatin, albumin, soda albumin, there are sugar and fat, leucin, xanthin, hypoxanthin, formic, acetic, butyric, and succinic acids. Potash and phosphoric acid are more abundant in the *ash* than soda, calcium, magnesium (? ammonium), chlorine, and sulphuric acid.

Function.—As long as it exists, it seems to perform the functions of a true lymph gland. This view is supported by the fact that in reptiles and amphibians, which do not possess lymph glands, the thymus remains as a permanently active organ. [**Extirpation** gave few positive results, but chemical investigation shows that the parenchyma contains a large number of products indicating considerable metabolic activity (*Friedleben*).]

III. The Thyroid.—Structure.—The gland consists of **lobes** and **lobules** held together by connective tissue rich in cells. Each lobule is made up of numerous **completely closed sacs** (0.04 to 0.1 mm. in diameter), which in the embryo and the newly-born animal are composed of a membrana propria lined by a single layer of nucleated cells (Fig. 127). The sacs contain a transparent, viscid, albuminous fluid. [Not unfrequently the sacs contain many colored blood corpuscles (*Baber*).] Each sac is surrounded by a plexus of capillaries which do not penetrate the membrana propria. There are also numerous lymphatics. At an early period the sacs dilate, their cellular lining atrophies, and their contents undergo colloid degeneration. When the gland vesicles are greatly enlarged, "**goitre**" is produced.

FIG. 127.

Section of the thyroid gland. *a*, closed vesicles; *b*, distended by colloid masses and lined by low columnar epithelium; *c*, inter-vesicular connective tissue.

The **chemical composition** of this gland has not been much investigated. In addition to the ordinary constituents, leucin, xanthin, sarkin, lactic, succinic, and volatile fatty acids have been found.

[**Excision.**—The effects differ according to the animal operated on. This gland has been excised in the human subject in cases of goitre. Reverdin pointed out that a peculiar condition results, called **cachexia stumipriva**, and practically the human being becomas a cretin. This operation, therefore, is highly questionable when performed on man. **Rabbits** endure the operation well, and so do the sheep, calf, and horse. Of **dogs**, cats, and foxes, only a very small number survive, nearly all die. It appears therefore that herbivora bear the operation and suffer fewer after-effects than carnivora (*Sanquirico and Orecchia*). The immediate effects are fibrillar contractions, which ultimately influence the gait of the animals, convulsions, anæsthesia, great diminution of sensibility, loss of flesh, redness of the ears and intense heat of the skin (which disappear after several days), difficulty in seizing and eating food, kerato-conjunctivitis, and frequently disturbance of the rhythm of respiration with dyspnœa and spasms of the abdominal muscles (*Schiff*). The arterial blood contains about the same amount of O as venous blood. Certain parts of the peripheral nerves undergo a kind of degenera-

tion similar to that found after nerve stretching. There is albuminuria and fall of the blood pressure. Death usually occurs between the third and fourth day, the animals being comatose (*Wagner*). Schiff found that if one-half of the gland was excised at once, and the other half a month afterward, death did not occur; but Wagner denies this, for he asserts that the remaining half hypertrophies, and if it be excised, death occurs with the usual symptoms. In **monkeys**, five days after the operation, there are symptoms of nervous disturbance. The animals have lost their appetite, there are fibrillar contractions of the muscles of the face, hands, and feet, but the tremors disappear on voluntary effort. The appetite returns and is increased, but notwithstanding, the animal grows thin and pale; while the tremors increase and affect all the muscles of the body. These tremors are of *central* origin, because they disappear on dividing the nerve. Thus there is profound alteration of the motor powers. Among the outward symptoms are puffiness of the eyelids, swelling of the abdomen, increased hebetude, and dyspnœa, while afterward there is a fall of the temperature and imbecility; the tremors disappear, there is a pallor of the skin, and ultimately after five to seven weeks the animals die comatose. Thus there is a slow onset of hebetude, terminating in imbecility. Very remarkable changes occur in the blood. There is a steady fall of the blood pressure; a diminution of the red blood corpuscles, or rather profound anæmia; leucocythæmia, the colorless corpuscles being increased to the ratio of four to fourteen; and lastly **mucin** is present in the blood, although normally it is not so. The salivary glands are hypertrophied, owing to the presence of mucin, which is found even in the parotid, although this is normally a serous gland (§ 141). The swelling of the abdomen is due to hypertrophy of the great omentum. Mucin is found in the peritoneal fluid, and the spleen is also enlarged. Thus these symptoms present many features in common with those of **myxœdema** as described by Ord (*v. Horsley*).]

[**Stages.**—Horsley distinguishes three stages. In the first or **neurotic** stage the animals exhibit constant tremors, 8 per second, and young animals do not appear to survive this stage. In the second or **mucinoid** stage, mucin is deposited in the tissues and blood; this change, however, is only seen to perfection in monkeys. If these animals be kept at a high artificial temperature, their life is considerably prolonged. In the third, **atrophic**, or **marasmic** period, the animals die of marasmus, while they lose their excess of mucin. **Age** seems to exert an important influence in thyroidectomy; young dogs survive but a short time, while old dogs merely exhibit symptoms of indolence and incapacity; and, as a matter of fact, the activity of the gland seems to be most active when tissue metabolism is most active.]

[The following table, after Horsley, indicates the symptoms that follow **loss of the function of the thyroid gland**:—

Stages.	Duration.	Symptoms.	Remarks.
I. **Neurotic.**	1 to 2 weeks in dogs; 1 to 3 weeks in monkeys.	Tremors, rigidity, dyspnœa.	Young dogs and monkeys alike die in this stage.
II. **Mucinoid.**	½ to 1 week in dogs; 3 to 7 weeks in monkeys.	Commencing hebetude and mucinoid degeneration of the connective tissues.	Dogs survive only to the beginning of this stage; monkeys die at the end, if not treated.
III. **Atrophic.**	5 to 8 weeks in monkeys.	Complete imbecility and atrophy of all tissues, especially muscles.	Monkeys survive according to the temperature of the air-bath.]

Functions.—The functions of the thyroid gland are very obscure. Perhaps it may be an apparatus for regulating the blood supply to the head (?). It becomes enlarged in **Basedow's disease**, in which there is great palpitation, as well as protrusion of the eyeball or exophthalmos, which seem to depend upon a simultaneous stimulation of the accelerating nerve of the heart, and the sympathetic fibres of the smooth muscles in the orbital cavity and the eyelids, as well as of the inhibitory fibres of the vessels of the thyroid. In many localities it is common to find swelling of the thyroid constituting **goitre**, which is sometimes, but far from invariably, associated with idiocy and cretinism. [Horsley finds that its removal is the essential cause of myxœdema and cretinism. He regards it (1) as a **blood-forming gland**, so that it has a hæmapoietic function, but Gibson finds no grounds for supporting this view. During the anemia resulting from its removal, the blood of the thyroid vein contains 7 per cent. more red blood corpuscles than the corresponding artery (*Horsley*). (2) It seems to regulate the formation of **mucin** in the body. After its removal the normal metabolism is no longer maintained, and there is a corresponding increasingly defective condition of nutrition.]

In the Tunicata, this gland, represented by a groove, secretes a digestive fluid. In vertebrates, it is an organ which has undergone a retrograde change (*Gegenbaur*).

IV. The Suprarenal Capsules.—Structure.—These organs are invested by a thin **capsule** which sends processes into the substance of the organ. They consist of an outer (broad) or **cortical** layer and an inner (narrow) or **medullary** layer. The former is yellowish in color, firm and striated, while the latter is softer and deeper in tint. In the outermost zone of the **cortex** (Fig. 128, *b*), the trabeculæ form polygonal meshes, which contain the cells of the gland substance; in the broader middle zone the meshes are elongated, and the cells filling them are arranged in columns radiating outward. Here the cells are transparent and nucleated, often containing oil globules; in the innermost narrow zone the polygonal arrangement prevails, and the cells often contain yellowish-brown pigment. In the **medulla** (*c*), the stroma forms a reticulum containing groups of cells of very irregular shape. Numerous **blood vessels** occur in the gland, especially in the cortex. [The **nerves** are extremely numerous, and are derived from the renal and solar plexuses. Many of the fibres are medullated. After they enter the gland, numerous ganglionic cells occur in the plexuses which they form. Indeed, some observers regard the cells of the medulla as nervous. Undoubtedly, numerous *multipolar nerve cells* exist within the gland.]

Chemical Composition.—The suprarenals contain the constituents of connective and nerve tissue; also leucin, hypoxanthin, benzoic, hippuric, and taurocholic acids, taurin, inosit, fats, and a body which becomes pigmented by oxidation. Among inorganic substances potash and phosphoric acid are most abundant.

FIG. 128.

Section of a human suprarenal capsule. *a*, capsule; *b*, gland cells of the cortex arranged in columns; *c*, glandular network of the medulla; *d*, blood vessels.

The **function** of the suprarenal bodies is very obscure. It is noticeable, however, that in **Addison's disease** ("bronzed skin"), which is perhaps primarily a nervous affection, these glands have frequently, but not invariably, been found to be diseased. Owing to the injury to adjacent abdominal organs, **extirpation** of these organs is often, although not always, fatal; in dogs pigmented patches have been found in the skin near the mouth. Brown-Séquard thinks they may be concerned in preventing the over-production of pigment in the blood.

[**Spectrum.**—MacMunn finds that the medulla of the suprarenal bodies (in man, cat, dog, guinea pig, rat, etc.) gives the spectrum of hæmochromogen (§ 18), while the cortex shows that of what he calls **histohæmatin**, the latter being a group of respiratory pigments. He finds that hæmochromogen is only found in excretory organs (the bile, the liver), hence he regards the medulla as **excretory**, so that part of the function of the adrenals may be "to metamorphose effete hæmoglobin or hæmatin into hæmochromogen," and when they are diseased, the effete pigment is not removed, hence the pigmentation of the skin and mucous membranes. Taurocholic acid has been found in the medulla by Vulpian, and pyrocatechin by Krukenberg. MacMunn believes that "they have a large share in the downward metamorphosis of coloring matter."]

V. Hypophysis Cerebri—Coccygeal and Carotid Glands.—The **hypophysis cerebri**, or **pituitary body**, consists of an anterior lower or larger lobe, partly embracing the posterior lower or smaller lobe. These two lobes are distinct in their structure and development. The *posterior* lobe is a part of the brain, and belongs to the infundibulum. The nervous elements are displaced by the ingrowth of connective tissue and blood vessels. The *anterior* portion represents an inflected and much altered portion of ectoderm, from which it is developed. It contains gland-like structures, with connective tissue, lymphatics, and blood vessels, the whole being surrounded by a capsule. According to Ecker and Mihalkowicz, it resembles the suprarenal capsule in its structure, while, according to other observers, in some animals it is more like the thyroid. Its functions are entirely unknown. [**Excision.**—Horsley has removed this gland twice successfully in dogs, which lived from five to six months. No nervous or other symptoms were noticed, but when the cortex of the brain was exposed and stimulated, a great increase in the excitability of the motor regions was induced, even slight stimulation being followed by violent tetanus and prolonged epilepsy.]

Coccygeal and **Carotid Glands.**—The former, which lies on the tip of the coccyx, is composed to a large extent of plexuses of small, more or less cavernous, arteries, supported and enclosed by septa and a capsule of connective tissue (*Luschka*). Between these lie polyhedral granular cells arranged in networks. The carotid gland has a similar structure (p. 118). Their functions are quite unknown. Perhaps both organs may be regarded as the remains of embryonal blood vessels (*Arnold*).

104. **COMPARATIVE.**—The heart in **fishes** (Fig. 129, I), as well as in the larvæ of amphibians with gills, is a **simple venous heart**, consisting of an auricle and a ventricle. The ventricle propels the blood to the gills, where it is oxygenated (arterialized); thence it passes into the aorta to be distributed to all parts of the body, and returns through the capillaries of the body and the veins to the heart. The **amphibians** (frogs) have **two auricles** and **one ventricle** (Frog, II). From the latter there proceeds *one* vessel which gives off the pulmonary arteries, and as the aorta supplies the rest of the body with blood, the veins of the systemic circulation carry their blood to the right auricle, those of the lung into the left auricle. In fishes and amphibians there is a dilatation at the commencement of the aorta, the bulbus arteriosus, which is partly provided with strong muscles. The **reptiles** (III) possess two separate auricles, and two imperfectly separated ventricles. The aorta and pulmonary artery arise separately from the two latter chambers. The venous blood

FIG. 129.



Schemata of the circulation. I. *Fish.*—*A*, auricle; *S*, sinus venosus; *V*, ventricle; *B*, bulbus aortæ: *c*, branchial arteries; *i*, branchial vessels; *Vv*, branchial veins; *E*, circulus cephalicus aortæ; *F*, common aorta; *G*, caudal artery; *H*, duct of Cuvier; *I*, anterior, and *K*, posterior cardinal veins; *L*, caudal vein; *M*, *M*, kidneys. II. *Frog.*—I, sinus venosus; II and III, right and left auricles; IV, ventricle; V, aorta with the bulb; 1, pulmonary arteries; 2, arch of the aorta; 3, carotid; 4, lingual; 5, carotid gland, and 6, axillary arteries; 7, common aorta; 8, cœliac artery; 9, cutaneous artery; *Vv*, pulmonary veins; *p*, *p*, lungs. III. *Saurians.*—I, right auricle, with the venæ cavæ; II, right ventricle; III, left auricle; IV, left ventricle. V, anterior common aorta; 1, pulmonary artery; 2, arch of the aorta; 3, carotid artery; 4, posterior common aorta; 5, cœliac, and 6, subclavian, arteries; 7, pulmonary veins; 8, lungs. IV. *Tortoise.*—I, right auricle with the venæ cavæ; II, right, and IV, left ventricles; III, left auricle; 1 and 2, right and left aortæ; 3, posterior common aorta; 4, cœliac; 5, subclavian; 6, carotid, and 7, pulmonary arteries; 8, pulmonary veins.

of the systemic and pulmonary circulations flows separately into the right and left auricles, and the two streams are mixed in the ventricle. In some reptiles the opening in the ventricular septum seems capable of being closed. The complete separation of the ventricle into two is seen in Fig. IV, in the tortoise. The lower vertebrates have valves at the orifices of the venæ cavæ, which are rudimentary in birds and some mammals. All **birds** and **mammals** have two completely separate auricles and two separate ventricles. In the halicore the apex of the ventricles is deeply cleft. Some animals have accessory hearts, *e.g.*, the eel in its caudal vein. They are very probably lymph hearts (*Robin*). The veins of the wing of the bat pulsate (*Schiff*). The lowest vertebrate, **amphioxus**, has no heart, but only a rhythmically pulsating vessel.

Among **blood glands**, the thymus and spleen occur throughout the vertebrata, the latter being absent only in amphioxus and a few fishes.

Among **invertebrata** a *closed vascular system*, with pulsatile movement, occurs here and there, *e.g.*, among **echinodermata** (star fishes, sea urchins, holothurians) and the higher **worms**. The **insects** have a pulsating "*dorsal vessel*" as the central organ of the circulation, which is a contractile tube provided with valves and dilated by muscular action; the blood being propelled rhythmically in one direction into the spaces which lie among the tissues and organs, so that these animals do not possess a closed vascular system. The **mollusca** have a heart with a lacunar vascular system. The **cephalopods** (cuttle fish) have three hearts—a simple arterial heart, and two venous simple gill hearts, each placed at the base of the gills. The vessels form a completely closed circuit. The *lowest animals* have either a pulsatile vesicle, which propels the colorless juice into the tissues (infusoria), or the vascular apparatus may be entirely absent.

105. **HISTORICAL RETROSPECT.**—The ancients held various theories regarding the movement of the blood, but they knew nothing of its *circulation*. According to Aristotle (384 B.C.), the heart, the acropolis of the body, prepared in its cavities the blood, which streamed through the arteries as a nutrient fluid to all parts of the body, but never returned to the heart. With Herophilus and Erasistratus (300 B.C.), the celebrated physicians of the Alexandrian school, originated the erroneous view that the arteries contain air, which was supplied to them by the respiration (hence the name *artery*). They were led to adopt this view from the empty condition of the arteries after death. By experiments upon animals, Galen disproved this view (131–201 A.D.)—"Whenever I injured an artery," he says, "blood always flowed from the wounded vessel. On tying part of an artery between two ligatures, the part of the artery so included is always filled with blood."

Still, the idea of a single *centrifugal* movement of the blood was retained, and it was assumed that the right and left sides of the heart communicated directly by means of openings in the septum of the heart, until Vesalius showed that there are no openings in the septum. Michael Servetus (a Spanish monk, burned at Geneva, at Calvin's instigation, in 1553) discovered the pulmonary circulation. Cesalpinus confirmed this observation, and named it "Circulatio." Fabricius ab Aquapendente (Padua, 1574) investigated the valves in the veins more carefully (although they were known in the 5th century to Theodoretus, Bishop in Syria), and he was acquainted with the *centripetal* movement of the blood in the veins. Up to this time it was imagined that the veins carried blood from the centre to the periphery, although Vesalius was acquainted with the centripetal direction of the blood stream in the large venous trunks. At length **William Harvey**, who was a pupil of Fabricius (1604), demonstrated the complete circulation (1616–1619), and published his great discovery in 1628. [For the history of the discovery of the circulation of the blood, see the works of Willis on "W. Harvey," "Servetus and Calvin," those of Kirchner, and the various Harveian orations.]

According to Hippocrates, the heart is the origin of all the vessels; he was acquainted with the large vessels arising from the heart, the valves, the chordæ tendineæ, the auricles, and the closure of the semilunar valves. Aristotle was the first to apply the terms aorta and venæ cavæ; the school of Erasistratus used the term carotid, and indicated the functions of the venous valves. In Cicero a distinction is drawn between arteries and veins. Celsus mentions that if a vein be struck below the spot where a ligature has been applied to a limb, it bleeds, while Aretaeus (50 A.D.) knew that arterial blood was bright and venous dark. Pliny (†79 A.D.) described the pulsating fontanelle in the child Galen (131–203 A.D.) was acquainted with the existence of a bone in the septum of the heart of large animals (ox, deer, elephant). He also surmised that the veins communicated with the arteries by fine tubes. The demonstration of the **capillaries**, however, was only possible by the use of the **microscope**, and employing this instrument, Malpighi (1661) was the first to demonstrate the capillary circulation. Leuwenhoek (1674) described the capillary circulation more carefully, as it may be seen in the web of the frog's foot and other transparent membranes. Blancard (1676) proved the existence of capillary passages by means of injections. William Cooper (1697) proved that the same condition exists in warm-blooded animals, and Ruysch made similar injections. Stenson (born 1638) established the muscular nature of the heart, although the Hippocratic and Alexandrian schools had already surmised the fact. Cole proved that the sectional area of the blood stream became wider toward the capillaries (1681). Joh. Alfons Borelli (1608–1679) was the first to estimate the amount of work done by the heart.

PHYSIOLOGY OF RESPIRATION.

The **object** of respiration is to supply the oxygen necessary for the oxidation processes that go on in the body, as well as to remove the carbon dioxide formed within the body. The most important organs for this purpose are the **lungs.** There is an **outer** and an **inner respiration**—the former embraces the exchange of gases between the external air and the blood gases of the respiratory organs (lungs and skin)—the latter, the exchange of gases between the blood in the capillaries of the systemic circulation and the tissues of the body.

[The pulmonary apparatus consists of (1) an immense number of small sacs—the **air vesicles**—filled with air, and covered externally by a very dense plexus of capillaries; (2) **air passages**—the nose, pharynx, larynx, trachea, and bronchi communicating with (1); (3) the **thorax** with its muscles, acting like a pair of bellows, and moving the air within the lungs.]

106. STRUCTURE OF THE AIR PASSAGES AND LUNGS.—The lungs are compound tubular glands, which separate CO_2 from the blood. Each lung is provided with an excretory duct (bronchus) which joins the common respiratory passage of both lungs—the trachea.

Trachea.—The trachea and extra-pulmonary bronchi are similar in structure. The basis of the trachea consists of 16–20 **C**-shaped incomplete cartilaginous hoops placed over each other. These rings consist of hyaline cartilage, and are united to each other by means of tough fibrous tissue containing much elastic tissue, the latter being arranged chiefly in a longitudinal direction. The **function of the cartilages** is to keep the tube open under varying conditions of pressure. Pieces of cartilage having a similar function occur in the bronchi and their branches, but they are absent from the bronchioles, which are less than 1 mm. in diameter. In the smaller bronchi, the cartilages are fewer and scattered more irregularly. [In a transverse section of a large **intra-pulmonary bronchus**, two, three, or more pieces of cartilage, each invested by its perichondrium, may be found.] At the points where the bronchi subdivide, the cartilages assume the form of irregular plates embedded in the bronchial wall.

An *external fibrous layer* of connective tissue and elastic fibres covers the trachea and the extra-pulmonary bronchi externally. Toward the œsophagus, the elastic elements are more numerous, and there are also a few bundles of plain muscular fibres arranged longitudinally. Within this layer there are bundles of *non-striped muscular fibres* which pass transversely between the cartilages behind, and also in the intervals between the cartilages. [These pale reddish fibres constitute the **trachealis muscle**, and are attached to the inner surfaces of the cartilages at a little distance from their free ends. The arrangement varies in different animals—thus, in the cat, dog, rabbit, and rat the muscular fibres are attached to the *external* surfaces of the cartilages, while in the pig, sheep, and ox they are attached to their *internal* surfaces (*Stirling*).] Some muscular fibres are arranged longitudinally external to the transverse fibres. The **function** of these muscular fibres is to prevent too great distention when there is great pressure within the air passages.

The mucous membrane consists of a basis of very fine connective tissue, containing much adenoid tissue with numerous lymph corpuscles. Numerous elastic fibres are arranged chiefly in a longitudinal direction under the basement membrane. They are also abundant in the deep layers of the posterior part of the membrane opposite the intervals between the cartilages. A small quantity of loose **submucous** connective tissue containing the large blood vessels, glands, and lymphatics unites the mucous membrane to the perichondrium of the cartilages. The **epithelium** consists of a layer of columnar ciliated cells with several layers of immature cells under them. [The superficial layer of cells is columnar and **ciliated** (Fig. 130, *b*), while those lying under them present a variety of forms, and below all is a layer of somewhat flattened squames, *c*, resting on the basement membrane, *d*. These squames constitute a layer quite distinct from the basement membrane, and they form the layer described as **Débove's membrane.** They are active germinating cells, and play a most important part in connection with the regeneration of the epithelium, after the superficial layers have been shed, in such conditions as bronchitis. Not unfrequently a little viscid

mucus (*a*) lies on the free ends of the cilia. In the intermediate layer, the cells are more or less pyriform or battledore-shaped, with their long tapering process inserted among the deepest layer of squames. According to Drasch, this long process is attached to one of these cells and is an outgrowth from it, the whole constituting a "foot cell."]

Under the epithelium is the homogeneous **basement membrane**, through which fine canals pass, connecting the cement of the epithelium with spaces in the mucosa. [This membrane is well marked in the human trachea, where it plays an important part in many pathological conditions, *e.g.*, bronchitis. It is stained bright red with picrocarmine.] The cilia act so as to carry any secretion toward the larynx. Goblet cells exist between the ciliated columnar cells. Numerous small compound tubular **mucous glands** occur in the mucous membrane, chiefly between the cartilages. Their ducts open on the surface by means of a slightly funnel-shaped aperture, into which the ciliated epithelium is prolonged for a short distance. [The acini of some of these glands lie outside the trachealis muscle. The acini are lined by cubical or columnar secretory epithelium. In some animals (dog) these cells are clear, and present the usual characters of a mucus-secreting gland; in man, some of the cells may be clear, and others "granular," but the appearance of the cells depends upon the physiological state of activity.] These glands secrete the mucus, which entangles particles inspired with the air, and is carried toward the larynx by ciliary action. [Numerous **lymphatics** exist in the mucous and submucous coat, and not unfrequently small aggregations of adenoid tissue occur (especially in the cat) in the mucous coat, usually around the ducts of the glands. They are comparable to the solitary follicles of the alimentary tract. The **blood vessels** are not so numerous as in some other mucous membranes. [A plexus of **nerves** containing numerous ganglionic cells at the nodes exists on the posterior surface of the trachealis muscle. The fibres are derived from the vagus, recurrent laryngeal, and sympathetic (*C. Frankenhauser, W. Stirling, Kandarazi*).]

FIG. 130.



Transverse section of part of a human bronchus (× 450). *a*, precipitated mucus; *b*, ciliated columnar epithelium; *c*, deep germinal layer of cells (Dêbove's membrane); *d*, elastic basement membrane; *e*, elastic fibres divided transversely (inner fibrous layer); *f*, bronchial muscle; *g*, outer fibrous layer with leucocytes and pigment granules (black); below a mass of adenoid tissue.

[The **mucous membrane of the trachea and extra-pulmonary bronchi**, therefore, consists of the following layers from within outward:—

(1) Stratified columnar ciliated epithelium.
(2) A layer of flattened cells (Dêbove's membrane).
(3) A clear homogeneous basement membrane.
(4) A basis of areolar tissue, with adenoid tissue and blood vessels, and outside this a layer of longitudinal elastic fibres.

Outside this, again, is the **submucous coat**, consisting of loose areolar tissue, with the larger vessels, lymphatics, nerves, and mucous glands.]

[The **Bronchi.**—In structure the **extra-pulmonary bronchi** resemble the trachea. As they pass into the lung they divide very frequently, and the branches do not anastomose. In the **intra-pulmonary bronchi** the subdivisions become finer and finer, the finest branches being called **terminal bronchi**, or **bronchioles**, which open separately into clusters of air vesicles.]

[**Eparterial and Hyparterial Bronchi.**—As the bronchi proceed, one main trunk passes into the lung, running toward its base, and from it are given off branches dorsally and ventrally, and these branches again subdivide. In man one main branch comes off from the right bronchus and proceeds to the upper right lobe, *above* the place where the pulmonary artery crosses the bronchus. Such branches are called *eparterial*, and they are more numerous in birds. In man, all the branches, both on the right and left side, come off below the point where the pulmonary artery crosses the bronchus, and are called *hyparterial bronchi* (*C. Aeby*).]

[In the middle-sized **intra-pulmonary bronchi**, the usual characters of the mucous membrane are retained, only it is thinner; the cartilages assume the form of irregular plates situated in the outer wall of the bronchus; while the muscular fibres are disposed in a complete circle, constituting the **bronchial muscle** (Fig. 130, *f*). When this muscle is contracted, or when the bronchus as a whole is contracted, the mucous membrane is thrown into longitudinal folds, and opposite these folds the elastic fibres form large elevations. This muscle is particularly well developed in the smaller microscopic bronchi. Numerous elastic fibres, *e*, disposed longitudinally, exist under the basement membrane, *d*. They are continuous with those of the trachea, and are prolonged onward into the lung. The mucous membrane of the larger **intra-pulmonary bronchi** consists of the following layers from within outward :—

(1) Stratified columnar ciliated epithelium (Fig. 130, *b*).
(2) Dèbove's membrane (Fig. 130, *c*).
(3) Transparent homogeneous basement membrane (Fig. 130, *d*).
(4) Areolar tissue with longitudinal elastic fibres (Fig. 130, *e*).
(5) A continuous layer of non-striped muscular fibres disposed circularly (*bronchial muscle*, Fig. 130, *f*).

Outside this is the **submucous coat**, consisting of areolar tissue mixed with much adenoid tissue (Fig. 130, *g*), sometimes arranged in the form of cords, the **lymph-follicular cords.** It also contains the acini of the numerous **mucous glands**, blood vessels, and lymphatics. The ducts of the glands perforate the muscular layer, and open on the free surface of the mucous membrane. The submucous coat is connected by areolar tissue with the perichondrium of the **cartilages.** Outside the cartilages are the **nerves** and **nerve ganglia** accompanying the bronchial vessels. The branches of the pulmonary artery and of the pulmonary vein usually lie on opposite sides of the bronchus, while there are several branches of the bronchial arteries and veins. **Fat cells** also occur in the peribronchial tissue.]

In the **small bronchi** the cartilages and glands disappear, but the circular muscular fibres are well developed. They are lined by lower columnar ciliated epithelium, containing goblet cells.

Bronchioles.—After repeated subdivision, the bronchi form the "*smallest bronchi*" (about 0.5 to 1 mm.) or *lobular bronchial tubes*. Each tube is lined by a layer of ciliated epithelium, but the glands and cartilages have disappeared. These tubes have a few lateral **alveoli** or **air cells** communicating with them. Each smallest bronchus ends in a "respiratory bronchiole (*Kölliker*), which gradually becomes beset with more air cells, and in which squamous epithelium begins to appear between the ciliated epithelial cells. [Each bronchiole opens into several wider *alveolar* or **lobular passages.** Each passage is completely surrounded with air cells, and from it are given off several similar but wider blind branches, the **infundibula**, which, in their turn, are beset on all sides with *alveoli* or *air cells*. Several infundibula are connected with each bronchiole, and the former are wider than the latter. Each bronchiole, with its alveolar passages, infundibula, and air vesicles, is termed a **lobule**, whose base is directed outward, and whose apex may be regarded as a terminal bronchus. The lung is made up of an immense number of these lobules, separated from each other by septa of connective tissue, the **interlobular septa** (Fig. 133, *e*) which are continuous on the one hand with the sub-pleural connective tissue, and on the other with the peribronchial connective tissue.]

[There is an alteration in the structure of the bronchi, as we proceed from the larger to the smaller tubes. The cartilages and glands are the first structures to disappear. The circular bronchial muscle is well developed in the smaller bronchi and bronchioles, and exists as a continuous thin layer over the alveolar passages, but it is not continued over and between the air cells. Elastic fibres, continuous, on the one hand, with those in the smaller bronchi, and on the other with those in the walls of the air cells, lie outside the muscular fibres in the bronchioles and infundibula. In the respiratory bronchioles, the ciliated epithelium is reduced to a single layer, and is mixed with the stratified form of epithelium, while, where the alveolar passages open into the air cells or alveoli, the epithelium is non-ciliated, low, and polyhedral.]

Alveoli or Air Cells.—The form of the cells, which are 250 μ ($\frac{1}{100}$ inch) in diameter, may be more or less spherical, polygonal, or cup-shaped. They are disposed around and in communication with the alveolar passages. Their form is determined by the existence of a nearly structureless membrane, composed of slightly fibrillated connective tissue containing a few corpuscles. This is surrounded by numerous fine elastic fibres, which give to the pulmonary parenchyma its well-marked elastic characters (Fig. 132, *e*, *e*). These fibres often bifurcate, and are arranged with reference to the alveolar wall. They are very resistant, and in some cases of lung disease may be recognized in the sputum. A few non-striped muscular fibres exist in the delicate connective tissue between adjoining air vesicles. These muscular fibres sometimes become greatly developed in certain diseases (*Arnold, W. Stirling*). The air cells are lined by two kinds of cells; (1) large, transparent, clear, polygonal (nucleated?) **squames** or placoids (22–45 μ) lying over and between the capillaries in the alveolar wall (Fig. 131, *a*); (2) small, irregular, "**granular**," nucleated cells (7–15 μ) arranged singly or in groups (two or three) in the interstices between the capillaries. They are well seen in a cat's lung (Fig. 131, *a*). [When acted on with nitrate of silver the cement substance bounding the clear cells is stained, but the small cells become of a uniform brown, granular appearance, so

that they are readily recognized. Small holes or "**pseudo-stomata**" seem to exist in the cement substance, and are most obvious in distended alveoli. They open into the lymph-canalicular system of the alveolar wall (*Klein*), and through them the lymph corpuscles, which are always to be found on the surface of the air vesicles, migrate, and carry with them into the lymphatics particles of carbon derived from the air.] In the alveolar walls is a very dense plexus of fine **capillaries** (Fig. 132, *c*), which lie more toward the cavity of the air vesicle, being covered only by the epithelial lining of the air cells. Between two adjacent alveoli there is only a single layer of capillaries (man), and on the boundary line between two air cells the course of the capillaries is twisted, thus projecting sometimes into the one alveolus, sometimes into the other.

FIG. 131.



Air vesicles injected with silver nitrate. *a*, outlines of squamous epithelium; *b*, alveolar wall; *c*, young epithelium cell; *d*, aggregation of young epithelial cells germinating.

[The **number of alveoli** is stated to be about 725 millions, a result obtained by measuring the size of the air vesicles and ascertaining the amount of air in the lung after an ordinary inspiration, determining how much of this air is in the air vesicles and bronchi respectively. The superficial area of the air vesicles is about 90 square metres, or 100 times greater than the surface of the body (.8 to .9 sq. metre).]

The **Blood vessels** of the lung belong to two different systems: (A) **Pulmonary vessels** (lesser circulation). The branches of the pulmonary artery accompany the bronchi and are closely applied to them. [As they proceed they branch, but the branches do not anastomose, and ultimately they terminate in small arterioles, which supply several adjacent alveoli, each arteriole splitting up into capillaries for *several* air cells (Fig. 132, *v*, *c*). An efferent vein usually arises at the opposite side of the air cells, and carries away the purified blood from the capillaries. In their course these veins unite to form the *pulmonary veins*, which, again, are joined in their course by a few small bronchial veins. The veins usually anastomose in the earlier part of their course, while the corresponding arteries do not.] Although the capillary plexus is very fine and dense, its sectional area is less than the sectional area of the systemic capillaries, so that the blood stream in the pulmonary capillaries must be more rapid than that in the capillaries of the body generally. The pulmonary veins, unlike veins generally, are collectively narrower than the pulmonary artery (water is given off in the lung), and they have no valves. [The pulmonary artery contains venous blood, and the pulmonary veins pure or arterial blood.]

(B) The **bronchial vessels** represent the nutrient system of the lungs. They (1–3) arise from the aorta (or intercostal arteries) and accompany the bronchi without anastomosing with the branches of the pulmonary artery. In their course they give branches to the lymphatic glands at the hilum of the lung, to the walls of the large blood vessels (vasa vasorum), the pulmonary pleura, the bronchial walls, and the interlobular septa. The blood which issues from their capillaries is returned —*partly* by the pulmonary veins—hence, any considerable interference with the pulmonary circulation causes congestion of the bronchial mucous membrane, resulting in a catarrhal condition of that membrane. The greater part of the blood is returned by the *bronchial veins*, which open into the vena azygos, intercostal vein, or superior vena cava. The veins of the smaller bronchi (fourth order onward) open into the pulmonary veins, and the anterior bronchial also communicate with the pulmonary vein (*Zuckerkandl.*)

[The **Pleura.**—Each pleural cavity is distinct, and is a large serous sac, which really belongs to the lymphatic system of the lung. The pleura consists of two layers, **visceral** and **parietal**. The visceral pleura covers the lung; the parietal portion lines the wall of the chest, and the two layers of the corresponding pleura are continuous with one another at the root of the lung. The visceral pleura is the thicker, and may readily be separated from the inner surface of the chest. Structurally, the pleura resembles a serous membrane, and consists of a thin layer of fibrous tissue covered by a layer of endothelium. Under this layer, or the pleura proper, is a *deep* or *sub-serous* layer of looser areolar tissue, containing many elastic fibres. The layer of the pleura pulmonalis of some animals, as the guinea pig, contains a network of non-striped muscular fibres (*Klein*). Over the lung it is also continuous with the interlobular septa. The **interlobular septa** (Fig. 133, *e*) consist of bands

of fibrous tissue separating adjoining lobules, and they become continuous with the peribronchial connective tissue entering the lung at its hilum. Thus the fibrous framework of the lung is continuous throughout the lung, just as in other organs. The connection of the sub-pleural fibrous tissue with the connective tissue within the substance of the lung has most important pathological bearings. The interlobular septa contain lymphatics and blood vessels. The endothelium covering the parietal layer is of the ordinary squamous type, but on the pleura pulmonalis the cells are less flattened, more polyhedral, and granular. They must necessarily vary in shape with changes in the volume of the lung, so that they are more flattened when the lung is distended, as during inspiration. The pleura contains many lymphatics, which communicate by means of **stomata** with the pleural cavity.]

[The **Lymphatics** of the lung are numerous, and are arranged in several systems. The various air cells are connected with each other by very delicate connective tissue, and, according to J. Arnold, in some parts this interstitial tissue presents characters like those of adenoid tissue; so that the lung is traversed by a system of **juice canals** or "Saft-canälchen."] [In the deep layer of the pleura there is a (*a*) **sub-pleural** plexus of lymphatics partly derived from the pleura, but chiefly

FIG. 132.

Semi-diagrammatic representation of the air vesicles of the lung. *v*, *v*, blood vessels at the margins of an alveolus; *c*, *c*, its blood capillaries; E, relation of the squamous epithelium of an alveolus to the capillaries in its wall; *f*, alveolar epithelium shown alone; *e*, *e*, elastic tissue of the lung.

from the lymph-canalicular system of the pleural alveoli. Some of these branches proceed to the bronchial glands, but others pass into the interlobular septa, where they join (*b*) the **perivascular** lymphatics which arise in the lymph-canalicular system of the alveoli. These trunks, provided with valves, run alongside the pulmonary artery and vein, and in their course they form frequent anastomoses. Special vessels arise within the walls of the bronchi, and occur chiefly in the outer coat of the latter, constituting (*c*) the **peri-bronchial** lymphatics, which anastomose with *b*. The branches of these two sets run toward the bronchial glands. Not unfrequently (cat) masses of adenoid tissue are found in the course of these lymphatics.] The lymph-canalicular system and the lymphatics become injected when fine-colored particles are inspired, or are introduced into the air cells artificially. The pigment particles pass through the semi-fluid cement substance into the lymph-canalicular system and thence into the lymphatics; or, according to Klein, they pass through actual holes or pores in the cement (p. 206).] [This pigmentation is well seen in coal-miner's lung or **anthracosis**, where the particles of carbon pass into and are found in the lymphatics. Sikorski and Küttner showed that pigment reached the lymphatics in this way during life. If pigment,

China ink, or indigo carmine be introduced into a frog's lung, it is found in the lymphatic system of the lung. Ruppert, and also Schotielius, showed that the same result occurred in dogs after the inhalation of charcoal, cinnabar, or precipitated Berlin blue, and von Ins after the inhalation of silica. Schestopal used China ink and cinnabar suspended in ¾ per cent. salt solution.] Excessively fine lymph canals lie in the wall of the alveoli in the interspaces of the capillaries, and there are slight dilatations at the points of crossing. According to Pierret and Renaut every air cell of the lung of the ox is surrounded by a large lymph space, such as occurs in the salivary glands. When a large quantity of fluid is injected into the lung, it is absorbed with great rapidity; even blood corpuscles rapidly pass into the lymphatics.

The **superficial** lymphatics of the pulmonary pleura communicate with the pleural cavity by means of free openings or **stomata**, and the same is true of the lymphatics of the parietal pleura, but these stomata are confined to limited areas over the diaphragmatic pleura. [The lymphatics in the costal pleura occur over the intercostal spaces and not over the ribs (*Dybkowski*).] The large arteries of the lung are provided with lymphatics which lie between the middle and outer coats. [The movements of the lung during respiration are most important factors in moving the lymph onward in the pulmonary lymphatics. The reflux of the lymph is prevented by the presence of valves.]

FIG. 133.



Human lung (× 50 and reduced ¼). *a*, small bronchus; *b*, *b*, pulmonary artery; *c*, pulmonary vein; *e*, interlobular septa, continuous with the deep layer of the pleura, *p*.

[The **nerves** of the lung are derived from the anterior and posterior pulmonary plexuses, and consist of branches from the vagus and sympathetic. They enter the lungs and follow the distribution of the bronchi, several sections of nerve trunks being usually found in a transverse section of a large bronchial tube. The nerves lie outside the cartilages, and are in close relation with the branches of the bronchial arteries. Medullated and non-medullated nerve fibres occur in the nerves, which also contain numerous small **ganglia** (*Remak*, *Klein*, *Stirling*). In the lung of the calf the ganglia are large. The exact mode of termination of the nerve fibres within the lung has yet to be ascertained in mammals, but some fibres pass to the bronchial muscle, others to the large blood vessels of the lung, and it is highly probable that the mucous glands are also supplied with nerve filaments. In the comparatively simple lungs of the frog, nerves with numerous nerve cells in their course are found (*Arnold*, *Stirling*), and in the very simple lung of the newt, there are also numerous nerve cells disposed along the course of the intra-pulmonary nerves. Some of these fibres terminate in the uniform layer of non-striped muscle which forms part of the pulmonary wall in the frog and newt, and others end in the muscular coat of the pulmonary blood vessels (*Stirling*). The functions of these ganglia are unknown, but they may be compared to the nerve plexuses existing in the walls of the digestive tract.]

The **Function** of the **non-striped muscle** of the entire bronchial system seems to be to offer a sufficient amount of resistance to increased pressure within the air passages; as in forced expiration, speaking, singing, blowing, etc. The vagus is the motor nerve for these fibres; and according to Longet, the "lung-tonus" during increased tension depends upon these muscles.

[**Effect of Nerves.**—By connecting the interior of a small bronchus with an oncograph (§ 103) in curarized dogs (the thorax being opened), Graham Brown and Roy found that **section** of one vagus causes a marked expansion of the bronchi of the corresponding lung, while **stimulation** of the peripheral end of a divided vagus causes a powerful contraction of the bronchi of *both* lungs.

Stimulation of the central end of one vagus, the other being intact, also causes a contraction (feebler) under the same circumstances. Especially in etherized dogs, expansion and not contraction results. If both vagi be divided, no effect is produced by stimulation of the central end of either vagus. It seems plain that the vagi contain centripetal or afferent fibres, which can cause both expansion and contraction of the bronchi. Asphyxia causes contraction provided the vagi are intact, but none if they are divided, although in etherized dogs expansion frequently occurs, while stimulation of the central end of other sensory nerves has very rarely any, or, if any, but a slight, effect on the calibre of the bronchi, so that in the dog the only connection between the cerebro-spinal centres and the bronchi is through the vagi.]

Pathological.—Stimulation of the smooth muscles, whereby a spasmodic narrowing of the smaller bronchi is produced, may excite asthmatic attacks. If the expiratory blast be interfered with, acute emphysema may take place (*Biernier*).

Chemistry.—In addition to connective, elastic, and muscular tissue, the lungs contain lecithin, inosit, uric acid (taurin and leucin in the ox), guanin, xanthin (?), hypoxanthin (dog)—soda, potash, magnesium, oxide of iron, much phosphoric acid, also chlorine, sulphuric and silicic acids—in diabetes sugar occurs—in purulent infiltration glycogen and sugar—in renal degeneration urea, oxalic acid, and ammonia salts; and in diseases where decomposition takes place, leucin and tyrosin.

[**Physical Properties of the Lungs.**—The lungs, in virtue of the large amount of elastic tissue which they contain, are endowed with **elasticity**; and when the chest is opened they collapse. If a cannula with a small lateral opening be tied into the trachea of a rabbit's or sheep's lungs, the lungs may be inflated with a pair of bellows, or elastic pump. After the artificial inflation, the lungs, owing to their elasticity, collapse and expel the greater part of the air. As much air remains within the light spongy tissue of the lungs, even after they are removed from the body, a healthy lung floats in water. If the air cells are filled with pathological fluids or blood, as in certain diseased conditions of the lung (pneumonia), then the lungs or parts thereof may sink in water. The lungs of the fœtus, before respiration has taken place, sink in water, but after respiration has been thoroughly established in the child, the lungs float. Hence, this **hydrostatic test** is largely used in medico-legal cases, as a test of the child's having breathed. If a healthy lung be squeezed between the fingers, it emits a peculiar and characteristic fine crackling sound, owing to the air within the air cells. A similar sound is heard on cutting the vesicular tissue of the lung. The **color** of the lungs varies much; in a young child it is rose-pink, but afterward it becomes darker, especially in persons living in towns or a smoky atmosphere, owing to the deposition of granules of carbon. In coal miners the lungs may become quite black.]

[**Excision of the Lung.**—Dogs recover after the excision of one entire lung, and they even survive the removal of portions of lung infected with tubercle (*Biondi*).]

107. **MECHANISM OF RESPIRATION.**—The mechanism of respiration consists in an alternate dilatation and contraction of the chest. The dilatation is called **inspiration**, the contraction **expiration**. As the whole external surfaces of both elastic lungs are applied directly, and in an air-tight manner, by their smooth, moist, pleural investment, to the inner wall of the chest, which is covered by the parietal pleura, it is clear that the lungs must be distended with every dilatation of the chest, and diminished by every contraction thereof. The **movements of the lungs**, therefore, are entirely **passive**, and are dependent on the thoracic movements.

On account of their complete elasticity and their great extensibility, the lungs are able to accommodate themselves to any variation in the size of the thoracic cavity, without the two layers of the pleura becoming separated from each other. As the capacity of the non-distended chest is greater than the volume of the collapsed lungs after their removal from the body, it is clear that the lungs, even in their natural position within the chest, are distended, *i. e.*, they are in a certain state of **elastic tension** (§ 60). The tension is greater the more distended the thoracic cavity, and *vice versâ*. As soon as the pleural cavity is opened by perforation from without, the lungs, in virtue of their elasticity, collapse, and a space

filled with air is formed between the surface of the lungs and the inner surface of the thoracic wall (**pneumothorax**), The lungs so affected are rendered useless for respiration; hence a double pneumothorax causes death.

Pneumothorax.—It is also clear that, if the pulmonary pleura be perforated from within the lung, air will pass from the respiratory passages into the pleural sac, and also give rise to pneumothorax. [Not unfrequently the surgeon is called on to open the chest, say by removing a portion of a rib, to allow of the free exit of pus from the pleural cavity. If this be done with proper precautions, and if the external wound be allowed to heal, after a time the air in the pleural cavity becomes absorbed, the collapsed lung tends to reign its original form, and again becomes functionally active.]

Estimation of Elastic Tension.—If a manometer be introduced through an intercostal space into the pleural cavity, in a dead subject, we can measure, by means of a column of mercury, the amount of the elastic tension required to keep the lung in its position. This is equal to 6 mm. in the dead subject, as well as in the condition of expiration. If, however, the thorax be brought into the position of inspiration by the application of traction from without, the elastic tension may be increased to 30 mm. Hg (*Donders*).

If the glottis be closed and a deep inspiration taken, the air within the lungs must become rarefied, because it has to fill a greater space. If the glottis be suddenly opened, the atmospheric air passes into the lungs until the air within the lungs has the same density as the atmosphere. Conversely, if the glottis be closed, and if an expiratory effort be made, the air within the chest must be compressed. If the glottis be suddenly opened, air passes out of the lungs until the pressure outside and inside the lung is equal. As the glottis remains open during ordinary respiration, the equilibration of the pressure within and without the lungs will take place gradually. During tranquil inspiration there is a slight negative pressure; during expiration, a slight positive pressure in the lungs; the former = 1 mm., the latter 2–3 mm. Hg in the human trachea (measured in cases of wounds of the trachea).

108. QUANTITY OF GASES RESPIRED.—As the lungs within the chest never give out all the air they contain, it follows that only a part of the air of the lungs is changed during inspiration and expiration. The volume of this air will depend upon the depth of the respirations.



Hutchinson defined the following:—

(1) **Residual air** is the volume of air which remains in the chest *after the most complete expiration*. It is = 1230–1640 c. c. [100–130 cubic inches].

(2) **Reserve or supplemental air** is the volume of air which can be expelled from the chest *after* a normal quiet expiration. It is = 1240–1800 c. c. [100 cubic inches].

(3) **Tidal air** is the volume of air which is taken in and given out at each respiration. It is = 500 cubic centimetres [20 cubic inches].

(4) **Complemental air** is the volume of air that can be forcibly inspired over and above what is taken in at a normal respiration. It amounts to about 1500 c. c. [100–130 cubic inches].

(5) **Vital Capacity** is the term applied to the volume of air which can be forcibly expelled from the chest after the deepest possible inspiration. It is equal to 3772 c. c. (or 230 cubic inches) for an Englishman (*Hutchinson*), and 3222 for a German (*Haeser*).

Hence, after every quiet inspiration, both lungs contain (1 + 2 + 3) = 3000 to 3900 c. cm. [220 cubic inches]; after a quiet expiration (1 + 2) = 2500 to 3400 c. cm. [200 cubic inches]. So that about $\frac{1}{6}$ to $\frac{1}{7}$ of the air in the lungs is subject to renewal at each ordinary respiration.

Donders calculated that the entire bronchial system and the trachea contain about 500 c. c. of air.

Estimation of Vital Capacity.—This was formerly thought to be of great utility, but at the present time not much importance is attached to it, nor is it frequently measured in cases of disease. It is estimated by means of the **spirometer** of Hutchinson (Fig. 134), which consists of a graduated cylinder filled with water and inverted like a gasometer over water, and balanced by means of a counterpoise. Into the cylinder a tube projects, and this tube is connected with a mouth-piece. The person to be experimented upon takes the deepest possible inspiration, closes his nostrils, and breathes forcibly into the mouth-piece of the tube. After doing so the tube is closed. The cylinder is raised by the air forced into it, and after the water inside and outside the cylinder is equalized, the height to which the cylinder is raised indicates the amount *of air expired*, or the vital or respiratory capacity. In a man of average height, 5 feet 8 inches, it is equal to 230 cubic inches.

FIG. 134.



Scheme of Hutchinson's Spirometer.

The following circumstances affect the vital capacity:—

(1) The **Height.**—Every inch added to the height of persons between 5 and 6 feet gives an increase of the vital capacity = 130 c. c. [8 cubic inches].

(2) The **Body weight.**—When the body weight exceeds the normal by 7 per cent. there is a diminution of 37 c. c. of the vital capacity for every kilo. of increase.

(3) **Age.**—The vital capacity is at its maximum at 35; there is an annual decrease of 23.4 c. c., from this age onward to 65, and backward to 15 years of age.

(4) **Sex.**—It is less in women than men, and even where there is the same circumference of chest, and the same height in a man and a woman, the ratio is 10 : 7.

(5) **Position** and **Occupation.**—More air is respired in the erect than in the recumbent position.

(6) **Disease.**—Abdominal and thoracic diseases diminish it.

109. **NUMBER OF RESPIRATIONS.**—In the **adult,** the number of respirations varies from 16 to 24 per minute, so that about 4 pulse beats occur during each respiration. The number of respirations is influenced by many conditions:—

(1) The **Position of the Body.**—In the adult, in the horizontal position, Guy counted 13, while sitting 19, while standing 22, respirations per minute.

(2) **Age.**—Quetelet found the mean number of respirations in 300 individuals to be:—

Year.	Respirations.		Year.	Respirations.	
0 to 1,	44	Average	20 to 25,	18.7	Average
5,	26	Number per	25 to 30,	16	Number per
15 to 20,	20	Minute.	30 to 50,	18.1	Minute.

(3) The **State of Activity.**—Gorham counted in children of 2 to 4 years of age during standing 32, in sleep 24, respirations per minute. During bodily exertion the number of respirations increases before the heart beats. [Very slight *muscular* exertion suffices to increase the frequency of the respirations.]

[(4) The **Temperature** of the surrounding medium.—The respirations become more numerous the higher the surrounding temperature, but this result only occurs when the actual temperature of the blood is increased, as in fever.

(5) **Digestion.**—There is a slight variation during the course of the day, the increase being most marked after mid-day dinner (*Vierordt*).

(6) The **Will** can to a certain extent modify the number and also the depth of the respirations, but after a short time the impulse to respire overcomes the voluntary impulse.

(7) The **Gases of the Blood** have a marked effect, and so has the heat of the blood in fever.]

[(8) In **Animals**—

Mammals.

	Per Min.
Tiger,	6
Lion,	10
Jaguar,	11
Panther,	18
Cat,	24
Dog,	15
Dromedary,	11
Giraffe,	8–10
Ox,	15–18
Squirrel,	70
Rabbit,	55
Rat (waking),	210
Rat (asleep),	100
Rhinoceros,	6–10
Hippopotamus,	1
Horse,	10–12
Ass,	7

Birds.

	Per Min.
Condor,	6
Sparrow,	90
Pigeon,	30
Siskin,	100
Canary,	18

Reptiles.

	Per Min.
Snake,	5
Tortoise,	12

Fish.

	Per Min.
Raja,	50
Torpedo,	51
Perch,	30
Mullet,	60
Eel,	50
Hippocampus,	33

Invertebrata.

	Per Min.
Crab,	12
Mollusca,	14–65

(*P. Bert.*)]

[(9) **In Disease.**—The number may be greatly **increased** from many causes, *e. g.*, in fever, pleurisy and pneumonia, some heart diseases, or in certain cases of alteration of the blood, as in anæmia; and **diminished** where there is pressure on the respiratory centre in the medulla, in coma. It is important to note the **ratio** of pulse beats to respirations.]

FIG. 135.



A, Brondgeest's tambour for registering the respiratory movements. *b*, *c*, inner and outer caoutchouc membranes; *a*, the capsule; *d*, *d*, cords for fastening the instrument to the chest; *S*, tube to the recording tambour. B, normal respiratory curve obtained on a vibrating plate (each vibration = 0.01613 sec.).

110. TIME OCCUPIED BY THE RESPIRATORY MOVEMENTS.—The time occupied in the various phases of a respiration can only be accurately ascertained by obtaining a curve or **pneumatogram** of the respiratory movements by means of recording apparatus.

Methods.—The graphic method can be employed in three directions: (1) *To record the movements of individual parts of the chest wall.*

(1) Vierordt and C. Ludwig transferred the movements of a part of the chest wall to a lever which inscribed its movements upon a revolving cylinder. Reigel (1873) constructed a "**double stethograph**" on the same principle. This instrument is so arranged that one arm of the lever may be applied in connection with the healthy side of a person's chest, and the other on the diseased side. In the case of animals placed on their backs, Snellon introduced a long needle vertically through the abdominal walls into the liver. Rosenthal opened the abdomen and applied a lever to the under surface of the diaphragm, and thus registered its movements (**Phrenograph**).

(2) An air tambour, such as is used in Brondgeest's pansphygmograph (Fig. 135, A) may be employed. It consists of a brass vessel, *a*, shaped like a small saucer. The mouth of the brass

vessel is covered with a double layer of caoutchouc membrane, *b*, *c*, and air is forced in between the two layers until the external membrane bulges outward. This is placed on the chest, and the apparatus is fixed in position by means of the bands, *d*, *d*. The cavity of the tambour communicates by means of a caoutchouc tube, *s*, with a recording tambour, which inscribes its movements upon a revolving cylinder. Every dilatation of the chest compresses the membrane, and thus the air within the tambour is also compressed. [A somewhat similar apparatus is used by Burdon-Sanderson, and called a **"recording stethograph."** By it movements of the corresponding points on opposite sides of the chest can be investigated.] A cannula or œsophageal sound may be introduced into that portion of the œsophagus which lies in the chest, and a connection established with Marey's tambour (*Rosenthal*). [This method also enables one to measure the *intra-thoracic pressure*.]

Marey's Stethograph or Pneumograph.—[There are two forms of this instrument, one modified by P. Bert and the more modern form (Fig. 136). A tambour (*h*) is fixed at right angles to a thin elastic plate of steel (*f*). The aluminium disk on the caoutchouc of the tambour is attached to an upright (*b*), whose end lies in contact with a horizontal screw (*g*). Two arms (*d*, *c*) are attached to opposite sides of the steel plate, and to them the belt (*e*) which fastens the instrument to the chest is attached. When the chest expands, these two arms are pulled asunder, the steel plate is bent, and the tambour is affected, and any movement of the tambour is transmitted to a registering tambour by the air in the tube (*a*)].

(2) *To record variation in volume of the thorax or of the respired gases.*

For this purpose E. Hering secures the animal, and places it in a tight box provided with two openings in its side; one hole contains a tube, which is connected to a cannula tied into the transversely divided trachea of the animal, so that respiration can go on undisturbed. In the other orifice is fixed a water manometer provided with a swimmer arranged to write on a recording surface. Gad registered graphically the respired air by means of a special apparatus; the expired air raised a very light and carefully equipoised box placed over water. As it was raised, it moved a writing style. During inspiration the box sank.

FIG. 136.



Marey's Stethograph.

(3) *To record the rate at which the respiratory gases are exchanged.*

If the trachea of an animal, or the mouth of a man (the nostrils being closed), be connected with a tube like that of the dromograph (Fig. 113), then during inspiration and expiration the pendulum will be moved to and fro by the air, and the movements of the pendulum can be registered. [Some years ago, an instrument, called the "Anapnograph," was constructed on this principle.]

The curve (Fig. 135, B) was obtained by placing the tambour of a Brondgeest's pansphygmograph upon the xiphoid process, and recording the movement upon a plate attached to a vibrating tuning fork. The *inspiration* (ascending limb) begins with moderate rapidity, is accelerated in the middle, and toward the end again becomes slower. The *expiration* also begins with moderate rapidity, is then accelerated, and becomes much slower at the latter part, so that the curve falls very gradually.

Inspiration is slightly shorter than Expiration.—According to Sibson, the ratio for an adult is as 6 to 7; in women, children, and old people, 6 to 8 or 6 to 9. Vierordt found the ratio to be 10 to 14.1 (to 24.1); J. R. Ewald, 11 to 12. It is only occasionally that cases occur where inspiration and expiration are equally long, or where expiration is shorter than inspiration. When respiration proceeds quietly and regularly, there is usually *no pause* (complete rest of the chest walls) *between the inspiration and expiration*. The very flat part of the

expiratory curve has been wrongly regarded as due to a pause. Of course, we may make a voluntary pause between two respirations, or at any part of a respiratory act.

Some observers, however, have described a pause as occurring between the end of expiration and the beginning of the next inspiration (expiration pause), and also another pause at the end of inspiration (inspiration pause). The latter is always of very short duration, and considerably shorter than the former. During very deep and slow respiration, there is usually an expiration pause, while it is almost invariably absent during rapid breathing. An inspiration pause is always absent under normal circumstances, but it may occur under pathological conditions.

In certain parts of the respiratory curve slight irregularities may appear, which are sometimes due to vibrations communicated to the thoracic walls by vigorous heart beats (Fig. 137).

The "**type**" of respiration may be ascertained by taking curves from various parts during the respiratory movements. Hutchinson showed that, in the female,

FIG. 137.



Pneumatograms obtained by means of Riegel's stethograph. I, normal curves; II, curve from a case of emphysema; *a*, ascending limb; *b*, apex; *c*, descending limb of the curve. The small elevations are due to the cardiac impulse.

the thorax is dilated chiefly by raising the sternum and the ribs (Respiratio costalis), while in man it is caused chiefly by a descent of the diaphragm (Respiratio diaphragmatica or abdominalis). In the former, there is the so-called "**costal type,**" in the latter the "**abdominal** or **diaphragmatic type.**"

This difference in the type of respiration in the sexes occurs only during normal quiet respiration. During deep and **forced respiration,** in both sexes the dilatation of the chest is caused chiefly by raising the chest and the ribs. In man, the epigastrium may be pulled in sooner than it is protruded. During **sleep,** the type of respiration in both sexes is thoracic, while at the same time the inspiratory dilatation of the chest precedes the elevation of the abdominal wall (*Mosso*). It is not determined whether the costal type of respiration in the female depends upon the constriction of the chest by corsets or other causes (*Sibson*), or whether it is a natural adaptation to the child-bearing function in women (*Hutchinson*). Some observers maintain that the difference of type is quite distinct, even in sleep, when all constrictions are removed, and that similar differences are noticeable in young children. This is denied by others, while a third class of observers hold that

the costal type occurs in children of both sexes, and they ascribe as a cause the greater flexibility of the ribs of children and women, which permits the muscles of the chest to act more efficiently upon the ribs.

III. **PATHOLOGICAL.—Examination of the Lungs.**—The same **methods** that are applicable to the heart, viz., I, Inspection; II, Palpation; III, Percussion; and IV, Auscultation, apply here also.]

[By **inspection** we may determine the presence of symmetrical or unilateral alterations in the shape of the chest, the presence of bulging or flattening at one part, and variations in the movement of the chest walls. By **palpation**, the presence or absence, character, seat, and extent of any movements are more carefully examined. But we may also study what is called **vocal fremitus** (§ 117). **Percussion** (§ 114), **Auscultation** (§ 116).]

[In investigating the respiratory movements, we should observe (1), the **frequency** (§ 109); (2), the **type** (§ 110); (3), the **nature**, character, and extent of the movements, noting also whether they are accompanied by **pain** or not (§ 110); (4), the **rhythm**.]

I. **Changes in the Mode of Movement.**—In persons suffering from disease of the respiratory organs, the dilatation of the chest may be diminished (to the extent of 5 or 6 cm.) on *both* sides or only on *one* side. In affections of the apex of the lung (in phthisis), the sub-normal expansion of the upper part of the wall of the chest may be considerable. *Retraction* of the soft parts of the thoracic wall, the xiphoid process, and the parts where the lower ribs are inserted, occurs in cases where air cannot freely enter the chest during inspiration, *e.g.*, in narrowing of the larynx; when this retraction is confined to the upper part of the thoracic wall, it indicates that the portion of the lung lying under the part so affected is less extensile and diseased.

Harrison's Groove.—In persons suffering from chronic difficulty of breathing, and in whom, at the same time, the diaphragm acts energetically, there is a slight groove, which passes horizontally outward from the xiphoid cartilage, caused by the pulling in of the soft parts and corresponding to the insertion of the diaphragm.

The **duration of inspiration** is lengthened in persons suffering from narrowing of the trachea or larynx; **expiration** is lengthened in cases of dilatation of the lung, as in emphysema, where all the expiratory muscles must be brought into action (Fig. 137, II).

II. **Variations in the Rhythm.**—When the respiratory apparatus is much affected, there is either an increase or a deepening of the respirations, or both. When there is great difficulty of breathing, this is called **dyspnœa**.

Causes of Dyspnœa.—(1) Limitation of the exchange of the respiratory gases in the blood due to (*a*) diminution of the respiratory surface (as in some diseases of the lungs); (*b*) narrowing of the respiratory passages; (*c*) diminution of the red blood corpuscles; (*d*) disturbances of the respiratory mechanism (*e.g.*, due to affections of the respiratory muscles or nerves, or painful affections of the chest wall); (*e*) impeded circulation through the lungs due to various forms of heart disease. (2) **Heat dyspnœa.**—The frequency of the respirations is increased in *febrile conditions*. The warm blood acts as a direct irritant of the respiratory centre in the medulla oblongata, and raises the number of respirations to 30–60 per minute ("Heat dyspnœa"). If the carotids be placed in warm tubes, so as to heat the blood going to the medulla oblongata, the same phenomena are produced (§ 368). [When a child sucks, it breathes exclusively through the nose, hence catarrhal conditions of the nasal mucous membrane are fraught with danger to the child.]

[**Orthopnœa.**—Sometimes the difficulty of breathing is so great that the person can only respire in the erect position, *i.e.*, when he sits or is propped up in bed. This occurs frequently toward the close of some heart affections, notably in mitral lesions; dropsical conditions, especially of the cavities, may be present.]

Cheyne-Stokes' Phenomenon.—This remarkable phenomenon occurs in certain diseases, where the normal supply of blood to the brain is altered, or where the quality of the blood itself is altered, *e.g.*, in certain affections of the brain and heart, and in uræmic poisoning. Respiratory pauses of one-half to three-quarters of a minute alternate with a short period (½–¾ min.) of increased respiratory activity, and during this time 20–30 respirations occur. The respirations constituting this "series" are shallow at first; gradually they become deeper and more dyspnœic, and finally become shallow or superficial again. Then follows the pause, and thus there is an alternation of pauses and series (or groups) of modified respirations. During the pause, the pupils are contracted and inactive; and when the respirations begin, they dilate and become sensible to light; the eyeball is moved as a whole at the same time. Hein observed that consciousness was abolished during the pause, and that it returned when respiration commmenced.

Causes.—Luciani and Rosenbach regard variations in the excitability of the respiratory centre as the cause of the phenomenon, which they compare with the periodic contraction of the heart (§ 58). The excitability of the respiratory centre is lowest during the pause. They observed this phenomenon after injury to the medulla oblongata above the respiratory centre, and after apnœa produced in animals deeply narcotized with opium, and in the last stages of asphyxia, during respiration in a closed space. During **hibernation**, this mode of respiration is normal in Myoxus, the hedgehog, and the caiman.

Periodic Respiration.—If frogs be kept under water, or if the aorta be clamped, after several hours, they become passive. If they be taken out of the water, or if the clamp be removed from the aorta, they gradually recover and always exhibit the Cheyne Stokes' phenomenon. In such frogs the blood current may be arrested temporarily, while the phenomenon itself remains (*Sokolow and Luchsinger*). If the blood current be arrested by ligature of the aorta, or if the frogs be bled, the respirations occur in groups. This is followed by a few single respirations, and then the respiration ceases completely. During the pause between the periods, mechanical stimulation of the skin causes the discharge of a group of respirations (*Siebert and Langendorff*).

Action of Drugs.—Muscarin, digitalin, curara, chloral, sulphuretted hydrogen, and the poison of many infectious diseases (typhus, diphtheria, scarlet fever) may also cause periodic respiration in frogs [which is not due to the action of these drugs on the heart].

Periodic respiration without any variation in the size of the individual respirations—the so-called "**Biot's respiration**"—occurs normally during sleep. While the nervous system as it were strives to rest, and thus forgets the respiration, the organism does not observe the short pauses (*Mosso*). [There is a periodic increase or decrease in the depth of the respiration, especially in old people and children, even to the extent of respiration becoming "remittent," or even "intermittent," for a period of 30 sec. during sleep. During periodic respiration the action of the several respiratory muscles does not coincide. As a rule, one respires more than is required by the organism. Mosso calls this "**luxus respiration.**"] Periodic irregularities in the respiration are often of reflex origin (*Knoll*).

112. GENERAL VIEW OF THE RESPIRATORY MUSCLES.

(A) Inspiration.

I. During Ordinary Inspiration.

1. The diaphragm (*Nervus phrenicus*).
2. The Mm. levatores costarum longi et breves (*Rami posteriores Nn. dorsalium*).
3. The Mm. intercostales externi et intercartilaginei (*Nn. intercostales*).

II. During Forced Respiration.

(*a*) *Muscles of the Trunk.*

1. The three Mm. scaleni (*Rami musculares of the plexus cervicalis et brachialis*).
2. M. sternocleidomastoideus (*Ram. externus N. accessorii*).
3. M. trapezius (*R. externus N. accessorii et Ram. musculares plexus cervicalis*).
4. M. pectoralis minor (*Nn. thoracici anteriores*).
5. M. serratus posticus superior (*N. dorsalis scapulæ*).
6. Mm. rhomboidei (*N. dorsalis scapulæ*).
7. Mm. extensores columnæ vertebralis (*Ram. posteriores nervorum dorsalium*).

[8. Mm. serratus anticus major (*N. thoracicus longus*). ??]

(*b*) *Muscles of the Larynx.*

1. M. sternohyoideus (*Ram. descendens hypoglossi*).
2. M. sternothyreoideus (*Ram. descendens hypoglossi*).
3. M. crico-arytaenoideus posticus (*N. laryngeus inferior vagi*).
4. M. thyreo-arytaenoideus *N.* (*laryngeus inferior vagi*).

(*c*) *Muscles of the Face.*

1. M. dilatator narium anterior et posterior (*N. facialis*).
2. M. levator alæ nasi (*N. facialis*).
3. The dilators of the mouth and nares, during forced respiration ["gaspi[illegible] for breath"], (*N. facialis*).

(*d*) *Muscles of the Pharynx.*

1. M. levator veli palatini (*N. facialis*).
2. M. azygos uvulæ (*N. facialis*).
3. According to Garland, the pharynx is always narrowed.

(B) Expiration.

I. During Ordinary Respiration.

The thoracic cavity is diminished by the *weight* of the chest, the *elasticity* of the lungs, costal cartilages, and abdominal muscles.

II. During Forced Expiration.

The Abdominal Muscles.

1. The abdominal muscles [including the obliquus externus and internus, and transversalis abdominis] (*Nn. abdominis internis anteriores e nervis intercostalibus*, 8–12).

2. Mm. intercostales interni, so far as they lie between the osseous parts of the ribs, and the Mm. infracostales (*Nn. intercostales*).

3. M. triangularis sterni (*Nn. intercostales*).

4. M. serratus posticus inferior (*Ram. externi nerv. dorsalium*).

5. M. quadratus lumborum (*Ram. muscular e plexu lumbali*).

113. ACTION OF THE INDIVIDUAL RESPIRATORY MUSCLES.—(A) **Inspiration.**—(1) **The Diaphragm** arises from the cartilages and the adjoining osseous parts of the lower six ribs (costal portion), by two thick processes or crura, from the upper three or four lumbar vertebræ, and a sternal portion from the back of the ensiform process. It represents an *arched double cupola* or dome-shaped partition, directed toward the chest; in the larger concavity on the right side lies the liver, while the smaller arch on the left side is occupied by the spleen and stomach. During the passive condition, these viscera are pressed against the under surface of the diaphragm, by the elasticity of the abdominal walls, and by the intra-abdominal pressure, so that the arch of the diaphragm is pressed upward into the chest. The elastic traction of the lungs also aids in producing this result. The greater part of the upper surface of the central tendon of the diaphragm is united to the pericardium. The part on which the heart rests, and which is perforated by the inferior vena cava (foramen quadrilaterum) is the deepest part of the middle portion of the diaphragm during the passive condition.

Action of the Diaphragm.—When the diaphragm contracts, both arched portions become flatter, and the chest is thereby elongated from above downward. In this act, the lateral muscular parts of the diaphragm pass from an arched condition into a flatter form (Fig. 138), and during a forced inspiration the lowest lateral portions, which during rest are in contact with the chest wall, become separated from it. The middle of the central tendon where the heart rests (fixed by means of the pericardium and inferior vena cava) takes no share in this movement, especially in ordinary quiet breathing, but during the deepest inspiration it sinks somewhat.

Undoubtedly, the diaphragm is the most powerful agent in increasing the cavity of the chest. Brücke believes that in addition to increasing the length of the thoracic cavity from above downward, it also increases the transverse diameter of the lower part of the chest. It presses upon the abdominal viscera from above, and strives to press these outward, thus tending to push out the adjoining thoracic wall. If the contents of the abdomen are removed from a living animal, every time the diaphragm contracts the ribs are drawn inward. This, of course, hinders the chest from becoming wider below, hence the presence of the abdominal viscera seems to be necessary for the normal activity of the diaphragm. Every contraction of the diaphragm, by increasing the intra-abdominal pressure, favors the venous blood current in the abdomen toward the vena cava inferior.

FIG. 138.

Sagittal section through the second rib on the right side. When the arched muscular part of the diaphragm contracts, a wedge-shaped space, with its apex downward, is formed around the circumference of the lower part of the chest.

Phrenic Nerve.—The immense importance of the diaphragm as *the great inspiratory muscle* is proved by the fact that, after both phrenic nerves (third and fourth cervical nerves) are divided, death occurs. The phrenic nerve contains some sensory fibres for the pleura, pericardium, and a portion of the diaphragm. The contraction of the diaphragm is not to be regarded as a "simple muscular contraction," since it lasts 4 to 8 times longer than a simple

contraction; it is rather a short tetanic contraction, which we may arrest in any stage of its activity, without bringing into action any antagonistic muscles (*Kronecker and Marckwald*).

(2) **The Elevators of the Ribs.**—The ribs at their vertebral ends (which lie much higher than their sternal ends) are united by means of joints by their heads and tubercles to the bodies and transverse processes of the vertebræ. A horizontal axis can be drawn through both joints, around which the ribs can rotate upward and downward. If the axis of rotation of each pair of ribs be prolonged on both sides until they meet in the middle line, the angles so formed are greatest above (125°), and smallest below (88°). Owing to the ribs being curved, we can imagine a plane which, in the passive (expiratory) condition of the chest, has a slope from behind and inward to the front and outward. If the ribs move on their axis of rotation, this plane becomes more horizontal, and the thoracic cavity is increased in its transverse diameter. As the axis of rotation of the upper ribs runs in a more frontal, and that of the lower ribs in a more sagittal direction, the elevation of the upper ribs causes a greater increase from before backward, and the lower ribs from within outward (as the movements of ribs which are directed downward are vertical to the axis). The costal cartilages undergo a slight tension at the same time, which brings their elasticity into play.

Changes in the Chest.—*All "inspiratory muscles" which act directly upon the chest wall do so by raising the ribs:* (*a*) When the ribs are raised, the intercostal spaces are widened. (*b*) When the upper ribs are raised, all the lower ribs and the sternum must be elevated at the same time, because all the ribs are connected with each other by means of the soft parts of the intercostal spaces. (*c*) During inspiration, there is an elevation of the ribs and a dilatation of the intercostal spaces. (The lowest rib is an exception; during forced respiration, at least, it is drawn downward.) (*d*) If, on a preparation of the chest, the ribs be raised as in inspiration, we may regard all those muscles as elevators of the ribs, whose origin and insertion become approximated. Every one is agreed that the *scaleni* and *levatores costarum longi et breves*, the *serratus posticus superior*, are inspiratory muscles. These are the most important inspiratory muscles which act upon the ribs.

FIG. 139.



Scheme of the action of the intercostal muscles.

Intercostal Muscles.—With regard to the action of the intercostal muscles, there is a great difference of opinion. According to the above experiment, the external intercostals and the intercartilaginous parts of the internal intercostals act as inspiratory muscles, while the remaining portions of the internal intercostals (as far as they are covered by the external) are elongated when the ribs are raised, while they shorten when the chest wall descends. A muscle shortens only during its activity. The internal intercostals were regarded by Hamberger as depressors of the ribs or expiratory muscles.

In Fig. 139, I, when the rods, *a* and *b* (which represent the ribs), are raised, the intercostal space must be widened ($e\,f > c\,d$). On the opposite side of the figure, it is evident that when the rods are raised, the line, $g\,h$, is shortened ($i\,k < g\,h$, direction of the external intercostals), $l\,m$ is lengthened ($l\,m < o\,n$, direction of internal intercostals.) Fig. 139, II, shows, that when the ribs are raised, the intercartilaginei, indicated by $g\,h$, and the external intercostals indicated by $l\,k$, are shortened. When the ribs are raised, the position of the muscular fibres is indicated by the diagonal of the rhomb becoming shorter.

The mode of action of the intercostal muscles is an old story, Galen (131–203 A. D.) regarding

the externals as inspiratory, the internals as expiratory. Hamberger (1727) accepted this proposition, and considered the intercartilaginei also as inspiratory. Haller looked upon both the external and internal intercostals as inspiratory, while Vesalius (1540) regarded both as expiratory. Landerer, observing that the upper two or three intercostal spaces became narrower during inspiration, regarded both as active during inspiration and expiration. They keep one rib attached to the other, so that their action is to transmit any strain put upon them to the wall of the chest. On this view they will be in action, even when the distance between their points of attachment becomes greater. Landois regards the external intercostals and intercartilaginei as active *only* during inspiration, the internal intercostals *only* during expiration. [Martin and Hartwell exposed the internal intercostals, and observed whether they contracted along with the diaphragm, or whether the contractions of these two muscles alternate. As the result of their experiments, they conclude that "the internal intercostal muscles are expiratory throughout their whole extent, at least in the dog and cat; and that in the former animal they are almost "ordinary" muscles of respiration, while in the latter they are 'extraordinary' respiratory muscles."] Landois is of opinion that the *chief* action of these muscles is not to raise or depress the ribs, but rather that the external intercostals and the intercartilaginei offer resistance to the inspiratory dilatation of the intercostal spaces, and to the simultaneously increased elastic tension of the lungs. The internal intercostals act during powerful expiratory efforts (*e. g.*, coughing), and oppose the distention of the lungs and chest caused by this act. Unless muscles were present to resist the uninterrupted tension and pressure, the intercostal substance would become so distended that respiration would be impossible. [According to Rutherford, the internal intercostals are probably muscles of inspiration.]

The **Pectoralis minor and (? Serratus anticus major)** can only act as elevators of the ribs when the shoulders are fixed, partly by the rhomboidei, and partly by fixing the shoulder joint and supporting the arms, as is done instinctively by persons suffering from breathlessness.

(3) **Muscles acting on the Sternum, Clavicle, and Vertebral Column.**—When the head is fixed by the muscles of the neck, the sternocleidomastoid raises the manubrium sterni and the sternal end of the clavicle, so that the thorax is raised and thereby dilated. The scaleni also aid in this act. The clavicular portion of the trapezius may act in a similar although less energetic manner. When the *vertebral column is straightened*, it causes an elevation of the upper ribs, and a dilatation of the intercostal spaces which aid inspiration. During deep respiration, the straightening of the vertebral column takes place involuntarily.

(4) **Laryngeal Movements.**—During labored respiration, with every inspiration, the *larynx descends* and the glottis is opened. At the same time the palate is raised, so as to permit a free passage to the air entering through the mouth.

(5) **Facial Movements.**—During labored respiration, the facial muscles are involved; there is an inspiratory dilatation of the nostrils (well marked in the horse and rabbit). When the need for respiration is very great, the mouth is gradually widened, and the person, as it were, gasps for breath. During expiration, the muscles that are active during (4) and (5) relax, so that a position of equilibrium is established without there being any active expiratory movement to counteract the inspiratory movement. During inspiration the pharynx becomes narrow (*Garland*).

(B) **Expiration.**—Ordinary expiration occurs without the aid of muscles, owing to the **weight of the chest,** which tends to fall into its normal position from the position to which it was raised during inspiration. This is aided by the **elasticity** of the various parts of the chest. When the costal cartilages are raised, which is accompanied by a slight rotation of their lower margins from below forward and upward, their elasticity is called into play. As soon, therefore, as the inspiratory forces cease, the costal cartilages return to their normal position, *i.e.*, the position of expiration, and tend to untwist themselves; at the same time, the **elasticity of the distended lungs** draws upon the thoracic walls and the diaphragm. Lastly, the **tense and elastic abdominal walls,** which, in man chiefly, are stretched and pushed forward, tend to return to their non-distended passive condition when the **abdominal viscera** are relieved from the pressure of the contracted diaphragm. (When the position of the body is reversed, the action

of the weight of the chest is removed, but in place of it there is the weight of the viscera, which press upon the diaphragm.)

The **abdominal muscles** [obliquus internus and externus, transversalis abdominis and levator ani] are always active during labored respiration. They act by diminishing the abdominal cavity, and they press the abdominal contents upward against the diaphragm. When they act simultaneously, the abdominal cavity is diminished throughout its whole extent. The **triangularis sterni** depresses the sternal ends of the united cartilages and bones, from the third to sixth ribs downward; and the **serratus posticus inferior** depresses the lowest four ribs, causing the other to follow. It is aided by the **quadratus lumborum**, which depresses the last rib. According to Henle, the serratus posticus inferior fixes the lower ribs for the action of the slips of the diaphragm inserted into them, so that it acts during inspiration. According to Landerer, the downward movement of the ribs in the lower part of the thorax dilates the chest.

In the erect position, when the vertebral column is fixed, deep inspiration and expiration naturally alter the position of the **centre of gravity**, so that during inspiration, owing to the protrusion of the thoracic and abdominal walls, the centre of gravity lies somewhat more to the front. Hence, with each respiration there is an involuntary balancing of the body. During very deep inspiration, the accompanying straightening of the vertebral column and the throwing backward of the head compensate for the protrusion of the anterior walls of the trunk.

114. **RELATIVE DIMENSIONS OF THE CHEST.**—The diameter of the chest is ascertained by means of callipers; the circumference with a flexible centimetre or other measure.

In strong men, the **circumference** of the upper part of the chest (immediately under the arms) is 88 centimetres (34.3 inches), in females 82 centimetres (32 inches); at the level of the ensiform process 82 centimetres (32 inches) and 78 centimetres (30.4 inches) respectively. When the arms are placed horizontally, during moderate expiration, the circumference immediately under the nipple and the angles of the scapulæ is equal to half the length of the body; in man 82, and during deep inspiration 89 centimetres. The circumference at the level of the ensiform cartilage is 6 centimetres less. In old people, the circumference of the upper part of the chest is diminished, so that the lower part becomes the wider of the two. The right half of the chest is usually slightly larger than the left half, owing to the greater development of the muscles on that side. The **long diameter** of the chest—from the clavicle to the margin of the lowest rib—varies very much.

The **transverse diameter** in man, above and below, is 25 to 26 centimetres (9.7 to 10.1 inches), in females 23 to 24 centimetres (8.9 to 9.2 inches); above the nipple it is 1 centimetre more. The **antero-posterior** diameter (distance of anterior chest wall from the tip of a spinous process) in the upper part of the chest is = 17 (6.6 inches), in the lower 19 centimetres (7.4 inches). Valentin found that in a man, during the deepest inspiration, the chest on a level with the groove in the heart was increased about $\frac{1}{12}$ to $\frac{1}{7}$; while Sibson estimates the increase at the level of the nipple to be $\frac{1}{10}$.

Thoracometer.—In order to obtain a knowledge of the degree of movement—rising or falling—of the chest wall during respiration, various instruments have been invented. The thoracometer (Fig. 141) measures the elevation in different parts of the sternum. It consists of two metallic bars placed at right angles to each other; one of them, A, is placed on the vertebral column. On B there is placed a movable transverse bar, C, which carries on its free end a toothed rod, Z, directed downward. The lower end of this rod is provided with a pad which rests on the sternum, while its toothed edge drives a small wheel, which moves an index, whose excursions are indicated on a circle with a scale attached to it.

The Cyrtometer of Woillez consists of a brass chain of movable links, to be applied in a definite direction to part of the chest wall, *e. g.*, transversely on a level with the nipple, or vertically upon the mammillary or axillary lines anteriorly. There are freely movable links at two parts, which permit the chain to be easily removed, so that as a whole it still retains its form. The chain is laid upon a sheet of paper, and a line drawn with a pencil around its inner margin gives the form of the thorax (Fig. 140). [A lead wire answers the same purpose.]

Limits of the Lungs.—The extent and boundaries of the lungs are ascertained in the living subject by means of **percussion**, which consists in lightly tapping the chest wall by means of a **hammer** (percussion hammer). A small ivory or bone plate or **pleximeter**, held in the left hand, is laid on the chest, and the hammer is made to strike this plate, whereby a sound is emitted, which sound varies with the condition of the subjacent lung tissue. Whenever the lung substance in contact with the chest wall contains air, a clear resonant tone or sound —such as is obtained by striking a vessel containing air, a clear percussion sound —is obtained. Where the lung does not contain air, a dull sound—like striking a limb—is obtained. If the parts containing air be very thin, or only partially filled with air, the sound is "muffled."

Fig. 142 indicates the relation of the lungs to the anterior surface of the chest. The *apices of the lungs reach* 3 to 7 centimetres (1.1 to 2.7 inches) above the clavicles anteriorly, while posteriorly they extend from the spines of the scapulæ as high as the seventh spinous process. The *lower margin* of the *right lung* in the passive position (moderate expiration) of the chest, commences at the *right* margin

FIG. 140.



Cyrtometer curve. Left side of the chest retracted in a girl aged twelve.

FIG. 141.



Sibson's Thoracometer.

of the sternum at the insertion of the sixth rib, runs under the right nipple, nearly parallel to the upper border of the sixth rib, and descends a little in the axillary line, to the upper margin of the seventh rib. On the *left* side (apart from the position of the heart), the lower limit reaches as far down anteriorly as the right. In Fig. 142 the line *a*, *t*, *b* shows the lowest limit of the passive lungs. *Posteriorly* both lungs reach as far down as the tenth rib. During the *deepest inspiration*, the lungs descend anteriorly as far as between the sixth and seventh ribs, and posteriorly to the eleventh rib—whereby the diaphragm is separated from the thoracic wall (Fig. 143). During the *deepest expiration*, the lower margins of the lungs are elevated almost as much as they descend during inspiration. In Fig. 142, *m*, *n* indicates the margin of the right lung during deep inspiration; *h*, *l*, during deep expiration. [The part of the chest wall covered by the costal pleura is considerably larger than the circumference of the lung. This is specially marked at the lower margin of the lung, and where the left lung is incised over the heart. In these regions, during expiration, the surfaces of the visceral and parietal pleuræ are in contact, but during inspiration they are separated, and allow the thin margins of the lung to be insinuated between them. This available space is called

complemental space (*Gerhardt*), or "disposable" or **reserve pleural space** by Luschka (*Eichhorst*).]

It is important to observe the relation of the margin of the left lung to the heart. In Fig. 142 a somewhat triangular space, reaching from the middle of the point of insertion of the fourth rib to the sixth rib on the left side of the sternum, is indicated. In the passive chest, the heart lies in contact with the thoracic wall in this triangular area (§ 56). This area is represented by the triangle *t*, *t'*, *t''*, and percussion over it gives a dull sound (**superficial dullness**).

In the area of the larger triangle, *d*, *d'*, *d''*, where the heart is separated from the chest wall by the thin anterior margins of the lung, percussion gives a muffled sound, while further outward a clear lung percussion sound is obtained. During deep inspiration, the inner margin of the left lung reaches over the heart as far as

FIG. 142.



Topography of the lungs and heart. *h*, *l*, upward limit of margin of lung during deepest expiration; *m*, *n*, lower limit during deepest inspiration; *t*, *t'*, *t''*, triangular area where the heart is uncovered by lung, dull percussion sound; *d*, *d'*, *d''*, muffled percussion sound; *i*, *i'*, anterior margin of left lung reaches this line during deep inspiration, and during deep expiration it recedes as far as *e*, *e'*.

the insertion of the mediastinum, whereby the dull sound is limited to the smallest triangle, *t*, *i*, *i'*. Conversely, during very complete expiration, the margin of the lung recedes so far that the cardiac dullness embraces the space, *t*, *e*, *e'*.

115. PATHOLOGICAL PERCUSSION SOUNDS.—Abnormal Dullness.—The normal clear resonant percussion sound of the lungs becomes muffled when infiltration takes place into the lungs, so as to diminish the normal amount of air within them, or when the lungs are compressed from without, *e.g.*, by effusion of fluid into the pleura. The percussion sound becomes clearer when the chest wall is very thin, as in spare individuals, during very deep inspiration, and especially in emphysema, where the air vesicles of certain parts of the lung (apices and margins) become greatly dilated.

The pitch of the percussion sound ought also to be noted. It depends upon the greater or less tension of the elastic pulmonary tissue, and on the elasticity of the thoracic wall. The tension of the elastic tissue is increased during inspiration and diminished during expiration, so that even under physiological conditions, the pitch of the sound varies.

The sound is said to be **tympanitic** when it has a musical quality resembling in its timbre the sound produced on drums, and when it has a slight variation in pitch. If a caoutchouc ball be placed near the ear, on tapping it gently, a well-marked tympanitic sound is heard, and the sound is of higher pitch the smaller the diameter of the ball. A tympanitic sound is always produced on tapping the trachea in the neck. *A tympanitic sound produced over the chest is always indicative of a diseased condition.* It occurs in cases of cavities or vomicæ within the substance of the lung (the sound becomes deeper when the mouth, or better, the mouth and nose, are closed), when air is present in one pleural cavity, as well as in conditions where the tension of the pulmonary tissues is diminished. The tympanitic sound resembles the *metallic tinkling* which is heard in large pathological cavities in the lungs, or which occurs when the pleural cavity contains air, and when the conditions which permit a more uniform reflection of the sound waves within the cavity are present.

[When a cavity, freely communicating with a large bronchus, exists in the upper and anterior part of the lung, a peculiar "**cracked-pot sound**" is heard on percussing over the part. Some notion of this sound may be obtained by clasping the two hands so as to bring the palms nearly together, leaving an air space between, and then striking them on the knee. When percussion is made over a large cavity communicating with a bronchus, some of the air is expelled, and the sound thereby emitted is blended with the fundamental note of the air in the cavity itself, the combination of these two sounds thus producing the "cracked-pot" sound.]

Resistance.—When percussing a chest, we may determine whether the substance lying under the portion of the chest under examination presents great or small resistance to the blow, either of the percussion hammer or of the tips of the fingers, as the case may be [*e.g.*, in great pleuritic effusion exerting much pressure on, and so distending, the thoracic walls].

Phonometry.—If the stem of a vibrating tuning fork be placed on the chest wall, over a part containing air, its sound is intensified; but if it be placed over a portion of the lung which contains little or no air, its sound is enfeebled (*Von Baas*).

116. THE NORMAL RESPIRATORY SOUNDS.—If the ear directly, or through the medium of a **stethoscope**, be placed in connection with the chest wall, we hear over the entire area, where the lung is in contact with the chest, the so-called "**normal vesicular sound,**" which is audible *during inspiration*, and its typical characters may be studied by listening in the infra-scapular region in an adult. It is a fine sighing or breezy sound [which gradually increases in intensity until it reaches a maximum, and falls away before expiration begins]. It is said to be caused by the sudden dilatation of the air vesicles (hence "vesicular") during inspiration, and it is also ascribed to the friction of the current of air entering the alveoli. The sound has, at one time, a soft, at another, a sharper character; the latter occurs constantly in children up to 12 years of age. In their case the sound is sharper, because the air, in entering vesicles one-third narrower, is subjected to greater friction. This is followed by an *expiratory* sound, which may be absent during quiet breathing. It is a feeble sighing sound, of an indistinct, soft character, caused by the air passing out of the air vesicles, is three or four times shorter than the inspiratory, is loudest at first, and soon disappears, the latter part of the expiratory act giving rise to no audible sound. Its absence is not a sign of disease, but when it is prolonged and loud, suspicion is aroused.]

Bronchial Respiration.—Within the larger air passages—larynx, trachea, bronchi—during inspiration and expiration, there are loud, rough, harsh sounds like a sharp h or ch—the "*bronchial*"—the laryngeal, tracheal, or "tubular" sound, or breathing. [In normal bronchial breathing, as heard over the trachea, there is a pause between the inspiratory and expiratory sounds, which are of nearly equal duration and of about the same intensity throughout. These sounds are also heard between the scapulæ, at the level of the fourth dorsal vertebra (bifurcation of trachea), and they occur also during expiration, being slightly louder on the right side, owing to the slightly greater calibre of the right bronchus. At all other parts of the chest, the vesicular sound obscures the tubular or bronchial sound. If the air vesicles are deprived of their air, the tubular breathing becomes distinct.

Bronchial respiration is produced chiefly in the larynx, owing to the formation of air eddies in consequence of the narrowing of the respiratory part of the glottis. This "laryngeal stenosis sound" excites resonance of the tracheo-bronchial column

of air, and communicates to it the specific character of bronchial breathing which is heard over the large tubes of the bronchial system (*Dehio*).

It is asserted that, when lungs containing air are placed over the trachea, the tubular sound there produced becomes vesicular. In this case, we must suppose that the vesicular sound arises from the tubular breathing becoming weakened, and acoustically altered by being conducted through the lung alveoli. A sighing sound is often produced at the apertures of the nose and mouth during forced inspiration.

117. **PATHOLOGICAL RESPIRATORY SOUNDS.**—[The breath sounds heard in disease may be merely modifications of the normal vesicular or bronchial sounds, or new sounds, such as friction sounds, râles, or rhonchi.]

[**Puerile Breathing** is merely an exaggerated vesicular sound, so called because it resembles the louder vesicular sound heard in children. It occurs when some part of the lung is unable to act, and there is, as it were, extra work of the other parts to compensate, and thus the sound is exaggerated.]

(1) **Bronchial or Tubular Breathing** occurs over the entire area of the lung, either when the air vessels are *devoid of air*, which may be caused by the exudation of fluid or solid constituents, or when the lungs are compressed from without. In both cases vesicular sounds disappear, and the condensed or solidified lung tissue *conducts* the tubular sound of the large bronchi to the surface of the chest. [The sound heard over a hepatized lobe of the lung in pneumonia is a typical example.] It also occurs in large cavities, with resistant walls near the surface of the lung, provided these cavities communicate with a large bronchus. [In this case it is termed **cavernous breathing.**]

(2) **The amphoric sound** is compared to that produced by blowing over the mouth of an empty bottle. It occurs either when a *cavity*—at least the size of the fist—exists in the lung, which is so blown into during respiration that a peculiar amphoric-like sound, with a metallic timbre, called **metallic tinkling,** is produced; or when the lung still contains air, and is capable of expansion; as there is still air in the pleural cavity, it acts as a resonator, and causes an amphoric sound, simultaneous with the change of air in the lungs. [The amphoric sound or echo and metallic tinkling are the only certain signs of the existence of a cavity in the lung.]

(3) If **obstruction** occurs in the course of the air passages of the lungs, various results may accrue, according to the nature of the resistance: (*a*) owing to various causes, *e. g.*, in the apices of the lungs, there may be partial swelling of the walls of the air tubes, or infiltration into the air cells, which hinders the regular supply of air. In these cases parts of the lung are not supplied with air continuously; it only reaches them periodically, when a **cogwheel sound** occurs. A similar sound may be heard occasionally in a normal lung, when the muscles of the chest contract in a periodic spasmodic manner. (*b*) When the air entering large bronchi causes the formation of bubbles in the mucus which may have accumulated there "**mucous râles**" are produced. They also occur in small spaces when the walls are separated from their fluid contents by the air entering during inspiration, or when the walls, being adherent to each other, are suddenly pulled asunder. The râles are distinguished as *moist* (when the contents are fluid), or as *dry* (when the contents are sticky); they may be inspiratory, expiratory, or continuous, or they may be coarse or fine; further, there is the very fine crepitation, or crackling sound, and, lastly, the metallic tinkling caused in large cavities through resonance. [**Crepitation** or **vesicular râles** are fine crepitating sounds like those produced by rubbing a lock of hair between the fingers near one's ear; they occur only during inspiration, and are a proof that some air is entering the air vesicles. It is heard in its typical form during the first stage of pneumonia, and seems to be produced by the bursting of minute bubbles of air in a fluid.] (*c*) When the mucous membrane of the bronchi is greatly swollen, or is so covered with viscid mucus that the air must force its way through, deep sonorous **rhonchi** (rhonchi sonori) may occur in the large air passages, and clear, shrill sibilant sounds (rhonchi sibilantes) in the smaller ones. [Rhonchi are usually due to catarrh or to affections of the bronchial mucous membrane or bronchitis.] When there is extensive bronchial catarrh, not unfrequently we feel the chest wall vibrating with the râle sounds (**bronchial fremitus**).

(4) If fluid and air occur together in one pleural cavity in which the lung is collapsed, on shaking the person's thorax vigorously we hear a sound such as is produced when air and water are shaken together in a bottle. This is the **succussion sound** of Hippocrates. Much more rarely this sound is heard under similar conditions in large pulmonary cavities.

(5) **Pleural Friction.**—When the two opposed surfaces of the pleura are inflamed, have become soft, and are covered with exudation, they move over each other during respiration, and in doing so give rise to **friction sounds,** which can be felt (often by the patient himself), and can also be heard. The sound is comparable to the sound produced by bending new leather.

(6) **Pectoral Fremitus.**—When we speak or sing in a loud tone, the walls of the chest vibrate, because the vibration of the vocal cords is propagated throughout the entire bronchial ramifications. The vibration is, of course, greatest near the trachea and large bronchi. The ear cannot detect the sounds distinctly. If there be much exudation or air in the pleura, or great accumulation of mucus in the bronchi, the pectoral fremitus is diminished or altogether absent. [In health, when a person

speaks, the **vocal resonance** over the trachea, although loud, may be inarticulate; and on listening over the sternum the sound is diminished and quite inarticulate; while over the chest wall generally the sound, though distinct, is feeble.

All conditions which cause bronchial breathing increase the pectoral fremitus. Under normal circumstances, therefore, it is louder where bronchial breathing is heard normally. The ear hears an intensified sound, called **bronchophony** [which is a sound like that heard normally over the trachea or bronchi, but audible over the vesicular lung tissue. The conditions that cause it are the same as those on which bronchial breathing depends, so that it is heard in pneumonia and phthisis. If, through effusion into the pleura or inflammatory processes in the lung tissue, the bronchi are pressed flat, a peculiar bleating sound (**ægophony**) may be heard.]

118. PRESSURE IN THE AIR PASSAGES DURING RESPIRATION.—Respiratory Pressure.—If a manometer be tied into the trachea of an animal, so that the respiration goes on completely undisturbed, *i. e.*, **normal respiration,** during every inspiration there is a negative pressure (−3 mm. Hg) and during expiration a positive pressure. Donders placed the U-shaped manometer tube in one nostril, closed his mouth, leaving the other nostril open, and respired quietly. During every quiet inspiration the mercury showed a negative pressure of − 1 mm., and during expiration a positive pressure of 2–3 mm. (Hg).

Forced Respiration.—As soon as the air was inspired or expired with greater force, the variations in pressure became very much greater, *e. g.*, during speaking, singing, and coughing. The inspiratory pressure was = − 57 mm. (36–74), the greatest expiratory pressure + 87 (82–100) mm. Hg. The pressure of forced expiration, therefore, is 30 mm. greater than the inspiratory pressure (*Donders*).

Resistance to Inspiration.—Notwithstanding this, we must not conclude that the expiratory muscles act more powerfully than the inspiratory; for during inspiration a variety of resistances have to be overcome, so that after these have been met, there is only a residue of the force for the aspiration of the mercury. The resistances to be overcome by the inspiratory muscles are: (1) The *elastic tension of the lungs*, which during the deepest expirations = 6 mm.; during the deepest inspirations = 30 mm. Hg (§ 107). (2) The raising of the weight of the chest. (3) The *elastic torsion* of the costal cartilages. (4) The depression of the abdominal contents, and the elastic distention of the abdominal walls. All these not inconsiderable resistances, which the inspiratory muscles have to overcome, act during expiration, and aid the expiratory muscles. The forces concerned in inspiration are decidedly much greater than those of expiration.

Intra-thoracic Pressure.—As the lungs within the chest, in virtue of their elasticity, continually strive to collapse, necessarily they must cause a negative pressure *within the chest.* This amounts in dogs, during inspiration, to − 7.1 to − 7.5 mm. Hg, and during expiration to − 4 mm. Hg. The corresponding values for man have been estimated at − 4.5 mm. Hg and − 3 mm. Hg, by Hutchinson.

[We must distinguish between the **respiratory pressure** of the air *within the respiratory passages*, and the intra-thoracic pressure. The former is the same as the atmospheric pressure when the chest is passive, but less than it as the chest is being enlarged, and greater than it when it is being diminished in size. The **intra-thoracic pressure** is the pressure within the chest, but *outside the lungs*, *i. e.*, in the pleura, mediastinum, etc. It is negative, *i. e.*, less than the atmospheric pressure, and must vary with the degree of distention of the lungs.]

[**Method.**—A direct estimation was made by Adamkiewicz and Jacobson. A trocar with its stylet was forced into the fourth left intercostal space near the sternum and pushed into the pericardium (sheep). The stylet was then withdrawn, and the trocar connected with a manometer, and the negative pressure of − 3 to − 5 mm. Hg was obtained. During severe dyspnœa it was − 9 mm. Hg. Rosenthal introduced an œsophageal sound with an elastic ampulla on its lower end into the œsophagus, so that the ampulla came to lie opposite the posterior mediastinum. The sound was connected with a registering tambour or manometer. During inspiration the manometer fell, and during expiration it rose.]

Even the greatest inspiratory or expiratory pressure is always much less than the blood pressure in the large arteries; but if the pressure be calculated upon the entire respiratory surface of the thorax, very considerable results are obtained.

Pneumatometer.—This instrument of Waldenburg is merely a mercurial manometer fixed to a stand, and connected to an elastic tube with a suitable mouth-piece, which is fitted over the mouth and nose, while the variations of the Hg can be read off on a scale. [In the male, the expiratory pressure is 90–120 mm. Hg, and the respiratory 70–100. The relation of the pressures during expiration and inspiration is more important than the absolute pressure.] The inspiratory pressure is diminished in nearly all diseases where the expansion of the lung is impaired [phthisis], or the expiratory pressure is diminished, as in emphysema and asthma.

Effects of the first Respiration on the Thorax.—Until birth, the airless lungs are completely collapsed (atelectic) within the chest, and fill it, so that on opening the chest in a dead fœtus, pneumothorax does not occur (*Bernstein*). Supposing, however, respiration to have been fully established after birth, and air to have freely entered the lungs, if a manometer be placed in connection with the trachea, and the chest be opened, the manometer will register a pressure of 6 mm. Hg, due to the collapse of the elastic lungs. Bernstein supposes that the thorax assumes a new permanent form, due to the first respiratory distention; it is as if, owing to the respiratory elevation of the ribs, the thorax had become permanently too large for the lungs, which are, therefore, kept permanently distended, but collapse as soon as air passes into the pleura. When a lung has once been filled with air, it cannot be emptied by pressure from without, as the small bronchi are compressed before the air can pass out of the alveoli. The expiratory muscles cannot possibly expel all the air from the lungs, while the inspiratory muscular force is sufficient to distend the lungs beyond their elastic equilibrium. Inspiration distends the lungs, increasing their elastic tension, while expiration diminishes the tension without abolishing it.

119. APPENDIX TO RESPIRATION.—Nasal Breathing.—During quiet respiration we usually breathe—or ought to breathe—through the nostrils, the mouth being closed. The current of air passes through the pharyngo-nasal cavity—so that, in its course during inspiration, it is (1) *warmed* and rendered *moist*, and thus irritation of the mucous membrane of the air passages by the cold air is prevented; (2) small *particles of soot*, or other foreign substances in the air, adhere to, and become embedded in the mucus covering the somewhat tortuous walls of the respiratory passages, and are carried outward by the agency of the ciliated epithelium of the respiratory passages; (3) disagreeable odors and certain impurities are detected by the sense of smell.

If a lung be inflated, air constantly passes through the walls of the alveoli and trachea. This also occurs during violent expiratory efforts (cutaneous emphysema in whooping cough), so that pneumothorax may occur (*J. R. Ewald and Kobert*).

Pulmonary Œdema, or the exudation of lymph into the pulmonary alveoli, occurs (1) When there is very great resistance to the blood stream in the aorta or its branches, *e. g.*, by ligaturing all the arteries going to the head or the arch of the aorta, so that only one carotid remains pervious. (2) When the pulmonary veins are occluded. (3) When the left ventricle, owing to mechanical injury, ceases to beat, while the right ventricle goes on contracting (§ 47). These conditions produce at the same time anæmia of the vasomotor centre, which results in stimulation of that centre, and consequent contraction of all the small arteries. Thus the blood stream through the veins to the right heart is favored, and this in its turn favors the production of œdema of the lungs. [The injection of muscarin rapidly causes pulmonary œdema, due to the increase of pressure and slowing of the blood stream in the pulmonary capillaries. It is set aside by atropin (*Weinzweig, Grossmann*).]

120. MODIFIED RESPIRATORY MOVEMENTS.—(1) **Coughing** consists in a sudden violent expiratory explosion after a previous deep inspiration and closure of the glottis, whereby the glottis is forced open, and any substance, fluid, gaseous, or solid, in contact with the respiratory mucous membrane is violently ejected through the open mouth. It is produced voluntarily or reflexly; in the latter case, it can be controlled by the will only to a limited extent.

[**Causes.**—A cough may be discharged **reflexly** from a large number of surfaces: (1) A draught of cold air striking the *skin*, especially of the upper part of the body. This may cause congestion of blood in the air passages, this in turn exciting the cough. (2) More frequently it is discharged from the respiratory mucous membrane, especially of the larynx, the sensory branches of the vagus and the superior laryngeal nerve being the afferent nerves. A cough cannot be discharged from every part of the larynx: thus there is none from the true vocal cords, but only from the glottis respiratoria. All other parts of the larynx are inactive, and so is the trachea as far as the bifurcation, where stimulation excites cough (*Kohts*). (3) Sometimes an offending body, such as a pea or inspissated cerumen in the external auditory meatus, gives rise to coughing, the afferent nerve being the auricular branch of the vagus. (4) There seems to be no doubt that there may be a "*gastric or stomach cough*," produced by stimulation of the gastric branches of the vagus, especially in cases of indigestion, accompanied by irritation of the larynx and trachea. (5) Irritation of the costal pleura and even of the œsophagus (*Kohts*). (6) Irritation of some parts of the nose.

(7) Sometimes also from irritation of the pharynx, as by an elongated uvula. (8) In some diseases of the liver, spleen, and generative organs, when pressure is exerted on these parts.]

(2) **Hawking,** or clearing the throat. An expiratory current is forced in a continuous stream through the narrow space between the root of the tongue and the depressed soft palate, in order to assist in the removal of foreign bodies. When the act is carried out periodically, the closed glottis is suddenly forced open, and it is comparable to a voluntary gentle cough. This act can only be produced voluntarily.

(3) **Sneezing** consists in a sudden violent expiratory blast through the *nose*, for the removal of mucus or foreign bodies (the mouth being rarely open) after a simple or repeated spasm-like inspiration—the glottis remaining open. It is usually caused reflexly by stimulation of sensory nerve fibres of the nose [nasal branch of the fifth nerve], or by sudden exposure to a bright light [the afferent nerve is the optic]. This reflex act may be interfered with to a certain extent, or even prevented, by stimulation of sensory nerves, or firmly compressing the nose where the nasal nerve issues. The continued use of sternutatories, as in persons who take snuff, dulls the sensory nerves, so that they no longer act when stimulated reflexly.

[**Sternutatories or Errhines,** such as powdered ipecacuanha, snuff, and euphorbium, also increase the secretion from the nasal glands. The afferent impulses sent to the respiratory centre also affect the vasomotor centre, so that, even when sneezing does not occur, the blood pressure throughout the body is raised.]

(4) **Snoring** occurs during respiration through the open mouth, whereby the inspiratory and expiratory stream of air throws the uvula and soft palate into vibration. It is involuntary, and usually occurs during sleep, but it may be produced voluntarily.

(5) **Gargling** consists in the slow passage of the expiratory air current in the form of bubbles through a fluid lying between the tongue and the soft palate, when the head is held backward. It is a voluntary act.

(6) **Crying,** caused by emotional conditions, consists in short, deep inspirations, long expirations with the glottis narrowed, relaxed facial and jaw muscles, secretion of tears, often combined with plaintive inarticulate expressions. When crying is long continued, sudden and spasmodic involuntary contractions of the diaphragm occur, which cause the inspiratory sounds in the pharynx and larynx known as **sobbing.** This is an involuntary act.

(7) **Sighing** is a prolonged inspiration, usually combined with a plaintive sound, often caused involuntarily, owing to painful or unpleasant recollections.

(8) **Laughing** is due to short, rapid expiratory blasts through the tense vocal cords, which cause a clear tone, and there are characteristic inarticulate sounds in the larynx, with vibrations of the soft palate. The mouth is usually open, and the countenance has a characteristic expression, owing to the action of the M. zygomaticus major. It is usually involuntary, and can only be suppressed, to a certain degree, by the will (by forcibly closing the mouth and stopping respiration).

(9) **Yawning** is a prolonged deep inspiration occurring after successive attempts at numerous inspirations—the mouth, fauces, and glottis being wide open; expiration shorter—both acts often accompanied by prolonged characteristic sounds. It is quite involuntary, and is usually excited by drowsiness or ennui.

[(10) **Hiccough** is due to a spasmodic involuntary contraction of the diaphragm, causing an inspiration, which is arrested by the sudden closure of the glottis, so that a characteristic sound is emitted. Not unfrequently it is due to irritation of the gastric mucous membrane, and sometimes it is a very troublesome symptom in uræmic poisoning.]

121. **CHEMISTRY OF RESPIRATION—CARBON DIOXIDE, OXYGEN, and WATERY VAPOR GIVEN OFF.—1. Estimation of CO_2.**—1. The **volume** of CO_2 is estimated by means of the **anthracometer** (Fig. 143, II). The volume of gas is collected in a graduated tube, *r*, *r*, provided with a bulb at one end (previously filled with water and carefully calibrated, *i. e.*, the exact amount which each part of the tube contains is accurately measured), and the tube is closed. The lower end has a stop-cock, *h*, and to this is screwed a flask, *n*, completely filled with a solution of caustic potash; the stop-cock is then opened, the potash solution is allowed to ascend into the tube, which is moved about until all the CO_2 unites with the potash to form potassium carbonate. Hold the tube vertically and allow the potash to run back into the flask, close the stop-cock, and remove the bottle with the potash. Place the stop-cock under water, open it, and allow the water to ascend in the tube, when the space in the tube occupied by the fluid indicates the volume of CO_2 which is combined with the potash.

2. By **Weight.**—A large quantity of the mixture of gases which has to be investigated is made to pass through a Liebig's bulb filled with caustic potash. The potash apparatus having been carefully weighed beforehand, the increase of weight indicates the amount of CO_2 which has been taken up by the potash from the air passed through it.

3. By **Titration.**—A large volume of the air to be investigated is conducted through a known volume of a solution of barium hydrate. The CO_2 unites with the barium and forms barium carbonate. The fluid is neutralized with a standard solution of oxalic acid, and the more barium that has united with the CO_2 the smaller will be the amount of oxalic acid used, and *vice versâ*.

II. **Estimation of Oxygen.**—According to **volume** (*a*) By the union of the O with potassium pyrogallate. The same procedure is adopted as for the estimation of CO_2, only the flask, *n*, is filled with the pyrogallate solution instead of potash. (*b*) By explosion in an eudiometer (see *Blood Gases*, § 35).

III. **Estimation of Watery Vapor.**—The air to be investigated is passed through a bulb containing *concentrated sulphuric acid*, or through a tube filled with pieces of *calcium chloride*. The amount of water is directly indicated by the increase of weight.

122. METHODS OF INVESTIGATION.—I. Collecting the Expired Air.—(1) The air expired may be collected in the cylinder of the spirometer, which is suspended in concentrated salt solution to avoid the absorption of CO_2 (§ 108).

Andral and Gavarret's Apparatus.—The operator breathed several times into a capacious cylinder (Fig. 143). A mouth-piece (M) was placed air-tight over the mouth, while the nostrils were closed. The direction of the respiratory current was regulated by two so-called "**Müller's Valves**" (mercurial), (*a* and *b*). With every inspiration the bottle or valve, *a* (filled below with Hg and hermetically closed above), permits the air inspired to pass to the lungs—during every expiration the expired air can pass only through *b* to the collecting cylinder C.

(2) If the gases given off by the **skin** are to be collected, a limb, or whatever part is to be investigated, is secured in a closed vessel, and the gases so obtained are analyzed.

FIG. 143.



I. Apparatus of Andral and Gavarret for collecting the expired air. C, large cylinder to collect the air expired; P, weight to balance cylinder; *a*, *b*, two Müller's valves; M, mouth-piece. II. Anthracometer of Vierordt.

II. The most important apparatus for this purpose are those of (*a*) **Scharling** (Fig. 144), which consists of a closed box, A, of sufficient size to contain a man. It is provided with an inlet *s* and outlet *b*. The latter is connected with an aspirator, C, a large barrel filled with water. When the stop-cock, *h*, is opened and the water flows out of the barrel, fresh air will rush in continuously into the box, A, and the air mixed with the expired gases will be drawn toward C. A Liebig's bulb, *d*, filled with caustic potash, is connected with the entrance tube, *s*, through which the in-going air must pass, whereby it is completely deprived of CO_2, so that the person experimented on is supplied with air free from CO_2. The air passing out by the exit tube, *b*, has to pass first through *e*, where it gives up its watery vapor to sulphuric acid, whereby the amount of watery vapor is estimated by the increase of the weight of the apparatus, *e*. Afterward the air passes through a bulb, *f*, containing caustic potash, which absorbs all the CO_2, while the tube, *g*, filled with sulphuric acid, absorbs any watery vapor that may come from *f*. The increase in weight of *f* and *g* indicates the amount of CO_2. The total volume of air used is known from the capacity of C.

(*b*) **Regnault and Reiset's Apparatus** is more complicated, and is used when it is necessary to keep animals for some time under observation in a bell-jar. It consists of a globe, R, in which is placed the dog to be experimented on (Fig. 145). Around this is placed a cylinder,

g, g (provided with a thermometer, t), which may be used for calorimetric experiments. A tube, c, leads into the globe, R; through this tube passes a known quantity of pure oxygen (Fig. 145, O). To absorb any trace of CO_2, a vessel containing potash (Fig. 145, CO_2) is placed in the course of the tube. The vessel for measuring the O is emptied toward R, through a solution of calcium chloride from a large pan ($CaCl_2$) provided with large flasks. Two tubes, d and e, lead from R,

FIG. 144.



Scharling's apparatus. d, bulb containing caustic potash to absorb CO_2 from in-going air; A, box for animal experimented on; e and g, tubes containing sulphuric acid to absorb watery vapor; f, potash bulb to absorb CO_2 given off; C, vessel filled with water to aspirate air; h, stop-cock.

and are united by caoutchouc tubes with the potash bulbs (KOH, K*oh*), which can be raised or depressed alternately by means of the beam, W. In this way they aspirate alternately the air from R, and the caustic potash absorbs the CO_2. The increase in weight of these flasks after the experiment indicates the amount of CO_2 expired. The manometer, f, shows whether there is a difference of the pressure outside and inside the globe, R.

FIG. 145.



Scheme of the respiration apparatus of Regnault and Reiset. R, globe for animal; g, g, outer casing for R, provided with a thermometer, t; d and e, exit tubes to movable potash bulbs, KOH and K*oh*; O, in-going oxygen; CO_2, vessel to absorb any carbonic acid; $CaCl_2$, apparatus for estimating the amount of O supplied; f, manometer.

(*c*) **v. Pettenkofer** has invented the most complete apparatus (Fig. 146). It consists of a chamber, Z, with metallic walls, and provided with a door and a window. At a is an opening for the admission of air, while a large double suction pump, PP_1 (driven by means of a steam engine) continually renews the air within the chamber. The air passes into a vessel, b, filled with pumice-

stone saturated with sulphuric acid, in which it is dried; it then passes through a large *gas meter*, *c*, which measures the total amount of the air passing through it. After the air is measured, it is emptied outward by means of the pump, PP_1. From the chief exit tube, *x*, of the chamber, provided with a small manometer, *q*, a narrow laterally placed tube, *n*, passes, conducting a small secondary stream, which is chemically investigated. This current passes through the *suction apparatus*, MM_1 (constructed on the principle of Müller's mercurial valve, and driven by a steam engine). Before

FIG. 146.



Respiration apparatus of v. Pettenkofer. Z, chamber for person experimented on; *x*, exit tube with manometer, *q*; *b*, vessel with sulphuric acid; C, gas meter; PP_1, pump; *n*, secondary current, with, *k*, bulb; MM_1, suction apparatus; *u*, gas meter; N, stream for investigating air before it enters Z.

reaching this apparatus, the air passes through the bulb, K, filled with sulphuric acid, whose increase in weight indicates the amount of *watery vapor*. After passing through MM_1, it goes through the tube, R, filled with *baryta solution*, which takes up CO_2. The quantity of air which passes through the accessory current, *n*, is measured by the *small* gas meter, *u*, from which it passes outward. The *second accessory stream*, N, enables us to investigate the air before it enters the chamber, and it is arranged in exactly the same way as *n*. The increase of CO_2 and H_2O in the accessory stream, *n* (*i. e.*, more than in N), indicates the amount of CO_2 given off by the person in the chamber, Z.

123. COMPOSITION OF ATMOSPHERIC AIR.—1. **Dry Air** contains:—

Gas.	By Weight.	By Volume.
O,	23.015	20.96
N,	76.985	79.02
CO_2,		0.03–0.034

2. **Aqueous vapor** is always present in the air, but it varies greatly in amount, and generally increases with the increase of the temperature of the air. We distinguish (*a*) the *absolute moisture, i. e.*, the quantity of watery vapor which a volume of air contains in the form of vapor; and (*b*) the *relative moisture, i. e.*, the amount of watery vapor which a volume of air contains with respect to its temperature.

Experience shows that people generally can breathe most comfortably in an atmosphere which is not completely saturated with aqueous vapor according to its temperature, but is only saturated to the extent of 70 per cent. If the air be too dry, it irritates the respiratory mucous membrane; if

too moist, there is a disagreeable sensation, and if it be too warm, a feeling of closeness. Hence, it is important to see that the proper amount of watery vapor is present in the air of our sitting rooms, bedrooms, and hospital wards.

The **absolute amount** of moisture varies. In towns during the day it increases with increase of temperature, and diminishes when the temperature falls; it also varies with the direction of the wind, season of the year, and the height above sea level.

The **relative amount** of moisture is greatest at sunrise, least at midday; small on high mountains; greater in winter than in summer; larger with a south or a west wind than with a north or an east wind.

The air in midsummer contains absolutely three times as much watery vapor as in midwinter, nevertheless the air in summer is *relatively* drier than the air in winter.

3. The **air expands by heat.** Rudberg found that 1000 volumes of air, at 0°, expanded to 1365 when heated to 100° C.

4. The **density** of the air diminishes with increase of the height above the sea level.

FIG. 147.

124. COMPOSITION OF EXPIRED AIR.—1. The expired air contains **more CO_2**—in normal respiration = 4.38 vols. per cent. (3.3 to 5.5 per cent.), so that it contains nearly 100 times more CO_2 than the atmospheric air.

2. It contains **less O** (4.782 vols. per cent. less) than the atmospheric air. *i. e.*, it contains only 16.033 vols. per cent. of O.

3. **Respiratory Quotient.**—Hence, during respiration, more O is taken into the body from the air than CO_2 is given off; so that the volume of the expired air is ($\frac{1}{40}$ to $\frac{1}{50}$) smaller than the volume of the air inspired, both being calculated as dry, at the same temperature, and at the same barometric pressure. The relation of the O absorbed to the CO_2 given off is 4.38 : 4.782. This is expressed by the "respiratory quotient"—

$$\frac{CO_2}{O}\left(=\frac{4.38}{4.782}=\right) 0.906.$$

4. An excessively small quantity of **N** is added to the expired air (*Regnault and Reiset*). Segen found that all the N taken in with the food did not reappear in the excreta (urine and fæces), and he assumed that a small part of it was given off by the lungs.

5. During ordinary respiration the expired air is **saturated with watery vapor.** It is evident, therefore, that when the watery vapor in the air varies, the lungs give off different quantities of water from the body. The percentage of watery vapor falls during rapid respiration (*Moleschott*).

6. The expired air is **warmer** (36.3° C.). It is very near the temperature of the body, and although the temperature of the surrounding atmosphere be very variable, the temperature of the expired air still remains nearly the same.

Fig. 147 shows the instrument used by Valentin and Brunner to determine the temperature of the expired air. It consists of a glass tube, A, A., with a mouth-piece, B, and in it is a fine thermometer, C. The operator breathes through the nose and expires slowly through the mouth-piece into the tube.

Temperature of the Air.	Temperature of the Expired Air.
−6.3° C.,	+ 29.8° C.
+ 17–19° C.,	+ 36.2–37° C.
+ 44° C.,	+ 38.5° C.

7. The diminution of the **volume** of the expired air mentioned under (3) is far more than compensated by the warming which the inspired air undergoes in the respiratory passages, so that the volume of the expired air is one-ninth greater than the air inspired.

8. A very small quantity of **ammonia** is found in the expired air = 0.0204 grammes in 24 hours; it is probably derived from the blood.

9. Small quantities of **H** and **CH_4** are expired, both being absorbed from the intestine. In herbivora, Reiset found that 30 litres of CH_4 were expired in 24 hours.

125. QUANTITY OF GASES EXCHANGED.—As under normal circumstances more O is absorbed than there is CO_2 given off (equal volumes of O and CO_2 contain equal quantities of O), a part of the O must be used for other oxidation processes in the body. According to the extent of these latter processes, the ratio of the O taken into the CO_2 given out —

$$\left(\frac{CO_2}{O} = 0.906 \text{ normally}\right) \text{ must vary.}$$

The amount of CO_2 given off may be less than the "mean" above stated. The quantity of CO_2 alone is not a reliable indication of the entire exchange of gases during respiration; we must estimate simultaneously the amount of O absorbed and the CO_2 given off.

126. DAILY GASEOUS INCOME AND EXPENDITURE :—

Income in 24 hours.	Expenditure in 24 hours.
Oxygen—	**Carbonic Acid—**
744 grms. = 516.500 c. cmtr. (*Vierordt*).	900 grms. = 455500 c. cmtr. (*Vierordt*).
	36 grms. per hour (*Scharling*).
	32.8 to 33.4 grms. " (*Liebermeister*).
	34 grms. . . " . (*Panum*).
	31.5 to 33 grms. . " . (*Ranke*).
	Water.—640 grms. . " . (*Valentin*).
(At 0° C. and mean barometric pressure.)	330 " . " . (*Vierordt*).

127. CONDITIONS INFLUENCING THE GASEOUS EXCHANGES—The formation of CO_2, in all probability, consists of two distinct processes. First, compounds containing CO_2, which are *oxidation products* of substances containing carbon, seem to be formed in the tissues. The second process consists in the separation of this CO_2, which, however, takes place without the absorption of O. Both processes do not always occur simultaneously, and the one process may exceed the other in extent. The formation of CO_2 is affected by—

1. **Age.**—Until the body is fully developed, the CO_2 given off increases, but it diminishes as the bodily energies decay. Hence, in young persons the O absorbed is relatively greater than the CO_2 given off; at other periods both values are pretty constant. Example :—

Age—Years.	In 24 Hours.	
	CO_2, Gram. Excreted. = Carbon.	O Absorbed, Gram.
8	443 gram. = 121 Carbon	375 grammes.
15	766 " = 209 "	652 "
16	950 " = 259 "	809 "
18–20	1003 " = 274 "	854 "
20–24	1074 " = 293 "	914 "
40–60	889 " = 242 "	757 "
60–80	810 " = 221 "	689 "

The *absolute* amount of CO_2 given off is less in children than in adults; but if the CO_2 given off be calculated with reference to body weight, then, weight for weight, a child gives off twice as much CO_2 as an adult.

2. Sex.—Males, from the eighth year onward to old age, give off about one-third more CO_2 than females. This difference is more marked at puberty, when the difference may rise to one-half. After cessation of the menses, there is an increase, and in old age the amount of CO_2 given off diminishes. Pregnancy increases the amount, owing to causes which are easily understood (*Andral and Gavarret.*)

3. Constitution.—In general, muscular, energetic persons use more O and excrete more CO_2 than less active persons of the same weight.

4. Alternation of Day and Night.—The CO_2 given off is diminished about one-fourth during sleep, due to the constant heat of the surroundings (bed), darkness, absence of muscular activity, and the non-taking of food (see 5, 6, 7, 9). O is not stored up during sleep (*S. Lewin*). After awaking in the morning, the respirations are deeper and more rapid, while the amount of CO_2 given off is increased. It decreases during the forenoon, until dinner at mid-day causes another increase. It falls during the afternoon, and increases again after supper.

During **hibernation**, when no food is taken, and when the respirations cease, or are greatly diminished, the respiratory exchange of gases is carried out by diffusion and the cardio-pneumatic movements (§ 59). The CO_2 given off falls to $\frac{1}{75}$, the O taken in to $\frac{1}{11}$, of what they are in the waking condition. Much less CO_2 is given off than O taken in, so that the body weight may increase through the excess of O.

5. Temperature of the Surroundings.—Cold-blooded animals become warmer when the temperature of their environment is raised, and they give off more CO_2 in this condition than when they are cooler; *e.g.*, a frog with the temperature of the surroundings at 39° C. excreted three times as much CO_2 as when the temperature was 6° C. **Warm-blooded animals** behave quite differently when the temperature of the surrounding medium is changed. When the temperature of the animal is lowered thereby, there is a considerable decrease in the amount of CO_2 given off, as in cold-blooded animals, but if the temperature of the animal be increased (and also in fever), the CO_2 is increased (*C. Ludwig and Sanders-Ezn*). Exactly the reverse obtains when the temperature of the surroundings varies and the bodily temperature remains constant. As the cold of the surrounding medium increases, the processes of oxidation within the body are increased through some as yet unknown reflex mechanism; the number and depth of the respirations increase, whereby more O is taken in and more CO_2 is given out. A man in January uses 32.2 grammes O per hour; in July only 31.7 grammes. In animals, with the temperature of the surroundings at 8° C., the CO_2 given off was one-third greater than with a temperature of 38° C. When the temperature of the air increases—the body temperature remaining the same—the respiratory activity and the CO_2 given off diminish, while the pulse remains nearly constant. On passing suddenly from a cold to a warm medium the amount of CO_2 is considerably diminished; and conversely, on passing from a warm to a cold medium, the amount is considerably increased (§ 214).

6. Muscular exercise causes a considerable increase in the CO_2 given out, which may be three times greater during walking than during rest (*Ed. Smith*). Ludwig and Sczelkow estimated the O taken in and the CO_2 given off by a rabbit during rest, and when the muscles of the hind limbs were tetanized. During tetanus the O and CO_2 were increased considerably, but in tetanized animals more O was given off in the CO_2 expired than was taken up simultaneously during respiration. The passive animal absorbed nearly twice as much O as the amount of CO_2 given off (§ 294).

7. Taking of food causes a not inconsiderable increase in the CO_2 given off, which depends upon the quantity taken; the increase generally occurs about an hour after the chief meal—dinner. During **inanition**, the exchange of gases diminishes considerably until death occurs. At first the CO_2 given off diminishes more quickly than the O is taken up. The **quality** of the food influences the

CO_2 given off to this extent, that substances rich in carbon (carbohydrates and fats) cause a greater excretion of CO_2 than substances which contain less C (albumins). Regnault and Reiset found that a dog gave off 79 per cent. of the O inspired after a flesh diet, and 91 per cent. after a diet of starch. If easily oxidizable substances (glycerin or lactate of soda) are injected into the blood, the O taken in and the CO_2 given off undergo a considerable increase (*Ludwig and Scheremetjewsky*). Alcohols, tea, and ethereal oils diminish the CO_2 (*Prout, Vierordt*). [Ed. Smith divided foods, with reference to the excretion of CO_2, into two classes. The **respiratory excitants** include nitrogenous foods, rum, beer, sugar, stout, etc.; the **non-exciters** starch, fat, some alcoholic mixtures. The most powerful respiratory excitants, however, are tea, sugar, coffee, and rum, and the maximum effect is usually experienced within an hour. He also found that the effects produced by alcoholic drinks varied with the nature of the spirituous liquor. Thus brandy, whisky, and gin diminish the amount; while pure alcohol, rum, ale, and porter tend to increase it.

8. The **number and depth of the respirations** have practically no influence on the formation of CO_2 or the oxidation processes within the body, these being regulated by the tissues themselves, by some mechanism as yet unknown (*Pflüger*). They have a marked effect, however, upon the removal of the already formed CO_2 from the body. An increase in the *number* of respirations (their depth remaining the same), as well as an increase of their *depth* (the number remaining the same), causes an *absolute* increase in the amount of CO_2 given off, which, with reference to the total amount of gases exchanged, is *relatively* diminished. The following example from Vierordt illustrates this:—

No. of Resps. per Minute.	Volume of Air.	Amount of CO_2.	= per cent. CO_2.	Depth of Resps.	Amount of CO_2.	= per cent. CO_2
12	6000	258 c. cmtr.	= 4.3%	500	21 c. cmtr.	= 4.3%
24	12000	420 "	= 3.5 "	1000	36 "	= 3.6 "
48	24000	744 "	= 3.1 "	1500	51 "	= 3.4 "
96	48000	1392 "	= 2.9 "	2000	64 "	= 3.2 "
				3000	72 "	= 1.4 "

9. Exposure to **bright light** causes an increase in the CO_2 given off in frogs, in mammals and birds, even in frogs deprived of their lungs, or in those whose spinal cord has been divided high up. The consumption of O is increased at the same time. The same results occur in blind persons, although to a less degree. Bluish-violet light is almost as active as white light, while red light is less active.

10. The experiments of Gréhant, on dogs, seem to show that intense inflammation of the bronchial mucous membrane influences the CO_2 given off.

11. Among **poisons**, thebaia increases the CO_2 given off, while morphia, codeia, narcein, narcotin, papaverin, diminish it (*Fübini*).

128. DIFFUSION OF GASES WITHIN THE LUNGS.—The air within the air vesicles contains most CO_2 and least O, and as we pass from the small to the large bronchi and onward to the trachea, the composition of the air gradually approaches more closely to that of the atmosphere. Hence, if the air expired be collected in two portions, the first half (*i. e.*, the air from the larger air passages) contains less CO_2 (3.7 vols. per cent.) than the second half (5.4 vols. per cent.). The difference in the percentage of gases gives rise to a diffusion of the gases within the air passages; the CO_2 must *diffuse* from the air vesicles outward, and the O from the atmosphere and nostrils inward (§ 33). This movement is aided by the cardio-pneumatic movement (§ 59). In hibernating animals and in persons *apparently* but not actually *dead*, the exchange of gases within the lungs can only occur

in the above-mentioned ways. For ordinary purposes this mechanism is insufficient, and there are added the respiratory movements whereby atmospheric air is introduced into the larger air passages, from which and into which the diffusion currents of O and CO_2 pass, on account of the difference of tension of the gases.

129. EXCHANGE OF GASES IN THE AIR VESICLES.—The exchange of gases between the gases of the blood and those in the air vesicles occurs almost exclusively through the agency of chemical processes, and therefore independently of the diffusion of gases.

Method.—It is important to ascertain the tension of the O and CO_2 in the venous blood of the pulmonary capillaries. Pflüger and Wolfberg estimated the tension by "**catheterizing the lungs.**" An elastic catheter was introduced through an opening in the trachea of a dog into the bronchus leading to the lowest lobe of the left lung. An elastic sac was placed round the catheter, and when the latter was introduced into the bronchus, the sac around the catheter was distended so as to plug the bronchus. No air could escape between the catheter and the wall of the bronchus. The outer end of the catheter was closed at first, and the dog was allowed to respire quietly. After four minutes the air in the air vesicles was completely in equilibrium with the blood gases. The air of the lung was sucked out of the catheter by means of an air-pump, and afterward analyzed.

Thus we may measure indirectly the tension of the O and CO_2 in the venous blood of the pulmonary capillaries. The *direct* estimation of the gases in different kinds of blood is made by shaking up the blood with another gas. The gases so removed indicate directly the proportion of blood gases.

The following statement shows the tension and percentage of O and CO_2 in arterial and venous blood, in the atmosphere, and in the air of the alveoli :—

I.

O-Tension in arterial blood = 29.6 mm. Hg (corresponding to a mixture containing 3.9 vol. per cent. of O).

II.

CO_2-Tension in arterial blood = 21 mm. Hg (corresponding to 2.8 vol. per cent.).

III.

O-Tension in venous blood = 22 mm. Hg (corresponding to 2.9 vol. per cent.).

IV.

CO_2-Tension in venous blood = 41 mm. Hg (corresponding to 5.4 vol. per cent.).

V.

O-Tension in the air of the alveoli of the catheterized lung = 27.44 mm. Hg (corresponding to 3.6 vol. per cent.).

VI.

CO_2-Tension in the air of the alveoli of the catheterized lung = 27 mm. Hg (corresponding to 3.56 vol. per cent.).

VII.

O-Tension in the atmosphere = 158 mm. Hg (corresponding to 20.8 vol. per cent.).

VIII.

CO_2-Tension in the atmosphere = 0.38 mm. Hg (corresponding to 0.03–0.05 vol. per cent.).

When we compare the tension of the O in the air (VII = 158 mm. Hg) with the tension of the O in venous blood (III = 22 mm. Hg, or V = 27.44 mm. Hg), we might be inclined to assume that the passage of the O from the air of the air vesicles into the blood was due solely to diffusion of the gases; and similarly, we might assume that the CO_2 of the venous blood (IV or VI) diffused into the air vesicles, because the tension of the CO_2 in the air is much less (VIII). There are a number of facts, however, which prove that the exchanges of the gases in the lungs is chiefly due to **chemical** forces.

[v. Fleischl finds that fluids yield up their gases very much more easily when they receive a shock, and he regards the shock communicated to the blood by the contraction of the heart as an important factor in preparing the blood for the diffusion of CO_2 from the blood plasma into the lungs.]

[**Changes produced in the Blood by Respiration.**—The blood of the pulmonary artery is changed from venous into arterial blood (§ 39), the most obvious alterations being (1) the change in **color** from dark crimson to bright scarlet. (2) It loses CO_2. (3) It gains O. (4) The reduced Hb of the venous blood is converted into HbO_2. (5) As to a supposed difference of temperature, see § 209, 3. (6) Pawlow finds that blood which passes several times through the

lungs loses its power of coagulation. Are we to assume that the pulmonary tissues have the property of destroying the fibrin-ferment?

1. **Absorption of O.**—Concerning the absorption of O from the air in the alveoli into the venous blood of the lung capillaries, whereby the blood is arterialized, it is proved that this is a **chemical process.** The gas-free (reduced) hæmoglobin takes up O to form oxyhæmoglobin (§ 15, 1). That this absorption has nothing to do directly with the diffusion of gases, but is due to a chemical combination of the atomic compounds, is shown by the fact that, when pure O is respired, the blood does not take up more O than when atmospheric air is respired; further, that animals made to breathe in a limited closed space can absorb almost all the O—even to traces—into their blood before suffocation occurs. Of course, if the absorption of O were due to diffusion, in the former case more O would be absorbed, while in the latter case the absorption of O could not possibly occur to such an extent as it does. The law of diffusion comes into play in connection with the absorption of O to this extent, viz., that the O diffuses from the air cells of the lung into the blood plasma, where it reaches the blood corpuscles floating in the plasma. The hæmoglobin of the blood corpuscles forms at once a chemical compound (oxyhæmoglobin) with the O.

Even in very rarefied air, such as is met with in the upper regions of the atmosphere during a balloon ascent, the absorption of O still remains independent of the partial pressure. But a much longer *time* is required for this process at the ordinary temperature of the body, so that in rarefied air the absorption of O is greatly delayed, but it is not diminished. This is the cause of death in aeronauts who have ascended so high that the atmospheric pressure is diminished to one-third (*Setschenow*).

2. **Excretion of CO_2.**—With regard to the excretion of CO_2 from the blood, we must remember that the CO_2 in the blood exists in two conditions. Part of the CO_2 forms a loose or feeble chemical compound, while another portion is more firmly combined. The former is obtained by those means which remove gases from fluids containing them in a state of absorption, so that in removing the CO_2 from the blood it is difficult to determine whether the CO_2 so removed, obeyed the law of diffusion, or if it was expelled by chemical means.

Although it is convenient to represent the excretion of CO_2 from the blood into the air vesicles of the lung, as due to equilibrium of the tension of the CO_2 on opposite sides of the alveolar membrane, *i. e.*, to diffusion—nevertheless, **chemical processes** play an important part in this act. The absorption of O by the colored corpuscles acts, at the same time, in expelling CO_2. This is proved by the fact that the expulsion of CO_2 from the blood takes place more readily when O is simultaneously admitted. The free supply of O not only favors the removal of the CO_2, which is loosely combined, but it also favors the expulsion of that portion of the CO_2 which is more firmly combined, and which can only be expelled by the addition of acids to the blood. That the oxygenated blood corpuscles (*i. e.*, their oxyhæmoglobin) are concerned in the removal of CO_2 is proved by the fact that CO_2 is more easily removed from serum which contains oxygenated blood corpuscles than from serum charged with O.

[The following scheme may serve to illustrate the extent to which diffusion comes into play. The O must pass through the alveolar membrane, AB—including the alveolar epithelium and the wall of the capillaries—as well as the blood plasma, to reach the hæmoglobin of the blood corpuscles. Similarly, the CO_2 must leave the salts of the plasma with which it is in combination, and diffuse in the opposite direction, through the wall of the capillaries, the alveolar membrane, and epithelium, to reach the air vesicles. Let AB represent the alveolar membrane; on the one side of it is represented the partial pressure of the CO_2 and O in the air vesicles; and on the other, the partial pressure of the CO_2 and O in the venous blood entering the lung. The indexes indicate the direction of diffusion.]



Nature of the Process.—The exchange of gases between the blood and the air in the lungs has been represented by Donders as due to the process of **dissociation.**

[Bohr used a modified rheometer of Ludwig's, whereby living arterial blood was brought into direct contact with a volume of air containing a greater or less percentage of CO_2. Even when the amount of CO_2 in the air in direct contact with the blood was very small, it was found that very little CO_2 diffused from the blood into the air space. Bohr therefore concludes that the separation of CO_2 from the venous blood in the lungs, and its passage into the air vesicles, are not explicable on the hypothesis of diffusion, but we must rather regard the CO_2 as removed from the blood by the pulmonary tissue by means of a kind of secretory process, analogous to the excretion processes in glands.]

130. **DISSOCIATION OF GASES.**—Many gases form *true chemical compounds* with other bodies (*i. e.*, they combine according to their equivalents), when the contact of these bodies is effected under conditions such that the partial pressure of the gases is high. The chemical compound formed under these conditions is broken up, whenever the partial pressure is diminished, or when it reaches a certain minimum level, which varies with the nature of the bodies forming the compound. Thus, by increasing and diminishing the partial pressure alternately, a chemical compound of the gas may be formed and again broken up. This process is called **dissociation of the gases.** The minimal partial pressure is constant for each of the different substances and gases, but *temperature*, as in the case of the absorption of gases, has a great effect on the partial pressure; with increase of temperature the partial pressure, under which dissociation occurs, diminishes.

As an example of the dissociation of a gas, take the case of calcium carbonate. When it is heated in the air to 440° C., CO_2 is given off from its state of chemical combination, but is taken up again and a chemical compound formed, which is changed into chalk when it cools.

Dissociation in the Blood.—The chemical combinations containing CO_2 and those containing O within the blood stream, viz., the salts of the plasma, which are combined with CO_2, and the oxyhæmoglobin, behave in a similar manner. If these compounds of O and CO_2 are placed under conditions where the partial pressure of these gases is very low—*i. e.*, in a medium containing a very small amount of these gases, the compounds are dissociated, *i. e.*, they give off CO_2 or O. If after being dissociated they are placed under conditions where, owing to the large amount of these gases, the partial pressure of O or of CO_2 is high, these gases are taken up again, and enter into the condition of chemical combination.

The hæmoglobin of the blood in the pulmonary capillaries finds plenty of O in the alveoli; hence, it unites with the O, owing to the high partial pressure of the O in the lung, and so forms the compound oxyhæmoglobin. On its course through the capillaries of the systemic circulation, the oxyhæmoglobin of the blood comes into relation with tissues poor in O; the oxyhæmoglobin is dissociated, the O is supplied to the tissues, and the blood freed from this O returns to the right heart, and passes to the lungs, where it takes up the new O.

The blood while circulating meets with most CO_2 in the tissues; the high partial pressure of the CO_2 in the tissues causes the CO_2 to unite with certain constituents in the blood so as to form chemical compounds, which carry the CO_2 from the tissues to the lungs. In the air of the lungs, however, the partial pressure of the CO_2 is very low, dissociation of these chemical compounds occurs under

the low partial pressure, and the CO_2 passes into the air cells of the lung, from which it is expelled during expiration. It is evident that the giving up of O from the blood to the tissues, and the absorption of CO_2 from the tissues, go on side by side and take place simultaneously, while in the lungs the reverse processes occur almost simultaneously.

131. **CUTANEOUS RESPIRATION.—Methods.**—If a man or an animal be placed in the chamber of the respiratory apparatus (§ 122), and if tubes be so arranged that the respiratory gases do not enter the chamber, of course we obtain only the "*perspiration*" of the skin in the chamber. It is less satisfactory to leave the head of the person outside the chamber, while the neck is fixed air-tight in the wall of the chamber. The extent of the cutaneous respiration of a limb may be ascertained by enclosing it in an air-tight vessel (*Röhrig*) similar to that used for the arm in the plethysmograph (§ 101).

Loss by Skin.—A healthy man loses by the skin, in 24 hours, $\frac{1}{27}$ of his body weight, which is greater than the loss by the lungs, in the ratio of 3 : 2. Only 10 grammes—150 grains,—or it may be 3.9 grammes, 60 grains,—of the entire loss are due to the CO_2 given off by the skin. The remainder of the excretion from the skin is due to **water** [$1\frac{1}{2}$–2 lb daily] containing a few salts in solution. When the surrounding temperature is raised, the CO_2 is increased, in fact it may be doubled; violent muscular exercise has the same effect.

O Absorbed.—The O taken up by the skin is either equal to, or slightly less than, the CO_2 given off. As the CO_2 excreted by the skin is only $\frac{1}{220}$ of that excreted by the lungs, while the O taken in $= \frac{1}{180}$ of that taken in by the lungs, it is evident that the *respiratory activity of the skin is very slight.* Animals whose skin has been covered by an impermeable varnish die, not from suffocation, but from other causes (§ 225).

In animals with a thin, **moist epidermis** (frog) the exchange of gases is much greater, and in them the skin so far supports the lungs in their function, and may even partly replace them functionally. In mammals with thick, dry cutaneous appendages, the exchange of gases is, again, much less than in man.

132. **INTERNAL RESPIRATION.—Where CO_2 is formed.**—By the term "**internal respiration**" is understood the exchange of gases between the capillaries of the systemic circulation and the tissues of the organs of the body. As organic constituents of the tissues, during their activity, undergo gradual oxidation, and form among other products, CO_2; we may assume (1) that the chief focus for the absorption of O and the formation of CO_2 is to be sought for **within the tissues** themselves. That the O from the blood in the capillaries rapidly penetrates or diffuses into the tissues, is shown by the fact that the blood in the capillaries rapidly loses O and gains CO_2, while blood containing O, and kept warm outside the body, changes very slowly and incompletely. If portions of fresh tissues be placed in defibrinated blood containing O, then the O rapidly disappears. Frogs deprived of their blood exhibit an exchange of gases almost as great as normal. This shows that the exchange of gases must take place in the tissues themselves. If the chief oxidations took place in the blood and not in the tissues, then, during suffocation, when O is excluded, the substances which use up O, *i.e.*, those substances which act as reducing agents, ought to accumulate in the blood. But this is not the case, for the blood of asphyxiated animals contains mere traces of reducing materials (*Pflüger*). It is difficult to say how the O is absorbed by the tissues, and what becomes of it immediately it comes in contact with the living elements of the tissues. Perhaps it is temporarily stored up, or it may form certain intermediate less oxidized compounds. This may be followed by a period of rapid formation and excretion of CO_2. On this supposition, it is evident that the absorption of O and the excretion of CO_2 need not occur to the same extent, so that the amount of CO_2 given off at any period is not necessarily an index of the amount of O absorbed during the same period (§ 127).

[There are two views as to where the CO_2 is formed as the blood passes through the tissues. One view is that the seat of oxidation is in the blood itself, and the other is that it is formed in the tissues. If we knew the tension of the gases in the tissues, the problem would be easily solved, but we can only arrive at a knowledge of this subject *indirectly*, in the following ways]:—

CO_2 in Cavities.—That the CO_2 is formed in the tissues, is supported by the fact that the amount of CO_2 in the fluids of the cavities of the body is greater than the CO_2 in the blood of the capillaries. The tension of CO_2 in—

	Mm.		Mm.
Arterial blood, . .	12.28 Hg tension.	Bile, ...	50.0 Hg tension.
Peritoneal cavity, . .	58.5 " "	Hydrocele fluid, . .	46.5 " "
Acid urine, . .	68.0 " "		(*Pflüger and Strassburg*).

The large amount of CO_2 in these fluids can only arise from the CO_2 of the tissues passing into them.

Gases of Lymph.—In the lymph of the ductus thoracicus the tension of $CO_2 = 33.4$ to 37.2 mm. Hg, which is greater than in arterial blood, *but considerably less than in venous blood* (41.0 mm. Hg). [*Ludwig and Hammarsten, Tschirjew.*] This does not entitle us to conclude that in the tissues from which the lymph comes only a small quantity of CO_2 is formed, but rather that in the lymph there is less attraction for the CO_2 formed in the tissues than in the blood of the capillaries, where chemical forces are active in causing it to combine, or that in the course of the long lymph current, the CO_2 is partly given back to the tissues, or that CO_2 is formed in the blood itself. Further, the muscles, which are by far the largest producers of CO_2 contain few lymphatics, nevertheless they supply much CO_2 to the blood. The amount of free "non-fixed" CO_2 contained in the juices and tissues indicates that the CO_2 passes from the tissues into the blood; still, Preyer believes that in venous blood CO_2 undergoes chemical combination. The exchange of O and CO_2 varies much in the different tissues. The **muscles** are the most important organs, for in their active condition they excrete a large amount of CO_2, and use up much O. The O is so rapidly used up by them that no free O can be pumped out of muscular tissue (*L. Hermann*). The exchange of gases is more vigorous during the activity of the tissues. Nor are the salivary glands, kidneys, and pancreas any exception, for although, when these organs are actively secreting, the blood flows out of the dilated veins in a bright red stream, still the relative diminution of CO_2 is more than compensated by the increased volume of blood which passes through these organs.

Reductions by the Tissues.—The researches of Ehrlich have shown that in most tissues very energetic reductions take place. If coloring matters, such as alizarin blue, indophenol blue, or methyl blue, be introduced into the blood stream, the tissues are colored by them. Those tissues or organs which have a particular affinity for O (*e.g.*, liver, cortex of the kidney, and lungs), absorb O from these pigments, and render them colorless. The pancreas and sub-maxillary gland scarcely reduce them at all.

(2) In the **blood itself**, as in all tissues, O is used up and CO_2 is formed. This is proved by the following facts: That blood withdrawn from the body becomes poorer in O and richer in CO_2; that in the blood of asphyxia, free from O, and in the blood corpuscles, there are slight traces of reducing agents, which become oxidized on the addition of O. Still, this process is comparatively insignificant as against that which occurs in all the other tissues. That the walls of the vessels—more especially the muscular fibres in the walls of the small arteries—use O and produce CO_2 is unquestionable, although the exchange is so slight that the blood in its whole arterial course undergoes no visible change.

Ludwig and his pupils have proved that CO_2 is actually formed in the blood. If the easily oxidizable lactate of soda be mixed with blood, and this blood be caused to circulate in an excised but living organ, such as a lung or kidney, more O is used up and more CO_2 is formed than in unmixed blood similarly transfused.

(3) That the tissues of the living lungs use O and give off CO_2 is probable. When C. Ludwig and Müller passed arterial blood through the blood vessels of a lung deprived of air, the O was diminished and the CO_2 increased. As the total amount of CO_2 and O found in the entire blood at any one time is only 4 grammes, and as the daily excretion of $CO_2 = 900$ grammes, and the O absorbed daily $= 744$ grammes, it is clear that exchange of gases must go on with great rapidity, that the O absorbed must be used quickly, and the CO_2 must be rapidly excreted.

Still, it is a striking fact that oxidation processes of such magnitude, as *e.g.*, the union of C to form CO_2, occur at the relatively low temperature of the blood and tissues. It has been surmised that the blood acts as an ozone producer, and transforms this active form of O to the tissues. Liebig showed that the *alkaline reaction* of most of the juices and tissues favors the processes of oxidation. Numerous organic substances, which are not altered by O alone, become rapidly oxidized in the presence of free alkalies, *e.g.*, gallic acid, pyrogallic acid, and sugar; while many organic acids, which are unaffected by ozone alone, are changed into carbonates when in the form of alkaline salts (*Gorup-Besanez*); and, in the same way, when they are introduced into the body in the form of acids, they are partly or wholly excreted in the urine, but when they are administered as alkaline compounds they are changed into carbonates.

133. **RESPIRATION IN A LIMITED SPACE.**—Respiration in a **limited space** causes (1) a gradual diminution of O; (2) a simultaneous increase of CO_2; (3) a diminution in the volume of the gases. If the space be of **moderate** dimensions, the animal uses up almost all the O contained therein, and dies ultimately of spasms caused by the asphyxia. The O is absorbed, therefore—independently of the laws of absorption—by chemical means. The O in the blood is almost completely used up (§ 129). In a **larger space**, the CO_2 accumulates rapidly, before the diminution of O is such as to affect the life of the animal. As CO_2 can only be excreted from the blood when the tension of the CO_2 in the blood is greater than the tension of CO_2 in the air, as soon as the CO_2 in the surrounding air in the closed space becomes the same as in the blood, the CO_2 will be retained in the blood, and finally CO_2 may pass back into the body. This occurs in a large closed space, when the amount of O is still sufficient to support life, so that death occurs under these circumstances (in rabbits) through poisoning with CO_2 causing diminished excitability, loss of consciousness, and lowering of temperature, but no spasms (*Worm Müller*). In **pure O** animals breathe in a normal way; the quantity of O absorbed and the CO_2 excreted is quite independent of the percentage of O, so that the former occurs through chemical agency independent of pressure. In limited spaces filled with O, animals died by absorption of the CO_2 excreted. Worm Müller found that rabbits died after absorbing CO_2 equal to half the volume of their body, although the air still contained 50 per cent. O. Animals can breathe quite quietly a mixture of air containing 14.8 per cent. (20.9 per cent. normal); with 7 per cent. they breathe with difficulty; with 4.5 per cent. there is marked dyspnœa; with 3 per cent. O there is tolerably rapid asphyxia. The air expired by man normally contains 14 to 18 per cent. O. According to Hempner, mammals placed in a mixture of gases poor in O use slightly less O.

Dyspnœa occurs when the respired air is deficient in O, as well as when it is overcharged with CO_2, but the dyspnœa in the former case is prolonged and severe; in the latter, the respiratory activity soon ceases. The want of O causes a greater and more prolonged increase of the blood pressure than is caused by an excess of CO_2. Lastly, the consumption of O in the body is less affected when the O in the air is diminished than when there is an excess of CO_2. If air containing a diminished amount of O be respired, death is preceded by violent phenomena of excitement and spasms, which are absent in cases of death caused by breathing air overcharged with CO_2. In poisoning with CO_2, the excretion of CO_2 is greatly diminished, while with diminution of O it is almost unchanged.

If animals be supplied with a mixture of gases similar to the atmosphere, in which N is replaced by H, they breathe quite normally (*Lavoisier and Seguin*); the H undergoes no great change.

Cl. Bernard found that, when an animal breathed in a limited space, it became partially accustomed to the condition. On placing a bird under a bell-jar, it lived several hours; but if several hours before its death, another bird fresh from the outer air were placed under the same bell-jar, the second bird died at once of convulsions.

Frogs, when placed for several hours in air devoid of O, give off just as much CO_2 as in air containing O, and they do this without any obvious disturbance. Hence, it appears that the formation of CO_2 is independent of the absorption of O, and the CO_2 must be formed from the decomposition of other compounds. Ultimately, however, complete motor paralysis occurs, while the circulation remains undisturbed (*Aubert*).

[134. **DYSPNŒA AND ASPHYXIA.**—For the causes of dyspnœa see § 111, and those of asphyxia see § 368. If from any cause an animal be not supplied with a due amount of air, normal respiration becomes greatly altered, passing through the phases of **hyperpnœa**, or increased respiration, **dyspnœa**, or difficulty of breathing, to the final condition of suffocation or **asphyxia**. The phenomena of asphyxia may be developed by closing the trachea of an animal with a clamp, or by any means which prevents the entrance of air or blood into the lungs.

The **phenomena of asphyxia** are usually divided into several stages: 1. During the **first stage** there is hyperpnœa, the respirations being deeper, more frequent, and labored. The extraordinary muscles of respiration—both those of inspiration and expiration (§ 118)—are called into action, dyspnœa is rapidly produced, and the struggle for air becomes more and more severe. At the same time the oxygen of the blood is being used up, while the blood itself becomes more and more venous. The venous blood circulating in the medulla oblongata and spinal cord stimulates the respiratory centres, and causes the violent respirations. This stage usually lasts about a minute, and gradually gives place to—

2. The **second stage**, when the inspiratory muscles become less active, while those concerned in labored expiration contract energetically, and indeed almost every muscle in the body may contract; so that this stage of violent expiratory efforts ends in general convulsions. The convulsions are due to stimulation of the respiratory centres by the venous blood. The convulsive stage is short, and is usually reached in a little over one minute. This storm is succeeded by—

3. The **third stage**, or stage of exhaustion, the transition being usually somewhat sudden. It is brought about by the venous blood acting on and paralyzing the respiratory centres. The pupils are widely dilated, consciousness is abolished, and the activity of the reflex centres is so depressed that it is impossible to discharge a reflex act, even from the cornea. The animal lies almost motionless, with flaccid muscles, and to all appearance dead, but every now and again, at long intervals, it makes a few deep inspiratory efforts, showing that the respiratory centres are not quite, but almost paralyzed. Gradually the pauses become longer and the inspirations feebler and of a gasping character. As the venous blood circulates in the spinal cord, it causes a large number of muscles to contract, so that the animal extends its trunk and limbs. It makes one great inspiratory spasm, the mouth being widely opened and the nostrils dilated, and ceases to breathe. After this stage, which is the longest and most variable, the heart becomes paralyzed, partly from being over-distended with venous blood, and partly, perhaps, from the action of the venous blood on the cardiac tissues, so that the pulse can hardly be felt. To this pulseless condition the term "asphyxia" ought properly to be applied. In connection with the resuscitation of asphyxiated persons, it is important to note that the heart continues to beat for a few seconds after the respiratory movements have ceased.

The whole series of phenomena occupies from 3 to 5 minutes, according to the animal operated on, and depending also upon the suddenness with which the trachea was closed. If the causes of suffocation act more slowly, the phenomena are the same, only they are developed more slowly.

The Circulation.—The *post-mortem* appearances in man or in an animal are generally well marked. The right side of the heart, the pulmonary artery, the venæ cavæ, and the veins of the neck are engorged with dark venous blood. The left side is comparatively empty, because the rigor mortis of the left side of the heart, and the elastic recoil of the systemic arteries, force the blood toward the systemic veins. The **blood** itself is almost black, and is deprived of almost all its oxygen, its hæmoglobin being nearly all in the condition of reduced hæmoglobin, while ordinary venous blood contains a considerable amount of oxyhæmoglobin as well as reduced Hb. The blood of an asphyxiated animal

practically contains none of the former and much of the latter. It is important to study the changes in the circulation in relation to phenomena exhibited by an animal during suffocation.

We may measure the blood pressure in any artery of an animal while it is being asphyxiated, or we may open its chest, maintain artificial respiration, and place a manometer in a systemic artery, *e. g.*, the carotid, and another in a branch of the pulmonary artery. In the latter case, we can watch the order of events in the heart itself, when the artificial respiration is interrupted. It is well to study the events in both cases.

If the **blood pressure** be measured in a systemic artery, *e. g.*, the carotid, it is found that the blood pressure rises very rapidly, and to a great extent during the first and second stages; the pulse beats at first are quicker, but soon become slower and more vigorous. During the third stage it falls rapidly to zero. The great rise of the blood pressure, during the first and second stages, is chiefly due to the action of the venous blood on the general vasomotor centre, causing constriction of the small systemic arteries. The peripheral resistance is thus greatly increased, and it tends to cause the heart to contract more vigorously, but the slower and more vigorous beats of the heart are also partly due to the action of the venous blood on the cardio-inhibitory centre in the medulla.

If the second method be adopted, viz., to open the chest, keep up artificial respiration, and measure the blood pressure in a branch of the pulmonary artery, as well as in a systemic artery—*e. g.*, the carotid—we find that when the artificial respiration is stopped, in addition to the rise of the blood pressure indicated in the carotid manometer, the cavities of the heart and the large veins near it are engorged with venous blood. There is, however, but a slight comparative rise in the blood pressure in the pulmonary artery. This may be accounted for, either by the pulmonary artery not being influenced to the same extent as other arteries by the vasomotor centre, or by its greater distensibility (§ 88). But, as the heart itself is supplied through the coronary arteries with venous blood, its action soon becomes weakened, each beat becomes feebler, so that soon the left ventricle ceases to contract, and is unable to overcome the great peripheral resistance in the systemic arteries, although the right ventricle may still be contracting. As the blood becomes more venous, the vasomotor centre becomes paralyzed, the small systemic arteries relax, and the blood flows from them into the veins, while the blood pressure in the carotid manometer rapidly falls. The left ventricle, now relieved from the great internal pressure, may execute a few feeble beats, but they can only be feeble, as its tissues have been subjected to the action of the very impure blood. More and more blood accumulates in the right side from the causes already mentioned. The violent inspiratory efforts in the early stages aspirate blood from the veins toward the right side of the heart, but of course this factor is absent when the chest is opened.]

[**Convulsions** during asphyxia occur only in warm-blooded animals, and not in frogs. If a drug when injected into a mammal excites convulsions, but does not do so in the frog, then it is usually concluded that the convulsions are due to its action on the circulation and respiration, and not to any direct stimulating effect upon the motor centres. But if the drug excites convulsions both in the mammal and frog, then it probably acts directly on the motor centres (*Brunton*).]

[**Recovery from the condition of Asphyxia.**—If the trachea of a dog be closed suddenly and completely, the average duration of the respiratory movements is 4 minutes 5 seconds, while the heart continues to beat for about 7 minutes. Recovery may be obtained if proper means be adopted before the heart ceases to beat; but after this, never. If a dog be drowned, the result is different. After complete submersion for 1½ minutes, recovery did not take place. In **drowning**, air passes out of the chest, and water is inspired into and fills the air vesicles. It is rare for recovery to take place in a person deprived of air for more than five minutes. If the statements of sponge divers are to be trusted, a person may become accustomed to the deprival of air for a longer time than usual. In cases where recovery takes place after a much longer period of

submersion, it has been suggested that, in these cases, syncope occurs, the heart beats but feebly or not at all, so that the oxygen in the blood is not used up with the same rapidity. It is a well-known fact that newly-born and young puppies can be submerged for a long time before they are suffocated.]

Artificial Respiration in Asphyxia.—In cases of suspended animation, *artificial respiration* must be performed. The first thing to be done is to remove any foreign substance from the respiratory passages (mucus or œdematous fluids) in the newly-born or asphyxiated. In doubtful cases, open the trachea and suck out any fluid by means of an elastic catheter (*v. Hüter*). Recourse must in all cases be had to artificial respiration. There are several methods of dilating and compressing the chest so as to cause an exchange of gases. One method is to compress the chest rhythmically with the hands.

[**Marshall Hall's Method.**—"After clearing the mouth and throat, place the patient on the face, raising and supporting the chest well on a folded coat or other article of dress. Turn the body very gently on the side and a little beyond, and then briskly on the face, back again, repeating these measures cautiously, efficiently, and perseveringly, about fifteen times in the minute, or once every four or five seconds, occasionally varying the side. By placing the patient on the chest, the weight of the body forces the air out; when turned on the side, this pressure is removed, and air enters the chest. On each occasion that the body is replaced on the face, make uniform but efficient pressure with brisk movement on the back between and below the shoulder blades or bones on each side, removing the pressure immediately before turning the body on the side. During the whole of the operations let one person attend solely to the movements of the head and of the arm placed under it."]

[**Sylvester's Method.**—"Place the patient on the back on the flat surface, inclined a little upward from the feet; raise and support the head and shoulders on a small firm cushion or folded article of dress placed under the shoulder-blades. Draw forward the patient's tongue, and keep it projecting beyond the lips; an elastic band over the tongue and under the chin will answer this purpose, or a piece of string or tape may be tied round them, or by raising the lower jaw the teeth may be made to retain the tongue in that position. Remove all tight clothing from about the neck and chest, especially the braces." "*To Imitate the Movements of Breathing.*—Standing at the patient's head grasp the arms just above the elbows, and draw the arms gently and steadily upward above the head, and *keep them stretched* upward for two seconds. By this means air is drawn into the lungs. Then turn down the patient's arms, and press them gently and firmly for two seconds against the sides of the chest. By this means air is pressed out of the lungs. Repeat these measures alternately, deliberately, and perseveringly about fifteen times in a minute, until a spontaneous effort to respire is perceived, immediately upon which cease to imitate the movements of breathing, and proceed to *induce circulation and warmth.*"]

Howard advises rhythmical compression of the chest and abdomen by sitting like a rider astride of the body, while Schüller advises that the lower ribs be seized from above with both hands and raised, whereby the chest is dilated, especially when the thigh is pressed against the abdomen to compress the abdominal walls. The chest is compressed by laying the hands flat upon the hypochondria. Artificial respiration acts favorably by supplying O to, as well as removing CO_2 from, the blood; further, it aids the movement of the blood within the heart and in the large vessels of the thorax. If the action of the heart has ceased, recovery is impossible. In asphyxiated newly-born children, we must not cease too soon to perform artificial respiration. Even when the result appears hopeless, we ought to persevere. Pflüger and Zuntz observed that the reflex excitability of the fœtal heart continued for *several* hours after the death of the mother.

Resuscitation by compressing the heart.—Böhm found that in the case of cats poisoned with potash salts or chloroform, or asphyxiated, so as to arrest respiration and the action of the heart—even for a period of forty minutes—and even when the pressure within the carotid had fallen to zero, he could restore animation by *rhythmical compression of the heart*, combined with artificial respiration. The compression of the heart causes a slight movement of the blood, while it acts at the same time as a rhythmical cardiac stimulus. After recovery of the respiration, the reflex excitability and gradually also voluntary movements are restored. The animals are blind for several days, the brain acts slowly, and the urine contains sugar. These experiments show how important it is in cases of asphyxia to act at the same time upon the heart.

For **physiological purposes**, artificial respiration is often made use of, especially after poisoning with curara. Air is *forced* into the lungs by means of an elastic bag or bellows, attached to a cannula tied in the trachea. The cannula has a small opening in the side of it to allow the expired air to escape.

Pathological.—After the lungs have once been properly distended with air, it is impossible by any amount of direct compression of them to get rid of all the air. This is probably due to the pressure acting on the small bronchi, so as to squeeze them, before the air can be forced out of the air vesicles. If, however, a lung be filled with CO_2, and be suspended in water, the CO_2 is absorbed by the water, and the lungs become quite free from air and are **atelectic** (*Hermann and Keller*). The atelectasis, which sometimes occurs in the lung, may thus be explained: If a bronchus is stopped with mucus or exudation, CO_2 accumulates in the air vesicles belonging to this bronchus. If the

CO_2 is absorbed by the blood or lymph, the corresponding area of the lung will become atelectic. Sometimes there is spasm of the respiratory muscles, brought about by direct or reflex stimulation of the respiratory centre.

135. RESPIRATION OF FOREIGN GASES.—No gas without a sufficient admixture of O can support life. Even with completely innocuous and indifferent gases, if no O be mixed with them, they cause suffocation in 2 to 3 minutes.

I. **Completely indifferent Gases** are N, H, CH_4. The living blood of an animal breathing these gases yields no O to them (*Pflüger*).

II. **Poisonous Gases.—O displacing Gases.**—(*a*) Those that displace O, and form a stable compound with the hæmoglobin (1) CO (§§ 16 and 17). (2) CNH (hydrocyanic acid) displaces (?) O from hæmoglobin, forming a more stable compound, and kills exceedingly rapidly. Blood corpuscles charged with hydrocyanic acid lose the property of decomposing hydric peroxide into water and O (§ 17, 5).

(*b*) **Narcotic Gases.**—(1) CO_2.—v. Pettenkofer characterizes atmospheric air containing .1 per cent. CO_2 as "bad air;" still, air in a room containing this amount of CO_2 produces a disagreeable feeling, rather from the impurities mixed with it than from the actual amount of CO_2 itself. Air containing 1 per cent. CO_2 produces decided discomfort, and with 10 per cent. it endangers life, while larger amounts cause death, with symptoms of coma. (2) N_2O (nitrous oxide), respired, mixed with $\frac{1}{3}$ volume O, causes, after 1 to 2 minutes, a short temporary stage of excitement ("Laughing gas" of H. Davy), which is succeeded by unconsciousness, and afterward by an increased excretion of CO_2. (3) Ozonized air causes similar effects (*Binz*).

(*c*) **Reducing Gases.**—(1) H_2S (sulphuretted hydrogen) rapidly robs blood corpuscles of O, S and H_2O being formed, and death occurs rapidly before the gas can decompose the hæmoglobin to form a sulphur-methæmoglobin compound.

(2) PH_3 (phosphuretted hydrogen) is oxidized in the blood to form phosphoric acid and water, with decomposition of the hæmoglobin.

(3) AsH_3 (arseniuretted hydrogen) and SbH_3 (antimoniuretted hydrogen) act like PH_3, but the hæmoglobin passes out of the stroma and appears in the urine.

(4) C_2N_2 (cyanogen) absorbs O, and decomposes the blood.

III. **Irrespirable Gases,** *i. e.*, gases which, on entering the larynx, cause reflex spasm of the glottis. When introduced into the trachea, they cause inflammation and death. Under this category come hydrochloric, hydrofluoric, sulphurous, nitrous, and nitric acids, ammonia, chlorine, fluorine, and ozone.

136. ACCIDENTAL IMPURITIES OF THE AIR.—Among these are **dust particles,** which occur in enormous amount suspended in the air, and thereby act injuriously upon the respiratory organs. The **ciliated epithelium** of the respiratory passages eliminates a large number of them (Fig. 148). Some of them, however, reach the air vesicles of the lung, where they penetrate the epithelium, reach the interstitial lung tissue and lymphatics, and so pass with the lymph stream into the bronchial glands. Particles of *coal* or *charcoal* are found in the lungs of all elderly individuals, and blacken the alveoli. In moderate amount, these black particles do not seem to do any harm in the tissues, but when there are large accumulations they give rise to lung affections, which lead to disintegration of these organs. [In coal miners, for example, the lung tissues along the track of the lymphatics and in the bronchial glands are quite black, constituting "coal miners' lung."]

FIG. 148.

Ciliated Epithelium.

In **many trades** various particles occur in the air; miners, grinders, stone masons, file makers, weavers, spinners, tobacco manufacturers, millers, and bakers suffer from lung affections caused by the introduction of particles of various kinds inhaled during the time they are at work.

Germs.—There seems no doubt that the seeds of some contagious diseases may be inhaled. Diphtheritic bacteria (Bacillus diphtheriæ) become localized in the pharynx and in the larynx—glanders in the nose—measles in the bronchi—whooping cough in the bronchi—hay monads in the nose—the Bacillus pneumoniæ of pneumonia in the pulmonary alveoli. Tuberculosis, according to R. Koch, is due to the introduction and development of the Bacillus tuberculosis in the lungs, the bacillus being derived from the dust of tuberculous sputa. The same seems to be the case with the Bacillus of leprosy and with Bacillus malariæ, which is the cause of malaria. The latter organism thus reaches the blood; it changes the Hb within the red blood corpuscles into melanin (§ 10, 3), and causes them to break up. The Micrococcus vaccinæ of smallpox gains

access to the blood in the same way, also the Spirillum of remittent fever (Fig. 23), the Microbe of scarlet fever, etc.

Seeds of disease passing into the mouth along with air, and also with the food, are swallowed, and undergo development in the intestinal tract, as is probably the case in cholera (Comma bacillus of *R. Koch*), dysentery, typhoid, and anthrax which is due to Bacterium anthracis (Fig. 24).

137. **VENTILATION OF ROOMS.**—**Fresh air** is as necessary for the healthy as for the sick. Every healthy person ought to have a cubic space of at the very least 800 cubic feet, and every sick person at the very least 1000 cubic feet of space. [The **cubic space** allowed per individual varies greatly, but 1000 cubic feet is a fair average. If the air in this space is to be kept sweet, so that the CO_2 does not exceed .06 per cent., 3000 cubic feet of air per hour must be supplied, *i. e.*, the air in the space must be renewed three times per hour.]

[**Floor Space.**—It is equally important to secure sufficient floor space, and this is especially the case in hospitals. If possible, 100–120 square feet of floor space ought to be provided for each patient in a hospital ward, and if it is obtainable a cubic space of 1500 cubic feet (*Parkes*). In all cases the minimum floor space should not be less than $\frac{1}{12}$ of the cubic space.]

Overcrowding.—When there is overcrowding in a room, the amount of CO_2 increases. v. Pettenkofer found the normal amount of CO_2 (.04 to .05 per 1000) increased in comfortable rooms to 0.54–0.7 per 1000; in badly ventilated sick chambers = 2.4; in overcrowded auditoriums, 3.2; in pits = 4.9; in school rooms, 7.2 per 1000. Although it is not the quantity of CO_2 which makes the air of an overcrowded room injurious, but the excretions from the outer and inner surfaces of the body, which give a distinct odor to the air, quite recognizable by the sense of smell, still the amount of CO_2 is taken as an index of the presence and amount of these other deleterious substances. Whether or not the ventilation of a room or ward occupied by persons is sufficient, is ascertained by estimating the amount of CO_2. A room which does not give a disagreeable, somewhat stuffy, odor has less than 0.7 per 1000 of CO_2, while the ventilation is certainly insufficient if the CO_2 = 1 per 1000. As the air contains only 0.0005 cubic metre CO_2 in 1 cubic metre of air, and as an adult produces *hourly* 0.0226 cubic metres CO_2, calculation shows that every person requires 113 cubic metres of fresh air per hour, if the CO_2 is not to exceed 0.7 per 1000; for $0.7 : 1000 = (0.0226 + x \times 0.0005) : x$, *i. e.*, $x = 113$.

[**Vitiating Products.**—In a state of repose, an adult man gives off from 12 to 16 cubic feet of CO_2 in twenty-four hours, or on an average .6 cubic feet per hour. To this must be added a certain quantity of **organic matter**, which is extremely deleterious to health. While the CO_2 diffuses readily and is easily disposed of by opening the windows, this is not the case with the organic matter, which adheres to clothing, curtains, and furniture; hence, to get rid of it, a room, and especially a sleeping apartment, requires to be well aired for a long time, together with the free admission of sunlight. We must also remember that an adult gives off from 25 to 40 oz. of **water** by the skin and lungs. The nature of the **organic matters** is not precisely known, but some of it is particulate, consisting of epithelium, fatty matters, and organic vapors from the lungs and mouth. It blackens sulphuric acid, and decolorizes a weak solution of potassic permanganate. As a test, if we expire through distilled water, and this water be set aside for some time in a warm place, it will soon become fœtid. We must also take into consideration the **products of combustion**; thus 1 cubic foot of coal gas, when burned, destroys all the O in 8 cubic feet of air (*Parkes*).]

Methods.—In ordinary rooms, where every person is allowed the necessary cubic space (1000 cubic feet), the air is sufficiently renewed by means of the pores in the walls of the room, by the opening and shutting of doors, and by the fireplace, provided the damper is kept open. It is most important to notice that the natural ventilation be not interfered with by dampness of the walls, for this influences the pores very greatly. At the same time, damp walls are injurious to health by conducting away heat, and in them the germs of infectious diseases may develop.

[**Natural Ventilation.**—By this term is meant the ventilation brought about by the ordinary forces acting in nature; such as diffusion of gases, the action of winds, and the movements excited owing to the different densities of air at unequal temperatures.]

[**Artificial Ventilation.**—Various methods are in use for ventilating public buildings and dwelling houses. Two principles are adopted for the former, viz., **extraction** and **propulsion of air.** In the former method, the air is sucked out of the rooms by a fan or other apparatus, while in the latter, air is forced into the rooms, the air being previously heated to the necessary temperature.]

[A very convenient method of introducing air into a room is by means of **Tobin's tubes**, placed in the walls. The air enters through these tubes from the outside near the floor, and is carried up six or more feet, to an opening in the wall; the cool air thus descends slowly. For a sitting room, a convenient plan of window ventilation is **H. Bird's Method**: Raise the lower sash and place under it, so as to fill up the opening, a piece of wood 3 or 4 inches high. Air will then pass in, in an upward direction, between the upper part of the lower sash frame and the lower part of the upper one.]

MATION OF MUCUS—SPUTUM.—The respiratory mucous
·red normally with a thin layer of mucus (Fig. 130, *a*). It so
ıation of new mucus by protecting the mucous glands from the

action of cold or other irritative agents. New mucus is secreted as that already formed is removed. An increased secretion accompanies congestion of the respiratory mucous membrane [or any local irritation]. Division of the nerves on one side of the trachea (cat) causes redness of the tracheal mucous membrane and increased secretion (*Rossbach*), [but the two processes do not stand in the relation of cause and effect]. [The secretion cannot be excited by stimulating the nerves going to the mucous membrane. This merely causes anæmia of the mucous membrane, while the secretion continues].

Modifying Conditions.—If ice be placed on the belly of an animal so as to cause the animal "*to take a cold*," the respiratory mucous membrane first becomes pale, and afterward there is a copious mucous secretion, the membrane becoming deeply congested. The injection of sodium carbonate and ammonium chloride into the blood limits the secretion. The local application of alum, silver nitrate, or tannic acid, makes the mucous membrane turbid, and the epithelium is shed. The secretion is excited by apomorphin, emetin, pilocarpin, and ipecacuanha when given internally, while it is limited by atropin and morphia (*Rossbach*).

FIG. 149.



Various objects found in sputum. 1, detritus and particles of dust; 2, alveolar epithelium with pigment; 3, fatty and pigmented alveolar epithelium; 4, alveolar epithelium with myelin-forms; 5, free myelin-forms; 6, 7, ciliated epithelium, some without cilia; 8, squamous epithelium from the mouth; 9, leucocytes; 10, elastic fibres; 11, fibrin cast of a small bronchus; 12, leptothrix buccalis with cocci, bacteria, and spirochætae; *a*, fatty acid crystals and free fatty granules; *b*, hæmatoidin; *c*, Charcot's crystals; *d*, cholesterin.

[**Expectorants** favor the removal of the secretions from the air passages. This they may do either by (*a*) altering the character and qualities of the secretion itself, or (*b*) by affecting the expulsive mechanism. Some of the drugs already mentioned are examples of the first class. The second class act chiefly by influencing the respiratory centre, *e. g.*, ipecacuanha, strychnia, ammonia, senega; emetics also act energetically as expectorants, as in some cases of chronic bronchitis; warmth and moisture in the air are also powerful adjuncts.]

Sputum.—Under normal circumstances, some mucus—mixed with a little saliva—may be coughed up from the back of the throat. In catarrhal conditions of the respiratory mucous membrane, the sputum is greatly increased in amount, and is often mixed with other characteristic products. **Microscopically**, sputum contains—

1. **Epithelial Cells**, chiefly squames from the mouth and pharynx (Fig. 149), more rarely alveolar epithelium and ciliated epithelium (7) from the respiratory

passages. They are often altered owing to maceration or other changes. Thus some cells may have lost their cilia (6).

The **epithelium of the alveoli** (2) is squamous epithelium, the cells being two to four times the breadth of a colorless blood corpuscle. These cells occur chiefly in the morning sputum in individuals over 30 years of age. In younger persons their presence indicates a pathological condition of the pulmonary parenchyma.

They often undergo fatty degeneration, and they may contain pigment granules (3); or they may present the appearance of what Buhl has called "*myelin degenerated cells*," *i. e.*, cells filled with clear refractive drops of various sizes, some colorless, others with colored particles, the latter having been absorbed (4). Mucin in the form of myelin drops (5) is always present in sputum.

2. **Lymphoid cells** (9) are colorless blood corpuscles which have wandered out of the blood vessels; they are most numerous in yellow sputum, and less numerous in the clear, mucus-like excretion. The lymph cells often present alterations in their characters; they may be shriveled up, fatty, or present a granular appearance.

The **fluid substance** of the sputum contains much **mucus**, arising from the mucous glands and goblet cells, together with nuclein, and lecithin, and the constituents of saliva, according to the amount of the latter mixed with the secretion. *Albumin* occurs only during the inflammation of the respiratory passages, and its amount increases with the degree of inflammation. Urea has been found in cases of nephritis.

In cases of **catarrh**, the sputum is at first usually sticky and clear (sputa cruda), but later it becomes more firm and yellow (sputa cocta). Under **pathological conditions**, there may be found in the sputum—(*a*) red **blood corpuscles** from rupture of a blood vessel. (*b*) **Elastic fibres** (10) from disintegration of the alveoli of the lung; usually the bundles are fine, curved, and the fibres branched. [In certain cases it is well to add a solution of caustic potash, which dissolves most of the other elements, leaving the elastic fibres untouched.] Their presence always indicates destruction of the lung tissue. (*c*) Colorless plugs of **fibrin** (11), casts of the smaller or larger bronchi, occur in some cases of fibrinous exudation into the finer air passages. (*d*) **Crystals** of various kinds—crystals of *fatty acids* in bundles of fine needles (Fig. 149, *a*). They indicate great decomposition of the stagnant secretion. Leucin and tyrosin crystals are rare (§ 269). Tyrosin occurs in considerable amount when an old abscess breaks into the lungs. Colorless, sharp pointed, octagonal or rhombic plates—**Charcot's crystals** (*c*)—have been found in the expectoration in asthma, and exudative affections of the bronchi. **Hæmatoidin** (*b*) and **cholesterin** crystals (*d*) occur much more rarely.

Fungi and **other lowly organisms** are taken in during inspiration (§ 136). The threads of Leptothrix buccalis (12), detached from the teeth, are frequently found (§ 147). Mycelium and spores are found in thrush (Oïdium albicans), especially in the mouths of sucking infants. In malodorous expectoration rod-shaped bacteria are present. In pulmonary gangrene are found monads, and cercomonads; in pulmonary phthisis the tubercle bacillus; very rarely sarcina, which, however, is often found in gastric catarrh in the stomach and also in the urine (§ 270).

Physical Characters.—Sputum, with reference to its physical characters, is described as *mucous*, *muco-purulent*, or *purulent*.

Abnormal coloration of the sputum—red from blood; when the blood remains long in the lung it undergoes a regular series of changes, and tinges the sputum dark red, bluish brown, brownish yellow, deep yellow, yellowish green, or grass green. The sputum is sometimes yellow in jaundice. The sputum may be tinged by what is inspired [as in the case of the "black spit" of miners].

The odor of the sputum is more or less unpleasant. It becomes very disagreeable when it has remained long in pathological lung cavities, and it is stinking in gangrene of the lung.

139. **ACTION OF THE ATMOSPHERIC PRESSURE.**—At the normal pressure of the atmosphere (height of the barometer, 760 millimetres Hg), pressure is exerted upon the entire surface of the body = 15,000 to 20,000 kilos., according to the extent of the superficial area. This pressure acts equally on all sides upon the body, and also occurs in all *internal cavities containing air*, both those that are constantly filled with air (the respiratory passages and the spaces in the superior maxillary, frontal, and ethmoid bones), and those that are temporarily in direct communication with the outer air (the digestive tract and tympanum). As the **fluids of the body** (blood, lymph, secretions, parenchymatous juices) are practically incompressible, their volume remains unchanged under the pressure;

but they absorb gases from the air corresponding to the prevailing pressure (*i. e.*, the partial pressure of the individual gases), and according to their temperature (§ 33). The **solids** consist of elementary parts (cells and fibres), each of which presents only a microscopic surface to the pressure, so that for each cell the prevailing pressure of the air can only be calculated at a few millimetres—a pressure under which the most delicate histological tissues undergo development. As an example of the action of the pressure of the atmospheric pressure upon large masses, take that brought about by the adhesion of the smooth, sticky, moist, articular surfaces of the shoulder and hip joints; the arm and the leg are supported without the action of muscles. The thigh bone remains in its socket after section of all the muscles and its capsule. Even when the cotyloid cavity is perforated, the head of the femur does not fall out of its socket. The ordinary barometric variations affect the respiration—a rise of the barometric pressure excites, while a fall diminishes, the respirations. The absolute amount of CO_2 remains the same (§ 127, 8).

Great diminution of the atmospheric pressure, such as occurs in ballooning (highest ascent, 8600 metres), or in ascending mountains, causes a series of characteristic phenomena: (1) In consequence of the diminution of the pressure upon the parts directly in contact with the air, they become greatly congested, hence there is redness and swelling of the skin and free mucous membranes; there may be hemorrhage from the nose, lungs, gums; turgidity of the cutaneous veins; copious secretion of sweat; great secretion of mucus. (2) A feeling of weight in the limbs, a pressing outward of the tympanic membrane (until the tension is equilibrated by opening the Eustachian tube), and as a consequence noises in the ears and difficulty of hearing. (3) In consequence of the diminished tension of the O in the air (§ 129), there is difficulty of breathing, pain in the chest, whereby the respirations (and pulse) become more rapid, deeper, and irregular. When the atmospheric pressure is diminished ½–⅓, the amount of O in the blood is diminished, the CO_2 is imperfectly removed from the blood, and in consequence there is diminished oxidation within the body. When the atmospheric pressure is diminished to one-half, the amount of CO_2 in arterial blood is lessened; and the amount of N diminishes proportionally with the decrease of the atmospheric pressure. The diminished tension of the air prevents the vibrations of the vocal cords from occurring so forcibly, and hence the voice is feeble. (4) In consequence of the amount of blood in the skin, the internal organs are relatively anæmic; hence, there is diminished secretion of urine, muscular weakness, disturbances of digestion, dullness of the senses, and it may be unconsciousness, and all these phenomena are intensified by the conditions mentioned under (3). Some of these phenomena are modified by usage. The highest limit at which a man may still retain his senses is placed by Tissandier at an elevation of 8000 metres (280 mm. Hg). In dogs the blood pressure falls, and the pulse becomes small and diminished in frequency, when the atmospheric pressure falls to 200 mm. Hg.

Those who live upon high mountains suffer from a disease "**mal de montagne,**" which consists essentially in the above symptoms, although it is sometimes complicated with anæmia of the internal organs. Al. v. Humboldt found that in those who lived on the Andes the thorax was capacious. At 6000 to 8000 feet above sea level, water contains only one-third of the absorbed gases, so that fishes cannot live in it. Animals may be subjected to a further diminution of the atmospheric pressure by being placed under the receiver of an air pump. Birds die when the pressure is reduced to 120 mm. Hg; mammals at 40 mm. Hg; frogs endure repeated evacuations of the receiver, whereby they are much distended, owing to the escape of gases and water, but after the entrance of air they become greatly compressed. The cause of death in mammals is ascribed by Hoppe-Seyler to the evolution of bubbles of gas in the blood; these bubbles stop up the capillaries, and the circulation is arrested. *Local diminution of the atmospheric pressure* causes marked congestion and swelling of the part, as occurs when a cupping glass is used.

Great increase of the atmospheric pressure causes phenomena, for the most part, the reverse of the foregoing, as in pneumatic cabinets and in diving bells, where men may work even under 4½ atmospheres pressure. (1) Paleness and dryness of the external surfaces, collapse of the cutaneous veins, diminution of perspiration, and mucous secretions. (2) The tympanic membrane is pressed inward (until the air escapes through the Eustachian tube, after causing a sharp sound), acute sounds are heard, pain in the ears, and difficulty of hearing. (3) A feeling of lightness and freshness during respiration, the respiration becomes slower (by 2–4 per minute), inspiration easier and shorter, expiration lengthened, the pause distinct. The capacity of the lungs increases, owing to the freer movement of the diaphragm, in consequence of the diminution of the intestinal gases. Owing to the more rapid oxidations in the body, muscular movement is easier and more active. The O absorbed and the CO_2 excreted are increased. The venous blood is reddened. (4) Difficulty of speaking, alteration of the tone of the voice, inability to whistle. (5) Increase of the urinary secretion, more muscular energy, more rapid metabolism, increased appetite, subjective feeling of warmth, pulse beats slower, and pulse curve is lower (compare § 74). In animals subjected to

excessively high atmospheric pressure, P. Bert found that the arterial blood contained 30 vols. per cent. O (at 760 mm. Hg); when the amount rose to 35 vol. per cent., death occurred with convulsions. Compressed air has been used for therapeutical purposes, but in doing so a too rapid increase of the pressure is to be avoided. Waldenburg has constructed such an apparatus, which may be used for the respiration of air under a greater or less pressure.

Frogs, when placed in compressed O (at 14 atmospheres), exhibit the same phenomena as if they were in a vacuum, or pure N. There is paralysis of the central nervous system, sometimes preceded by convulsions. The heart ceases to beat (not the lymph hearts), while the excitability of the motor nerves is lost at the same time, and lastly the direct muscular excitability disappears. An excised frog's heart placed in O under a very high pressure (13 atmospheres), scarcely beats one-fourth of the time during which it pulsates in air. If the heart be exposed to the air again, it begins to beat, so that compressed O renders the vitality of the heart latent before abolishing it.

Phosphorus retains its luminosity under a high pressure in O, but this is not the case with the luminous organisms, *e. g.*, Lampyris, and luminous bacteria. High atmospheric pressure is also injurious to plants.

140. **COMPARATIVE AND HISTORICAL.**—**Mammals** have lungs similar to those of man. The lungs of **birds** are spongy, and united to the chest wall, while there are openings on their surface communicating with thin-walled "**air-sacs**," which are placed among the viscera. The air sacs communicate with cavities in the bones, which give the latter great lightness. The diaphragm is absent. In **reptiles** the lungs are divided into greater and smaller compartments; in snakes one lung is abortive, while the other has the elongated form of the body. The **amphibians** (frog) possess two simple lungs, each of which represents an enormous infundibulum with its alveoli. The frog pumps air into its lungs by the contraction of its throat, the nostrils being closed and the glottis opened. When young—until their metamorphosis—frogs breathe like fishes by means of gills. The perennibranchiate amphibians (Proteus) retain their gills throughout life. Among **fishes**, which breathe by gills and use the O absorbed by the water, the Dipnoi have in addition to gills a swim bladder provided with afferent and efferent vessels, which is comparable to the lung. The Cobitis respires also with its intestine. **Insects** and centipedes respire by "tracheæ," which are branched canals distributed throughout the body; they open on the surface of the body by openings (stigmata) which can be closed. Spiders respire by means of tracheæ and tracheal sacs, crabs by gills. The mollusks and cephalopods have gills; some gasteropods have gills and others lungs. Among the lower invertebrata some breathe by gills, others by means of a special "water vascular system," and others again by no special organs.

Historical.—Aristotle (384 B.C.) regarded the object of respiration to be the cooling of the body, so as to moderate the internal warmth. He observed correctly that the warmest animals breathe most actively, but in interpreting the fact he reversed the cause and effect. Galen (131–203 A.D.) thought that the "soot" was removed from the body along with the expired water. The most important experiments on the mechanics of respiration date from Galen; he observed that the lungs passively follow the movements of the chest; that the diaphragm is the most important muscle of inspiration; that the external intercostals are inspiratory; and the internal, expiratory. He divided the intercostal nerves and muscles, and observed that loss of voice occurred. On dividing the spinal cord higher and higher, he found that as he did so the muscles of the thorax lying higher up became paralyzed. Oribasius (360 A.D.) observed that in double pneumothorax both lungs collapsed. Vesalius (1540) first described artificial respiration as a means of restoring the beat of the heart. Malpighi (1661) described the structure of the lungs. J. A. Borelli († 1679) gave the first fundamental description of the mechanism of the respiratory movements. The **chemical** processes of respiration could only be known after the discovery of the individual gases therein concerned. Van Helmont († 1644) detected CO_2. [Joseph Black (1757) discovered that CO_2, or "fixed air," is given out during expiration.] In 1774 Priestley discovered O. Lavoisier detected N (1775), and ascertained the composition of atmospheric air, and he regarded the formation of CO_2 and H_2O of the breath as a result of a combustion within the lungs themselves. J. Ingen-Houss (1730–1799) discovered the respiration of plants. Vogel and others proved the existence of CO_2 in venous blood, and Hoffmann and others that of O in arterial blood. The more complete conception of the exchange of gases was, however, only possible after Magnus had extracted and analyzed the gases of arterial and venous blood (§ 36).

PHYSIOLOGY OF DIGESTION.

141. **THE MOUTH AND ITS GLANDS.**—The **mucous membrane** of the cavity of the mouth, which becomes continuous with the skin at the red margin of the lips, has a number of **sebaceous glands** in the region of the red part of the lip. The buccal mucous membrane consists of bundles of fine fibrous tissue mixed with elastic fibres, which traverse it in every direction. **Papillæ**—simple or compound—occur near the free surfaces. The **submucous tissue**, which is directly continuous with the fibrous tissue of the mucous membrane itself, is thickest where the mucous membrane is thickest, and densest where it is firmly fixed to the periosteum of the bone

FIG. 150.

Cells of stratified squamous epithelium detached from the mouth. *s*, salivary corpuscles.

FIG. 151.

Section of a mucous follicle from the tongue.

and to the gum; it is thinnest where the mucous membrane is most movable, and where there are most folds. The cavity of the mouth is lined by **stratified squamous epithelium** (Fig. 150), which is thickest, as a rule, where the longest papillæ occur.

All the glands of the mouth, including the salivary glands, may be divided into different classes, according to the nature of their secretions.

1. The **serous** or **albuminous** glands [**true salivary**], whose secretion contains a certain amount of albumin, *e. g.*, the human parotid.

2. The **mucous** glands, whose secretion, in addition to some albumin, contains the characteristic constituent mucin.

3. The **mixed** [or **muco-salivary**] glands, some of the acini secreting an albuminous fluid and others mucin, *e. g.*, the human maxillary gland.

Numerous **mucous glands** (labial, buccal, palatine, lingual, molar) have the appearance of small macroscopic bodies lying in the sub-mucosa. They are **branched tubular glands**, and the contents of their secretory cells consist partly of mucin, which is expelled from them during secretion. The excretory ducts of these glands, which are lined by cylindrical epithelium, are constricted where they enter the mouth. Not unfrequently one duct receives the secretion of a neighboring gland.

The **glands of the tongue** form two groups, which differ morphologically and physiologically. (1) The **mucous glands** (*Weber's* glands), occurring chiefly near the root of the tongue, are

branched tubular glands lined with clear, transparent, secretory cells whose nuclei are placed near the attached end of the cells. The acini have a distinct membrana propria. (2) The **serous glands** (*Ebner's*) are acinous glands occurring in the region of the circumvallate papillæ (and in animals near the papillæ foliatæ). They are lined with turbid granular epithelium with a central nucleus, and secrete saliva. (3) The glands of Blandin and Nuhn are placed near the tip of the tongue, and consist of mucous and serous acini, so that they are mixed glands (*Podwisotzky*).

The **blood vessels** are moderately abundant, and the larger trunks lie in the sub-mucosa, while the finer twigs penetrate into the papillæ, where they form either a capillary network or simple loops.

The larger **lymphatics** lie in the sub-mucosa, while the finer branches form a fine network placed in the mucosa. The **lymph follicles** also belong to the lymphatic system (§ 197). On the dorsum of the posterior part of the tongue they form an almost continuous layer. They are round or oval (1–1.5 mm. in diameter), lying in the sub-mucosa, and consist of adenoid tissue loaded with lymph corpuscles. The outer part of the adenoid reticulum is compressed so as to form a kind of capsule for each follicle. Similar follicles occur in the intestine as solitary follicles; in the small intestine they are collected together into Peyer's patches, and in the spleen they occur as Malpighian corpuscles. On the **dorsum of the tongue** several of these follicles form a slightly oval elevation, which is surrounded by connective tissue. In the centre of this elevation there is a depression, into which a mucous gland opens, which fills the small crater with mucus (Fig. 151).

The **tonsils** have fundamentally the same structure. On their surface are a number of depressions into which the ducts of small mucous glands open. These depressions are surrounded by groups (10–20) of lymph follicles, and the whole is environed by a capsule of connective tissue (Fig. 152). Large lymph spaces, communicating with lymphatics, occur in the neighborhood of the tonsils, but as yet a direct connection between the spaces in the follicles and the lymph vessels has not been proved to exist. Similar structures occur in the **tubal and pharyngeal tonsils.** [Stöhr asserts that an enormous number of leucocytes wander out of the tonsils, solitary and Peyer's glands, and the adenoid tissue of the bronchial mucous membrane. The cells pass out between the epithelial cells, but do not pass into the interior of the latter.]

Nerves.—Numerous *medullated* nerve fibres occur in the sub-mucosa, pass into the mucosa, and terminate partly in the individual papillæ in Krause's end bulbs, which are most abundant in the lips and soft palate, and not so numerous in the cheeks and floor of the mouth. The nerves administer not only to common sensation, but they are also the organs of transmission for tactile (heat and pressure) impressions. It is highly probable, however, that some nerve fibres end in fine terminal fibrils, between the epithelial cells, as in the cornea and elsewhere.

FIG. 152.



Vertical section of a human tonsil, × 20. 1, cavity; 2, epithelium infiltrated with leucocytes below and on the left, but free on the right; 3, adenoid tissue with sections *a*, *b*, *c*, of masses of it; 4, fibrous sheath; 5, section of a gland duct; *d*, blood vessel.

[**Secretory glands** may be simple (Fig. 153, B, C, D) or compound (E). In the latter case the duct is branched. In the process of development, a solid process of the epithelium sinks into the subjacent fibrous tissue, and, to form a simple gland, a cavity appears in this bud, but for a compound gland, other epithelial buds sprout from its blind end. Each bud acquires a central cavity, these elongate and increase in number, thus forming a much branched system, the terminal blind ends forming the **acini, alveoli** or true secretory part. If the alveoli are tubular in shape, the gland is called a compound tubular gland. Thus in the compound glands some parts are secretory, and others act as ducts, while in the simple glands, all the parts may be secretory. All the glands opening on the surface of the body are of epiblastic origin. The secretory cells lining the acini rest on a basement membrane, and outside this are the lymph spaces and capillary blood vessels.]

142. **THE SALIVARY GLANDS.**—The **three pairs** of salivary glands, **sub-maxillary, sublingual,** and **parotid,** are compound tubular glands. Fig. 155, A, shows a fine duct, terminating in the more or less flask-shaped alveoli or acini. [Each gland consists of a number of **lobes,** and each lobe in turn of a number of **lobules,** which, again, are composed of **acini.** All these are held together by a **framework** of connective tissue. The larger branches of the **duct** lie between the lobules, and constitute the **interlobular** ducts, giving branches to each lobule which they enter, constituting the **intralobular** ducts, which branch and finally terminate in connection with the alveoli, by means of an **intermediary** or **intercalary** part. The larger interlobar and interlobular ducts consist of a membrana propria, strengthened outside with fibrous and elastic tissue, and in some places also by non-striped muscle, while the ducts are lined by columnar epithelial cells. In the largest branches, there is a second row of smaller cells, lying between the large cells and the membrana propria. The **intralobular ducts** are lined by a single layer of large cylindrical epithelium with the nucleus about the middle of the cell, while the outer half of the cell is finely striated longitudinally, or "rodded," which is due to fibrillæ (Fig. 154); the inner half next the lumen is granular. The **intermediary part** is narrow, and is lined by a single layer of flattened cells, each with an elongated oval nucleus. There is usually a narrow "neck," where the intralobular duct becomes continuous with the intermediary part, and here the cells are polyhedral.]

FIG. 153.



Evolution of glands. A, schema of skin; *ep*, epidermis; *d*, cutis with a capillary *c*; B, simple gland with its blood vessels; C, D, more complex glands; E, compound gland, blood vessels omitted.

FIG. 154.

Rodded epithelium lining the duct of a salivary gland.

FIG. 155.



A, duct and acini of the parotid gland of a dog; B, acini of the sub-maxillary gland of a dog; *c*, refractive mucous cells; *d*, granular half-moons of Gianuzzi; C, similar alveoli after prolonged secretion; D, basket-shaped tissue investment of an acinus; F, entrance of a non-medullated nerve fibre into a secretory cell.

The **acini,** or **alveoli,** are the parts where the actual process of secretion takes place. They vary somewhat in shape—some are tubular, others branched, some are dilated and resemble a

Florence flask, and several of them usually open into one intermediary part of a duct. Each alveolus is bounded by a basement membrane, with a reticulate structure made up of nucleated, branched, and anastomosing cells so as to resemble a basket (D). There is a homogeneous membrane bounding the alveoli in addition to this basket shaped structure. Immediately outside this membrane is a lymph space, and outside this again the network of capillaries is distributed. [The extent to which this lymph space is filled with lymph determines the distance of the capillaries from the membrana propria. The inter-alveolar lymph spaces communicate with large lymph spaces between the lobules, which in turn communicate with perivascular lymphatics around the arteries and veins.] The lymphatics emerge from the gland at the hilum.

The **secretory cells** vary in structure, according as the salivary gland is a **mucous** [sub-maxillary and sublingual of the dog and cat], a **serous** [parotid of man and mammals, and sub-maxillary of rabbit], or **mixed** gland [human sub-maxillary and sublingual].

Mucous Acini.—The secretory cells of mucous glands, and the mucous acini of mixed glands (Fig. 156), are lined by a single layer of "**mucin cells**" (Fig. 155, B, *c*), which are large cells distended with mucin, or with a hypothetical substance, **mucigen**, which yields mucin. The mucin cells are more or less spheroidal in shape, clear, shining, highly refractive, and nearly fill the acinus. The flattened nucleus is near the wall of the acinus. Each cell has a fine process which overlaps the fixed parts of the cell next to it. Owing to the body of each cell being infiltrated with mucin, these cells do not stain with carmine, although the nucleus and its immediately investing protoplasm do. Another kind of cell occurs in the sub-maxillary gland of the dog. It forms a half-moon shaped *structure* lying in direct contact with the wall of the acinus (*Gianuzzi*). Each "**half-moon**" or "**crescent**" consists of a number of small, closely packed, angular, highly albuminous cells with small oval nuclei, which, however, are separated only with difficulty. Hence, Heidenhain has called them "**composite marginal cells**" (B, *d'*). They are granular, darker, devoid of mucin, and stain readily with pigments. [In the sub-maxillary gland of the cat, there is a complete layer of these "marginal" carmine-staining cells lying between the mucous cells and the membrana propria.]

FIG. 156.

Section of a human sub-maxillary gland. On the left is a group of serous alveoli, and on the right a group of mucous alveoli.

[**Serous Acini.**—In true serous glands (parotid of man and mammals) and in the serous acini of mixed glands, the acini are lined by a single layer of secretory columnar finely-granular cells, which in the quiescent condition completely fill the acinus, so that scarcely any lumen is left. Just before secretion, or when these cells are quiescent, Langley has shown that they are large and filled with numerous granules, which obscure the presence of the nucleus. As secretion takes place, these granules seem to be used up or discharged into the lumen; at least, the outer part of each cell gradually becomes clear and more transparent, and this condition spreads toward the inner part of the cell.]

[In the **mixed** or **muco-salivary** glands (*e.g.*, human sub-maxillary) some of the alveoli are mucous and others serous in their characters, but the latter are always far more numerous, and the one kind of acinus is directly continuous with the others (Fig. 156).]

143. HISTOLOGICAL CHANGES DURING THE ACTIVITY OF THE SALIVARY GLANDS.—[The condition of physiological activity of the gland cells is accompanied by changes in the histological characters of the secretory cells. Changes in **serous glands** have been carefully studied in the parotid of the rabbit, but the appearances vary somewhat, according as the glands are examined in the fresh condition or after hardening in various reagents, such as absolute alcohol. When the gland is at **rest**, in a preparation hardened in alcohol, and stained with carmine, the cells consist of a pale, almost uncolored substance, with a few fine granules, and a small, irregular, red-stained, shriveled nucleus

devoid of a nucleolus. The appearance of the nucleus suggests the idea of its being shriveled by the action of the hardening reagent (Fig. 157).]

[**During activity,** if the gland be caused to secrete by stimulating the sympathetic, all parts of the cells undergo a change (Figs. 157, 158). In preparations **hardened in alcohol** (1) the cells diminish somewhat in size; (2) the nuclei are no longer irregular, but round, with a sharp contour and nucleoli; (3) the substance of the cell itself is turbid owing to the diminution of the clear substance, and the increase of the granules, especially near the nuclei; (4) at the same time, the whole cell stains more deeply with carmine (*Heidenhain*).]

[On studying the changes which occur in a **living serous gland,** Langley found that the substance of the cells of the parotid is pervaded by fine granules, which are so numerous as to obscure the nucleus, while the outlines of the cells are indistinct. No lumen is visible in the acini during **activity,** the granules disappear from the outer zone of the cells, the cells themselves becoming smaller and more distinct. After prolonged secretion the granules largely disappear from the cell substance except quite near the inner margin. The cells are smaller, their outlines more distinct, their spherical nuclei apparent, and the lumen of the acini is wide and distinct. Thus, it is evident that, during rest, granules are manufactured, which disappear during the activity of the cells, the disappearance taking place from without inward. Similar changes occur in the cells of the pancreas.]

FIG. 157.

FIG. 158.



Sections of a "serous" gland. The parotid of a rabbit, Fig. 157, at rest; Fig. 158, after stimulation of the cervical sympathetic.

[More complex changes occur in the **mucous glands,** such as the sub-maxillary or orbital glands of the dog (*Lavdovsky*). The appearances vary according to the intensity and duration of the secretory activity. The mucous cells at **rest** are large, clear, and refractive, containg a flattened nucleus (Fig. 155, C), surrounded with a small amount of protoplasm, and placed near the basement membrane. The clear substance does not stain with carmine, and consists of mucigen lying in the wide spaces of an intracellular plexus of fibrils. After **prolonged secretion,** produced, it may be, by strong and continued stimulation of the chorda, the mucous cells of the sub-maxillary gland of the dog undergo a great change.] The distended, refractive, and "mucous cells," which occur in the quiescent gland, and which do not stain with carmine, do not appear after the gland has been in a state of activity. Their place is taken by small, dark, protoplasmic cells devoid of mucin (Fig. 155, C). These cells readily stain with carmine, while their nucleus is scarcely, if at all, colored by the dye. The researches of R. Heidenhain (1868) have shed much light on the secretory activity of the salivary glands.

The change may be produced in two ways. Either it is due to the "mucous cells" during secretion becoming broken up, so that they yield their mucin directly to the saliva; in saliva rich in mucin, small microscopic pieces of mucin are found, and sometimes mucous cells themselves are present. Or, we must assume that the mucous cells simply eliminate the mucin from their bodies (*Ewald, Stöhr*); while, after a period of rest, new mucin is formed. According to this view, the dark granular cells of the glands, after active secretion, are simply mucous cells, which have given out their mucin. If we assume, with Heidenhain, that the mucous cells break up, then these granular non-mucous cells must be regarded as new formations produced by the proliferation and growth of the composite marginal cells, *i. e.*, the crescents, or half-moons of Gianuzzi.

[During rest, the protoplasm seems to manufacture **mucigen**, which is changed into and discharged as mucin in the secretion, when the gland is actively secreting. Thus, the cells become smaller, but the protoplasm of the cell seems to increase, new mucigen is manufactured during rest, and the cycle is repeated.]

144. THE NERVES OF THE SALIVARY GLANDS.—The nerves are for the most part medullated, and enter at the hilum of the gland, where they form a rich plexus provided with **ganglia** between the lobules. [There are no ganglia in the parotid gland (*Klein*).]

All the salivary glands are supplied by branches from two different nerves—from the sympathetic and from a cranial nerve.

FIG. 159.



Scheme of the nerves of the salivary glands. P., pons; M. O., medulla oblongata; J. N., nerve of Jacobson; O., S. M., I. M., ophthalmic, superior, and inferior maxillary divisions of fifth nerve, V.; VII., seventh nerve; S.s.p., small superficial petrosal nerve; Vag., vagus; Sym., sympathetic; O. G., otic, and S. G., sub-maxillary ganglia; P., S., and S. L., parotid, sub-maxillary, and sublingual glands: T., tongue.

1. The **sympathetic** nerve gives branches (*a*) to the sub-maxillary and the sublingual glands, derived from the plexus on the external maxillary artery; (*b*) to the parotid gland from the carotid plexus (Fig. 159).

2. The **facial** nerve gives branches to the sub-maxillary and sublingual glands from the chorda tympani, which accompanies the lingual branch of the fifth nerve (Fig. 159). The branches to the parotid arise from the tympanic branch of the **glosso-pharyngeal** nerve (dog). The tympanic plexus sends fibres to the small superficial petrosal nerve, and with it these fibres run to the anterior surface of the pyramid in the temporal bone, emerging from the skull through a fissure between the petrous and great wing of the sphenoid, and then joining the otic ganglion. This ganglion sends branches to the auriculo-temporal nerve (itself derived from the third branch of the trigeminus), which, as it passes upward to the temporal region under cover of the parotid, gives branches to this gland.

The **sub-maxillary ganglion**, which gives branches to the sub-maxillary and sublingual glands, receives fibres from the tympanico-lingual nerve (chorda

tympani) as well as sympathetic fibres from the plexus on the external maxillary artery.

Termination of the Nerve Fibres.—With regard to the ultimate distribution of these nerves we can distinguish (1) the **vasomotor nerves**, which give branches to the walls of the blood vessels, and (2) the **secretory nerves** proper.

Pflüger states, with regard to the latter, that (*a*) medullated nerve fibres penetrate the acini; the sheath of Schwann unites with the membrana propria of the acinus; the medullated fibre—still medullated—passes between the secretory cells, where it divides and becomes non-medullated, and its axial cylinder terminates in connection with the nucleus of a secretory cell. [This, however, is not proved] (Fig. 155, F). (*b*) According to Pflüger, some of the nerve fibres end in multipolar ganglion cells, which lie outside the wall of the acinus, and these cells send branches to the secretory cells of the acini. [These cells probably correspond to the branched cells of the basket-shaped structure.] (*c*) Again, he describes medullated fibres which enter the attached end of the cylindrical epithelium lining the excretory ducts of the glands (E). Pflüger thinks that those fibres entering the acini directly are cerebral, while those with ganglia in their course are derived from the sympathetic system. [(*d*) The direct termination of nerve fibres has been observed in the salivary glands of the cockroach by Kupffer.]

145. ACTION OF THE NERVOUS SYSTEM ON THE SECRETION OF SALIVA.—A. **Sub-maxillary Gland.**—Stimulation of the **facial nerve** at its origin causes a profuse secretion of a thin, **watery saliva**, which contains a very small amount of specific constituents. Simultaneously with the act of secretion, the blood vessels of the glands dilate, and the capillaries are so distended that the pulsatile movement in the arteries is propagated into the veins. Nearly four times as much blood flows out of the veins (*Cl. Bernard*), the blood being of a bright red color, and containing one-third more O than the venous blood of the non-stimulated gland. Notwithstanding this relatively high percentage of O, the secreting gland uses more O than the passive gland (§ 131, 1).

[**I. Stimulation of Chorda.**—If a cannula be placed in Wharton's duct, *e. g.*, in a dog, and the chorda tympani be divided, no secretion flows from the cannula. On stimulating the *peripheral end of the chorda tympani* with an interrupted current of electricity, the same results—copious secretion of saliva and vascular dilatation, with increased flow of blood through the gland—occur as when the origin of the seventh nerve itself is stimulated. The **watery** saliva is called **chorda saliva.**]

Two functionally different kinds of nerve fibres occur in the facial nerve—(1) true **secretory** fibres, (2) **vaso-dilator** fibres.

II. **Stimulation of the sympathetic nerve** causes a scanty amount of a very **thick**, sticky, mucous secretion, in which the specific salivary constituents, *mucin*, and the salivary corpuscles are very abundant. The specific gravity of the saliva is raised from 1007 to 1010. Simultaneously the blood vessels become contracted, so that the blood flows more slowly from the veins, and has a dark bluish color.

The sympathetic also contains *two* kinds of nerve fibres—(1) true **secretory** fibres, and (2) **vaso-constrictor** fibres.

[**Electrical Variations during Secretion.**—That changes in the electromotive properties of glands occur during secretion was shown in the frog's skin. Bayliss and Bradford find that the same is true of the sub-maxillary gland (dog). During secretion, the **excitatory change** on stimulating the **chorda** is a *positive* variation of the current of rest (the hilum of the gland becoming more positive), but it is frequently followed by a second phase of opposite sign. The latent period is always very short, about 0.37″. Atropin abolishes the chorda variation. On stimulating the **sympathetic**, the excitatory change is of an opposite sign to that of the chorda, and the hilum becomes less positive, so that there is a *negative* variation. It requires a more powerful stimulus, is less in amount, and its latent period is longer (2″–4″), while atropin lessens but does not abolish it.]

Relation to Stimulus.—On stimulating the *cerebral* nerves, at first with a weak and gradually with a stronger stimulus, there is a gradual development of the secretion in which the solid constituents—occasionally the organic—are increased (*Heidenhain*). If a strong stimulus be applied for a long time, the secretion diminishes, becomes watery, and is poor in specific constituents, especially

in the organic elements, which are more affected than the inorganic (*C. Ludwig and Becher*). After prolonged stimulation of the sympathetic, the secretion resembles the chorda saliva. It would seem, therefore, *that the chorda and sympathetic saliva are not specifically distinct, but vary only in degree.* On continuing the stimulation of the nerves up to a certain maximal limit, the rapidity of secretion becomes greater, and the percentage of *salts* also increases to a certain maximum, and this independently of the former condition of the glands. The percentage of organic constituents also depends on the strength of the nervous stimulation, but not on this alone, as it is essentially contingent upon the condition of the gland before the secretion took place, and it also depends upon the duration and intensity of the previous secretory activity. Very strong stimulation of the gland leaves an "after-effect," which predisposes it to give off organic constituents into the secretion (*Heidenhain*). A latent period of 1.2 sec. to 24 sec. may elapse between the nerve stimulation and the beginning of the secretion.

[Langley has shown that in the **cat** the sympathetic saliva of the sub-maxillary gland is *less* viscid than the chorda saliva.]

Relation to Blood Supply.—*The secretion of saliva is not simply the result of the amount of blood in the glands;* that there is a factor independent of the changes in the state of the vessels is shown by the following facts:—

(1) The secretory activity of the glands when their nerves are stimulated continues for some time after the blood vessels of the gland have been ligatured. [If the head of a rabbit be cut off, stimulation of the seventh nerve, above where the chorda leaves it, causes a flow of saliva, which cannot be accounted for on the supposition that the saliva already present in the salivary glands is forced out of them. Thus we may have **secretion without a blood stream.** The saliva is really secreted from the lymph present in the lymph spaces of the gland (*Ludwig*).]

(2) **Atropin** and **daturin** abolish the activity of the secretory fibres in the chorda tympani, but do not affect the vaso-dilator fibres (*Heidenhain*). The same results occur after the injection of acids and alkalies into the excretory duct (*Gianuzzi*).

[**Action of Atropin.**—The vascular dilatation and the increased flow of saliva, due to the activity of the secretory cells, produced by stimulation of the chorda tympani, although they occur simultaneously, do not stand in the relation of cause and effect. We may cause vascular dilatation without an increased flow of saliva, as already stated (2). If atropin be given to an animal, stimulation of the chorda produces dilatation of the blood vessels, but no secretion of saliva. Atropin paralyzes the secretory fibres, but not the vaso-dilator fibres (Fig. 160). The increased supply of blood, while not causing, yet favors the act of secretion, by placing a larger amount of pabulum at the disposal of the secretory elements, the cells.]

(3) The **pressure** in the excretory duct of the salivary gland—measured by means of a manometer tied into it—may be nearly *twice* as great as the pressure within the arteries of the glands, or even in the carotid itself (*Ludwig*). The pressure in Wharton's duct may reach 200 mm. Hg.

[**Secretory Pressure.**—The experiment described under (3) proves, in a definite manner, that the passage of the water from the blood vessels, or at least from the lymph into the acini of the gland, cannot be due to the blood pressure; that, in fact, it is *not a mere process of filtration*, such as occurs in the glomeruli of the kidney. In the case of the salivary gland, where the pressure within the gland may be double that of the arterial pressure, the water actually moves from the lymph spaces against very great resistance. We can only account for this result by ascribing it to the secretory activity of the gland cells themselves. Whether the activities of the gland cells, as suggested by Heidenhain, are governed directly by two distinct kinds of nerve fibres, a set of solid-secreting fibres, and a set of water-secreting fibres, remains to be proved.]

(4) Just as in the case of muscles and nerves, the salivary glands become **fatigued** or exhausted after prolonged action. This result may also be brought about by injecting acids or alkalies into the duct, which shows that the secretory activity of the gland is independent of the circulation (*Gianuzzi*).

All these facts lead us to conclude that **the nerves exercise a direct effect upon the secretory cells,** apart from their action on the blood vessels.

Extirpation of Salivary Glands.—When the chorda tympani is extirpated on one side in young dogs, the sub-maxillary gland on that side does not develop so much—its weight is 50 per cent. less—while the mucous cells and the "crescents" are smaller than on the sound side (*Bufalini*).

During secretion, the **temperature** of the gland rises 1.5° C. (*Ludwig*), and the blood flowing from the veins is often warmer than the arterial blood. [The **electro-motive changes** are referred to on p. 256.]

"Paralytic Secretion" of Saliva.—By this term is meant the continued secretion of a thin, watery saliva from the sub-maxillary gland, which occurs twenty-four hours after the section of the *cerebral nerves* (chorda of the seventh), *i.e.*, those branches of them that go to this gland, whether the sympathetic be divided or not (*Cl. Bernard*). It increases until the eighth day, after which it gradually diminishes, while the **gland tissue degenerates**. The injection of a small quantity of curara into the artery of the gland also causes it.

[Heidenhain showed that section of *one* chorda is followed by a continuous secretion of saliva from *both* sub-maxillary glands. The term **"paralytic"** secretion is applied to that which takes place on the side on which the nerve is cut, and Langley proposes to call the secretion on the opposite side the **antilytic**. Apnœa (§ 368) stops both the paralytic and antilytic secretion, while dyspnœa increases the flow in both cases; and as section of the sympathetic fibres to the gland (where the chorda is cut) arrests the paralytic secretion excited by dyspnœa, it is evident that both the paralytic secretion and the secretion following dyspnœa are caused by stimuli traveling down the sympathetic fibres. In the later stages of the paralytic secretion, the cause is in the gland itself, for it goes on even if all the nerves passing to the gland be divided, and is probably due to a local nerve centre. In this stage the secretion is arrested by a large dose of chloroform. The paralytic secretion in the first stage may be owing to a venous condition of the blood acting on a central secretory centre whose excitability is increased; and in the latter stages probably on local nerve centres within the gland. The fibres of the chorda in the cat are only partially degenerated thirteen days after section (*Langley*).]

[**Histological Changes.**—In the gland during paralytic secretion, the gland cells of the alveoli (serous, mucous, and demilunes) diminish in size and show the typical "resting" appearance, even to a greater extent than the normal resting gland (*Langley*).]

B. **Sub-lingual Gland.**—Very probably the same relations obtain as in the sub-maxillary gland.

C. **Parotid Gland.**—In the dog, stimulation of the sympathetic *alone* causes no secretion; it occurs when the glosso-pharyngeal branch to the parotid is simultaneously excited. This branch may be reached within the tympanum in the tympanic plexus. A *thick* secretion containing much organic matter is thereby obtained. Stimulation of the *cerebral* branch *alone* yields a clear, thin, watery secretion, containing a very small amount of organic substances, but a considerable amount of the salts of the saliva.

[**Stimulation of Jacobson's Nerve (Parotid of Dog)**—

	Total Solids.	Salts.	Organic Matter.
Without sympathetic, . .	0.56 per cent.	0.31	0.24
With sympathetic, . . .	2.42 per cent.	0.36	2.06]

[**Reflex Secretion of Saliva.**—If a cannula be placed in Wharton's duct, *e. g.*, in a dog, during fasting, no saliva will flow out, but on applying a sapid substance to the mucous membrane of the mouth or the tongue, there is a copious flow of saliva. If the sympathetic nerve be divided, secretion still takes place when the mouth is stimulated, but if the chorda tympani be cut, secretion no longer takes place. Hence, the secretion is due to a reflex act; in this case, the lingual is the afferent, and the chorda the efferent nerve carrying impulses from a centre situated in the medulla oblongata (Fig. 160).]

In the intact body, the secretion of saliva occurs through a **reflex** stimulation of the nerves concerned, whereby, under normal circumstances, the secretion is always watery (chorda or facial saliva). The **centripetal** or **afferent** nerve fibres concerned are: (1) The nerves of taste. (2) The sensory branches of the trigeminus of the entire cavity of the mouth and the glosso-pharyngeal

(which appear to be capable of being stimulated by mechanical stimuli, pressure, tension, displacement). The movements of mastication also cause a secretion of saliva. Pflüger found that one-third more saliva was secreted on the side where mastication took place; and Cl. Bernard observed that the secretion ceased in horses during the act of drinking. (3) The nerves of smell, excited by certain odors. (4) The gastric branches of the vagus. A rush of saliva into the mouth usually precedes the act of vomiting (§ 158).

FIG. 160.



Diagram of a salivary gland.

(5) The **stimulation of distant sensory nerves**, *e. g.*, the central end of the sciatic—certainly through a complicated reflex mechanism—causes a secretion of saliva (*Owsjannikow and Tschierjew*). Stimulation of the conjunctiva, *e. g.*, by applying an irritating fluid to the eye of carnivorous animals, causes a reflex secretion of saliva (*Aschenbrandt*). Perhaps the secretion of saliva which sometimes occurs during pregnancy is caused in a similar reflex manner.

(6) The **movements of mastication** excite secretion, but although, during the act of rumination, this is the case in ruminants, in whom the process of mastication is very thorough, there is no secretion from the sub-maxillary gland, although the parotid secretes (*Colin, Ellenberger and Hofmeister*).

The **reflex centre** for the secretion of saliva lies in the medulla oblongata, at the origin of the seventh and ninth cranial nerves. The centre for the sympathetic fibres is also placed here. This region is connected by nerve fibres with the cerebrum; hence, the thought of a savory morsel, sometimes, when one is hungry, causes a rapid secretion of a thin, watery fluid—[or, as we say, "makes the mouth water"]. If the centre be stimulated directly by a mechanical stimulus (puncture), salivation occurs, while asphyxia has the same effect. The reflex secretion of saliva may be **inhibited** by stimulation of certain sensory nerves, *e. g.*, by pulling out a loop of the intestine. Stimulation of the cortex cerebri of a dog, near the sulcus cruciatus, is often followed by secretion of saliva. Disease of the brain in man sometimes causes a secretion of saliva, owing to the effects produced on the intracranial centre.

So long as there is no stimulation of the nerves, there is no secretion of saliva, as in sleep. *Immediately after* the section of all nerves, secretion stops, for a time at least.

Pathological Conditions and Poisons.—Certain affections, as inflammation of the mouth, neuralgia, ulcers of the mucous membrane, and affections of the gums, due to teething or the prolonged administration of mercury, often produce a copious secretion of saliva or **ptyalism**. Certain **poisons** cause the same effect by direct stimulation of the nerves, as Calabar bean (physostigmin), digitalin, and especially pilocarpin. Many poisons, especially the narcotics—above all, atropin—*paralyze the secretory nerves*, so that there is a cessation of the secretion and the mouth becomes dry; while the administration of muscarin in this condition causes secretion. Pilocarpin acts on the chorda tympani, causing a profuse secretion, and if atropin be given, the secretion is again arrested. Conversely, if the secretion be arrested by atropin, it may be restored by the action of pilocarpin or physostigmin. Nicotin, in small doses, excites the secretory nerves, but in large doses paralyzes them. Daturin, cicutin, and iodide of æthylstrychnin, paralyze the chorda. The saliva is diminished in amount in man, in cases of *paralysis of the facial* or sympathetic nerves, as is observed in unilateral paralysis of these nerves.

[**Sialogogues** are those drugs which increase the secretion of saliva. Some are **topical**, and take effect when applied to the mouth. They excite secretion reflexly by acting on the sensory nerves of the mouth. They include acids, and various pungent bodies, such as mustard, ginger, pyrethrum, tobacco, ether, and chloroform; but they do not all produce the same effect on the amount or quality of the saliva; others, the **general** sialogogues, cause salivation when introduced

into the blood; physostigmin, nicotin, pilocarpin, muscarin. The drugs named act after all the nerves going to the gland are divided, so that they stimulate the peripheral ends of the nerves in the glands. The two former also excite the central ends of the secretory nerves.]

[**Antisialics** are those substances which diminish the secretion of saliva, and they may take effect upon any part of the reflex arc, *i. e.*, on the mouth, the afferent nerves, the nerve centre and afferent nerves, or upon the blood stream through the glands, or on the glands themselves. Opium and morphia affect the centre, large doses of physostigmin affect the blood supply, but atropin is the most powerful of all, as it paralyzes the terminations of the secretory nerves in the glands, *e. g.*, the chorda tympani, and even the sympathetic in the cat (but not in the dog).]

[**Excretion by the Saliva.**—Some drugs are excreted by the saliva. Iodide of potassium is rapidly eliminated by the kidneys, and by the salivary glands, and so also is iodide of iron.]

Theory of Salivary Secretion.—Heindenhain has recently formulated the following theory regarding the secretion of saliva: "During the passive or quiescent condition of the gland, the organic materials of the secretion are formed from and by the activity of the protoplasm of the secretory cells. A *quiescent* cell, which has been inactive for some time, therefore contains little protoplasm, and a large amount of these secretory substances. In an actively secreting gland, there are two processes occurring together, but independent of each other, and regulated by two different classes of nerve-fibres; *secretory fibres* cause the act of secretion, while *trophic fibres* cause chemical processes within the cells, partly resulting in the formation of the soluble constituents of the secretion, and partly in the growth of the protoplasm. According to the number of both kinds of fibres present in a nerve passing to a gland, such nerve being stimulated, the secretion takes place more rapidly (cerebral nerve) or more slowly (sympathetic), while the secretion contains less or more solid constituents. The *cerebral* nerves contain many secretory fibres and few trophic fibres, while the *sympathetic* contain more trophic but few secretory fibres. The rapidity and chemical composition of the secretion vary according to the strength of the stimulus. During continued secretion, the supply of secretory materials in the gland cells is used up more rapidly than it is replaced by the activity of the protoplasm; hence, the amount of organic constituents diminishes, and the microscopic characters of the cells are altered. The microscopic characters of the cells are altered also by the increase of the protoplasm, which takes place in an active gland. The mucous cells disappear, and seem to be dissolved after prolonged secretion, and their place is taken by other cells derived from the proliferation of the marginal cells. The energy which causes the current of fluid depends upon the protoplasm of the gland cells."

146. THE SALIVA OF THE INDIVIDUAL GLANDS.—(*a*) **Parotid saliva** is obtained by placing a fine cannula in Steno's duct; it has an *alkaline* reaction, but during fasting, the first few drops may be neutral or even acid on account of free CO_2; its specific gravity is 1003 to 1004. After standing it becomes turbid, and deposits, in addition to albuminous matter, calcium carbonate, which is present in the fresh saliva in the form of bicarbonate. It contains small quantities (more abundant in the horse) of a globulin-like body, and never seems to be without CNKS, *i. e.*, sulphocyanide of potassium (or sodium),—which, however, is absent in the sheep and dog.

[The **sulphocyanide** gives a dark red color (ferric sulphocyanide) with ferric chloride, and the color is discharged by mercuric chloride, but this is not the case with meconic acid, which gives a similar color reaction.] It also reduces iodic acid when added to saliva, causing a yellow color from the liberation of iodine, which may be detected at once by starch (*Solera*).

Among the **organic** substances the most important are **ptyalin**, a small amount of *urea*, and traces of a volatile acid. **Mucin is absent**, hence the parotid saliva is not sticky, and can readily be poured from one vessel into another. It contains 1.5 to 1.6 per cent. of solids in man, of which 0.3 to 1.0 per cent. is inorganic.

Of the **inorganic** constituents—the most abundant are potassium and sodium chlorides; then potassium, sodium, and calcium carbonates, some phosphates, and a trace of an alkaline sulphate.

Salivary calculi are formed in the ducts of the salivary glands owing to the deposition of lime salts, and they contain only traces of the other salivary constituents; in the same way is formed the **tartar** of the teeth, which contains many threads of leptothrix, and the remains of low organisms which live in decomposing saliva in carious cavities between the teeth.

(*b*) **Sub-maxillary saliva** is obtained by placing a cannula in Wharton's duct; it is alkaline, and may be strongly so. After standing for a time, fine crystals of calcium carbonate are deposited, together with an amorphous albuminous body. It always contains **mucin** (which is precipitated by acetic acid);

hence, it is usually somewhat tenacious. It contains **ptyalin**, but in less amount than in parotid saliva; and, according to Oehl, only 0.0036 per cent. of potassium sulphocyanide.

Chemical Composition.—Sub-maxillary saliva (dog):—

Water, 991.45 per 1000,
Organic Matter, 2.89 " "
Inorganic Matter, 5.66 { 4.50 NaCl and $CaCl_2$.
{ 1.16 $CaCO_3$, Calcium and Magnesium phosphates.

	Mixed Saliva (Human) (*Jacubowitsch*).	Parotid (Human) (*Hoppe-Seyler*).	Sub-maxillary (Dog) (*Herter*).
[Water,	99.51	99.32	99.44
Solids,	0.49	0.68	0.56
Soluble organic bodies (ptyalin),	0.13	0.34	0.066
Epithelium, mucin,	0.16		0.17
Inorganic salts,	0.102	0.34	0.43
Potassic sulphocyanide,	0.006	0.03	. .
Potassic and sodic chlorides,	0.084	. .	. .]

Gases.—Pflüger found that 100 cubic centimetres of the saliva contained 0.6 O; 64.7 CO_2 (part could be pumped out, and part required the addition of phosphoric acid); 0.8 N.; or, in 100 vol. gas, 0.91 O; 97.88 CO_2; 1.21 N. [It therefore contains much more CO_2 than venous blood. Külz obtained from 100 c.c. of human saliva 7 c.c. of gas—O = 1 c.c., N = 2.5 c.c. and CO_2 = 3.5 c.c. Besides this there is 40–60 c.c. of fixed CO_2 in the form of carbonates.]

(*c*) **Sub-lingual saliva** is obtained by placing a very fine cannula in the ductus Rivinianus; it is *strongly alkaline* in reaction, very sticky and cohesive, contains much mucin, numerous salivary corpuscles, and some potassium sulphocyanide.

147. THE MIXED SALIVA IN THE MOUTH.—The **mixed saliva** in the mouth is a mixture of the secretions from the salivary, mucous, and other glands of the mouth.

(1) **Physical Characters.**—It is an opalescent, tasteless, odorless, slightly glairy fluid, with a specific gravity of 1004 to 1009, and an alkaline reaction. The **amount** secreted in twenty-four hours = 200 to 1500 grammes (7 to 50 oz.); according to Bidder and Schmidt, however, = 1000 to 2000 grammes. The solid constituents = 5.8 per 1000.

Composition.—The **solids** are: Epithelium and mucus, 2.2; ptyalin and albumin, 1.4; salts, 2.2; potassium sulphocyanide, 0.04 per 1000. The ash contains chiefly potash, phosphoric acid, and chlorine (*Hammerbacher*).

Decomposition products of epithelium, salivary corpuscles, or the remains of food, may render it *acid temporarily*, as after long fasting, and after much speaking; the reaction is acid in some cases of dyspepsia and in fever, owing to the stagnation and insufficient secretion.

(2) **Microscopic Constituents.**—(*a*) The **salivary corpuscles** are slightly larger than the white blood corpuscles (8 to 11 μ), and are nucleated protoplasmic globular cells without an envelope (Fig. 150, *s*). During their living condition, the particles in their interior exhibit *molecular* or **Brownian movement.** The dark granules lying in the protoplasm are thrown into a trembling movement, from the motion of the fluid in which they are suspended. This dancing motion stops when the cell dies.

[The **Brownian movements** of these suspended granules are purely physical, and are exhibited by all fine microscopic particles suspended in a limpid fluid, *e. g.*, gamboge rubbed up in water, particles of carmine, charcoal, etc.]

(*b*) **Pavement epithelial cells** from the mucous membrane of the mouth and tongue; they are very abundant in catarrh of the mouth (Fig. 150).

(*c*) **Living organisms,** which live and thrive in the cavities of teeth, nourished by the remains of food. Among these are *Leptothrix buccalis* (Fig. 149, 12) and small bacteria-like organisms. The threads of the leptothrix penetrate into the canals of the dentine, and produce dental caries. [Miller has found twenty-five varieties of microörganisms, including cocci, bacteria, vibrios, spirilla, and spirochætæ, eight of them present in the stomach and twelve in the intestines.]

(3) **Chemical Properties.**—(*a*) **Organic Constituents.**—*Serum-albumin* is precipitated by heat and by the addition of alcohol. In saliva, mixed with much water and shaken up with CO_2, a *globulin-like* body is precipitated; *mucin* occurs in small amount. Among the extractives, the most important is **ptyalin**; *fats* and *urea* occur only in traces. In twenty-four hours 130 milligrammes of potassium or sodium sulphocyanide are secreted.

(*b*) **Inorganic Constituents.**—Sodium and potassium chlorides, potassium sulphate, alkaline and earthy phosphates, ferric phosphate.

According to Schönbein, the saliva contains traces of *nitrites* (detected by adding dilute sulphuric acid and diamido-benzol to dilute saliva), which give a yellow color (*Gries*). There are also traces of ammonia (*Brücke*).

Abnormal Constituents.—In diabetes mellitus, *lactic acid*, derived from a further decomposition of grape sugar, is found. It dissolves the lime in the teeth, giving rise to diabetic dental caries. Frerichs found *leucin*, and Vulpian increase of albumin in albuminuria. Of foreign substances taken into the body, the following appear in the saliva: Mercury, potassium, iodine, and bromine.

Saliva of New-born Children.—In new-born children, the parotid alone contains ptyalin. The diastatic ferment seems to be developed in the sub-maxillary gland and pancreas, at the earliest after two months. Hence, it is not advisable to give starchy food to infants. No ptyalin has been found in the saliva of infants suffering from thrush (Oïdium albicans—*Zweifel*). The diastatic action of saliva is not absolutely necessary for the suckling, feeding as it does upon milk. The mouth during the first two months is not moist, but at a later period saliva is copiously secreted (*Korowin*); after the first six months, the salivary glands increase considerably. The eruption of the teeth—owing to the irritation of the mucous membrane—produce a copious secretion of saliva.

148. PHYSIOLOGICAL ACTION OF SALIVA.—I. **Diastatic Action.**—The most important chemical action exerted by saliva in digestion is its diastatic or amylolytic action (*Leuchs*, 1831), *i. e.*, the transformation of starch into *dextrin* and some form of **sugar.** This is due to the **ptyalin**—a **hydrolytic ferment** or **enzym**—which, even when it is present in very minute quantity, causes starch to take up water and become soluble, the ferment itself undergoing no essential change in the process. [Ptyalin belongs to the group of unorganized ferments (§ 250, 9). Like all other ferments it acts only within a certain range of temperature, being most active about 40° C. Its energy is permanently destroyed by boiling. It acts best in a slightly alkaline or neutral medium.]

[**Action on Starch.**—Starch grains consist of *granulose* or starch enclosed by coats of *cellulose*. Cellulose does not appear to be affected by saliva, so that saliva acts but slowly on raw, unboiled starch. If the starch be boiled, so as to swell up the starch grains and rupture the cellulose envelopes, the amylolytic action takes place rapidly. If starch paste or starch mucilage, made by boiling starch in water, be acted upon by saliva, especially at the temperature of the body, the first **physical** change observable is the liquefaction of the paste, the mixture becoming more fluid and transparent. The change takes place in a few minutes. When the action is continued, important **chemical** changes occur.]

According to O'Sullivan, Musculus, and v. Mering, the diastatic ferment of saliva (and of the pancreas), by acting upon starch or glycogen, forms **dextrin** and **maltose** (both soluble in water). Several closely allied varieties of dextrin, distinguishable by their color reactions, seem to be produced (*Brücke*). **Erythrodextrin** is formed first, it gives a red color with iodine; then a reducing dextrin—**achroodextrin**, which gives no color reaction with iodine. The sugar formed by the action of ptyalin upon starch is **maltose** ($C_{12}H_{22}O_{11} + H_2O$), which is distinguished from grape sugar ($C_{12}H_{24}O_{12}$) by containing one molecule less of water, which, however, it holds as a molecule of water of hydration. [Maltose also differs from grape sugar in its greater rotatory power on polarized

light, the former = + 150°, the latter + 56°, the ratio being 61 : 100; and in its smaller power of reducing cupric oxide. Thus, between the original starch and the final product, maltose, several intermediate bodies are formed. The starch gives a blue with iodine, but after it has been acted on for a time it gives a red or violet color, indicating the presence of erythrodextrin, there being a simultaneous production of sugar; but ultimately no color is obtained on adding iodine—achroodextrin, which gives no color with iodine, maltose being formed. The presence of the maltose is easily determined by testing with Fehling's solution.]

[Brown and Heron suggest that the final result of the transformation may be represented by the equation—

$$\underset{\text{Soluble starch.}}{10(C_{12}H_{20}O_{10})} + \underset{\text{Water.}}{8H_2O} = \underset{\text{Maltose.}}{8(C_{12}H_{22}O_{11})} + \underset{\text{Achroodextrin.}}{2(C_{12}H_{20}O_{10})}$$

The ferment slowly changes maltose into grape sugar or dextrose. This result may be brought about much more rapidly by boiling maltose with dilute sulphuric or hydrochloric acid.] Achroodextrin ultimately passes into maltose, and this again into dextrose; the other form of dextrin does not seem to undergo this change (Seegen's Dystropodextrin). For the further changes that maltose undergoes in the intestine, see § 183, II, 2.

[The formula of starch is usually expressed as $C_6H_{10}O_5$, but the researches already mentioned, and those of Brown and Heron, make it probable that it is more complex, which we may provisionally represent by $n(C_{12}H_{20}O_{10})$. According to Musculus and Meyer, erythrodextrin is a mixture of dextrin and soluble starch.]

Preparation of Ptyalin.—(1) Like all other hydrolytic ferments, it is carried down with any copious precipitate that is produced in the fluid which contains it, and it can be isolated from the precipitate. The saliva is acidulated with phosphoric acid, lime-water is added until the reaction becomes alkaline, when a precipitate of the basic calcium phosphate occurs, which carries the ptyalin along with it. This precipitate is collected on a filter, washed with water, which dissolves the ptyalin, and from its watery solution it is precipitated by alcohol as a white powder. It is redissolved in water and reprecipitated, and is obtained pure (*Cohnheim*).

(2) **Glycerine or v. Wittich's Method.**—The salivary glands [rat] are chopped up, placed in absolute alcohol for twenty-four hours, taken out and dried, and afterward placed in glycerine for several days, which extracts the ptyalin. It is precipitated by alcohol from the glycerine extract.

(3) William Roberts recommends the following solutions for extracting ferments from organs which contain them: (1) A 3 to 4 per cent. solution of a mixture of 2 parts of boracic acid and 1 part borax. (2) Water, with 12 to 15 per cent. of alcohol. (3) 1 part chloroform to 200 of water.

Diastatic Action of Saliva.—(*a*) The diastatic or sugar-forming action is known by (1) The **disappearance of the starch.** When a small quantity of starch is boiled with several hundred times its volume of water, starch mucilage is obtained, which strikes a blue color with iodine. If to a small quantity of this starch a sufficient amount of saliva be added, and the mixture kept for some time at the temperature of the body, the blue color disappears. (2) The **presence of sugar** is proved directly by using the tests for sugar (§ 149).

(*b*) The action takes place more slowly in the *cold* than at the temperature of the body—its action is enfeebled at 55° C., and destroyed at 75° C. (*Paschutin*). The most favorable temperature is 35° to 39° C.

(*c*) The ptyalin itself does not seem to be changed during its action, but ptyalin which has been used for one experiment is less active when used the second time (*Paschutin*).

Ptyalin differs from diastase—the ferment in germinating grains—in so far that the latter first begins to act at + 66° C. Ptyalin decomposes salicin into saligenin and grape sugar (*Frerichs and Städler*).

(*d*) Saliva acts best in an exactly **neutral medium**, but it also acts in an alkaline and even in a slightly acid fluid; strong acidity prevents its action. The ptyalin is only active in the stomach when the acidity is due to *organic acids* (lactic or butyric), and not when free hydrochloric acid is present (*van de Velde*). In both cases, however, dextrin is formed. Ptyalin is destroyed by hydrochloric acid or digestion by pepsin (*Chittenden and Griswold, Langley*). Even butyric and lactic acids formed from grape sugar in the stomach may prevent its action; but if the acidity be neutralized, the action is resumed (*Cl. Bernard*).

(*e*) The addition of common salt, ammonium chloride, or sodium sulphate (4 per cent. solution), *increases* the activity of the ptyalin, and CO_2, acetate of quinine, strychnia, morphia, curara, 0.025 per cent. sulphuric acid, have the same effect.

(*f*) Much alcohol and caustic potash destroy the ptyalin; long exposure to the air weakens its action; sodium carbonate and magnesium sulphate delay the action (*Pfeiffer*). Salicylic acid and much atropin arrest the formation of sugar.

(*g*) Ptyalin acts very feebly and very gradually upon **raw starch**, only after 2 to 3 hours (*Schiff*); while upon boiled starch it acts rapidly. [Hence the necessity for boiling thoroughly all starchy foods.]

(*h*) The various kinds of starch are changed more or less rapidly according to the amount of cellulose which they contain; raw potato starch after 2 to 3 hours, raw maize starch after 2 to 3 minutes (*Hammarsten*); wheat starch more quickly than that of rice. When the starches are powdered and boiled, they are changed with equal rapidity.

(*i*) A *mixture* of the saliva from all the glands is more active than the saliva from any single gland (*Jakubowitsch*), while mucin is inactive.

[**Effect of Tea.**—Tea has an intensely inhibitory effect on salivary digestion, which is due to the large quantity of tannin contained in the tea-leaf. Coffee and cocoa have only a slight effect on salivary digestion. The only way to mitigate the inhibitory effect of tea on salivary digestion is "not to sip the beverage with the meal, but to eat first and drink afterward" (*Roberts*).]

II. Saliva dissolves those substances which are soluble in water; while the alkaline reaction enables it to dissolve some substances which are not soluble in water alone, but require the presence of an alkali.

III. Saliva moistens dry food and aids the formation of the "bolus," while by its mucin it helps the act of swallowing, the mucin being given off unchanged in the fæces. The ultimate fate of ptyalin is unknown.

[IV. Saliva also aids articulation, while according to Liebig it carries down into the stomach small quantities of O.]

[V. It is necessary to the sense of taste to dissolve sapid substances, and bring them into relation with the end organs of the nerves of taste.]

Saliva has no action on proteids or on fats.

The presence of a peptone-forming ferment has recently been detected in saliva (*Hüfner*, *Munk*, *Kühne*). [Perfectly healthy human saliva has no poisonous properties.]

149. TESTS FOR SUGAR.—1. Trommer's test depends upon the fact that, in alkaline solutions, sugar acts as a **reducing agent**; in this case a metallic oxide is changed into a sub-oxide. To the fluid to be investigated, add ½ of its volume of a solution of caustic potash (soda), specific gravity 1.25, and a few drops of a weak solution of cupric sulphate, which causes at first a bluish precipitate, consisting of hydrated cupric oxide, but it is redissolved, giving a clear blue fluid, if sugar be present. Heat the upper stratum of the fluid, and a yellow or red ring of cuprous oxide is obtained, which indicates the presence of sugar; $2CuO - O = Cu_2O$.

The solution of hydrated cupric oxide is caused by other organic substances; but the final stage, or the production of cuprous oxide, is obtained only with certain sugars—grape, fruit and milk (but not cane) sugar. Fluids which are turbid must be previously filtered, and if they are highly colored, they must be treated with basic lead acetate; the lead acetate is afterward removed by the addition of sodium phosphate and subsequent filtration. If very small quantities of sugar are present along with compounds of ammonia, a yellow color instead of a yellow precipitate may be obtained. In doing the test, care must be taken not to add too much cupric sulphate.

[2. **Fehling's Solution** is an alkaline solution of potassio-tartrate of copper. Boil a small quantity of the deep-blue colored Fehling's solution in a test-tube, and add to the boiling test a few drops of the fluid supposed to contain the sugar. If sugar be present, the copper solution is reduced, giving a yellow or reddish precipitate. The reason for boiling the test itself is, that the solution is apt to decompose when kept for some time, when it is precipitated by heat alone. This is one of the best and most reliable tests for the presence of sugar. In **Pavy's** modification of this test, ammonia is used instead of a caustic alkali (§ 267).]

(3) **Böttger's Test.**—Alkaline bismuth oxide solution is best prepared, according to **Nylander**, as follows: 2 grms. bismuth subnitrate, 4 grms. potassic and sodic tartrate, 100 grms. caustic soda of 8 per cent. Add 1 c.c. to every 10 c.c. of the fluid to be investigated. When boiled for several

minutes, the sugar causes the reduction and deposits a black precipitate of metallic bismuth. [According to Salkowski, the urine of a person taking rhubarb gives the same reaction with this test.]

(4) **Moore and Heller's Test.**—Caustic potash or soda is added until the mixture is strongly alkaline; it is afterward boiled. If sugar be present, a yellow, brown, or brownish-black coloration is obtained. If nitric acid be added, the odor of burned sugar (caramel) and formic acid is obtained.

(5) **Mulder and Neubauer's Test.**—A solution of indigo-carmine, rendered alkaline with sodic carbonate, is added to the sugar solution until a slight bluish color is obtained. When the mixture is heated, the color passes into purple, red, and yellow. When shaken with atmospheric air, the fluid again becomes blue.

Molisch's Test.—To 5 c.cm. of the fluid add 2 drops of a 17 per cent. alcoholic solution of α-naphthol, or a solution of thymol. Add 1 to 2 c.cm. of concentrated sulphuric acid, and shake the mixture. The presence of sugar colors the α-naphthol mixture deep violet, the thymol deep red. The subsequent addition of water causes a precipitate of similar color, which is insoluble in concentrated hydrochloric acid. Albumin, casein and peptone give the same reaction (*Seegen*), but the deposit on the addition of water is soluble in concentrated hydrochloric acid.

Other tests are described in § 266.

In all cases where albumin is present it must be removed—in urine by acidulating with acetic acid and boiling; in blood, by adding four times its volume of alcohol and afterward filtering, while the alcohol is expelled by heat.

150. **QUANTITATIVE ESTIMATION OF SUGAR.—I. By Fermentation.**—In the glass vessel (Fig. 161, *a*) a measured quantity (20 c.cm.) of the fluid (sugar) is placed along with some yeast, while *b* contains concentrated sulphuric acid. The whole apparatus is then weighed. When exposed to a sufficient temperature (10° to 40° C.), the sugar splits into 2 molecules of alcohol and 2 of carbon dioxide,

$$\underset{\text{Grape sugar}}{C_6H_{12}O_6} = \underset{2\text{ alcohol}}{2\,(C_2H_6O)} + \underset{2\text{ carbon dioxide}}{2\,(CO_2)},$$

and in addition there are formed traces of glycerine and succinic acid. The CO_2 escapes from *b*, and as it passes through the H_2SO_4, the CO_2 yields to the latter its water. The apparatus is weighed after two days, when the reaction is ended, and the amount of sugar is calculated from the loss of weight in the 20 c.cm. of fluid. 100 parts of water-free sugar = 48.89 parts CO_2, or 100 parts CO_2 correspond to 204.54 parts of sugar.

FIG. 161.



Apparatus for the quantitative estimation of sugar by fermentation.

II. Titration.—By means of Fehling's solution, which is made of such strength that all the copper in 10 cubic centimetres of the solution is reduced by 0.05 gramme of grape sugar (§ 267).

III. Circumpolarization.—The saccharimeter of Soleil-Ventzke may be used to determine the amount of sugar present. It may also be used for the quantitative estimation of albumin. Sugar rotates the ray of polarized light to the right and albumin to the left. The amount of rotation, or "specific rotatory power," is directly proportional to the amount of the rotating substance present in the solution, so that the amount of rotation of the ray indicates the amount of the substance present. By the term "specific rotatory power" is meant the degree of rotation which is produced by 1 grm. of the substance dissolved in 1 c.cm of water, when examined in a layer 1 decimeter thick. For yellow light the specific rotation of grape sugar is + 56°.

In Fig. 162 the light from the lamp falls upon a crystal of calc-spar. Two Nicol's prisms are placed at *v* and *s*, *v* is movable round the axis of vision, while *s* is fixed. In *m* Soleil's double plate of quartz is placed, so that one-half of it rotates the ray of polarized light as much to the right as the other rotates it to the left. In *n* the field of vision is covered by a plate of *left-rotatory* quartz. At *b c* is the *compensator*, composed of two right-rotatory prisms of quartz, which can be displaced laterally by the milled head, *g*, so that the polarized light passing through the apparatus can be made to pass through a thicker or thinner layer of quartz. When these right-rotatory prisms are placed in a certain position, the rotation of the left-rotatory quartz at *n* is exactly neutralized. In this position the scale on the compensator has its nonius exactly at *o*, and both halves of the double plate at *m* appear to have the same color to the observer, who from *v* looks through the telescope placed at *e*. Rotate the Nicol's prism at *v* until a bright rose-colored field is obtained. In this position the telescope must be so adjusted that the vertical line bounding the two halves shall be distinctly visible. The apparatus is now ready for use.

Fill a tube, 1 decimetre in length, with urine containing sugar or albumin, the urine being perfectly clear. The tube is placed between *m* and *n*. By rotating the Nicol's prisms, *v*, the rose color is again obtained. The compensator at *g* is then rotated until both halves of the field of vision

have exactly the same color. When this is obtained, read off on the scale the number of degrees the nonius is displaced to the right (sugar) or to the left (albumin) from zero. The number of degrees indicates directly the number of grammes of the rotating substance present in 100 c. c. of the fluid. If the fluid is very dark colored, it must be decolorized by filtering it through animal charcoal (*Seegen*), [or the coloring matter may be precipitated by the addition of lead acetate]. If the sugary urine contains albumin, the latter must be removed by boiling and filtration. A turbidity not removed by filtration may be got rid of by adding a drop of acetic acid or several drops of sodic carbonate or milk of lime, and afterward filtering. [One may also employ the apparatus of Mitscherlich, or the "half-shadow apparatus" of Laurent.]

FIG. 162.

Soleil-Ventzke's Polarization Apparatus.

151. MECHANISM OF THE DIGESTIVE APPARATUS.—This embraces the following acts:—

1. The introduction and mastication of the food; the movements of the tongue; insalivation; formation of the bolus of food.
2. Deglutition.
3. The movements of the stomach, small and large intestine.
4. The excretion of fecal matters.

152. INTRODUCTION OF THE FOOD.—**Fluids** are taken into the mouth in three ways: (1) By **suction**, the lips are applied air-tight to the vessel containing the fluid, while the tongue is retracted (the lower jaw being often depressed) and acts like the piston in a suction pump, thus causing the fluid to enter the mouth. Herz found that the negative pressure caused by an infant while sucking = 3 to 10 mm. Hg. (2) The fluid is **lapped** when it is brought into direct contact with the lips, and is raised by aspiration and mixed with air so as to produce a characteristic sound in the mouth. (3) Fluid may be **poured** into the mouth, and as a general rule the lips are applied closely to the vessel containing the fluid.

Solids, when they consist of small particles, are licked up with the lips, aided by the movements of the tongue. In the case of large masses, a part is bitten off with the incisor teeth, and is afterward brought under the action of the molar teeth by means of the lips, cheeks, and tongue.

153. MASTICATION.—The articulation of the jaw is provided with an interarticular cartilage—the meniscus—which prevents direct pressure being made upon the articular surface when the jaws are energetically closed, and which also divides the joint into two cavities, one lying over the other. The capsule is so lax that, in addition to the raising and depressing of the lower jaw, it permits of the lower jaw being displaced forward, whereby the meniscus moves with it, and covers the articular surface.

The **process of mastication** embraces: (*a*) The **elevation of the jaw**, accomplished by the combined action of the Temporal, Masseter, and Internal Pterygoid Muscles. If the lower jaw was previously so far depressed that its articular surface rested upon the tubercle, it now passes backward upon the articular surface.

(*b*) The **depression of the lower jaw** is caused by its own weight, aided by the action of the anterior bellies of the Digastrics, the Mylo- and Genio-hyoid and Platysma. The muscles act especially during forcible opening of the mouth. The necessary fixation of the hyoid bone is obtained through the action of the Omo- and Sterno-hyoid, and by the Sterno-thyroid and Thyro-hyoid.

When the articular surface of the lower jaw passes forward on to the tubercle, the External Pterygoids actively aid in producing this (*Bérard*).

(*c*) **Displacement of the Articular Surfaces.**—During rest, when the mouth is closed, the incisor teeth of the lower jaw are within the arch of the upper incisors. When in this position the jaw is protruded by the External Pterygoids, whereby the articular surface passes on to the tubercle (and, therefore, downward), while the lateral teeth are thereby separated from each other. The jaw is retracted by the Internal Pterygoids without any aid from the posterior fibres of the Temporals. When one articular surface is carried forward, the jaw is protruded and retracted by the External and Internal Pterygoid of the same side. At the same time, there is a transverse movement, whereby the back teeth of the protruded side are separated from each other.

During mastication, the individual movements of the lower jaw are variously combined, and especially with lateral grinding movements, while the food to be masticated is kept from passing outward by the action of the muscles of the lips (Orbicularis oris) and the Buccinators, while the tongue continually pushes the particles between the molar teeth. The energy of the muscles of mastication is regulated by the **sensibility of the teeth**, and the muscular sensibility of the muscles of mastication, as well as by the general sensibility of the mucous membrane of the mouth and lips. At the same time, the mass is mixed with saliva, the divided particles cohere, and are formed into a mass or **bolus**, of a long, oval shape, by the muscles of the tongue. The bolus then rests on the back of the tongue, ready to be swallowed.

Nerves of Mastication.—The muscles of mastication receive their **motor** nerves from the third branch of the trigeminus, the mylo-hyoid and the anterior belly of the digastric being sup-

plied from the same source. The genio-, omo-, and sterno-hyoid, sterno-thyroid, and thyro-hyoid are supplied by the hypoglossal, while the facial supplies the posterior belly of the digastric, the stylo-hyoid, the platysma, the buccinator, and the muscles of the lips. The general **centre** for the muscles of mastication lies in the medulla oblongata (§ 367).

When the mouth is closed, the jaws are kept in contact by the pressure of the air, as the cavity of the mouth is rendered free from air, and the entrance of air is prevented anteriorly by the lips, and posteriorly by the soft palate. The pressure exerted by the air is from 2 to 4 mm. Hg. (*Metzger and Donders*).

[**Effect on the Circulation.**—Marey found that mastication trebled the velocity of the blood current in the carotid (horse), while François Frank observed that the circulation of the brain (in man) is increased; hence it is evident that mastication implies an increased supply of blood to the nerve centres.]

FIG. 163.



Longitudinal section of an incisor tooth.

154. STRUCTURE AND DEVELOPMENT OF THE TEETH.—A **tooth** is just a papilla of the mucous membrane of the gum, which has undergone a characteristic development. In its simplest form, as in the teeth of the lamprey, the connective-tissue basis of the papilla is covered with many layers of corneous epithelium. In human teeth, part of the papilla is transformed into a layer of calcified **dentine**, while the epithelium of the papilla produces the **enamel**, the fang of the tooth being covered by a thin accessory layer of bone, the **crusta petrosa** or **cement.**

The **dentine** or ivory which surrounds the pulp cavity and the canal of the fang (Fig. 163) is very firm, elastic, and brittle. Dentine, like the matrix of bone, when treated in a certain way, presents a fibrillar structure. It is permeated by innumerable long, tortuous, wavy tubes —the **dentinal tubules**—each of which communicates with the pulp cavity by means of a fine opening, and passes more or less horizontally outward as far as the outer layers of the dentine. The tubules are bounded by an extremely resistant, thin, cuticular membrane, which strongly resists the action of chemical reagents. These tubules are filled completely by soft fibres, the "**fibres of Tomes,**" which are merely greatly elongated and branched processes of the **odontoblasts** of the pulp.

The dentinal tubules, as well as the fibres of Tomes, anastomose throughout their entire extent by means of fine processes. As the fibres approach the enamel, which they do not penetrate, some of them bend on themselves, and form a loop (Fig. 166, *c*), while others pass into the "**interglobular spaces**" (Fig. 165) which are so abundant in the outer part of the dentine. The interglobular spaces are small spaces bounded by curved surfaces. Certain curved lines, "**Schreger's lines,**" may be detected with the naked eye in the dentine (*e. g.*, of the elephant's tusk) running parallel with the contour of the tooth. They are caused by the fact that at these parts all the chief curves in the dentinal tubules follow a similar course.

The **enamel**, the hardest substance in the body (resembling apatite), covers the crown of the teeth. It consists of hexagonal flattened prisms arranged side by side like a palisade (Fig. 166, *B* and *C*). They are 3 to 5 μ ($\frac{1}{5000}$ inch) broad, not quite uniform in thickness, curved slightly in different directions, and, owing to inequalities of thickness, they exhibit transverse markings. They are elongated, **calcified, cylindrical, epithelial cells.** Retzius described dark brown lines running parallel with the outer boundary of the enamel, due to the presence of pigment (Fig. 163). The fully-formed enamel is negatively doubly refractive and uniaxial, while the developing enamel is positively doubly refractive (*Hoppe-Seyler*).

The **cuticula** or **Nasmyth's membrane** covers the free surface of the enamel as a completely structureless membrane 1 to 2 μ thick, but in quite young teeth it exhibits an epithelial structure, and is derived from the outer epithelial layer of the enamel organ.

The **cement** or **crusta petrosa** is a thin layer of bone covering the fang (Fig. 167, *a*). The bone lacunæ communicate directly with the dental tubules of the fang. Haversian canals and lamellæ are only found where the layer of cement is thick, and the former may communicate with the pulp cavity. Very thin layers of cement may be devoid of bone corpuscles. Sharpey's fibres occur in the cement of the dog's tooth; while in the horse's tooth single bone corpuscles are developed by a capsule. In the **periodontal membrane,** which is just the periosteum of the

alveolus, coils of blood vessels similar to the renal glomeruli occur. They anastomose with each other, and are surrounded by a delicate capsule of connective tissue.

Chemistry of a Tooth.—The teeth consist of a gelatine-yielding matrix infiltrated with calcium phosphate and carbonate (like bone). (1) The **dentine** contains—organic matter, 27.70; calcium phosphate and carbonate, 72.06; magnesium phosphate, 0.75; with traces of iron, fluorine, and sulphuric acid.

FIG. 164.

Transverse section of dentine. The light rings are the walls of the dentinal tubules; the dark centres with the light points are the fibres of Tomes lying in the tubules.

FIG. 165.

Interglobular spaces in dentine.

FIG. 166.



Section of a tooth between the dentine and enamel. *a*, enamel; *c*, dentinal tubules; *B*, enamel prisms highly magnified; *C*, transverse sections of enamel prisms.

FIG. 167.



Transverse section of the fang. *a*, cement with bone corpuscles; *b*, dentine with tubules; *c*, boundary between both.

(2) The **enamel** contains an organic proteid matrix allied to the substance of epithelium. It consists of 3.60 organic matter and 96.00 of calcium phosphate and carbonate, 1.05 magnesium phosphate, with traces of calcium fluoride and an insoluble chlorine compound.

(3) The **cement** is identical with bone.

The **pulp** in a fully-grown tooth represents the remainder of the dental papilla around which the dentine was deposited. It consists of a very vascular, indistinctly fibrillar connective tissue, laden with cells. The layers of cells, resembling epithelium, which lie in direct contact with the dentine,

are called **odontoblasts**, *i. e.*, those cells which build up the dentine. These cells send off long-branched processes into the dentinal tubules, while their nucleated bodies lie on the surface of the pulp, and form connections by processes with other cells of the pulp and with neighboring odontoblasts. Numerous non-medullated nerve fibres (sensory from the trigeminus), whose mode of termination is unknown, occur in the pulp.

The **periosteum** or **periodontal membrane** of the fang is, at the same time, the alveolar periosteum, and consists of connective tissue with elastic fibres and many nerves.

The **gums** are devoid of mucous glands, very vascular, and often provided with long vascular papillæ, which are sometimes compound.

Development of a Tooth.—It begins at the end of the second month of fœtal life. Along the whole length of the fœtal gum is a thick projecting ridge (Fig. 168, *a*) composed of many layers of epithelium. A depression, the **dental groove**, also filled with epithelium, occurs in the gum, and runs along under the ridge. The dental groove becomes deeper throughout its entire length, and on transverse section presents the appearance of a dilated flask (*b*), while at the same time it is filled with elongated epithelial cells, which form the "**enamel organ.**" A conical papilla, the "**dentine germ,**" grows up from the mucous tissue, of which the gum consists, toward the enamel organ (Fig. 169, *c*), so that the apex of the papilla comes to have the enamel organ resting upon it like a double cap. Afterward, owing to the development of connective tissue, the parts of the enamel organ lying between and uniting the individual dentine germs, disappear, and gradually the connective tissue forms a **tooth sac** enclosing the papilla and its enamel organ (*d*).

Those epithelial cells (Fig. 169, 3) of the enamel organ which lie next the top of the papilla, are cylindrical, and become calcified to form enamel prisms. The layer of cells of the double cap, which

FIG. 168. FIG. 169. FIG. 170.



FIG. 168.—*a*, Dental ridge; *b*, enamel organ; *c*, beginning of the dentine germ; *d*, first indication of the tooth sac. FIG. 169.—*a*, Dental ridge; *b*, enamel organ with (1) outer epithelium, (2) middle stellate layer, (3) enamel prism-cell layer; *c*, dentine germ with blood vessels and the long osteoblasts on the surface; *d*, tooth sac; *e*, secondary enamel germ. FIG. 170.—*a*, Dental ridge; *b*, enamel organ; *c*, dentine germ; *f*, enamel; *g*, dentine; *h*, interval between enamel organ and the position of the tooth; *k*, layer of odontoblasts.

is directed toward the tooth sac (1), becomes flattened, fuses, undergoes a horny transformation, and becomes the **cuticula**, while the cells which lie between both layers undergo an intermediate metamorphosis, so that they come to resemble the branched stellate cells of the mucous tissue (2), and gradually disappear altogether.

The **dentine** is formed in the most superficial layer of the projecting connective tissue of the dental papilla, owing to the calcification of the continuous layer of odontoblasts which occur there (Figs. 169 and 170, *k*). During the process, fibres or branches of these cells are left unaffected, and remain as the fibres of Tomes. Exactly the same process occurs as in the formation of bone, the odontoblasts forming around themselves a calcified matrix. The **cement** is formed from the soft connective tissue of the dental alveolus.

Dentition.—During the development of the first **temporary** or **milk teeth** a special enamel organ (Fig. 169, *c*) is formed near these, but it does not undergo development until the milk teeth are shed; even the papilla is wanting at first. When the **permanent** tooth begins to develop, it opens into the alveolar wall of the milk teeth from below. The tissue of this dental sac causes erosion, or eating away of the fang and even of the body of the milk teeth, without its blood vessels undergoing atrophy. The chief agents in the absorption are the amœboid cells of the granulation tissue. [Multinuclear giant cells also erode the fangs of the teeth.]

Eruption of the Milk Teeth.—The following is the order in which the twenty milk teeth cut the gum, *i. e.*, from the seventh month to the second year: Lower central incisors, upper central incisors, upper lateral incisors, lower lateral incisors, first molar, canine, the second molars.

[The figures indicate in **months** the period of eruption of each tooth.]

Molars.	Canines.	Incisors.	Canines.	Molars.
24 12	18	9 7 7 9	18	24 12

[The **permanent teeth** succeed the milk teeth, the process beginning about the *seventh year*. Ten teeth in each jaw take the place of the milk teeth, while six teeth appear further back in each jaw. Thus the total number of permanent teeth is thirty-two. As the sacs, from which the permanent teeth are developed, are formed before birth, they merely undergo the same process of development as the temporary teeth, only at a much later period. The last of the permanent molars —the *wisdom tooth*—may not cut the jaw until the *seventeenth to the twenty-fifth year*. At the sixth year the jaw contains the largest number of teeth, as all the temporary teeth are present, and, in addition, the crowns of all the permanent teeth, except the wisdom teeth, making forty-eight in all.]

[**Eruption of Permanent Teeth.**—The age at which each tooth cuts the gum is given in **years** in the following table :—

Molars.	Bicuspid.	Canines.	Incisors.	Canines.	Bicuspid.	Molars.
17 12 to to 6 25 13	10 9	11 to 12	8 7 7 8	11 to 12	9 10	12 17 6 to to 13 25

[**Action of Drugs on the Teeth.**—All the conditions for putrefaction are present in the mouth; and when putrefaction occurs, the products (often acid) attack the dentine and hasten its decay. Hence, the necessity for thorough daily cleansing of the teeth and mouth. The teeth may be cleaned by means of a soft tooth brush and water, with or without the use of any of the numerous dentifrices, such as powdered chalk or charcoal. Astringents, such as catechu and areca-nut, are sometimes used. Mineral acids attack the teeth, and ought, when taken, to be sucked through a tube.]

155. MOVEMENTS OF THE TONGUE.—The **tongue**, being a muscular organ, and extremely mobile, plays an important part in the process of mastication: (1) It keeps the food from passing from between the molar teeth. (2) It forms into a bolus the finely divided food after it is mixed with saliva. (3) When the tongue is raised, the bolus lying on its dorsum is pushed backward into the pharynx and œsophagus.

The **course of the fibres** is threefold—*longitudinally*, from base to tip: *transversely*, the fibres for the most part proceeding outward from the vertically placed septum linguæ; *vertically*, from below upward. Some of the muscles are confined to the tongue (**intrinsic**), while others (**extrinsic**) are attached beyond it to the hyoid bone, lower jaw, the styloid process, and the palate.

Microscopically, the fibres are transversely striated, with a delicate sarcolemma, and very often they are branched where they are inserted into the mucous membrane. The muscular bundles cross each other in various directions, and in the interspaces fat cells and glands occur.

Changes in form and position :—

(1) *Shortening and broadening* by the longitudinal muscle, aided by the hyo-glossus.

(2) *Elongation and narrowing*, by the transversus linguæ.

(3) *The dorsum is rendered concave* by the transversus and the simultaneous action of the median vertical fibres.

(4) *Arching of the dorsum:* (*a*) Transversely by the lowest transverse bundles; (*b*) longitudinally, by the lowest longitudinal muscles.

(5) *Protrusion*, by the genio-glossus, while at the same time the tongue usually becomes narrower and longer (2).

(6) *Retraction*, by the hyo-glossus and stylo-glossus, and (1) usually occurring at the same time.

(7) *Depression* into the floor of the mouth, by the hyo-glossus. The floor of the mouth may be made deeper by depressing the hyoid bone.

(8) *Elevation* of the tongue toward the palate: (*a*) At the tip by the anterior part of the longitudinal fibres; (*b*) in the middle by elevating the entire hyoid bone by the mylo-hyoid (*N. trigeminus*); (*c*) at the root by the stylo-glossus and palato-glossus, as well as indirectly by the stylo-hyoid (*N. facialis*).

(9) *Lateral movements*, the tip of the tongue passing to the right or left; these are caused by the longitudinal fibres of *one* side.

Motor Nerves.—The motor nerve of the tongue is the hypoglossal. When this nerve is divided or paralyzed on one side, the tip of the tongue lying in the floor of the mouth is directed toward the sound side, because the tonus of the non-paralyzed longitudinal fibres shortens the sound side slightly. If the tongue be *protruded*, however, the tip passes toward the *paralyzed* side. This arises from the direction of the genio-glossus (from the middle downward and outward), and the tongue follows the direction of its action. The tongues of animals which have been killed exhibit fibrillar contractions of the muscles, sometimes lasting for a whole day. [Stirling has frequently found nerve ganglia in the nerves of the tongue.]

156. DEGLUTITION.—The onward movements of the contents of the digestive canal are effected by a special kind of action whereby the tube or canal contracts upon its contents, and as this contraction proceeds along the tube, the contents are thereby carried along. This is the "**peristaltic movement**," or peristalsis.

In the first and most complicated part of the act of deglutition, we distinguish in order the following individual movements:—

(1) The aperture of the mouth is closed by the orbicularis oris (*N. facialis*).

(2) The jaws are pressed against each other by the muscles of mastication (*N. trigeminus*), while at the same time the lower jaw affords a fixed point for the action of the muscles attached to it and the hyoid bone.

(3) The tip, middle, and root of the tongue, one after the other, are pressed against the hard palate, whereby the contents of the mouth are propelled toward the pharynx.

(4) When the bolus has passed the anterior palatine arch (the mucus of the tonsillar glands making it slippery again), it is prevented from returning to the mouth by the palato-glossi muscles which lie in the anterior pillars of the fauces, coming together like two side screens or curtains, meeting the raised dorsum of the tongue (Stylo-glossus).

(5) The morsel is now behind the anterior palatine arch and the root of the tongue, and has reached the pharynx, where it is subjected to the successive action of the three pharyngeal constrictor muscles which propel it onward. The action of the superior constrictor of the pharynx is always combined with a horizontal elevation (Levator veli palatini; *N. facialis*) and tension (Tensor veli palatini; *N. trigeminus, otic ganglion*) of the soft palate. The upper constrictor presses (through the pterygo-pharyngeus) the posterior and lateral walls of the pharynx tightly against the posterior margin of the horizontal, tense, soft palate, whereby the margins of the posterior palatine arches (palato-pharyngeus) are approximated. The pharyngo-nasal cavity is thus completely shut off, so that the bolus cannot be pressed backward into the nasal cavity.

In persons with congenital or acquired defects of the soft palate, or **cleft-palate**, during swallowing, food passes into the nose.

(6) Falk and Kronecker assert that, by the energetic contraction of the muscles which diminish the cavity of the mouth, especially the mylo-hyoid, the bolus is "projected" through the pharynx and œsophagus. [They even assert that the bolus reaches the cardia before even the musculature of the pharynx or œsophagus can contract, and further that the pharyngeal muscles of a dog may be divided

without making swallowing impossible.] If we make a series of efforts to swallow, one after the other, as in drinking, contraction of the pharynx and œsophagus takes place only after the *last* effort. Thus each new act of deglutition in the mouth inhibits (by stimulation of the glosso-pharyngeal nerve) the movements in the parts of the œsophageal tube situated below it.

(7) The bolus is propelled onward by the successive contraction of the upper, middle, and lower constrictors of the pharynx until it passes into the œsophagus. At the same time the entrance to the glottis is closed, else the morsel would pass into the larynx, or, as is generally said, would "pass the wrong way."

Duration.—According to Meltzer and Kronecker, the duration of deglutition in the mouth is 0.3 sec.; then the constrictors of the pharynx contract 0.9 sec.; afterward, the upper part of the œsophagus; then after 1.8 sec. the middle; and after another 3 sec. the lower constrictor. The closure of the cardia, after the entrance of the bolus into the stomach, is the final act in the total series of movements.

Sounds during Deglutition.—If the region of the stomach be auscultated during the act of swallowing, two sounds may be heard; the first one is produced when the bolus is projected into the stomach; the second occurs when the peristalsis, which takes place at the end of swallowing, squeezes the contents of the œsophagus through the cardia (*Meltzer, Zenker, Ewald*). [The latter occurs 4–5 mins. afterward. In man, when water alone is swallowed, there is no sound, but when it is mixed with air there is, and it is generally heard because air is usually swallowed with the food or drink (*Quincke*).]

The **closure of the glottis** is effected in the following manner: (*a*) The whole larynx—the lower jaw being fixed—is raised *upward and forward*, while at the same time the root of the tongue hangs over it. The hyoid bone is raised forward and upward by the genio-hyoid, anterior belly of the digastric, and mylo-hyoid; the larynx is approximated close to the hyoid bone by the thyro-hyoid. (*b*) When the larynx is raised, so that it comes to lie below the overhanging root of the tongue, the epiglottis is pressed downward over the entrance to the glottis, and the bolus passes over it. The epiglottis is also pulled down by the special muscular fibres of the reflector epiglottidis and aryepiglotticus. (*c*) The closure of the glottis by the constrictors of the larynx also prevents the entrance of substances into the larynx (§ 313, II, 2).

Injury to the Epiglottis.—Intentional injury of the epiglottis in animals, or its destruction in man, may cause fluids to "go the wrong way," *i. e.*, into the glottis, while solid food can be swallowed without disturbance. In dogs, colored fluids placed on the root of the tongue have been observed to pass directly into the pharynx without coming into contact with it, so as to tinge the upper surface of the epiglottis (*Magendie*). [The basis of the epiglottis is yellow elastic cartilage, so that it shows no tendency to ossify, and always retains its elasticity (§ 313).]

In order that the descending bolus may be prevented from carrying the pharynx with it, the stylo-pharyngeus, salpingo-pharyngeus, and baseo-pharyngeus contract upward when the constrictors act.

Nervous Mechanism.—Deglutition is **voluntary** only during the time the bolus is in the mouth. When the food passes through the palatine arch into the gullet the act becomes **involuntary**, and is, in fact, a well-regulated reflex action. When there is no bolus to be swallowed, voluntary movements of deglutition can be accomplished only within the mouth; the pharynx only takes up the movement, provided a bolus (food or saliva) mechanically excites the reflex act. The **afferent** nerves, which, when mechanically stimulated, excite the involuntary act of deglutition, are, the palatine branches of the trigeminus (from the spheno-palatine ganglion) and the pharyngeal branches of the vagus. The **centre** for the nerves concerned (for the striped muscles) lies in the superior olives of the medulla oblongata. Swallowing can be carried out when a person is unconscious, or after destruction of the cerebrum, cerebellum, and pons (§ 367, 6). [Even in the deep coma of alcoholism, the tube of a stomach pump is carried into the stomach reflexly, provided the surgeon passes it back into the pharynx.] The nerves of the pharynx are derived from the **pharyngeal plexus**, which receives branches from the vagus, glosso-pharyngeal and sympathetic (§ 352, 4).

Within the **œsophagus**, whose stratified epithelium is moistened with the mucus derived from the mucous glands in its walls, the downward movement is involuntary, and depends upon a complicated reflex movement discharged from the centre for deglutition. There is a peristaltic movement of the outer longitudinal and inner circular non-striped muscular fibres.

In the upper part of the œsophagus, which contains striped muscular fibres, the peristalsis takes place more quickly than in the lower part. The movements of the œsophagus never occur independently, but are always the continuation of a foregoing act of deglutition. If food be introduced into the œsophagus through a hole in its wall, there it lies; and it is only carried downward when a movement to swallow is made. The peristalsis extends along the whole length of the œsophagus, even when it is ligatured or when a part of it is removed (*Mosso*). If a dog be allowed to swallow a piece of flesh tied to a string, so that the flesh goes half-way down the œsophagus, and if the flesh be withdrawn, the peristalsis still passes downward (*C. Ludwig and Wild*).

The **motor nerve of the œsophagus** is the vagus (not the accessory fibres) [œsophageal, whose branches have numerous small ganglia in their course]. After it is divided, the food lodges in the lower part of the œsophagus. Very large and very small masses are swallowed with more difficulty than those of moderate size. Dogs can swallow an olive-shaped body weighted with a counterpoise of 450 grammes (*Mosso*). When the thorax is greatly distended, as in Müller's experiment, or greatly diminished, as in Valsalva's experiment (§ 60), deglutition is rendered more difficult.

FIG. 171.



Transverse section of part of the œsophagus.

Goltz's Experiments.—The œsophagus and stomach of the frog become more excitable, *i. e.*, the excitability of the ganglionic plexuses in their walls is increased, when the brain and spinal cord or both vagi are destroyed. These organs contract energetically after slight stimulation, while frogs, whose central nervous system is intact, swallow fluids simply by peristalsis. Females, and sometimes men also, suffering from hysteria, not unfrequently have similar spasmodic contractions of the œsophageal region (globus hystericus). After section of both vagi in the dog, Schiff observed spasmodic contraction of the œsophagus.

Effect on Circulation.—Every time one swallows, the heart's action is accelerated, the blood pressure falls, the necessity for respiration diminishes, while many movements (labor pains, erection) are inhibited. These effects are brought about reflexly (*Kronecker and Meltzer*, § 369).

[**Structure of the Œsophagus.**—The walls of the œsophagus are composed of **four coats**—mucous, sub-mucous, muscular, and fibrous (Fig. 171).

(1) The **mucous coat** is firm, and is thrown into longitudinal folds, which disappear when the tube is distended. It is lined by several layers of **stratified squamous epithelium.** The membrane itself is composed, especially at its inner part, of dense fibrous tissue, which projects, in the form of **papillæ**, into the stratified epithelium. The papillæ are present in the child, but are largest in old people. At its outer part is a continuous longitudinal layer of non-striped muscle, the **muscularis mucosæ.** The layer consists of small bundles of non-striped muscle separate from each other.

(2) The **sub-mucous coat** is thicker than the foregoing, and consists of loose connective tissue, with the acini of small mucous glands imbedded in it. The ducts pierce the muscularis mucosæ to open on the inner surface of the tube.

(3) The **muscular coat** consists of an *inner*, thicker, circular, and an *outer*, thinner, longitudinal layer of non-striped muscle, commencing on a level with the cricoid cartilage. In man the upper third of the gullet consists of striped muscular fibres. (4) Outside the muscular coat is a layer of **fibrous tissue** with elastic fibres. The structure of the muscular coat of the œsophagus varies much in different animals. In the rabbit, in the first quarter of its length, it has two layers, but below this there are three layers, *i. e.*, a circular between an outer and an inner longitudinal layer, while the non-striped fibres are confined to the lowest quarter of the tube.]

[**Nerve Plexuses.**—As in the intestine, there are two plexuses of nerves with ganglia; one in the sub-mucous coat (*Meissner's*) and the other between the two muscular coats (*Auerbach's*), which are continuous with those in the stomach and intestine. Blood vessels and numerous lymphatics lie in the mucous and sub-mucous coats.]

157. MOVEMENTS OF THE STOMACH.—Position.—When the stomach is empty, the great curvature is directed downward and the lesser upward; but when the organ is full, it rotates on an axis running horizontally through the pylorus and cardia, so that the great curvature appears to be directed to the front and the lesser backward.

Arrangement of the Muscular Fibres.—The non-striped muscular fibres of the stomach are arranged in three directions or layers, an outer **longitudinal** continuous with those of the œsophagus. This layer is best developed along the curvatures, especially the lesser. At the pylorus the fibres form a thick layer, and become continuous with the longitudinal fibres of the duodenum. The **circular** fibres form a complete layer; at the pylorus they are more numerous, and constitute the sphincter muscle or **pyloric valve**; while at the cardia (inlet), such a muscular ring is absent. The innermost **oblique** or diagonal layer is complete.

The Movements of the Stomach are of two kinds—(1) The **rotatory** or **churning** movements, whereby the parts of the wall of the stomach in contact with the contents glide to and fro with a slow rubbing movement. Such movements seem to occur periodically, every period lasting several minutes (*Beaumont*). By these movements the contents are moistened with the gastric juice, while the masses of food are partly broken down. The formation of hair balls in the stomach of dogs and oxen indicates that such rotatory movements of the contents of the stomach take place. (2) The other kind of movement consists in a periodically occurring **peristalsis**, whereby, as with a push, the first dissolved portions of the contents of the stomach are forced into the duodenum. They begin after a quarter of an hour, and recur until about five hours after a meal. This peristalsis is most pronounced toward the pyloric end, and the muscles of the pyloric sphincter relax to allow the contents to pass into the duodenum. According to Rüdinger, the longitudinal muscular fibres, when they contract, especially when the pyloric end is filled, may act so as to dilate the pylorus.

Gizzard.—The strongly muscular walls of the stomach of grain-eating birds effect a trituration of the food. The older physiologists found that glass balls and lead tubes, which could be compressed only by a weight of 40 kilos, were broken or compressed in the stomach of a turkey.

Influence of Nerves.—[The stomach is supplied by the vagi and by the sympathetic, the right vagus being distributed to the posterior surface, and the left to the anterior surface, of the organs.] **Auerbach's ganglionic plexus** of nerve fibres and nerve cells, which lies between the muscular coats of the stomach, must be regarded as its proper motor centre, and to it motor impulses are conducted by the vagi. **Section of both vagi** does not abolish, but it diminishes the movements of the stomach. The muscular fibres of the cardia may be excited to action, or their action inhibited by fibres which run in the vagus (Nn. constrictores, et dilatator cardiæ). [If the vagi be divided in the neck, there is a short temporary spasmodic contraction of the cardiac aperture. On stimulating the peripheral end of the vagus with electricity, after a latent period of a few seconds, the cardiac end contracts, more especially if the stomach be distended, but the movements are slight if the stomach be empty. In curarized dogs, the

pylorus contracts with varying intensity, and irregularly whether the vagi and splanchnics be intact or divided. Stimulation of the vagi in the neck causes contraction of the pylorus, when the latent period may be seven seconds. Stimulation of the splanchnics in the thorax arrests the spontaneous pyloric contractions, the left splanchnic being more active than the right (*Oser*).]

Local electrical stimulation of the surface of the stomach causes circular constrictions of the organ, which disappear very gradually, while the movement is often propagated to other parts of the gastric wall. When heated to 25° C., the excised empty stomach exhibits movements. Injury to the pedunculi cerebri, optic thalamus, medulla oblongata, and even to the cervical part of the spinal cord, according to Schiff, causes paralysis of the vessels of certain areas of the stomach, resulting in congestion and subsequent hemorrhage into the mucous membrane. [It is no uncommon occurrence to find hemorrhage into the gastric mucous membrane of rabbits, after they have been killed by a violent blow on the head.]

[**Action of Drugs.**—The *automatic centres are* excited by emetin, apomorphin, tartar emetic, while muscarin causes general contraction of the stomach. The activity of the automatic centres is diminished by chloral, urethan, morphin, and nicotin, while atropin causes paralysis of the nerve endings (*E. Schütz*).]

158. VOMITING.—Mechanism.—Vomiting is caused by contraction of the walls of the stomach, the pyloric sphincter being closed. It occurs most readily when the stomach is distended—(dogs usually greatly distend the stomach by swallowing air before they vomit); it readily occurs in infants, in whom the cul-de-sac at the cardia is not developed. It is quite certain that in children vomiting occurs through contraction of the walls of the stomach, without the spasmodic action of the abdominal walls. When vomiting is violent, the abdominal muscles act energetically. [The act of vomiting is generally preceded by a feeling of nausea, and usually there is a rush of saliva into the mouth, caused by a reflex stimulation of afferent fibres in the gastric branches of the vagus, the efferent nerve for the secretion of saliva being the chorda tympani. After this a deep inspiration is taken and the glottis closed, so that the diaphragm is firmly pressed downward against the abdominal contents, and it is kept contracted; the lower ribs are pulled in. The diaphragm being kept contracted and the glottis closed, a violent expiratory effort is made, so that the contraction of the abdominal muscles acts upon the abdominal contents, the stomach being forcibly compressed. The cardiac orifice is opened at the same time, and the contents of the stomach are ejected. The chief agent seems to be the abdominal compression, but the walls of the stomach also help, though only to a slight extent.]

The contraction of the walls of the stomach, which causes a general diminution of the gastric cavity, is not a true anti-peristalsis, as can be seen in the stomach when it is exposed. The *cardia is opened* by the longitudinal muscular fibres, which pull toward the lower orifice of the œsophagus, so that when the stomach is full they must act as dilators. The act of vomiting is preceded by a ructus-like dilating movement of the intra-thoracic part of the œsophagus, which is caused thus: The glottis is closed, inspiration occurs suddenly and violently, whereby the œsophagus is distended by gases proceding from the stomach. The larynx and hyoid bone, by the combined action of the genio-hyoid, sterno-hyoid, sterno-thyroid, and thyro-hyoid muscles, are forcibly pulled forward, so that the air passes from the pharynx downward into the upper section of the œsophagus. If the abdominal walls contract suddenly, and if this sudden impulse be aided by the movements of the stomach itself, the contents of the stomach are forced outward. During continued vomiting, anti-peristalsis of the duodenum may occur, whereby bile passes into the stomach, and becomes mixed with its contents.

Children, in whom the fundus is absent, vomit more easily than adults. [In them also the nervous system is more excitable.]

Influence of Nerves.—The **centre** for the movements concerned in vomiting lies in the medulla oblongata, and is in relation with the respiratory centre, as is shown by the fact that nausea may be overcome by rapid and deep respirations. In animals, vomiting may be inhibited by vigorous artificial respiration. On the other hand, the administration of certain emetics prevents the occurrence of apnœa.

In vomiting, the **afferent** impulses may be discharged from (1) the mucous

membrane of the soft palate, pharynx, root of the tongue (*glosso-pharyngeal nerve*), as in tickling the fauces with the finger; (2) the nerves of the stomach (*vagus* and *sympathetic*); (3) stimulation of the uterine nerves (pregnancy); (4) the *mesenteric* nerves (inflammation of the abdomen and hernia); (5) nerves of the urinary apparatus (passing a renal calculus); (6) nerves to the liver and gall duct (*vagus*); (7) nerves to the lungs in phthisis (*vagus*). Vomiting is also produced by *direct* stimulation of the vomiting centre. [The **efferent** impulses are carried by the phrenics (diaphragm), vagus (œsophagus and stomach), and intercostals (abdominal muscles).]

Vomiting, produced by the thought of something disagreeable, appears to be caused by the conduction of the excitement from the cerebrum to the vomiting centre. [It may also be excited through the *brain* by a disagreeable smell, shocking sight, or by other impressions on the nerves of special sense.] Vomiting is very common in diseases of the brain [tubercle, inflammation, hemorrhage]. Section of both vagi generally, but not always, prevents vomiting.

Emetics act (1) partly by mechanically or chemically stimulating the ends of the centripetal (afferent) nerves of the mucous membrane. [These are *local* emetics.] Tickling the fauces, touching the surface of the exposed stomach (dog); and many chemical emetics, *e.g.*, mustard, cupric and zinc sulphate, and other metallic salts, act in this way. (2) Other substances cause vomiting when they are introduced into the blood (without being first introduced into the stomach), and act directly upon the vomiting centre, *e.g.*, apomorphin. [These are *general* emetics.] (3) Lastly, there are some substances which act in both ways, *e.g.*, tartar emetic. Emetics may also remove mucus from the lungs, and in this case it is probable that the emetic acts upon the respiratory centre, and so favors the respirations. The *general* emetics usually create considerable depression, while the vomiting lasts longer than with local emetics. The former increase the salivary, gastric, and respiratory secretions.

[**Uses of Emetics.**—Emetics are useful not only for removing from the stomach any offending body, be it a poison or the products of imperfect or perverted gastric digestion, or bile which has passed back into the stomach, but foreign bodies impacted in the œsophagus may be got rid of on exciting vomiting by the subcutaneous injection of apomorphin. As the diaphragm contracts vigorously during vomiting, it compresses the liver, and thus bile is expelled into the duodenum, or the passage of a small calculus along the bile duct may be aided. They also are useful in removing mucus or false membranes from the respiratory passages.]

[**Anti-Emetics.**—Vomiting may be allayed by *local* anti-emetics, such as ice, and many chemical substances, such as bismuth, hydrocyanic acid, opium, and morphia, as well as by *general* remedies which act on the vomiting centre. Some of the foregoing drugs perhaps act both locally and generally.]

Vomiting is analogous to the process of **rumination** in animals that chew the cud (§ 187). Some persons can empty their stomach in this way.

159. MOVEMENTS OF THE INTESTINE.—Peristalsis.—The best example of peristaltic movements is afforded by the small intestine; the progressive narrowing of the tube proceeds from above downward, thus propelling the contents before it. Frequently after death, or when air acts freely upon the gut, the peristalsis develops at various parts of the intestine simultaneously, whereby the loops of intestine present the appearance of a heap of worms creeping among each other. The advance of new intestinal contents again increases the movement. In the large intestine, the movements are more sluggish and less extensive. The peristaltic movements may be seen and felt when the abdominal walls are very thin, and also in hernial sacs. They are more lively in vegetable feeders than in carnivora. The peristalsis is perhaps conducted directly through the muscular substance itself, as in the heart and ureter. The movements of the stomach and intestine cease during sleep (*Busch*).

[**Rate of Motion.**—In a Thiry-Velly fistula (§ 183, II) Fubini estimated the rate of motion of a smooth sphere of sealing wax. It took 55 sec. to travel 1 ctm. [½ in.]; an induction current greatly increases the motion, to 1 ctm. in 10 seconds; NaCl does not affect it, but excites secretion; laudanum paralyzes it.]

Method of Observation.—Open the abdomen of an animal under a .6 per cent. saline solution to prevent the exposure of the gut to air (*Sanders and Braam-Houckgeest*).

The **ileo-colic valve**, as a rule, prevents the contents of the large intestine from passing backward into the small intestine.

When fluid is slowly introduced into the rectum through a tube, it passes upward into the intestine, and even goes through the ileo-colic valve into the small intestine. Muscarin excites very lively peristalsis of the intestines, which may be set aside by atropin (*Schmiedeberg and Koppe*).

Pathological.—When any condition excites an acute inflammation of the intestinal mucous membrane, catarrh is rapidly produced, and very strong contractions of the inflamed parts filled with food take place. When these parts of the gut become empty, the movements are not stronger than normal. If new material passes into the inflamed part, the peristalsis recurs, becomes more lively than normal, and the result is diarrhœa (*Nothnagel*). Sometimes a greatly contracted part of the small intestine is pushed into the piece of gut directly continuous with it, giving rise to **invagination** or intussusception.

Anti-peristalsis, *i. e.*, a movement which travels in an upward direction toward the stomach, does not occur normally. This has been inferred from the fact, that in cases where the intestine is occluded, called ileus, fecal matter is vomited. Nothnagel's experiments throw doubts upon this view, as he failed to observe anti-peristalsis in cases where the intestine was occluded artificially. The fecal odor of the ejecta may result from the prolonged retention of the material within the small intestine.

160. EXCRETION OF FECAL MATTER.—The contents of the small intestine remain in it about three hours, and about twelve hours in the large intestine, where they become less watery, and they assume the characters of fæces,

FIG. 172.



The perinæum and its muscles. 1, anus; 2, coccyx; 3, tuberosity; 4, sciatic ligament; 5, cotyloid cavity; B, bu... cavernosus muscle; Ts, superficial transverse perineal muscle; F, fascia of the deep transverse perineal mus... J, ischio-cavernosus muscle; M, obturator internus; S, external anal sphincter; L, levator ani; P, pyriform...

become "formed" in the lower part of the great intestine. The fæces are gr... ually carried along by the peristaltic movement, until they reach a point a li... above that part of the rectum which is surrounded by both sphincters, the inter... sphincter consisting of non-striped, and the external of striped muscle.

Immediately after the expulsion of the fæces the external sphincter (Fig. 172, S, and Fig. 173) usually contracts vigorously, and remains so for some time. Afterward it relaxes, when the elasticity of the parts surrounding the anal opening, particularly of the two sphincters, suffices to keep the anus closed. In the interval between two evacuations, there does not seem to be a continued tonic contraction of the sphincters. As long as the fæces lie above the rectum, they do not excite any conscious sensations, but the sensation of requiring to go to stool occurs when the fæces pass into the rectum. At the same time, the stimulation of the sensory nerves of the rectum causes a reflex excitement of the sphincters. The centre for these movements (Budge's centrum ano-spinale) lies in the lumbar region of the spinal cord (§ 362); in the rabbit between the sixth and seventh, and in the dog at the fifth lumbar vertebra (*Masius*).

FIG. 173.



Levator ani and sphincter ani externus.

In animals whose spinal cord is divided above the centre, a slight touch in the region of the anus causes this orifice to contract, but after this lively reflex contraction, the sphincters relax again, and the anus may remain open for a time. This occurs because the voluntary impulses which proceed from the brain to cause the contraction of the external sphincter are absent. Landois observed that in dogs with the posterior roots of their lower lumbar and sacral nerves divided, the anus remained open, and not unfrequently a mass of fæces remained half ejected. As the sensibility of the rectum and anus was abolished in these animals, the sphincters could not contract reflexly, nor could there be any voluntary contraction of the sphincters, the result of sensory impulses from the rectum.

The external sphincter can be contracted *voluntarily*, like any voluntary muscle, but the closure of the anus can only be effected up to a certain degree. When the pressure from above is very great, the energetic peristalsis at last overcomes the strongest voluntary impulses. Stimulation of the peduncles of the cerebrum

and of the spinal cord below this point causes contraction of the external sphincter.

Defecation.—The evacuation of the fæces, which in man usually occurs at certain times, begins with a lively peristalsis of the large intestine, which passes downward to the rectum. In order that the mass of fæces may not excite reflexly the sphincter muscles, in consequence of mechanical stimulation of the sensory nerves of the rectum, there seems to be a centre which **inhibits** the reflex action of the sphincters, which is called into play, owing, as it appears, to voluntary impulses. Its seat is in the brain, perhaps in the optic thalami. When this inhibitory apparatus is in action, the fecal mass passes through the anus, without causing it to close reflexely. The strong peristalsis which precedes defecation can be aided, and to a certain degree excited, by rapid voluntary movements of the external sphincter and levator ani, whereby the plexus myentericus of the large intestine is stimulated mechanically, thus causing lively peristaltic movements in the large intestine. The expulsion of the fæces is also aided by the pressure of the abdominal muscles, and most efficiently when a deep respiration is taken, so as to fix the diaphragm, whereby the abdominal cavity is diminished to the greatest extent. The soft parts of the floor of the pelvis, during a strong effort at stool, are driven downward in the form of a cone, causing the mucous membrane of the anus, which contains much venous blood, to be everted. The function of the levator ani (Figs. 172, 173) is to raise voluntarily the soft parts

FIG. 174.



Auerbach's plexus shown in section (human). *a*, ganglionic cells; *b*, nerve fibres; *c*, section of the circular muscular fibres; *d*, longitudinal muscular fibres.

of the floor of the pelvis, and to pull the anus to a certain extent upward over the descending fecal mass. At the same time, it prevents the distention of the pelvic fascia. As the fibres of both levatores converge below, and become united with the fibres of the external sphincter, they aid the latter, during energetic contraction of the sphincter; or, as Hyrtl put it, the levatores are related to the anus, like the two cords of a tobacco pouch. During the periods between the evacuation of the gut, the fæces appear only to reach the lower end of the sigmoid flexure. As a rule, from thence downward, the rectum is normally devoid of fæces. It seems that the strong circular fibres of the muscular coat, which Nélaton has called sphincter ani tertius, when they are well developed, contract and prevent the entrance of the fæces. When the tendency to the evacuation of the rectum is very pressing, the anus may be closed more firmly from without, by energetically rotating the thigh outward, and contracting the muscles of the gluteal region.

161. CONDITIONS INFLUENCING THE INTESTINAL MOVEMENTS.—The intestinal canal contains an *automatic motor centre* within its walls—the **plexus myentericus** of **Auerbach**—which lies between the longitudinal and circular muscular fibres of the gut. It is this plexus which enables the intestine, when cut out of the body, to execute, apparently spontaneously, movements for some time.

[**Structure.—Auerbach's Plexus** consists of non-medullated nerve fibres which form a dense network, groups of ganglion cells occurring at the nodes (Fig. 175, and when seen in vertical sections between the muscular coats it is like Fig. 174). A similar plexus extends throughout the whole intestine between the longitudinal and circular muscular coats from the œsophagus to the rectum. Branches are given off to the muscular bundles. A similar, but not so rich a plexus lies in the submucous coat, **Meissner's plexus**, which gives branches to supply the muscularis mucosæ, the smooth muscular fibres of the villi, and the glands of the intestine (Fig. 176).

1. If this centre is not affected by any stimulus, the movements of the intestine cease—comparable to the condition of the medulla oblongata in apnœa. The same is true—just as in the case of the respiration—during intra-uterine life, in consequence of the fœtal blood being well supplied with O. This condition may be termed **aperistalsis.** It also occurs during sleep, perhaps on account of the greater amount of O in the blood during that state.

FIG. 175.



Plexus of Auerbach, prepared from the small intestine of a dog, by the action of gold chloride. The nerve cells are shown at the nodes, while the fibrils proceeding from the ganglia, and the anastomosing fibres, lie between the muscular bundles.

2. When blood containing the normal amount of blood gases passes through the intestinal blood vessels, the quiet peristaltic movements of health occur (**euperistalsis**) provided no other stimulus be applied to the intestine.

3. All stimuli applied to the plexus myentericus increase the peristalsis, which may become so very violent as to cause evacuation of the contents of the large gut, and may even produce spasmodic contraction of the musculature of the intestine. This condition may be termed **dysperistalsis,** corresponding to dyspnœa. The *condition of the blood* flowing through the intestinal vessels affects the peristalsis.

Condition of the Blood.—Dysperistalsis may be produced by (*a*) interrupting the circulation of the blood in the intestines, no matter whether anæmia (as after compressing the aorta—*Schiff*) or venous hyperæmia be produced. The stimulating condition is the want of O, *i. e.*, the increase of CO_2. Very slight disturbance in the intestinal blood vessels, *e. g.*, venous congestion after copious transfusion into the veins, whereby the abdominal and portal veins become congested, causes

increased peristalsis. The intestines become nodulated at one part and narrow at another, and involuntary evacuation of the fæces takes place when there is congestion, owing to the plugging of the intestinal blood vessels when blood from another species of animal is used for transfusion (§ 102). The marked peristalsis which occurs on the approach of death is undoubtedly due to the derangements of the circulation, and the consequent alteration of the amount of gases in the blood of the intestine. The same is true of the increased movements of the intestines which occur as a result of psychical excitement, *e. g.*, grief. The stimulus, in this case, passes from the cerebrum through the medulla oblongata (vasomotor centre) to the intestinal nerves, and causes anæmia of the intestine (corresponding to the pallor occurring elsewhere). When the normal condition of the circulation is restored, the peristalsis diminishes. (*b*) Direct stimulation of the intestine, conducted to the plexus myentericus, causes *dysperistalsis*; direct exposure of the intestines to the air (stronger when CO_2 or Cl is present)—introduction of various irritating substances into the intestine—increased filling of the intestine when there is any difficulty in emptying the gut (often in man)—direct stimulation of various kinds (also inflammation)—all act upon the intestine, either from without or from within. Induction shocks applied to a loop of intestine in a hernial sac cause lively peristalsis in the hernia. The intestinal movements are favored by heat.

FIG. 176.

Plexus of Meissner. *a*, ganglia; *b*, anastomosing fibres; *c*, artery; *d*, vasomotor nerve fibres accompanying *c*.

4. The continued application of strong stimuli causes the dysperistalsis to give place to rest, owing to over-stimulation, which may be called "**intestinal paresis**," or exhaustion.

This condition is absolutely different from the passive condition of the intestine in aperistalsis. Continued congestion of the intestinal blood vessels ultimately causes intestinal paralysis, *e. g.*, when transfusion of foreign blood causes coagulation within these vessels. Filling the blood vessels with "indifferent" fluids, after the peristalsis has been previously brought about by compressing the aorta, also causes cessation of the movements (*O. Nasse*). The movements cease when the intestines are cooled to 19° C. (*Horwath*), while severe inflammation of the intestine has a similar effect. Under favorable circumstances, the intestine may recover from this condition. Arterial blood admitted into the vessels of the exhausted intestine causes peristalsis, which at first is more vigorous than normal.

5. The continued application of strong stimuli causes **complete paralysis** of the intestine, such as occurs after violent peritonitis, or inflammation of the musculature or mucous coat in man. In this condition, the intestine is greatly distended, as the paralyzed musculature does not offer sufficient resistance to the intestinal gases which are expanded by the heat. This constitutes the condition of **meteorism.**

Influence of Nerves.—With regard to the nerves of the intestine, stimulation of the **vagus** increases the movements (of the small intestine), either by conducting impressions to the plexus myentericus, or by causing contraction of the stomach, which stimulates the intestine in a purely mechannical manner (*Braam-Houckgeest*). The **splanchnic** is (1) the *inhibitory* nerve of the small intestine (*Pflüger*), but only as long as the circulation in the intestinal blood-vessels is undisturbed, and the blood in the capillaries does not become venous; when the latter

condition occurs, stimulation of the splanchnic increases the peristalsis. If arterial blood be freely supplied, the inhibitory action continues for some time. Stimulation of the origin of the splanchnics, of the spinal cord in the dorsal region (under the same conditions), and even when general tetanus has been produced by the administration of strychnia, causes an inhibitory effect. It is inferred that the splanchnic contains (2) inhibitory fibres, which are easily exhausted by a venous condition of the blood, and also *motor fibres*, which remain excitable for a longer time, because after death stimulation of the splanchnics always causes peristalsis, just like stimulation of the vagus. (3) It is the *vasomotor nerve* of the intestinal blood vessels, so that it governs the largest vascular area in the body. When it is stimulated, all the vessels of the intestine which contain muscular fibres in their walls contract; when it is divided, they dilate. In the latter case, a large amount of blood accumulates within the blood vessels of the abdomen, so that there is anæmia of the other parts of the body, which may be so great as to cause death—owing to the deficient supply of blood to the medulla oblongata. (4) It is the *sensory nerve* of the intestine, and, under certain circumstances, it may give rise to very painful sensations.

As stimulation of the splanchnic contracts the blood vessels, von Basch has raised the question whether the intestine does not come to rest, owing to the want of the blood, which acts as a stimulus. But when a weak stimulus is applied to the splanchnic, the intestine ceases to move before the blood vessels contract (*van Braam-Houckgeest*); it would therefore seem that the stimulation diminishes the excitability of the plexus myentericus. According to Engelmann and v. Brakel, the peristaltic movement is chiefly propagated by direct muscular conduction, as in the heart and ureter, without the intervention of any nerve fibres.

[**Effect of Nerves on the Rectum.**—The nervi erigentes, when stimulated, cause the longitudinal muscular fibres of the rectum to contract, while the circular muscular fibres are supplied by the hyposgastric nerves. Stimulation of the latter nerves also exerts an inhibitory effect on the longitudinal muscles. Stimulation of the nervi erigentes inhibits not only the spontaneous movements of the circular fibres of the rectum, but also those movements excited by stimulation of the hypogastric nerves (*Fellner*).]

[**Artificial Circulation in the Intestine.**—Ludwig and Salvioli excised a loop of intestine from an animal, tied a cannula into an artery and another into a vein, and kept it in a warm moist atmosphere. The arterial cannula was connected with a vessel containing defibrinated blood, to which different drugs could be added. A lever rested on the intestine, and registered its movements on a recording surface. As long as arterial blood was transfused, the intestine was nearly quiescent, but when it was arrested, so that the blood became *venous*, a series of contractions occurred. *Nicotin* diminished the flow of blood and quickened the intestinal movements, while at the same time the circular muscular fibres remained contracted or tetanic. *Tincture of opium*, in the proportion of .01 to .04 in the blood, causes at first contraction of the vessels, and lessens the amount of blood circulating in the intestine; but it very rapidly increases—even to six times—the amount of blood which transfuses, while at the same time the movements of the intestine cease, the walls of the intestine being contracted. *Peptone* caused first strong and then irregular contractions.]

Effect of Drugs.—Among the reagents which act upon the intestinal movements are: (1) Such as diminish the excitability of the plexus myentericus, *i. e.*, which lessen or even abolish intestinal peristalsis, *e. g.*, belladonna. (2) Such as stimulate the inhibitory fibres of the splanchnic, and in large doses paralyze them—opium, morphia; 1 and 2 produce constipation. (3) Other agents excite the motor apparatus—nicotin (even causing spasm of the intestine), muscarin, caffein, and many laxatives, which act as purgatives. The movements produced by muscarin are abolished by atropin. These substances accelerate the evacuation of the intestine, and, owing to the rapid movement of the intestinal contents, only a small amount of water is absorbed; so that the evacuations are frequently fluid. (4) Among *purgatives*, colocynth and croton oil act as direct irritants. With regard to drugs of this sort, they seem to cause a watery transudation into the intestine, just as croton oil causes vesicles when applied to the skin. (5) Calomel is said to limit the absorptive activity of the intestinal wall, and to control the decompositions in the intestine. The stools are thin and greenish, from the admixture of biliverdin. (6) Certain saline purgatives—sodium sulphate, magnesium sulphate—cause fluid evacuations by retaining the water in the intestine; and it is said that if they be injected into the blood vessels of animals, they cause constipation. [When a crystal of a *potash salt* is applied to the peritoneal surface of the intestine of an animal, it causes merely a local constriction of the muscular fibres of the gut, while a *sodium salt* excites a contraction which passes upward toward the stomach, and never toward the rectum. In any case it may serve as a useful guide to the surgeon, in determining which is the upper end of a piece of intestine during an operation on the intestines (*Nothnagel*).]

[**Saline Cathartics.**—A salt exerts a genuine excito-secretory action on the glands of the intestines, while at the same time, in virtue of its low diffusibility, it impedes absorption. Thus, between stimulated secretion and impeded absorption there is an accumulation of fluid within the canal, which reaches the rectum and results in purgation. Purgation does not ensue when water is withheld from the diet for one or two days previous to the administration of the salt in a concentrated form. When a concentrated solution of a salt is administered to an animal whose alimentary canal is empty, but whose blood is in a natural state of dilution, the blood becomes rapidly very concentrated, and reaches the maximum of its concentration in from half an hour to an hour and a half; within four hours the blood has gradually returned to its normal state of concentration, without having reabsorbed fluid from the intestine. It apparently recoups itself from the tissue fluids. The salt—sulphate of magnesia or sulphate of soda—becomes split up in the small intestine, and the acid is more rapidly absorbed than the base A portion of the absorbed acid shortly afterward returns to the intestines, evidently through the intestinal glands. The salt does not purge when injected into the blood, and excites no intestinal secretion; nor does it purge when injected subcutaneously, unless on account of its causing local irritation of the abdominal subcutaneous tissue, which acts reflexly on the intestines, dilating their blood vessels, and perhaps stimulating their muscular movements. (*M. Hay*).

162. STRUCTURE OF THE STOMACH.—[The stomach receives the bolus, and secretes a juice which acts on certain constituents of the food, while by its muscular walls it moves the latter within its own cavity, and after a time expels the partially digested products toward the duodenum.]

FIG. 177.

Vertical section of the wall of the human stomach, × 15. *E.*, epithelium; *Gl.*, glands; *Mm.*, muscularis mucosæ.

FIG. 178.

Goblet cells of the stomach.

FIG. 179.

Surface section of the dog's gastric mucous membrane, showing pits, *i*, *i*; *a*, the elevations round *i*, *i*.

Structure.—[The walls of the stomach consist of **four coats**, which are from without inward (Fig. 177)—

(1) The **serous layer**, from the peritoneum.
(2) The **muscular layer**, composed of three layers of non-striped muscular fibres—(*a*) longitudinal, (*b*) circular, (*c*) oblique (§ 15).
(3) The **sub-mucous layer** of loose connective tissue, with the larger blood vessels, lymphatics, and nerves.
(4) The **mucous layer**.]

The well-developed **mucous membrane** of the stomach is thrown into a series of folds or **rugæ**, in a contracted condition of the organ. With the aid of a hand lens, it is seen to be beset with small irregular depressions or *pits* (Fig. 179). Throughout its entire extent it is covered by a single layer of moderately tall, narrow, **cylindrical epithelium**, which seems to consist of **mucous-secreting goblet cells** (Fig. 178). The epithelium is sharply defined at the cardia from the stratified epithelium of the œsophagus, and also at the pylorus, from the true cylindrical epithelium with the striated disk in the duodenum. [The cells contain a plexus of fibrils, and in the passive condition seem to consist of two zones, an outer clear part, next the lumen of the organ, consisting of a substance (mucigen) which yields mucus, the attached end of the cell being granular.] The oval nucleus lies about the centre of the cells. Spindle-shaped, nucleated cells, probably for replacing the others, are said by Ebstein to occur at their bases. All the cells are open at their free ends, so that the mucus is readily discharged, leaving the cells empty. Numerous **tubular glands** of *two* distinct kinds are placed vertically, like rows of test-tubes, in the mucous membrane.

FIG. 180.



I. Transverse section of a duct of a fundus gland—*a*, membrana propria; *b*, mucous-secreting goblet cells; *c*, adenoid interstitial substance. II. Transverse section of a fundus gland—*a*, chief, *h*, parietal cells; *r*, adenoid tissue; *c*, capillaries.

The **cardiac portion** of the gastric mucous membrane consists of a number of microscopic tubular glands placed side by side, the **fundus glands** of Heidenhain, otherwise called peptic, or cardiac. Several gland tubes, which are wider below, usually open into the duct (Fig. 182). Each gland consists of a structureless membrana propria with anastomosing branched cells in relation with it. The **duct** is short, about one-fifth of the whole tube, and is lined by a layer of cells like those lining the stomach, while the **secretory part** of the tubes is lined throughout by a layer of granular, short, small, polyhedral, or columnar nucleated cells. These cells border the very narrow lumen, and are called **principal** (*Heidenhain*), **central** (Fig. 180, II, *a*), or **adelomorphous cells** (ἀδηλος, hidden). At various places, between these cells and the membrana propria, are large, oval, or angular, well-defined, granular, densely reticulated, nucleated cells, the **parietal** cells of Heidenhain, the **delomorphous** cells of Rollett, or the **oxyntic** (acid-forming) cells of Langley (Fig. 180, II, *h*). They are most numerous in the neck of the glands, and least so in the deep blind end of the tubes. These cells are stained deeply by osmic acid and aniline blue, so that they are readily distinguished from the other cells. They bulge out the membrana propria of the gland opposite where they are placed. The parietal cells in man are said to reach to the lumen of the gland tubes (*Stöhr*). Isolated cells are sometimes found under the epithelium of the surface of the stomach, and occasionally in individual pyloric glands. The fundus glands are most numerous (about five millions), and are of considerable size in the fundus.

FIG. 181.



A, Isolated pyloric gland.

2. The **pyloric glands** occur only in the region of the pylorus, where the mucous membrane is more yellowish-white in color (Fig. 181, A). These glands are generally branched at their lower ends, so that several tubes open into a single duct [which, in contradistinction to the duct of the other glands, is wide and long, extending often to half the depth of the mucous membrane. The **duct** is lined by epithelium like that lining the stomach, while the **secretory part** is lined by a single layer of short, finely granular, columnar cells, whose secretion is quite different from that of the cells lining the duct. The lumen is well defined. Nussbaum has occasionally found other cells, which stain deeply with osmic acid, between the base of these. The appearance of the cells differs according to their state of physiological activity (Figs. 183, 184). When they are exhausted they are smaller and more granular, owing to the denser reticulation of their network; at any rate they are granular in preparations hardened in alcohol (Fig. 184). There are no parietal cells.]

FIG. 182.



Vertical section of the gastric mucous membrane. *g*, *g*, pits on the surface; *p*, neck of a fundus gland opening into a duct, *g*; *x*, parietal, and *y*, chief cells; *a*, *v*, *c*, artery, vein, capillaries; *d*, *d*, lymphatics, emptying into a large trunk, *e*.

The glands are supported by very delicate connective tissue mixed with adenoid tissue (Fig. 180). Below this are two layers, circular and longitudinal, of non-striped muscle, the **muscularis mucosæ** (Fig. 177, Mm.), and from it fine processes of smooth muscular fibres pass up between groups of the glands toward the free epithelial surface of the mucous membrane. Perhaps these processes are concerned in emptying the glands. [In the gastric mucous membrane of the cat there is a clear, homogeneous layer, which is stained red by picro-carmine, and placed immediately internal to the muscularis mucosæ. It is pierced by the processes passing from the muscularis mucosæ.]

Masses of **adenoid tissue** occur in the mucous membrane, especially near the pylorus, constituting **lymph follicles**, which are comparable to the solitary glands of the small intestine. **The lymphatics** are numerous, and begin close under the epithelium by dilated extremities or loops (Fig. 182, *d'*); they run vertically, and anastomose in the mucosa between the gland tubes, which they envelop in sinus-like spaces. They join large trunks in the mucosa; another plexus of large vessels exists in the sub-mucosa (*Lovén*).

[**The Nerves.**—A plexus of non-medullated nerve fibres and a few ganglion cells exist in the muscular coat [**Auerbach's**], and another [**Meissner's**] in the sub-mucosa.]

The blood vessels are very numerous. Small arterial branches, *a*, run in the sub-mucosa, and ascend between the glands to form a longitudinal capillary network, *c*,*c*, under the epithelium, and between its meshes the gland-ducts open, *g*. The veins gradually collect from this horizontal capillary network, and run toward the large veins of the sub-mucosa, *v*.

FIG. 183.

Section of the pyloric mucous membrane.

FIG. 184.

Pyloric glands showing changes of the cells during digestion.

163. THE GASTRIC JUICE.—Properties.—The gastric juice is a tolerably clear, colorless fluid, with a strong **acid** reaction, sour taste, and peculiar characteristic odor; it rotates the plane of polarized light to the left. It is not rendered turbid by boiling, and resists putrefaction for a long time. Its specific gravity = 1002.5 (dog, 1005), and it contains only ½ per cent. of solid constituents. The **quantity** secreted in 24 hours was estimated by Beaumont, from observations upon Alexis St. Martin, who had a gastric fistula (1834)—at only 180 grms. daily (!); by Grunewald (1853), in a similar case, as equal to 26.4 per cent. of the body weight; while Bidder and Schmidt (from correspond-

ing observations on dogs) estimated it as equal to 6½ kilos. daily, corresponding to $\frac{1}{10}$ of the body weight. It contains:—

(1) **Pepsin**, the characteristic hydrolytic ferment or enzym, which dissolves proteids. E. Schütz obtained 0.41 to 1.17 per cent. from a fasting person by means of the œsophageal sound.

(2) **Free hydrochloric acid** (*Prout*, 1824), 0.2 to 0.3 (*Richet*, 0.8 to 2.1) per 1000; (in the dog, 0.52 per cent.). It occurs *free*, as the gastric juice always contains more free chlorine than bases, to which it can be united (*C. Schmidt*). Lactic acid is usually met with, but it arises from the fermentation of the carbohydrates of the food.

Tests.—Free hydrochloric acid is detected by the following reactions: 0.025 per cent. solution of **methyl-violet** becomes blue; or alkaline solution of **oo-tropæolin** becomes lilac; or, red Bordeaux wine, treated with amylic alcohol until its color *almost* disappears, becomes rose colored. [Günzburg recommends an alcoholic solution of **phloroglucin-vanillin.** 2 grammes of phloroglucin are mixed with 1 gramme of vanillin in 30 grammes of absolute alcohol, which gives a yellowish-red solution. Concentrated and even very weak mineral acids cause, with this solution, a bright red color with the formation of bright red crystals, while concentrated organic acids do not affect it. For gastric juice mix equal quantities of the filtered gastric juice and the above solution in a watch glass, and evaporate carefully, not allowing it to boil; a red pellicle with red crystals indicates the presence of minute traces of hydrochloric acid. **Congo red**, either in solution or as congo-red papers, becomes blue, but the reaction is interfered with by the presence of ammonia, or ammoniacal salts.]

Lactic Acid.—The freshly prepared blue solution of 10 c. c. of a 4 per cent. solution of carbolic acid, with 20 c. c. of distilled water, and 1 drop of liquor ferri perchloride, is changed to *yellow* by lactic acid (*Uffelmann*).

(3) The large amount of **mucus** covering the surface of the mucous membrane is secreted by the goblet cells of the mucous membrane (§ 162), (§ 136, II).

(4) **Mineral salts** (2 per 1000), and **a milk-curdling ferment.**

They are chiefly sodium and potassium chlorides, less calcic chloride (ammonium chloride, also in animals), and the compounds of phosphoric acid with lime, magnesium and iron.

Among foreign substances, which may be introduced into the body, the following appear in the gastric juice—HI, after the use of potassium iodide—potassium sulphocyanide, ferric lactate, and sugar; and ammonium carbonate in uræmia.

[**Composition of Gastric Juice** (*Hoppe-Seyler*, after *C. Schmidt.*).

Constituents.	I. Human.	II. Dog.	III. Dog.	IV. Sheep.
		With saliva.	No saliva.	
Water,	994.404	971.171	973.062	986.143
Organic matter,	3.195	17.336	17.127	4.055
Free HCl,	0.200	2.337	3.050	1.234
$CaCl_2$,	0.061	1.661	0.624	0.114
NaCl,	1.465	3.147	2.507	4.369
KCl,	0.550	1.073	1.125	1.518
NH_4Cl,		0.537	0.468	0.473
$Ca_3 2(PO_4)$,	0.125	2.294	1.729	1.182
$Mg_3 2(PO_4)$,		0.323	0.226	0.577
$FePO_4$,		0.121	0.082	0.331

Good human saliva is not so dilute or so poor in HCl as I. Szabo has found even 3 of HCl per 1000 in man.]

164. SECRETION OF GASTRIC JUICE.—After the discovery of the two kinds of glands in the stomach and the two kinds of cells in the fundus glands, the question arose as to whether the different constituents of gastric juice were formed by different histological elements.

Changes of the Cells during Digestion.—During the course of digestion, the cells of the fundus (and pyloric glands, dog) undergo important changes (*Heidenhain*). During hunger, the

chief cells are *clear* and large, the parietal investing cells are small, the pyloric cells *clear* and of moderate size. During the first six hours of digestion, the chief cells become *enlarged* and moderately turbid or granular, the parietal cells also *enlarge*, while the pyloric cells remain unchanged. The chief cells become *diminished* and more turbid or granular until the ninth hour, the parietal cells are still swollen, and the pyloric cells enlarge. During the last hours of digestion, the chief cells again become larger and clearer, the parietal cells diminish, the pyloric cells decrease in size and become turbid (Figs. 183 and 184).

[Langley gives a different description of the appearances presented by these cells. The results may be reconciled by remembering that the gland cells were examined under different conditions. The secretory cells consist of a cell substance composed of (*a*) a framework of living protoplasm, either in the form of an intracellular fibrillar network, or in flattened bands. The meshes of this framework enclose at least two chemical substances, viz., (*b*) a hyaline substance in contact with the framework, and (*c*) spherical granules which are embedded in the hyaline substance. During active secretion, the granules decrease in number and size, the hyaline substance increases in amount, the network grows. This is the reverse of what is stated above as the observation of Heidenhain, but the granular appearance described by Heidenhain after secretion is very probably due to the action of the hardening agent, alcohol. Langley found that in the living condition, or after the use of osmic acid, in some animals at least, the chief cells are granular during rest, but during a state of activity two zones are differentiated, an outer one, which is clear, owing to the disappearance of the granules, and an inner more or less granular one. Granules reappear in the outer part after rest. During digestion, the parietal cells increase in size, but do not become granular. In all cells containing much pepsinogen, distinct granules are present, and the quantity of pepsinogen varies directly with the number and size of the granules. In the glands of some animals there is little difference between the resting and active phases. Compare *Serous Glands*, § 143, and *Pancreas*, § 168.]

The **pepsin** is formed in the chief cells (*Heidenhain*). When these are clear and large, they contain much pepsin; when they are contracted and turbid, the amount is small. The pyloric glands are also said to secrete pepsin, but only to a small extent. Pepsin accumulates during the first stage of hunger, and it is eliminated during digestion and also during prolonged hunger. Pepsin, *as such*, is not present within the cells, but only as a "mother substance," a **pepsinogen substance** (**zymogen**), or **pro-pepsin**, which occurs in the granules of the chief cells. This zymogen, or mother substance, by itself, has no effect upon proteids; but if it be treated with hydrochloric acid or sodium chloride, it is changed into pepsin. Pepsin and pepsinogen may be extracted from the gastric mucous membrane by means of water free from acids.

[**Pepsinogen and Pepsin.**—Glycerine extracts very little pepsin from the perfectly fresh gastric mucous membrane, but a large amount is afterward obtained by extracting it with dilute hydrochloric acid, or with this acid and glycerine. The relative amount of pepsinogen and pepsin in a fluid may be determined approximately by the method of Langley and Edkins. A 1 per cent. solution of sodic carbonate exerts a greater destructive action on pepsin than on pepsinogen, while a current of CO_2 destroys pepsinogen to a greater extent than pepsin. Both substances are unaffected by CO, but are destroyed at 54° to 57° C.]

The pyloric glands secrete pepsin, but no acid. Klemensiewicz excised in a living dog the pyloric portion of the stomach, and afterward stitched together the duodenum and the remaining part of the stomach. The excised pyloric part, with its vessels intact, he stitched to the abdominal wall, after sewing its lower end. The animals experimented on died, at the latest, after six days. The secretion of this part was thin, *alkaline*, and contained 2 per cent. of solids, including *pepsin*.

FIG. 185.

Diagram of Klemensiewicz's experiment (*Stirling*)

[**Pyloric Fistula.**—In Fig. 185 P represents the excised pyloric portion, C the cardiac. The parts *a*, *a*, and *a' a'* were then stitched together, and the continuity of the organ established. The lower end (*d'*) of P was closed by sutures, while the edges of P at O were stitched to the abdominal walls, thus making a pyloric fistula.]

In the **frog** the alkaline glands of the œsophagus contain only chief cells which

produce pepsin; while the stomach has glands which secrete acid (and perhaps some pepsin), and are lined by parietal cells.

Among fishes the carps have no fundus glands in the stomach (*Luchau*). [The secreting portions of glands of the cardiac sac (crop) of the herring are lined by a *single* layer of polygonal cells (*W. Stirling*).]

The **hydrochloric acid** is formed, according to Heidenhain, by the parietal cells. It occurs on the free surface of the gastric mucous membrane as well as in the ducts of the fundus glands. The deep parts of the glands are usually alkaline. Free HCl is detected in human gastric juice, within 45 minutes to 1 to 2 hours after a moderate meal, but in 10 to 15 minutes in a fasting condition after drinking water; the amount gradually increases during the process of digestion. Lactic acid, perhaps derived from the food, is found in the stomach immediately after taking food, after half an hour along with HCl, while after an hour only HCl is found (*Ewald and Boas*).

Cl. Bernard injected potassium ferrocyanide and afterward lactate of iron into the veins of a dog. After death, blue coloration occurred only in the *upper acid* layers of the mucous membrane. Nevertheless, we must assume that the hydrochloric acid is secreted in the parietal cells of the fundus of the glands, and that it is rapidly carried to the surface along with the pepsin. Brücke neutralized the surface of the gastric mucous membrane with magnesia usta, chopped up the mucous membrane with water, and left it for some time, when the fluid had again an acid reaction.

As to the **formation of a free acid**, the following statements may be noted: The parietal cells form the hydrochloric acid from the chlorides which the mucous membrane takes up from the blood. According to Voit, the formation of acid ceases, if chlorides be withheld from the food. Maly suggests that the active agent is lactic acid, which splits up sodium chloride and forms free HCl. The base set free is excreted by the urine, rendering it at the same time less acid. The formation of acid is arrested during hunger. According to H. Shultz, watery solutions of alkaline and earthy chlorides are decomposed, even at a low temperature, by CO_2, free hydrochloric acid being formed.

[The source of the HCl is undoubtedly the sodic chloride in the blood and lymph, but what other acid displaces the HCl is a matter of conjecture. In this connection, it is important to remember that Jul. Thomsen has shown that every acid can displace a part of another acid from its combination with its base, and the weaker acid may even combine with the greater part of the base. Thomsen calls this "**avidity.**" Even strong mineral acids may be displaced by weak organic ones. Thus the free CO_2 in the alkaline blood may set free a small quantity of HCl from the sodic chloride. What is still more remarkable is, that the free HCl should be transferred by the cells toward the gland duct, while the sodic carbonate diffuses toward the blood and lymph.]

Secretion.—When the stomach is **empty**, there is usually no secretion of gastric juice; this takes place only after appropriate (mechanical, thermal, or chemical) stimulation. In the normal condition, it takes place immediately on the introduction of food, but also of indigestible substances, such as pebbles. The mucous membrane becomes red, and the circulation more active, so that the venous blood becomes brighter. [That the vagi are concerned in this vascular dilatation, is proved by the fact, that if both nerves be divided during digestion, the gastric mucous membrane becomes pale (*Rutherford*).] The secretion is probably caused reflexly, and the centre perhaps lies in the wall of the stomach itself (Meissner's plexus in the submucous coat). It is asserted that the idea of food, especially during hunger, excites secretion. As yet we do not know the effect produced upon the secretion by stimulation or destruction of other nerves, *e.g.*, vagus, sympathetic. [There is no nerve passing to the stomach, whose stimulation causes a secretion of gastric juice, as the chorda tympani does in the sub-maxillary gland. If the vagi be divided sufficiently low down not to interfere with respiration, the introduction of food still causes a secretion of gastric juice; even if the sympathetic branches be divided at the same time, secretion still goes on (*Heidenhain*). This experiment points to the existence of local secretory centres in the stomach. But there is evidence to show that there is some connection, perhaps indirect, between

the central nervous system and the gastric glands. Richet observed a case of complete occlusion of the œsophagus in a woman, produced by swallowing a caustic alkali. A gastric fistula was made, through which the person could be nourished. On placing sugar or lemon juice in the person's mouth, Richet observed a secretion of gastric juice. In this case no saliva could be swallowed to excite secretion, so that it must have taken place through some nervous channels. Even the sight or smell of food caused secretion. Emotional states also are known to interfere with gastric digestion.]

Effect of Absorption.—Heidenhain isolated a part of the mucous membrane of the *fundus* so as to form a blind sac of it, and he found that mechanical stimulation caused merely a scanty *local* secretion at the spots irritated. If, however, at the same time, absorption of digested matter also occurred, secretion took place over larger surfaces. [He distinguishes a primary and merely local secretion excited by the mechanical stimulus of the ingesta, and a secondary depending on absorption, and extending to the whole of the mucous membrane.]

The statement of Schiff, that active gastric juice is secreted only after absorption of the so-called **peptogenic substances** (especially dextrin), is denied.

The acid contents of the stomach called **chyme**, which pass into the duodenum after gastric digestion is completed, are *neutralized* by the alkali of the intestinal mucous membrane and the pancreatic juice [at the same time, a precipitate is formed and deposited on the walls of the duodenum, and it carries the pepsin down with it]. Part of the pepsin is reabsorbed as such, and is found in traces in the urine and muscle juice (*Brücke*). If the gastric juice be completely discharged externally through a gastric fistula, the alkalinity of the intestine is so strong that the urine becomes alkaline (*Maly*).

The acid gastric juice of the **new-born child** is already fairly active; casein is most easily digested by it, then fibrin and the other proteids (*Zweifel*). When the amount of acid is too great in the stomach of sucklings, large, firm, indigestible masses of casein are apt to be formed, especially after the use of cow's milk (§ 230).

[**Action of Drugs on Gastric Secretion.**—Dilute alkalies, if given before food; saliva; some substances called peptogens by Schiff, such as dextrin and peptones, alcohol and ether, all excite secretion, the last being very powerful. When the secretion is excessively acid, *antacids* are given, some diminishing the acidity in the stomach, as the carbonates and bicarbonates of the alkalies, liquor potassæ, and the carbonate of magnesia; while the citrates and tartrates of the alkalies, becoming converted into carbonates in their passage through the organism, diminish the acidity of the urine.] Small doses of **alcohol**, introduced into the stomach, increase the secretion of gastric juice; large doses arrest it. Artificial digestion is affected by 10 per cent. of alcohol, is retarded by 20 per cent., and is arrested by stronger doses. Beer and wine hinder digestion, and in an undiluted form interfere with artificial digestion.

165. METHODS OF OBTAINING GASTRIC JUICE.—Historical.—Spallanzani caused starving animals to swallow small pieces of sponge enclosed in perforated lead capsules, and after a time, when the sponges had become saturated with gastric juice, he removed them from the stomach. To avoid the admixture of saliva, the sponges are best introduced through an opening in the œsophagus. Dr. Beaumont (1825), an American physician, was the first to obtain human gastric juice, from a Canadian named Alexis St. Martin, who was injured by a gunshot wound, whereby a permanent gastric fistula was established. Various substances were introduced through the external opening, which was partially covered with a fold of skin, and the time required for their solution was noted. Bassow (1842), Blondlot (1843), and Bardeleben (1849), were thereby led to make artificial gastric fistulæ.

Gastric Fistula.—The anterior abdominal wall is opened by a median incision just below the ensiform cartilage, the stomach is exposed, and its anterior wall opened and afterward stitched to the margins of the abdominal walls. A strong cannula is placed in the fistula thus formed. The tube is kept corked. If the ducts of the salivary glands be tied, a perfectly uncomplicated object for investigation is obtained.

According to Leube, dilute human gastric juice may be obtained by means of a siphon-like tube introduced into the stomach. Water is introduced first, and after a time it is withdrawn.

An important advance was made when Eberle (1834) prepared **artificial gastric juice**, by extracting the pepsin from the gastric mucous membrane with dilute hydrochloric acid. Four litres of solution of hydrochloric acid, containing 4 to 8 c.c. HCl per 1000, are sufficient to extract the

chopped-up mucous membrane of a pig's stomach. Half a litre is infused with the stomach and renewed every six hours. The collected fluid is afterward filtered. The substance to be digested is placed in this fluid, and the whole is kept at the temperature of the body, but it is necessary to add a little HCl from time to time (*Schwann*). The HCl may be replaced by ten times its volume of lactic acid and also by nitric acid; while oxalic, sulphuric, phosphoric, acetic, formic, succinic, tartaric, and citric acids are much less active; butyric and salicyclic acids are inactive.

Von Wittich's Method.—(*a*) **Glycerine** extracts pepsin in a very pure form. The mucous membrane is rubbed up with powdered glass until it forms a pulp, mixed with glycerine, and allowed to stand for eight days. The fluid is pressed through cloth, and the filtrate mixed with alcohol, thus precipitating the pepsin, which is washed with alcohol and afterward dissolved in the dilute HCl, to form an artificial digestive fluid. (*b*) Or the mucous membrane may be placed for twenty-four hours in alcohol, and afterward dried and extracted for eight days with glycerine. (*c*) Wm. Roberts has used other agents for extracting enzymes (§ 148).

Preparation of Pure Pepsin.—Brücke pours on the pounded mucous membrane of the pig's stomach a 5 per cent. solution of phosphoric acid, and afterward adds lime-water until the acid reaction is scarcely distinguishable. A copious precipitate, which carries the pepsin with it, is produced. This precipitate is collected on cloth, repeatedly washed with water, and afterward dissolved in very dilute HCl. A copious precipitation is caused in this fluid by gradually adding to it a mixture of cholesterin in four parts of alcohol and one of ether. The cholesterin pulp is collected on a filter, washed with water containing acetic acid, and afterward with pure water. The cholesterin pulp is placed in ether to dissolve the cholesterin, and the ether is then removed. The small watery deposit contains the pepsin in solution.

Pepsin so prepared is a colloid substance; it does not react like albumin with the following tests, viz.: It does not give the xanthroprotein reaction (§ 248), is not precipitated by acetic acid and potassium ferrocyanide, nor by tannic acid, mercuric chloride, silver nitrate, or iodine. In other respects it belongs to the group of albuminoids. It is rendered inactive in an acid fluid by heating it to 55° to 60° C.

166. PROCESS OF GASTRIC DIGESTION.—[In the process of gastric digestion we have to consider—

1. The secretion of gastric juice and its action on food.
2. The absorption of the products of this digestion.
3. The movements of the stomach itself.]

Chyme.—The finely divided mixture of food and gastric juice is called *chyme*. The gastric juice acts upon certain constituents of chyme.

I. Action on Proteids.—Pepsin and the dilute hydrochloric acid, at the temperature of the body, transform proteids into a *soluble* form, to which Lehmann (1850) gave the name of "**peptone**" (§ 249, III). Fibrin (or coagulated proteids) first becomes clear and swollen up.

[It is commonly stated that the first product formed during the gastric digestion of proteids is **syntonin** or **parapeptone**, then **hemi-albumose** or **propeptone**, and finally **peptone**. The products vary, however, with the proteid digested. Kühne has shown that the proteid molecule is split up, and yields two groups, which he calls **anti-peptone** and **hemi-peptone**; the former can be split up into leucin and tyrosin by trypsin, while the latter does not undergo this change. A mixture of the two he calls **ampho-peptone**. The intermediate body or propeptone, is really a mixture of several bodies. Kühne calls it hemi-albumose. These intermediate bodies from albumin are called **albumoses**, from globulins globuloses, from casein caseoses. Halliburton calls all these intermediate bodies "**proteoses.**"]

Properties.—Hemi-albumose, although a composite body, gives the following reactions: It is highly soluble in water; when heated to 50° to 60° it becomes somewhat turbid, but when boiled it becomes clear, and gets turbid again on cooling. This effect is most marked when it is treated with acetic acid and sodic chloride, or the latter alone. It is precipitated by acetic acid and potassic ferrocyanide, but the precipitate disappears on heating and reappears on cooling. It gives the biuret rosy tint reaction like peptones. It is *precipitated by nitric acid*, and the precipitate adheres to the glass, but is *soluble in the acid with the aid of heat*, yielding a yellow fluid, but is *precipitated on cooling*. It is precipitated by boiling with acetic acid and a strong solution of sodic sulphate,

metaphosphoric acid, and pyrogallic acid (*Kühne*). It is said to be present in all animal tissues except muscle and nerve (§ 293).

[**Albumoses** are the first products of the splitting up of proteids by enzymes, and from them peptones are ultimately formed. They may be made from Witte's peptone, or by the peptic digestion of fibrin. Such a mixture, on being neutralized with sodic carbonate, gives a copious precipitate of parapeptones, which can be filtered off, leaving a clear solution of albumoses. On saturating the clear fluid with NaCl, a dense white precipitate, consisting of three albumoses, called **proto-**, **dys-**, and **hetero-albumose** is obtained; a fourth, **deutero-albumose**, remains in solution, but can be precipitated by adding acetic acid. If the albumose precipitate be treated with 10 per cent. NaCl solution, proto- and hetero-albumose are dissolved, leaving dys-albumose undissolved. Dialysis of the saline solution precipitates hetero-albumose, leaving proto-albumose in solution. It is probable, however, that hetero- and dys-albumose are identical, or that the former is merely an insoluble form of the latter. The albumoses are bodies intermediate between albumins and peptones, and of the three, deutero-albumose is nearest to peptones.]

[**Properties.**—**Proto-albumose** is soluble in distilled water, is not changed by heat, but is precipitated by saturation of the solution with sodic chloride, by HNO_3, acetic acid, potassic ferrocyanide, copper sulphate, mercuric chloride. **Deutero-albumose** is very like the foregoing, but it is not precipitated by HNO_3 or on adding sodic chloride to saturation, but precipitation occurs when 20 to 30 per cent. of acetic acid is added. **Hetero-albumose** resembles a globulin in its properties; it is insoluble in distilled water, but is soluble in saline solutions (10 to 15 per cent.), and is partly precipitated from its solution by saturation with NaCl or dialysis. It is coagulated by heat. All give the rosy-pink color with the biuret reaction, and they are all precipitated by saturation with neutral ammonia sulphate, which peptones are not (*Kühne and Chittenden*).]

[**Globuloses** from the globulin of ox serum are obtained in the same way, although the ferment has much less action on globulin than on albumin. Speaking generally, they resemble the albumoses.]

By the continued action of the gastric juice, the propeptone passes into a **true soluble peptone.** The unchanged albumin behaves like an anhydride with respect to the peptone. The formation of peptone is due to the taking up of a molecule of water, under the influence of the hydrolytic ferment pepsin, and the action takes place most readily at the temperature of the body. Gelatin is changed into a *gelatin-peptone*.

According to Kühne, the proteid molecule contains two substances preformed: **anti-albumin** and **hemi-albumin.** Gastric juice at first converts them into **anti-albumose** and **hemi-albumose,** and both ultimately into anti-peptone and hemi-peptone (§ 170, II). Only the latter is split up by trypsin into leucin and tyrosin.

The greater the amount of pepsin (within certain limits), the more rapidly does the solution take place. The pepsin suffers scarcely any change, and if care be taken to renew the hydrochloric acid, so as to keep it at a uniform amount, the pepsin can dissolve new quantities of albumin. Still, it seems that some pepsin is used up in the process of digestion (*Grützner*). Proteids are introduced into the stomach either in a solid (coagulated) or fluid condition. Casein alone of the fluid forms is precipitated or coagulated, and afterward dissolved. The non-coagulated proteids are transformed into syntonin, without being previously coagulated, and are then changed into propeptone and directly peptonized, *i. e.*, actually *dissolved.*

When albumin is digested by pepsin at the temperature of the body, a not inconsiderable amount of **heat disappears,** as can be proved by calorimetric experiment (*Maly*). Hence, the temperature of the chyme in the stomach falls 0°.2 to 0°.6 C. in two to three hours (*v. Vintschgau and Dietl*).

Coagulated albumin may be regarded as the anhydride of the fluid form, and the latter again as the anhydride of peptone. The peptones, therefore, represent the highest degree of hydration of the proteids.

Hence, peptones may be formed from proteids by those reagents which usually cause hydration, viz., treatment with strong acids (from fibrin, with 0.2 HCl), caustic alkalies, putrefactive and various other ferments, and ozone.

The anhydride proteid has been prepared from the hydrated form. Henniger and Hofmeister, by boiling pure peptone with dehydrating substances (anhydrous acetic acid at 80° C.), have succeeded in decomposing it into a body resembling syntonin.

Peptones.—(1) They are completely soluble in water. (2) They diffuse very easily through membranes. (3) They filter quite easily through the pores of animal membranes. (4) They are *not precipitated* by boiling, nitric acid, acetic acid and potassium ferrocyanide, acetic acid and saturation with common salt. (5) They are *precipitated* from neutral or feebly acid solutions by mercuric chloride, tannic acid, bile acids, and phosphoro-molybdic acid. (6) With Millon's reagent they react like proteids, and give a red color, and with nitric acid give the yellow xanthoprotein reaction. (7) With caustic potash or soda and a small quantity of cupric sulphate [or Fehling's solution] they give a beautiful *rosy-red* color, the biuret reaction. (8) They rotate the plane of polarized light to the left.

[Kühne and Chittenden, making use of the fact that ammonium sulphate to saturation precipitates all proteids from solution except peptone, have reinvestigated the subject, and they find that many of the peptones of commerce contain albumoses. Pure peptone has remarkable properties. When dissolved in water, it hisses and froths like phosphoric anhydride, heat is evolved, and a brown solution is formed. It is difficult to preserve it. It is not precipitated by NaCl, or NaCl and acetic acid, but is completely precipitated by phospho-tungstic and phospho-molybdic acids, tannin, iodo-mercuric iodide, picric acid. Peptones have a cheesy taste, while albumin and albumoses are tasteless.]

The biuret reaction is obtained with propeptone, as well as with a form of albumin, which is formed during artificial digestion and is soluble in alcohol. It is called "alkophyr" by Brücke. [Darby's fluid meat gives all the above reactions, and is very useful for studying the tests for peptones.]

The rapidity of solution of fibrin is tested by placing fibrin which is swollen up by the action of 0.2 per cent. HCl in a glass funnel, and adding the digestive fluid, observing the rapidity with which the fluid, the altered fibrin, drops from the funnel, and the fibrin disappears (*Grünhagen*). Or the fibrin may be colored with carmine, swollen up in 0.1 per cent. HCl, and placed in the digestive fluid. The more rapidly the fluid is colored red, the more energetic is the digestion.

Preparation.—Pure peptones are prepared by taking fluid which contains them and neutralizing it with barium carbonate, evaporating upon a water bath, and filtering. The barium is removed from the filtrate by the careful addition of sulphuric acid, and subsequent filtration.

Ptomaines.—Brieger extracted from gastric peptones by amylic alcohol a peptone-free poison, with actions like those of curara. It belongs to the group of *ptomaines, i. e.*, alkaloids obtained from dead bodies or decomposing proteids. [Ptomaines are identical with the alkaloids in plants, and many have been isolated. The term **leucomaine** has been applied by Gautier to alkaloids formed by the decomposition of albuminous bodies during the normal metabolic processes taking place in the tissues. They are not formed by the activity of microörganisms. Some seem to be formed in muscle, and are closely allied to creatin and xanthin.]

Peptones are undoubtedly those modifications of albumin or proteids which, after their absorption from the intestinal canal into the blood, are destined to make good the proteids used up in the human organism. By giving peptones (instead of albumin) as food, life cannot only be maintained, but there may even be an increase of the body weight (*Plósz and Maly, Adamkiewicz*). Very probably, before being absorbed into the blood stream, peptones are re-transformed into serum albumin (§ 192).

Conditions affecting Gastric Digestion.—The presence of already-formed peptones interferes with the action of the gastric juice, in so far as the greater concentration of the fluid interferes with and limits the mobility of the fluid particles. Boiling, concentrated acids, alum, and tannic acid, *alkalinity* of the gastric juice (*e. g.*, by the admixture of much saliva), abolish the action; also sulphurous and arsenious acids and potassic iodide. The salts of the heavy metals, which cause pre-

cipitates with pepsin, peptone, and mucin, interfere with gastric digestion, and so do concentrated solutions of alkaline salts, common salt, magnesium and sodium sulphates. A small quantity of NaCl increases the secretion (*Grützner*) and favors the action of pepsin. Alkalies rapidly destroy pepsin, but less rapidly pro-pepsin (*Langley*). Alcohol precipitates the pepsin, but by the subsequent addition of water it is redissolved, so that digestion goes on as before. Any means that prevent the proteid bodies from swelling up, as by binding them firmly, impede digestion. Slightly over half a pint of cold water does not seem to disturb healthy digestion, but it does so in cases of disease of the stomach. Copious draughts of water, and violent muscular exercise, disturb digestion; while warm clothing, especially over the pit of the stomach, aids it. Menstruation retards gastric digestion. [Oddi finds that the presence of large quantities of ox bile, or even of its own bile in the stomach of a dog, does not affect the activity of the gastric juice, does not precipitate peptones, and does not excite vomiting.]

[**Artificial Digestion.**—The action of gastric juice on proteids may be observed outside the body, and we can prove, as is shown in the following table, after Rutherford, that pepsin and an acid—*e. g.*, hydrochloric, along with water—are essential to the formation of gastric peptones:—

Beaker A.	Beaker B.	Beaker C.
Water. Pepsin, 0.3 per cent. Fibrin.	Water. HCl, 0.2 per cent. Fibrin.	Water. Pepsin, 0.3 per cent. HCl, 0.2 " Fibrin.
Keep all in water bath at 38° C.		
Unchanged.	Fibrin swells up, becomes clear, and is changed into acid albumin or syntonin.	Fibrin ultimately changed into peptone.]

[In all animals, gastric digestion is essentially an **acid** digestion, and between the native proteid, fibrin, albumin, or any other form of proteid, and the end product peptone, there are numerous intermediate substances, many of whose properties and characters have still to be investigated.]

[**Exclusion of the Stomach.**—Ogata finds that if the stomach be divided at the pyloric end so as to exclude the stomach from the digestive apparatus, a dog can be nourished for a long time by introducing food through the pylorus into the duodenum. A dog has lived several years after excision of its stomach (*Czerny*). Raw flesh so introduced is digested more rapidly in the small intestine than in the stomach. The stomach not only digests, but it acts on the connective tissue of flesh so as to prepare the latter for intestinal digestion.]

II. Action on other Constituents of Food.—Milk coagulates when it enters the stomach, owing to the precipitation of the casein, and in doing so it entangles some of the milk globules. During the process of coagulation, heat is given off. The free hydrochloric acid of the gastric juice is itself sufficient to precipitate it; the acid removes from the alkali-albuminate or casein the alkali which keeps it in solution. Hammarsten separated a special ferment from the gastric juice—quite distinct from pepsin—the **milk-curdling ferment** which, quite independently of the acid, precipitates the casein either in neutral or alkaline solutions. It is this ferment or **rennet** which is used to coagulale casein in the making of cheese. [Rennet is an infusion of the fourth stomach of the calf in brine (§ 231). The ferment which coagulates milk is quite distinct from pepsin. If magnesic carbonate be added to an infusion of calf's stomach, a precipitate is obtained. The clear fluid has strongly coagulating properties, while the precipitate is strongly peptic.]

The action of the milk-curdling ferment is, perhaps, like the action of all ferments, a hydration of casein; it is greater in the presence of 0.2 HCl.

One part of the rennet ferment can precipitate 800,000 parts of casein. When casein coagulates, two new proteids seem to be formed—the coagulated proteid which constitutes cheese, and a body resembling peptone dissolved in the whey. The addition of calcium chloride accelerates, while

water retards the coagulation (§ 231) (*Hammarsten*). [A ferment similar to rennet is contained in the seeds of *Withania coagulans* (*S. Lea*).]

Casein is first precipitated in the stomach, then a body like syntonin is formed, and finally peptone. During the process, a substance containing phosphorus and resembling nuclein appears (*Lubavin*).

There is a "**lactic acid ferment**" also present, which changes milk sugar into lactic acid (*Hammarsten*). Part of the milk sugar is changed in the stomach and intestine into grape sugar.

Action on Carbohydrates.—Gastric juice does not act as a solvent of starch, inulin, or gums. Cane sugar is slowly changed into grape sugar. According to Uffelmann, the gastric mucus, and according to Leube, the gastric acid, are the chief agents in this process. **On albuminoids.**—During the digestion of true cartilage, there is formed a chondrin peptone, and a body which gives the sugar reaction with Trommer's test. Perfectly pure elastin yields an elastin peptone, similar to albumin peptone, and hemi-elastin similar to hemi-albumose. A very minute quantity of **fat** is broken up into glycerine and fatty acids. [On neutral olive oil being injected into the stomach of a dog, after several hours—the pylorus being plugged with an elastic bag—it partly splits up and yields oleic acid (*Cash and Ogata*).]

[We still require further observations on the gastric digestion of fats. Richet observed in his case of fistula, that fatty matters remained a long time in the stomach, and Ludwig found the same result in the dog. In some dyspeptics, rancid eructations often take place toward the end of gastric digestion.]

III. Action on the Various Tissues.—(1) The **gelatine-yielding substances** (collagen) of all the connective tissues (connective tissue, white fibro-cartilage, and the matrix of bone), as well as glutin, is dissolved and peptonized by the gastric juice. [**Gelatin**, when acted on by gastric juice, no longer solidifies in the cold, but a *gelatin-peptone* is formed, which is soluble and diffusible, although it differs from true peptone. In the dog, connective tissues are especially acted on in the stomach, while the other parts of organs used as food are prepared for digestion in the small intestine, where the cellular and nuclear elements are digested by the pancreatic juice (*Bikfalvi*).] (2) The **structureless membranes** (membranæ propriæ) of glands, sarcolemma, Schwann's sheath of nerve fibres, capsule of the lens, the elastic laminæ of the cornea, the membranes of fat cells are dissolved, but the true elastic (fenestrated) membranes and fibres are not affected. (3) **Striped muscle**, after solution of the sarcolemma, breaks up transversely into disks, and, like non-striped muscle, is dissolved, and forms a true soluble peptone, but parts of the muscle always pass into the intestine. (4) The albuminous constituents of the soft cellular elements of glands, stratified epithelium, endothelium, and lymph cells, form peptones, but the nuclein of the nuclei does not seem to be dissolved. (5) The **horny parts** of the epidermis, nails, hair, as well as chitin, silk, conchiolin, and spongin of the lower animals are indigestible, and so are amyloid substance and wax. (6) The **red blood corpuscles** are dissolved, the hæmoglobin decomposed into hæmatin and a globulin-like substance; the latter is peptonized, while the former remains unchanged, and is partly absorbed and transformed into bile pigment. **Fibrin** is easily dissolved to form hemi- and anti-peptone. (7) **Mucin**, which is also secreted by the goblet cells of the stomach, passes through the intestines unchanged. (8) **Vegetable fats** are not affected by the gastric juice; these cells yield their protoplasmic contents to form peptones, while the **cellulose** of the cell wall, in the case of man at least, remains undigested (§ 184).

Why the Stomach does not digest itself.—That the stomach can digest *living* things is shown by the following facts: Bernard introduced the leg of a living frog through a gastric fistula into the stomach of a dog. Pavy did the same with the ear of a rabbit, and in both the objects introduced were digested. [Frenzel has modified this experiment, and shown that the legs of a living frog are digested by artificial gastric juice, the tissues being first killed and then digested. His experiments go to show that the alkalinity of the blood is not the protective medium.] The margins of a gastric ulcer and of gastric fistulæ in man are attacked by the gastric juice. John Hunter (1772) discussed the question why the stomach does not digest itself. Not unfrequently after death the posterior wall of the stomach is found digested [more especially if the person die after a full meal and the body be kept in a warm place, whereby the contents of the stomach may escape into the peritoneum. Cl. Bernard showed, that if a rabbit be killed and placed in an oven at the temperature of the body, the walls of the stomach are attacked by its own gastric juice. Fishes also are frequently found with their stomach partially digested after death]. It would seem, therefore, that so long as the circulation continues, the tissues are protected from the action of the acid by the *alkaline* blood; this action cannot take place if the reaction be alkaline (*Pavy*). [This, however, does not explain why the pancreatic juice does not digest the pancreas.] Ligature of the arteries of the stomach causes digestive softening of the gastric mucous membrane. The thick layer of the mucus may also aid in protecting the stomach from the action of its own gastric juice (*Cl. Bernard*).

167. GASES IN THE STOMACH.—The stomach always contains a certain quantity of gas, derived partly from the gases swallowed with the saliva, partly from gases which pass backward from the duodenum.

The air in the stomach is constantly undergoing changes, whereby its O is absorbed by the blood, and for 1 vol. of O absorbed 2 vols. of CO_2 are returned to the stomach from the blood. Hence, the amount of O in the stomach is very small, the CO_2 very considerable (*Planer*).

Gases in the Stomach.—Vol. per cent. (*Planer*).

	Human Subject after Vegetable Diet.		Dog.	
	I.	II.	I. After Animal Diet.	II. After Legumes.
CO_2,	20.79	33.83	25.2	32.9
H,	6.71	27.58	. .	. .
N	72.50	38.22	68.7	66.3
O,		0.37	6.1	0.8

By the acid of the stomach a part of the CO_2 is set free from the saliva, which contains much CO_2 (§ 146). The N acts as an indifferent substance.

Abnormal development of gases in persons suffering from gastric catarrh, occurs when the gastric contents are *neutral* in reaction; during the butyric acid fermentation H and CO_2 are formed; the acetic acid and lactic acid fermentations do not cause the formation of gases. Marsh gas (CH_4) has been found, but it comes from the intestine, as it can only be formed when no O is present (§ 184).

168. STRUCTURE OF THE PANCREAS.—The pancreas is a **compound tubular** gland, and in its general arrangement into lobes, lobules, and system of ducts and acini, it corresponds exactly to the true salivary glands. The epithelium lining the ducts is not at all, or only faintly, striated. The **acini** are tubular or flasked-shaped, and often convoluted. They consist of a membrana propria, resembling that of the salivary glands, lined by a single layer of somewhat cylindrical cells, with a more or less conical apex, directed toward the very narrow lumen of the acini. [As in the salivary glands, there is a narrow **intermediary part** of the ducts opening into the acini, and lined by flattened epithelium.] The **cells** lining the acini consist of **two zones** (Fig. 186):—

FIG. 186.

Section of the fresh pancreas.

FIG. 187.

Changes of the pancreatic cells in various stages of activity. 1, During hunger; 2, in the first stage of digestion; 3, in the second stage; 4, during paralytic secretion.

(1) The smaller outer or **parietal layer** is transparent, homogeneous, sometimes faintly striated, and readily stained with carmine and logwood; and (2) the **inner layer** (Bernard's granular layer) is granular, and stains but slightly with carmine (Fig. 186). It undoubtedly contributes to the secretion by giving off material, the granules being dissolved, while the zone itself becomes smaller. The spherical nucleus lies between the two zones. [The lumen of the acini is very small, and spindle-shaped or branched cells (**centro-acinar cells**) lie in it, and send their processes between the secretory cells, thus acting as *supporting cells* for the elements of the wall of the acini. During

secretion, there is a continuous change in the appearance of the cell substance; the granules of the inner zone dissolve to form part of the secretion; new granules are formed in the homogeneous substance of the outer zone, and pass toward the inner zone (*Heidenhain, Kühne and Lea*).

Changes in the Cells during Digestion.—During the *first* stage (6 to 10 hours) the granular inner zone diminishes in size, the granules disappear, while the striated outer zone increases in size (Fig. 187, 2). In the *second* stage (10 to 20 hours) the inner zone is greatly enlarged and granular, while the outer zone is small (Fig. 187, 3). During hunger the outer zone again enlarges (Fig. 187, 1). In a gland where paralytic secretion takes place, the gland is much diminished in size, the cells are shriveled (Fig, 187, 4) and greatly changed. According to Ogata, some cells actually disappear during secretion.

The axially-placed excretory **duct** consists of an inner thick and an outer loose wall of connective and elastic tissues, lined by a single layer of columnar epithelium. Small mucous glands lie in the largest trunks. Non-medullated **nerves**, with *ganglia* in their course, pass to the acini, but their mode of termination is unknown. The **blood vessels** form a rich capillary plexus round some acini, while round others there are very few. Kühne and Lea found peculiar small cells in groups between the alveoli, and supplied with convoluted capillaries like glomeruli. Their significance is entirely unknown. [They are probably lymphatic in their nature.] The **lymphatics** resemble those of the salivary glands. When a colored injection is forced into the ducts under a high pressure, fine intercellular passages between the secreting cells are formed (*Saviotti's canals*), but they are *artificial* products.]

[**Number of Ducts.**—In making experiments upon the pancreatic secretion, it is important to remember that the number of pancreatic ducts varies in different animals. In man there is one duct opening along with the common bile duct at Vater's ampulla, at the junction of the middle and lower third of the duodenum. The rabbit has two ducts, the larger opening separately about 14 inches (30 to 35 cm.) below the entrance of the bile duct. The dog and cat have each two ducts opening separately.]

Chemistry.—The *fresh* pancreas contains water, proteids, ferments, fats, and salts. In a gland which has been exposed for some time, much leucin, isoleucin, butalin, tyrosin, often xanthin and guanin, are found: lactic and fatty acids seem to be formed from chemical decompositions taking place.

169. **THE PANCREATIC JUICE.—Method.**—Regner de Graaf (1664) tied a cannula in the pancreatic duct of a dog, and collected the juice in a small bag. Other experimenters made a **temporary fistula.** To make a **permanent fistula,** the abdomen is opened (dog), the pancreatic duct pulled forward, and stitched to the abdominall wall, with which it unites. Heidenhain cuts out the part of the duodenum where the duct opens into it, from its continuity with the intestine, and fixes it outside the abdominal wound.

The **secretion** obtained from a **permanent fistula** is a copious, slightly active, watery secretion, containing much sodium carbonate; while the *thick* fluid obtained from the fistula before inflammation sets in, or that from a **temporary fistula,** acts far more energetically. This thick secretion, which is small in amount, is the *normal* secretion. The copious watery secretion is perhaps caused by the increased transudation from the dilated blood vessels (possibly in consequence of the paralysis of the vasomotor nerves). It is, therefore, in a certain sense, a "paralytic secretion" (§ 145). The **quantity** varies much, according as the fluid is thick or thin. During digestion, a large dog secretes 1 to 1.5 gramme of a thick secretion (*Cl. Bernard*). Bidder and Schmidt obtained in twenty-four hours 35 to 117 grammes of a watery secretion per kilo. of a dog. When the gland is not secreting, and is **at rest,** it is soft, and of a pale yellowish-red color, but **during secretion** it is red and turgid with blood, owing to the dilatation of the blood vessels.

The **normal secretion** is transparent, colorless, odorless, saltish to the taste, and has a strong **alkaline** reaction, owing to the presence of sodium carbonate, so that when an acid is added, CO_2 is given off. It contains albumin and alkali-albuminate; it is sticky, somewhat viscid, flows with difficulty, and is coagulated by heat into a white mass. In the cold, there separates a jelly-like albuminous coagulum. Nitric, hydrochloric, and sulphuric acids cause a precipitate; while the precipitate caused by alcohol is redissolved in water. Cl. Bernard found in the pancreatic juice of a dog 8.2 per cent. of organic substances, and 0.8 per cent. of ash. The juice (dog) analyzed by Carl Schmidt contained in 1000 parts:—

Solids, 90.38 in 1000 parts.	Organic,	81.84	*Sodic chloride*,	7.36
	Inorganic,	8.54	" phosphate,	0.45
	(like those of blood serum).		" sulphate,	0.10
			Soda,	0.32
			Lime,	0.22
			Magnesia,	0.05
			Potassic sulphate,	0.02
			Ferric oxide,	0.02

The more rapid and more profuse the secretion, the poorer it is in organic substances, while the inorganic remain almost the same; nevertheless, the total quantity of solids is greater than when the quantity secreted is small (*Bernstein*). Traces of leucin and soaps are present in the fresh juice. [It usually contains few or no structural elements. Any structural elements present in the fresh juice, as well as its proteids, are digested by the peptone-forming ferment of the juice, especially if the latter be kept for some time. If the fresh juice is allowed to stand for some time, and then mixed with chlorine water, a red color is obtained.]

Concretions are rarely formed in the pancreatic ducts; they usually consist of calcic carbonate. Dextrose has been found in the juice in diabetes, and urea in jaundice. Schiff's statement that the pancreas secretes only after the absorption of dextrin, has not been confirmed. The secretory activity of the pancreas is not dependent on the presence of the spleen.

170. ACTION OF THE PANCREATIC JUICE.—The presence of at least **four enzymes**, or hydrolytic ferments, makes the pancreatic juice one of the most important digestive fluids in the body.

I. **Diastatic action** is due to the diastatic ferment, **amylopsin**, a substance which seems to be identical with the saliva ferment; but it acts much more energetically than the ptyalin on saliva, on *raw* starch as well as upon boiled starch; at the temperature of the body the change is effected almost at once, while it takes place more slowly at a low temperature. Glycogen is changed into dextrin and grape sugar; and achroodextrin into sugar. Even cellulose is said to be dissolved, and gum changed into sugar by it, but inulin remains unchanged.

According to v. Mering and Musculus, the starch (as in the case of the saliva, § 148) is changed into **maltose**, and a reducing dextrin; so also is glycogen. Amylopsin changes achroodextrin into maltose; at 40° C. maltose is slowly changed into dextrose, but cane sugar is not changed into invert sugar. The ferment is precipitated by alcohol, while it is extracted by glycerine without undergoing any essential change. All conditions which destroy the diastatic action of saliva (§ 148) similarly affect its action, but the admixture with acid gastric juice (its acid being neutralized) or bile does not seem to have any injurious influence. This ferment is absent from the pancreas of new-born children (*Korowin*).

Preparation.—The ferment is isolated by the same methods as obtain for ptyalin (§ 148); but the tryptic ferment is precipitated at the same time. The addition of neutral salts (4 per cent. solution), *e. g.*, potassium nitrate, common salt, ammonium chloride, increases the diastatic action.

II. **Tryptic action**, or the action on proteids, depends upon the presence of a hydrolytic ferment which is now termed **trypsin** (*Kühne*). Trypsin acts upon proteids at the temperature of the body, when the reaction is *alkaline*, and changes them first into a globulin-like substance, then into propeptone or albumose, and lastly into a *true peptone*, sometimes called tryptone. The albumoses are not so abundant or so easily separated as in gastric digestion (see also p. 293). The proteids do not swell up before they are changed into peptone [but they are eroded or eaten away by the action of the juice]. When the proteid has been previously swollen up by the action of an acid, or when the reaction of the medium is acid, the transformation is interfered with.

Substances yielding gelatin, nuclein, and Hb, resist trypsin; glutin and swollen-up gelatin-yielding substances are changed into gelatin-peptone, but the latter undergoes no further change. Hb-O_2 is split up into albumin and hæmochromogen. In other respects, trypsin acts on tissues containing albumins just like pepsin (§ 166, III).

Trypsin is never absent from the pancreas of **new-born children** (*Zweifel*), and it may be extracted by water, which, however, also dissolves the albumin. Kühne has carefully separated the albumin and obtained the ferment in a pure state. It is soluble in water, insoluble in alcohol. Pepsin and hydrochloric acid together act upon trypsin and destroy it; hence it is not advisable to administer trypsin by the mouth, as it would be destroyed in the stomach. When dried it may be heated to 160° without injury.

Trypsin is formed within the pancreas by a "**mother substance,**" or **zymogen,** taking up oxygen. The zymogen is found in small amount, 6 to 10 hours after a meal, in the inner zone of the secretory cells, but after 16 hours it is very abundant in the inner zone of the cells. It is soluble in water and glycerine. Trypsin is formed in the watery solution from the zymogen, and the same result occurs when the pancreas is chopped up and treated with strong alcohol (*Kühne*). The addition of sodium chloride, carbonate, and glycocholate, favors the activity of the tryptic ferment (*Heidenhain*). [The following facts show that zymogen (ζύμη, ferment), or, as it has been called, **trypsinogen,** is the precursor of trypsin, that it exists in the gland cells, and requires to be acted upon before trypsin is formed. If a glycerine extract be made of a pancreas taken from an animal just killed, and if another extract be made from a similar pancreas which has been kept for 24 hours, it will be found that an alkaline solution of the former has practically no effect on fibrin, while the latter is powerfully proteolytic. If a fresh and still warm pancreas be rubbed up with an equal volume of a 1 per cent. solution of acetic acid, and then extracted with glycerine, a powerfully proteolytic extract is at once obtained. Trypsin is formed from zymogen by the action of acetic acid. There is reason to believe that trypsin is formed from zymogen by oxidation, and that the former loses its proteolytic power after removal of its oxygen. The amount of zymogen present in the gland cells seems to depend upon the number and size of the granules present in the inner granular zone of the secretory cells.]

Further Effects.—When trypsin is allowed to act upon the hemipeptone formed by its own action, the latter is partly changed into the amido-acid, **leucin,** or **amido-caproic acid** ($C_6H_{13}NO_2$), and **tyrosin** ($C_9H_{11}NO_3$), which belongs to the aromatic series (§ 252, IV, 3). Hypoxanthin, xanthin, and aspartic or amido-succinic acid ($C_4H_7NO_4$), are also formed during the digestion of fibrin and gluten, and so are glutamic ($C_5H_9NO_4$) and amido-valerianic acid ($C_5H_{11}NO_2$). *Gelatin* is first changed into a gelatin-peptone, and afterward is decomposed into *glycin* and ammonia.

Putrefactive Phenomena.—If the action of the pancreatic juice be still further prolonged, especially if the reaction be alkaline, a body with a strong, stinking, disagreeable fecal odor, **indol** (C_8H_7N), **skatol** (C_9H_9N), and **phenol** (C_6H_6O), and a substance which becomes red on the addition of chlorine water (*Bernard*), [or it gives with bromine water first a pale red and then a violet tint (*Kühne*),] volatile fatty acids are formed, while, at the same time, H, CO_2, H_2S, CH_4, and N are given off. The formation of indol and the other substances just mentioned depends upon **putrefaction** (§ 184, III). Their formation is prevented by the addition of salicylic acid, or thymol, which kills the organisms upon which putrefaction depends (*Kühne*).

[**Artificial Digestion.**—From fibrin placed in pancreatic juice, or in a 1 per cent. solution of sodium carbonate containing the ferment trypsin, peptones are rapidly formed at 40° C. When we **compare gastric with pancreatic digestion,** we find that the fibrin in pancreatic digestion is eroded, or eaten away, and never swells up. The process takes place in an alkaline medium, and never in an acid one. In fact, a 1 per cent. solution of sodic carbonate seems to play the same part in assisting trypsin that a .2 per cent. solution of HCl does for pepsin in gastric digestion. In gastric digestion acid albumin or *syntonin* is formed in addition to the true peptones. In pancreatic digestion a body resembling *alkali albumin,* which passes into a globulin-like body, and ultimately into a peptone, is formed. Of the peptones so produced, one is called **anti-peptone,** and it is not further changed, but part of the proteid is changed into **hemi-peptone.** This body, when acted upon, yields leucin and tyrosin. When putrefaction takes place, the bodies above mentioned are also formed. We might represent the action of trypsin thus: Proteid + trypsin + 1 per cent. sodium

carbonate, kept at 38° C. = formation of a globulin-like body, and then anti-peptone and hemi-peptone are formed.

ANTI-PEPTONE	HEMI-PEPTONE *yields*		
yields	Normal Digestive Products.	Putrefactive Products.	
undergoes no further change.	Leucin, Tyrosin, Hypoxanthin, Aspartic Acid.	Indol, Skatol, Phenol.	Volatile Fatty Acids, H, CO_2, H_2S, CH_4, N.

It seems that trypsin in pure water can act slowly upon fibrin to produce peptone. Pepsin cannot do this without the aid of an acid.]

[**Kühne's Pancreas Powder.**—This is prepared by the prolonged extraction of fresh pancreas of ox with alcohol and then with ether. If the dry powder be extracted for several hours with a 1 per cent. solution of salicylic acid, and filtered, a fluid with powerful proteolytic, but no diastatic, properties is obtained. Several hours afterward much tyrosin may separate out, which, of course, must be removed by filtration. The clear fluid, when mixed with fibrin and a 1 per cent. solution of sodic carbonate, rapidly digests fibrin. If it be desired to obtain a true pancreatic digestion, with none of the products of putrefaction, the mixture must be strongly "thymolized" with a 25 per cent. alcoholic solution of thymol (*Kühne*).]

[Setschenow finds that egg albumin, boiled in a vacuum at 35°–40° C., is more rapidly digested than fibrin by a specially prepared trypsin.] When proteids are boiled for a long time with dilute H_2SO_4, we obtain peptone, then *leucin* and *tyrosin*; gelatin yields *glycin*. Hypoxanthin and xanthin are obtained in the same way by similarly boiling fibrin, and the former may even be obtained by boiling fibrin with water (*Chittenden*).

It is very remarkable that the juice of the green fruit of the papaya tree, or Carica papaya, possesses digestive properties (*Roy*, *Wittmack*), and that the action is due to peptonizing ferment, closely related to trypsin, and called caricin or **papain**. [It forms a true peptone, an intermediate body, and leucin and tyrosin. It also contains a milk-coagulating ferment (*Martin*).] The milky juice of the fig tree has a similar action. Sprouting malt, vetch, hop, hemp during sprouting, and the receptacle of the artichoke contain a peptonizing ferment. Leucin, tyrosin, glutamic and aspartic acids, and xanthin are formed in the seeds of some plants; hence we may assume that the processes of decomposition in some seeds are closely allied to the fermentative actions that occur in the intestine.

III. **The action on neutral fats** is twofold: (1) It acts upon fats so as to form a **fine permanent emulsion.** (2) It causes neutral fats to take up a molecule of water and **split into glycerine** and their corresponding **fatty acids**:—

$$\underset{\text{Tristearin.}}{(C_{57}H_{110}O_6)} + 3\,\underset{\text{Water.}}{(H_2O)} = \underset{\text{Glycerine.}}{(C_3H_8O_3)} + 3\,\underset{\text{Stearic Acid.}}{(C_{18}H_{36}O_2)}.$$

The latter result is due to the action of an easily decomposable **fat-splitting ferment** (*Cl. Bernard*), also called **steapsin.** Lecithin is decomposed by it into glycero-phosphoric acid, neurin and fatty acids. The fatty acids thus liberated are partly *saponified* by the alkali of the pancreatic and intestinal juices, and partly emulsionized by the alkaline intestinal juice. Both the soaps and emulsions are capable of being absorbed (§ 191).

Emulsification.—The most important change effected on fats in the small intestine is the production of an emulsion, or their subdivision into exceedingly minute particles (§ 191). This is necessary in order that the fats may be taken up by the lacteals. If the fat to be emulsified contain a free fatty acid, *i. e.*, if it be slightly rancid, and if the fluid with which it is mixed be *alkaline*, emulsification takes place extremely rapidly (*Brücke*). A drop of cod-liver oil, which in its unpurified condition always contains fatty acids, on being placed in a drop of 0.3 per cent. solution of soda, instantly gives rise to an emulsion (*Gad*). The excessively minute oil globules that compose the

emulsion are first covered with a layer of soap, which soon dissolves, and in the process small globules are detached from the original oil globules. The fresh surface is again covered by a soap film, and the process is repeated over and over again until an excessively fine emulsion is obtained. If the fat contain much fatty acid, and the solution of soda be more concentrated, "*myelin forms*" are obtained similar to those which are formed when fresh nerve fibres are teased in water. Animal oils emulsionize more readily than vegetable oils; castor oil does not emulsionize (*Gad*). [It is extremely difficult to obtain a perfectly neutral oil, as most oils contain a trace of a fatty acid. In fact, if on adding a weak solution of sodic carbonate to oil or fatty matters, fluid at the temperature of the body, an emulsion is obtained, one may be sure that the oil contained a fatty acid, so that Bernard's view about an "emulsive ferment" being necessary is not endorsed. The fatty acid set free by the fat-splitting ferment enables the alkaline pancreatic juice at once to produce an emulsion.]

Fat-Splitting Ferment.—This is a very unstable body, and must be prepared from the perfectly fresh gland by rubbing it up with powdered glass, glycerine, and a 1 per cent. solution of sodic carbonate, and allowing it to stand for a day or two (*Grützner*). [This ferment is said to cause an emulsion of oil and mucilage tinged blue with litmus at 40° C. to become red (*Gamgee*). In performing this experiment notice that the mucilage is perfectly neutral, as gum arabic is frequently acid.]

[**Pancreatic Extracts.**—The action of the pancreas may be tested by making a watery extract of a perfectly fresh gland. Such an extract always acts upon starch and generally upon fats, but this extract and also the glycerine extract vary in their action upon proteids at different times. If the extract—watery or glycerine—be made from the pancreas of a fasting animal, the tryptic action is slight or absent, but is active if it be prepared from a gland 4 to 10 hours after a meal. The pancreatic preparations of Benger of Manchester, Savory and Moore, or Burroughs and Welcome, all possess active diastatic and proteolytic properties.]

[**Pancreas Salt.**—Prosser-James proposes to employ common salt mixed with pepsin, which he calls peptic salt; and he advocates the use of another preparation composed of the pancreatic ferments and common salt, pancreatic salt.]

The pancreas of **new-born children** contains trypsin and the fat-decomposing ferment, but not the diastatic one (*Zweifel*). A slight diastatic action is obtained after two months, but the full effect is not obtained until after the first year (*Korowin*).

IV. The pancreas contains a **milk-curdling ferment,** which may be extracted by means of a concentrated solution of common salt.

171. THE SECRETION OF THE PANCREATIC JUICE.—Rest and Activity.—As in other glands, we distinguish a quiescent state, during which the gland is soft and pale, and a state of secretory activity, during which the organ swells up and appears pale red. The latter condition only occurs after a meal, and is caused probably reflexly, owing to stimulation of the nerves of the stomach and duodenum. Kühne and Lea found that all the lobules of the gland were not active at the same time. The pancreas of the herbivora secretes uninterruptedly [but in the dog secretion is not constant].

Time of Secretion.—According to Bernstein and Heidenhain, the secretion begins to flow when food is introduced into the stomach, and reaches its maximum 2 to 3 hours thereafter. The amount falls toward the 5th or 7th hour, and rises again (owing to the entrance of the chyme into the duodenum), toward the 9th and 11th hour, gradually falling toward the 17th to 24th hour, until it ceases completely. When more food is taken, the same process is repeated. As a general rule, a rapidly-formed secretion contains less solids than one formed slowly.

Condition of Blood Vessels.—During secretion, the blood vessels behave like the blood vessels of the salivary glands after stimulation of the chorda—they dilate, and the venous blood is bright red—thus, it is probable that a similar nervous mechanism exists [but as yet no such mechanism has been discovered]. The secretion is excreted at a pressure of more than 17 mm. Hg. (rabbit).

Effect of Nerves.—The nerves arise from the hepatic, splenic, and superior mesenteric plexuses, together with branches from the vagus and sympathetic. The secretion is **excited** by stimulation of the medulla oblongata, as well as by direct stimulation of the gland itself by induction shocks. [It is not arrested by section of the cervical spinal cord.] The secretion is **suppressed** by atropin

[in the dog, but not the rabbit], by producing vomiting, by stimulation of the central end of the vagus, as well as by stimulation of other sensory nerves, *e. g.*, the crural and sciatic. Extirpation of the nerves accompanying the blood vessels prevents the above-named stimuli from acting. Under these circumstances, a thin "**paralytic secretion**," with feeble digestive powers, is formed, but its amount is not influenced by the taking of food. [Secretion is excited by the injection of ether into the stomach.]

Extirpation of the gland may be performed, or the duct ligatured in animals, without causing any very great change in their nutrition; the absorption of fat from the intestine does not cease. After the duct is ligatured it may be again restored. Ligature of the duct may cause the formation of cysts in the duct and atrophy of the gland substance. Pigeons soon die after this operation.

[172. **PREPARATION OF PEPTONIZED FOOD.**—Peptonized food may be given to patients whose digestion is feeble (*Roberts*). Food may be peptonized either by peptic or tryptic digestion, but the former is not so suitable as the latter, because in peptic digestion the grateful odor and taste of the food are destroyed, while bitter by-products are formed, so that pancreatic digestion yields a more palatable and agreeable product. As trypsin is destroyed by gastric digestion, obviously it is useless to give extract of the pancreas to a patient along with his food.]

FIG. 188.



Section of human liver, × 20, showing the liver lobules and the radiate arrangement of their cells from the central or intra-lobular vein.

[**Peptonized Milk.**—"A pint of milk is diluted with a quarter of a pint of water and heated to 60° C. Two or three teaspoonfuls of Benger's liquor pancreaticus, together with 10 or 20 grains of bicarbonate of soda, are then mixed therewith." Keep the mixture at 38° C. for about two hours, and then boil it for two or three minutes, which arrests the ferment action.]

[**Peptonized Gruel**, prepared from oatmeal, or any farinaceous food, is more agreeable than peptonized milk, as the bitter flavor does not appear to be developed in the pancreatic digestion of *vegetable* proteids.]

[**Peptonized Milk Gruel** yielded Roberts the most satisfactory results, as a complete and highly nutritious food for weak digestions. Make a thick gruel from any farinaceous food, *e. g.*, oatmeal, and while still hot add to it an equal volume of cold milk, when the mixture will have a temperature of 52° C. (125° F.). To each pint of this mixture add two or three teaspoonfuls of liquor pancreaticus and 20 grains of bicarbonate of soda. It is kept warm for two hours under a "cosey." It is then boiled for a few minutes and strained. The bitterness of the digested milk is almost completely covered by the sugar produced during the process.]

[Peptonized soups and beef tea have also been made and used with success, and have been administered both by the mouth and rectum.]

[Peptonizing powders containing the proper proportions of ferment and sodic bicarbonate are prepared by Benger, and Burroughs and Welcome.]

173. **STRUCTURE OF THE LIVER.**—The **liver**, the largest gland in the body, consists of innumerable small **lobules** or **acini**, 1 to 2 millimetres ($\frac{1}{24}$ to $\frac{1}{12}$ inch) in diameter. These lobules are visible to the naked eye. All the lobules have the same structure.

1. **The Capsule.**—The liver is covered by a thin, fibrous, firmly adherent capsule, which has on its free surface a layer of endothelium derived from the peritoneum. The capsule sends fine septa into the organ between the lobules, but it is also continued into the interior at the transverse fissure, where it surrounds the portal vein, hepatic artery, and bile-duct, and accompanies these structures as the **capsule of Glisson,** or inter-lobular connective tissue. The spaces in which these three structures lie are known as **portal canals.** In some animals (pig, camel, polar bear) the lobules are separated from each other by the somewhat lamellated connective tissue of Glisson's capsule, but in man this is but slightly developed, so that adjoining lobules are more or less fused. Very delicate connective tissue, but small in amount, is also found within the lobules. Leucocytes are sometimes found in the tissue of Glisson's capsule.

2. **Blood Vessels.**—(*a*) Branches of the **Venous System.**—The **portal vein,** after its entrance into the liver at the portal fissure, gives off numerous branches lying **between the lobules,** and ultimately forming small trunks which reach the periphery of the lobules, where they form a rich plexus. These are the **inter-lobular veins** (Figs. 188, 189, *V, i*). From these veins numerous **capillaries**

FIG. 189.



I, Scheme of a liver lobule—*V.i, V.i,* inter-lobular veins (portal); *V.c,* central or intra-lobular vein (hepatic); *c, c,* capillaries between both; *V.s,* sub-lobular vein; *V.v,* vena vascularis; *A, A,* hepatic artery, giving branches, *r, r,* to Glisson's capsule and the larger vessels, and ultimately forming the venæ vasculares at *i, i,* opening into the intra-lobular capillaries; *g,* bile ducts; *x, x,* intra-lobular biliary channels between the liver cells; *d, d,* position of the liver cells between the meshes of the blood capillaries. II, Isolated liver cells—*c,* a blood capillary; *a,* fine bile-capillary channel.

(*c, c*) are given off to the entire periphery of the lobule. The capillaries converge toward the centre of the lobule. As they proceed inward, they form elongated meshes, and between the capillaries lie rows or columns of liver cells (*d, d*). The capillaries are relatively wide, and are so disposed as to lie between the *edges* of the columns of cells, and never between the surfaces of two neighboring cells. The capillaries converge toward the centre of each lobule, where they join to form one large vein, the **intra-lobular, hepatic,** or **central vein** (*V.c*), which traverses each lobule, reaches its surface at one point, passes out, and joins similar veins from other lobules to form the **sub-lobular veins** (*V.s*). These in turn unite to form wide veins, the origins of the **hepatic vein,** which opens into the vena cava inferior.

(*b*) The branches of the **hepatic artery** accompany the branches of the portal vein and bile duct in the portal canals between the lobules, and in their course give off capillaries to supply the walls of the

portal vein and larger bile ducts. The branches of the hepatic artery anastomose frequently where they lie between the lobules. On reaching the periphery of the lobules, a certain number of capillaries are given off, which penetrate the lobule and terminate in the capillaries of the portal vein (*i*, *i*). These capillaries, however, which supply the walls of the portal vein and large bile ducts (*r*, *r*), terminate in veins which end in the portal vein (*V. v*). Several branches—*capsular*—pass to the surface of the liver, where they form a wide-meshed plexus under the peritoneum. The blood is returned by veins, which open into branches of the portal vein.

[**Hepatic Zones.**—Pathologists draw a sharp distinction between different zones within a hepatic lobule. Thus the central area, capillaries and cells, form the **hepatic vein zone,** which is specially liable to cyanotic changes; the area next the periphery of the lobule is the **portal vein zone,** whose

FIG. 190.

Human liver cells containing oil globules, *b*; *d*, has two nuclei.

FIG. 191.

Liver cells after withholding food for 36 hours.

cells under certain circumstances are particularly apt to undergo fatty degeneration; while there is an area lying midway between the two foregoing—the **hepatic artery zone**—which is specially liable to amyloid or waxy degeneration.]

3. **The hepatic cells** (Fig. 189, II, *a*) are irregular polygonal cells of about $\frac{1}{1000}$ of an inch (34 to 45 μ) in diameter (Fig. 190). The arrangement of the capillaries within a lobule determines the arrangement of the liver cells. The liver cells form anastomosing columns which radiate from the centre to the periphery of each lobule (Fig. 191). [The liver cells are usually stated to be devoid of an envelope, although Haycraft states that they possess one. They usually contain a single nucleus,

FIG. 192.



Blood capillaries; finest bile ducts in their relative position in a rabbit's liver.

with one or more nucleoli, but sometimes two nuclei occur. The protoplasm and nucleus of each cell contain a plexus of fibrils just like other epithelial cells. In some animals, globules of oil and pigment granules are found in the cell protoplasm (Fig. 190). Each cell is in relation with the wide-meshed blood capillaries (*d*, *d*), and also with the much narrower meshwork of bile ducts (I, *x*).

Changes in Liver Cells.—The appearance of the cells varies with the period of digestion. During **hunger,** the liver cells are finely granular and very cloudy (Fig. 191) [and contain little glycogen, but many pigment granules, and the nucleus is more frequently absent. Often free nucleoli and pale nuclei are found (*Ellenberger and Baum*). During **activity,** *i. e.*, after a full meal, especially of starchy food, the cells are larger and more distinct, stain more deeply with eosin, and contain fewer granules]. The protoplasm contains coarse, glancing masses of glyocen (Fig. 194, 2), and near the surface of the cell it is condensed, and a fine network stretches toward the centre of the cell, and in it is suspended the nucleus. All the hepatic cells are not in the same phase of activity at the same time. Afanassiew finds that if the formation of bile in the liver be increased (*e. g.*, by section of the hepatic nerves, or feeding with proteids), the cells are moderately enlarged in size, and contain numerous granules, which are proteid in their nature; such cells resist the action of caustic potash. When there is a great formation of glycogen (as after feeding with potatoes and sugar), all the cells are very large and sharply defined, and contain many granules of glycogen, the cells being so large as to compress the capillaries. These cells dissolve quickly in caustic potash.

Action of Drugs.—Some substances excite the cells to activity, and cause them to present the appearance of cells in activity, *e.g.*, pilocarpin, muscarin, aloes, less so salicylate and benzoate of soda and rhubarb, while atropin and lead acetate inhibit the signs of activity. These results were obtained in the horse by Ellenberger and Baum. [Stolnikow, by using the quadruple-staining method of Gaule, finds that the hepatic cells of the frog undergo remarkable changes in **poisoning by phosphorus.** It is well known that this drug produces fatty degeneration of the liver cells, but a deeper study shows that the changes are both histological and chemical. Besides producing remarkable changes in the protoplasm of the cell, the protoplasm of the nucleus, in the form of small

FIG. 193.

Liver cells of frog. *a*, early, and *b*, late stage in poisoning by phosphorus; *c*, liver cell of frog getting water only; *d*, getting sugar, and *e*, peptone (*Stirling, after Stolnikow.*)

masses called plasmosoma, passes out into the cell body, perhaps to renew the latter. The cells are increased in size, both after poisoning with phosphorus and after excision of the fat bodies in the frog (Fig. 193). The fat present in the liver in phosphorus poisoning is not present as droplets of oil, but probably in a loose combination, *e.g.*, lecithin, and as a matter of fact the amount of liver lecithin is extraordinarily increased. There is also an increase of the nuclein; while glycogen is absent. The season of the year also affects them. There is a period of growth from July to November, and one of decay from December to May (*A. Leonard*). **Antipyrin** also produces profound changes, especially in the nuclei.]

4. **The Bile Ducts.**—The finest bile capillaries, channels, or canaliculi arise from the centre of the lobule, and indeed throughout the whole lobule they form a regular anastomosing network of very fine tubes or channels. Each cell is surrounded by a polygonal—usually hexagonal—mesh (Fig. 194, 3). The bile capillaries always lie in the middle of the surface between two adjoining cells (II, *a*), where they form actual **intercellular passages** (Fig. 192). [According to some observers, they are merely excessively narrow channels (1 to 2 μ wide) in the cement substance between the cells, while according to others they have a distinct delicate wall. The bile-capillary network is much closer than the blood-capillary network. [Thus, there are *three* networks within each lobule—

(1) A network of blood capillaries;
(2) " hepatic cells;
(3) " bile capillaries; (Fig. 192).]

FIG. 194.

1, Liver cell during fasting; 2, containing masses of glycogen; 3, a liver cell surrounded with bile channels, from which fine twigs proceed into the cell substance to end in vacuoles.

Excessively minute **intra-cellular passages** are said to pass from the bile capillaries into the interior of the liver cells, where they communicate with certain small cavities or **vacuoles** (*Arp, Kupffer*) (Fig. 194, 3). As the blood capillaries run along the edge of the liver cells, and the bile capillaries between the opposed surfaces of adjacent cells, the two systems of canals within the

lobule are kept separate. Some bile capillaries run along the edges of the liver cells in the human liver, especially during embryonic life. Toward the peripheral part of the lobule, the bile capillaries are larger, while adjoining channels anastomose, and leave the lobule, where they become **inter-lobular ducts** (*g*), which join with other similar ducts to form larger inter-lobular bile ducts. These accompany the hepatic artery and portal vein, and leave the liver at the transverse fissure. The *finer* inter-lobular ducts frequently anastomose in Glisson's capsule, possess a structureless basement membrane, and are lined by a single layer of low polyhedral epithelial cells. The *larger* inter-lobular ducts have a distinct wall, consisting of connective and elastic tissue, mixed with circularly disposed smooth muscular fibres (Fig. 195). Capillaries are supplied to the wall, which is lined by a single layer of columnar epithelium. A sub-mucosa occurs only in the largest bile ducts, and in the gall bladder. Smooth muscular fibres, arranged in single bundles, occur in the largest ducts, and as longitudinal and circular layers in the gall bladder, whose mucous membrane is provided with numerous folds and depressions. The epithelium lining the gall bladder is cylindrical, with a distinct, clear disk, and between these cells are goblet cells. Small branched tubular **mucous glands** occur in the larger bile ducts and in the gall bladder.

FIG. 195.

Inter-lobular bile duct (human).

Vasa aberrantia are isolated bile ducts which occur on the surface of the liver, but have no relation to any system of liver lobules. They occur at the sharp margin of the liver, in the region of the inferior vena cava, of the gall bladder, and of the parts near the portal fissure. It seems that the liver lobules to which they originally belonged have atrophied and disappeared (*Zuckerkandl and Toldt*).

5. **The lymphatics** begin as *pericapillary* tubes around the capillaries within the lobules, emerge from the lobule, and run *within* the wall of the branches of the hepatic and portal veins, and afterward surround the venous trunks, thus forming the *inter-lobular* lymphatics. These unite to form larger trunks, which leave the liver partly at the portal fissure, partly along with the hepatic veins, and partly at different points on the surface of the organ. There is a narrow, superficial meshwork of lymphatics under the peritoneum—*sub-peritoneal*—which communicate with the thoracic lymphatics, through the triangular ligament and suspensorium, while on the under surface they communicate with the lymphatics of the inter-lobular connective tissue.

6. **The nerves** consist partly of medullated and partly of non-medullated fibres from branches of the sympathetic and left vagus to the hepatic plexus. They accompany the branches of the hepatic artery, and *ganglia* occur on their branches within the liver. Some of the nerve fibres are vasomotor in function, and, according to Pflüger, other nerve fibres terminate directly in connection with liver cells. [MacCallum describes an inter-lobular plexus of non-medullated fibres in man and menobranchus, from which a perivascular and inter-cellular plexus proceeds. From the latter fibrils pass to terminate within the cells near the nucleus.]

Pathological.—The connective tissue between the lobules may undergo great increase in amount, especially in alcohol and gin drinkers, and thus the substance of the lobules may be greatly compressed, owing to the cicatricial contraction of the newly-formed connective tissue (cirrhosis of the liver). In such inter-lobular connective tissue, newly-formed bile ducts are found.

Ligature of the ductus choledochus [causes enlargement of the spleen (rabbit), and a diminution in the number of the blood corpuscles], and, after a time, interstitial inflammation of the liver. In rabbits and guinea pigs the liver parenchyma disappears, and its place is taken by newly-formed connective tissue and bile ducts (*Charcot and Gombault*). In all these cases of interstitial inflammation, there is proliferation of the epithelium of the bile ducts.

[**Regeneration of the Liver.**—Tizzoni finds that there may be partial regeneration and new formation of liver lobules in the dog, the process being the same as that which occurs in the embryonic development of the organ, *i. e.*, the growth of solid cylinders of liver cells, formed by the preëxisting liver cells, which penetrate into the connective tissue uniting the edges of the wound. These cells ultimately differentiate into hepatic cells and bile ducts. Other observers attribute the new formation to outgrowths of the epithelial cells of the bile cells.]

174. CHEMICAL COMPOSITION OF THE LIVER CELLS.—(1) Proteids.—The fresh, soft, parenchyma of the liver is *alkaline* in reaction; after death, coagulation occurs, the cell contents appear turbid, the tissue becomes friable, ıally an acid reaction is developed. This process closely resembles what ·. and is due to the coagulation of a myosin-like body, which is but after death undergoes spontaneous coagulation (*Plósz*). :r proteids; one coagulating at 45° C., another at 70° C.,

and one which is slightly soluble in dilute acids and alkalies. The nuclei contain nuclein. The connective tissue yields gelatin.

(2) **Glycogen or Animal Starch**—1.2 to 2.6 per cent.—is a true carbohydrate most closely related to inulin, soluble in water, but diffuses with difficulty, and has the formula $6(C_6H_{10}O_5) + H_2O$. It is stored up in the liver cells in amorphous granules around the nuclei (Fig. 194, 2), but is not uniformly distributed in all parts of the liver. Like inulin, it gives a deep red color with solution of iodine in iodide of potassium. It is changed into dextrin and sugar by diastatic ferments, and when boiled with dilute mineral acids, it yields grape sugar (§ 148, I; § 170, I; § 252, III).

Preparation of Glycogen.—[Feed a rabbit on carrots or boiled rice, and kill it three or four hours thereafter. Remove the liver immediately after death, cut it into fine pieces, and place these in *boiling* water, and boil it for some time in order to obtain a watery extract of the liver. The boiling water destroys the ferment supposed to be present in the liver, which would transform the glycogen into grape sugar. To the cold filtrate are added alternately dilute hydrochloric acid and potassio-mercuric iodide, which precipitates the proteids. Filter, when a clear **opalescent fluid**, containing the glycogen in solution, is obtained. The glycogen is precipitated from the filtrate, as a white amorphous powder, on adding an excess of 70 to 80 per cent. alcohol. The precipitate is washed with 60 per cent. and afterward with 95 per cent. alcohol, then with ether, and lastly, with absolute alcohol; it is dried over sulphuric acid and weighed (*Brücke*). Külz modifies the method somewhat. After boiling the liver for half an hour, it is rubbed up with liquor potasse (100 grms. liver, 4 grms. KHO). Evaporate in the water bath until all is dissolved, which occurs in about 3 hours. After cooling, neutralize with HCl and precipitate the proteids as above. F. Eves asserts that the *post-mortem* conversion of sugar in the liver is not attributable to a ferment action, and the rapid appearance of sugar in the liver after death is due to the specific metabolic activity of the dying cells.]

Sources.—The "**mother substance**" of the glycogen of the liver has been variously stated to be the carbohydrates of the food (*Pavy*); fats (olive oil, *Salomon*); glycerine, taurin, and glycin (the latter splitting into glycogen and urea), the proteids (*Cl. Bernard*); and gelatin (*Salomon*). If it is derived from the albumins, it must be formed from a non-nitrogenous derivative thereof.

Rohmann found that the use of ammonia carbonate and asparagin or glycin, along with a carbohydrate diet, in rabbits considerably increased the formation of glycogen. The excessive formation of acid observed by Stadelmann in diabetes unites with the ammonia and diminishes considerably the formation of glycogen.

Effects of Food.—Rabbits, whose livers have been rendered free from glycogen by starvation, yield new glycogen from their livers when they are fed with cane sugar, grape sugar, maltose, or starch. Forced muscular movements soon make the liver of dogs free from glycogen, exposure to cold diminishes its amount. Dextrin and grape sugar occur in the dead liver, but, in addition, some glycogen is found for a considerable time after death in the liver and in the muscles.

If glycogen is injected into the blood, achroodextrin appears in the urine, and also hæmoglobin, as glycogen dissolves red blood corpuscles. Ligature of the bile duct causes decrease of the glycogen in the liver.

Other Situations.—Glycogen is not confined to the liver cells; it occurs during fœtal life in all the tissues of the body of the embryo [including the embryonic skeleton], in young animals (*Kühne*), the placenta (*Bernard*). [It occurs in large amount in the liver during intra-uterine life.] In the adult it occurs in the testicle, in the muscles (*MacDonnel, O. Nasse*), in numerous pathological products, in inflamed lungs (*Kühne*), and also in the corresponding tissues of the lower animals. It also occurs in the chorionic villi, in colorless blood corpuscles, in fresh pus cells which still exhibit amœboid movements, and in fact in all developing animal cells, with amœboid movement; it is a never failing constituent in cartilage, and in the muscles and liver of invertebrata, such as the oyster. There is none in the fresh brain of the dog or rabbit, but it is found in the brain in diabetic coma (*Abeles*).]

Modifying Conditions.—If large quantities of starch, milk-, fruit-, or cane-sugar, or glycerine, but not mannite, or glycol, or inosite, be added to the proteids of the food, the amount of glycogen in the liver is very greatly increased (to 12 per cent. in the fowl), while a purely albuminous or purely fatty diet diminishes it enormously. During hunger it almost disappears. The injection of dissolved carbohydrates into a mesenteric vein of a starving rabbit causes the liv viously free from glycogen to contain glycogen.

[**Effect of Drugs.**—Arsenic, phosphorus and antimony destroy the glycogenic function of the liver, no glycogen being present in the liver in animals poisoned with these drugs, so that puncture of the floor of the fourth ventricle no longer causes glycosuria in them. In animals poisoned by strychnia or curara, it is greatly diminished, both in the liver and in the muscles. Sugar is always present in the urine in the latter case but not in the former.]

During life, under normal conditions, the glycogen in the liver is either not transformed into grape sugar (*Pavy*), or, what is more probable, only a very small amount of it is so changed. The normal amount of sugar in blood is 0.5 to 1 per 1000, although the blood of the hepatic vein contains somewhat more. A considerable amount is transformed into sugar only when there is a decided derangement of the hepatic circulation, and in these circumstances the blood of the hepatic vein contains more sugar. The glycogen undergoes this change very rapidly after death, so that a liver which has been dead for some time always contains more sugar and less glycogen.

The diastatic ferment in the liver is small in amount, and can be obtained from the extract of the liver cells by the same means as are applicable for obtaining other similar ferments, such as ptyalin; but it does not seem to be formed within the liver cells, but only passes very rapidly from the blood into them. The ferment seems to be rapidly formed when the blood stream undergoes considerable derangement. A similar ferment is formed when red blood corpuscles are dissolved (*Tiegel*), and, as red blood corpuscles are continually destroyed within the liver, there is one source from which the ferment may be formed, whereby minute quantities of sugar would be continually formed in the liver.

According to Seegen, the **blood of the hepatic vein** contains twice as much sugar (0.23 per cent.) as that in the portal vein (0.119 per cent.); observations on dogs showed that the blood flowing through the liver gives up over 400 grms. sugar in 24 hours. Hence, in carnivora, the greatest part of the C of the animal food must pass into sugar, so that the formation of sugar in the liver, and its decomposition in the blood, or in the organs traversed by the blood, must be a very important function of the metabolism. Seegen is also of opinion that the liver glycogen takes no part in the formation of sugar in the liver.

[Blood when perfused through a freshly excised liver (or through the kidneys, lungs, or muscles), gains lactic acid (*G. Aglio and Wissokowitsch*).]

(3) **Fats**, in the form of highly refractive granules, occur in the liver cells, as well as free in the bile ducts; sometimes, when the food contains much fat (more abundant in drunkards and the phthisical), olein, palmatin, stearin, volatile fatty acids, and sarcolactic acid are found.

There are also found traces of cholesterin, minute quantities of urea, uric acid, and the little-known body jecorin. [**Jecorin**, discovered by Drechsel, contains S and P, and reduces alkaline solutions of copper like grape sugar. It is also found in the spleen, muscles, and blood (*Baldi*). The liver of birds contains a relatively large amount of uric acid, even 6 to 14 times as much as the blood (*v. Schræder*).] [Leucin (? guanin), sarkin, xanthin, cystin, and tyrosin occur pathologically in certain diseases where marked chemical decompositions occur.]

[**Fatty Degeneration and Infiltration.**—Fatty granules are of common occurrence within the cells of the liver, constituting fatty infiltration, and when not too numerous do not seem to interfere greatly with the functions of the liver cells. Fatty particles occur if too much fatty food be taken, and they are commonly found in the livers of stall-fed animals; the well-known *pâté-de-foi gras* is largely composed of the livers of geese, which have been fed on large amounts of farinaceous food, and which have been subjected to other unfavorable hygienic conditions. Fatty granules are recognized by their highly refractive appearance, by their solubility in ether, and by being blackened by osmic acid.]

(4) The **inorganic substances** in the human liver are—potassium, sodium, calcium, magnesium, iron, manganese, chlorine, and phosphoric, sulphuric, carbonic, and silicic acids; while copper, zinc, lead, mercury, and arsenic may be accidentally deposited in the hepatic tissue.

Tizzoni's Reaction.—If a section of a liver (especially of a young animal) hardened in alcohol be treated with a solution of potassic ferrocyanide, and then with dilute hydrochloric acid, as a general preparation becomes blue, even to the naked eye; but failing that, one can usually see with ranules of Prussian blue in the protoplasm of the cells, indicating the presence of free

175. DIABETES MELLITUS AND GLYCOSURIA.—[**Glycosuria** is characterized by the presence of **grape sugar** in the urine. According to Brücke a *trace* of sugar exists normally in urine, and when this amount is increased we have glycosuria. When the normal amount of grape sugar in the blood is increased, grape sugar appears in the urine. In **diabetes mellitus**, grape sugar also appears in the urine, but this is really a serious disease, involving the alteration of many tissues, and distinguished by profound disturbance of the whole metabolic activity, which leads to numerous pathological changes and often to death. The appearance of grape sugar in urine does not necessarily mean that a person is suffering from this disease.]

The formation of large quantities of grape sugar by the liver, and its passage into the blood, and from the blood into the urine, constitute glycosuria. Extirpation of the liver in frogs, or destruction of the hepatic cells, as by fatty degeneration from poisoning with phosphorus or arsenic, does not cause this condition. It occurs for several hours after the injury of a certain part—the centre for the hepatic vasomotor nerves—of the *floor of the lower part of the fourth ventricle* (*Cl. Bernard's* "piqûre"); also after section of the vasomotor channels in the spinal cord, from above down as far as the exit of the nerves for the liver, viz., to the lumbar region, and in the frog to the fourth vertebra (*Schiff*). When the vasomotor nerves, which proceed from this centre to the liver, are cut or paralyzed in any part of their course, melliturıa or glycosuria is produced. All the nerve channels do not run through the spinal cord alone. A number of vasomotor nerves leave the spinal cord higher up, pass into the sympathetic, and thus reach the liver; so that destruction of the superior (*Pavy*), as well as of the inferior cervical sympathetic ganglion, and the first thoracic ganglion (*Eckhara*) of the abdominal sympathetic, and often of the splanchnic itself produces it. The paralysis of the blood vessels causes the liver to contain much blood, and the intra-hepatic blood stream is slowed. The disturbance of the circulation causes a great accumulation of sugar in the liver, as the blood ferment has time to act upon the glycogen and transform it into sugar. By stimulation of the sympathetic at the lowest cervical and first thoracic ganglion, the hepatic vessels at the periphery of the liver lobules become contracted and pale (*Cyon*). It is remarkable that glycosuria when present may be set aside by section of the splanchnic nerves. This is explained by supposing that the enormous dilatation and congestion, or the hyperæmia of the abdominal blood vessels thereby produced, renders the liver anæmic.

Continued stimulation of peripheral nerves may act *reflexly* upon the centre for the vasomotor nerves of the liver. Diabetes has been observed to occur after stimulation of the central end of the vagus (*Cl. Bernard*), and also after stimulation of the central end of the depressor nerve (*Filehne*). Even section and subsequent stimulation of the central end of the sciatic nerve causes diabetes. This may explain the occurrence of diabetes in people who suffer from sciatica. [It may occur also after perverted nervous activity, as psychical excitement, neuralgias (sciatica, trigeminal or occipital), concussion of the brain, as well as after certain injuries to the skull and vertebral column and some cerebral diseases.]

According to Schiff, the stagnation of blood in other vascular regions of the body may cause the ferment to accumulate in the blood to such an extent that diabetes occurs. The glycosuria that occurs after compression of the aorta or portal vein may perhaps be ascribed to this cause, but perhaps the pressure caused by these procedures may paralyze certain nerves. According to Eckhard, injury to the vermiform process of the cerebellum of the rabbit causes diabetes. In man, affections of the above-named nervous regions cause diabetes.

[In most individuals the use of a large quantity of sugar in the food is not followed by the appearance of sugar in the urine; but in some exceptional cases it is often present, *e. g.*, in persons suffering from gastric catarrh, especially if they are gouty.]

A number of **poisons** which paralyze the hepatic vasomotor nerves produce diabetes; curara (when artificial respiration is not maintained), CO, amyl nitrite, ortho-nitro-propionic acid, and methyl-delphinin; less certainly morphia, chloral hydrate, HCN, and some other drugs; [phlorizin (*v. Mering*)]; and some infectious diseases. But congestion of the liver produced in other ways appears to cause diabetes, *e. g.*, after mechanical stimulation of the liver. To this class belongs the injection of

dilute saline solutions into the blood (*Bock, Hoffmann*), whereby either the change in form or the solution of the colored blood corpuscles causes the congestion. The circumstance that repeated blood letting makes the blood richer in sugar, may perhaps be explained by the slowing of the circulation.

[Most of the means which produce glycosuria in other animals fail to do so in birds; even the piqûre rarely produces it. This Thiel and Minkowski attribute to the intensely active oxidation processes in birds. Phlorizin causes glycosuria, even after extirpation of the liver, which shows that in these cases there are other causes at work that obtain in the forms of glycosuria.] Phlorizin makes animals which are free from carbohydrates diabetic. In this case the sugar must be derived from proteids (*v. Mering*).

Theoretical.—In order to explain the more immediate cause of these phenomena several hypotheses have been advanced:—

(*a*) The liver glycogen may be transformed unhindered into sugar, as the blood in its passage through the liver deposits or gives up the ferment to the liver cells. So that the normal function of the vasomotor system of the liver, and its centre in the floor of the fourth ventricle, may be regarded as, in a certain sense, an "inhibitory system" for the formation of sugar.

(*b*) If we assume that, normally there is continually a small quantity of sugar passing from the liver into the hepatic vein, we might explain the diabetes as due to the disappearance of these decompositions—diminished burning up of the sugar in the blood, which are constantly removing the sugar from the blood. In fact, diabetic persons have been found to consume less O and to have an increased formation of urea.

[**Injection of Grape Sugar into the Blood.**—When grape sugar is injected into the jugular vein of a dog, only 33 per cent. at most is given off in the urine; within 2 to 5 hours the urine is free from sugar. Even within a few minutes after the injection, only a certain proportion (½–¼) of the sugar is found in the blood; part of the sugar has been detected in the muscles, liver, and kidneys, but the fate of the remainder is not known. Immediately after the injection, the amount of hæmoglobin and also of serum-albumin is diminished (50 per cent.), which is due to increase of the quantity of water within the vessels; but within two hours the normal state is restored (*Brasol*). In a curarized dog the injection of grape sugar into a vein increase the blood pressure, but this effect is not observed after the injection of morphia and chloral.]

Persons suffering from diabetes require a large amount of food; they suffer greatly from thirst, and drink much fluid. They exhibit signs of marked emaciation, when the loss of the body is greater than the supply. [In advanced diabetes the glycogenic function of the liver is almost abolished, as was proved by removing with a trocar a small part of the liver from man, when almost no glycogen was found (*Ehrlich*). The absorbed sugar in the portal vein passes directly into the general circulation without being submitted to the action of the liver (*v. Frerichs*).] In severe cases, toward death, not unfrequently a peculiar comatose condition—**diabetic coma**—occurs, when the breath often has the odor of **aceton**, which is also found in the urine. But neither aceton nor its precursor, aceto-acetic acid, nor æthyl-diacetic acid, nor the unknown substance, in diabetic urine, which gives the red color with ferric chloride (*v. Jaksch*), is the cause of the coma (*Frerichs and Brieger*).

176. THE FUNCTIONS OF THE LIVER.—[To understand the functions of the liver, we must remember its **unique relation** to the vascular and digestive systems, whereby many of the products of gastric and intestinal digestion have to traverse it before they reach the blood, and some of them as they traverse the liver are altered. We have still much to learn regarding the liver. It has several distinct functions—some obvious, others not. (1) The liver secretes **bile**, which is formed by the hepatic cells, and leaves the organ by the bile ducts, to pass into the duodenum. (2) The liver cells also form **glycogen**, which does not pass into the ducts, but in some altered and diffusible form passes into the blood stream, and leaves the liver by the hepatic veins. Hence, the study of the liver materially influences our conception of a secreting organ. In this case, we have the products of its secretory activity leaving it by two different channels—the one by the ducts, and the other by the blood stream. The liver, therefore, is a great storehouse of carbohydrates, and it serves them out to the economy as they are required. All this points to the liver as being an organ intimately related to the **general metabolism** of the body. (3) In a certain period of development it is concerned in the formation of blood corpuscles (§ 7). (4) It has some relation to the breaking up of **blood corpuscles** and the formation of **urea** and other metabolic products (§ 20, § 177, 3). (5) Brunton attributes some importance to the liver in connection with the arrest of certain substances absorbed from the alimentary canal, whereby they are either destroyed, stored up in the liver, or, it may be, prevented from entering the general circula-

tion in too large amount. It is possible that ptomaines may be arrested in this way (§ 166).]

[The liver has no special action on certain mineral substances which traverse it in the blood, *e. g.*, potassic chloride, but it retains the vegetable alkaloids, provided they are not present in too large an amount in the blood. The ptomaines are similarly retained in the liver. The liver possesses this property only as long as it contains glycogen (*H. Rogers*).]

177. **CONSTITUENTS OF THE BILE.**—**Bile** is a yellowish-brown or dark green-colored transparent fluid, with sweetish, strongly bitter taste, feeble musk-like odor, and neutral reaction. The specific gravity of human bile from the gall bladder = 1026 to 1032, while that from a fistula = 1010 to 1011. It contains—

(1) **Mucus,** which gives bile its sticky character, and not unfrequently makes it alkaline; it is the product of the mucous glands and the goblet cells of the mucous membrane of the larger bile ducts. When bile is exposed to the air, the mucus causes it to putrefy rapidly. It is precipitated by acetic acid or alcohol.

[The bile formed in the ultimate bile ducts does not seem to contain mucin or mucus, but bile from the gall bladder always does. It is formed by the mucous glands in the larger bile ducts (§ 173).]

(2) **The Bile Acids.**—Glycocholic and taurocholic acids, so-called conjugate acids, are united with soda (in traces with potash) to form glycocholate and taurocholate of soda, which have a bitter taste, and rotate the plane of polarized light to the right. In human bile (as well as in that of birds, many mammals, and amphibians) taurocholic acid is most abundant; in other animals (pig, ox) glycocholic acid is most abundant but is absent in sucklings.

(*a*) **Glycocholic acid,** $C_{26}H_{43}NO_6$; when boiled with caustic potash, or baryta water, or with dilute mineral acids, it takes up H_2O and splits into—

Glycin (= Glycocoll = Gelatin Sugar = Amido-acetic acid) = $C_2H_5NO_2$.
+ Cholalic acid (also called Cholic acid), ... = $C_{24}H_{40}O_5$.
= Glycocholic acid + Water, ... = $C_{26}H_{43}NO_6 + H_2O$.

(*b*) **Taurocholic acid,** $C_{26}H_{45}NSO_7$, when similarly treated, takes up water and splits into—

Taurin (= Amido-æthyl-sulphuric acid) = $C_2H_7NSO_3$.
+ Cholalic acid, ... = $C_{24}H_{40}O_5$.
= Taurocholic acid + Water . . . . . = $C_{26}H_{45}NSO_7 + H_2O$ (*Strecker*.)

[Solutions of taurocholic acid are antiseptic, and if sufficiently strong interfere with the development of bacteria, and prevent the alcoholic and lactic fermentations, as well as the tryptic and diastatic action of the pancreas (*Emich*).]

Preparation of the Bile Acids.—Evaporate bile to ¼ of its volume, rub it up into a paste with excess of animal charcoal and dry at 100° C. Extract the black mass with absolute alcohol, and filter. After a part of the alcohol has been removed by distillation, the bile salts are precipitated in a resinous form, and on the addition of excess of ether, there is formed immediately a crystalline mass of glancing needles (**Platner's "crystallized bile"**). The alkaline salts of the bile acids are freely soluble in water or alcohol, and insoluble in ether. *Neutral* lead acetate precipitates the glycocholic acid—as lead glycocholate—from the solution of both salts; the precipitate is collected on a filter, dissolved in hot alcohol, and the lead is precipitated as lead sulphide by H_2S; after removal of the lead sulphide, the addition of water precipitates the isolated glycocholic acid. If, after precipitating the lead glycocholate, the filtrate be treated with *basic* lead acetate, a precipitate of lead taurocholate is formed, from which the acid may be obtained in the same way as described above (*Strecker*).

With regard to the **decomposition products** of the bile acids, **glycin,** as such, does not occur in the body, but only in the bile in combination with cholic acid, in urine in combination with benzoic acid, as hippuric acid, and lastly, in gelatin in complex combination.

Cholalic acid rotates the ray of polarized light to the right, and its chemical composition is unknown. It is insoluble in water, soluble in alcohol, but soluble with difficulty in ether, from which it separates in prisms. Its crystalline alkaline salts are readily soluble in water. It is colored blue by iodine, and occurs free only in the intestine.

Cholalic acid is replaced in the bile of many animals by a nearly related acid, *e. g.*, in pig's bile by hyo-cholalic acid (*Strecker*); in the bile of the goose, cheno-cholalic acid is present (*Marsson, Otto*).

When cholalic acid is boiled with concentrated HCl, or heated dry at 200° C., it becomes an anhydride, thus:—

Cholalic acid, . . . $= C_{24}H_{40}O_5$, produces
Choloidinic acid, . $= C_{24}H_{38}O_4 + H_2O$, and this again yields
Dyslysin, ... $= C_{24}H_{36}O_3 = H_2O$.

Choloidinic acid is, however, not improbably a mixture of cholalic acid and dyslysin; dyslysin, when fused with caustic potash, is changed into cholalate of potash. By oxidation cholalic acid yields a tribasic acid, as yet uninvestigated, and a fair amount of oxalic acid, but no fatty acids (*Cleve*).

Pettenkoffer's Test.—The bile acids, cholic acid, and their anhydrides, when dissolved in water, yield on the addition of $\frac{2}{3}$ concentrated sulphuric acid (added in drops so as not to heat the fluid above 70° C.), and several drops of a 10 per cent. solution of cane sugar, a *reddish-purple*, transparent fluid, which shows two absorption bands at E and F (*Schenk*). [A very good method is to mix a few drops of the cane-sugar solution with the bile, and to shake the mixture until a copious froth is obtained. Pour the sulphuric acid down the side of the test tube, and then the characteristic color is seen in the froth. Any albumin present must be removed before applying the test.]

According to Drechsel, it is better to add phosphoric acid, instead of sulphuric acid, until the fluid is syrupy, then add the cane sugar, and afterward place the whole in boiling water. When investigating the amount of bile acids in a liquid, the albumin must be removed beforehand, as it gives a reaction similar to the bile acids, but in that case the red fluid has only *one* absorption band. If only small quantities of bile acids are present, the fluid must in the first place be concentrated by evaporation.

[**Hay's Test.**—The bile acids or their soluble salts *lower the surface tension of fluids* in which they are dissolved. Throw a small quantity of sulphur (sublimed or precipitated) on the surface of the fluid containing bile acids, and if the bile acids be present, the sulphur will at once begin to sink, and will be wholly precipitated within a few minutes. (*Privately communicated.*)]

The **bile acids are formed** in the liver. After its extirpation, there is no accumulation of biliary matters in the blood.

How the formation of the nitrogenous bile acids is effected, is quite unknown. They must be obtained from the decomposition of albuminous materials, and it is important to note that the amount of bile acids is increased by albuminous food. Taurin contains part of the sulphur of albumin; bile salts contain 4 to 4.6 per cent., which may perhaps be derived from dissolved red blood corpuscles.

(3) **The Bile Pigments.**—The freshly secreted bile of man and many animals has a yellowish-brown color, due to the presence of **bilirubin**. When it remains for a considerable time in the gall bladder, or when alkaline bile is exposed to the air, the bilirubin absorbs O and becomes changed into a green pigment, **biliverdin.** This substance is present naturally, and is the chief pigment in the bile of herbivora and cold-blooded animals.

(*a*) **Bilirubin** ($C_{32}H_{36}N_4O_6$) is perhaps united with an alkali; crystallizes in transparent fox-red clinorhombic prisms. It is insoluble in water, *soluble in chloroform*, by which substance it may be separated from biliverdin, which is insoluble in chloroform. It unites as a monobasic acid with alkalies, and as such is soluble. It is identical with Virchow's hæmatoidin (§ 20).

Preparation.—It is most easily prepared from the red (bilirubin chalk) gall stones of man or the ox. The stones are pounded, and their chalk dissolved by hydrochloric acid; the pigment is then extracted with chloroform. That bilirubin is derived from hæmoglobin is very probable, considering its identity with hæmatoidin. Very probably red blood corpuscles are dissolved in the liver, and their hæmoglobin changed into bilirubin.

(*b*) **Biliverdin,** $C_{32}H_{36}N_4O_8$, is an oxidized derivative of the former, from which it can be obtained by various oxidation processes. It is readily *soluble in alcohol*, very slightly so in ether, and not at all soluble in chloroform. It occurs in the placenta of the bitch. As yet it has not been re-transformed by reducing agents into bilirubin.

Tests for Bile Pigments.—Bilirubin and biliverdin may occur in other fluids, *e. g.*, the urine, and are detected by the **Gmelin-Heintz' reaction.** When *nitric acid containing some nitrous acid* is added to a liquid containing these pigments, a play of colors is obtained, beginning with *green* (biliverdin), blue, violet, red, ending with yellow. [This reaction is best done by placing a drop of the liquid on a *white* porcelain plate, and adding a drop of the *impure* nitric acid.]

(*c*) If, when the blue color is reached, the oxidation process is arrested, **bilicyanin** (*Heynsius, Campbell*), in acid solution blue (in alkaline violet), is obtained, which shows two ill-defined absorption bands near D (*Jaffé*).

(*d*) **Bilifuscin** occurs in small amount in decomposing bile and in gall stones = bilirubin + H$_2$O.

(*e*) **Biliprasin** (*Städler*) also occurs = Bilirubin + H_2O + O.

(*f*) The yellow pigment, which ultimately results from the prolonged action of the oxidizing reagent, is the **choletelin** ($C_{16}H_{18}N_2O_6$) of Maly; it is amorphous, and soluble in water, alcohol, acids, and alkalies.

[**Spectrum of Bile.**—The bile of carnivorous animals is generally free from absorption bands, except when acids are added to it, in which case the band of bilirubin is revealed. Bilirubin and biliverdin yield characteristic spectra only when they are treated with nitric acid. The bile of some animals yields bands, but when this is the case they are due to the presence of a derivative of hæmatin, and MacMunn calls this body **cholohæmatin**, which gives a three- or four-banded spectrum (ox, sheep).]

(*g*) Bilirubin absorbs H + H_2O (by putrefaction, or by the treatment of alkaline watery solutions with the powerfully reducing sodium amalgam), and becomes converted into Maly's **hydrobilirubin** ($C_{32}H_{40}N_4O_7$), which is slightly soluble in water, and more easily soluble in solutions of salts, or alkalies, alcohol, ether, chloroform, and shows an absorption band at *b*, F. This substance, which, according to Hammarsten, occurs in normal bile, is a constant coloring matter of fæces and was called **stercobilin** by Vaulair and Masius, but is identical with hydrobilirubin (*Maly*). It is, however, probably identical with the urinary pigment *urobilin* of Jaffé (*Stokvis*, § 20).

[The bile of **invertebrates** contains none of the bile pigments present in vertebrates, although hæmochromogen is found in the cray-fish and pulmonate mollusks. In some organs, and in bile, a pigment-like vegetable chlorophyll—**entero-chlorophyll**—is found; but whether it is derived from without, or formed within the organism, is not certain (*MacMunn*).]

(4) **Cholesterin**, $C_{26}H_{44}O(H_2O)$, is a monatomic alcohol which rotates the ray of polarized light to the left; it occurs also in blood, yelk, nervous matter [and gall stones]. It forms transparent rhombic plates, which usually have a small oblong piece cut out of the corner (Fig. 196). It is insoluble in water, soluble in hot alcohol, ether, or chloroform. It is kept in solution in the bile by the bile salts.

FIG. 196.



Crystals of Cholesterin.

Preparation.—It is most easily prepared from so-called white gall stones, which not unfrequently consist entirely of cholesterin, by extracting them with hot alcohol after they are pulverized. Crystals are excreted after evaporation of the alcohol. **Tests.**—They give a red color with sulphuric acid (5 vols. to 1 vol. H_2O), while they give a blue—as cellulose does—with sulphuric acid and iodine. When dissolved in chloroform, one drop of concentrated sulphuric acid causes a deep red color (*H. Schiff*).

(5) Among the other organic constituents: **Lecithin** (§ 23), or its decomposition product, neurin (cholin), and glycero-phosphoric acid (into which lecithin may be artificially transformed by boiling with baryta); **palmatin, stearin, olein,** as well as their soda **soaps; diastatic ferment;** traces of **urea;** (in ox bile, acetic acid and propionic acid, united with glycerine and metals, *Dogiel*).

(6) **Inorganic constituents** of bile (0.6 to 1 per cent.):—

They are—sodic and potassic chloride, calcic and magnesic phosphate, and much iron, which in fresh bile gives the ordinary reactions for iron, so that iron must occur in one of its oxidized compounds in bile; manganese and silica. **Gases.**—Freshly-secreted bile contains in the dog more than 50 vols., and in the rabbit 109 vols. per cent. CO_2, partly united to alkalies, partly absorbed, the latter, however, being almost completely absorbed within the gall bladder.

The **mean composition** of **human bile** is:—

Water, ...	82 to 90 per cent.	Lecithin, ...	0.5 per cent.
Bile salts, ...	6 to 11 "	Mucin and pigments, .	1 to 3 "
Fat and soaps, ...	2 "	Ash, ...	0.61 "
Cholesterin, ...	0.4 "		

Further, unchanged fat probably always passes into the bile, but it is again absorbed therefrom (*Virchow*). The amount of S in dry dog's bile = 2.8 to 3.1 per cent., the N = 7 to 10 per cent. (*Spiro*); the sulphur of the bile is not oxidized into sulphuric acid, but it appears as a sulphur compound in the urine (*Kunkel, v. Voit*).

178. SECRETION OF BILE.—(1) **The secretion of bile** is not a mere filtration of substances already existing in the blood of the liver, but it is a chemical production of the characteristic biliary constituents, accompanied by oxidation, within the hepatic cells, to which the blood of the gland only supplies the raw material. The liver cells themselves undergo histological changes during the process of digestion. It is secreted continually; but part is stored up in the gall bladder, and is poured out copiously during digestion. The higher temperature of the blood of the hepatic vein, as well as the large amount of CO_2 in the bile, indicates that oxidations occur within the liver. The water of the bile is not merely filtered through the blood capillaries, as the pressure within the bile ducts may exceed that in the portal vein.

(2) **The quantity of bile** was estimated by v. Wittich, from a biliary fistula, at 533 cubic centimetres in twenty-four hours (some bile passed into the intestine); by Westphalen, at 453 to 566 grms. [by Murchison, at 40 oz.]; by Joh. Ranke, on a biliary-pulmonary fistula, at 652 cubic centimetres. The last observation gives 14 grms. (with 0.44 grms. solids) per kilo. of man in twenty-four hours.

Analogous values for animals are—1 kilo. dog, 32 grms. (1.2 solids); 1 kilo. rabbit, 137 grms. (2.5 solids); 1 kilo. guinea pig, 176 grms. (2.5 solids).

(3) **The excretion** of bile into the intestine shows two maxima *during one period of digestion;* the first from 3 to 5 hours, and the second from 13 to 15 hours, after food. The cause is due to simultaneous reflex excitement of the hepatic blood vessels, which become greatly dilated.

(4) **The influence of food** is very marked. The largest amount is secreted after a flesh diet, with some fat added; less after vegetable food; a very small amount with a pure fat diet; it stops during hunger. Draughts of water increase the amount, with a corresponding relative diminution of the solid constituents. [The biliary solids are increased by food, reaching their maximum about one hour after feeding.]

(5) **The influence of blood supply** is variable:—

(*a*) Secretion is greatly favored by a copious and rapid blood supply. The blood pressure is not the prime factor, as ligature of the cava above the diaphragm, whereby the greatest blood pressure occurs in the liver, *arrests* the secretion.

(*b*) Simultaneous ligature of the hepatic artery (diameter, 5½ mm.) and the portal vein (diameter, 16 mm.) abolishes the secretion (*Röhrig*). These two vessels supply the raw material for the secretion of bile.

(*c*) If the hepatic artery be ligatured, the portal vein alone supports the secretion. Ligature of the artery or one of its branches ultimately causes necrosis of the parts supplied by that branch, and eventually of the entire liver, as this artery is the nutrient vessel of the liver.

(*d*) If the branch of the portal vein to one lobe be ligatured, there is only a slight secretion in that lobe, so that the bile must be formed from the arterial blood. Complete ligature of the portal vein rapidly causes death (§ 87). Neither ligature of the hepatic artery by itself, nor *gradual* obliteration of the portal vein by itself, causes cessation of the secretion, but it is diminished. That *sudden* ligature of the portal vein causes cessation is due to the fact that, in addition to diminution of the secretion, the enormous stagnation of blood in the rootlets of the portal vein in the abdominal organs makes the liver very anæmic, and thus prevents it from secreting.

(*e*) If the blood of the hepatic artery is allowed to pass into the portal vein (which has been ligatured on the peripheral side), secretion continues (*Schiff*).

(*f*) Profuse loss of blood arrests the secretion of bile before the muscular and nervous apparatus are paralyzed. A more copious supply of blood to other organs—*e. g.*, to the muscles of the trunk—

during vigorous exercise, diminishes the secretion, while the transfusion of large quantities of blood increases it, but if too high a pressure is caused in the portal vein, by introducing blood from the carotid of another animal, it is diminished.

(*g*) **Influence of Nerves.**—All conditions which cause contraction of the abdominal blood vessels, *e. g.*, stimulation of the ansa Vieussenii, of the inferior cervical ganglion, of the hepatic nerves, of the splanchnics, of the spinal cord (either directly by strychnia, or reflexly through stimulation of sensory nerves), affect the secretion; and so do all conditions which cause stagnation or congestion of the blood in the hepatic vessels (section of the splanchnic nerves, diabetic puncture, § 175), section of the cervical spinal cord. Paralysis (ligature) of the hepatic nerves causes *at first* an increase of the biliary secretion.

(*h*) **Portal and Hepatic Veins.**—With regard to the raw material supplied to the liver by its blood vessels, it is important to note the difference in the composition of the blood of the hepatic and portal veins. The blood of the hepatic vein contains *more* sugar (?), lecithin, cholesterin (*Drosdoff*), and blood corpuscles, but *less* albumin, fibrin, hæmoglobin, fat, water, and salts.

[(*i*) Uffelmann observed that the flow of bile from a person with a biliary fistula was arrested during fever.]

(6) The formation of bile is largely dependent upon the **decomposition of red blood corpuscles**, as they supply the material necessary for the formation of some of its constituents.

Hence, all conditions which cause solution of the colored blood corpuscles are accompanied by an increased formation of bile (§ 180).

(7) Of course a normal condition of the hepatic cells is required for a normal secretion of bile.

Biliary Fistulæ.—The mechanism of the biliary secretion is studied in animals by means of biliary fistulæ. Schwann opened the belly by a vertical incision a little to the right of the ensiform process, cut into the fundus of the gall bladder, and sewed its margins to the edges of the wound in the abdomen, and afterward introduced a cannula into the wound (Fig. 197). To secure that all the bile is discharged externally, tie the common bile duct in two places and divide it between the two ligatures. After a fistula is freshly made the secretion falls. This depends upon the removal of the bile from the body. If bile be supplied, the secretion is increased. Regeneration of the divided bile duct may occur in dogs. V. Wittich observed a biliary fistula in man. [A temporary biliary fistula may also be made. The abdomen is opened in the same way as described above. A long bent glass cannula is introduced and tied into the common bile duct, and the cystic duct is ligatured or clamped (Fig. 197). The tube is brought out through the wound in the abdomen.

FIG. 197.



Schwann's permanent fistula, and a temporary fistula. *Abd*, abdominal wall; G. B., gall bladder; INT., intestine; T., tube in temporary fistula (*Stirling*).

[**Influence of the Liver on Metabolism.**—If the liver be excluded from the circulation, important changes must necessarily occur in the metabolism. In **birds** (the goose) there is an anastomosis between the portal system of the liver and that of the kidneys, so that, when the portal circulation is interrupted in these animals, there is never any great congestion in the abdominal organs. The goose dies generally eight to ten hours after the operation. The *uric acid* in the urine rapidly falls to a minimum ($\frac{1}{10}$ to $\frac{1}{30}$ of normal); the chief constituent of the urine is then sarcolactic acid, while in normal urine there is none; the ammonia is increased (*Minkowski*). This experiment goes to indicate that uric acid is formed in the liver. **Dog.**—If the liver be excluded from the portal circulation, by connecting the portal vein with the inferior vena cava, and ligaturing the hepatic artery, a dog will live in the former case three to six days, and in the latter one to two. The liver does not undergo necrosis, nor does bile cease to be secreted. The liver is nourished by the blood in the hepatic vein, the reflux in this vein being probably caused by the respiratory movements (*Stolnikow*). Noël Paton finds that in dogs, in a condition of nitrogenous balance, some drugs which increase the flow of bile (*e. g.*, salicylate and benzoate of soda, colchicum, perchloride of mercury, and euonymin) also increase the production of urea; hence, he concludes that the formation of urea in the liver bears a very direct relationship to the secretion of bile (§ 256).]

179. EXCRETION OF BILE.—[In this connection we must keep in view two distinct mechanisms. (1) The **bile-secreting mechanism** dependent upon the liver cells, which are always in a greater or less degree of activity;

(2) the **bile-expelling mechanism,** which is specially active at certain periods of digestion (§ 178).

Excretion of bile is due to (1) the continual pressure of the newly-formed bile within the inter-lobular bile ducts forcing onward the bile in the excretory ducts.

(2) The interrupted **periodic compression of the liver** from above, by the diaphragm, at every inspiration. Further, every inspiration assists the flow of blood in the hepatic veins, and every respiratory increase of pressure within the abdomen favors the current in the portal vein.

It is probable that the diminution of the secretion of bile, which occurs after bilateral division of the vagi, is to be explained in this way; still, it is to be remembered that the vagus sends branches to the hepatic plexus. It is not decided whether the biliary secretion is diminished after section of the phrenic nerves and paralysis of the abdominal muscles.

(3) The *contraction of the smooth muscles* of the larger bile ducts and the gall bladder. Stimulation of the spinal cord, from which the motor nerves for these structures pass, causes acceleration of the outflow, which is afterward followed by a diminished outflow. Under normal conditions, this stimulation seems to occur reflexly, and is caused by the passage of the ingesta into the duodenum, which, at the same time, excites movement of this part of the intestine.

(4) Direct stimulation of the liver, and reflex stimulation of the spinal cord, diminish the excretion; while extirpation of the hepatic plexus and injury to the floor of the fourth ventricle do not exert any disturbing influence.

(5) A relatively small amount of resistance causes bile to stagnate in the bile ducts.

Secretion Pressure.—A manometer, tied into the gall bladder of a guinea pig, supports a column of 200 millimetres of *water;* and secretion can take place under this pressure. If this pressure be increased, or too long sustained, the watery bile passes from the liver into the blood, even to the amount of four times the weight of the liver, thus causing solution of the red blood corpuscles by the absorbed bile; and very soon thereafter hæmoglobin appears in the urine. [This fact is of practical importance, as duodenitis may give rise to symptoms of jaundice, the resistance of the inflamed mucous membrane being sufficient to arrest the outflow of bile.]

Passage of Substances into the Bile.—Some substances which enter the blood pass into the bile; especially the metals, copper, arsenic, iron, etc.; potassium iodide, bromide, and sulphocyanide and turpentine; to a less degree, cane sugar and grape sugar; sodium salicylate, and carbolic acid. If a large amount of water be injected into the blood, the bile becomes albuminous; mercuric and mercurous chlorides cause an increase of the water of the bile. Sugar has been found in the bile in diabetes; leucin and tyrosin in typhus, lactic acid and albumin in other pathological conditions of this fluid.

180. **REABSORPTION OF BILE; JAUNDICE.—I. Absorption Jaundice.**—When resistance is offered to the outflow of bile into the intestine, *e. g.*, by a plug of mucus, or a gall stone which occludes the bile duct, or where a tumor or pressure from without makes it impervious—the bile ducts become filled with bile and cause an enlargement of the liver. The pressure within the bile ducts is increased. As soon as the pressure has reached a certain amount, which it soon does when the bile duct is occluded (in the dog 275 mm. of a column of bile), reabsorption of bile from the distended larger bile ducts takes place into the *lymphatics* (not the blood vessels) of the liver, the bile acids pass into the lymphatics of the liver. [The lymphatics can be seen at the portal fissure filled with yellow colored lymph.] The lymph passes into the thoracic duct, and so into the blood (*Fleischl*). Even when the pressure is very low within the portal vein, bile may pass into the blood without any obstruction to the bile duct being present. This is the case in Icterus neonatorum, as after ligature of the umbilical cord no more blood passes through the umbilical vein; further, in the icterus of hunger, "hunger jaundice" as the portal vein is relatively empty, owing to the feeble absorption from the intestinal canal (*Cl. Bernard*).

II. Cholæmia may also occur, owing to the excessive production of bile (hypercholia), the bile not being all excreted into the intestine, so that part of it is reabsorbed. This takes place when there is solution of a great number of blood corpsucles (§ 178, 6), which yield material for the formation of bile. Thick, inspissated bile accumulates in the bile ducts, so that stagnation, with subsequent reabsorption of the bile, takes place. The tranfusion of heterogeneous blood obtained by dissolving colored blood corpuscles acts in this direction. Icterus is a common phenomenon after too copious transfusion of the same blood. The blood corpuscles are dissolved by the injection into the blood of heterogeneous blood serum, by the injection of bile acids into the vessels, and by other salts, by

phosphoric acid, water, chloral, inhalation of chloroform and ether; the injection of dissolved hæmoglobin into the arteries or into a loop of the small intestine acts in the same way.

Icterus Neonatorum.—When, owing to compression of the placenta within the uterus, too much blood is forced into the blood vessels of the newly-born infant, a part of the surplus blood during the first few days becomes dissolved, part of the hæmoglobin is converted into bilirubin, thus causing jaundice (*Virchow, Violet*).

Absorption Jaundice.—When the jaundice is caused by the absorption of bile already formed in the liver, it is called hepatogenic or absorption jaundice. The following are the **symptoms:—**

(1) Bile pigments and bile acids pass into the tissues of the body; hence, the most pronounced external symptom is the yellowish tint or *jaundice*. The skin and the sclerotic become deeply colored **yellow.** In pregnancy the fœtus is also tinged.

(2) Bile pigments and bile acids pass into the **urine** (not into the saliva, tears, or mucus) (§ 177). When there is much bile pigment, the urine is colored a deep yellowish brown, and its froth is citron yellow; while strips of gelatin or paper dipped into it also become colored. Occasionally bilirubin (= hæmatoidin) crystals occur in the urine (§ 266).

(3) The **fæces** are "*clay colored*" (because the hydrobilirubin of the bile is absent from the fecal matter)—*very hard* (because the fluid of the bile does not pass into the intestine); contain much *fat* (in globules and crystals), because the fat is not sufficiently digested in the intestine without bile, so that 78 per cent. of the fat taken with the food reappears in the fæces (*v. Voit*); they have a very *disagreeable odor*, because the bile normally greatly limits the putrefaction in the intestine. [V. Voit finds that putrefaction does not take place if fats be withheld from the food.] The *evacuation of the fæces* occurs *slowly*, partly owing to the hardness of the fæces, partly because of the absence of the peristaltic movements of the intestine, owing to the want of the stimulating action of the bile.

(4) The **heart beats** are greatly diminished, *e.g.*, to 40 per minute. This is due to the action of the bile salts, which at first stimulate the cardiac ganglia, and then weaken them. Bile salts injected into the heart produce at first a temporary acceleration of the pulse, and afterward slowing (*Röhrig*). The same occurs when they are injected into the blood, but in this case the stage of excitement is very short. The phenomenon is not affected by section of the vagi. It is probable, that when the action of the bile salts is long continued, they act upon the heart muscle. In addition to the action on the heart, there is **slowing of the respiration** and **diminution of temperature.**

(5) That the **nervous system,** and perhaps also the muscles, are affected, either by the bile salts or by the accumulation of cholesterin in the blood, is shown by the very general relaxation, sensation of fatigue, weakness, drowsiness, and lastly, deep coma—sometimes there is sleeplessness, itchiness of the skin, even mania, and spasms. Löwit, after injecting bile into animals, observed phenomena referable to stimulation of the respiratory, cardio-inhibitory, and vasomotor nerve centres.

(6) In very pronounced jaundice there may be "*yellow vision*," owing to the impregnation of the retina and macula lutea with the bile pigment.

(7) The bile acids in the blood dissolve the red blood corpuscles. The hæmoglobin is changed into new bile pigment, and the globulin-like body of the hæmoglobin may form urinary cylinders or casts in the urinary tubules, which are ultimately washed out of the tubules by the urine.

[**Influence of Drugs on the Secretion of Bile.**—On animals one may make either a permanent or a temporary fistula. The latter is the more satisfactory method, and the experiments are usually made on fasting curarized dogs. A suitable cannula is introduced into the common bile duct (Fig. 197), the animal is curarized, artificial respiration being kept up, while the drug is injected into the stomach or intestine. Röhrig used this method, which was improved by Rutherford and Vignal. Röhrig found that some purgatives, croton oil, colocynth, jalap, aloes, rhubarb, senna, and other substances, increased the secretion of bile. Rutherford and Vignal investigated the action of a large number of drugs on the **bile-secreting mechanism.** They found that croton oil is a feeble hepatic stimulant, while podophyllin, aloes, colchicum, euonymin, iridin, sanguinarin, ipecacuan, colocynth, sodium phosphate, phytolaccin, sodium benzoate, sodium salicylate, dilute nitro-hydrochloric acid, ammonium phosphate, mercuric chloride (corrosive sublimate), are all powerful, or very considerable, hepatic stimulants. Some substances stimulate the intestinal glands, but not the liver, *e.g.*, magnesium sulphate, castor oil, gamboge, ammonium chloride, manganese sulphate, calomel. Other substances stimulate the liver as well as the intestinal glands, although not to the same extent, *e.g.*, scammony (powerful intestinal, feeble hepatic stimulant); colocynth excites both powerfully; jalap, sodium sulphate, and baptisin, act with considerable power both on the liver and the intestinal glands. Calabar bean stimulates the liver, and the increased secretion caused thereby may be reduced by sulphate of atropin, although the latter drug, when given alone, does not notably affect the secretion of bile. The injection of water or bile slightly increases the secretion. In all cases where purgation was produced by purely intestinal stimulants, such as magnesium sulphate, gamboge, and castor oil, the secretion of bile was diminished. In all such experiments it is most important that the *temperature of the animal be kept up*, else the secretion of bile diminishes. Paschkis's results on dogs differ considerably from those of Rutherford. He asserts that only the bile acids (salts) of all the substances he investigated excite a prompt and distinct cholagogue action.]

[As yet we cannot say definitely whether or not these substances stimulate the secretion of bile, by exciting the mucous membrane of the small intestine, and thereby inducing reflex excitement of the liver. Their action does not seem to be due to increase of the blood stream through the liver. More probably, as Rutherford suggests, these drugs act directly on the hepatic cells or their nerves. Acetate of lead directly depresses the biliary secretion, while some substances affect it indirectly.]

[**Cholesteræmia.**—Flint ascribes great importance to the excretion of cholesterin by the bile, with reference to the metabolism of the nervous system. Cholesterin, which is a normal ingredient of nervous tissue, is excreted by the bile; and if it be retained in the blood "cholesteræmia," with grave nervous symptoms, is said to occur. This, however, is problematical, and the phenomena described are probably referable to the retention of the bile acids in the blood.]

181. FUNCTIONS OF THE BILE.—[(1) Bile is concerned in the digestion of certain food stuffs; (2) part is absorbed; (3) part is excreted.]

(**A**) Bile plays an important part in the **absorption of fats**:—

(1) It *emulsionizes neutral fats*, whereby the fatty granules pass more readily through or between the cylindrical epithelium of the small intestine into the lacteals. It does *not* decompose neutral fats into glycerine and a fatty acid, as the pancreas does (§ 170, III).

When, however, fatty acids are dissolved in the bile, the bile salts are decomposed, the bile acids being set free, while the soda of the decomposed bile salts readily forms a soluble soap with the fatty acids. These soaps are soluble in the bile, and increase considerably the emulsifying power of this fluid. Bile can dissolve fatty acids to form an acid fluid, which has high emulsionizing properties (*Steiner*). Emulsification is influenced by a 1 per cent. solution of NaCl, or Na_2SO_4.

(2) As fluid fat flows more easily through capillary tubes moistened with bile, it is concluded that when the pores of the wall of the small intestine are moistened with bile, the fatty particles pass more easily through them.

(3) Filtration of fat takes place through a membrane moistened with bile or bile salts under less pressure than when it is moistened with water or salt solution (*v. Wistinghausen*).

(4) As bile, like a solution of soap, has a certain relation to watery solutions, as well as to fats, it permits diffusion to take place between these two fluids, as the membrane is moistened by both fluids.

It is clear, therefore, that the bile is of great importance in the absorption of fats. This is strikingly illustrated by experiments on animals, in which the bile is entirely discharged externally through a fistula. Dogs, under these conditions, absorbed at most 40 per cent. of the fat taken with the food [60 per cent. being given off by the fæces, while a normal dog absorbs 99 per cent. of the fat]. The chyle of such animals is very poor in fat, is not white but transparent; the fæces, however, contain much fat, and are oily; the animals have a ravenous appetite; the tissues of the body contain little fat, even when the nutrition of the animals has not been much interfered with. Persons suffering from disturbances of the biliary secretion, or from liver affections, ought, therefore, to abstain from fatty food. [The digestion of flesh and gelatin is not interfered with in dogs by the removal of the bile (*v. Voit*).]

(**B**) Fresh bile contains a **diastatic ferment**, which transforms starch into sugar, and also glycogen into sugar.

(**C**) Bile excites **contractions of the muscular coats** of the intestine, and contributes thereby to absorption.

(1) The bile acids act as a stimulus to the **muscles of the villi**, which contract from time to time, so that the contents of the origins of the lacteals are emptied toward the larger lymphatics, and the villi are thus in a position to absorb more. [The villi act like numerous small pumps, and expel their contents, which are prevented from returning by the presence of valves in the larger lymphatics.]

(2) The **musculature of the intestine** itself seems to be excited, perhaps through the agency of the plexus myentericus. In animals with a biliary fistula, and in which the bile duct is obstructed, the intestinal peristalsis is greatly diminished, while the salts of the bile acids administered by the mouth causes diarrhœa and vomiting. As contraction of the intestine aids absorption, bile is also necessary in this way for the absorption of the dissolved food stuffs.

(**D**) The presence of bile seems to be necessary to the vital activity of the intestinal epithelium in its supposed function of being concerned in the absorption of fatty particles (§ 190).

(**E**) Bile moistens the wall of the intestines, and gives to the fæces their normal

amount of water, so that they can be readily evacuated. Animals with biliary fistula, or persons with obstruction of the bile ducts, are very costive. The mucus aids the forward movement of the ingesta through the intestinal canal. [Thus, in a certain sense, bile is a *natural purgative*.]

(**F**) The bile diminishes putrefactive decomposition of the intestinal contents, especially with a fatty diet, § 190. [Thus, it is an **antiseptic**, although this is doubted by v. Voit.]

(**G**) When the strongly acid contents of the stomach pass into the duodenum, the glycocholic acid is precipitated by the gastric acid, and carries the pepsin with it (*Burkart*). Some of the albumin, which has been simply *dissolved* (but not peptone or propeptone), is also precipitated, by the taurocholic acid (*Maly and Emich*). The bile salts are decomposed by the acid of the gastric juice. When the mixture is rendered alkaline by the pancreatic juice and the alkali derived from the decomposition of the bile salts, the pancreatic juice acts energetically in this alkaline medium (*Moleschott*).

[Taurocholic acid and its soda salts precipitate albumin, but not peptone; glycocholic acid does not precipitate albumin, so that in the intestine the peptone is separated from the albumin (and syntonin), and may therefore be more readily absorbed, while the precipitate adhering to the intestinal wall can be further digested (*Maly and Emich*). Taurocholic acid behaves in the same way toward gelatin peptone.]

Bilious Vomit.—When bile passes into the stomach, as in vomitittg, the acid of the gastric juice unites with the bases of the bile salts; sodium chloride and free bile acids are formed, and the acid reaction is thereby somewhat diminished. The bile acids cannot carry on gastric digestion; the neutralization also causes a precipitation of the pepsin and mucin. As soon, however, as the walls of the stomach secrete more acid, the pepsin is redissolved. The bile which passes into the stomach deranges gastric digestion, by shriveling the proteids, which can only be peptonized when they are swollen up (p. 295).

182. **FATE OF THE BILE.**—Some of the biliary constituents are completely evacuated with the fæces, while others are reabsorbed by the intestinal walls.

(1) **Mucin** passes unchanged into the fæces.

(2) **The bile pigments** are reduced, and are partly excreted with the fæces as **hydrobilirubin**, and partly as the identical end-product **urobilin** by the urine (§ 177, 3 *g*).

From **meconium** hydrobilirubin is absent, while crystalline bilirubin and biliverdin, and an unknown red oxidation product of them, are present [bile acids, even taurocholic, and small trace of fatty acids] (*Zweifel*), so that it gives Gmelin's reaction. Hence, no reduction—but rather oxidation—processes occur in the fœtal intestine. [**Composition.**—Dary gives 72.7 per cent. water, 23.6 mucus and epithelium, 1 per cent. fat and cholesterin, and 3 per cent. bile pigments. Zweifel gives 79.78 per cent water, and solids 20.22 per cent. It does not contain lecithin, but so much bilirubin that Hoppe-Seyler uses it as a good source whence to obtain this pigment. It gives a spectrum of a body related to urobilin.]

(3) **Cholesterin** is given off with the fæces.

(4) The **bile salts** are for the most part reabsorbed by the walls of the jejunum and ileum, to be re-employed in the animal's economy. Tappeiner found them in the chyle of the thoracic duct—minute quantities pass normally from the blood into the urine. Only a very small amount of glycocholic acid appears unchanged in the fæces. The taurocholic acid, as far as it is not absorbed, is easily decomposed in the intestine, by the putrefactive processes, into cholalic acid and taurin; the former of these is found in the fæces, but the taurin at least seems not to be constantly present. Part of the cholalic acid is absorbed, and may unite in the liver either with glycin or taurin (*Weiss*).

(5) The fæces contain mere traces of **lecithin.**

Impaired Nutrition.—The greatest part of the most important biliary constituents, the bile acids, re-enter the blood, and thus is explained why animals with a biliary fistula, where all the bile is removed (without the animal being allowed to lick the bile), rapidly lose weight. This depends partly upon the digestion of the fats being interfered with, and also upon the direct loss of the bile salts. If

such dogs are to maintain their weight, they must eat twice as much food. In such cases, carbohydrates most beneficially replace the fats. If the digestive apparatus is otherwise intact, the animals, on account of their voracity, may even increase in weight, but the flesh and not the fat is increased.

Bile partly an Excretion.—The fact that bile is secreted during the fœtal period, while none of the other digestive fluids is, proves that it is an *excretion.*

The **cholalic acid** which is reabsorbed by the intestinal walls passes into the body and seems ultimately to be burned to form CO_2 and H_2O. The **glycin** (with hippuric acid) forms urea, as the urea is increased after the injection of glycin. The fate of **taurin** is unknown. When large quantities are introduced into the human stomach, it reappears in the urine as tauro-carbamic acid, along with a small quantity of unchanged taurin. When injected subcutaneously into a rabbit, nearly all of it reappears in the urine.

[**Practical.**—In practice it is important to remember that bile once in the intestine is liable to be absorbed unless it be carried down the intestine; hence, it is one thing to give a drug which will excite the secretion of bile, *i. e.*, a hepatic stimulant, and another to have the bile so secreted expelled. It is wise, therefore, to give a drug which will do both, or at least to combine a hepatic stimulant with one which will stimulate the musculature of the intestine as well. *Active exercise*, whereby the diaphragm is vigorously called into action to compress the liver, will aid in the expulsion of the bile from the liver (*Brunton*).]

FIG. 198.



Vertical section of duodenum (cat), × 30. *E*, epithelium; *c* and *l*, circular and longitudinal muscular fibres; *L.g*, Lieberkühn's glands; *B.g*, Brunner's glands, *g*, ganglion cells; *v*, villi.

183. THE INTESTINAL JUICE.—Length of Intestine.—The human intestine is ten times longer than the length of the body, as measured from the vertex to the anus. It is longer comparatively than that of the omnivora. Its minimum length is 507, its maximum 1194 centimetres [17 to 35 feet]; its capacity is relatively greater in children (*Beneke*).

The **succus entericus** is the digestive fluid secreted by the numerous glands of the intestinal mucous membrane. The largest amount is produced by Lieberkühn's glands, while in the duodenum there is added the scanty secretion of Brunner's glands.

Brunner's glands are small, branched, tubular glands, lying in the sub-mucosa of the duodenum. Their fine ducts run inward, pierce the mucous membrane, and open at the bases of the villi (Fig. 198). The acini are lined by cylindrical cells, like those lining the pyloric glands. In fact, Brunner's glands are structurally and anatomically identical with the pyloric glands of the stomach. During hunger, the cells are turbid and small, while during digestion they are large and clear. The glands receive nerve fibres from Meissner's plexus (*Drasch*).

I. The Secretion of Brunner's Glands.—The granular contents of the secretory cells of these glands, which occur singly in man, but form a continuous layer in the duodenum of the sheep, besides *proteids*, consist of *mucin* and a *ferment substance* of unknown constitution. The watery extract of the glands causes (1) Solution of proteids at the temperature of the body (*Krolow*). (2) It also has a diastatic action. It converts maltose into glucose (*Brown and Heron*). It does not appear to act upon fats.

On account of the smallness of the objects, such experiments are only made with great difficulty, and, therefore, there is a considerable uncertainty with regard to the action of the secretion.

Lieberkühn's glands are simply tubular glands resembling the finger of a glove [or a test-tube], which lie closely packed, vertically near each other, in the mucous membrane (Fig. 199); they are most numerous in the large intestine, owing to the absence of villi in this region. They consist of a structureless membrana propria lined by a single layer of low cylindrical epithelium, between which numerous goblet cells occur, the goblet cells being fewer in the small intestine and much more numerous in the large (Fig. 199). The glands of the small intestine yield a thin secretion, while those of

the large intestine yield a large amount of sticky mucus from their goblet cells (*Klose and Heidenhain*). [In a vertical section of the small intestine they lie at the base of the villi (Fig. 198). In transverse section they are shown in Fig. 200.]

II. The Secretion of Lieberkühn's Glands, from the duodenum onward, is the chief source of the intestinal juice.

Intestinal Fistula.—The intestinal juice is obtained by making a **Thiry's Fistula** (1864). A loop of the intestine of a dog is pulled forward (Fig. 201, 1), and a piece about 4 inches in length is cut out, so that the continuity of the intestinal tube is broken, but the mesentery and its blood vessels are not divided. One end of this tube is closed, and the other end is left open and stitched to the abdominal wall (Fig. 201, 3). The two ends of the intestine from which this piece was taken are brought together with sutures, so as to establish the continuity of the intestinal canal (Fig. 201, 2). The excised piece of intestine yields a secretion which is uncontaminated with any other digestive

FIG. 199.

Lieberkühn's gland from the large intestine (dog).

FIG. 200.

Transverse section of Lieberkühn's follicles.

FIG. 201.



Scheme of Thiry's Fistula. 1, 2, 3, 4, Vella's Fistula. AA' are stitched together; *Abd*, Abdominal wall (*Stirling*).

secretion. [Thiry's method is very unsatisfactory, as judged from the action of the separated loop in relation to medicaments, probably owing to its mucous membrane becoming atrophied from disuse, or injured by inflammation.]

[**Meade Smith** makes a small opening in the intestine, through which he introduces two small collapsed india-rubber balls, one above and the other below the opening, which are then distended by inflation until they completely block a certain length of the intestine. The loop thus blocked off, having been previously well washed out, is allowed to become filled with succus, which is secreted on the application of various stimuli. By means of Bernard's gastric cannula (§ 165) inserted into the fistula in the loop, the secretion can be removed when desired.]

[**Vella's Fistula.**—Open the belly of a dog, and pull out a loop (30 to 50 ctm.) [1 to 1½ feet] of small intestine, and ligature it; divide it above and below, re-establish the continuity of the rest of the intestine. Stitch *both* ends of the loop of intestine into the wound in the linea alba (Fig. 201, 4), so that there is a loop of intestine supplied by its blood vessels and nerves, isolated and with an upper and lower aperture.]

The intestinal juice of such fistulæ flows spontaneously in very small amount, and is increased during digestion; it is increased—especially its mucus—by mechanical, chemical, and electrical stimuli; at the same time, the mucous membrane becomes red, so that 100 centimetres yield 13 to 18 grammes of this juice in an hour (*Thiry*). The juice is light yellow, opalescent, thin, strongly alkaline, specific gravity 1011, evolves CO_2 when an acid is added; it contains albumin, ferments, and mucin—especially the juice of the large intestine. Its composition is—water, 97.59; proteids, 0.80; other organic substances = 0.73; salts, 0.88 per cent.; among these, sodium carbonate, 0.32 to 0.34 per cent.

[The intestinal juice obtained by Meade Smith's method contained only 0.39 per cent. of organic matter, and in this respect agreed closely with the juice which A. Moreau procured by dividing the mesenteric nerves of a ligatured loop of intestine. The secretion of the large intestine is much more viscid than that of the small intestine.]

Actions of Succus Entericus.—It is most active in the dog, and in other animals it is more or less inactive.

(1) It is less diastatic than the saliva and the pancreatic juice, but it does not form maltose; while the juice of the large intestine does not possess this property (*Eichhorst*).

(2) It converts maltose into grape sugar. It seems, therefore, to continue the diastatic action of saliva (§ 148) and pancreatic juice (§ 170), which usually form only maltose.

According to Bourquelot this action is due to the intestinal schizomycetes and not to the intestinal juice as such, the saliva, gastric juice or invertin. The greater part of the maltose appears, however, to be absorbed unchanged.

(3) Fibrin is slowly (by the trypsin and pepsin—*Kühne*) peptonized (*Thiry, Leube*); less easily albumin (*Masloff*), fresh casein, flesh raw or cooked, vegetable albumin; probably gelatin also is changed by a special ferment into a solution which does not gelatinize (*Eichhorst*).

(4) Fats are only partly emulsionized (*Schiff*), and afterward decomposed (*Vella*).

(5) According to Cl. Bernard, **invertin** occurs in intestinal juice (this ferment can also be extracted from yeast). It causes cane sugar ($C_{12}H_{22}O_{11}$) to take up water (+ H_2O), and converts it into invert-sugar, which is a mixture of left-rotating sugar (lævulose, $C_6H_{12}O_6$) and of grape sugar (dextrose, $C_6H_{12}O_6$). Heat seems to be absorbed during the process.

[Hoppe-Seyler has suggested that this ferment is not a natural product of the body, but is introduced from without with the food. Matthew Hay, however, finds it to be invariably present in the small intestine of the fœtus.]

[**Effect of Drugs.**—The subcutaneous injection of pilocarpin causes the mucous membrane of a Vella's fistula to be congested, when a strongly alkaline, opalescent, watery, and slightly albuminous secretion is obtained. This secretion produces a reducing sugar, converts cane sugar into invert-sugar, emulsifies neutral fats, ultimately splitting them up, peptonizes proteids, and coagulates milk, even although the milk be alkaline. The juice attacks the sarcous substance of muscle before the connective tissues—the reverse of the gastric juice. The mucous membrane in a Vella's fistula does not atrophy. K. B. Lehmann finds that the succus entericus obtained from the intestine of a *goat* by a Vella fistula has no digestive action.]

The Action of Nerves on the secretion of the intestinal juice is not well determined. Section or stimulation of the vagi has no apparent effect; while extirpation of the large sympathetic abdominal ganglia causes the intestinal canal to be filled with a watery fluid, and gives rise to diarrhœa. This may be explained by the paralysis of the vasomotor nerves, and also by the section of large lymphatic vessels during the operation, whereby absorption is interfered with and transudation is favored. **Moreau's Experiment.**—Moreau placed four ligatures on a loop of intestine at equal distances from each other (Fig. 202). The ligatures were tied so that three loops of intestine were shut off. The nerves (N) to the middle loop were divided, and the intestine was replaced in the abdominal cavity. After a time, a very small amount of secretion, or none at all, was found in two of the ligatured compartments of the gut, *i. e.*, in those with the nerves and blood vessels intact (1, 3),

FIG. 202.

Scheme of Moreau's experiment (*Stirling*).

but the compartment (2) whose nerves had been divided contained a watery secretion. Perhaps the secretion which occurs after section of the mesenteric nerves is a paralytic secretion. The secretion of the intestinal and gastric juices is **diminished** in man in certain nervous affections (hysteria, hypochondriasis, and various cerebral diseases); while in other conditions these secretions are increased.

Excretion of Drugs.—If an isolated intestinal fistula be made, and various drugs administered, the mucous membrane excretes iodine, bromine, lithium, sulphocyanides, but *not* potassium ferrocyanide, arsenious or boracic acid, or iron salts.

In **sucklings,** not unfrequently a large amount of acid is formed, when the fungi in the intestine split up milk sugar or grape sugar into lactic acid (*Leube*). Starch changed into grape sugar may undergo the same abnormal process; hence, infants ought not to be fed with starchy food.

[**Fate of the Ferments.**—Langley is of opinion that the digestive ferments are destroyed in the intestinal canal; the diastatic ferment of saliva is destroyed by the free HCl of the gastric juice; pepsin and rennet are acted upon by the alkaline salts of the pancreatic and intestinal juices, and by trypsin; while the diastatic and peptic ferments of the pancreas disappear under the influence of the acid fermentation in the large intestine.]

184. **FERMENTATION IN THE INTESTINE.**—Those processes which are to be regarded as fermentations or putrefactive processes, are quite different from those caused by the digestive enzymes or ferments just considered. The **putrefactive changes** are connected with the presence of lower organisms, so-called fermentation or putrefaction producers; and they may develop in suitable media outside the body. The lowly organisms which cause the intestinal fermentation are swallowed with the food and drink, and also with the saliva. When they are introduced, fermentation and putrefaction begin, and *gases are evolved.*

Intestinal Gases.—During the whole of the fœtal period, until birth, fermentation cannot occur; hence gases are never present in the intestine of the newly-born. The first air bubbles pass into the intestine with the saliva which is swallowed, even before food has been taken. The germs of organisms are thus introduced into the intestine, and give rise to the formation of gases. The evolution of intestinal gases goes hand-in-hand with the fermentations. Air is also swallowed, and an exchange of gases takes place in the intestine, so that the composition of the intestinal gases depends upon various conditions. Kolbe and Ruge collected the gases from the anus of a man, and found in 100 vols.:—

Food.	CO_2.	H.	CH_4.	N.	H_2S.
Milk, ...	16.8	43.3	0.9	38.3	Quantity not estimated.
Flesh, ...	12.4	2.1	27.5	57.8	
Peas, ...	21.0	4.0	55.9	18.9	

1. Air bubbles are swallowed with the food. The O is rapidly absorbed in the intestinal tract, so that in the lower part of the large intestine, even traces of O are absent. In exchange, the blood vessels in the intestinal wall give off CO_2 into the intestine, so that part of the CO_2 in the intestine is driven by diffusion from the blood.

2. H, CO_2, NH_3, and CH_4 are also formed from the intestinal contents by fermentation, which takes place even in the small intestine.

Fungi.—The chief agents in the production of fermentations, putrefaction and other similar decompositions are undoubtedly the group of fungi called **schizomycetes.** They are small unicellular organisms of various forms—globular, **micrococcus**; short rods, **bacterium**; long rods, **bacillus**; or spiral threads, **vibrio, spirillum, spirochæta** (Fig. 23). The mode of reproduction is by division, and they may either remain single or unite to form colonies. Each organism is usually capable of some degree of motion. They produce profound chemical changes in the fluids or media in which they grow and multiply, and these changes depend upon the vital activity of their protoplasm. These minute microscopic organisms take certain constituents from the "nutrient fluids" in which they live, and use them partly for building up their own tissues and partly for their own metabolism. In these processes, some of the substances so absorbed and assimilated undergo chemical changes, some *ferments* seem thereby to be produced, which in their turn may act upon material present in the nutritive fluid.

These fungi consist of a **capsule** enclosing protoplasmic **contents.** Many of them are provided with

excessively delicate cilia, by means of which they move about. The new organisms, produced by the division of pre-existing ones, sometimes form large colonies visible to the naked eye, the individual fungi being united by a jelly-like mass, the whole constituting **zoogloea**. In some fungi, reproduction takes place by **spores**; more especially when the nutrient fluids are poor in nutritive materials. The bacteria form longer rods or threads, which are jointed, and in each joint or segment small (1–2 μ), highly refractive globules or *spores* are developed (Fig. 203, 7). In some cases, as in the butyric acid fermentation, the rods become fusiform before spores are formed. When the envelope of the mother cell is ruptured or destroyed, the spores are liberated, and if they fall upon or into a suitable medium, they germinate and reproduce organisms similar to those from which they sprang. The process of **spore production** is illustrated in Fig. 203, 7, 8, 9, and in 1, 2, 3, 4 is shown the process of **germination** in the butyric acid fungus. The spores are very tenacious of life; they may be dried, when they resist death for a very long time; some of them are killed by being boiled. Some fungi exhibit their vital activities only in the presence of O (**ærobes**), while others require the exclusion of O (**anærobes**, *Pasteur*). According to the products of their action, they are classified as follows: Those that produce *fermentations* (**zymogenic** schizomycetes); those that produce *pigments* (**chromogenic**); those that produce disagreeable *odors*, as during putrefaction (**bromogenic**); and those that, when introduced into the living tissues of other organisms, produce *pathological conditions*, and even death (**pathogenic**). All these different kinds occur in the human body.

When we consider that numerous fungi are introduced into the intestinal canal with the food and drink—that the temperature and other conditions within this tube are specially favorable for their

FIG. 203.

A, *Bacterium aceti* in the form of cocci (1); diplococci (2); short rods (3); and jointed threads (4, 5). *Bacillus butyricus* (1) isolated spore; (2, 3, 4) germinating condition of the spores; (5, 6) short and long rods; (7, 8, 9) formation of spores within a cellular fungus.

development; that there also they meet with sufficient pabulum for their development and reproduction—we cannot wonder that a rich crop of these organisms is met with in the intestine, and that they produce there numerous fermentations.

I. Fermentation of Carbohydrates.—(1) **Bacillus acidi lactici** consists of biscuit-shaped cells, 1.5–3 μ in length, arranged in groups or isolated. They split up grape sugar into lactic acid;

$$1 \text{ grape sugar} = C_6H_{12}O_6 = 2(C_3H_6O_3) = 2 \text{ lactic acid.}$$

Milk sugar ($C_{12}H_{22}O_{11}$) can be split up by the same ferment causing it to take up H_2O, and forming 2 molecules of grape sugar, $2(C_6H_{12}O_6)$, which are again split into 4 molecules of lactic acid $4(C_3H_6O_3)$.

This fungus and its spores occur everywhere in the atmosphere, and are the cause of the spontaneous acidification and subsequent coagulation of milk (§ 230).

(2) **Bacillus butyricus**, which in the presence of starch is often colored blue by iodine, changes lactic acid into butyric acid, together with CO_2 and H (*Prazmowski*).

$$2(C_3H_6O_3) \text{ lactic acid} = \begin{cases} C_4H_8O_2 = 1 \text{ butyric acid.} \\ 2(CO_2) = 2 \text{ carbon dioxide.} \\ 4H = 4 \text{ hydrogen.} \end{cases}$$

This fungus (Fig. 203, B) is a true anærobe, and grows only in the absence of O. The lactic acid fungus uses O very largely, and is, therefore, its natural precursor. The butyric acid fermentation is the last change undergone by many carbohydrates, especially by starch and inulin. It takes place constantly in the fæces.

(3) Certain **micrococci** cause *alcohol* to be formed from carbohydrates. The presence of **yeast** may cause the formation of alcohol in the intestine, and in both cases also from milk sugar, which first becomes changed into dextrose.

(4) Bacterium aceti (Fig. 203, A) converts alcohol into acetic acid outside the body. Alcohol (C_2H_6O) + O = C_2H_4O (Aldehyd) + H_2O. Acetic acid ($C_2H_4O_2$) is formed from aldehyd by oxidation. According to Nägeli, the same fungus causes the formation of a small amount of CO_2 and H_2O. As the acetic fermentation is arrested at 35° C., this fermentation cannot occur in the intestine, and the acetic acid, which is constantly found in the fæces, must be derived from another source. During putrefaction of the proteids, with exclusion of air, acetic acid is produced (*Nencki*).

(5) **Starch** and **cellulose** are partly *dissolved* by the schizomycetes (Bac. butyricus and Vibrio rugula) of the intestine. If cellulose be mixed with cloacal mucus, or with the contents of the intestine, it passes into a saccharine carbohydrate which decomposes into equal volumes of CO_2 and CH_4 (*Hoppe-Seyler*).

(6) Fungi, whose rature is unknown, can partly transform *starch* (? and cellulose) into sugar.

(7) Others produce **invertin.** Invertin changes cane sugar into invert-sugar

FIG. 204.



Bacillus subtilis. 1, spore; 2, 3, 4, its germination; 5, 6, short rods; 7, jointed thread, with the formation of spores in each segment; 8, short rods, some of them containing spores; 9, spores in single short rods; 10, fungus with a cilium.

(§ 183, II, 5). Cane sugar, $C_{12}H_{22}O_{11} + H_2O = C_6H_{12}O_6$ (Dextrose) + $C_6H_{12}O_6$ (Lævulose).

II. Fermentation of Fats (§ 251). During putrefaction, organisms of an unknown nature cause neutral fats to take up water and split into glycerine and their corresponding fatty acid (§ 170). **Glycerine** is capable of undergoing several fermentations, according to the fungus which acts upon it (§ 251). With a neutral reaction, in addition to succinic acid, a number of fatty acids, H and CO_2, are formed.

Fitz found that the *hay bacillus* (Bacillus subtilis, Fig. 204) formed alcohol with caproic, butyric, and acetic acids; in other cases, especially butylic alcohol, van de Velde found butyric, lactic, and traces of succinic acid with CO_2, H_2O, N.

The **fatty acids**, especially as chalk soaps, form an excellent material for fermentation. Calcium formiate mixed with cloacal mucus ferments and yields calcium carbonate, CO_2 and H; calcium acetate, under the same conditions, produces calcium carbonate, CO_2 and CH_4. Among the *oxy-acids*, we are acquainted with the fermentations of lactic, glycerinic, malic, tartaric, and citric acids.

According to Fitz, *lactic acid* (in combination with chalk) produces propionic and acetic acids, CO_2, H_2O. Other ferments cause the formation of valerianic acid. *Glycerinic acid*, in addition to

alcohol and succinic acid, yields chiefly acetic acid; *malic acid* forms succinic and acetic acid. The other acids above enumerated yield somewhat similar products.

III. Fermentation of Proteids (§ 249).—The undigested proteids and their derivatives appear to be acted upon by fungi. Many schizomycetes (hay bacillus and Bac. subtilis), however, can produce a peptonizing ferment. We have already seen that pancreatic digestion acts upon the proteids, forming, among other products, amido-acids, leucin, tyrosin, and other bodies (§ 170, II). Under normal conditions, this is the greatest decomposition produced by the pancreatic juice. The putrefactive fermentation of the large intestine causes further and more profound decompositions. **Leucin** ($C_6H_{13}NO_2$) takes up two molecules of water and yields valerianic acid ($C_5H_{10}O_2$), ammonia, CO_2 and $2(H_2)$; **glycin** behaves in a similar manner. **Tyrosin** ($C_9H_{11}NO_3$) is decomposed into **indol** (C_8H_7N), which is constantly present in the intestine along with CO_2, H_2O, H. If O be present, other decompositions take place. These putrefactive products are absent from the intestinal canal of the fœtus and the newly-born. During the putrefactive decomposition of proteids, CO_2, H_2S, H, and CH_4, are formed; the same result is obtained by boiling them with alkalies. **Gelatin**, under the same conditions, yields much leucin and ammonia, CO_2, acetic, butyric, and valerianic acids, and glycin. Mucin and nuclein undergo no change. Artificial pancreatic digestion experiments rapidly tend to undergo putrefaction.

The substance which causes the peculiar **fecal odor** is produced by putrefaction, but its nature is not known. It clings so firmly to indol and skatol that these substances were formerly regarded as the odorous bodies, but when they are prepared pure they are odorless (*Bayer*).

Among the solid substances in the large intestine formed *only by putrefaction* is **indol** (C_8H_7N), a substance which is also formed when proteids are heated with alkalies, or by superheating them with water to 200° C. It is the stage preceding the indican in the urine. If the products of the digestion of the proteids—the peptones—are rapidly absorbed, there is only a slight formation of indol; but when absorption is slight, and putrefaction of the products of pancreatic digestion occurs, much indol is formed, and indican appears in the urine.

Jaffé found much indican in the urine in strangulated hernia, and when the small intestine was obstructed.

Reactions for Indol.—Acidulate strongly with HCl, and shake vigorously after adding a few drops of turpentine. If there be an intense red color, the pigment is removed by ether. The substance which is formed after the digestion of fibrin by trypsin, and which gives a violet color with bromine water (§ 170, 2), can be removed by chloroform. In addition to the last pigment, there is a second one, which passes over during distillation, and which can be extracted from the distillate by ether. Both substances seem to belong to the indigo group (*Krukenberg*).

A. Bayer prepared indigo-blue artificially from ortho-phenyl-propionic acid, by boiling it with dilute caustic soda, after the addition of a little grape sugar. He obtained indol and skatol from indigo-blue. Hoppe-Seyler found that on feeding rabbits with ortho-nitrophenyl-propionic acid, much indican was present in the urine.

Phenol (C_6H_6O) is formed during putrefaction in the intestine, and it is also formed when fibrin and pancreatic juice putrefy outside the body, while Brieger found it constantly in the fæces. It seems to be increased by the same circumstances that increase indol, as an excess of indican in the urine is accompanied by an increase of phenylsulphonic acid in that fluid (§ 262).

From putrefying flesh and fibrin, amido-phenylpropionic acid is obtained, as a decomposition product of tyrosin. A part of this is transformed by putrefactive ferments into hydrocinnamic acid (phenylpropionic acid). The latter is completely oxidized in the body into benzoic acid, and appears as hippuric acid in the urine. Thus is explained the formation of hippuric acid from a purely albuminous diet.

Skatol (C_9H_9N = methyl-indol) is a constant human fecal substance, and has been prepared artificially by Nencki and Secretan from egg albumin, by allowing

it to putrefy for a long time under water. It also appears in the urine as a sulphur compound. The **excretin** of human fæces, described by Marcet, is related to cholesterin, but its history and constitution are unknown.

According to Salkowski, skatol and indol are both formed from a common substance which exists preformed in albumin, and which, when it is decomposed, at one time yields more indol, at another skatol, according as the hypothetical "*indol fungus*," or "*skatol fungus*," is the more abundant.

It is of the utmost importance, in connection with the processes of putrefaction, to determine whether they take place when oxygen is excluded, or not. When O is absent, **reductions** take place; oxy-acids are reduced to fatty acids, and H_2CH_4 and H_2S are formed; while the H may produce further reductions. If O be present, the nascent H separates the molecule of free ordinary oxygen ($=O_2$) into two atoms of active oxygen ($=O$). Water is formed on the one hand, while the second atom of O is a powerful oxidizing agent (*Hoppe-Seyler*).

It is remarkable that the putrefactive processes, after the development of phenol, indol, skatol, cresol, phenylpropionic and phenylacetic acids are subsequently limited, and after a certain concentration is reached, they cease altogether. The putrefactive process produces antiseptic substances which kill the micro-organisms, so we may assume that these substances limit to a certain extent the putrefactive processes in the intestine.

The **reaction** of the intestine immediately below the stomach is acid, but the pancreatic and intestinal juices cause a neutral and afterward an alkaline reaction, which obtains along the whole small intestine. In the large intestine, the reaction is generally acid, on account of the acid fermentation and the decomposition of the ingesta and the fæces.

185. PROCESSES IN THE LARGE INTESTINE.—Within the large intestine, the fermentative and putrefactive processes are certainly more prominent than the digestive processes proper, as only a very small amount of the intestinal juice is found in it. The **absorptive** function of the large intestine is greater than its secretory function, for at the beginning of the colon its contents are thin and watery, but in the further course of the intestine they become more solid. Water and the products of digestion in the solution are not the only substances absorbed, but under certain circumstances, unchanged fluid egg albumin, milk and its proteids, flesh juice, solution of gelatin, myosin with common salt, may also be absorbed. Experiments with acid albumin, syntonin, or blood serum gave no result. Toxic substances are certainly absorbed more rapidly than from the stomach. [In the dog the secretion of the large intestine has no digestive properties, but fats are absorbed in it. Klug and Koreck regard its Lieberkühnian glands not as secreting but as absorbing structures.] The fecal matters are *formed* or rather *shaped* in the lower part of the gut. The cæcum of many animals, *e. g.*, rabbit, is of considerable size, and in it fermentation seems to occur with considerable energy, giving rise to an acid reaction. In man, the chief function of the cæcum is absorption, as is shown by the great number of lymphatics in its walls. From the lower part of the small intestine and the cæcum onward, the ingesta assume the fecal odor.

The **amount of fæces** is about [5 oz. or] 170 grms. (60 to 250 grms.) in twenty-four hours; but if much indigestible food be taken, it may be as much as 500 grms. The amount is less, and the absolute amount of solids is less, after a diet of flesh and albumin, than after a vegetable diet. The fæces are rendered lighter by the evolution of gases, and hence they float in water.

The **consistence** depends on the amount of water present—usually about 75 per cent. The amount of water depends partly on the food—pure flesh diet causes relatively dry fæces, while substances rich in sugar yield fæces with a relatively large amount of water. The quantity of water taken has no effect upon the amount of water in the fæces. But the energy of the peristalsis has. The more energetic the peristalsis is, the more watery the fæces are, because sufficient

time is not allowed for absorption of the fluid from the ingesta. Paralysis of the blood and lymph vessels, or section of the nerves, leads to a watery condition of the fæces (§ 183).

The **reaction** is often acid, in consequence of lactic acid being developed from the carbohydrates of the food. Numerous other acids produced by putrefaction are also present (§ 184). If much ammonia be formed in the lower part of the intestine, a neutral or even alkaline reaction may obtain. A copious secretion of mucus favors the occurrence of a neutral reaction.

The **odor**, which is stronger after a flesh diet than after a vegetable diet, is caused by some fecal products of putrefaction, which have not yet been isolated; also by volatile fatty acids and by sulphuretted hydrogen, when it is present.

The **color** of the fæces depends upon the amount of altered bile pigments mixed with them, whereby a bright yellow to a dark brown color is obtained.

The color of the food is also of importance. If much blood be present in the food, the fæces are almost brownish-black, from hæmatin; green vegetables = brownish-green, from chlorophyll; bones (*dog*) = white, from the amount of lime; preparations of iron = black, from the formation of sulphide of iron.

The **fæces** contain—

(1) The unchanged residue of animal or vegetable tissues used as food; hairs, horny and elastic tissues; most of the cellulose, woody fibres, spiral vessels of vegetable cells, gums.

(2) Portions of digestible substances, especially when these have been taken in too large amount, or when they have not been sufficiently broken up by chewing. Portions of muscular fibres, ham, tendon, cartilage, particles of fat, coagulated albumin—vegetable cells from potatoes, and other vegetables, raw starch, etc.

All food yields a certain amount of residue—white bread, 3.7 per cent.; rice, 4.1 per cent.; flesh, 4.7 per cent.; potatoes, 9.4 per cent.; cabbage, 14.9 per cent.; black bread, 15 per cent.; yellow turnip, 20.7 per cent. (*Rubner*).

(3) The decomposition products of the bile pigments, which do not now give Gmelin's reaction; as well as the altered bile acids (§ 177, 2). This reaction, however, may be obtained in pathological stools, especially in those of a green color; unaltered bilirubin, biliverdin, glycocholic and taurocholic acids occur in meconium (§ 182).

[MacMunn found no unchanged bile pigments in the fæces. A substance called **stercobilin** is obtained from the fæces, and it closely resembles what has been called "febrile" urobilin, but it is certainly different from normal urobilin.]

(4) Unchanged mucin and nuclein—the latter occasionally after a diet of bread, together with partially disintegrated cylindrical epithelium from the intestinal canal, and occasionally drops of oil. Cholesterin is very rare. [Ten grains of a substance, **stercorin**, said to be a modification of cholesterin, occur in the fæces, (*Flint*).] The less the mucus is mixed with the fæces, the lower the part of the intestine from which it was derived (*Nothnagel*).

(5) After a milk diet, and also after a fatty diet, crystalline needles of lime combined with fatty acids and chalk soaps constantly occur, even in sucklings (*Wegscheider*). Even unchanged masses of casein and fat occur during the milk cure. Compounds of ammonia, with the acids mentioned as the result of putrefaction (§ 184, III), belong to the fecal matters (*Brieger*).

(6) Among **inorganic residues**, soluble salts rarely occur in the fæces because they diffuse readily, *e. g.*, common salt, and the other alkaline chlorides, the compounds of phosphoric acid, and some of those of sulphuric acid. The **insoluble compounds** of which ammoniaco-magnesic or triple phosphate, neutral calcic phosphate, yellow-colored lime salts, calcium carbonate, and magnesium phosphate are the chief, form 70 per cent. of the ash. Some of these insoluble substances are derived from the food, as lime from bones, and in part they are

excreted after the food has been digested, as ashes are eliminated from food which has been burned.

Concretions.—The excretion of inorganic substances is sometimes so great, that they form incrustations around other fecal matters. Usually ammoniaco-magnesic phosphate occurs in large crystals by itself, or it may be mixed with magnesium phosphate.

(7) **Micro-organisms.**—A considerable portion of normal fecal matter consists of micrococci and micro-bacteria; yeast is seldom absent (*Frerichs, Nothnagel*).

To isolate the individual fungi, Escherich has made **pure cultivations** from the intestinal contents of sucklings, and Bienstock from adults. In the intestine of **sucklings** which have been nourished entirely on their mother's milk, the *Bacterium lactis aërogenes* (Fig. 205, 2) causes the lactic acid fermentation with the evolution of CO_2 and H, in the upper part of the canal where some milk sugar is still unabsorbed. In the **evacuations** is the characteristic slender *Bacterium coli commune* (Fig. 205, 1). In addition, occasionally there are other bacilli, cocci, spores of yeast, and a mould.

FIG. 205.



1, Bacterium coli commune; 2, bacterium lactis aërogenes; 3 and 4, the large bacilli of Bienstock, with partial endogenous spore formation: 5, the various stages in the development of the bacillus which causes the fermentation of albumin.

In the fæces of an **adult**, Bienstock detected two large forms of bacilli (Fig. 205, 3, 4), closely resembling Bacillus subtilis in form and size, but distinguished from it only by the form of its pure cultivation, by the mode of growth of its spores, and by the absence of movements. These two forms can be distinguished microscopically by the mode of their cultivation, which is either in the form of a grape or a flat membrane. These two do not excite a fermentative action. A third micrococcus-like, small, very slowly developing bacillus occurs in three-fourths of all stools. A fourth kind (absent in sucklings) is the specific bacillus (§ 184, III), causing the decomposition of albumin, resulting in the products of putrefaction and a fecal odor. This is the only bacillus that excites these processes in the intestine; but it does not decompose casein and alkali albumin. In Fig. 205, 5, *a–g*, the stages in the development of this bacillus are represented, but the stages from *c* and *g* are absent in the fæces, and are found only in artificial cultivations.

If the fæces are simply investigated microscopically and without special precautions, there are other fungi, some of which may be introduced through the anus. In stools that contain much starch, the bacillus butyricus, which is tinged blue with iodine, occurs (§ 184), and other small globular or rod-like fungi, which give a similar reaction (*Nothnagel, Uffelmann*).

The changes of the intestinal contents have been studied on persons with an accidental intestinal fistula, or an artificial anus.

[The following scheme from Krukenberg shows graphically the reaction of the contents of the various parts of the alimentary canal, and also the distribution of the ferments.]



186. PATHOLOGICAL VARIATIONS.—A. The **taking of food** may be interfered with by spasm of the muscles of mastication (usually accompanied by general spasms), stricture of the œsophagus, by cicatrices after swallowing caustic fluids (*e.g.*, caustic potash, mineral acids), or by the presence of a tumor, such as cancer. Inflammation of all kinds in the mouth or pharynx interferes with the taking of food. Inability to swallow occurs as part of the general phenomena in disease of the medulla oblongata, in consequence of paralysis of the motor centre (superior olives) for the facial, vagus, and hypoglossal nerves, and also for the afferent or sensory fibres of the glosso-pharyngeal, vagus, and trigeminus. Stimulation or abnormal excitation of these parts causes spasmodic swallowing, and the disagreeable feeling of a constriction in the neck (globus hystericus).

B. The **secretion of saliva is diminished** during inflammation of the salivary glands; occlusion of their ducts by concretions (salivary calculi); also by the use of atropin, daturin, and during fever, whereby the secretory (not the vasomotor) fibres of the chorda appear to be paralyzed (§ 145). When the fever is very high, no saliva is secreted. The saliva secreted during moderate fever is turbid and thick, and usually acid. As the fever increases, the diastatic action of the saliva diminishes. The secretion is **increased** by stimulation of the buccal nerves (inflammation, ulceration, trigeminal neuralgia), so that the saliva is secreted in great quantity. Mercury and jaborandi cause secretion of saliva, the former causing stomatitis, which excites the secretion of saliva reflexly. Even diseases of the stomach accompanied by vomiting cause secretion of saliva. A very thick, tenacious, sympathetic saliva occurs when there is violent stimulation of the vascular system during sexual excitement, and also during certain psychical conditions. The *reaction* of the saliva is acid in catarrh of the mouth, in fever in consequence of decomposition of the buccal epithelium, and in diabetes mellitus in consequence of acid fermentation of the saliva which contains sugar. Hence, diabetic persons often suffer from carious teeth. Unless the mouth of an infant be kept scrupulously clean, the saliva is apt to become acid.

C. Disturbances in the activity of the **musculature of the stomach** may be due to paralysis of the muscular layers, whereby the stomach becomes distended, and the ingesta remain a long time in it. A special form of paralysis of the stomach is due to non-closure of the pylorus (*Ebstein*). This may be due to disturbances of innervation of a central or peripheral nature, or there may be actual paralysis of the pyloric sphincter, or anæsthesia of the pyloric mucous membrane, which acts reflexly upon the sphincter muscle; and lastly, it may be due to the reflex impulse not being transferred to the efferent fibre within the nerve centre. Abnormal activity of the gastric musculature hastens the passage of the ingesta into the intestine; vomiting often occurs.

D. Gastric digestion is **delayed** by violent bodily or mental exercise, and sometimes it is arrested altogether. Sudden mental excitement may have the same effect. These efforts are very probably caused through the vasomotor nerves of the stomach. Feeble and imperfect digestion may be of a purely nervous nature (Dyspepsia nervosa—*Leube;* Neurasthenia gastrica—(*Burkart*). An excessive formation of acid may be due to nervous disturbance, and is called "nervous gastroxynsis" by Rossbach.

[**Action of Alcohol, Tea, etc., in Digestion.**—According to J. W. Fraser, all infused beverages, tea, coffee, cocoa, retard the peptic digestion of proteids, with few exceptions. The retarding action is less with coffee than with tea. The tannic acid and volatile oil seem to be the retarding ingredients in teas. Distilled Spirits—brandy, whisky, gin—have but a trifling retarding effect on the digestive processes; and when one considers their action on the secretory glands, it follows that in moderate dietetic doses they promote digestion. Wines are highly inimical to salivary digestion, but this is due to their acidity; and this effect can be removed by the addition of an alkali. Wines retard peptic digestion, the sparkling less than the still wines. Tea has an intensely inhibitory action on salivary digestion; in fact a small quantity paralyzes the action of saliva, while coffee has only a slight effect. This action of tea is due to the tannin. Tea, coffee, and cocoa all retard peptic digestion, when they form 20 per cent. of the digestive mixture (*W. Roberts*).]

Inflammatory or catarrhal affections of the stomach, as well as ulceration and new formations, interfere with digestion, and the same result is caused by eating too much food which is difficult of digestion, or taking too much highly spiced sauce or alcohol. In the case of a dog suffering from chronic gastric catarrh, Grützner observed that the secretion took place continuously, and that the gastric juice contained little pepsin, was turbid, sticky, feebly acid, and even alkaline. The introduction of food did not alter the secretion, so that in this condition the stomach really obtains no rest. The chief cells of the gastric glands were turbid. Hence, in gastric catarrh, we ought to eat frequently, but take little at a time, while at the same time dilute hydrochloric acid ought to be administered (0.4 per cent.). Small doses of common salt seem to aid digestion.

[**Absence of HCl.**—HCl is almost always absent in carcinoma of the stomach (*van de Velde*), amyloid degeneration of the gastric mucous membrane (*Edinger*), and sometimes in fever. In all these cases the acid reaction is due to lactic or butyric acid. The absence of HCl in cancer of the stomach is an important diagnostic and prognostic symptom. It is not absent in simple dilatation of the stomach. Test the contents of the stomach for free HCl with tropæolin (red color), methyl violet (blue), and with ferric chloride and carbolic acid (*Uffelmann*). $\frac{1}{20}$ per cent. of free HCl causes the

amethyst blue of the last to become steel gray, while somewhat more discharges the color altogether. [In testing for the presence of **free lactic acid** in the gastric contents use Uffelmann's reaction (§ 163). The lactic acid is easily extracted by ether from the gastric contents, and the reaction can then be performed with the residue obtained after evaporating the ether. A solution of 1 drop of the liquor perchloride in 50 c. c. of water is made yellow by lactic acid.]

Feeble digestion may be caused either by imperfect formation of acid or pepsin, so that both substances may be administered in such a condition. [It may also be due to deficient muscular power in the wall of the stomach.] In other cases, lactic, butyric, and acetic acids are formed, owing to the presence of lowly organisms. In such cases, small doses of salicylic acid, together with some hydrochloric acid, are useful. Pepsin need not be given often, as it is rarely absent, even from the diseased gastric mucous membrane. Albumin has been found in the gastric juice in cases of gastric catarrh and cholera.

E. Digestion during fever and Anæmia.—Beaumont found that in the case of Alexis St. Martin, when fever occurred, a small amount of gastric juice was secreted; the mucous membrane was dry, red, and irritable. Dogs suffering from septicæmic fever, or rendered anæmic by great loss of blood, secrete gastric juice of feeble digestive power and containing little acid (*Manassein*). [In acute diseases accompanied by fever, the inner cells of the fundus glands of the human stomach may disappear (*C. Kupffer*).] Hoppe-Seyler investigated the gastric juice of a typhus patient in which van de Velde found no free acid. Usually no free hydrochloric acid is found in cancer of the stomach. The gastric juice of the typhus patient did not digest artificially, even after the addition of hydrochloric acid. The diminution of acid, under these circumstances, favors the occurrence of a neutral reaction, so that, on the one hand, digestion cannot proceed, and on the other, fermentative processes (lactic and butyric acid fermentations with the evolution of gases) occur. These results are associated with the presence of micro-organisms and *Sarcina ventriculi* (*Goodsir*). Uffelmann found that the secretion of a peptone-forming gastric juice ceased in fever, when the fever is severe at the outset, when a feeble condition occurs, or when the temperature is very high. The amount of juice secreted is certainly diminished during fever. The excitability of the mucous membrane is increased, so that vomiting readily occurs. The increased excitability of the vasomotor nerves during fever is disadvantageous for the secretion of the digestive fluids (*Heidenhain*). Beaumont observed that fluids are rapidly absorbed from the stomach during fever, but the absorption of peptones is diminished on account of the accompanying catarrhal condition of the stomach, and the altered functional activity of the muscular mucosæ (*Leube*).

Many **salts**, when given in *large* amount, disturb gastric digestion, *e. g.*, the sulphates. While the alkaloids, morphia, strychnia, digitalin, narcotin, veratria have a similar action, quinine favors it (*Wolberg*). In some nervous individuals "peristaltic unrest of the stomach," conjoined with a dyspeptic condition, occurs (*Kussmaul*). [Professor James directs attention to the value of peptic and pancreatic salts, which are preparations of common salt mixed with pepsin and the ferments of the pancreas respectively.]

[**Artificial Digestion** is affected by various salts according to their nature and dilution. The digestion of *fibrin by pepsin* goes on best without the addition of salts, being diminished by magnesic sulphate, sodic carbonate, and sulphate. The digestion of fibrin by pancreatic extract is accelerated by sodic carbonate (*Heidenhain*), and retarded by $MgSO_4$ and Na_2SO_4. The diastatic action of the saliva and pancreas on starch is greatly accelerated by NaCl (2 per cent.), while Na_2CO_3, Na_2SO_4, and $MgSO_4$ hinder it (*Pfeiffer*).] According to Schütz, artificial gastric digestion is retarded by a 2 per cent. solution of alcohol, and also by a solution of salicylic acid (.06 to .1 per cent.). Buchner, however, finds that 10 per cent. of alcohol does not affect artificial gastric digestion, while above 20 per cent. arrests it. Beer hinders digestion.

F. In acute diseases, the **secretion of bile** is affected; it becomes less in amount and more watery, *i. e.*, it contains fewer specific constituents. If the liver undergoes great structural change, the secretion may be arrested.

G. Gall Stones.—When decomposition of the bile occurs, gall stones are formed in the *gall bladder* or in the *bile ducts*. Some are *white*, and consist almost entirely of stratified layers of crystals of **cholesterin.** The *brown* forms consist of bilirubin-lime, and calcium carbonate, often mixed with iron, copper, and manganese. The gall stones in the gall bladder become facetted by rubbing against each other. The nucleus of the white stones often consists of chalk and bile-coloring matters, together with nitrogenous residues, derived from shed epithelium, mucin, bile salts, and fats. Gall stones may occlude the bile duct and cause cholæmia. When a small stone becomes impacted in a duct, it gives rise to excessive pain, constituting hepatic colic, and may even cause rupture of the bile duct with its sharp edges.

H. Nothing certain has been determined regarding the **pancreatic secretion** in disease, but in fever it appears to be diminished in amount and digestive activity. The suppression of the pancreatic secretion [as by a cancerous tumor of the head of the pancreas], is often accompanied by the appearance of fat, in the form of globules or groups of crystals in the fæces.

I. Constipation is a most important derangement of the digestive tract. It may be caused by—(1) Conditions which *obstruct the normal channel, e. g.*, constriction of the gut from stricture—in the

large gut after dysentery, tumors, rotation on its axis of a loop of intestine (volvulus), or invagination, occlusion of a coil of gut in a hernial sac, or by the pressure of tumors or exudations from without, or congenital absence of the anus. (2) Too great *dryness* of the contents, caused by too little water in the articles of diet, diminution of the amount of the digestive secretions, *e. g.*, of bile in icterus; or in consequence of much fluid being given off by other organs, as after copious secretion of saliva, milk, or in fever. (3) Variations in the functional activity of the *muscles* and *motor nervous apparatus* of the gut may cause constipation, owing to imperfect peristalsis. This condition occurs in inflammations, degenerations, chronic catarrh, and diaphragmatic inflammation. Affections of the spinal cord, and sometimes also of the brain, are usually accompanied by slow evacuation of the intestine. Whether diminished mental activity and hypochondriasis are the cause of or are caused by constipation, is not proved. Spasmodic contraction of a part of the intestine may cause temporary retention of the intestinal contents, and, at the same time, give rise to great pain or colic; the same is true of spasm of the anal sphincter, which may be excited reflexly from the lower part of the gut. The fecal masses in constipation are usually hard and dry, owing to the water being absorbed; hence they form large masses or *scybala* within the large intestine, and these again give rise to new resistance. Among the reagents which prevent evacuation of the bowels, some paralyze the motor apparatus temporarily, *e. g.*, opium, morphia; some diminish the secretion of the intestinal mucous membrane, and cause constriction of the blood vessels, as tannic acid, vegetables containing tannin, alum, chalk, lead acetate, silver nitrate, bismuth nitrate.

J. Increased *evacuation of the intestinal contents* is usually accompanied by a watery condition of the fæces, constituting **diarrhœa.** The causes are:—

1. A too rapid movement of the contents through the intestine, chiefly through the large intestine, so that there is no time for the normal amount of absorption to take place. The increased peristalsis depends upon stimulation of the motor nervous apparatus of the intestine, usually of a reflex nature. Rapid transit of the contents through the intestine causes the evacuation of certain substances which cannot be digested in so short a time.

2. The stools become thinner from the presence of much water, mucus, and the admixture with fat, and by eating fruit and vegetables. In rare cases, when the evacuations contain much mucin, Charcot's crystals occur (Fig. 144, *c*). In ulceration of the intestine, leucocytes (pus) are present (*Nothnagel*).

3. Diarrhœa may occur as a consequence of disturbance of the diffusion processes through the intestinal walls, as in affections of the epithelium, when it becomes swollen in inflammatory or catarrhal conditions of the intestinal mucous membrane. [Irritation over the abdomen, as from the subcutaneous injection of small quantities of saline solutions, causes diarrhœa.]

4. It may also be due to increased secretion into the intestine, as in capillary diffusion, when magnesium sulphate in the intestine attracts water from the blood.

The same occurs in cholera, when the stools are copious and of a rice-water character, and are loaded with epithelial cells from the villi. The transudation into the intestine is so great that the blood in the arteries becomes very thick, and may even on this account cease to circulate.

Transudation into the intestine also takes place as a consequence of paralysis of the vasomotor nerves of the intestine. This is perhaps the case in diarrhœa following upon a cold. Certain substances seem directly to excite the secretory organs of the intestines or their nerves, such as the drastic purgatives (§ 180). Pilocarpin injected into the blood causes great secretion (*Masloff*).

During **febrile conditions,** the secretion of the intestinal glands seems to be altered quantitatively and qualitatively, with simultaneous alteration of the functional activity of the musculature and the organs of absorption, while the excitability of the mucous membrane is increased (*Uffelmann*). It is important to note that in many acute febrile diseases the amount of common salt in the urine diminishes, and increases again as the fever subsides.

187. **COMPARATIVE.—Salivary Glands.**—Among **mammals,** the herbivora have larger salivary glands than the carnivora; while midway between both are the omnivora. The whale has no salivary glands. The pinnipedia have a small parotid, which is absent in echidna. The dog and many carnivora have a special gland lying in the orbit, the *orbital* or *zygomatic gland*. In **birds** the salivary glands open at the angle of the mouth, but the parotid is absent. Among **reptiles** the parotid of some species is so changed as to form poison glands; the tortoise has sub-lingual glands; reptiles have labial glands. The **amphibia** and **fishes** have merely small glands scattered over the mouth. The salivary glands are large in **insects**; some of them secrete formic acid. The salivary glands are well developed in mollusks, and the saliva of Dolium galea contains more than 3 per cent. of free sulphuric acid (?). The cephalopods have double glands.

A **crop** is not present in any mammal; the stomach is either *simple*, as in man, or, as in many rodents, it is divided into two halves, into a cardiac and a pyloric portion. The *intestine* is short in flesh-eating animals and long in herbivora. The stomach of ruminants is **compound,** and consists of four cavities. The first and largest is the **paunch** or rumen, then the **reticulum.** In these two cavities, especially the former, the ingesta are softened and undergo fermentation. They are then returned to the mouth by the action of the voluntary muscular fibres, which reach to the stomach. This is the process of **rumination.** The ingesta are chewed again in the mouth, and are again

swallowed, but this time they enter the third cavity or **psalterium**—(which is absent in the camel)—and thence into the fourth stomach or **abomasum**, in which the fermentative digestion takes place. The cæcum is a very large and important digestive organ in herbivora and in most rodents; it is small in man, and absent in carnivora. The œsophagus in grain-eating **birds** not unfrequently has a blind diverticulum or *crop* for softening the food. In the crop of pigeons during the breeding season, there is formed a peculiar secretion—"pigeon's milk," which is used to feed the young (*J. Hunter*). The stomach consists of a glandular *proventriculus* and a strong *muscular stomach* which is covered with horny epithelium and triturates the food. There are usually two fluid diverticula on the small intestine near where it joins the large gut. In **fishes** the intestinal canal is generally simple; the stomach is merely a dilatation of the tube; and at the pylorus there may be one, but usually many, blind glandular appendages (the appendices pyloricæ). They are generally longitudinal folds in the intestinal mucous membrane, but in some fishes *e. g.*, the shark, there is a *spiral valve*. [The inversive (cane sugar) ferment is wanting in the herbivora, as the cow, horse, and sheep, but is present in the dog and cat. It is also met with in birds and reptiles, and in many of the invertebrates, as the ordinary earth-worm (*M. Hay*).]

In **amphibia** and **reptiles** the stomach is a simple dilatation; the gut is larger in vegetable feeders than in flesh feeders. The **liver** is never absent in vertebrates, although the gall bladder frequently is. The **pancreas** is absent in some fishes.

Digestion in Plants.—The observations on the albumin digesting power of some plants are extremely interesting (*Canby*, 1869; *Ch. Darwin*, 1875). The sundew or drosera has a series of tentacles on the surface of its leaves, and the tentacles are provided with glands. When an insect alights upon a leaf, it is suddenly seized by the tentacles; the glands pour out an acid juice over the prey, which is gradually digested, all except the chitinous structures. The secretion, as well as the subsequent absorption of the products of digestion, are accomplished by the activity of the protoplasm of the cells of the leaves The digestive juice contains a pepsin-like ferment and formic acid. Similar phenomena are manifested by the Venus flytrap (Dionæa), by pinguicula, as well as by the cavity of the altered leaves of nepenthes. About fifteen species of these "insectivorous" or carnivorous plants are known. [Papain, and other ferments analogous in their action to trypsin, are referred to in § 170.]

188. HISTORICAL.—Digestion in the Mouth.—The older observers regarded the *saliva* as a solvent, and in addition, many bad qualities, especially in starving animals, were ascribed to it. This arose from the knowledge of the saliva of mad animals, and the parotid saliva of poisonous snakes. The salivary glands have been known for a long time. Galen (131–203 A. D.) was acquainted with Wharton's duct, and Aëtius (270 A. D.) with the sub-maxillary and sub-lingual glands. Hapel de la Chenaye (1780) obtained large quantities of saliva from a horse, in which he was the first to make a salivary fistula. Spallanzani (1786) asserted that food mixed with saliva was more easily digested than food moistened with water. Hamberger and Siebold investigated the reaction, consistence, and specific gravity of saliva, and found in it mucus, albumin, common salt, calcium and sodium phosphates. Berzelius gave the name *ptyalin* to the characteristic organic constituent of saliva, but Leuchs (1831) was the first to detect its diastatic action.

Gastric Digestion.—Digestion was formerly compared to "coction," whereby solution was effected. According to Galen, only substances that have been dissolved passed through the pylorus into the intestine. He described the movements of the stomach and the peristalsis of the intestines. Aelian gave names to the four stomachs of the ruminants. Vidius († 1567) noticed the numerous small apertures of the gastric glands. Van Helmont († 1644) expressly notices the *acidity* of the stomach. Reaumur (1752) knew that a juice was secreted by the stomach, which effected solution, and with which he and Spallanzani performed experiments on digestion outside the body. Carminati (1785) found that the stomachs of carnivora during digestion secreted a very acid juice. Prout (1824) discovered the hydrochloric acid of the gastric juice, Sprott and Boyd (1836) the glands of the gastric mucous membrane, while Wasmann and Bischoff noted the two kinds of gastric glands. After Beaumont (1834) had made his observations upon Alexis St. Martin, who had a gastric fistula caused by a gunshot wound, Bassow (1842) and Blondlot (1843) made the first artificial gastric fistulæ upon animals. Eberle (1834) prepared artificial gastric juice. Mialhe called albumin, when altered by gastric digestion, albuminose; Lehmann, who investigated this substance more carefully, gave it the name *peptone*. Schwann isolated *pepsin* (1836), and established the fact of its activity in the presence of hydrochloric acid.

Pancreas, Bile, Intestinal Digestion.—The pancreas was known to the Hippocratic School; Maur. Hoffmann (1642) demonstrated its duct (fowl), and Wirsung described it in man. Regner de Graaf (1664) collected the pancreatic juice from a fistula, and Tiedemann and Gmelin found it to be alkaline, while Lauret and Lassaigne found that it resembled saliva. Valentin discovered its diastatic action, Eberle its emulsionizing power, and Cl. Bernard (1846) its tryptic and fat-splitting properties. The last mentioned function was referred to by Purkinje and Pappenheim (1836). Aristotle characterized the **bile** as a useless secretion; according to Erasistratus (304 B. C.), fine invisible channels conduct the bile from the liver into the gall bladder. Arëtaeus ascribed icterus to obstruction of the bile duct. Benedetti (1493) described gall stones. According to Jasolinus (1573), the

gall bladder is emptied by its own contractions. Sylvius noticed the lymphatics of the liver (1640); Walaeus, the connective tissue of the so called capsule of Glisson (1641). Haller indicated the uses of bile in the digestion of fats. The liver cells were described by Henle, Purkinje, and Dutrochet (1838). Heynsius discovered the urea and Cl. Bernard (1853) the sugar in the liver, and he and Hensen (1857) found glycogen in the liver. Kiernan gave a more exact description of the hepatic blood vessels (1834). Beale injected the lymphatics, and Gerlach the finest bile ducts. Schwann (1844) made the first biliary fistula; Demarcay particularly referred to the combination of the bile acids with soda (1838); Strecker discovered the soda compounds of both acids, and isolated them. Celsus mentions nutrient enemata (3–5 A.D.). Fallopius (1561) described the valvulæ conniventes and villi of the intestinal mucous membrane, and the nervous plexus of the mesentery. The agminated glands or patches of Peyer were known to Severinus (1645).

PHYSIOLOGY OF ABSORPTION.

189. THE ORGANS OF ABSORPTION.—[As most substances in the state in which they are used for food are either insoluble, or diffuse but imperfectly through membranes, the whole drift of the complicated digestive processes is to render these substances **soluble** and **diffusible**, and thus fit them for absorption; while most of the fats are emulsionized.]

The **mucous membrane** of the whole intestinal tract, as far as it is covered by a single layer of columnar epithelium, *i. e.*, from the cardiac orifice of the stomach to the anus—is adapted for absorption. The mouth and œsophagus, lined as they are by stratified squamous epithelium, are much less adapted for this purpose. Still, poisoning is caused by placing potassium cyanide in the mouth. The channels of absorption in the intestinal tract are (Fig. 206)—(1) the **capillaries** [*direct*], and (2) the **lacteals** [*indirect*] of the mucous membrane. Almost the whole of the substances absorbed by the former pass into the rootlets of the portal vein, *and traverse the liver*, while those that enter the lacteals really pass into lymphatics, so that the chyle passes through the thoracic duct and is poured by it into the blood, where the thoracic duct joins the subclavian vein.

FIG. 206.



Scheme of Intestinal Absorption. LAC., lacteals; T. D., thoracic duct; P.V. and H.V., portal and hepatic veins; INT., intestine.

Watery solutions of salts, grape sugar, peptone, poisons, and in a still higher degree alcoholic solutions of poisons, are absorbed **in the stomach.** The empty stomach absorbs more rapidly than one filled with food; gastric catarrh delays absorption. After a copious diet of milk, fatty granules have been found in the protoplasm of the goblet cells; so that according to this view, the goblet cells have a double function, to secrete mucus and to absorb nutriments.

The greatest area of absorption is undoubtedly the **small intestine**, especially its *upper* half, owing to the presence of the **valvulæ conniventes** and the **villi.**

190. STRUCTURE OF THE SMALL AND LARGE INTESTINES.—[The wall of the **small intestine** consists of **four coats**; which, from without inward, are named serous, muscular, sub-mucous, and mucous (Fig. 207).]

(1) The **serous coat** has the same structure as the peritoneum, *i. e.*, a thin basis of fibrous tissue covered on its outer surface by endothelium.

(2) The **muscular coat** consists of a thin **outer longitudinal** and an **inner** thicker **circular** layer of non-striped muscular fibres (Fig. 207).

(3) The **sub-mucous coat** consists of loose connective tissue containing large blood vessels and nerves, and it connects the muscular with the mucous coat.

(4) The **mucous coat** is the most internal coat, and its absorbing surface is largely increased by the presence of the valvulæ conniventes and villi. [The **valvulæ conniventes** are peramnent folds of the mucous membrane of the small intestine, arranged across the long axis of the gut. They pass round a half or more of the inner surface of the gut. They begin a little below the commence-

ment of the duodenum, and are large and well marked in the duodenum, and remain so as far as the upper half of the jejunum, where they begin to become smaller, and finally disappear about the lower part of the ileum.] The **villi** are characteristic of the small intestine, and are confined to it; they occur everywhere as closely-set projections over and between the valvulæ conniventes (Fig. 207). When the inner surface of the mucous membrane is examined in water, it has a velvety appearance owing to their presence. [They vary in length from $\frac{1}{50}$ to $\frac{1}{30}$ of an inch, are largest and most numerous in the upper part of the intestine, duodenum, and jejunum, where absorption is most active, but they are less abundant in the ileum. Their total number has been calculated at four millions by Krause.] Each villus is a projection of the entire mucous membrane, so that it contains within itself representatives of all the tissue elements of the mucosa. The orifices of the glands of Lieberkühn open between the bases of villi (Fig. 207).

FIG. 207.



Longitudinal section of the small intestine of a dog through a Peyer's patch.

Each **villus**, be it cylindrical or conical in shape, is covered by a single layer of **columnar epithelium**, whose protoplasm is reticulated, and contains a well-defined nucleus with an intranuclear plexus of fibrils. The ends of the epithelial cells directed toward the gut are polygonal, and present the appearance of a mosaic (Fig. 208, D). When looked at from the side, their free surface is seen to be covered with a clear, highly refractive **disk** or "**cuticula**," which is marked with vertical striæ. These striæ were supposed by Kölliker to represent pores for the absorption of fatty particles, but this has not been confirmed, while Brettauer and Steinach regarded them as produced by prisms placed side by side.

According to v. Thanhoffer, however, this clear disk is comparable to the thickened flange around the bottom of a vessel, such as is used for collecting gases. On this supposition, the upper end of each cell is open, and from it there project pseudopodia-like bundles of protoplasmic processes (Fig. 208, B). These processes are supposed to be extended beyond the margin of the cell, and again rapidly retracted, and in so acting they are said to carry the fatty particles into the interior of the cells, much as the pseudopodia of an amœba entangle its food. [This view has not been confirmed by a sufficient number of observers.] Between the epithelial cells are the so-called **goblet cells** (Fig. 208, C). [Each goblet cell is more or less like a chalice, narrower above and below, and broad in the middle, with a tapering fixed extremity. The outer part of these cells is filled with a clear substance or **mucigen**, which, on the addition of water, yields mucus. The mucigen lies in the intervals of a fine network of fibrils, which pervades the cell protoplasm, while the protoplasm, containing a globular or triangular nucleus, is pushed into the lower part of the cell. Those goblet cells are simply altered columnar epithelial cells, which secrete mucus in their interior. They are more numerous under certain conditions. Not unfrequently in a section of the mucous membrane of the gut, after it is stained with logwood, we may see a deep blue plug of mucus partly exuded from these cells. When looked at from above they give the appearance seen in Fig. 208, D.] The epithelial cells are shed in enormous numbers in cholera, and in poisoning with arsenic and muscarin (*Böhm*).

[The epithelial cells covering the villus are placed upon a layer of squamous epithelium (**basement membrane**)—the sub-epithelial membrane of Dêbove. This basement membrane is said to be connected by processes with the so-called branched cells of the adenoid tissue of the villus, while it also sends up processes between the epithelial covering.]

The villus itself consists of a basis of **adenoid tissue**, containing in its centre one or more lacteals, closely invested with bundles of longitudinal smooth muscular fibres, derived from the muscularis mucosæ, and a plexus of blood vessels. The adenoid tissue of the villus consists of a reticulum of fibrils with endothelial plates at its nodes. The spaces of the adenoid tissue form a spongy network

FIG. 208.



A scheme of a transverse section of part of a villus; *a*, columnar epithelium with, *b*, clear disk; *c*, goblet cell; *i*, *i*, adenoid reticulum; *d*, *d*, spaces containing leucocytes, *e*, *e*; *f*, section of the central lacteal. B, scheme of a cell with processes projected from its interior. C, columnar epithelium after the absorption of fatty granules. D, columnar epithelium of a villus seen from above with a goblet cell in the centre.

FIG. 209.



Injected blood vessels of a villus.

of inter-communicating channels containing stroma cells or leucocytes (Fig. 208, A, *e*, *e*). These leucocytes or lymph corpuscles have been seen to contain fatty granules, and they are perhaps concerned in the absorption of fatty particles.

The lymphatic or **lacteal** lies in the axis of the villus (Fig. 210, *d'*). Some regard the lacteal merely as a space in the centre of the villus, but more probably it has a distinct wall composed of endothelial cells, with apertures or stomata here and there between the cell plates. These stomata place the interior of the lacteal in direct communication with the spaces of the adenoid tissue. Perhaps, white blood corpuscles wander out of the blood vessels of the villi into the spaces of the adenoid tissue where they become loaded with fatty granules, and pass into the central lacteal. Zuwarykin and Wiedersheim suppose that the leucocytes pass from the parenchyma of the villus toward the epithelial layer, and even between the epithelial cells, from which they return toward the axis of the villus, laden with substances which they have taken into their interior (§ 192, II).

A small **artery** placed eccentrically passes into each villus (Fig. 209). In man it begins to divide about the middle of the villus, but in animals it usually runs to the apex before it divides. The capillaries resulting from the division of the artery form a fine dense network placed *superficially*, immediately under the epithelium of the surface. The blood is carried out of a villus by one or two veins (Figs. 207, 209).

Non-striped muscular fibres are present in villi. They are arranged longitudinally in several bundles from base to apex, immediately outside the central lacteal. When they contract they tend to empty the lacteal. A few muscular fibres are placed more superficially, and run in a more transverse direction. [The longitudinal bundles of non-striped muscle in the villi are connected together by oblique strands; while the longitudinal bundles shorten the villus, the oblique fibres keep the lacteal open; thus the parenchyma of the villus is also compressed transversely, whereby the products of absorption are forced into the lacteal. The muscles are fixed by cement to the sub-epithelial basal membrane. The muscular fibres of the villi are direct prolongations of the muscularis mucosæ.]

Nerves pass into the villi from Meissner's plexus lying in the sub-mucous coat. The nerves to the villi are said to have small granular ganglionic cells in their course, and they terminate partly in the muscular fibres and partly in the arteries of the villi.

[On making a vertical section of the **mucous membrane** of the small intestine, it is seen to consist of a network of adenoid tissue loaded with leucocytes. This tissue forms its basis, and in it are placed vertically, side by side, like test-tubes in a stand, immense numbers of simple tubular glands—the **crypts of Lieberkühn** (Fig. 207).] [Kultschitzki finds that the connective-tissue framework of the mucous membrane of the small intestine is not true adenoid tissue, but a transition form between the latter and loose fibrous tissue.] Lieberkühn's glands open above at the bases of the villi, while their closed lower extremity reaches almost to the muscularis mucosæ. Each tube consists of a basement membrane lined by a single layer of columnar epithelium, leaving a wide lumen, the cells lining them being continuous with those that cover the mucous membrane. Some goblet cells are often found between the columnar epithelium. Immediately below the bases of the follicles of Lieberkühn is the **muscularis mucosæ**, consisting of two or three narrow layers of non-striped muscular fibres arranged circularly and longitudinally. [It is continuous with the muscularis mucosæ of the stomach, and extends throughout the whole intestine, not as a continuous layer, but as a close network of bundles of smooth muscle. It sends fibres upward into the villi (Fig. 212, *e*).]

FIG. 210.



Mucous membrane of the small intestine of the dog; the lacteals are black, and the blood vessels lighter. *a*, artery; *b*, lymphatic; *c*, plexus of capillaries in the villi; *d*, lacteal; *e*, Lieberkühn's glands.

[**Brunner's Glands** are compound tubular glands lying in and confined to the submucous coat of the **duodenum** (Fig. 198). Their ducts perforate the muscularis mucosæ to open on the surface. They seem to be the homologues of the pyloric glands of the stomach.]

[**Solitary Follicles** are small round or oval white masses of adenoid tissue, with their deeper parts embedded in the submucosa, and their apices projecting into the mucosa of the intestine. They begin at the pyloric end of the stomach and are found throughout the whole intestine. They consist of small masses of adenoid tissue loaded with leucocytes (Fig. 214). They are well supplied with blood vessels (§ 197), although no lymphatic vessels enter them. They are surrounded by lymphatics, and, in fact, they may be said to hang into a lymph stream. The distribution of solitary follicles is fairly uniform in the small intestine; their number generally increases from the stomach to the large intestine; although there are considerable variations in different individuals, there seems to be the same number of solitary follicles and Peyer's patches in the infant as in the adult (*Passow*).]

[**Peyer's glands**, or agminated glands, consist of groups of lymph follicles like the foregoing (Figs. 207, 213). The masses are often more or less fused together, their bases lie in the sub-mucosa,

while their summits project into the mucosa, where they are covered merely by the columnar epit
of the intestine. The lymph corpuscles often pass between the epithelial cells. The patc
formed have their long axis in the axis of the intestine, and they are always placed opposite the

FIG. 211.

Villi with blood vessels injected. Solitary follicle.



Transverse section of duodenum of a rabbit injected, × 50.

FIG. 212.

Section of a solitary follicle of the small intestine (human). *a*, lymph follicle covered with epithelium (*b*) wh
fallen from the villi, *c*; *d*, Lieberkühn's follicle; *e*, muscularis mucosæ; *f*, sub-mucous tissue.

ment of the mesentery. Like the solitary glands, they are well supplied with blood vessels
around them is a dense plexus of lymphatics or lacteals. They are most abundant in the low
of the ileum. These glands are specially affected in typhoid fever.]

Nerves of the Intestine.—Throughout the whole intestinal tract there exists the **plexus of Auerbach,** lying between the longitudinal and circular muscular coats (Figs. 174, 175). This

FIG. 213.



Diagram of a vertical section of the mucous membrane of the small intestine of a dog, showing the closed follicles, *aa*; *b*, muscularis mucosæ.

FIG. 214.



Longitudinal section of the large intestine.

plexus consists of non-medullated nerves with groups of ganglionic cells at the nodes. Fibres are given off by it to the muscular coats. Connected by branches with the foregoing, and lying in the sub-

mucosa, is the **plexus of Meissner,** which is much finer, the meshes being wider, the nodes smaller, but also provided with ganglionic cells. It supplies the muscular fibres and arteries of the mucosa, including those of the villi. It also sends branches to Lieberkühn's glands (Fig. 176).

[**Structure of the Large Intestine.**—It has **four coats,** like those of the small intestine. The **serous** coat has the same structure as that of the small intestine. The **muscular** coat has external *longitudinal* fibres occurring all round the gut, but they form three flat, ribbon-like longitudinal bands in the cæcum and colon (Fig. 214). Inside this coat are the *circular* fibres. The **sub-mucosa** is practically the same as that of the small intestine. The **mucosa** is distinguished by negative characters. It has no villi and no Peyer's patches, but otherwise it resembles structurally the small intestine, consisting of a basis of adenoid tissue with the simple tubular **glands of Lieberkühn** (Fig. 199). These glands are very numerous and somewhat longer than those of the small intestine, and they always contain far more goblet cells—about ten times as many. The cells lining them are devoid of a clear disk. **Solitary glands** occur throughout the entire length of the large intestine. At the basis of Lieberkühn's glands is the **muscularis mucosæ.** The blood vessels and nerves have a similar arrangement to those in the stomach.]

[**Blood Vessels.**—On looking down on an opaque injection of the mucous membrane of the stomach, one sees a dense meshwork of polygonal areas of unequal size, with depressions here and there. The orifices are the orifices of the gastric glands, each surrounded by a capillary. A somewhat similar appearance is seen in an opaque injection of the mucous membrane of the large intestine, but in the latter the meshwork is *uniform*, all the orifices (of Lieberkühn's glands) being of the same size.]

191. ABSORPTION OF THE DIGESTED FOOD.—The physical forces concerned are endosmosis, diffusion, and filtration.

All the constituents of the food, with the exception of the fats, which in part are changed into a fine emulsion, are brought into a state of **solution** by the digestive processes. These substances pass through the walls of the intestinal tract, either into the blood vessels of the mucous membrane or into the beginning of the lymphatics. In this passage of the fluids two physical processes come into play —*endosmosis* and *diffusion*, as well as *filtration*.

I. Endosmosis and **diffusion** occur between two fluids which are capable of forming an intimate mixture with each other, *e. g.*, hydrochloric acid and water, but never between two fluids which do not form a perfect mixture, such as oil and water. If two fluids capable of mixing with each other, but of different compositions, be separated from each other by means of a septum with physical pores (which occur even in a homogeneous membrane), an exchange of the constituents in the fluids occurs until both fluids have the same composition. This exchange of fluids is termed *endosmosis* or *diosmosis*.

FIG. 215.



Endosmometer.

Diffusion.—If the two mixable fluids are placed in a vessel, the one fluid over the other, but without being separated by a porous septum, an exchange of the particles of the fluids also occurs, until the whole mixture is of uniform composition. This process is called *diffusion*.

Conditions Influencing Diffusion.—Graham's investigations showed that the rapidity of diffusion is influenced by (1) The nature of the fluids themselves; acids diffuse most rapidly; the alkaline salts more slowly; and most slowly, fluid albumin, gelatin, gum, dextrin. These last do not crystallize, and perhaps do not form true solutions. (2) The more concentrated the solutions, the greater the diffusion. (3) Heat accelerates, while cold retards, the process. (4) If a solution of a body which diffuses with difficulty be mixed with an easily diffusible one, the former diffuses with still greater difficulty. (5) Dilute solutions of several substances diffuse into each other without any difficulty, but if concentrated solutions are employed the process is retarded. (6) Double salts, one constituent of which diffuses more readily than the other, may be chemically separated by diffusion.

Endosmometer.—The exchange of the fluid particles takes place *independently of the hydrostatic pressure.* An endosmometer (Fig. 215) consists of a glass cylinder filled with distilled water, and into this is placed a flask, J, without a bottom, instead of which a membrane, *m*, is tied on. A glass tube, R, is fixed firmly, by means of a cork, into the neck of the flask. The flask is filled up to the lower end of the tube with a concentrated salt solution, and is then placed in the cylindrical vessel until both fluids are on the same level, *x*. The fluid in the tube, R, soon begins to rise, because water passes through the membrane into the concentrated solution in the flask, and this independently of the hydrostatic pressure. Particles of the concentrated salt solution pass into the cylinder and mix with the water, F. These outgoing and ingoing currents continue until the fluids without and within J are of uniform composition, whereby the fluid in R always stands higher (*e. g.*, at *y*), while it is lowered in the cylinder. The circumstance of the level

of the fluid within the tube being so high, and remaining so, is due to the fact that the pores in the membrane are too fine to allow the hydrostatic pressure to act through them.

Endosmotic Equivalent.—Experiment has shown that equal weights of different soluble substances attract different amounts of distilled water through the membrane *i. e.*, a known weight of a soluble substance (in the flask) can be exchanged by endosmosis for a definite weight of water. The term "endosmotic equivalent" indicates the weight of distilled water that passes into the flask of the endosmometer, in exchange for a known weight of the soluble substance (*Jolly*). For 1 grm. alcohol 4.2 grms. water were exchanged; while for 1 grm. NaCl, 4.3 grms. water passed into the endosmometer. The following numbers give the endosmotic equivalent of—

Acid potassium sulphate,	= 2.3	Magnesium sulphate,	= 11.7
Common salt,	= 4.3	Potassium sulphate,	= 12.0
Sugar,	= 7.1	Sulphuric acid,	= 0.39
Sodium sulphate,	=11.6	Potassium hydrate,	=215.0

The amount of the substance which passes through the membrane into the water of the cylinder is proportional to the concentration of the solution. If the water in the cylinder, therefore, be repeatedly renewed, the endosmosis takes place more rapidly, and the process of equilibration is accelerated. The larger the pores of the membrane, and the smaller the molecules of the substance in solution, the more rapid is the endosmosis. Hence, the rapidity of endosmosis of different substances varies, *e. g.*, the rapidity of sugar, sodium sulphate, common salt, and urea is in the ratio of 1 : 1.1 : 5 : 9.5.

The endosmotic equivalent is not constant for each substance. It is influenced by (1) The temperature, which, as it increases, generally increases the endosmotic equivalent. (2) It also varies with the degree of concentration of the osmotic solutions, being greater for dilute solutions of the substances.

If a substance other than water be placed in the cylinder, an endosmotic current occurs on both sides until complete equality is obtained. In this case, the currents in opposite directions disturb each other. If two substances be dissolved in the water in the flask at the same time, they diffuse into water without affecting each other. (3) It also varies with membranes of varying porosity. Common salt, which gives an endosmotic equivalent with a pig's bladder = 4.3, gives 6.4 when an ox bladder is used; 2.9 with a swimming bladder; and 20.2 with a collodion membrane.

Colloids.—There are many fluid substances which, on account of the great size of their molecules, do not pass, or pass only with difficulty, through the pores of a membrane impregnated with gelatinous bodies, which diffuse slowly. These substances are not actually in a true state of solution, but exist in a very dilute condition of imbibition. Such substances are the fluid proteids, starches, dextrin, gum, and gelatin. These diffuse when no septum is present, but diffuse with difficulty, or not at all, through a porous septum. Graham called these substances **colloids,** because, when concentrated, they present a glue-like or gelatinous appearance; further, they do not crystallize, while those substances which diffuse readily are crystalline, and are called **crystalloids.** Crystallizable substances may be separated from non-crystallizable by this process, which Graham called **dialysis.** Mineral salts favor the passage of colloids through membranes.

That **endosmosis** takes place in the intestinal tract, through the mucous membrane and the delicate membranes of the blood and lymph capillaries, cannot be denied. On the one side of the membrane, within the intestine, are relatively concentrated solutions of highly diffusible salts, peptones, sugar and soaps, and within the blood vessels are the colloids which are scarcely diffusible, *e.g.*, the proteids of blood and lymph.

II. Filtration is the passage of fluids through the **coarse** intermolecular pores of a membrane **owing to pressure.** The greater the pressure, and the larger and more numerous the pores, the more rapid does the fluid pass through the membrane; increase of temperature also accelerates it. Those substances which are imbibed by the membrane filter most rapidly, so that the same substance filters through different membranes with varying rapidity. The filtration is usually slower, the greater the concentration of the fluid. The filter has the property of retaining some of the substances from the solution passing through it, *e.g.*, colloid substances—or water (in dilute solutions of nitre). In the former case the filtrate is more dilute, in the latter more concentrated, than before filtration. Other substances filter without undergoing any change of concentration. Many membranes behave differently, according to which surface is placed next the fluid; thus the shell membrane of an egg permits filtration only from without inward; [and the same is true to a much less extent with filter paper; the smooth side of the filter paper ought always to be placed next the fluid to be filtered. The intact skin of the grape prevents the entrance of fungi into the fruit]. There is a similar difference with the gastric and intestinal mucous membrane.

[By using numerous layers of filter paper, many colloids and crystalloids are retained in the filter, *e.g.*, hæmoglobin, albumin, and many coloring matters, especially aniline colors, the last being arrested by glass wool (*Krysinski*).]

[**Filtration of Albumin.**—Runeberg finds that the amount of albumin in pathological transudations varies with (1) the *capillary area*, being least in œdema of the subcutaneous tissue. (2) The

presence or absence of *inflammatory processes* in the vascular wall, non-inflammatory pleuritic effusion containing 2 per cent., and inflammatory 6 per cent., of albumin. (3) The condition and amount of *albumin in the blood.* The amount of albumin in the transudate never reaches, although it sometimes approaches, that in blood. In ascites in general dropsy the amount is .03 to .04 per cent. (4) The *duration* of the transudation. (5) Perhaps the blood pressure and the condition of the circulation.]

Filtration of the soluble substance may take place from the canal of the digestive tract when: (1) The *intestine contracts* and thus exerts pressure upon its contents. This is possible when the tube is narrowed at two points, and the musculature between these two points contracts upon the fluid contents. (2) Filtration, under **negative pressure**, may be caused by the **villi** (*Brücke*). When the villi contract energetically, they empty their contents toward the blood and lymph vessels. The lacteal remains empty, as the chyle is prevented from passing backward into the origin of the lacteal within the villi, owing to the presence of numerous valves in the lymphatics. When the villi relax, they are refilled with fluids from the intestine.

192. **ABSORPTION BY THE INTESTINAL WALL.—I. True solutions** undoubtedly pass by endosmosis into the blood vessels and lymphatics of the intestinal walls, but numerous facts indicate that the protoplasm of the cells takes an active part in the process of absorption. The forces concerned have not as yet been proved to be purely physical and chemical in their nature.

(1) **Inorganic Substances.—Water** and the **soluble salts** necessary for nutrition are easily absorbed, the latter especially by the **blood** and **lymph vessels.** When saline solutions pass by endosmosis into the vessels, water must pass from the intestinal vessels into the intestine. The amount of water, however, is small, owing to the small endosmotic equivalent of the salts to be absorbed. More salts are absorbed from concentrated than from dilute solutions. If large quantities of salt, with a high endosmotic equivalent, *e. g.*, magnesiun or sodium sulphate, are introduced into the intestine, these salts retain the water necessary for their solution, and may thus cause diarrhœa. Conversely, when these substances are injected into the blood, a large quantity of water passes from the intestine into the blood, so that constipation occurs, owing to the dryness of the intestinal contents (*Aubert*).

[M. Hay concludes from his experiments (§ 161), that salts, when placed in the intestines, do not abstract water from the blood, or are themselves absorbed, in virtue of an endosmotic relation being established between the blood and the saline solution in the intestines. Absorption is probably due to the filtration and diffusion, or processes of inhibition other than endosmosis, as yet little understood. The result obtained by Aubert, which is not constant, is mostly caused by the great diuresis which the injected salt excites.] The absorption of fluids takes place best at a medium pressure of 80 to 140 c. cm. of water within the intestine; higher pressure compresses the blood vessels and diminishes the absorption. During digestion, owing to the dilatation of the vessels, absorption is more rapid. The fact that 0.5 per cent. solution of NaCl is absorbed better than water, and soda solution than potash solution, seems to show that physical forces are not the only factors concerned.

Numerous inorganic substances, which do not occur in the body, are absorbed by endosmosis from the intestine, *e.g.*, dilute sulphuric acid, potassium iodide, chlorate and bromide, and many other salts.

(2) The **soluble carbohydrates**, such as the **sugars**, of which the chief representatives are **dextrose** and **maltose**, with a relatively high endosmotic equivalent. Cane sugar is changed by a special ferment into invert-sugar (§ 183, 5). Absorption appears to take place somewhat slowly, as only very small quantities of grape sugar are found in the chyle vessels, or the portal vein, at any time. According to v. Mering, the *sugar passes from the intestine into the rootlets of the portal vein*; dextrin also occurs in the portal vein. When the blood of the portal vein is boiled with dilute sulphuric acid, the amount of sugar is increased. The amount of sugar absorbed depends upon the concentration of its solution in the intestine; hence the amount of sugar in the blood is increased after a diet containing much of this substance, so that it may appear in the urine; in which case

the blood must contain at least 0.6 per cent. of sugar. A small amount of **cane sugar** has also been found in the blood (*Cl. Bernard*). The sugar is used up in the bodily metabolism; some of it is perhaps oxidized in the muscles (§ 176).

(3) The **peptones** have a small endosmotic equivalent, a 2 to 9 per cent. solution = 7 to 10. Owing to their great diffusibility they are readily absorbed, and they are the chief representatives of the proteids which are absorbed. The amount absorbed depends upon the concentration of their solution in the intestine. When animals are fed on peptones (with the necessary fat or sugar), they serve to maintain the body weight. [According to Plósz and Györgyai, Drosdorff and Schmidt-Mulheim, peptones occur only in traces in the blood of the portal vein. Neumeister, however, using the best methods, finds that although peptones are abundant in the intestine, not a trace of peptone or of the albumoses is found either in the blood or lymph. This coincides with Hofmeister's researches, and is, of course, opposed to the results of the above-named observers. As no peptones or albumoses have been found in the blood, and as they can compensate for the total metabolism of the proteids within the body, we must assume that they are rapidly converted into albuminous bodies.] Hofmeister supposes that the leucocytes absorb the peptones and act as their carriers, much as the red corpuscles are oxygen carriers. They carry the peptones into the mucous membrane of the stomach and small intestine, which are very rich in peptone at the fourth hour of digestion. [The number of leucocytes is greatly increased in the mucous membrane, especially in the stomach and upper part of the duodenum, during digestion, and diminished during fasting in dogs and cats. The same is the case with the lymph follicles, the cells of which are formed by the division of the pre-existing cells.] It is asserted by Salvioli that the mucous membrane possesses the property of changing peptone into albumin.

[**Injection of Peptone into Blood.**—When peptone is injected into the blood of an animal, within twenty minutes thereafter no trace of the peptone is to be found in the blood, although it has not been excreted by any of the organs. Peptones so injected prevent the blood of the dog (not of the rabbit or pig) from coagulating. In large quantity they are fatal. Fano asserts that the peptone is taken up by the red blood corpuscles, which thus become of greater specific gravity, and change it into globulin. After three or more hours the corpuscles return the globulin to the blood, so that the corpuscles represent a reserve store of proteid. The peptones used in these experiments were really a mixture of peptones and albumoses. Neumeister finds that in the dog, when **albumoses** are injected into the blood they reappear in the urine, but somewhere in the body they undergo hydration in the sense in which peptic digestion causes hydration. The two primary albumoses reappear almost completely as deutero-albumose, and deutero-albumose, when introduced, reappears as peptone. Peptone, however, reappears unchanged. In rabbits, albumose reappears unchanged in the urine.]

(4) **Unchanged true proteids** filter with great difficulty, and much albumin remains upon the filter. On account of their high endosmotic equivalent they pass with extreme slowness, and only in traces, through membranes. Nevertheless, it has been conclusively proved that unchanged proteids can be absorbed (*Brücke*), *e. g.*, casein, soluble myosin, alkali-albuminate, albumin mixed with common salt, gelatin (*Voit, Bauer, Eichhorst*). They are absorbed even from the large intestine (*Czerny and Latschenberger*), although the human large intestine cannot absorb more than 6 grms. daily. But the amount of unchanged proteids absorbed is always very much less than the amount of peptone.

Egg albumin without common salt, syntonin, serum albumin, and fibrin are not absorbed (*Eichhorst*). Landois observed in the case of a young man who took the whites of 14 to 20 eggs along with NaCl, that albumin was given off by the urine for 4 to 10 hours thereafter. The amount of albumin given off rose until the third day, and ceased on the fifth day. The more albumin taken, the sooner the albuminuria appeared, and the longer it lasted. The unchanged egg albumin reappeared in the urine. If egg albumin be injected into the blood, part of it reappears in the urine (§ 41, 2) (*Stokvis, Lehmann*).

(5) The soluble **fat soaps** represent only a fraction of the fats of the food which are absorbed; the greater part of the neutral fats being absorbed in the

form of very fine particles—as an emulsion (§ 192, II). The *absorbed soaps have been found in the chyle*, and as the blood of the portal vein contains more soaps during digestion than during hunger, it has been assumed that the soaps pass into the intestinal blood capillaries. The investigations of Lenz, Bidder, and Schmidt, render it probable that the organism can absorb only a limited amount of fat within a given period; the amount perhaps bears a relation to the amount of bile and pancreatic juice. The maximum per kilo. (cat) was 0.6 grm. of fat per hour.

Perhaps the soaps reunite with glycerine in the parenchyma of the villi, to form neutral fats, as Perewoznikoff and Will found neutral fats, after injecting these two ingredients into the intestinal canal, while Ewald found that fat was formed when soaps and glycerine were brought into contact with the fresh intestinal mucous membrane. Perhaps this is the explanation of the observation of Bruch, who found fatty particles within the blood vessels of the villi. No **fatty acids** are found in blood, or chyle.

Absorption of other Substances.—Of soluble substances which are introduced into the intestinal canal, some are absorbed and others are not. The following are absorbed: alcohol, part of which appears in the urine (not in the expired air), viz., that part which is not changed into CO_2 and H_2O, within the body; tartaric, citric, malic, and lactic acids; glycerine, inulin; gum and vegetable mucin, which give rise to the formation of glycogen in the liver.

Among **coloring matters**, alizarin (from madder), alkannet, indigo-sulphuric acid, and its soda salt are absorbed; hæmatin is partly absorbed, while chlorophyll is not. **Metallic salts** seem to be kept in solution by proteids, are perhaps absorbed along with them, and are partly carried by the blood of the portal vein to the liver (ferric sulphate has been found in chyle). Numerous **poisons** are very rapidly absorbed, *e. g.*, hydrocyanic acid after a few seconds; potassium cyanide has been found in the chyle. [If salts (KI, sulphocyanide of ammonium) be injected into a ligatured loop of intestine (dog, cat, rabbit), these substances are absorbed both by the blood and lymph vessels, and in both nearly simultaneously.] Even for the absorption of completety fluid substances, endosmosis and filtration seem to be scarcely sufficient. An active participation of the protoplasm of the cells seems here also—in part at least—to be necessary, else it is diffiult to explain how very slight disturbances in the activity of these cells, *e. g.*, from intestinal catarrh, cause sudden variations of absorption, and even the passage of fluids into the intestine.

If absorption were due to diffusion alone, when alcohol is injected into the intestine, water ought to pass into the intestine, but this does not occur. Brieger found that the injection of a 0.5 to 1 per cent. solution of salts into a ligatured loop of intestine did not cause water to pass into the intestine; but it appeared when a 20 per cent. solution was injected.

II. Absorption of the Smallest Particles.—The largest amount of the fats is absorbed in the form of a milk-like **emulsion**, formed by the action of the bile and the pancreatic juice, and consisting of excessively small granules of uniform size (§ 170, III; § 181). The fats themselves are not chemically changed, but remain as undecomposed neutral fats. The particles seem to be surrounded by a delicate albuminous envelope, or haptogen membrane, partly derived from the pancreatic juice [probably from its alkali-albuminate]. The **villi** of the small intestine are the chief organs concerned in the absorption of the fatty emulsion, but the epithelium of the stomach and that of the large intestine also take a part. The fatty granules are recognized in the villi (1) Within the delicate canals? (§ 190) in the clear band of the epithelium (*Kölliker*). [It is highly doubtful if the vertical lines seen in the clear disk of the epithelium of the intestine are due to pores.] (2) The protoplasm of the epithelial cells is loaded with fatty granules of various sizes during the time of absorption, while the nuclei of the cells remain free, although, from the amount of fat within the cells, it is often difficult to distinguish them. (3) The granules pass into the spaces of the parenchyma of the villi; these spaces communicate freely with each other. (4) The origin of the **lacteal** in the axis of the villus is found to be filled with fatty granules. The amount of fat in the chyle of a dog, after a fatty meal, is 8 to 10 per cent., while the fat disappears from the blood within thirty hours.

With regard to the **forces concerned in the absorption of fats**, v. Wistinghausen proved, that when a porous membrane is moistened with bile, the

passage of fatty particles through it is thereby facilitated, but this fact alone does not explain the copious and rapid absorption of fats. It is possible that the protoplasm of the epithelial cells is actively concerned in the process, and that it takes the particles into its interior. Perhaps a fine protoplasmic process is thrown out by these cells, just as pseudopodia are thrown out and retracted by lower organisms. It is possible that absorption may take place through the open mouths of the goblet cells. The protoplasm of the epithelial cells is in direct communication with the numerous protoplasmic lymph cells within the reticulum of the villi, so that the particles may pass into these, and from them through the stomata (?) between the endothelial cells into the central lacteal of the villus. According to this view, the absorption of fatty particles, and perhaps also the absorption of true proteids, is due to an active vital process, as indicated by the observations of Brücke and v. Thanhoffer. This view is supported by the observation of Grünhagen, that the absorption of fatty particles in the frog is most active at the temperature at which the motor phenomena of protoplasm are most lively. That it is due to simple filtration alone is not a satisfactory explanation, for the amount of fatty particles in the chyle is independent of the amount of water in it. If absorption were chiefly due to filtration, we would expect that there would most probably be a direct relation between the amount of water and fat (*Ludwig and Zawilsky*). [The observations of Watney have led him to suppose that the fatty particles do not pass through the cell protoplasm to reach the lacteal, but that they pass through the *cement substance* between the epithelial cells covering a villus. If this view be correct, the absorbing surface is thereby greatly diminished. Zuwarykin and Schäfer suggest that the leucocytes, which have been observed between the columnar cells of the villi of the small intestine, are carriers of at least part of the fat from the lumen of the gut to the lacteal; they also, perhaps, alter it for further use in the economy. According to Zuwarykin, Peyer's patches in the rabbit seem to be especially active in the absorption of fat, so that he attaches great importance to the leucocytes of the adenoid tissue in the absorption of fat.]

[According to Grünhagen, there are several channels for the absorption of fats, but they are different in different animals. Some are absorbed by the columnar epithelium cells themselves, and some passes between them.]

The activity of the cells of the intestine with pseudopodial processes may be studied in the intestinal canal of Distomum hepaticum. Sommer has figured these pseudopodial processes actively engaged in the absorption of particles from the intestine.

193. **INFLUENCE OF THE NERVOUS SYSTEM.**—With regard to the influence of the nervous system upon intestinal absorption, we know very little. After extirpation of the semilunar ganglion, as well as after section of the mesenteric nerves (*Moreau*), the intestinal contents become more fluid, and are increased in amount (§ 183). This may be partly due to diminished absorption. V. Thanhoffer states that he observed the protrusion of threads from the epithelial cells of the small intestine only after the spinal cord, or the dorsal nerves, had been divided for some time.

194. **"NUTRIENT ENEMATA."**—In cases where food cannot be taken by the mouth, *e.g.*, in stricture of the œsophagus, continued vomiting, etc., food is given per rectum. As the digestive activity of the large intestine is very slight, fluid food ought to be given in a condition ready to be absorbed, and this is best done by introducing it into the rectum through a tube with a funnel attached, and allowing the food to pass in slowly by its own weight. The patient must endeavor to retain the enema as long as possible. When the fluid is slowly and gradually introduced, it may pass above the ileo-cæcal valve.

Solutions of grape sugar, and perhaps a small amount of soap solution, are useful; and among nitrogenous substances the commercial flesh-, bread-, or milk peptones of Sanders-Ezn, Adamkiewicz, in Germany, and Darby's fluid meat, and Carnrick's beef peptonoids in this country, are to be recommended. The amount of peptone required is 1.11 grm. per kilo. of body weight (*Catillon*); less useful are buttermilk, egg albumin with common salt. Leube uses a mixture of 150 grms. flesh with 50 grms. pancreas and 100 grms. water, which he slowly injects into the rectum, where the proteids

are peptonized and absorbed. [Peptonized food prepared after the method of Roberts is very useful (§ 172).] The method of nutrient enemata only permits imperfect nutrition, and at most only ¼ of the proteids necessary for maintaining the metabolism of the body is absorbed (*v. Voit, Bauer*).

195. **CHYLE VESSELS AND LYMPHATICS.—Lymphatics.**—Within the tissues of the body, and even in those tissues which do not contain blood vessels, *e. g.*, the cornea, or in those which contain few blood vessels, there exists a system of vessels or channels which contain the juices of the tissues, and within these vessels the fluid always moves in a centripetal direction. These canals arise within the tissues in a variety of ways, and unite in their course to form delicate and afterward thicker tubes, which ultimately terminate in two large trunks which open at the junction of the jugular and subclavian veins; that on the left side is the **thoracic duct,** and that on the right, **the right lymphatic trunk.**

With regard to the **lymph** and its movements in different organs, it is to be noticed that this occurs in different ways in different places. (1) In many tissues the lymphatics represent the **nutrient channels** by which the fluid that transudes through the neighboring vessels is distributed, as in the cornea and in many connective tissues. (2) In many tissues, as in glands, *e. g.*, the salivary glands and the testis, the lymph spaces are the chief **reservoirs for fluid,** from which the cells during the act of secretion derive the fluid necessary for that process. (3) The lymphatics have the general function of collecting the fluid which saturates the tissues, and carrying it back again to the blood. The capillary blood system may be regarded as an **irrigation system,** which supplies the tissues with nutrient fluids, while the lymphatic system may be regarded as a **drainage apparatus,** which conducts away the fluids that have transuded through the capillary walls. Some of the decomposition products of the tissues, proofs of their retrogressive metabolism, become mixed with the lymph stream, so that the lymphatics are at the same time **absorbing vessels.** Substances introduced into the parenchyma of the tissues in other ways, *e. g.*, by subcutaneous injection, are partly absorbed by the lymphatics. A study of these conditions shows that the lymphatic system represents an **appendix to the blood-vascular system,** and further that there can be no lymph system when the blood stream is completely arrested; it acts only as a part of the whole, and with the whole.

Lacteals.—When we speak of the lymphatics proper as against the *chyle vessels* or *lacteals*, we do so from anatomical reasons, because the important and considerable lymphatic channels coming from the whole of the intestinal tract are, in a certain sense, a fairly independent province of the lymphatic vascular area, and are endowed with a *high absorptive activity*, which, from ancient times, has attracted the notice of observers. The contents of the chyle vessels or lacteals are mixed with a large amount of fatty granules, giving the **chyle** a *white* color, which distinguishes them at once from the true lymphatics with their clear, watery contents. From a physiological point of view, however, the lacteals must be classified with the lymphatics, for, as regards their structure and function, they are true lymphatics, and their contents consist of true lymph mixed with a large amount of absorbed substances, chiefly fatty granules. [The contents of the lacteals are white only during digestion; at other times they are clear, like lymph.]

196. **ORIGIN OF THE LYMPHATICS.**—(1) **Origin in Spaces.**—Within the connective tissues (connective tissue proper, bone) are numerous stellate, irregular or branched spaces, which communicate with each other by numerous tubular processes (Fig. 216, 1); in these communicating spaces lie the cellular elements of these tissues. These spaces, however, are not completely filled by the cells, but an interval exists between the body of the cell and the wall of the space, which is greater or less according to the condition of movement of the protoplasmic cell. These spaces are the so-called "**juice canals**" or "**Saft-canälchen,**" and they represent the origin of the lymphatic vessels (*v. Recklinghausen*). As they communicate with neighboring spaces, the movement of the lymph is provided for. The cells which lie in the spaces exhibit amœboid movements. Some of these cells remain permanently, each in its own space, within which, however, it may change its form—these are the so-called "**fixed connective-tissue corpuscles,**" and bone corpuscles—while others merely wander or pass into these spaces, and are called "**wandering cells,**"

or "**leucocytes**;" but the latter are merely lymph corpuscles, or colorless blood corpuscles which have passed out of the blood vessels into the origin of the lymphatics. These cells exhibit amœboid movements. These spaces communicate with the small tubular lymphatics—the so-called *lymph capillaries* (L). The spaces lie close together where they pass into a lymph capillary (*a*). The lymph capillary, which is usually of greater diameter than the blood capillary, generally lies in the middle of the space within the capillary arch (B). The finest lymphatics are lined by a layer of delicate, nucleated, endothelial cells (*e*, *e*), with characteristic **sinous margins**, whose characters are easily revealed by the action of silver nitrate (Fig. 217, L). This substance blackens the cement substance which holds the endothelial cells together. Between the endothelial cells are small holes, or **stomata**, by means of which the lymph capillaries communicate (at *x*) with the juice canals.

It is assumed by Arnold that the blood vessels communicate with the juice canals, and that fluid passes out of the thin-walled capillaries through their stomata into these spaces (§ 65). This fluid nourishes the tissues, the tissues take up the substances appropriate to each, while the effete materials pass back into the spaces, and from these reach the lymphatics, which ultimately discharge them into the venous blood.

FIG. 216.

Origin of lymphatics from the central tendon of the diaphragm stained with nitrate of silver. *s*, the juice canals, communicating at *x* with the lymphatics; *a*, origin of the lymphatics by the confluence of several juice canals.

Whether the cells within these spaces are actively concerned in the pouring out of the blood plasma, or take part in its movement, is matter of conjecture. We can imagine that by contracting their body, after it has been impregnated with fluid, this fluid may be propelled from space to space toward the lymphatics. The leucocytes wander through these spaces until they pass into the lymphatics. Fine particles which are contained in these spaces—*e.g.*, after tattooing the skin, and even fatty particles after inunction—are absorbed by the leucocytes and carried by them to other parts of the body. [The pigment particles used to tattoo the finger are usually found within the first lymphatic gland at the elbow.]

The migration of cellular elements from the blood vessels into the origin of the lymphatics is to be considered as a normal process. *Granular coloring matter* passes from the blood into the protoplasmic body of the cells within the lymph spaces; and only when the granular pigment is in large amount, does it appear as a granular injection in the branches of the juice spaces.

FIG. 217.

Pleural surface of the central tendon of the diaphragm of the rabbit stained with silver nitrate. L, lymphatic with its sinuous endothelium; *c*, cells of the connective tissue brought into view by the silver nitrate.

(2) **Origin within villi**—*i. e.*, of the chyle vessel or **lacteal**—has been described (§ 190).

(3) **Origin in perivascular spaces** (Fig. 218).—The smallest blood vessels of bone, the central nervous system, retina and the liver, are completely surrounded by wide lymphatic tubes, so that the blood vessels are completely bathed by a lymph stream. In the brain these lymphatics are partly composed of delicate connective-tissue fibres, which traverse the lymph space and become attached to the wall of the included blood vessel. Fig. 218, B, represents a transverse section of a small blood vessel, B, from the brain; *p* is the divided perivascular space. This space is called the **perivascular space** of His, but in addition to it the blood vessels of the brain have a lymph space within the adventitia of the blood vessels (*Virchow-Robin's space*). It is partly lined by well-defined endothelium. Where the blood vessels begin to increase considerably in diameter, they pass through the wall of the lymphatics, and the two vessels afterward take separate courses. In all cases, where there is a perivascular space, the passage of lymph and blood corpuscles into the lymphatics is greatly facilitated. In the tortoise the large blood vessels are often surrounded with perivascular lymphatics. Fig. 218, A, gives a representation of the aorta surrounded by a perivascular space which is visible to the unaided eye. In mammals the perivascular spaces are microscopic.

(4) **Origin in the form of interstitial slits within organs.**—Within the testis the lymphatics begin simply in the form of numerous slits, which occur between the coils and twists of the seminal tubules. They take the form of elongated spaces bounded by the curved cylindrical surfaces of the tubules. The surfaces, however, are covered with endothelium. The lymphatics of the testis get independent walls after they leave the parenchyma of the organ. In many other glands the gland

FIG. 218.



Perivascular lymphatics. A, aorta of tortoise; B, artery from the brain.

FIG. 219.



Stomata in the great lymph sac (frog). *a*, open; *b*, half-closed; *c*, closed.

substance is similarly surrounded by a lymph space. The blood vessels pour the lymph into these spaces, and from them the secretiug cells obtain the materials necessary for the formation of their secretion.

(5) **Origin by means of free stomata** on the walls of the larger **serous cavities**, which (Fig. 219, *a*) communicate freely with the lymphatics. The investigation of the serous surfaces is most easily accomplished on the septum of the great abdominal lymph sac of the frog. Silver nitrate reveals the presence of relatively large free openings or **stomata** lying between the endothelium. Each stoma is bounded by several **germinating cells**, which have a granular appearance, and undergo a change of shape, so that the size of the stoma depends upon the degree of contraction of these cells; thus the stoma may be open (*a*), half-open (*b*), or completely closed (*c*). These stomata are the origin of the lymphatics. The serous cavities belong therefore to the lymphatic system, and fluids placed in the serous cavities readily pass into the lymphatics. The cavities of the peritoneum, pleura, pericardium, tunica vaginalis, testis, arachnoid space, aqueous chambers of the eye, and the labyrinth of the ear, are true lymph cavities, and the fluid they contain is to be regarded as lymph. [Hoffmann has found that a nerve fibre surrounds the stomata in the frog and sends branches between the germinal epithelium.]

(6) **Free open pores** have been observed on some *mucous membranes*, which are regarded as the origin of lymphatics, *e. g.*, in the bronchi, nasal mucous membrane, trachea and larynx.

Structure.—The larger lymphatics resemble in structure the veins of corresponding size. The valves are particularly numerous in the lymphatics, so that a distended lymphatic resembles a chain of pearls. [Lymphatics have dilations here and there in their course (Fig. 217).]

197. THE LYMPH GLANDS.—The **lymphatic glands** belong to the lymph apparatus. They are incorrectly termed glands, as they are merely much-branched lacunar labyrinthine spaces composed of adenoid tissue, and intercalated in the course of the lymphatic vessels. There are **simple** and **compound** lymph glands.

FIG. 220.



Two lymph follicles. A, a small follicle highly magnified, showing the adenoid reticulum; B, a follicle less highly magnified, showing injected blood vessels.

(1) The simple **lymph glands**, or, more correctly, **lymph follicles**, are small rounded bodies, about the size of a pin head. They consist of a mass of adenoid tissue (Fig. 220, A), *i. e.*, of a very delicate network of fine reticular fibres with nuclei at their points of intersection, and in the spaces of the meshwork lie the lymph and the lymph corpuscles. Near the surface, the tissue is somewhat denser, where it forms a capsule, which is not, however, a true capsule, as it is permeated with numerous small sponge-like spaces. Small lymphatics come directly into contact with these lymph follicles, and often cover their surface in the form of a close network. The surface of the lymph follicles is not unfrequently placed in the wall of a lymph vessel, so that it is directly bathed by the lymph stream. Although no direct canal-like opening leads from the follicle into the lymphatic stream in relation with it, a communication must exist, and this is obtained by the numerous spaces in the follicle itself, so that a lymph follicle is a true lymphatic apparatus whose juices and lymph corpuscles can pass into the nearest lymphatic. The follicles are surrounded by a network of blood vessels which sends loops of capillaries into their interior (Fig. 220, B). We may assume that lymph corpuscles pass from these capillaries into the follicle.

In connection with these follicles, including those of the back of the tongue, the solitary glands of the intestine and the adenoid tissue in the bronchial tract, the tonsils, and Peyer's patches, it is important to remember that enormous numbers of leucocytes pass out between the epithelial cells covering these follicles. The extruded leucocytes undergo disintegration subsequently.

FIG. 221.



Diagrammatic section of a lymphatic gland. *a. l.*, afferent, *e. l.*, efferent lymphatics; C, cortical substance: M, reticular cords of medulla; *l. s.*, lymph sinus; *c*, capsule, with trabeculæ, *tr.*

(2) The **compound lymph glands**—the **lymphatic glands**—represent a collection of lymph follicles, whose form is somewhat altered. Every lymph gland is covered externally with a connective-tissue **capsule** (Fig. 221, *c*), which contains numerous non-striped muscular fibres. From its inner surface, numerous **septa** and trabeculæ (*tr.*) pass into the interior, so that the gland substance is divided into a large number of **compartments**. These compartments in the *cortical* portion of the gland have a somewhat rounded form, and constitute the alveoli, while in the medullary portion they have a more elongated and irregular form. [On making a section of a lymph gland we can readily distinguish the **cortical** from the **medullary** portion of the gland,] All the compartments are of equal dignity, and they all communicate with each other by means of openings, so that the septa bound a rich network of spaces within the gland, which communicate on all sides with each other.

These spaces are traversed by the follicular threads (Fig. 222, *f, f*). These represent the con-

tents of the spaces, but are smaller than the spaces in which they lie, and do not come into contact anywhere with the walls of the spaces. If we imagine the spaces to be injected with a mass, which ultimately shrinks to one-half of its original volume, we obtain a conception of the relation of these follicular threads to the spaces of the gland. The **blood vessels** of the gland (*b*) lie within these follicular threads. They are surrounded by a tolerably thick crust of adenoid tissue, with very fine meshes (*x*, *x*) filled with lymph corpuscles, and with its surface (*o*, *o*) covered by the cells of the adenoid reticulum, in such a way as to leave free communications through the narrow meshes.

Between the surface of the follicular threads and the inner wall of all the spaces of the gland, lies the **lymph channel** or **lymph path** (B, B), which is traversed by a reticulum of adenoid tissue, containing relatively few lymph corpuscles. It is very probable that these lymph paths are lined by endothelium.

The **vasa afferentia** (Fig. 221, *a. l.*), of which there are usually several, expand upon the surface

FIG. 222.

Part of a lymphatic gland. A, vas afferens; B, B, lymph paths; *a*, *a*, trabeculæ seen on edge; *f*, *f*, follicular strand from the medulla; *x*, *x*, its adenoid reticulum; *b*, its blood vessels; *o*, *o*, narrow-meshed part limiting the follicular strands from the lymph path.

of the gland, perforate the outer capsule, and pour their contents into the lymph paths of the gland (C). The **vasa efferentia**, which are less numerous than the afferentia, and come out at the hilum, form large, wide, almost cavernous dilatations, and they anastomose near the gland (*e. l.*). Through them the lymph passes out at the opposite surface of the gland. The lymph percolates through the gland, and passes along the lymph paths, which represent a kind of rete mirabile interposed between the afferent and efferent lymph vessels.

During its passage through this complicated branched system of spaces, the movement of the lymph through the gland is retarded, and, owing to the numerous resistances which occur in its path, it has very little propulsive energy. The lymph corpuscles which lie in the meshes of the adenoid reticulum are washed out of the gland by the lymph stream. The lymph corpuscles lying within the follicular threads pass through the narrow meshes (*o*) into the lymph paths. The formation of lymph corpuscles either occurs locally, from division of the pre-existing cells, or new leuco-

tes wander out into the follicular threads. The movement of the lymph through the gland is ored by the muscular action of the capsule. When the capsule contracts energetically, it must mpress the gland like a sponge, and the direction in which the fluid moves is regulated by the sition and arrangement of the valves.

Chemistry.—In addition to the constituents of lymph, the following chemical substances have en found in lymphatic glands: leucin and xanthin.

198. PROPERTIES OF CHYLE AND LYMPH.—**Chyle** and **ymph** are albuminous, colorless, clear juices, containing **lymph corpuscles,** hich are identical with the colorless blood corpuscles (§ 9). In some places, *e.g.*, n the lymphatics of the spleen, especially in starving animals, and in the thoracic luct, a few colored blood corpuscles have been found. The lymph corpuscles are upplied to the lymph and chyle from the lymphatic glands and the adenoid issue. As to their source see § 200, 2. They also pass out of the blood vessels nd wander into the lymphatics. As red blood corpuscles have also been seen to ass out of the blood vessels, this explains the occasional presence of these cor- uscles in some lymphatics; but when the pressure within the veins is high, near he **central** orifice of the thoracic duct, red blood corpuscles may pass into the horacic duct. But we are not entitled to conclude from their presence that mph cells form red blood corpuscles. In addition, the **chyle** contains merous **fatty granules,** each surrounded with an albuminous envelope. Thus the chyle, in addition to the constituents of the lymph, contains, especially ring digestion, a very large amount of fat, in the form of the finely emul- sified fat of the food, which gives it its characteristic *white* or milky appearance. ring hunger, the fluid in the lacteals resembles ordinary lymph. The fine fat anules constitute the so-called "**molecular basis**" of the chyle.]

Composition of Lymph.—The lymph consists of **lymph plasma** with **mph corpuscles** suspended in it. The corpuscles or leucocytes are described § 24. The **lymph plasma** contains the three so-called fibrin factors, derived ry probably from the breaking up of lymph corpuscles (§ 29). When lymph is thdrawn from the body, these substances cause it to **coagulate.** Coagulation curs slowly, owing to the formation of a soft, jelly-like, small "**lymph clot,**" hich contains most of the lymph corpuscles. The exuded fluid or **lymph** rum contains *alkali albuminate* (precipitated by acids), *serum albumin* (coagu- ted by heat), and *paraglobulin*—the two latter occurring in the same proportion in blood serum; 37 per cent. of the coagulable proteids is paraglobulin.

(1) **Chyle,** which occurs within the lacteals of the intestinal tract, can only be btained in very small amount before it is mixed with lymph, and hence the diffi- lty of investigating it. A few *lymph corpuscles* occur even in the origin of cteals within the villi, but their number increases in the vessels beyond the testine, more especially after the chyle has passed through the mesenteric glands. he amount of **solids,** which undergoes a great increase during digestion, on e contrary, diminishes when chyle mixes with lymph. After a diet rich in tty matters, the chyle contains innumerable *fatty granules* (2–4 μ in size). [This the so-called "molecular basis" of the chyle.] The amount of *fibrin factors* creases with the increase of lymph corpuscles, as they are formed from the break- g up of the lymph-corpuscles; a *diastatic ferment* absorbed from the intestine; casionally *sugar* (to 2 per cent.); after much starchy food, *lactates;* peptone the leucocytes (§ 192, I, 3), and traces of urea and leucin.

The **Chyle** of a person who was executed contained 90.5 per cent. of water.

Solids,	9.5	Fibrin,	trace
		Albumin,	7.1
		Fats,	0.9
		Extractives,	1.0
		Salts,	0.5

Schmidt found the following **inorganic** substances in 1000 parts of chyle :—

Sodic chloride,	5.84	Sulphuric acid,	0.05	Magnesic phosphate,	0.05
Soda,	1.17	Phosphoric acid,	0.05	Iron,	trace.
Potash,	0.13	Ca'cic phosphate.	0.20		(Horse.)

(2) **The lymph** obtained from the beginning of the lymphatic system contains very few lymph corpuscles; it is clear, transparent, and colorless, and closely resembles the fluids of serous cavities. That the lymph coming from different tissues varies somewhat, is highly probable, but this has not been proved. After lymph has passed through lymphatic glands, it contains more corpuscles, and also more solids, especially albumin and fat. Ritter counted 8200 lymph corpuscles in 1 cubic centimetre of the lymph of a dog.

Pure lymph obtained from a lymphatic fistula in the leg of a man has an alkaline reaction and a saline taste, and the following composition :—

Pure Lymph (*Hensen & Dähnhardt*).	Cerebro-spinal Fluid (*Hoppe-Seyler*).	Pericardial Fluid (*v. Gorup-Besanez*).
Water, 98.63	98.74	95 51
Solids, 1.37	1.25	4.48
Fibrin, 0.11	...	0.08
Albumin, 0 14	0.16	2.46
Alkali-albuminate, 0.09	...	...
Extractives, ...	...	1.26
Urea, Leucin, 1.05	The cerebro-spinal fluid and abdominal lymph contain a kind of sugar (without the property of rotating polarized light—*Hoppe-Seyler*).	
Salts, 0.88		
70 vol. per cent. of absorbed CO_2, 50 per cent. could be pumped out, and 20 per cent. by the addition of an acid.		

100 parts of the **ash** of **lymph** contained the following substances :—

Sodium chloride,	74.48	Lime,	0.98	Sulphuric acid,	1.28
Soda,	10.36	Magnesia,	0.27	Carbonic acid,	8.21
Potash,	3.26	Phosphoric acid,	1.09	Iron oxide,	0.06

Just as in blood, **potash** and **phosphoric acid** are most abundant in the **corpuscles**; while **soda** (chiefly sodium chloride) is most abundant in the **lymph serum.** The potash and phosphoric acid compounds are most abundant in cerebro-spinal fluid, according to C. Schmidt. The amount of **water** in the lymph rises and falls with that of the blood. **Gases.**—Dog's lymph contains much CO_2—more than 40 vols. per cent., of which 17 per cent. can be pumped out, and 23 per cent. expelled by acids, while there are only traces of O and 1.2 vols. per cent. N (*Ludwig, Hammersten*).

[The **cerebro-spinal fluid** contains a substance which reduces an alkaline solution of cupric hydrate. The potassic are in excess of the soda salts, while the fluid of the meningoceles and chronic hydrocephalus contains proto-albumose, some serum globulin, no serum albumin, but the last is present in acute hydrocephalus fluid. No albumose is found in pericardial or pleuritic fluids (*Halliburton*).]

199. QUANTITY OF LYMPH AND CHYLE.—When it is stated that the total **amount** of the lymph and chyle passing through the large vessels in twenty-four hours is equal to the amount of the blood, it must be remembered that this is merely a conjecture. Of this amount one-half may be lymph and the other half chyle. The formation of lymph in the tissues takes place continually, and without interruption. Nearly 6 kilos. of lymph were collected in twenty-four hours from a lymphatic fistula in the arm of a woman, by Gubler and Quevenne; 70 to 100 grms. were collected in 1½ to 2 hours from the large lymph trunk in the neck of a young horse. The following conditions affect the **amount** of chyle and lymph :—

(1) The amount of chyle undergoes very considerable **increase during digestion,** more especially after a full meal, so that the lacteals of the mesentery and intestine are distended with white or milky chyle. During hunger the lymph vessels are collapsed, so that it is difficult to see the large trunks.

(2) The amount of lymph **increases** especially with the **activity of the organ** from which it proceeds. Active or passive muscular movements greatly increase its amount. Lesser obtained in this way 300 cubic centimetres of lymph from a fasting dog, whereby its blood became so inspissated as to cause death.

(3) All conditions which increase the **pressure** upon the juices of the tissues *increase* the amount of lymph, and *vice versâ*. These conditions are:—

(*a*) An **increase of the blood pressure,** not only in the whole vascular system, but also in the vessels of the corresponding organ, augments, the amount of lymph and *vice versâ* (*Ludwig, Tomsa*). This, however. is doubtful, as has been shown by Paschutin and Emminghaus. [In order to increase the amount of lymph depending upon pressure within the vessels, what must happen is increased pressure within the capillaries and veins.]

(*b*) **Ligature** or **obstruction** of the efferent **veins** greatly increases the amount of lymph which flows from the corresponding parts (*Bidder, Emminghaus*). It may be doubled in amount. Tight bandages cause a swelling of the parts on the peripheral side of the bandage, owing to a copious effusion of lymph into the tissue (congestive œdema).

(*c*) An increased **supply of arterial blood** acts in the same way, but to a less degree. Paralysis of the vasomotor nerves, or stimulation of vaso-dilator fibres, by increasing the supply of blood increases the amount of lymph; while diminution of the blood supply, owing to stimulation of vaso-motor fibres or other causes, diminishes the amount. Even after ligature of both carotids, as the head is still supplied with blood by the vertebrals, the lymph stream in the large cervical lymphatic does not cease.

(4) When the **total amount of the blood** is increased, by the injection of blood or serum into the arteries, much fluid passes into the tissues and increases the formation of lymph.

(5) The formation of lymph still goes on for a short time after death, and after complete cessation of the action of the heart, but only to a slight extent. If fresh blood be caused to circulate in the body of an animal, while it is still warm, more lymph flows from the lymphatics. It appears as if the tissues obtained plasma from the blood for a time after the stoppage of the circulation. This perhaps explains the circumstance that some tissues, *e. g.*, connective tissues, contain more fluid after death than during life, while the blood vessels have given out a considerable amount of their plasma after death.

(6) The amount of lymph is increased under the influence of **curara**, and so is the amount of solids in the lymph (*Lesser*). A large amount of lymph collects in the lymph sacs [especially the sub-lingual] of frogs poisoned with curara, which is partly explained by the fact that the lymph hearts are paralyzed by curara. The amount of lymph is also increased in inflamed parts.

200. ORIGIN OF LYMPH.—(1) Source of the Lymph Plasma.— The lymph plasma may be regarded as fluid which has been pressed through the walls of the blood vessels by the blood pressure, *i. e.*, by **filtration** into the tissues. The *salts* which pass most readily through membranes, go through nearly in the same proportion as they exist in blood plasma—the *fibrin factors* to about two-thirds, and *albumin* to about one-half of that in the blood. As in the case of other filtration processes, the amount of lymph must increase with increasing pressure.

This was proved by Ludwig and Tomsa, who found that when they passed blood serum under varying pressures through the blood vessels of an excised testis, the amount of transuded fluid which flowed from the lymphatics varied with the pressure. This "**artificial lymph**" had a composition similar to that of the natural lymph. Even the amount of al umin increased with increasing pressure. The lymph plasma is mixed in the different tissues with the decomposition products, the results of the metabolism of the tissues.

When the **muscles act,** not only is the lymph poured out more rapidly, but more lymph is formed. The tendons and fasciæ of the muscles of the skeleton, which are provided with numerous small stomata, absorb the lymph from the muscles. By the alternate contraction and relaxation of these fibrous structures, act like suction pumps, whereby the lymphatics are alternately filled and while the lymph is propelled onward. Even **passive movements**

act in the same way. If solutions be injected under the fascia lata, they may be propelled onward to the thoracic duct by passive movements of the limb (*Ludwig, Schweigger-Seidel*).

(2) **The source of the lymph corpuscles** varies.—(1) A very considerable number of lymph corpuscles are derived from the **lymphatic glands**; they are washed out of these glands into the vas efferens by the lymph stream, hence, the lymph always contains more corpuscles after it has passed through a lymph gland. Small isolated lymph follicles permit corpuscles to pass through their limiting layer into the lymph stream. (2) Those organs whose basis consists of **adenoid tissue**, and in whose meshes numerous lymph corpuscles occur, *e. g.*, the mucous membrane of the entire intestinal tract, red marrow of bone, and the spleen (§ 103). The cells reach the origin of the lymph stream by their own amœboid movements. (3) As lymph corpuscles are returned to the blood stream, where they appear as colorless blood corpuscles, so they again pass out of the **blood capillaries** into the tissues, partly owing to their amœboid movements, and they are partly expelled by the blood pressure. In rare cases lymph corpuscles wander from lymphatic spaces back again into the blood vessels.

Fine particles of cinnabar or milk globules introduced into the blood soon pass into the lymphatics. The extrusion of particles is greater during venous congestion than when the circulation is undisturbed, just as with diapedesis (§ 95); inflammatory affections of the vascular wall also favor their passage. The vessels of the portal system are especially pervious.

(4) By division **of the lymph corpuscles**, and also by **proliferation of the fixed connective-tissue corpuscles.** This process certainly occurs during inflammation of many organs. This has been proved for the excised cornea kept in a moist chamber; the nuclei of the cornea corpuscles also proliferate.

That the connective-tissue corpuscles proliferate is shown by the enormous production of lymph corpuscles in acute inflammations (with the formation of pus), *e. g.*, in extensive erysipelas, and inflammatory purulent effusions into serous cavities, where the number of corpuscles is too great to be explained by the wandering of blood corpuscles out of the blood vessels.

Decay of Lymph Corpuscles.—The lymph corpuscles disappear partly where the lymphatics arise. The presence of the fibrin factors in the lymph—formed as they are from the breaking up of lymph corpuscles—seems to indicate this. In inflammation of connective tissue, in addition to the formation of numerous new lymph corpuscles, a considerable number seems to be dissolved; hence the lymph, and also the blood, in this case contains more fibrin. Lymph corpuscles are also dissolved within the blood stream, and help to form the fibrin factors.

201. **MOVEMENT OF CHYLE AND LYMPH.**—The **ultimate cause** of the movement of the chyle and lymph depends upon the difference of the pressure at the origin of the lymphatics, and the pressure where the thoracic duct opens into the venous system.

(1) The forces which are active at the **origin of the lymphatics** are concerned in moving the lymph, but these must vary according to the place of origin. (*a*) The **lacteals** receive the first impulse toward the movements of their contents—the chyle—from the contraction of the **muscular fibres of the villi** (pp. 339, 344). When these contract and shorten, the axial lacteal is compressed, and its contents are forced in a centripetal direction toward the large lymphatic trunks. When the villi relax, the numerous valves prevent the return of the chyle into the villi. (*b*) Within those lymphatics which take the form of perivascular spaces, every time the contained *blood vessel* is *dilated* the surrounding lymph will be pressed onward. (*c*) In the case of the pleural lymphatics with open mouths, every **inspiratory movement** acts like a suction pump upon the lymph, and the same is the case with the openings or stomata of the lymphatics on the abdominal side of the *diaphragm*. (*d*) In the case of those vessels which begin

by means of fine juice canals, the movement of the lymph must largely depend upon the **tension of the juices of the parenchyma**, and this again must depend upon the tension or *pressure in the blood capillaries*, so that the blood pressure acts like a *vis a tergo* in the rootlets of the lymphatics.

[In some organs peculiar **pumping arrangements** are brought into action. The abdominal surface of the **central tendon** of the **diaphragm** is provided with stomata, or open communications between the peritoneal cavity and the lymphatics in the substance of the tendon. Von Recklinghausen found that milk put upon the peritoneal surface of the central tendon showed little eddies, caused by the milk globules passing through the stomata and entering the lymphatics. The central tendon consists of two layers of fibrous tissue arranged in different directions (Fig. 223, *b*, *c*). When the

FIG. 223.

Section of central tendon of diaphragm. The injected lymph spaces, *h* and *h*, are black. At *f* the walls of the space have collapsed.

diaphragm moves during respiration, these layers are alternately pressed together and pulled apart. Thus the spaces are alternately dilated and contracted, lymph being drawn into the lymphatics through the stomata (Fig. 223, *h*). The same kind of pumping mechanism exists over the **costal pleura.** The fascia covering the muscles is another similar mechanism. The fascia consists of two layers of fibrous tissue, with intervening lymphatics (Fig. 224). When a muscle contracts, lymph is forced out from between the layers of the fascia, while when it relaxes, the lymph from the muscle, carrying with it some of the waste products of muscular action, passes out of the muscle into the fascia, between the now partially separated layers.]

[**Ludwig's Experiment.**—Tie a respiration cannula in the trachea of a dead rabbit; cut across the body of the animal immediately below the diaphragm; remove the viscera, and ligature the vessels passing between the thorax and abdomen; tie the thorax to an iron ring, and hang it up with the head downward; pour a solution of Berlin blue upon the peritoneal surface of the diaphragm;

FIG. 224.



Injected lymph spaces (black) from the fascia lata of the dog.

connect the respiration cannula either with a pair of bellows or an apparatus for artificial respiration, and imitate the respiratory movements. After a few minutes the lymphatics are filled with a blue injection showing a beautiful plexus.]

(2) Within the lymph trunks themselves, the **independent contraction of their muscular fibres** partly aids the lymph stream. Heller observed in the mesentery of the guinea pig that the peristaltic movement of the lymphatic wall passed in a centripetal direction. The numerous **valves** prevent any reflux. The **contraction of the surrounding muscles,** and **pressure** upon the vessels and the tissues, aid the current. If the outflow of blood from the veins is interfered with, lymph flows copiously from the corresponding tissues. [If a

cannula be tied in a lymphatic of a dog, a few drops of lymph flow out at long intervals. But if even *passive* movements of the limb be made, *e. g.*, simply flexing and extending the limb, the outflow becomes very considerable and continuous.]

(3) The **lymph glands,** which occur in the course of the lymphatics, offer very considerable resistance to the lymph stream, which must pass through the lymph paths, whose spaces are traversed by adenoid tissue, and contain a few lymph corpuscles. But this is, to a certain extent, compensated for by the non-striped muscle which exists in the capsule and trabeculæ of the glands. When they contract they force on the lymph, while the valves prevent its reflux. Enlarged lymphatic glands have been seen to contract when stimulated electrically. [Botkin has stimulated enlarged lymphatic glands with electricity in cases of leukæmia.]

(4) The lymph vessels gradually join to form larger vessels, and finally end in one trunk. Thus the *sectional area* diminishes, so that the **velocity** of the current and the pressure are increased. Nevertheless, the velocity is always small; it varied from 230 to 300 millimetres per minute in the large lymphatic in the neck of a horse, a fact which enables us to conclude that the movement must be very slow in small vessels. The *lateral pressure* at the same place was 10 to 20 mm., and in the dog 5 to 10 mm. of a weak solution of soda, although it was 12 mm. Hg in the thoracic duct of a horse.

(5) The **respiratory movements** exercise a considerable influence upon the lymph stream in the thoracic duct, and in the right lymphatic duct; every inspiration favors the passage of the venous blood, and also of the lymph toward the heart, whereby the tension in the thoracic duct may even become negative. [The *diastolic suction of the heart*, by diminishing the pressure in the subclavian vein, also favors the inflow of lymph into the thorax.]

FIG. 225.



Posterior pair of lymph hearts (L) of the frog.

(6) **Lymph hearts** exist in certain cold-blooded animals. The frog has two *axillary* hearts (above the shoulder near the vertebral column), and two *sacral* hearts, one on each side of the coccyx near the anus (Fig. 225, L). They beat, but not synchronously, about sixty times per minute, and contain 10 cubic centimetres of lymph. They have transversely striped muscular fibre in their walls, and are also provided with *nerve ganglia*. The posterior pair pump the lymph into the branch of the vena iliaca communicans, and the anterior pair into the vena subscapularis. Their pulsation depends partly, but not exclusively, upon the spinal cord, for if the cord be rapidly destroyed, they may cease to pulsate, but not unfrequently they continue to pulsate after removal of the cord. [And if the cord be destroyed gradually, they continue to beat (*Kabrhel*).] A second source of their pulsatile movements is to be sought for in Waldeyer's ganglia. Stimulation of the skin, intestine, or blood heart influences them reflexly—partly accelerating and partly retarding them [most frequently arresting them in diastole, so that there seems to be an inhibitory mechanism in the cord, but it is not affected by atropine (*Kabrhel*)]. If the coccygeal nerve, which connects the sacral hearts to the spinal cord be divided, these effects do not occur. *Strychnia* accelerates their movements, and so does heating of the spinal cord; but if the cord be cooled, they are retarded. A lymph heart arrested by being exposed, or after the action of muscarin, can be caused to beat by filling it under pressure, but this is not the case when the arrest is caused by destruction of its nerves. *Antiarin* paralyzes the lymph heart and the blood heart at the same time, while *curara* paralyzes the former alone. In other amphibians there are two lymph hearts; in the ostrich and cassowary and some swimming birds, and in the embryo chick, 1 or 2. They occur in some fishes, *e. g.*, near the caudal vein of the eel.

(7) The **nervous system** has a direct effect upon the lymph stream, on account of its connection with the muscles of the lymphatics and lymph glands, and with the lymph hearts where these exist. Kühne observed that the cornea corpuscles contracted when the corneal nerves were stimulated [and Hoffman has described the termination of nerves in connective tissue corpuscles]. Goltz also observed that, when a dilute solution of common salt was injected under the skin of a frog, it was rapidly absorbed, but if the central nervous system had been destroyed, it was not absorbed.

If inflammation be produced in the hind legs of a dog, and if the sciatic nerve be divided on one side, œdema and a simultaneous increase of the lymph stream occur on that side. [A combination of congestion and inflammation greatly increases the lymph stream, and this is still more the case when the nerves are divided at the same time.]

Ligature the leg of a frog, except the nerves, so as to arrest the circulation, and place the leg in water; it swells up very rapidly, but a dead limb does not swell up. So that absorption is independent of the continuance of the circulation. Section of the sciatic nerve, or destruction of the spinal cord (but not section of the brain), arrests absorption.

202. **ABSORPTION OF PARENCHYMATOUS EFFUSIONS.**—Fluids which pass from the blood vessels into the spaces in the tissues, or those injected subcutaneously, are absorbed chiefly by the blood vessels, but also by the lymphatics. Small particles, as after tattooing with cinnabar or China ink, may pass from the tissue spaces into the lymphatics—and so do blood corpuscles from extravasations of blood, and fat granules from the marrow of a broken bone. If all the lymphatics of a part are ligatured, absorption takes place quite as rapidly as before; hence, absorbed fluid must pass through the thin membranes of the blood vessels. The corresponding experiment of ligaturing all the blood vessels, when no absorption of the parenchymatous juices takes place, does not prove that the lymphatics are not concerned in absorption, for, after ligaturing the blood vessels of a part, of course the formation of lymph, and also the lymph stream, must cease. When fluids are injected under the skin, absorption takes place very rapidly—more rapidly than when the substance is given by the mouth. The **subcutaneous injection** of drugs is extensively used, but of course the substances used must not corrode, irritate, or coagulate the tissues. Some substances do not act when given by the mouth, as snake poison, poisons from dead bodies, or putrid things, although they act rapidly when introduced subcutaneously. If **emulsin** be given by the mouth, and **amygdalin** be injected into the veins of an animal, hydrocyanic acid is not formed, as the emulsin seems to be destroyed in the alimentary canal. If the emulsin, however, be injected into the blood, and the amygdalin be given by the mouth, the animal is rapidly poisoned, owing to the formation of hydrocyanic acid, as the amygdalin is rapidly absorbed from the intestinal canal. The amygdalin, a glucoside ($C_{20}H_{27}NO_{11}$), is acted upon by fresh emulsin like a ferment; it takes up $2(H_2O)$ and yields hydrocyanic acid (CHN), + oil of bitter almonds (C_7H_6O), + sugar $2(C_6H_{12}O_6)$. **Serum** injected subcutaneously is rapidly absorbed; it is decomposed within the blood stream, and increases the amount of urea. Albuminous solutions, oil, peptones, and sugars are also absorbed.

203. **ŒDEMA, DROPSY, AND SEROUS EFFUSIONS.**—[**Dropsy.**—As aptly illustrated by Lauder Brunton, the lymph spaces may be represented by cisterns, each of which is provided with supply pipes—the arteries and capillaries; while there are two exit pipes—the veins and lymphatics. In health, the balance between the inflow and outflow is such that the spaces are merely moistened with fluid. When a cannula is placed in a lymphatic vessel in a dog, only a few drops of lymph flow out at long intervals, but if the veins of the limb be ligatured, the lymph flows much more quickly. This is in part due to the increased transudation of fluid from the small blood vessels, but it may also be due to fluid passing away by the lymphatics when it can no longer be carried away by the veins. We cannot say what is the relative share of the veins and the lymphatics, nor in the above experiment do we know how much is due to increased transudation or diminished absorption. When there is an undue accumulation of fluid more or less like serum in the lymph spaces, we have the condition termed **dropsy.** When there is general dropsy it is called **anasarca.**]

Œdema.—If the efferent veins and lymphatics of an organ be ligatured, or if resistance be offered to the outflow of their contents, congestion and a copious transudation of lymph into the tissue take place. These are most marked in the skin and subcutaneous cellular tissue. The soft parts swell up, without pain or redness, and a doughy swelling, which **pits** on **pressure** with the finger, results. These are the signs of lymph congestion, which is called **œdema** when the fluid is *watery* and localized.

Under similar circumstances lymph is effused in the **serous cavities.** [In the peritoneum it is **ascites**—thorax, **hydrothorax**—pericardium, **hydro-pericardium**—cranium, **hydrocephalus**—tunica vaginalis, **hydrocele**—joints, **hydrarthrosis,** etc.] If, at the same time, a large number of colorless blood corpuscles pass out of the blood vessels into the cavity, the fluid becomes more and more like pus. In order that these corpuscles may proliferate, a considerable percentage of albumin is necessary. When the pressure within the serous cavity rises above that in the small blood vessels,

water may pass into the blood. These sero-purulent effusions not unfrequently undergo changes, and yield decomposition products, such as leucin, tyrosin, xanthin, kreatin, kreatinin (?), uric acid (?), urea. Endothelium from the serous cavity, sugar in pleuritic effusions and in œdemas with little albumin, cholesterin frequently in hydrocele fluid, and succinic acid in the fluid of echinococci, have all been found in these effusions. The effusion of lymph may arise not only from pressure upon the lymphatics, but also from inflammation and thrombosis of the lymphatics themselves, in which cases not unfrequently new lymphatics are formed, so that the communication is reëstablished. Sometimes the ductus thoracicus bursts, and lymph is poured directly into the abdomen or thorax. [Ligature of the thoracic duct results in rupture of the receptaculum chyli and escape of chyle and lymph into the large serous cavities (*Ludwig*).

When dropsy or effusion of fluids occurs into serous cavities, there is always a greater transudation of fluid through the blood vessels. The abdominal blood vessels, and those which yield a watery effusion under normal circumstances, are those most liable to be affected.

Transudation is favored by (1) **Venous congestion,** so as to raise the **blood pressure**, in which case the effusion usually contains little albumin and few lymph corpuscles, while the colored corpuscles, on the contrary, are more numerous the greater the venous obstruction. Ranvier produced œdema artificially by ligaturing the vena cava in a dog, and at the same time dividing the sciatic nerve. The paralytic dilatation of the blood vessels thereby produced caused an increased amount of blood to pass to the limb, while the blood pressure was raised, and both factors favored the transudation of fluid. [Ranvier's experiment proves that mere ligature of the venous trunk of a limb *by itself* is not sufficient to cause œdema. The œdema is due to the concomitant paralysis of the vasomotor nerves. If the motor roots of the sciatic nerve alone be divided along with ligature of the vena cava, no œdema occurs, but if the vasomotor fibres are divided at the same time the limb rapidly becomes œdematous. There is such an increased transudation through the vascular walls that the veins and lymphatics cannot remove it with sufficient rapidity, and œdema occurs. If there be weakness of the vasomotor nerves, slight obstruction is sufficient to produce œdema.] When the leg veins are occluded with an injection of gypsum, œdema occurs. (2) Some unknown **physical changes** occur in the **protoplasm** of the endothelium of the capillaries and blood vessels, which favor the transudation of albumin, hæmoglobin, and even blood corpuscles. This occurs when abnormal substances accumulate in the blood—*e. g.*, dissolved hæmoglobin—and when the blood contains little O or albumin. The same has been observed after exposure to too high temperatures, and the swelling of soft parts in the neighborhood of an inflammatory focus seems due to the transudation of fluid through the altered vascular wall. It is probable that a nervous influence may affect particular areas through its action on the blood vessels of the part (it may be upon the protoplasm of the blood capillaries). The transudations of this nature usually contain much albumin and many lymph corpuscles. (3) When the **blood** contains a very large **amount of water,** the tendency to transudation of fluid is increased. After a time it may produce the changes indicated in (2), and when long continued may increase the permeability of the vascular wall. Watery lymphatic effusions from watery blood—"**cachectic œdema**"—occur in feeble and badly-nourished individuals. [One of the commonest forms of dropsy is the slight œdema of the legs in anæmic persons, in whom the heart and lungs are healthy. Many factors are involved—the blood pressure, watery condition of the blood, the condition of nutrition of the capillaries, and probably a tendency to vasomotor paresis (*Brunton*).]

[The fluid poured out varies according to the rapidity with which this occurs. In acute inflammations effusion or **exudation** takes place rapidly, and the fluid contains the fibrin factors, so that it tends to coagulate spontaneously. There is every gradation between the non-coagulable hydrocele fluid and the coagulable exudation in inflammation. The fluids in different dropsies vary in composition, and some have more cells in them, depending on local causes, as in some situations absorption is more active than in others. The pleural fluid contains most solids, then ascitic, cerebro-spinal, and lastly that in the subcutaneous tissue. Transudation corresponds to the process of filtration through animal membranes, *i. e.*, the transudation contains only those substances already present in the blood plasma. The filtrate may even contain more salts than the original fluid, as is often the case with fluids containing cry-talloid and colloid bodies. Senator finds, in cases of œdema of the leg, that increase of the venous pressure increases the proteids in the transudation, but causes no essential change in the amount of the salts.]

[(4) Ostroumoff found that stimulation of the lingual nerve not only causes the blood vessels of the tongue to dilate, but that the corresponding side of the tongue becomes œdematous. If a solution of dilute hydrochloric acid or quinine (§ 145) be injected into the duct of the sub-maxillary gland, and the chorda tympani stimulated, there is no secretion of saliva, but the gland becomes œdematous. In an animal poisoned with atropin, stimulation of the chorda causes dilatation of the blood vessels, although there is no secretion of saliva, nevertheless the gland does not become œdematous (*Heidenhain*). As Brunton suggests, this experiment points to some action of atropin on the blood vessels which has hitherto been entirely overlooked.]

204. COMPARATIVE PHYSIOLOGY.—In the **frog** large lymph sacs, lined with endothelium, exist under the skin, while large lymph sacs lie in relation with the vertebral column—one on each side—separated from the abdominal cavity by a thin membrane, perforated with stomata.

: **cysterna lymphatica magna** of Panizza. Some amphibians and many reptiles have skin large lymph spaces, which occupy the whole of the dorsal region of the body. All d the tailed amphibians have large elongated reservoirs for lymph along the course of the ıe lymph apparatus of the tortoise (Fig. 218) is very extensive. The **osseous fishes** e lateral parts of their backs an elongated lymph trunk, which reaches from the tail to the ns, and is connected with the dilated lymphatic rootlets in the base of the tail and in the largest internal lymph sinus is in the region of the œsophagus. Many **birds** possess a dilatation or lymph space in the region of the tail. The lymph spaces communicate with ı system—with valves properly arranged—usually in connection with the upper vena cava. :arts have already been referred to (§ 201, 6). In **carnivora** the lymph glands of the are united into one large compact mass, the so-called "pancreas Asellii."

ISTORICAL.—Although the Hippocratic School was acquainted with the lymph glands becoming swollen from time to time, and although Herophilus and Erasistratus had seen teric glands, yet Aselli (1662) was the first who accurately described the lacteals of the with their valves. Pecquet (1648) discovered the receptaculum chyli; Rudbeck and rtholinus the lymphatic vessels (1650–52); Eustachius (1563) was acquainted with the ıct, which Gassendus (1654) maintained that he was the first to see; Lister noticed that ɔecame blue when indigo was injected into the intestine (1671); Sömmering observed the of fibrin when lymph coagulated; Reuss and Emmert discovered the lymph corpuscles. ıical investigations date from the first quarter of this century; they were carried out by Tiedemann, Gmelin, and others. The two last-named observers noticed that the white ıyle was due to the presence of fatty granules.

PHYSIOLOGY OF ANIMAL HEAT.

206. SOURCES OF HEAT.—The heat of the body is an uninterrupted evolution of kinetic energy, which we must represent to ourselves as due to vibrations of the corporeal atoms. The **ultimate source** of the heat is contained in the potential energy taken into the body with the food, and with the O of the air absorbed during respiration. The **amount** of heat formed depends upon the amount of energy liberated.

FIG. 226.



Water calorimeter of Favre and Silbermann.

The energy of the food stuffs may be called **"latent heat,"** if we assume that when they are used up in the body, chiefly by a process of combustion, kinetic energy is liberated only in the form of heat. As a matter of fact, however, mechanical energy and electrical energy are developed from the potential energy. In order to obtain a unit measure for the energy liberated, it is advisable to express all the potential energy as **heat units.**

The Calorimeter.—This instrument enables us to transform the potential energy of the food into heat, and, at the same time, to measure the number of heat units produced.

Favre and Silbermann used a **water calorimeter** (Fig. 226). The substance to be burned is placed in a large cylindrical combustion chamber (K), suspended in a large cylindrical vessel (L) filled with water (*w*), so that the combustion chamber is completely surrounded by the water. Three tubes open into the upper part of the chamber; one of them (O) supplies the air which is necessary for combustion, it reaches almost to the bottom of the chamber; the second (*a*) is fixed in the middle of the lid, and is closed above with a thick glass plate, and on this is placed, at an angle, a small mirror (*s*), which enables an observer to look into the chamber, and observe the process of combustion at *c*. The third tube (*d*) is used only when combustible gases are to be burned in the chamber. It can be closed by means of a stop-cock. A lead tube (*e*, *e*), with many twists, passes from the upper part of the chamber through the water, and finally opens at *g*. The gaseous products of combustion pass out through this tube, and in doing so h
The cylindrical vessel with the water is closed with a lid which transm
cylinder stands on four feet within a large cylinder (M), whi
ductor of heat, and this again is placed in a large v
any heat reaching the inner cylinder from with
investigated is placed in the combustion c

inner water must be repeatedly stirred, the temperature of the water is ascertained by means of a delicate thermometer. If the increase of the temperature and the amount of water are known, then it is easy to calculate the number of **heat units** produced by the combustion of a known weight of substance (see *Introduction*).

The **ice calorimeter** may also be used. The inner cylinder is filled with ice and not with water, and ice is also placed in the outer cylinder to prevent any heat from without from acting upon the inner ice. The heat given off from the combustion chamber causes a certain amount of the ice to melt, and the water thereby produced is collected and measured. It requires 79 heat units to melt 1 grm. of ice to 1 grm. of water at 0° C.

FIG. 227.



Water calorimeter of Dulong.

[The amount of heat produced by a **living animal** is similarly measured. The animal (Fig. 227), in a cage, is placed in a large vessel, which is placed within another vessel, and the inter-space filled with water. The whole should be enclosed in a large box packed with fur, shavings, feathers, or other bad conductor of heat. A tube, D, opens into the inner space, and from it there is an exit tube, D′, which winds many times in the water space beneath. Air passes in through D and out by D′. The temperature of the water is ascertained by thermometers T and T′, while the water is moved by a stirrer (S) placed between the two.]

Just as in a calorimeter, although *much more slowly*, the food stuffs within our body are burned up, oxygen being supplied, and thus potential energy is transformed into kinetic energy, which, in the case of a person at *rest*, almost completely appears in the form of heat.

Heat Units.—Favre, Silbermann, Frankland, Rechenberg, B. Danilewsky, and others have made calorimetric experiments on the heat produced by food. According to Danilewsky, 1 gramme of the following dry substances yields heat units:—

Casein, ... 5855	Olein, ... 8958	Woman's milk, . 4837	Alcohol, ... 6980
Fibrin, ... 5772	Stearin, ... 9036	Egg yelk, . . . 4479	Urea, ... 2537
Peptone, ... 4876	Ox-fat, ... 9686	Potatoes, . . . 4234	Muscle Extractives (Liebig's) 4400
Gluin, ... 5493	Glycerine, . . . 4179	Rye bread, . . 4471	
Ox-blood, . . . 5900	Starch, ... 4479	Wheat bread, . . 4351	
Ox-flesh, ... 5724	Dextrose, . . . 3939	Rice, ... 4806	Flesh extract, . . 3216
Vegetable fibrin, . 6231	Maltose, ... 4163	Peas, ... 4889	Acetic acid, . . 3318
Gluten, ... 6141	Milk sugar, . . . 4162	Buckwheat, . . 4288	Butyric acid, . . 5647
Legumin, . . . 5573	Cane sugar, . . . 4173	Maize, ... 5188	Palmitic acid, . . 9316
Palmitin, ... 8883	Cow's milk, . . 5733		

As albumin is only oxidized to the stage of urea, we must deduct the heat units obtainable from urea from those of albumin, and as 1 part of albumin yields in round numbers about ⅓ of urea, we obtain about 5100 calories [= 2170 kilogram-metres] for 1 grm. of albumin.

Isodynamic foods, *i. e.*, those that produce an equal amount of heat; 100 grms. animal albumin (after deducting the heat units of urea) = 52 fat = 114 starch = 129 dextrose; 100 grms. fat are isodynamic with 243 dry flesh or 225 of dry syntonin (*Rubner*); 100 grms. of vegetable albumin = 55 fat = 121 starch = 137 dextrose (*Danilewsky*). Rubner calculated that in man, with a mixed diet, the *available* heat units for 1 grm. of albumin = 4100; 1 grm. fat = 9300; and for 1 grm. carbohydrate = 4100 calories.

[illegible] know the weight of any of the above-named substances consumed by
four hours, a simple calculation enables us to determine how
rmed in the body by oxidation, *i. e.*, provided the substance

[**Several sources of heat production or thermogenesis** are to be found in all tissues wherever oxidation is going on. The metabolism of protoplasm is always associated with the evolution of heat.]

(1) *In the transformation of the chemical constituents of the food, endowed with a large amount of potential energy, into such substances as have little or no energy.* The organic substances used as food consist of C, H, O, N, so that there takes place (*a*) **Combustion** of C into CO_2, of H into H_2O, whereby heat is produced; 1 grm. C burned to produce CO_2 yields 8080 heat units, while 1 grm. H oxidized to H_2O yields 37,460 heat units. The O necessary for these purposes is absorbed during respiration, so that, to a certain extent at least, the amount of heat produced may be estimated from the amount of O consumed. The same consumption of O gives rise to the same amount of heat whether it is used to oxidize H or C (*Pflüger*). There is a relation, amounting to cause and effect, between the amount of heat produced in the body and the O consumed. The cold-blooded animals, which consume little O, have a low temperature; among warm-blooded animals, 1 kilo. of a living rabbit takes up within an hour 0.914 grm. O, and its body is heated to a mean of 38° C. 1 kilo. of a living fowl uses 1.186 grms. O, and gives a mean temperature of 43.9° C. The amount of heat produced is the same whether the combustion occurs slowly or quickly; the rapidity of the metabolism, therefore, affects the rapidity, but not the absolute amount of heat production. The combustion of inorganic substances in the body *e.g.*, of the sulphur into sulphuric acid, the phosphorus into phosphoric acid, is another, although very small, source of heat.

[The **muscles** form about the half of the whole mass of the body and the bones nearly the other half. In the latter, oxidation does not go on actively, so that the muscles must be the great seats of heat production or thermogenesis in the body. This view is supported by the fact that the blood leaving a muscle at rest contains more CO_2 than the blood in the right ventricle. Muscular exercise greatly increases the metabolism and the CO_2 excreted (§ 127), but at the same time, there is a great increase in heat production. The muscles, therefore, are the great thermogenic tissues, and they yield $\frac{3}{5}$ of the heat in health. The several **secreting glands**, especially the liver, and the alimentary canal, during digestion, are also foci of heat formation.]

(*b*) In addition to the processes of combustion or oxidation, all those **chemical processes** in our body, by which the amount of the available potential energy which is present is diminished, in consequence of a greater satisfaction of atomic affinities, lead to the production of heat. In all cases where the atoms assume more stable positions with their affinities satisfied, chemical energy passes into kinetic thermal energy, as in the alcoholic fermentation of grape sugar and other similar processes.

Heat is also developed during the following chemical processes:—

(*a*) During the union of bases with acids. The nature of the base determines the amount of heat produced, while the nature of the acid is without effect. Only in those cases where the acid, *e.g.*, CO_2, is unable to set aside the alkaline reaction, the amount of heat produced is less. The formation of compounds of chlorine (*e.g.*, in the stomach) produces heat.

(β) When a neutral salt is changed into a basic one. In the blood the sulphuric and phosphoric acids derived from the combustion of S and P are united with the alkalies of the blood to form basic salts. The decomposition of the carbonates of the blood by lactic and phosphoric acids forms a double source of heat, on the one hand, by the formation of a new salt, and on the other, by the liberation of CO_2, which is partly absorbed by the blood.

(γ) The combination of hæmoglobin with O (§ 36).

During those chemical processes, whereby the heat of the body is produced, heat-absorbing intermediate compounds are not unfrequently formed. Thus, in order that the final stage of more complete saturation of the affinities be reached,

intermediary atomic groups are formed, whereby heat is absorbed. Heat is also absorbed when the solid aggregate condition is dissolved during retrogressive processes. But these intermediary processes, whereby heat is lost, are very small compared with the amonnt of heat liberated when the end products are formed.

(2) Certain **physical processes** are a **second source** of heat. (*a*) The **transformation of the kinetic mechanical energy** of internal organs, when the work done is not transferred outside the body, produces heat. Thus the whole of the kinetic energy of the heart is changed into heat, owing to the resistance opposed to the blood stream (§ 93). The same is true of the mechanical energy evolved by many muscular viscera. The torsion of the costal cartilages, the friction of the current of air in the respiratory organs, and the ingesta in the digestive tract, all yield heat.

An excessively minute amount of the mechanical energy of the heart is transferred to surrounding bodies by the cardiac impulse and the superficial pulse beats, but this is infinitesimally small. During respiration, when the respiratory gases and other substances are expired, a very small amount of energy disappears externally, which does not become changed into heat. If we assume that the daily work of the circulation exceeds 86,000 kilogram-metres, the heat evolved is equal to 204,000 calories, in twenty-four hours (§ 93), which is sufficient to raise the temperature of a person of medium size 2° C.

(*b*) When, owing to muscular activity, the body produces work which is transferred to external objects, *e. g.*, when a man ascends a tower or mountain, or throws a heavy weight, a portion of the kinetic energy passes into heat, owing to friction of the muscles, tendons, and the articular surfaces, as well as to the shock and pressure of the ends of the bones against each other.

(*c*) The electrical currents which occur in muscles, nerves, and glands very probably are changed into heat. The chemical processes which produce heat evolve electricity, which is also changed into heat. This source of heat, however, is *very small.*

(*d*) Other processes are the formation of heat from the *absorption of* CO_2, by the *concentration of water* as it passes through membranes, in *imbibition, and the formation of the solids, e. g.*, of chalk in the bones. After death, and in some pathological processes during life, the *coagulation of blood* and the production of *rigor mortis* are sources of heat.

207. HOMOIOTHERMAL AND POIKILOTHERMAL ANIMALS.—In place of the old classification of animals into "**cold-blooded**" and "**warm-blooded,**" another basis of classification seems desirable, viz., the relation of the temperature of the body to the temperature of the surrounding medium. Bergmann introduced the word **homoiothermal** for the **warm-blooded** animals (mammals and birds), because these animals can maintain a very uniform temperature, even although the surrounding temperature be subject to considerable variations. The so-called **cold-blooded** animals are called **poikilothermal,** because the temperature of their bodies rises or falls, within wide limits, with the heat of the surrounding medium.

When **homoiothermal animals** are kept for a long time in a cold medium, their heat production is increased, and when they are kept for a long time in a warm medium it is diminished.

Fordyce gave a proof of the nearly uniform temperature in man. A man remained ten minutes in an oven containing very dry hot air (§ 218), and yet the temperature of the palm of his hand, mouth, and urine was increased only a few tenths of a degree. Becquerel and Brechet investigated the temperature of the human biceps (by means of thermo-electric needles), when the arm had been one hour in iced water, and yet the temp rature of the muscular tissue was cooled only 0.2° C. The same muscle did not undergo any increase in temperature, or at most 0.2° C., when the man's arm was placed for a quarter of an hour in water at 42° C.

If heat be rapidly abstracted (§ 225) or rapidly supplied (§ 221) to the body, so as to produce rapid variation of the temperature, life is endangered.

Poikilothermal animals behave very differently; the temperature of their bodies generally follows, although with considerable variations, the temperature of the surroundings. When the temperature of the surroundings is increased, the amount of heat produced is increased, and when the surrounding temperature falls, the amount of heat evolved within the body also falls.

The following table shows very clearly the characters of **poikilothermal animals**, *e.g.*, **frogs**, which were placed in air and water of varying temperatures. They were immersed up to the mouth. The temperature was measured by means of a thermometer introduced through the mouth into the stomach.

In Water.		In Air.	
Temperature of the Water.	Temperature of Frog's Stomach.	Temperature of the Air.	Temperature of Frog's Stomach.
41.0° C.	38.0° C.	40.4° C.	31 7° C.
30.0	29.6	27.4	19.7
20.6	20.7	16.4	14.6
5.9	8.0	6.2	7.6
2.8	5.3	5.9	8.6

[**Temperature of Different Animals.**

Birds.	Temp.		Temp.		Temp.
Thalassidroma,	40.30	Swallow,	44.03	Panther,	38.90
Procellaria,	40.80	Gull,	37.8	Mouse,	41.1
Goose,	41.70	**Mammals.**		Dolphin,	35.5
Sparrow,	39.08–42.10	Tiger,	37.20	Sheep,	37.30–40.00; 39.50–40.00; 40.00–40 50
Pigeon,	41.80–42.50	Horse,	36.80–37.50	Ape,	35.50
Turkey,	42.70	Rat,	38.80	Guinea pig,	35.76–38.00
Guinea fowl,	43.90	Hare,	37.80	Rabbit,	37.50–38.00
Duck,	43.90–42.50	Cat,	38.30–38.90	Ox,	37.50
Crow,	41.17	Guinea pig,	38.80	Ass,	36 95
		Dog,	37.40; 39.00; 39.60	(*Gavarret & Rosenthal*).]	

Reptiles—Snakes, 10°–12°, but higher when incubating. *Amphibians and fishes*—0.5°–3° above the temperature of the surroundings. *Arthropoda*—0.1°–5.8° above the surroundings. Bees in a hive, 30°–32°, and when swarming, 40°. The following animals have a temperature higher than the surrounding temperature: Cephalopods, 0.57°; mollusks, 0.46°; echinoderms, 0.40; medusæ, 0.27°; polyps, 0.21° C.

208. **ESTIMATION OF TEMPERATURE.**—By using thermometric apparatus, we are enabled to obtain information regarding the degree of heat of the body to be investigated. For this purpose the following **methods** are employed:—

A. The Thermometer.—Celsius (1701–1744) divided his thermometer into 100 parts, and each part was again divided into 10 parts, so that $\frac{1}{10}$° C. could be easily read off. All thermometers which have been used for a long time give too high readings; hence they should be compared, from time to time, with a normal thermometer. When taking the temperature, the bulb ought to be surrounded for fifteen minutes, and during the last five minutes the mercury column ought not to vary. A very sensitive thermometer will indicate the temperature after seven seconds if the urine stream be directed upon its bulb. **Minimal** and **maximal** thermometers are often of use to the physician.

[**Clinically**, one of the thermometers shown in Fig. 228 may be used. They are self-registering maximum thermometers, *i. e.*, a portion of the mercury is separated from the mercurial column, to form the index, the top of which indicates the temperature. Before being used, the index must be well below the normal temperature. Various forms of surface thermometers have been used.]

Walferdin's **metastatic thermometer** (Fig. 229) is specially useful for comparative observation. The tube is very narrow in comparison with the bulb, and in order that the stem be not too long, it is constructed so that the amount of mercury can be varied. A quantity of mercury is taken, so that with the temperature expected the thread of mercury will

FIG. 228. FIG. 229.

A, Cassella's "infallible," B, "Ferris' perfect," and C, Evans' and Wormull's "standard" clinical thermometers.

stand about the middle of the stem. A small bulb at the upper part of the stem receives the excess of Hg. Suppose a temperature between 37°-40° C. is to be measured, the bulb is first heated a little over 40° C., it is then suddenly cooled, and shaken at the same time, so that the thread of mercury is thereby suddenly broken above 40°. The tube is so narrow that 1° C. is equal to about 10 centimetres of the length of the tube, so that $\frac{1}{100}$° C. is still 1 millimetre in length. The scale is divided empirically, but the value of the divisions must be compared with a normal thermometer.

Kronecker and Meyer used very small maximal "**outflow thermometers,**" and caused them to pass through the intestinal canal, or through large blood vessels. The mercury flows out of the short open tube, and of course more flows out, the higher the temperature. After these small bulbs have passed through the animal, a comparison is instituted with a normal thermometer, to determine at what temperature the mercury reaches the free margin of the tube.

B. Thermo-electric Method.—This method enables us to determine the temperature accurately and rapidly (Fig. 230, I). The **thermo-electric galvanometer** of Meissner and Meyerstein consists of a circular magnet (*m*) suspended by a thread of silk (*c*), to which a small mirror (S) is attached. A large stationary bar magnet (M) is placed near the magnet (*m*), so that the north poles (*n* and N) of both magnets point in the same direction, and it is so arranged that the suspended magnet is caused to point to the north by a minimal action of M. A thick copper wire (*b*, *b*) is coiled several times round *m* (although in the figure it is represented as a single coil), and the ends of the wire are soldered to two thermo-elements, each composed of two different metals—iron and German silver, the two similar free elements being united by a wire (*b*), so that the two thermo-elements form part of a closed circuit. A horizontal scale (K, K) is placed at a distance of 3 metres from the mirror, so that the divisions of the scale are seen in the mirror. The scale itself rests upon a telescope (F) directed toward the mirror. The observer (B), who looks through the telescope, can see the divisions of the scale in the mirror. When the magnet, and with it the mirror, swing out of the magnetic meridian, the observer notices other divisions of the scale in the mirror. When one of the thermo-elements is heated, an electrical current is produced, which passes from the iron to the German silver in the heated couple, and causes a deviation of the suspended magnet. Suppose a person were swimming in the direction of the current in the conducting wire, then the north pole of the magnet goes to the north (*Ampère*). The tangent of the angle ϕ, through which the freely movable magnet is diverted by a galvanic current, from its position of rest or zero, in the magnetic meridian, is the same as the galvanic stream; G is proportional to the magnetic energy D, *i. e.*, tang. $\phi = \frac{G}{D}$. If G is to remain the same, and the tang, ϕ to be as large as possible, the magnetic energy must be diminished as much as possible. If the magnetism of the suspended magnet be indicated by *m*, and that of the earth by T, the magnetic directing energy $D = Tm$, so that D can be distinguished in two ways: (1) by diminishing the magnetic moment of the suspended magnet, as may be done by using a pair of astatic needles, such as are used in Nobili's galvanometer; (2) and also by weakening the magnetism of the earth, by placing an accessory stationary magnet (Hauy's rod) in the same direction, and near the suspended magnet. An important arrangement for rapidly getting the magnet to zero is the dead-



Walferdin's metastatic thermometer.

beat arrangement of Gauss (not figured in the scheme). It consists of a thick copper cylinder, on which the wire of the coil is wound. This mass of copper may be regarded as a closed multiplicator with a very large transverse section. The vibrating magnet induces in this closed circuit a current of electricity, whose intensity is greatest when the velocity of the excursion of the magnet is greatest, and which takes the opposite direction as soon as the magnet returns toward zero. These induced currents cause a diminution of the vibration of the magnet in this way, that the arc of vibration of the magnet diminishes very rapidly, almost in a geometrical progression. The induced damping current is stronger, the less the resistance in the closed circuit, and in the damper or dead-beat arrangement itself, the greater the section of the copper ring. This damping arrangement limits

FIG. 230.



Scheme of thermo-electric arrangements for estimating the temperature.

the oscillations of the magnet, and it comes to rest rapidly and promptly after 3 or 4 small vibrations so that much time is saved. The angle of deviation is so small that the angle itself may be taken instead of the tangent.

The **thermo-electric needles** of Dutrochet (II) may be placed in the circuit. They consist of iron and German silver soldered at their points; or the needles of Becquerel (III) may be used. They consist of the same metal soldered in a straight line, one behind the other. The needles must always be covered by a varnish, which will prevent the parenchymatous juices from acting upon them, and causing a current. Before the experiment we must determine what extent of excursion on the scale is obtained with a certain temperature. In order to determine this, a delicate thermometer is fixed

to each of the thermo-couples, and both are placed in oil baths, which differ in temperature—say by 1° C.—as can be determined by the thermometer. When the current is closed, the excursion on the scale will indicate 1° C. Suppose that the excursion was 150 mm., then each mm. of the scale would be equal to $\frac{1}{150}$° C. When this is determined, the two thermo-needles may be placed in the different tissues or organs of animals, and, of course, we obtain the difference of temperature in these places. Or one thermo-couple may be placed in a bath of constant temperature (nearly that of the body), in which is placed a delicate thermometer, while the other needle is introduced into the organ to be investigated. In this case, we obtain the difference of temperature between the tissue and the source of the constant heat. The electric current passes in the warmer needle from the iron to the German silver, and thus through the wires of the apparatus. For small differences of temperature, such as occur in the body, the thermo-electric energy is always proportional to the difference of temperature of the two needles or couples. In place of a single pair of needles several may be used, whereby the sensitiveness of the apparatus is greatly increased. Helmholtz found that by using sixteen antimony-bismuth couples, he could detect an increase of $\frac{1}{4000}$° C. Schiffer prepared a simple thermopile (IV) by soldering together alternately four pairs of wires of iron (f) and German silver (a). These are placed in the two organs (A and B) which are to be investigated, whereby a very high degree of exactness is obtained.

209. **TEMPERATURE TOPOGRAPHY.**—Although the blood, in virtue of its continual motion (completing, as it does, the circulation in twenty-three seconds), must exercise a very considerable influence on the equilibration of the temperature in different organs, nevertheless, a completely uniform temperature does not exist, and the temperature varies in different parts :—

1. **Skin** (*J. Davy*).

Middle of the sole of the foot,	32.26° C.	Middle of upper arm,	35.40° C.
Near tendo-Achillis,	33.85	Inguinal fold,	35.80
Anterior surface of leg,	33.05	Near cardiac impulse,	34.40
Middle of calf,	33.85	Face,	31.00
Bend of knee,	35.00	Nose and tip of ear,	22.24

In the closed axilla, 36.49 (mean, of 505 individuals);—36.5 to 37.25 (*Wunderlich*);—36.89° C. (*Liebermeister*). The skin over muscles is warmer than that over bone (*Kunkel*).

The temperature of the skin of the head is higher in the forehead and parietal region than in the occipital region; the skin on the left side of the head is warmer than on the right. Dyspnœa increases the temperature of the skin.

Method.—Liebermeister determines the temperature of **free cutaneous surfaces** thus: The bulb of the thermometer is heated slightly above the temperature expected; after the mercury begins to fall, the bulb is placed on the skin, and if the bulb has the same temperature as the skin, the mercury remains stationary. This experiment must be repeated several times.

2. **Cavities.**

Mouth under the tongue,	37.19° C.	Vagina,	38.30° C.
Rectum,	38.01	Urine,	37.03

Uterine cavity somewhat warmer; cervical canal of the uterus somewhat cooler.

The temperature falls in the **stomach** during digestion (§ 166, 1). Cold injections (11° C.) into the rectum rapidly lower the temperature in the stomach 1° C. (*Winternitz*).

3. **The temperature of the blood** is, as a mean, 39° C. The venous blood in internal viscera is warmer than the arterial, but it is cooler in peripheral parts :—

Blood of the right heart,	38.8°	Blood of the superior vena cava,	36.78°
" left heart,	38.6	" inferior vena cava,	38.11
" aorta,	38.7	" crural vein,	37.20
" hepatic vein,	39.7	" (*Cl. Bernard and v. Liebig.*)	

The lower temperature of the **blood in the left heart** may be explained by the blood becoming cooled in its passage through the lungs during respiration. According to Heidenhain and Körner, the right heart is slightly warmer because it lies in relation with the warm liver, while the left heart is surrounded by the lung, which contains air. This observation is disputed by others, who say that the left heart is slightly warmer because the combustion processes are more active in arterial blood, and heat is evolved during the formation of oxyhæmoglobin. The blood in the **veins** is usually cooler than in the corresponding arteries, owing to the superficial position of the former, whereby they give off heat during their long course; thus the blood of the *jugular vein* is ½ to 2° C. lower than the blood in the *carotid*; the *crural vein* ¾ to 1° cooler than in the *crural artery*. **Superficial veins**, more especially those of the skin, give off much heat, and their blood is, therefore, somewhat cooler.

The **warmest blood** is that of the **hepatic vein**, 39.7° C., partly owing to the great chemical changes which occur within the liver, from its secretory activity (§ 210, *a*), and partly to its protected situation.

4. The individual **tissues** are warmer: (1) The greater the transformation of kinetic energy into heat, *i.e.*, the greater the tissue metabolism; (2) the more blood they contain; (3) and the more protected their situation. According to Heidenhain and Körner, the cerebrum is the warmest organ in the body.

Subcutaneous tissue (sheep), . .	37.35° C.	Rectum, ...	40.67° C.
Brain, ...	40.25	Right heart, ...	41.60
Liver, ...	41.25	Left heart, ...	40.90
Lungs, ...	41.40		(*Berger.*)

Becquerel and Brechet found the temperature of the human subcutaneous tissue to be 2.1° C. lower than that of the neighboring muscles. The **horny tissues** do not produce heat, and their low temperature is due to the conduction of heat from the parts on which they grow. The temperature of the **cornea** partly depends on that of the **iris**, and the more contracted the pupil is, the more heat it receives from the blood vessels of the iris.

210. CONDITIONS AFFECTING THE TEMPERATURE OF ORGANS.—The temperature of the individual organs is by no means constant; it is influenced by many conditions; among these are the following:—

(1) *The more heat* **produced** *independently within a part, the higher is its temperature.* As the amount of heat produced within a part depends upon its metabolism, therefore, when the metabolism is increased, the amount of heat produced is similarly increased.

(*a*) **Glands** produce more heat during the act of **secretion**, as is proved by the higher temperature of their secretion, or by the higher temperature of the **venous blood** flowing out of their veins.

Ludwig found that when he stimulated the chorda tympani, the **saliva** of the sub-maxillary gland was 1.5° C. warmer than the blood in the carotid, which supplied the gland with blood (p. 258). The blood in the renal vein in a **kidney** which is secreting is warmer than the blood in the renal artery. The secreting **liver** produces much heat (§ 178). Cl. Bernard investigated the temperature of the blood of the **portal** and **hepatic veins** during hunger, at the beginning of digestion, and when digestion was most active, and he found:—

Temperature of portal vein, . .	37.8° C.	*After 4 days' starvation.*	Blood of right heart. 38.8° (Hunger period.)
" hepatic vein, .	38.4		
Temperature of portal vein, . .	39.9	*Beginning of digestion.*	
" hepatic vein, .	39.5		
Temperature of portal vein,. .	39.7	*Digestion most active.*	Blood of right heart, during digestion, 39.2°.
" hepatic vein, .	41.3		

In the dog a moderate diet, chemical or mechanical stimulation of the gastric mucous membrane, or even the sight of food, raises the temperature in the **stomach** and **intestine.**

(*b*) When the **muscles contract**, they evolve heat. Davy found that an active muscle became 0.7° C. warmer; while Becquerel, by means of a thermo-galvanometer, found that human muscles, when kept contracted for five minutes, became 1° C. warmer (§ 302).

This is one of the reasons why the temperature may rise above 40° during **rapid running.** A temperature obtained by energetic muscular action usually does not fall to the normal until after resting for 1½ hour. The low temperature of paralyzed limbs depends partly upon the absence of the muscular contractions.

(*c*) With regard to the effect of **sensory nerves** upon the temperature, some of the chief points to ascertain are—whether the *circulation* is accelerated or retarded by their stimulation, or whether the *respiration* is increased or diminished (§ 214, II, 3), and whether the *muscles of the skeleton* are relaxed or contracted reflexly (§ 214, I, 3). In the former case the temperature of the interior and rectum is increased; in the latter, diminished.

(*d*) The temperature of the body rises during **mental exertion.** Davy observed an increase of 0.3° C. after vigorous mental exertion.

(*e*) The parenchymatous fluids, serous fluids and lymph produce little heat, owing to their feeble metabolism, hence they have the same temperature as their surroundings; the epidermal and horny tissues do not produce heat, they merely conduct it from subjacent structures.

(2) *The temperature depends, to a large extent, upon the amount of blood in* an organ, and also upon the *rapidity* with which the *blood is renewed* by the circulation. This is best observed in the difference of the temperature between a cold, pale, bloodless hand, and a warm, red, congested one.

Becquerel and Brechet found that the temperature of the human biceps fell several tenths of a degree when the axillary artery was compressed. Ligature of the crural artery and vein in a dog causes a fall of several degrees. If the extremities be kept suspended in the air, they become bloodless and cold.

Liebermeister has pointed out a difference with regard to the external and internal parts of the body. The **external parts** give off more heat than they produce, so that they become cooler the more slowly new blood flows into them, and warmer the greater the rapidity of the blood stream through them. Acceleration of the blood stream, therefore, causes the temperature of peripheral parts to approximate more and more to the temperature of internal organs, while retardation of the blood stream causes them to approach the temperature of the surrounding medium. Exactly the reverse is the case with **internal parts,** where a large amount of heat is produced, and heat is given up almost alone to the blood which flows through them. Their temperature must fall when the blood stream through them is accelerated, and it is raised when the blood stream is retarded. Hence it follows, that the *greater the difference of the temperature between peripheral and internal parts, the slower must be the velocity of the circulation.*

(3) If the **position of an organ** be such, or if other conditions cause it to give off heat by **conduction** or **radiation,** then its temperature *falls.*

A good example of this is the **skin,** which varies greatly in temperature according to the temperature of the surrounding medium, whether it is covered or uncovered, whether it is dry or moist with sweat (which abstracts heat when it evaporates). When much cold food or drink is taken, the **stomach** is cooled, and when ice-cold air is breathed, the **respiratory passages** as far as the bronchi are cooled.

211. ESTIMATION OF HEAT.—Calorimetry is the method of determining the amount of heat possessed by any body, or what amount of heat it is capable of producing. The unit of measurement is the "**heat unit,**" *i. e.,* the amount of heat (or potential energy) required to raise the temperature of 1 gramme of water 1° C. (see *Introduction*).

Experiment has shown that *equal quantities of different substances require very unequal amounts of heat to raise them to the same temperature, e. g.,* 1 kilo. water requires nine times as much heat as 1 kilo. iron to raise it to the same temperature. In the human body, therefore, which is composed of very different substances, unequal amounts of heat will be required to raise them all to the same temperature. The same amount of heat transferred to two different substances will raise them to different temperatures. Hence, bodies of different temperatures may contain equal amounts of heat. The amount of heat required to raise a definite quantity (*e. g.,* 1 grm.) of a substance to a certain higher degree (*e. g.,* 1° C.) is called "**specific heat.**" The specific heat of water (which of all bodies has the highest specific heat) is taken as = 1. By "**heat capacity**" is meant that property of bodies in virtue of which they must absorb a given amount of heat in order to have a certain temperature.

Calorimetry is employed:—*To determine the specific heat of the different organs of the body.*—Only a few observations have been made. The **mean specific heat** of the following animal parts (water = 1) is:—

Human blood = 1.02 (?)	Human muscle = 0.741	Fat tissue = 0.712
Arterial blood = 1.031 (?)	Ox muscle = 0.787	Striped muscle = 0.825
Venous blood = 0.892 (?)	Compact bone = 0.3	Defibrinated blood = 0.927
Cow's milk = 0.992	Spongy bone = 0.71	(*J. Rosenthal.*)

The specific heat of the *human body,* as a whole, is about that of an equal volume of water (?).

Kopp's Method.—The *solid* to be investigated is broken in pieces about the size of a pea, and placed in a test-tube, A, with thin walls, which is closed above with a cork, from which a copper wire with a hook on it projects (Fig. 231). The test-tube contains a certain quantity of fluid which does not dissolve the substance, but which lies between its pieces and covers it. It is weighed three times to ascertain the weight (1) of the empty glass, (2) after it is filled with the solid substance, (3) after the fluid is added, so that we obtain the weight of the solid substance, m, and that of the fluid, f. The test-tube and its contents are placed in a *mercury bath*, BB, and this again in an *oil bath*, CC, and the whole is raised to a high temperature. Into BB there is introduced a fine thermometer, T. When the tube, A, has reached the necessary temperature (say 40°), it is rapidly placed in the water of the accompanying calorimeter box, DD. The water in this box, which also contains a thermometer, D, is kept in motion until it has completely absorbed all the heat given off by A. Let T represent the temperature to which A and its contents were raised in the mercury bath, and T_1 the temperature to which it fell in the calorimeter; let s be the specific heat, and m the weight of the solid substance in the test-tube, while σ and μ represent the specific heat of the weight of the interstitial fluid in the test-tube; and lastly, let w equal the amount of water in contact with A, which absorbs and gives off heat; then W represents the amount of heat which the test-tube and its contents give off during cooling.

FIG. 231.



Kopp's apparatus for estimating specific heat.

$$W = (s \,.\, m + w + \sigma\,\mu)\,(T - T_1).$$

The amount of heat, W_1, absorbed by the calorimeter is

$$W_1 = M\,(t_1 - t),$$

where M represents the amount of water in the calorimeter, t the original temperature of the water in the calorimeter, and t_1 the temperature to which it is raised by placing A in it. If W and W_1 are equal, then

$$\textit{the specific heat, } s = \frac{M\,(t_1 - t) - (w + \sigma\,.\,\mu)\,(T - T_1)}{m\,(T - T_1)}.$$

If a fluid substance is placed in the test-tube, and its weight $= m$, and its specific heat $= s$, the formula for the specific heat of the fluid to be investigated is

$$s = \frac{M\,(t_1 - t) - w\,(T - T_1)}{m\,(T - T_1)}.$$

II. Calorimetry is more important for determining the amount of heat produced in a given time by the body as a whole, or by its *individual parts*.

Lavoisier and Laplace made the first calorimetric observations on animals in 1783, by means of an ice calorimeter; a guinea pig melted 13 oz. of ice in ten hours. Crawford, and afterward Dulong and Despretz, used Rumford's water calorimeter, which is similar to Favre and Silbermann's. Small animals are placed in the inner thin-walled copper chamber (K), which is placed in a water bath surrounded on all sides by some non-conducting material. We require to know the amount of water, and its original temperature. The number of calories is obtained from the increase of the temperature at the end of the experiment, which lasts several hours. The air is supplied to the animal through a special apparatus, resembling a gasometer. The amount of CO_2 in the gases evolved is estimated.

According to Despretz, a bitch forms 14,610 heat units per hour—*i.e.*, 393,000 in twenty-four hours. Other things being equal, a man seven times heavier than this would produce in twenty-four hours about 2,750,000 calories. Senator found that a dog weighing 6330 grms. produced 15,370 calories, and excreted at the same time 367 grms. CO_2. The first calorimetric experiments on man were made by Scharling (1849). Liebermeister estimated the amount of heat given off by a man placed in a cold bath, which was surrounded with a woolen covering. Leyden

placed a lower limb in the calorimeter, whereby 6000 grms. water were raised 1° C. in an hour. If we assume that the total superficial area of the body is fifteen times greater than that of the leg, the human body would produce 2,376,000 calories in twenty-four hours.

212. **THERMAL CONDUCTIVITY OF TISSUES.**—The thermal conductivity of animal tissues is of special interest in connection with the skin and subcutaneous fatty tissue. The fatty layer under the skin, more especially in the whale, walrus, and seal, forms a protective covering, whereby the conduction of heat from internal organs is rendered almost impossible. Investigations upon this subject, however, are few. Griess attempted to estimate the thermal conductivity by heating one part of the tissue, and determining when and in what direction pieces of wax placed on the tissue to be investigated began to melt. He investigated the stomach of the sheep, the bladder, skin, hoof, horn, and bones of an ox, deer's horn, ivory, mother-of-pearl, shell of haliotis. He found that fibrous tissues conducted heat more readily in the direction of their fibres than at right angles to the course of the fibres. Hence, the figures obtained from the melted wax were usually elliptical. Landois has made similar observations, and he finds that tissues conduct better in the direction of their fibres. After bones, blood clot was the best conductor, then followed spleen, liver, cartilage, tendon, muscle, elastic tissue, nail and hair, bloodless skin, gastric mucous membrane, washed fibrin. It is specially interesting to note how much better skin containing *blood* in its blood vessels conducts than does bloodless skin. Hence little heat is given off from a bloodless skin, while congested skin conducts and gives off much more heat.

Like all other substances, the human body is enlarged by heat. A man weighing 60 kilos., and whose temperature is raised from 37° C. to 40° C., is enlarged about 62 cubic centimetres. Connective tissue (tendon) is extended by heat, while elastic tissue and the skin, like caoutchouc, are contracted.

213. **VARIATIONS OF THE MEAN TEMPERATURE.**—(1) **General Climatic and Somatic Influences.**—In the **tropics** the mean temperature of the body is about ½° C. higher than in **temperate climates**, where again it is several tenths of a degree warmer than in **cold climates**; but this has recently been denied. The difference is comparatively trivial, when we remember that a man is subjected to a variation of over 40° C. in passing from the equator to the poles. Observations on more than 4000 persons show that when a person goes from a warm to a cold climate, his temperature is but slightly diminished, but when he goes from a cold to a warm climate his temperature rises relatively considerably more. In the *temperate* zone, the temperature of the body during a *cold winter* is usually 0.1° to 0.3° C. lower than it is on a warm summer day. The **elevation of a place** above sea level has no obvious effect on the temperature of the body. There seems to be no difference in different **races**, nor in the **sexes**, other conditions being the same. Persons of powerful physique and **constitution** are said to have generally a slightly higher temperature than feeble, weak, anæmic persons.

(2) **Influence of the General Metabolism.**—As the formation of heat depends upon the transformation of chemical compounds, whose chief final products in addition to H_2O, are CO_2 and urea, the amount of heat formed must go *pari passu* with the amount of these excreta. The more rapid metabolism which sets in after a full meal, causes a rise of temperature to several tenths of a degree ("Digestion fever"). As the metabolism is much diminished during **hunger**, this explains why the mean temperature in a fasting man is 36.6°, while it is 37.17° on ordinary days (§ 237).

Jürgensen also found that the temperature fell on the first day of inanition (although there was a temporary rise on the second day). In experiments made upon starving animals, the temperature at first fell rapidly, then remained constant for a considerable time, while during the last days it fell considerably. Schmidt starved a cat—on the 15th day the temperature was 38.6°; on the 16th, 38.3°; 17th, 37.64; 18th, 35.8; 19th (death) = 33.0°. Chossat found that starving mammals and birds had a temperature 16° C. below normal on the day of their death.

(3) **Age** has a decided effect upon the temperature of the body. The extent of the general metabolism is in part an index of the heat of the body at different ages, but it is possible that other, as yet unknown, influences are also active.

Age.	Mean Temperature at the Ordinary Temperature.	Normal Limits.	Where Measured.
Newly-born,	37.45° C.	37.35–37.55° C.	Rectum.
5–9 year,	37.72	36.87–37.62	Mouth and Rectum.
15–20 "	37.37	36.12–38.1	Axilla.
21–30 "	37.22	. .	"
25–30 "	36.91	. .	"
31–40 "	37.1	36.25–37.5	"
41–50 "	36.87	. .	"
51–60 "	36.83	. .	"
80 "	37.46	. .	Mouth.

Newly-born animals exhibit peculiarities owing to the sudden change in their conditions of existence. Immediately after birth, the infant is 0.3° warmer than the vagina of the mother, viz., 37.86°. A short time after birth, the temperature falls 0.9°, while twelve to twenty-four hours afterward it has risen to the normal temperature of an infant, which is 37.45°. Several irregular variations occur during the first weeks of life. During sleep, the temperature of an infant falls 0.34° to 0.56°, while continued crying may raise it several tenths of a degree. **Old people,** on account of their feeble metabolism, produce little heat; they become cold sooner, and hence ought to wear warm clothing to keep up their temperature.

(4) **Periodical Daily Variations.**—In the course of twenty-four hours there are regular periodic variations in the mean temperature, and these occur at all ages. As a general rule, the temperature *continues to rise during the day* (maximum at 5 to 8 P.M.), while it continues to *fall during the night* (minimum 2 to 6 A.M.). The mean temperature occurs at the third hour after breakfast.

FIG. 232.



Variations of the daily temperature in health during twenty-four hours. L——, after Liebermeister; J——, after Jürgensen.

The mean height of all the temperatures taken during a day in a patient is called the **"daily mean,"** and according to Jaeger it is 37.13° in the rectum in health. A daily mean of more than 37.8° is a "fever temperature," while a mean under 37.0° C. is regarded as a "collapse temperature."

Time.	Bärensprung.	J. Davy.	Hallman.	Gierse.	Jürgensen.		Jäger.
Morning, 5	. .	. .	. .	. .	36.7	36.6	36.9
6	36.68	. .	. .	. .	36.7	36.4	37.1
7	. .	36.94*	36.63	36.98	36.7*	36.5*	37.5*
8	37.16*	. .	36.80*	37.08*	36.8	36.7	37.4
9	. .	36.89	. .	. .	36.9	36.8	37.5
10	37.26	. .	10½ = 37.36	37.23	37.0	37.0	37.5
11	. .	36.89	. .	. .	37.2	37.2	37.3
Mid-day, 12	36.87	. .	. .	. .	37.3*	37.3*	37.5*
1	36.83	. .	37.21	37.13	37.3	37.3	37.4
2	. .	37.05	. .	37.50*	37.4	37.4	37.5
3	37.15*	. .	. .	37.43	37.4*	37.3*	37.5
4	. .	37.17	. .	. .	37.4	37.3	37.5*
5	37.48	37.05*	5½ = 37.31	37.43	37.5	37.5	37 5
6	. .	6½ = 36.83	. .	37.29	37.5	37.6	37.4
7	37.43	7½ = 36.50*	37.31*	. .	37.5*	37.6*	37.3
8	. .	. .	. .	. .	37.4	37.7	37.1*
9	37.02*	. .	. .	. .	37.4	37.5	36.9
10	. .	. .	. .	37.29	37.3	37.4	36.8
11	36.85	36.72	36.70	36.81	37.2	37.1	36.8
Night, 12	. .	. .	. .	. .	37.1	36.9	36 9
1	36.65	36.44	. .	. .	37.0	36.9	36.9
2	. .	. .	. .	. .	36 9	36.7	36.8
3	. .	. .	. .	. .	36.8	36.7	36.7
4	36.31	. .	. .	. .	36 7	36.7	36.7

As the variations occur when a person is **starved** for a day—although those that occur at the periods at which food ought to have been taken are less—it is obvious that the variations are not due entirely to the taking of food. [The * indicates taking of food.]

The daily variation in the **frequency of the pulse** often coincides with variation of the temperature. Bärensprung found that the mid-day temperature maximum slightly preceded the pulse maximum (§ 70, 3, C).

If we sleep during the day, and do all our daily duties during the night, the above described typical course of the temperature is reversed. With regard to the effect of activity or rest, it appears that the activity of the muscles during the day tends to increase the mean temperature slightly, while at night the mean temperature is less than in the case of a person at rest.

The **peripheral parts** of the body exhibit more or less regular variations of their temperature. In the **palm** of the hand, the progress of events is the following: After a relatively high night temperature there is a rapid fall at 6 A. M., which reaches its minimum at 9 to 10 A. M. This is followed by a slow rise, which reaches a high maximum after dinner; it falls between 1 to 3 P. M., and after two or three hours reaches a minimum. It rises from 6 to 8 P. M., and falls again toward morning. A rapid fall of the temperature in a peripheral part corresponds to a rise of temperature in internal parts.

(5) **Many operations** upon the body affect the temperature. After **hemorrhage** the temperature falls at first, but it rises again several tenths of a degree, and is usually accompanied by a shiver or slight rigor: several days thereafter it falls to normal, and may even fall somewhat below it. The sudden loss of a large amount of blood causes a fall of the temperature of ½ to 2° C. Very long-continued hemorrhage (dog) causes it to fall to 31° or 29° C.

This is obviously due to the diminution of the processes of oxidation in the anæmic body, and to the enfeebled circulation. Similar conditions causing diminished metabolism effect the same result. Continued stimulation of the peripheral end of the vagus, so that the heart's action is enormously slowed, diminishes the temperature several degrees in rabbits (*Landois and Ammon*).

The **transfusion** of a considerable quantity of blood raises the temperature about half an hour after the operation. This gradually passes into a febrile attack, which disappears within several hours. When blood is transfused from an artery to a vein of the same animal, a similar result occurs (§ 102).

(6) Many **poisons** diminish the temperature, *e. g.*, chloroform and the anæsthetics, **alcohol** (§ 235), digitalis, **quinine**, aconitin, muscarin. These appear to act partly by rendering *the tissues less liable to undergo molecular transformations* for the production of heat. In the case of the anæsthetics, this effect perhaps occurs, and is due possibly to a semi-coagulation of the nervous substance (?). They may also act partly by influencing the **giving off of heat** (§ 214, II). Other poisons increase the temperature for opposite reasons.

The temperature is **increased** by **strychnin**, nicotin, picrotoxin, veratrin, laudanin.

(7) Various **diseases diminish** the temperature, which may be due either to lessened production of heat (diminution of the metabolism), or to increased expenditure of heat. Loewenhardt found that in paralytics and in insane persons, several weeks before their death, the rectal temperature was 30° to 31° C., in diabetes 30° C., or less; the lowest temperature observed and life retained in a drunk person was 24° C.

The temperature is **increased** in *fever*, and the highest point reached just before death, and recorded by Wunderlich, was 44.65° C. (compare § 220).

214. REGULATION OF THE TEMPERATURE.—As the bodily temperature of man and similar animals is **nearly constant**, notwithstanding great variations in the temperature of their surroundings, it is clear that some mechanism must exist in the body, whereby the heat economy is **constantly regulated**. This may be brought about in **two ways**; either by controlling the transformation of potential energy into heat, or by affecting the amount of heat given off according to the amount produced, or to the action of external agencies.

[The constancy or thermostatic condition of the temperature is brought about by three co-operant factors, the **thermogenic** or heat producing, the **thermolytic** or heat discharging, and the **thermotaxic** or mechanism by which heat production and heat loss are balanced, and it is obvious that the last must be in relation with the other two. The thermotaxic mechanism is developed last, is least pronounced in the lower vertebrata, and is most *easily* liable to fail under injury or disease (*MacAlister*).]

I. Regulatory Arrangements governing the production of Heat.—Liebermeister estimated the amount of heat produced by a healthy man at 1.8 calorie per minute. It is highly probably that, within the body, there exist mechanisms which determine the molecular transformations upon which the evolution of heat depends. This is accomplished chiefly in a **reflex manner.** The peripheral ends of cutaneous nerves (by thermal stimulation), or the nerves of the intestine and the digestive glands (by mechanical or chemical stimulation during digestion or inanition), may be irritated, whereby impressions are conveyed to the **heat centre**, which sends out impulses through efferent fibres to the depôts of potential energy, either to increase or diminish the extent of the transformations occurring in them. The nerve channels herein concerned are entirely unknown. Many considerations, however, go to support such an hypothesis (§ 377).

[**Thermotaxic Mechanism, Thermal Nerves and Centres.**—Just as the respiration and the state of the blood vessels are regulated from a central focus, so the question arises, does the same obtain with regard to temperature? Studying this question, however, it must be borne in mind that thermometric observations alone are not sufficient; the true test must be calorimetric. Sir Benjamin Brodie observed that in a case of injury of the spinal cord in the neck the temperature in the thigh rose very high. In some cases the temperature falls. Wood has shown that section of the cord above the origin of the splanchnics leads to decided increase in the amount of heat dissipated, but to a decided diminution of heat production. The vasomotor paralysis has much to do in these cases with the loss of heat. In warm-blooded animals, exposed to a high temperature, the heat production is diminished, but when they are exposed to a low temperature it is increased. If a warm-blooded animal's medulla oblongata be divided, there is a fall of temperature, chiefly due to its vasomotor paralysis, and such an animal behaves, as regards the effect of heat and cold, exactly like a poikilothermal animal, *i.e.*, its metabolism and heat production are increased by cold and diminished by heat. If, however, the incision be made above the pons, so as to leave the vasomotor centre intact in the dog, there is a rise of the temperature and increased heat production for 24 hours afterward.

This suggests the idea that this region is traversed by inhibitory nerves, so that when they are cut off from their centres situate above, the augmentor nerves can act more vigorously. This suggests the existence of thermo-inhibitory centres situate higher up in the brain. If an animal be curarized, not only is there paralysis of voluntary motor acts, but on stimulating an ordinary motor nerve, not only is there no muscular contraction, but there is no rise of temperature of the muscles supplied by that nerve. In such an animal the temperature rises and falls with the temperature of the surrounding medium. Even although the respirations be kept constant and the vasomotor nerves intact, the thermogenic activity of muscles, therefore, seems to be dependent on their innervation.]

[**Cerebral Centres.**—Apart from the cortical heat centres (§ 377), Ott, Aronsohn, Sachs, Richet and others have shown that if a needle be thrust through the skull and brain, so as to injure certain deeper-seated parts, there is a rise of temperature and increased heat production for several hours. The experiment may be repeated several times in the same rabbit. Ott gives three areas which, when so injured, cause these effects: (1) a part of the brain in the median side of the corpus striatum, and near the nodus cursorius; (2) a part between the corpus striatum and the optic thalamus; and (3) the anterior end of the optic thalamus itself. From the effect of atropin, Ott suggests the existence of spinal centres as well.]

The following phenomena indicate the existence of mechanisms regulating the production of heat:—

(1) The temporary application of *moderate cold raises the bodily temperature*, while heat, similarly applied to the external surface, lowers it (§§ 222 and 224).

(2) Cooling of the surroundings increases the amount of CO_2 excreted, by increasing the production of heat, while the O consumed is also increased simultaneously; heating the surrounding medium diminishes the CO_2 (§ 127, 5).

D. Finkler found, from experiments upon guinea pigs, that the production of heat was more than doubled when the surrounding temperature was diminished 24° C. The metabolism of the guinea pig is increased in winter 23 per cent. as compared with summer, so that the same relation obtains as in the case of a diminution of the surrounding temperature of short duration.

C. Ludwig and Sanders-Ezn found that in a rabbit there was a rapid increase in the amount of CO_2 given off, when the surroundings were cooled from 38° to 6° or 7° C.; while the excretion was diminished when the surrounding temperature was raised from 4°–9° to 35°–37°, so that the thermal stimulation, due to the temperature of the surrounding medium, acted upon the combustion within the body. Pflüger found that a rabbit which was dipped in cold water used more O and excreted more CO_2.

If the cooling action was so great as to reduce the *bodily* temperature to 30°, the exchange of gases diminished, and where the temperature fell to 20°, the exchange of gases was diminished one-half. It is to be remembered, however, that the *excretion of* CO_2 does not go hand in hand with the formation of CO_2. If mammals be placed in a *warm* bath which is 2° to 3° higher than their own temperature, the excretion of CO_2 and the consumption of O are increased, owing to the stimulation of their metabolism, while the excretion of urea is also increased in animals and in man (§ 133, 5).

(3) **Cold** acting upon the skin causes **involuntary muscular movements** (shivering, rigors), and also **voluntary movements**, both of which produce heat.

The cold excites the action of the muscles, which is connected with processes of oxidation (*Pflüger*). After poisoning with **curara**, which paralyzes voluntary motion, this regulation of the heat falls to a minimum (*Röhrig* and *Zuntz*), [while the bodily temperature rises and falls with a rise or fall in the temperature of the surrounding medium].

(4) Variations in the **temperature of the surroundings** affect the **appetite for food**; in winter, and in cold regions, the sensation for hunger and the appetite for the fats, or such substances as yield much heat when they are oxidized, are increased; in summer and in hot climates, they are diminished. Thus the mean temperature of the surroundings, to a certain extent, determines the amount of the heat-producing substances to be taken in the food.

II. Regulatory Mechanisms governing the Excretion of Heat or Thermolysis.—The mean amount of heat given off by the human skin in twenty-four hours, by a man weighing 82 kilos., is 2092 to 2592 calories, *i.e.*, 1.36 to 1.60 per minute.

(1) **Heat** causes **dilatation of the cutaneous vessels**; the skin becomes red, congested, and soft; it contains more fluids, and becomes a better conductor of heat; the epithelium is moistened, and **sweat** appears on the surface. Thus

increased excretion of heat is provided for, while the evaporation of the sweat also abstracts heat.

The amount of heat necessary to convert into vapor 1 grm. of water at 100° C., is equal to that required to heat 10 grms. from 0° to 53.67° C. The sweat as secreted is at the temperature of the body; if it were completely changed into vapor, it would require the heat necessary to raise it to the boiling point, and also that necessary to convert it into vapor.

Cold causes contraction of the cutaneous vessels; the skin becomes pale, less soft, poorer in juices, and collapsed; the epithelium becomes dry, and does not permit fluids to pass through it to be evaporated, so that the excretion of heat is diminished. The *excretion of heat* from the periphery, and the transverse *thermal conduction* through the skin, are diminished by the contraction of the vessels and muscles of the skin, and by the expulsion of the well-conducting blood from the cutaneous and subcutaneous vessels. The cooling of the body is very much affected, owing to the diminution of the cutaneous blood stream, just as occurs when the current through a coil or worm of a distillation apparatus is greatly diminished. If the blood vessels dilate, the temperature of the surface of the body rises, the difference of temperature between it and the surrounding cooler medium is increased, and thus the excretion of heat is increased. Tomsa has shown that the fibres of the skin are so arranged anatomically, that the tension of the fibres produced by the erector pili muscles causes a diminution in the thickness of the skin, this result being brought about at the expense of the easily expelled blood.

By the systematic application of stimuli, *e.g.*, **cold baths**, and washing with cold water, the muscles of the skin and its blood vessels may be caused to contract, and become so vigorous and excitable, that when cold is suddenly applied to the body, or to a part of it, the excretion of heat is energetically prevented, so that cold baths and washing with cold water are, to a certain extent, "gymnastics of the cutaneous muscles," which, under the above circumstances, protect the body from cold.

(2) **Increased temperature causes increased heart beats**, while **diminished temperature diminishes** the **number** of contractions of the heart (§ 58, II, *a*). The relatively warm blood is pumped by the action of the heart from the internal organs of the body to the surface of the skin, where it readily gives off heat. The more frequently the same volume of blood passes through the skin—twenty-seven heart beats being necessary for the complete circuit of the blood—the greater will be the amount of heat given off, and conversely. Hence, the frequency of the heart beat is in direct relation to the rapidity of cooling. In very hot air (over 100° C.) the pulse rises to over 160 per minute. The same is true in fever (§ 70, 3 *c*.). Liebermeister gives the following numbers in an adult:—

Pulse beats, per min., . . .	78.6	91.2	99.8	108.5	110	137.5
Temperature in C°., . . .	37°	38°	39°	40°	41°	42°

(3) **Increased Temperature Increases the Number of Respirations.**—Under ordinary circumstances, a much larger volume of air passes through the lungs when it is warmed almost to the temperature of the body. Further, a certain amount of watery vapor is given off with each expiration, which must be evaporated, thus abstracting heat. Energetic respiration aids the circulation, so that respiration acts indirectly in the same way as (2). According to other observers, the increased consumption of O favors the combustion in the body, whereby the increased respiration must act in producing an amount of heat greater than normal (§ 127, 8). This excess is more than compensated for by the cooling factors above mentioned. Forced respiration produces cooling, even when the air breathed is heated to 54° C., and saturated with watery vapor.

(4) **Covering of the Body.**—Animals become clothed in winter with a winter fur or covering, while in summer their covering is lighter, so that the excretion of heat in surroundings of different temperatures is thereby rendered more constant.

Many animals which live in very cold air or water (whale) are protected from

too rapid excretion of heat by a *thick layer of fat* under the skin. Man provides for a similar result by adopting summer and winter clothing.

(5) The **position of the body** is also important; pulling the parts of the body together, approximation of the head and limbs, keep in the heat; spreading out the limbs, erection of the hairs, pluming the feathers, allow more heat to be evolved. If a rabbit be kept exposed to the air with its legs extended for three hours, the rectal temperature will fall from 39° C. to 37° C. Man may influence his temperature by remaining in a warm or a cold room—by taking hot or cold drinks—hot or cold baths—remaining in air at rest or air in motion, *e. g.*, by using a fan.

CLOTHING.—Warm Clothing is the Equivalent of Food.—As clothes are intended to keep in the heat of the body, and heat is produced by the combustion and oxidation of the food, we may say the body takes in heat directly in the food, while clothing prevents it from giving off too much heat. Summer clothes weigh 3 to 4 kilos., and winter ones 6 to 7 kilos.

In connection with clothes, the following considerations are of importance:—

(1) *Their capacity for conduction.*—Those substances which conduct heat badly keep us warmest. Hare skin, down, beaver skin, raw silk, taffeta, sheeps' wool, cotton wool, flax, spun silk, are given in order, from the worst to the best conductors. (2) The *capacity for radiation.*—Coarse materials radiate more heat than smooth, but color has no effect. (3) *Relation to the sun's rays.*—Dark materials absorb more heat than light-colored ones. (4) Their *hygroscopic properties* are important, whether they can absorb much moisture from the skin and gradually give it off by evaporation, or the reverse. The same weight of wool takes up twice as much as linen; hence the latter gives it off in evaporation more rapidly. Flannel next the skin is not so easily moistened, nor does it so rapidly become cold by evaporation; hence it protects against the action of cold. (5) The *permeability for air* is of importance, but does not stand in relation with the heat-conducting capacity, The following substances are arranged in order from the most to the least permeable—flannel, buckskin, linen, silk, leather, wax cloth.

215. HEAT BALANCE.—As the temperature of the body is maintained within narrow limits, the amount of heat taken in must balance the heat given off, *i. e.*, exactly the same amount of potential energy must be transformed in a given time into heat, as heat is given off from the body. An adult produces as much heat in half an hour as will raise the temperature of his body 1° C. If no heat were given off, the body would become very hot in a short time; it would reach the boiling point in thirty-six hours, supposing the production of heat continued uninterruptedly. The following are the most important calculations on the subject:—

A. Helmholtz was the first to estimate numerically the amount of heat produced by a man:—

(1) **Heat Income.**—(*a*) A healthy adult, weighing 82 kilos., expires in twenty-four hours 878.4 grms. CO_2 (*Scharling*). The combustion of the C therein into CO_2 produces . . . . . 1,730,760 cal.

(*b*) But he takes in more O than reappears in the CO_2; the excess is used in oxidation processes, *e. g.*, for the formation of H_2O, by union with H, so that 13,615 grms. H will be oxidized by the excess of O, which gives 318,000 "

2,049,360 "

(*c*) About 25 per cent. of the heat must be referred to sources other than combustion (*Dulong*), so that the total . . . . . = 2,732,000 "

2,732,000 calories are actually sufficient to raise the temperature of an adult, weighing 80 to 90 kilos., from 10° to 38° or 39° C., *i. e.*, to a normal temperature.

(2) **Heat Expenditure.**—(*a*) Heating the food and drink, which have a mean temperature of 12° C. . . . . 70,157 cal. = 2.6 per cent.

(*b*) Heating the air respired = 16,400 grms. with an initial temperature of 20° C. . . . . 70,032 " = 2.6 "

(*When the temperature of the air is* 0°, 140,064 *cal.* = 5.2 *per cent.*)

(*c*) Evaporation of 656 grms. water by the lungs, ... 397,536 " = 14.7 "

(*d*) The remainder given off by radiation and evaporation of water by the skin, ... (77.5 *per cent. to*) = 81.1 "

B. Dulong.—(1) **Heat Income.**—Dulong and others sought to estimate the amount of heat from the C and H contained in the food. As we know that the combustion of 1 grm. C = 8040 heat units, and 1 grm. H = 34,460 heat units, it would be easy to determine the amount of heat were the C simply converted into CO_2 and the H into H_2O. But Dulong omitted the H in the carbohydrates (*e. g.*, grape sugar = $C_6H_{12}O_6$) as producing heat, because the H is already combined with O, or at least is the proportion in which it exists in water. This assumption is hypothetical, for the atoms of C in a carbohydrate may be so firmly united to the other atoms, that before oxidation can take place their relations must be altered, so that potential energy is used up, *i. e.*, heat must be rendered latent; so that these considerations rendered the following example of Dulong's method given by Vierordt very problematical:—

An adult eats in twenty-four hours, 120 grms. proteids, 90 grms. fat, and 340 grms. starch (carbohydrates). These contain:—

Proteids,	120 grms.	contain	64.18	C. and	8.60	H.
Fat,	90 "	"	70.20	"	10.26	
Starch,	330 "	"	146.82		. .	
			281.20	and	18.86	
The urine and fæces contain still unconsumed,			29.8	"	6.3	
Remainder to be burned,			251.4	"	12.56	

As 1 grm. C. = 8040 heat units and 1 grm. H = 34,460 heat units, we have the following calculation:—

251.4 × 8,040 = 2,031,312 (from combustion of C).
12.56 × 34,460 = 432,818 (" " H),

2,464,130 heat units.

(2) **Heat Expenditure:**—

	Heat units.	Per cent. of the excreta.
1. 1900 grms. are excreted daily by the urine and fæces, and they are 25° warmer than the food,	47,500	1.9
2. 13,000 grms, air are heated (from 12° to 37° C.) (heat capacity of the air = 0.26),	184,500	3.38
3. 330 grms. water are evaporated by the respiration (1 grm. = 582 heat units),	192,060	7.68
4. 660 grms, water are evaporated from the skin,	384,120	15.37
Total,	708,180	
Remainder radiated and conducted from the skin,	1,791,820	71.67
Total amount of heat units given off,	2,500,000	100.00

C. Heat Income.—Frankland burned the food directly in a calorimeter, and found that 1 grm. of the following substances yielded:—

Albumin, 1 grm., ... 4998 heat units.
Grape sugar, 1 grm., ... 3217 "
Ox fat, 1 grm., ... 9069 "

The albumin, however, is only oxidized to the stage of urea, hence the heat units of urea must be deducted from 4998, which gives 4263 heat units obtainable from 1 grm. albumin. When we know the number of grammes consumed, a simple multiplication gives the number of heat units.

The heat units will vary, of course, with the nature of the food. J. Ranke gives the following:—

With **animal diet**, ... 2,779,524 heat units.
" **food free from N**, ... 2,059,506 "
" **mixed diet**, ... 2,200,000 "
" **during hunger**, ... 2,012,816 "

216. VARIATIONS IN HEAT PRODUCTION.—(1) **Influence of Bodily Surface.**—Rubner found that the production of heat depended more upon the size of the body and its superficial area than upon the body weight. Small or young animals have a relatively larger surface than large or older ones, and as the removal of the heat takes place chiefly from the external surface, animals with a larger surface must produce more heat. Small animals used relatively more O. Rubner's investigations on dogs of different size gave a heat production of 1,143,000 calories for every square metre of cutaneous surface. On comparing the body weight with the cutaneous surface in different animals, he found that for every 1 kilo. of body weight there was in the rat 1650, rabbit 946, man 287 square centimetres of surface.

(2) **Age and Sex.**—The heat production is less in infancy and in old age, and it is less in proportion in the female than in the male.

(3) **Daily Variation.**—The heat production shows variations in twenty-four hours corresponding with the temperature of the body (§ 213, 4).

(4) The heat production is greater in the **waking** condition, during physical and mental **exertion**, and during **digestion**, than in the opposite conditions.

217. RELATION OF HEAT PRODUCTION TO WORK.—The potential energy supplied to the body may be transformed into **heat** and **kinetic energy** (see *Introduction*). In the resting condition, almost all the potential energy is changed to heat; the workman, however, transforms potential energy into **work**—mechanical work—in addition to heat. These two may be compared by using an equivalent measurement, thus, 1 **heat unit** (energy required to raise 1 gramme of water 1° C.) = 425.5 gramme-metres.

Relation of Heat to Work.—The following example may serve to illustrate the relation between heat production and the production of work: Suppose a small steam engine to be placed within a capacious calorimeter, and a certain quantity of coal to be burned, then as long as the engine does not perform any mechanical work, heat alone is produced by the burning of the coal. Let this amount of heat be estimated, and a second experiment made by burning the same amount of coal, but allow the engine to do a certain amount of work—say, raise a weight—by a suitable arrangement. This work must, of course, be accomplished by the potential energy of the heating material. At the end of this experiment, the temperature of the water will be much less than in the first experiment, *i. e.*, fewer heat units have been transferred to the calorimeter when the engine was heated than when it did no work. Comparative experiments of this nature have shown that in the second experiment, the useful work is very nearly proportional to the decrease of the heat (*Hirn*).

Compare this with what happens within the body: A man in a **passive condition** forms from the potential energy of the food between 2½ to 2¾ million calories. The **work done** by a workman is reckoned at 300,000 kilogramme-metres (§ 300).

If the organism were precisely similar to a machine, a smaller amount of heat, corresponding to the work done, would be formed in the body. As a matter of fact, the organism produces less heat from the same amount of potential energy when mechanical work is done. There is one point of difference between a workman and a working machine. The workman consumes much more potential energy in the same time than a passive person; much more is transformed in his body; and hence the increased consumption is not only covered, but even overcompensated. Hence, the workman is warmer than the passive person, owing to the increased muscular activity (§ 210, 1, *b*). Take an example: Hirn remained *passive*, and absorbed 30 grms. O per hour in a calorimeter, and produced 155 calories. When in the calorimeter he did work equal to 27,450 kilogramme-metres, which was transferred beyond it; he absorbed 132 grms. O, and produced only 251 calories.

In estimating the work done, we must include only the heat equivalent of the work transferred beyond the body; lifting weights, pushing anything, throwing a weight, and lifting the body are examples. In ordinary walking we must take into account that we overcome the resistance of the air and the activity of the muscles.

The organism is superior to a machine in as far as it can, from the same amount of potential energy, produce more work in proportion to heat. While the very best steam engine gives ⅛ of the potential energy in the form of work, and ⅞ as heat, the body produces ⅕ as work and ⅘ as heat. *Chemical energy* can never do work alone, in a living or dead motor, without heat being formed at the same time.

218. ACCOMMODATION FOR VARYING TEMPERATURES.—All substances which possess high conductivity for heat, when brought into contact with the skin, appear to be very much colder or hotter than bad conductors of heat. The reason of this is that these bodies abstract far more heat, or conduct more heat than other bodies. Thus the water of a cool bath, being a better

conductor of heat, is always thought to be colder than air at the same temperature. In our climate it appears to us that—

Air, at 18° C. is moderately warm;	**Water**, at 18° C. is cold;
" at 25°–28° C., hot;	" from 18°–29° C., cool;
" above 28°, very hot.	" " 29°–30° C., warm;
	" " 37.5° and above, hot.

Warm Media.—As long as the temperature of the body is higher than that of the surrounding medium, heat is given off, and that the more rapidly the better the conducting power of the surrounding medium. As soon as the temperature of the surrounding medium rises higher than the temperature of the body, the latter absorbs heat, and it does so the more rapidly the better the conducting power of the medium. Hence, hot water appears to be warmer than air at the same temperature. A person may remain eight minutes in a **bath** at 45.5° C. (dangerous to life!); the hands may be plunged into water at 50.5° C., but not at 51.65° C., while at 60° violent pain is produced.

A person may remain for eight minutes in **hot air** at 127° C., and a temperature of 132° C. has been borne for ten minutes, and yet the body temperature rise only to 38.6° or 38.9°. This depends upon the air being a bad conductor, and thus it gives less heat to the body than water would do. Further, and what is more important, the skin becomes covered with sweat, which evaporates and abstracts heat, while the lungs also give off more watery vapor. The enormously increased heart-beats—over 160—and the *dilated blood vessels*, enable the skin to obtain an ample supply of blood for the formation and evaporation of sweat. In proportion as the secretion diminishes, the body becomes unable to endure a hot atmosphere; hence it is that in *air containing much watery vapor* a person cannot endure nearly so high a temperature as in dry air, so that heat must accumulate in the body. In a Turkish vapor bath of 53° to 60° C., the rectal temperature rises to 40.7° or 41.6° C. A person may work continuously in air at 31° C. which is almost saturated with moisture.

If a person be placed in **water** at the temperature of the body, the normal temperature rises 1° C. in one hour, and in 1½ hour about 2° C. A gradual increase of the temperature from 38.6° to 40.2° C. causes the axillary temperature to rise to 39.0° within fifteen minutes.

219. **STORAGE OF HEAT.**—As the uniform temperature of the body, under normal circumstances, is due to the reciprocal relation between the amount of heat produced and the amount given off, it is clear that heat must be stored up in the body when the evolution of heat is diminished. **The skin is the chief organ regulating the evolution of heat**; when it and its blood vessels contract, the heat evolved is diminished, when they dilate it is increased. **Heat may be stored up** when—

(*a*) The *skin* is extensively *stimulated*, whereby the cutaneous vessels are temporarily contracted. (*b*) Any other circumstances prevent heat from being given off by the skin. (*c*) When the *vaso-motor centre is excited*, causing all the blood vessels of the body—those of the skin included—to contract. This seems to be the cause of the rise of temperature after transfusion of blood, and the rise of temperature after the *sudden removal of water* from the body seems to admit of a similar explanation, as the inspissated blood occupies less space, and the contracted vessels of the skin admit less blood. (*d*) When the circulation in the cutaneous vessels of a large area is mechanically slowed, or when the smaller vessels are plugged by the injection of some sticky substance, or by the transfusion of foreign blood, the temperature rises (§ 102).

It is also obvious that when a normal amount of heat is given off, an increased production of heat must raise the temperature. The rise of the temperature after muscular or mental exertion, and during digestion, seems to be caused in this way. The rise which occurs several hours after a cold bath is probably due to the reflex excitement of the skin causing an increased production (*Jürgensen*).

When the temperature of the body, as a whole is raised 6° C., death takes

place, as in sunstroke. It seems as if there was a molecular decomposition of the tissues at this temperature; while, if a slightly lower temperature be kept up *continuously*, fatty degeneration of many tissues occurs (*Litten*). If animals, which have been exposed artificially to a temperature of over 42° to 44° C., be transferred to a cooler atmosphere, their temperature becomes sub-normal (36° C.), and may remain so for several days.

220. **FEVER.**—Fever consists in a "*disorder of the body heat*" and at the same time there is greatly *increased tissue metabolism* (especially in the muscles). Of course the mechanism regulating the balance of formation and expenditure of heat is disturbed. During fever the body is greatly incapacitated for performing mechanical work. It is evident, therefore, that the large amount of potential energy transformed is almost all converted into heat, so that the non-transformation of the energy into mechanical work is another important factor. We may take intermittent fever or **ague** as a type of fever, in which violent attacks of fever of several hours' duration alternate with periods free from fever. This enables us to analyze the symptoms. The **symptoms** of fever are:—

(1) The **increased temperature** of the body (38° to 39° C., slight; from 39° to 41° C. and upward, severe). The high temperature occurs not only in cases where the skin is red, and has a hot burning feeling (calor mordax), but even during the rigor or the shivering stage, the temperature is raised. The congested red skin is a good conductor of heat, while the pale, bloodless skin conducts badly; hence the former feels hot to the touch (§ 212).

[The following table in ° C. and ° F. indicates generally the degree of fever:—

35° C.	= 95° F.	. . . .	Collapse.	39° C.	= 102.2° F. } Moderate fever.
36	= 96.8	. . . .	Low.	39.5	= 103.1 }
36.5	= 97.7	. . . .	Sub-normal.	40	= 104 } High fever.
37	= 98.6	. . . .	**Normal.**	40.5	= 104.9 }
37.5	= 99.5 }			41	= 105.8 Hyperpyretic.
38	= 100.4 }	. . . .	Sub-febrile.		*Finlayson.*]
38.5	= 101.3 }				

(2) The **increased production of heat** is proved by calorimetic observations. This is, in small part, due to the increased activity of the circulation being changed into heat (§ 206, 2, *a*), but for the most part it is due to increased combustion within the body.

(3) The **increased metabolism** gives rise to the "consuming" or "wasting" character of fever, which was known to Hippocrates and Galen. In 1852 v. Bärensprung asserted that "all the so-called febrile symptoms show that the metabolism is increased." The increase of the metabolism is shown in the increased *excretion of* CO_2 = 70 to 80 per cent., while more O is consumed, although the respiratory quotient remains the same. According to D. Finkler, the CO_2 excreted shows greater variations than the O consumed. The *excretion of urea* is increased $\frac{1}{3}$ to $\frac{2}{3}$. In dogs suffering from septic fever, Naunyn observed that the urea began to increase before the temperature rose, "*prefebrile rise.*" Part of the urea, however, is sometimes retained during the fever, and appears after the fever is over, "*epicritical excretion of urea.*" The *uric acid* is also *increased;* the *urine pigment* (§ 19), derived from the hæmoglobin, may be increased twenty times, while the excretion of *potash* may be sevenfold. It is important to observe that the oxidation or combustion processes within the body of the fever patient are greatly increased when he is placed in a *warmer* atmosphere. The oxidation processes in fever, however, are also increased under the influence of *cooler* surroundings (§ 214, I, 2), but the increase of the oxidation in a warm medium is very much greater than in the cold (*D. Finkler*). The amount of CO_2 in the blood is diminished, but not at once after the onset even of a very severe fever (*Geppert*).

(4) The **diminished excretion of heat** varies in different stages of a fever. We distinguish several **stages in a fever**—(*a*) The **cold stage**, when the loss of heat is greatly diminished, owing to the pale, bloodless skin, but at the same time the heat production is increased $1\frac{1}{2}$ to $2\frac{1}{2}$ times. The sudden and considerable rise of the temperature during this stage shows that the diminished excretion of heat is not the only cause of the rise of the temperature. (*b*) During the **hot stage** the *heat given off* from the congested red skin is *greatly increased*, but at the same time more heat is produced. Liebermeister assumes that a rise of 1, 2, 3, 4° C. corresponds to an increased production of heat of 6, 12, 18, 24 per cent. (*c*) In the **sweating stage** the excretion of heat through the red moist skin and evaporation are greatest, more than two or three times the normal. The heat production is either increased, normal, or sub-normal, so that under these conditions the temperature may also be sub-normal (36° C.).

(5) The **heat-regulating mechanism is injured.**—A warm temperature of the surroundings raises the temperature of the fever patient more than it does that of a non-febrile person. The depression of the heat production, which enables normal animals to maintain their normal temperature in a warm medium (§ 214), is much less in fever (*D. Finkler*).

The **accessory phenomena** of fever are very important: Increase in the intensity and number of heart beats (§ 214, II, 2) and respirations (in adults 40, and children 60 per min.), both being

compensatory phenomena of the increased temperature; further, diminished digestive activity and intestinal movements (§ 186, D); disturbances of the cerebral activities; of secretion; of muscular activity; slower excretion, *e.g.*, of potassium iodide through the urine. In severe fever, molecular degenerations of the tissues are very common. For the condition of the blood corpuscles in fever, see § 10, the vascular tension, § 69, the saliva, § 146, digestion, § 186.

Quinine, the most important febrifuge, causes a decrease of the temperature by limiting the production of heat (§ 213, 6). Toxic doses of the metallic salts act in the same way, while there is at the same time diminished formation of CO_2. [**Antipyretics** or **Febrifuges.**—All methods which diminish abnormal temperature belong to this group. As the constant temperature of the body depends on (1) the amount of heat production, and (2) the loss of heat, we may lower the temperature either in the one way or the other. When cold water is applied to the body, it abstracts heat, *i. e.*, it affects the results of fever, so that Liebermeister calls such methods **antithermic.** But those remedies which diminish the actual heat production are true **antipyretic.** In practice, however, both methods are usually employed, and spoken of collectively as antipyretics.]

[Among the methods which are used to abstract heat from the body, are the application of colder fluids, such as the cold bath, affusion, douche, spray, ice, or cold mixtures, etc. A person suffering from high fever requires to be repeatedly placed in a cold bath to produce any permanent reduction of the temperature. Some remedies act by favoring the radiation of heat, by dilating the cutaneous vessels (alcohol), while others excite the sweat glands—*i. e.*, are *sudorifics*—so that the water by its evaporation removes some heat. Among the drugs which influence tissue changes and oxidation, and thereby lessen heat production, are quinine, salicylic acid, some of the salicylates, digitalis, and veratrin. Bloodletting was formerly used to diminish abnormal temperature. Among the newer antipyretic remedies are hydrochlorate of kairin and antipyrin, both of which belong to the aromatic group (derivatives of benzol), which includes also many of our best antiseptics.]

221. ARTIFICIAL INCREASE OF THE BODILY TEMPERATURE.—If **mammals** are kept *constantly* in air at 40° C., the excretion of heat from the body ceases, so that the heat produced is stored up. At first the temperature falls somewhat for a very short time, but soon a decided increase occurs. The respirations and pulse are increased, while the latter becomes irregular and weaker. The O absorbed and CO_2 given off are diminished after six to eight hours, and death occurs after great fatigue, feebleness, spasms, secretion of saliva, and loss of consciousness, when the bodily temperature has been increased 4° or at most 6° C. Death does not take place owing to rigidity of the muscles, for the coagulation of the myosin of mammals' muscles occurs at 49° to 50° C., in birds at 53° C., and in frogs at 40° C. If mammals are *suddenly* placed in air at 100° C., death occurs (in 15 to 20 min.) very rapidly, and with the same phenomena, while the bodily temperature rises 4° to 5° C. In rabbits the body weight diminishes 1 grm. per min. Birds bear a high temperature somewhat longer; they die when their blood reaches 48° to 50° C.

Even **man** may remain for some time in air at 100–110–132° C., but in ten to fifteen minutes there is danger to life. The skin is burning to the touch, and red; a copious secretion of sweat bursts forth, and the cutaneous veins are fuller and redder. The pulse and respirations are greatly accelerated. Violent headache, vertigo, feebleness, and stupefaction, indicate great danger to life. The rectal temperature is only 1° to 2° C. higher. The high temperature of fever may even be dangerous to human life. If the temperature remains for any length of time at 42.5° C., death is almost certain to occur. Coagulation of the blood in the arteries is said to occur at 42.6° C. If the artificial heating *does not produce death*, fatty infiltration and degeneration of the liver, heart, kidneys, and muscles begin after thirty-six to forty-eight hours.

Cold-blooded animals, if placed in hot air or warm water, soon have their temperature raised 6 to 10° C. The highest temperature compatible with life in a frog must be below 40° C., as the frog's heart and muscles begin to coagulate at this temperature. Death is preceded by a stage resembling death, during which life may be saved.

Most of the **juicy plants** die in half an hour in air at 52° C., or in water at 46° C. (*Sachs*). Dried seeds of corn may still germinate after long exposure to air at 120° C. Lowly organized plants, such as algæ, may live in water at 60° C. (*Hoppe-Seyler*). Several bacteria withstand a boiling temperature (*Tyndall*).

222. EMPLOYMENT OF HEAT.—Action of Heat.—The short, but not intense, action of heat on the surface causes, in the first place, a transient slight decrease of the bodily temperature,

partly because it retards reflexly the production of heat, and partly because, owing to the dilatation of the cutaneous vessels and the stretching of the skin, more heat is given off. A warm bath above the temperature of the blood at once increases the bodily temperature.

Therapeutic Uses.—The application of heat to the entire body is used where the bodily temperature has fallen, or is likely to fall, very low, as in the algid stage of cholera, and in infants born prematurely. The *general* application of heat is obtained by use of warm baths, packing, vapor baths, and the copious use of hot drinks. The *local* application of heat is obtained by the use of warm wrappings, partial baths, plunging the parts in warm earth or sand, or placing wounded parts in chambers filled with heated air. After removal of the heating agent, care must be taken to prevent the great escape of heat due to the dilatation of the blood vessels.

223. **INCREASE OF TEMPERATURE POST-MORTEM.—Phenomena.**— Heidenhain found that in a dead dog, before the body cooled, there was a constant temporary rise of the temperature, which slightly exceeded the normal. The same observation had been occasionally made on human bodies immediately after death, especially when death was preceded by muscular spasms [also in yellow fever]. Thus, Wunderlich measured the temperature fifty-seven minutes after death in a case of tetanus, and found it to be 45.375° C.

Causes.—(1) *A temporary increased production of heat after death*, due chiefly to the change of the semi-solid myosin of the muscles into a solid form (rigor mortis). As the muscle coagulates, heat is produced. All conditions which cause rapid and intense coagulation of the muscles—*e. g.*, spasms, favor a *post-mortem* rise of temperature (see § 295); a rapid coagulation of the blood has a similar result (§ 28, 5).

(2) Immediately after death a series of *chemical processes* occur within the body, whereby heat is produced. Valentin placed a dead rabbit in a chamber, so that no heat could be given off from the body, and he found that the internal temperature of the animal's body was increased. The processes which cause a rise of temperature *post-mortem* are more active during the first than the second hour; and the higher the temperature at the moment of death, the greater is the amount of heat evolved after death.

(3) Another cause is the *diminished excretion of heat post-mortem*. After the circulation is abolished, within a few minutes little heat is given off from the surface of the body, as rapid excretion implies that the cutaneous vessels must be continually filled with warm blood.

224. **ACTION OF COLD ON THE BODY.—Phenomena.**—A short, temporary, slight cooling of the skin (removing one's clothes in a cool room, a cool bath for a short time, or a cool douche) causes either no change or a slight rise in the bodily temperature. The slight rise, when it occurs, is due to the stimulation of the skin causing reflexly a more rapid molecular transformation, and therefore a greater production of heat, while the amount of heat given off is diminished owing to contraction of the small cutaneous vessels and the skin itself (*Liebermeister*). The continuous and intense application of cold causes a decrease of the temperature, chiefly by conduction, notwithstanding that at the same time there is a greater production of heat. After a cold bath the temperature may be 34°, 32°, and even 30° C.

As an **after-effect** of the great abstraction of heat, the temperature of the body after a time remains lower than it was before (*"primary after-effect"*—*Liebermeister*); thus after an hour it was 0.22° C. in the rectum. There is a *"secondary after-effect"* which occurs after the first after-effect is over, when the temperature rises (*Jürgensen*). This effect begins five to eight hours after a cold bath, and is equal to + 0.2° C. in the rectum. Hoppe-Seyler found that some time after the application of heat there was a corresponding lowering of the temperature.

Taking Cold.—If a rabbit be taken from a surrounding temperature of 35° C., and suddenly cooled, it shivers, and there may be diarrhœa. After two days the temperature rises 1.5° C., and albuminuria occurs. There are microscopic traces of interstitial inflammation in the kidneys, liver, lungs, heart, and nerve sheaths, the dilated arteries of the liver and lung contain thrombi, and in the neighborhood of the veins are accumulations of leucocytes. In pregnant animals the fœtus shows the same conditions. Perhaps the greatly cooled blood acts as an irritant causing inflammation.

Action of Frost.— The continued application of a high degree of cold causes at first contraction of the blood vessels of the skin and its muscles, so that it becomes pale. If continued paralysis of the cutaneous vessels occurs, the skin becomes red, owing to congestion of its vessels. As the passage of fluids through the capillaries is rendered more difficult by the cold, the blood stagnates, and the skin assumes a *livid appearance*, as the O is almost completely used up. Thus the peripheral circu-

lation is slowed. If the action of the cold be still more intense, the peripheral circulation stops completely, especially in the thinnest and most exposed organs—ears, nose, toes, and fingers. The sensory nerves are paralyzed, so that there is numbness with loss of sensibility, and the parts may even be frozen through and through. As the slowing of the circulation in the superficial vessels gradually affects other areas of the circulation, the pulmonary circulation is enfeebled, and diminished oxidation of the blood occurs, notwithstanding the greater amount of O in the cold air, so that the *nerve centres* are affected. Hence arise great dislike to making movements or any muscular effort, a painful sensation of fatigue, a peculiar and almost irresistible desire to sleep, cerebral inactivity, blunting of the sense organs, and lastly, coma. The blood freezes at —3.9° C., while the juices of the superficial parts freeze sooner. Too rapid movements of the frost bitten parts ought to be avoided. Rubbing with snow, and the very gradual application of heat, produce the best results. Partial death of a part is not unfrequently produced by the prolonged action of cold.

225. ARTIFICIAL LOWERING OF THE TEMPERATURE.—Phenomena.—The artificial cooling of **warm-blooded animals**, by placing them in cold air or in a freezing mixture, gives rise to a series of characteristic phenomena. If the animals (rabbits) are cooled so that the temperature (rectum) falls to 18°, they suffer great depression, without, however, the voluntary or reflex movements being abolished. The *pulse* falls from 100 or 150 to 20 beats per minute, and the blood pressure falls to several millimetres of Hg. The *respirations* are few and shallow. Suffocation does not cause spasms, the secretion of urine stops, and the liver is congested. The animal may remain for twelve hours in this condition, and when the muscles and nerves show signs of paralysis, coagulation of the blood occurs after numerous blood corpuscles have been destroyed. The retina becomes pale, and death occurs with spasms and the signs of asphyxia. If the bodily temperature be reduced to 17° and under, the voluntary movements cease before the reflex acts. An animal cooled to 18° C., and left to itself, at the same temperature as the surrounding, does not recover of itself, but if artificial respiration be employed, the temperature rises 10° C. If this be combined with the application of external warmth, the animals may recover completely, even when they have been apparently dead for forty minutes. Walther cooled adult animals to 9° C., and recovered them by artificial respiration and external warmth; while Horvath cooled *young* animals to 5° C. Mammals, which are born blind, and birds which come out of the egg devoid of feathers, cool more rapidly than others. Morphia, and more so, **alcohol**, accelerate the cooling of mammals, at the same time the exchange of gases falls considerably; hence, drunken men are more liable to die when exposed to cold.

Artificial Cold-blooded Condition.—Cl. Bernard made the important observation, that the muscles of animals that had been cooled remained irritable for a long time, to direct stimuli as well as to stimuli applied to their nerves; and the same is the case when the animals are asphyxiated for want of O. An "*artificial cold-blooded condition*," *i. e.*, a condition in which warm-blooded animals have a lower temperature, and retain muscular and nervous excitability, may also be caused in warm-blooded animals, by dividing the cervical spinal cord and keeping up artificial respiration; further, by moistening the peritoneum with a cool solution of common salt.

Hibernation presents a series of similar phenomena. Valentin found that hibernating animals become half awake when their bodily temperature is 28° C.; at 18° C. they are in a somnolent condition, at 6° they are in a gentle sleep, and at 1.6° C. in a deep sleep. The heart beats and the blood pressure fall, the former to 8 to 10 per minute. The respiratory, urinary, and intestinal movements cease completely, and the cardio-pneumatic movement alone sustains the slight exchange of gases in the lungs (§ 59). They cannot endure cooling to 0° C.; and awake before the temperature falls so low. Hibernating animals may be cooled to a greater degree than other mammals; they give off heat rapidly, and they become warm again rapidly, and even spontaneously. Newborn mammals resemble hibernating animals more closely in this respect than do

Cold-blooded animals may be cooled to 0°. F
formed in the lymph of the peritoneal cavity, from
dead, but when placed in a warm medium they
again. The germs and ova of lower animals,

cold be moderate, it merely retards development. Bacteria, *e. g.*, Bacillus anthracis, survive a temperature of — 130° C.; yeast, even — 100° C.

Varnishing the skin causes a series of similar phenomena. The varnished skin gives off a large amount of heat by radiation, and sometimes the cutaneous vessels are greatly dilated. Hence the animals cool rapidly and die, although the consumption of O is not diminished. If cooling be prevented by warming them and keeping them in warm wool, the animals live for a longer time. The blood *post-mortem* does not contain any poisonous substances, nor even are any materials retained in the blood which can cause death, for if the blood be injected into other animals, these remain healthy.

226. EMPLOYMENT OF COLD.—**Cold** may be applied to the whole or part of the surface of the body in the following conditions:—

(*a*) By placing the body for a time in a **cold bath**, to abstract as much heat as possible, when the bodily temperature in fever rises so high as to be dangerous to life. This result is best accomplished and lasts longest when the bath is gradually cooled from a moderate temperature. If the body be placed at once in cold water, the cutaneous vessels contract, the skin becomes bloodless, and thus obstacles are placed in the way of the excretion of heat. A bath gradually cooled in this way is borne longer. The addition of stimulating substances, *e. g.*, salts, which cause dilatation of the cutaneous vessels, facilitates the excretion of heat; even salt water conducts heat better. If alcohol be given internally at the same time, it lowers the temperature.

(*b*) Cold may be applied **locally** by means of ice in a bag, which causes contraction of the cutaneous vessels and contraction of the tissues (as in inflammation), while at the same time heat is abstracted locally.

(*c*) Heat may be abstracted locally by the **rapid evaporation** of volatile substances (ether, carbon disulphide), which causes numbness of the sensory nerves. The introduction of media of low temperature into the body, respiring cool air, taking cold drinks, and the injection of cold fluids into the intestine act locally, and also produce a more general action. In applying cold it is important to notice that the initial contraction of the vessels and the contraction of the tissues are followed by a greater dilatation and turgescence, *i. e.*, by a healthy reaction.

227. HEAT OF INFLAMED PARTS.—**"Calor," or heat,** is reckoned one of the fundamental phenomena of inflammation, in addition to rubor (**redness**), tumor (**swelling**), and dolor (**pain**). But the apparent increase in the heat of the inflamed parts is not above the temperature of the blood. Simon, in 1860, asserted that the arterial blood flowing to an inflamed part was cooler than the part itself, but this has been contradicted. The outer parts of the skin in an inflamed part are warmer than usual, owing to the dilatation of the vessels (rubor) and the consequent acceleration of the blood stream in the inflamed part, and owing to the swelling (tumor) from the presence of good heat-conducting fluids; but the heat is not greater than the heat of the blood. It is not proved that an increased amount of heat is produced owing to increased molecular decompositions within an inflamed part.

228. HISTORICAL AND COMPARATIVE.—According to Aristotle, the heart prepares the heat within itself, and sends it along with the blood to all parts of the body. This doctrine prevailed in the time of Hippocrates and Galen, and occurs even in Cartesius and Bartholinus (1667, "flammula cordis"). The **iatro-mechanical school** (*Boerhave, van Swieten*) ascribed the heat to the friction of the blood on the walls of the vessels. The **iatro-chemical school,** on the other hand, sought the source of heat in the fermentations that arose from the passage of the absorbed substances into the blood (*van Helmont, Sylvius, Ettmüller*). Lavoisier (1777) was the first to ascribe the heat to the combustion of carbon in the lungs. After the construction of the **thermometer** by Galileo, Sanctorius (1626) made the first thermometric observations on sick persons, while the first *calorimetric* observations were made by Lavoisier and Laplace. **Comparative** observations are given at § 207, and also under *Hibernation* (§ 225).

PHYSIOLOGY OF METABOLIC PHENOMENA.

By the term **metabolism** we mean those phenomena whereby all—even the most lowly—living organisms are capable of incorporating the substances obtained from their food into their tissues, and making them an integral part of their own bodies. This part of the process is known as **assimilation.** Further, the organism in virtue of its metabolism forms a store of potential energy, which it can transform into *kinetic energy*, and which, in the higher animals at least, appears most obvious in the form of muscular work and heat. The **changes of the constituents of the tissues,** by which these transformations of the potential energy are accompanied, result in the formation of **excretory products,** which is another part of the process of metabolism. The normal metabolism requires the supply of food quantitatively and qualitatively of the proper kind, the laying up of this food within the body, a regular chemical transformation of the tissues, and the formation of the effete products which have to be given out through the excretory organs. [Synthetic or constructive metabolism is spoken of as **anabolic,** and destructive or analytical metabolism as **katabolic,** metabolism.]

229. THE MOST IMPORTANT SUBSTANCES USED AS FOOD.—Water.—When we remember that 58.5 per cent. of the body consists of water, that water is being continually given off by the urine and fæces, as well as through the skin and lungs, that the processes of digestion and absorption require water for the solution of most of the substances used as food, and that numerous substances excreted from the body require water for their solution, especially in the urine, the great importance of water and its continual renewal within the organism are at once apparent. As put by Hoppe-Seyler, all organisms live in water, and even in running water, a saying which ranks with the old saying—"Corpora non agunt nisi fluida."

Water—as far as it is not a constituent of all fluid foods—occurs in different forms as drink: (1) **Rain water,** which most closely resembles distilled or chemically pure water, always contains minute quantities of CO_2, NH_3, nitrous and nitric acids. (2) **Spring water** usually contains much mineral substance. It is formed from the deposition of watery vapor or rain from the air, which permeates the soil, containing much CO_2; the CO_2 is dissolved by the water, and aids in dissolving the alkalies, alkaline earths, and metals, which appear in solution as bicarbonates, *e. g.*, of lime or iron oxide. The water is removed from the spring by proper mechanical appliances, or it bubbles up on the surface in the form of a "spring." (3) **River water** usually contains much less mineral matter than spring water. Spring water floating on the surface rapidly gives off its CO_2, whereby many substances—*e. g.*, lime—are thrown out of solution, and deposited as insoluble precipitates.

Gases.—Spring water contains little O, but much CO_2, the latter giving to it its fresh taste. Hence, vegetable organisms flourish in spring water, while animals requiring, as they do, much O, are but poorly represented in such water. Water flowing freely gives up CO_2, and absorbs O from the air, and thus affords the necessary conditions for the existence of fishes and other marine animals. River water contains $\frac{1}{30}$ to $\frac{1}{20}$ of its volume of absorbed gases, which may be expelled by boiling or freezing.

Drinking water is chiefly obtained from springs. River water, if used for this purpose, must be filtered to get rid of mechanically suspended impurities. For household purposes a charcoal filter may be used, as the charcoal acts as a disinfectant. **Alum** has a remarkable action. When added to give a dilution containing 0.0001 per cent., it makes turbid water clear

Investigation of Drinking Water.—Drinking water, even in a thick layer, ought to be completely *colorless, not turbid, and without odor.* Any odor is best recognized by heating it to 50° C., and adding a little caustic soda. It ought not to be *too hard, i. e.*, it ought not to contain too much lime (and magnesia) salts.

By the term "**degree of hardness**" of a water is meant the unit amount of lime (and magnesia) in 100,000 parts of water; a water of 20 degrees of hardness contains 20 parts of lime (calcium oxide) combined with CO_2, sulphuric, or hydrochloric acids (the small amount of magnesia may be neglected). *A good drinking water ought not to exceed 20 degrees of hardness.* The hardness is determined by titrating the water with a standard soap solution, the result being the formation of a scum of lime soap on the surface. The hardness of *unboiled* water is called its *total hardness*, while that of *boiled water* is called **permanent hardness.** Boiling drives off the CO_2, and precipitates the calcium carbonate, so that the water at the same time becomes softer.

The presence of **sulphuric acid,** or sulphates, is determined by the water becoming turbid on adding a solution of barium chloride and hydrochloric acid.

Chlorine occurs in small amount in pure spring water, but when it occurs there in large amount—apart from its being derived from saline springs, near the sea or manufactories—we may conclude that the water is contaminated from water closets or dunghills, so that the estimation of chlorine is of importance. For this purpose use a solution, A, of 17 grms. of crystallized silver nitrate in 1 litre of distilled water; 1 cubic centimetre of this solution precipitates 3.55 milligrammes of chlorine as silver chloride. Use also B, a cold saturated solution of neutral potassium chromate. Take 50 cubic centimetres of the water to be investigated, and place it in a beaker, add to it 2 to 3 drops of B, and allow the fluid A to run into it from a burette until the white precipitate first formed *remains* red, even after the fluid has been stirred. Multiply the number of cubic centimetres of A used by 7.1, and this will give the amount of chlorine in 100,000 parts of the water. **Example**—50 c. cmtr. requires 2.9 c. cmtr. of the silver solution, so that 100,000 parts of the water contain $2.9 \times 7.1 = 20.59$ parts chlorine (*Kubel Tiemann*). Good water ought not to contain more than 15 milligrammes of chlorine per litre.

The presence of **lime** may be ascertained by acidulating 50 cubic centimetres of the water with HCl, adding ammonia in excess, and afterward adding ammonia oxalate; the white precipitate is lime oxalate. According to the degree of turbidity, we judge whether the water is "soft" (poor in lime), or "hard" (rich in lime).

Magnesia is determined by taking the clear fluid of the above operation, after removing the precipitate of lime, and adding to it a solution of sodium phosphate and some ammonia; the crystalline precipitate which occurs is magnesia.

The more feeble all these reactions which indicate the presence of sulphuric acid, chlorine, lime, and magnesia, are, the better is the water. In addition, good water ought not to contain more than traces of nitrates, nitrites, or compounds of ammonia, as their presence indicates the decomposition of nitrogenous organic substances.

For **nitric acid,** take 100 cubic centimetres of water acidulated with two or three drops of concentrated sulphuric acid, add several pieces of zinc together with a solution of potassium iodide, and starch solution—a blue color indicates nitric acid. The following test is very delicate: Add to half a drop of water in a capsule two drops of a watery solution of Brucinum sulphuricum, and afterward several drops of concentrated sulphuric acid; a rose-red coloration indicates the presence of nitric acid.

The presence of **nitrous acid** is ascertained by the blue coloration which results from the addition of a solution of potassium iodide, and solution of starch, after the water has been acidulated with sulphuric acid.

Compounds of ammonia are detected by Nessler's reagent, which gives a yellow or reddish coloration when a trace of ammonia is present in water; while a large amount of these compounds gives a brown precipitate of the iodide of mercury and ammonia.

The **contamination of water** by decomposing animal substance is determined by the amount of N it contains. In most cases it is sufficient to determine the amount of *nitric acid* present. For this purpose we require (A) a solution of 1.871 grms. potassium nitrate in 1 litre distilled water—1 cubic centimetre contains 1 milligramme nitric acid; (B) a dilute solution of indigo, which is prepared by rubbing together one part of pulverized indigotin with six parts H_2SO_4, and allowing the deposit to subside, when the blue fluid is poured into forty times its volume of distilled water and filtered. This fluid is diluted with distilled water until a layer, 12 to 15 mm. in thickness, begins to be transparent.

To test the activity of B, place 1 cubic centimetre of A in 24 cubic centimetres water, add some common salt and 50 cubic centimetres concentrated sulphuric acid, and allow B to flow from a burette into this mixture until a faint green color is obtained. The number of cubic centimetres of B used correspond to 1 milligramme of nitric acid.

Twenty-five cubic centimetres of the water to be investigated are mixed with 50 cubic centimetres ...rated H_2SO_4, and titrated with B until a green color is obtained. This process must be

repeated, and on the second occasion the solution B must be allowed to flow in at once, when usually somewhat more indigo solution is required to obtain the green solution. The number of cubic centimetres of B (corresponding to the strength of B, as determined above) indicates the amount of nitric acid present in 25 c.cmtr. of the water investigated. As much as 10 milligrammes nitric acid have been found in spring water (*Marx, Trommsdorff*).

Sulphuretted Hydrogen is recognized by its *odor*; also by a piece of blotting paper moistened with alkaline solution of lead becoming brown when it is held over the boiling water. If it occurs as a *compound* in the water, sodium nitro-prusside gives a reddish-violet color

It is of the greatest importance that drinking water should be *free from the presence of* **organic matter** in a state of decomposition. Organic matter in a state of decomposition, and the organisms therewith associated, when introduced into the body, may give rise to fatal maladies, *e. g.*, cholera and typhoid fever. This is the case when the water supply has been contaminated from water which has percolated from water closets, privies and dung pits. *The presence of organic matter may be detected thus* (1) A considerable amount of the water is evaporated to dryness in a porcelain vessel, if the residue be heated again a brown or black color indicates the presence of a considerable amount of organic matter; and if it contain N, there is an odor of ammonia. Good water treated in this way gives only a light brown stain. The presence of **micro-organisms** may be determined microscopically after evaporating a small quantity of the water on a glass slide. (2) The addition of *potassio-gold chloride* to the water gives a black frothy precipitate after long standing. (3) A solution of *potassium permanganate*, added to the water in a covered jar, gradually becomes decolorized, and a brownish precipitate is formed.

Water containing much organic matter should *never* be used as drinking water, and this is especially the case when there is an epidemic of typhoid fever, cholera or diarrhœa. In all such circumstances, the water ought to be boiled for a long time, whereby the organic germs are killed. The insipid taste of the water after boiling may be corrected by adding a little sugar or lime juice.

230. **THE MAMMARY GLANDS AND MILK.—Milk Duct.**—About 20 galactoferous ducts open singly upon the surface of the nipple. Each of these, just before it opens on the surface, is provided with an oval dilatation—the **sinus lacteus.** When traced into the gland, the galactoferous ducts divide like the branches of a tree, and a large branch of the duct passes to each **lobe** of the gland, all the lobes being held together by loose connective tissue. Only during lactation do all the fine terminations of the ducts communicate with the globular glandular acini. Every gland **acinus** consists of a membrana propria, surrounded externally with a network of branched connective-tissue corpuscles, and lined internally with a somewhat flattened polyhedral layer of nucleated **secretory cells** (Fig. 233). The size of the lumen of the acini depends upon the secretory activity of the glands; when it is large, it is filled with milk containing numerous refractive fatty granules. The walls of the milk ducts consist of fibrillar connective tissue, some fibres are arranged longitudinally, but the chief mass are disposed circularly, and are permeated externally with elastic fibres, while in the finer ducts there is a membrana propria continuous with that of the gland acini. The ducts are lined by cylindrical epithelium.

FIG. 233.

Acini of the mammary gland of a sheep during lactation. *a*, membrana propria; *b*, secretory epithelium.

During the *first few days after delivery*, the breasts secrete a small amount of milk of greater consistence, and of a yellow color—the **colostrum**—in which large cells filled with fatty granules occur—the colostrum corpuscles (Fig. 235). Sometimes a nucleus is observable within them, and rarely they exhibit amœboid movements (Fig. 234, *c*, *d*, *e*). The regular secretion of milk begins after three to four days. It was formerly supposed that the cells of the acini underwent a fatty degeneration, and thus produced the fatty granules of the milk. It is more probable, from recent observations, that the cells of the acini manufacture the fatty granules, and their protoplasm eliminates them, at the same time forming the clear fluid part of the milk.

Changes during Secretion.—Pratsch and Heidenhain found that the secretory cells in the **non-secreting gland** (Fig. 234, I) were flat, polyhedral and uni-nucleated, while the **secreting cells** (Fig. 234, II) often contained several nuclei, were more albuminous, higher, and cylindrical in form. The edge of the cell directed toward the lumen of the acinus undergoes characteristic changes during secretion. Fatty granules are formed in this part of the cell, and are afterward extruded. The decomposed portion of the cell is dissolved in the milk, and the fatty granules become free as milk globules (Fig. 234, II, *a*). If nuclei are present in that part of the cell which is broken up, they also pass into the milk and give rise to the presence of nuclein in the secretion.

Besides the milk globules and colostrum corpuscles, Rauber has found leucocytes undergoing fatty

degeneration and single pale cells (*f*). Occasionally milk globules are found with traces of the cell substance adhering to their surface (*b*).

Formation of Milk.—Concerning the formation of the **individual constituents** of milk, H. Thierfelder, who digested fresh mammary glands directly after death, found that during the digestion of the glands, at the temperature of the body, a reducing substance, probably **lactose**, was formed by a process of fermentation. The mother substance (saccharogen) is soluble in water, but not in alcohol or ether, is not destroyed by boiling, and is not identical with glycogen. The ferment which forms the lactose is connected with the gland cells—it does not pass into the milk, nor into a watery extract of the gland. During the digestion of the mammary glands at the temperature of the body, **casein** is formed, probably from serum albumin, by a process of fermentation. This ferment occurs in the milk.

The **nipple** and its **areola** are characterized by the presence of pigment—more abundant during pregnancy—in the rete Malpighii of the skin, and by large papillæ in the cutis vera. Some of the papillæ contain touch corpuscles. Numerous non-striped muscular fibres surround the milk ducts in the deep layers of the skin and in the subcutaneous tissue, which contains no fat. These muscular fibres can be traced, following a longitudinal course, to the termination of the ducts on the surface. The small *glands of Montgomery*, which occur on the areola during lactation, are just small milk glands, each with a special duct opening on the surface of the elevation.

Arteries proceed from several sources to supply the mamma, but their branches do not accompany the milk ducts; each gland acinus is surrounded by a network of *capillaries*, which communicate with those of adjoining acini by small arteries and veins. The veins of the areola are arranged in a circle (circulus Halleri). The **nerves** are derived from the supraclavicular, and the II–IV–VI intercostals; they proceed to the skin over the gland, to the very sensitive nipple, to the blood vessels and non-striped muscle of the nipple, and to the gland acini, where their mode of termination is still

FIG. 234.



I. Inactive acinus of the mamma. II. During the secretion of milk—*a*, *b*, milk globules; *c*, *d*, *e*, colostrum corpuscles; *f*, pale cells (bitch).

unknown. **Lymphatics** surround the alveoli, and they are often full. The milk appears to be prepared from the lymph contained in the lymphatics surrounding the acini.

The **comparative anatomy** of the mamma.—The rodents, insectivora, and carnivora have 10 to 12 teats, while some of them have only 4. The pachydermata and ruminantia have 2 to 4 abdominal teats, the whale has 2 near the vulva. The apes, bats, vegetable-feeding whales, elephants, and sloths have 2, like man. In the marsupials the tubes are arranged in groups, which open on a patch of skin devoid of hair without any nipple. The young animals remain within the mother's pouch, and the milk is expelled into their mouths by the action of a muscle—the compressor mammæ.

The **development** of the human mamma begins in both sexes during the third month; at the fourth and fifth months a few simple tubular gland ducts are arranged radially around the position of the future nipple, which is devoid of hair. In the new-born child the ducts are branched twice or thrice, and are provided with dilated extremities, the future acini. Up to the twelfth year, in both sexes, the ducts continue to divide dendritically, but without any proper acini being formed. In the girl at **puberty**, the ducts branch rapidly; but the acini are formed *only at the periphery* of the gland; during **pregnancy**, acini are also formed in the centre of the gland, while the connective tissue at the same time becomes somewhat more opened out. At the **climacteric period**, or menopause, all the acini and numerous fine milk ducts degenerate. In the *adult male*, the gland remains in the non developed infantile condition. Accessory or supernumerary glands upon the breast and abdomen are not uncommon; sometimes the mamma occurs in the axilla, on the back, over the acromion process, or on the leg. A slight secretion of milk in a newly-born infant is normal.

During the **evacuation of the milk** (500–1500 cubic centimetres daily), there is not only the mechanical action of **sucking**, but also the activity of the gland itself (§ 152). This consists in the erection of the nipple, whereby its non-striped muscular fibres compress the sinuses on the milk ducts, and empty them, so that the milk may flow out in streams. The gland acini are also excited to

secretion reflexly by the stimulation of the **sensory nerves** of the nipple. The vessels of the gland are dilated, and there is a copious transudation into the gland—the transuded fluid being manufactured into milk under the influence of the secretory protoplasm. The amount of secretion depends upon the blood pressure (*Röhrig*). During sucking, not only is the milk in the gland extracted, but new milk is formed, owing to the accelerated secretion. Emotional di-turbances—anger, fear, etc.—arrest the secretion. Laffont found that stimulation of the mammary nerve (bitch) caused erection of the teat, dilatation of the vessels, and secretion of milk. After section of the cerebro-spinal nerves going to the mamma, Eckhard observed that erection of the teat ceased, although the secretion of milk in a goat was not interrupted. The rarely observed **galactorrhœa** is perhaps to be regarded as a paralytic secretion analogous to the paralytic secretion of saliva. Heidenhain and Pratsch found that the secretion (bitch) was increased by injecting strychnine or curara after section of the nerves of the gland. The **"milk fever,"** which accompanies the first secretion of milk, probably depends on stimulation of the vasomotor nerves, but this condition must be studied in relation with the other changes which occur within the pelvic cavity after birth. [Some substances, such as atropin, arrest the secretion of milk.]

231. **MILK AND ITS PREPARATIONS.—Milk** represents a **complete** or **typical food** in which are present all the constituents necessary for maintaining the life and growth of the body of an infant (§ 236). [If an adult were to live on milk alone, to get the 23 oz. of dry solids necessary, he would have to take 9 pints of milk daily, which would give far too much water, fat, and proteids.] To every 10 parts of proteids there are 10 parts fat and 20 parts sugar. Relatively more of the fat than the albumin of the milk is absorbed (*Rubner*); while a part of both is excreted in the fæces.

Characters.—Milk is an opaque, bluish-white fluid with a sweetish taste and a characteristic odor, probably due to the peculiar volatile substances derived from the cutaneous secretions of the glands, and it has a specific gravity of 1026 to 1035. When it stands for a time, numerous milk globules, butter globules, or **cream**, collect on its surface, under which there is a bluish watery fluid. Human milk is always *alkaline*, cow's milk may be alkaline, acid, or amphoteric; while the milk of carnivora is always acid.

FIG. 235.

Microscopic appearance of milk, (M) upper half, and colostrum (C) lower half.

Milk Globules.—When milk is examined *microscopically*, it is seen to contain numerous small, highly refractive **oil globules**, floating in a clear fluid—the **milk plasma** (Figs. 234, *a*, *b*, 235); while colostrum corpuscles and epithelium from the milk ducts are not so numerous. The white color and opacity of the milk are due to the presence of the milk globules, which reflect the light; the globules consist of a fat, or butter, and are said by some to be surrounded with a very thin envelope of *casein* or haptogen membrane.

If acetic acid be added to a microscopic preparation of milk, the fatty granules run together to form irregular masses. If cow's milk be shaken with caustic potash, the casein envelopes are dissolved, and if ether be added, the milk becomes clear and transparent, as the ether dissolves out all the fatty particles in the solution. Ether cannot extract the fat from cow's milk until acetic acid or caustic potash is added to liberate the fats from their envelopes; but shaking with ether is sufficient to extract the fats from human milk. Some observers deny that an envelope of casein exists, and according to them milk is a simple emulsion, kept emulsionized owing to the colloid swollen-up casein in the milk plasma. The treatment of milk with potash and ether makes the casein unable any longer to preserve the emulsion (*Soxhlet*).

The **fats of the milk globules** are the triglycerides of stearic, palmitic, oleic (very little), myristic, arachinic (butinic), capric, caprylic, caproic, and butyric acids, with traces of acetic and formic acids and cholesterin.

Butter.—When milk is beaten or stirred for a long time (*i.e.*, churned), the fat of the milk globules is ultimately obtained in the form of *butter*, owing to the rupture of the envelopes of casein. Butter is soluble in alcohol and ether, and it is clarified by heat (60° C.), or by washing in water at 40° C. When allowed to stand exposed to the air, it first becomes **sour**, owing to the formation of lactic acid, and afterward **rancid**, owing to the glycerine of the neutral fats being decomposed by fungi into acrolein, and formic acid, while the volatile fatty acids give it its rancid odor.

The **milk plasma**, obtained by filtration through a clay filter or membranes, is a clear, slightly opalescent fluid, and contains **casein** (§ 249, III, 3), some **serum albumin** (§ 32), **peptone** (0.13 per cent.), **nuclein**, and a trace of diastatic ferment (in human milk).

The presence of other peculiar chemical bodies, *e.g.*, lactoprotein, globulin, albumose, galactin, etc., is disputed by some chemists.

When milk is **boiled** the albumin coagulates, while the surface also becomes covered with a thin scum or layer of casein, which has become insoluble [the rest of the milk remaining fluid].

Casein.—When milk is filtered through fresh animal membranes or through a clay filter, the *casein* does not pass through. **Precipitation.**—It is precipitated by adding crystals of $MgSO_4$ to saturation. [If to milk twice its volume of a saturated solution of NaCl and crystals of NaCl be added, and the whole shaken thoroughly, casein is precipitated, and carries down with it fat, so that the clear filtrate contains the lactose, salts, and coagulable proteids.]

The plasma contains **milk sugar** (§ 252); a carbohydrate resembling dextrin, (? lactic acid), lecithin, urea, extractives, kreatin, sarkin (potassic sulphocyanide in cow's milk), sodic and potassic chlorides, alkaline phosphates, calcium and magnesium sulphates, alkaline carbonates, traces of iron, fluorine, and silica, CO_2, N, and O.

The **coagulation of milk** *depends upon the coagulation of its casein.* In milk, casein is combined with calcium phosphate, which keeps it in solution; acids which act on the calcium phosphate cause coagulation of the casein (acetic and tartaric acids in excess redissolve it). All acids do not coagulate human milk. It is coagulated by two or more drops of hydrochloric acid (0.1 per cent.) or acetic acid (0.2 per cent.). The *spontaneous* coagulation of milk after it has stood for a time, especially in a warm place, is due to the production of **lactic acid**, which is formed from the milk sugar in the milk by the action of **bacillus acidi lactici** [which is introduced from without] (§ 184, I). It changes the neutral alkaline phosphate into the acid phosphate, takes the casein from the calcium phosphate, and precipitates the casein. The sugar is decomposed into lactic acid and CO_2.

Rennet (§ 250, 9, *d*, § 166, II) coagulates milk with an *alkaline* reaction (sweet whey). This ferment *decomposes the casein* into the precipitated cheese and also into the slightly soluble whey albumin, so that the coagulation by rennet is a process quite distinct from the coagulation of milk by the gastric and pancreatic juices, [and also from the precipitation produced by acids. The presence of calcium phosphate seems to be necessary for the complete action of the rennet (*Hammarsten*)].

[**Experiments.**—Warm a little milk to 40° C., and add a few drops of commercial rennet, setting aside the mixture in a warm place; a solid coagulum is then formed, and by and by the whey separates from it. If the milk be previously diluted with water, no coagulum is formed; and if the rennet be boiled before, it, like other ferments, is destroyed. A solution of rennet may be prepared by extracting the fourth stomach of the calf with glycerine. [When the milk is coagulated we obtain the **curd**, consisting of casein with some milk globules entangled in it; the **whey** contains some soluble albumin and fat, and the great proportion of the salts and milk sugar, together with lactic acid.]

[A **milk-coagulating ferment** is found in certain plants (artichokes, figs, Carica papaya), and causes milk to coagulate in neutral or alkaline solutions. It is also found in the small intestine of the calf, while a 5 per cent. NaCl solution of the seeds of *Withania coagulans* coagulates milk in an alkaline medium.]

Boiling (by killing all the lower organisms), sodium bicarbonate ($\frac{1}{1000}$), ammonia, salicylic acid ($\frac{1}{2000}$), glycerine, and ethereal oil of mustard prevent the spontaneous coagulation. Fresh milk makes tincture of guaiacum blue, but boiled milk does not do so. When milk is exposed to the air for a long time, it gives off CO_2 and absorbs O; the fats are increased (? owing to the development of fungi in the milk), and so are the alcoholic and ethereal extracts, from the decomposition of the casein. According to Schmidt-Mülheim, some of the casein becomes converted into peptone, but this occurs only in unboiled milk.

Composition.—100 parts of milk contain—

	Human.		Cow.	Goat.	Ass.
Water,	87.24 to 90.58		86.23	86.85	89.01
Solids,	9.42 " 12.39		13.77	13.52	10.99
Casein,	2.91 " 3.92	1.90 to 2.36	3.23	2.53	3.57
Albumin,	... ...		0.50	1.26	
Butter,	2.67 " 4.30		4.50	4.34	1.85
Milk sugar,	3.15 " 6.09		4.93	3.78	5.05
Salts,	0.14 " 0.28		0.61	0.65	

Human milk contains less albumin, which is more soluble than the albumin in the milk of animals.

Colostrum contains much serum-albumin, and very little casein, while all the other substances, and especially the fats, are more abundant.

Gases.—Pflüger and Setschenow found in 100 vols. of milk 5.01 to 7.60 CO_2; 0.09 to 0.32 O; 0.70 to 1.41 N, according to volume. Only part of the CO_2 is expelled by phosphoric acid.

Salts.—The *potash salts* (as in blood and muscle) are more abundant than the soda compounds, while there is a considerable amount of calcium phosphate, which is necessary for *forming the bones* of the infant. Wildenstein found in 100 parts of the **ash** of human milk—sodium chloride, 10.73; potassium chloride, 26.33; potash, 21.44; lime, 18.78; magnesia, 0.87; phosphoric acid, 19; ferric phosphate, 0.21; sulphuric acid, 2.64; silica, traces. The amount of salts present is affected by the salts of the food.

Conditions Influencing the Composition.—The oftener the breasts are *emptied*, the richer the milk becomes in casein. The last milk obtained at any time is always richer in butter, as it comes from the most distant part of the gland—viz., the acini. Some substances are diminished and others increased in amount, according to the *time after delivery*. The following are *increased:* Until the second month after delivery, casein and fat; until the 5th month, the salts (which diminish progressively from this time onward); from the 8th to the 10th month, the sugar. The following are *diminished:* From 10th to 24th month, casein; from 5th to 6th and 10th to 11th month, fat; during 1st month, the sugar; from the 5th month, the salts.

The greater the amount of milk that is secreted (woman), the more casein and sugar, and the less butter it contains. The milk of a primipara is less watery. Rich feeding, especially proteids (small amount of vegetable food), increases the amount of milk and the casein, sugar and fat in it; a large amount of carbohydrates (not fats) increases the amount of sugar.

[**Modifying Conditions.**—That cow's milk is influenced by the pasture and food is well known. Turnip as food gives a peculiar odor, taste, and flavor to the milk, and so do the fragrant grasses. The mental state of the nurse influences the quantity and quality of the milk. Jaborandi is the nearest approach to a galactagogue, but its action is temporary. Atropin is a true anti-galactagogue. The composition of the milk may be affected by using fatty food, by the use of salts, and above all by the diet (*Dolan*).]

[Milk may be a **vehicle for communicating disease**—by direct contamination, from the water used for adulterating it or cleansing the vessels in which it is kept; by the milk absorbing deleterious gases; by the secretion being altered in diseased animals.] Milk ought not to be kept in zinc vessels, owing to the formation of zinc lactate.

Substitutes.—If other than human milk has to be used, ass's milk most closely resembles human milk. Cow's milk is best when it contains plenty of fatty matters—it must be diluted with its own volume of water at first, and a little milk sugar added. The casein of cow's milk differs qualitatively from that of human milk; its coagulated flocculi or curd are much coarser than the fine curd of human milk, and they are only ¾ dissolved by the digestive juices, while human milk is completely dissolved. Cow's milk when boiled is less digestible than unboiled.

Tests for Milk.—The **amount of cream** is estimated by placing the milk for twenty-four hours in a tall cylindrical glass graduated into a hundred parts, or **creamometer**; the cream collects on the surface, and ought to form from 10 to 24 vols. per cent. [The cream is generally about $\frac{8}{100}$.] The specific gravity (fresh cow's milk, 1029 to 1034; when creamed, 1032 to 1040) is estimated with the **lactometer** at 15° C. The **sugar** is estimated by titration with Fehling's solution (§ 150, II), but in this case 1 cubic centimetre of the solution corresponds to 0.0067 grm. of milk sugar; or its amount may be estimated with the *polariscopic apparatus* (§ 150). The **proteids** are precipitated and the fats extracted with ether. The fats in fresh milk form about 3 per cent., and in skimmed milk 1½ per cent. The amount of **water** in relation to the milk globules is estimated by the **lactoscope** or the **diaphanometer** of Donné (modified by Vogel and Hoppe-Seyler), which consists of a glass vessel with plane parallel sides placed 1 centimetre apart. A measured quantity of milk is taken, and water is added to it from a burette until the outline of a candle flame placed at a distance of 1 metre can be distinctly seen through the diluted milk. This is done in a dark room For 1 cubic centimetre of good cow's milk, 70 to 85 centimetres water are required. [Other forms of lactoscope are used, all depending on the same principle of an optical test, viz., that the opacity of milk varies with and is proportional to the amount of butter-fats present, *i.e.*, the oil globules. Bond uses a shallow cylindrical vessel with the bottom covered by black lines on a white surface. A measured

quantity of water is placed in this vessel, and milk is added, drop by drop, until the parallel lines on the pattern at the bottom of the dish cease to be visible. On counting the number of drops, a table accompanying the appliance gives the percentage of fats. This method gives approximate results. In all cases it is well to use fresh milk.]

Various substances pass into the milk *when they are administered to the mother*—many odoriferous vegetable bodies, *e.g.*, anise, vermuth, garlic, etc.; chloral, rhubarb, opium, indigo, salicylic acid, iodine, iron, zinc, mercury, lead, bismuth, antimony. In osteomalacia the amount of lime in the milk is increased (*Gusserow*). Potassium iodide diminishes the secretion of milk by affecting the secretory function. Among **abnormal constituents** are—hæmoglobin, bile pigments, mucin, blood corpuscles, pus, fibrin. Numerous fungi and other low organisms develop in evacuated milk, and the rare *blue* milk is due to the development of bacillus cyanogenēum. The milk serum is blue, not the fungus. Blue milk is unhealthy, and causes diarrhœa. There are fungi which make milk *bluish-black* or *green*. *Red* and *yellow* milk are produced by a similar action of chromogenic fungi (§ 184). The former is produced by Micrococcus prodigiosus, which is colorless. The color seems to be due to fuchsin. The yellow color is produced by bacillus synxanthus. Some of the pigments seem to be related to the aniline and others to the phenol coloring matters (*Hüppe*).

The **rennet-like action of bacteria** is a widely diffused property of these organisms; they coagulate and peptonize casein and may ultimately produce further decompositions. The butyric acid bacillus (§ 184) first coagulates casein, then peptonizes it, and finally splits it up, with the evolution of ammonia (*Hüppe*)

Milk becomes *stringy* owing to the action of cocci which form a stringy substance [= *dextran*, $C_{12}H_{10}O_{10}$ (*Scheibler*)], just as beer or wine undergoes a similar or ropy change. [The milk of diseased animals may contain or transmit directly infectious matter.]

Preparations of Milk.—(1) **Condensed milk**—80 grms. cane sugar are added to 1 litre of milk; the whole is evaporated to $\frac{1}{3}$; and while hot sealed up in tin cans. For children one teaspoonful is dissolved in a pint of cold water, and then boiled.

(2) **Koumiss** is prepared by the Tartars from mare's milk. After the addition of koumiss and sour milk, the whole is violently stirred, and it undergoes the alcoholic fermentation, whereby the milk sugar is first changed into galactose, and then into alcohol; so that koumiss contains 2 to 3 per cent. of alcohol; while the casein is at first precipitated, but is afterwards partly re-dissolved and changed into acid albumin and peptone. Tartar koumiss seems to be produced by the action of a special bacterium (Diaspora caucasia).

(3) **Cheese** is prepared by coagulating milk with rennet, allowing the whey to separate, and adding salt to the curd. When kept for a long time cheese "**ripens**," the casein again becomes soluble in water, probably from the formation of soda albuminate; in many cases it becomes semi-fluid, when it takes the characters of peptones. When further decomposition occurs, leucin and tyrosin are formed. The fats increase at the expense of the casein, and they again undergo further change, the volatile fatty acids giving the characteristic odor. The formation of peptone, leucin, tyrosin, and the decomposition of fat recall the digestive processes. [Cheese is coagulated casein entangling more or less fat, so that the richness of the cheese will depend upon the kind of milk from which it is made. There are, in this sense, three kinds of cheese, *whole milk*, *skimmed milk*, and *cream* cheese, the last being represented by Stilton, Roquefort, Cheshire, etc. The composition is shown in the following table, after Bauer:—

	Water.	Nitrogenous Matter.	Fat.	Extractives.	Ash.
Cream cheese, . .	35.75	7.16	30.43	2.53	4.13
Whole milk, . . .	46.82	27.62	20.54	2.97	3.05
Skim milk, ...	48.02	32.65	8.41	6.80	4.12

Cream cheese, especially if it be made from goat's milk, acquires a very high odor and strong flavor when it is kept and "**ripens**"; the casein is partly decomposed to yield ammonia and ammonium sulphide, while the fats yield butyric, caproic, and other acids]

232. EGGS must be regarded as a complete food, as the organism of the young chick is developed from them. The **yolk** contains a characteristic proteid body—*vitellin* (§ 249), and an *albuminate* in the envelopes of the yellow yolk spheres—*nuclein*, from the white yolk; *fats* in the yellow yolk (palmitin, olein), cholesterin, much *lecithin*; and as its decomposition product, glycerin-phosphoric acid—*grape sugar*, *pigments* (lutein), and a body containing iron and related to hæmoglobin;

lastly, *salts* qualitatively the same as in blood—quantitatively as in the *blood corpuscles*—and *gases*. The chief constituent of the **white of egg** is *egg albumin* (§ 249), together with a small amount of palmitin and olein partly saponified with soda; grape sugar, extractives; lastly salts, qualitatively resembling those of blood, but quantitatively like those of *serum*, and a trace of fluorine. Relatively more of the nitrogenous constituents than of the fatty constituents of eggs are absorbed (*Rubner*).

[The **shell** is composed chiefly of mineral matter (91 per cent. of calcic carbonate, 6 per cent. of calcic phosphate, and 3 per cent. of organic matter.) A hen's egg weighs about 1¾ oz., of which the shell forms about $\frac{1}{10}$. Note the amount of **fats** in the yolk.]

Composition :—

	White of Egg.	Yolk.
Water,	84.8	51.5
Proteids,	12.0	15.0
Fats, etc.,	2.0	30.0
Mineral matter,	1.2	1.4
Pigment extractives,	...	2.1

233. **FLESH AND ITS PREPARATIONS.—Flesh**, in the form in which it is eaten, contains in addition to the muscle substance proper, more or less of the elements of fat, connective and elastic tissue mixed with it (§ 293). The following results refer to flesh freed as much as possible from those constituents. The chief proteid constituent of the contractile muscular substance is **myosin**; *serum albumin* occurs in the fluid of the fibres, in the lymph and blood of muscle. The *fats* are for the most part derived from the interfascicular fat cells, while *lecithin* and *cholesterin* come from the nerves of the muscles; the *gelatin* is derived from the connective tissue of the perimysium, perineurium, and the walls of blood vessels and tendons. The *red color* of the flesh is due to the hæmoglobin present in the sarcous substance, but in some muscles, *e. g.*, the heart, there is a special pigment, myohæmatin (*MacMunn*). *Elastin* occurs in the sarcolemma, neurilemma, and in the elastic fibres of the perimysium and walls of the vessels; the small amount of *keratin* is derived from the endothelium of the vessels. The chief muscular substance, the result of the retrogressive metabolism of the sarcous substance, is *kreatin* (—0.05 per cent.); *kreatinin*, the inconstant *inosinic acid*, then lactic, or rather *sarcolactic acid* (§ 293). Further, *taurin*, *sarkin*, *xanthin*, *uric acid*, *carnin*, *inosit* (most abundant in the muscles of drunkards), *urea* (0.1 per cent.) *dextrin* (in horse or rabbit, not constant); *grape sugar*, but this is very probably derived *post-mortem* from glycogen (0.43 per cent.), which occurs in considerable amount in fœtal muscles; lastly *fatty acids*. Among the **salts**, potash and phosphoric acid compounds are most abundant; magnesium phosphate exceeds calcium phosphate in amount. [The composition varies somewhat even in different muscles of the same animal.]

In 100 parts **Flesh** there are, according to Schlossberger and v. Bibra—

	Ox.	Calf.	Deer.	Pig.	Man.	Fowl.	Carp.	Frog.
Water	77 50	78.20	74.63	78 30	74.45	77.30	79.78	80.43
Solids,	22.50	21.80	25.37	21.70	25.55	22.7	20.22	19.57
Soluble albumin,	2.20	2.60	1.94	2.40	1.93	3.0	2.35	1.86
Coloring matter,							...	...
Glutin,	1.30	1.60	0.50	0.80	2.07	1.2	1.98	2.48
Alcoholic extract,	1.50	1.40	4.75	1.70	3.71	1.4	3.47	3.46
Fats,	...	...	1.30	...	2.30	...	1.11	0.10
Insoluble albumin, Blood vessels, etc.,	17.50	16.2	16.81	16.81	15.54	16.5	11.31	11.67

In 100 parts **Ash** there are—

	Horse.	Ox.	Calf.	Pig.
Potash,	39.40	35 94	34.40	37.79
Soda,	4.86	...	2 35	4.02
Magnesia,	3.88	3.31	1.45	4 81
Chalk,	1.80	1.73	1.99	7.54
Potassium,	...	5.36	...	...
Sodium,	1.47	...	10.59	0.40
Chlorine,		4 86		0.62
Iron oxide,	1.0	0.96	0.27	0.35
Phosphoric Acid,	46.74	34.36	48.13	44.47
Sulphuric "	0.30	3.37	...	...
Silicic "	...	2.07	0.81	...
Carbonic "	...	8.02	...	...
Ammonia,	...	0.15	...	...

The **amount of fat** in flesh varies very much according to the condition of the animal. After removal of the visible fat, human flesh contains 7.15; ox, 11.12; calf, 10.4; sheep, 3.9; wild goose, 8.8; fowl, 2.5 per cent.

The amount of **extractives** is most abundant in those animals which exhibit energetic muscular action; hence it is largest in wild animals. The extract is increased after vigorous muscular action, whereby sarcolactic acid is developed, and the flesh becomes more tender and is more palatable. Some of the extractives excite the nervous system, *e. g.*, kreatin and kreatinin; and others give to flesh its characteristic agreeable flavor ["osmasome,"] but this is also partly due to the different fats of the flesh, and is best developed when the flesh is cooked. The extractives in 100 parts of flesh are, in man and pigeon, 3; deer and duck, 4; swallow, 7 per cent.

Cooking of Flesh.—As a general rule, the flesh of *young* animals, owing to the sarcolemma, connective tissue, and elastic constituents being less tough, is more tender and more easily digested than the flesh of old animals; after flesh has been kept for a time it is more friable and tender, as the inosit becomes changed into sarcolactic acid and the glycogen into sugar, and this again into lactic acid, whereby the elements of flesh undergo a kind of maceration. Finely divided flesh is more digestible than when it is eaten in large pieces. In cooking meat, the heat ought not to be too intense, and ought not to be continued too long, as the muscular fibres thereby become hard and shrink very much. Those parts are most digestible which are obtained from the centre of a roast where they have been heated to 60° to 70° C., as this temperature is sufficient, with the aid of the acids of the flesh, to change the connective tissue into gelatin, whereby the fibres are loosened, so that the gastric juice readily attacks them. In roasting beef, apply heat suddenly at first, to coagulate a layer on the surface, which prevents the escape of the juice.

Meat Soup is best prepared by cutting the flesh into pieces and placing them for several hours in cold water, and afterward boiling. Liebig found that 6 parts per 100 of ox flesh were dissolved by cold water. When this cold extract was boiled, 2.95 parts were precipitated as coagulated albumin, which is chiefly removed by "skimming," so that only 3.05 parts remain in solution. From 100 parts of flesh of fowl, 8 parts were extracted, and of these 4.7 was coagulated and 3.3 remained dissolved in the soup. By boiling for a very long time, part of the albumin may be redissolved. The dissolved substances are: (1) Inorganic salts of the meat, of which 82.27 per cent. pass into the soup; the earthy phosphates chiefly remain in the cooked meat. (2) Kreatin, kreatinin, the inosinates and lactates which give to broth or beef tea their stimulating qualities, and a small amount of aromatic extractives. (3) Gelatin, more abundantly extracted from the flesh of young animals. According to these facts, therefore, flesh broth or beef-tea is a powerful stimulant, supplying muscle with re-toratives, but is not a food in the ordinary sense of the term, as kreatin in general leaves the body unchanged (*v. Voit*). The flesh, especially if it be cooked in a large mass, after the extraction of the broth is still available as a food.

Liebig's Extract of Meat is an extract of flesh evaporated to a thick syrupy consistence. It contains no fat or gelatin, and is chiefly a solution of the extractives and salts of flesh.

[**Extract of Fish.**—A similar extract is now prepared from fish, and such extract has no fishy flavor, but presents much the same appearance, odor, and properties as extract of flesh.]

234. **VEGETABLE FOODS.**—The nitrogenous constituents of plants are not so easily absorbed as animal food (*Rubner*). Carbohydrates, starch, and sugar are very completely absorbed, and even a not inconsiderable proportion of cellulose may be digested. The more fats that are contained in the vegetable food, the less are the carbohydrates digested and absorbed.

1. The **cereals** are most important vegetable foods; they contain proteids, starch, salts, and water about 14 per cent. The nitrogenous body **glutin** is most abundant under the husk (Fig. 236, *c*). The use of whole meal containing the outer layers of the grain is highly nutritive, but bread containing much bran is somewhat indigestible (*Rubner*). Their composition is the following:—

100 Parts of the Dry Meal contain			100 Parts of Ash contain		
Of	Albumin.	Starch.	Red Wheat.		White Wheat.
Wheat, ...	16.52%	56.25%	27.87	**Potash,**	33.84
Rye, ...	11.92	60.91	15.75	Soda, ...	...
Barley, ...	17.70	38.31	1.93	Lime, ...	3.09
Maize, ...	13.65	77.74	9.60	Magnesia	13.54
Rice, ...	7.40	86.21	1.36	Iron oxide	0.31
Buckwheat, . . .	6.8–10.5	65.05	49.36	**Phosphoric Acid,**	59.21
			0.13	Silica, ...	...

It is curious to observe that soda is absent from white wheat, its place being taken by other alkalies. Rye contains more cellulose and dextrin than wheat, but less sugar; rye bread is usually less porous.

[**Oatmeal** contains more nitrogenous substances (gliadin and glutin-casein) than wheaten flour, but owing to the want of adhesive properties it cannot be made into bread. The amount of fat and salts is large.]

In the preparation of bread the meal is kneaded with water until dough is formed, and to it is added salt and *yeast* (Saccharomycetes cerevisiæ). When placed in a warm oven, the proteids of the meal begin to decompose and act as a ferment upon the swollen-up starch, which becomes in part changed into sugar. The sugar is further decomposed into CO_2 and alcohol, the CO_2 forms bubbles, which cause the bread to "rise" and thus become spongy and porous. The alcohol is driven off by the baking (200°), while much soluble dextrin is formed in the crust of the bread. [But CO_2 may be set free within the dough by chemical means, without yeast or leaven, thus forming **unfermented bread.** This is done by mixing with the dough an alkaline carbonate and then adding an acid. Baking powders consist of carbonate of soda and tartaric acid. In Daughlish's process for **aerated** bread, the CO_2 is forced into water, and a dough is made with this water under pressure, and when the dough is heated, the CO_2 expands and forms the spongy bread. Bread as an article of food is deficient in N, while it is poor in fats and some salts. Hence the necessity for using some form of fat with it (butter or bacon).]

FIG. 236.



Microscopic characters of wheat (+ 200). *a*, cells of the bran; *b*, cells of thin cuticle; *c*, glutin cells; *d*, starch cells.

2. The **pulses** contain **much albumin**, *especially* **legumin**; together with starch, lecithin, cholesterin, and 9 to 19 per cent. water. Peas contain 18.02 proteids, and 34.81 starch; beans 28.54, and 37.50; lentils, 29.31, and 40, and more cellulose. Owing to the absence of glutin they do not form dough, and bread cannot be prepared from them. On account of the large amount of proteids which they contain, they are admirably adapted as food for the poorer classes.

[3. The whole group of **farinaceous** substances used as "pudding stuffs," such as corn-flour, arrow-root, rice, hominy, are really very largely composed of starchy substances.]

4. **Potatoes** contain 70 to 81 per cent. water. In the fresh juicy cellular tissue, which has an acid reaction, from the presence of phosphoric, malic, and hydrochloric acids, there is 16 to 23 per cent. of starch, 2.5 soluble albumin, globulin, and a trace of asparagin. The envelopes of the cells swell up by boiling, and are changed into sugar and gums by dilute acids. The poisonous solanin

occurs in the sprouts. In 100 parts of *potato ash*, May found 49.96 potash, 2.41 sodium chloride, 8.11 potassium chloride, 6.50 sulphuric acid derived from burned proteids, 7.17 silica.

5. In **fruits** the chief nutrient ingredients are sugar and salts; the organic acids give them their characteristic taste; the gelatinizing substance is the soluble so-called **pectin** ($C_{32}H_{48}O_{32}$), which can be prepared artificially by boiling the very insoluble pectose of unripe fruits and mulberries.

6. **Green Vegetables** are especially rich in salts, which resemble the salts of the blood; thus, dry salad contains 23 per cent. of salts, which closely resemble the salts of the blood. Of much less importance are the starch, cell substance, dextrin, sugar, and the small amount of albumin which they contain.

[Vegetables are chiefly useful for the salts they contain, while many of them are **antiscorbutic.** Their value is attested by the serious defects of nutrition, such as scurvy, which result when they are not supplied in the food. In Arctic expeditions and in the navy, lime juice is served out as an anti-scorbutic.]

[**Preserved Vegetables.**—The dried and compressed vegetables of Messrs. Chollet & Company are an excellent substitute for fresh vegetables, and are used largely in naval and military expeditions.]

[**Utilization of Food.**—As regards what percentage of the food swallowed is actually absorbed, we know that, stated broadly, vegetable food is assimilated to a much less extent than animal food in man. Fr. Hofmann gives the following table as showing this:—

Weight of Food.	Vegetable.		Animal.	
	Digested.	Undigested.	Digested.	Undigested.
Of 100 parts of solids, ...	75 5	24.5	89 9	11.1
" 100 " albumin, ...	46.6	53.4	81.2	18.8
" 100 " fats or carbohydrates, . .	90 3	9.7	96.9	3.1]

[The following table, abridged from Parkes, shows the composition of the chief articles of diet, and is also used for calculating diet tables:—

Articles.	Water.	Proteids.	Fats.	Carbo-hydrates.	Salts.
Beef steak, ...	74.4	20.5	3.5	...	1.6
Fat pork, ...	39.0	9 8	48.9	...	2.3
Smoked ham, ...	27.8	24.0	36.5	...	10.1
White fish, ...	78.0	18.1	2.9	...	1.0
Poultry, ...	74.0	21.0	3.8	...	1.2
White wheaten bread, ...	40.0	8.0	1.5	49.2	1.3
Wheat flour, ...	15.0	11.0	2.0	70.3	1.7
Biscuit, ...	8.0	15.6	1.3	73.4	1.7
Rice, ...	10.0	5.0	0.8	83.2	0.5
Oatmeal, ...	15.0	12.6	5.6	63.0	3.0
Maize, ...	13.5	10.0	6.7	64.5	1 4
Macaroni, ...	13.1	9.0	0.3	76.8	0.8
Arrow root, ...	15 4	0.8	...	83.3	0.27
Peas (dry), ...	15.0	22.0	2.0	53.0	2.4
Potatoes, ...	74.0	2 0	0.16	21,0	1.0
Carrots, ...	85.0	1.6	0.25	8.4	1.0
Cabbage, ...	91.0	1.8	5.0	5.8	0.7
Butter, ...	6.0	0.3	91.0	...	2.7
Egg ($\frac{1}{10}$ for shell), ...	73.5	13.5	11.6	...	1.0
Cheese, ...	36 8	33.5	24.3	...	5 4
Milk (S. G. 1032), ...	86.8	4.0	3.7	4.8	0.7
Cream, ...	66.0	2.7	26.7	2.8	1.8
Skimmed milk, ...	88.0	4.0	1.8	5.4	0.8
Sugar, ...	3.0	...	...	96.5	0.5]

235. **CONDIMENTS, COFFEE, TEA, ALCOHOL.**—Some substances are used along with food, not so much on account of their nutritive properties as on account of their stimulating effects and agreeable qualities, which are exerted partly upon the organ of taste and partly upon the nervous system. These are called **condiments.**

Coffee, Tea, and **Chocolate** are prepared as infusions of certain vegetables [the first of the roasted berry, the second of the leaves, and the third of the seeds.] Their chief active ingredients are respectively **caffein, thein** ($C_8H_{10}N_4O_2 + H_2O$), and **theobromin** ($C_7H_8N_4O_2$), which are regarded as alkaloids of the vegetable bases, and which have recently been prepared artificially from xanthin (*E. Fischer*). [**Guarana,** or Brazilian cocoa, is made of the seeds ground into a paste in the form of a sausage. **Maté** or Paraguay tea (the leaves of a species of holly) is used in South America, and so also is the **coca** of the Andes (Erythroxylon Coca).] These "alkaloids" occur as such in the plants containing them; they behave like ammonia; they have an alkaline reaction, and form crystalline salts with acids. All these vegetable bases act upon the nervous system; some more feebly (as the above), others more powerfully (quinine); some stimulate powerfully, or completely paralyze (morphia, atropin, strychnin, curarin, nicotin).

Effects.—All these substances act on the nervous system; they quicken thought, accelerate movement, and stir one to greater activity. In these respects they resemble the stimulating extractives of beef tea. Coffee contains about ⅓ per cent. of caffein, part of which only is liberated by the act of roasting. Tea has 6 per cent. of thein; while green tea contains 1 per cent. ethereal oil, and black tea ½ per cent.; in green tea there is 18 per cent., in black 15 per cent. tannin; green tea yields about 46 per cent., and the black scarcely 30 per cent. of extract. The **inorganic salts** present are also of importance; tea contains 3.03 per cent. of salts, and among these are soluble compounds of iron, manganese, and soda salts. In coffee, which yields 3.41 per cent. of ash, potash salts are most abundant; in all three substances the other salts which occur in the blood are also present.

Alcoholic drinks owe their action chiefly to the **alcohol** which they contain. Alcohol, when taken into the body, undergoes certain changes and produces certain effects: (1) About 95 per cent. of it is oxidized chiefly into CO_2 and H_2O, so that it is so far a source of heat. As it undergoes this change very readily when taken to a certain extent, it may act as a substitute for the consumption of the tissues of the body, especially when the amount of food is insufficient. [Hammond found that when he lived on an insufficient amount of food, alcohol, if given in a certain quantity, supplied the place of the deficiency of food, and he even gained in weight. If, however sufficient food was taken, alcohol was unnecessary. As it interferes with oxidation, and where there is a sufficient amount of other food, in health, it is unnecessary, for dietetic reasons.] Small doses diminish the decomposition of the proteids to the extent of 6 to 7 per cent. Only a very small part of the alcohol is excreted in the urine; the odor of the breath is not due to alcohol, but to other volatile substances mixed with it, *e. g.*, fusel oil, etc. (2) In small doses it excites, while in large doses it paralyzes the nervous system. By its stimulating qualities it excites to greater action, which, however, is followed by depression. (3) It diminishes the sensation of hunger. (4) It excites the vascular system, accelerates the circulation, so that the muscles and nerves are more active, owing to the greater supply of blood. It also gives rise to a subjective feeling of warmth. In large doses, however, it paralyzes the vessels, so that they dilate, and thus much heat is given off (§ 213, 7; § 227). The action of the heart also becomes affected, the pulse becomes smaller, feebler, and more rapid. In high altitudes the action of alcohol is greatly diminished, owing to the diminished atmospheric pressure, whereby it is rapidly given off from the blood.

Alcohol in small doses is of great use in conditions of **temporary want,** and where the food taken is insufficient in quantity. When alcohol is taken regularly, more especially in large doses, it affects the nervous system, and undermines the physical and corporeal faculties, partly from the action of the impurities which it may contain, such as fusel oil, which has a poisonous effect upon the nervous

system, partly by the direct effects, such as catarrh and inflammation of the digestive organs, which it produces, and lastly, by its effect upon the normal metabolism.

[The action of alcohol in **lowering the temperature**, even in moderate doses, is most important. By dilating the cutaneous vessels, it thus permits of the radiating of much heat from the blood. When the action of alcohol is pushed too far, and especially when this is combined with the action of great cold, its use is to be condemned. Brunton has pointed out that, as regards its action on the **nervous system**, it seems to induce progressive paralysis, affecting the nervous tissues "in the inverse order of their development, the highest centres being affected first and the lowest last." The *judgment* is affected first, although the imagination and "emotions may be more than usually active." The *motor centres* and *speech* are affected, then the cerebellum is influenced, and afterward the cord, while by and by the centres essential to life are paralyzed, provided the dose be sufficiently large.]

Preparation.—Alcoholic drinks are prepared by the **fermentation** of various carbohydrates, such as sugar derived from starch. The alcoholic fermentation, such as occurs in the manufacture of beer, is caused by the development of the yeast plant, **Saccharomycetes cerevisiæ**; while in the fermentation of the grape (wine), S. Ellipsoideus is the species present (Fig. 237). The yeast takes the substances necessary for the maintenance of its organic processes directly from the mixture of the sugar, viz., carbohydrates, proteids and salts, especially calcium and potassium phosphates and magnesium sulphate. These substances undergo decomposition within the cells of the yeast plant, which multiply during the process, and there are produced alcohol and CO_2 (⅔ 150), together with glycerine (3.2 to 3.6 per cent.) and succinic acid 0.6 to 0.7 per cent.). Yeast is either added intentionally or it reaches the mixture from the air, which always contains its spores. When yeast is completely excluded, or if it be killed by boiling [or if its action be prevented by the presence of some germicide], the fermentation does not occur. The alcoholic fermentation is due to the activity of a low organism.

FIG. 237.



1, Isolated yeast cells; 2, 3, yeast cells budding; 4, 5, so-called endogenous formation of cells; 6, sprouting and formation of buds.

In the preparation of **brandy**, the starch of the grain or potatoes is first changed into sugar by the action of diastase or maltin. Yeast is added, and fermentation thereby produced; the mixture is distilled at 78.3°C. The fusel oil is prevented from mixing with the alcohol by passing the vapor through heated charcoal. The distillate contains 50 to 55 per cent. of alcohol.

In the preparation of **wine**, the saccharine juice of the grape — the **must** — after being expressed from the grapes, is exposed to the air at 10° to 15° C., and the yeast cells, which are floating about, drop into it and excite fermentation, which lasts 10 to 14 days, when the yeast sinks to the bottom. The clear wine is drawn off into casks, where it becomes turbid by undergoing an after-fermentation, until the sugar is converted into alcohol and CO_2, which is accompanied by the deposition of some yeast and tartar. If all the sugar is not decomposed—which occurs when there is not sufficient nitrogenous matter present to nourish the yeast—a *sweet wine* is obtained. Wine contains 89 to 90 per cent. water, 7 to 8 per cent. alcohol, together with æthylic, propylic, and butylic alcohol. The red color of some wines is due to the coloring matter of the skin of the grapes, but if the skins be removed before fermentation, red grapes yield white wine. When wine is stored, it develops a fine flavor or bouquet, The characteristic vinous odor is due to **œnanthic ether**. The *salts* of wine closely resemble the salts of the blood.

In the preparation of **beer** the grain is moistened, and allowed to germinate, when the temperature rises, and the starch (68 per cent. in barley) is changed into sugar. Thus "**malt**" is formed, which is dried, and afterward pulverized, and extracted with water at 70° to 75°, the watery extract being the "**wort.**" Hops are added to wort, and the whole is evaporated, when the proteids are coagulated. Hops give beer its bitter taste, and make it keep, while their tannic acid precipitates any starch that may be present, and clarifies the wort. After being boiled, it is cooled rapidly (12° C.); yeast is added, and fermentation goes on rapidly and with considerable effervescence at 10° to 14°. Beer contains 75 to 95 per cent. water; alcohol, 2 to 5 per cent. (porter and ale, to 8 per cent.); CO_2, 0.1 to 0.8 per cent.; sugar 2 to 8 per cent.; gum, dextrin, 2 to 10 per cent.; the hops yield traces of protein, fat, lactic acid, ammonia compounds, the salts of the grain and of the hops. In the **ash** there is a great preponderance of phosphoric acid and potash, both of which are of great importance for the formation of blood. In 100 parts of ash there are 40.8 potash, 20.0 phosphorus, magnesium phosphate 20, calcium phosphate 2.6, silica 16.6 per cent. The formation of blood, muscle, and other tissues from the consumption of beer is due to the phosphoric acid and potash, while if too much be taken, the potash produces fatigue.

Condiments are taken with food, partly on account of their taste, and partly because they excite secretion. Common salt, in a certain sense, is a condiment. We may also include many substances of unknown constitution which act upon the gustatory organs, *e. g.*, dextrin, and substances in the crust of bread and in meat which has been roasted.

236. EQUILIBRIUM OF THE METABOLISM.—By this term is meant that, under normal physiological conditions, just as much material is absorbed and assimilated from the food as is removed from the body by the excretory organs in the form of effete or end products, the result of the retrogressive tissue changes. The income must always balance the expenditure; wherever a tissue is used up, it must be replaced by the formation of new tissue. During the period of **growth**, the increase of the body corresponds to a certain increase of formation, whereby the metabolism of the growing parts of the body is 2.5 to 6.3 times greater than that of the parts already formed. Conversely, during senile **decay**, there is an excess of expenditure from the body.

Methods.—The normal equilibrium of the metabolism of the body is investigated (1) By determining chemically that the sum of all the substances passing into the body is equal to the sum of all the substances given off from it. Thus the C, N, H, O, salts and water of the food, and the O inspired, must be equal to the C, N. H, O, salts and water given off in the excreta (urine, fæces, air expired, water excreted). (2) The **physiological equilibrium** is determined empirically by observing that the body retains its normal weight with a given diet; so that, by simply weighing a person, a physician is enabled to determine exactly the state of convalescence of his patient. The tedious process of making an **elementary analysis** of the metallic substances was first undertaken in the Munich School by v. Bischoff, v. Voit, v. Pettenkofer, and others.

Circulation of C.—In the circulation of materials the total amount of C taken in the food, if the metabolism be in a condition of physiological equilibrium, must be equaled by the C in the CO_2 given off by the lungs and skin (90 per cent.), together with the relatively small amount of C in the organic excreta of the urine and fæces (10 per cent.).

Circulation of N.—*Nearly all the N* taken in with the food is excreted within twenty-four hours in the form of urea. A very small amount of nitrogenous matter is excreted in the fæces, while the other nitrogenous urinary constituents (uric acid, kreatinin, etc.) represent about 2 per cent. of N. A trace of the N is given off by the breath (§ 124), and a minute proportion in combination, in the epidermal scales (50 milligrammes daily in the hair and nails), and in the sweat.

Deficit of N.—That nearly all the N taken in the food reappears in the urine and fæces, as was stated by v. Voit to be the case in the carnivora and in the herbivora, and by v. Ranke in man, is contradicted partly by old and partly by new observations, which go to show that the whole of the N cannot be recovered from these excretions, but that on the contrary there is a considerable *deficit*.

According to Leo, only 0.55 per cent. of the albumin transformed within the body (assuming 15 per cent. N in albumin) gives off its N in the form of gaseous N (according to Seegen and Nowak, 12 times more). In every exact analysis of the metabolism of N this gaseous excretion of N must be taken into account.

The **excretion of N** after food does not take place regularly from hour to hour, but it increases at once and distinctly, reaches its maximum in five to six hours, and then gradually falls. The same is true of the excretion of **S** and **P**; but in these cases the maximum of excretion is reached at the fourth hour. When fat is added to a diet of flesh, the excretion of N and S is uniformly distributed over the individual hours of the day (*v. Voit and Feder*).

The nitrogenous constituents in the body during metabolism become poorer in C, and richer in N and O. Thus in **albumin** to 1 atom of N there are 4 atoms C; in **gelatin**, 3½ C; in **glycocoll**, 2 C; in **kreatin**, 1⅓ C; in **uric acid**, 1¼ C; in **allantoin**, 1 C; in **urea**, only ½ atom of C.

The **H** leaves the body chiefly in the form of **water**—a part, however, is in combination in other excreta; the **O** is chiefly excreted as CO_2 and water; a

little is given off in combination in other excreta; **water** is given off by evaporation from the lungs and skin, and also in the urine and fæces. As H is oxidized to H_2O, more water is excreted than is taken in. Most of the readily soluble **salts** are given off by the urine; the less soluble salts, especially those of potash, and the insoluble salts, in the fæces; while others are given off in the sweat. Of the **sulphur** of albumin, about one-half is excreted in the sulphur compounds in the urine, and the other half in the fæces (taurin) and in the epidermal tissues.

Every organism has a **minimum** and a **maximum limit** of **metabolism**, according to the amount of work done by the body, and its weight. If less food be given than is necessary to maintain the former, the body loses weight; while, if more be given after the maximum limit is reached, the food so given is not absorbed, but remains as a floating balance, and is given off with the fæces. When food is liberally supplied and the weight increases, of course the minimum limit rises; hence, during the process of "feeding" or "fattening," the amount of food necessary is very much greater than in poorly fed animals, for the same increase of the body weight. By continuing the process, a condition is at last reached in which the digestive organs are just sufficient to maintain the existing condition, but cannot act so as to admit of new additions being made to the body weight (*v. Bischoff, v. Voit, v. Pettenkofer*).

By the term "**luxus consumption**" is meant the direct combustion or oxidation of the superfluous food stuffs absorbed in the blood. This, however, does not exist; on the contrary, the material in the juices is always being used for building up the tissues. The albumin found in the fluids which everywhere permeate the tissues, has been called "**circulating albumin**," and according to v. Voit it undergoes decomposition sooner than the organized or "**organic albumin**" which forms an integral part of the tissue. According to v. Voit, in 24 hours 1 per cent. of the organic and 70 per cent. of the circulating albumin is used up.

[Liebig taught that the nitrogenous metabolism of the body depended on a corresponding decomposition of the proteids of the organs, so that the proteids in the food supplied the place of the proteids of the organs thus used up. He called the proteids "**plastic foods**" or "**tissue formers**," while he regarded the fats and carbohydrates as "**respiratory foods**," as he supposed that they alone were concerned in the evolution of heat. As a matter of fact, experiment proved that the N metabolism is to a large extent independent of the proteids of the food. The luxus-consumption theory was invented to explain this. It simply means, that proteids taken with the food not only replace the amount of proteids which have been decomposed during the activity of organs and tissues, but that any excess is immediately consumed without being converted into tissue, and thus this surplus amount giving rise to heat, by being oxidized, to a certain extent replaces the fats and carbohydrates. But Voit showed that the nitrogenous metabolism is not influenced by the activity of the organism, and he proved that in ordinary conditions only a small amount of the organic albumin, *i. e.*, that composing tissues and organs, undergoes decomposition, while, owing to the action of the cellular elements of the tissue, a large amount of the circulating albumin is split up, so that under ordinary conditions the organic albumin is comparatively stable. This he demonstrated from a comparison of the urea excreted, for the urea may be taken as an index of the N metabolism in well fed, fasting, and starving animals. But in certain **pathological conditions** the organic albumin may undergo rapid change, having become less stable, as in fevers, and poisoning with phosphorus.]

Quality and Quantity of the Diet.—As far as his organization is concerned, man belongs to the **omnivorous** animals, *i. e.*, those that can live upon a mixed diet. For an **adequate diet** man requires for his existence and to maintain health a mixture of the following **four** chief groups of food stuffs along with the necessary relishes; none of them must be absent from the food for any length of time. They are:—

1. **Water**—for an adult in his food and drink, 2700 to 2800 grms. [70 to 90 oz.] daily (§ 229 and § 247, 1).

[**Thirst.**—The needs of the economy for water are expressed by the sensation of thirst. The sensation of heat and dryness may be confined to the tongue, mouth and fauces, and indeed may be

excited by inhaling dry air. This **local** thirst may be allayed by swallowing water or by eating substances which excite the secretion of saliva. More frequently, however, the sensation is the expression of a **general** condition indicating the diminution of water in the tissues; or it may be due to excess of saline matters in the blood. In some diseases this sensation is very intense, *e.g.*, diabetes. If water be injected into the blood vessels, or stomach, both the general and local thirst are abolished, even although no water enters the mouth.]

FIG. 238.



2. **Inorganic substances** or **Salts** are an integral part of all tissues, without them the tissues cannot be formed. They occur in ordinary food. addition of too much salt increases the consumption of water, and this in t increases the transformation of N in the body. If an animal be deprived of s nutrition is interfered with; food deprived of its lime affects the formation of bones; deprival of common salt causes albuminuria (247, A, III). The alka salts serve to neutralize the sulphuric acid formed by the oxidation of the sulp

of the proteids. **Iron**, which is so essential for the formation of blood, exists in animals and plants in combination with complex organic bodies.

Only in times of famine is man driven to eat large quantities of inorganic substances, to extract the organic matter mixed therewith. A. v. Humboldt states, in regard to the inhabitants of the Orinoco, that they eat a kind of earth which contains innumerable infusoria.

3. At least **one** animal or vegetable albuminous body or **proteid** (§§ 248, 250). The proteids are required to replace the used-up nitrogenous tissues, *e. g.*, for muscles. They contain 15.4 to 16.5 per cent. N.

The **proteids** are in blood = 20.56 per cent.; muscles, 19.9 per cent.; liver, 11.74 per cent.; brain, 8.63 per cent.; blood plasma, 7.5 per cent.; milk, 3.94 per cent.; lymph, 2.46 per cent. According to Pflüger and Bohland, a youth of full stature, and 62 kilos. [136 lbs.] weight, decomposes 89.9 grms. of albumin daily.

Asparagin, in combination with gelatin, can replace albumin in the food (*Weiske*), while asparagin alone limits the decomposition of albumin in herbivora but not in carnivora (*J. Munk*). Ammoniacal salts, glycocoll, sarkosin, and benzamid increase with the amount of albumin in the body.

4. At least **one fat** (§ 251), **or** a digestible **carbohydrate** (§ 252). These chiefly serve to replace the transformed fats and non-nitrogenous constituents. Owing to the large amount of C which they contain, when they undergo oxidation, they form the chief source of the heat of the body (§ 206). Fats and carbohydrates may replace each other in the food, and in inverse proportion too, corresponding to the amount of C which each contains. As far as the mere evolution of heat is concerned, 100 parts of fat = 256 of grape sugar = 234 of cane sugar = 221 of dry starch (*Rubner*). A man consumes 210 grms. fat daily.

[5. Every proper diet ought to have a certain degree of **sapidity** or **flavor.** The substances which give this are not useful in the evolution of energy or building up the tissues, but they stimulate the nervous system and excite secretion. They are called "Genussmittel" (means of enjoying food) by the Germans, but we have no exact equivalent for this word in English, though the articles themselves are included under our expression "condiments." These substances are the aromatic matter in roast meat (osmasome), tea, vinegar, salt, mustard, pepper, etc.]

[**Condition of Diet for Health.**—In an adequate diet, not only (1) should the total quantity be sufficient and not more than sufficient, but (2) the constituents should exist in proper proportions, (3) be digestible, and (4) the whole should be in good condition, wholesome, and not adulterated with any substance prejudicial to health.]

With regard to the **relative proportions** of the various kinds of food which ought to be taken, experience has shown that the diet best suited for the body must contain 1 *part of nitrogenous foods to* 3½ *or, at most,* 4½ *of the non-nitrogenous.* Looking at ordinary foods from this point of view, we see how far they correspond to this requirement, and how several substances may be combined to produce a satisfactory diet.

	Nit.	Non-Nit.
1. Veal,	10	1
2. Hare's flesh,	10	2
3. Beef,	10	17
4. Lentils,	10	21
5. Beans,	10	22
6. Peas,	10	23
7. Mutton,	10	27
8. Pork,	10	30
9. Cow's milk,	10	30
10. Human milk,	10	37
11. Wheaten flour,	10	46
12. Oat meal,	10	50
13. Rye meal,	10	57
14. Barley meal,	10	57
15. White potatoes,	10	86
16. Blue "	10	115
17. Rice,	10	123
18. Buckwheat meal,	10	130

An examination of this table shows that, in addition to human milk, wheat flour has the right proportion of nitrogenous to non-nitrogenous substances. A man who tries to nourish himself on beef alone, commits as great a mistake as the one who would feed himself on potatoes alone. Experience has taught people that man may live upon milk and eggs, but that in addition to flesh we must eat bread or potatoes, while pulses require fat or bacon.

The diet varies with the **climate** and with the **season of the year.** As the organism must produce more heat in cold latitudes, the inhabitants of northern climates must eat more non-nitrogenous foods, such as fats and sugars or starches, which, on account of the large amount of C they contain, are admirably adapted for producing heat (§ 214, I, 4).

The graphic representation of the composition of foods (Fig. 238) shows the

relative proportions of the most important food stuffs, and how they vary from the standard of 1 nitrogenous to 3½ or 4½ non-nitrogenous.

The **absolute amount** of food stuffs required by an adult in twenty-four hours depends upon a variety of conditions. As the food represents the chemical reservoir of potential energy, from which the kinetic energy (in its various forms) and the heat of the body are obtained, the absolute amount of food must be increased when the body loses more heat, as in winter, and when more muscular activity (work) is accomplished. As a general rule *an adult requires daily* **130 grammes proteids, 84 grammes fats, 404 grammes carbohydrates, and 30 grammes salts.**

A HEALTHY ADULT **requires** IN 24 HOURS, OF **water-free** solids—

Food in Grammes.	At Rest. (*Playfair.*)	Moderate Work. (*Moleschott.*)	Laborious Work.	
			(*Playfair.*)	(*v. Pettenkofer and v. Voit.*)
Proteids,	70.87	130	155.92	137
Fats,	28.35	84	70.87	117
Carbohydrates (Sugar, Starch, etc.),	310.20	404	567.50	352
Salts,	14.00	30	40.00	40

[When we record these numbers in **ounces** we get the following results as **water-free solids** required by an average man (*Parkes*):—

	At Rest.	Ordinary Work.	Laborious Work.
Proteids,	2.5	4.6	6 to 7
Fats,	1.0	3.0	3.5 to 4.5
Carbohydrates,	12.0	14.4	16 to 18
Salts,	0.5	1.0	1.2 to 1.5
Total water-free food,	16.0	23.0	26.7 to 31

During ordinary work the proportion is about:—

Proteids 1: fats 0.6: carbohydrates 3.0,

i. e., 1 nitrogenous to 3.6 non-nitrogenous.]

[In a diet for ordinary work (23 oz. of *dry* solids) a man takes about $\frac{1}{100}$ part of his own weight daily; *ordinary food*, however, as it is consumed, contains between 50 and 60 per cent of water; if we add this proportion of water to the actually dry food, we get 48 to 60 oz. of ordinary food (exclusive of liquids). But we consume 50 to 80 oz. of water in some liquid form, making the total amount of water 70 to 90 oz. (*Parkes*).]

The following tables show the elementary composition of the income and expenditure:—

AN ADULT DOING A MODERATE AMOUNT OF WORK **takes in**:—

	C.	H.	N.	O.
120 grammes albumin, containing	64.18	8.60	18.88	28.34
90 " fats, "	70.20	10.26	. .	9.54
330 " starch, "	146.82	20.33	. .	162.85
	281.20	39.19	18.88	200.73

Add 744.11 grm. O from the air by respiration.
" 2818 " H_2O.
" 32 " Inorganic compounds (salts).

The whole is equal to $3\frac{1}{2}$ kilos. [7 lbs.], *i. e.*, about $\frac{1}{20}$ of the body weight; so that about 6 per cent. of the water, about 6 per cent. of the fat, about 1 per cent. albumin, and about 0.4 per cent. of the salts of the body are daily transformed within the organism.

AN ADULT DOING A MODERATE AMOUNT OF WORK **gives off**, in grammes:—

	Water.	C.	H.	N.	O
By respiration,	330	248.8	. .	?	651.15
Perspiration,	660	2.6	. .	. .	7.2
Urine,	1700	9.8	3.3	15.8	11.1
Fæces,	128	20.0	3 0	3.0	12.0
	2818	281.2	6.3	18.8	681.45

Add to this (besides 2818 grammes water as drink) 296 grammes water formed in the body by the oxidation of H. These 296 grammes of water contain 34.89 grms. H, and 263.41 grms. O; 26 grms. of salts are given off in the urine, and 6 by the fæces. 96.5 grms. of proteid (= 1.46 grm. per kilo.) are used up by a resting adult in 24 hours; but while working 107.6 grms. are used. Nominally 2.3 times as much fat as albumin are used up.

The investigations of the Munich School have shown that the following numbers represent the **minimum amount** of food necessary for different ages:—

Age.	Nitrogenous.	Fat.	Carbohydrates.
Child until 1½ years,	20–36 grms.	30–45 grms.	60–90 grms.
" from 6 to 15 years,	70–80 "	37–50 "	250–400 "
Man (moderate work),	118 "	56 "	500 "
Woman, "	92 "	44 "	400 "
Old man,	100 "	68 "	350 "
Old woman,	80 "	50 "	260 "

Small animals have a more lively metabolism than large ones. In small animals the decomposition of albumin per unit weight of body is greater than in large animals (*v. Voit*). Small animals as a rule consume more proteid than larger ones, because they generally have less bodily fat (*Rubner*).

Relation of N to C.—In most of the ordinary articles of diet, nitrogenous and non-nitrogenous substances are present, but in very varying proportion, in the different foods. Man requires that these shall be in the proportion of 1 : $3\frac{1}{2}$ to 1 : $4\frac{1}{2}$. If food be taken in which this proportion is not observed, in order to obtain the necessary amount of that substance which is contained in too small proportion in his food, he must consume far too much food. In order to obtain the **130 grammes of proteids** necessary a person must use

Cheese, ... 388 grms.	Beef, ... 614 grms.	Rice, ... 2562 grms.
Lentils, ... 491 "	Eggs, ... 968 "	Rye bread, . . 2875 "
Peas, ... 582 "	Wheat bread, . . . 1444 "	Potatoes, . . . 10,000 "

provided he were to take only one of these substances as food; so that if a workman were to live on potatoes alone, in order to get the necessary amount of N he would have to consume an altogether excessive amount of this kind of food.

To obtain the **448 grammes of carbohydrates**, or the equivalent amount of fat necessary to support him, a man must eat

Rice, ... 572 grms.	Peas, ... 819 grms.	Cheese, ... 2011 grms.
Wheat bread, . . . 625 "	Eggs, ... 902 "	Potatoes, ... 2039 "
Lentils, ... 806 "	Rye bread, ... 930 "	Beef, ... 2261 "

so that if he were to live upon cheese or flesh alone, he would require to eat an enormous amount of these substances.

In the case of **herbivora**, the proportion of nitrogenous to non-nitrogenous food necessary is 1 of the former to 8 or 9 parts of the latter.

237. HUNGER AND STARVATION.—If a warm-blooded animal be **deprived of all food**, it must, in order to maintain the temperature of its body and to produce the necessary amount of mechanical work, transform and utilize the potential energy of the constituents of its own body. The result is that its body weight diminishes from day to day, until death occurs from starvation.

The following table, from Bidder and Schmidt, shows the amounts of the different excreta in the case of a starved cat:—

Day.	Body weight.	Water taken.	Urine.	Urea.	Inorganic Substances in Urine.	Dry Fæces.	Expired C.	Water in Urine and Fæces.
1.	2464	...	98	7.9	1.3	1.2	13.9	91.4
2.	2297	11.5	54	5.3	0.8	1.2	12.9	50.5
3.	2210	...	45	4.2	0.7	1.1	13	42.9
4.	2172	68.2	45	3.8	0.7	1.1	12.3	43
5.	2129	...	55	4.7	0.7	1.7	11.9	54.1
6.	2024	...	44	4.3	0.6	0.6	11.6	41.1
7.	1946	...	40	3.8	0.5	0.7	11	37.5
8.	1873	...	42	3.9	0.6	1.1	10.6	40
9.	1782	15.2	42	4	0.5	1.7	10.6	41.4
10.	1717	...	35	3.3	0 4	1.3	10.5	34
11.	1695	4	32	2.9	0.5	1.1	10.2	30.9
12.	1634	22.5	30	2.7	0.4	1.1	10.3	29.6
13.	1570	7.1	40	3.4	0.5	0.4	10.1	36.6
14.	1518	3	41	3.4	0.5	0.3	9.7	38
15.	1434	...	41	2.9	0.4	0.3	9.4	38.4
16.	1389	...	48	3	0.4	0.2	8.8	45.5
17.	1335	...	28	1.6	0.2	0.3	7.8	26.6
18.†	1267	...	13	0.7	0.1	0.3	6.1	12.9
	−1197	131.5	733	65.8	9.8	15.7	190.7	734.4

The cat lost 1197 grms. in weight before it died, and this amount is apportioned in the following way: 204.43 grams. (= 17.01 per cent.) loss of albumin; 132.75 grms. (= 11.05 per cent.) loss of fat; 863.82 grms. loss of water (= 71.91 per cent. of the total body weight).

Methods.—In order to investigate the condition of **inanition** it is necessary (1) to weigh the animal daily; (2) to estimate daily all the C and N given off from the body in the fæces, urine, and expired air. The N and C, of course, can only be obtained from the decomposition of tissues containing them.

Among the **general phenomena of inanition**, it is found that strong, well-nourished dogs die after 4 weeks, man after 21 to 24 days—(6 melancholics who took water died after 51 days); small mammals and birds 9 days, and frogs 9 months. Vigorous adults die when they lose $\frac{1}{2}$ of their body weight, but young individuals die much sooner than adults. **The symptoms** are obvious. The mouth is dry, the walls of the alimentary canal become thin, and the digestive secretions cease to be formed; pulse beats and respirations are fewer; urine very acid, from the presence of an increased amount of sulphuric and phosphoric acids, while the chlorine compounds rapidly diminish and almost disappear. The blood contains less water and the plasma less albumin, the gall bladder is distended, which indicates a continuous decomposition of blood corpuscles within the liver. The liver is small and very dark colored, the muscles are very brittle and dry, so that there is great muscular weakness, and death occurs with the signs of great depression and coma.

The relations of the metabolism are given in the foregoing table, the diminution in the excretion of urea is much greater than that of CO_2, which is due to

a larger amount of fats than proteids being decomposed. According to the calculation, there is daily a tolerably constant amount of fat used up, while, as starvation continues, the proteids are decomposed in much smaller amounts from day to day, although the drinking of water accelerates their decomposition.

Loss of Weight of Organs.—It is of importance to determine to what extent the individual organs and tissues lose weight; some undergo simple loss of weight, *e. g.*, the bones, the fat undergoes very considerable and rapid decomposition, while other organs, as the heart, undergo little change, because they seem to be able to nourish themselves from the transformation products of other tissues.

A **starving cat**, according to v. Voit, lost—

	Per cent. originally present.	Per cent. of the total loss of body weight.
1. Fat,	97	26.2
2. Spleen,	66.7	0.6
3. Liver,	53.7	4.8
4. Testicles,	40.0	0.1
5. Muscles,	30.5	42.2
6. Blood,	27.0	3.7
7. Kidneys,	25.9	0.6
8. Skin,	20.6	8.8
9. Intestine,	18.0	2.0
10. Lungs,	17.7	0.3
11. Pancreas,	17.0	0.1
12. Bones,	13.9	5.4
13. Central Nervous System,	3.2	0.1
14. Heart,	2.6	0.02
15. Total loss of the rest of the body,	36.8	5.0

There is a very important difference according as the animals before inanition have been fed freely on flesh and fat [*i. e.*, if they have a surplus store of food within themselves], or as they have merely had a subsistence diet. Well-fed animals lose weight much more rapidly during the first few days than on the later days. V. Voit thinks that the albumin derived from the excess of food occurs in a state of loose combination in the body as "**circulating**" or "*storage albumin*," so that during hunger it must decompose more rapidly and to a greater extent than the "**organic albumin**," which forms an integral part of the tissues (§ 236). Further, in fat individuals, the decomposition of fat is much greater than in slender persons.

238. METABOLISM ON A PURELY FLESH DIET.—A man is not able to maintain his metabolism in equilibrium on a purely flesh diet; if he were compelled to live on such a diet, he would succumb. The reason is obvious. In beef the proportion of nitrogenous to non-nitrogenous elementary constituents of food is 1 : 1.7 (p. 405). A healthy person excretes 280 grammes [8 to 9 oz.] of carbon in the form of CO_2, in the expired air, and in the urine and fæces. If a man is to obtain 280 grammes C. from a flesh diet he must consume—digest and assimilate—more than 2 kilos. [4.4 lbs.] of beef in twenty-four hours. But our digestive organs are unequal to this task for any length of time. The person is soon obliged to take less beef, which would necessitate the using of his own tissues, at first the fatty parts and afterward the proteid substances.

A carnivorous animal (**dog**), whose digestive apparatus, being specially adapted for the digestion of flesh, has a short intestine and powerfully active digestive fluids, can only maintain its metabolism in a state of equilibrium when fed on a flesh diet free from fat, provided its body is already well supplied with fat, and is muscular. It consumes $\frac{1}{25}$ to $\frac{1}{20}$ part of the weight of its body in flesh, so that the excretion of urea increases enormously. If it eats a larger amount, it may "put on flesh," when, of course, it requires to eat more to maintain itself in this condition, until the limit of its digestive capacity is reached. If a well-nourished dog is fed on less than $\frac{1}{25}$ to $\frac{1}{20}$ of its body weight of flesh, it uses part of its own fat and muscle, gradually diminishes in weight, and ultimately succumbs. Poorly fed, non-muscular dogs are unable from the very beginning to maintain their metabolism in equilibrium for any length of time on a purely flesh diet, as they must eat so large a quantity of flesh that their digestive organs cannot digest it. The **herbivora** cannot live upon flesh food, as their digestive apparatus is adapted solely for the digestion of vegetable food.

[The **proteid metabolism** depends (1) on the amount of proteids ingested,

for the great mass of these becomes changed into circulating albumin; (2) upon the previous condition of nutrition of the organism, for we know that a certain amount of proteid may produce very different results in the same individual when he is in good health, and when he has suffered from some exhausting disease. (3) The use of other foods, *e. g.*, fats and carbohydrates. If a certain amount of fat be added to a diet of flesh, much less flesh is required, so that the N metabolism is reduced by fat. This is spoken of as the "**albumin-sparing action**" of fats.]

Exactly the same result occurs with **other forms of proteids**, as with flesh. It has been proved that **gelatin** may to a certain extent replace proteids in the food, in the proportion of 2 of gelatin to 1 of albumin. The carnivora, which can maintain their metabolism in equilibrium by eating a large amount of flesh, can do so with less flesh when gelatin is added to their food. A diet of gelatin alone, which produces much urea, is not sufficient for this purpose, and animals soon lose their appetite for this kind of food.

[**Gelatin.**—Voit has shown that gelatin readily undergoes metabolism in the body and forms urea, and if a small quantity be taken, it is completely and rapidly metabolized. When administered it acts just like fats and carbohydrates, as an "albumin-sparing" substance. It seems that gelatin is not available directly for the growth and repair of tissues.] Owing to the great solubility of gelatin, its value as a food used to be greatly discussed. The addition of gelatin in the form of calf's-foot jelly is recommended to invalids. [When a large amount of gelatin is given as food, owing to the large and rapid excretion of urea, the latter excites diuresis.] When chondrin is given along with flesh for a time, grape sugar is found in the urine.

[The **Metabolism of Peptones.**—Most of the proteids absorbed into the blood are previously converted into peptones by the digestive juices. It has been asserted, more especially by Brücke, that some albumin is absorbed unchanged (§ 192, 4), and that only this is capable of forming organic albumin, while the peptones, after undergoing a reconversion into albumin, undergo decomposition as such. This view is opposed by many observers, who maintain that peptones perform all the functions of proteids, so that peptones, with the other necessary constituents of an adequate diet, suffice to maintain a proper standard of health.]

239. **A DIET OF FAT OR OF CARBOHYDRATES.**—If **fat alone** be given as a food, the animal lives but a short time. The animal so fed excretes even less urea than when it is starving; so that the consumption of fat limits the decomposition of the animal's own proteids. As fat is an easily oxidized body, it yields heat chiefly, and becomes sooner oxidized than the nitrogenous proteids which are oxidized with more difficulty. If the amount of fat taken be very large, all the C of the fat does not reappear, *e. g.*, in the CO_2 of the expired air; so that the body must acquire fat, while at the same time it decomposes proteids. The animal thus becomes poorer in proteids and richer in fats at the same time.

[The **metabolism of fats** is not dependent on the amount of fats taken with the food. 1. It is largely influenced by **work**, *i. e.*, by the activity of the tissues, and in fact with muscular work CO_2 is excreted in greatly increased amount (§ 127, 6). 2. By the **temperature** of the surroundings, as more CO_2 is produced in the cold (§ 214, 2), and far more fatty foods are required in high latitudes. In their action on the organism, proteids and fats so far oppose each other, as the former increase the waste, and therefore oxidation, while the latter diminish it, probably by affecting the metabolic activity of the cells themselves (*Bauer*). As a matter of fact, fat animals or persons bear starvation better than spare individuals. In the latter, the small store of fat is soon used up, and then the albumin is rapidly decomposed. For the same reason corpulent persons are very apt to become still more so, even on a very moderate diet.]

When **carbohydrates alone** are given, they must first be converted by digestion into sugar. The result of such feeding coincides pretty nearly with feeding

with fat alone. But the sugar is more easily burned or oxidized within the body than the fat, and 17 parts of carbohydrate are equal to 10 parts of fat. Thus the diet of carbohydrates limits the excretion of urea more readily than a purely fat diet. The animals lose flesh, and appear even to use up part of their own fat.

[The **metabolism of carbohydrates** also serves to diminish the proteid metabolism, as they are rapidly burned up, and thus "spare" the circulating albumin. But Pettenkofer and Voit assert that they are rapidly destroyed in the body, even when given in large amount, so that they differ from fats in this respect. They are more easily oxidized than fats, so that they are always consumed first in a diet of carbohydrates and fats. By being consumed they protect the proteids and fats from consumption.]

The direct introduction of grape and cane sugar into the blood does not increase the amount of O used, but the amount of CO_2 is increased. [The doctrine of Liebig, that the oxygen taken in is a measure of the metabolic processes, is refuted by these and other experiments. It would seem that fat is not directly oxidized by O, but that it is split up into other simpler compounds which are slowly and gradually oxidized; in fact, fat may lessen the amount of O taken in, as it diminishes waste.]

240. FLESH AND FAT, OR FLESH AND CARBOHYDRATES.—An amount of flesh equal to $\frac{1}{25}$ to $\frac{1}{20}$ of the weight of the body is required to nourish a dog, which is fed on a purely flesh diet; if the necessary amount of fat or carbohydrates be added to the diet, a smaller quantity of flesh is required (*v. Voit*). For 100 parts of fat added to the flesh diet, 245 parts of dry flesh or 227 of syntonin can be dispensed with. If instead of fats carbohydrates are added, then 100 parts of fat = 230 to 250 of the latter (*Rubner*). When the amount of flesh is insufficient, the addition of fat or carbohydrates to the food always limits the decomposition of the animal's own substance. Lastly, when too much flesh is given along with these substances, the weight of the body increases more with them than without them. Under these circumstances, the animal's body puts on more fat than flesh. The **consumption of O** in the body is regulated by the mixture of flesh and non-nitrogenous substances, rising and falling with the amount of flesh consumed. It is remarkable that more O is consumed when a given amount of flesh is taken, than when the same amount of flesh is taken with the addition of fat.

It seems that, instead of fat, the corresponding amount of **fatty acids** has the same effect on the metabolism. [If a dog be fed with fatty acids and a sufficient amount of proteid, no fatty acids are found in the chyle, while fat is formed synthetically, the glycerin for the latter probably being produced in the body.] They are absorbed as an emulsion just like the fats. When so absorbed, they seem to be reconverted into fats in their passage from the intestine to the thoracic duct probably by the action of the leucocytes (*J. Munk, Will*). [**Glycerin** in small doses has no effect on the metabolism of proteid, but in large doses it increases it. It is consumed in the body, as shown by experiments on the respiratory products, and it prevents a certain amount of fat from being used up. About 20 per cent. is excreted in the urine (*Arnschink*).]

241. ORIGIN OF FAT IN THE BODY.—I. *Part* of the fat of the body is derived directly from the fat of the **food**, *i. e.*, it is absorbed and **deposited** in the tissues. This is shown by the fact that, with a diet containing a small amount of albumin, the addition of more fat causes a deposition of a larger amount of fat in the body (*v. Voit, Hofmann*).

[Hofmann starved a fat dog for 30 days until all its fat was used up. He fed it on lard and a little albumin for 5 days and then killed it. In 5 days it absorbed 1854 grms. of fat and 254 grms. of albumin. It added to its body 1353 grms. of fat; but this amount could not be formed from the proteids of the food, and therefore the fat must have come from the fat of the food. Pettenkofer and Voit arrived at the same result in another way. They fed dogs on fish and much fat, and by their respiration apparatus estimated the gaseous income and expenditure (§ 122). *All the N taken in reappeared in the excreta, but not all the C.* The amount of C retained was very large, therefore a non-nitrogenous residue must have been laid up in the body, and it could only be fat, as this was the only substance found in large amount in the body. They estimated the possible amount of

fat that could be formed from the proteids, and found that the amount stored up was far greater than this; so that the fat of the food must have been stored up in the tissues.]

Lebedeff found that dogs, which were starved for a month, so as to get rid of all their own fat, on being fed with linseed oil, or mutton suet and flesh, had these fats restored to their tissues. These fats, therefore, must have been absorbed and deposited. J. Munk found the same on feeding animals with rape-seed oil. Fatty acids may also contribute to the formation of fats, as glycerin when formed in the body must be stored up during metabolism (*J. Munk*).

Fatty acids may contribute to the formation of fats by union with the glycerin of the body during the metabolism.

II. A second source of the fats is albuminous bodies. In the case of the formation of fats from **proteids**, which may yield 11 per cent. of fat (according to Henneberg 100 parts of dry albumin can form 51.5 parts of fat), these proteids split up into a non-nitrogenous and a nitrogenous atomic compound. The former, during a diet containing much albumin, when it is not completely oxidized into CO_2, and H_2O, is the substance from which the fat is formed—the latter leaves the body oxidized chiefly to the stage of urea.

Examples.—That *fats are formed from proteids* is shown by the following: 1. A cow which produces 1 lb. of butter daily does not take nearly this amount of fatty matter in its food, so that the fat would appear to be formed from vegetable proteids. 2. Carnivora giving suck, when fed on plenty of flesh and *some* fat, yield milk rich in fat. 3. Dogs fed with plenty of flesh and some fat, add more fat to their bodies than the fat contained in the food. 4. Fatty degeneration, *e.g.*, of nerve and muscle, is due to a decomposition of proteids. 5. The transformation of entire bodies, *e.g.*, such as have lain for a long time surrounded with water, into a mass consisting almost entirely of palmitic acid or **adipocere** is also a proof of the transformation of part of the proteids into fats. 6. Fungi are also able to form fat from albumin during their growth. [7. In starving dogs, Bauer estimated the N and CO_2 given off, and O taken in, and then slowly poisoned them with phosphorus, and he found that the excretion of N was increased twofold, while the excretion of CO_2 and the absorption of O were diminished one-half. Therefore from a large amount of nitrogenous tissue, a nitrogenous body and a small amount of a carbonaceous compound were excreted, while a large amount of a non-nitrogenous residue was retained unconsumed. There was fatty degeneration of all the organs, the fat being derived from the non-nitrogenous part of the proteid. The same obtains with arsenic and antimony.]

Fats not merely absorbed.—Experiments which go to show that the fat of animals, during the fattening process, is not absorbed as such, from the food, are: 1. Fattening occurs with flesh and soaps; it is most improbable that the soaps are transformed into neutral fats by taking up glycerin and giving up alkali. 2. If a lean dog be fed with flesh and palmitin- and stearin-soda soap, the fat of its body contains, in addition to palmitin and stearin, *olein* fat, so that the last must be formed by the organism from the proteids of the flesh. Further, Ssubotin found that, when a lean dog was fed on lean meat and spermaceti frt, a very small amount of the latter was found in the fat of the animal. Although these experiments show that the fat of the body must be formed from the decomposition of proteids, they do not prove that *all* the fat arises in this way, and that none of it is absorbed and redeposited (§ 241, I).

III. According to v. Voit, no fat is formed in the body directly from **carbohydrates**, *e.g.*, by reduction. As fattening occurs on a diet of pure flesh with the addition of carbohydrates, it is assumed that the carbohydrates are consumed or oxidized in the body, and that thereby a non-nitrogenous body derived from the proteids is prevented from being burned up, and that it is changed into fat, and stored up as such. No doubt fat is formed *indirectly* in the blood in this way (§ 240).

From experiments upon fattening animals, however, Lawes and Gilbert, Lehmann, Heiden, v. Wolff, and others, think they are entitled to conclude that the carbohydrates absorbed are *directly* concerned in the formation of fats, a view which is supported by Henneberg, B. Schulze, and Soxhlet. According to Pasteur, glycerin (the basis of neutral fats) may be formed from carbohydrates.

[Tscherwinsky fed two similar pigs from the same litter; No. I weighed 7300 grms.; No. II 7290 grms. No. I was killed and its fat and proteids estimated. No. II was fed for four months on grain and then killed, the grain and excreta and the undigested fat and proteids were analyzed, so that the amount of fat and proteid absorbed in four months was estimated. The pig then weighed 24 kilos., it was killed and its fat and proteids estimated.

No. II contained	2.50	kilos.	albumin and	9.25	kilos.	fat.
No. I "	0.96	"	"	0.69	"	"
Assimilated,	1.56	"	"	8.56	"	"
Taken in in food,	7.49	"	"	0.66	"	"
Difference,	—5.93	"	"	+7.90	"	"

There were therefore 7.90 kilos of fat in the body which could not be accounted for in the fat of the food. The 5.93 kilos. of albumin of the food which were not assimilated as albumin could yield only a small part of the 7.90 kilos of fat, so that at least 5 kilos. of fat must have been formed from carbohydrates. Lawes and Gilbert calculated that 40 per cent. of the fat in pigs was derived from carbohydrates. How the carbohydrates are changed into fat in the body is entirely unknown.]

Formerly it was believed that bees could prepare wax from honey alone; this is a mistake—an equivalent of albumin is required in addition—the necessary amount is found in the raw honey itself.

242. CORPULENCE —The addition of too much fat to the body is a pathological phenomenon which is attended with disagreeable consequences. With regard to the **causes** of obesity, without doubt there is an **inherited tendency** (in 33 to 56 per cent. of the cases) in many families —and in some breeds of cattle, to lay up fat in the body, while other families may be richly supplied with fat, and yet remain lean. The chief cause, however, is taking **too much food**, *i. e.*, more than the amount required for the normal metabolism; corpulent people, in order to maintain their bodies, must eat absolutely and relatively more than persons of spare habit, under analogous conditions of nutrition (§ 236).

Conditions favoring Corpulence.—(1) A diet rich in *proteids*, with a corresponding addition of *fat* or *carbohydrates*. As flesh or muscle is formed from proteids, and part of the fat of the body is also formed from albumin; the assumption that fats and carbohydrates fatten, or, when taken alone, act as fattening agents, is completely without foundation. (2) *Diminished disintegration* of materials within the body, *e. g.*, (*a*) *diminished muscular activity* (much sleep and little exercise); (*b*) *abrogation of the sexual functions* (as is shown by the rapid fattening of castrated animals, as well as by the fact that some women, after cessation of the menses, readily become corpulent); (*c*) *diminished mental activity* (the obesity of dementia), phlegmatic temperament. On the contrary, vigorous mental work, excitable temperament, care and sorrow, counteract the deposit of fat; (*d*) *diminished extent of the respiratory activity*, as occurs when there is a great deposition of fat in the abdomen, limiting the action of the diaphragm (breathlessness of corpulent people), whereby the combustion of the fatty matters which become deposited in the body is limited; (*e*) a corpulent person requires to use relatively *less heat-giving substances* in his body, partly because he gives off *relatively* less heat from his compact body, than is done by a slender, long-bodied individual, and partly because the thick layer of fat retards the conduction of heat (§ 214, 4). Thus, corresponding to the relatively diminished production of heat, more fat may be stored up; (*f*) a *diminution of the red blood corpuscles*, which are the great exciters of oxidation in the body, is generally followed by an increase of fat—fat people, as a rule, are fat because they have relatively less blood (§ 41)—women with fewer red blood corpuscles are usually fatter than men; (*g*) the *consumption of alcohol* favors the conservation of fat in the body, the alcohol is easily oxidized, and thus prevents the fat from being burned up (§ 235).

Disadvantages.—Besides the inconvenience of the great size and weight of the body, corpulent people suffer from breathlessness—they are easily fatigued, are liable to intertrigo between the folds of the skin, the heart becomes loaded with fat, and they not unfrequently are subject to apoplexy.

In order to **counteract corpulence** we ought to (1) *Reduce uniformly all articles of diet.* The diet and body ought to be weighed from week to week, and as long as there is no diminution in the body weight the amount of food ought to be gradually and uniformly reduced (notwithstanding the appetite). This must be done very gradually and not suddenly. A *moderate* reduction of fat and carbohydrates in a normal diet, at the same time leads to a diminution of the fat of the body itself. Let a person who is capable of muscular exertion take 156 grms. proteid, 43 grms. fat, and 114 grms. carbohydrates; but in those where congestions, hydræmia, breathlessness have taken place, take 170 grms. proteid, 25 grms. fat, and 70 grms. carbohydrates (*Oertel*). It is not advisable to limit the amount of fat and carbohydrates alone, as is done in the **Banting cure** or Bantingism. Apart altogether from the fact that fat is formed from proteids, if too little non-nitrogenous food be taken, severe disturbance of the bodily metabolism is apt to occur. (2) It is advisable during the chief meal to limit the consumption of fluids of all sorts (even until three-quarters of an hour thereafter), and thus render the absorption and digestive activity of the intestine less active (*Oertel*). (3) The *muscular activity* ought to be greatly developed by doing plenty of muscular work, or taking plenty of exercise, both physical and mental. (4) *Favor the evolution of heat* by taking baths of considerable duration, and afterward rubbing the skin strongly so as to cause it to red; further, dress lightly, and at night use light bed-clothing; tea and coffee are useful, as the circulation. (5) Use gentle laxatives; acid fruits, cider; alkaline carbonates (of

Marienbad, Carlsbad, Vichy, Neuenahr, Ems, etc.) act by increasing the intestinal evacuations and diminishing absorption. (6) If from accumulation of fat there is danger of failure of the heart's action, Oertel recommends hill climbing, whereby the cardiac muscle is exercised and strengthened. At the same time the circulation becomes more lively and the metabolism is increased.

[**Oertel's Method** goes on the idea of strengthening the cardiac musculature, which is sought to be accomplished by (1) limiting the amount of fluids consumed, and (2) carefully regulated muscular exertion. The amount of food is first reduced one-half, and the water to a still lower amount, while the nitrogenous elements in food are increased, the non nitrogenous are decreased. The person is then instructed to take exercise under certain medical precautions, first on level ground, and then on gradually increasing gradients.]

Fatty Degeneration.—The process of fattening consists in the deposition of drops of fat within the fat cells of the panniculus and around the viscera, as well as in the marrow of bone (but they are never deposited in the subcutaneous tissue of the eyelids, of the penis, of the red part of the lips, in the ears and nose). This is quite different from the fatty atrophy or **fatty degeneration** which occurs in the form of fatty globules or granules in albuminous tissues, *e. g.*, in muscular fibres (heart), gland cells (liver, kidney), cartilage cells, lymph and pus corpuscles, as well as in nerve fibres separated from their nerve centres. The fat in these cases is derived from albumin, much in the same way as fat is formed in the gland cells of the mammary and sebaceous glands. Marked fatty degeneration not unfrequently occurs after severe fevers, and after artificial heating of the tissues; when a too small amount of O is supplied to the tissues, as occurs in cases of phosphorus poisoning (*Bauer*); in drunkards; after poisoning with arsenic and other substances, and after some disturbances of the circulation and innervation. Some organs are especially prone to undergo fatty degeneration during the course of certain diseases.

243. METABOLISM OF THE TISSUES.—The **blood stream** is the chief medium whereby new material is supplied to the tissues and the effete products removed from them. The **lymph** which passes through the thin capillaries comes into actual contact with the tissue elements. Those tissues which are devoid of blood vessels in their own substance, such as the cornea and cartilage, receive nutrient fluid or lymph from the adjacent capillaries, by means of their cellular elements, which act as juice-conducting media. Hence, when the normal circulation is interfered with, by atheroma or calcification of the walls of the blood vessels, these tissues are secondarily affected [this, for example, is the case in arcus senilis of the cornea, due to a fatty degeneration of the corneal tissue, owing to some affection of the blood vessels on which the cornea depends for its nutrition]. Total compression or ligature of *all* the blood vessels results in necrosis of the parts supplied by the ligatured blood vessels.

Atrophies caused by diminution of the normal supply of blood, gradually, in the course of time become less and less (*Samuel*).

Hence, there must be a *double current* of the tissue juices; the **afferent** or **supply current,** which supplies the new material, and the **efferent stream,** which *removes* the effete products. The former brings *to* the tissues the proteids, fats, carbohydrates, and salts from which the tissues are formed. It is evident that any interruption of the arterial supply to the tissues will diminish this supply.

That such a current exists is proved by injecting an indifferent, easily recognizable substance into the blood, *e.g.*, potassium ferrocyanide, when its presence may be detected in the tissnes, to which it has been carried by the outgoing current.

The **efferent stream** carries away the decomposition products *from* the various tissues, more especially urea, CO_2 H_2O, and salts, and these are transferred as quickly as possible to the organs through which they are excreted.

That such a current exists is proved by injecting such a substance as potassium ferrocyanide into the tissues, *e. g.*, subcutaneously, when its presence may be detected in the urine within two to five minutes.

If the current from the tissues to the blood is so active that the excretory organs cannot eliminate all the effete products from the blood, then these products are found in the tissues. When certain poisons are injected subcutaneously, they pass rapidly into the blood and are carried in great quantity to other tissues, *e. g.*, to the nervous system, on which they act with fatal effect, before they are eliminated

to any great extent from the blood by the action of the excretory organs. The effete materials are carried away from the tissues by *two* channels, viz., by the **veins** and by the **lymphatics**, so that if these be interfered with, the metabolism of the tissues must also suffer. When a limb is ligatured so as to compress the veins and the lymphatics, the efferent stream stagnates to such an extent that considerable swelling of the tissues or œdema may occur (§ 203). The action of the muscles and fasciæ are very important in removing these effete matters.

H. Nasse found that the blood of the jugular vein is 0.225 per 1000 specifically heavier than the blood of the carotid, and contains 0.9 parts per 1000 more solids; 1000 cubic centimetres of blood circulating through the head yield about 5 cubic centimetres of transudation into the tissues.

The **extent and intensity of the metabolism** of the tissues depend upon a variety of factors.

1. Upon their **activity.**—The increased activity of an organ is indicated by the increased amount of blood going to it, and by the more active circulation through it (§ 100). When an organ is completely inactive, such as a paralyzed muscle, or the peripheral end of a divided nerve, the amount of blood and the nutritive exchange of fluid diminish within these parts. The parts thus thrown out of activity become pale, relaxed, and ultimately undergo fatty degeneration. The increased metabolism of an organ during its activity has been proved experimentally in the case of **muscle**, and [(§ 263) also in the brain (*Speck*)]. Langley and Sewell have recently observed directly the metabolic changes within sufficiently thin lobules of **glands** during life. The cells of serous glands (§ 143), and those of mucous, and pepsin-forming glands (§ 164), during quiescence, become filled with coarse granules, which are dark in transmitted light and white in reflected light, which granules are consumed or disappear during granular activity. During **sleep**, when most organs are at rest, the metabolism is limited, darkness also diminishes it; while **light** excites it, obviously owing to nervous influences. The variations in the total metabolism of the body are reflected in the excretion of CO_2 (§ 127, 9) and urea (§ 257), which may be expressed graphically in the form of a curve corresponding with the activity of the organism; this curve corresponds very closely with the daily variations in the respirations, pulse, and temperature (p. 374).

2. The **composition of the blood** has a marked effect upon the current on which the metabolism of the tissues depends. Very **concentrated** blood, which contains a small amount of water, as after profuse sweating, severe diarrhœa, cholera, makes the tissues dry, while if much water be absorbed into the blood, the tissues become more succulent and even œdema occur. When much common salt is present in the blood, and when the red blood corpuscles contain a diminished amount of O, and especially if the latter condition be accompanied by muscular exertion causing dyspnœa, a large amount of albumin is decomposed, and there is a great formation of urea. Hence, exposure to a rarefied atmosphere is accompanied by increased excretion of urea. Certain abnormal conditions of the blood produce remarkable results; blood charged with *carbonic oxide* cannot absorb O from the air, and does not remove CO_2 from the tissues (§ 16). The presence of *hydrocyanic acid* in the blood (§ 16) is said to interrupt at once the chemical oxidation processes in the blood, so that rapid asphyxia, owing to cessation of the *internal* respiration, occurs. Fermentation is interrupted by the same substance in a similar way. A *diminution of the total amount* of the blood causes more fluid to pass from the tissues into the blood, but the absorption of substances—such as poisons or pathological effusions—from the tissues or intestines is delayed. If the substances which pass from the tissues into the blood be rapidly eliminated from it, absorption takes place more rapidly.

3. The **blood pressure**, when it is greatly increased, causes the tissues to contain more fluid, while the blood itself becomes more concentrated, to the extent of 3 to 5 per 1000. We may convince ourselves that blood plasma easily passes

through the capillary wall, by pressing upon the efferent vessel coming from the chorium deprived of its epidermis, *e. g.*, by a burn or a blister, when the surface of the wound becomes rapidly suffused with plasma. Diminution of the blood pressure produces the opposite result. The oxidation processes in the body are diminished after the use of P, Cu, ether, chloroform, and chloral.

4. **Increased temperature of the tissues** (several hours daily) does not increase the breaking up of albumin and fats. (See §§ 220, 221, 225.)

5. The **influence of the nervous system** on the metabolism is twofold. On the one hand, it acts indirectly through its effect upon the blood vessels, by causing them to contract or dilate through the agency of **vasomotor nerves**, whereby it influences the amount of blood supplied, and also affects the blood pressure. But quite independently of the blood vessels, it is probable that certain special nerves—the so-called **trophic nerves**—influence the metabolism or nutrition of the tissues (§ 342, *c*). That nerves do influence directly the transformation of matter within the tissues is shown by the secretion of saliva resulting from the stimulation of certain nerves, after cessation of the circulation (§ 145), and by the metabolism during the contraction of bloodless muscles. Increased respiration and apnœa are not followed by increased oxidation (*Pflüger*) (§ 127, 8).

[Gaskell has raised the question as to the existence of **katabolic** and **anabolic nerves** controlling respectively the analytic and synthetic metabolism of the tissues.]

244. **REGENERATION.**—The extent to which lost parts are replaced varies greatly in different organs. Among the *lower animals*, the parts of organs are replaced to a far greater extent than among warm-blooded animals. When a hydra is divided into two parts, each part forms a new individual—nay, if the body of the animal be divided into several parts in a particular way, then each part gives rise to a new individual (*Spallanzani*). The Planarians also show a great capability of reproducing lost parts (*Dugès*). Spiders and crabs can reproduce lost feelers, limbs, and claws; snails, part of the head, feelers, and eyes, provided the central nervous system is not injured. Many fishes reproduce fins, even the tail fin. Salamanders and lizards can produce an entire tail, including bones, muscles, and even the posterior part of the spinal cord; while the triton reproduces an amputated limb, the lower jaw, and the eye. This reproduction necessitates that a small stump be left, while total extirpation of the parts prevents reproduction. In amphibians and reptiles the regeneration of organs and tissues, as a whole, takes place after the type of the embryonic development, and the same is true as regards the histological processes which occur in the regenerated tail and other parts of the body of the earth-worm.

The extent to which regeneration can take place in mammals and in man is very slight, and even in these cases it is chiefly confined to young individuals. A true regeneration occurs in—

1. The **blood**, including the plasma, the colorless and colored corpuscles. (§ 7 and § 41.)

2. The **epidermal appendages** (§ 283) and the **epithelium** of the mucous membranes are reproduced by a proliferation of the cells of the deeper layers of the epithelium, with simultaneous division of their nuclei. Epithelial cells are reproduced as long as the matrix on which they rest and the lowest layer of cells are intact. When these are destroyed cell regeneration from below ceases, and the cells at the margins are concerned in filling up the deficiency. Regeneration, therefore, either takes place from below or from the margins of the wound in the epithelial covering; leucocytes also wander into the part, while the deepest layer of cells forms large multi-nucleated cells, which reproduce by division polygonal flat nucleated cells. [In the process of division of the cells, the nucleus plays an important part, and in so doing it shows the usual karyokinetic figures (§ 431).] The **nails** grow from the root forward; those of the fingers in four to five months, and that of the great toe in about twelve months, although growth is slower in the case of fracture of the bones. The matrix is co-extensive with the *lunule*, and if it be destroyed the nail is not reproduced (§ 284). The **eyelashes** are changed in 100 to 150 days, the other hairs of the body somewhat more slowly. If the papilla of the hair follicle be destroyed, the hair is not reproduced. Cut-

ting the hair favors its growth, but hair which has been cut does not grow longer than uncut hair. After hair has grown to a certain length, it falls out. The hair never grows at its apex. The **epithelial cells** of mucous membranes and secretory glands seem to undergo a regular series of changes and renewal. The presence of secretory cells in the milk (§ 231) and in the sebaceous secretion (§ 285) proves this; the spermatozoa are replaced by the action of spermatoblasts. In **catarrhal conditions** of mucous membranes, there is a great increase in the formation and excretion of new epithelium, while many cells are but indifferently formed and constitute mucous corpuscles. The **crystalline lens**, which is just modified epithelium, is reorganized like epithelium; its matrix is the anterior wall of its capsule, with the single layer of cells covering it. If the lens be removed and this layer of cells retained, these cells proliferate and elongate to form lens fibres, so that the whole cavity of the empty lens capsule is refilled. If much water be withdrawn from the body, the lens fibres become turbid. [A turbid or opaque condition of the lens may occur in diabetes, or after the transfusion of strong common salt or sugar solution into a frog.]

3. The **blood vessels** undergo extensive regeneration, and they are regenerated in the same way as they are formed (§ 7, B). Capillaries are always the first stage, and around them the characteristic coats are added to form an artery or a vein. When an artery is injured and permanently occluded, as a general rule the part of the vessel up to the nearest collateral branch becomes obliterated, whereby the derivatives of the endothelial lining, the connective-tissue corpuscles of the wall, and the leucocytes change into spindle-shaped cells, and form a kind of cicatricial tissue. Blind and solid outshoots are always found on the blood vessels of young and adult animals, and are a sign of the continual degeneration and regeneration of these vessels. **Lymphatics** behave in the same way as blood vessels; after removal of a lymphatic gland, a new one may be formed (*Bayer*).

4. The **contractile substance of muscle** may undergo regeneration after it has become partially degenerated. This takes place after amyloid or wax-like degeneration, such as occurs not unfrequently after typhus and other severe fevers. This is chiefly accomplished by an increase of the muscle corpuscles. After being compressed, the muscular nuclei disappear, and at the same time the contractile contents degenerate. After several days, the sarcolemma contains numerous nuclei which reproduce new muscular nuclei and the contractile substance. In fibres injured by a subcutaneous wound, Neumann found that, after five to seven days, there was a bud-like elongation of the cut ends of the fibres, at first without transverse striation, but with striation ultimately. If a large extent of a muscle be removed, it is replaced by cicatricial connective tissue. **Non-striped** muscular fibres are also reproduced; the nuclei of the injured fibres divide after becoming enlarged, and exhibit a well-marked intra-nuclear plexus of fibrils. The nuclei divide into two, and from each of these a new fibre is formed, probably by the differentiation of the perinuclear protoplasm.

5. After a **nerve** is divided, the two ends do not join at once so as to permit the function of the nerve to be established. On the contrary, marked changes occur. If a piece be cut out of a nerve trunk, the peripheral end of the divided nerve degenerates, the axial cylinder and the white substance of Schwann disappear. The interval is filled up at first with juicy cellular tissue. The subsequent changes are fully described in § 325, 4. There seems to be in peripheral nerves a continual disappearance of fibres by fatty degeneration, accompanied by a consecutive formation of new fibres (*Sigm. Mayer*). The regeneration of peripheral **ganglionic cells** is unknown. v. Voit, however, observed that a pigeon, part of whose brain was removed, had within five months reproduced a nervous mass within the skull, consisting of medullated nerve fibres and nerve cells. Eichhorst and Naunyn found that in young dogs, whose spinal cord was divided between the dorsal and lumbar regions, there was an anatomical and physiological regeneration, to such an extent

that voluntary movements could be executed (§ 338, 3). Vaulair, in the case of frogs, and Masius in dogs, found that mobility or motion was first restored, and afterward sensibility. Regeneration of the spinal ganglia did not occur.

6. In many **glands**, the regeneration of their cells during normal activity is very active—sebaceous, mucous, Lieberkühnian, uterine, mammary glands during pregnancy—in others less. If a large portion of a **secretory gland** be removed, as a general rule, it is not reproduced. A gland, if injured, and if suppuration follows, is not regenerated. But the **bile ducts** (§ 173) and the **pancreatic** duct may be reproduced (§ 171). According to Philippeaux and Griffini, if part of the **spleen** be removed it is reproduced (§ 103). Tizzoni and Collucci observed the formation of new liver cells and bile ducts after injury to the **liver** (§ 173), and Pisenti makes the same statement as regards the **kidney.** After **mechanical injury** to the secretory cells of glands (liver, kidney, salivary, Meibomian), neighboring cells undergo proliferation and aid in the restoration of the cells.

7. Among connective tissues, **cartilage,** provided its perichondrium be not injured, reproduces itself by division of its cartilage cells; but usually when a part of a cartilage is removed, it is replaced by connective tissue.

8. When a **tendon** is divided, proliferation of the tendon cells occurs, and the cut ends are united by connective tissue.

9. The reproduction of **bone** takes place to a great extent under certain conditions. If the articular end be removed by excision, it may be reproduced, although there is a considerable degree of shortening. Pieces of bone which have been broken off or sawn off heal again, and become united with the original bone. A **tooth** may be removed, replanted in the alveolus, and become fixed there. If a piece of **periosteum** be transplanted to another region of the body, it eventually gives rise to the formation of new bone in that locality. If part of a bone be removed, provided the periosteum be left, new bone is rapidly reproduced; hence, the surgeon takes great care to preserve the periosteum intact in all operations where he wishes new bone to be reproduced. Even the **marrow** of bone, when it is transplanted, gives rise to the formation of bone. This is due to the osteoblasts adhering to the osseous tissue.

In **fracture of a long bone,** the periosteum deposits on the surface of the ends of the broken bones a ring of substance which forms a temporary support, the **external callus.** At first this callus is jelly-like, soft, and contains many corpuscles, but afterward it becomes more solid and somewhat like cartilage. A similar condition occurs within the bone, where an **internal callus** is formed. The formation of this **temporary callus** is due to an inflammatory proliferation of the connective-tissue corpuscles, and partly to the osteoblasts of the periosteum and marrow. According to Rigal and Vignal, the internal callus is always osseous, and is derived from the marrow of the bone. The outer and inner callus become calcified and ultimately ossified, whereby the broken ends are reunited. Toward the fortieth day a thin layer of bone is formed (**intermediary callus**) between the ends of the bone. Where this begins to be definitely ossified, the outer and inner callus begin to be absorbed, and ultimately the intermediary callus has the same structure as the rest of the bone.

There are many interesting observations connected with the **growth and metabolism of bones.** 1. The addition of a very small amount of *phosphorus* or *arsenious acid* to the food causes considerable thickening of the bones. This seems to be due to the non-absorption of those parts of the bones which are usually absorbed, while new growth is continually taking place. 2. When food *devoid of lime salts* is given to an animal, the growth of the bones is not arrested, but the bones become thinner, whereby all parts, even the organic basis of the bone, undergo a uniform diminution. 3. Feeding with **madder** makes the bones red, as the coloring matter is deposited with the bone salts in the bone, especially in the growing and last formed parts. In birds the shell of the egg becomes colored. 4. The continued use of *lactic acid* dissolves the bones. The ash of bone is thereby diminished. If lime salts be withheld at the same time, the effect is greatly increased, so that the bones come to resemble rachitic bones. (Development of Bone, § 447.)

When a lost tissue is not replaced by the same kind of tissue, its place is always taken by **cicatricial connective tissue.**

When this is the case, the part becomes inflamed and swollen, owing to an exudation of plasma. The blood vessels become dilated and congested, and, notwithstanding the slower circulation, the

amount of blood is greater. The blood vessels are increased, owing to the formation of new ones. Colorless blood corpuscles pass out of the vessels and reproduce themselves, and many of them undergo fatty degeneration, while others take up nutriment and become converted into large uninucleated protoplasm cells, from which giant cells are developed. The newly formed blood vessels supply all these elements with blood.

245. **TRANSPLANTATION OF TISSUES.**—The nose, ear, and even a finger, after having been severed from the body by a clean cut, have, under certain circumstances, become united to the part from which they were removed. The **skin** is frequently transplanted by surgeons, as, for example, to form a new nose. The piece of skin is cut from the forehead or arm, to which it is left attached by a bridge of skin, is then stitched to the part which it is desired to cover in, and when it has become attached in its new situation, the bridge of skin is severed. Reverdin cut a piece of skin into pieces about the size of a pea and fixed them on an ulcerated surface, where they, as it were, took root, grew, and sent off from their margins epithelial outgrowths, so that ultimately the whole surface was covered with epithelium. [White skin transplanted to a negro ultimately becomes pigmented, and black skin transplanted to a white person becomes white.] The excised *spur* of a cock was transplanted and fixed in the comb of the same animal, where it grew (*John Hunter*). P. Bert cut off the tail and legs of rats and transplanted them under the skin of the back of other rats, where they united with the adjoining parts. Ollier found that, when **periosteum** was transplanted, it grew and reproduced bone in its new situation. Even blood and lymph may be transfused (Transfusion, § 102.) [Small portions (1.5 mm.) of epiphyses, costal cartilage, of a rabbit or kitten, when transplanted quite fresh into the anterior chamber of the eye, testis, sub-maxillary gland, kidney, and under the skin of a rabbit, attach themselves and grow, and the growth is more rapid the more vascular the site on which the tissue is transplanted. The cartilage is not essentially different from hyaline cartilage, but the cells are fewer in the centre, while the matrix tends to become fibrous. Small pieces of epiphyseal cartilage introduced into the jugular vein were found as cartilaginous foci in the lungs. Tissues transplanted from embryonic structures grow far better than adult tissues. If a portion of the **cornea** of a rabbit be transplanted to a human eye, provided Descemet's membrane be clear, it will grow and remain clear (*v. Hippell*). A rabbit's nerve has been transplanted to the human subject, but without success.]

Many of these results seem only to be possible between individuals of the *same species*, although Helferich has recently found that a piece of a dog's muscle, when substituted for human muscle, united to the adjoining muscle, and became functionally active. [J. R. Wolfe has transplanted the conjunctiva of the rabbit to the human eye.] Most tissues, however, do not admit of transplantation, *e.g.*, glands and the sense organs. They may be removed to other parts of the body, or into the peritoneal cavity, without exciting any inflammatory reaction; they, in fact, behave like inert foreign matter.

246. **INCREASE IN SIZE AND WEIGHT.**—The **length of the body**, which at birth is usually $\frac{1}{3.5}$ of the adult body, undergoes the greatest elongation at an early period: in the first year, 20; in the second, 10; in the third, about 7 centimetres; while from five to sixteen years the annual increase is about 5½ centimetres. In the twentieth year the increase is very slight. From fifty onward the size of the body diminishes, owing to the intervertebral disks becoming thinner, and the loss may be 6 to 7 centimetres about the eighteenth year. The **weight of the body** ($\frac{1}{20}$ of an adult) sinks during the first five to seven days, owing to the evacuation of the meconium and the small amount of food which is taken at first. Only on the tenth day is the weight the same as at birth.

Age.	Length (Cmtr.).		Weight (Kilo.).		Age.	Length (Cmtr.).		Weight (Kilo.).	
	Man.	Woman.	Man.	Woman.		Man.	Woman.	Man.	Woman.
0	49.6	48.3	3.20	2.91	15	155.9	147.5	46.41	41.30
1	69.6	69.0	10.00	9.30	16	161.0	150.0	53.39	44 44
2	79.6	78.0	12.00	11.40	17	167.0	154.4	57.40	49.08
3	86.0	85.0	13.21	12.45	18	170.0	156.2	61.26	53.10
4	93.2	91.0	15.07	14.18	19	170.6	...	63.32	...
5	99.0	97.0	16.70	15.50	20	171.1	157.0	65.00	54.46
6	104.6	103.2	18.04	16.74	25	172.2	157.7	68.29	55.08
7	111.2	109.6	20.16	18.45	30	172.2	157.9	68.90	55.14
8	117.0	113.9	22.26	19.82	40	171.3	155.5	68.81	56.65
9	122.7	120.0	24.09	22.44	50	167.4	153.6	67.45	58.45
10	128.2	124.8	26.12	24.24	60	163.9	151.6	65.50	56.73
11	132.7	127.5	27.85	26.25	70	162.3	151.4	63.03	53.72
12	135.9	132.7	31.08	30.54	80	161.3	150.6	61.22	51.52
13	140.3	138.6	35.32	34.65	90	...	...	57.83	49.34
14	148.7	144.7	40.50	38.10	(Chiefly from Quetelet.)				

The increase of weight is greater in the same time than the increase in length. Within the first year a child trebles its weight. The greatest weight is usually reached about forty, while toward sixty a decrease begins, which at eighty may amount even to 6 kilos. The results of measurements, chiefly by Quetelet, are given on the preceding page.

Between the twelfth and fifteenth years the weight and size of the girl are greater than of the boy. Growth is most active in the last months of fœtal life, and afterward from the sixth to the ninth year until the thirteenth to the sixteenth. The full stature is reached about thirty, but not the greatest weight.

GENERAL VIEW OF THE CHEMICAL CONSTITUENTS OF THE ORGANISM.

247. (A) INORGANIC CONSTITUENTS.—I. Water forms 58.5 per cent. of the whole body, but it occurs in different quantity in the different tissues. The kidneys contain the most water, 82.7 per cent.; bones, 22 per cent.; teeth, 10 per cent.; white enamel contains the least, 0.2 per cent. (§ 229). According to some observers, *peroxide of hydrogen* (H_2O_2) is also present in the body.

[Approximately, **water** forms about two-thirds of the weight of the body, so that a body weighing .75 kilos. (165 lbs.) contains .50 kilos. (110 lbs.) of water. The following table, modified from Beaunis, shows the percentage of water in several tissues and organs:—

Solids.

Tissue or Organ.	Water.	Solids.	Tissue or Organ.	Water.	Solids.	Tissue or Organ.	Water.	Solids.
Enamel,	.2	99.8	Spinal Cord,	69.7	30.3	Thymus,	77.0	23 0
Dentine,	10.0	90.0	White matter of brain,	70.0	30.0	Connective tissue,	79.6	20 4
Bone,	48.6	51.4	Skin,	72.0	28.0	Kidney,	82.7	17.3
Fat,	29.9	70.1	Brain,	75.0	25.0	Gray matter of brain,	85.8	14.2
Elastic tissue,	49.6	50.4	Muscles,	75.7	24.3			
Cartilage,	55.0	45.0	Spleen,	75.8	24.2	Vitreous humor,	98.7	1 3
Liver,	69.3	30.7						

Liquids.

Blood,	79 1	20.9	Lymph,	95.8	4.2	Aqueous humor,	98 6	1.4
Bile,	86.4	13 6	Serum,	95.9	4.1	Cerebro-spinal fluid,	98.8	1.2
Milk,	89.1	10.9	Gastric juice,	97.3	2.7			
Liquor sanguinis,	90.1	9.9	Intestinal juice,	97.5	2.5	Saliva,	99.5	0.5
Chyle,	92.8	7 2	Tears,	98.2	1.8	Sweat,	99.5	0 5

II. Gases.—O, – ozone (§ 37) – H, – N – CO_2 (§ 38). Marsh gas CH_4 (§ 124), NH_3 (§ 30, § 124. § 184), H_2S (§ 184).

III. Salts.—Sodium chloride [is one of the most important inorganic substances present in the body. It occurs in all the tissues and fluids of the body, and plays a most prominent part in connection with the diffusion of fluids through membranes, and its presence is necessary for the solution of the globulins (p. 424). Sometimes it exists in a state of combination with proteid bodies, as in the blood plasma. Common salt is absolutely necessary for one's existence; if it be withdrawn entirely, life soon comes to an end. About 15 grammes are given off in the twenty-four hours, chiefly by the urine. Boussingault showed that the addition of common salt to the food of cattle greatly improved their condition.]

[**Calcium phosphate** ($Ca_3P_2O_8$) is the most abundant salt in the body, as it forms more than one-half of our bones; but it also occurs in dentine, enamel, and to a much less extent in the other solids and fluids of the body. Among secretions, milk contains relatively the largest amount (2.72 per cent.). In milk it is necessary for forming the calcareous matter of the bones of the infant. It gives bones their hardness and rigidity. It is chiefly derived from the food, and, as only a small quantity is given off in the excretions, it seems not to undergo rapid removal from the body.]

[**Sodium phosphate** (PNa_3O_4), *acid sodium phosphate* (PNa_2HO_4), *acid potassium phosphate* (PK_2HO_4). The sodium phosphate and the corresponding potash salt give most of the fluids of the body their alkaline reaction. The alkaline reaction of the blood plasma is partly due to alkaline phosphates, which are chiefly derived from the food. The acid sodium phosphate is the chief cause of the acid reaction of the urine. A small quantity of phosphoric acid is formed in the body owing to the oxidation of lecithin, which contains phosphorus.]

[**Sodium carbonate** (Na_2CO_3) and **sodium bicarbonate** ($NaHCO_3$) exist in small quantities in the food, and are formed in the body from the decomposition of the salts of the vegetable acids.

They occur in the blood plasma, where they play an important part in carrying the CO_2 from the tissues to the lungs.]

[**Sodium and potassium sulphates** (Na_2SO_4 and K_2SO_4) exist in very small quantity in the body, and are introduced with the food, but part is formed in the body from the oxidation of organic bodies containing sulphur.]

[**Potassium chloride** (KCl) is pretty widely distributed, and occurs specially in muscle, colored blood corpuscles, and milk. **Calcium fluoride** ($CaFl_2$) occurs in small quantity in bones and teeth. **Calcium carbonate** ($CaCO_3$) is associated with calcium phosphate in bone, tooth, and in some fluids, but it occurs in relatively much smaller amount. It is kept in solution by alkaline chlorides, or by the presence of free carbonic acid. **Ammonium chloride** (NH_4Cl).—Minute traces occur in the gastric juice and the urine. **Magnesium phosphate** (Mg_3PO_4) occurs along with calcium phosphate, but in very much smaller quantity.]

Table, by Beaunis, of the relative proportions of **Salts.**

	Heintz.	Staffel.	Breed.	Oidtmann.	C. Schmidt	Oidtmann.
	Bone.	Muscle of calf.	Brain.	Liver.	Lungs.	Spleen.
Sodic chloride,	. .	10.59	4.74	. .	13.0	. .
Potassic chloride,	. .	. .	. .	. .	. .	. .
Soda,	. .	2.35	10.69	14.51	19 5	44.33
Potash,	. .	34.40	34.42	25.23	1.3	9.60
Lime,	37.58	1.99	0 72	3.61	1.9	7.48
Magnesia,	1.22	1.45	1.23	0.20	1.9	0.49
Ferric oxide,	. .	. .	. .	2.74	3.2	7.28
Chlorine,	. .	. .	. .	2.58	. .	0.54
Fluorine	1.66	. .	. .	. .	. .	. .
Phosphoric acid (free),	. .	. .	9.15	. .	. .	. .
Phosphoric acid (combined)	53 31	48.13	39.02	50 18	48.5	27.10
Sulphuric acid,	. .	. .	0.75	0 92	1.4	2 54
Carbon dioxide,	5 47	. .	. .	. .	. .	. .
Silicic acid;	. .	0 81	0.12	0.27	. .	0 17
Ferric phosphate,	. .	. .	1.23	. .	. .	. .

Table, by Beaunis, of the Mineral Matter in Animal Fluids.

	Verdeil.	Weber.	Weber.	Dahnhardt.	Porter.	Wilderstein.	Rose.	Porter.
	Blood.	Blood serum.	Blood.	Lymph.	Urine.	Bulk.	Bile.	Faces.
Sodic chloride,	58.81	72.88	17.36	74.48	67.28	10.73	27.70	4.33
Potassic chloride,	. .	. .	29 87	. .	. .	26.33	. .	. .
Soda,	4.15	12 93	3.55	10.35	1.33	. .	36.73	5.07
Potash,	11.97	2.95	22.36	3.25	13.64	21.44	4.80	6.10
Lime,	1.76	2.28	2.58	0.97	1.15	18.78	1.43	26.40
Magnesia,	1.12	0.27	0.53	0.26	1.34	0.87	0.53	10.54
Ferric oxide,	8.37	0.26	10.48	0.50	. .	0.10	0.33	2.50
Phosphoric acid,	10.23	1.73	10.64	1 09	11.21	19.00	10.45	36.03
Sulphuric acid,	1.67	2.10	0.09	. .	. .	2.64	6.39	. .
Carbon dioxide,	1.19	4.40	2.17	8.20	. .	. .	11.26	. .
Silicic acid,	. .	0.20	0.42	1.27	4.06	. .	0.36	3.13

IV. Free Acids.—**Hydrochloric acid** (HCl) [occurs *free* in the gastric juice, but in combination with the alkalies it is widely distributed as chlorides]. **Sulphuric acid** (H_2SO_4) [is said to occur free in the saliva of certain gasteropods, as Dolium galea. In the body it forms sulphates, chiefly in combination with soda and potash].

V. Bases.—**Silicon** as silicic acid (SiO_2); **manganese, iron,** the last forms an integral constituent of hæmoglobin; **copper** (?), (§ 174).

248. (B) **ORGANIC COMPOUNDS.**—I. The Albuminous or Proteid Substances.—(1) **True Proteids and their allies** are composed of **C, H, O, N,** and **S,** and are derived from plants (see *Introduction*). [The formation of albumin from the elements is accomplished only by plants. What the chemical processes are is quite unknown. We only know that the N is in the first instance obtained from the nitric acid or ammonia of the soil. The former is probably not used directly as such, but serves, perhaps, for the formation of amides or amido acids, from which, by the action of non-nitrogenous bodies, proteids are formed.]

[According to Hoppe Seyler their general percentage composition is—

	O.	H.	N.	C.	S.
From	20.9	6.9	15.2	51.5	0.3
To	23.5	to 7.3	to 17.0	to 54.5	to 2.0.]

They exist in almost all animal fluids and tissues partly in the fluid form, although Brücke maintains that the molecule of albumin exists in a condition midway between a state of imbibition and a true solution—and partly in a more concentrated condition. Besides forming the chief part of muscle, nerve and gland, they occur in nearly all the fluids of the body, including the blood, lymph, and serous fluids, but in *health* mere traces occur in the sweat, while they are absent from the bile and the urine. Unboiled **white of egg** is the type. In the alimentary canal they are changed into peptones. The chief products derived from their oxidation within the body are CO_2, H_2O, and especially **urea**, which contains nearly all the N of the proteids.

Constitution.—Their chemical constitution is quite unknown. The N seems to exist in two distinct conditions, partly loosely combined, so as to yield ammonia readily when they are decomposed, and partly in a more fixed condition. According to Pflüger, part of the N in *living* proteid bodies exists in the form of cyanogen. [Loew supports Pflüger's view that the molecule of living (active) albumin differs from that of dead albumin, as he finds that the living protoplasm of certain algæ can reduce silver in very dilute alkaline solutions, which dead protoplasm cannot do.] The proteid molecule is very large, and is a very complex one; a small part of the molecule is composed of substances from the group of *aromatic* bodies (which become conspicuous during putrefaction), the larger part of the molecule belongs to the *fatty* bodies; during the oxidation of albumin fatty acids especially are developed. *Carbohydrates* may also appear as decomposition products. For the decompositions during digestion see § 170, and during putrefaction § 184. The proteids form a large group of closely related substances, all of which are perhaps modifications of the same body. When we remember that the infant manufactures most of the proteids of its ever-growing body from the casein in milk, this last view seems not improbable.

Characters.—Proteids, the anhydrides of peptones (§ 166) are **colloids** (§ 191), and therefore do not diffuse easily through animal membranes; they are amorphous and do **not crystallize,** and hence are isolated with difficulty; some are soluble, others are insoluble in water; insoluble in alcohol and ether; rotate the ray of polarized light to the *left;* when burned they give the odor of burned horn. Various metallic salts and alcohol precipitate them from their solution; they are **coagulated** by heat, mineral acids, and the prolonged action of alcohol. Caustic alkalies dissolve them (yellow), and from this solution they are precipitated by acids. By powerful oxidizing agents they yield carbamic acid, guanidin, and volatile fatty acids.

Decomposition.—[The number and varieties of these products are exceedingly great, so that it is not easy to separate the several products. In the first place, there is great difficulty in getting in sufficient quantity a perfectly pure proteid, wherewith to institute the necessary experiments. The decomposition products of albumin when acted on by barium hydrate have been most fully investigated. The action of concentrated HCl, potassic permanganate, and bromine has also been studied. The action of the animal or vegetable digestive ferments is very important (§ 170), and especially that of bacteria causing putrefaction (§ 184).] When acted upon in a suitable manner by acids and alkalies, they give rise to the decomposition products—leucin (10 to 18 per cent.), tyrosin (0.25 to 2 per cent.), aspartic acid, glutamic acid, and also volatile fatty acids, benzoic and hydrocyanic acids, and aldehydes of benzoic and fatty acids; also indol (*Hlasiwetz, Hebermann*). Similar products are formed during pancreatic digestion (§ 170) and during putrefaction (§ 184). [Although it is assumed that the proteids have the closest relation to urea, no one, so far, has succeeded in preparing urea by the direct decomposition of albumin. Both by the action of acids and barium hydrate, the splitting up into simpler compounds does not take place at once, but by successive stages, on to the formation of different bodies. Proteids, when fully decomposed, either by acids or alkalies, yield as the final products ammonia, and amido acids; by alkalies also carbonic, acetic, and oxalic acids. The amido acids contain several series including leucin, tyrosin, and glutamic acid. But all proteids do not yield these three bodies, for tyrosin may be absent, while leucin, so far, has been always found. It has therefore been attempted to classify proteids into those that yield tyrosin (*i.e.*, aromatic compounds) and those that do not. Classes I–VII, p. 424, yield when decomposed aromatic bodies (tyrosin, indol, phenol), while gelatin-yielding bodies and spongin yield no aromatic bodies.]

General Reactions.—(1) **Xanthoproteic Reaction.**—Heated with strong nitric acid they give a *yellow,* the addition of ammonia gives a deep orange color.

(2) With **Millon's reagent** they give a precipitate, and when heated with this reagent above

60° C. they give a *red* one, probably owing to the formation of tyrosin. [If the proteids are present in large amount, a red precipitate occurs, but if mere traces are present only the fluid becomes red.]

(3) The addition of a few drops of a dilute solution of **cupric sulphate**, and the subsequent addition of **caustic potash** or soda, give a *violet* color, which depends on boiling; [the same color is obtained by adding a few drops of Fehling's solution (**biuret reaction**)].

(4) They are precipitated after strong acidulation by acetic acid and by potassium ferrocyanide.

(5) When boiled with concentrated hydrochloric acid, they give a violet-red color (**Liebermann's reaction**).

(6) Sulphuric acid containing molybdic acid gives a blue color (*Fröhde*).

(7) Their solution in acetic acid is colored violet with concentrated sulphuric acid, and shows the absorption band of hydrobilirubin (*Adamkiewicz*).

(8) Iodine is a good microscopic reagent, which strikes a brownish yellow, while sulphuric acid and cane sugar give a purplish violet (*E. Schultze*).

[(9) When rendered strongly acid with acetic acid and boiled with an equal volume of a concentrated solution of sodic sulphate, they are precipitated. This method is used for removing proteids from other liquids, as it does not interfere with the presence of other substances. Saturation with sodio-magnesic sulphate precipitates the proteids, but not peptones, and the same is the case with saturation with neutral ammonia sulphate (§ 249).]

[(10) The precipitation of albumin by *acids* is more delicate when the acid is dissolved in alcohol containing 10 per cent. of ether; the precipitate is not dissolved by an excess of the reagent.]

[(11) Most of them are *precipitated* by strong mineral acids, and metaphosphoric acid, tannic acid (in an acid solution), phospho-wolframic and phospho-molybdic acids (in acid solution); potassio-mercuric iodide (in acid solutions); many metallic salts, *e.g.*, of Cu, Pb, Ag, Hg; chloral, phenol, trichloracetic acid, picric acid, alcohol. Taurocholic acid precipitates albumin and syntonin, but not peptone or hemi-albumose (§ 275).]

249. **THE ANIMAL PROTEIDS AND THEIR CHARACTERS.—Class I.—Native Albumins** occur in a natural condition in animal solids and fluids. They are **soluble in water**, and are not precipitated by alkaline carbonates, NaCl, or by very little dilute acids. Their solutions are coagulated by heating at 65° to 73° C. Dried at 40° C., they yield a clear, yellow, amber-colored, friable mass, "**soluble albumin**," which is soluble in water.

(1) **Serum albumin** (§ 32 and § 41).—[Its specific rotatory power is —56°.] Almost all its salts may be removed from it by dialysis, when it is no longer coagulated by heat. It is coagulated by strong alcohol; and not very readily precipitated by hydrochloric acid, while the precipitate so formed is easily dissolved on adding more acid. When precipitated it is readily soluble in strong nitric acid. It is not coagulated when shaken up with ether. The addition of water to the hydrochloric solution precipitates acid albumin. For its presence in urine, see § 264.

(2) **Egg albumin.**—When injected into the blood vessels or under the skin, or even when introduced in large quantity into the intestine, part of it appears unchanged in the urine (§ 192, 4, and § 264). When shaken with ether it is precipitated. These two reactions serve to distinguish it from (1). The specific rotation is —35.5°, *i. e.*, for yellow light. Amount of S, 1.6 per cent.

(**Metalbumin and Paralbumin** have been found by Scherer in ropy solutions in ovarian cysts; they are only partially precipitated by heat. The precipitate thrown down by the action of strong alcohol is soluble in water.)

Class II.—Globulins are native proteids, **insoluble in distilled water**, but **soluble in dilute neu ral saline solutions**, *i.e.*, neutral solutions of the alkalies and alkaline earths, *e.g.*, NaCl, KCl, NH_4Cl, $MgSO_4$, (but not Na_2CO_3, Na_2HPO_4), sodium chloride of 1 per cent., and in magnesium sulphate. These solutions are coagulated by heat, and are precipitated by the addition of a large quantity of water. Most of them are *precipitated* from their sodium chloride solution by the addition of crystals of sodium chloride, and also *by saturating their neutral solution at 30° with crystals of magnesium sulphate.* When acted upon by dilute acids they yield acid albumin, and by dilute alkalies, alkali albumin.

(1) **Globulin** (Crystallin) is obtained by passing a stream of CO_2 through a watery extract of the crystalline lens.

(2) **Vitellin** is the chief proteid in the yolk of egg. It is also said to occur in the chyle (?) and in the amniotic fluid (*Weyl*). Both the foregoing are not precipitated from their neutral solutions by saturation with sodium chloride.

(3) **Paraglobulin** or **Serum globulin** (§ 29), and in urine (§ 264).

(4) **Fibrinogen** (§ 29).—In the clear jelly-like secretion of the vesiculæ seminales of the guinea pig, there is a globulin-like body closely resembling fibrinogen. It contains 29 per cent. of albumin, with scarcely any ash. If it be touched with a trace of blood serum, without mixing them, it gradually and completely forms a solid mass quite like fibrin.

(5) **Myosin** is the chief proteid in dead muscle. Its coagulation in muscle *post-mortem* constitutes rigor mortis. If muscle be repeatedly washed, and afterward treated with a 10 per cent. solution of sodium or ammonium chloride, it yields a viscid fluid which, when dropped into a large

quantity of distilled water, gives a white flocculent precipitate of myosin. It is also precipitated from its NaCl solution by crystals of NaCl. For Kühne's and other methods see § 293.

(6) **Globin** (*Preyer*), the proteid residue of hæmoglobin (§ 18).

Class III.—Derived Albumins (Albuminates).—(1) **Acid albumin or Syntonin.**—When proteids are dissolved in the stronger acids, *e. g.*, hydrochloric, they become changed into acid albumins. They are precipitated from solution by the addition of many salts, sodic chloride, acetate or phosphate, or by neutralization with an alkali, *e. g.*, sodic carbonate, but they are not precipitated by heat. The concentrated solution gelatinizes in the cold, and is redissolved by heat. **Syntonin**, which is obtained by the prolonged action of dilute hydrochloric acid (2 per 1000) upon minced muscles, is also an acid albumin. It is formed also in the stomach during digestion (§ 166, I). According to Soyka, the alkali and acid albumins differ from each other only in so far as the proteid in the one case is united with the base (metal) and in the other with the acid.

(2) **Alkali albumin.**—If egg or serum albumin be acted upon for some time by dilute alkalies, a solution of alkali albumin is obtained. Strong caustic potash acts upon white of egg, and yields a thick jelly, **Lieberkühn's jelly**. The solution is not precipitated by heat, but it is precipitated by the addition of an acid. [Although alkali albumin is precipitated on neutralization, this is not the case in the presence of alkaline phosphates, *e. g.*, sodic phosphate.]

(3) **Casein** is the chief proteid in milk (§ 231.) It is precipitated by acids and by rennet at 40° C. In its characters it is closely related to alkali albuminate, but it contains more N. It contains a large amount of phosphorus (0.83 per cent.). It may be precipitated from milk by diluting it with several times its volume of water and adding dilute acetic acid, or by adding magnesium sulphate crystals to milk and shaking vigorously. Owing to the large amount of phosphorus which it contains, it is sometimes referred to the nucleo-albumins. When it is digested with dilute HCl (0.1 per cent.) and pepsin at the temperature of the body, it gradually yields nuclein.

Class IV.—Fibrin.—(§ 27) and for the fibrin factors (§ 29).

Class V.—Peptones.—For **peptones** and **propeptone** or the **albumoses** (§ 166, I), in urine (§ 264).

Class VI.—Lardacein and Other Bodies.—There fall to be mentioned the "**yelk plates**," which occur in the yelk: **Ichthin** (cartilaginous fishes, frog); **Ichthidin** (osseous fishes); **Ichthulin** (salmon); **Emydin** (tortoise); also the indigestible **amyloid substance** or **lardacein**, which occurs chiefly as a pathological infiltration into various organs, as the liver, spleen, kidneys, and blood vessels. It gives a blue with iodine and sulphuric acid (like cellulose), and a mahogany brown with iodine. It is difficult to change it into an albuminate by the action of acids and alkalies.

Class VII.—Coagulated Proteids.—When any native albumins or globulins are coagulated, *e. g.*, at 70° C., they yield bodies with altered characters, insoluble in water and saline solutions, but soluble in boiling strong acids and alkalies, when they are apt to split up. They are dissolved during gastric and pancreatic digestion to produce peptones.

Appendix: Vegetable Proteid Bodies.—Plants, like animals, contain proteid bodies, although in less amount. They occur either in solution in the juices of living plants or in the solid form. In composition and reaction they resemble animal proteids.

[The **characters** of vegetable proteids have a great resemblance to animal proteids. They have frequently been obtained in a crystalline form, *e. g.*, from the seeds of the gourd and various oleaginous seeds. They occur in greatest bulk in the seeds of plants, **aleurone grains** being for the most part composed of them. In seeds, globulins and "vegetable peptone" form the greater proportion of the proteid constituents.]

[**Globulins.**—These varieties have been described as occurring in the seeds of plants: **vegetable myosin, vitellin** and **paraglobulin** (*Martin*). They have practically the same properties as those found in the animal kingdom; vegetable vitellin has, however, not been sufficiently studied. Paraglobulin has been found in papaw juice (*Martin*). Myosin occurs in the seed of leguminosæ, in flour, and in the potato.]

[**Albumin.**—The existence of a body corresponding to egg or serum albumin in the vegetable kingdom is doubtful (*Kilthausen*). Such a body has been described in papaw juice (*Martin*).]

[**Vegetable Peptone; Albumoses.**—A true peptone has not yet been recognized in plants: what has been described as such is hemi-albumose (*Vines*). Albumoses have been found in the seeds of leguminosæ, in flour, and in papaw juice. In the last, two forms occur, called respectively α- and β- **phytalbumose**. The former, α-phytalbumose, agrees with the hemi-albumose described by Vines, being soluble in cold and boiling water; giving also a biuret reaction, and a precipitate by saturation with sodium chloride only in an acid solution. The latter, β phytalbumose, is soluble in cold, but not in boiling, distilled water; hence it is precipitated by heat. It is also readily thrown down by saturation with sodium chloride, and gives a faint biuret reaction (*Martin*).]

[**Vegetable Casein** is said to occur in the seeds of leguminosæ; and it is slightly soluble in water, but readily so in weak alkalies and in solutions of basic calcic phosphate. A solution of this body is precipitated by acids and rennet. Two varieties have been described—(α) **legumin**, in peas, beans, lentils; acid in reaction, soluble in weak alkalies and very dilute HCl or acetic acid; (β) **conglutin**, a very similar body occurring in hops and almonds. The existence of vegetable casein is denied.

Vines states that both legumin and conglutin are artificial products, being formed from the globulins present by the dilute alkali used in extraction of the proteids. This is denied by Ritthausen.]

[**Gluten and Glutin.**—Gluten is readily prepared from flour by washing and kneading it in a muslin bag under a stream of water. So prepared it is yellowish brown in color, very sticky, and capable of being drawn out into long shreds. It is insoluble in water, soluble (but not completely) by prolonged action in dilute acids and alkalies (.2 per cent. KHO and HCl). The prolonged action of alcohol (80 to 85 per cent.) dissolves part of the substance of gluten, leaving a residue, called by Liebig plant fibrin and by Ritthausen gluten casein. The alcohol contains **gliadin** (glutin), gluten fibrin, and **mucedin.** **Gluten casein** is readily soluble in dilute alkalies, almost insoluble in dilute acetic acid, and quite insoluble in cold and boiling water; the products of its decomposition, by heating with H_2SO_4, are leucin, tyrosin, glutamic, and asparaginic acids. The three bodies dissolved from glutin by alcohol differ chiefly in their solubility in alcohol and water. **Gluten fibrin,** the least soluble, is coagulated by the action of absolute alcohol; it is readily soluble in dilute acids and alkalies, being precipitated by neutralization. **Gliadin** (glutin, plant gelatin) may be prepared by boiling gluten with water: it deposits on cooling the solution Though soluble in water at 100° C. at first, it becomes insoluble by the prolonged action of water at that temperature. It is, like gluten fibrin, soluble in dilute acids and alkalies. **Mucedin** differs from gliadin in being less soluble in strong alcohol. The water used in washing the flour in the preparation of gluten contains hemi-albumose (*Vines*) and a globulin (*Weyl*). Rye flour, as well as wheaten, yields gluten under similar treatment with water.]

[**Nitrogenous Crystalline Principles.**—Leucin, tyrosin, asparagin, and glutamic acid have been found in the seeds of plants.]

250. (2) **THE ALBUMINOIDS.**—These substances closely resemble true proteids in their composition and origin, and are amorphous non-crystalline colloids; some of them do not contain S, but the most of them have not been prepared free from ash. Their reactions and decomposition products closely resemble those of the proteids; some of them produce, in addition to leucin and tyrosin, **glycin** and **alanin** (amido-propionic acid). They occur as organized constituents of the tissues and also in fluid form. It is unknown whether they are formed by oxidation from proteid bodies or by synthesis.

1. **Mucin** is the characteristic substance present in **mucus.** That obtained from the sub-maxillary gland contains—C 52.31, H 7.22, N 11.84, O 28.63. According to Hammarsten it contains S 1.79 and N 13.5 per cent. It dissolves in water, making it sticky or slimy, and can be filtered. It is precipitated by acetic acid and alcohol; and the alcohol precipitate is again soluble in water. It is not precipitated by acetic acid and ferrocyanide of potassium, but HNO_3 and other mineral acids precipitate it. It occurs in saliva (§ 146), in bile, in mucous glands, secretions of mucous membranes, in mucous tissue, in synovia, and in tendons. Pathologically it occurs not unfrequently in cysts; in the animal kingdom, especially in snails and in the skin of holothurians. It yields lucin and 7 per cent. of tyrosin when it is decomposed by prolonged boiling with sulphuric acid. [The precipitate called mucin has not always the same characters, and, in fact, it differs according to the animal from which it is obtained (*Landwehr.*)]

2. **Nuclein** (*Miescher*, § 198)—(C 29, H 49, N 9, P 3, O 22)—contains phosphoric acid, and is slightly soluble in water, easily in ammonia, alkaline carbonates, strong HNO_3; it gives the biuret reaction; no reaction with Millon's reagent; when decomposed it yields phosphorus. It occurs in the nuclei of pus and blood corpuscles (§ 22), in spermatozoids, yelk spheres, liver, brain, and milk, yeast, fungi, and many seeds. It has resemblances to mucin, and is perhaps an intermediate product between albumin and lecithin (*Hoppe-Seyler*). It is prepared by the artificial digestion of pus, when it remains as an indigestible residue; acids precipitate it from an alkaline solution. It gives a feeble xanthoproteic reaction; after the prolonged action of alkalies and acid, substances similar to albumin and syntonin are formed. Hypoxanthin and guanin have been obtained as decomposition products from it (*Kossel*).

3. **Keratin** occurs in all horny and epidermic tissues (epidermic scales, hairs, nails, feathers)—C 50.3–52.5, H 6.4–7, N 16.2–17, O 20.8–25, S 0.7–5 per cent.—is soluble in boiling caustic alkalies, but swells up in cold concentrated acetic acid. When decomposed by H_2SO_4 it yields 10 per cent. leucin and 3.6 per cent tyrosin. **Neuro-keratin** (§ 321).

4. **Fibroin** is soluble in strong alkalies and mineral acids, in ammonio-sulphate of copper; when boiled with H_2SO_4 it yields 5 per cent. tyrosin, leucin, and glycin. It is the chief constituent of the cocoons of insects and threads of spiders.

5. **Spongin,** allied to fibroin, occurs in the bath sponge, and yields, as decomposition products, leucin and glycin (*Stadeler*).

6. **Elastin,** the fundamental substance in elastic tissue, is soluble only when boiled in concentrated caustic potash—C 55–55.6, H 7.1–7.7, N 16.1–17.7, O 19.2–21.1 per cent. It yields 36 to 45 per cent. of leucin and ½ per cent. of tyrosin.

7. **Gelatin** (**Glutin**), obtained from **connective tissues** by prolonged boiling with water; it gelatinizes in the cold—C 52.2–50.7, H 6.6–7.2, N 17.9–18.8, S + O 23.5–25 (S 0.7 per cent.). [The ordinary connective tissues are supposed to contain the hypothetical anhydride **collagen,** while the

organic basis of bone is called **ossein.**] It rotates the ray of polarized light strongly to the left = — 130°. By prolonged boiling and digestion, it is converted into a peptone-like body (gelatin peptone), which does not gelatinize (§ 161, I). [It swells up, but does not dissolve in cold water; when dissolved in warm water, and tinged with Berlin blue or carmine, it forms the usual colored mass which is employed by histologists for making fine transparent injections of blood vessels.] A body resembling gelatin is found in leukæmic blood and in the juice of the spleen (§ 103, I). When decomposed with sulphuric acid it yields glycin, ammonia, leucin, *but no tyrosin.* [It is precipitated from its solution by alcohol, mercuric chloride, metaphosphoric acid, phospho-wolframic acid, taurocholic acid, tannic acid, but the precipitate with the last does not occur when salts are absent. It is readily soluble in dilute acids, even in acetic acid. When boiled with Millon's reagent, it is not colored red. With cupric sulphate and caustic soda it gives a violet color which, on boiling, becomes light red. It gives no color with concentrated H_2SO_4 and acetic acid.]

8. **Chondrin** occurs in the matrix of hyaline **cartilage** and between the fibres in fibro-cartilage. It is obtained from hyaline cartilage and the cornea by boiling. [Its solutions gelatinize on cooling.] It occurs also in the mantle of mollusks—C 49.5–50.9, H 6.6–7.1, N 14.4–14.9, S + O 27.2–29 (S 0.4 per cent.). When boiled with sulphuric acid it yields leucin; with hydrochloric acid, and when digested, chondro-glucose (*Meissner*); it belongs to the glucosides, which contain N. When acted upon by oxidizing reagents it is converted into gelatin (*Brame*). The substance, which yields chondrin is called **chondrogen,** which is perhaps an anhydride of chondrin. The following properties of gelatin and chondrin are to be noted: **Gelatin is precipitated** by tannic acid, mercuric chloride, chlorine water, platinic chloride, and alcohol, but not by acids, alum, or salts of silver, iron, copper, or lead; its specific rotation is = — 130°. [Compare these precipitants with those of albumin.] **Chondrin** is precipitated by acetic acid and dilute sulphuric and hydrochloric acids, by alum, and by salts of silver, iron, and lead; its specific rotation = — 213°.

9 **The hydrolitic ferments** have recently been called **enzymes** by W. Kühne, in order to distinguish them from organized ferments, such as yeast. The enzymes, hydrolytic or organic ferments, act only in the presence of water. They act upon certain bodies, causing them to take up a molecule of water. They all decompose hydric peroxide into water and O. They are most active between 30° to 35° C., and are destroyed by boiling, but when dry they may be subjected to a temperature of 100° without being destroyed. Their solutions, if kept for a long time, gradually lose their properties and undergo more or less decomposition.

(*a*) **Sugar-forming** or **diastatic ferment** occurs in saliva (§ 148), pancreatic juice (§ 170), intestinal juice (§ 183), bile (§ 180), blood (§ 22), chyle (§ 189), liver (§ 174), in human milk (§ 231). **Invertin** in intestinal juice (§ 183). Almost all dead tissues, organic fluids, and even proteids, although only to a slight degree, may act diastatically. Diastatic ferments are very generally distributed in the *vegetable kingdom.*

(*b*) **Proteolytic, or ferments which act upon proteids.**—Pepsin in gastric juice and in muscles (§ 166), in vetches, myxomycetes (*Krukenberg*), trypsin in the pancreatic juice (§ 170), a similar ferment in the intestinal juice (§ 183), and urine (§ 264).

(*c*) **Fat-decomposing** in pancreatic juice (§ 170), in the stomach (§ 166).

(*d*) **Milk-coagulating** in the stomach (§ 166), pancreatic juice (§ 170), and perhaps also in the intestinal juice (?)—(*W. Roberts*).

[The importance of **fermentative processes** has already been referred to in detail under "Digestion." Ferments are bodies which excite chemical changes in other matter with which they are brought into contact. They are divided into two classes:—

(1) **Unorganized**; soluble or non-living.
(2) **Organized,** or living.]

[(1) **The Unorganized Ferments** are those mentioned in the following table. They seem to be nitrogenous bodies, although their exact composition is unknown, and it is doubtful if they have ever been obtained perfectly pure. They are present in many secretions, and are *produced* within the body by the vital activity of the protoplasm of cells. They are termed *soluble* because they are soluble in water, glycerin, and some other substances (§ 148), while they can be precipitated by alcohol and some other reagents. They do not multiply during their activity, nor is their activity prevented by a certain proportion of salicylic acid. They are not affected by oxygen subjected to the compression of many atmospheres (*P. Bert*). They are *non-living.* Their other properties are referred to above.]

[The unorganized ferments present in the body, and their actions (*W. Roberts*):—

Fluid or Tissues.	Ferment.	Actions.
Saliva, ...	1. Ptyalin (§ 148), ...	Converts starch chiefly into maltose.
Gastric juice,	1. Pepsin, ...	Converts proteids into peptones in an acid medium, certain by-products being formed (§ 166).
	2. Milk-curdling, ...	Curdles casein of milk.
	3. Lactic acid ferment, . . .	Splits up milk sugar into lactic acid.
	4. Fat-splitting, ...	Splits up fats into glycerin and fatty acids.
Pancreatic juice,	1. Diastatic or amylopsin, . .	Converts starch chiefly into maltose.
	2. Trypsin, ...	Changes proteids into peptones in an alkaline medium, certain by-products being formed (§ 170).
	3. Emulsive (?), ...	Emulsifies fats.
	4. Fat-splitting or steapsin, . .	Splits fats into glycerin and fatty acids.
	5. Milk-curdling, ...	Curdles casein of milk.
Intestinal juice,	1. Diastatic, ...	Does not form maltose, but maltose is changed into glucose (§ 183).
	2. Proteolytic, ...	Fibrin into peptone (?).
	3. Invertin, ...	Changes cane- into grape sugar.
	4. Milk-curdling, ...	(? in small intestine).
Blood, ... Chyle, ... Liver (?), . . . Milk, ... Most tissues . .	Diastatic ferments	. .
Muscle, . . . Urine, ...	Pepsin and other ferments.	. .
Blood, ...	Fibrin-forming ferment.	. .

[(2) **The Organized** or living ferments are represented by yeast (§ 235). Other living ferments belonging to the schizomycetes, occurring in the intestinal canal, are referred to in § 184. Yeast causes fermentation by splitting up sugar into CO_2 and alcohol (§ 156), but this result only occurs so long as the yeast is *living*. Hence, its activity is coupled with the vitality of the cells of the yeast. If yeast be boiled, or if it be mixed with carbolic or salicylic acid, or chloroform, all of which destroy its activity, it cannot produce the alcoholic fermentation. As yet no one has succeeded in extracting from yeast a substance which will excite the alcoholic fermentation. All the organized ferments grow and **multiply** during their activity at the expense of the substances in which they occur. Thus the alcoholic fermentation depends upon the "life" of the yeast. They are said to be killed by oxygen subjected to the compression of many atmospheres (*P. Bert*). But it is important to note that Hoppe-Seyler has extracted from *dead* yeast (killed by ether) an unorganized ferment which can change cane sugar into grape sugar.]

10. **Hæmoglobin**, the coloring matter of blood, which, in addition to C, H, O, N, and S, contains *iron*, may be taken with the albuminoids (§ 11). [**Hæmocyanin** (§ 32).]

(3) Glucosides containing Nitrogen.

In addition to **chondrin**, the following glucosides containing nitrogen, when subjected to hydrolytic processes, may combine with water, and form sugar and other substances:—

Cerebrin (§ 322) = $C_{87}H_{110}N_2O_{25}$ (*Geoghegan*). [Parcus has shown that cerebrin as originally prepared by W. Müller is a mixture of three bodies, viz., cerebrin, **homocerebrin**, and **encephalin**.]

Protagon—C 66.29, H 10.69, N 2.39, P 1.068, per cent.—occurs in nerves, and contains phosphorus (§ 322).

Chitin, $2(C_{15}H_{26}N_2O_{10})$, is a glucoside containing nitrogen, and occurs in the cutaneous coverings of arthropoda, and also in their intestine and tracheæ; it is soluble in concentrated acids, *e.g.*,

hydrochloric or nitric acid, but insoluble in other reagents. According to Sandwick, chitin is an amin derivative of a carbohydrate with the general formula $n(C_{12}H_{20}O_{10})$. The **hyalin** of worms is closely related to chitin. (Solanin, amygdalin (§ 202), and salicin, etc., are glucosides of the vegetable kingdom.)

(4) Coloring Matters containing Nitrogen.

Their constitution is unknown, and they occur only in animals. They are in all probability derivatives of hæmoglobin. They are (1) **hæmatin** (§ 18, A), **myohæmatin** (§ 232, § 292, *a*), **histohæmatin** (§ 103, IV), and **hæmatoidin** (§ 20). (2) **Bile pigments** (§ 177, 3). (3) **Urine pigments** (except Indican). (4) **Melanin**—$C_{44.2}$, H_3, $N_{9.9}$, $O_{42.6}$—or the black pigment, which occurs partly in epithelium (choroid, retina, iris, and in the deep layers of epidermis in colored races) and partly in connective-tissue corpuscles (Lamina fusca of the choroid). [**Turacin** occurs in the red feathers of Corythaix Buffoni or Plantain Eater. Its ash contains nearly 6 per cent. of copper (*Church*). The reddish spots or parts of feathers burn with a green flame.]

II. Organic Acids free from Nitrogen.

(1) The **fatty acids**, with the formula $C_nH_{2n-1}O(OH)$, occur in the body partly free and partly in combination. Free volatile fatty acids occur in decomposing cutaneous secretions (sweat). In combination, acetic acid and caproic acid occur as amido compounds in glycin (= amido-acetic acid) and leucin (= amido-caproic acid). More especially do they occur united with glycerin to form neutral fats, from which the fatty acid is again set free by pancreatic digestion (§ 170, III).

(2) The acids of the **acrylic acid series**, with the formula $C_nH_{2n-2}O(HO)$, are represented in the body by one acid **oleic acid**, which in combination with glycerin yields the neutral fat olein.

251. FATS.—(1) **Neutral fats** occur very abundantly in animals, but they also occur in all plants; in the latter more especially in the seeds (nuts, almonds, cocoanut, poppy), more rarely in the pericarp (olive) or in the root. They are obtained by pressure, melting, or by extracting them with ether or boiling alcohol. They [*e. g.*, tristearin, $C_{57}H_{110}O_6$] contain much less O than the carbohydrates, such as sugar and starch; they give a greasy spot on paper, and when shaken with colloid substances, such as albumin, they yield an **emulsion**. When treated with superheated steam or with certain ferments (p. 301), they take up water and yield **glycerin** and **fatty acids**, and if the latter be volatile they have a rancid odor. Treated with caustic alkalies they also take up water, and are decomposed into glycerin and fatty acids; the fatty acid unites with the alkali and forms a **soap**, while glycerin is set free. The soap solution dissolves fats.

Glycerin is a triatomic alcohol, $C_3H_5(OH)_3$, and unites with (1) the following monobasic *fatty acids* (those occurring in the body are printed in italics) :—

Acids.	Acids.	Acids.
1. *Formic*, ... CH_2O_2	7. Œnanthylic, . . $C_7H_{14}O_2$	[Margaric, . . $C_{17}H_{34}O_2$
2. *Acetic*, ... $C_2H_4O_2$	8. *Caprylic*, . . . $C_8H_{16}O_2$	is a mixture of
3. *Propionic*, . . . $C_3H_6O_2$	9. Pelargonic, . . . $C_9H_{18}O_2$	13 and 14.]
4. *Butyric*, ... $C_4H_8O_2$	10. *Capric*, ... $C_{10}H_{20}O_2$	14. *Stearic*, ... $C_{18}H_{36}O_2$
[Isobutyric, . . $C_4H_8O_2$]	11. *Laurostearic*, . $C_{12}H_{24}O_2$	15. Arachinic, . . . $C_{20}H_{40}O_2$
5. *Valerianic*, . . $C_5H_{10}O_2$	12. *Myristic*, . . . $C_{14}H_{28}O_2$	16. Hyænic, ... $C_{22}H_{36}O_2$
6. *Caproic*, . . . $C_6H_{12}O_2$	13. *Palmitic*, . . . $C_{16}H_{32}O_2$	17. Cerotinic, . . . $C_{27}H_{54}O_2$

The acids form a homologous series with the formula $C_nH_{2n-1}O(OH)$. With every CH_2 added their boiling point rises 19°. Those containing most carbon are solid, and non-volatile; those containing less C (up to and including 10) are fluid like oil, have a burning acid taste, and a rancid odor. The earlier members of the series may be obtained by oxidation from the later, by CH_2 being removed, while CO_2 and H_2O are formed; thus, butyric acid is obtained from propionic acid. Nos. 13 and 14 are found in human and animal fat, less abundant and more inconstant are 12, 11, 6, 8, 10, 4. Some occur in sweat (§ 287) and in milk (§ 231). Many of them are developed during the decomposition of albumin and gelatin. Most of the above (except 15 to 17) occur in the contents of the large intestine (§ 185).

(2) **Glycerin** also unites with the monobasic **oleic acid**, which also forms a series, whose general formula is $C_nH_{2n-3}O(OH)$, and they all contain 2H less than the corresponding members of the fatty acid series. The corresponding fatty acids can be obtained from the oleic acid series and *vice versâ*. **Oleic acid** (olein elainic acid), $C_{18}H_{34}O_2$, is the only one found in the organism; united with glycerin, it forms the fluid fat, **olein**. The fat of new-born children contains more glyceride of palmitic and stearic acid than that of adults, which contains more glyceride of oleic acid. Oleic acid also occurs united with alkalies (in soaps) and (like some fatty acids) in the lecithins (§ 23). If **lecithin** be acted on with barium hydrate, we obtain insoluble stearic, or oleic, or palmitic acids and barium oleate, together with dissolved **neurin** (§ 322, *b*) and baric glycerin phosphate. It appears as if there were several lecithins, of which the most abundant are the one with stearic acid and that with palmitin + oleic acid radicle (*Diakonow*). Lecithin occurs in the blood corpuscles (§ 23), semen and nerves, while neurin is constantly present in fungi.

The **neutral fats** [palmitin, stearin (both solid), and olein (fluid)], the glycerides of fatty acids, and of oleic acid, are triple ethers of triatomic alcohol glycerin. With the neutral fats may be associated **glycerin-phosphoric acid**, an acid glycerin ether, formed by the union of glycerin and phosphoric acid, with the giving off of a molecule of water ($C_3H_9PO_6$); it is a decomposition product of lecithin (§ 23).

(3) The **glycolic acids** (acids of the lactic acid series) have the formula $C_nH_{2n-2}O(OH)_2$. They are formed by oxidation from the fatty acid series by substituting OH (hydroxyl) for one atom of H of the fatty acids. Conversely, fatty acids may be obtained from the glycolic acids. The following acids of this series occur in the body:—

(*a*) **Carbonic Acid** (oxy-formic acid), $CO(OH)_2$; in this form, however, it only makes salts. Free carbonic acid or carbon dioxide is an anhydride of the same $= CO_2$.

(*b*) **Glycolic Acid** (oxy-acetic acid), $C_2H_2O(OH)_2$, does not occur free in the body. One of its compounds, **glycin** (glycocoll, amido-acetic acid, or gelatin sugar), occurs as a conjugate acid, viz., as glycocolic acid in the bile (§ 177, 2), and as hippuric acid in the urine (§ 260). Glycin exists in complex combination in the gelatin.

(*c*) **Lactic Acid** (oxy-propionic acid) $C_3H_4O(OH)_2$, occur in the body in two isomeric forms—1. The *ethylidene-lactic acid*, which occurs in two modifications—as the right rotatory *sarcolactic acid* (paralactic), a metabolic product of muscle; and as the ordinary optically inactive product of "lactic fermentation," which occurs in gastric juice, in sour milk (sauerkraut, acid cucumber), and can be obtained by fermentation from sugar (§ 184). 2. The isomer, *ethylene-lactic acid*, occurs in the watery extract of muscles (§ 293).

(*d*) **Leucic Acid** (oxy-caproic acid), $C_6H_{12}O_3$, does not occur as such, but only in the form of one of its derivatives, **leucin** (amido-caproic acid), as a product of the metabolism in many tissues, and is formed during pancreatic digestion (§ 170, II). Leucic acid may be prepared from leucin, and glycolic acid from glycin, by the action of nitrous acid.

(4) **Acids of the Oxalic Acid** or **Succinic Acid Series**, having the formula $C_nH_{2n-4}O_2(OH)_2$, are bi-basic acids, which are formed as completely oxidized products by the oxidation of fatty acids and glycolic acid, water being removed. It is important to note their origin from substances rich in carbon, *e.g.*, fats, carbohydrates, and proteids.

(*a*) **Oxalic Acid**, $C_2O_2(OH)_2$, arises from the oxidation of glycol, glycin, cellulose, sugar, starch, glycerin, and many vegetable acids— it occurs in the urine as calcium oxalate (§ 260).

(*b*) **Succinic Acid**, $C_4H_4O_2(OH)_2$, has been found in small amount in animal solids and fluids; spleen, liver, thymus, thyroid; in the fluids of echinococcus, hydrocephalus, and hydrocele, and more abundantly in dog's urine after fatty and flesh food; in rabbit's urine after feeding with yellow turnips. It is also formed in small amount during alcoholic fermentation (§ 150).

(5) **Cholalic Acid** in the bile (§ 177) and in the intestine (§ 182).

(6) **Aromatic Acids** contain the radicle of benzol. **Benzoic acid** (= phenyl-formic acid) occurs in urine united with glycerin, as hippuric acid (§ 260).

III. Alcohols.

Alcohols are bodies which originate from carbohydrates, in which the radical hydroxyl (HO) is substituted for one or more atoms of H. They may be regarded as water, $\left.\begin{matrix}H\\H\end{matrix}\right\}O$, in which the half of the H is replaced by a CH compound. Thus, C_2H_6 (ethyl hydrogen) passes into $\left.\begin{matrix}C_2H_5\\H\end{matrix}\right\}O$ (ethylic alcohol).

(*a*) **Cholesterin**, $\left.\begin{matrix}C_{26}H_{43}\\H\end{matrix}\right\}O$, is a true monatomic alcohol, and occurs in blood, yelk, brain, bile (§ 177, 4), and generally in vegetable cells, and it is the only solid monatomic alcohol in the body.

(*b*) **Glycerin**, $C_3H_5\left\{\begin{matrix}OH\\OH\\OH\end{matrix}\right.$, is a triatomic alcohol. It occurs in neutral fats united with fatty acids and oleic acid; it is formed by the splitting up of neutral fats during pancreatic digestion (§ 170, III), and during the alcoholic fermentation (§ 150).

(*c*) **Phenol** (= phenylic acid, carbolic acid, oxybenzol) (§ 184, III).

(*d*) **Pyrokatechin** (= dioxybenzol) (§ 252).

(*e*) The **Sugars** are closely related to the alcohols, and they may be regarded as poly-atomic alcohols. Their constitution is unknown. Together with a series of closely related bodies they form the great group of the **carbohydrates**, some of which occur in the animal body, while others are widely distributed in the vegetable kingdom.

252. **THE CARBOHYDRATES.**—Occur in plants and animals, and received their name, because in addition to C (at least 6 atoms), they contain H and O, in the proportion in which these occur in water. They are all solid, chemically indifferent, and without odor. They have either a sweet taste (sugars), or can be readily changed into sugars by the action of dilute acids; they rotate the ray of polarized light either to the right or left; as far as their constitution is concerned, they may be regarded as fatty bodies, as hex-atomic alcohols, in which 2H are wanting.

They are divided into the following groups:—

I. Division.—Glucoses ($C_6H_{12}O_6$).—(1) **Grape sugar** (glucose, dextrose, or diabetic sugar) occurs in minute quantities in the blood, chyle, muscle, liver (?), urine, and in large amount in the urine in diabetes mellitus (§ 175). It is formed by the action of diastatic ferments upon other carbohydrates, during digestion. In the **vegetable kingdom**, it is extensively distributed in the sweet juices of many fruits and flowers (and thus it gets into honey). It is formed from cane sugar, maltose, dextrin, glycogen, and starch, by boiling with dilute acids. It crystallizes in warty masses with one molecule of water of crystallization; unites with bases, salts, acids, and alcohols, but is easily decomposed by bases; it **reduces** many **metallic oxides** (§ 149). Fresh solutions have a rotatory power of + 106°. By **fermentation** with yeast it splits up into alcohol and CO_2 (§ 150); with decomposing proteids it splits into 2 molecules of lactic acid (§ 184, I); the lactic acid splits up under the same conditions in alkaline solutions, into butyric acid, CO_2, and H. For the qualitative and quantitative estimation of glucose, see § 149 and § 150. In alcoholic solution, it forms very insoluble compounds with chalk, barium, and potassium, and it also forms a crystalline compound with common salt (Estimation, § 150).

(2) **Galactose**, obtained by boiling milk sugar (lactose) with dilute mineral acids; it crystallizes readily, is very fermentable, and gives all the reactions of glucose. When oxidized with nitric acid it becomes transformed into mucic acid. Its specific rotatory power = + 88.08°.

(3) **Laevulose** (left-fruit-, **invert-**, or mucin sugar) occurs as a colorless syrup in the acid juices of some fruits and in honey; is non-crystallizable, and insoluble in alcohol; specific rotatory power = — 106°. It is formed normally in the intestine (§ 183), and occurs rarely as a pathological product in urine.

II. Division.—This contains carbohydrates with the formula $C_{12}H_{22}O_{11}$, and its members may be regarded as anhydrides of the first division—1. **Milk sugar** or **lactose** occurs only in milk, crystallizes in cakes (with 1 molecule of water) from the syrupy concentrated whey; it rotates polarized light to the right = + 59.3, and is much less soluble in water and alcohol than grape sugar. When boiled with dilute mineral acids it passes into galactose, and can be directly transformed into lactic acid only by fermentation; the galactose, however, is capable of undergoing the alcoholic fermentation with yeast (Koumiss preparation, § 232). For its quantitative estimation (§ 231). Rare in urine (§ 267).

2. **Maltose** ($C_{12}H_{22}O_{11}$) + H_2O (*O'Sullivan*) has 1 molecule of water less than grape sugar ($C_{12}H_{24}O_{12}$), is formed during the action of a diastatic ferment, such as saliva upon starch (§ 148); is soluble in alcohol, right-rotatory power = + 150°; it is crystalline, while its reducing power is only two-thirds that of dextrose. [The ratio of the reducing power of maltose to that of glucose is 100 to 66.]

(3. **Saccharose** (cane sugar) occurs in sugar cane and some plants, it does not reduce a solution of copper, is insoluble in alcohol, is right-rotatory, and not capable of fermentation. When boiled with dilute acids, it becomes changed into a mixture of easily fermentable glucose (right-rotatory) and laevulose (invert sugar, § 183, 5, and § 184, I, 6), which ferments with difficulty and is left-rotatory (§ 183). When oxidized with nitric acid, it passes into glucic acid and oxalic acid.)

(4. **Melitose**, from Eucalyptus manna; **Meleztose**, from Larch manna; **Trehalose** (Mycose), from Ergot: all are right-rotatory, and do not reduce alkaline cupric solutions.)

III. Division.—This contains carbohydrates, with the formula, $C_6H_{10}O_5$, which may be regarded as anhydrides of the second division.

1. **Glycogen**, with a dextro-rotatory power of 211°, does not reduce cupric oxide. It occurs in the liver (§ 174), muscles, many embryonic tissues, the embryonic area of the chick (*Külz*), in normal and pathological epithelium; in diabetic persons it is widely distributed; brain, pancreas, and cartilage; and in the spleen, pancreas, kidney, ovum, brain, and blood, together with a small amount of glucose (*Pavy*). It also occurs in the oyster and some of the mollusks (*Bizio*), and indeed in all tissues and classes of the animal kingdom.

2. **Dextrin** was discovered by Limpricht in the muscles of the horse. It is right-rotatory = + 138°, soluble in water, and forms a very sticky solution, from which it is precipitated by alcohol or acetic acid; it is tinged slightly red with iodine. It is formed in roasted starch (hence it occurs in large quantity in the crust of bread—see *Bread*, § 234), by dilute acids, and in the body by the action of ferments (§ 148). It is formed from cellulose by the action of dilute sulphuric acid. It occurs in beer, and is found in the juices of most plants.

3. **Amylum** or **Starch** occurs in the "mealy" parts of many plants, is formed within vegetable cells, and consists of concentric layers with an eccentric nucleus (Fig. 239). The diameter and characters of starch grains vary greatly with the plant from which they are derived. At 72° C. it swells up in water and forms a mucilage; in the cold, iodine colors it blue. Starch grains always contain more or less cellulose and a substance, **erythrogranulose**, which is colored red with iodine (§ 148). It and *glycogen* are transformed into dextrose by certain digestive ferments in the saliva, pancreatic, and intestinal juices, and artificially by boiling with dilute sulphuric acid.

(4. **Gum**, $C_{10}H_{20}O_{10}$, occurs in vegetable juices (especially in acaciæ and mimosæ), also in the salivary glands, mucous tissue, lungs, and urine; is partly soluble in water (arabin), partly swells

up like mucin (bassorin). Alcohol precipitates it. It is fermentable, and when boiled with dilute acids yields a reducing sugar.)

(5. **Inulin**, a crystalline powder occurring in the root of chicory, dandelion, and specially in the bulbs of the dahlia; it is not colored blue by iodine.)

(6. **Lichenin** occurs in the intercellular substance of Iceland moss (Cetraria islandica) and algæ; is transformed into glucose by dilute sulphuric acid.)

(7. **Paramylum** occurs in the form of granules resembling starch, in the infusoria, Euglena viridis.)

(8. **Cellulose** occurs in the cell walls of all plants (in the exo-skeleton of arthropoda, and the skin of snakes); soluble only in ammonio-cupric oxide; rendered blue by sulphuric acid and iodine. Boiled with dilute sulphuric acid, it yields dextrin and glucose. Concentrated nitric acid mixed

FIG. 239.

a, West Indian arrowroot; *c*, Tahiti arrowroot; *d*, Potato starch.

with sulphuric acid changes it (cotton) into nitro-cellulose (gun cotton), $C_6H_7(NO_2)_3O_5$, which dissolves in a mixture of ether and alcohol and forms **collodion.**)

(9. **Tunicin** is a substance resembling cellulose, and occurs in the integument of the Tunicata or Ascidians.)

IV. Division.—This contains the carbohydrates which do not ferment.

1. **Inosit** (phaseo-mannit, muscle sugar) occurs in muscle (*Scherer*), lung, liver, spleen, kidney, brain of ox, human kidney; pathologically in urine and the fluid of echinococcus. In the vegetable kingdom, in beans (leguminosæ), and the juice of the grape. It is an isomer of grape sugar; optically it is inactive, crystallizes in warts with 2 molecules of water, in long monoclinic crystals; it has a sweet taste, is insoluble in water, does not give Trommer's reaction, is capable of undergoing only the sarcolactic acid fermentation. (Nearly allied are **Sorbin**, from sorbic acid—**Scyllit**, from the intestines of the hag fish and skate—and **Eukalyn**, arising from the fermentation of melitose.)

IV. Derivatives of Ammonia and their Compounds.

The **ammonia derivatives** are obtained from the proteids, and are decomposition products of their metabolism.

(1) **Amines**, *i. e.*, compound ammonias which can be obtained from ammonia (NH_3), or from ammonium hydroxide ($NH_4 — OH$), by replacing one or all the atoms of H by groups of carbohydrates (alcohol radicals). The amine derived from *one* molecule of ammonia is called **monamine.** We are only acquainted with

$\left.\begin{matrix} H \\ H \\ CH_3 \end{matrix}\right\}$ N **Methylamine and Tri-Methylamine.** $\left.\begin{matrix} CH_3 \\ CH_3 \\ CH_3 \end{matrix}\right\}$ N,

as decomposition products of cholin (neurin) and of kreatin. Neurin occurs in lecithin in a very complex combination (see Lecithin, p. 429, and also § 23).

(2) **Amides**, *i. e.*, derivatives of acids, which have exchanged the hydroxyl (HO) of the acids for NH_2. **Urea**, $CO(NH_2)_2$, the bi-amid of CO_2, is the chief end product of the metabolism of the nitrogenous constituents of our bodies (see *Urine*, § 256). Carbon dioxide containing water = $CO(OH)_2$, where both OH are replaced by NH_2—thus we get $CO(NH_2)_2$, urea.

(3) **Amido acids**, *i. e.*, nitrogenous compounds, which show partly the character of an acid and partly that of a weak base, in which the atoms of H of the acid radical are replaced by NH_2, or by the substituted ammonia groups.

(*a*) **Glycin** (or amido-acetic acid, glycocoll, gelatin sugar, § 177, 2) is formed by boiling gelatin with dilute sulphuric acid. It has a sweet taste (gelatin sugar), behaves as a weak acid, but also unites with acids as an amine base. It occurs as glycin + benzoic acid = hippuric acid in urine (§ 260); and also as glycin + cholalic acid = glycocholic acid in bile (§ 177). (*b*) **Leucin**

—(§ 170) = amido-caproic acid. (*c*) **Serin**—(= ? amido-lactic acid) obtained from silk gelatin. (*d*) **Aspartic acid**—(amido-succinic acid); and (*e*) **Glutamic acid**, obtained by the splitting up of proteids (§ 170). Other amido acids are—(*f*) **Cystin** = amido-lactic acid, in which O is replaced by S (§ 268). (*g*) **Taurin**—(§ 177), amido-ethyl-sulphonic acid, occurs (except in certain glands) chiefly in combination with cholalic acid, as taurocholic acid in bile. **Tyrosin** (parahydro-oxyphenyl-amido-propionic acid), an amido acid of unknown constitution, occurs along with leucin during pancreatic digestion (§ 170), is a decomposition product of proteids, and occurs plentifully in the urine in acute yellow atrophy of the liver (§ 269).

To the amido acids are related—(*a*) **Kreatin** in muscle, brain, blood, urine, regarded as methyl-uramido-acetic acid ($C_4H_9N_3O_2$). It has been prepared artificially. When boiled with baryta water, it takes up H_2O, and splits into urea—and (*b*) **Sarkosin** ($C_3H_7NO_2$), methyl-amido-acetic acid. When boiled with water, heated with strong acids, in the presence of putrefying substances, kreatin gives off water, and is changed into **kreatinin** ($C_4H_7N_3O$). This strong base can be rechanged by alkalies into kreatin.

(4) **Ammonia Derivatives of Unknown Constitution.**—**Uric acid** (§ 258); **allantoin** (§ 260), is formed by the oxidation of uric acid by means of potassium permanganate; **cyanuric acid** in dog's urine; **inosinic acid** in muscle; **guanin** in traces in the liver and pancreas, in guano, the excrements of spiders, in the skin of amphibia and reptiles, in the silver sheen of many fishes (*A. Ewald and Krukenberg*) (§ 283); by oxidation it yields urea; **hypoxanthin** or **sarkin** occurs along with **xanthin** in many organs and in urine. Kossel prepared hypoxanthin from nuclein by prolonged boiling of the latter. It may be obtained from fibrin by putrefaction, by gastric and pancreatic digestion, and by dilute acids (*Salomon, H. Krause, Chittenden*); **xanthin** is prepared by oxidation from hypoxanthin. It occurs very rarely in the form of a urinary calculus. **Paraxanthin** in urine and a similar body **carnin** in flesh (§ 233). [**Adenin** ($C_5H_5N_5$), discovered by Kossel in the pancreas, yeast, and tea leaves, has also been isolated from the spleen, lymphatic glands, and kidney; it appears to be present in all highly cellular animal and vegetable tissues. Like the allied bases—xanthin and guanin, it is a derivative of the nuclein of the nuclei.]

Aromatic Substances.

1. **Monatomic phenols**—(*a*) **Phenol** (hydroxyl of benzol) in the intestine (§ 184). Phenyl sulphonic acid in urine (§ 262). (*b*) **Kresol**, in the form of *orthokresol* and *parakresol*, united with sulphonic acid, occur in urine (§ 262). 2. **Diatomic phenols**—(*a*) **pyrokatechin** united with sulphonic acid in urine (§ 262). 3. **Aromatic oxyacids**—(*a*) *Hydroparacumaric acid*; (*b*) *Paraoxyphenylacetic acid* in urine (§ 262). 4. **Indol** and **skatol** in the intestine (§ 184), conjoined with sulphonic acid in urine (§ 262).

253. **HISTORICAL.**—According to Aristotle, the organism requires food for three purposes—for growth, for the production of heat, and to compensate for the loss of the bodily excreta. The formation of heat takes place in the heart by a process of concoction, the heat so formed being distributed to all parts of the body by means of the blood, while respiration is regarded as an act whereby the blood is cooled. Galen accepted this view in a somewhat modified form; according to him, the metabolic processes may be compared to the processes going on in a lamp; the blood represents the oil; the heart, the wick; the lungs, the fanning apparatus. According to the view of the iatro-chemical school (*van Helmont*), the metabolic processes of the body are fermentations, whereby the food is mixed with the juices of the body. Since the middle of the seventeenth century (*Boyle*), the knowledge of the metabolic processes has followed the development of chemistry. A. v. Haller regarded heat as due to chemical processes—the food continually supplying the waste which is excreted from the body. After the discovery of oxygen (1774, by Priestley and Scheele), Lavoisier formulated the theory of combustion in the lungs, whereby carbonic acid and water were formed. Mitscherlich compared the decomposition processes in the living body with putrefactive processes. Magendie was the first to emphasize the difference between nitrogenous and non-nitrogenous foods, and he showed that the latter alone were not able to support life. Even gelatin alone is not sufficient for this purpose. The greatest advance in the theory of nutrition was made by J. v. Liebig, who laid the foundation of our present knowledge of this subject. According to Liebig, foods may be divided into two classes, viz., the "**plastic**," suitable for the construction of the organism, and the "**respiratory**" for the maintenance of the temperature; to the former class he referred the albuminates or proteids, to the latter, the non-nitrogenous carbohydrates and fats (p. 403). Among recent observers, the Munich School, as represented by v. Bischoff, v. Pettenkofer, and v. Voit, has done most to give us an exact knowledge of this department of physiology.

THE SECRETION OF URINE.

254. STRUCTURE OF THE KIDNEY.—[**Capsule.**—The kidney is a compound tubular gland, and is invested by a thin, tough, fibrous capsule, easily stripped off from the substance of the organ, to which it is attached by fine processes of connective tissue and blood vessels.]

[**Naked Eye Appearances.**—On dividing the kidney longitudinally from the hilum to its outer border, and examining the cut surface with the naked eye, we observe the **parenchyma** of the

FIG. 240.



Longitudinal section through the kidney (*Tyson, after Henle*).

kidney, consisting of an outer **cortical** and an inner **medullary**, or pyramidal portion, the latter composed of about twelve conical papillæ, or **pyramids** of **Malpighi**, with their apices directed toward and embraced by the calices of the pelvis of the kidney (Fig. 240). The medullary portion is further subdivided into the **boundary layer** of Ludwig and the **papillary portion.** According to Klein, the relative proportions of these three parts are—cortex, 3.5; boundary layer, 2.5; and papillary portion, 4. The cortex has a light brown color, and when torn presents a slightly granular aspect, with radiating lines running at regular distances. The granules are due to the presence of the

Malpighian corpuscles, and the striæ to the medullary rays. The boundary zone is darker, and often purplish in color. It is striated with clear and red lines alternating with opaque ones, the former being blood vessels and the latter uriniferous tubules. The papillary zone is nearly white and uniformly striated, the striæ converging to the apex of the pyramid. The medulla is much denser and less friable than the cortex, owing to the presence of a large amount of connective tissue between the tubules. The bundles of straight tubes of the medulla may be traced at regular intervals running outward into the cortex, constituting **medullary rays,** which become smaller as they pass outward in the cortical zone, so that they are conical and form the **pyramids of Ferrein** (Fig. 241, PF). The portion of the cortex lying between the medullary rays is known as the **labyrinth,** from the complicated arrangement of its tubules.]

FIG. 241.



Longitudinal section of a Malpighian pyramid. PF, pyramids of Ferrein; RA, branch of renal artery; RV, lumen of a renal vein receiving an inter-lobular vein; VR, vasa recta; PA, apex of a renal papilla; *b*, *b*, embrace the bases of the renal lobules.

[**Size, Weight.**—The adult kidney is about 11 centimetres (4.4 inches) in length, 5 centimetres (2 inches) wide, and 3 centimetres (1 inch) in thickness. It weighs in the male 113.5 to 170 grms. (4 to 6 oz.), in the female 113.5 to 156 grms. (4 to 5½ oz.). The width of the cortex is usually 5 to 6 millimetres (⅕ to ¼ inch).]

I. The **uriniferous tubules** all rise within the labyrinth of the cortex by means of a globular enlargement, 200 to 300 μ [$\frac{1}{130}$ to $\frac{1}{85}$ inch] in diameter, called **Bowman's capsule** (Figs. 242, 243). After pursuing a complicated course, altering their direction, diameter, and structure, and being joined by other tubules, they ultimately form large collecting tubes, which terminate by minute apertures, visible with the aid of a hand lens, on the apices of the papillæ projecting into the calices of the kidney. Each urinary tubule is composed of a homogeneous **membrana propria,** lined by epithelial cells, so as to leave a lumen for the passage of the urine from the Malpighian corpuscles to the pelvis of the kidney. The diameter and direction of the tubules vary, and the epithelium differs in its characters at different parts of the tube, while the lumen also undergoes alterations in its diameter.

Course and Structure of the Tubules.—In the labyrinth of the cortex, tubules arise in the spherical enlargement known as **Bowman's capsule** (Fig. 242, 1), which invests (in the manner presently to be described) the tuft of capillary blood vessels called a **glomerulus** or **Malpighian corpuscle.** By means of a short and narrow **neck** (2) the capsule becomes continuous with a convoluted tubule, X in Fig. 243. This tubule is of considerable length, forming many windings in the cortex (Fig. 242, 3); the first part of it is 45 μ wide, constituting the **proximal** or first **convoluted tubule.** It becomes continuous with a **spiral tubule** of Schachowa (4), which lies in a medullary ray where it pursues a slightly wavy or spiral course. On the boundary line between the cortical and boundary zone, the spiral tubule suddenly becomes smaller and passes into the **descending portion of Henle's loop** (5), which is 14 μ in breadth, and is continued downward through the boundary zone into the medulla, where it forms the narrow **loop of Henle** (6), which runs backward in the medullary part to the boundary zone. Here it becomes wider (20–26 μ), and as it continues its undulating course, it enters a medullary ray, where it constitutes the **ascending looped tube** (7), which becomes narrower in the cortex. Leaving the medullary ray again, it passes into the labyrinth, where it forms a tube with irregular angular outlines—the **irregular tubule** (10), which is continuous with (Fig. 243, *n*, *n*) the **second** or **distal convoluted tubule** (11), which resembles the proximal tubule of the same name. Its diameter is 40 μ. A short, narrow, wavy **junctional** or **curved collecting** tubule (12) connects the latter with one of the **straight collecting tubes** (13) of a medullary ray. As the collecting tubule proceeds through the boundary zone, it receives numerous junctional tubes, and when it reaches the boundary zone, it forms one of the **collecting tubes** (Fig. 243, O), which unite with one another at acute angles to form the larger straight **excretory tubes** or ducts of Bellini (15), which open on the summit of

the Malpighian pyramids into a calyx of the pelvis of the kidney. In the cortex the collecting tubules are 45 μ in diameter, but where they have formed an excretory tube (O), their diameter is 200 to 300 μ; 24 to 80 of these tubes open on the apex of each of the 12 to 15 Malpighian pyramids. In the lowest and broadest part, the membrana propria is strengthened by the presence of a thick supporting framework of connective tissue.

Structure of the Tubules.—[Below the neck, the tubules are lined everywhere by a **single** layer of nucleated **epithelium.**] **Bowman's capsule**, which is about $\frac{1}{250}$ inch in diameter (Fig. 244, II), consists of a homogeneous basement membrane lined internally by a single continuous layer of flattened cells (*k*). According to Roth, the basement membrane itself is composed of

FIG. 242.



Diagram of the course of two uriniferous tubules (*Klein and Noble-Smith*).

endothelial cells. [In the fœtus the lining cells are more polyhedral.] Within the capsule lies the glomerulus or tuft of blood vessels. The cells lining the capsule are reflected over and between the lobules of which the glomerulus consists. The glomerulus may not completely fill the capsule, so that, according to the activity of the kidney, there may be a larger or smaller space between the glomerulus and the capsule into which the filtered urine passes. The **neck** is lined by cubical cells. These cells, in some animals, *e. g.*, the rabbit, sheep, mouse, and frog, are ciliated.

The **proximal convoluted tubule** is lined by characteristic epithelium. The cells, which are short or polyhedral, contain a turbid or cloudy protoplasm (Fig. 244, III, 1 and 2), which not

unfrequently contains oil globules, and they form a single layer. Each cell consists of two parts; the inner, containing the spherical nucleus, is next the lumen, and granular (III, 2, *g*), while the outer part, next the membrana propria, appears fibrillated, or "**rodded**," from the presence of rods or fibrils placed vertically to the basement membrane (Fig. 245). These appear like the hairs of a brush pressed upon a plate of glass (III, 2). The cells are not easily separated from each other, as neighboring cells interlock by means of the branched ridges on their surfaces (III, 1)—(*Heidenhain, Schachowa*). The lumen is well defined, but its size seems to depend upon the state of imbibition of the cells bounding it.

The **spiral tubule** has similar epithelium and a corresponding lumen, although the epithelium becomes lower and somewhat altered in its characters at the lower part of the tube.

The **descending limb of Henle's loop**, and the **loop** itself with a relatively wide lumen, are bounded by clear, flattened, epithelial cells, with a bulging nucleus (IV, S); the cells lying on one side of the tube being so placed that the bulging part of the bodies of the cells is opposite the thin part of the cells on the opposite side of the tube. [These tubes might be mistaken for blood capillaries, but in addition to their squamous lining, they have a basement membrane, which capillaries have not.] In the **ascending limb**, the lumen is relatively wide, while its epithelium agrees generally with that in the convoluted tubule, excepting that the "rods" are shorter. Sometimes the cells are arranged in an "imbricate" manner.

In the **irregular tubule**, which has a very small lumen, the polyhedral cells lining it contain oval nuclei, and are shorter than those of the convoluted tubules. The cells, again, are very irregular in size, while their "rodded" character is much coarser and more defined (Fig. 246).

The **distal convoluted tubule** closely resembles in its structure the proximal convoluted tubule, and is lined by similar cells. The *curved collecting*, or **junctional tubule**, although narrow, has a relatively wide lumen, as it is lined by clear, somewhat flattened cells.

The **collecting tubes** have a distinct lumen, and are lined by *clear*, somewhat irregular, cubical cells (Fig. 244, V), which in the larger *excretory* tubes are distinctly columnar (VI). The basement membrane is said to be absent in the larger tubes. [Klein describes a thin, delicate, nucleated, centro-tubular membrane lining the surface of the epithelium next the lumen.]

FIG. 243.



I, Blood vessels and uriniferous tubules of the kidney (semi-diagrammatic); A, capillaries of the cortex, B, of the medulla; *a*, inter-lobular artery; 1, vas afferens; 2, vas efferens; *r*, *e*, vasa recta; *c*, venæ rectæ; *v*, *v*, inter-lobular vein; S, origin of a vena stellata; *i*, *i*, Bowman's capsule and glomerulus; X, X, convoluted tubules; *t*, *t*, Henle's loop; *n*, *n*, junctional piece; *o*, *o*, collecting tubes; O, excretory tube.

II. The Blood Vessels.—The **renal artery** (Fig. 250) divides into four or five branches, which pass into the kidney at the hilum. These branches, surrounded by connective tissue continuous with that of the capsule, continue to divide, and pass between the papillæ, to reach the bases of the pyramids on the limits between the cortical and boundary zones, where they form incomplete arches. From these horizontal trunks, the **inter-lobular arteries** (Fig. 243, *a*) run vertically and singly into the cortex, between each two medullary rays, and in their course they give off on all sides the short, undivided **vasa afferentia** (1), each of which enters a Malpighian capsule at the opposite pole from which the urinary tubule is given off. Within the capsule, each afferent artery breaks up into capillaries arranged in lobules and supported by connective tissue, the whole forming a tuft of capillary blood

FIG. 244.



II, Bowman's capsule and glomerulus. *a*, vas afferens; *e*, vas efferens; *c*, capillary network of the cortex; *k*, endothelium of the capsule; *h*, origin of a convoluted tubule. III, "rodded" cells from a convoluted tubule—2, seen from the side, with *g*, inner granular zone; 1, from the surface. IV, cell lining Henle's looped tubule. V, cells of a collecting tube. VI, section of an excretory tube.

vessels, or a **glomerulus.** Each glomerulus is covered on its surface, directed toward the wall of the capsule by a layer of flat, nucleated, epithelial cells (Fig. 229, II), which also dip down between the capillaries. A vein, the **vas efferens** (2), which is always smaller than the afferent arteriole, proceeds from the centre of the glomerulus, and leaves the capsule close to the point at which the afferent vessel enters it (Fig. 244, II). In their structure and distribution all the efferent vessels resemble arteries, as they divide into branches to form a dense, narrow-meshed **capillary network** (Fig. 243, A, and Fig. 244, II, *c*), which ramifies over and between the convoluted tubules. The meshes are elongated around the tubules of the medullary rays, and more polygonal around the convoluted tubules

FIG. 245.

Convoluted tubule (after ammonium chromate) showing "rodded" epithelium.

FIG. 246.

Epithelium of an irregular tubule of the kidney of a dog.

(Fig. 243). Some of the lowest efferent vessels split up into **vasa recta,** which run toward the medulla. The interlobular arteries become smaller as they pass toward the surface of the kidney, and some of their terminal capillaries communicate with the capillaries of the external capsule itself. Venous trunks proceed from the capillary network, to terminate in the **inter-lobular veins** (V), which begin close under the capsule by venous radicals arranged in a stellate manner (constituting the stellulæ Verheynii, or **venæ stellatæ**), and accompany the corresponding artery to the limit between the cortex and boundary zone, where they communicate with the large venous trunks in that situation.

The **blood vessels of the medulla** arise from the **vasa recta** (Fig. 243, *r*), which begin on the limit of the cortex and medulla, either as single, direct, muscular branches (*r*) of the large arterial

trunks, or from those efferent vessels (*e*) which lie next to the medulla. The latter are said to be devoid of muscle. According to Huschke, a few vasa recta are formed by the union of the capillaries of the medullary rays. All the vasa recta enter the boundary layer, where they split up into a leash or pencil of small arterioles, which pass between the straight tubules toward the pelvis, and form in their course a capillary network with elongated meshes. From these capillaries there arise venous radicles, which, as they proceed toward the limit between the cortex and medulla, form the **venæ rectæ** (*c*), and open into the concave side of the venous trunks in this region. At the apex of the papillæ, the capillaries of the medulla form connections with the rosette-like capillaries surrounding the excretory ducts (at 1).

[The circulation through the vasa recta is most important. The cortical system of blood vessels communicates with the medullary, but as most of the vasa recta are derived from the same vessel as the interlobular arteries, it is evident that they may form a side stream through which much of the blood may pass without traversing the vessels of the cortex. Very probably the "short cut" is useful in congestions of the kidney. The amount of distention of these vessels also will influence the size of the tubules lying between them. There are two other channels by which blood can pass through the renal arteries without traversing the glomeruli (1) The anastomoses between the terminal twigs of the renal artery and the subcapsular venous plexus; (2) small branches given off, either by the interlobular arteries or by the afferent vessels before entering the glomeruli (*Brunton*).]

The **blood vessels of the external capsule** are derived partly from the terminal twigs of the interlobular arteries, partly from branches of the suprarenal, phrenic, and lumbar arteries, which anastomose with each other. The capillary network has simple meshes. The venous radicles pass partly into the venæ stellatæ, and partly into the veins of the same name as the arteries. The connection of the area of the renal artery with the other arteries of the capsule explains why, after ligature of the renal artery within the kidney, the blood still circulates in the external capsule (*C. Ludwig, M. Herrmann*); in fact, these blood vessels still supply the kidney with a small amount of blood, which may suffice to permit a slight secretion of urine to take place (*Litten, Pautynski*).

III. The **lymphatics** form a wide-meshed plexus in the capsule of the kidney, while under it they form large spaces (*Heidenhain*). In the parenchyma of the kidney, the lymphatics are said to be represented by large slits devoid of a wall in the tissues, and are more numerous around the convoluted than the straight tubules. The slits pass to the surface of the kidney, and expand under the capsule. When the lymphatics are greatly distended, they tend to compress the uriniferous tubules and the blood vessels (*C. Ludwig and Zawarykin*). According to Ryndowsky, the uriniferous tubules are surrounded by true lymphatics with an endothelial lining, and they even penetrate into the capsule of Bowman along with the vas afferens. [The large blood vessels are also surrounded by lymphatics]. Large lymphatics, provided with valves, pass out of the kidneys at the hilum, while others emerge through the capsule; both sets are connected with the lymph spaces of the capsule of the kidney (*A. Budge*).

IV. The **nerves** form small trunks provided with **ganglia**, and accompany the blood vessels. [They are derived from the renal plexus and the lesser splanchnic nerve.] They contain medullated and non-medullated fibres, and the latter have been traced by W. Krause as far as the apices of the papillæ. Their mode of termination is unknown. *Physiologically*, we are certain that they contain both *vasomotor* and *sensory* fibres; perhaps there may be also vaso-dilator and secretory fibres.

V. The **connective tissue**, or interlobular stroma, forms in the papillæ, especially at their apices, fibrous, concentric layers of considerable thickness between the excretory tubules (Fig. 247). Further outward, the fibrillar character becomes less distinct, while at the same time branched connective-tissue corpuscles occur in greater numbers. In the cortex, the interstitial stroma consists almost entirely of branched corpuscles, which anastomose with each other.

FIG. 247.

Transverse section of apex of Malpighian pyramid. *a*, large collecting tubes; *b*, *c*, *d*, tubules of Henle; *e*, *f*, blood capillaries.

[There is also a small quantity of delicate fibrous tissue around Bowman's capsule, and along the course of the arteries. The connective tissue often plays an important rôle in pathological conditions of the kidney, as interstitial nephritis.] The outer layers of the capsule of the kidney are composed of dense bundles of fibrous tissue, while the deeper layers are more loose, and send processes into the cortical layers. The capsule is easily stripped off. None of the secretory substance is removed with it. Under the capsule in the human kidney, there is a thin plexus of **non-striped muscular fibres.** At the hilum it becomes continuous with the outer fibrous coat of the dilated upper end of the ureter. Smooth muscular fibres also occur in a sphincter-like arrangement round the apex of each papilla, while others proceed from the pelvis between the pyramids along the blood vessels (*Jardet*). The **fat** surrounding the kidney is united to the latter partly by blood vessels and partly by bands of connective tissue. [The subcapsular layer of the cortex, and a thin layer next the boundary zone (Fig. 242, *a*, *a*,), are devoid of Malpighian corpuscles.]

[**Development of a Malpighian Capsule.**—The upper end of the urinary tubule is dilated and closed, and into it there grows a tuft of blood vessels (*a*) pushing one layer of the tube before it (*b*), hence the capillaries become invested by it, just as an organ is surrounded by a serous sac, so that one layer—the reflected one (*b*)—of the tubule is closely applied to the blood vessels, while the other (*c*) lies loosely over it with a space between the two (Fig. 248).]

255. THE URINE.—Physical Characters.—A knowledge of the composition of this secretion is of the greatest value to the physician and surgeon.

1. The **quantity** of urine passed by an adult man in twenty-four hours is between 1000 and 1500 cubic centimetres, or about **50 ozs.**, and in the female 900 to 1200 c.c. The minimum is secreted between 2 to 4 A. M., and the maximum between 2 to 4 P. M. (*Weigelin*).

The amount is **diminished** by profuse sweating, diarrhœa, thirst, non-nitrogenous food, diminution of the general blood pressure, after severe hemorrhage, and in some diseases of the kidneys. The minimum, which may be normal, is 400 to 500 c.c. It is **increased** by increase of the general blood pressure, or of the pressure within the area of the renal artery, by copious drinking, contraction of the cutaneous vessels through the action of cold, the passage of a large amount of soluble substances (urea, salts, and sugar) into the urine, a large amount of nitrogenous food, as well as by various drugs, such as digitalis, alcohol, squills. After taking fluids charged with CO_2, the amount of urine is increased during the following hours (*Quincke*).

The secretion is influenced directly by the **nervous system**, as in the sudden **polyuria** following nervous excitement, such as hysteria [when the person usually passes a large amount of very pale-colored urine]; after an epileptic attack, and also after pleasureable excitement (*Beneke*). We may have polyuria unaccompanied by the presence of sugar in the urine, which follows injury to a certain part of the floor of the fourth ventricle (*Cl. Bernard*). The urine is measured in tall graduated cylindrical vessels (Fig. 249). [In estimating the quantity of urine passed, the patient must, of course, be directed always to empty his bladder at a particular hour, and collect the urine passed during the next twenty-four hours.]

2. The **specific gravity** varies, as a mean, between 1015 and 1025; the minimum, after copious draughts of water, may be 1002; while the maximum, after profuse perspiration and great thirst, may be 1040. The mean specific gravity is about 1020. In newly-born children, the specific gravity falls very considerably during the first three days, which is due to the amount of food taken (*Martin and Ruge*). [The specific gravity of the urine in **infants** is about 1003 to 1006.] A healthy adult excretes about 70 grms. [2½ oz.] daily of solids by the urine, or about 1 grm. of solids per 1 kilo. of body weight.

The **specific gravity is estimated** by means of a urinometer (Fig. 250), the urine being at the temperature of 16° C. [The **urinometer**, when placed in distilled water, ought to float at the mark 0° or zero, which is conventionally spoken of as 1000. Place the urine to be tested in a tall cylindrical glass, of such width that the urinometer, when placed in it, may float freely and not touch the sides. Take care that no air bubbles adhere to the instrument. When reading off the mark on the stem, raise the vessel to the eye and bring the eye on a level with the surface of the water, noting the number which corresponds to this. This rule is adopted because the water rises on the stem in virtue of capillarity. It is essential that a sample of the **mixed urine** of the twenty-four hours be used for ascertaining the mean specific gravity.]

Christison's Formula.—To estimate the amount of solids in the urine. This may be done approximately by means of the formula of Trapp or Haeser, or, as it is called in this country, "Christison's formula," viz., "Multiply the two last figures of a specific gravity expressed in four figures by 2.33" (*Christison and Haeser*), or by 2 (*Trapp*), or 2.2 (*Loebisch*). This gives the

of solids in every 1000 parts. [Suppose a person passes 1200 c.c. urine in twenty-four and the specific gravity is 1022, then

$$22 \times 2.33 = 51.26 \text{ grms. in 1000 c.c.}$$

ertain the amount in 1200 c.c.

$$1000 : 1200 :: 51.26 : \times = \frac{51.26 \times 1200}{1000} = 61.51. \text{ grms.}]$$

ct Estimation of Solids.—Place 15 c.c. of urine in a capsule of known weight, and evapo- over a water bath, afterward completely dry the residue in an air bath at 100° C., and then over concentrated sulphuric acid. During the process a small amount of urea is decomposed, the value obtained is slightly too small. Of course the specific gravity varies with the amount er in the urine. The *most concentrated* (highest specific gravity) urine is the morning urine

FIG. 248.

velopment of a glomerulus and Malpighian capsule. *a*, capillary; *b*, visceral; *c*, parietal layer of capsule.

FIG. 249.

Graduated cylinder and flask for measuring the amount of urine.

FIG. 250.

Urinometer.

a notis), especially after being retained in the bladder, *e.g.*, in prolonged sleep a certain nt of ater is absorbed, so that the urine becomes more concentrated. The most dilute urine reted aer copious drinking (**Urina potus**). Under **pathological conditions**, as in diabetes us (§ 15), the urine is, at the same time, very copious (as much as 10,000 c.c.), and very con- ted, while the specific gravity varies from 1030 to 1060 [due to the presence of a large amount pe sug]. In fever the urine is concentrated, and small in amount. In polyuria, due to cer- ervous onditions, the urine is very dilute and copious, while the specific gravity may be as low 01.

The **olor** of the urine depends on the coloring matters present in it, and s great, but the differences in color are due chiefly to variations in the amount ater. lormally it has a pale straw color, but if it contains more water than

usual it has a very pale tint, and in certain cases (as in the sudden polyuria occurring after an attack of hysteria) it may be as clear as water. Concentrated urine, as after meals, or the first urine passed in the morning, has a darker color; it is a dark yellow or brownish red; while it is usually dark colored in fever.

Fœtal urine, and also the urine first passed after birth, are as clear and colorless as water. The admixture of various substances with the urine alters its color. When mixed with **blood**, according to the degree of decomposition of the hæmoglobin, the urine is red or dark brownish red [more frequently it is *smoky*], especially if the blood comes from the kidneys and the urine is acid. When mixed with **bile pigments**, it is of a deep yellowish brown, with an intense yellow froth; senna taken internally makes it intensely red, rhubarb brownish yellow, and carbolic acid black. Urine undergoing the ammoniacal fermentation may present a dirty bluish appearance, owing to the formation of indigo. The color of urine is estimated by Neubauer and Vogel by means of an empirical "color scale."

Urine, but especially ammoniacal urine, exhibits **fluorescence**, which disappears on the addition of an acid, and reappears after the addition of an alkali.

Normal urine, after standing for several hours, deposits a fine cloud of vesical **mucus** [like delicate cotton wool]. The froth of normal urine is white, and disappears pretty rapidly, while that on an albuminous urine perists much longer. The urine not unfrequently contains some **epithelial cells** from the bladder and urethra.

[AMOUNTS OF THE SEVERAL URINARY CONSTITUENTS (*Loebisch*).

CONSTITUENTS.	Man, 28 years of age, weight, 72 kilos, observations over 8 days (*Kerner*). In 24 hours.			Mean of analyses in different individuals (*Vogel*).
	Min.	Max.	Mean.	In 24 hours.
	c.c.	c.c.	c.c.	c.c.
Quantity,	1099	2150	1491	1500
Specific gravity,	1015	1027	1021	1020
Water,	. .	. .	. .	1440
Solids,	. .	. .	. .	60
Urea,	32.00	43.4	38.1	35
Uric acid,	0.69	1.37	0.94	0 75
Sodium chloride,	15.00	19.20	16.8	16.5
Phosphoric acid,	3.00	4.07	3:42	3.5
Sulphuric acid,	2.26	2.84	2.48	2.0
Phosphorus, Calcium,	0.25	0.51	0.38	. .
Magnesium phosphate	0.67	1.29	0.97	. .
Total quantity of earthy phosphates.	0.92	1.80	1.35	1.2
Ammonia,	0.74	1.01	0.83	0 65
Free acid,	1.74	2.20	1.95	3]

[AMOUNTS OF THE SEVERAL URINARY CONSTITUENTS PASSED IN 24 HOURS (*Parkes*).

CONSTITUENTS.	By an average man of 66 kilos.	Per 1 kilo. of body-weight.
	grms.	grms.
Water,	1500.000	23 000
Total solids,	72.000	1.100
Urea,	33.180	0.500
Uric acid,	0.555	0 0084
Hippuric acid,	0.400	0.0060
Kreatinin,	0.910	0.0140
Pigment and other substances,	10.300	0.1510
Sulphuric acid,	2.012	0.0305
Phosphoric acid,	3.164	0 0486
Chlorine,	7.000 (8.12	0.1260
Ammonia,	0.770	. .
Potassium,	2.500	. .
Sodium,	11.090	. .
Calcium,	0.260	. .
Magnesium,	0.207	. .]

4. **Consistence.**—Normal urine, like water, is a freely mobile fluid.

Large quantities of sugar, albumin or mucus make it less mobile; while the so-caled chylous urine of warm climates may be like a white jelly.

5. The **taste** is a saline bitter; the **odor** is characteristic and aromatic.

Ammoniacal urine has the odor of ammonia. Turpentine taken internally gives rise to the odor of violets, copaiba and cubebs a strongly aromatic, and asparagus an unpleasant odor. Valerian, assafœtida, and castoreum [but not camphor] also produce a characteristic odor. [The odor of diabetic urine is described as "sweet."]

6. The **reaction** of normal urine is **acid**, owing to the presence of acid salts, chiefly **acid sodic phosphate**, which seems to be derived from basic sodic phosphate, owing to the uric acid, hippuric acid, sulphuric acid, and $C0_2$ taking to themselves part of the soda, so that the phosphoric acid forms an acidsalt. After a diet of flesh, acid potassic phosphate is the cause of the acidity. That the urine

contains no free acid is proved by the fact that it gives no precipitate with sodic hyposulphite (*v. Voit, Huppert*).

The acid reaction is **increased** after the use of acids, *e.g.*, hydrochloric and phosphoric, also by ammoniacal salts, which are changed within the body into nitric acid; lastly, after prolonged muscular exertion. The morning urine is strongly acid.

The urine becomes **less acid or alkaline**—(1) By the use of caustic alkalies, alkaline carbonates, or alkaline salts of the vegetable acids, the last being oxidized within the body into carbonates. (2) By the presence of calcic, or magnesic carbonate. (3) By admixture with alkaline blood, or pus. (4) By removing the gastric juice through a gastric fistula (p. 291, *Maly*); further, from one to three hours after a meal. [The reaction of urine passed **during digestion** may be neutral, or even alkaline. This is due either to the formation of acid in the stomach (*Bence Jones*), or to a fixed alkali derived from the basic alkaline phosphates taken with the food (*W. Roberts*).] (5) The urine is rarely alkaline in anæmia, owing to a deficiency of phosphoric and sulphuric acids. [(6) The *nature of the food*—vegetable food makes it alkaline. (7) By profuse sweating. (8) By absorption of alkaline transudations (blood, serum).]

[**Method.**—The reaction of urine is tested by means of litmus paper. Normal urine turns blue litmus paper red, and does not affect red litmus. An alkaline urine makes red litmus paper blue, while a neutral urine does not alter either blue or red litmus paper.] Sometimes *violet* litmus paper is used, which becomes red in acid, and blue in alkaline urine.

Estimation of the Acidity.—This is done by determining the amount of caustic soda necessary to produce a neutral reaction in 100 c.c. of urine. A soda solution, containing 0.0031 grm. of soda in each c.c. is used; 1 c.c. of this solution exactly neutralizes 0.0063 grm. oxalic acid. To the 100 c.c. of urine in a beaker, soda solution is added, drop by drop, from a graduated burette (Fig. 251), until violet litmus paper becomes neither red nor blue. The number of c.c. of soda solution is now read off on the burette, and as each c.c. corresponds to 0.0063 grm. oxalic acid, we can easily calculate the amount of oxalic acid which is equivalent to the degree of acidity in 100 c.c. of urine. So that the degree of acidity of the urine is expressed by the equivalent amount of oxalic acid, which is completely neutralized by the same amount of caustic soda.

FIG. 251.



Graduated Burette.

Urine of Mammals.—The urine of **carnivora** is pale, passing into a golden yellow; its specific gravity is high, and its reaction strongly acid. The urine of **herbivora** is alkaline; it shows a precipitate of earthy carbonates (hence, it effervesces on the addition of an acid), and of basic earthy phosphates. During hunger, the urine presents the character of that of carnivora, as the animal in this case practically lives upon its own flesh and tissues.

256. I. THE ORGANIC CONSTITUENTS OF URINE.—Urea, $CO(NH_2)_2$, the diamide of CO_2, or carbamid, is the chief end product of the oxidation of the nitrogenous constituents of the body. Its composition is comparatively simple: 1 carbonic acid + 2 ammonia — 1 water. It **crystallizes** in silky four-sided prisms with oblique ends (rhombic system), without water of crystallization (Fig. 252, 1), if it crystallizes rapidly it forms delicate white needles. It has no action on litmus, is odorless, and has a weak, bitter, cooling taste, like

saltpetre; is readily soluble in water and alcohol, but insoluble in ether. It is an isomer of ammonium cyanate, from which it may be prepared by evaporation, whereby the atoms rearrange themselves (*Wöhler*, 1828). It can be prepared artificially in many other ways.

Decomposition.—When heated above 120°, it gives off ammonia vapor, while a glassy mass of biuret and cyanic acid is left. When urine undergoes the alkaline fermentation (§ 263), or when urea is treated with strong mineral acids, or boiled with the hydrates of the alkalies, or superheated with water (240° C.), it takes up two molecules of water and produces ammonium carbonate, thus—

$$CO(NH_2)_2 + 2H_2O = CO(NH_4O)_2.$$

When brought into relation with nitrous acid, it splits up into water, CO_2, and N. The two last decompositions are made the basis of methods for the quantitative estimation of urea (§ 257).

Quantity.—In normal urine, urea occurs to the extent of 2.5 to 3.2 per cent. An **adult** man excretes daily from 30 to 40 grms. [500 grains, or a little over 1 oz.]; women less, **children** relatively more; owing to the relatively greater metabolism in children, the unit weight of body produces more urea than the unit weight of an

FIG. 252.



1, 2, Prisms of pure urea; 3, rhomboidal plates; 4, hexagonal tablets; 5, 6, irregular scales and plates of urea nitrate.

adult, in the proportion of 1.7 : 1. If the metabolism of the body is in a condition of equilibrium (§ 236), the urea excreted contains almost as much N as is taken in with the nitrogenous constituents of the food.

Variations in the Quantity.—The amount of urea increases when the amount of proteids in the food is increased; and also when there is a more rapid breaking up of the nitrogenous tissues of the body itself. As this breaking up is increased by diminution of O, and by loss of blood, so these conditions also increase the urea (§ 41). It is also increased by drinking large draughts of water, by various salts, by frequent urination, and by exposure to compressed air. In diabetic persons, who eat very large quantities of food, it may exceed 100 grms. [over 3 oz.] per day; during hunger it sinks to 6.1 grms. [90 grains] per day During inanition, the maximum amount is excreted toward mid-day, and the minimum in the morning. The daily amount of urea varies with the quantity of urine; three to five hours after a meal, the formation of urea is at a maximum, when it sinks and reaches its minimum during the night. **Muscular exercise**, as a rule, does not increase it (*v. Voit, Fick and Wislicenus*—§ 295), but only when deficiency of O, causing dyspnœa, occurs at the same time (*Oppenheim*).

Pathological.—In acute febrile inflammations, and in fevers generally (§ 22, 3), the urea increases until the crisis is reached, and afterward it diminishes. After the fever has passed off, the amount excreted is often under the normal. In some cases of high fever, although the amount of urea formed is increased, it may not be excreted; there is a *retention of the urea*, which, later on, may lead to an increased excretion (*Naunyn*). In *chronic diseases*, the amount depends largely upon the state of the nutrition, the metabolism, and also upon the degree of fever present. Degenerative changes in the liver, *e.g.*, due to poisoning with phosphorus, may be accompanied by diminished excretion of urea and increased excretion of ammonia (*Stadelmann*). It is increased in man by morphia, narcotin, narcein, papaverin, codein, thebain (*Fubini*), arsenic (*Gäthgens*), compounds of antimony, and small doses of phosphorus (*Bauer*), which favor the decomposition of proteids, and by substances which increase the bile formation in the liver (*N. Paton*). Quinine, which "spares" the proteids, diminishes it.

Occurrence.—Urea occurs in the blood (1 : 10,000), lymph, chyle (2 : 1000), liver, lymph glands, spleen, lungs, brain, eye, bile, saliva, amniotic fluid, and pathologically in sweat, *e.g.*, in cholera, in the vomit and sweat of uræmic patients, and in dropsical fluids.

Formation.—It is certain that it is the chief end product of the metabolism of the **proteids.** Less oxidized products are uric acid, guanin, xanthin, hypoxanthin, alloxan, allantoin. Uric acid administered internally appears in the urine as urea; alloxan and hypoxanthin can be changed directly into urea. The urea excretion is increased by the administration of leucin, glycin, aspartic acid, or ammonia salts (*Schulzen, Nencki*). As yet it has not been definitely determined where urea is formed, but the **liver** and, perhaps, the lymph glands, are organs where it is produced (§ 178).

In **birds**, the liver forms uric acid from ammonia. The liver can be readily excluded from the circulation in birds, and Minkowski found that after this operation the uric acid was diminished and the ammoniacal salts were increased (§ 178).

Antecedents.—During digestion, the proteids are converted into leucin, tyrosin, glycin, and aspartic acid. If the amido acids, glycin, leucin, or aspartic acid, or ammoniacal salts, be given to an animal, the amount of urea excreted is increased. As the molecule of the amido acids contains only one atom of N, and the molecule of urea contains two of N, it is probable that urea may be formed *synthetically* from these acids. It is possible that the amido acids meet with nitrogenous residues in the juices of the body, *e. g.*, carbamic acid or cyanic acid. The union of these may produce urea. According to Salkowski, feeding with these substances causes the breaking up of the proper proteids of the body so as to provide the necessary components. Schmiedeberg is of opinion that urea is formed in the body from ammonia carbonate by the removal of water; and v. Schröder found that, when he passed blood containing ammonia carbonate through a fresh liver, the urea in the blood was greatly increased Drechsel succeeded in producing urea at ordinary temperatures by the rapid alternating oxidation and reduction of a watery solution of ammonia carbonate. [We know that the greater part of the urea exists in the blood, and that the renal epithelium removes it from the blood. Although it is surmised that some of the nitrogenous bodies named above, more especially leucin, and perhaps also kreatin, are the precursors of urea, yet we cannot say definitely how or where the transformation takes place. Perhaps this is effected in the liver, and, it may be, also in the spleen (§ 193).]

Preparation.—Urea may be prepared from **dog's urine** (especially after a diet of flesh) by evaporating it to a syrupy consistence, extracting it with alcohol, and again evaporating the filtrate to a syrupy consistence. The crystals which separate are washed with water to remove any extractives that may be mixed with them, and dissolved in absolute alcohol. It is then filtered, and allowed to crystallize slowly. Or, **human urine** may be evaporated to one-sixth of its volume and cooled to 0°, and excess of strong nitric acid added, which precipitates urea nitrate mixed with coloring matter. This precipitate is pressed in blotting paper, then dissolved in boiling water containing animal charcoal, and filtered while hot. When it cools, colorless crystals of urea nitrate separate (Fig. 252). These crystals are redissolved in warm water, and barium carbonate added until effervescence ceases; urea and barium carbonate are formed. Evaporate to dryness, extract with absolute alcohol, filter, and allow evaporation to take place, when urea separates.

Compounds of Urea.—Urea combines with acids, bases, and salts. The following are the most important combinations:—

1. **Urea nitrate** (CH_4N_2O, HNO_3) is easily soluble in water, and not so soluble in water containing nitric acid. It forms characteristic rhombic crystals (Fig. 252, 3, 4, 5, 6). Sometimes the formation of these crystals is used to determine **microscopically** the presence of urea in a fluid. If a fluid is suspected to contain minute traces of urea, it is concentrated and a drop of the fluid is put on a microscopic slide. A thread is placed in the fluid, and the whole is covered with a cover-

glass. A drop of concentrated nitric acid is allowed to flow under the cover-glass, and after a time crystals of urea nitrate adhering to the thread may be detected with the microscope.

2. **Urea oxalate** ($CH_4N_2O)_2$, $C_2H_2O_4 + H_2O$, is made by mixing a concentrated solution of urea with oxalic acid. The crystals form groups of rhombic tables, often of irregular shape. It is only slightly soluble in cold water, and still less so in alcohol (Fig. 253).

3. **Urea phosphate** (CH_4N_2O, H_3PO_4), forms large, glancing, rhombic crystals, very easily soluble in water. It is obtained by evaporating the urine of pigs fed on dough.

4. **Sodic chloride + urea** (CH_4N_2O, $NaCl + H_2O$) forms rhombic, shining prisms, which are sometimes deposited in evaporated human urine.

5. **Urea + mercuric nitrate** is obtained as a white cheesy precipitate, when mercuric nitrate is added to a solution of urea. Liebig's titration method for urea depends on this reaction (§ 257, II).

257. QUALITATIVE AND QUANTITATIVE ESTIMATION OF UREA.—I. The qualitative Estimation of Urea.—(1) *It may be isolated as such.* If *albumin* be present, add to the fluid three or four times its volume of alcohol, and, after several hours, filter. Evaporate the filtrate over a water bath, and dissolve the residue in a few drops of water.

(2) The crystals of **urea nitrate** may be detected microscopically (Fig. 252).

II. Quantitative Estimation.—(1) **Sodic hypobromite** decomposes urea into CO_2, H_2O, and N. On this reaction depends the Knop-Hüfner method of quantitative estimation. The N rises in

FIG. 253.

Perfect crystals of oxalate of urea.

FIG. 254.

Ureameter of Charteris.

the form of small bubbles in the mixed fluid, while the CO_2 is absorbed by the caustic soda. [The reaction is the following:—

$$N_2H_4CO + 3NaBrO = 3NaBr + CO_2 + 2H_2O + N.$$

The nitrogen is collected and estimated in a graduated tube, and the amount of urea calculated from the volume of nitrogen. The uric acid is also decomposed, but that can be estimated separately and a correction made. We may use the apparatus of Russell and West, or Dupré, or that of Charteris (Fig. 254).]

[**Ureameter.**—Make a solution of hypobromite of soda by mixing 100 grammes NaHO in 250 c. c. of water, and adding 25 c. c. of bromine. It is better to be made fresh, as it decomposes by keeping. The graduated tube is placed in a cylindrical vessel, filled with water, and depressed until the zero on the tubes coincides with the level of the water. Introduce 15 c. c. of the hypobromite solution into the pyramidal-shaped bottle, while into a short test-tube are placed 5 c. c. of urine. The test-tube with the urine is introduced into the bottle by means of a pair of forceps in such a way that it does not spill. Close the bottle tightly with the caoutchouc stopper, through which passes a glass tube to connect it with the graduated burette. Incline the bottle so as to allow the urine to mix with the hypobromite solution when the gases are given off, and pass into the collecting tube, which is gradually raised until the surfaces of the liquids, outside and in, coincide. Time should be allowed to permit the whole apparatus to have the same temperature. Read off the amount of gas N

evolved, for the CO_2 is absorbed by the caustic soda. The collecting tube is usually graduated beforehand, so that each division of the tube is = 0.1 per cent. of urea, or 0.44 gr. per fluid oz. Thus, suppose that 50 oz. of urine are passed in twenty-four hours, and that 5 c. c. of urine evolve 18 measures of N, then $0.44 \times 18 \times 50 = 396$ grs. of urea. If, however, the tube be graduated into c. c., then 30.3 c. c. of N = 0.1 grm. of urea at the ordinary temperature and pressure.]

III. Volumetric Method (*Liebig*).—By means of a graduated pipette (Fig. 255), 40 cubic centimetres of the urine are placed in a beaker; add 20 cubic centimetres of **barium mixture** to precipitate the sulphuric and phosphoric acids. The barium mixture consists of 1 vol. of a cold saturated solution of barium nitrate and 2 vols. of a cold saturated solution of barium hydrate. Filter through a *dry* filter, and take 15 cubic centimetres of the filtrate, *which correspond to* 10 c. c. *of urine*, and place in a beaker. Allow a titrated **standard solution** of **mercuric nitrate** to drop from a burette into the urine until a precipitate no longer occurs. The mercuric nitrate is made of such a strength that 1 cubic centimetre of it will combine with 10 milligrammes of urea. Test a drop of the mixture from time to time in a watch glass or piece of glass blackened on its under surface, with a solution of **sodic carbonate**, which is called the **indicator**. Whenever the slightest excess of mercuric nitrate is added, the mixture strikes a *yellow* color with the soda. The standard solution must be added drop by drop until this result is obtained. Read off the number of cubic centimetres of the standard solution used; as each centimetre corresponds to 10 milligrammes of urea, multiply by ten, and the amount of urea in 10 cubic centimetres of urine is obtained.

FIG. 255.

Graduated Pipette.

This method does not give quite accurate results even in normal urine. To urine containing much phosphates is added an equal volume of the barium mixture. Very acid urines may require several volumes to be added. Urine containing albumin or blood must be boiled, after the addition of a few drops of acetic acid, to remove the albumin. The sodic chloride in the urine also interferes with the accuracy of the process, as on adding mercuric nitrate to urine, mercuric chloride and sodic nitrate are formed, so that the urine does not combine until the sodic chloride is decomposed. When the urine contains, as is usually the case, 1 to 1½ per cent. NaCl, deduct 2 c. c. from the number of c. c. of the S.S. added to 10 c. c. of urine.

Estimation of the total N in Urine.—Pflüger and Bohland recommend the following modification of the method of *Kjeldahl*. Five c.c. of a urine of medium concentration are allowed to flow from a burette into Erlenmeyer's flask, capable of containing about 300 c.c., and to it are added 20 c.c. of concentrated sulphuric acid. The whole is boiled until all the water and gases are driven off. The fluid at first becomes black from the action of the sulphuric acid, but when it has become of brownish tone lessen the heat of the Bunsen burner. About half an hour suffices to heat it, when the fluid at last becomes bright yellow. Allow it to cool, dilute it with water to 200 c.c., and place the whole in a flask, add 80 c.c. of caustic soda (S.g. 1.3), cork the flask as quickly as possible, and distill its contents. The distillate must pass over into sulphuric acid, which must be titrated beforehand. The quantity of sulphuric acid not combined with ammonia must be estimated by titration with caustic soda.

The **N in the Urine** may be estimated approximately thus. To 10 c.c. of the urine add from a burette Liebig's mercuric nitrate solution, and test the mixture in a black glass plate with dry sodic bicarbonate until a yellow speck remains. Multiply the number of c.c. of the burette fluid used by 0.04 (*Pflüger and Bohland*).

258. URIC ACID = $C_5H_4N_4O_3$ is the nitrogenous substance which, next to urea, carries off most of the N from the body; in twenty-four hours 0.5 grm. (7 to 10 grains); during hunger, 0.24 grm. (4 grains); after a strongly animal diet, 2.11 grm. (30 to 35 grains) are excreted. The proportion of urea to uric acid is 45 : 1. If a mammal be fed with uric acid, part of it becomes more highly oxidized into urea, while the oxalic acid in the urine is also increased (§ 260); in fowls, feeding with leucin, glycin, or aspartic acid (*v. Knieriem*), or ammonia carbonate (*Schroeder*), increases the amount of uric acid. When urea is administered to fowls, it is *reduced* chiefly to uric acid.

It is the chief nitrogeneous product in the urine of birds, reptiles, and insects, while it is absent from herbivorous urine.

Properties.—It is dibasic, colorless, and crystallizes in various forms (Figs. 256 and 257), belonging to the **rhombic system** (1). When the angles are rounded, the *whetstone* form (2) is produced, and if the long surfaces be flattened, six-sided tables occur. Not unfrequently diabetic urine deposits spontaneously, large, yellow, transparent rosettes (6, 8). If 20 c.c. of HCl, or acetic acid, be added to 1 litre of

urine, crystals (9) are deposited, like cayenne pepper, on the surface and sides of the glass, *after several hours*. [The HCl decomposes the urates, and liberates the acid, which does not crystallize at once, owing to the presence of the phosphates in the urine. Crystals of uric acid are usually yellowish in color from the pigment of the urine, and they are soluble in caustic potash.]

Solubility.—It is tasteless and odorless; reddens litmus; is soluble in 18,000 parts of cold and in 15,000 of boiling water, and insoluble in alcohol and ether. Horbaczewski prepared it synthetically by melting together glycin, or, as it is also called, glycocin, and urea. It is freely soluble in alkaline carbonates, borates, phosphates, lactates, and acetates, these salts at the same time removing a part of the base; thus, there are formed acid urates and acid salts from the neutral salts. It is soluble in concentrated sulphuric acid, from which it may be precipitated by the addition of water.

Decomposition.—During dry distillation it decomposes into urea, cyanuric acid, hydrocyanic acid, and ammonium carbonate. Superoxide of lead converts it into urea, allantoin, oxalic acid, and CO_2; while ozone forms the same substances, with the addition of alloxan. When it is reduced by H *in statu nascendi*, as by sodium amalgam, it forms xanthin and sarkin. It is a less oxidized metabolic product than urea, but it is by no means proved that uric acid is a precursor of urea.

FIG. 256.

Forms of uric acid. 1, Rhombic plates; 2, whetstone forms; 3, quadrate forms; 4, 5, prolonged into points; 6, 8, rosettes; 7, pointed bundles; 9, barrel forms precipitated by adding hydrochloric acid to urine.

Occurrence.—Uric acid occurs dissolved in the urine in the form of **acid urates of soda and potash.** These salts occur also in urinary calculi, gravel, and in gouty deposits. Ammonium urate occurs in very small quantity in a deposit of **"urates,"** but is formed in considerable amount when urine becomes ammoniacal from decomposition (Fig. 261). *Free uric acid* occurs in normal urine only in the very smallest amount. It is sometimes deposited *after a time* (Fig. 260). It frequently forms urinary calculi and gravel.

The urine of newly-born children contains much uric acid. Uric acid and its salts are **increased** after severe muscular exertion, accompanied by perspiration, in catarrhal and rheumatic fevers, and such conditions as are accompanied by disturbance of the respiration; in leukæmia and tumors of the spleen, cirrhotic liver, and generally in cases of catarrah of the stomach and intestinal tract, following the excessive use of alcohol. [It is also increased during ague and fevers, and perhaps this has some relation to the congestion of the spleen which accompanies these conditions.] It is **diminished** after copious draughts of water, after large doses of quinine, caffein, potassic iodide, common salt, sodic and lithic carbonates, sodic sulphate, inhalation of O, slight muscular exertion. In gout, the amount excreted in the urine is small. In chronic tumors of the spleen, anæmia, and chlorosis, when the respiration is not at the same time embarrassed, it is also diminished.

Urates.—Uric acid forms salts—chiefly *acid* urates—with several bases, which dissolve with difficulty in cold water, but are easily soluble in warm water. Neutral urates are changed by CO_2 into acid salts. Hydrochloric and acetic acids break up the compounds, and crystals of uric acid separate.

(1) **Acid sodic urate** usually appears as a brick-red deposit in urine; more rarely gray or white (lateritious deposit), tinged with uroërythrin, in catarrhal conditions of the digestive organs, and in rheumatic and febrile affections. **Microscopically,** it is completely amorphous, consisting of granules, sometimes disposed in groups (Fig. 260, *b*)—sometimes the granules have spines on them. The corresponding potash salt occurs not unfrequently under the same conditions, and presents the same characters.

(2) **Acid ammonium urate** (Fig. 261, *a*) always occurs as a sediment in ammoniacal urine, either with (1), or mixed with free uric acid, accompanied by a triple phosphate. Microscopically, it is the same as (1). (1) *and* (2) *are distinguished by the sediment dissolving when the urine is heated.* If a drop of hydrochloric acid be added to a microscopic preparation of the sediment, crystals of uric acid separate.

(3) **Acid calcic urate** occurs sometimes in calculi, and is a white, amorphous powder, slightly soluble in water. When heated on platinum it leaves an ash of calcium carbonate. Magnesium urate rarely occurs in urinary calculi.

259. ESTIMATION OF URIC ACID.—I. Qualitative.—1. Microscopic Characters.—The appearances presented by uric acid and its salts under the microscope. It is deposited from urine after several hours, on adding acetic or hydrochloric acid.

2. **Murexide Test.**—Gently heat a urate or uric acid in a porcelain vessel along with nitric acid. Decomposition takes place and the color changes to yellow. N and CO_2 are given off; urea and alloxan ($C_4H_2N_2O_4$) remain. Evaporate slowly and allow the yellowish-red stain to cool; on adding a drop of dilute ammonia a *purplish-red* color of murexide is obtained, it becomes blue on the addition of caustic potash. If potash or soda be added instead of ammonia, a violet color is obtained.

3. **Schiff's Test.**—Dissolve uric acid or a urate in a solution of an alkaline carbonate, and drop it upon blotting-paper saturated with a solution of *silver nitrate;* reduction of the silver takes place at once, and a black spot is formed.

4. On boiling a solution of uric acid or a urate in an alkali, with Fehling's solution (§ 149, 2), at first white urate of the suboxide of copper is deposited, while later, red copper suboxide is formed.

II. Quantitative Estimation.—Add 5 cubic centimetres of concentrated HCl to 100 c.c. of urine, and allow it to stand for forty-eight hours in the dark, when the uric acid is precipitated like fine cayenne pepper crystals. All the uric acid is not precipitated by the HCl, even after standing for a time. [E. A. Cook uses sulphate of zinc to precipitate the uric acid as urate of zinc. Caustic soda is added to precipitate the phosphates, and then to the clear fluid zinc sulphate solution, which precipitates urate of zinc as a white gelatinous deposit.]

Fokker-Salkowski Method.—Make 200 c.c. of urine strongly alkaline with sodic carbonate, and after an hour add 200 c.c. of a concentrated solution of ammonium chloride, whereby acid urate of ammonium is precipitated. After forty-eight hours filter, through a small weighed filter, and wash it several times. Fill the filter with dilute HCl and collect the filtrate. Do this until all the acid urate is dissolved. From the total filtrate after a time all the uric acid separates. It is collected in the same filter, washed with water and alcohol until the acid reaction disappears, dried at 100° C. and weighed. To the weight in excess of the filter add 0.030 grm.

260. KREATININ AND OTHER SUBSTANCES.—**Kreatinin,** $C_4H_9N_3O_2$, is derived from the kreatin of muscle by the removal of a molecule of water, and partly from flesh food. The **quantity** excreted daily is 0.6 to 1.3 gramme (8 to 18 grains).

It is **diminished** in progressive muscular atrophy, tetanus, anæmia, marasmus, chlorosis, consumption, paralysis; and is **increased** in typhus, inflammation of the lung; it is absent from the urine of sucklings.

Properties.—Kreatinin is alkaline, easily soluble in water and hot alcohol. It forms colorless, oblique rhombic columns; unites with acids and salts, silver nitrate, mercuric chloride, and especially with *zinc chloride.* **Kreatinin-zinc chloride** (Fig. 257) is used to detect its presence. **Weyl's Test.**—Add to urine a few drops of a slightly brownish solution of nitro-prusside of soda, and then weak caustic soda solution, producing a Burgundy-red color, which soon disappears.

When heated with glacial acetic acid, the color changes to green, which after a time changes to blue (*Salkowski*). [The blue color—Berlin blue—is due to the formation of an iron salt, ferrocyanide of sodium, from the decomposition of the nitro-prusside. The reaction also succeeds with formic acid—instead of glacial acetic acid—if some time be allowed to elapse after Weyl's reaction.]

Xanthin = $C_5H_4N_4O_2$ occurs only to the amount of 1 gramme in 300 kilos. of urine. It is a substance intermediate between sarkin and uric acid. Guanin and hypoxanthin may be changed into xanthin; in contact with water and ferments it passes into uric acid. When evaporated with nitric acid, it gives a yellow stain, which becomes yellowish-red on adding potash, and violet-red on applying more heat. It is an amorphous, yellowish-white powder, fairly soluble in boiling water. It has also been found in traces in muscles, brain, liver, spleen, pancreas and thymus. The crystalline body **paraxanthin** (dimethylxanthin) and the amorphous **heteroxanthin** (methylxanthin) occur in traces in the urine (*Salomon*).

Sarkin or Hypoxanthin, $C_5H_4N_4O$.—As yet this substance has been found only in the urine of leukæmic patients (*Jakubasch*), and it has been prepared in the form of needles or flattened scales from muscle, spleen, thymus, brain, bone, liver and kidney. In *normal* urine a body nearly related to, and possibly identical with, hypoxanthin occurs (*E. Salkowski*). Hypoxanthin closely resembles xanthin, and can be changed into it by oxidation. Nascent hydrogen, on the other hand, reduces uric acid to xanthin and hypoxanthin. When evaporated with nitric acid it gives a light yellow stain, which becomes deeper, but not reddish-yellow, on adding caustic soda. It is more easily soluble in water than xanthin, and by this means the two substances can be separated from each other. Guanin is insoluble in water.

FIG. 257.



Kreatinin-zinc chloride. *a*, balls with radiating marks; *b*, crystallized from water; *c*, from alcohol.

FIG. 258.

Oxalate of lime. *a*, *b*, octahedra; *c*, compound forms; *d*, dumb bells.

Oxaluric acid ($C_3H_4N_2O_4$) occurs in *very small quantity* combined with ammonia in uri[illegible]ne. Physiologically, it is interesting on account of its relation to uric acid. It is a white powder sligh[illegible]tly soluble in water. Ammonia oxalurate can be prepared from uric acid.

Oxalic Acid ($C_2H_2O_4$) occurs, but not constantly, to the amount of 20 mil[illegible]li-grammes daily as **oxalate of lime,** which is known by the "envelope" shape of the crystals (Fig. 258); insoluble in acetic acid, and forming transparent octahedr[illegible]ra. More rarely it assumes a biscuit or sand-glass form. The genetic relation of oxal[illegible]lic acid to uric acid is shown by the fact that dogs fed with uric acid excrete muc[illegible]ach oxalate of lime. Oxalic acid may also be produced by the oxidation of produc[illegible]cts derived from the fatty acid series (p. 430).

Oxaluria.—The eating of substances containing oxalate of lime (rhubarb) increases the exc[illegible]re-tion. Increased excretion is called oxaluria; it is regarded as a sign of retarded metabolism (*Benek[illegible]br*), and it may give rise to the formation of a calculus. In oxaluria the uric acid is also often increas[illegible]sed in amount. Perhaps, in the first instance, there is an increased formation of uric acid, from whi[illegible]nich oxalic acid, urea, and CO_2 may be formed. The amount of oxalic acid is increased after the use [illegible]of wine and sodic bicarbonate.

Hippuric Acid = $C_9H_9NO_3$ (Benzoylamidoacetic acid) occurs in large amount in the urine of herbivora, and in them is the chief end product of the metabolism of nitrogenous substances; in human urine the daily **quantity** is small, 0.3 to 3.8 grms. (5 to 50 grains). It is an odorless monobasic acid with a bitter taste, crystallizing in colorless four-sided prisms (Fig. 259). Readily soluble in alcohol, and soluble in 600 parts of water.

[Crystals of hippuric acid when **heated** in a test-tube are decomposed, and a sublimate of benzoic acid and ammonic benzoate condenses on the upper cool part of the tube, while there is an odor of new hay, and oily drops remain in the tube.]

It is a conjugated acid, and is formed in the body from benzoic acid, or some nearly related chemical body, such as the cuticular substance of plants, or from oil of bitter almonds, cinnamic or chinic acid, which easily pass by reduction (chinic acid) or by oxidation (cinnamic acid) into benzoic acid; glycin uniting with it, with the formation of water—

$$\underset{\text{Benzoic acid}}{C_7H_6O_2} + \underset{\text{Glycin}}{C_2H_5NO_2} = \underset{\text{Hippuric acid}}{C_9H_9NO_3} + \underset{\text{Water.}}{H_2O}$$

[**Formation.**—When benzoic acid is introduced into the alimentary canal of an animal (rabbit or dog), it appears in the urine as hippuric acid; while nitro-benzoic acid appears as nitro-hippuric acid. As the benzoic acid passes through the body, it becomes conjugated with glycin or glycocin, chiefly in the kidneys. The hippuric acid in the urine of herbivora is chiefly derived from some substance with a benzoic acid residue present in the cuticular coverings of the food. That hippuric acid, in part at least, is **formed in the kidneys** is shown by the following considerations: If arterialized blood, containing benzoic acid and glycin, or even benzoic acid alone, be passed through the blood vessels of a fresh, living, excised kidney, hippuric acid is found in the blood after it is perfused. Even after forty-eight hours, if the kidney be kept cool, the synthesis takes place. If the kidney be kept too long, the conjugation does not take place. If the fresh kidney be chopped up, and kept at the temperature of the body with benzoic acid and glycin, hippuric acid is formed. Oxygen seems to be necessary for the process, for, if blood or serum containing carbonic oxide be used, there is no formation of hippuric acid.]

FIG. 259.

Hippuric Acid.

According to this view, it is derived chiefly from the food of herbivorous animals, and hence it is absent from the urine of sucking calves, as well as after feeding with grain devoid of husk. But it is also formed in the body from the proteids. In the dog, the formation of hippuric acid occurs in the kidney (*Schmiedeberg and Bunge*), and in the frog also outside the kidney. Kühne and Hallwachs thought it was formed in the liver, and Jaarsveld and Stockvis in the kidney, liver, and intestine. The observation of Salomon that, after excision of the kidneys in rabbits, and injection of benzoic acid into the blood, hippuric acid was found in the muscles, blood, and liver, goes to show that it must be formed in other organs beside the kidneys. The power of changing benzoic acid introduced into the human body into hippuric acid, may even be abolished in disease of the kidney. Under certain circumstances it seems that hippuric acid, already formed, may be again decomposed in the tissues.

It is greatly **increased** after eating pears, plums and cranberries; in icterus, some liver affections,

and in diabetes. When boiled with strong acid or alkalies, or with putrid substances, it takes up H_2O and splits into benzoic acid and glycin.

Preparation.—Add milk of lime to the *fresh* urine of horses or cows to form calcic hippurate. Filter, evaporate the filtrate to a small bulk, and precipitate the hippuric acid with excess of hydrochloric acid. To purify the hippuric acid, crystallize it several times from a hot watery solution.

Cyanuric Acid.—$C_{20}H_{14}N_2O_6 + H_2O$ occurs in the urine of dogs (*J. v. Liebig*).

Allantoin, $C_4H_6N_4O_3$, which occurs in the amniotic fluid of the cow, is found in minute traces in normal urine after flesh food, and is more abundant during the first weeks of life, and during pregnancy.

After large doses of tannic acid, the amount is increased (*Schottin*), while in dogs feeding with uric acid also increases it (*Salkowski*).

Properties.—It forms shining prismatic crystals; from the urine of sucking calves it crystallizes in transparent prisms. It is decomposed by ferments into urea, ammonium oxalate, and carbonate, and another as yet unknown body. **Preparation**—(*a*) the urine is precipitated with basic lead acetate, the lead in the filtrate is removed by sulphuretted hydrogen, and the filtrate itself is then evaporated to a syrup, from which the crystals separate, after standing for several days. They are then washed with water, and recrystallized from the water (*Salkowski*).

261. COLORING MATTERS OF THE URINE.—1. **Urobilin** is most abundant in the highly colored urine of fevers, but it also occurs in normal urine (*Jaffé*). It is identical with the hydrobilirubin of Maly (§ 117, 3, *g*). It is a derivative of hæmatin, which also yields the *bile pigments* (§ 177). It gives a *red* or *reddish-yellow* color to urine, which becomes yellow on the addition of ammonia.

[MacMunn, chiefly from spectroscopic observations, finds that two entirely different substances have been included under the name of "urobilin," viz., that of normal and that of pathological urine, and that hydrobilirubin is not identical with either. The pathological urobilin seems to be closely connected with stercobilin (§ 185).]

Preparation.—Prepare a chloroform extract of urine containing urobilin—add iodine to the extract, and remove the iodine by shaking the mixture with dilute caustic potash, which forms potassic iodide. This potash solution becomes yellow or brownish-yellow, and exhibits beautiful green *fluorescence* (*Gerhardt*).

Urobilin may be extracted from many urines by ether (*Salkowski*). When subjected to the action of reducing agents, *e.g.*, sodium amalgam, a colorless product is obtained, which on exposure to the air absorbs O, and becomes re-transformed into urobilin. This colorless body is identical with the chromogen which Jaffé found in urine.

If urine is treated with soda or potash, the characteristic absorption band lying between *b* and F passes nearer to *b*, becomes darker and more sharply defined. According to Hoppe-Seyler, urobilin is formed in urine after it is voided, from another urobilin-forming body (Jaffé's chromogen) absorbing oxygen. If urine containing urobilin be made alkaline with ammonia, and zinc chloride be added, it exhibits marked *fluorescence*; it has a *green* shimmer by reflected light. When urobilin is *isolated*, it fluoresces without the addition of zinc chloride. In cases of jaundice (§ 180), where Gmelin's test sometimes fails to reveal the presence of bile pigments, urobilin occurs. This "urobilin-icterus" (*Gerhardt*) occurs chiefly after the absorption of large extravasations of blood. According to Cazeneuve, the urobilin is increased in all diseases where there is increased disintegration of blood corpuscles.

2. **Urochrome** (*Thudichum*) is regarded as the chief coloring matter of urine. It may be isolated in the form of yellow scales, soluble in water, and in dilute acids and alkalies. The watery solution oxidizes, and when exposed to air becomes red, owing to the formation of **uroerythrin.** When acted on by acids, new decomposition products are formed, *e.g.*, **uromelanin.** Uroerythrin gives the red color to deposits of urates (§ 258).

3. A brown pigment containing iron is carried down with uric acid, which is precipitated on the addition of hydrochloric acid (§ 258). By repeatedly adding sodic urate to the urine, and precipitating the uric acid by hydrochloric acid, a considerable amount may be obtained (*Kunkel*).

4. Urine boiled with HCl yields a garnet-red crystalline pigment, **urorubin,** to ether.

In cases of melanotic tumors, there has been occasionally observed urine, which becomes dark, owing to **melanin** (§ 250, 4), or to a coloring matter containing iron (*Kunkel*).

262. INDIGO, PHENOL, KRESOL, PYROKATECHIN, AND SKATOL-FORMING SUBSTANCES.—1. **Indican** [$C_8H_7NSO_4$], or indigo-forming substance (*Schunck*), is derived from indol, C_8H_7N, the basis of

indigo, which is formed in the intestine by the pancreatic digestion of proteids (§ 170, II), but it also arises as a putrefactive product (§ 184, 6). Indol, when united with the radical of sulphuric acid, HSO_3, and combined with potassium, forms the so-called *indigogen* or *indican* of urine (*Brieger, Baumann*). This substance ($C_8H_6NSO_4K$ = potassium indoxyl-sulphate) forms white glancing tablets and plates; readily soluble in water, and less so in alcohol. By oxidation it forms indigo-blue; 2 indican + O_2 = $C_{16}H_{10}N_2O_2$ (indigo blue) + $2HKSO_4$ (acid potassic sulphate). It is more abundant in the urine in the tropics, and it is absent from the urine of the newly born (*Senator*).

Tests.—(1) Add to 40 drops of urine 3 to 4 c.c. of strong fuming hydrochloric acid, and 2 to 3 drops of nitric acid. Boil, a *violet red* color (with the deposition of true *crystalline indigo blue* (rhombic) and indigo red attest its presence. Putrefaction causes a similar decomposition in indican; hence, we not unfrequently observe a bluish-red pellicle of microscopic crystals of indigo blue, or even a precipitate of the same. (2) Mix in a beaker equal quantities of urine and hydrochloric acid, and add two drops of solution of chlorinated lime; the mixture at first becomes clear, then blue (*Jaffé*). Add chloroform, and shake the mixture vigorously for some time; the chloroform dissolves the blue coloring matter, which is obtained as a deposit, when the chloroform evaporates (*Senator, Salkowski*). (3) Heat to 70° one part of urine with two parts of nitric acid, and shake up with chloroform; the chloroform dissolves the indigo which is formed, assumes a violet color, and gives an absorption band between C and D, slightly nearer D (*Hoppe-Seyler*). **Quantity.**—Jaffé found in 1500 c.c. of normal human urine 4.5 to 19.5 milligrammes of indigo; horse's urine contains 23 times as much. The subcutaneous injection of indol increases the indican in the urine (*Jaffé*). E. Ludwig obtained indican by heating hæmatin or urobilin with a caustic alkali and zinc dust. It has also been found in the sweat (*Bizio*).

Pathological.—The indican in the urine is **increased** when much indol is formed in the intestine (§ 172, II), *e.g.*, in typhus, lead colic, trichinosis, catarrh, and hemorrhage of the stomach, cholera, carcinoma of the liver and stomach; obstruction of the bowel or ileus, peritonitis, and diseases of the small intestine.

2. **Phenol**, C_6H_6O (carbolic acid, § 252), was discovered by Städeler in human urine (more abundant in horse's urine). It does not occur as carbolic acid, but in combination with a substance from which it is separated by distillation with dilute mineral acids. The "phenol-forming substance" is, according to Baumann, "**phenolsulphonic acid**" (C_6H_5O,SO_3H), which in urine is united with potash.

Phenol is derived from the decomposition of proteids by pancreatic digestion (§ 172, II), and also from putrefaction (§ 184, 6), the mother substance being tyrosin. Hence the formation of phenolsulphonic acid is analogous to the formation of indican.

If in the employment of carbolic acid it be absorbed, the phenolsulphonic acid becomes greatly increased in amount, so that sulphuric acid must be united with it; hence, alkaline sulphates are decomposed in the body, so that the latter may be absent from the urine (*Baumann*). Living muscle or liver, when digested in a stream of air for several hours with blood to which phenol and sodic sulphate are added, yields phenolsulphonic acid; while, under the same circumstances, pyrokatechin forms ethersulphonic acid.

Carboluria.—When carbolic acid is used externally or internally, and it is absorbed, it causes a *deep, dark colored* urine, due to the oxidation of phenol into **hydrochinon** (orthobioxybenzol = $C_6H_6O_2$), which for the most part appears in the urine as ethersulphonic acid (*Baumann and others*).

3. **Parakresol** (hydroxyltoluol, C_7H_8O), with its isomers **ortho-** and **meta-kresol** (the latter in traces), is more abundant in urine (*Baumann, Preusse*). It also occurs in combination with sulphonic acid.

Test for phenol (and also kresol): Distill 150 c.c. urine with dilute sulphuric acid. The distillate gives a brown crystalline deposit of tribromophenol with bromine water, as well as a red color with Millon's reagent.

Hydroxybenzol (pyrokatechin, hydrochinon) is obtained from urine, when it is heated for a long time with hydrochloric acid.

Resorcin, which is an isomer of hydrochinon, when administered internally, also appears in the urine as ethersulphonic acid. Toluol and naphthalin behave similarly. Benzol is oxidized to phenol.

4. **Pyrokatechin** = $C_6H_6O_2$ (metadihydroxylbenzol), is formed along with

hydrochinon from phenol, and is an isomer of the former. It behaves like indol and phenol, for when united with sulphonic acid, it yields the pyrokatechin-forming substance. Small quantities sometimes occur in human urine; it is more abundant in the urine of children; it becomes darker when the urine putrefies.

5. **Skatol,** which is crystalline, and is formed during putrefaction in the intestine, also appears in the urine as a compound of sulphonic acid (§ 252). On feeding a dog with skatol, Brieger found much potassic skatol-oxysulphate.

Test.—Skatol compounds are recognized by adding dilute nitric acid, which causes a violet color, or fuming nitric acid, which precipitates red flakes (*Nencki*). Its quantity is regulated by the same conditions as indican.

The **aromatic oxyacids, hydroparacumaric acid,** and **paraoxyphenylacetic acid** (the former a putrefactive product of flesh, the latter obtained by E. and H. Salkowski from putrid albumin) occur in the urine (*Baumann*, § 252). Shake the urine treated with a mineral acid with ether, evaporate the latter, and dissolve the residue in water. If aromatic oxyacids are present, they give a red color with Millon's reagent.

Baumann gives the following series of bodies, which are formed from tyrosin by decomposition and oxidation; most of the substances are formed both during the decomposition of albumin, and also in the intestine, whence they pass into the urine: Tyrosin, $C_9H_{11}NO_3 + H_2 = C_9H_{10}O_3$ (hydroparacumaric acid) $+ NH_3$. $C_9H_{10}O_3 = C_8H_{10}O$ (paraethylphenol, not yet proved) $+ CO_2$. $C_8H_{10}O + O_3 = C_8H_8O_3$ (paraoxyphenylacetic acid) $+ H_2O$. $C_8H_8O_3 = C_7H_8O$ (parakresol) $+ CO_2$. $C_7H_8O + O_3 = C_7H_6O_3$ (paraoxybenzoic acid, not yet proved) $+ H_2O$. $C_7H_6O = C_6H_6O$ phenol $+ CO_2$.

Potassium sulphocyanide, derived from the saliva, also occurs in urine. After acidulation with hydrochloric acid, its presence may be detected by the ferric chloride test (§ 146—*Gscheidlen and J. Munk*). One litre of human urine contains 0.02 to 0.08 gramme combined with an alkali.

Succinic Acid ($C_4H_6O_4$) occurs chiefly after a diet of flesh and fat, and almost disappears after a vegetable diet. It is a decomposition product of asparagin, and occurs in considerable amount in the urine after eating asparagus. It is also a product of the alcoholic fermentation (§ 150), and as it passes out of the body unchanged, it occurs in the urine of those who imbibe spirituous liquors. It passes unchanged into the urine (*Neubauer*).

Lactic acid ($C_3H_6O_3$) is a constant constituent of urine. Other observers have found fermentable lactic acid in diabetic urine; sarcolactic acid after poisoning with phosphorus and in trichinosis. Occasionally traces of **volatile fatty acids** are present. Some **animal gum** occurs in urine (p. 431), and Bechamp's "**nephrozymose**" consists for the most part of gum (*Landwehr*). This substance is precipitated from urine by adding to it three times its volume of 90 per cent. alcohol. It is not a simple body, but at 60° to 70° C. it transforms starch into sugar (*v. Vintschgau*).

Ferments.—Traces of **diastatic, peptic,** and **rennet** ferment have been found, especially in urine of high specific gravity. Trypsin is said not to occur normally (*Leo*).

Traces of **sugar** (*Brücke, Bence Jones*), to the amount of 0.05 to 0.01 per cent., occur in normal urine. After the ingestion of milk-, cane-, or grape sugar, (50 grms.) these varieties of sugar appear in small quantity in the urine (*Worm-Müller*—§ 267, 7).

Kryptophanic acid ($C_9H_9NO_5$), according to Thudichum, occurs as a free acid in urine, but Landwehr regards it as an animal gum.

Aceton (C_3H_6O) is formed when normal urine is oxidized with potassic bichromate and sulphuric acid, and it is formed from a reducing substance present in normal urine (apparently derived from the grape sugar of the blood). Aceton occurs in traces as a normal urinary constituent, which is increased during increased decomposition of the tissues, *e.g.*, carcinoma, inanition. It has also been found in the blood in fever (*v. Jacksch*). **Lieben's Test.**—Acidulate half a litre of urine with HCl and distill; when treated with tincture of iodine and ammonia there is a turbidity due to iodoform.

II. THE INORGANIC CONSTITUENTS OF THE URINE.—The inorganic constituents are either taken into the body as such with the food and pass off unchanged in the urine, or they are formed in the body, owing to the sulphur and phosphorus of the food being oxidized and the products uniting with bases to form salts, The **quantity** of salts excreted daily in the urine is 9 to 25 grammes [¼ to ¾ oz.].

1. **Sodic chloride**—to the **amount** of 12 (10 to 13) grammes [180 grains]—is excreted daily. It is **increased,** after a meal, by muscular exercise, drinking of water, and generally, when the quantity of urine is increased, by the free use of large quantities of common salt, but by potash salts also; it is **diminished** under the opposite conditions.

In **disease** it is greatly **diminished**; in pneumonia and other inflammations accompanied by

effusions, in continued diarrhœa and profuse sweating, constantly in albuminuria and in dropsies. [In cases of pneumonia, sodic chloride may at a certain stage almost disappear from the urine, and it is a good sign when the chlorides begin to reappear.] In other chronic diseases, the amount of NaCl excreted runs nearly parallel with the amount of urine passed. In conditions of excitement the amount of sodic chloride is diminished, and potassic chloride increased; in conditions of depression the reverse is the case (*Zeulzer*).

Test.—Add to the urine nitric acid and then nitrate of silver solution, which gives a white curdy precipitate of chloride of silver. In albuminous urine the albumin must first be removed. *Microscopically* look for the step-like forms of common salt, and also for the crystals of sodic chloride and urea (§ 256, 4).

2. **Phosphoric acid** occurs in urine as **acid sodic phosphate** and **acid calcic** and **magnesic phosphates** to the **amount** of about 2 grammes daily [30 grains]; it is more abundant after an animal than after a vegetable diet. The amount increases after a midday meal until evening, and falls during the night until next day at noon. It is partly derived from the alkaline and earthy phosphates of the food, and partly as a decomposition product of lecithin and nuclein. As phosphorus is an important constituent of the nervous system, the relative increase of phosphoric acid is due to increased metabolism of the nervous substance.

Pathological.—In fevers, the increased excretion of potassic phosphate is due to a consumption of blood and muscle (§ 220, 3.) It is also **increased** in inflammation of the brain, softening of the bones, diabetes, and oxaluria; after the administration of lactic acid, morphia, chloral, or chloroform. It is **diminished** during pregnancy, owing to the formation of the fœtal bones; also after the use of ether and alcohol, and in inflammation of the kidney.

[**Tests.**—To urine add nitric acid and solution of ammonium molybdate and boil, a canary yellow precipitate of ammonium phosphomolybdate indicates the presence of phosphoric acid. Or, add half its volume of caustic potash to urine, and boil. The earthy phosphates are precipitated, but not the alkaline phosphates.]

Earthy phosphates are precipitated by heat in some pathological urines. This precipitate is distinguished from albumin, which is also precipitated by heat, by being soluble in nitric acid, which precipitated albumin is not. [The earthy phosphates are not precipitated until near the boiling point.]

Quantitative.—The *amount* of phosphoric acid is estimated by titration with a *standard solution of uranium acetate; ferrocyanide of potassium* being the *indicator*. The indicator gives a brownish red color when there is an excess of free uranium acetate.

In addition to phosphoric acid, phosphorus occurs in an incompletely oxidized form in the urine, *e.g.*, **glycerinphosphoric acid** (§ 251, 2), which occurs to the amount of 15 milligrammes in a litre of urine; it is **increased in nervous** diseases and after chloroform narcosis.

3. **Sulphuric acid** occurs in the urine, the greater part in combination with the *alkalies*, and the remainder united with indol, skatol, and pyrokatechin, in the form of *aromatic ethersulphonic compounds*, the ratio being 1 : 0.1045. All conditions which favor the formation of indol, skatol, or pyrokatechin, increase the amount of combined sulphuric acid. The total daily **amount** of sulphuric acid is 2.5 to 3.5 grammes [37 to 52 grains]. It is increased by the administration of sulphur (*Krause*). The sulphuric acid is chiefly derived from the decomposition of proteids, and hence its amount runs parallel with the amount of urea excreted. The amount of alkaline sulphates in the food is, as a rule, very small.

An **increased** excretion of sulphuric acid in fevers indicates an increased metabolism of the tissues of the body. In renal inflammation it has been observed to be diminished, and in eczema it is greatly increased. Feeding with taurin (which contains sulphur), in the case of rabbits, (but not in carnivora or man), increases the sulphuric acid in the urine (*Salkowski*). According to Zülzer, a copious secretion of bile lessens the relative amount of sulphuric acid in the urine.

Test.—Barium chloride gives a copious white heavy precipitate of barium sulphate, insoluble in nitric acid.

In addition to sulphuric acid, sulphur ($\frac{1}{5}$) occurs in an incompletely oxidized form in the urine (potassium sulphocyanide, cystin, and sulphur-bearing compounds derived from the bile) (*Kunkel, v. Voit*—§ 177, 6). *Hyposulphurous acid*, as an alkaline salt, is an *abnormal* constituent in typhus; and so is sulphuretted hydrogen, which is recognized by the blackening of a piece of paper moistened with lead acetate and ammonia, held over the urine.

4. Excessively minute traces of **silicic acid** and **nitric acid** derived from drinking water have been found in urine. *Organic acids, e.g.*, citric and tartaric, when taken internally, increase the amount of *carbonates* in the urine. The urine may effervesce on the addition of an acid.

The **sodium** in the urine is chiefly combined with chlorine, but a small part of it is united with phosphoric and uric acids; **potassium** (which is about ⅓ of the sodium) is chiefly combined with chlorine. In fevers, more potash is excreted than soda, and during convalescence, the reverse is the case; **calcium** and **magnesium** exist in normal **acid** urine as chlorides or acid phosphates. If the urine is **neutral**, neutral calcium phosphate and magnesium phosphate are precipitated. Ebstein found the latter in alkaline urine, as large, clear, four-sided prisms, in diseases of the stomach. If the urine is **alkaline**, calcium carbonate (Fig. 281) and tribasic calcic phosphate are deposited as such, while the magnesium is precipitated in the form of ammonio-magnesium phosphate, or triple phosphate. The calcium is derived from the food, and depends upon the amount of lime salts absorbed from the intestine. **Free ammonia** is said to occur (0.72 gramme, or 7 grains daily) in perfectly fresh urine (*Neubauer, Brücke*), and the amount is greater with an animal than with a vegetable diet (*Coranda*). The amount of fixed ammonia is increased by the administration of mineral acids (*Walter, Schmiedeberg, Gäthgens*). **Iron** (1 to 11 milligrammes per litre) is never absent. There is a trace of **hydric peroxide** (*Schonbein*), which is detected by its decolorizing indigo solution on the addition of iron sulphate.

Gases.—24.4 c.c. of gas was obtained from one litre of urine—100 volumes of the gases pumped out consisted of 65.40 vol. CO_2, 2.74 O, 13.86 N. After severe muscular action, the amount of CO_2 may be doubled; digestion also increases it, copious drinking diminishes it.

263. FERMENTATIONS OF URINE.—Acid Fermentation.

When perfectly fresh urine is set aside, it gradually becomes more acid from day to day. This is called the "**acid fermentation.**" It seems to be due to the development of special fungi (Fig. 260, *a*), and the process is accompanied by the

FIG. 260.

Deposit in "acid fermentation" of urine. *a*, fungus; *b*, amorphous sodium urate; *c*, uric acid; *d*, calcium oxalate.

FIG. 261.

Deposit in ammoniacal urine (alkaline fermentation). *a*, acid ammonium urate; *b*, ammonio-magnesium phosphate; *c*, bacterium ureæ.

deposition of *uric acid* (*c*), *acid sodium urate*, in amorphous grains (*b*), and *calcium oxalate* (*d*). According to Scherer the fungus and the mucus from the bladder decompose part of the urinary pigment into lactic and acetic acids. The latter set free uric acid from neutral sodium urate, so that free uric acid and sodium urate must be formed. *Butyric* and *formic acids* have been found as abnormal decomp

sition products of other urinary constituents. When the acid fermentation begins, the urine absorbs oxygen (*Pasteur*). According to Brücke, it is the lactic acid, formed from the minute traces of sugar present in urine, which causes the acidity. According to Röhmann, who recognizes the acid fermentation as an exceptional phenomenon, the acids are formed from the decomposition of sugar, and from alcohol which may be present accidentally. While the urine is still acid, it becomes turbid and contains nitrous acid, whose source is entirely unknown. According to v. Voit and Hofmann, phosphoric acid and a basic salt are formed from acid sodium phosphate, whereby part of the uric acid is displaced from sodium urate, thus causing the formation of an acid urate.

Alkaline Fermentation.—When urine is exposed for a still longer time, more especially in a warm place, it becomes neutral and ultimately ammoniacal, *i.e.*, it undergoes the **alkaline fermentation** (Fig. 261).

This condition is accompanied by the formation of the **micrococcus ureæ** (Fig. 262) (*Pasteur, Cohn*) and Bacterium ureæ (Fig. 261), which causes the urea to take up water and decompose into CO_2 and ammonia.

Urea $[CO(HN_2)_2 + 2(H_2O) =$ ammonium carbonate $[(NH_4)_2CO_3]$.

The property of decomposing urea belongs to many different kinds of bacteria, including even the sarcina of the lungs—whose germs seem to be universally diffused in the air. These organisms produce a **soluble ferment** (*Musculus*), which, however, only passes from the body of the cells into the fluid after the cell or organism has been killed by alcohol (*Lea*).

The presence of ammonia causes the urine to become turbid, and those substances which are insoluble in an alkaline urine are precipitated—**earthy phosphates,** consisting of the amorphous **calcic phosphate, acid ammonium urate** (Fig. 261, *a*), in the form of small, dark granules covered with spines; and, lastly, the large, clear, knife-rest or "coffin lid" form of **ammonio-magnesic phosphate, or triple phosphate** (Fig. 282). [The last substance does not exist *as such* in normal urine, but it is formed when ammonia is set free by the decomposition of urea, the ammonia uniting with the magnesium phosphate. Its presence, therefore, always indicates ammoniacal fermentation of the urine.] In cases of **catarrh** or **inflammation of the bladder,** this decomposition may take place within the bladder, when the urine always contains pus cells (Fig. 267) and detached epithelium. When much pus is present, the urine contains albumin. Ammoniacal urine forms white fumes of ammonium chloride, when a glass rod dipped in hydrochloric acid is brought near it. [When ammonia is added to normal urine, triple phosphate is precipitated in a *feathery* form (Fig. 283).]

FIG. 262.



Micrococcus ureæ.

[**Significance of Triple Phosphate.**—If urine be alkaline when it is passed, and the alkalinity be due to a *volatile alkali*, *i.e.*, to NH_3, then decomposition of the urine has taken place, and this kind of urine is a sure sign that there is disease of the genito-urinary mucous membrane.]

264. ALBUMIN IN URINE OR ALBUMINURIA.—**Serum albumin** is the most important **abnormal** constituent in urine which engages the attention of the physician. It occurs in blood (§ 32), and its characters are described in § 249.

Causes of Albuminuria.—1. Serum albumin may appear in urine without any apparent anatomical or structural change of the renal tissues. This condition has been called by v. Bamberger "*Hæmatogenous albuminuria.*" It occurs but rarely, however, and sometimes in healthy individuals when there is an excess of albumin in the blood plasma (*e.g.*, after suppression of the secretion of milk), and after too free use of albuminous food. 2. As a result of *increased blood pressure* in the renal vessels, *e.g.*, after copious drinking. It may be temporary, or it may be persistent, as in cases of congestion following *heart disease*, emphysema, chronic pleuritic effusions, infiltrations of the lungs, and after compression of the chest, causing congestion in the pulmonary circuit, which extends even into the renal veins, etc. 3. After section or paralysis of the *vasomotor nerves* of the kidneys, which causes great congestion of these organs. The albuminuria, which accompanies intense and long-continued abdominal pain, is brought about owing to a reflex paralysis of the renal vessels.

4. After violent muscular exercise. [Senator found that forced marches in young recruits were very frequently followed by the appearance of albumin in the urine, which persisted for several days.] *Convulsive* disorders, *e.g.*, epilepsy, the spasms of dyspnœa after strychnin poisoning, in shock of the brain, apoplexy, spinal paralysis, and violent emotions; the excessive use of morphia, which, perhaps, acts on the vasomotor centres. 5. It may accompany many acute febrile diseases, *e.g.*, the exanthemata (scarlet fever), typhus, pneumonia, and pyæmia. In these cases, it may be due to the increase of temperature paralyzing the vessels, but more probably the secretory apparatus of the kidney is so changed (*e.g.*, cloudy swelling of the renal epithelium) that the albumin can pass through the renal membrane. 6. Certain degenerations and inflammations of the kidneys at several of their stages. 7. Inflammation or suppuration in the ureter or urinary passages. 8. Certain chemical substances which irritate the renal parenchyma, *e.g.*, cantharides, carbolic acid. 9. The complete withdrawal of common salt from the food. The albumin disappears when the common salt is given again. 10. The *epithelium* may be in such a condition that it *cannot retain the albumin within the vessels*, due to imperfect nourishment and functional weakness of the excretory elements. This includes the albuminuria of ischæmia, and that after hemorrhage, in anæmia, scorbutus, icterus, diabetes. [Grainger Stewart finds that albuminnria is more common among presumably healthy people than was formerly supposed.]

[Besides being derived from the secreting parenchyma of the kidney, albumin may be present owing to admixture with the secretions from any part of the urinary tract, including the vagina and uterus in the female. In some cases the transudation of albumin is favored by changes in the capillary walls, the albumin being forced through by the intra-vascular pressure. Sometimes albuminuria occurs during the course of severe typhoid fever, and in acute fevers generally, where the temperature is persistently above 40° C. (104° F.). The high temperature alters the filtering membrane and permits the filtration of albumin.]

[**Physiological Albuminuria.**—This term has been applied to that condition of the urine, where traces of albumin are found in individuals *apparently* in perfect health. Johnson and Pavy cite such cases, while Posner asserts that all urine—even healthy urine—contains traces of proteids, whose presence is ascertained after concentrating the urine. It is safe to assume that normal urine should give no reaction with the usual tests for albumin. Posner precipitated the urine with alcohol, washed the precipitate, dissolved it in acetic acid, and tested it with the ferrocyanide test for albumin. He finds that minute traces of proteid are detected by the following modification of the biuret test: Make the urine alkaline, and by the "contact method" bring a layer of very dilute cupric sulphate over it; when the two fluids touch, a reddish-violet ring is obtained.]

The **tests for albumin in urine** depend upon the facts that it is **coagulated** by **heat** in neutral or acid solutions, and it is **precipitated** by various reagents.

[(1) **Heller's Test.**—Place 10 c.c. of the urine in a test-glass, and pour in pure colorless HNO_3 so as to run down the side of the glass, forming a layer beneath the urine. A white zone of coagulated albumin indicates the presence of albumin. In this test it is important to wait a certain time for the development of the reaction. In urines of high specific gravity, a haziness due to *acid urates* may be formed above where the two fluids meet, but its upper edge is not circumscribed. The acid decomposes the neutral urates and forms a more insoluble acid salt. This cloud of acid urates is readily dissolved by heat, while the albumin is not; the latter is always a sharply-defined zone between the two fluids. In very concentrated urine (rare), nitric acid may gradually precipitate *crystalline* urea nitrate. In patients taking copaiba, nitric acid, by acting on the resin, causes a slight milkiness.]

[(2) **Boiling and Nitric Acid.**—Place 10 c.c. of urine in a test-tube and boil. If albumin be present in small quantity, a faint haziness, which may be detected in a proper light, will be produced. Add 10 to 12 drops of HNO_3. If the turbidity disappears it is due to phosphates, while if it remain it is due to albumin. If albumin be present in large quantity, a copious whitish coagulum is obtained. **Precautions.**—(*a*) In all cases, if the urine be turbid, filter it before applying any test. (*b*) *How to boil.*—Boil the upper strata of the liquid, and take care, if any coagulum be formed, that it does not adhere to the side of the tube, else the tube is liable to break. (*c*) In performing this test with a *neutral* solution, note when the precipitate falls, for albumin is precipitated about 40° C., phosphates not till about the boiling point. (*d*) *Amount of Acid.*—If too little (2 or 3 drops) HNO_3 be added, or too much (30 or 40 drops), we may fail to detect albumin, although it is present.

(3) **Ferrocyanide Test.**—By the addition of *acetic acid* and *potassium ferrocyanide*. [If albumin be present, a white flocculent precipitate separates in the cold. Dr. Pavy has introduced **pellets**, consisting of a mixture of citric acid and sodic ferrocyanide. All that is required is to add a pellet to the suspected urine. **Oliver's papers.**—Dr. Oliver uses papers, one saturated with citric acid and another with ferrocyanide of potassium. The two papers are added to the clear filtered urine. Other precipitants of albumin, such as small pieces of paper impregnated with potassio-mercuric iodide, are used by Oliver.]

(4) **Boiling Acid Urine.**—If the urine be alkaline, although albumin may be present, it is not precipitated by heat alone. We require to add acetic acid until a slightly acid reaction is obtained. Boiling may give a precipitate of earthy phosphates in an **alkaline** urine, owing perhaps to the

being driven off. This precipitate might be mistaken for albumin, but on adding acetic or nitric acid, the earthy precipitate is dissolved, while the precipitate of albumin is not dissolved. In testing for albumin, always use *clear* urine. If it is turbid, filter it.

[(5) **Metaphosphoric acid** is dissolved in water just before it is to be used and added to clear urine (*Hindenlang*). Graham pointed out that metaphosphoric acid precipitated albumin. A 20 per cent. solution of the ordinary glacial phosphoric acid is a good test for albumin, but it also precipitates peptones. It, however, changes into ordinary phosphoric acid by keeping, and then it no longer precipitates albumin.]

[(6) **Sodic Sulphate and Acetic Acid.**—Acidulate 10 c.c. of urine with acetic acid, and add ⅙ of its volume of a concentrated solution of sulphate of soda or magnesia. On heating, if albumin be present, a distinct cloudiness is obtained.]

[(7) In **picric acid**, according to Dr. Johnson, we have a more delicate test for minute traces of albumin than either heat or nitric acid, or than both these tests combined. It is used either in the form of crystals or powder, or as a saturated aqueous solution. Take a four-inch column of urine in a test-tube, hold the tube in a slanting direction, and pour an inch of the picric acid solution on the surface of the urine, where in consequence of its low specific gravity (1005) it mixes only with the upper layer of the urine. It coagulates any albumin present. The precipitate occurs at once, and is increased by heat, while the urate of soda, which is sometimes precipitated, is soluble on heating.]

[Dr. Roberts regards any test for albumin which requires strong acidulation with an *organic* acid, citric, acetic, or lactic, as unsatisfactory, since it precipitates mucin. For this reason he rejects the tungstate, mercuric iodide, and potassic ferrocyanide tests. Dr. Roberts regards the heat test, with the addition of a small definite quantity of acetic acid, as the best test for the detection of small quantities of albumin.]

1. **Quantitative Estimation of Albumin.**—100 c.c. of urine are boiled in a capsule, some acetic acid being ultimately added, whereby the albumin is precipitated in flakes. The precipitate is collected on a weighed, dried (110°), ash-free filter, and repeatedly washed with hot water, then with alcohol, and dried in an air bath at 110°. The weight of the filter is deducted, and finally the dried filter with the albumin is burned in a weighed platinum capsule, and the weight of the ash also deducted. [This method is not available for the busy practitioner on account of the time it takes. Practically, it is sufficient to compare from day to day the proportion that the precipitated albumin bears to the bulk of the urine tested. A graduated tube may be used, so that after the prepipitate has subsided, the physician may see what proportion of the whole the precipitate occupies.]

FIG. 263.

Esbach's Albumimeter.

Esbach's Albumimeter (Fig. 263).—A glass cylinder is filled with the urine up to the mark U, and to R with the precipitant (20 citric acid, 10 picric acid, 970 water). The vessel is corked and then shaken. After twenty-four hours the coagulated albumin subsides, when the graduation on the tube indicates the number of grms. of albumin per 1000 c.c. of urine. Very albuminous urine must be previously diluted.

2. **Globulin** occurs only in albuminous urine, and is frequently present. Its **presence** is ascertained by adding powdered magnesium sulphate in excess to the urine; when it is present it is precipitated (§ 32). The more globulin there is in the presence of albumin, the more difficult it is to precipitate it. [Sometimes, when an albuminous urine is dropped into a large cylinder of water, each drop as it sinks is followed by a milky train, and when a sufficient number of drops has been added, the water becomes opalescent, the opalescence disappearing on adding an acid. The globulin is kept in solution by common salt and other neutral salts, but when these are largely diluted, the globulin is precipitated (*Roberts*).]

3. **Peptone** occurs in some specimens of albuminous urine, but also in non-albuminous urine. Maixner found it constantly in the urine in all cases where suppuration is present, and even in phthisis, constituting **pyogenic peptonuria.** Peptone occurs in pus, and the **peptonuria** in these cases is a sign of the breaking up of the pus cells (*Hofmeister*). Also when many leucocytes are broken up in the blood (**hæmatogenic**). It occurs in cases where there is great disintegration of albuminous tissues, *e.g.*, in cancer. It is frequently found after childbirth. Ammonium sulphate precipitates all proteids except peptones (p. 294).

Test.—Separate the albumin by boiling and the addition of acetic acid. Treat the filtrate with three volumes of alcohol; this precipitates the peptone, which, when dissolved in water, gives the characteristic reactions for peptone (§ 166, I).

4. **Propeptone**, or **Hemialbumose**, occurs very rarely *e.g.*, in osteomalacia and intestinal tuberculosis (*Bence Jones*). The urine is treated to saturation with NaCl and a large quantity of acetic acid added, and filtered while hot, to separate the albumin and globulin. In the cold filtrate propeptone forms a turbidity, which is redissolved by heat. The precipitate thrown down by HCl and HNO_3 is soluble by heat (*Kühne*). The precipitate is isolated by filtration, and dissolved in a little warm water, when it gives with HNO_3 a yellow reaction; like peptone the solution gives the biuret reaction (p. 293).

5. **Egg albumin** appears in the urine when much egg albumin is taken in the food, and also

when it is injected into the blood vessels (§ 192, 4). According to Semmola, the albumin present in the urine in Bright's disease has undergone a molecular change (similar to egg albumin), and hence it is excreted.

6. **Mucus** is present in large amount, especially in catarrh of the bladder. It contains numerous mucus corpuscles, which are scarcely distinguishable from pus corpuscles. They contain albumin, so that urine containing much mucus is albuminous; mucin is not precipitated by heat, but acetic acid gives a flocculent precipitate in clear urine. [Minute traces of mucin occur normally in urine. If clear, normal urine be set aside for a short time, a flocculent haziness, like a cloud of cotton wool, is seen floating in the urine. This is mucus entangling a few epithelial cells from the genito-urinary tract. **Mucin Reaction.**—According to W. Roberts, the addition of a concentrated solution of citric acid to urine, as in Heller's test (§ 264, *a*), where the two fluids meet, causes an opalescent zone gradually to be formed above the layer of acid.]

265. **BLOOD IN URINE (HÆMATURIA)—HÆMOGLOBINURIA.—I. Source of the Blood.**—(1) In **hæmaturia**, the blood may come from any part of the urinary apparatus, 1. In hemorrhage from the **kidney**, the amount of blood is usually small and well mixed with the urine. The presence of "blood cylinders," long microscopic blood coagula, casts of the uriniferous tubules, washed out of them by the urine, is characteristic when they are found in the urine (Fig. 275). The urine usually has a **smoky** appearance. [The urine slowly dissolves out the coloring matter, the stroma of the corpuscles after a time being deposited as a brownish sediment. The smoky hue occurs

FIG. 264.

Crenated red blood corpuscles in urine, × 350.

FIG. 265.



Peculiar changes of the red blood corpuscles in renal hæmaturia.

FIG. 266.



Colored and (*a*) colorless blood corpuscles of various forms.

only in acid urine; if the urine becomes alkaline, the hue becomes brighter red.] The blood corpuscles show peculiar changes of form [they become crenated] (Fig. 264), and exhibit evidence of division, due to the action of urea on them (§ 5). Large coagula are never found in urine mixed with blood derived from the kidney. 2. In hemorrhage from the **ureter**, we occasionally find worm-like masses of clotted blood, casts of the canal of the ureter. 3. The relatively largest coagula occur in hemorrhage from the **bladder**. In all cases where blood is present, we must examine microscopically for the blood corpuscles, and it may be for coagula of fibrin. In acid urine, blood corpuscles, but never arranged in rouleaux, may be found after two to three days. The blood corpuscles settle as a red sediment at the bottom. If the hemorrhage is copious many retain their original shape, but if the urine is very concentrated, they may become crenated.

FIG. 267.

Shriveled blood corpuscles in urine (catarrh of the bladder), with numerous lymph corpuscles, and crystals of triple phosphate, × 350.

When there is a small and slow hemorrhage from ruptured small capillaries, the red blood corpuscles are of unequal size, many ½ to ⅓ the size of normal, while the pigment has become brownish-yellow (Fig. 265).

If a hemorrhage of this kind be accompanied by **catarrhal inflammation of the bladder**, there is found between the red, numerous shriveled leucocytes (Fig. 265), which in freshly passed urine often exhibit lively amœboid movements. If the urine be alkaline, as it usually is, crystals of triple phosphate also occur.

If the remains of the red blood corpuscles become very pale, their presence may be frequently ascertained by adding iodine in a solution of KI (Fig. 265). Blood is constantly present in the urine during menstruation.

II. Hæmoglobinuria is quite distinct from hæmaturia. It depends upon the excretion of **hæmoglobin as such** through the kidneys, and it is produced when hæmoglobin occurs free

within the blood vessels, as in cases where the colored blood corpuscles have been dissolved inside the blood vessels (hæmocytolysis). It occurs when foreign blood is transfused, *e. g.*, when lamb's blood is transfused into man. The foreign blood corpuscles are dissolved in the blood of the recipient, and the hæmoglobin appears in the urine (§ 102). In addition, microscopic "**cylinders**," or "**casts**," consisting of a globulin-like body tinged yellow with hæmoglobin, may likewise be found in the urine. It also occurs in cases of severe burns (§ 10, 3); after decomposition of the blood in pyæmia, scorbutus, purpura, severe typhus, after respiring arseniuretted hydrogen, and after the passage of azobenzol, naphthol, pyrogallic acid, potassic chlorate, chloral, phosphorus, or carbolic acid into the circulation. [The injection of laky blood, water, ether, glycerin (*Adams*), or toluylendiamin (*Afanassiew*), also causes it, and in such cases Afanassiew asserts that the Hb passes out through the glomeruli, while brown degeneration products of the red blood corpuscles, which are dissolved by these agents, were found in the convoluted tubules.] These substances dissolve the red blood corpuscles. Sometimes it occurs **periodically** from causes and conditions as yet but little understood, *e. g.*, the application of cold to the skin.

Tests for Blood in Urine.—1. The **color** of bloody urine shows every tint, from a faint red to a dark blackish-brown, according to the amount of blood present. The urine is often turbid.

2. Urine containing blood or blood pigment contains **albumin.**

FIG. 268.



Spectroscope for investigating the presence of hæmoglobin in urine.

3. **Heller's Blood Test.**—Add to urine half its volume of solution of caustic potash, and heat gently. The earthy phosphates are precipitated, and they carry the hæmatin with them, falling as garnet-red flocculi. [This is not a reliable test.]

4. **Hæmin Test.**—The colored earthy phosphates may be collected on a filter, and from them hæmin may be prepared as directed in § 19.

5. **Almén's Test.**—Add to urine, freshly prepared tincture of guaiacum and ozonized ether; a blue color indicates the presence of blood (§ 37).

6. **Spectroscope** (see § 14). Fig. 268 shows the arrangement of the apparatus. The urine is placed in a glass vessel, D, with parallel sides, 1 centimetre apart (**hæmatinometer**). Light from a lamp, E, passes through the fluid. The lamp, F, illuminates the scale which is seen by the observer through the telescope, A. (*a*) **Fresh urine containing blood** gives the spectrum of **oxyhæmoglobin** (Fig. 17). (*b*) When bloody urine is exposed for some time, especially in a warm place, it becomes more *acid*, and assumes a dark, brownish black color. The hæmoglobin becomes changed into **methæmoglobin** (§ 15). It is precipitated by lead acetate, which does not precipitate oxyhæmoglobin; the spectrum of methæmoglobin resembles that of hæmatin in an acid solution (§ 15, Fig. 17). The spectra may be combined. (*c*) The **microscopic** investigation must never be omitted. The shape of the corpuscles may vary considerably (Figs. 264 to 266).

266. **BILE IN URINE (CHOLURIA).**—The physiological conditions which cause the bile constituents to appear in the urine are mentioned in part at § 180.

Hæmatogenic, or Anhepatogenic Icterus (*Quincke*), occurs when bilirubin (§ 20) is formed from extravasated blood by the action of the connective-tissue corpuscles, so that bile pigments, in addition to coloring the tissues, pass into the urine.

I. Bile Pigments.—Their presence is ascertained by **Gmelin-Heintz's test.** *Green* (Biliverdin) is the characteristic hue in the play of colors obtained with this test, which is fully described in § 177.

Modifications of the Test.—1. If icteric urine be filtered through filtering or blotting paper, a drop of nitric acid containing nitrous acid, when applied to the inner surface of the spread-out filter, gives a yellowish-colored ring (*Rosenbach*). 2. In order that the reaction may not take place too rapidly, add a concentrated solution of sodic nitrate, and then slowly pour in sulphuric acid (*Fleischl*). 3. On shaking 50 c.c. of icteric urine with 10 c.c. of chloroform, the bilirubin is dissolved by the latter. On adding bromide water, a beautiful ring of colors is obtained (*Maly*). If the chloroform extract be treated with ozonized turpentine and dilute caustic potash, a green color, due to biliverdin, occurs in the watery fluid (*Gerhardt*).

In slight degrees of jaundice, **urobilin** alone may be found (§ 261, 1) (*Quincke*).

In persistent high fever, the urine contains especially **biliprasin** (*Huppert*). If it contains **cholетelin** alone, add to the urine some hydrochloric acid, and examine it with the spectroscope, which gives a pale absorption band between *b* and F (§ 177, 3, *f*).

Hæmatoidin.—Sometimes crystals of *hæmatoidin* (§ 20, Fig. 14) appear in the urine, especially when blood corpuscles are dissolved within the blood stream; occasionally in scarlet fever and typhus, and sometimes in cases of periodic hæmoglobinuria. The breaking up of old blood clots in the urinary passages, as in pyonephrosis (*Ebstein*), or the dissolution of necrotic areas (*Hofmann and Ultzmann*) produces them, and similar crystals occur in analogous cases in the sputum (§ 138). In jaundice due to congestion (§ 180), the identical crystalline substance, bilirubin, is found.

II. Bile acids occur in largest amount in absorption jaundice, but they are never present to any extent. The **test** is described at § 177, 2, the cane-sugar solution consisting of 0.5 grm. to 1 litre of water. If the urine be dilute, it is advisable to concentrate it on a water bath. [It is rare to get a satisfactory result with Pettenkofer's test in ordinary icteric urine.] v. Pettenkofer's test may be used with the alcoholic extract of the nearly dry residue, but no albumin must be present. Dragendorff found 0.8 grm. in 100 litres of *normal* urine.

Strassburg's Modification.—Dip filter paper into the urine, to which a little cane sugar has been added; dry the paper and apply to it a drop of sulphuric acid. A violet-red color is obtained after a short time. [**Hay's Reaction** (§ 177).]

267. **SUGAR IN URINE (GLYCOSURIA).**—**Diabetes Mellitus.**—The excessively minute trace of **grape sugar** or **dextrose,** which is constantly present in normal urine, sometimes becomes greatly increased and constitutes the conditions of **diabetes mellitus** and **glycosuria.** The physiological conditions which determine this result are given at § 175. In this condition, the **quantity** of urine is greatly increased, it may reach 10 or more litres. Many pints may be passed daily. [The usual abnormal amount of sugar is from 1 to 8 per cent., although 15 per cent. has been found, *i. e.*, found from 5 to 50 grs. per fluid oz., or 300 to 4000 grs. in twenty-four hours.] The **specific gravity** is also increased (1030 to 1040). [In a case where a large amount of urine is passed of a *pale* color and a specific gravity above 1030, always suspect sugar.] A diabetic person gives off relatively more water by the kidneys and less by the skin (and lungs ?) than a healthy person. The **color** is very pale yellow, although the amount of pigment is by no means diminished—it is only diluted [the depth of the color being inversely as the quantity passed]. The amount of the nitrogenous urinary excreta is increased. The sugar is increased by a diet of carbohydrates and diminished by an albuminous diet. The uric acid and oxalate of lime are often increased at the commencement of the disease, while yeast cells are constantly present after the urine has been exposed to the air for some time.

Sugar has been found *occasionally* after poisoning with or after the use of morphia, CO, chloral, chloroform, curara; after the injection of ether and amyl nitrite into the blood; and in gout, intermittent fever, cholera, cerebro-spinal meningitis, hepatic cirrhosis, and cardiac and pulmonary affections.

[There is no doubt that normal healthy human urine contains a reducing agent, which reduces cupric oxide to the same extent as if the urine on an average contained 6 grains of glucose in every 10 fluid ounces of urine, or 1.34 grms. per litre. As this substance does not cause alcoholic fermentation in its solutions, its identity with glucose appears to be doubtful. The most active reducing agent is probably kreatinin (*G. S. Johnson*).]

Tests.—Any of the tests described at § 149 may be used, but the urine must be free from albumin. The quantitative estimation by fermentation and the titration methods are described in § 149. [The tests for grape sugar described in § 149 are (1) Trommer's; (2) Fehling's; (3) Moore & Heller's; (4) Böttger's; (5) Mulder & Neubauer's; (6) Fermentation test.]

Worm-Müller recommends the following modification of Fehling's test: Use a 2.5 per cent. solution of cupric sulphate solution, and another of 10 parts of sodio-potassic tartrate in 100 parts of 4 per cent. solution of soda. Boil 5 c.cm. of urine in a test-tube, while in a second test-tube is

boiled 1 to 3 c.cm. of the copper solution and 2.5 c.cm. of the potassio-tartrate solution. The boiling of both fluids is stopped simultaneously, and after 20 to 25 seconds the contents of one test-tube are added to those of the other, but without shaking the mixture, the reduction taking place spontaneously.

8. **Nylander's** modification of Böttger's test is also good (§ 149).

[9. **Picric Acid and Potash Test.**—Braun showed that grape sugar, when boiled with picric acid and potash, reduces the yellow picric acid to the deep red picramic acid, the depth of the color depending on the amount of sugar present. Dr. Johnson uses this test for detecting the presence of sugar in urine, and also for estimating the amount of sugar present, the depth of the red color obtained in boiling being compared with a standard dilution of ferric acetate. In doing the test, use 1 drachm of urine, ½ a drachm of liquor potassæ, and 10 minims of picric acid solution; make up to 2 drachms with distilled water, and boil the mixture for one minute. This test indicates the presence of 0.6 grain of sugar per fluid ounce of normal urine. Dr. Johnson claims for this test that it possesses all the advantages of the other tests, while it is not affected by uric acid or any other normal ingredient of urine; neither does the presence of albumin interfere with the action of the test as it does with all the forms of copper testing.]

[10. **Indigo-carmine Test.**—A blue solution of this substance, when boiled with diabetic urine containing sodic carbonate, changes from a blue to a violet, purple, red, yellow, and finally, straw-yellow color. After cooling and exposure to the air, the various colors are obtained in the reverse order until the mixture becomes blue again. Dr. Oliver uses this test in the form of **test papers.** One bibulous paper is impregnated with the indigo carmine and the other with sodic carbonate. Drop one of the test papers and a sodic-carbonate paper into a test-tube containing 1½ inches of water, heat gently, when a blue solution is obtained. Add the urine slowly, one drop at a time, and boil the mixture, observing any change of color by holding the tube against a white surface below the level of the eye, Uric acid and urates, which reduce Fehling's solution, do not affect the carmine test, nor does kreatinin, although it reacts with the picric acid test.]

[**Quantitative Estimation.**—(*a*) **Fermentation Test** (§ 150). Take 4 oz. (120 c.c.) of the urine; add a lump of German yeast, about the size of a walnut, lightly cork the bottle, and place it aside for twenty-four hours in a moderately warm place, *e. g.*, on the mantelpiece. Take the specific gravity before and after the fermentation. Thus, if the specific gravity be 1038 before and 1013 afterward, the difference or "density lost" is 25, which gives 25 grs. of sugar per fluid oz. (*Roberts*). If it be desired to get the percentage, multiply the density lost by 0.23, thus $25 \times 0.23 = 5.69$ in 100 parts.]

[(*b*) **Volumetric Analysis.**—10 c.c. of Fehling's solution = .05 of sugar.

1. Ascertain the quantity of urine passed in twenty-four hours. 2. Filter the urine, and remove any albumin present by boiling and filtration. 3. Dilute 10 c.c. of Fehling's solution with about twenty times its volume of distilled water, and place it in a white porcelain capsule on a wire gauze support under a burette. (It is diluted because any change of color is more easily observed.) 4. Take 5 c.c. of the urine, and 95 c.c. of distilled water, and place the diluted urine in a burette. 5. Gradually boil the diluted Fehling's solution, and while it is boiling gradually add the diluted urine from the burette, until all the cuprous oxide is precipitated as a reddish powder, and the supernatant fluid has a straw-yellow color, not a trace of blue remaining. Read off the number of c.c. of *dilute* urine employed. Say 36 c.c. were used—that, of course, represents 1.8 c.c of the original urine. Suppose the patient passes 1550 c.c., as 1.8 c.c. of urine reduced all the cupric oxide in the 10 c.c. of Fehling's solution, it must contain .05 gramme sugar, hence,

$$1.8 : 1550 :: .05 : \frac{1550 \times .05}{1.8} = 237.5 \text{ grammes of sugar passed in 24 hours.}]$$

[**Preparation of Fehling's Solution.**—34.64 grammes of pure crystalline cupric sulphate are powdered and dissolved in 200 c.c. of distilled water; in another vessel dissolve 173 grammes of Rochelle salts in 480 c.c. of pure caustic soda, specific gravity 1.14. Mix the two solutions, and dilute the deep colored fluid which results to 1 litre. *N.B.*—Fehling's ought not to be kept too long; it is apt to decompose, and should therefore be preserved from the light, or protected with opaque paper pasted on the bottle. Some other substances in urine, *e.g.*, urates and uric acid, reduce cupric oxide.]

(*c*) According to Worm-Müller, the polarization method is almost valueless for diabetic urine.

[**Picro-Saccharimeter.**—G. Johnson uses a stoppered bottle 12 inches long and ¾ inch wide, graduated in $\frac{1}{10}$ and $\frac{1}{100}$ (Fig. 269). To it is fixed a shorter bottle containing the standard iron solution for comparison, a standard solution, composed of liquor ferri perchloride ℥ j, liq. ammon. acetatis ℥ iv, glacial acetic acid ℥ iv, liq. ammoniæ ℥ j, and water to make up ℥ iv. All B. P. preparations give a color identical with a solution containing 1 gr. of grape sugar per oz., reduced by picric acid and afterward diluted four times, so that this tint = ¼ gr. of sugar per oz. After reducing the sugar with the picric acid, pour into the tall tube the dark saccharine liquid produced by boiling to occupy ten divisions of the tube, and add distilled water cautiously until the color approaches that of the standard; read off the level of the fluid. The amount of sugar present is determined from the amount of water added. In making the test, the picric acid must be added in proportion to the amount of sugar present.]

If large quantities of dextrose are taken in the food, a part of it (and more in diabetic persons) appears in the urine. Lævulose, when taken internally, does not increase the amount of sugar in diabetes. The free use of starch does not cause glycosuria in health, but in diabetes it increases the amount of

FIG. 269.

Picro-saccharimeter of G. Johnson.

FIG. 270.

Inosit crystallized partly from alcohol and partly from water (after *Funke*).

sugar. A large consumption of cane or milk sugar causes the passage of small quantities of both of these sugars into the urine in health, while in diabetes the amount of dextrose is increased (*Worm-Müller*). According to Külz, in diabetic persons cane sugar splits up into grape and fruit sugar, the latter being used up in the body, the former partly excreted; and the same is the case with milk sugar.

In severe cases of diabetes mellitus, Külz found the left-rotatory β-oxybutyric acid (the next highest analogue of lactic acid) in the urine, from which acetic acid is formed by oxidation (§ 175), which in its turn readily yields CO_2 and aceton. α-Crotonic acid is formed in urine by the removal of water from oxybutyric acid in the urine in diabetes (*Stadelmann*). The administration of aceton causes albuminuria, and this may in part explain in some cases the complication of albuminuria in diabetes (*Albertoni and Pisenti*).

Aceton, or aceton-yielding substance, probably aceto-acetic acid, is sometimes found in diabetic urine. It has a peculiar vinous odor, and it has been detected in the urine during fever. Gerhardt described a peculiar substance in diabetic urine, which gave a deep red color with perchloride of iron. This substance is probably diacetic ether, and he considered it to be the source of aceton; but it is more probably derived from aceto-acetic acid. **Test for Aceton.** (1) Perchloride of iron = Burgundy red color; but this is not reliable. (2) Lieben suggested an iodoform test. Dissolve 20 grains of KI in a fluid drachm of liq. potassæ and boil the fluid. Pour the suspected urine on the surface, when a ring of phosphates is deposited from the urine by the hot alkaline solution. If aceton be present, after a time the deposit becomes yellow, and yellow granules of iodoform appear and sink to the bottom of the test-tube. The only other substance which may be met with in the urine giving this reaction is lactic acid.

Milk sugar is sometimes found in the urine of women who are nursing, when the secretion of milk is arrested, absorption taking place from the breasts (*Kirsten, Spiegelberg*). **Lævulose** is sometimes found in diabetic urine (§ 252).

Dextrin has also been found in diabetic urine. **Inosit, or muscle sugar** (§ 252), is sometimes found in diabetes, in polyuria, and albuminuria. It is found in traces, even in normal urine. Occasionally, after the piqûre in animals (§ 175), inosit, instead of grape sugar, appears in the urine (Fig. 270). In testing for inosit, remove the grape sugar by fermentation, and the albumin by heat after the addition of a few drops of acetic acid and sodic sulphate. Some of the filtrate is evaporated nearly to dryness on a capsule. To the residue add two drops of mercuric nitrate (Liebig's titration fluid for urea), which gives a yellow precipitate. When this colored residue is spread out and carefully heated, a *dark red* color, which disappears on cooling, is obtained (*Gallois, Külz*). [Inosit gives a green when boiled with Fehling's solution.]

268. **CYSTIN.**—This left-rotatory body, $C_6H_{12}N_2S_2O_4$, occurs very seldom in large amount in urine, although it seems to be a constituent of normal urine. It may be in solution or in the form of hexagonal crystals (Fig. 271, A). It is insoluble in water, alcohol, and ether, but easily soluble

in ammonia, from which solution it may be crystallized. According to Baumann and Preusse there are intermediate products of the metabolism, from which are furnished the materials necessary for the formation of cystin. During normal metabolism these materials undergo further changes, and the sulphur appears oxidized in the urine as sulphuric acid. In rare cases these oxidations do not take place, and then the sulphur appears in the cystin of the urine (*Stadthagen*).

269. **LEUCIN** $= C_6H_{13}NO_2$. **TYROSIN** $= C_9H_{11}NO_3$.—Both bodies occur in the urine in **acute yellow atrophy of the liver,** and in poisoning by phosphorus. (Their formation during pancreatic digestion has been referred to in § 170, II.) As the urea excreted is usually diminished at the same time, it is assumed that, in these diseases, the further oxidation of the derivatives of the

FIG. 271.

A, crystals of cystin; B, oxalate of lime; *c*, hour-glass forms of B.

FIG. 272.

a, *a*, leucin balls; *b*, *b*, tyrosin sheaves; *c*, double balls of ammonium urate.

proteids is interfered with. **Leucin,** which is either precipitated spontaneously or obtained after evaporating an alcoholic extract of the concentrated urine, occurs in the form of yellowish-**brown balls** (Fig. 272, *a*, *a*), often with concentric markings, or with fine spines on their surface. When heated, it sublimes without fusing.

Tyrosin forms silky, **colorless sheaves of needles** (Fig. 272, *b*, *b*). When boiled with mercuric nitrate and nitric acid it gives a red color, and afterward a brownish-red precipitate. **Piria's Test.**—When slightly heated with a few drops of concentrated sulphuric acid, it dissolves with a temporary deep red color. On diluting with water, adding barium carbonate until it is neutralized, boiling, filtering, and adding dilute ferric chloride, a violet color is obtained (*Piria*, *Städeler*).

270. **DEPOSITS IN URINE.**—Deposits may occur in normal and in pathological urine, and they may be either "**organized**" or "**unorganized.**"

I. Organized Deposits.

A. Blood: red and white blood corpuscles and sometimes fibrin (Figs. 264–266).

B. Pus, in greater or less amount in catarrh or inflammation of the urinary passages. Pus cells exactly resemble colorless blood corpuscles (Figs. 9, 267). **Donné's Test.**—Pour off the supernatant fluid and add a piece of caustic potash to the deposit; if it be pus it becomes gelatinous, ropy, and more viscid (alkali-albuminate). **Mucus,** when so acted on, becomes more fluid and mixed with flocculi.

C. Epithelium of various forms occurs, but it is not always possible to say whence it is derived.

D. Spermatozoa may be present.

E. Lower organisms occur in the urinary passages very seldom, but they may be present, *e.g.*, in the bladder, when germs are introduced from without by means of a dirty catheter. [Before introducing a catheter into the bladder one ought always to make sure that the instrument is perfectly aseptic.] Micrococci are found in the urine in certain diseases, *e.g.*, diphtheria. The following forms are distinguished:—

1. **Schizomycetes** (§ 184). *Normal* human urine contains neither schizomycetes nor their spores. In pathological conditions, however, fungi may pass from the blood into the urinary tubules and thus reach the urine (*Leube*). During the alkaline fermentation of urine, **micrococci**, rod-shaped **bacteria** or **bacilli** (Fig. 273) appear. **Sarcinæ** belong to the group (§ 186).

FIG. 273.

Fungi in urine. *e*, mould; *f*, yeast; *d*, *g*, micrococci and bacilli; *a*, *b*, *c*, uric acid.

2. **Saccharomycetes** (fermentation fungi): (*a*) The fungus of the acid urine fermentation (S. urinæ) consists of small bladder-like cells arranged either in chains or in groups (Figs. 260, *a*; 273, *f*). (*b*) Yeast (S. fermentum) occurs in diabetic urine, as oval cells with dotted eccentrically-placed nucleus (Fig. 237).

3. **Phytomycetes** (moulds) occur in putrid urine (Fig. 273, *e*). They are without clinical significance.

F. Tube Casts.—The occurrence of tube casts, *i. e.*, casts of the uriniferous tubules (*Henle*, 1837), is of great importance in the diagnosis of renal diseases. If these structures are relatively thick and straight, they probably come from the collecting tubules, but if they are smaller and twisted, they probably come from the convoluted tubules. There are various forms of tube casts: 1. **Epithelial casts**, consisting of the actual cells of the

FIG. 274.

Epithelial casts.

FIG. 275.

Blood cast.

FIG. 276.

Leucocyte cast.

FIG. 277.

Acid sodic urate in cylinders.

FIG. 278.

Finely granular cast.

uriniferous tubules. They indicate that there is no very great change going on, but only that, as in catarrhal inflammation of any mucous membrane, the epithelium is in process of desquamation. 2. **Hyaline casts** (Fig. 280) are quite clear and homogeneous, usually long and small; sometimes they are "finely granular," from the presence of fat or other particles. They are best seen after the addition of a solution of iodine. They are probably formed from albumin, which passes into the uriniferous tubules. They are dissolved in alkaline urine, while acid urine favors their formation. They usually occur in the late stages of renal disease, after the tubular epithelium has been shed. 3. **Coarsely granular casts** (Fig. 279) are brownish-yellow, opaque, and granular, usually broader than 2. There are various forms. Not unfrequently there are **fatty** granules, and, it may be, epithelial cells in them. 4. **Amyloid casts** occur in amyloid degeneration of the kidneys (Fig. 280). They are refractive and completely homogeneous, and give a blue color (amyloid reaction) with sulphuric acid and iodine. 5. **Blood casts** occur in capillary hemorrhage of the kidney, and consist of coagulated blood entangling blood corpuscles (Fig. 275). When tube casts are present, the urine is always *albuminous*.

Leucocyte casts occur in suppurating conditions of the urinary tubules (Fig. 280). The urates in the form of casts (Fig. 277) are without significance.

II. Unorganized Deposits.

Some of these are **crystalline** and others are **amorphous**, and they have been referred to in treating of the urinary constituents.

271. SCHEME FOR DETECTING URINARY DEPOSITS.—I. In **acid urine** there may occur—

1. An **amorphous granular deposit**:—
   (*a*) Which is dissolved by heat and reappears in the cold; the deposit is often reddish in color = **urates** (Fig. 260).
   (*b*) Which is not dissolved by heat, but is dissolved by acetic acid, but without effervescence = probably **tribasic calcic phosphate.**
   (*c*) Small bright refractive granules, soluble in ether = **fat or oil granules** (§ 41), (Lipæmia). Fat occurs in the urine, especially when the round worm, Filaria sanguinis hominis, is present in the blood; sometimes, along with sugar, in phthisis, poisoning with phosphorus, yellow fever, pyæmia, after long-continued suppuration, and lastly, after the injection of fat or milk into the blood (§ 102). It occurs also in fatty degeneration of the urinary apparatus, admixture with pus from old abscesses, and after severe injuries to bones. In these cases attention ought to be directed to the presence of cholesterin and lecithin. Very rarely is the fat present in such amount in the urine as to form a cream on the surface (**chyluria**).

FIG. 279.

Coarsely granular casts.

FIG. 281.

a, Granules of calcic carbonate of lime; *b*, *c*, crystalline neutral calcic phosphate.

FIG. 280.

Hyaline casts, *a*; *b*, with leucocytes; *c*, with renal epithelium.

FIG. 282.

Ammonio-magnesic phosphate.

FIG. 283.

Imperfect forms of the same.

2. A **crystalline** deposit may be—
   (*a*) **Uric acid** (Fig. 256).
   (*b*) **Calcium oxalate** (Fig. 258)—octahedra insoluble in acetic acid.
   (*c*) **Cystin** (Fig. 271).
   (*d*) **Leucin** and **tyrosin**—very rare (Fig. 272).

II. In **alkaline urine** there may occur—

1. *A completely* **amorphous granular deposit**, soluble in acids without effervescence = **tribasic calcic phosphate.**

2. *Sediment*, **crystalline**, *or with a characteristic form.*

(*a*) **Triple phosphate** (Figs 282, 283), soluble at once in acids.

(*b*) **Acid ammonium urate**—dark-yellowish, small balls often beset with spines, also amor- phous (Fig. 284).

(*c*) **Calcium carbonate**—small whitish balls or biscuit-shaped bodies. Acids dissolve them with effervescence (Fig. 281).

(*d*) **Leucin** and **tyrosin** (Fig. 272)—very rare.

(*e*) **Neutral calcic phosphate** and long plates of tribasic magnesic phosphate (Fig. 285).

Organized deposits may occur both in alkaline and in acid urine; pus cells are more abunda- ant in alkaline urine, and so are the lower vegetable organisms.

272. URINARY CALCULI.—Urinary concretions may occur in granules the size of sa- nd, or in masses as large as the fist. According to their size they are spoken of as **sand, grav-** el, **stone**, or **calculi**. They occur in the pelvis of the kidney, urete- rs, bladder, and sinus prostaticus.

We may classify them as follows (*Ultzmann*):—

1. Calculi whose nucleus consists of the sedimentary deposits t- hat occur in **acid urine** (primary formation of calculi). They are all

FIG. 284.

Acid ammonium urate.

FIG. 285.

Basic magnesic phosphate.

formed in the kidney, and pass into the bladder, where they enlarge by the deposition of m- alter on their surface.

2. Calculi which are either sedimentary forms from **alkaline urine**, or whose nucleus consi- ts of a *foreign body* (secondary formation of calculi). They are formed in the bladder.

The **primary** formation of calculi begins with free uric acid in the form of sheaves (Fig. 256) which form a nucleus, with concentric layers of oxalate of lime. The **secondary** formation oc- curs in *neutral* urine by the deposition of calcic carbonate and crystalline calcic phosphate; in *alk- aline* urine, by the deposition of acid ammonium urate, triple phosphate, and amorphous calcic phosp- hate.

Chemical Investigation.—Scrape the calculus, burn the scrapings on platinum foil to asce- rtain if they are burned or not.

I. Combustible concretions can consist only of organic substances.

(*a*) Apply the murexide test (§ 259, 2), and, if it succeeds, **uric acid** is present. Uric acid calculi are very common, often of considerable size, smooth, fairly hard, and yellow to red- dish-brown in color.

(*b*) If another portion, on being boiled with caustic potash, gives the odor of ammonia (or w- when the vapor makes damp turmeric paper brown, or if a glass rod dipped in HCl and held over it g- gives white fumes of ammonium chloride), the concretion contains **ammonium urate**. If *b* gives- s no result, pure uric acid is present. Calculi of ammonium urate are rare, usually small, of an ea- rthy consistence, *i. e.*, soft and pale yellow or whitish in color.

(*c*) If the **xanthin** reaction succeeds (§ 260), this substance is present (rare). **Indigo** has b- been found on one occasion in a calculus (*Ord*).

(*d*) If, after solution in ammonia, hexagonal plates (Fig. 271, A) are found, **cystin** is present- t.

(*e*) Concretions of **coagulated blood** or **fibrin**, without any crystals, are rare. When bur- rned they give the odor of singed hair. They are insoluble in water, alcohol and ether; but are sol- oluble in caustic potash, and are precipitated therefrom by acids.

(*f*) **Urostealith** is applied to a caoutchouc-like, soft elastic substance, and is very rare. W- When dry it is brittle and hard, brown or black. When warm it softens, and if more heat be applie- ed it melts. It is soluble in ether, and the residue after evaporation becomes violet on being heated. - It is soluble in warm caustic potash, with the formation of a soap.

II. If the concretions are only **partly combustible**, thus leaving a residue, they contain org- ganic and inorganic constituents.

(*a*) Pulverize a part of the stone, boil it in water, and filter while hot. The urates are dissol- olved. To test if the uric acid is united with soda, potash, lime, or magnesia, the filtrate is evaporated - and burned. The ash is investigated with the spectroscope (§ 14), when the characteristic band- ds of

sodium or potash are observed. Magnesic urate and calcic urate are changed into carbonate by burning. To separate them, dissolve the ash in dilute hydrochloric acid, and filter. The filtrate is neutralized with ammonia, and again redissolved by a few drops of acetic acid. The addition of ammonium oxalate precipitates **calcic oxalate.** Filter, and add to the filtrate sodic phosphate and ammonia, when the magnesia is precipitated as **ammonio-magnesic phosphate.**

(*b*) **Calcic oxalate** (especially in children, either as small, smooth, pale stones, or in dark, warty, hard "mulberry calculi") is not affected by acetic acid, is dissolved by mineral acids without effervescence, and again precipitated by ammonia. Heated on platinum foil it chars and blackens, then it becomes white, owing to the formation of calcic carbonate, which effervesces on the addition of an acid.

(*c*) **Calcic carbonate** (chiefly in whitish-gray, earthy, chalk-like calculi, somewhat rare) dissolves with effervescence in hydrochloric acid. When burned it first becomes black, owing to admixture with mucus, and then white.

(*d*) **Ammonio-magnesic phosphate** and **basic calcic phosphate** usually occur together in soft, white, earthy stones, which occasionally are very large. These stones show that the urine has been ammoniacal for a very long time. The first substance when heated gives the odor of ammonia, which is more distinct when heated with caustic potash; is soluble in acetic acid without effervescence, and is again precipitated in a crystalline form from this solution on the addition of ammonia. When heated it fuses into a white enamel-like mass [hence it is called "fusible calculus"]. **Basic calcic phosphate** does not effervesce with acids. The solution in hydrochloric acid is precipitated by ammonia. When ammonium oxalate is added to the acetic acid solution, it yields calcic oxalate.

(*e*) **Neutral calcic phosphate** is rare in calculi, while it is frequent in the form of gravel. Physically and chemically, these concretions resemble the earthy phosphates, only they do not contain magnesia.

273. THE SECRETION OF URINE.—[The **functions of the kidney** are—

1. To excrete waste products, chiefly nitrogenous bodies and salts;

2. To excrete water;

3. And perhaps also to reabsorb water from the uriniferous tubules, after it has washed out the waste products from the renal epithelium.

The chief parts of the organs concerned in 1, are the epithelial cells of the convoluted tubules; the glomeruli permit water and some solids to pass through them, while the constrictions of the tubules may prevent the too rapid outflow of water, and thus enable part of it to be reabsorbed.]

Theories.—The two chief older theories regarding the secretion of urine are the following: 1. According to **Bowman** (1842), through the glomeruli are filtered only the *water* and some of the highly diffusible and soluble salts present in the blood, while the specific urinary constituents are secreted by the activity of the epithelium of the urinary tubules, and are extracted or removed from the epithelium by the water flowing along the tubules. This has been called the "vital" theory. 2. **C. Ludwig** (1844) assumes that *very dilute urine* is secreted or filtered through the glomerulus. As it passes along the urinary tubules it becomes more concentrated, owing to endosmosis. It gives back some of its water to the blood and lymph of the kidney, thus becoming more concentrated, and assuming its normal character. [This is commonly known as the "mechanical" theory.]

The secretion of urine in the kidneys does not depend upon definite physical forces *only*. A great number of facts force us to conclude that the vital activity of certain secretory cells plays a foremost part in the process of secretion (*R. Heidenhain*).

The secretion of urine embraces (1) The **water,** and (2) the **urinary constituents** therein dissolved; both together form the urinary secretion. The **amount of urine** depends chiefly upon the amount of water which is filtered through or secreted by the glomeruli; the **amount of solids** dissolved in the urine determines its **concentration.**

(**A**) The **amount of urine,** which is secreted chiefly within the Malpighian capsules, *depends primarily upon the blood pressure in the area of the renal artery,* and follows, therefore, the laws of **filtration** (§ 191, II) (*Ludwig and Goll*). [In this respect the secretion of urine differs markedly from that of saliva, gastric juice, or bile. We may state it more accurately thus, that the amount of urine depends

very closely upon the differences of pressure between the blood in the glomeruli and the pressure within the renal tubules. If the ureter be ligatured, the secretion of urine is ultimately arrested, even although the blood pressure be high. The secretion may also be arrested by ligature of the renal vein; and in some cases of cardiac or pulmonary disease the venous congestion thereby produced may bring about the same result.]

Glomerular Epithelium.—The amount of urine secreted does not depend upon the hydrostatic pressure alone, but it seems that the epithelial cells covering the glomerulus also participate *actively* in the process of secretion. Besides the water, a certain amount of the salts present in the urine is excreted through the glomeruli. The *serum albumin of the blood, however, is prevented from passing through.* With regard to the secretory activity of these cells, the quantity of water must also depend upon the amount of the urinary constituents and water present in the blood (*R. Heidenhain*).

Only when the vitality of the secretory cells is intact, is there **independent activity** of these secretory cells (*Heidenhain*). When the renal artery is closed temporarily, their activity is paralyzed, so that the kidneys cease to secrete, and even after the compression is removed and the circulation re-established, secretion does not take place for some time (*Overbeck*).

That the secretion depends **in part upon the blood pressure** is proved by the following considerations:—

1. *Increase of the total contents of the vascular system, so as to increase the blood pressure,* increases the amount of water which filters through the glomeruli. The injection of water into the blood vessels, or drinking copious draughts of water, acts partly in this way. If the blood pressure rises above a certain height, albumin may pass into the urine. The *active participation* of the cells of the glomeruli is rendered probable by the fact that, after very copious drinking, the blood pressure is not always raised (*Pawlow*); further, after *copious transfusion,* the quantity of urine is not increased. Conversely, the loss of water, owing to profuse sweating or diarrhœa, copious hemorrhage, or prolonged thirst, diminishes the secretion of the urine.

2. *Diminution of the capacity of the vascular system,* provided the pressure within the renal area be thereby increased, acts in a similar manner. This may be produced by contraction of the cutaneous vessels, owing to the action of cold, stimulation of the vasomotor centre, or large vasomotor nerves, ligature, or compression of large arteries (§ 85, *e*), or enveloping the extremities in tight bandages. All these conditions cause an increase in the amount of urine, and of course the opposite conditions bring about a diminution of urine, *e. g.*, the action of heat on the skin causing redness and dilatation of the cutaneous vessels, weakening of the vasomotor centre, or paralysis of a large number of vasomotor nerves.

3. *Increased action of the heart,* whereby the tension and rapidity of the blood in the arteries are increased (§ 85, *c*), augments the amount of urine; conversely, feeble action of the heart (paralysis of motor cardiac nerves, disease of the cardiac musculature, certain valvular lesions) diminishes the amount. Artificial stimulation of the vagi in animals, so as to slow the action of the heart, and thus diminish the mean blood pressure from 130 to 100 mm. Hg, causes a diminution in the amount of urine to the extent of one-fifth (*Goll, Cl. Bernard*); when the pressure in the aorta falls to 40 mm. the secretion of urine ceases. [If the medulla oblongata be divided (dog), there is an immediate fall of the *general* blood pressure, and although, as a general rule, the secretion of urine is arrested when the pressure falls to 40 to 50 mm. Hg, yet secretion has been observed to take place with a lower pressure than this.]

4. The amount of urine secreted *rises or falls according to the degree of fullness of the renal artery* (*Ludwig, Max Hermann*); even when this artery is moderately constricted in animals, there is a decided diminution in the amount of urine.

Pathological.—In fever the renal vessels are less full, and there is consecutive diminution of urine (*Mendelson*). It is most important, in connection with certain renal diseases, to note that ligature of

the renal artery, even when it is obliterated for only two hours, causes necrosis of the epithelium of the uriniferous tubules. When the arterial anæmia is kept up for a long time, the whole renal tissue dies (*Litten*). After long-continued ligation of the renal artery, the epithelium of the glomeruli becomes greatly changed (*Ribbert*).

5. Most **diuretics** act in one or other of the above mentioned ways.

[Some diuretics act by increasing the *general* blood pressure (digitalis and the action of cold on the skin), others may increase the blood pressure *locally* within the kidney, and this they may do in several ways. The nitrites are said to paralyze the muscular fibres in the vasa afferentia, and thus raise the blood pressure within the glomeruli But some also act on the *secretory epithelium*, such as urea and caffein. Brunton recommends the combination of diuretics in appropriate cases, and the diuretics must be chosen according to the end in view—as we wish to remove excess of fluids from the tissues and serous cavities, or as we wish to remove injurious waste products, or merely to dilute the urine.]

[6. The amount of urine also depends upon the *composition of the blood.* Drinking a large quantity of water, whereby the blood becomes more watery, increases the amount of urine, but this is true only within certain limits. It is not merely the increase of volume of the blood acting mechanically which causes this increase, as we know that large quantities of fluid may be transfused without the general blood pressure being materially raised thereby.]

[Heidenhain argues, that it is not so much the *pressure* of the blood in the glomeruli as its **velocity**, which determines the process of the secretion of water in the kidney. He contends that, while increase of the pressure in the renal artery causes an increased flow of urine, ligature of the renal vein, whereby the pressure in the glomeruli is also increased, arrests the secretion altogether. In both cases the pressure is increased within the glomeruli, and the two cases differ essentially in the *velocity* of the blood current through the glomeruli.]

Pressure in the Vas Afferens.—The pressure in each *vas afferens* must be relatively great, because (1) the double set of capillaries in the kidney offers considerable resistance, and (2) the lumen of the vas efferens is narrower than that of the vas afferens. Hence, owing to the high blood pressure in the capillaries of the renal glomeruli, filtration must take place from the blood into the Malpighian capsules. When the vasa afferentia are dilated, the filtration pressure is increased, while, when they are contracted, the secretion is lessened. When the pressure becomes so diminished as to retard greatly the blood stream in the renal vein, the secretion of urine begins to be arrested. **Occlusion of the renal vein** completely suppresses the secretion (*H. Meyer, v. Frerichs*). Ludwig concluded from this observation, that the filtration or excretion of fluid could not take place through the renal capillaries *proper*, as, owing to occlusion of the renal vein, the blood pressure in these capillaries must rise, which ought to lead to increased filtration. Such an experiment points to the conclusion that the *filtration must take place through the capillaries of the glomeruli.* The venous stasis distends the vas efferens, which springs from the centre of the glomerulus, and compresses the capillary loops against the wall of the Malpighian capsule, so that filtration cannot take place through them. It is not decided whether any fluid is given off through the convoluted urinary tubules.

Venous congestion in the kidneys diminishes the quantity of urine and the urea. The NaCl remains constant, but pathological albumin is increased (*Senator and Munk*).

Pressure in Ureter.—As the blood pressure in the renal artery is about 120 to 140 mm. Hg, and the urine in the ureter is moved along by a very slight propelling force, so that a counter-pressure of from 10 (*Löbell*) to 40 mm. of Hg is sufficient to arrest its flow, it is clear that the blood pressure can also act as a *vis a tergo* to propel the urine through the ureter. The pressure in the ureter is measured by dividing the ureter transversely and inserting a manometer in it.

(B) Secretory Activity of the Renal Epithelium.—The degree of concentration of the urine depends upon the quantity of the dissolved constituents which has passed from the blood into the urine. The secretory cells of the convoluted tubules, by their own proper vital activity, seem to be able to take up,

or secrete, some at least of these substances from the blood (*Bowman, Heidenhain*). The watery part of the urine, containing only easily diffusible salts, as it flows along the tubules from the glomeruli, extracts or washes out these substances from the secretory epithelium of the convoluted tubules.

Experiments.—1. Sulphindigotate of soda and sodium urate when injected into the blood, pass into the urine, and are found in the protoplasm of the *cells* of the *convoluted tubules* [only in those parts lined by "rodded" epithelium] but not in the Malpighian capsules (*Heidenhain*). A little later these substances are found in the *lumen* of the urinary tubules, from which they are washed out by the watery part of the urine coming from the glomeruli. If, however, two days before the injection of these substances into the blood, the cortical part of the kidney containing the Malpighian capsules be cauterized, [*e. g.*, by nitrate of silver], or sliced off, the blue pigment remains within the convoluted tubules. It cannot be carried onward, as the water which should carry it along has ceased to be secreted, owing to the destruction of the glomeruli. This experiment also goes to show that, through the *glomeruli* the *watery part* of the urine is *chiefly excreted*, while through the *convoluted tubules the specific urinary constituents* are excreted. *Uric acid salts*, injected into the blood, were observed by Heidenhain to be excreted by the convoluted tubules. Von Wittich had previously observed that in *birds*, crystals of uric acid were excreted by the epithelium of the convoluted tubules. [The presence of crystals of uric acid in the renal epithelium was observed by Bowman, and used as an argument to support his theory.] Nussbaum, in 1878, stated that *urea* is secreted by the urinary tubules and not by the glomeruli.

The same is true for the *bile pigments*, for the *iron salts* of the vegetable acids when injected subcutaneously, and for hæmoglobin. After injection of *milk* into the blood vessels, numerous fatty granules occur within the epithelium of the urinary tubules (§ 102).

[**Nussbaum's Experiments.**—In the frog and newt, the kidney is supplied with blood in a manner different from that obtaining in mammals. The glomeruli are supplied by branches of the renal artery. The tubules are supplied by the renal-portal vein. The vein coming from the posterior extremities divides at the upper end of the thigh into two branches, one of which enters the kidney, and breaks up to form a capillary plexus which surrounds the uriniferous tubules, but this plexus is also joined by the efferent vessels of the glomeruli. These two systems are partly independent of each other. After ligaturing the renal artery, Nussbaum asserted that the circulation in the glomeruli was cut off, while ligature of the renal-portal vein excluded the functional activity of tubules. By injecting a substance into the blood, after ligaturing either the artery or renal-portal vein, and observing whether it occurs in the urine, he infers that it is given off either by the glomeruli or the tubules. *Sugar*, *peptones*, and *egg albumin* rapidly pass through an intact kidney, but if the renal artery be tied they are not excreted. *Urea* when injected into the circulation is excreted after the artery is tied, so that it is excreted through the tubules, but at the same time it takes with it a considerable quantity of water. Thus, water is excreted in *two* ways from the kidney, by the glomeruli and also from the venous plexus around the tubules along with the urea. *Indigo carmine* merely passes into the tubular epithelium of the convoluted tubules, but it does not cause a secretion of urine. *Albumin* passes through the glomeruli, but only after their membranes have been altered in some way, as by clamping the renal artery for a time.]

[**Adami's Experiments** on the kidney of the frog tend to show that Nussbaum's conclusions are not justified, for Adami found that if the renal arteries in the frog be ligatured, within a few hours a collateral circulation is established, and a certain amount of blood flows through the kidney. He proved this by injecting into the blood, carmine or painter's vermilion, in a state of fine suspension, and after ligature of the renal arteries, he found it in many of the glomeruli, while laky blood similarly injected revealed its presence as menisci of Hb in the Malpighian corpuscles. Even secretion of some urine may go on after ligature of the renal arteries. It is evident, then, that

Nussbaum's method is not a reliable one for locating the parts of the kidney through which certain substances are excreted. Adami's experiments also give some support to Heidenhain's view, that the glomerular epithelium "possesses powers of a selective secretory nature," for he finds that in frogs, after ligature of the renal arteries, where, of course, the pressure in the glomeruli is just nearly that in the veins, and in the dog after section of the spinal cord, so that the blood pressure has fallen below 40 mm. Hg, whereby the secretion of urine is arrested, the injection of laky blood causes Hb to appear in the capsules, although there is no simultaneous excretion of water.]

Excretion of Pigments.—Only during very **copious excretion** does the capsule participate. After the introduction of a large amount of sodic sulphindigotate, and when the experiment has lasted for a long time, the epithelium of the capsule becomes blue. **In albuminuria,** the abnormal excretion of urine takes places first in the urinary tubules, and afterward in the capsules; Hb is partly found in the capsules. According to Nussbaum, egg albumin passes out through the capsule.

2. Even when the secretion of the *watery part* of the urine is completely *arrested*, either by ligature of the ureter, or after a very great fall of the blood pressure in the renal artery [as after section of the cervical spinal cord], the before-mentioned substances, when injected into the blood, are found in the cells of the convoluted tubules. The injection of urea under these circumstances causes renewed secretion. These facts show that, independently of the filtration pressure, the *secretory activity of these cells* is still maintained.

The independent **vital activity of the secretory cells** of the urinary tubules, which as yet we are unable to explain on purely physical grounds, renders it probable that the tubules are not to be compared to an apparatus provided with physical membranes. This is proved by the following experiment: Abeles caused arterial blood to circulate through freshly excised living kidneys. A pale, urine-like fluid dropped from the ureter. On adding some urea or sugar to the blood, the secretion became more concentrated. Thus, the **excised living kidney** also excretes substances in a more concentrated form than those supplied to it in the diluted blood streaming through it. J. Munk obtained similar results in excised kidneys with common salt, nitre, caffein, grape sugar, glycerin, with increase in the amount of urine secreted. The addition of caffein or theobromin to the perfused blood increases the secretion, exciting the secretory cells to greater activity (*v. Schroeder*).

Salts and Gases.—The vital activity explains why the serum albumin of the blood does not pass into the urine, while egg albumin and dissolved hæmoglobin readily do so. Among the *salts* which occur in the blood and blood corpuscles, of course only those in solution can pass into the urine. Those which are united with proteid bodies, or are fixed in the cellular elements, cannot pass out, or at least only after they have been split up. Thus, we may explain the difference between the salts of the urine and those of the blood. Similarly, the urine can only contain the absorbed and not the chemically united *gases*.

Ligature of the Ureter.—If the secretion be arrested by compression or by ligature of the ureter, the lymph spaces of the kidney become filled with fluid, which may pass into the blood, so that the organ becomes œdematous, owing to the passage of fluid into its lymph spaces. The secretion undergoes a change, as, first, water passes back into the blood, then the sodic chloride, sulphuric, and phosphoric acids diminish, and lastly the urea (*C. Ludwig, Max Hermann*). Kreatinin is still present in considerable amount. There is no longer secretion of proper urine (*Löbell*).

Non-symmetrical Renal Activity.—It is remarkable that both kidneys do not secrete symmetrically—there is an alternate condition of hyperæmia and secretory activity on opposite sides (§ 100). One kidney secretes a more watery urine, which at the same time contains more NaCl and urea. Von Wittich observed that the secretion of uric acid was not uniform in all the urinary tubules of the same bird. **Extirpation** of one kidney, or disease of one kidney in man, does not seem to diminish the secretion (*Rosenstein*). The remaining kidney becomes more active and larger.

Reabsorption in the Kidney.—In discussing the secretion of the kidney, we must attach considerable importance to the variations in the calibre of the renal tubules in their course. Perhaps in the narrowing of the descending part of the looped tubule of Henle there may be either a reabsorption of water, so that the urine becomes more concentrated, or there may be absorption even of albumin, which may perhaps pass through the glomeruli in small amount. [That reabsorption of fluid takes place within the kidney was part of Ludwig's theory, which is practically a process of filtration and reabsorption. Hüfner pointed out that the structure of the kidneys of various classes of vertebrates corresponded closely with the requirements for reabsorption of water. The experiments of Ribbert show that the urine actually secreted in the cortex of the kidney is more watery than that secreted normally by the entire organ. He extirpated the medullary portion in rabbits, leaving the cortical part intact, and in this way collected the dilute urine from the Malpighian corpuscles before it passed through Henle's loops.]

274. FORMATION OF THE URINARY CONSTITUENTS.—The question has often been discussed, whether all the urinary constituents are merely excreted through the kidneys, *i. e.*, that they exist preformed in the blood;

or whether some of them do *not* exist preformed in the blood, but are formed within the kidneys, as a result of the activity of the renal epithelium.

Urea is formed Outside the Kidney.—Urea exists preformed in the blood, from which it is separated by the activity of the kidney. This is proved by the following considerations :—

1. The blood contains one part of urea in 3000 to 5000 parts, but the **renal vein** contains less urea than the blood of the corresponding artery.

2. After **extirpation** of the kidneys, or **nephrotomy**, or after ligature of the renal vessels, the amount of urea accumulates in the blood, and increases with the duration of the experiment to $\frac{1}{150}$ to $\frac{1}{100}$. At the same time there is vomiting and diarrhœa, and the fluids so voided contain urea (*Cl. Bernard*). Animals die in from one to three days after the operation.

3. After ligature of the ureters, the secretion of urine is soon arrested. Urea accumulates in the blood, but not to a greater extent than after nephrotomy. It is possible, however, that the kidneys, like other organs, may form a small amount of urea, due to the metabolism of their own tissues.

[**Urea exists in the blood**; whence does the blood derive it? It can only obtain it from one or more of several organs—(1) muscle, (2) nervous system, and (3) glands, of which the liver is the most prominent. This is best stated by the method of exclusion.]

[1. That urea is not formed in muscle is shown, among other considerations, by the fact that only a trace of urea occurs in muscle (§ 293), and that the amount is not increased by exercise. Blood which has been transfused through a muscle, or the blood after circulating in a muscle during violent exercise, does not contain an increase of urea, nor does the addition of ammonia carbonate to blood circulating through muscle show any increase of urea. Again, muscular exertion does not (as a rule) increase the amount of urea in the urine, as shown by the experiments of Fick and Wislicenus (§ 294), Parkes, and others. The excretion chiefly increased by muscular exertion is the pulmonary CO_2 (§ 127).]

[2. From what we know of the nervous system, it is not formed there. We are therefore forced to consider the evidence as to the **liver**, as the organ, or, at least, the chief organ in which it is formed. This evidence is in some respects contradictory, but it is partly **experimental** and partly **clinical**. Although Hoppe-Seyler denies the existence of urea in the liver, its existence there was proved by Gscheidlen; and Cyon, on passing blood through an excised liver by the "perfusion" method of Ludwig, found that blood, after being passed several times through the organ, contained an *increased* amount of urea. The objection to these experiments is that Cyon's method of estimating the urea was unreliable. But von Schroeder, using a similar method, finds that if blood be perfused through the liver of a dog in full digestion, there is a great increase in the amount of urea, while there is none in the liver of a fasting dog. If ammonia carbonate be added to the blood, there is a very much greater amount of urea in the blood of the hepatic vein. This last fact is confirmed by Salomon. The experiments of Minkowski on the liver of the goose (§ 386) show that, when the liver is excluded from the circulation, lactic acid takes the place of uric acid in this bird. Brouardel further states, that if the region of the liver be so beaten as to cause congestion of that organ, there is an increase of the urea in the urine.]

[The **clinical** evidence points strongly to the formation of urea in the liver. Parkes pointed out that in hepatic abscess, during the early congestive stage, the urea in the urine is increased, while it is diminished in the suppurative stage, when the hepatic parenchyma is destroyed. The urea is also diminished in cancer of the liver, phthisis, and some forms of hepatic cirrhosis, while it is increased during hepatic congestion, and specially so in some cases of diabetes mellitus. The most striking fact of all is that, in **acute yellow atrophy** of the liver, the urea is enormously diminished in the urine, and may even disappear from it while its place is taken by the intermediate products, leucin and tyrosin (*v. Frerichs*). In poisoning by phosphorus, coincident with the atrophy of the liver, there is a fall in the urea excretion. Noël-Paton finds that some drugs which increase the quantity of bile in dogs in a state of N-equilibrium (§ 178), *e.g.*, sodic salicylate and benzoate, colchicum, mercuric chloride and eunonymin also increase the urea in the urine, he therefore concludes "that the formation of urea in the liver bears a very direct relationship to the secretion of bile by that organ."]

As to the **antecedents** of urea there is the greatest doubt (§ 256).

Uric Acid is formed Outside the Kidneys.—1. Birds' blood normally contains uric acid (*Meissner*). [The liver of the pigeon contains 6 to 14 times as much uric acid as the blood.] Ligature of the ureters or renal blood vessels (*Pawlinoff*), or gradual destruction of the renal secretory parenchyma by the subcutaneous injection of neutral potassium chromate (*Ebstein*), is followed by the deposition of uric acid in the joints and tissues, and it may even form a white incrustation on

the serous membranes. The brain remains free (*Zalesky, Oppler*). Acid urates of ammonia, soda, and magnesia are also similarly deposited. Extirpation of a snake's kidneys gives the same result, but to a less degree.

[Minkowski found that, after excluding the liver from the circulation, lactic acid took the place of uric acid in the urine (p. 474). Some uric acid still appears in the urine, which cannot be derived from the small amount in the blood, so that, according to v. Schroeder, there are perhaps other foci of formation of uric acid.]

[The latter experiment points to the formation of uric acid in the **liver** in birds, and this is supposed to be strengthened by the appearance of the deposition of urates in the urine in certain disorders of digestion.] Von Schroeder and Colasanti, however, as the result of their experiments upon snakes, come to the conclusion that there is no special organ concerned in the formation of uric acid.

Hippuric acid is partly formed in the **kidney,** for the blood of herbivora does not contain a trace of it (*Meissner and Shepard*). In rabbits, perhaps it is formed synthetically, in other tissues as well as in the kidney. If blood containing sodic benzoate and glycin be passed through the blood vessels of a fresh kidney, hippuric acid is formed (§ 260) (*Bunge, Schmiedeberg, Kochs*). [The other evidence is given in § 260.]

Kreatinin has intimate relations to kreatin of muscle, but where it is formed is not known. If *phenol* and pyrokatechin are digested along with fresh *renal substance, a compound of sulphuric acid* similar to that occurring in urine is formed (§ 262). The latter substance, however, is also formed by similarly digesting liver, pancreas, and muscle. It is concluded from these experiments that these substances are formed in the body within the kidneys and the other organs mentioned (*Kochs*).

Chemistry of the Kidney.—The kidneys contain a very large amount of *water*. Besides serum albumin, globulin, albumin soluble in sodium carbonate (*Gottwalt*), gelatin-yielding substances, fat in the epithelium, elastic substance derived from the membrana propria of the tubules, the kidneys contain leucin, xanthin, hypoxanthin, kreatin, taurin, inosit, cystin (the last in no other tissue), but only in very small amount. The occurrence of these substances points to a lively metabolism in the kidneys, which is also proved by the liberal supply of blood they receive.

Blood Vessels.—The kidneys receive a very large supply of blood, and during secretion the blood of the **renal vein is bright red.** [In the dog, the diameter of the renal artery may be diminished to .5 mm. without the amount of blood flowing through the kidney being thereby greatly interfered with. Hence, within wide limits, the amount of blood is independent of the size of the arterial lumen, and is therefore dependent on the blood pressure in the aorta, and the resistance to the blood current within and beyond the kidney (*Heidenhain*).]

The **reaction** of the kidneys is *acid*, even in those animals whose urine is alkaline. Perhaps this fact is connected with the retention of the albumin in the vessels.

275. PASSAGE OF VARIOUS SUBSTANCES INTO THE URINE.—1. The following substances pass **unchanged** into the urine: Sulphate, borate, silicate, nitrate, and carbonate of the alkalies; alkaline chlorides, bromides, iodides; potassium sulphocyanide and ferrocyanide; bile salts, urea, kreatinin; cumaric, oxalic, camphoric, pyrogallic, and carbolic acids. Many *alkaloids, e.g.*, morphia, strychnia, curara, quinine, caffein; *pigments*, sulphindigotate of soda, carmine, madder, logwood, coloring matter of cranberries, cherries, rhubarb; santonin; lastly, salts of gold, silver, mercury, antimony, arsenic, bismuth, iron (but not lead), although the greatest part of these is excreted by the bile and the fæces.

2. Inorganic acids reappear in man and carnivora as neutral salts of ammonia, in herbivora, as neutral salts of the alkalies.

3. Certain substances which, when injected in small amount, seem to be **decomposed** in the blood, pass in part into the urine, when they occur in such large amount in the blood that they cannot be completely decomposed—sugar, hæmoglobin, egg albumin, alkaline salts of the vegetable acids, alcohol, chloroform.

4. Many substances appear in an **oxidized form** in the urine—moderate quantities of organic alkaline salts as alkaline carbonates (*Wöhler*), uric acid in part as allantoin (*Salkowski*), sulphides and sulphites of soda, in part as sodium sulphate, potassium sulphide as potassium sulphate, some oxyduls as oxides, benzol as phenol (*Naumyn and Schulzen*).

5. Those bodies which are completely decomposed, as glycerin, resins, give rise to no special derivatives in the urine.

6. Many substances **combine** and appear as conjugated compounds in the urine, *e. g.*, the origin of the hippuric acid by conjugation (§ 260), the conjugation of sulphonic acid (§ 262), and the formation of urea by synthesis from carbamic acid and ammonia (*Drechsel*) (§ 256). After the use of

camphor, chloral; or butylchloral, a conjugated compound with glycuronic acid (an acid nearly related to sugar) appears in the urine. Taurin and sarcosin unite with sulphaminic acid. When bromophenol is given, it unites with mercapturic acid, a body nearly related to cystin (§ 268).

7. Tannic acid, $C_{14}H_{10}O_9$, takes up H_2O, and is decomposed into two molecules of gallic acid = 2 ($C_7H_6O_5$).

8. The iodates of potash and soda are **reduced** to iodides; malic acid ($C_4H_6O_5$) partly to succinic acid ($C_4H_6O_4$); indigo-blue ($C_{16}H_{10}N_2O_2$) takes up hydrogen and becomes indigo-white ($C_{16}H_{12}N_2O_2$).

9. Some substances **do not pass** into the urine at all, *e. g.*, oils, insoluble metallic salts and metals.

276. INFLUENCE OF NERVES AND OTHER CONDITIONS.—At present we are acquainted merely with the influence of the **vasomotor** nerves on the filtration of the urine through the renal vessels. *Each* kidney seems to be supplied with vasomotor nerves, which spring from *both* halves of the spinal cord (*Nicolaides*). As a general rule, dilatation of the branches of the renal artery, chiefly the vasa afferentia, must raise the pressure within the glomeruli, and thus increase the amount of water filtered through them. The more the dilatation is confined to the area of the renal artery alone, the greater is the amount of the urine. [As yet we know the nervous system influences the secretion of urine only in so far as it modifies the pressure and velocity of the blood current in the kidney. We have no satisfactory evidence of the existence of direct secretory nerves in the kidney.]

1. **Renal Plexus and its Centre.**—Section of the nerves of the renal plexus—the nerves around the renal artery—generally causes a considerable increase in the secretion of urine, **hydruria** or **polyuria**; sometimes, on account of the great rise of the pressure within the glomeruli, albumin passes into the urine, and there may be rupture of the vessels of the glomeruli, leading to the passage of blood into the urine. The **nerve centre** for the renal nerves lies in the floor of the fourth ventricle, in front of the origin of the vagus. Injury to this part of the floor of the fourth ventricle, *e. g.*, by puncture (piqûre), may increase the amount of urine (**diabetes insipidus**), which is sometimes accompanied by the simultaneous appearance of albumin and blood in the urine (*Cl. Bernard*). Section of the parts which lie directly in the course of these fibres, as they pass from their centre to the kidney, produces the same effects. Close to this centre in the medulla, lies the centre for the vasomotor nerves of the liver, whose injury causes **diabetes mellitus** (§ 175). Eckhard found that stimulation of the vermiform process of the cerebellum produced hydruria. In man, stimulation of these parts by tumors or inflammation, etc., produces similar results.

2. **Paralysis of Limited Vascular Areas.**—If, simultaneously with the paralysis of the nerves of the renal artery, the nerves of a neighboring large vascular area be paralyzed, necessarily the blood pressure in the renal artery area will not be so high, as more blood flows into the other paralyzed province. Under these circumstances, there may be only a temporary, or, indeed, no increase of urine, provided the paralyzed area be sufficiently large. There is a moderate increase of urine for several hours after **section of the splanchnic nerve.** This nerve contains the renal vasomotor nerves (which, in part, at least, leave the spinal cord at the first dorsal nerve and pass into the sympathetic nerve), but it also contains the vasomotor nerves for the large area of the intestinal and abdominal viscera. Stimulation of this nerve has the opposite effect (*Cl. Bernard, Eckhara*). [The polyuria thus produced is not so great as after section of the renal nerves, because the splanchnic supplies such a large vascular area, that much blood accumulates in that area, and also because all the renal nerves do not run in the splanchnics.]

3. **Paralysis of Large Areas.**—If, simultaneously with paralysis of the renal nerves, the great majority of the vasomotor nerves of the body be paralyzed [as by section of the medulla oblongata], then, owing to the great dilatation of all these vessels, the blood pressure falls at once throughout the arterial system. The result of this may be, provided the pressure is sufficiently low, that there is a great decrease,

or, it may be, entire cessation of the secretion of urine. The secretion is arrested when the cervical cord is completely divided, down even as far as the seventh cervical vertebra (*Eckhard*). The polyuria caused by injury to the floor of the fourth ventricle at once disappears when the spinal cord (even down to the twelfth dorsal nerve) is divided.

[4. **Other Conditions.**—As already stated, section of the renal nerves is followed by polyuria, owing to the increased pressure in the glomeruli, but this polyuria may be increased by stimulating the spinal cord below the medulla oblongata, because the contraction of the blood vessels throughout the body still further raises the blood pressure within the glomeruli. If, however, the spinal cord be divided below the medulla oblongata—the renal nerve being also divided—the polyuria ceases, because of the fall of the general blood pressure thereby produced. Division of the spinal cord in the dorsal region also diminishes or arrests the secretion of urine, owing to the fall of the blood pressure; but animals recover from this operation, the general blood-pressure rises, and with it the secretion of urine. Stimulation of the cord below the medulla arrests the secretion, as it causes contraction of the renal arteries along with the other arteries of the body.]

[**Volume of the Kidney—Oncometer.**—By means of the plethysmograph (§ 101) we can measure the variations in the size of a limb, while by the oncograph

FIG. 286.



FIG. 287.



FIG. 286.—Oncometer. K, kidney; the thick line is the metallic capsule; *h*, hinge; I, tube for filling apparatus; T, tube to connect with T_1; *a*, *v*, *u*, artery, vein, ureter (*Stirling, after Roy*).
FIG. 287.—Oncograph. C', chamber filled with oil, communicating by T_1 with T; *p*, piston; *l*, writing lever (*Stirling, after Roy*).

(ὄγκος, volume) similar variations in the volume of the spleen are measured (§ 103). Roy and Cohnheim have measured the variations in the volume of the kidney by means of an instrument which consists of two parts, one termed the **oncometer** or **renal plethysmometer**, in which the organ is enclosed, while the other part is the registering portion, or **oncograph**. The kidney is enclosed in a kidney-shaped metallic capsule (Fig. 286), composed of two halves which move on the hinge, *h*, to introduce the organ. The renal vessels pass out at *a*, *v*. The kidney is surrounded with a thin membrane, and between this membrane and the inner surface of the capsule is a space filled with warm *oil* through the tube, I, which is closed by means of a stop-cock after the space is filled with oil. The tube, T, can be made to communicate with another tube, T_1, leading into a metallic chamber, C', of the oncograph (Fig. 287), which is provided with a movable piston, *p*, attached by a thread to the writing-lever, *l*. Any increase in the size of the organ expels oil from the chamber, O, into C', and thus the piston is raised, while a diminution in the size of the kidney diminishes the fluid in C', and the lever falls. The actual volume of the living kidney depends upon the state of distention of its

structural elements, upon the amount of lymph in its lymph spaces, but chiefly upon the amount of blood in its blood vessels, and this again must depend upon the condition of the non-striped muscles in the renal arteries. When the vessels dilate, the kidney increases in size, and when they contract it contracts, so that we can register on the same revolving cylinder the variations of the volume at the same time that we record the general arterial blood pressure.]

[In the **normal circulation** through the kidney, the kidney curve, *i. e.*, the curve of the volume of the kidney, runs parallel with the blood-pressure curve, and shows the large respiratory undulations, as well as the smaller elevations due to the systole of the heart (Fig. 288). Usually, when the blood pressure falls, the kidney curve sinks, and when the blood pressure rises the volume of the kidney increases. When the blood-pressure curve is complicated by Traube-Hering waves (§ 85) the *opposite* effect is produced on the kidney curve; the highest blood pressure corresponds to the smallest size of the kidney, and conversely. This is due to the fact that, when these curves occur, all the small arterioles, including those in the kidney, are contracted. A kidney placed in an oncometer secretes urine like a kidney under natural conditions.]

[**Arrest of the respiration** in a curarized animal produces a rapid and great diminution of the volume of the kidney, caused by the venous blood stimulating the vasomotor centres, and thus contracting the small arterioles, including those of the

FIG. 288.



B. P., Blood-pressure curve; K., curve of the volume of the kidney; T, time curve, intervals indicate a quarter of a minute; A, abscissa (*Stirling, after Roy*).

kidney. This result occurs whether one or both splanchnics are divided, proving that all the vasomotor nerves of the kidney do not reach it through the splanchnics. When *all* the renal nerves at the hilum are divided, arrest of the respiration causes dilatation of the organ, which condition runs parallel with the rise of the blood pressure. Stimulation of a sensory nerve, *e. g.*, the central end of the sciatic nerve, while causing an increase of the blood pressure, makes the kidney shrink.]

[In poisoning with **strychnin**, the kidney shrinks while the blood pressure rises. Stimulation of the central or peripheral end of the **splanchnics**, divided at the diaphragm, causes contraction of the renal vessels of *both* sides; the former is a reflex, the latter a direct effect. Stimulation of the peripheral end of *one* splanchnic sometimes affects both kidneys. Stimulation of the peripheral end of the renal nerves always causes a diminution in the volume of the kidney, so that Cohnheim and Roy inferred that, although there was evidence of the existence of **vasomotor** and **sensory nerves** to the kidney, they found none of vaso-dilators. Each kidney acts independently of the other. Sudden compression of one renal artery has not the slightest effect upon the blood current of the other kidney. If a kidney be exposed in an animal, by making an incision in the lumbar region, on stimulating the medulla oblongata directly with electricity, we may observe the kidney itself becoming paler, the pallor appearing in a great many small spots on the surface of the organ, corresponding to the distribution of the interlobular arteries.]

[Cohnheim showed that the **composition of the blood** has a remarkable effect

on the renal circulation. Some substances (water and urea), when injected into the blood, cause the kidney first to shrink and then to expand, while sodic acetate dilates the kidney, even after all the renal nerves are divided—an operation which is very difficult indeed. Provided all the renal nerves be divided, these effects would indicate the existence of some local intra-renal vasomotor mechanism governing the renal blood vessels. The general blood pressure is not thereby modified; nor need we wonder at this, as ligature of one renal artery does not increase the pressure in the aorta.]

[The reciprocal relation between the **skin and the kidneys** is known to every one. On a cold day, when the skin is pallid, owing to contraction of the cutaneous vessels, the amount of urine secreted is great, and conversely, in summer less urine is passed than in winter. Washing the skin of a dog for two minutes with ice-cold water causes a great contraction of the kidney.]

The perfusion of blood through a living excised kidney is materially influenced by the substances mixed with the blood perfused. This effect may in part be due to the action of these chemical ingredients upon the nuclei of the endothelial lining of the blood vessels, especially the capillaries, or the effects upon the muscular fibres of the blood vessels.

[Strychnin seems to cause contraction of the renal vessels, independently of its action on the general vasomotor centre. Brunton and Power found that digitalis caused an increase of the blood pressure (dog), but the secretion of urine was either at the same time diminished, or it ceased altogether. The latter result was due to contraction of the renal blood vessels, but when the aortic blood pressure began to fall, the amount of urine secreted rose much above normal, *i. e.*, when the arteries had begun to relax.]

During **fever**, the renal vessels are probably contracted in consequence of the stimulation of the renal centre by the abnormally warm blood (*Mendelson*).

The repeated respiration of CO is said to produce polyuria, perhaps in consequence of paralysis of the renal vasomotor centre.

Action of the Vagus.—According to Cl. Bernard, stimulation of the vagus at the cardia increases the urinary secretion, while at the same time the blood of the renal vein becomes red. This nerve may contain vaso-dilator nerve fibres corresponding to the fibres in the facial nerve for the salivary glands (§ 145).

277. **URÆMIA—AMMONIÆMIA.—Symptoms of Uræmia.**—After excision of the kidneys, **nephrotomy**, or ligature of the ureter; in man, also, as a result of certain diseased conditions of the kidney, leading to the suppression of the secretion of urine, there is developed a series of characteristic symptoms which are followed by death. The condition is called uræmic intoxication or *uræmia*. There are marked cerebral phenomena, drowsiness, and deep coma, and occasionally local or more general *spasms*. Sometimes there is *delirium;* Cheyne-Stokes phenomenon is often observed (§ 111, 11), and there may be vomiting and diarrhœa, while in the fluids voided, as well as in the expired air, ammonia may sometimes be detected.

The **cause** of these phenomena has been ascribed to the retention in the blood of those substances which normally are excreted by the urine, but as yet it has not been definitely ascertained which of these substances cause the phenomena:—

1. The first thought is to ascribe them to the retention of the **urea.** v. Voit found that dogs exhibited uræmic symptoms if they were fed for a long time on food containing urea and little water. Meissner found that in nephrotomized animals, the uræmic symptoms were hastened by the injection of urea into the blood. The injection of a moderate amount of urea in perfectly healthy animals is not followed by uræmic symptoms, probably because the urea is rapidly excreted by the kidneys; 1 to 2 grms. [15 to 30 grains] so injected produce comatose symptoms in rabbits.

2. The injection of **ammonium carbonate** produces symptoms resembling those of uræmia, so that v. Frerichs thought that the urea was decomposed in the blood, yielding ammonium carbonate—**ammoniæmia.** Demjankow observed uræmic phenomena after nephrotomy, if at the time he injected urea ferment into the blood (§ 263). Feltz and Ritter obtained uræmic symptoms in dogs by injecting salts of ammonia.

3. As ligature of the ureters produces a comatose condition in those animals which excrete chiefly uric acid in the urine—*e. g.*, birds and snakes (*Zalesky*)—it is possible that other substances may produce the poisonous symptoms. The injection of kreatinin causes feebleness and contraction of the muscles in dogs (*Meissner*). Bernard, Traube, and more recently Feltz and Ritter, ascribe the symptoms to an accumulation of the neutral potassium salts in the blood (§ 54). The injection of kreatin, succinic acid (*Meissner*), uric acid, and sodic urate (*Ranke*), is without effect. Schottin and Oppler ascribe the results to an accumulation of normal or abnormal *extractives*. It is possible that several

substances and their decomposition products contribute to produce the result, so that there is a combined action of several factors, but perhaps the retention of the *potash salts* plays the most important part.

The direct application of some ordinary substances (kreatinin, kreatin, acid potassic phosphate, urates) to the surface of the cerebrum causes all the symptoms of uræmia. Urea is inactive, and slightly active are ammonium and sodic carbonate, leucin, NaCl, KCl (*Landois*).

[**Alkaloids in Urine.**—Human urine, and especially febrile urine, when injected under the skin of frogs or rabbits, acts as a poison, and even causes death, by arresting the respiration. The alkaloids seem to be formed by the action of vegetable organisms in the intestine, whence they are absorbed into the blood and pass into the urine (§ 116). Urine rendered colorless by charcoal loses half its toxic power, and the poisonous substance is not volatile, and even resists boiling. These alkaloids are **increased** in the urine in typhoid fever, pneumonia, but not in diabetes.]

Ammoniæmia.—When urine undergoes the alkaline fermentation within the bladder, and ammonium carbonate is formed, the ammonia may be absorbed and produce this condition. The breath and excretions smell strongly of ammonia; the mouth, pharynx, and skin are very dry; there is vomiting, with diarrhœa or constipation, while ulcers may form in the intestine. The patient rapidly loses flesh, and death occurs without any disturbance of the mental faculties.

Uric Acid Diathesis.—When too much nitrogenous food, too much of any alcoholic fluid, is persistently used, and little muscular exercise taken, especially if the respiratory organs are interfered with, uric acid may not unfrequently accumulate in the blood (*Garrod*). It may be deposited in the joints and their ligaments, especially in the foot and hand, giving rise to painful inflammation, and forming gout stones or chalk stones. The heart, liver and kidneys are rarely affected. The tissues near these deposits undergo necrosis.

278. **STRUCTURE AND FUNCTIONS OF THE URETER.**—**Mucous Membrane.**—The pelvis of the kidney and the ureter are lined by a *mucous membrane*, consisting of connective tissue, and covered with several layers of stratified "**transitional**" epithelium (Fig. 290).

FIG. 289.



Transverse section of the lower part of human ureter, × 15. *e*, epithelium; *t*, tunica propria; *s*, sub-mucosa; *l* and *r*, longitudinal and circular fibres.

The cells are of various shapes, those of the lowest layer being usually more or less spherical and small, while many of the cells in the upper layers are irregular in shape, often with long processes passing into the deeper layers.

Sub-mucosa.—Under the epithelium there is a layer of adenoid tissue (*Hamburger, Chiari*), which may contain small lymph follicles [embedded in loose connective tissue]. In the pelvis of the kidney and ureter there are a few small mucous glands lined by a single layer of columnar epithelium (*Unruh, Egli*).

The **muscular coat** consists of an inner somewhat stronger layer of *longitudinal* non-striped fibres, and an outer *circular* layer (Fig. 289). In the lowest third of the ureter there are in addition a number of scattered muscular fibres. All these layers are surrounded and supported by connective tissue. The outer layers of the connective tissue form an outer coat or **adventitia**, which contains the

large vessels and nerves. The various coats of the ureter can be followed up to the pelvis of the kidney, and to its calices. The papillæ are covered only by the mucous membrane, while the muscular layer ceases at the apex of the pyramids, where they are disposed circularly, to form a kind of *sphincter* muscle for each papilla (*Henle*).

The **blood vessels** supply the various coats, and form a capillary plexus under the epithelium. The **nerves** are not very numerous, but they contain medullated (few) and non-medullated fibres, with numerous ganglia scattered in their course. They are partly *motor*, and supply the muscular layers, and some pass toward the epithelium, and are *sensory* and *excito-reflex* in function. These nerves are excited when a calculus passes along the ureter, and thus give rise to severe pain. The ureter perforates the wall of the bladder *obliquely*. The inner opening is a narrow slip in the mucous membrane, directed downward and inward, and provided with a pointed, valve-like process (Fig. 291).

Movement of the Urine. — The urine is propelled along the ureter thus: (1) The secretion, which is continually being formed under a high pressure in the kidney, propels the urine onward in front of it, as the urine is under a low pressure in the ureter. (2) *Gravity* aids the passage of the urine when the person is in the erect posture. (3) The muscles of the ureter contract rhythmically and peristaltically, and so propel it toward the bladder. This movement is reflex, and is due to the presence of the urine in the ureter. Every three-quarters of a minute several drops of urine pass into the bladder. But the fibres may also be excited directly. The contraction passes along the tube at the rate of 20 to 30 mm. per second, always from above downward. The greater the tension of the ureter due to the urine, the more rapid is the peristaltic movement.

FIG. 290.

Transitional epithelium from the bladder. Many of the large cells lie upon the summit of the columnar and caudate cells, and depressions are seen on their under surface.

Local Stimulation.—On applying a stimulus to the ureter directly, the contraction passes both upward and downward. Engelmann observed that the movements occur in parts of the ureter where neither nerves nor ganglia were to be found, and he concluded that the movement was propagated by "**muscular conduction.**" If this be so, then an impulse may be propagated from one non-striped muscular cell to another without the intervention of nerves (see Heart, § 58, I, 3).

Prevention of Reflux.—The urine is prevented from exerting a backward pressure toward the kidneys: (1) The urine which collects in the pelvis of the kidney is under a high pressure, and thus tends uniformly to compress the pyramids, so that the urine cannot pass into the minute orifices of the urinary tubules. (2) When there is a considerable accumulation of urine in a ureter, *e. g.*, from the presence of an impacted calculus or other cause, there is also more energetic peristalsis, and, at the same time, the circular muscular fibres round the apices of pyramids compress the pyramids and prevent the reflux of urine through the collecting tubules. The urine is prevented from passing back from the bladder into the ureter, the wall of the bladder itself, and the part of the ureter which passes through it, are compressed, so that the edges of the slit-like opening of the ureter are rendered more tense, and are thus approximated toward each other (Fig. 291).

279. **URINARY BLADDER AND URETHRA.—Structure.—The mucous membrane** of the bladder resembles that of the ureter; the upper layers of the stratified transitional epithelium are flattened. It is obvious that the form of the cells must vary with the state of distention or contraction of the bladder. [The mucous membrane and muscular coats are thicker than in the ureter. There are mucous glands in the mucous membrane, especially near the neck of the bladder.]

Sub-mucous Coat.—There is a layer of delicate fibrillar connective tissue mixed with elastic fibres between the mucous and muscular layers.

[The **serous coat** is continuous with and has the same structure as the peritoneum, and it covers only the posterior and upper half of the organ.]

Musculature.—The *non-striped* muscular fibres are arranged in bundles in several layers, an *external longitudinal* layer, best developed on the anterior and posterior surfaces, and an *inner circular* layer. [Between these two is an *oblique* layer.] There are other bundles of muscular fibres arranged in different directions. **Physiologically**, the musculature of the bladder represents a single or common hollow muscle, whose function when it contracts is to diminish uniformly the size of the bladder, and thus to expel its contents (§ 306).

The **blood vessels** resemble those of the ureter. The **nerves** form a plexus, and are placed partly in the mucous membrane and partly in the muscular coat, and, like all the extra-renal parts of the urinary apparatus, are provided with **ganglia**, lying in the mucosa, sub-mucosa, and connected to each other by fibres (*Maier*). Ganglia occur in the course of the motor nerve fibres in the bladder (*W. Wolff*). Their functions are **motor, sensory, excito-motor,** and **vasomotor.** [Sympathetic nerve ganglia also exist underneath the serous coat (*F. Darwin*).]

A too minute dissection of the several layers and bundles of the musculature of the bladder has given rise to erroneous inferences. Thus, we speak of a **detrusor urinæ**, which, however, consists chiefly of fibres running on the anterior and posterior surfaces, from the vertex to the fundus. There does not seem to be a special **sphincter vesicæ internus**; it is merely a thicker circular (6 to 12 mm.) layer of non-striped muscle which surrounds the beginning of the urethra, and which, from its shape, helps to form the funnel-like exit of the bladder. Numerous muscular bundles, connected

FIG. 291.



Lower part of the human bladder laid open, showing clear part, or trigone, the slit-like openings of the ureters, the divided ureters, and vesiculæ seminales; the sinus prostaticus, and on each side of it the openings of the ejaculatory ducts, and below both numerous small apertures of the prostate ducts.

partly with the longitudinal and partly with the circular fibres of the bladder, exist, especially in the trigone, between the orifice of the ureters.

In the **female**, the urethra serves merely for the passage of urine. The mucous membrane consists of connective tissue with many elastic fibres, and provided with papillæ. It is covered by stratified epithelium and contains several mucous glands (*Littré*). Outside this is a layer of longitudinal, smooth, muscular fibres, and outside this again a layer of circular fibres. Many elastic fibres exist in all the layers, which are traversed by numerous wide venous channels.

The proper **sphincter urethræ** is a *transversely striped* muscle subject to the will, and consists of completely circular fibres which extend downward as far as the middle of the urethra, and partly of longitudinal fibres, which extend only on the posterior surface toward the base of the bladder, where they become lost between the fibres of the circular layer.

In the **male urethra**, the **epithelium** of the prostatic part is the same as that in the bladder; in the membranous portion it is stratified, and in the cavernous part the simple cylindrical form. The mucous membrane, under the epithelium itself, is beset with *papillæ*, chiefly in the posterior part of the urethra, and contains the mucous glands of Littrè.

Non-striped muscle occurs in the prostatic part arranged longitudinally, chiefly at the colli[illegible]

seminalis; in the membranous portion the direction of the fibres is chiefly circular, with a few longitudinal fibres intercalated; the cavernous part has a few circular fibres posteriorly, but anteriorly the muscular fibres are single and placed obliquely and longitudinally.

Closure of the Bladder.—The so-called internal vesical sphincter of the anatomists, which consists of non-striped muscle, is in reality an integral part of the muscular coat of the bladder and surrounds the orifice of the urethra as far down as the prostatic portion, just above the colliculus seminalis. It is, however, not the sphincter muscle. The proper **sphincter urethræ** (sph. vesicæ externus) lies below the latter. It is a completely circular muscle disposed around the urethra, close above the entrance of the urethra into the septum urogenitale at the apex of the prostate, where it exchanges fibres with the deep transverse muscle of the perineum which lies under it.

Some longitudinal fibres, which run along the upper margin of the prostate from the bladder, belong to this sphincter muscle. Single transverse bundles passing forward from the surface of the neck of the bladder, the transverse bands which lie within the prostate, the apex of the colliculus seminalis, and a strong transverse bundle passing in front of the origin of the urethra into the substance of the prostate—all belong to the sphincter muscle (*Henle*). In the male urethra, the *blood vessels* form a rich capillary plexus under the epithelium, below which is a wide-meshed *lymphatic* plexus.

[**Tonus of Sphincter Urethræ.**—Open the abdomen of a rabbit, ligature one ureter, tie a cannula in the other, and pour water into the bladder until it runs out through the urethra, which is usually under a pressure of 16 to 20 inches. If the spinal cord be divided between the fifth and seventh lumbar vertebræ, a column of 6 inches is sufficient to overcome the resistance of the sphincter, while section at the fourth lumbar vertebra has no effect on the height of the pressure. In such an animal the bladder becomes distended, but in one with its cord divided between the fifth and seventh lumbar vertebræ, there is incontinence of urine—in the former case because the excito-motor impulses are cut off from the centre (5 to 7 vert.), and in the latter because the tonus of the sphincter is destroyed (*Kupressow*). This tonus is denied by Landois and others.]

280. ACCUMULATION OF URINE—MICTURITION.—After emptying the bladder, the urine slowly collects again, the bladder being thereby gradually distended. [A healthy bladder may be said to be full when it contains 20 oz.] As long as there is a moderate amount of urine in the bladder, the elasticity of the elastic fibres surrounding the urethra, and that of the sphincter of the urethra (and in the male of the prostate), suffice to retain the urine in the bladder. This is shown by the fact that the urine does not escape from the bladder after death. If the bladder be greatly distended (1.5 to 1.8 litre), so that its apex projects above the pubes, the sensory nerves in its walls are stimulated and cause a feeling of a full bladder, while at the same time the urethral opening is dilated, so that a few drops of urine pass into the beginning of the urethra. Besides the subjective feeling of a full bladder, this tension of the walls of the bladder causes a *reflex* effect, so that the urinary bladder contracts periodically upon its fluid contents, and so do the sphincter of the urethra and the muscular fibres of the urethra, and thus the urethra is closed against the passage of these drops of urine. As long as the pressure within the bladder is not very high, the reflex activity of the transversely striped sphincter overcomes the other (as during sleep); but, as the pressure rises and the distention increases, the contraction of the walls of the bladder overcomes the closure produced by the sphincter, and the bladder is emptied, as occurs normally in young children.

As age advances, the sphincter urethræ comes under the control of the will, so that it can be contracted voluntarily, as occurs in man when he forcibly contracts the bulbo-cavernosus muscle to retain urine in the bladder. The sphincter ani usually contracts at the same time. The reflex activity of the sphincter may also be inhibited voluntarily, so that it may be completely relaxed. This is the condition when the bladder is emptied voluntarily.

Slight **movements**, confined to the bladder, occur during psychical or emotional disturbances (*e.g.*, anger, fear), [the bladder may be emptied involuntarily during a fright], after stimulation of sensory nerves, auditory impressions, restraining the respiration, and by arrest of the heart's action. There are slight periodic variations coincident with variations in the blood pressure. The contractions of the bladder cease after deep inspiration, and also during apnœa (*Mosso and Pellacani*). The excised

bladder of the frog, and even portions free from ganglia, exhibit rhythmical contractions, which are increased by heat (*Pfalz*). [Ashdown found in dogs that the bladder exhibits regular rhythmical contractions, which were influenced by the degree of distention of the bladder, being most marked with moderate dilatation and least when the bladder was feebly or over-distended. The contractions could be registered by means of a water manometer communicating with the interior of the bladder.]

Nerves.—The nerves concerned in the retention and evacuation of the urine are: 1. The **motor** nerves of the sphincter urethræ, which lie in the pudendal nerve (anterior roots of the third and fourth sacral nerves). When these nerves are divided, as soon as the bladder becomes so distended as to dilate the urethral opening, the urine begins to trickle away (incontinence of urine). 2. The **sensory** nerves of the urethra, which excite these reflexes, leave the spinal cord by the posterior roots of the third, fourth and fifth sacral nerves. Section of these nerves causes incontinence of urine. The **centre** in dogs lies opposite the fifth, and in rabbits, opposite the seventh lumbar vertebra (*Budge*). 3. Fibres pass from the cerebrum —those that convey voluntary impulses through the peduncles, and the anterior columns of the spinal cord (according to Mosso and Pellacani, through the posterior columns and the posterior part of the lateral columns), to the motor fibres of the sphincter urethræ. 4. The **inhibitory fibres** concerned in the reflex inhibition of the sphincter urethræ, take the same course (perhaps from the optic thalamus?) downward through the cord to where the third, fourth, and fifth sacral nerves leave it. 5. Sensory nerves proceed from the urethra and bladder to the brain, but their course is not known. Some of the motor and sensory fibres lie for a part of their course in the sympathetic.

Transverse section of the spinal cord above where the nerves leave it, is always followed in the first instance by retention of urine, so that the bladder becomes distended. This occurs because (1) the section of the spinal cord increases the reflex activity of the urethral sphincter; and (2), because the inhibition of this reflex can no longer take place. As soon, however, as the bladder becomes so distended, as in a purely mechanical manner to cause dilatation of the urethral orifice, then the urine trickles away, but the amount of urine which trickles out in drops is small. Thus the bladder becomes more and more distended, as the continuously distended walls of the organ yield to the increased tension, so that the bladder may become distended to an enormous extent. The urine very frequently becomes ammoniacal, accompanied by catarrh and inflammation of the bladder (§ 263).

Voluntary Micturition.—Observers are not agreed as to the mechanism concerned in emptying the bladder when it is only partially full. It is stated by some that a voluntary impulse passes from the brain along a cerebral peduncle, and the cord, to the anterior roots of the 3d and 4th sacral nerves, and partly through motor fibres from the 2d to the 5th lumbar nerves (especially the 3d), to act directly upon the smooth muscular fibres of the bladder. This is assumed, because electrical stimulation of any part of this nervous channel causes contraction of the bladder. This view, however, does not seem to be the true one. It is to be remembered that Budge showed that the sensory nerves of the wall of the bladder are contained in the first, second, third, and fourth sacral nerves, and also in part in the course of the hypogastric plexus, whence they ultimately pass by the rami communicantes into the spinal cord.

According to Landois, the smooth musculature of the bladder cannot be excited directly by a voluntary impulse, but it is always caused to contract reflexly. If we wish to micturate when the urinary bladder contains a small quantity of urine, we first excite the sensory nerves of the opening of the urethra, either by causing contraction or relaxation of the sphincter urethræ, or by means of slight abdominal pressure, and thus force a little urine into the urethral orifice. This sensory stimulation causes a reflex contraction of the walls of the urinary bladder. At the same time, this condition is maintained voluntarily, by the action of the intra-cranial

reflex-inhibitory centre of the sphincter urethræ. The **centre** for the reflex stimulation of the movements of the *walls of the urinary bladder* is placed somewhat higher in the spinal cord than that for the sphincter urethræ. In dogs, it is opposite the 4th lumbar vertebra (*Gianuzzi, Budge*).

[Two centres are assumed to exist in the cord, Fig. 293, one the automatic (A.C.) at the segment corresponding to the 2d, 3d, and 4th sacral nerves, which maintains the tonic action of the sphincter; the other, a reflex centre (R. C.), is situated higher, and through it the detrusor urinæ is excited to contraction. Both centres are connected to and governed or controlled by a cerebral centre (C.). The automatic centre is connected with the sphincter, and the other with the urine-expelling fibres. They are also connected with afferent fibres from the bladder and elsewhere. The afferent or sensory fibres are also connected with the brain. The automatice centre maintains the closure of the bladder, but if the latter be distended, different impulses proceeding from it reach the spinal centre, and it may be the cerebrum. The impulses reaching the automatic centre inhibit its action and those to the reflex centre excite it, so that the detrusor urinæ contracts. If the afferent impulses be powerful, a desire to urinate is excited, and voluntary impulses are excited which act upon the spinal centres as the afferent impulses do, and thus the act of urination is more easily accomplished.]

We may conceive a voluntary impulse to pass down special fibres to an inhibitory centre, which may either act directly on the motor centre, or possibly may send branches directly to the sphincter muscles.

Painful stimulation of sensory nerves causes reflex contraction of the bladder and evacuation of the urine (in children during teething). Reflex contraction of the bladder can be brought about in cats, by stimulation of the inferior mesenteric ganglion. After section of all the nerves going to the bladder, hemorrhage and asphyxia cause contraction by a direct effect upon the structures in the wall of the bladder. As yet no one has succeeded in exciting artificially the inhibitory centre in the brain for the sphincter muscle (*Sokowin and Kowalesky*).

It seems probable that, as in the case of the anal sphincter (§ 160), there is not a *continuous tonic* reflex stimulation of the sphincter urethræ; the reflex is excited each time by the contents. The sphincter vesicæ of the anatomists, which consists of smooth muscular tissue, does not seem to take part in closing the bladder. Budge and Landois found that, after removal of the transversely striped sphincter urethræ, stimulation of the smooth sphincter did not cause occlusion of the bladder, nor could L. Rosenthal or v. Wittich convince themselves of the presence of tonus in this muscle. Indeed, its very existence is questioned by Henle.

FIG. 292.



Scheme of micturition: A.C., R.C., C., automatic, reflex, and cerebral centres; B, bladder; S., sensory centre acted on by afferent impulses.

Changes of the Urine in the Bladder.—When the urine is retained in the bladder for a considerable time, according to Kaupp, there is an increase in the sodium chloride and a decrease in the urea and water. Urine which remains for a long time in the bladder is prone to undergo ammoniacal decomposition.

Absorption.—Many observers have shown that the mucous membrane of the bladder is capable of absorbing substances—potassium iodide and other soluble salts. [Ashdown has shown that poisons, such as watery solutions of strychnin, curare, eserin, emulsions of chloroform and ether, are absorbed when injected into the bladder of rabbits. In rabbits, KI injected into the bladder through a catether was found in the urine obtained from the divided ureters. Water and urea are also absorbed—the latter in larger proportion than the former.]

As the ureters enter near the base of the bladder, the last secreted urine is always lowest. If a person remain perfectly quiet, strata of urine are thus formed, and the urine may be voided so as to prove this (*Ealefsen*).

The **pressure within the bladder,** when in the supine position = 13 to 15 centimetres of water. Increase of the intra-abdominal pressure (by inspiration, forced expiration, coughing, bearing-down) increases the pressure within the bladder. The erect posture also increases it, owing to the pressure of the viscera from above (*Schatz, Dubois*). [James obtained 4 to 4.5 inches Hg as the highest expulsive power of the bladder including the abdominal pressure, voluntary and involuntary. In paraplegia, where there is merely the expulsive power of the bladder, he found 20 to 30 inches of water.]

[**Hydronephrosis** occurs when the ureters and pelvis of the kidney become dilated, owing to partial and gradual obstruction of the outflow of urine from the ureters: if the obstruction become complete, there is cessation of the urinary secretion. James has shown that the bladder remains contracted for several seconds after it is emptied, and this is specially

the case in irritable bladder; so that this condition may also give rise to hydronephrosis by damming up the urine in the ureters.]

Rapidity of Micturition.—The amount of urine voided at first is small, but it increases with the time, and toward the end of the act it again diminishes. In men, the last drops of urine are ejected from the urethra by voluntary contractions of the bulbo-cavernosus muscle. Adult dogs increase the stream rhythmically by the action of this muscle.

281. **RETENTION AND INCONTINENCE OF URINE.**—**Retention of urine or ischuria** occurs: 1. When there is obstruction of the urethra, from foreign bodies, concretions, stricture, swelling of the prostate. 2. Paralysis or exhaustion of the musculature of the bladder; the latter sometimes occurs after delivery, in consequence of the pres ure of the child against the bladder. 3. After section of the spinal cord (p. 484). 4. Where the voluntary impulses are unable to act upon the inhibitory apparatus of the sphincter urethræ reflex, as well as when the sphincter urethræ reflex is increased.

Incontinence of urine (stillicidium urinæ) occurs in consequence of—1. Paralysis of the sphincter urethræ. 2. Loss of sensibility of the urethra, which of course abolishes the reflex of the sphincter. 3. Trickling of the urine is a secondary consequence of section of the spinal cord, or of its degeneration.

Strangury is an excessive reflex contraction of the walls of the bladder and sphincter, due to stimulation of the bladder and urethra; it is observed in inflammation, neuralgia [and after the use of some poisons, *e. g.*, cantharides].

Enuresis nocturna, or involuntary emptying of the bladder at night, may be due to an increased reflex excitability of the wall of the bladder, or weakness of the sphincter.

282. **COMPARATIVE AND HISTORICAL.**—Among **vertebrates,** the urinary and genital organs are frequently combined, except in the osseous fishes. The Wolffian bodies which act as organs of excretion during the embryonic period, remain throughout life in fishes and amphibians and continue to act as such. **Fishes.**—The *myxinoids* (cyclostomata) have the simplest kidneys; on each side is a long ureter with a series of short-stalked glomeruli with capsules arranged along it. Both ureters open at the genital pore. In the other fishes, the kidneys lie often as elongated compact masses along both sides of the vertebral column. The two ureters unite to form a urethra, which always opens behind the anus, either united with the opening of the genital organs, or behind this. In the sturgeon and hag-fish, the anus and orifice of the urethra together form a cloaca. Bladder-like formations, which, however, are morphologically homologous with the urinary bladder of mammals, occur in fishes, either on each ureter (ray, hag-fish), or where both join. In **amphibians,** the vasa efferentia of the testicles are united with the urinary tubules; the duct in the frog unites with the one on the other side, and both conjoined opens into the cloaca, while the capacious *urinary bladder* opens through the anterior wall of the cloaca. From **reptiles** upward, the kidney is no longer a persistent Wolffian body, but a new organ. In reptiles, it is usually flattened and elongated; the ureters open singly into the cloaca. Saurians and tortoises have a urinary bladder. In **birds,** the isolated ureters open into the uro-genital sinus, which opens into the cloaca, internal to the excretory ducts of the genital apparatus. The urinary bladder is always absent. In **mammals,** the kidneys often consist of many lobules, *e. g.*, dolphin, ox.

Among **invertebrates,** the **mollusca** have excretory organs in the form of canals, which are provided with an outer and an inner opening. In the mussel, this canal is provided with a sponge-like organ, often with a central cavity, and consisting of ciliated secretory cells, placed at the base of the gills (organ of Bojanus). In gasteropods, with analogous organs, uric acid has been found. **Insects, spiders,** and **centipedes** have the so-called Malpighian vessels, which are excretory organs, partly for uric acid and partly for bile. These vessels are long tubes, which open into the first part of the large intestine. In crabs, blind tubes connected with the intestinal tube, perhaps have the same functions. The **vermes** also have renal organs.

Historical.—Aristotle directed attention to the relatively large size of the human bladder—he named the ureters. Massa (1552) found lymphatics in the kidney. Eustachius († 1580) ligatured the ureters and found the bladder empty. Cusanus (1565) investigated the color and weight of the urine. Rousset (1581) described the muscular nature of the walls of the bladder. Vesling described the trigone (1753). The first important **chemical** investigations on the urine date from the time of van Helmont (1644). He isolated the solids of the urine and found among them common salt; he ascertained the higher specific gravity of fever urine, and ascribed the origin of urinary calculi to the solids of the urine. Scheele (1766) discovered uric acid and calcium phosphate; Arand and Kunckel, phosphorus; Rouelle (1773), urea; and it got its name from Fourcroy and Vauquelin (1799). Berzelius found lactic acid; Seguin, albumin in pathological urine; Liebig, hippuric acid; Heintz and v. Pettenkofer, kreatin and kreatinin; Wollaston (1810), cystin. Marcet found xanthin; and Lindbergson, magnesic carbonate.

FUNCTIONS OF THE SKIN.

283. STRUCTURE OF THE SKIN, HAIRS, AND NAIL.—The **skin** (3.3 to 2.7 mm. thick; specific gravity, 1057) consists of—

[1. The **epidermis**;

2. The **chorium**, or **cutis vera**, with the papillæ (Fig. 294).]

The **epidermis** (0.08 to 0.12 mm. thick) consists of many layers of stratified epithelial cells united to each other by cement substance (Figs. 293, 294). The superficial layers—**stratum corneum**—consist of several layers of dry, horny, non-nucleated squames, which swell up in solution of caustic soda (Fig. 294, E). [It is always thickest where intermittent pressure is applied, as on the sole of the foot and palm of the hand.] The next layer is the **stratum lucidum**, which is clear and transparent in a section of skin, hence the name, and consists of compact layers of clear cells with vestiges of nuclei. Under this is the **rete mucosum** or rete Malpighii (Fig. 294, *d*), consisting of many layers of nucleated protoplasmic epithelial cells which contain pigment in the dark races, and in the skin of the scrotum, and around the anus. [The superficial cells are more fusiform and contain granules which stain deeply with carmine. They constitute, 3, the **stratum granulosum**. In these cells the formation of keratin is about to begin, and the granules have been called **eleidin** granules by Ranvier. They are chemically on the way to be transformed into keratin. All corneous structures contain similar granules in the area where the cells are becoming corneous. Then follow several layers of more or less polyhedral cells, softer and more plastic in their nature, and exhibiting the characters of so-called "**prickle cells**" (Fig. 294, R). [The spaces between the fibrils connecting adjacent cells are lymph spaces.] The deepest layers of cells are more or less columnar, and the cells are placed vertically upon the papillæ. Granular **leucocytes** or wandering cells are sometimes found between these cells. This, the fourth layer, has been called the **stratum Malpighii**. The rete Malpighii dips down between adjacent papillæ and forms interpapillary processes. According to Klein, a delicate **basement membrane** separates the epidermis from the true skin.] The superficial layers of the epidermis are continually being thrown off, while new cells are continually being formed in the deeper layers of the skin by proliferation of the cells of the rete Malpighii. There is a gradual change in the microscopic and chemical characters of the cells from the deepest to the superficial layers of the epidermis. [In a vertical section of the skin **stained with picro-carmine**, the S. granulosum is deeply stained red, and is thus readily distinguished among the other layers of the epidermis.]

FIG. 293.



Vertical section of the human epidermis: the nerve fibrils, *n*, *b*, stained with gold chloride.

[Epidermis (Fig. 293), { (1) *Stratum corneum*, (2) *Stratum lucidum*, } Cuticle. { (3) *Stratum granulosum*, (4) *Stratum Malpighii*, } Rete Mucosum.]

No **pigment** is formed within the epidermis itself; when it is present, it is carried by leucocytes from the subcutaneous tissue (*Riehl, Ehrmann, Aeby*). This explains how it is that a piece of white skin, transplanted to a negro, becomes black (*Karg*).

The **chorium** (Fig. 294, I, C) is beset over its entire surface by numerous (0.5 to 0.1 mm. high) **papillæ** (Fig. 294), the largest being upon the volar surface of the hand and foot, on the nipple and glans penis. Most of the papillæ contain a looped **capillary** (*g*), while in certain regions some of them contain a **touch corpuscle** (Fig. 295, *a*). The papillæ are disposed in groups, whose

FIG. 294.



I, Vertical section of the skin, with a hair and sebaceous gland, T. Epidermis and chorium shortened—1, outer, 2, inner fibrous layer of the hair follicle; 3, its hyaline layer; 4, outer root sheath; 5, Huxley's layer of the inner root sheath; 6, Henle's layer of the same; *p*, root of the hair, with its papilla; A, arrector pili muscle; C, chorium; *a*, subcutaneous fatty tissue; *b*, epidermis (horny layer); *d*, rete Malpighii; *g*, blood vessels of papillæ; *v*, lymphatics of the same; *h*, horny or corneous substance; *i*, medulla or pith; *k*, epidermis or cuticle of hair; K, coil of sweat gland; E, epidermal scales (seen from above and *en face*) from the stratum corneum; R, prickle cells from the rete Malpighii; *n*, superficial, and *m*, deep cells from the nail; H, hair magnified: *c*, cuticle; *c*, medulla, with cells; *f*, *f*, fusiform fibrous cells of the substance of the hair; *x*, cells of Huxley's layer; *l*, those of Henle's layer; S, transverse section of a sweat gland from the axilla; *a*, smooth muscular fibres surrounding it; *t*, cells from a sebaceous gland, some of them containing granules of oil.

arrangement varies in different parts of the body. In the palm of the hand and sole of the foot they occur in rows, which are marked out by the existence of delicate furrows on the surface visible to the naked eye. The chorium consists of a dense network of bundles of white fibrous tissue mixed with a network of **elastic fibres**, which are more delicate in the papillæ. In silversmiths the elastic fibres are blackened by the partial deposition of reduced silver, and the same obtains in those who take silver nitrate in such quantity as to produce argyria. The connective tissue contains many connective-tissue corpuscles and numerous leucocytes. The deeper connective tissue layer

of the chorium gradually pass into the **subcutaneous tissue**, where they form a trabecular arrangement of bundles, leaving between them elongated rhomboidal spaces filled for the most part with groups of **fat cells** (Fig. 294, *a*, *a*). [In microscopic sections, after the action of alcohol, the fat cells not unfrequently contain crystals of **margarin**.] The long axis of the rhomb corresponds to the greater tension of the skin at that part (*C. Langer*). In some situations the subcutaneous tissue is devoid of fat [penis, eyelids]. In many situations, the skin is fixed by solid fibrous bands to subjacent structures, as fasciæ, ligaments or bones (tenacula cutis); in other parts, as over bony prominences, bursæ partially lined with endothelium and filled with synovia-like fluid, occur.

Smooth muscular fibres occur in the chorium in certain situations on extensor surfaces (*Neumann*); nipple, areola mammæ, prepuce, perinæum, and in special abundance in the tunica dartos of the scrotum.

[**Guanin in the Skin.**—The skin of many amphibians and reptiles contains brown or black pigment granules, and other granules of a white, silvery, or chalky appearance. Ewald and Krukenberg have shown that the latter consists of guanin, and that this substance is very widely diffused in the skin of fishes, amphibians, and reptiles. **Test:** Select a piece of skin from the belly of a frog; place it in a porcelain capsule as for the murexide test; add concentrated nitric acid, and heat to dryness, when a yellow residue is obtained; on adding a drop of caustic soda a red color is struck. The yellow residue gives no reaction with ammonia. If to the fluid more water be added, and it be then heated, distributed over the surface of the capsule, and cooled by blowing upon it, various shades of purple and violet are obtained.]

The **nails** (specific gravity 1.19) consist of numerous layers of solid, horny, homogeneous, epidermal, or nail cells, which may be isolated with a solution of caustic alkali, when they swell up and exhibit the remains of an elongated nucleus (Fig. 294, *n*, *m*). The whole under surface of the nail rests upon the **nail bed**; the lateral and posterior edges lie in a deep groove, the **nail groove** (Fig. 296, *e*). The chorium under the nail is covered throughout its entire extent by longitudinal rows of **papillæ** (Fig. 296, *d*). Above this there lies, as in the skin, many layers of prickle cells like those in the rete Malpighii (Fig. 294, *a*), and above this again is the substance of the nail (Fig. 296, *a*). [The stratum granulosum is rudimentary in the nail bed. The substance of the nail represents the stratum lucidum, there being no stratum corneum (*Klein*).] The posterior part of the nail groove and the half moon, brighter part or **lunule**, form the *root* of the nail. They are, at the same time, the **matrix**, from which growth of the nail takes place. The lunule is present in an isolated nail, and is due to diminished transparency of the posterior part of the nail, owing to the special thickness and uniform distribution of the cells of the rete Malpighii (*Toldt*).

FIG. 295.

Papillæ of the skin, epidermis removed, blood vessels injected; some contain a Wagner's touch corpuscle, *a*, the others a capillary loop.

FIG. 296.

Transverse section of one-half of a nail. *a*, nail substance; *b*, more open layer of cells of the nail bed; *c*, stratum Malpighii of the nail bed; *d*, transversely divided papillæ; *e*, nail groove; *f*, horny layer of *e* projecting over the nail; *g*, papillæ of the skin on the back of the finger.

Growth of the Nail.—According to Unna, the matrix extends to the front part of the lunule. The nail grows continually from behind forward, and is formed by layers secreted or formed by the

matrix. These layers run parallel to the surface of the matrix. They run obliquely from above and behind, downward and forward, through the thickness of the substance of the nail. The nail is of the same thickness from the anterior margin of the lunule forward to its free margin. Thus the nail does not grow in thickness in this region. In the course of a year the fingers produce about 2 grms. of nail substance, and relatively more in summer than in winter.

Development—1. From the second to the eighth month of fœtal life, the position of the nail is indicated by a partial but marked horny condition of the epidermis on the back of the first phalanx, the "**eponychium.**" The remainder of this substance is represented during life by the normally formed epidermal layer, which separates the future nail from the surface of the furrow. 2. The future nail is formed under the eponychium, with its first nail cells still in front of the nail groove; then the nail grows and pushes forward toward the groove. At the seventh month, the nail (itself covered by the eponychium) covers the whole extent of the nail bed. 3. When, at a later period, the eponychium splits off, the nail is uncovered. After birth the papillæ are formed on the bed of the nail, while simultaneously the matrix passes backward to the most posterior part of the groove (*Unna*).

Absence of Hairs.—The whole of the skin, with the exception of the palmar surface of the hand, sole of the foot, dorsal surface of the third phalanx of the fingers and toes, outer surface of the eyelids, glans penis, inner surface of the prepuce, and part of the labia is covered with hairs, which may be strong or fine (lanugo).

A Hair (specific gravity 1.26) is fixed by its lower extremity (root) in a depression of the skin or a **hair follicle** (Fig. 294, I, *p*) which passes obliquely through the thickness of the skin, sometimes as far as the subcutaneous tissue. The structure of a hair follicle is the following: 1. The **outer fibrous layer** (Figs. 294, 1, 293), composed of interwoven bundles of connective tissue, arranged for the most part longitudinally, and provided with numerous blood vessels and nerves. [It is just the connective tissue of the surrounding chorium.] 2. The **inner fibrous layer** (Figs. 294, 2, 297) consists of a layer of fusiform cells (? smooth muscular fibres) arranged circularly. [It does not extend throughout the whole length of the follicle.] 3. Inside this layer is a transparent, hyaline, glass-like **basement membrane** (Figs. 292, 3, 297), which ends at the neck of the hair follicle; while above it is continued as the basement membrane which exists between the epidermis and chorium. In addition to these coverings, a hair follicle has epithelial coverings which must be regarded in relation to the layers of the epidermis. Immediately within the glass-like membrane is the **outer root sheath** (Figs. 294, 4, 297, 298), which consists of so many layers of epithelial cells that it forms a conspicuous covering. It is, in fact, a direct continuation of the stratum Malpighii, and consists of many layers of soft cells, the cells of the outer layer being cylindrical. Toward the base of the hair follicle it becomes narrower, and is united to, and continues with the cells of the root of the hair itself, at least in fully developed hairs. The horny layer of the epidermis continues to retain its properties as far down as the orifice of the sebaceous follicle; below this point, however, it is continued as the **inner root sheath.** This consists of (1) a single layer of elongated, flat, homogeneous, non-nucleated cells (Figs. 294, 6, 297, *f—Henle's layer*) placed next and within the outer root sheath. Within this lies (2) *Huxley's layer* (Figs. 294, 5, 297, *g*), consisting of nucleated elongated polygonal cells (Fig. 294, *x*, and 3), while the *cuticle* of the hair follicle is composed of cells analogous to those of the surface of the hair itself. Toward the bulb of the hair these three layers become fused together.

FIG. 297.



Transverse section of a hair and its follicle. *a*, outer fibrous coat with *b*, blood vessels; *c*, inner circularly disposed layer; *d*, glass-like layer; *e*, outer, *f*, *g*, inner, root sheath; *f*, outer layer of the same (Henle's sheath); *g*, inner layer of the same (Huxley's sheath); *h*, cuticle; *l*, hair.

[**Coverings of a hair follicle** arranged from without inward—

1. Fibrous layers, { (*a*) Longitudinally arranged fibrous tissue. (*b*) Circularly arranged spindle cells.
2. Glass-like (hyaline) membrane.
3. Epithelial layers, { (*a*) Outer root sheath. (*b*) Inner root sheath. { Henle's layer. Huxley's layer. (*c*) Cuticle of the hair.
4. The hair itself.]

The **arrector pili muscle** (Fig. 294, A) is a fan-like arrangement of a layer of smooth muscular fibres, attached below to the side of a hair follicle and extending toward the surface of the chorium; as it stretches obliquely upward, it subtends the obtuse angle formed by the hair follicle and the surface of the skin [or, in other words, it forms an acute angle with the hair follicle, and between it and the

follicle lies the **sebaceous gland**]. When these muscles contract, they raise and erect the hair follicles, producing the condition of **cutis anserina** or *gooseskin*. As the sebaceous gland lies in the angle between the muscle and the hair follicle, contraction of the muscle compresses the gland and favors the evacuation of the sebaceous secretion. It also compresses the blood vessels of the papilla (*Unna*).

The **hair** with its large bulbous extremity—**hair bulb**—sits upon or rather embraces, the **papilla**. It consists of (1) the *marrow* or **medulla** (Fig. 294, *i*), which is absent in woolly hair and in the hairs formed during the first year of life. It is composed of two or three rows of cubical cells (H, *c*). (2) Outside this lies the thicker **cortex** (*k*), which consists of elongated, rigid, horny, fibrous cells (H, *f*, *f*), while in and between these cells lie the pigment granules of the hair. (3) The surface of the hair is covered with a **cuticle** (*k*), and consists of imbricated layers of non-nucleated squames.

FIG. 298.



Section of a hair follicle while a hair is being shed. *a*, outer and middle sheaths of hair follicle; *b*, hyaline membrane; *c*, papilla, with a capillary; *d*, outer, *e*, inner root sheath; *f*, cuticle of the latter; *g*, cuticle of the hair; *h*, young non-medullated hair; *i*, tip of new hair; *l*, hair knob of the shed hair, with *k*, the remainder of the cast-off outer root sheath.

Gray Hair.—When the hair becomes *gray*, as in old age, this is due to defective formation of pigment in the cortical part. The silvery appearance of white hair is increased when small air cavities are developed, especially in the medulla and to a less extent in the cortex, where they reflect the light. Landois records a case of the hair becoming *suddenly* gray, in a man whose hair became gray during a single night, in the course of an attack of delirium tremens. Numerous hair spaces were found throughout the entire marrow of the (blond) hairs, while the hair pigment still remained.

[**Blood Pigment in Hairs.**—The feelers of albino rabbits contain in some part of their substances blood pigment (*Sig. Mayer*).]

Development of Hair.—According to Kölliker, from the 12th to 13th week of intra-uterine life, solid finger like processes of the epidermis are pushed down into the chorium. The process becomes flask-shaped, while the central cells of the cylinder become elongated and form a conical body, arising, as it were, from the depth of the recess. It soon differentiates into an inner darker part, which becomes the hair, and a thinner, clearer layer covering the former, the inner rooth sheath. The outer cells, *i. e.*, those lying next the wall of the sac, form the outer root sheath. Outside this, again, the fibrous tissue of the chorium forms a rudimentary hair follicle, while one of the papillæ grows up against it, indents it, and becomes embraced by the bulb of the hair. This is the hair papilla, which contains a loop of blood vessels. The cells of the bulb of the hair proliferate rapidly, and thus the hair grows in length. The point of the hair is thereby gradually pushed upward, pierces the inner root sheath, and passes obliquely through the epidermis. The hairs appear upon the forehead at the 19th week; at the 23d to 25th week the lanugo hairs appear free, and they have a characteristic arrangement on different parts of the body.

Physical Properties.—Hair has very considerable **elasticity** (stretching to 0.33 of its length), considerable cohesion (carrying 3 to 5 lbs.), **resists putrefaction** for a long time, and is highly **hygroscopic.** The last property is also possessed by epidermal scales, as is proved by the pains that occur in old wounds and scars during damp weather.

Growth of a hair occurs by proliferation of the cells on the surface of the hair papilla, these cells representing the matrix of the hair. Layer after layer is formed, and gradually the hair is raised higher within its follicle.

Change of the Hair.—According to one view, when the hair has reached its full length, the process of formation on the surface of the hair papilla is interrupted; the root of the hair is raised from the papilla, becomes horny, remains almost devoid of pigment, and is gradually more and more lifted upward from the surface of the papilla, while its lower bulbous end becomes split up like a brush. The lower empty part of the hair follicle becomes smaller, while on the old papilla a new formation of a hair begins, the old hair at the same time falling out (*Unna*). According to Stieda, the old papilla disappears, while a new one is formed in the hair follicle, and from it the new hair is developed. According to Kölliker, again, both processes obtain.

284. THE GLANDS OF THE SKIN.—The **sebaceous glands** (Fig. 294, I, T) are simple acinous glands, which open by a duct into the hair follicles of large hairs near their upper part; in the case of small hairs, they may project from the duct of the gland (Fig. 299). In some situations, the ducts of the glands open free upon the surface, *e. g.*, the glands of labia minora, glans, prepuce (Tyson's glands), and the red margins of the lips. The largest glands occur in the nose and in the labia; they are absent only from the vola manus and planta pedis. The oblong alveoli of the gland consist of a basement membrane lined with small polyhedral nucleated granular secretory cells (Fig. 294, *t*). Within this are other polyhedral cells, whose substance contains numerous oil globules; the cells become more fatty as we proceed toward the centre of the alveolus. The cells lining the duct are continuous with those of the outer root sheath. The detritus formed by the fatty metamorphosis of the cells constitutes the **sebum** or sebaceous secretion. [If the "oil or coccygeal gland" of a duck be removed, it is found that, when the animal is submerged, it takes up between its feathers about the same amount of water as an intact duck; but it retains 2 to 2½ times as much water in its feathers (*Max Joseph*).]

The **sweat glands** (Fig. 294, I, *k*), sometimes called **sudoriparous** glands, consist of a long blind tube, whose lower end is arranged in the form of a coil placed in the areolar tissue under the skin, while the somewhat smaller upper end or excretory portion winds in a vertical, slightly wave-like manner, through the chorium, and in a corkscrew or **spiral manner** through the epidermis, where it opens with a free, somewhat trumpet-shaped, mouth. The glands are very numerous and large in the palm of the hand, sole of the foot, axilla, forehead, and around the nipple; few on the back of the trunk, and are absent on the glans, prepuce, and margin of the lips. The **circumanal** glands and the **ceruminous glands** of the external auditory meatus, and **Moll's glands**, which open into the hair follicles of the eyelashes, are modifications of the sweat glands.

FIG. 299.



Sebaceous gland, with a lanugo hair. *a*, granular epithelium; *b*, rete Malpighii continuous with *a*; *c*, fatty cells and free fat; *d*, acini; *e*, hair follicle, with a small hair, *f*.

Each gland tube consists of a basement membrane lined by cells; the **excretory** part or **sweat canal** of the tube is lined by *several* layers of cubical cells, whose surface is covered by a delicate cuticular layer, a small central lumen being left. Within the coil the structure is different. The first part of the coil resembles the above, but as the coil is the true **secretory part** of the gland, its structure differs from the sweat canal. This, the so-called *distal* portion of the tube, is lined by a *single* layer of moderately tall, clear, nucleated, cylindrical epithelium (Fig. 294, S), often containing oil globules. Smooth muscular fibres are arranged longitudinally along the tube in the large glands (Fig. 294, S, *a*). There is a distinct lumen present in the tube. As the duct passes through the epidermis, it winds its way between the epidermal cells without any independent membrane lining it (*Heynold*). A network of **capillaries** surrounds the coil. Before the arteries split up into capillaries, they form a true rete mirabile around the coil (*Brücke*). This is comparable to the glomerulus of the kidney, which may also be regarded as a rete mirabile. Numerous **nerves** pass to form a plexus, and terminate in the glands (*Tomsa*).

The **total number** of sweat glands is estimated by Krause at 2½ millions, which gives a secretory surface of nearly 1800 square metres. *These glands secrete sweat.* Nevertheless, an oily or fatty substance is often mixed with the sweat. In some animals (glands in the sole of the foot of the dog, and in birds) this oily secretion is very marked.

Numerous **lymphatics** occur in the cutis, some arise by a blind end, and others from loops within the papilla on a plane lower than the vascular capillary. [These open into more or less horizontal networks of tubular lymphatics in the cutis, and these again into the wide lymphatics of the subcutaneous tissue, which are well provided with valves.] Special lymphatic spaces are disposed in relation with the hair follicles and their glands (*Neumann*), [and also with the fat (*Klein*). The lymphatics of the skin are readily injected with Berlin blue by the puncture method].

The **blood vessels** of the skin are arranged in several systems. There is a superficial system, from which proceed the capillaries for the papillæ. There is a deeper system of vessels which supplies special blood vessels to (*a*) the fatty tissue; (*b*) the hair follicles, each of which has a special vascular arrangement of its own, and in connection with this each sebaceous gland receives a special artery; (*c*) an artery goes also to each coil of a sweat gland, where it forms a dense plexus of capillaries (*Tomsa*).

285. THE SKIN AS A PROTECTIVE COVERING.—The **subcutaneous fatty tissue** fills up the depressions between adjoining parts of the body and covers projecting parts, so that a more rounded appearance of the body is thereby obtained. It also acts as a soft elastic pad and protects delicate parts from external pressure (sole of the foot, palm of the hand), and it often surrounds and protects blood vessels, nerves, etc. It is a bad conductor of heat, and thus acts as one of the factors regulating the radiation of heat (§ 214, II, 4), and, therefore, the temperature of the body. The epidermis and cutis vera also act in the same manner (§ 212). Klug found that the heat conduction is less through the skin and subcutaneous fatty tissue than through the skin alone; the epidermis conducts heat less easily than the fat and the chorium.

The solid, elastic, easily movable cutis affords a good *protection against external, mechanical injuries;* while the dry, impermeable, horny epidermis, devoid of nerves and blood vessels, affords a further protection against the absorption of poisons, and at the same time it is capable of resisting, to a certain degree, thermal and even chemical actions. A thin layer of fatty matter protects the free surface of the epidermis from the macerating action of fluids, and from the disintegrating action of the air. The epidermis is important in connection with the *fluids of the body.* It exerts pressure upon the cutaneous capillaries, and, to a limited extent, prevents too great diffusion of fluid from the cutaneous vessels. Parts of the skin devoid of epidermis are red and always moist. When dry, the epidermis and the epidermal appendages are bad conductors of electricity (§ 326). Lastly, the existence of uninjured epidermis prevents adjoining parts from growing together.

As the epidermis is but slightly extensile it is stretched over the folds and papillæ of the cutis vera, which becomes level when the skin is stretched, and the papillæ may even disappear with strong tension (*Lewinski*).

286. CUTANEOUS RESPIRATION: SEBUM—SWEAT.—The skin, with a surface of more than 1½ square metre, has the following **secretory** functions:—

1. The **respiratory excretion;**
2. The **secretion of sebaceous matter;** and
3. The **secretion of sweat.**

[Besides this the skin is **protective,** contains **sense organs,** is largely concerned in **regulating the temperature,** and may be concerned in **absorption.**]

1. **Respiration by the skin** has been referred to (§ 131). The organs concerned are the tubes of the sweat glands, moistened as they are with fluids, and surrounded by a rich network of capillaries. It is uncertain whether or not the skin gives off a small amount of N or ammonia. Röhrig made experiments upon an arm placed in an air-tight metal box. According to him, the amount of CO_2 and H_2O excreted is subject to certain daily variations; it is **increased** by digestion, increased temperature of the surroundings, the application of cutaneous stimuli, and by impeding the pulmonary respiration. The exchange of gases also depends upon the vascularity of certain parts of the skin, while the cutaneous absorption of O also depends upon the number of colored corpuscles in the blood.

In **frogs** and other amphibians, with a thin, always moist epidermis, the cutaneous respiration is more considerable than in warm-blooded animals. In winter, in frogs, the skin alone yields ¾ of the total amount of CO_2 excreted; in summer, ⅔ of the same (*Bidder*); thus, in these animals it is a more important respiratory organ than the lungs themselves.

Suppression of the cutaneous activity by varnishing or dipping the skin in oil, causes death by asphyxia (frogs) sooner than ligature of the lungs. **Varnishing the Skin.**—When the skin of a warm-blooded animal is covered with an impermeable varnish [such as gelatin] (*Fourcault, Becquerel, Brechet*), death occurs after a time, probably owing to the loss of too much heat. The formation of crystalline ammonio-magnesic phosphate in the cutaneous tissue of such animals (*Edenhuizen*) is not sufficient to account for death, nor are congestion of internal organs and serous effusions satisfactory explanations. The retention of the volatile substances (acids) present in the sweat is not sufficient. Strong animals live longer than feeble ones; horses die after several days (*Gerlach*); they shiver and lose flesh. The larger the cutaneous suface left unvarnished, the later does death take place. Rabbits die when ⅓ of their surface is varnished. When the entire surface of the animal is varnished, the temperature rapidly ralls (to 19°), the pulse and respirations

vary; usually they fall when the varnishing process is limited; increased frequency of respiration has been observed (§ 225). Pigs, dogs, horses, when one-half of the body is varnished, exhibit only a temporary fall of the temperature, and show signs of weakness, but do not die (*Ellenberger and Hofmeister*). [In extensive **burns** of the skin, not only is there disintegration of the colored blood corpuscles (*v. Lesser*), but in some cases ulcers occur in the duodenum. The cause of the ulceration, however, has not been ascertained satisfactorily (*Curling*).]

2. Sebaceous Secretion.—The fatty matter as it is excreted from the acini of the sebaceous glands is fluid, but even within the excretory duct of the gland it stagnates and forms a white, fat-like mass, which may sometimes be expressed (at the side of the nose) as a worm-like white body, the so-called comedo. The sebaceous matter keeps the skin supple, and prevents the hair from becoming too dry. **Microscopically** the secretion is seen to contain innumerable fatty granules, a few gland cells filled with fat, visible after the addition of caustic soda, crystals of cholesterin, and in some men a microscopic, mite-like animal (**Demodex folliculorum**).

Chemical Composition.—The constituents are for the most part **fatty**; chiefly *olein* (fluid) and *palmitin* (solid) fat, soaps, and some cholesterin; a small amount of albumin and unknown extractives. Among the inorganic constituents, the insoluble earthy phosphates are most abundant; while the alkaline chlorides and phosphates are less abundant.

The **vernix caseosa** which covers the skin of a new-born child, is a greasy mixture of sebaceous matter and macerated epidermal cells (containing 47.5 per cent. fat). A similar product is the **smegma præputialis** (52.8 per cent. fat), in which an ammonia soap is present.

The **cerumen** or ear wax is a mixture of the secretions of the ceruminous glands of the ear (similar in structure to the sweat glands) and the sebaceous glands of the auditory canal. Besides the constituents of sebum, it contains yellow or brownish particles, a bitter, yellow extractive substance derived from the ceruminous glands, potash soaps, and a special fat. The secretion of the **Meibomian glands** is sebum.

[**Lanoline.**—Liebreich finds in feathers, hairs, wool, and keratin tissues generally, a cholesterin fat, which, however, is not a true fat, although it saponifies, but an ethereal compound of certain fatty acids with cholesterin. In commerce it is obtained from wool, and is known by the above name; it forms an admirable basis for ointments, and it is very readily absorbed by the skin.] Thus, the fat-like substance for protecting the epidermis is partly formed along with keratin in the epidermis itself.

3. The Sweat.—The sweat is secreted in the **coil** of the sweat glands. As long as the secretion is small in amount, the water secreted is evaporated at once from the skin along with the volatile constituents of sweat; as soon, however, as the secretion is increased, or evaporation is prevented, drops of sweat appear on the surface of the skin. The former is called **insensible perspiration**, and the latter **sensible perspiration.** [Broadly, the quantity is about 2 lbs. in twenty-four hours.]

The sensible perspiration varies greatly; as a rule, the right side of the body perspires more freely than the left. The palms of the hands secrete most, then follow the soles of the feet, cheek, breast, upper arm, and forearm (*Peiper*). It falls from morning to mid-day, and rises again toward evening, reaching its maximum before midnight. Much moisture and cold in the surrounding atmosphere diminish it, and so does diuresis. In children, the insensible perspiration is relatively great. The drinking of water favors it, alcohol diminishes it (*H. Schmid*).

Method.—Sweat is obtained from a man by placing him in a metallic vessel in a warm bath; the sweat is rapidly secreted and collected in the vessel. In this way Favre collected 2560 grammes of sweat in 1½ hour. An arm may be inclosed in a cylindrical vessel, which is fixed air tight round the arm with an elastic bandage (*Schottin*).

Among **animals**, the horse sweats, so does the ox, but to a less extent; the vola and planta of apes, cats, and the hedgehog secrete sweat; the snout of the pig sweats (?), while the goat, rabbit, rat, mouse, and dog are said not to sweat (*Luchsinger*). [The skin over the body and the pad on the dog's foot contain numerous sweat glands, which open free on the surface of the pad and into the hair follicles on the general surface of the skin (*W. Stirling*).]

Microscopically.—The sweat contains only a few epidermal scales accidentally mixed with it, and fine fatty granules from the sebaceous glands.

Chemical Composition.—Its reaction is **alkaline**, although it frequently is acid, owing to the admixture of fatty acids from decomposed sebum. During profuse secretion it becomes neutral, and lastly alkaline again (*Trümpy and Luchsinger*). The sweat is colorless, slightly turbid, of a saltish *taste*, and has a charac-

teristic odor varying in different parts of the body; the *odor* is due to the presence of volatile fatty acids. The constituents are *water*, which is increased by copious draughts of that fluid, and **solids**, which amount to 1.180 per cent. (0.70 to 2.66 per cent.—*Funke*), and of these 0.96 per cent. is organic and 0.33 inorganic. Among the *organic* constituents are *neutral fats* (palmitin, stearin), also present in the sweat of the palm of the hand, which contains no sebaceous glands, *cholesterin*, *volatile fatty acids* (chiefly formic, acetic, butyric, propionic, caproic, capric acids), varying qualitatively and quantitatively in different parts of the body. These acids are most abundant in the sweat first (acid) secreted. There are also traces of *albumin* (similar to casein) and *urea*, about 0.1 per cent. In uræmic conditions (anuria in cholera) urea has been found crystallized on the skin. When the secretion of sweat is greatly increased, the amount of urea in the urine is diminished, both in health and in uræmia (*Leube*). The nature of the reddish-yellow pigment, which is extracted from the residue of sweat by alcohol, and colored green by oxalic acid, is unknown. Among *inorganic* constituents, those that are easily soluble are more abundant than those that are soluble with difficulty, in the proportion of 17 to 1; sodium chloride, 0.2; potassium chloride, 0.2; sulphates, 0.01 per 1000, together with traces of earthy phosphates and sodium phosphate. Sweat contains CO_2 in a state of absorption and some N. When decomposed with free access of air, it yields ammonia salts (*Gorup-Besanez*).

Excretion of Substances.—Some substances when introduced into the body reappear in the sweat—benzoic, cinnamic, tartaric, and succinic acids are readily excreted; quinine and potassic iodide with more difficulty. Mercuric chloride, arsenious and arsenic acids, sodium and potassium arseniate have also been found. After taking arseniate of iron, arsenious acid has been found in the sweat, and iron in the urine. Mercury iodide reappears as a chloride in the sweat, while the iodine occurs in the saliva.

Formation of Pigments.—The leucocytes furnish the material, and the pigment is deposited in granules in the deeper layers, and, to a less extent, in the upper layers, of the rete Malpighii. This occurs in the folds around the anus, scrotum, nipple [especially during pregnancy], and everywhere in the colored races. There is a diffuse, whitish-yellow pigment in the stratum corneum, which becomes darker in old age. The pigmentation depends on chemical processes, reduction taking place, and these processes are aided by light. Granular pigment lies also in the layers of prickle cells. The dark coloration of the skin may be arrested by free O [hydric peroxide], while the corneous change is prevented at the same time (*Unna*).

Pathological.—To this belongs the formation of liver spots or **chloasma, freckles**, and the pigmentation of **Addison's disease** [pigmentation round old ulcers, etc.] (§ 103, IV). [The curious cases of pigmentation, especially in neurotic women *e.g.*, in the eyelids, deserve further study in relation to the part played by the nervous system in this process.]

287. INFLUENCE OF NERVES ON THE SECRETION OF SWEAT.—The secretion of the skin, which averages about $\frac{1}{67}$ of the body weight, *i. e.*, about double the amount of water excreted by the lungs, may be increased or diminished. The liability to perspire varies much in different individuals. The following conditions influence the secretion: 1. **Increased temperature** of the surroundings causes the skin to become red, while there is a profuse secretion of sweat (§ 214, II, 1). Cold, as well as a temperature of the skin about 50° C., arrests the secretion. 2. A very **watery condition of the blood,** *e.g.*, after copious draughts of warm water, increases the secretion. Increased **cardiac** and **vascular activity**, whereby the blood pressure within the cutaneous capillaries is increased, have a similar effect; increased sweating follows increased **muscular activity.** 3. Certain **drugs** favor sweating, *e. g.*, pilocarpin, Calabar bean, strychnin, picrotoxin, muscarin, nicotin, camphor, ammonia compounds; while others, as atropin and morphia, in large doses, diminish or paralyze the secretion. [Drugs which excite copious perspiration, so that it stands as beads of sweat on the skin, are called **sudorifics**, while those that excite the secretion gently are **dia-**

phoretics, the difference being one of degree. Those drugs which lessen the secretion are called **antihydrotics.**] 4. It is important to notice the *antagonism* which exists, probably upon mechanical grounds, between the secretion of sweat, the urinary secretion, and the evacuation of the intestine. Thus copious secretion of urine (*e. g.*, in diabetes) and watery stools coincide with dryness of the skin. If the secretion of sweat be increased, the percentage of salts, urea, and albumin is also increased, while the other organic substances are diminished. The more saturated the air is with watery vapor, the sooner does the secretion appear in drops upon the skin, while in dry air or air in motion, owing to the rapid evaporation, the formation of drops of sweat is prevented, or at least retarded. [The **complementary** relation between the **skin** and **kidneys** is well known. In summer, when the skin is active, the kidneys separate less **water**; in winter, when the skin is less active, it is cold and comparatively bloodless, while the kidneys excrete more water, so that the action of these two organs is in inverse ratio.]

The influence of nerves upon the secretion of sweat is very marked.

I. Just as in the secretion of saliva (§ 145), **vasomotor nerves** are usually in action at the same time as the proper **secretory nerves**; the **vaso-dilator** nerves (sweating with a *red congested* skin) are most frequently involved. The fact that secretion of sweat does occasionally take place when the skin is *pale* (fear, death agony) shows that, when the vasomotor nerves are excited, so as to constrict the cutaneous blood vessels, the sweat-secretory nerve fibres may also be active.

Under certain circumstances, the **amount of blood** in the skin seems to determine the occurrence of sweating; thus, Dupuy found that section of the cervical sympathetic caused secretion on that side of the neck of a horse; while Nitzelnadel found that percutaneous electrical stimulation of the cervical sympathetic in man, limited the sweating.

[We may draw a parallel between the secretion of **saliva** and that of **sweat.** Both are formed in glands derived from the outer layer of the embryo. Both secretions are formed from lymph supplied by the blood stream, and if the lymph be in sufficient quantity, secretion may take place when there is no **circulation**, although in both cases secretion is most lively when the circulation is most active and the secretory nerves of both are excited simultaneously; both glands have **secretory nerves** distinct from the nerves of the blood vessels; both glands may be paralyzed by the action of the nervous system, or in disease (fever), or conversely, both are paralyzed by **atropine** and excited by other drugs, *e. g.*, pilocarpin. In the gland cells of both, histological **changes** accompany the secretory act, and no doubt similar electromotor phenomena occur in both glands.]

II. **Secretory nerves**, altogether independent of the circulation, control the secretion of sweat. Stimulation of these nerves, even in a limb which has been amputated in a kitten, causes a temporary secretion of sweat, *i. e.*, after complete arrest of the circulation (*Goltz, Kendall and Luchsinger, Ostroumow*). In the intact condition of the body, however, profuse perspiration, at all events, is always associated with simultaneous dilatation of the blood vessels (just as, in stimulation of the facial nerve, an increased secretion of saliva is associated with an increased blood stream—§ 145, A, I). The secretory nerves and those for the blood vessels seem to lie in the same nerve trunks.

The secretory nerves for the **hind limbs** (cat) lie in the sciatic nerve. Luchsinger found that stimulation of the peripheral end of this nerve caused renewed secretion of sweat for a period of half an hour, provided the foot was always wiped to remove the sweat already formed. If a kitten, whose sciatic nerve is divided on one side, be placed in a chamber filled with heated air, all the three intact limbs soon begin to sweat, but the limb whose nerve is divided does not, nor does it do so when the veins of the limb are ligatured so as to produce congestion of its blood vessels. [The cat sweats only on the hairless soles of the feet.] As to the **course** of the secretory fibres to the sciatic nerve, some pass directly from the spinal cord (*Vulpian*), some pass into the abdominal sympathetic (*Luchsinger, Nawrocki, Ostroumow*), through the rami communicantes and the anterior spinal roots from the upper lumbar and lower dorsal spinal cord (9th to 13th dorsal vertebræ—cat), where the **sweat centre** for the lower limbs is situated.

The **sweat centre** may be excited **directly**: (1) By a highly venous condition of the blood, as during dyspnœa, *e. g.*, the secretion of sweat that sometimes precedes death; (2) by overheated blood (45° C.) streaming through the centre; (3) by certain poisons (see p. 495). The centre may be also excited **reflexly**, although the results are variable, *e. g.*, stimulation of the crural and peroneal nerves, as well as the central end of the opposite sciatic nerve, excites it. [The pungency of mustard in the mouth may excite free perspiration on the face.]

Anterior Extremity.—The secretory fibres lie in the ulnar and median nerves, for the fore limbs of the cat; most of them, or indeed all of them (*Nawrocki*), pass into the thoracic sympathetic (Ggl. stellatum), and part (?) run in the nerve roots direct from the spinal cord (*Luchsinger, Vulpian, Ott*). A similar **sweat centre** for the upper limbs lies in the lower part of the cervical spinal cord. Stimulation of the central ends of the brachial plexus causes a reflex secretion of sweat upon the foot of the other side (*Adamkiewicz*). At the same time the hind feet also perspire.

Pathological.—Degeneration of the motor ganglia of the anterior horns of the spinal cord causes loss of the secretion of sweat, in addition to paralysis of the voluntary muscles of the trunk. The perspiration is increased in paralyzed as well as in œdematous limbs. In nephritis, there are great variations in the amount of water given off by the skin.

Head.—The secretory fibres for this part (horse, man, snout of pig) lie in the thoracic sympathetic, pass into the ganglion stellatum, and ascend in the cervical sympathetic. Percutaneous electrical stimulation of the cervical sympathetic in man, causes sweating of that side of the face and of the arm (*M. Meyer*). In the cephalic portion of the sympathetic, some of the fibres pass into, or become applied to, the branches of the trigeminus, which explains why stimulation of the infra-orbital nerve causes secretion of sweat. Some fibres, however, arise *directly* from the roots of the trigeminus (*Luchsinger*), and the facial (*Vulpian, Adamkiewicz*). Undoubtedly the cerebrum has a direct effect either upon the vasomotor nerves (p. 496, I) or upon the sweat-secretory fibres (II), as in the sweating produced by psychical excitement (pain, fear, etc.).

Adamkiewicz and Senator found that, in a man suffering from abscess of the motor region of the cortex cerebri for the arm, there were spasms and perspiration in the arm.

Sweat Centre.—According to Adamkiewicz, the medulla oblongata contains the **dominating sweat centre** (§ 373). When this centre is stimulated in a cat, all the four feet sweat, even three-quarters of an hour after death (*Adamkiewicz*).

III. The nerve fibres which terminate in the *smooth muscular fibres of the sweat glands* act upon the **excretion** of the secretion.

[**Changes in the Cells during Secretion.**—In the resting glands of the horse, the cylindrical cells are clear with the nucleus near their attached ends, but after free perspiration they become granular, and their nucleus is more central (*Renaut*).]

If the sweat nerves be divided (cat), injection of pilocarpin causes a secretion of sweat, even at the end of three days. After a longer period than six days, there may be no secretion at all. This observation coincides with the phenomenon of dryness of the skin in paralyzed limbs. Dieffenbach found that transplanted portions of skin first began to sweat when their sensibility was restored. If a motor nerve (tibial, median, facial) of a man be stimulated, sweat appears on the skin over the muscular area supplied by the nerve, and also upon the corresponding area of the opposite non-stimulated side of the body. This result occurs when the circulation is arrested as well as when it is active. Sensory and thermal stimulation of the skin always cause a bilateral reflex secretion independently of the circulation. The area of sweating is independent of the part of the skin stimulated.

288. **PATHOLOGICAL VARIATIONS.**—1. **Anidrosis** or **diminution** of the secretion of sweat occurs in diabetes and the cancerous cachexia, and along with other disturbances of nutrition of the skin in some nervous diseases, *e. g.*, in dementia paralytica; in some limited regions of the skin, it has occurred in certain tropho-neuroses, *e. g.*, in unilateral atrophy of the face and in paralyzed parts. In many of these cases it depends upon paralysis of the corresponding nerves or their *spinal sweat centres*.

2. **Hyperidrosis,** or **increase** of the secretion of sweat, occurs in easily excitable persons, in consequence of the irritation of the nerves concerned (§ 288), *e. g.*, the sweating which occurs in debilitated conditions and in the hysterical (sometimes on the head and hands), and the so-called epileptoid sweats (*Eulenburg*). Sometimes the increase is confined to *one side of the head* (H. unilateralis). This condition is often accompanied with other nervous phenomena, partly with the symptoms of paralysis of the cervical sympathetic (redness of the face, narrow pupil), partly with symptoms of stimulation of the sympathetic (dilated pupil, exophthalmos). It may occur without these phenomena, and is due, perhaps, to stimulation of the proper secretory fibres alone. [Increased sweating is very marked in certain fevers, both during their course and at the crisis in some; while the sweat is not only copious but acid in acute rheumatism. The "night sweats" of phthisis are very marked and disagreeable.]

3. **Paridrosis** or **qualitative changes** in the secretion of sweat, *e. g.*, the rare case of "*sweating of blood*" (**hæmatohidrosis**), is sometimes unilateral. According to Hebra, in some cases this condition represents a vicarious form of menstruation. It is, however, usually one of many phenomena of nervous affections. Bloody sweat sometimes occurs in yellow fever. Bile pigments have been found in the sweat in jaundice; blue sweat from indigo (*Bizio*), from pyocyanin (the rare blue coloring matter of pus), or from phosphate of the oxide of iron (*Osc. Kollmann*) is extremely rare. Such colored sweats are called **chromidrosis.** Numerous **micro-organisms** (which, however, are innocuous) live between the epidermal scales and on the hairs, two varieties of Saccharomycetes; in cutaneous folds Leptothrix epidermalis, various Schizomycetes, and five kinds of Micrococci; and between the toes—Bacterium graveolens (*Bordoni-Uffreduzzi*), which causes the odor of the sweat of the feet. Microörganisms are also the cause of yellow, blue, and red sweat; the last is due to Micrococcus hæmatodes.

Grape sugar occurs in the sweat in diabetes mellitus; uric acid and cystin very rarely; and in the sweat of stinking feet, leucin, tyrosin, valerianic acid, and ammonia. Stinking sweat (**bromidrosis**) is due to the decomposition of the sweat, from the presence of a special microörganism (Bacterium fœtidum—*Thin*). In the sweating stage of ague butyrate of lime has been found, while in the sticky sweat of acute articular rheumatism there is more albumin (*Anselmino*), and the same is the case in artificial sweating (*Leube*); lactic acid is present in the sweat in puerperal fever.

The sebaceous secretion is sometimes increased, constituting **seborrhœa,** which may be local or general. It may be diminished (**Asteatosis cutis**). The sebaceous glands degenerate in old people, and hence the glancing of the skin (*Rémy*). If the ducts of the glands are occluded the sebum accumulates. Sometimes the duct is occluded by black particles or ultramarine (*Unna*) from the blue used in coloring the linen. When pressed out, the fatty worm-shaped secretion is called "**comedo.**"

289. **CUTANEOUS ABSORPTION—GALVANIC CONDUCTION.**—After long immersion in water the superficial layers of the epidermis become moist and swell up. The skin is unable to absorb any substances, either salts or vegetable poisons, from **watery solutions** of these. This is due to the fat normally present on the epidermis and in the pores of the skin. If the fat be removed from the skin by alcohol, ether, or chloroform, absorption may occur in a few minutes (*Parisot*). According to Röhrig, all **volatile** substances, *e. g.*, carbolic acid and others, which act upon and corrode the epidermis, are capable of absorption. While, according to Juhl, such watery solutions as impinge on the skin, in a finely divided spray, are also capable of absorption, which very probably takes place through the interstices of the epidermis.

[**Inunction.**—When ointments are **rubbed** into the skin so as to press the substance into the pores, absorption occurs, *e. g.*, potassium iodide in an ointment so rubbed in is absorbed; so is mercurial ointment. v. Voit found globules of mercury between the layers of the epidermis, and even in the chorium of a person who was executed, into whose skin mercurial ointment had been previously rubbed. The mercury globules, in cases of mercurial inunction, pass into the hair follicles and ducts of the glands, where they are affected by the secretion of the glands and transformed into a compound capable of absorption. An abraded or inflamed surface (*e. g.*, after a blister), where the epidermis is removed, absorbs very rapidly, just like the surface of a wound (**Endermic method**).]

[**Drugs** may be applied locally where the epidermis is intact—**epidermic method**—as when drugs which affect the sensory nerves of a part are painted over a painful area to diminish the pain. Another method, the **hypodermic,** now largely used, is that of injecting, by means of a hypodermic syringe, a non-corrosive, non-irritant drug, in solution, into the subcutaneous tissue, where it practically passes into the lymph spaces and comes into direct relation with the lymph and blood stream; absorption takes place with great rapidity, even more so than from the stomach.]

Gases.—Under normal conditions, minute traces of O are absorbed from the air; hydrocyanic acid, sulphuretted hydrogen—CO, CO_2, the vapor of chloroform and ether may be absorbed (*Chaussier, Gerlach, Röhrig*). In a bath containing sulphuretted hydrogen, this gas is absorbed, while CO_2 is given off into the water (*Röhrig*).

Absorption of watery solutions takes place rapidly through the skin of the **frog** (*Guttmann, W. Stirling, v. Wittich*). Even after the circulation is excluded and the central nervous system destroyed, much water is absorbed through the skin of the frog, but not to such an extent as when the circulation is intact (*Spina*).

Galvanic Conduction through the Skin.—If the two electrodes of a *constant* current be impregnated with a watery solution of certain substances and applied to the skin, and if the direction of the current be changed from time to time, strychnin may be caused to pass through the skin of a rabbit in a few minutes, and that in sufficient amount to kill the animal (*H. Munk*). In man, quinine and potassium iodide have been introduced into the body in this way, and their presence detected in the urine. This process is called the **cataphoric action** of the constant current (§ 328).

290. **COMPARATIVE—HISTORICAL.**—In all **vertebrates**, the skin consists of chorium and epidermis. In some **reptiles** the epidermis becomes horny, and forms large plates or scales. Similar structures occur in the edentata among mammals. The **epidermal appendages** assume various forms, such as hair, nail, spines, bristles, feathers, claws, hoof, horns, spurs, etc. The scales of some fishes are partly osseous structures. Many **glands** occur in the skin; in some amphibia they secrete mucus, in others the secretion is poisonous. Snakes and tortoises are devoid of cutaneous glands; in lizards the "leg glands" extend from the anus to the bend of the knee. In the crocodile, the glands open under the margins of the cutaneo-osseous scales. In **birds**, the cutaneous glands are absent; the "**coccygeal glands**" form an oily secretion for lubricating the feathers. [This is denied by O. Liebreich, as he finds no cholesterin fats in their secretion.] The *civet glands*, at the anus of the civet cat, the preputial glands of the musk deer, the glands of the hare, and the pedal glands of ruminants, are really greatly developed sebaceous glands. In some **invertebrata**, the skin, consisting of epidermis and chorium, is intimately united with the subjacent muscles, forming a musculo-cutaneous tube for the body of the animal. The cephalopoda have **chromatophores** in their skin, *i. e.*, round or irregular spaces filled with colored granules. Muscular fibres are arranged radially around these spaces, so that when these muscles contract the colored surface is increased. The change of color in these animals is due to the play or contraction of these muscles (*Brücke*). Special glands are concerned in the production of the shell of the snail. The **annulosa** are covered with a chitinous investment, which is continued for a certain distance along the digestive tract and the tracheæ. It is thrown off when the animal sheds its covering. It not only protects the animal, bu it forms a structure for the attachment of muscles. In echinodermata, the cutaneous covering contains calcareous masses; in the holothurians, the calcareous structures assume the form of calcareous spicules.

Historical.—Hippocrates (born 460 B. C.) and Theophrastus (born 371 B. C.) distinguished the perspiration from the sweat; and, according to the latter, the secretion of sweat stands in a certain antagonistic relation to the urinary secretion and to the water in the fæces. According to Cassius Felix (97 A.D.), a person placed in a bath absorbs water through the skin; Sanctorius (1614) measured the amount of sweat given off; Alberti (1581) was acquainted with the hair bulb; Donatus (1588) described hair becoming gray suddenly; Riolan (1626) showed that the color of the skin of the negro was due to the epidermis.

PHYSIOLOGY OF THE MOTOR APPARATUS.

291. [**CILIARY MOTION—PIGMENT CELLS.**]—[(*a*) **Muscular Movement.**—By far the greatest number of the movements occurring in our bodies is accomplished through the agency of **muscular fibre**, which, when it is excited by a stimulus, contracts, *i. e.*, it forcibly shortens, and thus brings its two ends nearer together, while it bulges to a corresponding extent laterally. In muscle, the contraction takes place in a **definite direction.**]

[(*b*) **Amœboid Movement.**—Motion is also exhibited by colorless blood corpuscles, lymph corpuscles, leucocytes, and some other corpuscles. In these structures we have examples of amœboid movement (§ 9), which is movement in an **indefinite direction.**]

[(*c*) **Ciliary Movement.**—There is also a peculiar form of movement, known as *ciliary movement*. There is a gradual transition between these different forms of movement. The **cilia** which are attached to the ciliated epithelium are the motor agents (Fig. 300).]

[**Ciliated epithelium—where found.**—In the nasal mucous membrane, except the olfactory region; the cavities accessory to the nose; the upper half of the pharynx, Eustachian tube, larynx, trachea, and bronchi; in the uterus, except the lower half of the cervix; Fallopian tubes; vasa efferentia to the lower end of epididymis; ventricles of brain (child); and the central canal of the spinal cord.]

FIG. 300.

Ciliated Epithelium.

[The **cilia** are flattened, blade-like or hair-like appendages attached to the free end of the cells. They are about $\frac{1}{3000}$ inch in length, and are apparently homogeneous and structureless. They are planted upon a clear, non-contractile **disk** on the free end of the cell, and some observers state that they pass through the disk to become continuous with the protoplasm of the cell, or with the plexus of fibrils which pervades the protoplasm, so that by some observers they are regarded as prolongations of the intra-epithelial plexus of fibrils. They are specially modified parts of an epithelial cell, and are contractile and elastic. They are colorless, tolerably strong, not colored by staining reagents, and are possessed of considerable rigidity and flexibility. They are always connected with the protoplasm of cells, and are never outgrowths of the solid cell membranes. There may be ten to twenty cilia distributed uniformly on the free surface of a cell (Fig. 300).]

[In the large ciliated cells in the intestine of some **mollusks** (mussel), the cilia perforate the clear refractile disk, which appears to consist of small globules—**basal pieces**—united by their edge, so that a cilium seems to spring from each of these, while continued downward into the protoplasm of the cell, but not attached to the nucleus, there is a single varicose fibril—**rootlet**, and the leash of these fibrils passes through the substance of the cell and may unite toward its lower tailed extremity (*Engelmann*).]

[**Ciliary motion** may be studied in the gill of a mussel, a small part of the gill being teased in *sea water;* or the hard palate of a frog, newly killed, may be so
¾ p. c. salt solution. On analyzing the movement, all the cil
periodic, to-and-fro rhythmical movement in a plane usu
direction of the movement being parallel to the long axis
by the movements of the cilia is sometimes described as

moved by the wind. Each **vibration** of a cilium consists of a rapid forward movement or flexion, the tip moving more than the base, and a slower backward movement, the cilium again straightening itself. The forward movement is about twice as rapid as the backward movement. The **amplitude** of the movement varies according to the kind of cell and other conditions, being less when the cells are about to die, but it is the same for all the cilia attached to one cell, and is seldom more than 20° to 50°. There is a certain **periodicity** in their movement; in the frog they contract about twelve times per second. The result of the rapid forward movement is that the surrounding fluid, and any particles it may contain, are moved in the direction in which the cilia bend. All the cilia of adjoining cells do not move at once, but in regular succession, the movement traveling from one cell to the other, but how this **co-ordination** is brought about we do not know. At least it is quite independent of the nervous system, as ciliary movement goes on, in isolated cells, and in man it has been observed in the trachea two days after death. **Conditions for movement.**—In order that ciliary movement may go on, it is essential that (1) the cilia be connected with part of a cell; (2) moisture; (3) oxygen be present; and (4) the temperature be within certain limits.]

[A ciliated epithelial cell is a good example of the **physiological division of labor.** It is derived from a cell which originally held motor, automatic, and nutritive functions all combined in one mass of protoplasm, but in the fully developed cell, the nutritive and regulative functions are confined to the protoplasm, while the cilia alone are contractile. If the cilia be separated from the cell, they no longer move. If, however, a cell be divided so that part of it remains attached to the cilia, the latter still move. The nucleus is not essential for this act. It would seem, therefore, that though the cilia are contractile, the motor impulse probably proceeds from the cell. Each cell can regulate its own nutrition, for during life they resist the entrance of certain colored fluids.]

[**Effect of Reagents.**—Gentle **heat** accelerates the number and intensity of the movements, **cold** retards them. A temperature of 45° C. causes coagulation of their proteids, makes them permanently rigid, and kills them, just in the same way as it acts on muscle, causing heat stiffening (§ 295, 1). **Weak alkalies** may cause them to contract after their movement is arrested or nearly so (*Virchow*), and any current of fluid in fact may do so. Lister showed that the vapor of **ether** and **chloroform** arrests the movements as long as the narcosis lasts, but if the vapor be not applied for too long a time, the cilia may begin to move again. The prolonged action of the vapor kills them. As yet we do not know any specific poison for cilia—atropin, veratrin, and curara acting like other substances with the same endosmotic equivalent (*Engelmann*).]

[**Functions of Cilia.**—The moving cilia propel fluids or particles along the passages which they line. By carrying secretions along the tubes which they line toward where these tubes open on the surface, they aid in **excretion.** In the respiratory passages, they carry outward along the bronchi and trachea, the mucus formed by the mucous glands in these regions. When the mucus reaches the larynx it is either swallowed or coughed up. That the cilia carry particles upward in a spiral direction in the trachea has been proved by actual laryngoscopic investigation, and also by excising a trachea and sprinkling a colored powder on its mucous membrane, when the colored particles (Berlin blue or charcoal) are slowly carried toward the upper end of the trachea. In bronchitis the ciliated epithelium is shed, and hence the mucus tends to accumulate in the bronchi. They remove mucus from cavities accessory to the nose, and from the tympanum, while the ova are carried partly by their agency from the ovary along the Fallopian tube to the uterus. In some of the lower animals they act as organs of locomotion, and in others as adjuvants to respiration, by creating currents of water in the region of the organs of respiration.]

[**The Force of Ciliary Movement.**—Wyman and Bowditch found that the amount of work that can be done by cilia is very considerable. The work was estimated by the weight which a measured surface of the mucous membrane of the frog's hard palate was able to carry up an inclined plane of a definite slope in a given time.]

[**Pigment cells** belong to the group of contractile tissues, and are well developed in the frog, and many other animals where their characters have been carefully studied. They are generally regarded as comparable to branched connective-tissue corpuscles, loaded with pigmented granules of melanin. The pigment granules may be diffused in the cell, or aggregated around the nucleus; in
e skin of the frog appears dark in color, in the latter, it is but slightly pigmented
tion has been raised whether they are actual cells or merely spaces, branched,
th granules in suspension. In any case, they undergo marked changes of
es. If the motor nerve to one leg of a frog be divided, the skin of the
lly darker in color than the intact leg. A similar result is seen in
e ligatured except the nerve. Local applications affect the

state of diffusion of the pigment, as v. Wittich found that turpentine or electricity caused the cells of the tree frog to contract, and the same effect is produced by light. In Rana temporaria local irritation has little effect, but light, on the contrary, has, although the effect of light seems to be brought about through the eye, probably by a reflex mechanism (*Lister*). A pale-colored frog, put in a dark place, assumes, after a time, a different color, as the pigment is diffused in the dark; but if it be exposed to a bright light it soon becomes pale again. The same phenomenon may be seen on studying the web of a frog's leg under the microscope. The marked variations of color—within a certain range—in the chameleon is due to the condition of the pigment cells in its skin, covered as they are by epidermis, containing a thin stratum of air (*Brücke*). When it is poisoned with strychnin, its whole body turns pale; if it be ill, its body becomes spotted in a dendritic fashion, and if its cutaneous nerves be divided, the area supplied by the nerve changes to black. The condition of its skin, therefore, is readily affected by the condition of its nervous system, for psychical excitement also alters its color. If the sympathetic nerve in the neck of a turbot be divided, the skin on the dorsal part of the head becomes black. It is notorious that the color of fishes is adapted to the color of their environment. If the nerve proceeding from the stellate ganglion in the mantle of a cuttle-fish be divided, the skin on one-half of the body becomes pale.]

FIG. 301.

Pigment cells from the web of frog's foot; *a*, cell with pigment granules diffused; *b*, granules more concentrated; *c*, more concentrated still; *d*, cells with guanin granules (*Stirling*).

[**Guanin in Cells.** — Besides the pigment cells in the web of a frog's foot (especially in Rana temporaria) there are other cells which contain granules of guanin (Fig. 301, *d*). If the web of a frog's foot be mounted in Canada balsam and examined microscopically between crossed Nicol's prisms, each guanin cell is seen to contain numerous very strongly doubly refractive granules of guanin (§ 283).]

292. STRUCTURE AND ARRANGEMENT OF MUSCLES.— [**Muscular Tissue** is endowed with **contractility**, so that when it is acted upon by certain forms of energy or stimuli, it contracts. There are two varieties of this tissue—

(1) **Striped**, striated (or voluntary);
(2) **Non-striped**, smooth, organic (or involuntary).

Some muscles are completely under the control of the will, and are hence called "**voluntary**," and others are not directly subject to the control of the will, and are hence called "**involuntary**;" the former are for the most part striped, and the latter non-striped; but the heart muscle, although striped, is an involuntary muscle.]

1. **Striped Muscles.**—The surface of a muscle is covered with a connective-tissue envelope or **perimysium externum**, from which septa, carrying blood vessels and nerves, the **perimysium internum**, pass into the substance of the muscle, so as to divide it into bundles of fibres or **fasciculi**, which are fine in the eye muscles and coarse in the glutei. In each such compartment or mesh there lie a number of *muscular fibres* arranged more or less parallel to each other. [The fibres are held together by delicate connective tissue or **endomysium**, which surrounds groups of the fibres; each fibre being, as it were, separated from its neighbor by delicate fibrillar connective tissue.] Each muscular fibre is surrounded with a rich plexus of *capillaries* [which form an elongated meshwork, lying between adjacent fibres, but never penetrating the fibres, which, however, they cross (Fig. 307). In a contracted muscle, the capillaries may be slightly sinuous in their course, but when a muscle is on the stretch, these curves disappear. The capillaries lie in the endomysium, and near them are *lymphatics*]. Each muscular fibre receives a nerve fibre. [**Where found.**—Striped muscular fibres occur in the skeletal muscles, heart, diaphragm, pharynx, upper part of œsophagus, muscles of the middle ear and pinna, the true sphincter of the urethra, and external anal sphincter.]

A muscular fibre (Fig. 302, 1) is a more or less cylindrical or polygonal fibre, 11 to 67 μ ($\frac{1}{1000}$ to $\frac{1}{600}$ in.] in diameter, and never longer than 3 to 4 centimetres [1 to 1½ in.]. Within short muscles, *e.g.*, stapedius, tensor tympani, or the short muscles of a frog, the fibres are as long as the muscle itself; within longer muscles, however, the individual fibres are pointed, and are united obliquely by cement substance with a similar beveled or pointed end of another fibre lying in the same direction. Muscular fibres may be isolated by maceration in nitric acid with excess of potassic chlorate, or by a 36 per cent. solution of caustic potash.

[Each muscular fibre consists of the following parts:—

1. **Sarcolemma**, an elastic sheath, with transverse partitions, stretching across the fibre at regular intervals—the *membrane of Krause;*
2. The included **sarcous substance**;
3. The **nuclei** or muscle corpuscles.]

FIG. 302.

Histology of muscular tissue. 1, Diagram of part of a striped muscular fibre; S, sarcolemma; Q, transverse stripes; F, fibrillæ; K, the muscle nuclei; N, a nerve fibre entering it with *a*, its axis cylinder and Kühne's motorial end plate, *e*, seen in profile; 2, transverse section of part of a muscular fibre, showing Cohnheim's areas, *c*; 3, isolated muscular fibrillæ; 4, part of an insect's muscle greatly magnified; *a*, Krause-Amici's line limiting the muscular cases; *b*, the doubly refractive substance; *c*, Hensen's disk; *d*, the singly refractive substance; 5, fibres cleaving transversely into disks; 6, muscular fibre from the heart of a frog; 7, development of a striped muscle from a human fœtus at the third month; 8, 9, muscular fibres of the heart; *c*, capillaries; *b*, connective-tissue corpuscles; 10, smooth muscular fibres; 11, transverse section of smooth muscular fibres.

Sarcolemma.—Each muscular fibre is completely enclosed by a thin, colorless, structureless, transparent elastic sheath (Fig. 302, 1, S), which, chemically, is midway between connective and elastic tissue, and within it is the contractile substance of the muscle. [When a muscular fibre is being digested by trypsin, Chittenden observed, at the beginning, the sarcolemma raised from its sarcous contents as a folded tube, but it is ultimately digested by trypsin. It is thus distinguished from the collagen substance of connective tissue, which is not digested by trypsin. It is not dissolved by boiling, and it resists the action of acids and dilute alkalies, while it is dissolved by concentrated alkalies. Thus, it differs from elastic fibres, and on the whole, chemically, it seems to be most closely related to the membrana propria of glands. It has much more cohesion than the sarcous substance which it encloses, so that sometimes, when teasing fresh muscular tissue under the microscope, one may

observe the sarcous substance torn across, with the unruptured sarcolemma stretching between the ends of the ruptured sarcous substance. If muscular fibres be teased in distilled water, sometimes fine clear blebs are seen along the course of the fibre, due to the sarcolemma being raised by the fluid diffusing under it. The sarcous substance, but not the sarcolemma, may be torn across by plunging a muscle in water at 55° C., and keeping it there for some time (*Ranvier*).]

Sarcous Substance.—The sarcous substance is marked transversely by alternate light and dim layers, bands, **stripes** or disks (Fig. 302, 1, Q), so that each fibre is said to be "**transversely striped.**" [The stripes do not occur in the sarcolemma, but are confined to the sarcous substance, and they involve its whole thickness.]

[The animals most suited for studying the structure of the sarcous substance are some of the insects. The muscles of the water beetle, Dytiscus marginalis, and the Hydrophilus piceus are well suited for this purpose. So is the crab's muscle. In examining a living muscle microscopically, no fluid except the muscle juice should be added to the preparation, and very high powers of the microscope are required to make out the finer details.]

Bowman's Disks.—If a muscular fibre be subjected to the action of hydrochloric acid (1 per 1000), or if it be digested by gastric juice, or if it be frozen, it tends to cleave transversely into **disks** (*Bowman*), which are artificial products, and resemble a pile of coins which has been knocked over (Fig. 302, 5).

Fibrillæ.—Under certain circumstances, a fibre may exhibit *longitudinal striation*. This is due to the fact that it may be split up longitudinally into an immense number of (1 to 1.7 μ in diameter) fine, contractile threads, the **primitive fibrillæ** (Fig. 302, 1, F), placed side by side, each of which is also transversely striped, and they are so united to each other by semi-fluid cement substance, that the transverse markings of all the fibrillæ lie at the same level. Several of these fibrils are united together owing to the mutual pressure, and prismatic in form, so that when a transverse section of a perfectly fresh muscular fibre is observed after it is frozen, the end of each fibre is mapped out into a number of small polygonal areas called **Cohnheim's areas** (Fig. 302, 2). [Each bundle of fibrils or polygonal area represents what Kölliker called "**Muscle Column.**"]

FIG. 303.

Human muscular fibre, × 300.

Fibrillæ are easily obtained from insects' muscles, while those from a mammal's muscle are readily isolated by the action of dilute alcohol, Müller's fluid [or, best of all, $\frac{1}{4}$ per cent. solution of chromic acid] (Fig. 302, 3).

[In studying the structure of muscle, it is well to remember that there are considerable differences between the muscles of Vertebrates and those of Arthropoda.]

[When a **living** unaltered **vertebrate muscular fibre** is examined microscopically, in its own juice, we observe the alternate dim and light transverse disks. Amici, Krause, and Dobie showed that a fine dark line runs across the light disk, and divides it into two (Fig. 303). Amici resolved it into a row of granules, and by others (*e. g.*, Krause) it is regarded as due to the existence of a membrane—hence it is called **Krause's membrane,**—which runs transversely across the fibre, being attached all round to the sarcolemma, thus dividing each fibre into a series of *compartments* placed end to end. Hensen described a disk or stripe in the centre of the dim disk.]

[On **Krause's theory,** each **muscular compartment** contains (1) a **broad dim disk,** which is the *contractile* part of the sarcous substance. It is doubly refractive (**anisotropous**), and is composed of Bowman's sarcous elements. (2) On each end of this disk, and between it and Krause's membranes, is a narrower, clear, homogeneous, and but singly refractile (**isotropous**), soft or fluid substance, which forms the **lateral disk** of Engelmann. In some insects it contains a row of refractive granules, constituting the **granular layer** of Flögel. If a muscular fibre be stretched and stained with logwood, the central part of the dim disk appears lighter in color than the two ends of the same disk. This has been described as a separate disk, and is called the **median disk** of Hensen (Fig. 302, 4, *c*).]

[In an unaltered fibre, the dim broad stripe may appear homogeneous, but after a time it cleaves throughout its entire extent, in the long axis of the fibre, into a number of prismatic elements or fibres, the **sarcous elements** of Bowman (Fig. 302). These at first are prismatic, but as they solidify they shrink and seem to squeeze out of them a fluid, becoming at the same time more constricted in the centre. This separation into bundles of fibrils with an interstitial matter gives rise to the appearance seen on transverse section of a frozen muscle, and known as Cohnheim's areas (Fig. 302, 2, *c*). In all probability the cleavage also extends through the lateral disks, and thus fibrils are formed by longitudinal cleavage of the fibre.]

[**Muscles of Arthropoda.**—Engelmann showed that the muscles of these animals have a large number of disks. In a muscle of an animal killed by being plunged into alcohol, according to the position of the lens of the microscope, one sees:—

1. The broad dim disk, composed of two darker lateral portions or disks, and a lighter disk—that of Hensen, between them. In Fig. 304 the whole disk is marked Q, and Hensen's disk is distinguished as *h*.

2. On both sides of this is a small, clear, slightly refractive stripe, J, corresponding to one of Engelmann's isotropous stripes.

3. On both sides there follows symmetrically a dark, strongly refractive stripe, N, corresponding to Engelmann's accessory stripe and Flögel's granular layer.

4. Then on both sides there is a clear, feebly refractive disk, E.

5. Beyond E is a small, dark, highly refractive stripe, Z—usually the darkest—corresponding to the Amici-Krause line.]

[From Z, the stripes are repeated in the inverse order to Q, then in the same order to Z, and so on. This is the appearance with a low position of the lens. Many muscles do not show all these stripes; thus *h* is often absent.]

[If the lens of the microscope be raised, to get a more superficial view of the fibre, the distribution of the light is reversed (Fig. 304, II), as all strongly refractive sections become light, and all feebly refractive appear darker, while with a deep position of the lens, the reverse is the case.]

[Experiment shows that the dim disk rapidly swells up in dilute acids, and also that the dim disks (Q), the accessory disks (N), and the Amici-Krause line (Z), stain more deeply with logwood than the other disks, and *h* less than the rest of Q.]

[If a muscle which has been some time in alcohol be examined as to its **longitudinal striation**,

FIG. 304.

Insect's muscle; I, with a high position of the lens, and II, with a deeper position.

FIG. 305.



Muscular fibre of Carabus cancellatus.

it will be seen to consist of rods with light intervals between them (Fig. 305). The rods are thicker at their ends, and thinner and lighter at their middle. Rollett regards the clear intervals between these rods as consisting of **sarcoplasma**, a body closely related to protoplasm, and the rods as bundles of fibrillæ or "muscle columns."]

[If a muscle be acted upon by certain acids the relative appearance of the muscle columns and the sarcoplasma is altered; and the latter may appear in these and in gold preparations as a plexus of fibrils with regular longitudinal and transverse meshes (*Melland, Marshall*, Fig. 306).]

[**Muscle Rods.**—Schäfer describes the appearance differently: Double rows of granules are seen lying in or at the boundaries of the light streaks (disks), and very fine longitudinal lines may be detected running through the dark streak (dim disk) and uniting the minute granules. These fine lines, with their enlarged extremities, are "**muscle rods.**" They are most conspicuous in insects. During the contraction of a living muscular fibre, Schäfer describes the "reversal of the stripes" (§ 297) as follows: "When the fibres contract, the light stripes are seen, as the fibre shortens and thickens, to become dark, an apparent reversal being thereby produced in the striæ. This reversal is due to the enlargement of the rows of dark dots and the formation by their juxtaposition and blending of dark disks, while the muscular substances between these disks has by contrast a bright appearance." With **polarized light** in a living muscular fibre, all the sarcous substance, except the muscle rod, is doubly refractive or anisotropous, so that it appears bright on a dark field when the Nicol's prisms are crossed, while under the same conditions contracted muscle and dead muscle show alternate dark and light bands (*Schäfer*).]

The **nuclei** or muscle corpuscles are found immediately under the sarcolemma in all mammals and their long axis lies in the long axis of the fibre (8 to 13 μ long, 3 to 4 μ broad).

[In the muscles of the frog, reptiles and some other animals, *e.g.*, the red muscles of the rabbit and hare and in some muscles of birds, they lie in the substance of the fibre surrounded by a small amount of protoplasm.] When they occur immediately under the sarcolemma they are more or less flattened, and lie embedded in a small amount of protoplasm (Fig. 302, 1 and 2, K). They contain one or two nucleoli, and it is said that the protoplasm sends out fine processes which unite with similar processes from adjoining corpuscles, so that, according to this view, a branched protoplasmic network exists under the sarcolemma. [Each nucleus has a reticulated appearance due to the presence of a plexus of fibrils, consisting of chromatin; in its meshes lies an achromatic substance. The nuclei are specially large in Otiorrhynchus planatus, one of the beetles. Mitotic figures indicating division of the nuclei have been observed. The nuclei are not seen in a perfectly fresh muscle, because, until they have undergone some change, their refractive index is the same as that of the sarcous substance.] They become specially evident after the addition of acetic acid. Histogenetically, they are the remainder of the cells from which the muscular fibres were developed (Fig. 302, 7). According to M. Schultze, the sarcous substance is an intercellular substance differentiated and formed by their activity. Perhaps they are the centres of nutrition for the muscular fibres. In amphibians, birds, fishes and reptiles, they lie in the axis of the fibres between the fibrils.

It is said that the protoplasm of the muscle corpuscles forms a fine network throughout the whole

FIG. 306. FIG. 307. FIG. 308.



Network in a muscular fibre.

Relation of a tendon, S, to its muscular fibre.

Injected blood vessels of a human muscle. *a*, small artery; *b*, vein; *c*, capillaries. × 250.

muscular fibre, the transverse branches taking the course of the lines of Krause or Dobie, and the longitudinal branches running in the interstices between Cohnheim's area (*Retzius*, *Bremer*, *Melland*, Fig. 306).

Relation to Tendons.—According to Toldt, the delicate connective-tissue elements which cover the several muscular fibres pass from the ends of the latter directly into the connective-tissue elements of the tendon. The end of the muscular fibre is perhaps united to the smooth surface or hollow end of the tendon by means of a special cement (*Weismann*—Fig. 307, S). In arthropoda, the sarcolemma passes directly into and becomes continuous with the tendon (*Leydig*). The tendon itself consists of longitudinally arranged bundles of white fibrous tissue with cells—*tendon cells*—embracing them. There is a loose capsule or sheath of connective tissue—the **peritendineum** of Kollman—surrounding the whole and carrying the blood vessels, lymphatics, and nerves. The tendons move in the tendon sheaths, which are moistened by a mucous fluid. In most situations, muscular fibres are attached by means of tendons to some fixed point, but in other situations (face) the ends terminate between the connective-tissue elements of the skin.

[**Blood Vessels.**—Muscles, being very active organs, are richly supplied with blood. The blood supply of a muscle differs from some organs in not constituting an actual vascular unit, supplied only by one artery and one vein, thus being unlike the kidney, spleen, etc. Each muscle usually receives

several branches from different arteries, and branches enter it at certain distances along its whole length. The artery and vein usually lie together in the connective tissue of the perimysium, while the capillaries lie in the endomysium. The capillaries lie between the muscular fibres, but **outside the sarcolemma**, where they form an elongated rich plexus with numerous transverse branches (Fig. 308). The lymph to nourish the sarcous substance must traverse the sarcolemma to reach the former. In the **red muscles** of the rabbit (*e.g.*, semitendinosus) the capillaries are more wavy, while on the transverse branches of some of the capillaries, and on the veins, there are small, oval, saccular dilatations, which act as reservoirs for blood (*Ranvier*).]

[**Lymphatics.**—We know very little of the lymphatics of muscle, although the lymphatics of tendon and fascia have been carefully studied by Ludwig and Schweigger-Seidel. There are lymphatics in the endomysium of the heart, which are continuous with those under the pericardium. This subject still requires further investigation. Compare the lymphatics of the fascia lata of the dog (Fig. 227, § 201).]

Entrance of the Nerve.—The *trunk* of the motor nerve, as a rule, enters the muscle at its geometrical centre (*Schwalbe*); hence, the point of entrance in muscles with long, parallel, or spindle-shaped fibres lies near its middle. If the muscle with parallel fibres is more than 2 to 8 centimetres [1–3 inches] in length, several branches enter its middle. In triangular muscles, the point of entrance of the nerve is displaced more toward the strong tendinous point of convergence of the muscular fibres. A nerve fibre usually enters a muscle at the point where there is the least displacement of the muscular substance during contraction.

Motor Nerve.—Every muscle fibre receives a motor nerve fibre (Fig. 302, 1, N). Each nerve does not contain originally as many motor nerve fibres as there are muscular fibres in the muscle it enters; in the human eye muscles there are only 3 nerve fibres to 7 muscular fibres; in other muscles (dog), 1 nerve fibre to 40 or 80 (*Tergast*). Hence, when a nerve enters a muscle it must divide, which occurs dichotomously [at Ranvier's nodes], the structure undergoing no change until there are exactly as many nerve fibres as muscular fibres. In warm-blooded animals each muscular fibre has only one, while cold-blooded animals have several points of insertion of the nerve fibre (*Sandmann*). A nerve fibre enters each muscular fibre, and where it enters it forms an eminence (*Doyère*, 1840), the "**motorial end plate**" (Fig. 302, 1, *e*, 309, 310, 311).

FIG. 309.



Muscular fibres with motorial end plates.

[The elaborate investigations of K. Mays on the exact distribution of nerve fibres in the muscles of the frog have conclusively proved—apart from experimental reasons—that parts of muscles receive no nerve fibres at all, large portions being free from nerves. This has been proved for all classes of vertebrates except osseous fishes.]

[The mode of termination of a motor nerve in a muscular fibre is not the same in all animals, but in every case it pierces the sarcolemma, and its ultimate distribution has a distinct hypolemmal character. The Doyère's eminence is present in most mammals and reptiles, but in amphibians and birds, the ending is flat on the muscle fibre. Most of the results known to us have been worked out by Kühne. The nerve endings, then, are confined to very small spots or areas on the muscular fibres, termed by Kühne "**fields of innervation.**" Most nerve fibres have only one such field, but very long fibres may have, at most, eight. One or more medullated nerve fibres pass—as pre-terminal or epilemmal fibres—from the point of division of the nerve fibre to the muscular fibre, to pass into the nerve endings. The nerve-endings consist of divisions of the axial cylinder, which are distributed over the sarcous substance without (so far as is known) forming any direct connection with it. The endings, however, lie in direct contact with it. This branched arrangement of the axis cylinder under the sarcolemma, Kühne has called a "motor spray" ("motorisches Geweih"), and the mode of distribution of the branches varies in different classes of animals. In the frog (Fig. 310),

tailed amphibians, and birds, the hypolemmal branches of the axis cylinder form bayonet-like and branched endings. In the lizard, snakes and mammals, the branches are often curved or twisted, and possessed of lobes, and as the division is very variable, there is every form from a simple hook-like bend to a highly arborescent termination.]

[Where a motor nerve enters a muscular fibre at the eminence of Doyère, the sheath of the nerve fibre, known as the perineural or Henle's sheath (§ 321), becomes continuous with the sarcolemma. The eminence itself consists of a mass of protoplasm—or sarcoplasm—called by Kühne **sarcoglia**—which contains granules and nuclei, the latter with a membrane and peculiar nucleoli; the nuclei themselves are the fundamental or basal nuclei of the sarcoglia. The outer surface of the eminence is covered by a membrane called **telolemma** by Kühne, but which in reality consists of two membranes, an outer one, the **epilemma**, continuous with the perineural or Henle's sheath, and an inner one, the **endolemma**, the continuation of the sheath of Schwann of the nerve fibre, both ultimately being connected with the sarcolemma. As the nerve pierces the muscular fibre, it loses its myeline, and with it disappears the keratin sheath or axilemma of the axis cylinder, so that the spray-like ending is accompanied only by the telolemma (Fig. 311). The telolemma contains nuclei which are derived from Henle's sheath (*Kühne*).]

FIG. 310.



Motor nerve ending in the frog (*Kühne*). *a*, Profile view of entrance of the nerve; *b*, *b*, nuclei of the branches of the axial cylinder; *c*, *c*, *c*, nuclei of Henle's sheath; *e*, muscle nuclei.

FIG. 311.



Motor nerve ending in lizards, mammals, and man. Schematic after Kühne. A, axis cylinder; A'A', terminal branches of A; *a*, *a*, myelin of nerves; *b*, perineural or Henle's sheath, and its nuclei (*c*); *d*, nuclei of telolemma; B, bed; D, large granule in B; C, nuclei of the bed; E, muscle nuclei; F, contractile substance.

"Tache motrice" Ranvier

[In some animals, such as the lizard, in order to see the nerve terminations, it is sufficient to stain portions of fresh muscles with Delafield's logwood.]

[Nerve endings, then, are sublemmar, and the terminations of the nerves never penetrate into the depth of the muscular fibre, but come into direct contact with the contractile prism or cylinder moistened by the fluids of the muscle. In many cases the striped substance is separated from the blunt nerve endings by some of the sarcoglia, which in some cases penetrate and traverse the other constituent of the fibre. The latter Kühne has called "rhabdia." The antler-like division of the axis cylinder or spray, in contact with the muscular substance, serves to conduct the excitation from the former to the latter, but excitation of the muscular substance is never transmitted in the reverse order to the nerve ending (*Kühne*).]

Each muscular fibre of the cray fish is supplied by two nerve fibrils arising from separate axis cylinders (*Biedermann*).

Sensory fibres also occur in muscles, and they are the channels for muscular

sensibility. They seem to be distributed on the outer surface of the sarcolemma, where they form a branched plexus and wind round the muscular fibres (*Arndt, Sachs*); but, according to Tschirjew, the sensory nerves traverse the substance of the muscle, and after dividing dichotomously, end *only* in the aponeurosis, either suddenly or by means of a small swelling—a view confirmed by Rauber. The existence of sensory nerves in muscles is also proved by the fact that stimulation of the central end of a motor nerve, *e. g.*, the phrenic, causes increase of the blood pressure and dilatation of the pupil (*Asp, Kowalewsky, Nawrocki*), as well as by the fact that when they are inflamed they are painful. They of course do not degenerate after section of the anterior root of the spinal nerves.

Red and Pale Muscles.—In many fishes (skate, plaice, herring, mackerel) (*W. Stirling*), birds, and mammals (rabbits), there are two kinds of striped muscle (*Krause*), differing in color, histological structure (*Ranvier*), and physiological properties (*Kronecker and Stirling*). Some are "**red**," *e. g.*, the soleus and semitendinosus of the rabbit, and others "**pale**," *e. g.*, the adductor magnus. In the *pale* muscles the transverse striation is less regular, and their nuclei fewer than in the red muscles (*Ranvier*); they contain less glycogen and myosin. [W. Stirling finds that the red muscles in many fishes, *e. g.*, the mackerel, contain granules of oil, and present all the appearance of muscle in a state of fatty degeneration, while the pale muscles, lying side by side, contain no fatty granules.]

Julius Arnold found in human muscles an extensive distribution of pale fibres among the red ones, and indeed in the same muscle in the frog and mammals, red and pale fibres occur together, in fact this is the case in almost every muscle (*Grützner*).

[**Spectrum.**—The red color of the ordinary skeletal muscle is due to hæmoglobin in the sarcous substance (*Kühne*). This is proved by the fact that the color is retained after all the blood is washed out of the vessels, when a thin muscle still shows the absorption bands of hæmoglobin when examined with the spectroscope.]

[**Myo-hæmatin.**—MacMunn points out that although most voluntary muscles owe their color to hæmoglobin, it is accompanied by *myo-hæmatin* in most cases, and sometimes entirely replaced by it. Myo-hæmatin is found in the *heart* of vertebrates, in the papillary muscles of the human heart, and in abundance in the pectoral muscles of pigeons, and in some muscles of vertebrates and invertebrates, *e. g.*, certain beetles (Hydrophilus, Dytiscus), the common fly, and other insects, spiders, crustaceans, and mollusks.]

Muscular Fibres of the Heart.—The mammalian **cardiac muscle** has certain peculiarities already mentioned (§ 43): (1) It is striped, but it is involuntary; (2) it has no sarcolemma; (3) its fibres branch and anastomose; (4) the transverse striation is not so distinct, and it is sometimes striated longitudinally; (5) the nucleus is placed in the centre of each cell (see § 43). [The cardiac muscle, viewed from a *physiological* point of view, stands midway between striped and unstriped muscle. Its contraction occurs slowly and lasts for a long time (p. 127), while, although it is transversely striped, it is involuntary.]

[**Purkinje's Fibres.**—These fibres, which form a plexus of grayish fibres under the endocardium of the heart of ruminants, have been described already (Fig. 28); the cells have, as it were, advanced only to a certain stage of development (§ 46).]

Development.—Each muscular fibre is developed from a uni-nucleated cell of the mesoblast, which elongates into the form of a spindle. As the cell elongates, the nuclei multiply. The superficial or parietal part of the cell substance shows transverse markings (Fig. 302, 7), while the nuclei with a small amount of protoplasm are continuous along the axis of the fibre, where they remain in some animals, but in man they pass to the surface where they come to lie under the sarcolemma. The muscles of the young are smaller and have fewer fibres than those of adults (*Budge*). In developing muscle, the number of fibres is increased by the proliferation of the muscle corpuscles, which form new fibres.

Striped muscle, besides occurring in the corresponding organs of vertebrata, occurs in the iris and choroid of birds. The arthropoda have only striped muscle, the mollusks, worms, and echinoderms chiefly smooth muscles; in the latter are muscles with double oblique striation (*Schwalbe*). According to Paneth, in old individuals separate cells with aggregation of contractile substance—so-called **Sarcoplasts**—unite to form new muscular fibres. Sig. Mayer regards these structures as retrogressive structures, and he calls them **Sarcolytes** (§ 103, II).

2. **Non-striped Muscle.**—[**Distribution.**—It occurs very widely distributed in the body, in the muscular coat of the lower half of the human œsophagus, stomach, small and large intestine, muscularis mucosæ of the intestinal tract, in the arteries, veins, and lymphatics, posterior part of the trachea, bronchi, infundibula of the lung, muscular coat of the ureter, bladder, urethra, vas deferens, vesiculæ seminales, and prostate; corpora cavernosa and spongiosa penis, ovary, Fallopian tube, uterus, skin, ciliary muscle, iris, upper eyelid, spleen and capsule of lymphatic glands, tunica dartos of the scrotum, gall bladder, in ducts of glands, and in some other situations.]

Structure.—Smooth muscular fibres consist of fusiform or spindle-shaped elongated cells, with their ends either tapering to fine points or divided (Fig. 312). These contractile fibre cells may be

isolated by steeping a piece of the tissue in a 30 per cent. solution of caustic potash, or a strong solution of nitric acid. They are 45 to 30 μ [$\frac{1}{800}$ to $\frac{1}{1200}$ in.] in length, and 4 to 10 μ [$\frac{1}{6000}$ to $\frac{1}{2500}$ in.] in breadth. Each cell contains a solid oval elongated **nucleus**, which may contain one or more nucleoli. It is brought into view by the action of dilute acetic acid, or by staining reagents. The mass of the cell appears more or less homogeneous [and is surrounded by a thin elastic envelope]. In some places it shows longitudinal fibrillation. [**Method.**—This fibrillation is revealed more distinctly thus: Place the mesentery of a newt (*Klein*) or the bladder of the salamandra maculata (*Flemming*) in a 5 per cent. solution of ammonium chromate, and afterward stain it with picro carmine. Each cell consists of a thin elastic **sheath** (sarcolemma of Krause) enclosing a bundle of **fibrils** (F) which run in a longitudinal direction within the fibre (Fig. 313). They are continuous at the poles of the nucleus with the plexus of fibrils which lies within the nucleus, and, according to Klein, they are the contractile part, and when they contract the sheath becomes shriveled transversely and exhibits what looks like thickenings (S). These fibrils have been observed by Flemming in the cells while *living*. Sometimes the cells are branched, while in the frog's bladder they are triradiate.]

[**Arrangement.**—Sometimes the fibres occur singly, but usually they are arranged in groups, forming lamellæ, sheets, or bundles, or in a plexiform manner, the bundles being surrounded by connective tissue.] A very delicate elastic cement substance unites the individual cells to each other. [This **cement** may be demonstrated by the action of nitrate of silver. In transverse section (Fig. 312, 11) they appear oval or polygonal, with the delicate homogeneous cement between them; but, as the

FIG. 312.



Smooth muscular fibres (10); (11) transverse section.

FIG. 313.



Smooth muscular fibre from the mesentery of a newt (ammonium chromate). N, nucleus; F, fibrils; S, markings in the sheath.

FIG. 314.



Termination of nerve in non-striped muscle.

fibres are cut at various levels, the areas are unequal in size, and all of them, of course, are not divided at the position of the nucleus.]

They vary in length from $\frac{1}{100}$ to $\frac{1}{200}$ of an inch; those in the middle coat of the arteries are short, while they are long in the intestinal tract, and especially in the pregnant uterus. According to Engelmann, the separation of the smooth muscular substance into its individual spindle-like elements is a *post-mortem* change of the tissue. Sometimes transverse thickenings are seen, which are not due to transverse striation, but to a partial contraction. Occasionally they have a tendinous insertion.

Blood Vessels.—Non-striped muscle is richly supplied with blood vessels, and the capillaries form elongated meshes between the fibres [although it is not so vascular as striped muscle]. **Lymphatics** also occur between the fibres,

Motor Nerves.—According to J. Arnold, they consist of medullated and non-medullated fibres [derived from the sympathetic system] which form a plexus—**ground plexus**—partly provided with ganglionic cells, and lying in the connective tissue of the perimysium. [The fibres are surrounded with an endothelial sheath.] Small branches [composed of bundles of fibrils] are given off from this plexus, forming the **intermediary plexus** with angular nuclei at the nodal points. It lies either immediately upon the musculature or in the connective tissue between the individual bundles. From the intermediary plexus, the finest fibrillæ (0.3 to 0.5 μ) pass off, either singly or in groups, and reunite to form the **intermuscular plexus** (Fig. 314, *d*), which lies in the cement substance between

the muscle cells, to end, according to Frankenhäuser, in the nucleoli of the nucleus, or in the neighborhood of the nucleus (*Lustig*). According to J. Arnold, the fibrils traverse the fibre and the nucleus, so that the fibres appear to be strung upon a fibril passing through their nuclei. According to Löwit, the fibrils reach only the interstitial substance, while Gscheidlen also observed that the finest terminal fibrils, one of which goes to each muscular fibre, ran along the margins of the latter (Fig. 314). The course of these fibrils can only be traced after the action of gold chloride. [Ranvier has traced their terminations in the stomach of the leech.]

Nerves of Tendon.—Within the tendons of the frog, there is a plexus of medullated nerve fibres, from which brush-like divided fibres proceed, which ultimately end with a point in nucleated plates, the **nerve flakes** of Rollett. According to Sachs, bodies like **end bulbs** occur in tendons, while Rauber found **Vater's corpuscles** in their sheaths; Golgi found, in addition, **spindle-shaped terminal corpuscles**, which he regards as a specific apparatus for estimating tension.

293. PHYSICAL AND CHEMICAL PROPERTIES OF MUSCLE.—1. The **consistence** of the sarcous substance is the same as that of living protoplasm, *e. g.*, of lymph cells; it is semi-solid, *i. e.*, it is not fluid to such a degree as to flow like a fluid, nor is it so solid that, when its parts are separated, these parts are unable to come together to form a continuous whole. The consistence may be compared to a jelly at the moment when it is dissolved (*e. g.*, by heat). The power of *imbibition* is increased in a contracted muscle (*Ranke*).

Proofs.—The following facts corroborate the views expressed above: (*a*) The analogy between the function of the sarcous substance and the contractile protoplasm of cells (§ 9). (*b*) The so-called **Porret's phenomenon**, which consists in this, that when a galvanic current is conducted through the living, fresh, sarcous substance, the contents of the muscular fibre exhibit a streaming movement from the positive to the negative pole (as in all other fluids), so that the fibre swells at the negative pole (*Kühne*). (*c*) By the fact that wave movements have been observed to pass along the muscular fibre. (*d*) Direct observation has shown that a small parasitic round worm (Myoryctes Weismanni) moved freely in the sarcous substance within the sarcolemma, while the semi-solid mass closed up in the tract behind it (*Kühne, Eberth*).

2. **Polarized Light.**—The contractile substance doubly refracts light, and is said to be **anisotropous**, while the ground substance causes single refraction, and is **isotropous**. According to Brücke, muscle behaves like a doubly refractive, positively uniaxial body, whose optical axis lies in the long axis of the fibre. When a muscular fibre is examined under the polarization microscope, the doubly refractive substance is recognized by its appearing *bright* in the dark field of the microscope when the Nicols are crossed (§ 297). During contraction of the muscular fibre, the contractile part of the fibre becomes narrower, and at the same time broader, while the optical constants do not thereby undergo any change. Hence, Brücke concludes that the contractile disks are not simple bodies like crystals, but must consist of a whole series of small, doubly refractive elements arranged in groups, which change their position during contraction and relaxation. These small elements Brücke called **disdiaclasts.** According to Schipiloff, Danielewsky, and O. Nasse, the contractile anisotropous substance consists of myosin, which occurs in a crystalline condition and represents the disdiaclasts. According to Engelmann, however, all contractile elements are doubly refractive, and the direction of contraction always coincides with the optical axis.

The investigations of v. Ebner have shown that during the process of growth of the tissue, *tension* is produced—the tension of bodies subjected to imbibition—which results in double refraction, and so gives rise to the condition called anisotropous. During a sustained contraction, the index of refraction of the muscular fibre increases (*Exner*).

[**Reaction.**—If a transverse section of a living excised muscle be pressed upon a strip of blue litmus paper, the latter may assume a reddish tinge, and if upon a red litmus paper the latter may assume a bluish tinge, but it will not alter violet litmus paper. This is the amphochromatic or amphoteric reaction, indicating that the muscle is neutral. It may, however, give only an alkaline reaction. A living muscle plunged into boiling water still retains its neutral or alkaline reaction; but a muscle, which has been tetanized, or is in rigor mortis, is decidedly acid.]

The **chemical composition** of muscle undergoes a great change after death, owing to the spontaneous coagulation of a proteid within the muscular fibres. As frog's muscles may be frozen and thawed, and still remain contractile, they cannot, therefore, be greatly changed by the process of freezing. Kühne bled frogs, cooled their muscles to -10° or -7° C., pounding them in an iced mortar, and expressed their juice through linen. The juice so expressed, when filtered in the cold, forms a neutral or alkaline, slightly yellowish, opalescent fluid, the so-called "**muscle plasma.**" Like blood plasma, it coagulates spontaneously; at first it is like a uniform soft jelly, but soon becomes opaque; doubly refractive fibres

and specks, similar to the fibrin of blood, appear in the jelly, and as these begin to contract, they squeeze out of the jelly an *acid* "**muscle serum.**" [Halliburton finds that the muscles of warm-blooded animals yield a similar muscle plasma.] Cold prevents or delays the coagulation of the muscle plasma; above 0°, coagulation occurs very slowly, and the rapidity of coagulation increases rapidly as the temperature rises, while coagulation takes place very rapidly at 40° C. in cold-blooded animals, or at 48° to 50° C. in warm-blooded animals. The addition of distilled water or an acid to muscle plasma causes coagulation at once. The coagulated proteid, most abundant in muscle, and which arises from the doubly refractive substance, is called "**myosin**" (*W. Kühne*).

Myosin.—It is a globulin (§ 245), and is soluble in strong (10 per cent.) solution of common salt, and is again precipitated from such a solution by dilution with water, or by the addition of very small quantities of acids (0.1 to 0.2 per cent. lactic or hydrochloric acid). It is soluble in dilute alkalies or slightly stronger acids (0.5 per cent. lactic or hydrochloric acid), and also in 13 per cent. ammonium chloride solution. [The more myosin is freed from salts (especially of calcium) by washing, the more insoluble does it become, both in saline solutions and weak hydrochloric acid. When once precipitated from its solution, it can be redissolved, reprecipitated, and again undergo coagulation a second or even a third time (*Halliburton*).] Like fibrin, myosin rapidly decomposes hydric peroxide. When treated with dilute hydrochloric acid and heat, it is very rapidly changed ir to syntonin (§ 245). Myosin may be extracted from muscle by a 10 to 15 per cent. solution of NH_4Cl, and if it be heated to 65°, it is precipitated again (*Danielewsky*). Danielewsky succeeded in partly changing syntonin into myosin by the action of milk of lime and ammonium chloride. Myosin occurs in other animal structures (cornea), nay, even in some vegetables (*O. Nasse*).

Muscle serum, according to Kühne, still contains three proteids (2.3 to 3 per cent.), viz.: 1. **Alkali albuminate,** which is precipitated on adding an acid, even at 20° to 24° C. 2. Ordinary **serum albumin,** 1.4 to 1.7 per cent. (§ 32, *a*), which coagulates at 73° C. 3. An albuminate which coagulates at 47° C.

[Halliburton finds, however, the following **proteids in muscle plasma**:—

Name.	Precipitated by Heat at	Saturation with NaCl or Na_2SO_4.	
Paramyosinogen, ...	47° C.	Causes precipitation.	Proteids which go to form muscle clot.
Myosinogen, ...	56°	" "	
Myoglobulin, ...	63°	" "	Proteids of the muscle serum.
Albumin, ...	73°	No ↓	
Myoalbumose, ...	Not ↓	No ↓	

Although the first two go to form the clot of muscle or myosin, paramyosinogen is not essential for coagulation. Besides these bodies there are **hæmoglobin** and also **myo-hæmatin,** which is not identical with the blood pigment. It can be extracted by ether from muscle (*e. g.*, the breast muscle of a pigeon), whereby the ether becomes red. It can exist in an oxidized and reduced condition (*MacMunn*).]

The other chemical constituents of muscle have been referred to in treating of flesh (§ 233). 1. **Muscle ferments.**—Brücke found traces of **pepsin** and peptone in muscle juice [the latter is denied by Halliburton]; Piotrowsky, a trace of a **diastatic ferment.** [When muscle becomes acid, as in rigor mortis, the pepsin at a suitable temperature (35° to 40° C.) acts on the proteids, and albumoses and peptones are formed. Halliburton found a **myosin ferment** which has the characters of an albumose. 2. In addition to volatile *fatty acids* (formic, acetic, butyric), there are two isomeric forms of *lactic acid* ($C_3H_6O_3$) present in muscle with an acid reaction: (*a*) *Ethylidene-lactic acid,* in the modification known as right-rotatory *sarcolactic* or *paralactic* acid, which occurs only in muscles, and some other animal structures. (*b*) *Ethylene-lactic acid* in small amount (§ 251, 3, *c*). It was formerly assumed that lactic acid is formed by fermentation from the carbohydrates of the muscle (glycogen, dextrin, sugar), and Maly has observed that paralactic acid is occasionally formed when these bodies undergo fermentation. Accord-

ing to Böhm, however, the glycogen of muscle does not pass into lactic acid, as during rigor mortis, if putrefaction be prevented, the amount of glycogen does not diminish. If muscle be suddenly boiled or treated with strong alcohol, the ferment is destroyed, and hence the acidification of the muscular tissue is prevented (*Du Bois-Reymond*). *Acid potassium phosphate* also contributes to the acid reaction. 3. *Carnin* ($C_7H_8N_4O_3$) which is changed by bromine or nitric acid into sarkin, occurs to the extent of 1 per cent. in Liebig's extract of meat (*Weidel*). 4. *Urea*, 0.01 per cent. (*Haycraft*). [There is much urea in the muscles of the skate.] 5. *Glycogen* occurs to the amount of over 1 per cent. after copious flesh feeding, and to 0.5 per cent. during fasting. It is stored up in the muscles, as well as in the liver, during digestion, but it disappears during hunger. It is perhaps formed in the muscles from proteids (§ 174, 2). 6. *Lecithin*, derived in part from the motor nerve endings (§ 23 and § 251). 7. The **gases** are CO_2 (15 to 18 vol. per cent.), partly absorbed, partly chemically united; some absorbed N, but no O, although muscle continually absorbs O from the blood passing through it (*L. Hermann*). The muscles contain a substance whose decomposition yields CO_2. When muscles are exercised, this substance is used up, so that severely fatigued muscles yield less CO_2 (*Stinzing*). [All muscles have not the same chemical composition.]

294. **METABOLISM IN MUSCLE.**—[In living muscle we have to study the transformations of energy, and the chemical changes on which these depend. But as we cannot examine the chemical changes which occur during a contraction, we are confined to a study of (1) the composition of a muscle before and after contraction, and (2) the effect of contraction on the medium surrounding or passing through a muscle. We may observe the effect produced by a muscle upon air or other gases to which an excised muscle is exposed, or we may investigate the changes which the blood undergoes in passing through a muscle, and if the muscle be still *in situ*, the effect upon the general excreta. These methods may be applied to muscle in various conditions, passive or active, dead or dying, to excised muscles or those still under normal circumstances.]

I. A passive muscle continually absorbs a certain amount of O from the blood flowing through its capillaries, and returns a certain amount of CO_2 to the blood stream. The amount of CO_2 given off is less than corresponds to the amount of O absorbed. Excised muscles freed from blood exhibit an analogous but diminished gaseous exchange. As an excised muscle remains longer excitable in O or in air than in an atmosphere free from O, or in indifferent gases, we must conclude that the above-named gaseous exchange is connected with the normal metabolism, and is a condition on which the life and activity of the muscle depend. [Resting living muscles also exhale CO_2.]

If a living muscle be excised, and if blood be perfused through its blood vessels, the amount of O used up is, within pretty wide limits, almost independent of temperature; if the variations of temperature be great, it rises and falls with the temperature. The CO_2 given off by muscular tissue (less than the O used up) falls when the muscle is cooled, but it is not increased when the muscle is subsequently warmed (*Rubner*).

This exchange of gases must be distinguished from the putrefactive phenomena due to the development of living organisms in the muscle. These putrefactive phenomena are also connected with the consumption of O and the excretion of CO_2, and occur soon after death (*L. Hermann*).

II. In an active muscle the **blood vessels** are always **dilated** (*Ludwig and Sczelkow, Gaskell*)—a condition pointing to a more lively material exchange in the organ. [The dilatation of the blood vessels can be observed microscopically in the contracting mylo-hyoid muscle of the frog.] Hence, the active muscle is distinguished from the passive one by a series of chemical transformations.

1. **Reaction.**—The neutral or feebly alkaline reaction of a passive muscle (also of the non-striped variety) passes into an *acid* reaction during the activity of the muscle, owing to the formation of paralactic acid (*Du Bois-Reymond*, 1859); the degree of acidity increases up to a certain extent, according to the amount of

work performed by the muscle (*R. Heidenhain*). The acidification is due, according to Weyl and Zeitler, to the phosphoric acid produced by the decomposition of lecithin and (? nuclein).

It is doubtful if the acidity is due to lactic acid, as Warren and Astaschewsky find that there is less lactic acid in the active than in the passive muscle. Marcuse, however, supports the lactic acid theory, while Moleschott and Battistini, agree that the passive muscle contains acid, but the fatigued muscle contains more, especially of phosphoric acid and CO_2.

2. **Production of CO_2.**—An active muscle excretes considerably more CO_2 than a passive one: (*a*) active muscular exertion on the part of a man or of animals increases the amount of CO_2 given off by the lungs (§ 127); (*b*) venous blood flowing from a tetanized muscle of a limb contains more CO_2, more CO_2 being formed than corresponds to the O which has simultaneously been absorbed (*Ludwig and Sczelkow*). The same result is obtained when blood is passed through an excised muscle artificially; (*c*) an excised muscle caused to contract excretes more CO_2. (Compare § 368.)

3. **Consumption of Oxygen.**—An active muscle uses up more O—(*a*) when more muscular work is done, the body absorbs much more O (§ 217)—even 4 to 5 times as much (*Regnault and Reiset*); (*b*) venous blood flowing from an active muscle of a limb contains less O (*Ludwig, Sczelkow, and Al. Schmidt*). Nevertheless, the increase of O used up by the active muscle is not so great as the amount of CO_2 given off (*v. Pettenkofer and v. Voit*). The increase of O used up may be ascertained even during the period of rest directly following the period of activity, and the same is the case with the CO_2 excreted (*v. Frey*).

As yet, it is not possible to prove by gasometric methods, that O is used up in an **excised muscle** free from blood. Indeed, the presence of O does not seem to be absolutely necessary for the activity of muscle during short periods, as an excised muscle may continue to contract in a vacuum, or in a mixture of gases free from O, and no O can be obtained from muscular tissue (*L. Hermann*). A frog's muscles rob easily reducible substances of their O; they discharge the color of a solution of indigo; muscles which have rested for a time, acting less energetically than those which have been kept in a state of continued activity (*Grützner, Gscheidlen*).

4. **Glycogen.**—The amount of glycogen (0.43 per cent. in the muscles of a frog or rabbit) and grape sugar is diminished in an active muscle (*O. Nasse, Weiss*), but muscles devoid of glycogen do not lose their excitability and contractility. Hence, glycogen is certainly not the direct source of the energy in an active muscle. Perhaps it is to be sought for in an as yet unknown decomposition product of glycogen (*Luchsinger*). [There is more glycogen in the red than in the pale muscles of a rabbit.]

5. **Extractives.**—An active muscle contains less extractive substances soluble in water, but more extractives soluble in alcohol (*v. Helmholtz*, 1845); it also contains less of the substances which form CO_2 (*Ranke*); less fatty acids (*Sczelkow*); less kreatin and kreatinin (*v. Voit*).

6. During contraction, the amount of **water** in the muscular tissue increases, while that of the blood is correspondingly diminished (*J. Ranke*). The solid substances of the blood are increased, while they (albumin) are diminished in the lymph (*Fano*).

7. **Urea.**—The amount of urea excreted from the body is not materially increased during muscular exertion (*v. Voit, Fick and Wislicenus*). According to Parkes, however, although the excretion of urea is not increased immediately, yet after 1 to 1½ day there is a slight increase. The amount of work done cannot be determined from the amount of albumin which is changed into urea.

[**Relation of Muscular Work to Urea.**—Ed. Smith, Parkes, and others have made numerous investigations on this subject. Fick and Wislicenus (1866) ascended the Faulhorn, and for seventeen

hours before and for six hours after the ascent no proteid food was taken—the diet consisting of cakes made of fat, sugar, and starch. The urine was collected in three periods, as follows :—

	Fick.		Wislicenus.	
1. Urea of 11 hours before the ascent, . .	238.55 grs.		221.05 grs.	
2. " 8 " during " . .	109.44 "	} 189.77	103.46 "	} 183.35
3. " 6 " after " . .	80.33 "		79.89 "	

A hearty meal was taken after this period, and the urine of the next eleven hours after the period of rest contained 159.15 grains of urea (*Fick*), and 176.71 (*Wislicenus*). All the experiments go to show that the amount of urea excreted in the urine is far more dependent upon the nitrogen ingested, *i. e.*, the **nature of the food**, than upon the decomposition of the muscular substance. A vegetable diet diminishes, while an animal diet greatly increases, the amount of urea in the urine. North's researches confirm those of Parkes, but he finds that the disturbance produced by severe muscular labor is considerable. The elimination of phosphates is not effected, while the sulphates in the urine are increased.]

During the **activity of a muscle**, *all* the groups of the chemical substances present in muscle undergo more rapid transformations (*J. Ranke*). It is still a matter of doubt, therefore, whether we may assume that the kinetic energy of a muscle is chiefly due to the transformation of the chemical energy of the carbohydrates which are decomposed or used up in the process of contraction. As yet we do not know whether the glycogen is supplied by the blood stream to the muscles, perhaps from the liver, or whether it is formed within the muscles themselves from some unknown derivative of the proteids. The normal circulation is certainly one of the conditions for the formation of glycogen in muscle, as glycogen diminishes after ligature of the blood vessels (*Chandelon*). A muscle in which the blood circulates freely is capable of doing more work than one devoid of blood, and even in the intact body, more blood is always supplied to the contracted muscles.

[**Source of Muscular Energy.**—The experiment of Fick and Wislicenus definitely proved that the proteids are not the exclusive, or by any means the chief source of muscular energy. As it is conclusively proved that during muscular work there is a great increase in the amount of O absorbed, and CO_2 given off, it is evident that the non-nitrogenous substances of the food must be the chief sources of this energy. We turn naturally to the carbohydrates, and as the latter are chiefly stored up in the form of glycogen in the muscles, it is assumed that glycogen is the chief source of the energy. Glycogen in muscle diminishes during muscular work, and is stored up during rest (*Bernard*). Külz also found that in dogs the glycogen disappears from the liver during work, and Voit found that the muscle glycogen disappears before that in the liver. It appears, therefore, that the *carbohydrates* are a source of muscular energy. But they, again, are not the only source. It is highly probable that glycogen can be formed from proteids, and it is allowable, therefore, to assume that *proteids* may also serve as a source of muscular energy. If this be not so, it is difficult to understand how carnivora can be fed and maintained in good health for long periods on lean flesh. The fats are probably also another source. Hence, it would appear that all three of the chief groups of food stuffs—carbohydrates, proteids, and fats—*may* serve as the source of muscular energy; but that, so long as non-nitrogenous elements are supplied in the food in sufficient quantity, or are stored up in the body, the muscles do their work chiefly on these. After they are used up, the proteids are, as it were, called up.]

295. RIGOR MORTIS.—Cause.—Excised striped, or smooth muscles, and also the muscles of an intact body, at a certain time after death, pass into a condition of rigidity—**cadaveric rigidity** or **rigor mortis**. When all the

muscles of a corpse are thus affected, the whole cadaver becomes completely stiff or rigid. The **cause** of this phenomenon depends upon the spontaneous coagulation of a proteid, viz., the **myosin** of the muscular fibres (*Kühne*). Under certain circumstances, the coagulation of the other proteids of the muscle may increase the rigidity. During the process of coagulation, an acid is formed, heat is set free (*v. Walther, Fick*—§ 223), owing to the passage of the fluid myosin into the solid condition, and also to the simultaneous and subsequently increased density of the tissue.

Properties of a Muscle in Rigor Mortis.—It is shorter, thicker, and somewhat denser (*Schmulewitsch*); stiff, compact, and solid; turbid and opaque (owing to the coagulation of the myosin); incompletely elastic, less extensible, and more easily torn or ruptured; it is completely inexcitable to stimuli; the muscular electrical current is abolished (or there is a slight current in the opposite direction); its reaction is *acid*, owing to the formation of both forms of lactic acid (§ 293), glycero-phosphoric acid (*Diakanow*); while it also develops free CO_2. When an incision is made into a rigid muscle, a fluid, the muscle serum, appears spontaneously in the wound (§ 293).

The first formed lactic acid converts the salts of the muscle into acid salts; thus, potassium lactate and acid potassium phosphate are formed from potassium phosphate. The lactic acid, which is formed thereafter, remains free and ununited in the muscle.

Amount of Glycogen.—The newest observations of Böhm are against the view that, during rigor mortis, a partial or complete transformation of the glycogen into sugar and then into lactic acid takes place. During digestion, a temporary storage of glycogen occurs in the muscles as well as in the liver, so that about as much is found in the muscles as in the liver. There is no diminution of the glycogen when rigidity takes place, provided putrefaction be prevented; so that the lactic acid of rigid muscles cannot be formed from glycogen, but more probably it is formed from the decomposition of the albuminates (*Demant, Böhm*).

The **amount of acid** does not vary, whether the rigidity occurs rapidly or slowly (*J. Ranke*); when acidification begins, the rigidity becomes more marked, owing to the coagulation of the alkali-albuminate of the muscle. Less CO_2 is formed from a rigid muscle, the more CO_2 it has given off previously, during muscular exertion. A rigid muscle gives off N, and absorbs O. In a cadaveric rigid muscle, **fibrin ferment** is present (*Al. Schmidt and others*). It seems to be a product of protoplasm, and is never absent where this occurs (*Rauschenbach*). [The myosin ferment seems not to be identical with the fibrin ferment (p. 512).]

[**Rigor Mortis and Coagulation of Blood.**—Thus, there is a marked analogy between the coagulation of the blood and that of muscle. In both cases, a fluid body yields a solid body, fibrin from blood, and myosin from muscle; the coagulation of blood is prevented by neutral salts, and so is the coagulation of myosin; dilution of the salted plasma produces coagulation in both cases; and perhaps the coagulation in both is due to the action of a ferment, the one the fibrin ferment, the other the myosin ferment. There are, however, points of difference, for myosin can be dissolved, reprecipitated, and coagulated several times, while fibrin does not undergo recoagulation; the formation of myosin from myosinogen, again, is accompanied by the development of an acid, whereas that of fibrin from fibrinogen is not; further, the formation of myosin is not accompanied by the formation of another globulin, whereas that of fibrin from fibrinogen is.]

Stages of Rigidity.—Two stages are recognizable in cadaveric muscles: In the **first stage**, the muscle is rigid, but still excitable; in this stage the myosin seems to be in a jelly-like condition. Restitution is still possible during this stage. In the **second stage**, the rigidity is well pronounced, with all the phenomena above mentioned.

The onset of the rigidity varies in man from ten minutes to seven hours [but as a rule it is complete within four to six hours after death. The muscles of the jaws are first affected, then those of the neck and trunk, afterward (as a rule) the lower limbs, and finally the upper limbs]. Its **duration** is equally variable—one to six days. After the cadaveric rigidity has disappeared, the muscles, owing to further

decompositions and an alkaline reaction, become soft, and the rigidity disappears (*Nysten*). The onset of the rigidity is always preceded by a loss of nervous activity. Hence, the muscles of the head and neck are first affected, and the other muscles in a descending series (§ 352). Disappearance of the rigidity occurs first in the muscles first affected (*Nysten*). Great muscular activity before death (*e. g.*, spasms of tetanus, cholera, strychnin, or opium poisoning) causes rapid and intense rigidity; hence, the heart becomes rigid relatively rapidly, and strongly. Hunted animals may become affected within a few minutes after death. Usually the rigidity lasts longer the later it occurs. Rigidity does not occur in a fœtus before the seventh month. A frog's muscle cooled to 0° C. does not begin to exhibit cadaveric rigidity for four to seven days.

Stenson's Experiment.—The **amount of blood** in a muscle has a marked effect upon the onset of the rigidity. Ligature of the muscular arteries causes at first in all mammals an increase of the muscular excitability, and then a rapid fall of the excitability (*Schmulewitsch*); thereafter stiffness occurs, the one stage following closely upon the other (*Swammerdam, Nic. Stenson*, 1667). [If the ligature be removed in the first stage, the muscle recovers, but in the later stages the rigidity is permanent.] If the artery going to a muscle be ligatured, Stannius observed that the excitability of the motor nerves disappeared after an hour, that of the muscular substance after four to five hours, and then cadaveric rigidity set in.

Pathological.—When the blood vessels of a muscle are occluded, by coagulation taking place within them, rigidity of the muscles is produced (§ 102). True cadaveric rigidity may be produced by too tight bandaging; the muscles are paralyzed, rigid, and break up into flakes, while the contents of the fibre are afterward absorbed (*R. Volkmann*). Occlusion of the blood vessels of muscles by infarcts, especially in persons with atheromatous arteries, may even cause necrosis of the muscles implicated (*Finch, Girandeau*).

If the **circulation be re-established** during the first stage of the rigidity, the muscle soon recovers its excitability (*Stannius*). When the second stage has set in, restitution is impossible (*Kühne*). In cold-blooded animals, cadaveric rigidity does not occur for several days after ligaturing the blood vessels. Brown-Sèquard, by injecting fresh oxygenated blood into the blood vessels, succeeded in restoring the excitability of the muscles of a human cadaver four hours after death, *i. e.*, during the first stage of cadaveric rigidity. Ludwig and Al. Schmidt found that the onset of cadaveric rigidity was greatly retarded in excised muscles, when arterial blood was passed through their blood vessels. Blood deprived of its O did not produce this effect. Cadaveric rigidity occurs relatively early after severe hemorrhage. If a weak alkaline fluid be perfused through the blood vessels of the dead muscles of a frog, cadaveric rigidity is prevented (*Schipiloff*).

Section of Nerves.—Preliminary **section of the motor nerves** causes a later onset of the rigidity in the corresponding muscles (*Brown-Sèquard, Heineke*). [The same result occurs after a hemi-section of the spinal cord or after removal of one cerebral hemisphere (*Bierfreund*).] In fishes, whose medulla oblongata is suddenly destroyed, cadaveric rigidity occurs much more slowly than in those animals that die slowly (*Blane*).

[**Other Influences.**—Rigidity begins much later in the red (11 to 15 hours) than in pale muscles (1 to 3 hours post-mortem); the rigor is complete in the white muscles in 10 to 14 hours, in the red in 52 to 58 hours. The extent of shortening due to the rigor is 2 to 2½ times as great as in the white. In both muscles the resolution of the rigor begins 12 to 15 hours after the completion of the rigidity, so that the red muscles are not completely rigid before the other muscles appear to have passed from a state of rigidity. Temperature has a marked effect, but it acts more on the resolution than on the onset of the rigor. At 60° C. the onset begins almost at once, and is complete in a few minutes (*Bierfreund*). Ether and chloroform injected into the blood vessels cause almost instantaneous rigor (*Kussmaul*).]

Rigidity may be produced **artificially** by various reagents:—

1. **Heat** ["**Heat stiffening**"] causes the myosin to coagulate at 40° C. in

cold-blooded animals, in birds about 53° C., and in mammals at 48° to 50° C. The protoplasm of plants and animals, *e. g.*, of the amœba, is coagulated by heat, giving rise to heat rigor.

Schmulewitsch found that the longer a muscle had been excised from the body, the greater was the heat required to produce stiffening. Heat stiffening differs from cadaveric rigidity thus: a 13 per cent. solution of ammonium chloride dissolves out the myosin from a cadaveric rigid muscle, but not from one rendered rigid by heat (*Schipiloff*). If the rigid cadaveric muscles of a frog be heated, another proteid coagulates at 45°, and lastly at 75° the serum albumin itself. Hence, both processes together make the muscle more rigid (§ 295).

2. When a muscle is saturated with **distilled water**, it produces "**water stiffening**"—an acid reaction being developed at the same time.

Muscles rendered stiff by water still exhibit electro-motive phenomena, while muscles rendered rigid by other means do not (*Biedermann*). If the upper limb of a frog be ligatured, deprived of its skin, and dipped in warm water, it becomes rigid. If the ligature be removed and the circulation reëstablished, the rigidity may be partially set aside. If there be well-marked rigidity, it can only be set aside by placing the limb in a 10 per cent. solution of common salt, which dissolves the coagulum of myosin (*Preyer*).

3. **Acids**, even CO_2, rapidly produce "**acid stiffening**," which is probably different from ordinary stiffening, as such muscles do not evolve any free CO_2 (*L. Hermann*). The injection of 0.1 to 0.2 per cent. solutions of lactic or hydrochloric acid into the muscles of a frog produces stiffening at once, which may be set aside by injecting 0.5 per cent. solution of an acid, or by a solution of soda, or by 15 per cent. solution of ammonium chloride. The acids form a compound with myosin (*Schipiloff*).

4. **Freezing** and **thawing** a part alternately, rapidly produce stiffening; and it is aided by **mechanical injuries.**

Poisons.—Rigor mortis is favored by quinine, caffein, digitalin [a concentrated solution of caffein or digitalin, applied to the muscle of a frog, produces rigor mortis], veratrin, hydrocyanic acid, ether, chloroform, the oil of mustard, fennel, and aniseed; direct contact of muscular tissue with potassium sulphocyanide (*Bernard, Setschenow*), ammonia, alcohol, and metallic salts.

Position of the Body.—The attitude of the body during cadaveric rigidity is generally that occupied at death; the position of the limbs is the result of the varying tensions of the different muscles. During the occurrence of rigor mortis, a limb, or more frequently the arm and fingers, may move (*Sommer*). Thus, if stiffening occurs rapidly and firmly in certain groups of muscles, this may produce movements, as is sometimes seen in cholera. If cadaveric rigidity occurs very rapidly, the body may occupy the same position which it did at the moment of death, as sometimes happens on the battle field. In these cases it does not seem that a contracted condition of the muscle passes at once into rigor mortis; but between these two conditions, according to Brücke, there is always a very short relaxation.

Muscles which have been plunged into **boiling water** do not undergo rigor mortis, neither do they become acid (*Du Bois-Reymond*), nor evolve free CO_2 (*L. Hermann*).

Work done during Rigidity.—A muscle in the act of becoming stiff will lift a weight, but the height to which it is lifted is greater with small weights, less with heavier weights, than when a living muscle is stimulated with a maximal stimulus.

Analogy between Contraction and Rigidity.—L. Hermann has drawn attention to the analogy which exists between a muscle in a state of contraction and one in a state of cadaveric rigidity—both evolve CO_2 and the other acids from the same source; [both acts take place without the consumption of O]. The form of the contracted and of the stiffened muscles is shorter and thicker; both are denser, less elastic, and evolve heat; in both cases, the muscular contents behave negatively as regards their electro-motive force, in reference to the unaltered, living, resting substance. Hence, he is inclined to regard a muscular contraction as a temporary, physiological, rapidly disappearing rigor. Rigor mortis is in a certain sense the last flickering act of a living muscle [and he regards contraction as partial death of a muscle. But this is no explanation, and moreover there are important points of difference. We have no proof of a coagulum being formed during contraction, while the extensibility is increased during contraction and much diminished during rigor.]

Disappearance of Rigidity.—When rigor mortis passes off, there is a considerable amount of acid formed in the muscle, which dissolves the coagulated myosin. After a time **putrefaction** sets in, accompanied by the presence of microörganisms and the evolution of ammonia and putrefactive gases (H_2S, N, CO_2 —§ 184). [Hermann and Bierfreund attach much importance to the resolution of rigor mortis independently of putrefaction.]

According to Onimus, the **loss of excitability** which precedes the onset of rigor mortis occurs in the following order in man: left ventricle, stomach, intestine (55 minutes); urinary bladder, right ventricle (60 min.); iris (105 min.); muscles of face and tongue (180 min.); the extensors of the extremities (about one hour before the flexors); the muscles of the trunk (five to six hours). The œsophagus remains excitable for a long time (§ 325).

296. MUSCULAR EXCITABILITY.—By the term **excitability** or **irritability** of a muscle, is meant that property of a muscle in virtue of which it responds to stimuli, at the same time becoming shorter and correspondingly thicker. The condition of excitement is the active condition of a muscle produced by the application of stimuli, and is usually indicated by the act of contraction. **Stimuli** are simply various forms of energy, and they throw the muscle into a state of excitement, while at the moment of activity the chemical energy of the muscle is transformed into work and heat, so that stimuli act as "**liberating**" or "**discharging forces.**" [These "discharging forces" may themselves be very feeble, but they are capable of causing the manifestation of the transformation of a large amount of energy.] The normal temperature of the body is most favorable for maintaining the normal muscular excitability; the excitability varies as the temperature rises or falls.

As long as the **blood stream** within a muscle is uninterrupted, the first effect of stimulation of a muscle is to increase its energizing power, partly because the circulation is more lively and the blood vessels are dilated, but after a time, the energizing power is diminished. Even in excised muscles, especially when the large nerve trunks have already lost their excitability, the excitability is increased after a stimulus, so that the application of a series of stimuli of the same strength causes a series of contractions which are greater than at first (*Wundt*). Hence, we account for the fact that, although the first feeble stimulus may be unable to discharge a contraction, the second may, because the first one has increased the muscular excitability (*Fick*).

Effects of Cold.—If the muscles of a frog or tortoise be kept in a cool place, they may remain excitable for ten days, while the muscles of warm-blooded animals cease to be excitable after one and a half to two and a half hours. (For the heart, see § 55.) A muscle, when stimulated *directly*, always remains excitable for a longer time when its motor nerve is already dead.

[**Independent Muscular Excitability.**—Since the time of Albrecht v. Haller, and R. Whytt, physiologists have ascribed to muscle a condition of excitability which is entirely independent of the existence of motor nerves, but is dependent on certain constituents of the sarcous substance. Excitability, or the property of responding to a stimulus, is a widely distributed function of protoplasm or its modifications. A colorless blood corpuscle or an amœba is excitable, and so are secretory and nerve cells. In the first case, the application of a stimulus results in motion in an indefinite direction, in the second in the formation of a secretion, and in the third in the discharge of nerve energy. In the case of muscle, a stimulus causes movement in a definite direction, called a contraction, and depending on the contractility of the sarcous substance. There are many considerations which show that *excitability is independent of the nervous system*, although in the higher animals, nerves are the usual medium through which the excitability is brought into action. Plants, however, are excitable, and they contain no nerves.]

Numerous experiments attest the "**independent excitability**" of muscles: 1. There are chemical stimuli, which do not cause movement when applied to motor nerves, but do so when they are applied directly to muscle; ammonia, lime-water,

carbolic acid. 2. The ends of the sartorius of the frog, in which no ner terminations are observable by means of the microscope, contract when they a stimulated directly (*Kühne*). 3. Curara paralyzes the extremities of the mot nerves, while the muscles themselves remain excitable (*Cl. Bernard, Kölliker* The action of *cold*, or *arrest of the blood supply* in an animal, abolishes t excitability of the nerves, but not of the muscles at the same time. 4. Aft section of its nerve, a muscle still remains excitable, even after the nerves ha undergone fatty degeneration (*Brown-Séquard, Bidder*). 5. Sometimes electri stimuli act only upon the nerves, and not upon the muscle itself (*Brücke*). The fœtal heart contracts rhythmically before any nervous structures are discov able in it.]

[**The Action of Curara.**—Curara, woorali, urari, or Indian arrow poison of South Americ the inspissated juice of the Strychnos crevauxi. A watery extract of the drug, when injected u the skin or into the blood of an animal, acts chiefly upon the **motor nerve endings**, and doe affect the muscular contractility. An active substance, *curarin*, has been isolated from it (p. 23). Poison a frog by injecting a few milligrammes into the dorsal lymph sac. In a few minutes afte poison is absorbed, the animal ceases to support itself on its fore-limbs; it lies flat on the tab limbs are paralyzed, and so are the respiratory movements in the throat. When completely under the action of the poison, the frog lies in any position, limp and motionless, neither exhibiting volun tary nor reflex movements. If the brain be destroyed and the skin removed, on faradizing the sciatic nerve, no contraction of the muscles of the hind limb occurs; but if the electrical stimulus be applied directly to the muscles, they contract, thus proving that curara poisons the **motor connections** and not the muscles. If the dose be not too large, the heart still continues to beat, and the vasomotor nerves remain active.]

[**Methods.—(1) Local Application.**—Bernard took two nerve-muscle preparations, put some solution of curara into two watch glasses, and dipped the nerve into one glass and the muscle of the other preparation into the other glass. The curara penetrated into both preparations, and he found, on stimulating the nerve which had been steeped in curara, that its muscle still contracted, so that the curara had not acted on the motor nerve fibres; while stimulation of the nerve of the other preparation produced no contraction, although the corresponding muscle contracted. In the latter case, the curara had penetrated into the muscle and affected the **intra-muscular portions of the nerve.**]

[(2) But it is the terminal or **intra-muscular portions** of the nerves, not the nerve trunk, which are paralyzed. Ligature the sciatic artery, or, better still, tie all the parts of the hind limb of a frog, except the sciatic nerve, at the upper part of a thigh (Fig. 315). Inject curara into the dorsal lymph sac. The poisoned blood will, of course, circulate in every part of the body except the ligatured limb. The shaded parts are traversed by the poison. The animal can still, at a certain stage of the poisoning, pull up the non-poisoned limb, while it cannot move the poisoned one. At this time, although poisoned blood has circulated in the sacral and intra-abdominal parts of the nerves, yet they are not paralyzed, so that the poison does not act on this part of the trunk of the nerve. But we can show that it does not act on any part of the extra-muscular trunk of the nerve. This is done by ligaturing the arteries going to the gastrocnemius muscle, and then poisoning the animal. On stimulating the nerve on the ligatured side, the gastrocnemius of that side contracts, although the whole length of the nerve trunk was supplied by poisoned blood. Therefore, it is the *intra-muscular terminations* of the nerves which are acted on.]

[By means of the following arrangement we may prove that the terminal parts of the nerve are paralyzed. Ligature the sciatic artery of one leg of a frog, and then inject curara into a lymph sac. After the animal is fully poisoned, expose the sciatic nerve in both legs, leaving all the muscles below the knee joint; then clean and divide the femur at its middle. Pin a straw flag to each limb, and fix both femora in a clamp, with the gastrocnemii uppermost, as in Fig. 316. Place the two nerves, N, on electrodes attached to two wires coming from a commutator,

C (Fig. 316). From the opposite binding screws of the commutator two wires pass to the gastrocnemii. The other two binding screws of the commutator are connected with the secondary coil of an induction machine (§ 330). The bridge of the commutator can be turned so as to pass the current either through both muscles or both nerves—the latter is the case in the diagram (H). When *both nerves* are stimulated, only the *non-poisoned leg* (NP) contracts. Reverse the commutator, and pass the current through *both muscles*, when *both contract.*]

[**Rosenthal's Modification.**—Pull the secondary coil far away from the primary, and pass the current through both muscles. Gradually approximate the secondary to the primary coil, and in doing so it will be found that the non-poisoned leg contracts first, but on continuing to push up the secondary coil, both limbs contract. Thus, the poisoned limb does not respond to so feeble a faradic stimulus as the non-poisoned one, a result which is not due to the action of the curara on the excitability of the muscle. The non-poisoned limb responds to a feebler stimulus because its motor nerve terminations are not paralyzed, while the poisoned leg does not do so, because the motor terminations are paralyzed. A feebler induced shock suffices to cause a muscle to contract when it is applied to

FIG. 315.

Frog with sciatic artery ligatured. S.P., spinal cord with afferent and efferent nerves; P., poisoned, N.P., non-poisoned leg; M, gastrocnemius muscles.

FIG. 316.



Scheme of the curara experiment. B, battery; I, primary; II, secondary spiral; N, nerves; F, clamp; NP, non-poisoned leg; P, poisoned leg; C, commutator; K, key.

the nerve than when it is applied to the muscle itself directly. In large doses, curara also affects the spinal cord (p. 523).]

[**On what structures does curara act?**—These experiments prove that curara does not paralyze the motor nerve trunks, nor the muscular fibres, and that it acts on the motor terminations within the muscles, but they do not enable us to state the precise part of the nerve ending so affected. It may act on (1) the nerve just before it pierces the sarcolemma, (2) the sub-lemmar axis cylinder, (3) the end plates, (4) the terminal branches or spray. Kühne and Pollitzer have made it probable that, even when a muscle is thoroughly impregnated with curara, some of the nervous apparatus is unaffected. The sartorius is most excitable where there are most nerves (Fig. 318), and even in a muscle profoundly poisoned with curara, the distribution of excitability varies with the number of nerves in the several parts of the muscle (Fig. 317) just as in a normal muscle, with this difference, that the excitability of all the parts of the muscle containing nerves is less than normal. That this variation in excitability is due to nervous structures, is shown by using a polarizing anelectrotonic current (§ 335), which depresses the excitability of nerve fibres, and then this difference of excitability disappears, the curve of excitability running parallel with the abscissa, so that the difference does not seem to be due to purely muscular causes.]

[Pollitzer, speculating as to which part of the terminal nerve is affected, supposes that all parts

beyond the last node of Ranvier retain their functions, and he supposes that it is not the axis cylinders themselves, but the cement at the nodes, on which the drug exerts its specific action.]

Neuro-Muscular Cells.—Even in the lower animals, *e. g.*, Hydra and Medusæ, there are unicellular structures called "*neuro-muscular cells*," in which the nervous and muscular substances are represented in the same cell (*Kleinenberg and Eimer*). [The outer part of these cells is adapted for the action of stimuli, and corresponds to the nervous receptive organ, while the inner deeper part is contractile, and is the representative of the muscular part.]

Muscular Stimuli.—Various stimuli cause a muscle to contract, either by acting upon its motor nerve, or upon the muscular substance itself (§ 324). [The former is called **indirect stimulation,** the latter **direct stimulation.**]

1. Under ordinary circumstances, the **normal stimulus** exciting a muscle to contract is the **nerve impulse** which passes along a nerve, but its exact nature is unknown.

2. **Chemical Stimuli.**—All chemical substances which alter the chemical composition of a muscle with sufficient rapidity, act as *muscular stimuli*. Mineral acids (HCl 0.1 per cent.), acetic and oxalic acids, the salts of iron, zinc, copper,

FIG. 317.

Curve showing the excitability in the sartorius of a frog in a normal and curarized muscle.

FIG. 318.

Distribution of nerves in the sartorius of a frog and the curve of excitability in different parts of the muscle, *i. e.*, the excitability is greatest where there are most nerve endings.

silver, and lead, bile, all act in weak solutions as muscular stimuli; they act upon the motor nerve only when they are more concentrated. Lactic acid and glycerin, when concentrated, excite only the nerve; when dilute, only the muscle. [The lower end of the sartorius, which contains no nerves, may be dipped into glycerin, and it will not contract, but if it be dipped deeper to where there are nerve endings, it will contract at once.] Neutral alkaline salts act equally upon nerve and muscle; alcohol and ether act on both very feebly. When water is injected into the blood vessels, it causes fibrillar muscular contractions (*v. Wittich*), while a 0.6 per cent. solution of NaCl may be passed through a muscle for days without causing contraction (*Kölliker, O. Nasse*). [Carslaw, under Ludwig's direction, however, found that solutions containing 0.5 to 0.2 per cent. NaCl, when perfused through the muscles of a frog, excite many short, powerful attacks of tetanus, separated from each other by periods of rest. Solutions containing 0.5 to 0.7 per cent. NaCl, *i. e.*, so-called "indifferent fluids" or "normal saline," are not without

influence, but of all known saline solutions, they injure a nerve-muscle preparation least. Solutions of 1 to 2 per cent. rapidly kill the muscle.] Acids, alkalies, and extract of flesh diminish the muscular excitability, while the muscular stimuli, in small doses, increase it (*Ranke*). *Gases* and *vapors* stimulate muscle; they cause either a simple contraction (*e. g.*, HCl), or at once permanent contraction or contracture (*e. g.*, Cl). Long exposure to the gas causes rigidity. The vapor of bisulphide of carbon stimulates only the *nerves*, while most vapors (*e. g.*, HCl) kill without exciting them (*Kühne and Jani*).

Method.—In making experiments upon the chemical stimulation of muscle, it is inadvisable to dip the transverse section of the muscle into the solution of the chemical reagent (*Hering*). The chemical stimulus ought to be applied in solution to a limited portion of the uninjured surface of the muscle; after a few seconds, we obtain a contraction or fibrillar twitchings of the superficial muscular layers (*Hering*).

[**Rhythmical Contraction.**—While rhythmical contractions are very marked in smooth muscle, (especially if it is stretched or subjected to considerable internal pressure, as in the hollow viscera), *e. g.*, the intestine, uterus, ureter, blood vessels, and also in the striped but involuntary cardiac musculature (§ 58), they are not, as a rule, very common in striped voluntary muscle. Chemical stimuli are particularly effective in producing them.] If the sartorius of a curarized frog be dipped into a solution composed of 5 grms. NaCl, 2 grms. alkaline sodium phosphate, and 0.5 grm. sodium carbonate in 1 litre of water, at 10° C., the muscle contracts **rhythmically**, and may do so for several days, especially with a low temperature (*Biedermann*). This recalls the rhythmical contraction of the heart. [Kühne found a similar result. The rhythm is arrested by lactic acid and restored by an alkaline solution of NaCl.] Rhythmical movements may also be induced in the sartorius (frog), by the combined action of a dilute solution of sodic carbonate and an ascending constant electrical current. Compare also the action of a constant current on the heart (§ 58).

3. **Thermal Stimuli.**—If an excised frog's muscle be rapidly heated to 28° C., a gradually increasing contraction occurs, which, at 30° C., is more pronounced, reaching its maximum at 45° C. If the temperature be raised, "**heat stiffening**" rapidly ensues. The *smooth* muscles of warm-blooded animals also contract when they are warmed, but those of cold-blooded animals are elongated by heat (*Grünhagen*). If a frog's muscle be cooled to 0°, it is very excitable to mechanical stimuli (*Grünhagen*); it is even excited by a temperature under 0° (*Eckhard*).

Cl. Bernard observed that the muscles of animals, artificially cooled, remained excitable many hours after death (§ 225). Heat causes the excitability to disappear rapidly, but increases it temporarily.

4. **Mechanical Stimuli.**—Every kind of sudden mechanical stimulus, provided it be applied with sufficient rapidity to a muscle (and also to a nerve), causes a *contraction*. If stimuli of sufficient intensity be repeated with sufficient rapidity, *tetanus* is produced. *Strong local* stimulation causes a wheal-like, long-continued contraction at the part stimulated (§ 297, 3, *a*). Moderate tension of a muscle increases its excitability.

5. **Electrical Stimuli** will be referred to when treating of the stimulation of nerve (§ 324).

Other Actions of Curara.—When it is injected into a **frog**, either into the blood or subcutaneously, it causes at first paralysis of the *intra-muscular ends of the motor nerves* (p. 520), while the muscles themselves remain excitable. The sensory nerves, the central nervous system, viscera, heart, intestine, and the blood vessels are not affected at first (*Cl. Bernard, Kölliker*). [If the skin be stimulated, the frog pulls up the ligatured leg reflexly, although the other leg remains quiescent; this shows that the **sensory nerve** and **nerve centres** are still intact; but when the action of the drug is fully developed, no amount of stimulation of the skin or the posterior roots of the nerves will give rise to a reflex act, although the motor nerve of the ligatured limb is known to be excitable; hence, it is probable that the nerve centres in the cord themselves are ultimately affected. If the dose be very large, the heart and blood vessels are affected.] In **warm-blooded animals**, death takes place by **asphyxia**, owing to paralysis of the diaphragm, but of course there are no spasms. In **frogs**, where the skin is the most important respiratory organ, if a suitable dose be injected subcutaneously, the animal may remain motionless for days and yet recover, the poison being eliminated by the urine (*Kühne*). If the dose be large, the inhibitory fibres of the vagus may be paralyzed. In electrical fishes, the sensory nerves, and in frogs, the lymph hearts are paralyzed. A dose sufficient to kill a frog, when injected under its skin, will not do so if administered by the mouth, because the poison seems to be eliminated as rapidly by the kidneys as it is absorbed from the gastric mucous membrane. For the same reason the flesh of an animal killed by curara is not poi-

sonous when eaten. If, however, the ureters be tied, the poison collects in the blood, and poisoning takes place (*L. Hermann*). [In this case the mammal may exhibit convulsions. Why? Curara paralyzes the respiratory nerves, so that asphyxia is produced from the venosity of the blood. It affects the respiratory nerve endings before those in the muscles generally, so that when the venous blood stimulates the nerve centres, the partially affected muscles respond by convulsions. Other narcotics may excite convulsions indirectly by inducing a venous condition of the blood, while the motor centres, nerves, and muscles are still unaffected.] Large doses, however, poison uninjured animals even when given by the mouth. The nerves and muscles of poisoned animals exhibit considerable electro-motive force. [For the effect of curara on lymph formation see (§ 199, 6).]

Atropin appears to be a specific poison for **smooth muscular tissue**, but different muscles are differently affected (*Szpilmann, Luchsinger*). [This is doubtful. A small quantity of atropin seems to affect the motor nerves of smooth muscle in the same way that curara does those of striped muscle; we must remember, however, that there are no end plates proper in the former, so that the link between the nerve fibrils and the contractile substance is probably different in the two cases. It is well known that the amount of striped and smooth muscle varies in the œsophagus in different animals. Szpilmann and Luchsinger found that, after the action of atropin, stimulation of the peripheral end of the vagus will still cause contraction of the striped muscular fibres in the œsophagus, but not of the smooth fibres, although both forms of muscular tissue respond to direct stimulation.]

After **section of the motor nerve** of a muscle, the excitability undergoes remarkable changes; after three to four days the excitability of the paralyzed muscle is diminished, both for direct and indirect stimuli (p. 522); this condition is followed by a stage, during which a constant current is more active than normal, while induced currents are scarcely or not at all effective (§ 339, 1). The excitability to mechanical stimuli is also increased. The increased excitability occurs until about the seventh week; it gradually diminishes until it is abolished toward the sixth to the seventh month. Fatty degeneration begins in the second week after section of the motor nerve, and goes on until there is complete muscular atrophy. Immediately after section of the sciatic nerve, Schmulewitsch found that the excitability of the muscles supplied by it was increased.

297. CHANGES IN A MUSCLE DURING CONTRACTION.—

I. Macroscopic Phenomena.—1. When a muscle contracts, it becomes **shorter** and at the same time correspondingly **thicker.**

The degree of contraction, which in very excitable frogs may be 65 to 85 per cent. (72 per cent. mean) of the total length of the muscle, depends upon various conditions: (*a*) Up to a certain point, increasing the **strength of the stimulus** causes a greater degree of contraction; (*b*) as the **muscular fatigue** increases, *i. e.*, after continued vigorous exertion, the stimulus remaining the same, the extent of contraction is diminished; (*c*) the **temperature** of the surroundings has a certain effect. The extent of the contraction is increased in a frog's muscle—the strength of stimulus and degree of fatigue remaining the same—when it is heated to 33° C. If the temperature be increased above this point, the degree of contraction is diminished (*Schmulewitsch*).

2. The **volume** of a contracted muscle is slightly diminished (*Swammerdam*, † 1680). Hence, the **specific gravity** of a contracted muscle is slightly increased, the ratio to the non-contracted muscle being 1062 : 1061 (*Valentin*); the diminution in volume is, however, only $\frac{1}{1370}$, although this has recently been denied by J. Ewald.

Methods.—(*a*) Erman placed portions of the body of a live eel in a glass vessel filled with an indifferent fluid. A narrow tube communicated with the glass vessel, and the fluid rose in the tube to a certain level. As soon as the muscles of the eel were caused to contract, the fluid in the index tube sank. (*b*) Landois demonstrates the decrease in volume by means of a manometric flame. The cylindrical vessel containing the muscle is provided with two electrodes fixed into it in an air-tight manner. The interior of the vessel communicates with the gas supply, while there is a small, narrow exit tube for the gas, which is lighted. Every time the muscle contracts, the flame diminishes. The same experiment may be performed with a contracting heart.

3. **Total and Partial Contraction.**—Normally, all stimuli applied to a muscle or its motor nerve cause contraction in all its muscular fibres. Thus, the muscle conducts the state of excitement to all its parts. Under certain circumstances, however, this is not the case, viz.: (*a*) When the muscle is greatly fatigued, or when it is about to die, *violent mechanical* stimuli, as a vigorous tap with the finger or a percussion hammer (and also chemical or electrical stimuli), cause a localized contraction of the muscular fibres. This is Schiff's "**idio-muscular contraction.**" The same phenomenon is exhibited by the muscles of a healthy man, when the blunt edge of an instrument is drawn transversely over the direction of the muscular fibres. (*b*) Under certain as yet but imperfectly known conditions, a muscle exhibits

so-called **fibrillar contractions,** *i. e.*, short contractions occur alternately in different bundles of muscular fibres. This is the case in the muscles of the tongue, after section of the hypoglossal nerve; and in the muscles of the face, after section of the facial nerve.

[In some phthisical patients there is marked muscular excitability, so that if the pectoral muscle be percussed, a local contraction—idio-muscular—occurs, either confined to the spot, or two waves may proceed outward and return to the spot struck.]

Cause of Fibrillar Contraction.—According to Bleuler and Lehmann, section of the hypoglossal nerve in rabbits is followed by fibrillar contractions after sixty to eighty hours; these contractions may continue for months, even when the divided nerve has healed and is stimulated above the cicatrix so as to produce movements in the corresponding half of the tongue. Stimulation of the lingual nerve increases the fibrillar contractions or arrests them. This nerve contains vaso-dilator fibres derived from the chorda tympani. Schiff is of opinion that the increased blood stream through the organ is the cause of the contractions. Sig. Mayer found that, by compressing the carotids and subclavian, and again removing the pressure so as to permit free circulation, the muscles of the face contracted. Section of the motor nerves of the face did not abolish the phenomenon, but compression of the arteries did. The cause of the phenomenon, therefore, seems to lie within the muscles themselves. This phenomenon may be compared to the *paralytic secretion* of saliva and pancreatic juice which follows section of the nerves going to these glands (pp. 258, 303). Similar fibrillar contractions occur in man under pathological conditions, but they may also occur without any signs of pathological disturbance. [Fibrillar contractions, due to a central cause, occur in monkeys after excision of the thyroid gland (§ 103, III). Some **drugs** cause fibrillar contractions, *e. g.*, aconitin, guanidin, nicotin, pilocarpin, but physostigmin produces them in warm-blooded animals (not in frogs). According to Brunton these drugs probably act by **irritating the motor nerve endings,** as the contractions are gradually abolished by curara.]

II. Microscopic Phenomena.—1. Single muscular *fibrillæ* exhibit the same phenomena as an entire muscle, in that they contract and become thicker. 2. There is great difficulty in observing the changes that occur in the individual parts of a muscular fibre during the act of contraction. This much is certain, that the muscular elements become shorter and broader during contraction, and that the transverse striæ approach nearer to each other (*Bowman*, 1840). 3. There is great difference of opinion as to the behavior of the doubly refractive (anisotropous) and the singly refractive media.

Engelmann's View.—Fig. 319, 1, on the left represents a passive muscular element—from *c* to *d* is the doubly refractive contractile substance, with the median disk, *a*, *b*, in it; *h* and *g* are the lateral disks. Besides these, in each of the singly refractive disks there is a *clear* disk—"secondary disk" *f* and *e*, which is only slightly doubly refractive. This occurs only in the muscles of insects. Fig. 1, on the *right*, shows the same element in polarized light, whereby the middle area of the element, as far as the contractile substance proper extends, is, owing to its double refraction, bright; while the other part of the muscular element, owing to its being singly refractive, is black. Fig. 319, 2, is the transition stage, and 3 the proper stage of contraction of the muscular element. In both cases, the figures on the *left* are viewed in ordinary light, and on the *right*, in polarized light. During contraction (Fig. 319, 3), the singly refractive disk becomes as a whole more refractive, the doubly refractive less so. Consequently, a fibre at a certain degree of contraction (2), when viewed in *ordinary* light, may appear homogeneous and but slightly striped transversely = *the homogeneous or transition stage.* During a greater degree of contraction (3), very dark transverse stripes reappear, corresponding to the singly refractive disks. At every stage of the contraction, as well as in the transition stage, the singly and doubly refractive disks are sharply defined, and are recognized by the polariscope as regular alternating layers (in 1, 2, and 3 on the

FIG. 319.



The microscopic appearances during a muscular contraction in the individual elements of the fibrillæ. 1, 2, 3 (after *Engelmann*); 4, 5 (after *Merkel*).

right). These do not change places during the contraction. The height of both disks is diminished during contraction, but the singly refractive do so more rapidly than the doubly refractive disks. The total volume of each element does not undergo any appreciable alteration in volume during the contraction. Hence, the doubly refractive disks increase in volume at the expense of the singly refractive. From this it is concluded that, during the contraction, fluid passes from the singly refractive into the doubly refractive disks; the former shrink, the latter swell.

Merkel's view is partially different. In Fig. 319, 4, are two muscular elements at rest; in (5), two in a state of contraction, after Merkel. The gray punctuated areas are the doubly refractive substance, *c*, the median disk. According to Merkel, during contraction the *dark* substance lying in the middle of the element changes its position—either in part or as a whole; it leaves the middle of the element (the two surfaces of Hensen's median disks, 4, *c*), and places itself at the lateral disks, 5 at *e* and *d*, while the clear substance leaves the lateral disk, 4, *e* and *d*, and applies itself to both surfaces of the median disk, 5, *c*. The clear substance of the isotropous disks is fluid, and plays a more passive rôle; during contraction it is in part absorbed by the dark substance which thus swells up. This mutual exchange of place of the substances is accompanied by an intermediate "*stage of dissolution*," in which the whole contents of the element appear equally homogeneous, in which, therefore, the fluid singly refractive substance has uniformly penetrated the doubly refractive substance. At this moment only the lateral disks are still visible.

[If a living portion of an insect's muscle be examined in its own juice, contraction waves may be seen to pass over the fibres. When a contraction wave passes over part of the fibres, the disks become *shorter* and *broader;* at the same time, in the fully contracted part, the dim disk appears lighter than the centre of the light disk. There is said to be a "**reversal of the stripes**" from what obtains in a passive muscle. Before this stage is reached, there is an intermediate stage where the two bands are almost uniform in appearance.]

Methods.—These phenomena are best observed by "fixing" the different stages of rest or contraction, by suddenly plunging the muscular fibrillæ of insect's muscles into alcohol or osmic acid, which coagulates the muscle substance. The actual contraction may be observed under the microscope in the transparent parts of the larvæ of insects.

Spectrum.—A thin muscle, *e.g.*, the sartorius of the frog, when placed directly behind a narrow slit running at right angles to the course of the fibres, yields a **diffraction spectrum.** When the muscle contracts, as by mechanical stimulation, the spectrum broadens, a proof that the interspaces of the transverse stripes become narrower (*Ranvier*).

298. MUSCULAR CONTRACTION.—Methods.—In order to determine the duration of each phase of a muscular contraction, **myographs** of various forms are used.

FIG. 320.



Scheme of v. Helmholtz's myograph. M, muscle fixed in a clamp, K; F, writing style; P, weight or counterpoise for the lever; W, scale pan for weights; S, S, supports for the lever.

v. Helmholtz's Myograph is shown in Fig. 320. A muscle, M—say the gastrocnemius of a frog attached to the femur—is fixed by the femur in a clamp, K; its lower end is attached to a movable lever carrying a scale pan and weight, W, the weight being varied at pleasure. When the muscle contracts, necessarily it raises the lever. At the free end of the lever is a movable style, F, which inscribes its movements on a revolving cylinder caused to rotate at a uniform rate by means of clockwork. The cylinder is covered with smoked enameled paper in the flame of a turpentine lamp. When the muscle contracts, it inscribes a curve—the "**muscle curve,**" or "**myogram.**" The **abscissa** of the curve indicates the **duration** of the contraction, but of course the rate at which the cylinder is moving must be known. The **ordinates** represent the **height** of contraction at any particular part of the curve.

The muscle curve may be inscribed upon a smoked glass plate attached to one limb of a vibrating tuning fork. Such a curve registers the time units in all its parts. Suppose each vibration of the tuning fork = 0.01613 second, then the duration of any part of such a curve is obtained by counting the number of vibrations and multiplying by 0.01613 second.

[**Fick's Pendulum Myograph.**—A board fixed to the wall carries a heavy iron **pendulum,** P, whose axis, A, A, moves on friction rollers (Fig. 321). At the lower swinging end are two glass

G and G′, fixed to a bearer, T. The plates can be adjusted by means of the screw, *s*, so that curves can be written one above the other. The plate, G′, on the posterior surface is merely pensator, so that, when G is elevated, G′ is lowered, and thus the duration of the oscillation is ered. The **spring catches**, H, H, which can be turned inward or outward, are used to fix ndulum by the teeth, *a*, *a*, when it is drawn to one side. The pendulum is drawn to one side ed, *a*, in H, so that when H is pulled down, it is liberated and swings to the other side, where ught by H at the opposite side. In the improved form, the catches, H, are made to slide along like the arc of a circle, so that the length of the swing can be varied. As the pendulum from one side to the other, the projecting points, *a*, *a*, knock over the **contact key**, *b*, and

FIG. 321.



Fick's pendulum myograph, as improved by v. Helmholtz ($\frac{1}{12}$ natural size), side and front view.

rrent is opened and a shock transmitted to the muscle. The **writing lever** to which the is attached is usually a heavy one, and a style writes upon the smoked surface of the glass. rse, when the pendulum swings, it moves with unequal velocities at different parts of its .]

en using the pendulum myograph to study a muscular contraction, arrange it as in Fig. 322. pg's muscle is attached to a writing lever, which is very like the lever in Fig. 321, while the scribes its movements on the blackened plate.]

e pendulum is fixed in the catch, C, as shown in the figure; the key, K′, is closed and placed

in the primary circuit, while two wires from the secondary coil of an induction machine are attached to the muscle. When the pendulum swings, the projecting tooth, S, knocks over the contact at K′, and breaks the primary circuit, when a shock is instantly transmitted through the muscle. Before stimulating, allow the pendulum to swing to obtain an abscissa. The time is recorded by a vibrating tuning fork, of known rate of vibration, connected with a Dupré's electric chronograph. Dupré's chronograph is merely a small electro-magnet with a fine writing style attached, which vibrates when it is introduced in an electrical circuit, in which is placed a vibrating tuning fork. The signal vibrates just as often as the tuning fork.]

[**Du Bois' Spring Myograph.**—It consists of a glass plate fixed in a frame, and moving on two polished steel wires, stretched between the supports A and B (Fig. 323). At *b* is a spring which, when it is compressed between the upright, B, and the knob, *b*, drives the glass plate from B to A. As the plate moves from one side to the other, a small tooth, *d*, on its under surface, opens the key, *h*, and thus a shock is transmitted to the muscle. The arrangement otherwise is the same as for the pendulum myograph. The smoked glass plate is liberated by the projecting finger plate attached to the upright, A.]

[**Marey's Simple Myograph.**—The gastrocnemius is attached to a horizontal lever, which inscribes its movements on a revolving cylinder. This form of myograph, when provided with two levers, is very useful for comparing the action of a poison on one limb, the other being unpoisoned.]

[**Pflüger's stationary form** is simply a Helmholtz's myograph (Fig. 320) arranged to record its movements on a stationary glass plate, so that the muscle merely makes a vertical line or ordinate instead of a curve; it thus merely indicates the height or extent of the contraction, not its duration.]

A **rapidly rotating disk** was used by Valentin and Rosenthal for registering the muscle curve, while Harless used a plate which was allowed to fall rapidly, the so-called "**Fallmyograph.**" In all these experiments it is necessary to indicate at the same time the moment of stimulation.

FIG. 322.



Scheme of the arrangement of the pendulum myograph. B, battery; I, primary, II, secondary spiral of the induction machine; S, tooth; K′, key; C, C, catches; K′, in the corner, scheme of K′; K, key in primary circuit.

Contraction Curve of Human Muscle.—In man, another principle is adopted, viz., to measure the increase in **thickness** during the contraction, either by means of a lever or a compressible tambour, such as is used in Brondgeest's pansphygmograph (Fig. 36). [The *thickening* of the adductor muscles of the thumb may be registered by means of Marey's **pince myographique.**]

I. Simple Contraction.—If a *single shock or stimulus of momentary duration* be applied to a muscle, a "**simple muscular contraction**" [or shortly, a *contraction* or **twitch**] is the result, *i. e.*, the muscle rapidly shortens and quickly returns again to its original relaxed condition.

Myogram or Muscle Curve.—Suppose a single stimulus be applied to a muscle attached to a light writing lever, which is not "overweighted" with any weight attached to it, then, when the muscle contracts, the following events take place:—

[(1) A period or stage of latent stimulation (Figs. 324, 325).
(2) A period of increasing energy or contraction.
(3) A period of decreasing energy or more rapid relaxation.
(4) A period of slow relaxation, or the elastic after vibration.]

The muscle curve proper is composed of 2, 3, and 4.

1. **The latent period** (Fig. 324, *a*, *b*) consists in this, that the muscle does not begin to contract precisely at the moment the stimulus is applied to it, but the contraction occurs somewhat *later*, *i. e.*, a short, but measurable interval, elapses between the application of a momentary stimulus and the contraction (*v. Helmholtz*). If the entire muscle be stimulated by a momentary stimulus, *e. g.*, a single

break induction shock, the duration of the latent period is about 0.01 second. In smooth muscle, the latent period may last for several seconds.

[Although no change be visible in a muscle during the latent period, nevertheless we have proof that some change does take place within the muscle substance,

FIG. 323.



Spring myograph or "shooter."

for we know that the electrical current of the muscle is diminished during this period, or we have what is known as the **negative variation** of the muscle current (*Bernstein*—§ 333).]

In man, the latent period varies between 0.004 and 0.01 second. If the experiment be so arranged that the muscle can contract as soon as the stimulus is applied to it, *i. e.*, before time is lost in making the muscle tense; or to put it otherwise, if the muscle has not "to take in slack," as it were, the latent period may fall below 0.004 second (*Gad*). If the muscle be still attached to the body, protected as much as possible from external influences and properly supplied with blood, the latent period may be reduced to 0.0033 or even 0.0025.

FIG. 324.



Muscle curve produced by a single induction shock applied to a muscle. *a–f*, abscissa; *a–c*, ordinate; *a b*, period of latent stimulation; *b d*, period of increasing energy; *d e*, period of decreasing energy; *e f*, elastic after vibrations.

Modifying Influences.—The latent period is shortened by an increased strength of the stimulus and by heat; while fatigue, cooling, and increasing weight lengthen it (*Lauterbach, Mendelssohn, Yeo, Cash*). The latent period of a break contraction is longer than that of a make contraction. The red muscles have a longer latent period than the white. Before the muscle contracts as a whole, the individual fibres within it must have contracted. We must, therefore, conclude that the latency of the individual muscular elements is shorter than that of the entire muscle (*Gad, Tigerstedt*).

2. **The contraction or stage of increasing energy,** *i. e.*, from the moment the muscle begins to shorten until it reaches its greatest degree of contraction (*b d*). At first the muscle contracts slowly, then more rapidly, and again more slowly, so that the ascending limb of the curve has somewhat the form of an *f*. The stage lasts 0.03 to 0.4 second. It is shorter when the contraction

is shorter (weak stimulus), and the less the weight the muscle has to lift. It also varies with the excitability of the muscle, being shorter in a fresh, non-fatigued muscle.

3. **Elongation or stage of decreasing energy.**—After the muscle has contracted up to its maximum for any particular stimulus, it begins to relax—at first slowly, then rapidly—and lastly more slowly, so that an inverse of an *f* is obtained (*d e*). This stage is usually of shorter duration than 2. The duration varies with the strength of the stimulus, being shorter than 2 with a weak stimulus, and longer with a strong stimulus. It also depends upon the extent to which the muscle is loaded during contraction.

4. The fourth stage has received various names—**stage of elastic after vibration** [**residual contraction** or **contraction remainder** (*Hermann*). The after vibrations (*e f*), which disappear gradually, depend upon the elasticity of the muscle. The duration of this stage is longest with a powerful contraction, and when the weight attached to the muscle is small].

If the stimulus be applied to the motor nerve instead of to the muscle itself, the contraction is greater (*Pflüger*), and lasts longer (*Wundt*) the nearer to the spinal cord the stimulus is applied to the nerve.

[In **studying a muscle curve,** the more or less vertical character of the ascent

FIG. 325.



Pendulum myograph curve of a frog's gastrocnemius. S, point of stimulation; A, latent period; B, period of shortening, and C, of relaxation. 250 DV., tuning fork vibrating 250 double vibrations per sec. The dotted vertical lines are ordinates (*Stirling*).

will indicate the rapidity of the contraction, the height above the base line its extent, the length of the curve the duration, and the line of descent the rate of its extensibility. The **form** of the muscle curve will vary with the kind of myograph used; if it be stationary, then the muscle will merely record a vertical line; if the recording surface move quickly, the two parts of the curve will form an acute angle (Fig. 327); and if it move with great rapidity, they will have the form of Fig. 325, that obtained with a **pendulum myograph.** A vibrating tuning fork records time directly under the tracing, whereby the duration of each part of the curve is readily determined.]

[In **measuring the myogram,** all that is required is to know the moment at which the stimulus was applied, and to note when the curve begins to leave the base line or abscissa. Raise a vertical line or ordinate from each of these points, and the interval between these lines, as measured by the chronograph, indicates the time (Fig. 325).]

[The **time relations** of a simple muscular contraction caused by a **single induction shock** may be studied by means of the following arrangement: Attach a frog's gastrocnemius to a lever, as in Fig. 326, and through the frog's muscle place two wires from the secondary coil of an induction machine. A scale pan with a weight is attached to the lever. On the same support adjust an electro-magnet with a writing style in the primary circuit, and in this circuit also place a key (K) to make and break the current. Fix also a Dupré's chronograph to the same support, and make it vibrate by connecting it in circuit with

a tuning fork of known rate of vibration, and driven by a galvanic battery. See that the points of all three levers write exactly over each other on the revolving cylinder. The upper lever registers the contraction, the electro-magnet the moment the stimulus is applied to the muscle, and the electrical chronograph the time.]

FIG. 326.



Arrangement for estimating the time relations during contraction of a muscle produced by a faradic shock. B, battery; K, key in primary circuit; I, primary, II, secondary spiral; *l*, muscle lever; *e*, electro-magnet in primary circuit; *t*, electric signal; *St*, support; RC, revolving cylinder (after *Rutherford*).

FIG. 327.



Frog's muscle stimulated alternately by a single break (B) and make shock (M). The lower curve shows the same, but with the muscle fatigued.

[**Single make** (closing) or **break** (opening) **induction shocks.** A muscle or nerve may be stimulated either with a "make" or "break" induction shock, but it is important to notice that the break shock is stronger than the make. In Fig. 327, B shows the effect produced by a single break induction shock, and M that of a single make shock.]

Overweighted Muscles.—The foregoing remarks apply to curves obtained by a *light* lever connected with the muscle. If the muscle lever be "*overweighted*" or **overloaded**, *i. e.*, if the lever be loaded so that when the muscle contracts it has to lift these weights, the course of the curve varies according to the weight to be lifted. It is necessary, however, to support the lever in the intervals when the muscle is at rest. As the weights are increased, the occurrence of the contraction is delayed. This is due to the fact that the muscle, at the moment of stimulation, must accumulate as much energy as is necessary to lift the weight. The greater the weight, the longer is the time before it is raised. Lastly, the muscle may be so "loaded," or "overloaded," that it cannot contract at all; this is the limit of the muscular or mechanical energy of the muscle (*v. Helmholtz*).

FIG. 328.



I, Contraction of a *fatigued* frog's muscle writing its contraction on a vibrating plate attached to a tuning fork. Each vibration = 0.01613 second; *a b*, = latent period; *b c*, stage of increasing energy; *c d*, of decreasing energy. II, The most rapid writing movements of the right hand inscribed on a vibrating plate. III, The most rapid trembling tetanic movements of the right forearm inscribed on the same plate.

Fatigue.—If a muscle be caused to contract so frequently that it becomes "*fatigued*," the latent period is longer, the curve is not so high, because the muscular contraction is less, and the abscissa is longer, *i. e.*, the contraction is

slower and lasts longer (Fig. 328). *Cooling* a muscle has the same effect. Soltmann finds that the fresh muscles of *new-born* animals behave in a similar manner. The myogram has a flat apex and considerable elongation in the descending limb of the curve.

Constant Current.—If the *motor nerve* of a muscle be stimulated by a make or break shock of a *constant current*, the resulting muscular contraction corresponds exactly to that already described. If, however, the current be made or broken with the muscle itself directly in the circuit, during the make shock, there is a certain degree of contraction which lasts for a time, so that the curve assumes the form of Fig. 329, where S represents the moment of closing or making the current, and O the moment of opening or breaking it (§ 336, D).

FIG. 329.

Effect on a muscle of closing and opening a constant current. S, closing; O, opening shock (*Wundt*).

The investigations of Cash and Kronecker show that **individual muscles** have a special form of muscle curve; the omo-hyoid of the tortoise contracts more rapidly than the pectoralis. Similar differences occur in the muscles of frogs and mammals. The flexors of the frog contract more rapidly than the extensors (*Grützner*). Sometimes within one and the same muscle there are "red" (rich in glycogen) and "pale" fibres (§ 292). The red fibres contract more slowly, are less excitable, and less easily fatigued (*Grützner*). The muscles of flying insects contract very rapidly, even more than 100 times per second.

Poisons.—Very small doses of **curara** or quinine increase the height of the contraction (excited by stimulation of the motor nerve), while larger doses diminish it, and finally abolish it altogether. **Guanidin** has a similar action in larger doses, but the maximum of contraction lasts for a longer time. Suitable doses of **veratrin** also increase the contractions, but the stage of relaxation is greatly strengthened (*Rossbach and Clostermeyer*). **Veratrin**, antiarin, and digitalin, in *large* doses, act upon the sarcous substance in such a way that the contractions become very prolonged, not unlike a condition of prolonged tetanus (*Harless*, 1862). The latent period of muscles poisoned with veratrin and strychnin is shortened at first, and afterward lengthened. The gastrocnemius of a frog supplied by blood containing soda contracts more rapidly (*Grützner*). Kunkel is of opinion that muscular poisons act by controlling the imbibition of water by the sarcous substance. As muscular contraction depends on imbibition (§ 297, II), the form of the contraction of the poisoned muscle will depend upon the altered condition of imbibition produced by the drug.

[**Veratrin.**—If a frog be poisoned with veratrin, and then be made to spring, it does so rapidly, but when it alights again the hind legs are extended, and they are only drawn up after a time. Thus, rapid and powerful contraction, with slow and prolonged relaxation, are the character of the movements. In a muscle poisoned with veratrin, the ascent is quick enough, but it remains contracted for a long time, so that this condition has been called "**contracture.**" A single stimulation may cause a contraction lasting five to fifteen seconds, according to circumstances (Fig. 330). Brunton and Cash find that **cold** has a marked effect on the action of veratrin—in fact, its effect may be permanently destroyed by exposure to extremes of heat or cold. The muscle curve of a brainless frog cooled artificially, and then poisoned by veratrin, occasionally gives no indication of the action of the poison until its temperature is raised, and this is not due to non-absorption of poison. Cold, therefore, abolishes or lessens the contracture peculiar to a veratrin curve. Similar results are obtained with salts of **barium**, and to a less degree by those of strontium and calcium (*Brunton and Cash*).]

Smooth Muscles.—The muscle curve of smooth or non-striped muscles is similar to that of the striped muscles, but the duration of the contraction is visibly much longer, and there are other points of difference. Some muscles stand midway between these two, at least as far as the duration of their contractions is concerned.

The "red" muscles of rabbits, the muscles of the tortoise, the adductors of the common mussel, and the heart, all react in a similar manner.

Contraction Remainder.—A contracted muscle assumes its original length only when it is extended by sufficient traction, *e. g.*, by means of a weight. Otherwise, the muscle may remain partially shortened for a long time. This

condition has been called "**contracture**" (*Tiegel*), or, better, **contraction remainder** (*Hermann*). This condition is most marked in muscles that have been previously subjected to strong, direct stimulation, and are greatly fatigued, which are distinctly acid, and ready to pass into rigor mortis, or in muscles excised from animals poisoned with veratrin (Fig. 330).

Rapidity of Muscular Contraction.—In **man**, single muscular movements can be executed with great rapidity. The time relations of such movements can be ascertained by inscribing the movements upon a smoked glass plate attached to a tuning fork. Fig. 328, II, represents the most rapid *voluntary* movements that Landois could execute, as, *e. g.*, in writing the letters *n*, *n*, and every contraction is equal to about 3.5 vibrations (1 vibration = 0.01613 second) = 0.0564 second. In III, the right arm was tetanized, in which case 2 to 2.5 vibrations occur = 0.0323 to 0.0403 second.

v. Kries found that a simple muscular twitch, caused by a single induction shock, is shorter than a momentary voluntary single movement. If the thickening caused by a single voluntary contraction of a muscle be registered directly, the curve shows that the contraction within the muscle lasts longer than the duration of the movement produced in the passive motor apparatus itself. This paradoxical phenomenon is due to the fact that, shortly after the primary voluntary muscular

FIG. 330.



Lower curve is the normal muscle curve (frog), upper one of the same muscle with veratrin (*Stirling*).

contraction, there is a contraction of the antagonistic muscles, whereby a part of the intended movement is, as it were, cut off. During the most rapid voluntary movement in human muscles, v. Kries found that 4 stimuli per second were active, so that a voluntary contraction is really a short tetanus.

Pathological.—In secondary degeneration of the spinal cord after apoplexy, atrophic muscular anchylosis of the limbs, muscular atrophy, progressive ataxia, and paralysis agitans of long standing, the latent period is *lengthened*; while it is *shortened* in the contracture of senile chorea and spastic tabes (*Mendelssohn*). The whole curve is lengthened in jaundice and diabetes (*Edinger*). In cerebral hemiplegia, during the stage of contracture, the muscle curve resembles the curve of a muscle poisoned with veratrin, and the same is the case in spastic spinal paralysis and amyotrophic lateral sclerosis; in pseudo-hypertrophy of the muscles the ascent is short and the descent very elongated. In muscular atrophy, after cerebral hemiplegia, and in tabes, the latent period increases, while the height of the curve diminishes. In chorea, the curve is short (*Reaction of Degeneration*, § 339). In rare cases in man, it has been observed that the execution of spontaneous movements results in a very prolonged contraction (**Thomsen's disease**). In such cases the muscular fibres are very broad, and the nuclei increased (*Erb*).

II. Action of Two Successive Stimuli. Let two momentary stimuli be applied successively to a muscle: (**A**) If *each stimulus* or shock be of itself sufficient to cause a **maximal** contraction, *i. e.*, the greatest possible contraction which the muscle can accomplish, then the effect will vary according to the *time* which elapses between the application of the two stimuli. (*a*) If the second

stimulus is applied to the muscle *after* the relaxation of the muscle following upon the first stimulus, we obtain merely two maximal contractions. (*b*) If, however, the second stimulus be applied to the muscle *during* the time that the effect of the first is present, *i. e.*, while the muscle is in the phase of contraction or of relaxation; in this case the second stimulus causes a new maximal contraction, according to the time of the particular phase of the contraction. (*c*) When, lastly, the second stimulus follows the first so rapidly that both occur during the latent period, we obtain only *one* maximal contraction (*v. Helmholtz*). It is to be specially noted that a single maximal stimulus never excites the same degree of shortening as tetanic stimulation (III), but only about ⅓ of the height of the contraction in tetanus.

FIG. 331.



I, two successive sub-maximal contractions; II, successive contractions produced by stimulating a muscle with 12 induction shocks per second; III, curve produced with very rapid induction shocks (complete tetanus).

(**B**) If the stimuli be not maximal, but only such as cause a medium or **sub-maximal** contraction, the effects of both stimuli are superposed, or there is a **summation** of the contractions (Fig. 331). It is of no consequence at what particular phase of the primary contraction the second shock is applied. In all cases, the second stimulus causes a contraction, just as if the phase of contraction caused by the first shock was the natural passive form of the muscle, *i. e.*, the new contraction (*b*, *c*) starts from that point as from an abscissa (Fig. 331, I, *b*). Thus, under favorable conditions, the contraction may be twice as great as that caused by the first stimulus. The most favorable time for the application of the second stimulus is $\frac{1}{20}$ second after the application of the first (*Sewall*). The effects of both stimuli are obtained even when the second stimulus is applied during the latent period (*v. Helmholtz*).

III. Tetanus—Summation of Stimuli.—If stimuli, each capable of causing a contraction, and following each other with medium rapidity, be applied to a muscle, the muscle has not sufficient time to elongate or relax in the intervals of stimulation. Therefore, according to the rapidity of the successive stimuli, it remains in a condition of continued vibratory contraction, or in a state of **tetanus**. Tetanus is, however, not a continuous uniform condition of contraction, but it is a discontinuous condition or form of the muscle, depending upon the **summation** or accumulation of contractions. If the stimuli are applied with moderate rapidity, the individual contractions appear in the curve (Fig. 331, II); if they occur rapidly, and thus become superposed and fused, the curve appears continuous and unbroken by elevations and depressions (Fig. 331, III). As a fatigued muscle contracts slowly, it is evident that such a muscle will become tetanic by a smaller number of stimuli per second than will suffice for a fresh muscle (*Marey*). All muscular movements of *long duration* occurring in our bodies are probably tetanic in their nature (*Ed. Weber*).

[**Summation of Stimuli.**—If a stimulus, insufficient in itself to cause contraction of a muscle, be repeatedly applied to a muscle in proper tempo and of sufficient strength, at first a slight and then a stronger or maximal contraction may be produced. This process of summation occurs also in nervous tissue (§ 360).]

[**Staircase** or "**Treppe.**" Bowditch showed that the cardiac contractions exhibited a "staircase" character, *i.e.*, the height of the second beat is greater than that of the first; and the third than that of the second (p. 126). The same occurs in the case of the muscles of the frog (*Tiegel, Minot*) and in mammals (*Rossbach*). Bohr showed that the successive ascending apices in a tetanus curve have really a staircase character, and that its exact form is that of a hyperbola. Bohr found that (1) this form—the muscle not being fatigued—is independent of the strength and frequency of the stimuli. (2) The height of the series of contractions in tetanus is independent of the frequency of the stimuli, increase of frequency merely causing the staircase to reach its maximum more rapidly. (3) The height of the staircase increases—within certain limits—with the strength of the stimulus. Buckmaster has confirmed this for simple contractions, but as shown in Fig. 332, when the stimuli are minimal or sub-maximal, there is usually no staircase character of the contractions, but maximal stimuli always cause it.]

FIG. 332.



Four groups of contractions; interval of simulation 2 seconds, and 5 minutes' pause between two groups (*Buckmaster*).

A continued **voluntary contraction** in man, consists of a series of single contractions rapidly following each other. Every such movement, on being carefully analyzed, consists of intermittent vibrations, which reach their maximum when a person shivers (*Ed. Weber*).—[Baxt found that the simplest possible voluntary contractions, *e. g.*, striking with the index finger, occupies on an average nearly twice as long a time as a similar movement discharged by a single induction shock.]

FIG. 333.



I, vibration obtained from the flexor brevis pollicis; II, from the extensor digiti tertii.

The **number** of **single impulses** sent to our muscles during a voluntary movement is tolerably variable, during a slow contraction = 8 to 12, and during a rapid contraction = 18 to 20 impulses per second. Fig. 333, I, represents a myogram of a sustained contraction of the flexor brevis pollicis and abductor pollicis, recorded on a vibrating plate. The wave-like elevations indicate the single impulses, each tooth = 0.01613 second. II is a similar curve registered by the extensor digiti tertii (*Landois*). [Schäfer finds that a prolonged voluntary contraction in man is an incomplete tetanus produced by 8 to 13 successive nervous impulses per second. About 10 per second may be taken as the average.]

The requisite degree of shortening is obtained by the summation of single stimuli applied to the slowly contracting muscle, until the desired degree of shortening is obtained. In estimating exactly the amount of movement, we generally oppose some resistance by contracting antagonistic muscles, as is shown by observations on spare individuals (*Brücke*).

The **tetanic contractions**, which occur normally in an **intact body**, are proved to consist of a series of successive contractions, because they can give rise to *secondary tetanus* (§ 332,) which may also be caused by muscles thrown into tetanus by strychnin poisoning (*Lovèn*). The **muscle sound** cannot be regarded as a proof of the oscillatory movement in tetanus [as Helmholtz has shown that this sound coincides with the resonance sound of the ear (*Hering and Friedrich*)].

If a muscle be connected with a telephone, whose wires are brought into connection with two needles, one placed in the tendon, and the other in the substance of the muscle, we hear a **sound** when the muscle is thrown into tetanus, which proves that periodic vibratory processes, *i. e.*, succes-

sive contractions, occur in the muscle (*Bernstein and Schönlein*). The sound is most distinct when the tetanizing Neef's hammer of an induction machine vibrates about 50 times per second (*Wedenski and Kronecker*).

The **number of stimuli** requisite to **produce tetanus** varies in different animals, and in different muscles of the same animal. About 15 stimuli per second are required to produce tetanus in the muscles of the *frog* (hyoglossus only 10, gastrocnemius 27); very feeble stimuli (more than 20 per second) cause tetanus (*Kronecker*); the muscles of the *tortoise* become tetanic with 2 to 3 shocks per second; the *red* muscles of the *rabbit* by 10, the *pale* by over 20 (*Kronecker and Stirling*); muscles of birds not even with 70 (*Marey*); muscles of insects 330 to 340 per second (*Marey*). Tetanic stimulation of the muscles of the crayfish (Astacus) and also in hydrophilus, may cause **rhythmical** contractions (*Richet*), or rhythmically interrupted tetanus (*Schönlein*).

Curarized muscles sometimes pass into tetanus on the application of a momentary stimulus (*Kühne, Hering*).

O. Soltmann found that the *pale* muscles of **new-born** rabbits were rendered tetanic with 16 stimuli per second, so that tetanus was produced in them with the same number of shocks as in fatigued adult muscles. This may serve partly to explain the facility with which spasms occur in new-born animals.

FIG. 334.



Curves obtained from red (upper) and pale (lower) muscles of a rabbit, by stimulating the sciatic nerve with a single induction shock. The lowest line indicates time, and is divided into $\frac{1}{100}$ second (*Kronecker and Stirling*).

[**The red and pale muscles** of a rabbit, as already shown, differ **structurally**, and also in regard to their blood supply (p. 507). They also differ **physiologically and chemically** (p. 509). When both muscles are caused to contract, by stimulating the sciatic nerve with a single induction shock, the curves obtained are shown in Fig. 334; the lower one from the pale, and the upper from the red muscle. The latent period is longer, while the duration of a simple contraction of a red muscle is three times longer than that of a pale muscle. Four stimuli per second cause an incomplete tetanus, and 10 per second a nearly complete tetanus in the red muscles of a rabbit, while the pale muscles require 20 to 30 stimuli per second to be completely tetanized. Fig. 335 shows the results produced by induction shocks applied to both muscles at intervals of $\frac{1}{4}$ second.]

The extent of shortening in a tetanically contracted muscle, within certain limits, is dependent upon the strength of the individual stimuli—but not upon their frequency. The contraction remainder after tetanus is greater the stronger the stimuli, the longer they are applied, and the feebler the muscle used (*Bohr*). For an unweighted muscle, the height of a contraction and that of tetanus are the same (*v. Frey*). Only when a muscle is weighted is the height of a single contraction less than by a tetanic contraction. Sometimes a stimulus applied to a muscle immediately after tetanus produces a greater effect than it did before the tetanus (*Rossbach, Bohr*).

FIG. 335.

Make and break induction shocks of 300 units, applied at intervals of a $\frac{1}{4}$ second to the pale (lower) and red (upper) muscles of a rabbit. The lowest line marks $\frac{1}{4}$ second (*Kronecker and Stirling*).

Duration of Tetanus.—A tetanized muscle cannot remain contracted to the same extent for an indefinite period, even if the stimuli are kept constant. It gradually begins to elongate, at first somewhat rapidly, and then more slowly, owing to the occurrence of fatigue. If the tetanic stimulation is arrested, the muscle does not regain its original position and shape at once, but a contraction remainder exists for a certain time, this being more evident after stimulation with induction shocks.

IV. If very rapid induction shocks (224 to 360 per second) be applied to a muscle, the tetanus after a so-called "**initial contraction**" (*Bernstein*) may cease (*Harless, Heidenhain*). This occurs most readily when the nerves are cooled. Kronecker and Stirling, however, found that stimuli following each other at greater rapidity than 24,000 per second produced tetanus.

[**Tone inductorium of Kronecker and Stirling.**—This apparatus (Fig. 336), consists of a rod of iron, *d*, fixed in an iron upright at *a*. The primary, s_I, and secondary spiral, s_{II}, rest on wooden supports, which can be pushed over both ends of the rod. One end of the rod lies between leather rollers, *f* and *g*, which can be made to rub on the rod by moving the toothed wheels, *h*. In this way a tone is produced by the **longitudinal vibrations** of the rod, the number of vibrations being proportional to the length of the rod, so that by means of this instrument we can produce from 1000 to 24,000 alternating induction shocks per second.]

FIG. 336.



Tone inductorium of Kronecker and Stirling. *d*, iron rod, clamped at *a*; s_I, primary, s_{II}, secondary spiral, with a key, *k*; leather rollers, *f* and *g*, driven by wheels, *h*.

Fick has recently investigated the changes—**tension**—undergone by a muscle when it is stimulated, and when its length remains constant, and he calls this process an "**isometrical muscular act.**" He finds that a voluntary contraction in an isometrical act in man causes a higher tension than a contraction excited electrically. In the frog, the tension is nearly twice as great during tetanus as during a single maximal muscular contraction; in human muscles, it may be ten times as great.

299. RAPIDITY OF TRANSMISSION OF A CONTRACTION.

1. If a long muscle be stimulated **at one end**, a contraction occurs at that point, and is rapidly propagated in a **wave-like** manner through the whole length of the muscle, until it reaches its other end. The condition of excitement or molecular disturbance is communicated to each successive part of the muscle, in virtue of a special conductive capacity of the muscle. The mean **velocity** of the contraction wave is 3 to 4 metres per second in the frog (*Bernstein*, 3.869 metres); rabbit, 4 to 5 metres (*Bernstein and Steiner*); lobster 1 metre (*Frédéricq and van de Velde*); in **smooth muscle** and in the **heart**, only 10 to 15 millimetres per second (§ 58, 4). These results have reference only to excised muscles, the velocity of transmission being much greater in the voluntary muscles of a living man, viz., 10 to 13 metres (*Hermann*, § 334, II).

...hods.—Aeby placed writing levers upon both ends of a muscle, the levers resting transversely ...n of the muscular fibres. The muscle was stimulated, and both levers registered their ... directly over the other on a revolving cylinder. On stimulating one end of ...rest to this point is raised by the contraction-wave, and a little later the other ...ate at which the cylinder is moving, and the distance between the two ... rapidity of transmission of the contraction wave.

Duration and Wave Length.—The time, corresponding to the length of the abscissa of the muscle curve inscribed by each writing lever, is equal to the *duration of the contraction* of this part of the muscle (according to Bernstein, 0.053 to 0.098 second). If this value be multiplied by the rapidity of transmission of the muscular contraction wave, we obtain the *wave length* of the *contraction wave* (= 206 to 380 millimetres).

Modifying Influences.—Cold (Fig. 337), fatigue, approaching death, and many poisons [veratrin, KCy] diminish the velocity and the height of the contraction wave, while the strength of the stimulus and the extent to which the muscle is loaded are without any effect upon the velocity of the wave (*Aeby*). In excised muscles, the size of the wave diminishes as it passes along the muscle, but this is not the case in the muscles of living men and animals. The contraction wave never passes from one muscular fibre to a neighboring fibre.

[Fig. 337 shows the effect of cold on the muscles of a rabbit, in delaying the contraction wave. There is a longer distance between 1 and 2 in the lower than in the upper curves.]

2. If a long muscle be stimulated locally **near its middle,** a contraction wave is propagated toward both ends of the muscle. If several points be stimulated simultaneously, a wave movement sets out from each, the waves passing over each other in their course (*Schiff*).

3. If a stimulus be applied to the **motor nerve** of a muscle, an impulse is

FIG. 337.

Upper two curves, 2 and 1, obtained from a rabbit's muscle by the above arrangement; the lower two curves from the same muscle, when it was cooled by ice.

communicated to *every muscular fibre*; a contraction wave begins at the *end organ* [motorial end plate], and must be propagated in both directions along the muscular fibres, whose length is only 3 to 4 centimetres. As the length of the motor fibres from the nerve trunk to where they terminate in the motorial end plate is unequal, contraction of all the muscular fibres cannot take place absolutely at the same moment, as the nerve impulse takes a certain time to travel along a nerve. Nevertheless, the difference is so small that, when a muscle is caused to contract by stimulation of its motor nerve, practically the whole muscle appears to contract simultaneously and at once.

4. *A complete, uniform, momentary contraction of all the fibres* of a muscle can only take place when all the fibres are excited at the same moment. This occurs when the electrodes are placed at both ends of the muscle, and an electrical stimulus of momentary duration passes through the whole length of the muscle.

300. **MUSCULAR WORK.**—Muscles are most perfect machines, not only because they make the most thorough use of the substances on which their activity depends (§ 217), but they are distinguished from all machines of human manufacture by the fact that, by frequent exercise they become stronger, and are thereby capable of accomplishing more work (*Du Bois-Reymond*).

The **amount** of work (W) which a muscle can perform is equal to the product

of the weight lifted (p) and the height to which it is lifted (h), *i. e.*, $W = ph$ (*Introduction*). Hence, it follows that when a muscle is not loaded (where $p = 0$), then w must be $= 0$, *i. e.*, no work is performed. If, again, it be overloaded with too great a load, so that it is unable to contract ($h = 0$), here also the work is nil. Between these two extremes an active muscle is capable of doing a certain amount of "work."

I. Work with Maximal Stimulation.—When the strongest possible, or **maximal stimulus** is applied—*i. e.*, when the strength of the stimulus is such as to cause a muscle to contract to the greatest possible extent of which it is capable, the amount of work done increases more and more as the weight is increased, but only up to a certain maximum. If the weight be gradually increased, so that it is lifted to a less height, the amount of work diminishes more and more, and gradually falls to be $= 0$, when the weight is not lifted at all.

Example of the work done by a frog's muscle (*Ed. Weber*):—

Weight lifted in Grammes.	Height in Millimetres.	Work done in Gramme-Millimetres.
5	27.6	138
15	25.1	376
25	11.45	286
30	7·3	220

[Suppose a muscle be loaded with a certain number of grammes, and then caused to contract, we get a certain height of contraction. Fig. 338 shows the result of an experiment of this kind. The vertical lines represent the height to which the weights (in grammes) noted under them were raised, so that, as a rule, as the weight increases the height to which it is raised decreases.]

FIG. 338.



Laws of Muscular Work.—1. A muscle can lift a greater load the larger its transverse section, *i. e.*, the more fibres it contains arranged parallel to each other.

2. The longer the muscle, the higher it can lift a weight.

3. When a muscle begins to contract, it can lift the largest load; as the contraction proceeds, it can only lift a less and less load, and when it is at its maximum of shortening, only relatively very light loads.

4. By the term "**absolute muscular force**" is meant, according to Ed. Weber, just the weight which a muscle undergoing maximal stimulation is no longer able to lift (the muscle being in its normal resting phase), and without the muscle at the moment of stimulation being elongated by the weight.

Comparative.—Comparing the **absolute muscular force** of different muscles, even in different animals, it is usual to calculate it with reference to that of a square centimetre. The mean transverse section of a muscle is obtained by dividing its volume by its length. The volume is equal to the absolute weight of the muscles divided by its specific gravity = 1058. The absolute muscular force for 1 □ centimetre of a frog's muscle = 2.8 to 3 kilos. [6.6 lbs.] (*J. Rosenthal*); for 1 □ centimetre of human muscle = 7 to 8 (*Henke and Knorz*), or even 9 to 10 kilos. [20 to 23 lbs.] (*Korster, Haughton*). **Insects** can perform an extraordinary amount of work—an insect can drag along sixty-seven times its body weight; a horse scarcely three times its own weight.

5. During **tetanus**, when a weight is kept suspended, no work is done as long as the weight is suspended, but of course work is done in the act of lifting the load. To produce tetanus, successive stimuli are required, the muscular metabolism is increased, and fatigue rapidly occurs. The potential energy in this case is

converted into heat (§ 302). When a muscle is stimulated with a *maximal stimulus*, it cannot lift so great a weight with *one* contraction as when it is stimulated tetanically (*Hermann*). The energy evolved, even during tetanus, is greater the more frequent the stimulation, at least up to 100 stimuli per second (*Bernstein*).

II. Medium Stimuli.—If a muscle be caused to contract by stimuli of *moderate strength, i. e.*, such as do not cause a maximal contraction, there are two possibilities: Either the feeble stimulus is kept constant while the load is varied, in which case the amount of work done follows the same law as obtains for maximal stimulation; or, the load may be kept the same, while the strength of the stimulus is varied. In the latter case, Fick observed that the height to which the load was lifted increased in a direct ratio with the strength of the stimulus.

The stimulus which causes a muscle to contract must reach a certain strength or intensity before it becomes effective, *i. e.*, the "**liminal intensity**" of the stimulus, but this is independent of the weight applied to the muscle. With minimal stimuli, a small weight is raised higher than a large one, but as the stimulus is increased, the contractions also increase in a larger ratio with an increased load (*v. Kries*).

The **blood stream** within the muscles of an intact body is increased during muscular activity. The blood vessels of the muscle **dilate**, so that the amount of blood flowing through them is increased (*Ludwig and Sczelkow*). At the time that the motor fibres are excited, so also are the **vaso-dilator fibres**, which lie in the same nervous channels (§ 294, II). [Gaskell found that faradization of the nerve of the mylo-hyoid muscle of the frog not only caused tetanus of the muscle, but also dilatation of its blood vessels.]

Testing Individual Muscles.—In estimating the **absolute force** of the *individual muscles* or groups of muscles in man, we must always pay particular attention to the physical relations, *i. e.*, to the arrangement of the levers, direction of the traction, degree of shortening, etc. (§ 306.) **Dynamometer.**—The absolute force of certain groups of muscles is very conveniently and practically ascertained by means of a dynamometer (Fig. 339). This instrument is very useful for testing the difference between the power of the two arms in cases of paralysis. The patient grasps the instrument in his hand and an index registers the force exerted. Quetelet has estimated the force of certain muscles—the pressure of both hands of a man to be = 70 kilos.; while by pulling he can move double this weight. The force of the female hand is one-third less. A man can carry more than double his own weight; a woman about the half of this. Boys can carry about one-third more than girls. [Very convenient dynamometers are made by Salter, of Birmingham, both for testing the strength of **pull** and **squeeze**; in testing the former, the instrument is held as an archer holds his bow when in the act of drawing it, and the strength of pull is given by an index; in the latter another form of the instrument is used. Large numbers of observations were made by means of these instruments by Francis Galton at the Health Exhibition, 1885.]

FIG. 339.

Dynamometer of Mathieu.

Amount of Work Daily.—In estimating the work done by a man, we have to consider, not only the amount of work done at any one moment, but how often, time after time, he can succeed in doing work. The **mean value** of the daily work of a man working eight hours a day is 10 (10.5 to 11 at most) kilogramme-metres per second, *i. e.*, a daily amount of work = 288,000 (300,000) kilogramme-metres.

[**Ergostat.**—Sometimes it is desirable that patients—especially those who suffer from excessive corpulence—should do a certain amount of work daily; this can be carried out by Gaertner's Ergostat, which resembles a winch, driven by a handle. The pressure upon the wheel can be regulated by means of a strap, lever, and weights, and according to the weight and number of revolutions of the wheel, can the amount of mechanical work be accurately regulated. This instrument is recommended for therapeutical purposes.]

Modifying Conditions.—Many substances, after being introduced into the body, **diminish**, and ultimately paralyze the production of work—mercury, digitalin, helleborin, potash salts, etc. Others **increase** the muscular activity— veratrin (*Rossbach*), glycogen [caffein and allied alkaloids], muscarin (*Klug and Fr. Högyes*), kreatin and hypoxanthin; extract of meat rapidly restores the muscles after fatigue (*Kobert*). [Those drugs which excite muscular tissue restore it after fatigue.

Kreatin is a waste product of muscle, and beef-tea and Liebig's extract of meat perhaps owe their restorative qualities partly to these extractives.]

301. THE ELASTICITY OF MUSCLE.—Physical.—Every elastic body has its "natural shape," *i. e.*, its shape when no external force (tension or pressure) acts upon it so as to distort it. Thus, the passive muscle has a "natural form." If, however, a muscle be extended in the course of its fibres, the parts of the muscle are evidently pulled asunder. If the stretching be carried only to a certain degree, the muscle, in virtue of its elasticity, will regain its natural form. Such a body is said to possess "**complete elasticity**," *i. e.*, after being stretched it regains exactly its original shape. By the term "**amount of elasticity**" (*modulus*) is meant the weight (expressed in kilogrammes) necessary to extend an elastic body 1 □ millimetre in diameter, its own length, without the body breaking. Of course many bodies are ruptured before this occurs. For a passive muscle it is = 0.2734 (*Wundt*), [that of bone = 2264 (*Wertheim*), tendon = 1.6693, nerve = 3.0905, the arterial walls = 0.0726 (*Wundt*)]. Thus, the amount of elasticity of a passive muscle is small, as it requires only a slight stretching force to extend it to its own length. It has, therefore, no great amount of elasticity. The term "**coefficient of elasticity**" is applied to the fraction of the length of an elastic body, to which it is elongated by the unit of weight applied to stretch it. It is large in a passive muscle. If the tension be sufficiently great, the elastic body ruptures at last. The "*carrying capacity*" of muscular tissue, until it ruptures, is in the following ratios for youth, middle, and old age, nearly 7 : 3 : 2. [Instead of the word "elasticity," Brunton suggests the use of **extensibility** and **retractibility**, terms suggested by Marey, the one referable to the elongation on the application of a weight, and the other to the shortening after its removal.]

Curve of Elasticity.—In **inorganic** elastic bodies, the line of elongation, or the *extension, is directly proportional to the extending weight;* in **organic** bodies, and, therefore, in muscle, this is not the case, as the weight is continually increased by equal increments—the muscle is less extended than at the beginning, so that the extension is *not proportional to the weight.* If equal weights be added to a scale

FIG. 340.

Curve of elasticity from an inorganic body (india-rubber).

FIG. 341.

Curve of elasticity from the sartorius of a frog, obtained by adding equal increments of weight at A, B, C, etc.

FIG. 342.

Curve of elasticity produced by continuous extension and recoil of a frog's muscle; *o x*, abscissa before, *x'* after extension.

pan attached to a piece of india-rubber, with a writing lever connected with it, and writing its movements on a plate of glass that can be moved with the hand, we get such a curve as in Fig. 340, while, if the same be done with the sartorius of a frog, we get a result similar to Fig. 341. A **straight line** joins the apices of the former, while the curve of elasticity is a **hyperbola**, or something near it, in the latter case.

Elastic After-effect.—At the same time, after the first elongation, corresponding to the extending weight, is reached, the muscle may remain for days, and even weeks, somewhat elongated. This is called the "*elastic after-effect*" (§ 65). [Marey attached a lever to a frog's muscle, and allowed the latter to record its movements on a slowly revolving cylinder. To the lever was fixed a vessel into which mercury slowly flowed. This extended the muscle, and when it had ceased to elongate, the mercury was allowed slowly to run out again. The curve obtained is shown in Fig. 342. The abscissæ, *o x* and *x'*, indicate the position of the writing style before and after the experiment, and we observe that *x'* is lower than *o x*, so that the recoil is imperfect. There has been an actual elongation of the

muscle, so that the limit of its elasticity is exceeded. Although a frog's gastrocnemius may be loaded with 1500 grammes without rupturing it, 100 grammes will prevent its regaining its original length.]

Method.—In order to test the **elasticity** of a muscle, fix it to a support provided with a graduated scale, and to the lower end of the muscle attach a scale pan, in which are placed various weights, measuring on each occasion the corresponding elongation of the muscle thereby obtained (*Ed. Weber*). In order to obtain the **curve of elongation** or **extensibility** take as abscissæ the successive units of weight added, and the elongation corresponding to each weight as ordinates. Example from the hyoglossus of the frog :—

Weight in Grammes.	Length of the Muscle in Millimetres.	Extension.	
		In Millimetres.	Percentage.
0.3	24.9	. .	. .
1.3	30.0	5.1	20
2.3	32.3	2.3	7
3.3	33.4	1.1	3
4.3	34.2	0.8	2
5.3	34.6	0.4	1

The elasticity of passive muscle is *small*, but *very complete*, and is comparable to that of a caoutchouc fibre. Small weights greatly elongate the muscle. If the weights be uniformly increased, there is not a uniform elongation ; with equal increments of weight, the greater the load, the increase in elongation always becomes less ; or, to express it in another way, the amount of elasticity of the passive muscle increases with its increased extension (*Ed. Weber*).

In **inorganic** bodies, the **curve of extension** is a **straight line**, but in **organic** bodies, it more closely resembles a **hyperbola** (*Wertheim*). The elasticity of a passive *fatigued* muscle does not differ essentially from that of a non-fatigued muscle.

Muscles in the living body, and still in connection with their nerves and blood vessels, are more extensible than excised ones. Muscles, when quite fresh, are elongated (within certain small limits as regards the weight) at first with a uniformly increasing weight, to an extent proportional to the latter, just as with an inorganic body. When heavy weights are used, we must be careful to take into consideration the "*elastic after-effect*" (§ 65).

The **volume** of a stretched muscle is slightly *less* than an unstretched one, similar to the contracted (§ 297, 2) and stiffened muscle (§ 295).

Dead muscles and muscles in *rigor mortis* have greater elasticity, *i.e.*, they require a heavier weight to stretch them than fresh muscles; but, on the other hand, the elasticity of dead muscles is less complete, *i.e.*, after they are stretched, they only recover their original form within certain limits.

Elasticity of Intact Muscles.—Normally, within the body, the muscles are stretched to a very slight extent, as can be shown by the slight degree of retraction which occurs when the insertion of a muscle is divided. This slight degree of extension, or stretching, is important. If this were not so, when a muscle is about to contract, and before it could act upon a bone as a lever, it would have to "take in so much slack." The elasticity of muscles is manifested during the contraction of antagonistic muscles. The position of a passive limb depends upon the resultant of the elastic tension of the different muscle groups.

The elasticity of an active muscle is less than that of a passive muscle, *i. e.*, it is elongated by the same weight to a greater extent than a passive muscle. For this reason, the active muscle, as can be shown in an excised contracted muscle, is *softer;* the apparently great hardness manifested by stretched contracted muscles depends upon their tension. When the active muscle becomes *fatigued*, its elasticity is diminished (§ 304).

Method.—Ed. Weber took the hyoglossus muscle of a frog and suspended it vertically, noticing its length when it was passive. It was then tetanized with indnction shocks and its height again

noted. One after the other heavier weights were attached to it, and the length of the passive and tetanized muscle observed for each weight. The extent to which the active loaded muscle shortened from the position of the passive loaded muscle he called the "**height of the lift**" (or "Hubhöhe"). The latter becomes less as the weight increases, and lastly, the tetanized muscle may be so loaded that it cannot contract, *i. e.*, the height of the lift is = 0.

Weber's Paradox.—The case may occur where, when a muscle is so loaded that it cannot contract when it is stimulated, it may even **elongate.** According to Wundt, even in this condition the elasticity is not changed. [The usual explanation given is that, as the elasticity of a muscle is diminished during contraction, it is more extended with the same weight in the contracted as compared with the passive or uncontracted state, so that a heavily-weighted muscle, when stimulated, may elongate instead of shorten.] According to Wundt, however, as stated, there is no change in the elasticity of the muscle. In these experiments, the length of the active loaded muscle is equal to the length of the passive muscle when similarly loaded, minus the "height of the lift."

Poisons.—Potash causes shortening of a muscle with simultaneous increase of its elasticity. Digitalin produces other changes with increased elasticity. Physostigmin increases it, while veratrin diminishes it, and interferes with its completeness (*Rossbach and v. Anrep*), and tannin makes a muscle less extensible, but more elastic (*Lewin*). Ligature of the blood vessels produces at first a decrease, and then an increase, of the elasticity; section of the motor nerve diminishes the elasticity (*v. Anrep*); heat increases it.

Eduard Weber concluded from his experiments that a muscle assumes two forms, the active and the passive form. Each of these corresponds to a special natural form. The passive muscle is longer and thinner—the active is shorter and thicker in form. The passive as well as the active muscle strives to retain its form. If the passive muscle be set into activity, the passive rapidly changes into the active form, in virtue of its elastic force. The latter is the energy which causes muscular work. Schwann compared the force of an active muscle to a long, elastic, tense spiral spring. Both can lift the greatest weight, only from that form in which they are most stretched. The more they shorten, the less the weight which they can lift.

[**Uses of Elasticity.**—As already pointed out, all muscles are slightly on the stretch, so that no time is lost nor energy wasted, in "taking in slack," as it were; but the elasticity also lessens the shock of the contraction, so that it is developed gradually, and muscles are not liable to be torn from their attachments. The muscular energy is transmitted to the mass to be moved through an elastic and easily extensible body (muscle), whereby the shock due to the contraction is lessened, but, as Marey has shown, the amount of work is thereby considerably increased.]

[**Tonicity of Muscle** (§ 362)—**Sensibility of Muscle.**—That muscles contain sensory fibres is certain (§ 430). Section of inflamed muscles is painful, and during muscular cramp intense pain is felt. Sachs discharged a reflex action by stimulating the central end of an intra-muscular nerve filament in a frog, while stimulation of the central end of the phrenic nerve raises the blood pressure (*Muscular Sense*, § 430).]

302. FORMATION OF HEAT IN AN ACTIVE MUSCLE.—After Bunzen, in 1805 (§ 209, 1, *b*), showed that during muscular activity heat is evolved, v. Helmholtz proved that an *excised* frog's muscle, when *tetanized* for two to three minutes, exhibited an **increase of its temperature** of 0.14° to 0.18° C. R. Heidenhain succeeded in showing an increase of 0.001° to 0.005° C. for each *single contraction*. The heart is warmer during every systole (*Marey*).

[**Method.**—The rise in temperature of a frog's muscle may be estimated by placing the two gastrocnemii of a frog's muscle on the two junctions of a thermo-electric pile, connected with a heat galvanometer. Of course, when the two muscles are at the same temperature, the needle of the galvanometer is stationary; but, if one muscle is made to contract, or is tetanized, then an electrical current is set up which deflects the needle (§ 208, B). Lujankow has, by means of a delicate thermometer placed between the thigh muscles of a dog, estimated the rise of temperature under different conditions of the muscle, while the latter was still *in situ* and intact.]

The following facts have been ascertained with regard to the development of heat:—

1. **Relation to Work.**—It bears a relation to the amount of work.

(a) If a muscle during contraction carries a weight which extends it again during rest, no work is transferred beyond the muscle (§ 300). In this case all the chemical potential energy during this movement is converted into heat. Under these circumstances, the amount of heat evolved runs parallel with the

amount of work done, *i. e.*, it increases as the load and the height increase up to a maximum point, and afterward diminishes as the load is increased. The heat maximum is reached with a less load sooner than the work maximum (*Heidenhain*).

(b) If, when the muscle is at the height of its contraction, the *load be removed*, then the muscle has produced work referable to something outside itself; in this case the amount of heat produced is less (*A. Fick*). The amount of work produced, and the diminished amount of heat formed, when taken together, represent the same amount of energy, corresponding to the law of the conservation of energy.

(c) If the same amount of work is performed in one case by many but small contractions, and in another by fewer but larger contractions, then, in the latter case, the amount of heat is greater (*Heidenhain and Nawalichin*). This shows that larger contractions are accompanied by a *relatively* greater metabolism of the muscular substance than small contractions, which is in harmony with practical experience; thus the ascent of a tower with steep high steps causes fatigue more rapidly (metabolism greater) than the ascent of a more gentle slope with lower steps.

(d) If the weighted muscle executes a series of contractions one after the other, and at the same time does work, then the amount of heat it produces is greater than when it is tetanic, and keeps a weight suspended. Thus, the transition of the muscle into a shortened form causes a greater production of heat than the maintenance of this form.

2. Relation to Tension.—The amount of heat evolved depends upon the *tension of the muscle;* it also increases as the muscular tension increases (*Heidenhain*). If the ends of a muscle be so fixed that it cannot contract, the maximum of heat is obtained (*Bèclard*), and this the more quickly the more rapidly the stimuli follow each other (*Fick*). Such a condition occurs during tetanus, in which condition the violently contracted muscles oppose each other, and very high temperatures have been registered by Wunderlich (§ 213, 7), while the same is true of animals that are tetanized (*Leyden*). Dogs kept in a state of tetanus by electrical stimulation die, because their temperature rises so high (44° to 45° C.) that life no longer can be maintained (*Richet*). In addition to the formation of heat, there is a considerable amount of *acid*, and of alcoholic extractives produced in the muscular tissue.

3. Relation to Stretching.—Heat is also evolved during the *elongation* or relaxation of a contracted muscle, *e. g.*, by causing a muscle to contract without the addition of any weight, and loading it when it begins to relax, whereby heat is produced (*Steiner, Schmulewitsch, and Westerman*). If weights be attached to a muscle by means of an inextensible medium, and the weights be allowed to fall from a height so as to give a jerk to the muscle, then an amount of heat equivalent to the work done by the drop, is set free in the muscle (*Fick and Danilewsky*).

4. The formation of heat diminishes as the muscular fatigue increases.

5. In a muscle duly supplied with blood, the production of heat (as well as the mechanical work) is far more active than in a muscle whose blood vessels are ligatured or its blood stream cut off. Recovery takes place more rapidly and completely after fatigue, while, at the same time, there is a new increase in the production of heat (*Meade Smith*).

The amount of work and heat in a muscle must always correspond to the transformation of an equivalent amount of chemical energy. A greater part of this energy is manifested as work, the greater the resistance that is offered to the muscular contraction. When the resistance is great, ¼ of the chemical energy may be manifested as work, but when it is small, only a small part of it is so converted.

It was stated that a **nerve** in action is $\frac{1}{30}$° C. warmer (*Valentin*), but this is denied by v. Helmholtz and Heidenhain.

In man, if the muscles be stimulated with electricity or contracted voluntarily, the production of heat may be detected through the skin (*v. Ziemssen*). The venous blood flowing from an actively contracting muscle is 0.6° C. warmer than the arterial blood (*Meade Smith*).

303. THE MUSCLE SOUND.—When a muscle contracts, and is at the same time kept in a state of tension by the application of sufficient resistance, it emits a distinct sound or **tone** with a semi-musical quality, depending upon the intermittent variations of tension occurring within it (*Wollaston*).

Methods.—The muscle sound may be heard by placing the ear over the tetanically contracted and tense biceps of another person; or we may insert the tips of our index fingers into our ears, and forcibly contract the muscles of our arm; or the sound of the muscles that close the jaw may be heard by forcibly contracting them, especially at night when all is still, and when the outer ears are closed. v. Helmholtz found that this tone coincides with the resonance tone of the ear, and he thought that the vibrations of the muscles caused this resonance tone. The sound of an isolated frog's muscle may be heard by placing one end of a rod in the ear, the other ear being closed. To the other end of the rod is attached a loaded frog's muscle kept in a tetanic condition. The pitch of the note, *i. e.*, the number of vibrations, may be estimated by comparing the muscle sound with that produced by elastic springs vibrating at a known rate.

When a muscle contracts **voluntarily**, *i. e.*, through the will, it makes 19.5 vibrations per second. [Schäfer and others give the number as 10 successive nervous impulses per second, p. 535.] We do not hear this very low tone, owing to the number of vibrations per second being too few, but what we actually hear is the *first over-tone*, with double the number of vibrations.* The muscle sound has 19.5 vibrations, when the muscles of an animal are caused to contract, by stimulating its *spinal cord* (*v. Helmholtz*), and also when the *motor nerve trunk* is excited by chemical means (*Bernstein*). If, however, **tetanizing** induction shocks be applied to a muscle, then the number of vibrations of the muscle sound corresponds exactly with the number of vibrations of the vibrating spring or hammer of the induction apparatus. Thus, the tone may be raised or lowered by altering the tension of the spring.

Lovèn found that the muscle sound was loudest when the weakest currents capable of producing tetanus were employed. The sound corresponded to the number of vibrations of the octave just below it in the scale. With stronger currents the muscle sound disappears, but it reappears with the same number of vibrations as that of the interrupter of the induction apparatus, if still stronger currents are used.

If the induction shocks be applied to the nerve, the sound is not so loud, but it has the same number of vibrations as the interrupter. With rapid induction shocks, tones caused by 704 (*Lovèn*) and 1000 vibrations per second have been produced (*Bernstein*).

The first heart sound is partly muscular (§ 53).

*A single induction shock is said to cause the muscle sound in a contracting muscle. If this be so, it is doubtful if the muscle sound can be regarded as a sign that tetanus is due to a series of single variations of the muscle (§ 298, III).

304. FATIGUE AND RECOVERY OF MUSCLE.—Fatigue.—By the term fatigue is meant that condition of diminished capacity for work which is produced in a muscle by prolonged activity. This condition is accompanied in the living person with a peculiar feeling of lassitude, which is referred to the muscles. A fatigued muscle rapidly **recovers** in a living animal, but an excised muscle recovers only to a slight extent (*Ed. Weber, Valentin*).

[Waller recognizes a certain resemblance between experimental fatigue and the natural decline of excitability at death, in disease, and in poisoning.]

The cause of fatigue is probably partly due to the accumulation of decomposition products—"**fatigue stuffs**"—in the muscular tissue, these products being formed within the muscle itself during its activity. They are *phosphoric acid*, either free or in the form of acid phosphates, *acid potassium phosphate* (§ 294), glycerin-phosphoric acid (?) and CO_2. If these substances be removed from a muscle, by passing through its blood vessels an indifferent solution of common salt (0.6 per cent.), or a weak solution of sodium carbonate [or a dilute solution of permanganate of potash (*Kronecker*)], the muscle again becomes capable of energizing (*J. Ranke*,

1863). The using up of O by an active muscle favors fatigue (*v. Pettenkofer and v. Voit*). The transfusion of *arterial blood* (not of venous—*Bichat*) removes the fatigue (*Ranke, Kronecker*), probably by replacing the substances that have been used up in the muscle. Conversely, an actively energizing muscle may be rapidly fatigued by injecting into its blood vessels a dilute solution of phosphoric acid, of acid potassium phosphate, or dissolved extract of meat (*Kemmerich*). A muscle fatigued in this way absorbs less O, and when so fatigued, it evolves only a small amount of acids and CO_2. The conditions which lead up to fatigue are connected with considerable metabolism in the muscular tissue.

[Zabludowski found that if a frog's muscles be systematically stimulated by maximum induction shocks until they cease to contract, **massage** or kneading them rapidly restored their excitability, while simple rest had little effect. Massage acts on the nerves, but chiefly by favoring the blood and lymph streams which wash out the waste products from the muscle. A similar result obtains in man, so that the ancient Roman practice of "rubbing" after a bath and after exercise was one conducive to restoration of the power of the muscles.]

Modifying Conditions.—In order to obtain the same amount of work from a fatigued muscle, a much more powerful stimulus must be applied to it than to a fresh one. A fatigued muscle is incapable of lifting a considerable load, so that its absolute muscular force is diminished. If, during the course of an experiment, an excised muscle be loaded with the same weight, and if the muscle be stimulated at regular intervals with maximal stimuli (strong induction shocks), contraction after contraction gradually and regularly diminishes in height, the decrease being a constant fraction of the total shortening. Thus the fatigue curve is represented by a *straight line* [*i. e.*, a straight line will touch the apices of all the contractions]. The more rapidly the contractions succeed each other, the greater is the fall in the height of the contraction [*i. e.*, if the *interval* between the contractions be short, the fatigue curve falls rapidly toward the abscissa], and conversely. After a certain number of contractions, an excised muscle becomes exhausted.

This result occurs whether the stimuli are applied at short or long intervals (*Kronecker*), and a similar result is obtained with sub-maximal stimuli (*Tiegel*). A fatigued muscle contracts more *slowly* than a fresh one, while the latent period is also longer during fatigue (p. 529). The fatigued muscle is said to be more extensible (*Donders and van Mansvelt*). If a muscle be so loaded that, when it contracts, it cannot lift the load, fatigue occurs even to a greater extent than when the load is such that the muscle can lift it (*Leber*). The metabolism and the formation of acid are greater in a contracted muscle kept on the stretch, than in a contracted muscle allowed to shorten (*Heidenhain*). If a muscle contract, but be not required to lift any load, it becomes fatigued only very gradually. If a muscle be loaded only during contraction, and not during relaxation, it is fatigued more slowly than when it is loaded during both phases; and the same is true when a muscle has to lift its load only during the *course* of its contraction, instead of at the beginning of the contraction. Loads may be suspended to perfectly passive muscles without fatiguing them (*Harless, Leber*).

FIG. 343.

Fatigue curve of a frog's muscle. The sciatic nerve was stimulated with maximal induction shocks and every fifteenth contraction recorded (*Stirling*).

[**Signs of Fatigue** (Fig. 343).—In the record of the series of contractions: (1) the contractions become more prolonged; (2) they decrease in height; (3) the latent period becomes longer; (4) if maximal shocks be used, the beginning of the series exhibits a "staircase" character of its contractions, just like the heart [§ 57).]

[While an **excised frog's muscle** is fairly rapidly exhausted by single opening induction shocks, at intervals of one second, **human muscle** in its normal relations may be almost indefinitely so treated, and there is no change in the record or any sensation of fatigue. Waller regards this as favoring the view that the "fatigue consequent upon prolonged muscular exertion is normally central rather than peripheral." Such results, however, do not harmonize with those of Zabludowski on the kneading of muscles, or massage. Probably there are two factors, one central, the other peripheral.]

Blood Supply.—If the arteries of a mammal be ligatured, stimulation of the motor nerves produces complete fatigue after 120 to 240 contractions (in two to four minutes), but direct muscular stimulation still causes the muscles to contract. In both cases the fatigue curve is in the form of a straight line. If the blood supply to a mammalian muscle be normal, on stimulating the motor nerve, the muscular contractions at first increase in height and then fall, their apices forming a straight line (*Rossbach and Harteneck*). In persons who have used their muscles until fatigue sets in, it is found that at the beginning the nerves and muscles react better to galvanic and faradic stimulation, but afterward always to a less degree (*Orschanski*). According to v. Kries, a muscle tetanized and fatigued with maximal stimuli behaves like a fresh muscle tetanized with sub-maximal stimuli; both show an incomplete transition from the passive to the active condition.

[**Relation of End Plates.**—Muscle is fatigued far more rapidly than nerve, and the fatigue begins in the muscle and not in the nerve, and it seems to be the weakest link in the chain between nerve and muscle which is affected during excessive action, viz., the motor **end plate** (*Waller*). In a **nerve** its conductivity is sooner affected by fatigue than its direct excitability. Waller finds that after death "the excitability of a nerve persists when its action upon muscle has ceased, such muscle being still excitable by direct stimulation." Some link in the chain is obviously affected, and it is perhaps the end plates.]

[**Action of Drugs on Fatigue.**—Waller finds, in a frog poisoned with veratrin, that if the muscles be stimulated electrically, the characteristic elongation of the descent (§ 298) gradually disappears,

FIG. 344.



Curves obtained by direct stimulation of the gastrocnemius of a frog poisoned with strychnin, the sciatic nerve divided on one side (upper curve) and not on the other (lower or fatigue curve).

but reappears after a period of rest. In this respect, strychnin in its action on the spinal cord behaves precisely the same as veratrin on muscle, viz., its effect is dissipated by action and restored by rest.] Curara and the ptomaines cause an irregular course of the fatigue curve (*Guareschi and Mosso*). [If strychnin be injected into a frog, and the sciatic nerve on one side be divided after the strychnin tetanus has lasted for a time, the leg muscles of the side with the nerve undivided exhibit signs of fatigue, as shown by direct stimulation of the muscles of both legs, when a curve similar to Fig. 344 is obtained. The higher one is the non-fatigued, the lower that of the side with the nerve undivided (*Waller*).]

Recovery from the condition of fatigue is promoted by passing a *constant electrical current* through the entire length of the muscle (*Heidenhain*), also by injecting fresh arterial blood into its blood vessel, or by very small doses of veratrin [or permanganate of potash], and by rest.

If the muscle of an intact animal be stimulated continuously (fourteen days or so), until complete fatigue occurs, the muscular fibres become granular and exhibit a wax-like degeneration. The transverse striation is still visible as long as the sarcous substance is in large masses, but as soon as it breaks up into small pieces the transverse striation disappears completely (*O. Roth*).

305. MECHANISM OF THE BONES AND JOINTS.—Bones exhibit in the inner architecture of their spongiosa an arrangement of their lamellæ and spicules which represents the static results of those forces—pressure

and traction—which act on the developing bone (Structure of Bone, § 447). They are so arranged that, with the minimum of material, they afford the greatest resistance as a supporting structure or framework (*H. v. Meyer, Culmann, Jul. Wolff*).

I. **The joints** permit the freest movements of one bone upon another [such as exist between the extremities of the bones of the limbs. In other cases, sutures are formed, which, while permitting no movement, allow the contents of the cavity which they surround to enlarge, as in the case of the cranium]. The articular end of a fresh bone is covered with a thin layer or plate of hyaline cartilage, which in virtue of its elasticity moderates any shocks or impulses communicated to the bones. The surface of the articular cartilage is perfectly smooth, and facilitates an easy gliding movement of the one surface upon the other. At the outer boundary line of the cartilage, there is fixed the **capsule** of the joint, which encloses the articular ends of the bones like a sac. The inner surface of the capsule is lined by a synovial membrane, which secretes the sticky, semi-fluid **synovia**, moistening the joint. The outer surface of the capsule is provided at various parts with bands of fibrous tissue, some of which strengthen it, while others *restrain* or limit the movement of the joint. Some osseous processes limit the movements of particular joints, *e. g.*, the coronoid process of the ulna, which permits the forearm to be flexed on the upper arm only to a certain extent; the olecranon, which prevents over-extension at the elbow joint. The joint surfaces are kept in apposition (1) by the adhesion of the synovia-covered, smooth, articular surface; (2) by the capsule and its fibrous bands; and (3) by the elastic tension and contraction of the muscles.

[**Structure of Articular Cartilage.**—The thin layer of hyaline encrusting cartilage is fixed by an irregular surface upon the corresponding surface of the head of the bone (Fig. 345). In a vertical section through the articular cartilage of a bone which has been softened in chromic or other suitable acid, we observe that the cartilage cells are flattened near the free surface of the cartilage, and their long axes are parallel to the surface of the joint; lower down, the cells are arranged in irregular groups, and further down still, nearer the bone, in columns or rows, whose long axis is in the long axis of the bone. These rows are produced by transverse cleavage of preëxisting cells. In the upper two-thirds, or thereby, the matrix of the cartilage is **hyaline**, but in the lower third, near the bone, the matrix is granular and sometimes fibrillated. This is the **calcified zone**, which is impregnated with lime salts, and sharply defined by a *nearly straight line* from the hyaline zone above it, and by a very bold *wavy line* from the osseous head of the bone.]

FIG. 345.

Vertical section of articular cartilage. (*Stirling.*)

Synovial Membrane.—Synovial membrane consists of bundles of delicate connective tissue mixed with elastic tissue, while on its inner surface it is provided with folds, some of which contain fat, and others blood vessels (synovial villi). The inner surface is lined with endothelium. The intra-capsular ligaments and cartilages are not covered by the synovial membrane, nor are they covered by endothelium. The **synovia** is a colorless, stringy, alkaline fluid, with a chemical composition closely allied to that of transudations, with this difference, that it contains much **mucin**, together with albumin and traces of fat. Excessive movement diminishes its amount, makes it more inspissated, and increases the mucin, but diminishes the salts.

Joints may be divided into several classes, according to the kind of movement which they permit:—

1. *Joints with movement around* **one** *axis:* (*a*) **The Ginglymus, or Hinge Joint.**—The one articular surface represents a portion of a cylinder or sphere, to which the other surface is adapted by a corresponding depression, so that, when flexion or extension of the joint takes place, it moves only on *one* axis of the cylinder or sphere. The joints of the fingers and toes are hinge joints of this description. *Lateral* ligaments, which prevent a lateral displacement of the articular surfaces, are always present.

The **Screw-hinge Joint** is a modification of the simple hinge form (*Langer, Henke*), *e. g.*, the humero-ulnar articulation. Strictly speaking, simple flexion and extension do not take place at the elbow joint, but the ulna moves on the capitellum of the humerus like a nut on a bolt; in the right humerus, the screw is a right spiral, in the left, a left spiral. The ankle joint is another example; the nut or female screw is the tibial surface, the right joint is like a left-handed screw, the left the reverse. (*b*) The **Pivot Joint** (**rotatoria**), with a cylindrical surface, *e. g.*, the joint between

the atlas and the axis, the axis of rotation being around the odontoid process of the axis. In the acts of **pronation** and **supination** of the forearm at the elbow joint, the axis of rotation is from the middle of the cotyloid cavity of the head of the radius to the styloid process of the ulna. The other joints which assist in these movements are *above* the joint, between the circumferential part of the head of the radius and the sigmoid cavity of the ulna, and *below* the joint, between the sigmoid cavity of the radius which moves over the rounded lower end of the ulna.

2. *Joints with movements around* **two** *axes.*—(*a*) Such joints have two unequally curved surfaces which intersect each other, but which lie in the same direction, *e.g.*, the atlanto-occipital joint, or the wrist joint, at which lateral movements, as well as flexion and extension, take place. (*b*) Joints with curved surfaces, which intersect each other, but which do not lie in the same direction. To this group belong the **saddle-shaped** articulations, whose surface is concave in one direction, but convex in the other, *e.g.*, the joint between the metacarpal bone of the thumb and the trapezium. The chief movements are (1) flexion and extension, (2) abduction and adduction. Further, to a limited degree, movement is possible in all other directions; and, lastly, a pyramidal movement can be described by the thumb.

3. *Joints with movement on a* **spiral** *articular surface* (*spiral joints*), *e.g.*, the knee joint (*Goodsir*). The condyle of the femur, curved from before backward, in the antero-posterior section of its articular surface, represents a *spiral* (*Ed. Weber*), whose centre lies nearer the posterior part of the condyle, and whose radius vector increases from behind, downward and forward. Flexion and extension are the chief movements. The strong lateral ligaments arise from the condyles of the femur corresponding to the centre of the spiral, and are inserted into the head of the fibula and internal condyle of the tibia. When the knee joint is strongly flexed, the lateral ligaments are relaxed—they become tense as the extension increases; and when the knee joint is fully extended, they act quite like tense bands which secure the lateral fixation of the joint. Corresponding to the spiral form of the articular surface, flexion and extension do not take place around *one* axis, but the axis moves continually with the point of contact; the axis moves also in a spiral direction. The greatest flexion and extension cover an angle of about 145°. The anterior crucial ligament is more tense during extension, and acts as a check ligament for too great extension, while the posterior is more tense during flexion, and is a check ligament for too great flexion. The movements of extension and flexion at the knee are further complicated by the fact that the joint has a screw-like movement, in that during the greater extension the leg moves outward. Hence, the thigh, when the leg is fixed, must be rotated outward during flexion. Pronation and supination take place during the greatest flexion to the extent of 41° (*Albert*) at the knee joint, while with the greatest extension it is nil. It occurs because the external condyle of the tibia rotates on the internal. In all positions during flexion the crucial ligaments are fairly and uniformly tense, whereby the articular surfaces are against each other. Owing to their arrangement, during increasing tension of the anterior ligament (extension), the condyles of the femur must roll more on to the anterior part of the articular surface of the tibia, while by increasing tension of the posterior ligament (flexion), they must pass more backward.

4. *Joints with the axis of rotation round* **one** *fixed point.*—These are the freely movable **arthrodial** joints. The movements can take place around innumerable axes, which all intersect each other in the centre of rotation. One articular surface is nearly spherical; the other is cup-shaped. The shoulder and hip joints are typical **"ball-and-socket joints."** We may represent the movements as taking place around *three* axes, intersecting each other at right angles. The movements which can be performed at these joints may be grouped as: (1) pendulum-like movements in any plane, (2) rotation round the long axis of the limb, and (3) circumscribing movements [circumduction], such as are made round the circumference of a sphere; the centre is in the point of rotation of the joint, while the circumference is described by the limb itself.

Limited arthrodial joints are ball joints with limited movements, and where rotation on the long axis is wanting, *e.g.*, the metacarpo-phalangeal joints.

5. **Rigid joints** or **amphiarthroses** are characterized by the fact that movement may occur in all directions, but only to a very limited extent, in consequence of the tough and unyielding external ligaments. Both articular surfaces are usually about the same size, and are nearly plane surfaces, *e.g.*, the articulations of the carpal and the tarsal bones.

II. Symphyses, synchondroses, and syndesmoses unite bones without the formation of a proper articular cavity, are movable in all directions, but only to the slightest extent. Physiologically they are closely related to amphiarthrodial joints.

III. Sutures unite bones without permitting any movement. The physiological importance of the suture is that the bones can still grow at their edges, which thus renders possible the distention of the cavity enclosed by the bones (*Herm. v. Meyer*).

306. **ARRANGEMENT AND USES OF MUSCLES.**—The muscles form 45 per cent. of the total mass of the body, those of the right side being heavier than those on the left. Muscles may be arranged in the following groups, as far as their mechanical actions are concerned:—

A. Muscles without a definite origin and insertion:—

1. **The hollow muscles** surrounding globular, oval, or irregular cavities, such as the urinary bladder, gall bladder, uterus, and heart; or the walls of more or less cylindrical canals (intestinal tract, muscular gland ducts, ureters, Fallopian tubes, vasa deferentia, blood vessels, lymphatics). In all these cases the muscular fibres are arranged in several layers, *e. g.*, in a longitudinal and a circular layer, and sometimes also in an oblique layer. All these layers act together and thus diminish the cavity. It is inadmissible to ascribe different mechanical effects to the different layers, *e. g.*, that the circular fibres of the intestine narrow it, while the longitudinal dilate it. Both sets of fibres rather seem to act simultaneously, and diminish the cavity by making it narrower and shorter at the same time. The only case where muscular fibres may act in partially dilating the cavity is when, owing to pressure from without, or from partial contraction of some fibres, a fold, projecting into the lumen, has been formed. When the fibres, necessarily stretching across the depression thereby produced, contract, they must tend to undo it, *i. e.*, enlarge the cavity. The various layers are all innervated from the same motor source, which supports the view of their conjoint action.

2. **The sphincters** surround an opening or a short canal, and by their action they either constrict or close it, *e. g.*, sphincter pupillæ, palpebrarum, oris, pylori, ani, cunni, urethræ.

B. Muscles with a definite origin and insertion:—

1. **The origin is completely fixed** when the muscle is in action. The course of the muscular fibres, as they pass to where they are inserted, permits of the insertion being approximated in a straight line toward their origin during contraction, *e. g.*, the attollens, attrahens, and retrahentes of the outer ear, and the rhomboidei. Some of these muscles are inserted into soft parts which necessarily must follow the line of traction, *e. g.*, the azygos uvulæ, levator palati mollis, and most of the muscles which arise from bone and are inserted into the skin, such as the muscles of the face, styloglossus, stylopharyngeus, etc.

2. **Both Origin and Insertion movable.**—In this case the movements of both points are inversely as the resistance to be overcome. The resistance is often voluntary, which may be increased either at the origin or insertion of the muscle. Thus, the sterno-cleido-mastoid may act either as a depressor of the head or as an elevator of the chest; the pectoralis minor may act as an abductor and depressor of the shoulder, or as an elevator of the 3d to 5th ribs (when the shoulder girdle is fixed).

3. **Angular Course.**—Many muscles having a fixed origin are diverted from their straight course; either their fibres or their tendons may be *bent* out of the straight course. Sometimes the curving is slight, as in the occipito-frontalis and levator palpebræ superioris, or the tendon may form *an angle* round some bony process, whereby the muscular traction acts in quite a different direction, *i. e.*, as if the muscle acted directly from this process upon its point of insertion, *e. g.*, the obliquus oculi superior, tensor tympani, tensor veli palatini, obturator internus.

4. Many of the muscles of the extremities act upon the **long bones as upon levers:** (*a*) Some act upon a lever with **one arm**, in which case the insertion of the muscle (power) and the weight lie upon one side of the fulcrum or point of support, *e. g.*, biceps, deltoid. The insertion (or power) often lies very close to the fulcrum. In such a case, the *rapidity* of the movement at the end of the lever is greatly increased, but force is lost [*i. e.*, what is gained in rapidity is lost in power]. This arrangement has this advantage, that, owing to the slight contraction of the muscle, little energy is involved, which would be the case had the muscular contraction been more considerable (§ 300, I, 3). (*b*) The muscles act

upon the bones as upon a lever with **two arms**, in which case the power (insertion of the muscle) lies on the other side of the fulcrum opposite to the weight, *e. g.*, the triceps and muscles of the calf. In both cases, the muscular force necessary to overcome the resistance is estimated by the principles of the lever: equilibrium is established when the static moments (= product of the power in its vertical distance from the fulcrum) are equal; or when the power and weight are inversely proportional, as their vertical distance from the fulcrum.

FIG. 346.



The three orders of levers.

[**The Bony Lever.**—All the three orders of levers are met with in the body. Indeed, in the elbow joint all the three orders are represented. The annexed scheme shows the relative positions of P, W, and F (Fig. 346). The first order represented by such a movement as nodding the head, the second by raising the body on the tiptoes by the muscles of the calf, and the third by the action of the biceps in raising the forearm. At the elbow joint the first order is illustrated by extending the flexed forearm on the upper arm, as in striking a blow on the table, where the triceps attached to the olecranon is the power, the trochlea the fulcrum, and the hand the weight. If the hand rest on the table and the body be raised on it, then the hand is the fulcrum, while the triceps is the power raising the humerus and the parts resting on it (W). The third order has already been referred to, *e. g.*, flexing the forearm.]

Direction of Action.—It is most important to observe the *direction* in which the muscular force and weight act upon the lever arm. Thus, the direction may be vertical to the lever in one position, while after flexion it may act obliquely upon the lever. The static moment of a power acting *obliquely* on the lever arm is obtained by multiplying the power with the power acting in a direction vertical to the point of rotation.

Examples.—In Fig. 347, **I**, B x represents the humerus, and x Z the radius; A y, the direction of the traction of the biceps. If the biceps acts at a right angle only, as by lifting horizontally a weight (P) lying on the forearm or in the hand, then the power of the biceps (= A) is obtained from the formula, A $y\ x = P\ x\ Z$, *i. e.*, $A = (P\ x\ Z) : y\ x$. It is evident that, when the

FIG. 347.



Scheme of the action of the muscles on bones.

radius is depressed to the position x C, the result is different; then the force of the biceps = $A_1 = (P_1\ v\ x) : o\ x$. In Fig. 347, II, TF is the tibia, F, the ankle joint, MC, the foot in a horizontal position. The power of the muscles of the calf (= a) necessary to equalize a force, p, directed from below against the anterior part of the foot, would be $a = (p\ M\ F) : F\ C$. If the foot be altered to the position R S, the force of the muscles of the calf would then be $a_1 = (p_1\ M\ F) : F\ C$.

In muscles also, which, like the coraco-brachialis, are stretched over the angle of a hinge, the same result obtains.

In Fig. 347, III, H E is the humerus, E, the elbow joint, E R, the radius, B R, the coraco-brachialis. Its moment in this position is = A, *a* E. When the radius is raised to E R_1, then it is = A, *a* E. We must notice, however, that B R_1 < B R. Hence, the absolute muscular force must be less in the flexed position, because every muscle, as it becomes shorter, lifts less weight. What is lost in power is gained by the elongation of the lever arm.

5. Many muscles have a **double action**; when contracted in the ordinary way they execute a combined movement, *e. g.*, the biceps is a flexor and supinator of the forearm. If one of these movements be prevented by the action of other muscles, the muscle takes no part in the execution of the other movement.

If the forearm be strongly pronated and flexed in this position, the biceps takes no part therein; or, when the elbow joint is rigidly supinated, only the supinator brevis acts, not the biceps. The muscles of mastication are another example. The masseter elevates the lower jaw, and at the same time pulls it forward. If the depressed jaw, however, be strongly pulled backward when the jaw is raised, the masseter is not concerned. The temporal muscle raises the jaw, and at the same time pulls it backward. If the depressed jaw be raised after being pushed forward, then the temporal is not concerned in its elevation.

6. **Muscles acting on two or more joints** are those which, in their course from their origin to their insertion, pass over two or more joints. Either the tendons may deviate from a straight course, *e. g.*, the extensors and flexors of the fingers and toes, as when the latter are flexed; or the direction is always straight, *e. g.*, the gastrocnemius. The muscles of this group present the following points of interest: (*a*) The phenomenon of so-called "**active insufficiency.**" If the position of the joints over which the muscle passes be so altered that its origin and insertion come too near each other, the muscle may require to contract so much before it can act on the bones attached to it, that it cannot contract actively any further than to the extent of the shortening from which it begins to be active; *e. g.*, when the knee joint is bent, the gastrocnemius can no longer produce plantar flexion of the foot, but the traction on the tendo-Achilles is produced by the soleus. (*b*) "**Passive insufficiency**" is shown by many-jointed muscles under the following circumstances: In certain positions of the joint, a muscle may be so stretched that it may act like a rigid strap, and thus limit or prevent the action of other muscles, *e. g.*, the gastrocnemius is too short to permit complete dorsal flexion of the foot when the knee is extended. The long flexors of the leg, arising from the tuber ischii, are too short to permit complete extension of the knee joint when the hip joint is flexed at an acute angle. The extensor tendons of the fingers are too short to permit of complete flexion of the joints of the fingers when the hand is completely flexed.

7. **Synergetic muscles** are those which together subserve a certain kind of movement, *e. g.*, the flexors of the leg, the muscles of the calf, and others. The abdominal muscles act along with the diaphragm in diminishing the abdomen during straining, while the muscles of inspiration or expiration, even the different origins of one muscle, or the two bellies of a biventral muscle, may be regarded from the same point of view.

Antagonistic muscles are those which, during their action, have exactly the opposite effect of other muscles, *e. g.*, flexors and extensors—pronators and supinators—adductors and abductors—elevators and depressors—sphincters and dilators—inspiratory and expiratory.

When it is necessary to bring the full power of our muscles into action, we quite involuntarily bring them beforehand into a condition of the greatest tension, as a muscle in this condition is in the most favorable position for doing work (§ 300, I, 3). Conversely, when we execute delicate movements requiring little energy, we select a position in which the corresponding muscle is already shortened.

All the fasciæ of the body are connected with muscles, which, when they contract, alter the tension of the former, so that they are, in a certain sense, aponeuroses or tendons of the latter (*K. Bardeleben*). [For the importance of muscular movements and those of fasciæ in connection with the movements of the lymph, see § 201.]

307. **GYMNASTICS; MOTOR PATHOLOGICAL VARIATIONS.**—**Gymnastic exercise** is most important for the proper development of the muscles and motor power, and it ought to be commenced in both sexes at an early age. Systematic muscular activity increases the volume of the muscles, and enables them to do more work. The amount of blood is increased with increase in the muscular development, while at the same time the bones and ligaments become more resistant. As the circulation is more lively in an active muscle, gymnastics favor the circulation, and ought to be practiced, especially by persons of sedentary habits, who are apt to suffer from congestion of blood in abdominal organs (*e.g.*, hæmorrhoids), as it favors the movement of the tissue juices [§ 201]. An active muscle also uses more O and produces more CO_2, so that respiration is also excited. The total increase of the metabolism gives rise to the feeling of well-being and vigor, diminishes abnormal irritability, and dispels the tendency to fatigue. The whole body becomes firmer, and specifically heavier (*Jäger*).

By **Ling's,** or the **Swedish system,** a systematic attempt is made to strengthen certain weak muscles, or groups of muscles, whose weakness might lead to the production of deformities. These muscles are exercised systematically by opposing to them resistances, which must either be overcome, or against which the patient must strive by muscular action.

Massage, which consists in kneading, pressing, or rubbing the muscles, favors the blood stream; hence, this system may be advantageously used for such muscles as are so weakened by disease that an independent treatment by means of gymnastics cannot be adopted. [The importance of massage as a restorative practice in getting rid of the waste products of muscular activity has been already referred to (§ 304).]

Disturbances of the normal movements may partly affect the **passive motor organs** (*e.g.*, the bones, joints, ligaments, and aponeuroses), or the **active organs** (muscles with their tendons, and motor nerves).

Passive Organs.—Fractures, caries and necrosis, and inflammation of the bones, which make movements painful, influence or even make movement impossible. Similarly, dislocations, relaxation of the ligaments, arthritis, or anchylosis interfere with movement. Also curvature of bones, hyperostosis or exostosis; lateral curvature of the vertebral column (**Scoliosis**), backward angular curvature (**Kyphosis**), or forward curvature (**Lordosis**). The latter interfere with respiration. In the lower extremities, which have to carry the weight of the body, **genu valgum,** may occur in flabby, tall, rapidly-growing individuals, especially in some trades, *e.g.*, in bakers. The opposite form, **genu varum,** is generally a result of rickets. **Flat foot** depends upon a depression of the arch of the foot, which then no longer rests upon its three points of support. Its causes seem to be similar to those of genu valgum. The ligaments of the small tarsal joints are stretched, and the long axis of the foot is usually directed outward; the inner margin of the foot is more turned to the ground, while pain in the foot and malleoli make walking and standing impossible. Club foot (**Talipes varus**), in which the inner margin of the foot is raised, and the point of the toes is directed inward and downward, depends upon imperfect development during fœtal life. All children are born with a certain very slight degree of bending of the foot in this direction. **Talipes equinus,** in which the toes, and **T. calcaneus,** in which the heel touches the ground, usually depend upon contracture of the muscles causing these positions of the foot, or upon paralysis of the antagonistic muscles.

Rickets and Osteomalacia.—If the earthy salts be withheld from the food, the bones gradually undergo a change; they become thin, translucent, and may even bend under pressure. In certain persistent defects of nutrition, the lime and other salts of the food are not absorbed, giving rise to **rachitis,** or rickets, in children. If fully formed bones lose their lime salts to the extent of ½ to ⅓ (**halisterisis**), they become brittle and soft (**osteomalacia**). This occurs to a limited extent in old age.

Muscles.—The normal nutrition of muscle is intimately dependent on a proper supply of *sodium chloride and potash salts* in the food, as these form integral parts of the muscular tissue (*Kemmerich, Forester*). Besides the atrophic changes which occur in the muscles when these substances are withheld, there are disturbances of the central nervous system and digestive apparatus, and the animals ultimately die. The condition of the muscles during inanition is given in § 237. If muscles and bones be kept inactive, they tend to atrophy (§ 244). In atrophic muscles, and in cases of anchylosis, there is an enormous increase, or "atrophic proliferation," of the muscle corpuscles, which takes place at the expense of the contractile contents (*Cohnheim*). A certain degree of muscular atrophy takes place in old age. The **uterus,** after delivery, undergoes a great decrease in size and weight—from 1000 to 350 grammes—due chiefly to the diminished blood supply to the organ. In chronic *lead poisoning*, the extensors and interossei chiefly undergo atrophy. Atrophy and degeneration of the muscles are followed by shortening and thinning of the bones to which the muscles are attached.

Section and paralysis of the motor nerves cause palsy of the muscle, thus rendering them inactive, and they ultimately degenerate. Atrophy also occurs after inflammation or softening of the **multipolar nerve cells** in the anterior horn of the gray matter of the spinal cord, or the *motor nuclei* (facial, spinal accessory, and hypoglossal of Stilling in the medulla oblongata), in the muscles connected with these parts. Rapid atrophy takes place in certain forms of spinal paralysis and in acute bulbar paralysis (paralysis of the medulla oblongata), and in a chronic form in progressive muscular

atrophy, and progressive bulbar paralysis. The muscles and their nerves become small and soft. The muscles show many nuclei, the sarcous substance becomes fatty, and ultimately disappears. According to Charcot, these areas are at the same time the trophic centres for the nerves proceeding from them, as well as for the muscles belonging to them. According to Friedreich, the primary lesion in progressive muscular atrophy is in the muscles, and is due to a primary interstitial inflammation of the muscle, resulting in atrophy and degenerative changes, while the nerve centres are affected secondarily, just as after amputation of a limb, the corresponding part of the spinal cord degenerates.

In **pseudo-hypertrophic muscular atrophy** the muscular fibres atrophy completely, with copious development of fat and connective tissue between the fibres, without the nerves or spinal cord undergoing degeneration. The muscular substance may also undergo *amyloid* or *wax-like* degeneration, whereby the amyloid substance infiltrates the tissue (§ 249, VI). Sometimes atrophic muscles have a *deep brown color*, due to a change of the hæmoglobin of the muscle. When muscles are much used, they **hypertrophy**, as the heart in certain cases of valvular lesion or obstruction (§ 40), the bladder, and intestine. [In true **hypertrophy** there is an increased number or increase in the size of its tissue elements, throughout the entire tissue or organ, without any deposit of a foreign body. Perhaps, in hypertrophy of the bladder, the thickened muscular coat not only serves to overcome resistance, but it offers greater resistance to bursting under the increased intra-vesical pressure. Mere **enlargement** is not hypertrophy, for this may be brought about by foreign elements. In **atrophy** there is a diminution in size or bulk, even when the blood stream is kept up, the decrease being due to pressure. An atrophied organ may be even enlarged, as seen in pseudo hypertrophic paralysis, where the muscles are larger, owing to the interstitial growth of fatty and connective tissue, while the true muscular tissue is diminished and truly atrophied.]

308. STANDING.—The act of **standing** is accomplished by muscular action, and is the vertical position of equilibrium of the body, in which a line drawn from the centre of gravity of the body falls within the area of both feet placed upon the ground. In the military attitude, the muscles act in two directions—(1) to fix the jointed body, as it were, into one unbending column; and (2) in case of a variation of the equilibrium, to compensate by muscular action for the disturbance of the equilibrium.

The following individual motor acts occur in standing:—

1. **Fixation of the head** upon the vertebral column. The occiput may be moved in various directions upon the atlas, as in the acts of *nodding*. As the long arm of the lever lies in front of the atlas, necessarily when the muscles of the back of the neck relax, as in sleep or death, the chin falls upon the breast. The strong neck muscles, which pull from the vertebral column upon the occiput, fix the head in a firm position on the vertebral column. The chief rotatory movement of the head on a vertical axis occurs round the odontoid process of the axis. The articular surfaces on the pedicles, and part of the bodies of the 1st and 2d vertebræ, are convex toward each other in the middle, becoming somewhat lower in front and behind, so that the head is highest in the erect posture. Hence, when the head is greatly rotated, compression of the medulla oblongata is prevented (*Henke*). In standing, these muscles do not require to be fixed by muscular action, as no rotation can take place when the neck muscles are at rest.

2. **Fixed Vertebral Column.**—The vertebral column itself must be fixed, especially where it is most mobile, *i.e.*, in the cervical and lumbar regions. This is brought about by the strong muscles situate in these regions, *e.g.*, the cervical spinal muscles, *Extensor dorsi communis* and *Quadratus lumborum*.

Mobility of the Vertebræ.—The least movable vertebræ are the 3d to the 6th dorsal; the sacrum is quite immovable. For a certain length of the column, the mobility depends on (*a*) the number and height of the inter-articular fibro-cartilages. They are most numerous in the neck, thickest in the lumbar region, and relatively also in the lower cervical region. They permit movement to take place in every direction. Collectively the inter-articular disks form one-fourth of the height of the whole vertebral column. They are compressed somewhat by the pressure of the body; hence, the body is longest in the morning and after lying in the horizontal position. The smaller periphery of the bodies of the cervical vertebræ favors the mobility of these vertebræ compared with the larger lower ones. (*b*) The position of the processes also influences greatly the mobility. The strongly depressed spines of the dorsal region hinder hyper-extension. The articular processes on the cervical vertebræ are so placed that their surfaces look obliquely from before and upward, backward, and downward; this permits relatively free movement, rotation, lateral and nodding movements. In the dorsal region, the articular surfaces are directed vertically and directly to the front, the lower directly backward; in the lumbar region, the position of the articular processes is almost completely vertical and antero-posterior. In bending backward, as far as possible, the most mobile parts of the column are the lower cervical vertebræ, the 11th dorsal to the 2d lumbar and the lower two lumbar vertebræ (*E. H. Weber*).

3. The **centre of gravity** of the head, trunk, and arms when fixed as above, lies in front of the 10th dorsal vertebra. It lies further forward, in a horizontal plane, passing through the xiphoid pro-

cess, the greater the distention of the abdomen by food, fat, or pregnancy. A line drawn vertically downward from the centre of gravity passes *behind* the line uniting both hip joints. Hence, the trunk would fall backward on the hip joint, were it not prevented partly by ligaments and partly by muscles. The former are represented by the ileo-femoral band and the anterior tense layer of the fascia lata. As ligaments alone, however, never resist permanent traction, they are aided, especially by the ileo-psoas muscle inserted into the small trochanter, and in part, also, by the rectus femoris. Lateral movement at the hip joint, whereby the one limb must be abducted and the other adducted, is prevented especially by the large mass of the glutei. When the leg is extended, the ileo-femoral ligament, aided by the fascia lata, prevents adduction.

4. The rigid part of the body, head, and trunk, with the arms and legs, whose centre of gravity lies lower and only a little in front, so that the vertical line drawn downward intersects a line connecting the posterior surfaces of the knee joints, must now be fixed at the knee joint. Falling backward is prevented by a slight action of the quadriceps femoris, aided by the tension of the fascia lata. Indirectly it is aided also by the ileo-femoral ligament. Lateral movement of the knee is prevented by the disposition of the strong lateral ligaments. Rotation cannot take place at the knee joint in the extended position (§ 305, I, 3).

5. A line drawn downward from the centre of gravity of the whole body, which lies in the promontory, falls slightly in front of a line between the two ankle joints. Hence, the body would fall *forward* on the latter joint. This is prevented especially by the muscles of the calf, aided by the muscles of the deep layer of the leg (tibialis posticus, flexors of the toes, peroneous longus et brevis).

Other Factors.—(*a*) As the long axis of the foot forms with the leg an angle of 50°, falling forward can only occur after the feet are in a position more nearly parallel with their long axis. (*b*) The form of the articular surfaces helps, as the anterior broad part of the astragalus must be pressed between the two malleoli. The latter mechanism cannot be of much importance.

6. The metatarsus and phalanges are united by tense ligaments to form the arch of the foot, which touches the ground at three points—tuber calcanei (heel), the head of the first metatarsal bone (ball of the great toe), and of the fifth toe. Between the latter two points, the heads of the metatarsal bones also form points of supports. The weight of the body is transmitted to the highest part of the arch of the foot, the caput tali. The arching of the foot is fixed only by ligaments. The toes play no part in standing, although, when moved by their muscles, they greatly aid the balancing of the body. The maintenance of the erect attitude fatigues one more rapidly than walking.

309. SITTING.—**Sitting** is that position of equilibrium whereby the body is supported on the tubera ischii, on which a to and fro movement may take place (*H. v. Meyer*). The head and trunk together are made rigid to form an immovable column, as in standing. We may distinguish: (1) the **forward posture**, in which the line of gravity passes in front of the tubera ischii; the body being supported either against a fixed object, *e.g.*, by means of the arm on a table, or against the upper surface of the thigh. (2) The **backward posture**, in which the line of gravity falls behind the tubera. A person is prevented from falling backward either by leaning on a support, or by the counter-weight of the legs kept extended by muscular action, whereby the sacrum forms an additional point of support, while the trunk is fixed on the thigh by the ileo-psoas and rectus femoris, the leg being kept extended by the extensor quadriceps. Usually the centre of gravity is so placed that the heel also acts as a point of support. The latter sitting posture is of course not suited for resting the muscles of the lower limbs. (3) When "**sitting erect**" the line of gravity falls between the tubera themselves. The muscles of the legs are relaxed, the rigid trunk only requires to be balanced by slight muscular action. Usually the balancing of the head is sufficient to maintain the equilibrium.

310. WALKING, RUNNING, AND SPRINGING.—By the term **walking** is understood progression in a forward horizontal direction with the least possible muscular exertion, due to the alternate activity of the two legs.

Methods.—The Brothers Weber were the first to analyze the various positions of the body in walking, running, and springing, and they represented them in a *continuous series*, which represents the successive phases of locomotion. These phases may be examined with the zoetrope (§ 398, 3.) Marey estimated the *time relations* of the individual acts, by transferring the movements, by means of his air tambours, to a recording surface. Recently, by means of a revolving camera, he has succeeded in **photographing**, in instantaneous pictures ($\frac{1}{1000}$ second), the whole series of acts. Of course this series, when placed in the zoetrope, represents the natural movements. Figs. 349, 350, 351 represent these acts.

In **walking**, the legs are active alternately; while one—the "supporting" or "active" leg—carries the trunk, the other is "inactive" or "passive." Each leg is alternately in an active and a passive phase. Walking may be divided into the following movements:—

I. Act (Fig. 348, 2).—The *active* leg is vertical, slightly flexed at the knee, and it alone supports the centre of gravity of the body. The passive leg is completely extended, and touches the ground

only with the tip of the great toe (z). This position of the leg corresponds to a right-angled triangle, in which the active leg and the ground form two sides, while the passive leg is the hypothenuse.

II. Act.—For the forward movement of the trunk, the active leg is inclined slightly from its vertical position (cathetus) to an oblique and more forward (hypothenuse) position (3). In order that the trunk may remain at the same height, it is necessary that the active leg be lengthened. This is accomplished by completely extending the knee (3, 4, 5), as well as by lifting the heel from the

FIG. 348.



Phases of walking. The thick lines represent the active, the thin the passive leg; *h*, the hip joint; *k*, *a*, knee; *f*, *b*, ankle; *c*, *d*, heel; *m*, *e*, ball of the tarso-metatarsal joint; *z*, *g*, point of great toe.

ground (4, 5), so that the foot rests on the balls or the heads of the metatarsal bones, and, lastly, by elevating it on the point of the great toe (2, thin line). *During* the extension and forward movement of the active leg, the tips of the toes of the passive leg have left the ground (3). It is slightly flexed at the knee joint (owing to the shortening), it performs a "pendulum-like movement" (4, 5), whereby its foot is moved as far in front of the active leg as it was formerly behind it. The foot is then placed flat upon the ground (1, 2, thick lines); the centre of gravity is now transferred to this

FIG. 349.

Phases of slow walking. Instantaneous photograph (*Marey*), only the side directed to the observer is shown. From the vertical position of the right, active leg; (I), all the phases of this leg are represented in six pictures (I to VI), while after VI the vertical position is regained. The Arabic numerals indicate the simultaneous position of the corresponding left leg; thus 1 = I, 2 = II, etc., so that during the position IV of the right leg, at the same time the left leg has the position as 1.

active leg, which, at the same time, is slightly flexed at the knee, and placed vertically. The first act is then repeated.

Simultaneous Movements of the Trunk.—During walking, the trunk performs certain characteristic movements. (1) It leans every time toward the active leg, owing to the traction of the glutei and the tensor fasciæ latæ, so that the centre of gravity is moved, which in short, heavy persons with a broad pelvis leads to their "waddling" gait. (2) The trunk, especially during rapid walking, is inclined slightly forward to overcome the resistance of the air. (3) During the "pendulum-

like action," the trunk rotates slightly on the head of the active femur. This rotation is compensated, especially in rapid walking, by the arm of the same side as the oscillating leg swinging in the opposite direction, while that on the other side at the same time swings in the same direction as the oscillating limb.

Modifying Conditions: 1. *The Duration of the Step.*—As the rapidity of the vibration of a pendulum (leg) depends upon its length, it is evident that each individual, according to the length of his legs, must have a certain natural rate of walking. The "*duration of a step*" depends also upon the time during which both feet touch the ground simultaneously, which, of course, can be altered voluntarily. When "walking rapidly" the time = O, *i. e.*, at the same moment in which the active leg reaches the ground, the passive leg is raised. 2. *The length of the step* is usually about 6 to 7 decimetres [23 to 27 inches], and it must be greater, the more the length of the hypothenuse of the passive leg exceeds the cathetus of the active one. Hence, during a long step, the active leg is greatly shortened (by flexion of the knee), so that the trunk is pulled downward. Similarly, long legs can make longer steps.

According to Marey and others, the **pendulum movement** of the passive leg is not a true pendulum movement, because its movement, owing to muscular action, is of more uniform rapidity. During the pendulum movement of the whole limb, the leg vibrates by itself at the knee joint (*Luca, H. Vierordt*).

Fixation of the Femur.—According to Ed. and W. Weber, the head of the femur of the passive leg is fixed in its socket chiefly by the **atmospheric pressure,** so that no muscular action is necessary for carrying the whole limb. If all the muscles and the capsule be divided, the head of the femur

FIG. 350.

Instantaneous photograph of a runner (*Marey*). Ten pictures per second. The abscissa indicates the length of the step in metres.

still remains in the cotyloid cavity. Rose refers this condition not to the action of the atmospheric pressure, but to two adhesion surfaces united by means of synovia. The experiments of Aeby show that not only the weight of the limb is supported by the atmospheric pressure, but that the latter can support several times this weight. When traction is exerted on the limb, the margins of the cotyloid ligament of the cotyloid cavity are applied like a valve tightly to the margin of the cartilage of the head of the femur. According to the Brothers Weber, the leg falls from its socket as soon as air is admitted by making a perforation into the articular cavity.

Work done during Walking.—Marey and Demery estimate the amount done by a man weighing 64 kilos. [10 stones], when walking slowly, as = 6 kilogramme-metres per second; rapid running = 56 kilogramme-metres. The work done is due to the raising of the entire body and extremities, to the velocity communicated to the body, as well as to the maintenance of the centre of gravity.

In **springing** or **leaping**, the body is rapidly projected upward by the greatest possible and most rapid contraction of the muscles, while at the same time the centre of gravity is maintained by other muscular acts (Fig. 351).

The **pressure** upon the sole of the foot in walking is distributed in the following manner: The supporting leg always presses more strongly on the ground than the other; the longer the step the greater the pressure. The heel receives the maximum amount of pressure sooner than the point of the foot (*Carlet*).

Running is distinguished from rapid walking by the fact that, at a particular moment both legs do not touch the ground, so that the body is raised in the air.

The active leg, as it is forciby extended from a flexed position, gives the body the necessary impetus (Fig. 350).

Pathological.—Variations of the walking movements depend primarily upon diseases of bones, ligaments, muscles, and tendons, and also upon affections of the motor nerves. The effect of sensory nerves and the reflex mechanism of the spinal cord, and also of the muscular sense on walking, are stated in §§ 355, 360, 430.

311. **COMPARATIVE.**—The **absolute muscular force** in animals is not, as a rule, much different from that in man. The great motor power exerted by animals results from the **thickness** and **number** of the muscles, as well as from the different arrangement of the levers and the action of muscles on them. Insects particularly exert a large amount of force; some insects can drag a body sixty-seven times their own weight; a horse scarcely its own weight. A man pressing upon a dynamometer with one hand exerts pressure = 0.70 times his own weight, while a dog lifting its lower jaw exerts 8.3 times. A crab by closing its pincers 28.5 times. A mussel on closing its shell 382 times its body weight (*Plateau*).

In **mammals** standing is much more easy, as they have four supporting surfaces. The springing animals have a sitting attitude, while the tail is often used as a support (kangaroo, squirrel). In **birds,** there is a mechanical arrangement by which, while perching, the tendons are flexed; hence,

FIG. 351.

High leap. Instantaneous photograph (*Marey*). The pictures partly overlap each other, as soon as the velocity of the forward movement on the descent diminishes after springing. In the left-hand corner is the dial plate, the radius of which moved one division in $\frac{1}{10}$ second. The abscissa indicates the distance in metres.

a bird while sleeping can still retain its hold (*Cuvier*). In the stork and crane, which stand for a long time on one leg, this act is unaccompanied by muscular action, as the tibia is fixed by means of a process which fits into a depression of the articular surface of the femur.

In **walking,** we distinguish in mammals the **step** (le pas)—the four feet are generally moved in four tempo, and usually diagonally, *e. g.*, in the horse right fore, left hind; left fore, right hind. [The camel is an exception—it moves the fore and hind limbs simultaneously on each side.] In **trotting** this movement is accelerated; the two limbs in a diagonal direction lift together, so that only two hoof sounds are heard while at the same time, the body is raised more in the air. During the interval between two hoof beats the body is free in the air, all the limbs having left the ground. Strictly speaking, the fore limb leaves the ground slightly sooner than the hind one. The **gallop.**—When a (right) galloping horse moves in the air, the upper part of its body is fairly horizontal; when it touches the ground, the left hind foot is the first to touch the ground. Shortly thereafter, the left fore and right hind foot touch the ground, while the right fore leg has not yet reached the ground and is directed forward. The upper part of the body still retains its horizontal direction. When, however, a few moments thereafter, the left hind leg again leaves the ground, it is higher than the fore leg—simultaneously the right fore leg is thrown forward and lower, while the right hind and left fore leg are stretched to the extreme. Immediately thereafter these limbs leave the ground, while the hind limb so far overtakes the fore limb that it comes to lie higher than the latter. The body, therefore, is projected forward and downward until the right fore limb, which alone touches the

ground, actively contracts and again raises the body from the ground. When this happens, the horse again floats in the air, its body being directed horizontally. The long axis of the horse's body in galloping is placed obliquely to the direction of movement, and forming a right angle. In forced galloping (la carrière), which is really a springing movement, the right hind leg and left fore leg do not touch the ground at the same time, but the former does so sooner. The **amble** is a modification of the step, which consists in this, that both feet on the *same* side move at the same time or shortly after each other (camel, giraffe, elephant). Marey attached compressible ampullæ under the hoof of a horse, connecting them with registering apparatus, and thus accurately registered the time relation of each act. Muybridge photographed the actions of a horse and the different phases of the movement.

In **snakes** the rudder-like elevation and depression of the ribs cause the progression of the body.

Swimming is an acquired art in **man**. The specific gravity of the body is slightly greater than that of ordinary water, but slightly lighter than that of sea water. When lying quietly on the back, so that only the mouth and nose are at last above the water, very slight movements of the hands are necessary to keep a person from sinking. In this position, progression can be accomplished by extending and adducting the legs, while the movement is accelerated by rudder-like movements of the arms. Swimming belly downward is more difficult, because the head, being held above the water, makes the body specifically heavier. The forward movement and the act of supporting the body in the water consist of three acts:—*First*, horizontal, rudder-like movements of the extended arms from before backward, until they reach the horizontal position (forward movement); *second*, pressure of the arms downward, with subsequent adduction of the elbow-joint to the body (elevation of the body), together with retraction of the extended legs; *third*, projection of the arms, now brought together, and at the same time extension and adduction of the legs obliquely backward and downward, thus causing elevation of the body as well as a forward movement. Too rapid movements cause fatigue, while the respirations must be carefully regulated. Many **land mammals**, whose body is specifically lighter than water, can swim, especially with the aid of their hind limbs, while at the same time, all the legs being directed downward, and being specifically the heaviest part of the body, keep the trunk in the normal position. **Fishes** chiefly use their tail fin as a motor organ, which is moved by powerful lateral muscles. When the tail is suddenly extended, it presses upon the water and displaces it. Some fish, as the salmon, can lift their body out of the water by a blow of their tail fin. The dorsal and anal fins enable the animal to preserve the erect position. The pectoral and abdominal fins corresponding to the extremities execute slight movements, especially upward and downward, which are greater during sleep. The **swimming bladder** is the homologue of the lung, and is used for hydrostatic purposes in some fishes, and as an auxiliary respiratory organ in others, *e. g.*, the dipnoi (§ 140). It is absent or rudimentary in the cyclostomata. In **swimming birds**, the body is specifically very much lighter than the water, while their feathers are lubricated by the oily secretion of the coccygeal glands (§ 291). Their feet are usually webbed.

Flight.—Bats and their allies are the only flying mammals. The bones of the upper limb and phalanges are greatly elongated, and between these and the elongated hind limb (except the foot) there is stretched a thin membrane. The membrane is moved by the powerful pectoral muscles. The flying squirrel has only a duplicature of the skin stretched between the large bones of the extremities, which serves as a parachute when the animals spring. In **birds** the body is specifically light; numerous air sacs in the chest and belly communicate with the lungs, and with the cavities of most of the bones (§ 140). The modified upper extremities are supported by the coracoid bone and the united clavicles or furculum, and are moved by the powerful pectoral muscles attached to the keeled sternum. Marey, by means of his revolving photographic camera, has analyzed all the phases of flight in a bird.

[Werner has studied the **movements of the fingers** and correlated these movements with changes in the nerve centres in certain diseased conditions, *e. g.*, chorea. An india-rubber tube is attached to each finger, and this "motor" part of the apparatus is connected with a Marey's tambour. The several finger tubes are fixed to an arrangement not unlike a cricketer's glove, so that voluntary or involuntary movements of the fingers can be registered and studied.]

312. VOICE AND SPEECH, PHYSICAL CONSIDERATIONS.

—The blast of **expired** air—and under certain circumstances, the inspiratory blast also—is employed to throw the tense vocal cords into a state of regular vibration, whereby a sound is produced. The sound so produced is the human voice.

The **true vocal cords** are really elastic membranous reeds. If a blast of air be forcibly driven upward through the partially closed glottis, the vocal cords are pushed asunder, as the elastic tension of the air overcomes the resistance of the cords. After the escape of air from below, the cords rapidly return to their former position, and are again pushed asunder, and caused to vibrate.

1. Thus, when a membrane vibrates, the air must be alternately condensed and rarefied. The condensation and rarefaction are the chief cause of the tone or note (as in the siren), not so much the membranes themselves (*v. Helmholtz*).

2. The **air tube** or "**porte vente**," conducting the air to the membranes in man is the lo portion of the larynx, the trachea, and the whole bronchial system; the **bellows** are represented the chest and lungs, which are forcibly diminished in size by the expiratory muscles.

3. The cavities which lie above the membranes constitute "**resonators**," and consist of the up part of the larynx, pharynx, and also of the cavities of the nose and mouth, arranged, as it were, two stories, the one over the other, which can be closed alternately.

The **pitch of the tone** produced by a membranous apparatus depends upon the followi factors:—

(*a*) On the *length* of the elastic membranes or plates. The pitch is inversely proportional to t length of the elastic membrane, *i. e.*, the shorter the membrane the higher the pitch, or the gre the number of vibrations per second. Hence, the pitch of a child's vocal cords (shorter) is hig than that of an adult.

(*b*) The pitch of the tone is directly proportional to the square root of the amount of the elastic of the elastic membrane. In membranous reeds, and also with silk, it is directly proportional to square root of the extending weight, which in the case of the larynx is the force of the mus rendering the cords tense.

(*c*) The tone of membranous reeds is not only *strengthened by a more powerful blast*, as amplitude of the vibrations is increased, but the *pitch of the tone may also be raised* at the s time, because, owing to the great amplitude of the vibration, the mean tension of the elastic m brane is increased.

(*d*) The supra-laryngeal cavities, which act as **resonators**, are also inflated when the larynx action, so that the tone produced by these cavities is added to and blended with the sound of elastic membranes, whereby certain partial tones of the latter are strengthened (§ 415). The acteristic timbre of the voice largely depends upon the form of the resonators.

(*e*) When vocalizing, the strongest resonance takes place in the *air tubes*, as they co compressed air. It causes the vocal fremitus which is audible on placing the ear over the (§ 117, 6).

(*f*) *Narrowing or dilating* the glottis has no effect on the pitch of the tone, only with a glottis much more air must be driven through it, which, of course, greatly increases the work of thorax.

313. ARRANGEMENT OF THE LARYNX.—I. Cartilages and Ligaments.—The fundamental part of the larynx consists of the **cricoid** cartilage, whose small, narrow portion is directed forward and the broad plate backward. The **thyroid** cartilage articulates by its inferior cornu with the posterior lateral portion of the cricoid. This permits of the thyroid cartilage rotating upon a horizontal axis directed through both of the articular surfaces, so that the upper margin of the thyroid passes forward and downward, while the joint is so constructed as to permit also of a slight upward, downward, forward, and backward movement of the thyroid upon the cricoid cartilage. The triangular **arytenoid** cartilages articulate at some distance from the middle line, with oval, saddle-like, articular surfaces placed upon the upper margin of the plate of the cricoid cartilage. The articular surfaces permit two kinds of movements on the part of the arytenoid cartilages; first, **rotation** on their base around their ver cal long axis, whereby either the anterior angle or processus vocalis, which directed forward, is rotated outward; while the processus muscularis, which directed outward and projects over the margin of the cricoid cartilage, is rotate backward and inward, or conversely. Further, the arytenoids may be slightl **displaced** upon their bases either outward or inward.

The true vocal cords, or thyro-arytenoid ligaments, are in man about 1 millimetres, and in woman 11 millimetres in length, and consist of numerous elastic fibres. They arise close to each other from near the middle of the inner angle of the thyroid cartilage, and are inserted, each into the anterior angle or processus vocalis of the arytenoid cartilages. The **ventricles of Morgagni** permit free vibration of the true vocal cords, and separate them from the upper or false cords, which consist of folds of mucous membrane. The false vocal cords are not concerned in phonation, but the secretion of their numerous mucous glands moistens the true vocal cords.

The obliquely directed under-surface of the vocal cords causes the cords to come together very easily when the glottis is narrow during respiration (*e. g.*, in sobbing), while the closure may be made more secure by respiration. The opposite is the condition of the false vocal cords, which,

when they touch, are easily separated during inspiration; while during expiration, owing to the dilatation of the ventricles of Morgagni, they easily come together and close (*Wyllie, L. Brunton and Cash*).

II. Action of the Laryngeal Muscles.—These muscles have a double function: 1. One connected with **respiration,** in as far as the glottis is widened and narrowed alternately during respiration; further, when the glottis is firmly closed by these muscles, the entrance of foreign substances into the larynx is prevented. The glottis is closed immediately before the act of coughing (§ 120). 2. The laryngeal muscles give the vocal cords the proper tension and other conditions for **phonation.**

FIG. 352.



Larynx from the front, with the ligaments and the insertions of the muscles. *O.h.*, Os hyoideum; *C.th.*, Cart. thyreoidea; *Corp. trit.*, Corpus triticeum; *C.c.*, Cart. cricoidea; *C.tr.*, Cart. tracheales; *Lig. thyr.-hyoid. med.*, Ligamentum thyreo-hyoideum medium; *Lig. th.-h. lat.*, Ligam. thyreo-hyoideum laterale; *Lig. cric. thyr. med.*, Ligam. crico-thyreoideum medium; *Lig. cric.-trach.*, Ligam. crico-tracheale; *M. St.-h.*, Musc. sterno-hyoideus; *M. th.-hyoid.*, Musc. thyreo-hyoideus; *M. st.-th.*, Musc. sterno-thyreoideus; *M. cr.-th.*, Musc. crico-thyreoideus.

FIG. 353.



Larynx from behind after removal of the muscles. *E.*, Epiglottis cushion (W.); *L. ar.-ep.*, Lig. ary-epiglotticum; *M.m.*, Membrana mucosa; *C.W.*, Cart. Wrisbergii; *C.S.*, Cart. Santorini; *C. aryt.*, Cart. arytænoidea; *C.c.*, Cart. cricoidea; *P.m.*, Processus muscularis of Cart. arytæn; *L. cr.-ar.*, Ligam. crico-arytæan; *C.s.*, Cornu superius; *C.i.*, Cornu inferius Cart. thyreoidea. *L. ce.-cr. p. i.*, Lig. kerato-cricoideum. post. inf.; *C.tr.*, Cart. tracheales; *P.m.tr.*, Pars membranacea tracheæ.

1. The **glottis is dilated** by the action of the **posterior crico-arytenoid** muscles. When they contract they pull both processus musculares of the arytenoid cartilages backward, downward, and toward the middle line (Fig. 356), so that the processus vocales (I, I) must go apart and upward (II, II). Thus, between the vocal cords (**glottis vocalis**), as well as between the inner margins of the arytenoid cartilages, a large triangular space is formed (**glottis respiratoria**), and these spaces are so arranged that their bases come together, so that the aperture between the cords and the arytenoid cartilages has a rhomboidal form. Fig. 356 shows the action of the muscles. The vocal cords, represented by lines converging in front, arise from the anterior angle of the arytenoid cartilages (I, I). When

these cartilages are rotated into the position (II, II), the cords take the position indicated by the dotted lines. The widening of the respiratory portion of the glottis between the arytenoid cartilages is also indicated in the diagram.

Pathological.—When these muscles are paralyzed, the widening of the glottis does not take place, and there may be severe dyspnœa during inspiration, although the voice is unaffected (*Riegel, L. Weber*). In a larynx just excised, the dilators are the first to lose their excitability (*Semon and Horsley*).

2. The entrance to the **glottis is constricted** by the **arytenoid muscle** (transverse), which extends transversely between both outer surfaces of the aryte-

FIG. 354.



Larynx from behind with its muscles. *E.*, Epiglottis, with the cushion (W.); *C.W.*, Cart. Wrisbergii; *C.S.*, Cart. Santorini; *C.c.*, Cart. cricoidea. Cornu sup.—Cornu inf., Cart. thyreoideæ; *M. ar. tr.*, Musc. arytænoideus transversus; *Mm. ar. obl.*, Musculi arytænoidei obliqui; *M. cr.-aryt. post.*, Musculus crico-arytænoideus posticus; *Pars cart.*, Pars cartilaginea; *Pars memb.*, Pars membranacea tracheæ.

FIG. 355.



Nerves of the larynx. *O.h.* Os hyoideum; *C.th.*, Cart. thyreoidea; *C.c.*, Cart. cricoidea; *Tr.*, Trachea; *M. th.-ar.*, M. thyreo-arytænoideus *M. cr.-ar. p.*, M. crico-arytænoideus posticus; *M. cr.-ar. l.*, M. crico-arytæn. lateralis; *M. cr.-th.*, M. crico-thyreoideus; *N. lar. sup. v.*, N. laryngeus sup.; *R.I.*, Ramus internus; *R.E.*, Ramus ext.; *N. lar. rec. v.*, N. laryngeus recurrens; *R.I.N.L.R.*, Ramus int.; *R.E.N.L.R.*, Ramus ext. nervi laryngei recurrentis vagi.

noids along their whole length (Fig. 357). On the posterior surface of this muscle is placed the cross bundles (Fig. 354) of the thyro-aryepiglotticus (or arytænoidei obliqui); they act like the foregoing. The action of these muscles is indicated in Fig. 357; the arrows point to the line of traction.

Pathological.—Paralysis of this muscle enfeebles the voice and makes it hoarse, as much air escapes between the arytenoid cartilages during phonation.

3. In order that the **vocal cords** be **approximated** to each other, which occurs during phonation, the processus vocales of the arytenoid cartilages must be closely apposed, whereby they must be rotated inward and downward. This

result is brought about by the processus musculares being moved in a forward and upward direction by the **thyro-arytenoid** muscles. These muscles are applied to, and in fact are imbedded in, the substance of the elastic vocal cords, and

FIG. 356.



Schematic horizontal section of the larynx. I, Position of the horizontally divided arytenoid cartilages during respiration; from their anterior processes run the converging vocal cords. The arrows show the line of traction of the *posterior crico-arytenoid* muscles; II, II, the position of the arytenoid muscles as a result of this action.

FIG. 357.



Schematic horizontal section of the larynx, to illustrate the action of the *arytenoid muscle*. I, I, position of the arytenoid cartilages during quiet respiration. The arrows indicate the direction of the contraction of the muscle; II, II, the position of the arytenoid cartilages after the arytenoideus contracts.

their fibres reach to the external surface of the arytenoid cartilages. When they contract, they rotate these cartilages so that the processus vocales must rotate inward. The glottis vocalis is thereby narrowed to a mere slit (Fig. 358), while the glottis respiratoria remains as a broad triangular opening. The action of these muscles is indicated in Fig. 358.

FIG. 358.



Scheme of the closure of the glottis by the *thyro-arytenoid* muscles. II, II, position of the arytenoid cartilages during quiet respiration. The arrows indicate the direction of the muscular traction. I, I, position of the arytenoid cartilages after the muscles contract.

The **lateral crico-arytenoid** muscle is inserted into the anterior margin of the articular surface of the arytenoid cartilage; hence, it can only pull the cartilage forward; but some have supposed that it can also rotate the arytenoid cartilage in a manner similar to the thyro-arytenoid (?), with this difference, that the processus vocales do not come so close to each other.

Pathological.—Paralysis of both thyro-arytenoid muscles causes loss of voice.

4. The **vocal cords are rendered tense** by their points of attachment being removed from each other by the action of muscles. The chief agents in this action are the **crico-thyroid muscles,** which pull the thyroid cartilage forward and downward. At the same time, however, the

posterior crico-arytenoids must pull the arytenoid cartilages slightly backward, and also keep them fixed.

The genio-hyoid and thyro-hyoid, when they contract, pull the thyroid upward and forward toward the chin, and also tend to increase the tension of the vocal cords (*C. Mayer*, *Grützner*).

Pathological.—Paralysis of the crico-thyroid causes the voice to become harsh and deep, owing to the vocal cords not being sufficiently tense.

Position during Phonation.—The tension of the vocal cords brought about in this way is not of itself sufficient for phonation. The triangular aperture of the glottis respiratoria between the arytenoid cartilages, produced by the unaided action of the internal thyro-arytenoid muscles (see 3) must be closed by the action of the transverse and oblique arytenoid muscles. The vocal cords themselves must have a concave margin, which is obtained through the action of the crico-thyroids and posterior crico-arytenoids, so that the glottis vocalis presents the appearance of a myrtle leaf (*Henle*), while the rima glottidis has the form of a linear slit (Fig. 362). The contraction of the internal thyro-arytenoid converts the concave margin of the vocal cords into a straight margin. This muscle adjusts the delicate variations of tension of the vocal cords themselves, causing more especially such variations as are necessary for the production of tones of slightly different pitch. As these muscles come close to the margin of the cords, and are securely woven, as it were, among the elastic fibres of which the cords consist, they are specially adapted for the above-mentioned purpose. When the muscles contract, they give the necessary resistance to the cords, thus favoring their vibration. As some of the muscular fibres end in the elastic fibres of the cords, these fibres, when they contract, can render certain parts of the cords more tense than others, and thus favor the modifications in the formation of the tones. The *coarser* variations in the tension of the vocal cords are produced by the separation of the thyroid from the arytenoid cartilages, while the *finer* variations of tension are produced by the thyro-arytenoid muscles. The value of the elastic tissue of the cords does not depend so much upon its extensibility, as upon its property of shortening without forming folds and creases.

Pathological.—In paralysis of these muscles, the voice can only be produced by forcible expiration, as much air escapes through the glottis; the tones are at the same time deep and impure. Paralysis of the muscle of one side causes flapping of the vocal cord on that side (*Gerhardt*).

5. The relaxation of the vocal cords occurs spontaneously when the stretching forces cease to act; the elasticity of the displaced thyroid and arytenoid cartilages comes into play, and restores them to their original position. The vocal cords are also relaxed by the action of the thyro-arytenoid and lateral crico-arytenoid muscles.

It is evident, from the above statements, that **tension of the vocal cords** and **narrowing of the glottis** are necessary for **phonation.** The tension is produced by the crico-thyroids and posterior crico-arytenoids; the narrowing of the glottis respiratoria by the arytenoids, transverse and oblique, the glottis vocalis being narrowed by the thyro-arytenoids and (? lateral crico-arytenoids), the former muscles causing the cords themselves to become tense.

Nerves (§ 352, 5).—The crico-thyroid is supplied by the superior laryngeal branch of the vagus, which at the same time is the sensory nerve of the mucous membrane of the larynx. All the other intrinsic muscles of the larynx are supplied by the inferior laryngeal.

The mucous membrane of the larynx is richly supplied with elastic fibres, and so is the submucosa. The sub-mucosa is more lax near the entrance to the glottis and in the ventricles of Morgagni, which explains the enormous swelling that sometimes occurs in these parts in œdema glottidis. A thin, clear, limiting membrane lies under the epithelium. The **epithelium** is stratified, cylindrical, and ciliated with intervening goblet cells. On the true vocal cords and the anterior surface of the epiglottis, however, this is replaced by stratified squamous epithelium, which covers the small papillæ of the mucous membrane. Numerous branched *mucous glands* occur over the car-

ages of Wrisberg, the cushion of the epiglottis, and in the ventricles of Morgagni; in other situa-ons, as on the posterior surface of the larynx, the glands are more scattered. The **blood vessels** rm a dense capillary plexus under the membrana propria of the mucous membrane; under this, owever, there are other two strata of blood vessels. The **lymphatics** form a superficial, narrow eshwork under the blood capillaries, with a deeper, coarser plexus. The medullated **nerves** ve ganglia in their branches, but their mode of termination is unknown. [W. Stirling has escribed a rich sub-epithelial plexus of medullated nerve fibres on the anterior surface of the epi-ottis, while he finds that there are ganglionic cells in the course of the superior laryngeal nerve.]

Cartilages.—The thyroid, cricoid, and nearly the whole of the arytenoid cartilages consist of *aline* cartilage. The two former are prone to ossify. The apex and processus vocalis of the ytenoid cartilages consist of *yellow fibro-cartilage*, and so do all the other cartilages of the larynx.

The larynx grows until about the sixth year, when it rests for a time, but it becomes again much rger at puberty (§ 434).

FIG. 359.



ertical section through the head and neck, to the first dorsal vertebra. *a*, position of the laryngoscope on observing the posterior part of the glottis, arytenoid cartilages, and upper surface of the posterior wall of the larynx; *b*, its position on observing the anterior angle of the glottis. Large, *a*, and *b*, small laryngoscopic mirrors.

314. **LARYNGOSCOPY.—Historical.**—After Bozzini (1807) gave the first impulse toward he investigation of the internal cavities of the body, by illuminating them with the aid of mirrors, Babington (1829) actually observed the glottis in this way. The famous singer, Manuel Garcia 1854), made investigations both on himself and other singers, regarding the movements of the ocal cords, during respiration and phonation. The examination of the larynx by means of the aryngoscope was rendered practicable chiefly by Türck (1857) and Czermak, the latter observer eing the first to use the light of a lamp for the illumination of the larynx. Rhinoscopy was actu-lly first practiced by Baumès (1838), but Czermak was the first person who investigated this subject ystematically.

The Laryngoscope consists of a small mirror fixed to a long handle, at an angle of 125° to 130° (Fig. 359, *a*, *b*). When the mouth is opened, and the tongue drawn forward, the mirror is introduced, as is shown in Fig. 360. The position of the mirror must be varied, according to the portion of the larynx we wish to examine; in some cases, the soft palate has to be raised by the back of the mirror, as in the position *b*. A picture of the part of the larynx examined is formed in the small mirror, the rays of light passing in the direction indicated by the dotted lines from the mirror; they are reflected at the same angle through the mouth into the eye of the observer, who must place himself in the direction of the reflected rays.

The illumination of the larynx is accomplished either by means of direct sunlight or by light from an artificial source, *e.g.*, an ordinary lamp, an oxyhydrogen lime-light, or the electric light.

FIG. 360.

Method of examining the larynx.

The beam of light impinges upon a *concave mirror* of 15 to 20 centimetres focus, and 10 centimetres in width, and from its surface the concentrated beam of light is reflected through the mouth of the patient, and directed upon the small mirror held in the back part of the throat. The beam of light is reflected at the same angle toward the larynx by the small throat mirror, so that the larynx is brightly illuminated. The observer has now to direct his eye in the same direction as the illuminating rays, which can be accomplished by having a hole in the centre of the concave mirror, through which the observer looks. Practically, however, this is unnecessary; all that is necessary is to fix the concave mirror to the forehead by means of a broad elastic band, so that the observer, by looking just under the margin of the concave mirror, can see the picture of the larynx in the small throat mirror (Fig. 360).

FIG. 361.

The larynx, as seen with the laryngoscope. *L.*, tongue; *E.*, epiglottis; *V.*, valleculla; *R.*, glottis; *L. v.*, true vocal cords; *S. M.*, sinus Morgagni; *L. v. s.*, false vocal cords; *P.*, position of pharynx; *S.*, cartilage of Santorini; *W.*, of Wrisberg; *S. p.*, sinus piriformes.

In order to examine the larynx, place the patient immediately in front of you, and cause him to open his mouth and protrude his tongue. A lamp is placed at the side of the head of the patient, and light from this source is reflected from the concave mirror on the observer's forehead, and concentrated upon the laryngoscopic mirror introduced into the back part of the throat of the patient (Fig. 360).

Oertel was able by means of a rapid intermittent illumination of the larynx through a stroboscopic disk, to study the movements of the vocal cords directly with the eye. Simanowsky put a photographic camera in the position of the eye and photographed the movements of the vocal cords of an artificial larynx. [Brown and Behnke have photographed the human vocal cords.]

Laryngeal Electrodes.— v. Ziemssen introduces long narrow electrodes into the larynx, to stimulate the muscles and study their actions. Rossbach finds that the muscles and nerves of the interior of the larynx may be

Those methods are used both for ph

Picture of the Larynx.—Fig. 361 shows the following structures: *L.*, the root of the tongue, with the ligamentum glosso-epiglotticum continued from its middle; on each side of the latter are *V. V.*, the so-called *valleculæ*. The *epiglottis* (*E.*) appears like an arched upper lip; under it, during normal respiration, are the lancet-shaped *glottis* (*R.*) and on each side of it the *true vocal cords* (*L. v.*). The length of the vocal cord in a child is 6 to 8 mm., in the female 10 to 15 mm. when they are relaxed, and 15 to 20 mm. when tense. In man, the lengths under the same conditions are 15 to 20 mm. and 20 to 25 mm. The breadth varies from 2 to 5 mm. On the external side of each vocal cord is the entrance to the *sinus of Morgagni* (*S. M.*), represented as a dark line. Further upward and more external are (*L. v. s.*) the upper or *false vocal cords*. [The upper or false vocal cords are red, the lower or true, white.] On each side of *P.* are (*S. S.*),

FIG. 362.

Position of the vocal cords on uttering a high note.

FIG. 363.

View of the rings and bifurcation of trachea.

FIG. 364.



Position of the laryngoscopic mirror in rhinoscopy.

the apices of the *cartilages of Santorini*, placed upon the apices of the arytenoid cartilages, while immediately behind is the wall of the pharynx, *P.* In the aryteno-epiglottidean fold are (*W. W.*) the *cartilages of Wrisberg*, while outside these are the depressions (*S. p.*) constituting the *sinus piriformes*.

During normal respiration, the glottis has the form of a lancet-shaped slit between the bright, yellowish-white, vocal cords (Fig. 362). If a **deep inspiration** be taken, the glottis is considerably widened (Fig. 363), and if the mirror be favorably adjusted we may see the rings of the trachea, and even the bifurcation of the trachea.

If a **high note** be uttered, the glottis is contracted to a very narrow slit (Fig. 362).

Rhinoscopy.—If a small mirror, fixed to a handle at an angle of 100° to 110°, be introduced into the pharynx, as shown in Fig. 364, and if the mirror be directed *upward*, certain structures are with difficulty rendered visible (Fig. 365). In the middle is the septum narium (*S. n.*), and on each side of it the long oval large posterior nares (*Ch.*), below this the *soft palate* (*P.m.*), with the pendant *uvula* (*U.*). In the posterior nares are the posterior extremities of the lower (*C.i.*), middle (*C.m.*), and upper *turbinated bones* (*C.s.*). At the upper part, a portion of the roof of the pharynx (*O.R.*) is seen, with the arched masses of adenoid tissue lying between the openings of the *Eustachian tubes* (*T.T.*), and called by Luschka the *pharyngeal tonsils*. External to the openings of the Eustachian tube is the *tubular eminence* (*W.*), and outside this is the groove of Rosenmüller (*R.*).

FIG. 365.

Composite rhinoscopic view. *S.n.*, Septum narium; *C.i.*, *C.m.*, *C.s.*, lower, middle, and upper turbinated bones; *T*, Eustachian tube; *W.*, tubular eminence; *R.*, groove of Rosenmüller; *P. m.*, soft palate; *O. R.*, roof of pharynx; *U.*, uvula.

Experiments on the Larynx.—Ferrein (§ 741) and Joh. Müller made experiments upon the excised larynx. A tracheal tube was tied into the excised human larynx, and air was blown through it, the pressure being measured by means of a mercurial manometer, while various arrangements were adopted for putting the vocal cords on the stretch and for opening or closing the glottis.

315. CONDITIONS INFLUENCING THE LARYNGEAL SOUNDS.—The pitch of the note emitted by the larynx depends upon—

1. **The Tension of the Vocal Cords,** *i. e.*, upon the degree of contraction of the crico-thyroid and posterior crico-arytenoid muscles, and also of the internal thyro-arytenoids (§ 313, II, 4).

2. **The Length of the Vocal Cords.**—(*a*) Children and females with short vocal cords produce high notes. (*b*) If the arytenoid cartilages are pressed together by the action of the arytenoid muscles (transverse and oblique), so that the vocal cords alone can vibrate, while their intercartilaginous portions lying between the processus vocales do not, the tone thereby produced is higher (*Garcia*). In the production of low notes, the vocal cords, as well as the margins of the arytenoid cartilages, vibrate. At the same time the space above the entrance to the glottis is enlarged and the larynx becomes more prominent. (*c*) Every individual has a certain medium pitch of his voice, which corresponds to the smallest possible tension of the intrinsic muscles of the larynx.

3. **The Strength of the Blast.**—That the strength of the blast from below raises the pitch of the tones of the human larynx is shown by the fact, that tones of the highest pitch can only be uttered by powerful expiratory efforts. With tones of *medium* pitch, the pressure of the air in the trachea is 160 mm., with *high* pitch 200 mm., and with *very high* notes 945 mm., and in *whispering* 30 mm., of water (*Cagniard-Latour*). These results were obtained in a case of tracheal fistula.

Accessory Phenomena.—The following as yet but partially explained phenomena are observed in connection with the production of high notes: (*a*) As the pitch of the note rises, the larynx is elevated, partly because the muscles raising it are active, partly because the increased intra-tracheal pressure so lengthens the trachea, that the larynx is thereby raised; the uvula is raised more and more (*Labus*). (*b*) The upper vocal cords approximate to each other more and more, without, however, coming into contact, or participating in the vibrations. (*c*) The epiglottis inclines more and more backward over the glottis.

4. **The falsetto voice** with its soft timbre and the absence of resonance or pectoral fremitus in the air tubes is particularly interesting. Oertel observed that, during the falsetto voice, the vocal cords vibrated so as to form nodes across them, but sometimes there was only one node, so that the free margin of the cord and the basal margin vibrated, being separated from each other by a nodal line (par-

allel to the margins of the vocal cord). During a high falsetto note, there may be three such nodal lines parallel to each other. The nodal lines are produced probably by a partial contraction of the fibres of the thyro-arytenoid muscle (p. 563), while at the same time the vocal cords must be reduced to as thin plates as possible by the action of the crico-thyroid, posterior arytenoid, thyro- and genio-hyoid muscles (*Oertel*). The form of the glottis is elliptical, while with the chest voice the vocal cords are limited by straight surfaces; the air also passes more freely through the larynx.

Oertel also found that during the **falsetto voice** the epiglottis is erect. The apices of the arytenoid cartilages are slightly inclined backward, the whole larynx is larger from before backward, and narrower from side to side, the aryepiglottidean folds are tense with sharp margins, and the entrance to the ventricles of Morgagni is narrowed. The vocal cords are narrower, the processus vocales touch each other. The rotation of the arytenoid cartilages necessary for this is brought about by the action of the crico-arytenoid alone, while the thyro-arytenoid is to be regarded only as an accessory aid. The pitch of the note is increased solely by increased tension of the vocal cords. In addition, there are a number of transverse and longitudinal *partial vibrations*. During the **chest voice**, a smaller part of the margin vibrates than in the falsetto voice, so that in the production of the latter we are conscious of less muscular exertion in the larynx. The uvula is raised to the horizontal position.

Production of Voice.—In order that voice be produced, the following conditions are necessary: (1) The necessary amount of air is collected in the chest; (2) the larynx and its parts are fixed in the proper position; (3) air is then forced by an expiratory effort either through the linear chink of the closed glottis, so that the latter is forced open, or at first some air is allowed to pass through the glottis without producing a sound, but as the blast of air is strengthened the vocal cords are thrown into vibration.

316. RANGE OF THE VOICE.—The range of the human voice for **chest notes** is given in the following scheme:—

The accompanying figures indicate the number of vibrations per second in the corresponding tone. It is evident that from *c'* to *f'* is common to all voices, nevertheless, they have a different timbre. The lowest note or tone, which, however, is only occasionally sung by bass singers, is the contra-F, with 42 vibrations—the highest note of the soprano voice is *a'''*, with 1708 vibrations.

Timbre.—The voice of every individual has a peculiar *quality*, *clang*, or *timbre*, which depends upon the shape of all the cavities connected with the larynx. In the production of *nasal tones*, the air in the nose is caused to vibrate strongly, so that the entrance to the nares must necessarily be open.

317. SPEECH—THE VOWELS.—The motor processes connected with the production of **speech** occur in the **resonating cavities**, the pharynx, mouth, and nose, and are directed toward the production of musical tones and noises.

Whispering and Audible Speech.—When sounds or noises are produced in the resonating chambers, the larynx being passive, the vox clandestina, or **whispering** is produced; when the vocal cords, however, vibrate at the same time, "**audible speech**" is produced. [Whispering, therefore, is speech without voice.] Whispering may be fairly loud, but it requires great exertion, *i. e.*, a great expiratory blast for its production; hence it is very fatiguing. It may be performed both with inspiration and expiration, while audible speech is but temporary and indistinct, if it is produced during inspiration. Whispering is caused by the sound produced by the air passing over the obtuse margins of the cords. During the production of *audible sounds*, however, the sharp margins of the vocal cords are directed toward the air by the position of the processus vocales.

During speech the **soft palate** is in action; at each word it is raised, while at the same time, Passavant's transverse band is formed in the pharynx (§ 156). The soft palate is raised highest when **u** and **i** are sounded, then with *o* and *e*, and least with *a*. When sounding **m** and **n** it does not move; it is high (like **n**) during the utterance of the explosives. With **l**, **s**, and especially with the guttural **r**, it exhibits a trembling movement (*Gentzen*, *Falkson*).

Speech is composed of **vowels** and **consonants.**

A. Vowels (analysis and artificial formation, § 415).—**A.** During **whispering,** a vowel is the musical tone produced, either during expiration or inspiration, by the inflated characteristic form of the mouth, which not only has a definite *pitch*, but also a particular and characteristic *timbre*. The characteristic form of the mouth may be called "*vowel cavity*."

I. The pitch of the vowels may be estimated musically. It is remarkable that the fundamental tone of the "vowel cavity" is nearly constant at different ages and in the sexes. The different capacities of the mouth can be compensated for by different sizes of the oral aperture. The pitch of the vowel cavity may be estimated by placing a number of vibrating tuning forks of different pitch in front of the mouth, and testing them until we find the one which corresponds with the fundamental tone of the vowel cavity. This is known by the fact that the tone of the tuning-fork is intensified by the *resonance* of the air in the mouth, or the vibrations may be transferred to a vibrating membrane and recorded on a smoked surface, as in the phonautograph of Donders.

According to König, the **fundamental tones** of the vowel cavity are for

$$U = b,\ O = b',\ A = b'',\ E = b''',\ I = b''''.$$

If the vowels be whispered in this series, we find at once that their pitch rises. The fundamental tone in the production of a vowel may vary within certain limits. This may be shown by giving the mouth the characteristic position and then percussing the cheeks (*Auerbach*); the sound emitted is that of the vowel, whose pitch will vary according to the position of the mouth.

When **sounding A,** the mouth has the form of a funnel widening in front (Fig. 366, A). The tongue lies in the floor of the mouth, and the lips are wide open. The soft palate is moderately raised (*Czermak*). It is more elevated successively with O, E, U, I. The hyoid bone appears as if at rest, but the larynx is slightly raised. It is higher than with U, but lower than with I.

If we sound A to I, the larynx and the hyoid bone retain their *relative* position, but both are raised. In passing from A to U, the larynx is depressed as far as possible. The hyoid bone passes slightly forward (*Brücke*). When sounding A, the space between the larynx, posterior wall of the pharynx, soft palate, and the root of the tongue, is only moderately wide; it becomes wider with E, and especially with I (*Purkinje*), but it is smallest with U.

When **sounding U** (Fig. 366), the form of the cavity of the mouth is like that of a capacious flask with a short, narrow neck. The whole resonance apparatus is then longest. The lips are protruded as far as possible, are arranged in folds and closed, leaving only a small opening. The larynx is depressed as far as possible, while the root of the tongue is approximated to the posterior margin of the palatine arch.

When **sounding O,** the mouth, as in U, is like a wide-bellied flask with a short neck, but the latter is shorter and wider as the lips are nearer to the teeth. The larynx is slightly higher than with U, while the resonance chambers also are shorter (Fig. 366).

When **sounding I,** the cavity of the mouth, at the posterior part, is in the form of a small-bellied flask with a long narrow neck, of which the belly has the fundamental tone, f, the neck that of d''''. The resonating chambers are shortest, as the larynx is raised as much as possible, while the mouth

owing to the retraction of the lips, is bounded in front by the teeth. The cavity between the hard palate and the back of the tongue is exceedingly narrow, there being only a median narrow slit. Hence, the air can only enter with a clear piping noise, which sets even the vertex of the skull in vibration, and when the ears are stopped the sounds seem very shrill. When the larynx is depressed and the lips protruded, as for sounding U, I cannot be sounded.

When **sounding E**, which stands next to I, the cavity has also the form of a flask with a small belly (fundamental tone, f′), and with a long, narrow neck (fundamental tone, b‴′). The neck is wider, so that it does not give rise to a piping noise. The larynx is slightly lower than for I, but not so high as for A.

Fundamentally, there are only *three primary* vowels—I, A, U, the others and the so-called diphthongs standing between them (*Brücke*).

Diphthongs occur when, *during vocalization*, we pass from the position of one vowel into that of another. Distinct diphthongs are sounded only on passing from one vowel with the mouth wide open to one with the mouth narrow; during the converse process, the vowels appear to our ear to be separate (*Brücke*).

II. Timbre or **Clang Tint.**—Besides its pitch, every vowel has a special timbre, quality, or clang tint.

The vocal timbre of U (whispering) has, in addition to its fundamental tone, b, a deep piping timbre. The timbre depends upon the number and pitch of the *partials* or *overtones* of the vowel sound (§ 415).

FIG. 366.



Section of the parts concerned in phonation. Z, tongue; *p*, soft palate; *e*, epiglottis; *g*, glottis; *h*, hyoid bone; 1, thyroid, 2, 3, cricoid, 4, arytenoid cartilage.

Nasal Timbre.—The timbre is modified in a special manner when the vowels are spoken with a "nasal" twang, which is largely the case in the French language. The nasal timbre is produced by the soft palate not cutting off the nasal cavity completely, which happens every time a *pure* vowel is sounded, so that the air in the nasal cavity is thrown into sympathetic vibration. When a vowel is spoken with a nasal timbre, air passes out of the nose and mouth simultaneously, while with a pure vowel sound, it passes out only through the mouth.

When sounding a pure vowel (non-nasal), the shutting off of the nasal cavity from the mouth is so complete, that it requires an artificial pressure of 30 to 100 mm. of mercury to overcome it (*Hartmann*).

The vowels, a, ä (æ), ö (œ), o, e, are used with a nasal timbre—a nasal i does not occur in any language. Certainly it is very difficult to sound it thus, because when sounding i, the mouth is so narrow that when the passage to the nose is open, the air passes almost completely through the latter, while the small amount passing through the mouth scarcely suffices to produce a sound.

In sounding vowels, we must observe if they are sounded through a previously closed glottis, as is done in the German language in all words beginning with a vowel (spiritus lenis). The glottis, however, may be previously opened with a preliminary breath, followed by the vowel sound; we obtain the aspirate vowel (spiritus asper of the Greeks).

B. If the vowels are sounded in an **audible** tone, *i. e.*, along with the sound from the larynx, the fundamental tone of the vocal cavity strengthens in a characteristic manner the corresponding partial tones present in the laryngeal sound (*Wheatstone, v. Helmholtz*).

318. **CONSONANTS.**—The consonants are **noises** which are produced at certain parts of the resonance chamber. [As their name denotes, they can only be sounded in conjunction with a vowel.]

Classification.—The most obvious classification is according to (I) Their *acoustic properties*, so that they are divided into (1) *liquid* consonants, *i. e.*, such as are appreciable without a vowel (**m, n, l, r, s**); (2) *mutes*, including all the others, which cannot be distinctly heard without an accompanying vowel. (II) According to their *mechanism of formation*, as well as the type of the organ of speech, by which they are produced. They are divided into—

1. **Explosives.**—Their enunciation is accompanied by a kind of bursting open of an obstacle, or an explosion, occasioned by the confined and compressed air which causes a stronger or weaker noise; or, conversely, the current of air is suddenly *interrupted*, while, at the same time, the nasal cavities are cut off by the soft palate.

2. **Aspirates,** in which one part of the canal is constricted or stopped, so that the air rushes out through the constriction, causing a faint whistling noise. (The nasal cavity is cut off.) In uttering L, which is closely related to the aspirates, but differs from them in that the narrow passage for the rush of air is not in the middle, but at both sides of the middle of the closed part. (The nasal cavity is shut off.)

3. **Vibratives,** which are prodnced by air being forced through a narrow portion of the canal, so that the margins of the narrow tube are set in vibration. (The nasal cavity is shut off.)

4. **Resonants** (also called nasals or semi-vowels). The nasal cavity is completely free, while the vocal canal is completely closed in the front part of the oral channel. According to the position of the obstruction in the oral cavity, the air in a larger or smaller portion of the mouth is thrown into sympathetic vibration.

We may also classify them according to the *position* in *which they are produced* —the "**articulation positions**" of Brücke. These are:—

A. Between both lips; B, between the tongue and the hard palate; C, between the tongue and the soft palate; D, between the true vocal cords.

A. Consonants of the First Articulation Position.

1. **Explosive Labials.**—**b,** the voice is sounded before the slight explosion occurs; **p,** the voice is sounded after the much stronger explosion has taken place (*Kempelen*). [The former is spoken of as "voiced" and the latter as "breathed."]

2. **Aspirate Labials.**—**f,** between the upper incisor teeth and the lower lip (labio-dental). It is absent in all true Slavic words (*Purkiñe*); **v,** between both lips (labial); **w** is formed when the mouth is in the position for **f,** but instead of merely forcing in the air, the voice is sounded at the same time. Really there are two different **w**—one corresponding to the **labial f,** as in würde, and the labio-dental, *e. g.*, quelle (*Brücke*).

3. **Vibrative Labials.**—The burring sound, emitted by grooms, but not used in civilized language.

4. **Resonant Labials.**—**m** is formed essentially by sounding the voice whereby the air, in the mouth and nose, is thrown into sympathetic vibration ["voiced"].

B. Consonants of the Second Articulation Position.

1. The **explosives,** when enunciated sharply and without the voice, are **T** hard (also **dt** and **th**); when they are feeble and produced along with simultaneous laryngeal sounds (voice), we have **D** soft.

2. The **aspirates** embrace **S,** including **s** sharp, written **s s** or **s z,** which is produced without any audible laryngeal vibration; or soft, which requires the voice. Then, also, there are modifications according to the position where the noises are produced. The sharp aspirates include **Sch,** and the hard English **Th**; to the soft belong the French **J** soft, and the English **Th** soft. **L,** which occurs in many modifications, appears here, *e. g.*, the **L** soft of the French. **L** may be sounded soft with the voice, or sharp without it.

3. The **vibrative,** or **R,** which is generally voiced, but it can be formed without the larynx.

The **resonants** are **N** sounds, which also occur in several modifications.

C. Consonants of the Third Articulation Position.

1. The **explosives** are the **K** sounds, which are hard and breathed and not voiced; **G** sounds, which are voiced.

2. The **aspirates,** when hard and breathed but not voiced, the **Ch,** and when sounded softly and not voiced, **J** is formed.

3. The **vibrative** is the palatal **R,** which is produced by vibration of the uvula (*Brücke*).

4. The **resonant** is the palatal **N.**

D. Consonants of the Fourth Articulation Position.

1. An **explosive** sound does not occur when the glottis is forced open, if a vowel is loudly sounded with the glottis previously closed. If this occurs during whispering, a feeble short noise, due to the sudden opening of the glottis, may be heard.

2. The **aspirates** of the glottis are the **H** sounds, which are produced when the glottis is moderately wide.

3. A **glottis vibrative** occurs in the so-called laryngeal **R** of lower Saxon (*Brücke*).

4. A **laryngeal resonant** cannot exist.

The **combination** of different consonants is accomplished by the successive movements necessary for each being rapidly executed. Compound consonants, however, are such as are formed when the oral parts are adjusted simultaneously for two different consonants, so that a mixed sound is formed from two. Examples: **Sch—tsch, tz, ts—Ps** (ψ)**—Ks** ($X\Xi$).

319. PATHOLOGICAL VARIATIONS OF VOICE AND SPEECH.—Aphonia.—Paralysis of the motor nerves (vagus) of the larynx by injury, or the pressure of tumors, causes **aphonia** or **loss of voice** (*Galen*). In aneurism of the aortic arch, the left recurrent nerve may be paralyzed from pressure. The laryngeal nerves may be temporarily paralyzed by rheumatism, over-exertion, and hysteria, or by serous effusions into the laryngeal muscles. If the tensors are paralyzed, **monotonia** is the chief result: the disturbances of respiration in paralysis of the larynx are important. As long as the respiration is tranquil, there may be no disturbance, but as soon as increased respiration occurs, great dyspnœa sets in, owing to the inability of the glottis to dilate.

If only **one vocal cord** is paralyzed, the voice becomes impure and falsetto-like, while we may feel from without that there is less vibration on the paralyzed side (*Gerhardt*), Sometimes the vocal cords are only so far paralyzed that they do not move during phonation, but do so during forced respiration and during coughing (**phonetic paralysis**).

Diphthongia.—Incomplete unilateral paralysis of the recurrent nerve is sometimes followed by a **double tone**, owing to the unequal tension of the two vocal cords. According to Türck and Schnitzler, however, the double tone occurs when the two vocal cords touch at some part of their course (*e.g.*, from the presence of a tumor, Fig. 367), so that the glottis is divided into two unequal portions, each of which produces its own sound.

Hoarseness is caused by mucus upon the vocal cords, by roughness, swelling, or laxness of the cords. If, while speaking, the cords are approximated, and suddenly touch each other, the "speech is broken," owing to the formation of nodal points (§ 352). Disease of the pharynx, naso-pharyngeal cavity, and uvula may produce a change in the voice *reflexly*.

Paralysis of the soft palate (as well as congenital perforation or cleft palate) causes a *nasal timbre* of all vowels; the former renders difficult the normal formation of consonants of the third articulation position; resonance is imperfect, while the explosives are weak, owing to the escape of the air through the nose.

Paralysis of the tongue weakens I; E and A (Æ) are less easily pronounced, while the formation of consonants of the second and third articulation position is affected. The term **aphthongia** is applied to a condition in which every attempt to speak is followed by spasmodic movements of the tongue (*Fleury*).

FIG. 367.

Tumors on the vocal cords causing double tone from the larynx.

In **paralysis of the lips** (*facial nerve*), and in hare-lip, regard must be had to the formation of consonants of the first articulation position. When the nose is closed, the speech has a characteristic sound. The normal formation of resonants is of course at an end. After excision of the larynx, a metal reed, enclosed in a tube, and acting like an artificial larynx, is introduced between the trachea and the cavity of the mouth (*Czerny*).

Stammering is a disturbance of the formation of sounds. [Stammering is due to long-continued spasmodic contraction of the diaphragm, just as hiccough is (§ 120), and, therefore, it is essentially a spasmodic inspiration. As speech depends upon the expiratory blast, the spasm prevents expiration. It may be brought about by mental excitement or emotional conditions. Hence, the treatment of stammering is to regulate the respirations. In **stuttering**, which is defective speech due to inability to form the proper sounds, the breathing is normal.]

320. COMPARATIVE—HISTORICAL.—Speech may be classified with the "**expression of the emotions**" (*Darwin*). Psychical excitement causes in man characteristic movements, in which certain groups of muscles are always concerned, *e.g.*, laughing, weeping, the facial expression in anger, pain, shame, etc. These movements afford a means whereby one creature can communicate with another. Primarily in their origin, the movements of expression are *reflex* motor phenomena; when they are produced for purposes of explanation, they are voluntary imitations of this reflex. Besides the emotional movements, impressions upon the sense organs produce characteristic reflex movements, which may be used for purposes of expression (*Geiger*), *e.g.*, stroking or painful stimulation of the skin, movements after smelling pleasant or unpleasant or disagreeable odors, the action of sound and light, and the perception of all kinds of objects.

The expression of the emotions occurs in its simplest form in what is known as expression by means of **signs** or pantomime or **mimicry**. Another means is the **imitation of sounds** by the organ of speech, constituting *onamatopoesy*, *e.g.*, the hissing of a stream, the roll of thunder, the tumult of a storm, whistling, etc. The expression of speech is, of course, dependent upon the process of ideation and perception.

The *occurrence of different sounds* in different languages is very interesting. Some languages (*e.g.*, of the Hurons) have no labials; in some South Sea Islands, no laryngeal sounds are spoken; *f* is absent in Sanscrit and Finnish; the short *e*, *o*, and the soft sibilants in Sanscrit; *d*, in Chinese and Mexican; *s*, in many Polynesian languages; *r*, in Chinese, etc.

Voice in Animals.—Animals, more especially the higher forms, can express their emotions by facial and other gestures. The vocal organs of **mammals** are essentially the same as those of man. Special *resonance organs* occur in the orang-outang, mandril, macacus, and mycetes monkeys, in the form of large cheek pouches, which can be inflated with air, and open between the larynx and the hyoid bone.

Birds have an upper (**larynx**) and a lower larynx (**syrinx**); the latter is placed at the bifurcation of the trachea, and is the true vocal organ. Two folds of mucous membrane (three in singing birds) project into each bronchus, and are rendered tense by muscles, and are thus adapted to serve for the production of voice.

Among **reptiles**, the tortoises produce merely a sniffing sound, which in the Emys has a peculiar piping character. The blind snakes are voiceless, the chameleon and the lizards have a very feeble voice; the cayman and crocodile emit a feeble roaring sound, which is lost in some adults owing to changes in the larynx. The *snakes* have no special vocal organs, but by forcing out air from their capacious lung, they make a peculiar hissing sound, which in some species is loud. Among **amphibians**, the frog has a larynx provided with muscles. The sound emitted without any muscular action is a deep intermittent tone, while more forcible expiration, with contraction of the laryngeal constrictors, causes a clearer continuous sound. The male, in Rana esculenta, has at each side of the angle of the mouth a sound bag, which can be inflated with air and acts as a resonance chamber. The "croaking" of the male frog is quite characteristic. In Pipa, the larynx is provided with two cartilaginous rods, which are thrown into vibration by the blast of air, and act like vibrating rods or the limbs of a tuning fork. Some **fishes** emit sounds, either by rubbing together the upper and lower pharyngeal bones, or by the expulsion of air from the swimming bladder, mouth, or anus.

Some **insects** cause sounds partly by forcing the expired air through their stigmata provided with muscular reeds, which are thus thrown into vibration (bees and many diptera). The wings, owing to the rapid contraction of their muscles, may also cause sounds (flies, cockroach, bees). The Sphinx atropos (death-head moth) forces air from its sucking stomach. In others, sounds are produced by rubbing their legs on the wing cases (Acridium), or the wing cases on each other (Gryllus, locust), or on the thorax (Cerambyx), on the leg (Geotrupes), on the abdomen or the margin of the wing (Nekrophorus). In Cicadaciæ, membranes are pulled upon by muscles, and are thus caused to vibrate. Friction sounds are produced between the cephalo-thorax and the abdomen in some spiders (Theridium), and in some crabs (Palinurus). Some mollusca (Pecten) emit a sound on separating their shells.

Historical.—The Hippocratic School was aware of the fact that division of trachea abolished the voice, and that the epiglottis prevented the entrance of food into the larynx. Aristotle made numerous observations on the voice of animals. The true cause of the voice escaped him as well as Galen. Galen observed complete loss of voice after double pneumothorax, after section of the intercostal muscles or their nerves, as well as after destruction of part of the spinal cord, even although the diaphragm still contracted. He gave the cartilages of the larynx the names that still distinguish them; he knew some of the laryngeal muscles, and asserted that voice was produced only when the glottis was narrowed. He compared the larynx to a flute. The weakening of the voice, in feeble conditions, especially after loss of blood, was known to the ancients. Dodart (1700) was the first to explain voice as due to the vibration of the vocal cords by the air passing between them.

The production of vocal sounds attracted much attention among the ancient Asiatics and Arabians —less among the Greeks. Pietro Ponce (†1584) was the first to advocate instruction in the art of speaking in cases of dumbness. Bacon (1638) studied the shape of the mouth for the pronunciation of the various sounds. Kratzenstein (1781) made an artificial apparatus for the production of vowel sounds, by placing resonators of various forms over vibrating reeds. Von Kempelen (1769 to 1791) constructed the first speaking machine. Rob. Willis (1828) found that an elastic vibrating spring gives the vowels in the series—U, O, A, E, I—according to the depth or height of its tone; further, that by lengthening or shortening an artificial resonator on an artificial vocal apparatus, the vowels may be obtained in the same series. The newest and most important investigations on speech are by Wheatstone, v. Helmholtz, Donders, Brücke, etc., and are mentioned in the context. Hensen succeeded in showing exactly the pitch of vocal tone, thus: The tone is sung against a König's capsule with a gas flame. Opposite the flame is placed a tuning fork vibrating horizontally, and in front of one of its limbs is a mirror, in which the image of the flame is reflected. When the vowel to the same number of vibrations as the tuning fork, the flame in the mirror sh double, *i.e.*, the octave, 2, and with the double octav-

GENERAL PHYSIOLOGY OF THE NERVES AND ELECTRO-PHYSIOLOGY.

321. STRUCTURE OF THE NERVE ELEMENTS.—The **nervous elements** present two distinct forms:—

I. Nerve Fibres. { Non-medullated. / Medullated. **II. Nerve Cells.** { Of various forms and functions.

An aggregation of nerve cells constitutes a **nerve ganglion.** The *fibres* represent a *conducting* apparatus, and serve to place the central nervous organs in connection with peripheral end organs. The *nerve cells*, however, besides transmitting impulses, act as *physiological centres* for automatic or reflex movements, and also for the sensory, perceptive, trophic, and secretory functions.

I. (1) The non-medullated nerve fibres occur in several forms:—

1. **Primitive Fibrils.**—The simplest form of nerve fibre, which is visible with a magnifying power of 500 to 800 diameters linear, consists of **primitive nerve fibrils.** They are very delicate fibres (Fig. 368, 1), often with small varicose swellings here and there in their course, which, however, are due to changes *post-mortem*. They are stained of a brown or purplish color by the gold chloride method, and they occur when a nerve fibre is near its termination, being formed by the splitting up of the axis cylinder of the nerve fibre, *e. g.*, in the terminations of the corneal nerves, the optic nerve layer in the retina, the terminations of the olfactory fibres, and in a plexiform arrangement in non-striped muscle (p. 510). Similar fine fibrils occur in the gray matter of the brain and spinal cord, and in the finely divided processes of nerve cells.

2. **Naked or simple axial cylinders** (Fig. 368, 2), which represent bundles of primitive fibrils held together by a slightly granular cement, so that they exhibit very delicate longitudinal striation with fine granules scattered in their course. The best example is the axial cylinder process of nerve cells (Fig. 368, I, 2). [The thickness of the axis cylinder depends upon the number of fibrils entering into its composition.]

3. **Axis cylinders surrounded with Schwann's sheath, or Remak's fibres** (3.8 to 6.8 μ broad), the latter name being given to them from their discoverer (Fig. 368, 3). [These fibres are also called *pale* or **non-medullated,** and from their abundance in the sympathetic nervous system, *sympathetic.*] They consist of a sheath, corresponding to Schwann's sheath [neurilemma, or primitive sheath, which encloses an axial cylinder; while lying here and there under the sheath, and between it and the axial cylinder are nerve corpuscles. These fibres are always fibrillated longitudinally]. The sheath is delicate, structureless, and elastic. Dilute acids clear the fibrils without causing them to swell up, while gold chloride makes them brownish-red. They are widely distributed in the sympathetic nerves, [*e. g.*, splenic], and in the branches of the olfactory nerves. All nerves in the *embryo*, as well as the nerves of many invertebrata, are of this kind. [According to Ranvier, these fibres do not possess a sheath, but the nuclei are merely applied to the surface, or slightly embedded in the superficial parts of the fibre, so that they belong to the fibre itself. These fibres also *branch* and form an anastomosing network (Fig. 370). This the medullated fibres never do. These fibres, when acted on by silver nitrate, never show any crosses. The branched forms occur in the ordinary nerves of distribution, and they are numerous in the vagus, but the olfactory nerves have a distinct sheath which is nucleated.]

(2) Medullated fibres occur also in several forms:—

4. **Axis cylinders,** or nerve fibrils, **covered only by a medullary sheath,** or white substance of Schwann, are met with in the white and gray matter of the central nervous system, in the optic and olfactory nerves. These *medullated nerve fibres, without any neurilemma,* often show after [illegible] rings in their course [due to the accumulation of fluid between the medulla of [illegible]order.] Hence they are called *varicose fibres.* [The varicose appearance [illegible]ng a small piece of the white matter of the spinal cord between a slide

and a cover glass. Nitrate of silver does not reveal any crosses, and there are no nodes of Ranvier. When acted upon by coagulating reagents, *e. g.*, chromic acid, the medullary sheath appears laminated, so that on transverse section, when the axis cylinder is stained, it is surrounded by concentric circles (Fig. 369).

5. **Medullated Nerve Fibres with Schwann's Sheath** (Fig. 368, 5, 6).—These are the most

FIG. 368.



1, Primitive fibrillæ; 2, axis cylinder; 3, Remak's fibres; 4, medullated varicose fibre; 5, 6, medullated fibre, with Schwann's sheath: *c*, neurilemma; *t*, *t*, Ranvier's nodes; *b*, white substance of Schwann; *d*, cells of the endoneurium; *a*, axis cylinder; *x*, myelin drops; 7, transverse section of nerve fibres; 8, nerve fibre acted on with silver nitrate and showing Fromann's lines. I, multipolar nerve cell from the spinal cord; *z*, axial cylinder process; *y*, protoplasmic processes—to the right of it a bipolar cell. II, peripheral ganglionic cell, with a connective-tissue capsule. III, ganglionic cell, with *o*, a spiral, and *n*, straight process; *m*, sheath.

complex nerve fibres, and are 10 to 22.6 μ [$\frac{1}{2000}$ to $\frac{1}{3500}$ inch] broad. They are most numerous in, and in fact they make up the great mass of, the cerebro-spinal nerves, although they are also present in the sympathetic nerves. [When examined in the fresh and living condition *in situ*, they appear refractive and homogeneous (*Ranvier*, *Stirling*); but if acted upon by reagents, they are not only refractive, but exhibit a *double* contour, the margins being dark and well defined.] Each fibre consists of—

[1. **Schwann's sheath,** (neurilemma,) or primitive sheath;
2. **White substance of Schwann,** medullary sheath, or myelin;
3. **Axis cylinder** composed of fibrils and surrounded by a sheath called the **axilemma**;
4. **Nerve corpuscles.**]

A. The axis cylinder, which occupies ¼ to ⅓ of the breadth of the fibre, is the essential part of the nerve, and lies in the centre of the fibre like the wick in the centre of a candle (Fig. 368, 6, *a*). Its usual shape is cylindrical, but sometimes it is flattened or placed eccentrically—[this is most probably due to the hardening process employed]. It is composed of *fibrils* [united by cement or stroma; they become more obvious near the terminations of the nerve, or after the action of reagents, which sometimes cause the fibrils to appear beaded. It is quite transparent, and stains deeply with carmine or logwood], while during life, its *consistence* is semi-fluid. According to Kupffer, a fluid—"**neuroplasma**"—lies between the fibrils [while, according to other observers, the whole cylinder is enclosed in an elastic sheath peculiar to itself and composed of neuro-keratin. This sheath is called by Kühne, the **axilemma**. Each axis cylinder is an enormously long process of a ganglionic cell].

Fromann's Lines.—Chloroform and collodion render it visible, while it is most easily isolated as a solid rod, by the action of nitric acid with excess of potassium chlorate. When acted on by silver nitrate, Fromann observed transverse markings on it, but their significance is unknown (Fig. 368, 8).

B. The white substance of Schwann, medullary sheath or **myelin,** surrounds the axis cylinder, like an insulating medium around an electric wire. In the perfectly fresh condition it is quite homogeneous, highly glistening, bright, and refractive; its consistence is fluid, so that it oozes out of the cut ends of the fibres in spherical drops (Fig. 368, *x*) [**myelin drops,** which are always marked by concentric lines, are highly refractive, and best seen when a fresh nerve is teased in salt solution]. After death, or after the action of reagents, it shrinks slightly from the sheath, so that the fibres have a **double contour,** while the substance itself breaks up into smaller or larger droplets, due not to coagulation (*Pertik*), but, according to Toldt, to a process like emulsification, the drops pressing against each other. Thus the fibre is broken up into masses, so that it has a characteristic appearance (Fig. 368, 6). It contains a large amount of *cerebrin* and *lecithin*, which swell up to form myelin-like forms in warm water. It also contains fatty matter, so that these fibres are blackened by osmic acid [while boiling ether extracts cholesterin from them]. Chloroform, ether, and benzin, by dissolving the fatty and some other constituents of the fibres, make them very transparent. [Some observers describe a fluid lying between the medulla and the axis cylinder.]

C. The Sheath of Schwann or the **neurilemma,** lies immediately outside of and invests the white sheath (Fig. 368, 6, *c*), and is a delicate structureless membrane, comparable to the sarcolemma of a muscular fibre.

D. Nerve Corpuscles.—At fairly wide intervals under the neurilemma, and lying in depressions between it and the medullary sheath, are the nucleated *nerve corpuscles*, which are readily stained by pigments (Fig. 371). [They may be compared to the muscle corpuscles, the nuclei being surrounded by a small amount of protoplasm which sometimes contains pigment. They are not so numerous as in muscle.] [Adamkiewicz describes nerve corpuscles, or "**demilunes**" under the neurilemma, quite distinct from the ordinary nerve corpuscles. They are stained yellow by safranin, while the ordinary nerve corpuscles are stained by methylanilin.]

Ranvier's Nodes or **Constrictions.**—The neurilemma forms in broad fibres at longer, and in narrower ones at shorter intervals, the *nodes* or *constrictions of Ranvier* (Fig. 368, 6, *t*, *t*; Fig. 371; Fig. 372, *fs*). They are constrictions which occur at regular intervals along a nerve fibre; at them the white substance of Schwann is interrupted, so that the sheath of Schwann lies upon the axis cylinder [or its elastic sheath] at the nodes. The part of the nerve lying between any two nodes is called an *inter-annular* or *inter-nodal segment*, and each such segment contains one or more nuclei, so that some observers look upon the whole segment as equivalent to one cell.

The function of the nodes seems to be to permit the diffusion of plasma through the outer sheath into the axis cylinder, while the decomposition products are similarly given off. [A coloring matter like picro-carmine diffuses into the fibre only at the nodes, and stains the axis cylinder red, although it does not diffuse through the white substance of Schwann.]

Incisures (of Schmidt and Lantermann).—Each inter-annular segment in a stretched nerve shows, running across the white substance, a number of oblique lines, which are called *incisures* (Figs. 372, 373). They indicate that the segment is built up of a series of conical sections, each of which is beveled at its ends, and the bevels are arranged in an imbricate manner, the one over the other, while the slight interval between them appears as an incisure. Each such section of the white matter is called **a cylinder cone** (*Kuhnt*).

Neuro-Keratin Sheath.—According to Ewald and Kühne, the axis cylinder, as well as the white substance of Schwann, is covered with an excessively delicate sheath, consisting of *neuro-keratin*, and the two sheaths are connected by numerous transverse and oblique fibrils, which permeate the white substance. [The myelin seems to lie in the interstices of this meshwork.]

[**Rod-like Structures in Myelin.**—If a nerve be hardened in *ammonium chromate* (or *picric acid*), M'Carthy has shown that the myelin exhibits rod-like structures, radiating from the axis

FIG. 369.

Transverse section of the nerve fibres of the spinal cord, the axis cylinders like dots surrounded by a clear space (myelin).

FIG. 370.

Remak's fibre from vagus of dog. *b*, fibrils; *n*, nucleus; *p*, protoplasm surrounding it.

FIG. 371.



Medullated nerve fibre of a rabbit acted on by osmic acid, × 400.

FIG. 372.

Medullated nerve fibres blackened by osmic acid. *fs*, Ranvier's node; *sch*, Schwann's sheath.

FIG. 373.



Medullated nerve fibres with o… acid. *a*, axis cylinder; … sheath of Schwann; *n*, nucl… *p*, *p*, granular substance a… poles of the nucleus; *r*, *r*, Ranvier's nodes where the medullary sheath is interru… and the axis cylinder app… *i*, *i*, incisures of Schmidt.

cylinder outward, which are stained with logwood and carmine. The rods are probably not distinct from each other, but are perhaps part of the neuro-keratin network already described.]

Action of Nitrate of Silver.—When a small nerve, *e.g.*, the intercostal nerve of a mouse, is acted on by silver nitrate, it is seen to be covered by an endothelial sheath composed of flattened endothelial cells (Fig. 374), while the nerve fibres themselves exhibit **crosses** along their course. These crosses are due to the penetration of the silver solution at the nodes, where it stains the cement substance and also part of the axis cylinder, so that the latter sometimes exhibits transverse markings called **Fromann's lines** (Fig. 368, 8).]

FIG. 374.

Intercostal nerve of a mouse (single fasciculus of nerve fibres) stained with silver nitrate. Endothelial sheath stained, and some nodes of Ranvier indicated by crosses.

[**New Methods.**—Much progress has recently been made in tracing the course of medullated nerve fibres by the action of new staining reagents; thus acid fuchsin stains the myelin deeply, leaving the other parts unstained, at least it can be so manipulated as to yield this result. **Weigert's Method** and its modifications have yielded most important results, and proved that medullated nerve fibres exist in many parts of the central nervous system where they cannot be seen in the ordinary way. The nerve tissue is hardened in a solution of a chromium salt, and placed in a half-saturated solution of cupric acetate; it is then stained with logwood, and afterward the elements are differentiated by steeping the sections in a solution of ferricyanide of potash and borax. The myelin is colored a logwood tint.]

In the spinal nerves, those fibres are thickest which have the longest course before they reach their end organ (*Schwalbe*), while those ganglion cells are largest which send out the longest nerve fibres (*Pierret*). [Gaskell finds that the longest nerves are not necessarily the thickest, for the visceral nerves in the vagus are small nerves, and yet run a very long course.]

Division of Nerves.—Nerve fibres run in the nerve trunks without dividing; but when they approach their termination they often divide dichotomously [at a node], giving rise to two similar fibres, but there may be several branches at a node (Fig. 376, *t*). [The divisions are numerous in motor nerves to striped muscles.] In the electrical nerves of the malapterurus and gymnotus, there is a great accumulation of Schwann's sheaths round a nerve, so that a nerve fibre is as thick as a sewing needle. Such a fibre, when it divides, breaks up into a bundle of smaller fibres.

FIG. 375.



Trans. section of a nerve (median). *ep*, epineurium; *pe*, perineurium; *ed*, endoneurium.

[**Nerve Sheaths.**—A nerve trunk consists of *bundles* of nerve fibres. The bundles are held together by a common connective-tissue sheath (Fig. 375, *ep*), the **epineurium** which contains the larger blood vessels, lymphatics, and sometimes fat and plasma cells. Each bundle is surrounded

with its own sheath or **perineurium** (*pe*), which consists of lamellated connective tissue disposed circularly, and between the lamellæ are lymph spaces lined by flattened endothelial plates. These lymph spaces may be injected from and communicate with the lymphatics (*Axel Key and Retzius*).] The nerve fibres within any bundle are held together by delicate connective tissue, which penetrates between the adjoining fibres, constituting the **endoneurium** (*ed*). It consists of delicate fibres with branched connective-tissue corpuscles (Fig. 368, 6, *d*), and in it lie the capillaries, which are not very numerous, and are arranged to form elongated open meshes.

[**Henle's Sheath.**—When a nerve is traced to its distribution, it branches and becomes smaller, until it may consist only of a few bundles or even a single bundle of nerve fibres. As the bundle branches, it has to give off part of its lamellated sheath or perineurium to each branch, so that, as we pass to the periphery, the smaller bundles are surrounded by few lamellæ. In a bundle containing only a few fibres, this sheath may be much reduced, or may consist only of thin, flattened, connective-tissue corpuscles with a few fibres. A sheath surrounding a few nerve fibres is called *Henle's Sheath* by Ranvier.]

[**Nervi Nervorum.**—Marshall and v. Horsley have shown that the nerve sheaths are provided with special nerve fibres, in virtue of which they are endowed with sensibility.]

Development.—At first nerve fibres consist only of fibrils, *i.e.*, of axis cylinders, which become covered with connective substance, and ultimately the white substance of Schwann is developed in some of them. The growth in length of the fibres takes place by elongation of the individual "inter-annular" segments, and also by the new formation of these (*Vignal*).

FIG. 376.

Cell from the Gasserian ganglion. *n*, nuclei of the sheath; *t*, fibre dividing at a node of Ranvier.

II. Ganglionic or Nerve Cells.—1. Multipolar nerve cells (Fig. 368, I) occur partly as *large* cells (100 μ), and are visible to the unaided eye as in the anterior horn of the spinal cord, and in a different form in the cerebellum, and partly in a *smaller* form (20 to 10 μ) in the posterior horns of the spinal cord, many parts of the cerebrum and cerebellum, and in the retina. They may be spherical, ovoid, pyramidal [cerebrum], pear- or flask-shaped [cerebellum], and are provided with **numerous branched processes** which give the cells a characteristic appearance. [Deiters isolated such cells from the anterior horn of the gray matter of the spinal cord, so that this special form of cell is sometimes called "Deiters' cell" (Fig. 368, I).] They are devoid of a cell envelope, are of soft consistence, and exhibit a fibrillated structure, which may extend even into the processes. Fine granules lie scattered throughout the cell substance between the fibrils. Not unfrequently yellow or brown granules of pigment are also found, either collected at certain parts in the cell or scattered throughout it. The relatively large *nucleus* consists of a clear envelope enclosing a resistant substance. It does not appear to have a membrane in youth (*Schwalbe*). Within the nucleus lies the *nucleolus*, which in the recent condition is angular, provided with processes and capable of motion, but after death is highly refractive and spherical. There is always **one unbranched process**, constituting the **axial cylinder process** (I, *z*) which remains unbranched, but it soon becomes covered with the substance of Schwann, and the other sheaths of a medullated nerve, so that it becomes the axial cylinder of a nerve fibre. [Thus a nerve fibre is merely an excessively long, unbranched process of a nerve cell pushed outward toward the periphery.] It is not definitely ascertained that the cerebral cells have such processes. All the other processes divide very frequently until they form a branched, root-like, complex arrangement of the finest primitive fibrils. These are called **protoplasmic processes** (I, *y*). By means of these processes, adjoining cells are brought into communication with each other, so that impulses can be conducted from one cell to another. Further, many of these fibrils approximate to each other and join together to form axis cylinders of other nerve fibres. [v. Thanhoffer states that he has traced the axis-cylinder process to the nucleus and nucleolus.]

2. **Bipolar cells** are best developed in fishes, *e.g.*, in the spinal ganglia of the skate, and in the Gasserian ganglion of the pike. They appear to be nucleated, fusiform enlargements of the axis cylinder (Fig. 368, on the right of I). The white substance often stops short on each side of the enlargement, but sometimes the white substance and the sheath of Schwann pass over the enlargement

3. **Nerve cells with connective-tissue capsules** occur in the peripheral ganglia of man (Fig. 368, II), *e.g.*, in the spinal ganglia. The soft body of the cell, which is provided with several processes, is covered by a thick, tough capsule composed of several layers of connective-tissue cor-

puscles; while the inner surface of the composite capsule is lined by a layer of delicate endothelial cells (Fig. 376). The body of the cells in the spinal ganglia is traversed by a network of fine fibrils (*Flemming*). The capsule is continuous with the sheath of the nerve fibre.

Rawitz and G. Retzius find that the cells of the spinal ganglia are *unipolar*, the outgoing fibre taking a half-turn within the capsule before it leaves the cell (Fig. 376). Retzius [and Ranvier] observed the process to divide like a **T**. Perhaps this division corresponds to the two processes of a bipolar cell. The jugular ganglion and plexus gangliiformis vagi in man contain only unipolar cells, so that, in this respect, they may be compared to spinal ganglia. The same is the case in the Gasserian ganglion; while the ciliary, spheno-palatine, otic, and submaxillary ganglia structurally resemble the ganglia of the sympathetic.

4. **Ganglionic cells with spiral fibres** occur chiefly in the abdominal sympathetic of the frog (*Beale, J. Arnold*). The body of the cell is usually pyriform in shape, and from it proceeds a **straight** unbranched process (Fig. 368, III, *n*), which ultimately becomes the axis cylinder of a nerve. A **spiral** fibre springs from the cell (? a network), emerges from it, and curves in a spiral direction round the former (*o*). The whole cell is surrounded by a nucleated capsule (*m*). We know nothing of the significance of the different fibres.

322. CHEMICAL AND MECHANICAL PROPERTIES OF NERVOUS SUBSTANCE.—1. **Proteids.**—Albumin occurs chiefly in the axis cylinder and in the substance of the ganglionic cells. Some of this proteid substance presents characters not unlike those of myosin (§ 293). Dilute solution of common salt extracts a proteid from nervous matter, which is precipitated by the addition of much water and also by a concentrated solution of common salt (*Petrowsky*). *Potash albumin* and a *globulin-like substance* are also present. **Nuclein** occurs especially in the gray matter (§ 250, 2), while **neuro-keratin**, a body containing much sulphur and closely related to keratin, occurs in the corneous sheath of nerve fibres (p. 577). If gray nervous matter be subjected to artificial digestion with trypsin, both of these substances remain undigested (*Kühne and Ewald*). Pure neuro-keratin is obtained by treating the residue with caustic potash. The *sheath of Schwann* does not yield gelatin, but a substance closely related to *elastin* (§ 250, 6), from which it differs, however, in being more soluble in alkalies. The connective tissue of nerves yields gelatin.

2. **Fats** *and other allied substances soluble in ether*, more especially in the white matter: (*a*) **Cerebrin**, free from phosphorus (§ 250, 3).

Cerebrin is a white powder composed of spherical granules soluble in hot alcohol and ether, but insoluble in cold water. It is decomposed at 80° C., and its solutions are neutral. When boiled for a long time with acids, it splits up into a left-rotatory body like sugar and another unknown product. **Preparation.**—Rub up the brain into a thin fluid with baryta water. Extract the separated coagulum with boiling alcohol. The extract is frequently treated with cold ether to remove the cholesterin (*W. Müller*). Parkus separated from cerebrin its homologue, **homocerebrin**, which is slightly more soluble in alcohol, and the clyster-like body, **encephalin**, which is soluble in hot water.

(*b*) **Lecithin** and its decomposition products—glycero-phosphoric acid and oleo-phosphoric acid (§ 251).

Neurin (or Cholin $= C_5H_{15}NO_2$) is a strongly alkaline, colorless fluid, forming crystalline salts with acids. It is soluble in water and alcohol, and has been formed synthetically from glycol and trimethylamin. Lecithin is a salt of the base neurin.

(*c*) **Protagon**, which contains N and P, is similar to cerebrin, and is, according to its discoverer, the chief constituent of the brain (*Liebreich*).

According to Hoppe-Seyler and Diaconow, it is a mixture of lecithin and cerebrin. [The investigations of Gamgee and Blankenhorn have shown, however, that protagon is a definite chemical body. They find that, instead of being unstable, it is a very stable body.] It is a glucoside, and crystalline, and can be extracted from the brain by warm alcohol, and when boiled with baryta yields the decomposition products of lecithin.

3. The following substances are extracted by water: Xanthin and hypoxanthin (*Scherer*), kreatin (*Lerch*), inosit (*W. Müller*), ordinary lactic acid (*Gscheidlen*), acetic and formic acids, uric acid (?), and volatile fatty acids; leucin (in disease), urea (in uræmia), and a substance like starch in the human brain (*Jaffé*). All these substances are for the most part products of the regressive metabolism of the tissues.

Reaction.—Nervous substance, when passive, is neutral or feebly alkaline in reaction, while active (? and dead) it is acid (*Funke*). The gray matter of the brain, when quite fresh, is alkaline (*Liebreich*), but death rapidly causes it to become acid (*Gscheidlen*).

The reaction of nerve fibres varies during life. After introducing **methyl-blue** into the body of a living animal, Ehrlich found that the axis cylinder became blue, *i. e.*, in those nerves which have an alkaline reaction (cortex cerebri, cardiac, sensory, motor (non-striped), gustatory and olfactory fibres), while the termination of motor (voluntary) nerves remained uncolored. The latter he regards as acid.

The nerves after death have a more solid consistence, so that in all probability some coagulation or change, comparable to the stiffening of muscle, occurs in them after death, while at the same time a free acid is liberated (§ 295). If a fresh brain be rapidly "broiled" at 100° C., it, like a muscle similarly treated, remains alkaline (§ 295).

Chemical Composition.	Gray Matter.	White Matter.
Water,	81.6 per cent.	68.4 per cent.
Solids,	18.4 "	31.6 "
The solids consist of—		
Albumins and glutin,	55.4 "	24.7 "
Lecithin,	17.2 "	9.9 "
Cholesterin and fats,	18.7 "	52.1 "
Cerebrin,	0.5 "	9.5 "
Substances insoluble in ether,	6.7 "	3.3 "
Salts,	1.5 "	0.5 "
	100.0	100.0

In 100 parts of **ash**, Breed found **potash** 32, soda 11, magnesia 2, lime 0.7, NaCl 5, iron phosphate 1.2, fixed **phosphoric acid** 39, sulphuric acid 0.1, silicic acid 0.4.

[Ptomaines (§ 166) are obtained from putrefying brain. They have an effect on the motor nerves like curara, but in much less degree, while the phenomena last for a much shorter time (*Guareschi and Mosso*).]

Mechanical Properties.—One of the most remarkable mechanical properties of nerve fibres is the absence of elastic tension according to the varying positions of the body. Divided nerves do not retract; such nerves exhibit delicate, microscopic, transverse folds [like watered silk], or Fontana's transverse markings.

The **cohesion** of a nerve is very considerable. When a limb is forcibly torn from the body, as sometimes happens from its becoming entangled in machinery, the nerve not unfrequently remains unsevered, while the other soft parts are ruptured. [Tillaux found that a weight of 110 to 120 lbs. was required to rupture the sciatic nerve at the popliteal space, while to break the median or ulnar nerve of a fresh body, a force equal to 40 to 50 lbs. was required. The toughness and elasticity of nerves are often well shown in cases of injury or gunshot wounds. The median or ulnar nerve will gain 15 to 20 centimetres (6 to 8 inches) before breaking. Weir Mitchell has shown that a healthy nerve will bear a very considerable amount of pressure and handling, and, in fact, the method of nerve stretching depends upon this property of a nerve trunk.]

323. METABOLISM OF NERVES.—Influence of Blood Supply.—We know very little regarding the metabolic processes that occur in nerve tissue. Some **extractives** are obtained from nerve tissue, and they may, perhaps, be regarded as decomposition products (p. 581). It has not been proved satisfactorily that during the activity of nerves there is an exchange of O and CO_2. That there is an exchange of materials within the nerves is proved by the fact that, after **compression of the blood vessels** of the nerves, the excitability of the

nerves falls, and is restored again when the circulation is reëstablished. Compression of the abdominal aorta causes paralysis and numbness of the lower half of the body, while occlusion of the cerebral vessels causes almost instantaneously cessation of the cerebral functions. The metabolism of the central nervous organs is much more active than that of the nerves themselves. [If the abdominal aorta of a rabbit be compressed for a few minutes, the hind limbs are quickly paralyzed, the animal crawls forward on its forelegs, drawing the hind limbs in an extended position after it.] The ganglia form much lymph.

324. EXCITABILITY OF THE NERVES—STIMULI.—Nerves possess the property of being thrown into a state of excitement by **stimuli**, and are, therefore, said to be **excitable** or irritable. The stimuli may be applied to, and may act upon, any part of the nerve. [The following are the various kinds of stimuli, *i. e.*, modes of motion, which act upon nerves]:—

1. **Mechanical stimuli** act upon nerves when they are applied with sufficient rapidity to produce a change in the form of the nerve particles, *e. g.*, a blow, pressure, pinching, tension, puncture, and section. In the case of **sensory** nerves, when they are stimulated, pain is produced, as is felt when a limb "sleeps," or when pressure is exerted upon the ulnar nerve at the bend of the elbow. When a **motor** nerve is stimulated, motion results in the muscle attached to the nerve. If the continuity of the nerve fibres be destroyed, or, what is the same thing, if the continuity of the axial cylinder be interrupted by the mechanical stimulus, the *conduction* of the impulse across the injured part is interrupted. If the molecular arrangements of the nerves be permanently deranged, *e. g.*, by a violent shock, the excitability of the nerves may be thereby extinguished.

A slight blow applied to the radial nerve in the forearm, or to the axillary nerves in the supraclavicular groove, is followed by a contraction of the muscles supplied by these nerves. Under pathological conditions, the excitability of a nerve for mechanical stimuli may be increased enormously.

Tigerstedt ascertained that the *minimal* mechanical stimulus is represented by 900 milligramme-millimetres, and the *maximum* by 7000 to 8000. Strong stimuli cause fatigue, but the fatigue does not extend beyond the part stimulated. A nerve when stimulated mechanically does not become acid. Slight pressure without tension increases the excitability, which diminishes after a short time. The mechanical work produced by an excited muscle in consequence of a stimulus was 100 times greater than the mechanical energy of the mechanical nerve stimulus.

Continued pressure upon a *mixed* nerve paralyzes the motor sooner than the sensory fibres. If the stimulus be applied *very gradually*, the nerve may be rendered inexcitable without manifesting any signs of its being stimulated (*Fontana*, 1758). Paralysis, due to continuous pressure gradually applied, may occur in the region supplied by the brachial nerves; the left recurrent laryngeal nerve also may be similarly paralyzed from the pressure of an aneurism of the arch of the aorta.

By increasing the **pressure** on a nerve by using a gradually increasing weight, there is at first an increase and then a decrease of the excitability. Pressure on a mixed nerve abolishes reflex conduction sooner than motor conduction (*Kronecker and Zederbaum*).

Nerve stretching is employed for therapeutical purposes. If a nerve be exposed and stretched, or if it be made sufficiently tense, the nerve is stimulated. Slight tension increases the reflex excitability (*Schleich*), while violent extension produces a temporary diminution or abolition of the excitability (*Valentin*). The centripetal or sensory fibres of the sciatic nerve are sooner paralyzed thereby than the centrifugal or motor (*Conrad*). During the process of extension, mechanical changes are produced, either in the nerve itself or in its end organs, causing an alteration of the excitability, but it may also affect the central organs. The paralysis, which sometimes occurs after forcible stretching, usually rapidly disappears. Therefore, when a nerve is in an excessively excitable condition, or when this is due to an inflammatory fixation or constriction of the nerve at some part of its course, nerve stretching may be useful, partly by diminishing the excitability, partly by breaking up the inflammatory adhesions. In cases where stimulation of an afferent nerve gives rise to *epileptic or tetanic spasms*, nerve stretching may be useful by diminishing the excitability at the periphery, in addition to the other effects already described. It has also been employed in some spinal affections, which may not as yet have resulted in marked degenerative changes.

For physiological purposes, a nerve may be stimulated mechanically by means of Heidenhain's tetanomotor, which is simply an ivory hammer attached to the prolonged spring of a Neef's hammer of an induction machine. [A more delicate form of this instrument was used by Tigerstedt (§ 335).] The rapid vibration of the hammer communicates a series of mechanical shocks to the nerve upon which it is caused to beat. Rhythmic extension of a nerve causes contractions and even tetanus.

2. **Thermal Stimuli.**—If a frog's nerve be heated to 45° C., its *excitability* is first increased and then diminished. The higher the temperature, the greater is the excitability, and the shorter its duration (*Afanasieff*). If a nerve be heated to 50° C. for a short time, its excitability and conductivity are abolished. The frog's nerve alone regains its excitability on being cooled (*Pickford*). If the temperature be raised to 65° C., the excitability is abolished without the occurrence of a contraction, while its medulla is broken up (*Eckhard*). Sudden cooling of a nerve to 5° C. acts as a stimulus, causing contraction in a muscle, while sudden heating to 40° or 45° C. produces the same result. If the temperature be increased still more, instead of a single contraction a tetanic condition is produced. All such rapid variations of temperature quickly exhaust the nerve and kill it. If a nerve be frozen gradually, it retains its excitability on being thawed. The excitability lasts long in a *cooled* nerve; in fact, it is increased in a motor nerve, but the contractions are not so high and more prolonged, while the conduction in the nerve takes place more slowly. Among *mammalian* nerves, the afferent and vaso-dilator nerves at 45° to 50° C. exhibit the results of stimulation, while the others only show a change in their excitability. When cooled to + 5° C., the excitability of all the fibres is diminished (*Grützner*).

3. **Chemical Stimuli** excite nerves when they act with a certain rapidity, and thereby alter the condition of the nerve (p. 522). Most chemical stimuli act by first increasing the nervous excitability, and then diminishing or paralyzing it. Chemical stimuli, as a rule, have less effect upon the *sensory* than upon motor fibres (*Eckhard*). According to Grützner, the inactivity of chemical stimuli, so often observed when they are applied to sensory nerves, depends in great part upon the non-simultaneous stimulation of all the nerve fibres. Among chemical stimuli are (*a*) *rapid abstraction of water* by dry air, blotting paper, exposure in a chamber containing sulphuric acid, or by the action of solutions which absorb fluids, *e. g.*, concentrated solutions of neutral alkaline salts (NaCl, excites only motor fibres in mammals—*Grützner*), sugar, urea, concentrated glycerin (and ? some metallic salts). The subsequent addition of water may abolish the contractions, while the nerve may still remain excitable. The abstraction of water first increases and afterward diminishes the excitability. The *imbibition of water* diminishes the excitability. (*b*) Free alkalies, mineral acids (not phosphoric), many organic acids (acetic, oxalic, tartaric, lactic), and most salts of the heavy metals. While the acids act as stimuli, only when they are somewhat concentrated, the caustic alkalies act in solutions of 0.8 to 0.1 per cent. (*Kühne*). Neutral potash salts, in a concentrated form, rapidly kill a nerve, but they do not excite it nearly so strongly as the soda compounds. Dilute solutions of the neutral potash salts first increase and afterward diminish it (*Ranke*), as can be shown by stimulation with an induction shock (*Biedermann*). (*c*) Various substances, *e. g.*, dilute alcohol, ether, chloroform, bile, bile salts, and sugar. These substances usually excite contractions, and afterward rapidly kill the nerve. Ammonia, lime water, some metallic salts, carbon bisulphide, and ethereal oils kill the nerve without exciting it—at least without producing any contraction in a frog's nerve-muscle preparation. [The nerve of a nerve-muscle preparation may be dipped into ammonia, but no contraction results, while the slightest traces of ammonia applied to a muscle cause contraction.] Carbolic acid does the same, although when applied directly to the spinal cord it produces spasms. These substances excite the muscles when they are directly applied to them. Tannic acid does not act as a stimulus either to nerve or muscle. As a

general rule, the stimulating solutions must be more *concentrated* when applied to a nerve than to muscle, in order that a contraction may be produced.

[**Methods.**—If a nerve-muscle preparation of a frog's limb be made, and a straw flag (p. 520) attached to the toes while the femur is fixed in a clamp, and its nerve be then dipped in a saturated solution of common salt, the toes soon begin to twitch, and by and by the whole limb becomes tetanic, and thus keeps the straw flag extended. The effect of fluid on a muscle or nerve is easily tested by fixing the muscle in a clamp, while a drop of the fluid is placed on a greased surface, which gives it a convex form. The end of the muscle or nerve is then brought into contact with the cupola of the drop (*Kühne*).]

4. **The Physiological** or **normal** stimulus excites the nerves in the normal intact body. Its nature is entirely unknown. The "nerve motion" thereby set up travels either in a "**centrifugal**" or outgoing direction from the central nervous system, giving rise to motion, inhibition of motion, or secretion; or in a "**centripetal**" or ingoing direction from the specific *end organs* of the nerves of the special senses or the sensory nerves. In the latter case, the impulse reaches the central organs, where it may excite sensation or perception, or it may be transferred to the motor areas and be conducted in a centrifugal direction, constituting a "**reflex**" stimulation (§ 360). A single physiological nerve impulse travels more slowly than that excited by the momentary application of an induction shock (*Lovèn, v. Kries*). It is not a uniform process excited by varying intensity and greater or less frequency of stimulation, but it is essentially a process varying considerably in duration, and it may even last as long as ⅓ second (*v. Kries*).

5. **Electrical Stimuli.**—[The following forms of electrical stimuli may be used:—

(1) A **constant current**, which may be made or broken (§ 328).
(2) **Induction shocks**, either make or break shocks (§ 329).
(3) An **interrupted current** (§ 329).]

The electrical current acts most powerfully upon the nerves at the moment when it is *applied*, and at the moment when it *ceases* (§ 336); in a similar way, any increase or decrease in the strength of a constant current acts as a stimulus. If an electrical current be applied to a nerve, and its strength be very gradually increased or diminished, then the visible signs of stimulation of the nerve are very slight. As a general rule, the stimulation is more energetic the more rapid the variations of the strength of the current applied to the nerve, *i. e.*, the more suddenly the **intensity** of the stimulating current is increased or diminished (*du Bois-Reymond*).

An electrical current must have a certain **strength** or **liminal intensity** before it is effective. By uniformly increasing the strength of the current, the size of the contraction increases rapidly at first, then more slowly (*Tigerstedt and Willhard*).

An electrical current, in order to stimulate a nerve, must have a certain **duration**, it must act at least during 0.0015 second (*Fick*, 1863); even with currents of slightly longer duration, the opening shock may have no effect. If the duration of the closing shock of a constant current be so arranged that it is just too short to be active, then it merely requires to last 1.3 to 2 times longer to produce the most complete effect (*Grünhagen*).

The electrical current is most active when it flows in the **long axis** of the nerve; it is inactive when applied vertically to the axis of the nerve (*Galvani*). Similarly, muscles are incomparably less excited by transverse than by longitudinal currents (*Giuffrè*).

The *greater* the **length** of nerve traversed by the current, the *less* the stimulus that is required (*Pfaff*).

Constant Current.—If the constant current be used as a nervous stimulus, the stimulating effect on the **sensory nerves** is most marked at the moment of making and breaking the current; during the time the current passes, only slight excitement is perceived, but, even under these circumstances, very strong currents may cause very considerable, and even unbearable, sensations. If a constant current be

applied to a **motor nerve**, the greatest effect is produced when the current is made or closed [**closing** or **make contraction**], and when it is broken or opened [**opening** or **break contraction**]. But while the current is passing, the stimulation does not cease completely, for, with a certain strength of stimulus, the muscle remains in a state of tetanus (**galvanotonus** or "**closing tetanus**") (*Pflüger*). For the same effect on muscles, see p. 532. With strong currents this tetanus does not appear, chiefly because the current diminishes the excitability of the nerves, and thus develops resistance, which prevents the stimulus from reaching the muscle. According to Hermann, a descending current applied to the nerve, at a distance from the muscles, causes this tetanus more readily, while an ascending current causes it more readily when the current is closed near the muscle. The constant current is said by Grützner to have no effect on *vasomotor* and *secretory* fibres.

Over-maximal Contraction.—By gradually increasing the strength of the electrical stimulus applied to a motor nerve, Fick observed that the muscular contractions (height of the lift) at first increased proportionally to the increase of the stimulus, until a maximal contraction was obtained. If the strength of the stimulus be increased still further, another increase of the contraction above the first-reached maximum is obtained. This is called an "**over-maximal contraction.**" Occasionally between the first maximum and the second there is a diminution, or indeed absence of, or **gap** or **hiatus**, in the contractions. The cause of this lies in the positive pole, which with a certain strength of current is sufficient to prevent the further transmission of the excitement (§ 335). On continuing to increase the induction current, ultimately a stage is reached where the stimulation at the negative pole again becomes stronger than the inhibition at the positive, and this overcomes the latter. The contractions before the gap are caused by the occurrence of the induction current (their latent period is short); the contractions (long latent period, like that after all opening shocks—*Waller*), after the gap, are caused by the disappearance of the induction current, *i. e.*, by polarization; this is added to the stimulation proceeding from the negative pole, which after the gap overcomes the inhibition at the positive pole, and excites the over-maximal contractions (*Tigerstedt and Willhard*).

Tetanus.—If single shocks of short duration be rapidly applied after each other to a nerve, tetanus in the corresponding muscle is produced (§ 298, III).

A motor nerve has a greater *specific* excitability for electrical stimuli than the muscle substance. This is proved by the fact that, a feebler stimulus suffices to excite a muscle when applied to the nerve than when it is applied to the muscle directly, as occurs when the terminations of the motor nerves are paralyzed by curara (*Rosenthal*).

Soltmann found that the excitability of the motor nerves of **new-born** animals for electrical stimuli is less than in adults. The excitability increases until the 5th to 10th month.

Unequal Excitability.—Under certain circumstances, the nearer the part of the motor nerve stimulated lies to the central nervous system, the greater is the effect produced (contraction); [or what is the same thing, the further the point of a nerve which is stimulated is from the muscle, the stimulus being the same, the greater is the contraction. This led Pflüger to his "avalanche theory," *i. e.*, that the "nerve motion" increases in the nerve as it passes toward the muscles. This effect is explained, however, by the unequal excitability of different parts of the same nerve]. According to Fleischl, all parts of the nerve are equally excitable for *chemical* stimuli. Further, it is said that the higher placed parts of a nerve are more excitable only when the stimulating current passes in a descending direction; the reverse is the case when the current ascends (*Hermann*). On stimulating a *sensory* nerve, Rutherford and Hällsten found that the reflex contraction was greater the nearer the stimulated point was to the central nervous system.

Unequal Excitability in the same Nerve.—Nerve fibres, even when functionally the same and included in the same nerve trunk, are not all equally excitable. Thus, feeble stimulation of the sciatic nerve of a frog causes contraction of the flexor muscles, while it requires a stronger stimulus to produce contraction of the extensors (*Ritter*, 1805, *Rollett*). According to Ritter, the nerves for the flexors die first.

Direct stimulation of the muscles in curarized animals shows that the flexors contract with a feebler stimulus (but also fatigue sooner) than the extensors; the pale [illegible] rabbit are

also more excitable than the red. As a rule, **poisons** affect the flexors sooner than the extensors. In some muscles some pale fibres are present, and they are more excitable than the red (*Grützner*) (§ 298). If a frog's nerve-muscle preparation be exposed to the action of ether, on strong stimulation of the sciatic nerve, flexion occurs (*Grützner, Bowditch*), but if the current be made stronger, extension takes place. During deep ether-narcosis, strong stimulation of the recurrent nerve causes dilatation, and with slight narcosis, narrowing of the glottis takes place; dilatation occurs on slight stimulation (*Bowditch*). The adductor muscle of the claw of a crayfish is relaxed under a weak stimulus, but it contracts when a strong stimulus is applied to it. The reverse is the case with the muscle which opens the claw (*Biedermann*).

Unipolar Stimulation.—If *one* electrode of an induction apparatus be applied to a nerve, it may act as a stimulus. Du Bois-Reymond has called this "unipolar induction action." It is due to the movement of the electrical current to and from the free ends of the open induction current at the moment of induction. [Unipolar induction is more apt to occur with the opening than the closing shock, because the former is more intense.]

Upon **muscle**, electrical stimuli act quite as they do upon nerves. Electrical currents of *very short* duration have no effect upon muscles whose nerves are paralyzed by curara (*Brücke*), and the same is true of greatly fatigued muscles, or muscles about to die or greatly weakened by diseased conditions (§ 399).

325. DIMINUTION OF THE EXCITABILITY—DEGENERATION AND REGENERATION OF NERVES.—1. Normal Nutrition.—The continuance of the normal excitability in the nerves of the body depends upon the maintenance of the normal nutrition of the nerves themselves and a due supply of blood. Insufficient nutrition causes, in the first instance, increased excitability, and if the condition be continued the excitability is diminished (§ 339, I).

When the physician meets with the *signs of increased excitability of the nerves*, under bad or abnormal conditions of nutrition, this is to be regarded as the beginning of the stage of decrease of the nerve energy. Invigorating measures are required.

If the *terminal nervous apparatus* be subjected to a temporary disturbance of its nutrition, the return of the normal nutritive process is heralded by a more or less marked stage of excitement. The more excitable the nervous apparatus, the shorter must be the duration of the disturbance of nutrition, *e.g.*, cutting off the arterial blood supply or interfering with the respiration.

2. **Fatigue.**—Continued **excessive stimulation** of a nerve, without sufficient intervals of repose, causes **fatigue** of the nerve, and by exhaustion rapidly diminishes the excitability. A nerve is more slowly fatigued than a muscle (*Bernstein*), but it recovers more slowly (§ 304). [Nerves of cold-blooded animals (*Widenskii*) and mammals (*Bowditch*) may be tetanized for hours without becoming fatigued.]

[To show that a **muscle is much more rapidly** fatigued than a **nerve**, Bernstein arranged two nerve-muscle preparations so that both nerves were tetanized simultaneously, but through one of the nerves, a polarizing constant current was passed by means of non-polarizable electrodes (§ 327), so that the condition of anelectrotonus (§ 335) was set up in this nerve, and thus "blocked" the propagation of impulses to the corresponding muscle. Only one muscle, therefore, was tetanized. Both nerves were continuously stimulated until fatigue of the contracting muscle took place, and on breaking the polarizing current applied to the other nerve, the corresponding muscle at once became tetanic. Now, as both nerves were equally stimulated, and the muscle in connection with one nerve was fatigued, while the other muscle at once contracted, it is evident that a muscle is much more rapidly fatigued than a motor nerve. In **sensory** nerves, fatigue and recovery are analogous to the corresponding processes in motor nerves (*Bernstein*).]

Recovery.—When a nerve recovers, at first it does so slowly, then more rapidly, and afterward again more slowly. If recovery does not occur within half an hour after a frog's nerve has been subjected to very long and intense stimulation, it will not take place at all.

3. **Continued inaction** of a nerve diminishes, and may ultimately abolish the excitability.

Thus, the **central ends** of divided sensory nerves, after **amputation** of a limb, lose their excitability, although the nerves are still connected with the central nervous system, because the end organs through which they were normally excited have been removed.

FIG. 377.



Degeneration and regeneration of nerves. A, subdivision of the myelin; B, further disintegration thereof (osmic acid staining); C, interruption of the axial cylinder, which is surrounded with the broken-up myelin; D, accumulation of nuclei, with the remainder of the myelin in a spindle-shaped fibre; E, a new nerve fibre, with a new sheath of Schwann, *sn*, within the old sheath of Schwann, *sa*; F, a new nerve fibre passing in a curved course through an old nerve fibre sheath.

FIG. 378.

Diagram of the roots of a spinal nerve, showing the effect of section (the black parts represent the degenerated parts). A, section of the nerve trunk beyond the ganglion; B, of the anterior root, and C, of the posterior; D, excision of the ganglion; *a*, anterior, *β*, posterior root; *g*, ganglion.

4. **Separation from their Nerve Centres.**—The nerve fibres remain in a condition of normal nutrition, only when they are directly connected with their **centre**, which governs the **nutritive processes** within the nerve. If a nerve within the body be separated from its "**nutritive centre**"—either by section

of the nerve or compressing it—within a short time it loses its excitability, and the *peripheral* end undergoes fatty degeneration, which begins in four to six days in warm-blooded animals, and after a long time in cold-blooded ones (*Joh. Müller*). See also the changes of the excitability during this condition, the so-called "**Reaction of degeneration**" (§ 339). If the *sensory* nerve fibres of the root of a spinal nerve be divided on the central side of the ganglion, the fibres on the peripheral side do not degenerate, for the ganglion is the trophic or nutritive centre for the sensory nerves; but the fibres still in connection with the cord degenerate (*Waller*).

[**Wallerian Law of Degeneration.**—If a spinal nerve be divided, the peripheral part of the nerve and its branches, including the sensory and motor fibres, degenerate completely (Fig. 378, A), while the central parts of the nerve remain unaltered. If the *anterior root* of a spinal nerve alone be divided before it joins the posterior root, all the peripheral nerve fibres connected with the anterior root degenerate (Fig. 378, B), so that in the nerve of distribution only the motor fibres degenerate. The portion of the nerve root which remains attached to the cord does not degenerate. If the *posterior root* alone be divided, between the spinal cord and the ganglion, the effect is reversed, the part of the nerve root lying between the section and the spinal cord degenerates, while the part of the nerve connected with the ganglion does not degenerate (Fig. 378, C). The central fibres degenerate because they are separated from the ganglion. If the ganglion be excised, or if separated, as in Fig. 378, D, both the central and peripheral parts of the posterior root degenerate. These experiments of Waller show that the fibres of the anterior and posterior roots are governed by different centres of nutrition or "**trophic centres.**" As the anterior root degenerates when it is separated from the cord, and the posterior when it is separated from its own ganglion, it is assumed that the trophic centre for the fibres of the anterior root lies in the multipolar nerve cells of the anterior horn of the gray matter of the spinal cord, while that for the fibres of the posterior root lies in the cells of the ganglion placed on it. The nature of this supposed trophic influence is entirely unknown.]

Traumatic and Fatty Degeneration.—Both ends of the nerve at this point of section immediately begin to undergo "**traumatic degeneration.**" (In the frog on the 1st and 2d day.) After a time neither the myelin nor axis cylinder is distinguishable (*Schiff*). According to Engelmann, this condition extends only to the nearest node of Ranvier, and afterward the so-called "**fatty degeneration**" begins. The process of "*fatty*" degeneration begins simultaneously in the whole peripheral portion; the white substance of Schwann breaks up into masses (Fig. 377, A), just as it does after death, in microscopic preparations; afterward, the myelin forms globules and round masses (B), the axial cylinder is compressed or constricted, and is ultimately broken across (C) in many places (7th day). The nerve fibre seems to break up into two substances—one fatty, the other proteid in constitution, the fat being absorbed (*S. Mayer*). The nuclei of Schwann's sheath swell up and proliferate (D—until the 10th day). According to Ranvier, the nuclei of the inter-annular segments and their surrounding protoplasm proliferate, and ultimately interrupt the continuity of the axis cylinder and the myelin. They then undergo considerable development with simultaneous disappearance of the medulla and axis cylinder, or at least fatty substances formed by their degeneration, so that the nerve fibres look like fibres of connective tissue. [According to this view, the process is in part an *active* one, due to the growth of the nerve corpuscles breaking up the contents of the neurilemma, which then ultimately undergo chemical degenerative changes.] According to Ranvier, Tizzoni, and others, leucocytes wander into the cut ends of the nerves, and also at Ranvier's nodes, insinuating themselves into the nerve fibres, where they take myelin into their bodies, and subject it to certain changes. [These cells are best revealed by the action of osmic acid, which blackens any myelin particles in their interior.] Degeneration also takes place in the motorial end plates, beginning first in the non-medullated branches, then in the terminal fibrils, and lastly in the nerve trunks (*Gessler*).

Regeneration of Nerves.—In order that regeneration of a divided nerve may take place (*Cruickshank*, 1795), the divided ends of the nerve must be brought into contact (§ 244). In man this is done by means of sutures. About the middle of the fourth week, small clear bands appear within the neurilemma, winding between the nuclei and the remains of the myelin (E). They soon become wider, and receive myelin with incisures, and nodes, and a sheath of Schwann (2d to 3d

month—F). The regeneration process takes place in each inter-annular segment, while the individual segments unite end to end at the nodes of Ranvier (§ 321, I, 5). On this view, each nerve segment of the fibre corresponds to a "cell unit" (*E. Neumann, Eichhorst*). The same process occurs in nerves *ligatured* in their course. *Several* new fibres may be formed within *one* old nerve sheath. The divided axis cylinders of the *central* end of the nerve begin to grow about the 14th day, until they meet the newly formed ones, with which they unite.

[**Primary and Secondary Nerve Suture.**—Numerous experiments on animals and man have established the fact that, immediate or **primary suture** of a nerve, after it is divided, either accidentally, or intentionally, hastens reunion and regeneration, and accelerates the restoration of function. **Secondary suture**, *i. e.*, bringing the ends together long after the nerve has been divided, has been practiced with success. Surgeons have recorded cases where the function was restored after division had taken place for 3 to 16 months, and even longer, and in most cases the sensibility was restored first, the average time being 2 to 4 weeks. Motion is recovered much later. The ends of the nerve should be stitched to each other with catgut, the muscles at the same time being kept from becoming atrophied by electrical stimulation and the systematic use of massage (§ 307). After suture of a nerve, conductivity is restored in the rabbit in 40 days, on the 31st in dogs, and 25th in fowls, but after simple division without suture, not until the 60th day in the rabbit. Transplantation of nerve does not succeed (*Johnson*).]

Union of Nerves.—The central end of a divided motor nerve may unite with the peripheral end of another, and still conduct impulses (*Rava*). [It is stated that sensory fibres will reunite with sensory fibres, and motor fibres with motor fibres, and the regenerated nerve will, in the former case, conduct sensory impulses, and the latter motor impulses. There is very considerable diversity of opinion, however, as to the regeneration or union of sensory with motor fibres. Paul Bert made the following experiment: He stitched the tail of a rat into the animal's back, and after union had taken place, he cut the tail from the body at the root, so that the tail, as it were, grew out of the animal's back, broad end uppermost. On irritating the end of the tail, which was formerly the root, the animal gave signs of pain. This experiment was devised by Bert to try to show that nerve fibres can conduct impulses in both directions. One of two things must have occurred. Either the motor fibres, which normally carried impulses down the tail, now convey them in the opposite direction, and convey them to sensory fibres with which they have united; or the sensory fibres, which normally conducted impulses from the tip upward, now carrying them in the opposite direction. If the former were actually what happened, it would show that nerve fibres of different function do unite (§ 349). Reichert asserts that he has succeeded in uniting the hypoglossal with the vagus in the dog. According to Gessler the end plate is the first to regenerate.]

Trophic Centres.—The regeneration of the nerves seems to take place under the influence of the **nerve centres**, which act as their nutritive, or trophic centres. Nerves permanently separated from these centres never regenerate.

During the regeneration of a *mixed* nerve, sensibility is restored first, subsequently *voluntary* motion, and lastly the movements of the muscles, when their motor nerves are stimulated directly (*Schiff, Erb, v. Ziemssen*).

Wallerian Method of Investigation.—As the *peripheral* end of a nerve undergoes degeneration after section, we use this method for determining the course of nerve fibres in a complex arrangement of nerves. The course of special nerve fibres may be ascertained by tracing the degeneration tract (*Waller*). If after section, reunion or regeneration of a motor nerve does not take place, the muscle supplied by this nerve ultimately undergoes fatty degeneration.

5. **Modifying Conditions.**—Under the action of various operations, *e. g.*, *compressing* a nerve [so as not absolutely to sever the physiological continuity], it has been found that voluntary impulses or stimuli applied *above* the compressed spot, give rise to impulses which are conducted through the nerve, and in the case of a motor nerve, cause contraction of the muscles, while the excitability of the parts *below* the injured spot is greatly diminished (*Schiff*). In a similar manner, it is found that the nerves of animals poisoned with CO_2, curara or coniin, sometimes even the nerves of paralyzed limbs in man, are not excitable to direct stimuli, while they are capable of conducting impressions coming from the central nervous system (*Duchenne*). The injured part of the nerve, therefore, loses its excitability sooner than its power of conducting an impulse.

6. Certain **poisons**, such as *veratrin*, at first increase the excitability of the nerves, and afterward abolish it; with some other poisons, the abolition of the excitability passes off very rapidly, *e.g.*, curara. Conium, cynoglossum, iodide of methylstrychnin, and iodide of æthylstrychnin have a similar action.

If the nerve or muscle of a frog be placed in a solution of the poison, we obtain a different effect from that which results when the poison is injected into the body of the animal. Atropin diminishes the excitability of a nerve-muscle preparation of the frog without causing any previous increase, while alcohol, ether, and chloroform increase and then diminish the excitability (*Mommsen*).

7. **Ritter-Valli Law.**—If a nerve be separated from its centre, or if the centre die, the excitability of the nerve is *increased;* the increase begins at the central end, and travels toward the periphery—the excitability then *falls* until it disappears entirely. This process takes place more rapidly in the central than in the peripheral part of the nerve, so that the peripheral end of a nerve separated from its centre remains excitable for a longer time than the central end.

The *rapidity of the transmission* of impulses in a nerve is increased when the excitability is increased, but it is lessened when the excitability is diminished. In the latter condition, an electrical stimulus must last longer in order to be effective; hence rapid induction shocks may not produce any effect.

The *law of contraction* also undergoes some modification in the different stages of the changes of excitability (§ 336, II).

8. **Excitable Points.**—Many nerves are more excitable at certain parts of their course than at others, and the excitability may last longer at these parts. One of these parts is the upper third of the sciatic nerve of a frog, just where a branch is given off (*Budge*).

The motor and sensory fibres of the upper third of the sciatic nerve of a frog are more excitable for all stimuli than the lower parts (*Grützner and Elpon*). Whether this arises from injury during preparation (a branch is given off there), or is due to anatomical conditions, *e.g.*, more connective tissue and more nodes in the lower part of the sciatic, is undetermined (*Clara Halperson*).

This increased excitability may be due to injury to the nerve in preparing it for experiment. After section or compression of a nerve, all electrical currents employed to stimulate the nerve are far more active when the direction of the current passes away from the point of injury, than when they pass in the opposite direction. This is due to the fact, that the current produced in the nerve after the lesion is added to the stimulation current (§ 331, 5). Even in intact nerves—sciatic of a frog—where the nerve ends at the periphery or at the centre, or where large branches are given off, there are points which behave in the same way as those points where a lesion has taken place (*Grützner and Moschner*).

Death of a Nerve.—In a dead nerve the excitability is entirely abolished, death taking place according to the Ritter-Valli Law, from the centre toward the periphery. The **reaction** of a dead nerve has been found by some observers to be acid (§ 322).

The functions of the **brain** cease immediately death takes place, while the vital functions of the **spinal cord**, especially of the white matter, last for a short time; the large **nerve trunks** gradually die, then the nerves of the extensor muscles, those of the flexors after three to four hours; while the **sympathetic** fibres retain their excitability longest, those of the intestine even for ten hours (*Onimus*). Compare § 295. The nerves of a dead frog may remain excitable for several days, provided the animal be kept in a cool place.

Electro-Physiology.—Before beginning the study of electro-physiology, the student ought to read and study carefully the following short preliminary remarks on the **physics** of this question:—

326. **PHYSICAL—THE GALVANIC CURRENT—RHEOCORD.**—1. **Electro-motive Force.**—If two of the under-mentioned bodies be brought into direct contact, in one of them positive electricity, and, in the other, negative electricity can be detected. The cause of this phenomenon is the *electro-motive force.* The electro-motive substances may be arranged in a series of the **first class**, so that if the first-mentioned substance be brought into contact with any of the other bodies, the first substance is negatively, the last positively, electrified. This series is: carbon, platinum, gold, silver, copper, iron, tin, lead, zinc +.

The **amount** of the electro-motive force produced by the contact of two of these bodies is greater, the further the bodies are apart in the series. The contact of the bodies may take place at one or more points. If several of the bodies of this series be arranged in a pile, the electrical tension thereby produced is just as great as if the two extreme bodies were brought into contact, the intermediate ones being left out.

2. The nature of the two electricities is readily determined by placing *one* of the bodies of the series in contact *with a fluid.* If zinc be placed in pure or acidulated water, the zinc is + (posi-

tive) and the water — (negative). If copper be taken instead of zinc, the copper is + but the fluid —. Experiment shows that those metals, in contact with fluid, are negatively electrified most strongly which are most acted on chemically by the fluid in which they are placed. Each such combination affords a constant difference of tension or potential. The tension [or power of overcoming resistance] of the amount of electricity obtained from both bodies depends upon the size of the surfaces in contact. The fluids, *e. g.*, the solutions of acids, alkalies, or salts, are called exciters of electricity of the **second class.** They do not form among themselves a definite series with different tensions. When placed in these fluids, the metals lying next the + end of the above series, especially zinc, are most strongly electrified negatively, and to a less extent those lying nearer the — end of the series.

3. **Galvanic Battery.**—If two different exciters of the first class be placed in fluid, without the bodies coming into contact, *e. g.*, zinc and copper, the projecting end of the (negative) zinc shows free negative electricity, while the free end of the (positive) copper shows free positive electricity. Such a combination of two electro-motors of the first class with an electro-motor of the second class is called a *galvanic battery*. As long as the two metals in this fluid are kept separate, the circuit is said to be *broken* or *open*, but as soon as the free projecting ends of the metals are connected outside the fluid, *e. g.*, by a copper wire, the circuit or current is *made* or *closed*, and a *galvanic* or **constant current** of electricity is obtained. The galvanic current has resistance to encounter in its course, which is called "*conduction resistance*" (W). It is directly proportional (1) to the *length* (l) of the circuit; (2) and with the same length of circuit, inversely as the section (q) of the same; and (3) it also depends on the molecular properties of the conducting material (*specific conduction resistance* $= s$), so that the conduction resistance, $W = (s.\ l) : q$. The resistance to conduction increases with the increase of the temperature of the metals, but diminishes under similar conditions with fluids.

Ohm's Law.—The strength of a galvanic current (S), or the amount of electricity passing through the closed circuit, is proportional to the electro-motive force (E)—or the electrical tension, but inversely proportional to the total resistance to conduction (L)—

So that $S = E : L$ (Ohm's Law, 1827).

The total **resistance to conduction,** however, in a closed circuit is composed of (1) the resistance outside the battery ("extraordinary resistance"); and (2) the resistance within the battery itself ("essential resistance"). The specific resistance to conduction is very variable in different substances; it is relatively small in metals (*e. g.*, for copper = 1, iron = 6.4, German silver = 12), but very great in fluids (*e. g.*, for a concentrated solution of common salt 6,515,000, for a concentrated solution of copper sulphate 10,963,600).

Conduction in Animal Tissues.—It is also very great in **animal tissues,** almost a million times greater than in metals. When a constant current is applied to the **skin** so as to traverse the body, the resistance diminishes because of the conduction of water in the epidermis under the action of the constant current (§ 290), and the congestion of the cutaneous blood vessels in consequence of the stimulation. But the resistance varies in different parts of the skin, the least being in the palm of the hand and sole of the foot. The chief seat of the resistance is the epidermis, for after its removal by means of a blister, the resistance is greatly diminished. Dead tissue, as a rule, is a worse conductor than living tissues (*Jolly*). When the current is passed *transversely* to the direction of the fibres of a **muscle,** the resistance is nearly nine times as great as when the current passes in the direction of the fibres—a condition which disappears in rigor mortis (*Hermann*). In **nerves,** the resistance longitudinally is two and a half million times greater than in mercury, transversely about twelve million times greater (*Hermann*). Tetanus and rigor mortis diminish the resistance in muscle (*Du Bois-Reymond*).

Deductions.—It follows from Ohm's law that—**I.** If there is very great resistance to the current outside the battery [*i. e.*, between the electrodes], as is the case when a nerve or a muscle lies on the electrodes, the strength of the current can only be increased by increasing the number of the electro-motive elements. **II.** When, however, the extraordinary resistance is very small compared with that within the battery itself, the strength of the current cannot be increased by increasing the number of the elements, but only by increasing the surfaces of the plates in the battery.

Strength and Density.—We must carefully distinguish the *strength* (intensity) of the current from its *density*. As the same amount of electricity always flows through any given transverse section of the circuit, then, if the size of the transverse section of the circuit varies, the electricity must be of greater *density* in the narrower parts, and it is evident that the density will be less where the transverse section is greater. Let S = the strength of the current, and q the transverse section of the given part of the circuit, then the density (d) at the latter part is $d = S : q$.

If the galvanic current passing from the positive pole of a battery is divided into two or more streams, which are again reunited at the other pole, then the sum of the strength of all the streams is equal to the strength of the undivided stream. If, however, the different streams are different as regards length, section and material, then the strength of the current passing in each of the streams is inversely proportional to the resistance to the conduction.

Du Bois-Reymond's Rheocord.—This instrument, constructed on the principle of the "secondary" or "**short circuit,**" enables us to graduate the strength of a galvanic current to any

required degree, for the stimulation of nerve and muscle. From the two poles (Fig. 379, *a*, *b*) of a constant battery, there are two conducting wires (*a*, *c* and *d*, *b*), which go to the nerve of a frog's nerve-muscle preparation (F). The portion of nerve (*c*, *d*) introduced into this circuit (*a*, *c*, *d*, *b*) offers *very great* resistance. The second stream or secondary circuit (*a* A, *b* B) conducted from *a* and *b* passes through a thick brass plate (A, B), consisting of seven pieces of brass (1 to 7) placed end to end, but not in contact. They can all, with the exception of 1 and 2, be made to form a continuous conductor by placing in the spaces between them the brass plugs (S_1 to S_5). Evidently, with the arrangement shown in Fig. 379, only a minimal part of the current will pass through the nerve (*c*, *a*), owing to the very great resistance in it, while by far the greatest part will pass through the good conducting medium of brass (A, L, B). If new **resistance** be introduced into this circuit, then the *a*, *c*, *d*, *b* stream will be strengthened. This resistance can be introduced into the latter circuit by means of the thin wires marked I *a*, I *b*, I *c*, II, V, X. Suppose all the brass plugs from S_1 to S_5 to be removed, then the current entering at A must traverse the whole system of thin wires. Thus, there is more resistance to the passage of this current, so that the current through the nerve must be strengthened. If only one brass plug be taken out, then the current passes through only the corresponding length of wire. The resistances offered by the different lengths of wire from I *a* to X are so arranged that I *a*, I *b* and I *c* each represents a unit of resistance; II, double; V, five times; and X, ten times the resistance. The length of wire, I *a*, can also be shortened by the movable **bridge** (L) [composed of a small tube filled with mercury, through which the wires pass], the scale (*x*, *y*) indicating the length of the resistance wires. It is evident that, by means of the bridge, and by the method of using the brass plugs, the apparatus can be graduated to yield very variable currents for stimulating nerve or muscle. When the bridge (L) is pushed hard up to 1 and 2, the current passes directly from A to B, and not through the thin wires (I *a*).

FIG. 379.



Scheme of du Bois-Reymond's rheocord.

The **rheostat** is another instrument used to vary the resistance of a galvanic current (*Wheatstone*).

327. ACTION OF THE GALVANIC CURRENT ON A MAGNETIC NEEDLE—GALVANOMETER.—In 1820, Oerstedt, of Copenhagen, found that a **magnetic needle**, suspended in the magnetic meridian, was deflected by a constant current of electricity passed along a wire parallel to it. [The side to which the north pole is deflected depends upon the direction of the current, and whether it passes above or below the needle.]

Ampère's Rule.—Ampère has given a simple rule for determining the direction. If an observer be placed parallel to and facing the needle, and if the current be passing from his feet to his head, then the north pole of the needle will always be deflected to the *left*, and the south pole in the opposite direction. The effect exerted by the constant current acts always in a direction toward the so-called electro-magnetic plane. The latter is the plane passing through the north pole of the needle, and two points in the straight wire running parallel with the needle. The force of the constant current, which causes the deflection of the magnetic needle, is proportional to the sine of the angle between the electro-magnetic plane and the plane of vibration of the needle.

Multiplicator.—The deflection of the needle caused by the constant current may be increased by coiling the conducting wire *many* times in the same direction on a rectangular frame, or merely around and in the same direction as the needle [provided that each turn of the wire be properly insulated from the other]. An instrument constructed on this principle is called a multiplicator or multiplier. The greater the number of turns of the wire, the greater is the angle of deflection of the needle, although the deflection is not directly proportional, as the several turns or coils are not at the same distance from, or in the same position as, the needle. By means of the multiplier we may detect the presence [and also the amount and direction] of *feeble currents*. [The instrument is now termed a **galvanometer.**] Experience has shown that, when great resistance (as in animal tissues) is opposed to the weak galvanic currents, we must use a very large number of turns of thin wire round the needle. If, however, the resistance in the circuit is but small, *e.g.*, in thermo-electrical arrangements, a few turns of a *thick* wire round the needle are sufficient. The multiplier may be made more sensitive by *weakening the magnetic directive force of the needle*, which keeps it pointing to the north.

Galvanometer and Astatic Needles.—In the multiplier of Schweigger, used for physiological purposes, the tendency of the needle to point to the north is greatly weakened by using the astatic needles of Nobili. [A multiplier or galvanometer with a single magnetic needle always requires comparatively strong currents to deflect the needle. The needle is continually acted upon by the directive magnetic influence of the earth, which tends to keep it in the magnetic meredian, and, as soon as it is moved out of the magnetic meridian, the directive action of the earth tends to bring it back. Hence, such a simple form of galvanometer is not sufficiently sensitive for detecting feeble currents. In 1827, Nobili devised an astatic combination of needles, whereby the action of the earth's magnetism was diminished.] Two similar magnetic needles are united by a solid light piece of horn [or tortoise shell], and are so arranged that the north pole of the one is placed over or opposite to the south pole of the other (Fig. 380). [If both needles are equally magnetized, then the earth's influence on the needle is neutralized, so that the needles no longer adjust themselves to the magnetic meridian; hence, such a system is called **astatic**.] As it is impossible to make both needles of absolutely equal magnetic strength, one needle is always stronger than the other. The difference, however, must not be so great that the stronger needle points to the north, but only that the freely suspended system of needles forms a certain angle with the magnetic meridian, into which position the system always swings after it is deflected from this position. This angular deviation of the astatic system toward the magnetic meridian is called the "free deviation." The more perfectly an astatic condition is reached, the nearer does the angle formed by the direction of the free deviation with the magnetic meridian become a right angle. The greater, therefore, the astatic condition, the fewer vibrations will the astatic system make in a given time, after it has been deflected from its position. The duration of each single vibration is also very great. [Hence, when using a galvanometer, and adjusting its needle to zero, if the magnets dance about or move quickly, then the system is not sensitive, but a sensitive condition of the needles is indicated by a *slow* period of oscillation.]

FIG. 380.



Scheme of the galvanometer. N, N, astatic needles suspended by the silk fibre, G; P, P, non-polarizable electrodes, containing zinc sulphate solution, *s*, and pads of blotting paper, *b*, covered with clay, *t*, *t*, on which the muscle, M, is placed; II and III, arrangement of the muscle on the electrodes; IV, non-polarizable electrodes; Z, zinc wire; K, cork; *a*, zinc sulphate solution; *t*, *t*, clay points.

In making a galvanometer, the turns of the wire must have the same direction as the needles. In Nobili's galvanometer, as improved by du Bois-Reymond, the upper needle swings above a card divided into degrees (Fig. 380), on which the extent of its deflection may be read off. Even the purest copper wire used for the coils round the needles always contains a trace of iron, which exerts an influence upon the needles. Hence, a small fixed directive or compensatory magnet (*r*) is placed near one of the poles of the upper needle to compensate for the action of the iron on the needles.

328. ELECTROLYSIS, POLARIZATION, BATTERIES.—Electrolysis.—Every galvanic current which traverses a fluid conductor causes decomposition or electrolysis of the fluid. The decomposition products, called "**ions**," accumulate at the **poles** (**electrodes**) in the fluid, the positive pole (+) being called the **anode** [*ανά*, up, *ὁδὸς*, a way], the negative pole (—) the **cathode** (*κατά*, down, *ὁδὸς*, a way). The **anions** accumulate at the anode and the **kations** at the cathode.

Transition Resistance.—When the decomposition products accumulate upon the electrodes, by their presence they either increase or diminish the resistance to the electrical current. This is called *transition resistance*. If the resistance within the battery is thereby increased, the transition resistance is said to be *positive*; if diminished, *negative*.

Galvanic Polarization.—The ions accumulated on the electrodes may also vary the strength of the current, by developing between the anions and kations a new galvanic current, just as occurs between two different bodies connected by a fluid medium. The phenomenon is called *galvanic polarization*. Thus, when water is decomposed, the electrodes being of platinum, the oxygen (negative) accumulates at the + pole, and the hydrogen (positive) at the — pole. Usually the polarization current has a direction *opposite* to the original current; hence, we speak of *negative polariza-*

tion. When the two currents have the same direction, *positive polarization* obtains. Of course, transition resistance and polarization may occur together during electrolysis.

Test.—Polarization, when present, may be so slight as not to be visible to the eye, but it may be detected thus: After a time exclude the primary source of the current, especially the element connected with the electrodes, and place the free projecting end of the electrodes in connection with a galvanometer, which will at once indicate, by the deflection of its needle, the presence of even the slightest polarization.

Secondary Decompositions.—The ions excreted during electrolysis cause, especially at their moment of formation, secondary decompositions. With platinum electrodes in a solution of common salt, chlorine accumulates at the anode and sodium at the cathode, but the latter at once decomposes the water, and uses the oxygen of the water to oxidize itself, while the hydrogen is deposited secondarily upon the cathode. The amount of polarization increases, although only to a slight extent, with the *strength of the current*, while it is nearly proportional to the *increase of the temperature.* The attempts to get rid of polarization, which obviously must very soon alter the strength of the galvanic current, have led to the discovery of two important arrangements, viz., the construction of **constant galvanic batteries**, and **non-polarizable electrodes** (*du Bois-Reymond*).

Constant Batteries, Elements, or Cells.—A perfectly constant element produces a *constant* current, *i. e.*, one remaining of equal strength, by the ions produced by the electrodes being got rid of the moment they are formed, so that they cannot give rise to polarization. For this purpose, each of the substances from the tension series used is placed in a special fluid (§ 326), both fluids being separated by a porous septum (porcelain cylinder).

Grove's cell has two metals and two fluids (Fig. 381). The zinc is in the form of a roll placed in dilute sulphuric acid [1 acid to 7 of water, which is contained in a glass, porcelain, or ebonite vessel]. The platinum is in contact with strong nitric acid [which is contained in a porous cell placed inside the roll of zinc]. The O, formed by the electrolysis and deposited on the zinc plate, forms zinc oxide, which is at once dissolved by the sulphuric acid. The hydrogen on the platinum unites at once with the nitric acid, which gives up O and forms nitrous acid and water, thus—

$$[H_2 + HNO_3 = HNO_2 + H_2O.]$$

[Platinum is the + pole, and zinc the — .]

FIG. 381.

Large Grove's cell.

[Grove's battery is very powerful, but the nitrous fumes are very disagreeable and irritating; hence these elements should be kept in a special well-ventilated recess in the laboratory, in an evaporating chamber, or under glass. The fumes also attack instruments.]

Bunsen's cell is similar to Grove's, only a piece of compressed carbon is substituted for the platinum in contact with the nitric acid.

[The carbon is the + pole, the zinc the — .]

[**Daniell's cell** consists of an outer vessel of glass or earthenware, and sometimes of metallic copper, filled with a saturated solution of cupric sulphate (Fig. 382). A roll of copper, perforated with a few holes, is placed in the copper solution, and in order that the latter be kept *saturated*, and to supply the place of the copper used up by the battery when in action, there is a small shelf on the copper roll, on which are placed crystals of cupric sulphate. A porous earthenware vessel containing zinc in contact with dilute sulphuric acid (1 : 7) is placed within the copper cylinder. When the circuit is completed, the zinc is acted on, zinc sulphate being formed, and hydrogen liberated. The hydrogen in statu nascendi passes through the porous cell, reduces the cupric sulphate to metallic copper, which is precipitated on the copper cylinder, so that the latter is always kept bright and clean. The liberated sulphuric acid replaces that in contact with the zinc. Owing to the absence of polarization, the Daniell is one of the most constant batteries, and is generally taken as the standard of comparison.]

[The copper is the + pole, zinc the — .]

[**Smee's cell** contains only one fluid, viz., dilute sulphuric acid (1 : 7), in which the two metals, zinc and platinum, or zinc and platinized silver, are placed.

The platinum is the + pole, and zinc the — .]

[**Grennet's or the Bichromate cell** consists of one plate of zinc and two plates of compressed

carbon in a fluid, containing bichromate of potash, sulphuric acid, and water. The fluid cons
1 part of potassium bichromate dissolved in 8 parts of water, to which one part of sulphuric
added. Measure by *weight*. The cell consists of a wide-mouthed glass bottle (Fig. 383
carbons remain in the fluid, while the zinc can be raised or depressed. When not in actio
zinc, which is attached to a rod (B), is lifted out of the fluid. It is not a very constant b
When in action, the zinc is acted on by the sulphuric acid, hydrogen being liberated, which r
the bichromate of potash.

The carbon is the + pole, and the zinc the — .]

FIG. 382.

Daniell's Cell.

FIG. 383.



Grennet's cell. A, glass vessel; K, K, carbon; Z, zinc; D, E, binding screws for the wires; B, rod to raise the zinc from the fluid; C, screw to fix B.]

FIG. 384.



Leclanché's cell. A, outer vessel; T, porous cylinder, contai
carbon; B, binding screw; Z, zinc; C, binding screw of
pole.

[**Leclanché's cell** (Fig. 384) consists of an outer glass vessel containing zinc in a solutio
ammonium chloride, while the porous cell contains compressed carbon in a fluid mixture of
oxide of manganese and carbon. It is most frequently used for electric bells, as its feeble cur
lasts for a long time.

The carbon is the + pole, and the zinc the — .]

Non-polarizable Electrodes.—If a constant current be applied to moist animal tissues, a
nerve or muscle, by means of ordinary electrodes composed either of copper or platinum, of

electrolysis must occur, and in consequence thereof polarization takes place. In order to avoid this, non-polarizable electrodes (Figs. 380, 385) are used. Such electrodes are made by taking two pieces of carefully amalgamated, pure, zinc wire (z, z), and dipping these in a **saturated solution of zinc sulphate** contained in tubes (a, a), whose lower ends are closed by means of modeler's clay (t, t), moistened with 0.6 per cent. normal saline solution. The contact of the tissues with these electrodes does not give rise to polarity. [The **brush electrodes** of v. Fleischl are very serviceable (Fig. 386). The lower end of the glass tube is plugged with a camel-hair pencil, moistened with modeler's clay, otherwise the arrangement is the same as shown in Fig. 380, IV.]

Arrangement for the Muscle or Nerve Current.—In order to investigate the electrical currents of nerve or muscle, the tissue must be placed on non-polarizable electrodes, which may either be one of the forms described above, or the original form used by du Bois-Reymond. (Fig. 380). The last consists of two zinc troughs (p, p) thoroughly amalgamated inside, insulated on vulcanite,

FIG. 385.



Non-polarizable electrode of du Bois-Reymond. Z, zinc; H, movable support; C, clay point—the whole on a universal joint.

FIG. 386.

Brush electrodes of v. Fleischl.

FIG. 387.

Thomson's reflecting galvanometer. u, upper, l, lower coil; s, s, leveling screws; m, magnet on a brass support, b.

and filled with a saturated solution of zinc sulphate (s, s). In each trough is placed a thick pad or cushion of white blotting paper (b, b) saturated with the same fluid [**deriving cushions**]. [The cushion consists of many layers, almost sufficient to fill the trough, and they are kept together by a thread. To prevent the action of the zinc sulphate upon the tissue, each cushion is covered with a thin layer of modeler's clay (t, t), moistened with 0.6 per cent. saline solution, which is a good conductor [**clay guard**]. The clay guard prevents the action of the solution upon the tissue. Connected with the electrodes are a pair of binding screws, whereby the apparatus is connected with the galvanometer (Fig. 380).

[**Reflecting Galvanometer.**—The form of galvanometer, used in this country for physiological purposes, is that of Sir William Thomson (Fig. 387). In Germany, Weidemann's form is more commonly used. In Thomson's instrument, the **astatic needles** are very light, and connected to each other by a piece of aluminium, and each set of needles is surrounded by a separate coil of wire,

the lower coil (l) winding in a direction opposite to that of the upper (u). A small, round, light, slightly **concave mirror** is fixed to the upper set of needles. The needles are suspended by a delicate silk fibril, and they can be raised or lowered as required by means of a small milled head. When the milled head is raised, the system of needles swings freely. The coils are protected by a glass shade, and the whole stands on a vulcanite base, which is leveled by three screws (s, s). On a brass rod (b) is a feeble magnet (m), which is used to give an artificial meridian. The magnet (m) can be raised or lowered by means of a milled head.]

FIG. 388.

Lamp and scale for Thomson's galvanometer.

FIG. 389.

Shunt for galvanometer.

[**Lamp and Scale.**—When the instrument is to be used, place it so that the coils face east and west. At 3 feet distant from the front of the galvanometer, facing west, is placed the lamp and scale (Fig. 388). There is a small vertical slit in front of the lamp, and the image of this slit is projected on the mirror attached to the upper needles, and by it is reflected on to the paper scale fixed just above the slit. The spot of light is focused at zero by means of the magnet, m. The needles are most sensitive when the oscillations occur slowly. The sensitiveness of the needles can be regulated by means of the magnet. In every case the instrument must be quite level, and for this purpose there is a small spirit-level in the base of the galvanometer.]

[**Shunt.**—As the galvanometer is very delicate, it is convenient to have a shunt to regulate to a certain extent the amount of electricity transmitted through the galvanometer. The shunt (Fig. 389) consists of a brass box containing coils of German silver wire, and is constructed on the same principle as resistance coils or the rheocord (§ 326). On the upper surface of the box are several plates of brass separated from each other, like those of the rheocord, but which can be united by brass plugs. The two wires coming from the electrodes are connected with the two binding screws, and from the latter two wires are led to the outer two binding screws of the galvanometer. By placing a plug between the brass plates attached to the two binding screws in the figure, the current is short circuited. On removing both plugs, the whole of the current must pass through the galvanometer. If *one* plug be placed between the central disk of brass and the plate marked $\frac{1}{9}$ (the other being left out), then $\frac{1}{10}$ of the current goes through the galvanometer and $\frac{9}{10}$ to the electrodes. If the plug be placed as shown in the figure opposite $\frac{1}{99}$, then $\frac{1}{100}$ part of the current goes to the galvanometer, while $\frac{99}{100}$ are short circuited. If the plug be placed opposite $\frac{1}{999}$, only $\frac{1}{1000}$ part goes through the galvanometer.]

Internal Polarization of Moist Bodies.—Nerves and muscular fibres, the juicy parts of vegetables and animals, fibrin, and other similar bodies possessing a porous structure filled with fluid, exhibit the phenomena of polarization when subjected to strong currents—a condition termed internal polarization of moist bodies by du Bois-Reymond. It is assumed that the solid parts in the interior of these bodies which are better conductors, produce electrolysis of the adjoining fluid, just like metals in contact with fluid. The ions produced by the decomposition of the internal fluids give rise to differences of potential, and thus cause internal polarization (§ 333).

Cataphoric Action.—If the two electrodes from a galvanic battery be placed in the two compartments of a fluid, separated from each other by a porous septum, we observe that the fluid particles pass in the direction of the galvanic current, from the + to the — pole, so that after some time, the fluid in the one-half of the vessel increases, while it diminishes in the other. The phenomena of direct transference were called by du Bois-Reymond the *cataphoric action of the constant current.* The introduction of dissolved substances through the skin by means of a constant current depends upon this action (§ 290), and so does the so-called **Porret's phenomenon** in living muscle (§ 293, I, *b*).

External Secondary Resistance.—This condition also depends on cataphoric action. If the copper electrodes of a constant battery be placed in a vessel filled with a solution of cupric sulphate, and from each electrode there project a cushion saturated with this fluid, then, on placing a piece of muscle, cartilage, vegetable tissue, or even a prismatic strip of coagulated albumin across these cushions, we observe that, very soon after the circuit is closed, there is a considerable variation of the current. If the direction of the current be reversed, it first becomes stronger, but afterward diminishes. By constantly altering the direction of the current we cause the same changes in the intensity. If a prismatic strip of coagulated albumin be used for the experiment, we observe simultaneously with the enfeeblement of the current in the neighborhood of the + pole loses water and becomes more shriveled, while at the — pole the albumin is swol

more water. If the direction of the current be altered, the phenomena are also changed. The shriveling and removal of water in the albumin at the positive pole must be the cause of the resistance in the circuit, which explains the enfeeblement of the galvanic current. This phenomenon is called "external secondary resistance" (*du Bois-Reymond*).

329. **INDUCTION—EXTRA CURRENT—MAGNETIC INDUCTION.—Induction of the Extra Current.**—If a galvanic element is closed by means of a short arc of wire, at the moment the circuit is again opened or broken, a *slight* spark is observed. If, however, the circuit is made or closed by means of a very long wire rolled in a coil, then on breaking the circuit there is a *strong* spark. If the wires be connected with two electrodes, so that a person can hold one in each hand, the current at the moment it is opened must pass through the person's body, then there is a violent shock communicated to the hand. This phenomenon is due to a current induced in the long spiral of wire which Faraday called the **extra current.** It is caused thus: When the circuit is closed by means of the spiral wire, the galvanic current passing along it excites an electric current in the adjoining coils of the same spiral. At the moment of closing or making the circuit in the spiral, the induced current is in the opposite direction to the galvanic current in the circuit; hence its strength is lessened, and it causes no shock. At the moment of opening, however, the induced current has the same direction as the galvanic stream, and hence its action is strengthened.

Magnetization of Iron.—If a **rod of soft iron** be placed into the cavity of a spiral of copper wire, then the soft iron remains magnetic as long as a galvanic current circulates in the spiral. If one end of the iron rod be directed toward the observer, and the other away from him, and if, further, the positive current traverse the spiral in the same direction as the hands of a clock, then the end of the magnet directed toward the person is the negative pole of the magnet. The power of the magnet depends upon the number of spiral windings, and on the thickness of the iron bar. As soon as the current is opened, the magnetism of the iron rod disappears.

Induced or Faradic Current.—If a very long, insulated wire be coiled into the form of a spiral roll, which we may call the **secondary spiral,** and if a similar spiral, the **primary spiral,** be placed near the former, and the ends of the wire of the primary spiral be connected with the poles of a constant battery, every time the current in the primary circuit is made (closed), or broken (opened), a current takes place, or, as it is said, is **induced in the secondary spiral.** If the primary circuit be kept closed, and if the secondary spiral be brought nearer to, or removed further from, the primary spiral, a current is also induced in the secondary spiral (*Faraday*, 1832). The current in the secondary circuit is called the **induced** or **Faradic current.** When the primary circuit is *closed*, or when the two spirals are brought nearer to each other, the current in the secondary spiral has a direction *opposite* to that in the primary spiral, while the current produced by *opening* the primary circuit, or by removing the spirals further apart, has the *same* direction as the primary. During the time the primary circuit is closed, or when both spirals remain at the same distance from each other, there is no current in the secondary spiral.

Difference between the Opening [break] and Closing [make] Shocks.—The opening and closing shocks in the secondary spiral are distinguished from each other in the following respects (Fig. 390): The amount of electricity is the same, during the opening, as during the closing shock; but during the **opening** shock the electricity **rapidly** reaches its maximum of intensity and lasts but a short time, while during the **closing** shock it **gradually** increases, but does not reach the high maximum, and this occurs more slowly. [In Fig. 390, P_1 and S_0 are the abscissæ of the primary (inducing) and induced currents respectively. The vertical lines or *ordinates* represent the **intensity** of the current, while the length of the *abscissa* indicates its **duration.** Curve 1 indicates the course of the primary current, and 2, that in the secondary spiral (induced) when the current is *closed*, while at I the primary current is suddenly opened, when it gives rise to the induced current, 4, in the secondary spiral.] The cause of the difference is the following: When the primary circuit is *closed*, there is developed in it the **extra current,** which is *opposite* in direction to the primary current. Hence, it opposes considerable resistance to the complete development of the strength of the primary current, so that the current induced in the secondary spiral must also develop slowly. But when the primary spiral is *opened*, the extra current in the latter has the *same* direction as the primary current —there is no extra resistance. The rapid and intense action of the *opening* induction shock is of great physiological importance.

Break or Opening Shock.—[On applying a *single* induction shock to a nerve or a muscle, the effect is greater with the *break* or *opening* shock. If the secondary spiral be separated from the primary, so that the induced currents are not sufficient to cause contraction of a muscle when applied to its motor nerve, then, on gradually approximating the secondary to the primary spiral, the *break* or *opening* shock will cause a contraction before the closing one does so.]

Helmholtz's Modification.—Under certain circumstances, it is desirable to equalize the make and break shocks. This may be done by greatly weakening the extra current, which may be accomplished by making the primary spiral of only a few coils of wire. v. Helmholtz accomplishes the same result by introducing a secondary circuit into the primary current. By this arrangement

the current in the primary spiral never completely disappears, but by alternately making and breaking this secondary circuit where the resistance is much less, it is alternately weakened and strengthened.

[In Fig. 391 a wire is introduced between *a* and *f*, while the binding screw, *f*, is separated from the platinum contact, *c*, of Neef's hammer, but, at the same time, the screw, *d*, is raised so that it touches Neef's hammer. The current passes from the battery, K, through the pillar, *a*, to *f* in the direction of the arrow, through the primary spiral, P, to the coil of soft wire, *g*, and back to the battery, through *h* and *e*. But *g* is magnetized thereby, and when it is so, it attracts *c* and makes it touch the screw, *d*. Thus a secondary circuit, or short circuit, is formed through *a*, *b*, *c*, *d*, *e*, which weakens the current passing through the electro-magnet, *g*, so that the elastic metallic spring flies up again and the current through the primary spiral is long-circuited, and thus the process is repeated. In Fig. 390 the lines 1 and 7 indicate the course of the current in the primary circuit at closing (*a*), and opening (*e*). It must be remembered that in this arrangement there is always a current passing through the primary spiral, P (Fig. 391). The dotted lines, 6 and 8, above and below S_0, represent the course of the opening (*a*) and closing shocks (*e*) in the secondary spiral. Even with this arrangement the opening is still slightly stronger than the closing shock.] The two shocks, however, may be completely equalized by placing a resistance coil or rheostat in the short circuit, which increases the resistance, and thus increases the current through the primary spiral when the short circuit is closed.

FIG. 390.



Scheme of the induced currents. P_1, abscissa of the primary, and S_0, of the secondary current; A, beginning, and E, end of the inducing current; 1, curve of the primary current weakened by the extra current; 3, where the primary current is opened; 2 and 4, corresponding currents induced in the secondary spiral; P_2, height, *i. e.*, the strength of the constant inducing current; 5 and 7, the curve of the inducing current when it is opened and closed during Helmholtz's modification; 6 and 8, the corresponding currents induced in the secondary circuit.

FIG. 391.



Helmholtz's modification of Neef's hammer. As long as *c* is not in contact with *d*, *g* remains magnetic; thus *c* is attracted to *d* and a secondary circuit, *a*, *b*, *c*, *d*, *e*, is formed; *c* then springs back again, and thus the process goes on. A new wire is introduced to connect *a* with *f*. K, battery.

Unipolar Induction.—When there is a very rapid current in the primary spiral, not only is there a current induced in the secondary spiral, when its free ends are closed, *e. g.*, by being connected with an animal tissue, but there is also a current when *one* wire is attached to a binding screw connected with one end of the wire of the secondary spiral (p. 587). A muscle of a frog's leg, when connected with this wire, contracts, and this is called a *unipolar induced contraction.* It usually occurs when the primary circuit is opened. The occurrence of these contractions is favored when the other end of the spiral is placed in connection with the ground, and when the frog's muscle preparation is not completely insulated.

Magneto-Induction.—If a magnet be brought near to, or thrust into the interior of, a coil of wire, it excites a current, and also when a piece of soft iron is suddenly rendered magnetic or suddenly demagnetized. The direction of the current so induced in the spiral is exactly the same as that with Faradic electricity, *i. e.*, the occurrence of the magnetism, on approximating the spiral to a magnet, excites an induced current in a direction opposite to that supposed to circulate in the magnet. Conversely, the demagnetization, or the removal of the spiral from the magnet, causes a current in the same direction.

Acoustic Tetanus.—If a magnet be rapidly moved to and fro near a spiral, which can easily be done by fixing a vibratory magnetic rod at one end and allowing the other end to swing freely near

the spiral, then the pitch of the note of the vibrating rod gives us the rapidity of the induction shocks. If a frog's nerve-muscle preparation be stimulated, we get what Grossmann called "acoustic tetanus."

330. DU BOIS-REYMOND'S INDUCTORIUM—MAGNETO-INDUCTION APPARATUS.—The inductorium of du Bois-Reymond, which is used for physiological purposes, is a modification of the magneto-electromotor apparatus of Wagner and Neef. A scheme of the apparatus is given in Fig. 392. D represents the galvanic battery. The wire from the positive pole, *a*, passes to a metallic column, S, which has a horizontal **vibrating spring,** F, attached to its upper end. To the outer end of the spring a square piece of iron, *e*, is attached. The middle point of the upper surface of the spring [covered with a little piece of platinum] is in contact with a movable screw, *b*. A moderately thick copper wire, *c*, passes from the screw, *b*, to the **primary spiral or coil,** *x*, *x*, which contains in its interior a number of pieces of soft iron wire, *i*, *i*, covered with an insulating varnish. The copper wire which surrounds the primary spiral is covered with silk. The wire, *d*, is continued from the primary spiral to a *horseshoe* piece of soft iron, H, around which it is coiled spirally, and from thence it proceeds, at *f*, back to the negative pole of the battery, *g*. When the current in this circuit—called the **primary circuit**—is closed, the following effects are produced: The **horseshoe,** H, becomes magnetic, in consequence of which it attracts the movable spring or Neef's hammer, *e*, whereby the contact of the spring, F, with the screw, *b*, is broken. Thus the current is broken, the horseshoe is demagnetized, the spring, *e*, is liberated, and, being elastic, it

FIG. 392.



I, Scheme of du Bois-Reymond's sledge induction machine. D, galvanic battery; *a*, wire from + pole, (*g*) — pole; S, brass upright; F, elastic spring; *b*, binding screw; *c*, wire round primary spiral (*x*, *x*), containing (*i*, *i*) soft iron wire; K, K, secondary spiral, with board (*p*, *p*) on which it can be moved; H, soft iron magnetized by current (*d*, *f*) passing round it. II, key for secondary circuit; as shown it is short-circuited. III, electrodes (*r*, *r*), with a key (K) for breaking the circuit.

springs upward again to its original position in contact with *b*, and thus the current is reëstablished. The new contact causes H to be remagnetized, so that it must alternately rapidly attract and liberate the spring, *e*, whereby the primary current is rapidly made and broken between F and *b*.

A **secondary spiral** or coil (K, K) is placed in the same direction as the primary (*x*, *x*), but having no connection with it. It moves in grooves upon a long piece of wood (*p*, *p*). The secondary spiral consists of a hollow cylinder of wood covered with numerous coils of *thin*, silk-covered wire. The secondary spiral, moving in slots, can be approximated to or even pushed entirely over the primary spiral, or can be removed from it to any distance desired.

[Fig. 393 shows the actual arrangement of **du Bois-Reymond's inductorium.** The **primary coil** (R′) consists of about 150 coils of **thick** insulated copper wire, the wire being thick to offer slight resistence to the galvanic current. The **secondary** coil (R″) consists of 6000 turns of **thin** insulated copper wire arranged on a wooden bobbin; the whole spiral can be moved along the board (B) to which a millimetre scale (I) is attached, so that the distance of the secondary from the primary spiral may be ascertained. At the left of the apparatus is **Wagner's hammer,** as adapted by Neef, which is just an automatic arrangement for opening and breaking the primary circuit. When Neef's hammer is used, the wires from the battery are connected as in the figure; but when single shocks are required, the wires from the battery are connected with a key, and this again with the

two terminals of the primary spiral, S″ and S‴. In the improved form of this apparatus (Fig. 394) the secondary spiral is equipoised over a pulley with a back weight, so that it can move easily in a vertical direction to and from the primary spiral. A. de Watteville has used a form similar to this for a long time.]

According to the law of induction (§ 329), when the primary circuit is closed, a current is induced in the secondary circuit in a direction the *reverse* of that in the primary, while, when it is opened, the induced current has the *same* direction. Further, according to the laws of magneto induction, the magnetization of the iron rods (*i*, *i*) within the primary spiral (*x*, *x*), causes a *reverse* current in the secondary spiral (K, K), while the demagnetization of the iron rods, on opening the primary circuit causes an induced current in the *same* direction. Thus, we explain the much more powerful action of the opening or break shock as compared with the closing or make shock (p. 531). [The direction of the *inducing* current remains the *same*, while the **induced currents** are **constantly reversed.**]

The **magneto-induction** (R) apparatus of Pixii, as improved by Stöhrer, consists of a very powerful horseshoe **steel magnet** (Fig. 395). Opposite its two poles (N and S) is a horseshoe-shaped piece of iron (H), which rotates on a horizontal axis (*a*, *b*). On the ends of the horseshoe are fixed wooden bobbins (*c*, *d*′), with an insulated wire coiled round them. When the horseshoe is at rest, as in the figure, it becomes magnetized by the steel magnet, while in the wires of both bobbins (*c* and *d*′) an electric current is developed every tine the horseshoe is demagnetized, and again magnetized. When the bobbins rotate in front of the magnet, as each coil approaches one pole, a current is induced, and similarly when it is carried past the pole of the magnet, so that four currents are induced in each coil by a single rotation. By means of Stöhrer's commutator (*m*, *n*) attached to the spindle (*a*, *b*), and the divided metal plates (*y*, *z*) which pass to the electrodes, the two currents induced in the bobbins are obtained in the same direction.

FIG. 394.

New form of du Bois-Reymond's inductorium.

FIG. 393.



Induction apparatus of du Bois-Reymond. R′, primary, R″, secondary spiral; B, board on which R″ moves; I, scale; + —, wires from battery; P′, P″, pillars; H, Neef's hammer; B′, electro-magnet; S′, binding screw touching the steel spring (H); S″ and S‴, binding screws to which to attach wires where Neef's hammer is not required.

Keys, or arrangements for opening or closing a circuit, are of great use. Fig. 392, II, shows a scheme of the **friction key** of du Bois-Reymond, introduced into the secondary circuit. It consists of two brass bars (*z* and *y*) fixed to a plate of ebonite, and as long as the key is down on the metal bridge (*y*, *r*, *z*) it is "*short-circuited*," *i. e.*, the conduction is so good through the thick brass bars that none of the current goes through the wires leading from the left of the key. When the bridge (*r*) is lifted the current is open. [Fig. 396 shows the form of the key, *v* being a screw wherewith to clamp it to the table.] Similarly the key electrodes (III) may be used, the current being made as soon as the spring connecting plate (*e*) is raised by pressing upon *k*. This instrument is opened by the hand; *a*, *b* are the wires from the battery or induction machine; *r*, *r*, those going to the tissue; G, the handle of the instrument.

[**Plug Key.**—Other forms of keys are in use, *e. g.*, Fig. 397, the plug key, the two brass plates to which the wires are attached being fixed on a plate of ebonite. The brass plug is used to connect the two brass plates. All these are *dry* contacts, but sometimes a *fluid* contact is used as in the **mercury key**, which merely consists of a block of wood with a cup of mercury in its centre. The

ends of the wires from the battery dip into the mercury; when both wires dip into the mercury the circuit is made, and when one is out it is broken.]

[**Capillary Contact Key.**—Where an ordinary mercury key is used to open and close the primary circuit, the layer of oxide formed on the surface by the opening spark disturbs the conduction after a short time; hence, it is advisable to wash the surface of the mercury with a dilute solution of

FIG. 395.



Magneto-induction apparatus, with Stöhrer's commutator.

FIG. 396.

Du Bois-Reymond's friction key.

alcohol and water (*W. Stirling*). A handy form of "capillary contact" is shown in Fig. 398, such as was used by Kronecker and Stirling in their experiments on the heart. "A glass **T** tube is provided at the crossing point with a small opening (*a*). The vertical tube (*b*) is bent in the form of a **U**, and filled so full with mercury that the convex surface of the latter projects within the lumen of

FIG. 397.

Plug Key.

FIG. 398.

Capillary contact. *e*, vibrating platinum style adjustable by *f* and *g* and dipping into mercury at *a*; *b*, bent tube filled with mercury, into which dips a wire (*d*); *a*, opening in cross tube (*c*).

the transverse tube (*c*). One end of *c* is connected with a Mariotte's flask containing diluted alcohol, and the supply of the latter can be regulated by means of a stop-cock. The fluid flows over the apex of the mercury and keeps it clean. The vibrating platinum style (*e*) is attached to the end of a rod which in turn is connected with the positive pole of the battery, while the platinum wire (*d*) is connected with the negative pole of the "battery."]

[331. **ELECTRICAL CURRENTS in PASSIVE MUSCLE and NERVE—SKIN CURRENTS.—Methods.**—In order to investigate the laws of the muscle current, we must use a muscle composed of parallel fibres, and with a simple arrangement of its fibres in the form of a prism or cylinder (Fig. 339, I and II). The sartorius muscle of the frog supplies these conditions. In such a muscle, we distinguish the **surface** or the **natural longitudinal section**, its **tendinous ends** or the **natural transverse section**; further, when the latter is divided transversely to the long axis, the **artificial transverse** section (Fig. 399, I, *c*, *d*); lastly, the term **equator** (*a*, *b*–*m*, *n*) is applied to a line so drawn as exactly to divide the length of the muscle into halves. As the currents are very feeble, it is necessary to use a galvanometer with a periodic damped magnet (Figs. 380, I, and 387), or a tangent mirror boussole similar to that used for thermo-electric purposes (Fig. 230). The wires leading from the tissue are connected with non-polarizable electrodes (Fig. 380, P, P).

The **capillary electrometer** of Lippmann may be used for detecting the current (Fig. 400). A thread of mercury enclosed in a capillary tube and touching a conducting fluid, *e. g.*, dilute sulphuric acid, is displaced by the constant current, in consequence of the polarization taking place at the point of contact altering the constancy of the capillarity of the mercury. The displacement of the mercury which the observer (B) detects by the aid of the microscope (M) is in the direction of the positive current. R is a capillary glass tube, filled from above with mercury, and from below with

FIG. 399.



Scheme of the muscle current.

FIG. 400.

Capillary electrometer. R, mercury in tube; capillary tube; *s*, sulphuric acid; *q*, Hg; B, observer; M, microscope.

dilute sulphuric acid. Its lower narrow end opens into a wide glass tube, provided below with platinum wire fused into it and filled with Hg (*q*), and this again is covered with dilute sulphu acid (*s*). The wires are connected with non-polarizable electrodes applied to the + and — surfaces the muscle. On closing the circuit, the thread of mercury passes downward from *c* in the directi of the arrow.

Compensation.—The **strength** of the current in animal tissues is best measured by the co pensation method of Poggendorf and du Bois-Reymond. A current of known strength, or wh can be accurately graduated, is passed in an opposite direction through the same galvanometer boussole, until the current from the animal tissue is just neutralized or compensated. [When occurs, the needle deflected by the tissue current returns to zero. The principle is exactly the s as that of weighing a body in terms of some standard weights placed in the opposite scale pa the balance.]

[Hermann calls the current obtained from an injured muscle, *i. e.*, one on w an artificial transverse or other section has been made, a **demarcation cur** while the currents obtained when such a muscle contracts, he calls **action**

rents. This section deals with demarcation currents, or the muscle current of du Bois-Reymond.]

1. Perfectly fresh **uninjured muscles** yield **no current**, and the same is true of dead muscle (*L. Hermann*, 1867).

2. **Strong** electrical currents are observed when the *transverse section* of a muscle is placed on one of the cushions of the non-polarizable electrodes (Fig. 380, I, M), while the *surface* is in connection with the other (*Nobili, Matteucci, du Bois-Reymond*). The **direction** of the current is from the (positive) longitudinal section to the (negative) transverse section in the conducting wires (*i. e.*, within the muscle itself from the transverse to the longitudinal section (Figs. 380, I, and 399, I). This current is stronger the nearer one electrode is to the equator, and the other to the centre of the transverse section; while the strength diminishes, the nearer the one electrode is to the end of the surface, and the other to the margin of the transverse section.

Smooth muscles also yield similar currents between their transverse and longitudinal surfaces (§ 334, II).

3. **Weak** electrical currents are obtained when (*a*) two points at unequal distances from the equator are connected; the current then passes from the point nearer the equator (+) to the point lying further from it (—), but of course this direction is reversed within the muscle itself (Fig. 399, II, *ke* and *le*). (*b*) Similarly weak currents are obtained by connecting points of the transverse section at unequal distances from the centre, in which case the current outside the muscle passes from the point lying nearer the edge of the muscle to that nearer the centre of the transverse section (Fig. 399, II, *i*, *c*).

4. When two points on the surface are **equidistant** from the equator (Fig. 399, I, *x*, *y*, *v*, *z*,—II, *r*, *e*), or two equidistant from the centre of the transverse section (II, *c*) are connected, no current is obtained. [Because the points are iso-electrical, that is of equal potentiality.]

5. If the transverse section of the muscle be **oblique** (Fig. 399, III), so that the muscle forms a **rhomb**, the conditions obtaining under III are disturbed. The point lying nearer to the *obtuse* angle of the transverse section or surface is positive to the one lying near to the acute angle. The equator is oblique (*a*, *c*). These currents are called "*deviation currents* or *inclination currents*" by du Bois-Reymond, and their course is indicated by the lines 1, 2, and 3.

The **electromotive force of a strong muscle current** (frog) is equal to 0.05 to 0.08 of a Daniell's element; while the strongest deviation current may be 0.1 Daniell. The muscles of a curarized animal at first yield stronger currents; *fatigue* of the muscle diminishes the strength of the current (*Roeber*), while it is completely abolished when the muscle dies. *Heating* a muscle increases the current; but above 40° C. it is diminished (*Steiner*). *Cooling* diminishes the electromotive force. The warmed *living* muscular and nervous substance is positive to the cooler portions (*Hermann*); while, if the *dead* tissues be heated, they behave practically as indifferent bodies as regards the tissues that are not heated.

6. The **passive nerve** behaves like muscle, as far as 2, 3, and 4 are concerned.

The **electromotive force of the strongest nerve current**, according to du Bois-Reymond, is 0.02 of a Daniell. Heating a nerve from 15° to 25° C. increases the nerve current, while high temperatures diminish it (*Steiner*)

7. If the two transversely divided ends of an excised **nerve**, or two points on the surface equidistant from the equator, be tested, a current—the **axial current**—flows in the nerve fibre in the opposite direction to the direction of the normal impulse in the nerve; so that in centrifugal nerves it flows in a centripetal direction, and in centripetal nerves in a centrifugal direction (*Mendelssohn and Christiani*).

The electromotive force increases with the length of the nerve and with the area of its transverse section. Fatigue (*e. g.*, tetanic stimulation) weakens it, especially in motor nerves, and to a less extent in centripetal nerves.

[**Nerve-muscle Preparation.**—This term has been used on several occasions. It is simply the sciatic nerve with the gastrocnemius of the frog attached to it (Fig. 401). The sciatic nerve is dissected out entire from the vertebral column to the knee; the muscles of the thigh separated from the femur, and the latter divided about its middle, so that the preparation can be fixed in a clamp by the remaining portion of the femur; while the tendon of the gastrocnemius is divided near to the foot. If a straw flag is to be attached to the foot, do not divide the tendo-Achilles.]

FIG. 401.

Nerve-muscle preparation of a frog. F, femur; S, sciatic nerve; I, tendo-Achilles.

Rheoscopic Limb.—The existence of a **muscle current** may be proved **without the aid of a galvanometer**: 1. By means of a sensitive nerve-muscle preparation of a frog, or the so-called "*physiological rheoscope.*" Place a moist conductor on the transverse and another on the longitudinal surface of the gastrocnemius of a frog. On placing the sciatic nerve of a nerve-muscle preparation of a frog on these conductors, so as to bridge over or connect their two surfaces, contraction of the muscle connected with the nerve occurs at once; and the same occurs when the nerve is removed.

Make a transverse section of the gastrocnemius muscle of a frog's nerve-muscle preparation, and allow the sciatic nerve to fall upon this transverse section; the limb will contract as the muscle current from the longitudinal to the transverse surface now traverses the nerve (*Galvani, Al. v. Humboldt*). These experiments have long been known as "**contraction without metals.**"

[Use a nerve-muscle preparation, or, as it is called, a physiological limb. Hold the preparation by the femur, and allow its own nerve to fall upon the gastrocnemius, and the muscle will contract, but it is better to allow the nerve to fall suddenly upon the cross section of the muscle. The nerve then completes the circuit between the longitudinal and transverse section of the muscle, so that it is stimulated by the current from the latter, the nerve is stimulated, and through it the muscle. That it is so, is proved by tying a thread round the nerve near the muscle, when the latter no longer contracts.]

2. **Self-stimulation of the Muscle.**—We may use the *muscle current* of an isolated muscle to stimulate the latter directly and cause it to contract. If the transverse and longitudinal surfaces of a curarized frog's nerve-muscle preparation be placed on non-polarizable electrodes, and the circuit be closed by dipping the wires coming from the electrodes in mercury, then the muscle contracts. Similarly a **nerve** may be stimulated with its own **demarcation** current (*du Bois-Reymond and others*). If the lower end of a muscle with its transverse section be dipped into normal saline solution (0.6 per cent. NaCl), which is quite an indifferent fluid, this fluid forms an accessory circuit between the transverse and adjoining longitudinal surface of the muscle, so that the muscle contracts. Other indifferent fluids used in the same way produce a similar result.

FIG. 402.

Kühne's nerve demarcation-current experiment.

[**Kühne's Experiment** (Fig. 402). —The demarcation current of the nerve of a nerve-muscle preparation may be used as the stimulus to that nerve on completing the circuit. On an earthenware bowl (B) is fixed a glass plate (G), and thin rolls of modeler's clay (P P′) are bent over G. A nerve-

muscle preparation is placed with its nerve (N) on the clay, touching the latter with its transverse and longitudinal surfaces. On dipping the clay into a vessel containing normal saline (C), the muscle contracts, and on withdrawing the normal saline, it again contracts. In this case the nerve is stimulated by the completion of the circuit of its own demarcation current.]

3. **Electrolysis.**—If the muscle current be conducted through *starch mixed with potassic iodide*, then the iodine is deposited at the + pole, where it makes the starch blue.

Frog Current.—It is asserted that the total current in the body is the sum of the electrical currents of the several muscles and nerves which, in a frog deprived of its skin, pass from the tip of the toes toward the trunk, and in the trunk from the anus to the head. This is the "*corrente propria della rana*" of Leopoldo Nobili (1827), or the "*frog current*" of du Bois-Reymond. In mammals, the corresponding current passes in the opposite direction.

After death, the currents disappear sooner than the excitability (*Valentin*); they remain longer in the muscle than the nerves, and in the latter they disappear sooner in the central portions. If the nerve current after a time become feeble, it may be strengthened by making a new transverse section of the nerve. A motor nerve completely paralyzed by **curara** gives a current (*Funke*), and so does a nerve beginning to undergo degeneration, even two weeks after it has lost its excitability. Muscles in a state of **rigor mortis** give currents in the opposite direction, owing to inequalities, which take place during decomposition. The nerve current is reversed by the act on of boiling water or drying.

Currents from Skin and Mucous Membranes.—In the skin of the frog the outer surface is +, the inner is — (*du Bois-Reymona*), and the same is true of the mucous membrane of the intestinal tract (*Rosenthal*), the cornea (*Grünhagen*), as well as the *non-glandular* skin of fishes (*Hermann*), and mollusks (*Oehler*). Currents are also manifested by **glands.**

332. CURRENTS OF STIMULATED MUSCLE AND NERVE —ACTION CURRENTS.—1. **Negative Variation of the Muscle Current.**—If a muscle, which yields a strong electrical current, be thrown into a state of tetanic contraction by stimulating its motor nerve, then, when the muscle contracts, there is a **diminution of the muscle current**, and occasionally the needle of the galvanometer may swing almost to zero. This is the "negative variation of the muscle current" (*du Bois-Reymond*). It is larger, the greater the primary deflection of the galvanometer needle and the more energetic the contraction.

After tetanus, the muscle current is weaker than it was before. If the muscle was so placed upon the electrodes that the current was "feeble," equally during tetanus there is a diminution of this current. In the inactive arrangement, the contraction of the muscle has no effect on the needle. If the muscle be prevented from shortening, as by keeping it tense, the negative variation still takes place.

2. **Current during Tetanus.**—An *excised* frog's muscle *tetanized* through its *nerve* shows electromotive force—the so-called "**action current.**" In a tetanized frog's gastrocnemius, there is a *descending* current. In completely uninjured human muscles, however, thrown into tetanus by acting on their nerves, there is no such current (*L. Hermann*); similarly, in *quite uninjured* frog's muscles, as well as when these muscles are *directly* and *completely tetanized*, there is no current.

3. **Current during the Contraction Wave.**—If one end of a muscle be directly excited with a momentary stimulus, so that the *contraction wave* (§ 299) rapidly passes along the whole length of the muscular fibres, then each part of the muscle, successively and immediately before it contracts, shows the negative variation. Thus, the "*contraction wave*" is preceded by a "*negative wave*" of the muscle current, the latter occurring during the *latent period.* Both waves have the same velocity, about 3 metres per second. The negative wave, which first increases and then diminishes, lasts at each point only 0.003 second (*Bernstein*).

4. **During a Single Contraction.**—A *single* contraction also shows a muscle current. [The electrical variation takes place during the latent period of the muscular contraction, so that it precedes the latter. The variation begins .01″ to .04″ after excitation, while the contraction does not begin until .11″ to .33 (*Wal-*

ler). A frog's muscle may be made to record its contraction, and simultaneously the variation of the electrical current, as ascertained by the capillary electrometer, may be photographed (Fig. 403), and the same may be done in the case of the heart (Fig. 404). The capillary electrometer may with advantage be employed to measure this time difference, the electrical and the mechanical events being simultaneously recorded.]

FIG. 403.



Frog. Gastrocnemius led off to electrometer from the middle of the muscle and from the tendon. Contraction excited by a single break induction shock applied to the sciatic nerve. *e*, electrometer; *m*, muscle; *t*, time in $\frac{1}{10}$ sec. (muscle to H_2SO_4; tendon to Hg) (*Waller*).

The diphasic variation—1st phase middle negative to end; 2d phase and negative to middle begins about .01″ before the commencement of muscular contraction (*Waller*).

The variation is diphasic—1st phase base negative to apex; 2d phase apex negative to base (*Waller*). The first phase begins $\frac{1}{10}$″ before the commencement of contraction.

One of the best objects for this purpose is the **contracting heart**, which is placed upon the non-polarizable electrodes connected with a sensitive galvanometer. Each beat of the heart causes a deflection of the needle, which occurs *before* the contraction of the cardiac muscle (*Kölliker and H. Müller*). The electrical disturbance in the muscle causing the negative variation always precedes the actual contraction (*v. Helmholtz*, 1845). Still it lasts throughout the whole duration of the contraction (*Lee*). When the completely uninjured frog's gastrocnemius contracts by stimulating the nerve, there is at first a descending and then an ascending current (*Sig. Mayer*, § 334, II).

More exact observations on the electrical processes of the pulsating heart show that complicated phenomena occur. The apex of the dog's heart is negative to the base during systole. In many cases this is preceded, and in some it is followed, by an opposite condition (*Frédéricq*), *i. e.*, a

FIG. 404.

Frog's heart. Spontaneous contraction, *e*, *e*, electrometer; *h*, *h*, heart's contraction; *t*, *t*, time in $\frac{1}{10}$ sec. (apex to H_2SO_4, base to Hg) (*Waller*).

diphasic variation. If the heart be arrested in diastole by stimulation of the vagus (§ 369), there is a *positive* variation of the muscle current (*Gaskell, Fano*). Waller has demonstrated a true electrical variation of the human intact heart.

[**Heart.**—Gaskell has shown that, when the vagus of a tortoise is stimulated so as to arrest its heart in diastole, the action of the inhibitory nerve is accompanied

by a *positive* electrical variation of the heart current, while stimulation of the sympathetic (augmentor) nerve causes an electrical variation of the same sign as that caused by a contraction in the non-beating tissue of the ventricle of the toad. In both cases, the respective nerves can produce their electrical effect after the heart has been brought to standstill by the application of muscarin to the sinus. These experiments are of the utmost importance in connection with the theory of the action of these nerves on the heart (§ 370), and the mode of action of poisons on the heart itself.]

Secondary Contraction.—A *nerve-muscle* preparation may be used to demonstrate the electrical changes that occur during a *single* contraction. If the sciatic nerve, A, of such a preparation be placed upon another muscle, B, as in Fig. 405, then every time the latter, B, contracts, the frog's muscle, A, connected with the nerve also contracts.

If the nerve of a frog's nerve-muscle preparation be placed on a contracting mammalian heart, then a contraction of the muscle occurs with every beat of the heart (*Matteucci*, 1842). The diaphragm, even after section of the phrenic nerve, especially the left, also contracts during the heart beat (*Schiff*). This is the "**secondary contraction**" of Galvani.

FIG. 405.

Secondary contraction. The sciatic nerve of A lies on B; E, electrodes applied to the sciatic nerve of B.

Secondary Tetanus.—Similarly, if a nerve of a nerve-muscle preparation be placed on a muscle which is tetanized, then the former also contracts, showing "secondary tetanus" (*du Bois-Reymond*). The latter experiment is regarded as a proof that, during the process of negative variation in the muscle, many successive variations of the current must take place, as only rapid variations of this kind can produce tetanus by acting on a nerve—*continuous* vibrations being unable to do so.

Usually, there is no secondary tetanus in a frog's nerve-muscle preparation when it is laid upon a muscle which is tetanized voluntarily, or by chemical stimuli, or by poisoning with strychnin (*Hering, Kühne*); still, Lovèn has observed secondary strychnin tetanus composed of six to nine shocks per second. Observations with a sensitive galvanometer, or Lippmann's capillary electrometer (Fig. 400), show that the spasms of strychnin poisoning, as well as a voluntary contraction, are discontinuous processes (*Lovèn*, p. 485).

Biedermann observed that striped muscle, under the influence of the vapor of ether, passes into a condition in which it shows no obvious change of form or movement when it is stimulated, while at the spot stimulated, there are galvanometric variations of the same strength as occurred during stimulation before the action of the ether. Owing to the abolition of the power of conductivity, they can only manifest themselves locally.

[**Secondary Contraction from Muscle to Muscle** (*Kühne*).—If 5 mm. of one end of the sartorius of a curarized frog be laid upon a corresponding 5 mm. of the other sartorius, so that both muscles are in line, and if the surfaces of contact be pressed together, either by an ebonite press or other means, on stimulating the free end of one of the muscles—either electrically, mechanically, or chemically—the other muscle also contracts, and if the first one be tetanized, the second one also is thrown into tetanus. The experiment may be repeated with five or six muscles in line. The conduction is interrupted at once by ligature of the muscle. The second muscle contracts, because it is stimulated directly by the **action currents** of the contracting muscular fibres. The effect is prevented by introducing, between the overlapping ends of the muscle, a thin plate of gutta percha, tinfoil, or any insulator. This experiment of Kühne's shows us how important a *rôle* electrical phenomena play in connection with muscular contraction. Secondary contraction from nerve has long been known.]

Negative Variation in Nerve.—If a nerve be placed with its transverse

section on one non-polarizable electrode, and its longitudinal surface on the other, and if it be stimulated electrically, chemically, or mechanically, the nerve current is also diminished (*du Bois-Reymond*). This **negative variation** is propagated toward *both* ends of a nerve, and is composed of very rapid, successive, periodic interruptions of the original current, just as in a contracted muscle (*Bernstein*). Hering succeeded in obtaining from a nerve, as from a muscle, a secondary contraction or secondary tetanus. The amount of the negative variation depends upon the extent of the primary deflection, also upon the degree of nervous excitability and on the strength of the stimulus employed. The negative variation occurs on stimulating with tetanic as well as with single shocks. The negative variation is not observed in completely uninjured nerves.

Hering found that the negative variation of the nerve current caused by tetanic stimulation is followed by a *positive* variation, which occurs immediately after the former, *i. e.*, it is diphasic. It increases to a certain degree with the duration of the stimulation, as well as with the strength of the stimulus, and with the drying of the nerve (*Head*). (*Effect of Electrotonus*, § 335, 1).

FIG. 406.



Scheme of Bernstein's differential rheotome; N *n*, nerve; J, induction machine; G, galvanometer, *x*, *y*, deflection of needle; E, battery and primary circuit with C for opening it at *o*; *c*, for closing galvanometer circuit; *z z*, electrodes in galvanometer circuit; S, motor.

Negative Variation of the Spinal Cord.—This is the same as in nerves generally. If a current be conducted from the transverse and longitudinal surfaces of the upper part of the medulla oblongata, we observe *spontaneous*, intermittent, *negative variations*, perhaps due to the intermittent excitement of the nerve centres, more especially of the respiratory centre. Similar variations are obtained reflexly by single stimuli applied to the sciatic nerve, while strong stimulation by common salt or induction shocks inhibits them.

Velocity.—The process of negative variation is propagated at a measurable velocity along the nerve, most rapidly at 15° to 25° C. (*Steiner*), and at the same rate as the velocity of the nervous impulse itself, about 27 to 28 metres per second. The duration of a single variation (of which the process of negative variation is composed) is only 0.0005 to 0.0008 second, while the wave length in the nerve is calculated by Bernstein at 18 mm.

Differential Rheotome.—J. Bernstein estimated the velocity of the negative variation in a nerve by means of a differential rheotome thus (Fig. 406): A long stretch of a nerve (N *n*) is so arranged that at *one* end of it (N) its transverse and longitudinal surfaces are connected with a galvanometer (G), while at the *other* end (*n*) are placed the electrodes of an induction machine (J). A disk (B) rapidly rotating on its vertical axis (A) has an arrangement (C) at one point of its circumference, by means of which the current of the primary circuit (E) is rapidly opened and closed during each revolution. This causes, with each rotation of the disk, an opening and a closing shock to be applied to the end of the nerve. At the diametrically opposite part of the circumference is an arrangement

c) by which the galvanometer circuit is closed and opened during each revolution. Thus, the **stimulation** and the **closing** of the galvanometer circuit occur at the same moment. On rapidly rotating the disk, the galvanometer indicates a **strong** nerve current, an excursion of the magnetic needle to . At the moment of stimulation, the negative variation has not yet reached the other end of the erve. If, however, the arrangement which closes the galvanometer circuit be so displaced (to *o*) long the circumference, that the galvanometer circuit is closed somewhat *later* than the nerve is timulated, then the current is **weakened** by the negative variation (the needle passing backward to). When we know the velocity of rotation of the disk, it is easy to calculate the rate at which the mpulse causing the negative variation passes along a given distance of nerve from N to *n*.

The negative variation is absent in **degenerated nerves** as soon as they lose their excitability.

Retinal and Eye Currents.—If a freshly-excised eyeball be placed on the non-polarizable electrodes connected with a galvanometer, and if light fall upon the eye, then the normal eye current from the cornea (+) to the transverse section of the optic nerve (—) is at first increased. Yellow light is most powerful, and less so the other colors (*Holmgren, M'Kendrick and Dewar*). The inner surface of the *passive* retina is positive to the posterior. When the retina is illuminated there is a double variation, a negative variation with a preliminary positive increase; while, when the light ceases, there is a simple positive variation. Retinæ, in which the visual purple has disappeared owing to the action of light, show smaller variations (*Kühne and Steiner*).

Stimulation of the secretory nerves of the *glandular* membranes, besides causing secretion, affects the current of rest (*Roeber*). This **secretion current** passes in the *same* direction in the skin of the frog and warm-blooded animals as the current of rest, although in the frog it is occasionally in the opposite direction (*Hermann*). If the current be conducted uniformly from both hind feet of a cat, on stimulating the sciatic nerve of one side, not only is there a secretion of sweat (§ 288), but a secretion current is developed (*Luchsinger and Hermann*). If two symmetrical parts of the skin in the leg or arm of a man be similarly tested, and the muscle of one side be contracted, a similar current is developed. Destruction or atrophy of the glands abolishes both the power of secretion and the secretion current. There is no secretion current from skin covered with hairs, but devoid of glands (*Bubnoff*). [The secretion current from the sub-maxillary gland is referred to in § 145 (*Bayliss and Bradford*).]

333. ELECTROTONIC CURRENTS IN NERVE AND MUSCLE.

—[When a **constant current** called the "**polarizing current**" is passed through a stretch of nerve, the nerve is thrown into a peculiar condition, called the "electrotonic condition," or briefly **electrotonus.** In this condition, the vital properties of the nerve are modified, *i. e.*—

(1) Its **electromotivity** (§ 333).

(2) Its **excitability** (§ 335).

The former is considered in this section, and the latter in a subsequent section.]

FIG. 407.



Nerve current in electrotonus. *a*, galvanometer; *b*, electrodes; E, constant current.

1. **Positive Phase of Electrotonus.**—If a nerve be so arranged upon the electrodes (Fig. 407, I) that its transverse section lies on one, and its longitudinal on the other electrode, then the galvanometer indicates a strong current. If now a **constant current** be transmitted through the end of the nerve projecting beyond the electrodes (the so-called "*polarizing*" end of the nerve), and if the direction of this current *coincide* with that in the nerve, then the magnetic needle gives a greater deflection, indicating an *increase* of the nerve current—"**the positive phase of electrotonus.**" The increase is greater the longer the stretch of nerve traversed by the current, the stronger the galvanic current, and the less the distance between the part of the nerve traversed by the constant current and that on the electrodes.

2. **Negative Phase of Electrotonus.**—If in the same length of nerve the constant current passes in the **opposite** direction to the nerve current (Fig. 407, II), there is a diminution of the electromotive force of the latter—"**negative phase of electrotonus.**"

3. **Equator.**—If two points of the nerve equidistant from the equator be placed on the electrodes (III), there is no deflection of the galvanometer needle (p. 605, 4). If a constant current be passed through one free projecting end of the nerve, then the galvanometer indicates an electromotive effect in the same direction as the constant current.

Electrotonus.—These experiments show that a constant current causes a change of the electromotive force of the part of the nerve directly traversed by the constant current, *i. e.*, in the intra-polar area, and also in the part of the nerve outside the electrodes, *i. e.*, in the extra-polar area. This condition is called *electrotonus* (*du Bois-Reymond*, 1843).

The electrotonic current is strongest not far from the electrodes, and it may be twenty-five times as strong as the nerve current of rest (§ 331, 5); it is greater on the anode than on the cathode side; it undergoes a negative variation like the resting nerve current during tetanus; it occurs at once on closing the constant current, although it diminishes uninterruptedly at the cathode (*du Bois-Reymond*). On the contrary, between the electrodes, besides the polarizing current itself, there is no obvious electrotonic increase of the current to be observed (*Hermann*). These phenomena take place only as long as the nerve is excitable. If the nerve be ligatured in the projecting part in the galvanometer circuit, the phenomena cease in the ligatured part. The above described galvanic electrotonic changes of the extra-polar part are absent in **non-medullated nerve fibres**, while, on the contrary, the physiological electrotonus is present. The physiological electrotonus of medullated nerves can be set aside by treating medullated nerves with ether, while the physical phenomena remain (*Biedermann*).

The negative variation (§ 332) occurs more rapidly than the electrotonic increase of the current, so that the former is over before the electromotive increase occurs. The **velocity** of the electrotonic change in the current is less than the rapidity of propagation of the excitement in the nerves—being only 8 to 10 metres per second (*Tschirjew, Bernstein*).

"**The secondary contraction from a nerve**" depends upon the electrotonic state. If the sciatic nerve of a frog's nerve-muscle preparation be placed on an excised nerve, and if a constant current be passed through the free end of the latter—non-electrical stimuli being inactive—the muscles contract. This occurs because the electrotonizing current in the excised nerve stimulates the nerve lying on it. By rapidly closing and opening the current, we obtain "*secondary tetanus from a nerve*" (p. 609).

[**Paradoxical Contraction.**—Exactly the same occurs when the current is applied to one of the two branches into which the sciatic nerve of the frog divides. The sciatic nerve of the frog divides at the lower end of the thigh into the *peroneal* and *tibial* branches. If the sciatic nerve be divided above, and the peroneal branch be also divided and stimulated with interrupted induction shocks, the muscles supplied by the tibial branch will contract. There is no contraction of the muscle if the peroneal nerve be ligatured.]

Polarizing After-Currents.—When the constant current is opened, there are **after-currents** depending upon internal polarization (§ 328). In *living* nerves, muscle, and electrical organs this internal polarization current, when a strong primary current of very short duration is used, is always *positive*, *i. e.*, has the same direction as the primary current. Prolonged duration of the primary current ultimately causes negative polarization. Between these two is a stage when there is no polarization. Positive polarization is especially strong in nerves when the primary current has the direction of the impulse in the nerve; in muscle, when the primary current is directed from the point of entrance of the nerve into the muscle toward the end of the muscle (§ 334, II).

4. **Muscle Current during Electrotonus.**—The constant current also produces an electrotonic condition in **muscle**; a constant current in the same direction increases the muscle current, while one in an opposite direction weakens it, but the action is relatively feeble.

[**Electrotonic Phenomena in Conductors.**—Matteucci found that a metallic wire surrounded by a moist conductor, when traversed by a galvanic current, exhibits currents possessing the properties of electrotonic currents of nerves. He also found that the currents ceased if the wire was of zinc and the envelope a saturated solution of zinc sulphate. This shows that these currents were due to polarization between the core and the fluid. Hermann finds that the currents only obtain when a polarizable core is present. A straw without joints, if filled with a saturated solution of common salt, or the tentacles of a lobster when moistened with saline solution, and traversed by a constant current, exhibit similar electrotonic currents (*Hering*).]

334. THEORIES OF MUSCLE AND NERVE CURRENTS.—I. Molecular or pre-existence Theory.—To explain the currents in muscle and nerve, du Bois-Reymond proposed the so-called molecular theory. According to this theory, a nerve or muscle fibre is composed of a series of small electromotive molecules arranged one behind the other, and surrounded by a conducting indifferent fluid. The molecules are supposed to have a positive equatorial zone directed toward the surface, and two negative polar surfaces directed toward the transverse section. Every fresh transverse section exposes new negative surfaces, and every artificial longitudinal section new positive areas.

This scheme explains the **strong** currents—when the + longitudinal surface is connected with the — transverse surface, a current is obtained from the former to the latter—but it does not explain the *feeble* currents. To explain their occurrence we must assume that, on the one hand, the electromotive force of the molecules is weakened with varying rapidity at unequal distances from the equator; on the other, at unequal distances from the transverse section. Then, of course, differences of electrical tension obtain between the stronger and the feebler molecules.

Parelectronomy.—But the *natural* transverse section of a muscle, *i. e.*, the end of the tendon, is not negative, but more or less positive electrically. To explain this condition, du Bois-Reymond assumes that on the end of the tendon there is a layer of electropositive muscle substance. He supposes that each of the peripolar elements of muscle consists of two bipolar elements, and that a layer of this *half* element lies at the end of the tendon, so that its positive side is turned toward the free surface of the tendon. This layer he calls the "**parelectronomic layer.**" It is never completely absent. Sometimes it is so marked as to make the end of the tendon + in relation to the surface. Cauterization destroys it. [It is supposed to be favored by cold.]

The negative variation is explained by supposing that, during the action of a muscle and nerve, the electromotive force of all the molecules is diminished. During partial contraction of a muscle, the contracted part assumes more the characters of an indifferent conductor, which now becomes connected with the negative zone of the passive contents of the muscular fibres.

The electrotonic currents beyond the electrodes in nerves must be explained. To explain the electrotonic condition, it is assumed that the bipolar molecules are capable of rotation. The polarizing current acts upon the direction of the molecules, so that they turn their negative surfaces toward the anode, and their positive surfaces to the cathode, whereby the molecules of the intra-polar region have the arrangement of a Volta's pile. In the part of the nerve outside the electrodes, the further removed it is, the less precisely are the molecules arranged. Hence, the swing of the needle is less, the further the extra-polar portion is from the electrodes.

II. Difference or Alteration Theory.—The difference theory was proposed by L. Hermann, and, according to him, the four following considerations are sufficient to explain the occurrence of the galvanic phenomena in living tissues: (1) Protoplasm, by undergoing partial *death* in its continuity, whether by injury or by (horny or mucous) metamorphosis, becomes negative toward the uninjured part. (2) Protoplasm, by being partially *excited* in its continuity, becomes negative to the uninjured part. (3) Protoplasm, when partially *heated* in its continuity, becomes positive, and by cooling negative, to the unchanged part. (4) Protoplasm is strongly *polarizable* on its surface (muscle, nerve), the polarization constants diminishing with excitement and in the process of dying.

Streamless Fresh Muscles.—It seems that passive, uninjured, and absolutely fresh nerves, and muscles, are completely devoid of a current, *e. g.*, the heart (*Engelmann*), also the musculature of fishes while still covered by the skin.

[According to Hermann, the currents obtained from muscle are due to injury of the muscle substance, whereby a difference of potential is set up, the injured part being negative to the uninjured. In fact, it is impossible to isolate a muscle without injuring it, owing to its connections. Frogs exhibit skin currents after the skin is destroyed; the muscles still exhibit currents, but Hermann explains this by the action of the irritant, used to destroy the skin, also affecting the muscle. In **fishes**, however, there are no skin currents, and if they be curarized, absolutely no current is obtained from their uninjured muscles (*Hermann*). The heart also when passive and uninjured gives no current, although it exhibits an action current when it contracts, and every injured part in it possesses a negative electrical potential with reference to the rest.]

L. Hermann also finds that the muscle current is always developed after a time, which is very short, when a new transverse section is made. [By means of his "**Fall-rheotom**," an arrangement whereby a weight, covered with shagreen, injured a muscle, and at the same time, closed and opened a galvanometer circuit, Hermann was able to show that the current—demarcation current—took a certain time to develop. Had it been prëexistent, as supposed by du Bois-Reymond, this ought not to have been the case.]

Demarcation Current.—Every **injury** of a muscle or nerve causes at the point of injury (*demarcation surface*) a dying substance, which behaves negatively to the positive intact substance. The current thus produced is called by Hermann the "*demarcation current*." If individual parts of a muscle be moistened with potash salts or muscle juice, they become negatively electrical; if these substances be removed these parts cease to be negative (*Biedermann*).

It appears that all living protoplasmic substance has a special property, whereby injury of a part of it makes it, **when dying, negative**, while the intact parts remain positively electrical. Thus, all transverse sections of living parts of plants are negative to their surface (*Buff*); and the same occurs in animal parts, *e. g.*, glands and bones. Engelmann made the remarkable observation that the heart and smooth muscle again lose the negative condition of their transverse section, when the muscle cells are completely dead, as far as the cement substance of the nearest cells; in nerves, when the divided portion dies, as far as the first node of Ranvier. When all these organs are again completely streamless, then the absolutely dead substance behaves essentially as an indifferent moist conductor. Muscles divided subcutaneously and healed do not exhibit a negative reaction of the surface of their section.

All these considerations go to show that *the prëexistence of a current in living, uninjured tissues can no longer be maintained.*

Theoretical.—Grünhagen and L. Hermann explain the **electrotonic currents** as being due to **internal polarization** in the nerve fibre between the conducting core of the nerve and the enclosing sheaths. Matteucci found that, when a wire is surrounded with a moist conductor, and the covering placed in connection with the electrodes of a constant current, currents similar to the electrotonic currents in nerves, and due to polarization, are developed. If either the wire or the moist covering be interrupted at any part, then the polarization current does not extend beyond the rupture (p. 612). The polarization developed on the surface of the wire by its transition resistance causes the conducted current to extend much beyond the electrodes.

Muscles and nerves consist of fibres surrounded by indifferent conductors. As soon as a constant current is closed on their surface, internal polarization is developed, which produces the electrotonic variation; it disappears again on opening or breaking the current. Polarization is detected by the fact that, in living nerve, the galvanic resistance to conduction across a fibre is about five times, and in muscles about seven times greater than in the longitudinal direction.

Action Currents.—The term "action current" is applied by L. Hermann to the currents obtained during the **activity of a muscle** or **nerve.** When a **single** stimulation wave (contraction) passes along muscular fibres, which are connected at two points with a galvanometer, then that point through which the wave is just passing is negative to the other. Occasionally, in excised muscles, local contractions occur, and these points are negative to the other passive parts of the muscle (*Biedermann*). In order, therefore, to explain the currents obtained from a frog's leg during **tetanus**, we must assume that the end of the fibre which is negative participates less in the excitement than the middle of the fibre. But this is the case only in dying or fatigued muscles.

According to § 336, D, the direct application of a constant current to a muscle causes contraction first at the cathode, when the current is closed, and when it is opened, at the anode. This is explained by assuming that, during the closing contraction, the muscle is negative at the cathode, while with the opening contraction the negative condition is at the anode.

If a **muscle** be thrown into contraction by stimulating its **nerve**, then the wave of excitement travels from the **entrance of the nerve** to both ends of the muscle, which also behave negatively to the passive parts of the muscle. According to the point at which the nerve enters the muscle, the ascending or descending wave of excitement will reach the end (origin or insertion) of the muscle sooner than the other. On placing such a muscle in the galvanometer circuit, then at first that end of the muscle will be negative which lies nearest to the point of entrance of the nerve (*e. g.*, the upper end of the gastrocnemius), and afterward the lower end. Thus, there appears rapidly after each other, at first a descending, and then an ascending, current in the galvanometer circuit, of course reversed within the muscle itself (*Sig. Mayer*) (§ 332, 4).

The same occurs in the muscles of the **human forearm.** When these were caused to contract through their **nerves**, at first the point of entrance of the nerve (10 cm. above the elbow joint) was negative, and then followed the ends of the muscles when the contraction wave, with a velocity of 10 to 13 metres per second, reached them (*L. Hermann*) (§ 399, 1).

If a completely uninjured, streamless muscle be made to contract *directly and in toto*, then neither during a single contraction, nor in tetanus, is there a current, because the whole of the muscle passes *at the same moment* into a condition of contraction.

Nerve Currents.—Hermann also supposes that the contents of dying or active nerves behave negatively to the passive normal portions.

Imbibition Currents.—When water flows through capillary spaces, this is accompanied by an electrical movement in the same direction (*Quincke, Zöllner*). Similarly, the forward movement of water in the capillary interspaces of non-living parts (pores of a porcelain plate) is also connected with electrical movements, which have the same direction as the current of water. The same effect occurs in the movement of water, which results in that condition known as *imbibition* of a body. We must remember, that at the demarcation surface of an injured nerve or muscle, imbibition takes place; that also at the contracted parts of a muscle imbibition of fluid occurs (§ 227, II); and that during secretion there is a movement of the fluid particles.

In **plants**, electrical phenomena have been observed during the *passive* bending of vegetable plants (leaves or stalks), as well as during the *active* movements which are associated with the bending of certain parts, *e.g.*, as in the mimosa and dionæa (*Burdon-Sanderson*). These phenomena are perhaps explicable by the movement of water which must take place in the interior of the vegetable parts (*A. G. Kunkel*). The root cap of a sprouting plant is negative to the seed coverings (*Hermann*); the cotyledons positive to the other parts of the seedling (*Müller-Hettlingen*). In the incubated hen's egg, the embryo is +, the yelk — (*Hermann and v. Gendre*).

335. ELECTROTONIC ALTERATION OF THE EXCITABILITY.—Cause of Electrotonus.—If a certain stretch of a living nerve be traversed by a **constant** electrical (*"polarizing"*) current, it passes into a condition of **altered excitability** (*Ritter*, 1802, and others), which du Bois-Reymond called the electrotonic condition, or simply *electrotonus*. This condition of altered excitability extends not only over the part actually traversed by the current, *intra-polar portion*, but it is communicated to the entire nerve, *i.e.*, to the extra-polar portions. Pflüger (1859) discovered the following laws of electrotonus:—

At the **positive** pole or *anode* (Fig. 408, *A*) the excitability is *diminished*—this is the region of **anelectrotonus**; at the **negative** pole or *cathode* (*K*) it is *increased*—this is the region of **cathelectrotonus.** The changes of excitability are most marked in the regions of the poles themselves.

Indifferent Point.—In the **intra-polar region** a point must exist where the anelectrotonic and cathelectrotonic regions meet, where therefore the excitability is unchanged; this is called the **indifference** or **neutral point**. This point lies nearer the anode (*i*) with a weak current, but with a strong current nearer the cathode ($i_{,,}$); hence, in the first case, almost the whole intra-polar portion is more excitable; in the latter, less excitable. [Expressed otherwise, a weak current increases the area over which the negative pole prevails, while the reverse is the case with a strong current. Or in the intra-polar region, the diminution of excitability extends as the strength of the current increases, or to put it otherwise, with an increasing strength of current, the indifferent point moves from the positive to the negative pole.] Very strong currents greatly diminish the conductivity at the anode, and indeed may make the nerve *completely incapable of conduction* at this part.

At the cathode also, but only after the polarizing current has passed for some time through the nerve (*Werigo*), the excitability is diminished, and the nerve in this area is rendered incapable of conduction (*Grünhagen*).

Extra-polar Region.—The extra-polar area, or that lying outside the electrodes, is greater, the stronger the current. Further, with the weakest currents, the extra-polar anelectrotonic area is greater than the extra-polar cathelectrotonic. With strong currents this relation is reversed.

Fig. 408 shows the excitability of a nerve (*N, n*) traversed by a constant current in the direction of the arrow. The curve shows the degree of increased excitability in the neighborhood of the cathode (*K*) as an elevation above the nerve, diminution at the anode (*A*) as a depression. The curve *m, o, $i_{,,}$, p, r*, shows the degree of excitability with a strong current; *e, f, $i_{,}$, h, k*, with a medium current; lastly, *a, b, i, c, d*, with a weak current.

The electrotonic effect increases with the length of the nerve traversed by the current. The changes of the excitability in electrotonus occur instantly when the circuit is closed, while anelectrotonus develops and extends more slowly. Cold diminishes electrotonus (*Hermann and v. Gendre*).

When the polarizing current is opened or broken, at first there is a **reversal** of the relations of the excitability, and then there follows a transition to the normal

FIG. 408.



Scheme of the electrotonic excitability.

condition of excitability of the passive nerve (*Pflüger*). At the very first moment of closing, Wundt observed that the excitability of the whole nerve was increased.

I. Proof of Electrotonus in Motor Nerves.—To test the laws of electrotonus, take a frog's nerve-muscle preparation (Fig. 401). A constant current (p. 592) is applied to a limited part of the nerve by means of non-polarizable electrodes. A stimulus, electrical, chemical (saturated solution of common salt), or mechanical, is applied either in the region of the anode or cathode; and we observe whether the contraction which results is greater when the polarizing current is opened or closed. We shall consider the following cases (Fig. 409).

FIG. 409.



Method of testing the excitability in electrotonus. R, r, R_1, r_1, where the common salt (stimulus) is applied.

(a) **Descending extra-polar anelectrotonus.** With a descending current we have to test the excitability of the extra-polar region at the anode. If the stimulus (common salt) applied at R (while the circuit was open) causes in this case (A) moderately strong contractions in the limb, then these at once become *weaker*, or *disappear* as soon as the constant current is transmitted through the nerve. After the circuit is opened, the contractions produced by the salt again occur of the original strength.

(b) **Descending extra-polar cathelectrotonus** (A). The stimulus (salt) is at R_1, and the contractions thereby produced are at once *increased* after closing the polarizing current. On opening it they are again weakened.

(c) **Ascending extra-polar anelectrotonus** (B). The salt lies at r_1; the moderately strong contractions excited by the salt before the current is made, become feebler after the current is made.

(d) **Ascending extra-polar cathelectrotonus** (B). The salt lies at *r*. In this case we must distinguish according to the *strength* of the polarizing current: (1) When the current is *very weak*, which can be obtained with the aid of the rheocord (Fig. 379), on closing the polarizing current, there is an *increase* of the contraction produced by salt. (2) If, however, the current is *stronger*, the contractions become either smaller or cease. This is due to the fact that with strong currents the conductivity of the nodes is diminished or even abolished (p. 615). Although the salt acts on the excitable nerve, there is no contraction of the muscle, as the conduction of an impulse is prevented by the resistance in the nerve.

The **law of electrotonus** may also be **demonstrated** on a **completely isolated nerve.** The end of the nerve is properly disposed upon electrodes connected with a galvanometer, so as to obtain a *strong* current. If the nerve, when the constant current is closed, is stimulated in the anelectrotonic area, *e.g.*, by an induction shock, then the *negative variation is weaker* than when the polarizing circuit was open. Conversely, it is stronger when it is stimulated in the cathelectrotonic area. The currents from the extra-polar areas of a nerve in a condition of electrotonus, exhibit the negative variation when the nerve is stimulated (*Bernstein*).

[Tigerstedt, instead of employing an electrical or chemical stimulus to excite the electrotonic nerve, used an apparatus like Heidenhain's tetanometer, whereby the nerve was beaten gently with a small ivory hammer. He fully confirms Pflüger's results.]

Proof in Man.—In performing this experiment it is important to remember the distribution of the current in the body. If both electrodes, for example, be placed over the course of the ulnar nerve (Fig. 410), the currents entering the nerve at the anode (+ *a a*) must diminish the excitability; only above and below the anode (at *c c*) the positive current emerges from the nerve and excites cathelectrotonus at these points. Similarly, where the cathode is applied (— *c c*) there is increased excitability, but in higher and lower parts of the nerve, where (at *a a*) the positive current (coming from +) enters the nerve, the excitability is diminished (anelectrotonus) (*v. Helmholtz, Erb*). If we desire to stimulate in the neighborhood of an electrode, then we cannot act upon that part of the nerve whose excitability is influenced by the electrode. In order, therefore, to stimulate *directly* the same point on which the electrode acts, it is necessary to apply the stimulus at the same time by the electrode itself, *e.g.*, either mechanically or by conducting the stimulating current through the polarizing current (*Waller and de Watteville*).

II. Proof of Electrotonus in Sensory Nerves.—Isolate the sciatic nerve of a decapitated frog. When this nerve is stimulated in its course with a saturated solution of common salt, *reflex movements* are excited in the other leg, the spinal cord being intact. These disappear as soon as a constant current is applied to the nerve, provided the salt lies in the anelectrotonic area (*Pflüger and Zurhelle, Hallstén*).

III. Proof of Electrotonus in Inhibitory Nerves.—To show this, proceed thus: On causing dyspnœa in a rabbit, the number of heart beats is diminished, owing to the action of the dyspnœic blood on the cardio-inhibitory centre in the medulla oblongata. If, after dividing the vagus on one

FIG. 410.



Scheme of the distribution of an electrical current in the nerve on galvanizing the ulnar nerve.

side, a constant descending current be passed through the other intact vagus, the number of pulse beats is again decreased (descending extra-polar anelectrotonus). If, however, the current through the nerve be an ascending one, then with *weak* currents the number of heart beats increases still more (ascending extra-polar cathelectrotonus). Hence, the action of inhibitory nerves in electrotonus is the opposite of that in motor nerves.

During the electrotonus of **muscle**, the excitability of the *intra-polar* portion is altered. The delay in the conduction is confined to this area alone (*v. Bezold*)—compare § 337, 1.

336. ELECTROTONUS—LAW OF CONTRACTION.—Opening and Closing Shocks.—A nerve is stimulated both at the moment of the occurrence and that of disappearance of electrotonus (*i. e.*, by closing and opening the current—*Ritter*): (1) When the current is **closed**, the stimulation occurs only at the **cathode**, *i. e.*, at the moment when the electrotonus takes place. (2) When the current is **opened**, stimulation occurs only at the **anode**, *i. e.*, at the moment when the electrotonus disappears. [This is Pflüger's well-known principle—"*A given tract of nerve is stimulated by the appearance of cathelectrotonus and the disappearance of anelectrotonus—not, however, by the disappearance of cathelectrotonus nor by the appearance of anelectrotonus.*" From this principle can be deduced the

law of contraction.] (3) The stimulation at the occurrence of cathelectrotonus is stronger than that at the disappearance of anelectrotonus (*Pflüger*).

Ritter's Opening Tetanus.—That stimulation occurs only at the anode, when the current is opened, was proved by Pflüger by means of "Ritter's opening tetanus." Ritter's tetanus consists in this, that when a constant current is passed for a long time through a long stretch of nerve, on opening the current, tetanus lasting for a considerable time results. If the current was a descending one, then this tetanus ceases at once after section of the intra-polar area, a proof that the tetanus resulted from the now separated anode. If the current was an ascending one, section of the nerve has no effect on the tetanus.

Pflüger and v. Bezold found a further proof *that the closing or make contraction proceeds from the cathode, and the opening or break contraction from the anode*, by showing that with a **descending** current, the closing contraction in the muscle, at the moment of closing occurred *earlier*, while the opening contraction at the moment of opening occurred *later*; and, conversely, with an **ascending** current the closing contraction occurred later, and the opening contraction sooner. The difference in time corresponds to the time required for the propagation of the pulse in the intra-polar region (§ 337). If a large part of the intra-polar region in a frog's nerve be rendered inexcitable by applying ammonia to it, then only the electrode next the muscle stimulates, *i. e.*, always on closing or making a descending current and on opening or breaking an ascending one (*Biedermann*).

A. The law of contraction is valid for all kinds of nerves—**I.** The contraction occurring at the closing or opening of a constant current varies with (*a*) the **direction** (*Pfaff*), and (*b*) the **strength** of the current (*Heidenhain*).

(1) **Very feeble** currents, in conformity with the third of the above statements, cause only a **closing contraction**, both with an ascending and a descending current. The disappearance of electrotonus is so feeble a stimulus as not to excite the nerve.

(2) **Medium** currents cause opening or closing contractions both with an ascending and descending current.

(3) **Very strong** currents cause only a *closing contraction* with a *descending* current; the opening shock does not occur, because, with very strong currents, almost the whole of the intra-polar portion of the electrotonic nerve is incapable of conducting an impulse (p. 615). *Ascending* currents cause only an *opening contraction* for the same reason. With a certain strength of current, the muscle remains tetanic while the current is closed ("*closing tetanus*").

[The *law of contraction* is formulated: R = rest; C = contraction.]

Strength of Current.	Ascending.		Descending.	
	On Closing.	On Opening.	On Closing.	On Opening.
Weak, ...	C	R	C	R
Medium, ...	C	C	C	C
Strong, ...	R	C	C	R

II. In a **dying** nerve, losing its excitability, according to the Ritter-Valli law (§ 325, 7), the law of contraction is modified. In the stage of increased excitability, *weak* currents cause only closing contractions with both directions of the current. In the following stage, when the excitability begins to diminish, weak currents cause opening and closing contractions with both currents. Lastly, when the excitability is very greatly diminished, the descending current is followed only by a closing contraction, and the ascending by an opening contraction (*Ritter*, 1829).

III. As the various changes in excitability occur in a centrifugal direction along the nerve, we may detect the various stages simultaneously at different parts along the course of the nerve. According to Valentin and Fick, the living intact nerve shows only a closing contraction with both directions of the current, and opening contractions only with very strong currents.

Fleischl's Law of Contraction.—v. Fleischl and Stricker have stated a different law, in respect to the fact, that the excitability varies at certain points in the course of a nerve. The sciatic nerve is divided into three areas: (1) Stretches from the muscle to the place where the branches for

the thigh muscles are given off; (2) from here to the intervertebral ganglion; (3) from here into the spinal cord. Each of these three areas consists of two parts ("upper and lower pole"), which adjoin each other at an equator. In each upper pole, the excitability of the nerve is greater for descending currents, and in each lower pole for ascending ones. At each equator the excitability of the nerve is the same for ascending and descending currents. The difference in the activity, due to the direction of the current, is greater for each stretch of nerve the greater this stretch is distant from the equator. The excitability is less at those points of the nerve where the three areas join each other.

Eckhard observed that, on opening an ascending medium current applied to the hypoglossal nerve of a rabbit, one-half of the tongue exhibited a *trembling* movement instead of a contraction, while on closing a descending current, the same result occurred (§ 297, 3). According to Pflüger, the molecules of the passive nerve are in a certain state of medium mobility. In cathelectrotonus the mobility of the molecules is increased, in anelectrotonus diminished.

B. The law for inhibitory nerves is similar. Moleschott, v. Bezold, and Donders have found similar results for the vagus, with this difference, that, instead of the contraction of a muscle, there is inhibition of the heart.

C. For sensory nerves also the result is the same, but we must remember that the perceptive organ lies at the central end of the nerve, while in a motor nerve it is at the periphery (muscle). Pflüger studied the effect of closing and opening a current on sensory nerves by observing the **reflex movement** which resulted. *Weak* currents cause only closing contractions; *medium* currents both opening and closing contractions; *strong* descending currents only opening contractions; and ascending only closing contractions. *Weak* currents applied to the human *skin* cause a sensation with both directions of the current only at closing; *strong descending* currents a sensation only at *opening*; strong *ascending* currents a sensation only at closing (*Marianini*, *Matteucci*). When the current is closed, there is prickly feeling, which increases with the strength of the current (*Volta*). Analogous phenomena have been observed in the **sense organs** (sensations of light and sound by Volta and Ritter).

D. In **muscle**, the law of contraction is proved thus: by fixing one end of the muscle, keeping it tense, so that it cannot shorten, and opening and closing the current at this end. The end of the muscle which is free to move, shows the same law of contraction as if the motor nerve were stimulated (*v. Bezold*). On closing the current, the contraction begins at the cathode; on opening, at the anode (*Engelmann*). E. Hering and Biedermann showed more clearly that both the closing and opening contractions are purely polar effects; when a *weak* current applied to a muscle is *closed*, the first effect is a small contraction limited to the cathodic surface of the muscle. Increase of the current causes increased contraction which extends to the anode, but which is weaker there than at the cathode; at the same time, the muscle *remains contracted* during the time the current is closed. On *opening*, the contraction begins at the anode; even after opening, the muscle for a time may remain contracted, which ceases on closing the current in the same direction.

By killing the end of a muscle in various ways, the excitability is diminished near this part. Hence, at such a place the polar action is feeble (*van Loon and Engelmann*, *Biedermann*). Touching a part with extract of flesh, potash, or alcohol diminishes locally the polar action, while soda salts and veratrin increase it (*Biedermann*).

Closing Continued Contraction.—The moderate continued contraction, which is sometimes observed in a muscle while the current is closed (Fig. 329, O), depends upon the abnormal prolongation of the closing contraction at the cathode when a strong stimulus is used, or during the stage of dying, or in cooled winter frogs; sometimes the opening of the current is accompanied by a similar contraction proceeding from the anode *Biedermann*). This tetanus is also due to the summation of a series of simple contractions (§ 298, III). By acting on a muscle with a 2 per cent. saline solution containing sodic carbonate, the duration of the contraction is increased considerably, and occasionally the muscle shortens rhythmically (§ 296) (*Biedermann*).

If the whole muscle is placed in the circuit, the closing contraction is strongest with both directions of the current; during the time the current is closed, a continued contraction is strongest when the current is ascending (*Wundt*).

Inhibitory Action.—The constant current, when applied to a muscle in a condition of continued and sustained contraction, has exactly the opposite effect

to that on a relaxed muscle. If a constant current be applied by means of non-polarizable electrodes to a muscle in a state of continued contraction, *e. g.*, after poisoning with veratrin or through the contracted ventricle, when the current is closed, there is a **relaxation** beginning at the anode and extending to the other parts; on opening the current applied to muscle in continued contraction, the relaxation procedes from the cathode.

Corresponding to this remarkable phenomenon, Biedermann found as regards the currents in the muscle substance following the ordinary law, that every contracted part is negative to every passive section of the muscle. Perhaps the experiment of Pawlow, who found nerve fibres in the adductor muscle of the mussel, whose stimulation caused relaxation of the muscular contraction, may throw some light on this question.

Ritter's Opening Tetanus.—If a nerve or muscle be traversed by a constant current for some time, we often obtain a prolonged *tetanus*, after opening the current (Ritter's opening tetanus, 1798). It is set aside by closing the original current, while closing a current in the opposite direction increases it ("**Volta's alternative**"). The continued passage of the current increases the excitability for the opening of the current in the same direction, and for the closing of the reverse current; conversely, it diminishes it for the closing of the current in the same direction, and for the opening of the reverse current (*Volta*).

According to Grützner and Tigerstedt, the cause of the opening contraction is partly due to the occurrence of polarizing after currents (§ 333), and according to Hermann to a diminution of the anodic positive polarization.

Engelmann and Grünhagen explain the occurrence of opening and closing tetanus, thus, as due to latent stimulations, drying, variations of the temperature of the prepared nerve, which of themselves are too feeble to cause tetanus, but which become effective if an increased excitability obtains at the cathode after closure, and at the anode after opening the current.

Biedermann showed that, under certain conditions, two successive opening contractions can be obtained in a frog's nerve-muscle preparation, the second and later one corresponding to Ritter's tetanus. The first of these contractions is due to the disappearance of anelectrotonus in Pflüger's sense; the second is explained, like Ritter's opening tetanus, in Engelmann and Grünhagen's sense.

Simultaneous action of the constant current and the nerve current.—Action of two currents. In a nerve-muscle preparation used to prove the law of contraction, of course a demarcation current is developed in the nerve (§ 334, II). If an artificial weak stimulating current be applied to such a nerve, we obtain an inteference effect due to these two currents; closing a weak constant current causes a contraction, which, however, is not properly a closing contraction, but depends upon the opening (or derivation) of a branch of the demarcation current; conversely, the opening of a weak constant current may excite a contraction, which is really due to the closing of a side branch of the nerve current, in a secondary circuit through the electrodes (*Hering, Biedermann, Grützner*).

If two induction shocks be simultaneously applied to a motor nerve, two cases are possible. Either the one shock is so feeble that the nerve is not thereby sufficiently excited to cause a contraction, while the other shock causes only a feeble contraction. In this case, the sub-maximal shock plays the part of a weak constant current, and the size of the contraction depends only upon whether the effective stimulus was applied in the area of the anode or the cathode of the sub-maximal shock (*Sewall, Grünhagen, Werigo*). If, however, unequal, strong induction shocks, each of which is effective—but separated from each other on account of the electrotonic action—be applied to a nerve, then the result is as if the stronger alone was active. The feebler wave of excitation passes completely into the stronger one (*Grünhagen, Werigo*).

337. **TRANSMISSION OF NERVOUS IMPULSES.**—1. If a **motor** nerve be stimulated at its central end (1) **a condition of excitation** is set up, and (2) an **impulse** is transmitted along the nerve to the muscle with a certain velocity. The latter depends on the former and represents the function of **conductivity.** The velocity is about 27¼ metres [about 90 feet] per second (*v. Helmholtz*), and for the human motor nerves 33.9 [100 to 120 feet per second] (*v. Helmholtz and Baxt*).

The velocity is less in the **visceral nerves**, *e.g.*, in the pharyngeal branches of the vagus 8.2 metres [26 feet] (*Chauveau*); in the motor nerves of the lobster 6 metres [18 feet] (*Frédéricq and van de Velde*).

Modifying Conditions.—The velocity is influenced by various conditions: *Temperature.*—It is **lessened** considerably by cold (*v. Helmholtz*), but both high

and low temperatures of the nerve (above or below 15° to 25° C.) lessen it (*Steiner and Trojtzky*); also *curara*, the *electrotonic condition* (*v. Bezold*); or only anelectrotonus, while cathelectrotonus increases it (*Rutherford, Wundt*). It varies also with the length of the conducting nerve, but it increases with the strength of the stimulus (*v. Helmholtz and Baxt*), although not at first (*v. Vintschgau*).

Methods.—1. v. Helmholtz (1850) estimated the velocity of the nerve impulse in a frog's motor nerve after the method of Pouillet. The method depends upon the fact that the needle of a galvanometer is deflected by a current of very short duration, the extent of the deflection being proportional to the duration and strength of the current. The apparatus is so arranged that the "time-marking current" is closed at the moment the nerve is stimulated, and opened again when the muscle contracts. If the nerve attached to a muscle be now stimulated at the further point from the muscle, and a second time near its entrance to the muscle, then in the latter case the time between the application of the stimulus and the beginning of the contraction of the muscle, *i. e.*, the deflection of the galvanometer, will be less than in the former case, as the impulse has to traverse the whole length of the nerve to reach the muscle. The difference between the two times is the time required by the impulse to traverse a given distance of nerve. Fig. 411 shows in a diagrammatic manner the arrangement of the experiment. The *galvanometer*, G, is placed in the time-marking circuit (open at first), *a*, *b* (element), *c* (piece of platinum on a key, W), introduced into the time-marking circuit, *d*, *e*, *f*, *h*. The circuit is made by closing the key, S, when *d* depresses the platinum plate of the key, W. *At once* when the current is closed, the magnetic needle is deflected, and its extent noted. At the same moment in which the current between *c* and *d* is closed, the primary circuit of the *induction machine* is opened, the circuit being *i*, *k*, *l* (element), *m*, O (primary spiral), *p*. Thereby an *opening shock* is induced in the secondary spiral, R, which stimulates the nerve of the frog's leg at *n*. Thus, the closing of the galvanometer circuit exactly coincides with the stimulation of the nerve. The impulse is propagated through the nerve to the muscle, M, and the latter contracts when the impulse reaches it, at the same time opening the time-measuring circuit at the double contact, *e* and *f*, by raising the lever, H, which rotates on *x*. At the moment of opening, the further deflection of the magnetic needle ceases. The contact at *f* is made by a pointed cupola of mercury. When the lever, H, falls after the contact of the muscle, so that the point, *e*, comes into contact with the underlying *solid* plate, *y*, the contact at *f* still remains open, *i. e.*, through the galvanometer circuit. If the nerve be stimulated with the opening shock, first at *n*, and then at N, the deflection of the needle

FIG. 411.



v. Helmholtz's method of estimating the velocity of a nerve pulse.

FIG. 412.



Scheme for measuring the velocity of nerve energy. *f*, clamp for femur; *m*, muscle; N, nerve; *a*, near, *b*, removed from, C, commutator; II, secondary; I, primary spiral of induction machine; B, battery; 1, 2, key; 3, tooth on the smoked plate, P.

is greater in the former than in the latter case. From the difference we calculate the *time* for the conduction of the impulse in the stretch of the nerve between *n* and N.

[2. A simpler method is that shown in the scheme, Fig. 412. Use a pendulum or **spring myograph** (Fig. 323), and suspend in a suitable manner a frog's gastrocnemius (*m*), with a long portion of the sciatic nerve (N) dissected out, by fixing the femur in a clamp (*f*), while the tendo-Achilles is fixed to a lever, which inscribes its movements on the smoked glass plate (P) of the myograph; place the **key** of the myograph (2) in the circuit with the battery (B), and the primary circuit of the induction machine (I). To the secondary coil (II) attach two wires, and connect them with a **commutator** *without cross bars* (C). Connect the other binding screws of the commutator with two pairs of wires, arranged so that one pair can stimulate the nerve near the muscle (*a*), and the other at a distance from it (*b*). When the glass plate flies from one side to the other, the tooth (3) on its framework opens the key (2) in the primary circuit; and if the commutator be in the position indicated, then the induced current will stimulate the nerve at *a*, and a curve will be obtained on the glass plate. Rearrange the pendulum as before, but turn the handle of the commutator, and allow the glass plate to fly again. This time the induced current will stimulate the nerve at *b*, and a second contraction, a *little later* than the first one, will be obtained. Register the velocity of the glass plate by means of a tuning fork, and the curve obtained will be something like Fig. 413, although this curve was obtained on a cylinder traveling at a uniform

FIG. 413.



1, curve obtained on stimulating a nerve (man) near the muscle; 2, when the stimulus was applied to the nerve at a distance from the muscle; D, vibrations of a tuning fork (250 per second).

rate. The difference between the beginning of the *a* and *b* curves indicates the time that the nerve impulse took to travel from *b* to *a*. This time is measured by the tuning fork, and if the distance between the points *a* and *b* is known, then the calculation is a simple one. Suppose the stretch of nerve between *a* and *b* to be 2 inches, and the time required by the impulse to travel from *a* to *b* to be $\frac{1}{480}$ second, then we have the simple calculation—2 inches : 12 inches :: $\frac{1}{480}''$: $\frac{1}{80}''$, or 80 feet per second. In Fig. 413 the experiment was made on **man**; the curve 1 was obtained by stimulating the nerve near the muscle, and 2 when the nerve was stimulated at a distance of 30 centimetres. The interval between the vertical lines corresponds to $\frac{1}{100}$ second, *i. e.*, the time required by the nerve impulse to pass along 30 centimetres of nerve, which is equal to a velocity of 30 metres (90 feet) per second.]

In man, v. Helmholtz and Baxt estimated the velocity of the impulse in the *median nerve* by causing the muscles of the ball of the thumb to write off their contractions on a rapidly revolving cylinder. [In this case the "pince myographique" of Marey may be used (§ 708). The ends of the pince are applied so as to embrace the ball of the thumb, so that when the muscles contract, the increase in *thickness* of the muscles expands the pince, which acts on a Marey's tambour, by which the movement is transmitted to another tambour provided with a writing style, and inscribing its movements upon a rapidly moving surface, either rotatory or swinging.] The nerve is stimulated at one time in the axilla and again at the wrist. Two curves are obtained, which, of course, do not begin at the same time. The difference in time between the beginning of the two curves is the time

taken by the impulse to traverse the above-mentioned length of nerve. [The time is easily ascertained by causing a tuning fork of a known rate of vibration to write its movements under the curves.]

3. In the **sensory nerves** of man, the velocity of the impulse is probably about the same as in motor nerves. The rates given vary between 94 to 30 metres [280 to 90 feet] per second (*v. Helmholtz*).

Method.—Two points are chosen as far apart as possible, and at unequal distances from the brain, and they are successively excited by a momentary stimulus, *e. g.*, an opening induction shock applied successively to the tip of the ear and the great toe. The moment of the application of the stimulus is indicated on the registering surface. The person experimented on is provided with a key attached to an electric arrangement, by which he can mark on the registering surface the moment he feels the sensation in each case.

Reaction Time.—The time which elapses between the application of the stimulus and the reaction is called the "*reaction time.*" It is made up of the time necessary for conduction in the sensory nerve, that for the process of perception in the brain, for the conduction in the motor nerves to the muscles, by which the signs on the registering surface were made, and lastly by the latent period (p. 528). The reaction time is usually about 0.125 to 0.2 second (§ 374).

Pathological.—The conduction in the cutaneous nerves is sometimes greatly *delayed*, in alterations of the cutaneous sensibility, in certain diseases of the spinal cord (§ 364). The *sensation* itself may be unchanged. Sometimes only the conduction for painful impressions is retarded, so that a painful impression on the skin is first perceived as a tactile sensation, and afterward as pain, or conversely. When the interval of time between these two sensations is long, then there is a distinctly *double* sensation (*Naunyn*). It is rarely that voluntary movements are executed much more slowly from causes depending on the *motor* nerves, but occasionally the time between the voluntary impulse and the contraction is lengthened, but there may be in addition slower or longer continued contraction of the muscle. In tabes dorsalis or locomotor ataxia, the discharge of *reflex movements* is delayed; it is slower with thermal stimuli (60°) than with cold ones (0.52° C., *Ewald*).

338. DOUBLE CONDUCTION IN NERVES.—Conductivity is that property of a living nerve in virtue of which, on the application of a stimulus, it transmits an *impulse*. [The *nature* of a nerve impulse is entirely unknown; we may conveniently term the process **nerve motion**, but there is some reason to believe that nerve energy is transmitted by some sort of molecular vibration.] The conductivity is *destroyed* by all influences or conditions which injure the nerve in its *continuity* (section, ligature, compression, destruction by chemical agents); or which abolish the *excitability* at any part of its course (absolute deprival of blood; certain poisons, *e. g.*, curara for motor nerves; also strong anelectrotonus, § 335).

Law of Isolated Conduction.—Conduction always takes place only in the continuity of fibres, the impulse never being transferred to adjoining nerve fibres.

Double Conduction.—Although apparently conduction in motor nerves takes place only in a *centrifugal* direction toward the muscles, and in sensory nerves in a *centripetal* direction, *i. e.*, toward the centre; nevertheless, experiment has proved that a nerve conducts an impulse in *both* directions, just as in a non-living conductor. If a pure motor or sensory nerve be stimulated in its course, an impulse is propagated at the same time in a centrifugal and in a centripetal direction. This is the phenomenon of "*double conduction.*"

Proofs.—1. If a nerve be stimulated, its **electro-motive properties** are affected both above and below the point of stimulation (see *Negative Variation in Nerves*, § 332).

2. **Electrical Nerves.**—If the posterior free end of the electrical centrifugal nerves of the malapterurus be stimulated, the branches given off above the point of stimulation are also excited, so that the whole electrical organ discharges its electricity (*Babuchin, Mantey*).

3. **Kühne's Experiments.**—The **sartorius** of the frog has no nerve fibres at its upper and lower ends. If the lower end be cut off, and if the lower third of the muscle be suspended and divided vertically, on stimulating mechanically one apex of the muscle, then the impulse passes in the motor nerves centripetally to the place where the nerve fibre bifurcates in the muscle, and from thence centrifugally into the other or non-stimulated apex, and causes it to contract.

[The **Gracilis** of the frog is divided into a larger and smaller portion (L) by a tendinous inscription (K) running across it (Fig. 414). The nerve (N) enters at the hilum in the larger portion, bifurcates, and gives a branch (*k*) to the smaller portion and another to the larger portion of the muscle. Let the muscle be cut as shown in Fig. 414, avoiding injury to the nerves, so that only the nerve twig (*k*) connects the larger and smaller portions of the muscle. If the tongue or tip of muscle (Z) with its nerves be stimulated, contraction occurs both in L and M, which is due to centripetal conduction in the motor nerve. The nerve fibres divide dichotomously above where the nerves are given off to the portions L and M.]

FIG. 414.



Kühne's Gracilis experiment.

[If the inscription be left, and the lower tip of the muscle (which is devoid of nerves) be stimulated, only the lower and not the upper part twitches; but if a part of the muscle containing nerves common to both parts be stimulated, then both parts of the muscle contract. This also proves that pure muscular excitation does not travel backward from the muscle to the nerves. How this comes about, we are entirely ignorant.]

The following experiments used to be cited as proofs, but they do not stand the test of criticism.

4. **Union of Motor and Sensory Nerves.**—If the hypoglossal and lingual nerves be divided in a dog, and if the peripheral end of the hypoglossal be stitched, so as to unite with the central end of the lingual (*Bidder*), then, several months after the union and restitution of the nerves, stimulation of the central end of the lingual causes contraction in the corresponding half of the tongue. Hence, it has been assumed that the lingual, which is the *sensory* nerve of the tongue, must conduct the impulse in a peripheral direction to the end of the hypoglossal. This experiment is not conclusive, as the trunk of the lingual receives high up the centrifugal fibres from the seventh, viz., the chorda tympani, which may unite with those of the hypoglossal. Further, if the chorda be divided and allowed to degenerate before the above described experiment is made, then no contractions occur on stimulating the lingual above the point of union (§ 349).

FIG. 415. FIG. 416. FIG. 417.

Double sponge rheophore. Disk rheophore. Metallic brush.

5. **Bert's Experiment.** — Paul Bert removed the skin from the tip of the *tail of a rat*, and stitched it into the skin of the back of the animal, where it united with the tissues. After the first union had taken place, the tail was then divided at its base, so that the tail, as it were, grew out of the skin on the back of the animal. On stimulating the tail, the animal exhibited signs of sensation. For the explanation of this experiment, see § 325.

339. **ELECTRO-THERAPEUTICS—REACTION OF DEGENERATION.**—Electricity is frequently employed for therapeutical purposes, the rapidly interrupted current of the induction machine, or *Faradic current*, being frequently used (especially since Duchenne, 1847), the *magneto-electrical* apparatus, and the *extra-current* apparatus. The *constant* or galvanic current is also used, especially since Remak's time, 1855 (§ 330).

1. **In paralysis,** *Faradic* currents are applied, either to the muscles themselves (*Duchenne*), or

the points of entrance of the motor nerves, by means of suitable electrodes, or rheophores covered with sponge, etc., and moistened (*v. Ziemssen*).

[**Rheophores.**—Many different forms are used, according to the organ or part to be stimulated,

FIG. 418.



Motor points of the radial nerve and the muscles supplied by it; dorsal surface.

FIG. 419.



Motor points of the median and ulnar nerves, with the muscles supplied by them.

or the effect desired. When electricity is applied to the skin to remove anæsthesia, hyperæsthesia, or altered sensibility, and we desire to limit the effect to the skin alone, then the rheophores are applied dry, and are usually made of metal. If, however, deeper-seated structures, as muscles or

nerve trunks, are to be affected, the skin must be well **moistened** and softened by sponging with warm water, while the rheophores are fitted with sponges moistened with common salt and water, which diminishes the resistance of the skin to the passage of electricity (Figs. 415–417).]

In faradizing the paralyzed muscle, the object is to cause artificial movements in it, and thus prevent the degeneration which it would otherwise undergo, merely from inaction. If, in addition to the motor nerves, its *trophic* nerves are also paralyzed, then a muscle atrophies, notwithstanding the faradization (§ 325, 4). The use of the induced current also improves a paralyzed muscle, as it increases the **blood stream** through it, while it affects the **metabolism** of the muscle reflexly. In addition, weak currents may restore the excitability of enfeebled nerves (*v. Bezold, Engelmann*).

The Figs. 418, 419, 420, 421 indicate the positions of the motor points of the extremities, where,

FIG. 420.



Motor points of the peroneal and tibial nerves on the front of the leg; the peroneal on the left, the tibial on the right (after *Eichhorst*).

by stimulating at the entrance of the nerve, each muscle may be caused to contract singly. In § 349 the motor points of the face, and in § 347 those of the neck, are indicated.

The **constant current** may be employed as a stimulus, when it is closed and opened, in the form of an *interrupted* current, by altering its direction and increasing or diminishing its intensity, but it also causes a *polar action*. On *closing* the current, the nerve at the *cathode* is stimulated; similarly, on *opening* the current, at the *anode* (§ 336). Thus, when the current is closed, the excitability of the nerve is increased at the cathode (§335), which may act favorably upon the nerve. Increased excitability in electrotonus at the anode, although feebler, has been observed during percutaneous galvanization in man. This is especially the case by repeatedly reversing the current, sometimes also by opening and closing, or even with a uniform current. If the increase of the excitability is

obtained, then the direction of the current increases the excitability on closing the reverse current, and on opening the one in the same direction.

Restorative Effect.—Further, in using the constant current, we have to consider its restorative effects, especially when it is *ascending*. R. Heidenhain found that feeble and fatigued muscles recover after the passage of a constant current through them.

Lastly, the constant current may be useful from its **catalytic** or **cataphoric** action (§ 328). The effect is directly upon the tissue elements. It may also act directly or reflexly upon the blood and lymph vessels.

Faradization in Paralysis.—If the primary cause of the paralysis is in the muscles themselves, then the *induced* current is generally applied directly to the muscles themselves by means of sponge electrodes (Fig. 415); while, if the motor nerves are the primary seat, then the electrodes are applied over them. The current used must be only of *very moderate* strength; strong tetanic contractions are injurious, and so is too prolonged application (*Eulenburg*).

FIG. 421.



Motor points of the sciatic nerve and its branches; the peroneal and tibial nerves.

The galvanic current may also be applied to the muscles or to their motor nerves, or to the centres of the latter, or to both muscle and nerve simultaneously. As a rule, the *cathode* is placed *nearer the centre*, as it increases the excitability. When the electrode is moved along the course of the nerve, or when the strength of the current is varied, the action is favored. If the seat of the lesion is in the central nervous system, then the electrodes are applied along the vertebral column, or on the vertebral column and the course of the nerves at the same time, or one on the head and the other on a point as near as possible to the supposed seat of the lesion. The current must not be too strong nor applied too long.

Induced *v.* Constant Current: Reaction of Degeneration.—Paralyzed nerves and muscles behave quite differently as regards the *induced* (rapidly interrupted) and the *constant* current. This is called the "**reaction of degeneration.**" We must remember the physiological fact that a *dying* nerve attached to a muscle (§ 325), and also the muscles of a curarized animal, react much less strongly to rapidly interrupted currents than fresh non-curarized muscles. Baierlacher, in 1859,

found that, in a case of facial paralysis, the facial muscles contracted but feebly to the induced current, but very energetically on the constant current being used. The excitability for the constant current may be abnormally increased, but may disappear on recovery taking place. According to Neumann, it is the longer duration of the constant current as opposed to the momentary closing and opening of the induced current which makes the contraction of the muscle possible. If the constant current be broken as rapidly as the Faradic current is broken, then the constant current does not cause contraction. Conversely, the induced current may be rendered effective by causing it to last longer. We may also keep the primary circuit of the induction machine closed, and move the secondary spiral to and fro along the slots. Thus we obtain slow gradations of the induced current which act energetically upon curarized muscles (*Brücke*). Hence, in stimulating a muscle or nerve, we have to consider not only the **strength**, but also the **duration**, of the current, just as the deflection of the magnetic needle depends upon these two factors.

[**Galvanic excitability** is the term applied to the condition of a nerve or muscle, whereby it responds to the opening or closing of a continuous current. The effects differ according as the current is opened or closed, and according to its strength. As a rule, the cathode causes a contraction chiefly at closure, the anode at opening the current, while the cathode is the stronger stimulus. With a *weak* current, the cathode produces a simple contraction on closing the current, but no contraction from the anode. With a *medium* current, we get with the cathode a strong closing contraction but no opening contraction, while the anode excites feeble opening and closing contractions. With a *strong* current, we get with the cathode a tetanic contraction at closure, and a perceptible contraction at opening, while with the anode there is contraction both at opening and closing.]

[The **law of contraction** is usually expressed by the following formula (*Erb*): An = anode, Ca = cathode, C = contraction, *c* = feeble contraction, C′ = strong contraction, S = closure of current, O = opening of current, Te = tetanic contraction—so that, expressing the above statements briefly, we have—

Weak currents produce		Ca S C;
Medium	"	Ca S C′, An S *c*, An O *c*;
Strong	"	Ca S Te, An S C, An O C, Ca Oc.]

[**Typical Reaction of Degeneration.**—When the reaction of the nerve and muscle to electrical stimulation is altered both **qualitatively** and **quantitatively**, we have the reaction of degeneration, which is characterized essentially by the following conditions]: The excitability of the *muscles* is diminished or abolished for the Faradic current, while it is increased for the galvanic current from the 3d to 58th day; it again diminishes, however, with variations, from the 72d to 80th day; the anode closing contraction is stronger than the cathode closing contraction. The contractions in the affected muscles occur slowly in a peristaltic manner, and are local, in contrast with the rapid contraction of normal muscle. The diminution of the excitability of the *nerves* is similar for the galvanic and Faradic currents. If the reaction of the nerves be normal, while the muscle during direct stimulation with the constant current exhibits the reaction of degeneration, we speak of "**partial reaction of degeneration,**" which is constantly present in progressive muscular atrophy (*Erb*).

[The "**reaction of degeneration**" may occur before there is actual paralysis, as in lead poisoning. When it occurs we have to deal with some affection of the nerve fibres, or of the trophic nerve cells. When it is established, (1) stimulation of the nerve with Faradic and galvanic electricity does not cause contraction of the muscle; (2) direct Faradic stimulation of the muscles does not cause contraction; (3) the galvanic current usually excites contraction more readily than in a normal muscle, so that the muscle responds to much feebler currents than act on healthy muscles, but the contraction is longer and more of a tonic character, and shows a tendency to become tetanic. The electrical excitability is generally unaffected in paralysis of cerebral origin, and in some forms of spinal paralysis, as primary lateral sclerosis and transverse myelitis, but the "reaction of degeneration" occurs in traumatic paralysis, due to injury of the nerve trunks, neuritis, rheumatic facial paralysis, lead palsy, and in affections of the nerve cells in the anterior cornu of the gray matter of the spinal cord.] In rare cases the contraction of the muscles, caused by applying a *Faradic* current to the nerve, follows a slow peristaltic-like course—"*Faradic reaction of degeneration*" (*E. Remak, Erb*).

II. **In Various Forms of Spasm** (spasms, contracture, muscular tremor) the **constant current** is most effective (*Remak*). By the action of anelectrotonus, a pathological increase of the excitability is subdued. Hence, the anode ought to be applied to the part with increased excitability, and if it be a case of reflex spasm, to the points which are the origin or seat of the increased excitability. Weak currents of uniform intensity are most effective. The constant current may also be useful from its *cataphoric* action, whereby it favors the removal of irritants from the seat of the irritation.

Further, the constant current increases the *voluntary control* over the affected muscles. In spasms of central origin, the constant current may be applied to the central organ itself. **Faradization** is used in spasmodic affections to increase the vigor of enfeebled antagonistic muscles. Muscles in a condition of contracture are said to become more extensible under the influence of the Faradic current (*Remak*), as a normal muscle is more excitable during active contraction (§ 301).

In Cutaneous Anæsthesia, the *Faradic current* applied to the skin by means of hair-brush electrodes is frequently used (Fig. 417). When using the *constant current*, the cathode must be applied to the parts with diminished sensibility. The constant current alone is applied to the *central* seat of the lesion, and care must be taken to what extent the occurrence of cathelectrotonus in the centre affects the occurrence of sensation.

III. **In Hyperæsthesia and Neuralgias,** Faradic currents are applied with the object of overstimulating the hypersensitive parts, and thus to benumb them. Besides these powerful currents, *weak* currents act *reflexly* and accelerate the blood stream, increase the heart's action, and constrict the blood vessels, while *strong* currents cause the opposite effects (*O. Naumann*). Both may be useful. In employing the constant current in **neuralgia** (*Remak*), one object is by exciting anelectrotonus in the hypersensitive nerves, to cause a diminution of the excitability. According to the nature of the case, the anode is placed either on the nerve trunk, or even on the centre itself, and the cathode on an indifferent part of the body. The *catalytic* and *cataphoric* effects also are most important, for by means of them, especially in recent rheumatic neuralgias, the irritating inflammatory products are distributed and conducted away from the part. A descending current is transmitted continuously for a time through the nerve trunk, and in recent cases its effects are sometimes very striking. Lastly, of course, the constant current may be used as a *cutaneous stimulus*, while the Faradic current also acts reflexly on the cardiac and vascular activity.

Recently, Charcot and Ballet have used the electric spark from an electrical machine in cases of anæsthesia, facial paralysis, and paralysis agitans. In some cases of spinal paralysis, muscles can be made to contract with the electric spark, which do not contract to a Faradic current. [Electricity is sometimes used to distinguish real from feigned disease, or to distinguish death from a condition of trance.]

Galvano-Cautery.—The electrical current is used for *thermal* purposes, as in the galvanocautery.

Galvano-Puncture.—The *electrolytic* properties of electrical currents are employed to cause coagulation in aneurisms or varix. [If the electrodes from a constant battery in action be inserted in an aneurismal sac, after a time the fibrin of the blood is deposited in the sac, whereby the cavity of the aneurism is gradually filled up. A galvanic current passed through defibrinated blood causes the formation of a coagulum of proteid matter at the positive pole and bubbles of gas at the negative.]

340. **ELECTRICAL CHARGING OF THE BODY.**—Saussure investigated by means of the electroscope the "charge" of a person standing on an insulated stool. The phenomena observed by him, which were always inconstant, were due to the *friction* of the clothes upon the skin. Gardini, Hemmer, Ahrens (1817), and Nasse regarded the body as normally charged with *positive* electricity, while Sjösten and others regarded it as *negatively* charged. Most probably all these phenomena are due to friction, and are modified effects of the air in contact with the heterogeneous clothing (*Hankel*). A strong charge resulting in an actual spark has frequently been described. Cardanus (1553) obtained sparks from the tips of the hair of the head. According to Horsford (1837), long sparks were obtained from the tips of the fingers of a nervous woman in Oxford, when she stood upon an insulated carpet. Sparks have often been observed on combing the hair or stroking the back of a cat in the dark. Freshly voided *urine* is negatively electrical (*Vasalli-Eandi, Volta*); so is the freshly formed web of a spider, while the *blood* is positive.

341. **COMPARATIVE—HISTORICAL.—Electrical Fishes.**—Some of the most interesting phenomena connected with animal electricity are obtained in electrical fishes, of which there are about fifty species, including the electrical eel, or *Gymnotus electricus*, of the lagoons of the region of the Orinoco in South America—it may measure over 7 feet in length—the *Torpedo marmorata* and some allied species, 30 to 70 centimetres [1 to 2½ feet), in the Adriatic and Mediterranean, the *Malapterurus electricus* of the Nile, and the *Mormyrus* also of the same river. By means of special **electrical organs** (*Redi*, 1666), these animals can in part voluntarily (gymnotus and malapterurus), and in part reflexly (torpedo), give a very powerful electrical shock. The electrical organ consists of "compartments" of various forms, separated from each other by connective tissue, and filled with a jelly like substance, which the nerves enter on one surface and ramify to produce a plexus. From this plexus there proceed branches of the axial cylinder, which end in a nucleated plate, the "**electrical plate**" (*Billharz, M. Schulze*). When the "**electrical nerves**" proceeding to the organ are stimulated, an electrical discharge is the result.

In **Gymnotus,** the electrical organ consists of several rows of columns arranged along both sides of the spinal column of the animal, under the skin as far as the tail. It receives on the anterior surface several branches from the intercostal nerves. Besides this large organ there is a smaller one

lying on both sides above the anal fins. Here the plates are vertical, and the direction of the electrical current in the fish is ascending, so that of course it is descending in the surrounding water (*Faraday, du Bois-Reymond*).

In **Malapterurus**, the organ surrounds the body like a mantle, and receives only one nerve-fibre (p. 579), whose axis cylinder arises near the medulla oblongata from one gigantic ganglionic cell (*Billharz*), and is composed of protoplasmic processes (*Fritsch*). The plates are also vertical, and receive their nerves from the posterior surface. The direction of the current is descending in the fish during the discharge (*du Bois-Reymond*).

In the **Torpedo**, the organ lies immediately under the skin laterally on each side of the head, reaching as far as the pectoral fins. It receives several nerves which arise from the lobus electricus, between the corpora quadrigemina and the medulla oblongata. The plates, which do not increase in number with the growth of the animal (*Delle Chiaje, Babuchin*), lie horizontally, while the nerve fibres enter them on their dorsal surfaces, the current in the fish being from the abdominal to the dorsal surface (*Galvani*).

It is extremely probable that the electric organs are modified muscles, in which the nerve terminations are highly developed, the electrical plates corresponding to the motorial end plates of the muscular fibres, the contractile substance having disappeared, so that during physiological activity the chemical energy is changed into electricity alone, while there is no "work" done. This view is supported by the observation of Babuchin, that during development the organs are originally formed like muscles; further, that the organs when at rest are neutral, but when active or dead, acid; and lastly, they contain a substance related to myosin which coagulates after death (§ 295—*Weyl*). The organs manifest fatigue; they have a "latent period" of 0·016 second, while one shock of the organ (comparable to the current in an active muscle) lasts 0·07 second. About twenty-five of these shocks go to make a discharge, which lasts about 0·23 second. The discharge, like tetanus, is a discontinuous process (*Marey*). Mechanical, chemical, thermal, and electrical stimuli cause a discharge; a single induction shock is not effective (*Sachs*). During the electrical discharge the current traverses the muscles of the animal itself; the latter contract in the torpedo, while they do not do so in the gymnotus and malapterurus during the discharge (*Steiner*). A torpedo can give about fifty shocks per minute; it then becomes fatigued, and requires some time to recover itself. It may only partially discharge its organ (*Al. v. Humboldt, Sachs*). Cooling makes the organ less active, while heating it to 22 C. makes it more so. The organ becomes tetanic with strychnin (*Becquerel*), while curara paralyzes it (*Sachs*). Stimulation of the electrical organ of the torpedo causes a discharge (*Matteucci*); cold retards it, while section of the electrical nerves paralyzes the organ. The electrical fishes themselves are but slightly affected by very strong induction shocks transmitted through the water in which they are swimming (*du Bois-Reymond*). The substance of the electrical organs is singly refractive; excised portions give a current during rest, which has the same direction as the shock; tetanus of the organ weakens the current (*Sachs, du Bois-Reymond*). Perhaps the electrical organ of malapterurus is evolved from modified cutaneous glands (*Fritsch*).

Historical.—Richer (1672) made the first communication about the gymnotus. Walsh (1772) made investigations on the torpedo, on its discharge, and its power of communicating a shock. J. Davy magnetized particles of steel, caused a deflection of the magnetic needle, and obtained electrolysis with the electrical discharge. Becquerel, Brechet, and Matteucci studied the *direction* of the discharge. Al. v. Humboldt described the habits and actions of the gymnotus of South America. Hausen (1743) and de Sauvages (1744) supposed that electricity was the active force in nerves. The actual investigations into animal electricity began with G. Aloisio Galvani (1791), who observed that frogs' legs connected with an electrical machine contracted, and also when they were touched with two different metals. He believed that nerves and muscles generated electricity. Alessandro Volta ascribed the second experiment to the electrical current produced by the contact of dissimilar metals, and therefore outside the tissues of the frog. The contraction without metals described by Galvani was confirmed by Alex. v. Humboldt (1798). Pfaff (1793) first observed the effect of the direction of the current upon the contraction of a frog's leg obtained by stimulating its nerve. Bunzen made a galvanic pile of frogs' legs. The whole subject entered on a new phase with the construction of the galvanometer and since the introduction of the classical methods devised by du Bois-Reymond, *i.e.*, from 1843 onward.

PHYSIOLOGY OF THE PERIPHERAL NERVES.

342. FUNCTIONAL CLASSIFICATION OF NERVE FIBRES.

—As nerve fibres, on being stimulated, are capable of conducting impulses in both directions (§ 338), it is obvious that the physiological position of a nerve fibre must depend essentially upon its relations to the **peripheral end organ** on the one hand, and its **central connection** on the other. Thus, each nerve is distributed to a special area within which, under normal circumstances, in the intact body, it performs its functions. This function of the individual nerves, determined by their anatomical connections, is called their "specific energy."

I. Centrifugal or Efferent Nerves.—(a) **Motor.**—Those nerve fibres whose peripheral end organ consists of a **muscle**, the central ends of the fibres being connected with nerve cells :—

1. Motor fibres of **striped muscle** (§§ 292 to 320).
2. Motor nerves of the **heart** (§ 57).
3. Motor nerves of **smooth muscle**, *e.g.*, the intestine (§ 171). The **vasomotor** nerves are specially treated of in § 371.

(b) **Secretory.**—Those nerve fibres whose peripheral end organ consists of a **secretory cell**, the central ends of the fibres being connected with nerve cells.

Examples of secretory nerves are the secretory nerves for saliva (§ 145) and those for sweating (§ 289, II). It is to be remembered, however, that these fibres not unfrequently lie in the same sheath with other nerve fibres, so that stimulation of a nerve may give rise to several results, according to the kind of nerve fibres present in the nerve. Thus, the secretory and vasomotor nerves of glands may be excited simultaneously.

(c) **Trophic.**—The end organs of these nerve fibres lie in the **tissues** themselves, and are as yet unknown. These nerves are called trophic, because they are supposed to govern or control the normal metabolism of the tissues.

In some tissues, we know of a direct connection of their elements with nerve fibres, which may influence their nutrition. Nerves are connected with the corneal corpuscles (§ 201, 7), with the pigment cells of the frog's skin (*Ehrmann*), the connective-tissue corpuscles of the serous membrane of the stomach of the frog, and the cells around the stomata of lymphatic surfaces (§ 196, 5) (*E. F. Hoffmann*).

Trophic Influence of Nerves.—The trophic functions of certain nerves are referred to as follows: On the influence of the trigeminus on the **eye**, the mucous membrane of the **mouth** and **nose**, the **face** (§ 347); the influence of the vagus on the **lungs** (§ 352); motor nerves on **muscle** (§ 307); nerve centres on **nerve fibres** (§ 325, 4); certain central organs upon certain **viscera** (§ 379).

Section of certain nerves influences the **growth of the bones**. H. Nasse found that, after section of their nerves, the bones showed an absolute diminution of all their individual constituents, while there was an increase of the fat. Section of the spermatic nerve is followed by degeneration of the **testicle** (*Nélaton, Obolensky*). After extirpation of their secretory nerves, there is degeneration of the **sub-maxillary glands** (p. 258). Section of the nerves of the **cock's comb** interferes with the nutrition of that organ (*Legros, Schiff*). After section of the 2d cervical nerve in rabbits and cats, the hair falls off the **ear** on that side (*Joseph*). Section of the cervical sympathetic nerve in *young, growing* animals is followed by a more rapid growth of the **ear** upon that side (*Bidder, Stirling, Stricker*), also of the **hair** on that side (*Schiff, Stirling,*); while it is said that the corresponding half of the brain is smaller, which, perhaps, is due to the pressure from the dilated blood vessels (*Brown-Séquard*).

Blood Vessels.—Lewaschew found that prolonged, uninterrupted stimulation of the sciatic nerve of dogs, by means of chemical stimuli [threads dipped in sulphuric acid], caused hypertrophy of the lower limb and foot, together with the formation of aneurismal dilatations upon the blood vessels.

Skin and Cutaneous Appendages.—In man, stimulation or paralysis of nerves, or degeneration of the gray matter of the spinal cord, is not unfrequently followed by changes in the pigmentation of the skin, in the nails, in the hair and its mode of growth and color (*Jarisch*). [Injury to the brain, as by a fall, sometimes results in paralysis of the hair follicles, so that, after such an injury, the hair is lost over nearly the whole of the body.] Sometimes there may be eruptions upon the skin, apparantly traumatic in their origin (*v. Bärensprung*). Sometimes there is a tendency to decubitus (§ 379), and in some rare cases of tabes, there is a peculiar degeneration of the joints (**Charcot's disease**). The changes which take place in a nerve separated from its centre are described in § 325.

[**Tropho-neuroses.**—Some of the chief data on which the existence of trophic nerves is assumed are indicated above. There are many pathological conditions referable to diseases or injuries of nerves.]

[**Muscles.**—As is well known, paralysis of a motor nerve leads to simple atrophy of the corresponding muscle, provided it be not exercised; but when the motor ganglionic cells of the anterior horn of gray matter, or the corresponding cells in the crus, pons, and medulla, are paralyzed, there is an active condition of atrophy with proliferation of the muscular nuclei. **Progressive muscular atrophy,** or wasting palsy, is another trophic change in muscle, whereby either individual muscles, or groups of muscles, are one after the other paralyzed and become atrophied. In **pseudo-hypertrophic paralysis,** there is cirrhosis or increased development of the connective tissue, with a diminution of the true muscular elements, so that although the muscles increase in bulk their power is diminished.]

Cutaneous Trophic Affections.—Among these may be mentioned the occurrence of red patches or erythema, urticaria or nettle-rash, some forms of lichen, eczema, the bullæ or blebs of pemphigus, and some forms of ichthyosis, each of which may occur in limited areas after injury to a nerve or its spinal or cerebral centre. The relation between the cutaneous eruption and the distribution of a nerve is sometimes very marked in **herpes zoster,** which frequently follows the distribution of the intercostal and supraorbital nerves. **Glossy skin** (*Paget, Weir Mitchell*) is a condition depending upon impaired nutrition and circulation, and due to injuries of nerves. The skin is smooth and glossy in the area of distribution of certain nerves, while the wrinkles and folds have disappeared. In **myxœdema,** the subcutaneous tissue and other organs are infiltrated with, while the blood contains, *mucin*. The subcutaneous tissue is swollen, and the patient looks as if suffering from renal dropsy. There is marked alteration of the cerebral faculties, and a condition resembling a "cretinoid state" occurs after the excision of the thyroid gland. Victor Horsley has shown that a similar condition occurs in monkeys after excision of the thyroid gland (§ 103, III). [Laycock described a condition of **nervous œdema** which occurs in some cases of hemiplegia, and apparently it is independent of renal or cardiac disease.]

[There are alterations in the **color** of the skin depending on nervous affections, including localized **leucoderma,** where circumscribed patches of the skin are devoid of pigment. The pigmentation of the skin in **Addison's disease** or **bronzed skin,** which occurs in some cases of disease of the suprarenal capsules, may be partly nervous in its origin, more especially when we consider the remarkable pigmentation that occurs around the nipple and some other parts of the body during pregnancy, and in some uterine and ovarian affections.

In **anæsthetic leprosy,** the anæsthesia is due to the disease of the nervous structure, which results in disturbance of motion and nutrition. Among other remarkable changes in the skin, perhaps due to trophic conditions, are those of symmetrical and local *gangrene*, and **acute decubitus** or bed sores.]

[**Bed Sores.**—Besides the simple chronic form, which results from over pressure, bad nursing, and inattention to cleanliness, combined with some defect of the nervous conditions, there is another form, **acute decubitus,** which is due directly to nerve influence (*Charcot*). The latter usually appears within a few hours or days of the cerebral or spinal lesion, and the whole cycle of changes —from the appearance of the erythematous dusky patch to inflammation, ulceration, and gangrene of the buttock—is completed in a few days. An acute bed sore may form when every attention is paid to the avoidance of pressure and other unfavorable conditions. When it depends on cerebral affections, it begins and develops rapidly in the centre of the gluteal region on the paralyzed side, but when it is due to disease of the spinal cord it forms more in the middle line in the sacral region; while in unilateral spinal lesions it occurs not on the paralyzed, but on the anæsthetic side, a fact which seems to show that the trophic, like the sensory fibres, decussate in the cord (*Ross*).]

[There are other forms due to nervous disease, including **symmetrical gangrene** and local asphyxia of the terminal parts of the body, such as toes, nose, and external ear, caused perhaps by spasm of the small arterioles (**Raynaud's disease**); and the still more curious condition of **perforating ulcer of the foot.** Hemorrhage of nervous origin sometimes occurs in the skin, including those that occur in locomotor ataxia after severe attacks of pain, and **hæmatoma aurium,** or the insane ear, which is specially common in general paralytics.]

(d) [**Inhibitory nerves** are those nerves which modify, inhibit, or suppress a motor or secretory act already in progress.]

Take as an **example** the effect of the vagus upon the action of the heart. Stimulation of the peripheral end of the vagus causes the heart to stand still in diastole (§ 85); see also the effect of the splanchnic upon the intestinal movements (§ 161). The vaso-dilator nerves, or those whose stimulation is followed by dilatation of the blood vessels of the area which they supply, are referred to especially in § 237.

[There is the greatest uncertainty as to the **nature and mode of action of inhibitory nerves**, but take as a type the vagus, which depresses the function of the heart, as shown by the slower rhythm, diminution of the contractions, relaxation of the muscular tissue, lowering of the excitability and conduction. These phenomena are not due to exhaustion. Gaskell points out that the action is beneficial in its after effects, so that this nerve, although it causes diminished activity, is followed by repair of function; hence, he groups it as **anabolic** nerve, the outward symptoms of cessation of function indicating that constructive chemical changes are going on in the tissue.]

(e) **Thermic and electrical nerves** have also been surmised to exist.

[Gaskell classifies the **efferent nerves** differently. Beside **motor nerves** to striped muscle, he groups them as follows:—

1. Nerves to **vascular muscles.**
   (*a*) *Vasomotor, i. e.*, vaso-constrictor, accelerators and augmentors of the heart.
   (*b*) *Vaso-inhibitory, i. e.*, vaso-dilators and inhibitors of the heart.
2. Nerves of the **visceral muscles.**
   (*a*) *Viscero-motor.*
   (*b*) *Viscero-inhibitory.*
3. **Glandular nerves.**]

[Other terms are applied to nerves with reference to the **chemical changes** they excite in a tissue in which they terminate. The ordinary metabolism is the resultant of two processes—one constructive, the other destructive, or of assimilation and dissimilation respectively. The former process is anabolism, the latter katabolism. A motor nerve excites chemical destructive changes in a muscle, and is so far the **katabolic nerve** of that tissue; in the same way the sympathetic to the heart, by causing more rapid contraction, is also a katabolic nerve, while the vagus, as it arrests the heart's action, and brings about a constructive metabolism of the cardiac tissue, is an **anabolic nerve** (*Gaskell*).]

II. Centripetal or Afferent Nerves.—(a) **Sensory Nerves** (sensory in the narrower sense), which by means of special end organs conduct sensory impulses to the central nervous system.

(b) **Nerves of Special Sense.**

(c) **Reflex or Excito-motor Nerves.**—When the periphery of one of these nerves is stimulated, an impulse is set up which is conducted by them to a nerve centre, from whence it is transferred to a *centrifugal* or *efferent* fibre, and the mechanism (I, a, b, c, d) in connection with the peripheral end of this efferent fibre is set in action; thus, there are—**Reflex motor, Reflex secretory,** and **Reflex inhibitory** fibres. [Fig. 422 shows the simplest mechanism necessary for a reflex motor act. The impulse starts from the skin, S, travels up the nerve, *af*, to the nerve centre or nerve cell, N, situate in the spinal cord, where it is modified and transferred to the outgoing fibre, *ef*, and conveyed by it to the muscle, M.]

FIG. 422.



Scheme of a reflex motor act. S, skin; *af*, afferent nerve; N, nerve cell; *ef*, efferent fibre.

III. Inter-central Nerves.—These fibres serve to connect ganglionic centres with each other, as, for example, in co-ordinated movements, and in extensive reflex acts.

THE CRANIAL NERVES.

343. **I. NERVUS OLFACTORIUS.—Anatomical.**—The three-sided prismatic **tractus olfactorius**, lying in a groove on the under surface of the frontal lobe, arises by means of an inner, outer, and middle root, from the tuber olfactorium (Fig. 428, I). The tractus swells out upon the cribriform plate of the ethmoid bone, and becomes the **bulbus olfactorius**, which is the analogue of the special portion of the brain, existing in different mammals with a well-developed sense of smell (*Gratiolet*). From twelve to fifteen olfactory filaments pass through the foramina in the cribriform plate of the ethmoid bone. At first they lie between the periosteum and the mucous membrane, but in the lower third of their course they enter the mucous membrane of the regio olfactoria. The bulb consists of white matter below, and above of gray matter mixed with small spindle-shaped ganglionic cells. Henle describes six, and Meynert eight, layers of nervous matter seen on transverse section. [The **centre for smell** lies in the tip of the uncinate gyrus on the inner surface of the cerebral hemisphere (*Ferrier*).] According to Gudden, removal of the olfactory bulb is followed by atrophy of the gyrus uncinatus on the same side. According to Hill, the three roots of the olfactory bulb stream backward, the inner one is small, the middle one is a thick bundle, which grooves the head of the caudate nucleus, curves inward to the anterior commissure, and crosses *viâ* this commissure, where it decussates, and passes to the extremity of the temporo-sphenoidal lobe. The outer roots pass transversely into the pyriform lobe, thence *viâ* the fornix, corpora albicantia, the bundle of Vicq d'Azyr into the anterior end of the optic thalamus. Hill also points out that the elements contained in the olfactory bulb are identical with those contained in the four outer layers of the retina. Flechsig traces its origin (1) to the gyrus fornicatus, (2) through the lamina perforata anterior to the internal capsule (sensory part), and to the gyrus uncinatus (sensory area of the cerebrum) (§ 378, IV). Probably the fibres at their origin cross to the cerebrum. There is a connection between the olfactory bulbs in the anterior commissure. [Each nerve is related to both hemispheres.]

Function.—It is the only nerve of **smell.** Physiologically, it is excited only by gaseous, odorous bodies—(*Sense of Smell*, § 420). Stimulation of the nerve, by any other form of stimulus, in any part of its course, causes a sensation of smell. [It also conveys those impressions which we call flavors, but in this case the sensation is combined with impressions from the organs of taste. In this case also the stimulus reaches the nerve by the posterior nares.] Congenital absence or section of both olfactory nerves abolishes the sense of smell (easily performed on young animals—*Biffi*).

Pathological.—The term **hyperosmia** is applied to cases where the sense of smell is excessively and abnormally acute, as in some hysterical persons, and in cases where there is a purely subjective sense of smell, as in some insane persons. The latter is perhaps due to an abnormal stimulation of the cortical centre (§ 378, IV). **Hyposmia** and **anosmia** (*i. e.*, diminution and abolition of the sense of smell) may be due to mechanical causes, or to over-stimulation. Strychnin sometimes increases, while morphia diminishes, the sense of smell. [**Method of Testing**, § 421.]

344. **II. NERVUS OPTICUS.—Anatomical.**—The **tractus opticus** (Fig. 428, II) arises from the anterior corpora quadrigemina, the corpus geniculatum externum, and the thalamus opticus (Fig. 428), as well as from the gray matter which lines the third ventricle (*Tartuferi*). A broad bundle of fibres passes from the origin of the optic tract to the **cortical visual centre**, at the apex of the occipital lobe on the same side (*Wernicke*—§ 379, IV). Fibres pass from the cerebellum through the crura.

The **optic tract** bends round the pedunculus cerebri, where it unites with its fellow of the opposite side to form the chiasma, and from the opposite side of this the two **optic nerves** spring.

[**Connections of Optic Tract.**—There is very considerable difficulty in ascertaining the exact origin of all the fibres of the optic tract. Although as yet the statement of Gratiolet is not proved that the optic tract is directly connected with every part of the cerebral hemisphere in man, from the frontal to the occipital lobe, still the researches of D. J. Hamilton have shown that its connections are very extensive. It is certain that some of them are ganglionic, *i. e.*, connected with the ganglia at the base of the brain, while others are *cortical*, and form connections with the cortex cerebri. The **ganglionic** fibres arise from the corpora geniculata, pulvinar, and anterior corpora quadrigemina, and probably also from the substance of the thalamus. The **cortical** fibres join the ganglionic to form the optic tract. According to D. J. Hamilton, the connection with the cortex in the *frontal* region is brought about by "Meynert's commissure" The latter arises directly from the lenticular nucleus loop, decussates in the lamina cinerea, and passes into the optic nerve of the opposite side. The lenticular nucleus loop is formed below the lenticular nucleus by the junction of the striæ medullares; the striæ medullares form part of the fibres of the internal capsule, and the inner cap-

sule is largely composed of fibres descending from the cortex. Hamilton also asserts that other cortical connections join the tract as it winds round the pedunculus cerebri, and they include (*a*) a large mass of fibres coming from the motor areas of the opposite cerebral hemisphere, crossing in the corpus callosum, entering the outer capsule, and joining the tract directly; (*b*) fibres uniting it to the temporo-sphenoidal lobe of the same side, especially the first and second temporo-sphenoidal convolutions; (*c*) fibres to the gyrus hippocampi of the same side; (*d*) a large leash of fibres forming the "**optic radiation**" of Gratiolet, which connect it directly with the tip of the occipital lobe. There are probably also *indirect* connections with the occipital region through some of the basal ganglia. Although some observers do not admit the connections with the frontal and sphenoidal lobes, all are agreed as to its connection with the occipital by means of the "optic radiation."]

[The **optic radiation** of Gratiolet is a wide strand of fibres expanding and terminating in the occipital lobes. It is composed of, or, stated otherwise, gives branches to (*a*) the optic tract directly, (*b*) the corpus geniculatum internum and externum, (*c*) to the pulvinar and substance of the thalamus, (*d*) a direct sensitive band (Meynert's "Sensitive band") to the posterior third of the posterior limb of the inner capsule, (*e*) fibres which run between the island of Reil and the tip of the occipital lobe (*D. J. Hamilton*).]

FIG. 423.



Scheme of the semi-decussation of the optic nerves. *L.A.*, left eye; *R.A.*, right eye.

FIG. 424.



Diagram of the relation of the field of vision, retina, and optic tracts. RF, LF, right and left fields of vision—the asterisk is at the fixing point; RR, LR, right and left retina—the asterisk is at the macula lutea; *l.h.*, *r.h.*, left half and right half of each retina, receiving rays from the opposite half of the field; RN, LN, right and left optic nerves; *Ch*, chiasma; RT, LT, right and left optic tracts; below, the halves of the fields from which impressions pass by each optic tract are superimposed (*Gowers*).

Chiasma.—The extent of the decussation of the optic fibres in the chiasma is subject to variations. As a rule, rather more than half of the fibres of one tract cross to the optic nerve of the opposite side (Fig. 423), so that the left optic tract sends fibres to the left half of both eyes, while the right tract supplies the right half of both eyes (§ 378, IV). [Thus, the corresponding regions of each retina are brought into relation with one hemisphere. The fibres which cross are from the nasal half of each retina (Fig. 424).]

Hence, in man, destruction of one optic tract (and its central continuation in the occipital lobe of the cerebrum) produces "**equilateral or homonymous hemianopia.**" In the cat there is a semi-decussation; hence, in this animal extirpation of one eyeball causes atrophy and degeneration of half of the nerve fibres in both optic tracts (*Gudden*). Baumgarten and Mohr have observed a similar result in man. A sagittal section of the chiasma in the cat produces partial blindness of both eyes

(*Vicati*). According to Gudden, the fibres which decussate are more numerous than those which do not, although J. Stilling maintains that they are only slightly more numerous. According to J. Stilling, the decussating fibres lie in the central axis of the nerve, while those which do not decussate form a layer around the former.

Other observers maintain that there is complete decussation of all the fibres in the chiasma. Hence, *section of one optic nerve* causes dilatation of the pupil and blindness on the *same* side, while section of one *optic tract* causes dilatation of the pupil and blindness of the *opposite* eye (*Knoll*). In osseous fishes, both optic nerves are isolated and merely cross over each other, while in the cyclostomata they do not cross at all. [Total decussation occurs in those animals where the eyes do not act together.]

Injury of the external geniculate body and section of the anterior brachium have the same effect as section of the optic tract of the *same* side (§ 359—*Bechterew*).

In very rare cases the decussation is absent in man, so that the right tract passes directly into the right eyeball, and the left into the left eyeball (*Vesalius, Caldani*), the sight not being interfered with.

It is quite certain that the individual fibres do not divide in the chiasma. Two commissures, the inferior commissure (*Gudden*) and Meynert's commissure, unite both optic tracts further back.

A special commissure (**C. inferior**) extends in a curved form across the posterior angle of the chiasma (*Gudden*). It does not degenerate after enucleation of the eyeballs, so that it is regarded as an inter-central connection. After **excision of an eye**, there is central degeneration of the fibres of the optic nerve entering the eyeball (*Gudden*), and in man about the half of the fibres in the corresponding optic tract (*Baumgarten, Mohr*). After section of **both** optic nerves, or enucleation of both eyeballs, there is a **degeneration**, proceeding centrally, of the whole optic tract. The degeneration extends to the origins in the corpora quadrigemina, corpora geniculata, and pulvinar, but not into the conducting paths leading to the cortical visual centre (*v. Monakow*) (§ 378, IV, I).

FIG. 425.



Diagram of the decussation of the optic tracts. T, semi-decussation in the chiasma; TQ, decussation of fibres behind the ext. geniculate bodies (CG); *a'b*, fibres which do not decussate in the chiasma; *b'a*, fibres proceeding from the right eye, and coming together in the left hemisphere (LOG); LOG, K, lesion of the left optic tract producing right lateral hemianopsia; *A*, lesion in the left hemisphere producing crossed amblyopia (right eye); T, lesion producing temporal hemianopsia; NN, lesion producing nasal hemianopsia.

[**Hemianopia and Hemianopsia.**—When one optic tract is interfered with or divided, there is interference with or loss of sight in the lateral halves of both retinæ, the blind part being separated from the other half of the field of vision by a vertical line. When it is spoken of as paralysis of one-half of the retina, the term **hemiopia**, or preferably **hemianopia**, is applied to it; when with reference to the field of vision, the term **hemianopsia** is used (see *Eye*). Suppose the *left* optic tract to be divided or pressed upon by a tumor at K (Fig. 425), then the outer half of the left and the inner half of the right eye are blind, causing *right lateral hemianopsia, i. e.*, the two halves are affected which correspond in ordinary vision, so that the condition is spoken of as **homonymous hemianopsia**. Suppose the lesion to be at T (Fig. 425), then there is paralysis of the *inner* halves of *both* eyes, causing *double temporal hemianopsia*. When there are two lesions at NN, which is very rare, the *outer* halves of both retinæ are paralyzed, so that there is *double nasal hemianopsia*. In order to explain some of the eye symptoms that occasionally occur in cerebral disease, Charcot has supposed that some of the fibres which pass from the external geniculate body to the visual centres in the occipital lobe cross behind the corpora quadrigemina, and this is represented in the diagram as occurring at TQ, in the corpora quadrigemina. On this view, all the occipital cortical fibres from one eye would ultimately pass to the cortex of the occipital lobe of the opposite hemisphere. This view, however, by no means explains all the facts, for in cases of homonymous hemianopsia the point of central vision on both sides, *i. e.*, both maculæ luteæ are always unaffected, so that it is assumed that each macula lutea is connected with both hemispheres. The second crossing suggested by Charcot probably does not occur. Affections of the optic nerve, *e. g.*, between the eyeball and the chiasma, *i. e.*, in the orbit, optic foramen, or within the skull, affect one eye only; of the middle of the chiasma, cause temporal hemiopia; of the optic tract, between the chiasma and occipital cortex, hemiopia, which is always symmetrical (*Gowers*).]

Fig. 424, reduced from that of Gowers, shows the relation of the fields of vision of the retina, optic tracts, and the cerebral optic centre.

Function.—The optic nerve is the nerve of **sight**; physiologically, it is excited only by the transference of the vibrations of the ether to the rods and cones of the retina (§ 383). Every other form of stimulus, when applied to the nerve in its course or at its centre, causes the sensation of light. Section or degeneration of the nerve is followed by blindness. Stimulation of the optic nerve causes a reflex contraction of the pupils, the efferent nerve being the oculo-motorius or third cranial nerve. If the stimulus be very strong, the eyelids are closed and there is a secretion of tears. The influence of light upon the general metabolism is stated at § 127, 9.

As the optic nerve has **special** and independent connections with the so-called *visual centre* (§ 378, IV), as well as with the *centre for narrowing the pupil* (§ 345), it is evident that, under pathological circumstances, there may be, on the one hand, blindness with retention of the action of the iris, and on the other loss of the movements of the iris, the sense of vision being retained (*Wernicke*).

Pathological.—Stimulation of almost the whole of the nervous apparatus may cause excessive sensibility of the visual apparatus (**hyperæsthesia optica**), or even visual impressions of the most varied kinds (**photopsia, chromatopsia**), which in cases of stimulation of the visual centre may become actual visual hallucinations (§ 378, IV). Material change in, and inflammation of, the nervous apparatus are often followed by a nervous weakness of vision (**amblyopia**), or even by blindness (**amaurosis**). Both conditions, however, may be the signs of disturbances of other organs, *i. e.*, they are "sympathetic" signs, due it may be to changes in the movement of the blood stream, depending upon stimulation of the vasomotor nerves. The discovery of the partial origin of the optic nerve from the spinal cord explains the occurrence of amblyopia with partial atrophy of the optic nerve, in disease of the spinal cord, especially in tabes. Many **poisons**, such as lead and alcohol, disturb vision. There are remarkable intermittent forms of amaurosis known as day blindness or **hemeralopia**, which occurs in some diseases of the liver and is sometimes associated with incipient cataract. [The person can see better in a dim light than during the day or in a bright light. In night blindness or **nyctalopia**, the person cannot see at night or in a dim light, while vision is good during the day or in a bright light. It depends upon disorder of the eye itself, and is usually associated with imperfect conditions of nutrition.]

345. **III. NERVUS OCULOMOTORIUS.—Anatomical.**—It springs from the **oculomotorius nucleus** (united with that of the trochlearis), which is a direct continuation of the anterior horn of the spinal cord, and lies unner the aqueduct of Sylvius (Fig. 428). [The motor nucleus (Fig. 427) gives origin to three sets of fibres, for (1) the most of the muscles of the eyeballs, (2) the sphincter pupillæ, (3) ciliary muscle. The nucleus of the third and fourth nerves is also connected with that of the sixth under the iter, so that all the nerves to the ocular muscles are thus co-related at their centres.]

The origin is connected with the corpora quadrigemina, to which the intra-ocular fibres may be traced, and also with the opposite half of the brain to the angular gyrus (§ 378, I) through the pedunculus cerebri Beyond the pons, it appears on the inner side of the cerebral peduncle, between the superior cerebellar and posterior cerebral arteries (Fig. 428, III).

Function.—It contains—(1) the voluntary motor fibres for all the external muscles of the eyeballs—except the external rectus and superior oblique—and for the levator palpebræ superioris. The coördination of the movements of both eyeballs, however, is independent of the will. (2) The fibres for the *sphincter pupillæ*, which are excited reflexly from the retina. (3) The voluntary fibres for the *muscle of accommodation*, the tensor choroideæ or ciliary muscle. The intra-bulbar fibres of 2 and 3 proceed from the branch for the inferior oblique muscle, as the short root of the ciliary ganglion (Fig. 429). They reach the eyeball through the short ciliary nerves of the ganglion. v. Trautvetter and others observed that stimulation of the nerve caused changes in the eye similar to those which accompany near vision. The three centres for the muscle of accommodation, the sphincter pupillæ, and the internal rectus muscle, lie directly in relation with each other, in the most posterior part of the floor of the third ventricle (*Hensen and Völckers*).

The **centre** for the *reflex* stimulation of the sphincter fibres by light was said to be in the corpora quadrigemina, but newer researches locate it in the medulla oblongata (§§ 379, 392). The narrowing of the pupil, which accompanies the

act of accommodation for a near object, is to be regarded as an associated movement (§ 392, 5).

Anastomoses.—In man, the nerve anastomoses on the sinus cavernosus with the ophthalmic branch of the trigeminus, whereby it receives *sensory fibres for the muscles* to which it is distributed (*Valentin, Adamük*), with the sympathetic through the carotid plexus, and (?) indirectly through the abducens, whereby it receives vasomotor fibres (?).

Varieties.—In some rare cases, the pupillary fibres for the sphincter run in the abducens (*Adamük*), or even in the trigeminus (*Schiff, v. Gräfe*).

Atropin paralyzes the intra-bulbar fibres of the oculomotorius, while **Calabar bean** stimulates them (or paralyzes the sympathetic, or both—compare § 392).

Stimulation of the nerve, which causes contraction of the pupil, is best demonstrated on the decapitated and opened head of a bird. The pupil is **dilated** in paralysis of the oculomotorius, in asphyxia, sudden cerebral anæmia (*e. g.*, by ligature of the carotids, or beheading), sudden venous congestion, and at death.

Pathological.—Complete paralysis of the oculomotorius is followed by (1) drooping of the upper eyelid (**ptosis paralytica**); (2) immobility of the eyeball; (3) squinting (strabismus) outward and downward, and consequently there is double vision (**diplopia**); (4) slight protrusion of the eyeball, because the action of the superior oblique muscle in pulling the eyeball forward is no longer compensated by the action of three paralyzed recti muscles. In animals provided with a retractor bulbi muscle, the protrusion of the eyeball is more pronounced; (5) moderate dilatation of the pupil (**mydriasis paralytica**); (6) the pupil does not contract to light; (7) inability to accommodate for a near object. It is to be noted, however, that the paralysis may be confined to individual branches of the nerve, *i. e.*, there may be incomplete paralysis.

[**Squinting.**—In **paralysis** of the **superior rectus,** the eye cannot be moved upward, and especially upward and outward. There is diplopia on looking upward, the false image being above the true, and turned to the right when the left eye is affected (Fig. 426, 3). **Inferior Rectus.**—Defect of downward, and especially downward and outward movement, the eye being directed upward and outward. Diplopia with crossed images, the false one is below the true image and placed obliquely, being turned to the left when the left eye is affected. Diplopia is most troublesome when the object is below the line of vision (Fig. 426, 5). **Internal Rectus.**—Defective inward movement, divergent squint, and diplopia, the images being on the same plane, the false one to the patient's right when the left eye is affected. The head is turned to the healthy side, when looking at an object, while there is secondary deviation of the healthy eye outward (Fig. 426, 1). **Inferior oblique** is rare, the eye is turned slightly downward and inward, and defective movement upward. Diplopia with the false image above the true one, especially on looking upward; the false image is oblique, and directed to the patient's left when the left eye is affected (Fig. 426, 4).]

FIG. 426.

The black cross represents the true image, the light cross the false image. The left eye is represented as affected in all cases (*Bristow*).

Stimulation of the branch supplying the levator palpebræ in man causes **lagophthalmus spasticus,** while stimulation of the other motor fibres causes a corresponding **strabismus spasticus.** The latter form of squinting may be caused also reflexly—*e. g.*, in teething, or in cases of diarrhœa in children; [the presence of worms or other source of irritation in the intestines of children is a frequent cause of squinting]. Clonic spasms occur in *both* eyes, and also as involuntary movements of the eyeballs constituting **nystagmus,** which may be produced by stimulation of the corpora quadrigemina, as well as by other means. Tonic contraction of the sphincter pupillæ is called **myosis spastica,** and clonic contraction, **hippus.** Spasm of the muscle of accommodation (ciliary muscle) is sometimes observed; owing to the imperfect judgment of distance, this condition is not unfrequently associated with macropia.

[**Conjugate Deviation.**—Some movements are produced by non-corresponding muscles; thus, on looking to the right, we use the right external rectus and left internal rectus, and the same is the case in turning the head to the right, *e. g.*, the inferior oblique, some muscles of the right side act along with the left sterno-mastoid. In hemiplegia, the muscles on one side are paralyzed, so that the

head and often the eyes are turned away from the paralyzed side, *i. e.*, to the side of the brain on which the lesion occurs. This is called "**conjugate deviation**" of the eyes, with rotation of the head and neck. If the right external rectus be paralyzed from an affection of the sixth nerve, on telling the patient to look to the right it will be found that the left eye will squint more inward even than the right eye, *i. e.*, owing to the strong voluntary effort, the muscle, the left internal rectus which usually acts along with the right external rectus, contracts vigorously, and so we get **secondary deviation of the sound eye.** Similar results occur in connection with paralysis of the other ocular muscles.]

FIG. 427.



Medulla oblongata, with the corpora quadrigemina. The numbers *IV—XII* indicate the superficial origins of the cranial nerves, while those (3–12) indicate their deep origin, *i. e.*, the position of their central nuclei; *t*, funiculus teres.

346. **IV. NERVUS TROCHLEARIS.—Anatomical.**—It arises from the valve of Vieussens, *i. e.*, *behind* the fourth ventricle, but its fibres pass to the oculomotorious from the *trochlearis nucleus*, which is to a certain extent a continuation of the anterior horn of the spinal cord (Fig. 427). It passes to the lower margin of the corpora quadrigemina, pierces the roof of the aqueduct of Sylvius, then into the velum medullare superius, and after **decussating** with the root of the opposite side behind the iter, it pierces the crus at the superior and external border (Fig. 428). Its fibres cross between its nucleus and its distribution. It has also an origin from the locus cœruleus. The root of the nerve receives some fibres from the nucleus of the abducens of the opposite side. Physiologically, there is a necessity for a connection between the centre and the cortical motor centre for the eye muscles.

Function.—It is the voluntary motor nerve of the superior oblique muscle. (In coördinated movements, however, it is involuntary.)

FIG. 428.

Part of the base of the brain, with the origins of the cranial nerves; the convolutions of the island of Reil on the right side, but removed on the left. I', olfactory tract cut short; II, left optic nerve; II', right optic tract; *Th*, cut surface of the left optic thalamus; C, central lobe, or island of Reil; *Sy*, fissure of Sylvius; XX, the locus perforatus anticus; *e*, the external, and *i*, the internal corpus geniculatum; *h*, hypophysis cerebri; *tc*, tuber cinereum, with the infundibulum; *a*, points to one of the corpora albicantia; P, the cerebral peduncle; *f*, the fillet; III, left oculomotor nerve; X, the locus perforatus posticus; PV, pons Varolii; V, the greater part of the fifth nerve; +, the lesser root (on the right side this mark is placed on the Gasserian ganglion and points to the lesser root); 1, ophthalmic division of the fifth; VII *a*, facial, VII *b*, auditory; VIII, vagus; VIII *a*, glosso-pharyngeal; VIII *b*, spinal accessory; IX, hypoglossal; *fl*, flocculus; *fh*, horizontal fissure of the cerebellum (*Ce*); *am*, amygdala; *pa*, anterior pyramid; *o*, olivary body; *e*, restiform body; *d*, anterior median fissure; *cl*, the lateral column of the spinal cord; CI, the sub-occipital or first cervical nerve.

Anastomoses. — Its connections with the plexus caroticus sympathici, and with the first branch of the trigeminus, have the same significance as similar branches of the oculomotorius.

Pathological. — **Paralysis** of the trochlearis nerve causes a very slight loss of the mobility of the eyeball outward and downward. There is slight squinting inward and upward, with diplopia, or double vision. The images are placed obliquely over each other [the false image being the lower, and directed to the patient's right when the left eye is affected (Fig. 426, 6)]; they approach each other when the head is turned toward the sound side, and are separated when the head is turned toward the other side. The patient at first directs his head forward; later he rotates it round a vertical axis toward the sound side. In rotating his head (whereby the *sound* eye may retain the primary position), the eye rotates with it. **Spasm** of the trochlearis causes squinting outward and downward.

347. V. NERVUS TRIGEMINUS. — **Anatomical.** — The trigeminus (Fig. 429, 5), arises like a spinal nerve by **two roots** (Fig. 428, V). The smaller, **anterior, motor** root proceeds from the "**motor trigeminal nucleus**" (5), which is provided with many multipolar nerve cells, and lies in the floor of the medulla oblongata, not far from the middle line. Fibres connect this nucleus with the cortical motor centres on the opposite side of the cerebrum. Besides this the "**descending root**" also supplies motor fibres. It extends laterally from the corpora quadrigemina along the aqueduct of Sylvius downward to the exit of the nerve (*Henle*, *Forel*). The large **posterior sensory** root receives fibres: (1) From the small cells of the "**sensory trigeminal nucleus**" which lies at the level of the pons, and is the analogue of the posterior horn of the gray matter of the spinal cord. (2) From the gray matter of the posterior horn of the spinal cord, downward as far as the second cervical vertebra. These fibres run into the posterior column of the cord and then appear as the "**ascending root**" in the trigeminus. (3) Some fibres come from the cerebellum, through the crura cerebelli. The origins of the sensory root anastomose with the motor nuclei of all the nerves arising from the medulla oblongata, with the exception of the abducens. This explains the vast number of **reflex relations** of the fifth nerve. The thick trunk appears on each side of the pons (Fig. 428), when its posterior root (perhaps in connection with some fibres from the anterior) forms the **Gasserian ganglion**,

upon the tip of the petrous part of the temporal bone (Fig. 429). Fibres from the sympathetic proceed from the plexus cavernosus to the ganglion. The nerve divides into **three** large **branches.**

I. The ophthalmic division (Fig. 429, *d*) receives *sympathetic* fibres (*vasomotor nerves*) from the plexus cavernosus; it passes through the superior orbital fissure [sphenoidal] into the orbit. Its **branches** are:—

1. The small **recurrent** nerve which gives **sensory** branches to the tentorium cerebelli. Fibres—the **vasomotor** nerves for the dura mater—proceed along with it from the carotid plexus of the sympathetic.

2. The **lachrymal** nerve gives off (*a*) **Sensory** branches to the conjunctiva, the upper eyelid, and the neighboring part of the skin over the temple (Fig. 429, *a*); (*b*) true **sensory** fibres to the lachrymal gland (?). Stimulation of this nerve is said to cause a secretion of tears, while its section prevents the reflex secretion excited through the sensory nerves of the eye. After a time, section of the nerve is followed by a paralytic secretion of tears (*Herzenstein and Wolferz*), although the statement is contested by Reich. The secretion of tears may be excited reflexly, by strong stimulation of the retina by light, by stimulation of the first and second branches of the trigeminus, and through all the sensory cranial nerves (*Demtschenko*) (§ 356, A, 6).

3. The **frontal** (*f*) gives off the **supra-trochlear**, which supplies **sensory** fibres to the upper eyelids, brow, glabella, and those which excite the **secretion of tears** reflexly; and by its **supra-orbital** branch (*b*), analogous branches to the upper eyelid, skin of the forehead, and the adjoining skin over the temple as far as the vertex.

4. The **naso-ciliary** nerve (*nc*), by its **infra-trochlear** branch supplies fibres, similar to those of 3, to the conjunctiva, caruncula, and saccus lacrimalis, the upper eyelid, brow, and root of the nose. Its **ethmoidal** branch supplies the tip and alæ of the nose, outside and inside, with sensory branches, as well as the upper part of the septum and the turbinated bones with **sensory** fibres, which can act as afferent nerves in the reflex secretion of tears; while it is probable that **vasomotor** fibres are supplied to these parts through the same channel. (These fibres may be derived from the anastomosis with the sympathetic (?).) The naso-ciliary nerve gives off the long root (*l*) of the ciliary ganglion (*c*), and 1 to 3 long ciliary nerves.

The **ciliary ganglion** (Fig. 429, *c*), which, according to Schwalbe, perhaps belongs rather to the third than the fifth nerve, has **three roots** (*a*) the **short** or oculomotorius (3—see § 345); (*b*) the **long** (*l*), from the naso-ciliary; and (*c*) the **sympathetic** (*s*) sometimes united with *b*, from the carotid plexus. The **short ciliary nerves** (*t*), six to ten in number, proceed from the ganglion, along with the long ciliary nerves, to near the entrance of the optic nerve, where they perforate the sclerotic coat and run forward between it and the choroid.

Ciliary Nerves.—*Physiologically*, these nerves contain:—

1. The **motor** fibres for the **sphincter pupillæ** and the **tensor choroideæ** from the root of the oculomotorius (§ 345, 2, 3).

2. **Sensory** fibres for the **cornea**, which are distributed as excessively fine fibrils between the epithelium of the *conjunctiva bulbi;* they perforate the sclerotic. These fibres cause a reflex secretion of tears (N. lacrimalis) and closure of the eyelids (N. facialis). Sensory fibres are supplied to the **iris** (pain in iritis and in operations on the iris), the **choroid** (painful tension when the ciliary muscle is strained), and the **sclerotic.**

3. **Vasomotor nerves** for the blood vessels of the iris, choroid, and retina. They arise in part from the **sympathetic** root, and the anastomosis of the sympathetic with the ophthalmic division of the trigeminus (*Wegner*). The **iris** and **retina** receive most of their vasomotor nerves from the trigeminus itself (*Rogow*), and few from the sympathetic; according to Klein and Svetlin, the retinal vessels are not influenced either by stimulation or division of the sympathetic.

FIG. 429.



Semi-diagrammatic representation of the nerves of the eyeball, the connections of the trigeminus and its ganglia, together with the facial and glosso-pharyngeal nerves. 3, Branch to the inferior oblique muscle from the oculomotorius, with the thick, short root, to the ciliary ganglion (*c*); *l*, ciliary nerves; *l*, long root to the ganglion from the naso-ciliary (*nc*); *s*, sympathetic root from the sympathetic plexus (*Sy*) surrounding the internal carotid (G); *d*, first or ophthalmic division of the trigeminus (5), with the naso-ciliary (*nc*), and the terminal branches of the lachrymal (*a*), supra-orbital; (*b*), and frontal (*f*); *e*, second or superior maxillary division of the trigeminus; R, infra-orbital; *n*, spheno-palatine (Meckel's) ganglion with its roots; *j*, from the facial, and *v*, from the sympathetic; N, the nasal branches, and pp_1, the palatine branches of the ganglion; *g*, third or inferior maxillary division of the trigeminus; *k*, lingual; *i i*, chorda tympani; *m*, otic ganglion, with the roots from the tympanic plexus, the carotid plexus, and from the 3d branch, and with its branches to the auriculo-temporal (A), and to the chorda (*i i*); L, sub-maxillary ganglion with its roots from the tympanico-lingual, and the sympathetic plexus on the external artery (*q*). 7. Facial nerve—*j*, its great superficial petrosal branch; α, gang. geniculatum; β, branch to the tympanic plexus; γ, branch to the stapedius; δ, anastomotic twig to the auricular branch of the vagus; *i i*, chorda tympani; S, stylo-mastoid foramen. 9. Glosso-pharyngeal—λ, its tympanic branch; π, and ε, connections with the facial; U, terminations of the gustatory fibres of 9 in the circumvallate papillæ; *Sy*, sympathetic with *G g*, *s*, the superior cervical ganglion; *I. II, III, IV*, the four upper cervical nerves; P, parotid, M, sub-maxillary gland.

4. **Motor fibres** for the dilator pupillæ, which for the most part are derived from the *sympathetic* (*Petit*, 1727), through the sympathetic root of the ganglion, and the anastomosis of the sympathetic with the trigeminus (*Balogh*, *Oehl*). Some observers deny altogether the existence of a dilator pupillæ muscle (§ 384). The ophthalmic division contains independent fibres for the dilatation of the pupil (*Schiff*), which arise in the medulla oblongata and proceed directly into the ophthalmic (? or arise from the Gasserian ganglion—*Oehl*).

It is not conclusively determined whether **in man** dilator fibres also proceed through the sympathetic root of the ciliary ganglion, and reach the iris through the ciliary nerves. In the dog and cat these fibres do not pass through the ciliary ganglion, but go directly along the optic nerve to the eye (*Hensen and Völckers*) through the Gasserian ganglion, to its ophthalmic branch and through the long ciliary nerves (*Jegorow*). In birds, the dilator fibres run only in the fifth (*Zeglinski*). For the centre (§ 367, 8).

After **section** of the trigeminus, the pupil becomes contracted after a short period of dilatation (rabbit, frog), but this effect is not permanent. After excision of the superior cervical ganglion of the sympathetic, the power of dilatation of the pupil is not completely abolished. The narrowing of the pupil which follows section of the trigeminus in the rabbit, and which rarely lasts more than half an hour, may be regarded as due to a reflex stimulation of the oculomotorius fibres of the sphincter, in consequence of the painful stimulation caused by section of the trigeminus.

Stimulation of the Sympathetic.—Either in the neck, or in its course to the eye, when the peripheral end of the cervical sympathetic is stimulated, besides the effect on the blood vessels, there is *dilatation of the pupil*, as well as contraction of the *smooth muscular fibres* in the orbit and eyelids. The membrana orbitalis, which separates the orbit from the temporal fossa in animals, contains numerous smooth muscular fibres (*muscular orbitalis*). The corresponding membrane of the nferior orbital fissure [spheno-maxillary fissure] in man has a layer of smooth muscle, one millimetre thick, and arranged for the most part longitudinally. Both *eyelids* contain smooth muscular fibres which serve to close them; in the upper lid they lie as if they were a continuation of the levator palpebræ superioris; in the lower lid they close under the conjunctiva. *Tenon's capsule* also contains smooth muscular fibres. The sympathetic nerve supplies all these muscles (*Heinr. Müller*) —(the orbital muscle is partly supplied from the spheno-palatine ganglion); in animals, the retractor of the third eyelid at the inner angle of the eye is similarly supplied. Hence, *stimulation of the sympathetic* causes dilatation of the pupil and of the palpebral fissure, with protrusion of the eyeball. This result may be caused reflexly by strong stimulation of sensory nerves. Strong stimulation of the nerves of the sexual organs is followed by similar phenomena in the eye. The dilatation of the pupil, which occurs in children affected with intestinal worms, is perhaps an analogous phenomenon. The pupil is dilated when the spinal cord is stimulated (at the origin of the sympathetic), as in tetanus.

Section of the sympathetic, besides other effects, causes narrowing of the fissure between the eyelids, the eyeball sinks in its socket (and in animals, the third eyelid is relaxed and protruded). In dogs, section causes internal squint, as the external rectus receives some motor fibres from the sympathetic. (Origin of these fibres from the cilio-spinal region. *Spinal Cord*, § 362, 1.)

5. It is probable that **trophic fibres** occur in the trigeminus, and pass through the ciliary nerves to reach the eye. If the trigeminus be divided within the cranium, after six to eight days, inflammation, necrosis of the cornea, and ultimately complete destruction of the eyeball, take place, constituting **panophthalmia** (*Fodèra*, 1823; *Magendie*).

Trophic Fibres.—In weighing the evidence for and against the existence of trophic fibres, we must bear in mind the following considerations: 1. **Section of the trigeminus** makes the whole **eye insensible**; the animal is therefore unconscious of direct injury to its eye, and cannot therefore remove any offending body. Dust or mucus, which may adhere to the eye, is no longer removed by the reflex closing of the eyelids; while, owing to the absence of the reflex, the eye is more open and is therefore subject to more injuries; the reflex secretion of tears is also arrested. Snellen (1857) fixed the ear of a rabbit in front of its eye so as to protect the latter and shield it from injuries, and he found that the inflammation and other events occurred at a later date, while, according to Meissner and Büttner, if the eye be protected by means of a complete capsule, the inflammation does not occur at all. There can be no doubt that the loss of the sensibility of the eye favors the occurrence

of inflammation. But Meissner, Büttner, and Schiff observed that inflammation of the eye occurred when the **trophic** (most internal) fibres alone were divided, the eye at the same time retaining its sensibility; this would seem to indicate the existence of trophic fibres, but Cohnheim and Senfileben dispute the statement. Conversely, the sensibility of the eye may be abolished by partial section of the nerve, yet the eye does not become inflamed (*Schiff*). Ranvier, who denies the existence of trophic nerves, made a circular incision round the margin of the cornea through its superficial layers, so as to divide all the corneal nerves. Insensibility of the cornea was thereby produced, but never keratitis. Further, in man and animals, when they are unable to close their eyelids, there is redness with secretion of tears, or slight dryness and opacity of the surface of the eyeball (**xerosis**), but never the inflammation already described (*Samuel*). 2. We must also take into consideration the following: Section of the trigeminus paralyzes the vasomotor nerves in the interior of the eyeball, which must undoubtedly cause a disturbance in the intra-ocular circulation. According to Jesner and Grünhagen, the trigeminus also contains *vaso-dilator fibres*, whose stimulation is followed by increased flow of blood to the eye, with consecutive excretion of the fibrin factors and increase in the amount of albumin of the aqueous humor. 3. After section of the nerve, the **intra-ocular tension is diminished** (while stimulation of the nerve is followed by increase of the intra-ocular pressure) (*Hippell, Grünhagen*). This diminution of the normal tension necessarily must alter the normal relation of the filling of the blood and lymph vessels, and also the movement of the fluids, upon which the normal nutrition is largely dependent. 4. Kühne observed that stimulation of the corneal nerves was followed by contraction of the so-called corneal corpuscles. Perhaps the movements of these corpuscles may influence the normal movement of the lymph in the canalicular system of the cornea (§ 384); these movements, however, would seem to depend upon the nervous system, so that its destruction is likely to produce disturbance of nutrition.

[There are **three** conditions on which the changes may depend: (1) mere loss of sensibility, which alone is not sufficient to explain the phenomena; (2) vasomotor disturbance, which is excluded by the above facts, and also by the other consideration that, if the fifth nerve be divided and the superior cervical ganglion excised simultaneously, ophthalmia does not occur, and, in fact, excision of this sympathetic ganglion may modify the results of section of the fifth (*Sinitzin*). Thus we are forced to (3) the theory of trophic fibres, whose centre is the Gasserian ganglion.]

Pathological.—In cases of anæsthesia of the trigeminus in man, and, more rarely, in severe irritation of this nerve, inflammation of the conjunctiva, ulceration and perforation of the cornea, and finally panophthalmia, have been observed (*Charles Bell*). This condition has been called **ophthalmia neuro-paralytica**. Samuel found that a similar result was produced by electrical stimulation of the Gasserian ganglion in animals.

There are other affections of the eye depending upon disease of the **vasomotor nerves**, which are quite different from the foregoing, as they never lead to degenerative changes. Such is **ophthalmia intermittens** (due to malaria), a unilateral, intermittent, excessive filling of the blood vessels of the eye, accompanied by the secretion of tears, photophobia, often accompanied by iritis and effusion of pus into the chambers of the eye. This condition is regarded as a vaso-neurotic affection of the ocular blood vessels by Eulenburg. Pathological observations, as well as experiments upon animals, have shown that there is an intimate physiological connection between the vascular areas of both eyes, so that affections of the vascular area of one eye are apt to induce similar disturbances of the opposite eye. This serves to explain the fact that inflammatory processes in the interior of one eyeball are apt to produce a similar condition in the other eye. This is the so-called "**sympathetic ophthalmia.**" Thus stimulation of the ciliary nerves, or the fifth on *one* side, causes dilatation of the blood vessels not only on its own side, but also on the other side as well (*Jesner and Grünhagen*). The pathological condition of **glaucoma simplex**, where the intra-ocular tension is greatly increased, is ascribed by Donders to irritation of the trigeminus. [Increased intra-ocular tension may be produced by irritation of the secretory fibres contained in the fifth nerve (*Donders*), by stimulating the nucleus of the trigeminus in the medulla oblongata (*Hippell and Grünhagen*), and also reflexly by irritation of the peripheral branches of the fifth, as by nicotin placed in the eye. It is possible, however, that some forms of glaucoma are produced by diminished removal of the aqueous humor from the eye.] Unilateral secretion of tears, due to irritation of the ophthalmic division of the fifth, has been repeatedly observed, but unilateral cessation of tears, due to paralytic conditions, very rarely.

II. Superior Maxillary Division (Fig. 429, *e*).—It gives off—

1. The delicate **recurrent nerve**, a **sensory** branch to the dura mater, which accompanies the **vasomotor** nerves, derived from the superior cervical ganglion of the sympathetic, and is distributed to the area of the middle meningeal artery.

2. The **subcutaneous malar** or orbital (*o*) supplies by its temporal and orbital branches **sensibility** to the lateral angle of the eye and the adjoining area of skin of the temple and cheek. Certain fibres are said to be the true secretory nerves for tears. Compare N. lacrimalis, p. 641.

3. The **dental**, anterior, posterior, and median, and with them the anterior fibres from the infra-orbital nerve, supply **sensory** fibres to the teeth in the upper jaw, the gum, periosteum, and the cavities of the jaw (p. 642). The vasomotor nerves of all these parts are supplied from the upper cervical ganglion of the sympathetic.

4. The **infra-orbital** (R), after its exit from the infra-orbital foramen, supplies **sensory** nerves to the lower eyelid, the bridge and sides of the nose, and the upper lip as far as the angle of the mouth. The accompanying artery receives its vasomotor fibres from the superior cervical ganglion of the sympathetic. For the **sweat-secreting** fibres which occur in it (pig) see § 288.

The **spheno-palatine ganglion** (**Meckel's**—*n*) forms connections with the second division. To it pass two short **sensory** root fibres from the second division itself, which are called *spheno-palatine*. **Motor** fibres enter the ganglion from behind, through the large superficial petrosal branch of the facial (*f*); and gray **vasomotor** fibres (*v*) from the sympathetic plexus on the carotid (the deep large petrosal nerve). The motor and vasomotor fibres from the Vidian nerve, which reach the ganglion through the canal of the same name.

Branches of the Ganglion.—(1) The **sensory** fibres (N) which supply the roof, lateral walls, and septum of the nose (posterior and superior nasal); the terminal fibres of the *naso-palatine* pass through the canalis incisivus to the hard palate, behind the incisor teeth. The sensory inferior and posterior nasals for the lower and middle turbinated bones, and both lower nasal ducts, are derived from the *anterior* palatine branch of the ganglion, which descends in the palato-maxillary canal. Lastly, the sensory branches for the hard (*p*) and soft palate (p_1), and the tonsils arise from the *posterior* palatine nerve. All the sensory fibres of the nose (see also the *Ethmoidal nerve*), when stimulated, cause the reflex act of **sneezing** (§ 120). Preparatory to the act of sneezing, there is always a peculiar feeling of tickling in the nose, which is perhaps due to dilatation of the nasal blood vessels. This dilatation is rapidly caused by cold, more especially when it is applied directly to the skin. The dilatation of the vessels is followed by an increased secretion of watery fluid from the nasal mucous membrane. Stimulation of the nasal nerves also causes a reflex secretion of **tears**, and it may also cause standstill of the respiratory movements in the expiratory phase (*Hering and Kratschmer*)—(compare *Respiratory centre*, § 368). (2) The **motor** branches descend in the posterior palatine nerve through the small palatine canal, and give off (*h*) motor branches to the elevator of the soft palate and azygos uvulæ (*Nuhn*) The sensory fibres for these muscles are supplied by the trigeminus. According to Politzer, spasmodic contraction of these muscles occasionally causes crackling noises in the ears. (3) The **vasomotor** nerves of this entire area arise from the sympathetic root, *i. e.*, from the upper cervical ganglion. (4) The root of the trigeminus supplies the **secretory** nerves of the mucous glands of the nasal mucous membrane. Stimulation excites secretion, while section of the trigeminus diminishes it with simultaneous atrophic degeneration of the mucous membrane. Thus, **trophic** functions for the mucosa have been ascribed to the trigeminus (*Aschenbrandt*).

Stimulation of the Ganglion.—Feeble electrical stimulation of the exposed ganglion causes a copious secretion of mucus and an increase of the temperature in the nose (*Prévost*), with dilation of the vessels (*Aschenbrandt*). [Meckel's ganglion has been excised in certain cases of neuralgia (*Walsham*).]

III. Inferior Maxillary (g).—It contains all the **motor** fibres of the fifth, along with a number of **sensory** fibres; it gives off—

1. The **recurrent**, which springs by itself from the *sensory* root, enters the skull through the foramen spinosum, and, along with the nerve of the same name from the II division, supplies **sensory** fibres to the dura mater. Fibres proceed from it through the petroso-squamosal fissure to the mucous membrane of the cells of the mastoid process.

2. **Motor** fibres for the muscles of mastication, viz., the masseteric, the two

deep temporal nerves, and the internal and external pterygoid nerves. The sensory fibres for the muscles are supplied by the sensory fibres.

3. The **buccinator** is a *sensory* nerve for the mucous membrane of the cheek, and the angle of the mouth as far as the lips.

According to Jolyet and Laffont, it contains, in addition, vasomotor fibres for the mucous membrane of the cheek, lower lip, and their mucous glands; but these fibres are probably derived from the sympathetic.

Trophic Fibres.—As this region of the mucous membrane of the mouth ulcerates after section of the trigeminus, some have supposed that the buccinator nerve contains **trophic** fibres. But, as Rollett pointed out, section of the inferior maxillary nerve paralyzes the muscles of mastication on the same side, and hence the teeth do not act vertically upon each other, but press against the cheek. Owing to the loss of the sensibility of the mouth, food passes between the gum and the cheek, where it may remain attached, undergo decomposition, and perhaps chemically irritate the mucous membrane. At a later stage, owing to the wearing away of the teeth in an oblique manner, ulcers begin to form on the *sound* side. Hence, there is no necessity for assuming the existence of trophic fibres in this nerve. After section of the trigeminus, the nasal mucous membrane on the same side becomes red and congested. This is due to the fact that dust or mucus, not being removed from the nose by the usual reflex acts, remains there, irritates, and ultimately causes inflammation.

4. The **lingual** (*k*) receives at an acute angle the chorda tympani (*i i*), a branch of the facial coming from the tympanic cavity. The lingual does not contain any motor fibres; it is the **sensory** and **tactile** nerve of the anterior two-thirds of the tongue, of the anterior palatine arch, the tonsil, and the floor of the mouth. These, as well as all the other sensory fibres of the mouth, when stimulated, cause a reflex **secretion of saliva** (compare § 145). The lingual is accompanied by the *nerve of taste* (chorda) for the tip and margins of the tongue (*i. e.*, the parts not supplied by the glosso-pharyngeal). After section of the lingual nerve in man, Busch, Inzani, and Lusanna found that the tactile sensibility was lost in the half of the tongue, and there was loss of taste in the anterior part [two-thirds] of the tongue. The fibres which administer to the sense of taste do not, as a rule, belong to the lingual itself, but are derived from the *chorda tympani* (p. 650). According to Schiff, the lingual nerve is the gustatory nerve, and some cases of Erb and Senator support this view. Such cases, however, seem to be exceptions to the general rule. The lingual nerve in the substance of the tongue is provided with small ganglia (*Remak*, *Stirling*). Schiff observed that section of the lingual (and also of the hypoglossal) caused *redness of the tongue*, so that vasomotor fibres are present in its course. It is unknown whether these are derived from the anastomoses of the Gasserian ganglion with the sympathetic. The lingual appears to receive **vaso-dilator fibres** from the chorda for the tongue and gum (§ 349).

After section of the trigeminus, animals frequently bite their tongue, as they cannot feel the position and movements of this organ in the mouth.

5. The **inferior dental** is the **sensory** branch to the teeth and gum; the vasomotor fibres reach it from the superior cervical ganglion. Before it passes into the canal in the lower jaw, it gives off the **mylo-hyoid nerve**, which supplies **motor** fibres to the mylo-hyoid and the anterior belly of the digastric, and also some fibres to the triangularis menti and the platysma; the **muscular sensory nerves** also lie in these branches. The mental nerve, which issues from the mental foramen, is the *sensory* nerve for the chin, lower lip, and the skin at the margin of the jaw.

6. The **auriculo-temporal** gives **sensory** branches to the anterior wall of the external auditory meatus, the tympanic membrane, the anterior part of the ear, the adjoining region of the temple, and to the maxillary articulation.

Fig. 430 shows the distribution of the branches of the trigeminus on the head, and the cervical nerves, so that the distribution of anæsthetic and hyperæsthetic areas may easily be made out.

The **otic ganglion** (*m*) lies beneath the foramen ovale on the inner side of the third division. Its **roots** are—(1) short **motor** fibres from the third division; (2) **vasomotor** from the plexus around the middle meningeal artery (ultimately

derived from the cervical ganglion of the *sympathetic*); (3) fibres (λ) run from the tympanic branch of the glosso-pharyngeal to the tympanic plexus, and from thence through the canaliculus petrosus in the small superficial petrosal in the cranium, then through a small canal between the apex of the petrous bone and the sphenoid, to reach the otic ganglion. Through the chorda tympani the facial nerve is constantly connected with the ganglion (Fig. 430).

The **branches** of the otic ganglion are—(1) **motor** twigs for the tensor tympani and tensor of the soft palate (these fibres are mixed with muscular sensory fibres—*Ludwig and Politzer*); (2) one or more branches connecting the ganglion with the

FIG. 430.



Distribution of the sensory nerves on the head as well as the position of the motor points on the neck. *SO*, area of distribution of the supra-orbital nerve; *ST*, supra-trochlear; *IT*, infra-trochlear; *L*, lachrymal; *N*, ethmoidal; *IO*, infra-orbital; *B*, buccinator; *SM*, subcutaneus malæ; *AT*, auriculo-temporal; *AM*, great auricular; *OMj*, great occipital; *OMi*, lesser occipital; C_3, three cervical nerves; *CS*, cutaneous branches of the cervical nerves; *CW*, region of the central convolutions of the brain; *SC*, region of the speech centre (third left frontal convolution).

auriculo-temporal are carried by the roots 2 and 3 from the sympathetic and glosso-pharyngeal, which the auriculo-temporal nerve (A), as it passes through the parotid gland (P), gives off to the gland. These are the **secretory** fibres for the parotid; their functions are stated in § 145.

Section of the trigeminus is followed by inflammatory changes in the tympanic cavity (rabbit); the degree of inflammation varies much (*Berthold and Grünhagen*). Section of the sympathetic or glosso-pharyngeal has no effect.

The **submaxillary ganglion** (Fig. 429, L) lies close to the convex arch of the

tympanico-lingual nerve and the excretory duct of the sub-maxillary gland (M). Its **roots** are—(1) branches of the **chorda tympani**, *i i*, which undergo fatty degeneration after section of facial nerve. This root supplies **secretory** fibres to the sub-maxillary and sub-lingual glands, but it also supplies **vaso-dilator** fibres for the blood vessels of the same glands (§ 145). In addition, fibres are supplied to the smooth muscular fibres in Wharton's duct. All the fibres of the chorda do not pass into the gland; some pass along with the lingual nerve into the tongue (see *Chorda*, under *Facial Nerve*). (2) The **sympathetic** root of the ganglion arises from the plexus around the sub-mental branch of the external maxillary artery (*q*), *i. e.*, ultimately from the superior cervical ganglion; it passes to the gland, and contains **secretory** fibres, whose stimulation is followed by the secretion of thick concentrated saliva (**trophic** nerve of the gland). It also carries the vaso-constrictor nerves to the gland (p. 256). (3) The **sensory** root springs from the lingual. Some of the fibres, after passing through the ganglion, supply the gland and its excretory ducts, while a few issue from the ganglion, and again join the tympanico-lingual nerve to reach the tongue.

Pathological.—Trismus, or *spasm of the muscles of mastication*, supplied by the third division, is usually bilateral; it may be **clonic** in its nature (chattering of the teeth), or **tonic**, when it constitutes the condition of lockjaw or trismus. The spasms are usually individual symptoms of more extensive convulsions; more rarely when they occur alone, they are symptomatic of disease of the cerebrum, medulla, pons, and cortex of the motor convolutions (*Eulenburg*). The spasms may be caused reflexly, *e. g.*, by stimulation of the sensory nerves of the head.

Paralysis.—Degeneration of the motor nuclei, or an affection of the intra-cranial root of the nerve, causes paralysis of the muscles of mastication, which is very rarely bilateral. Paralysis of the tensor tympani is said to cause difficulty of hearing (*Romberg*), or buzzing in the ears (*Benedict*). We require further observations upon this point, as well as upon paralysis of the tensor of the soft palate.

Neuralgia may occur in all the branches of the fifth. It consists of severe attacks of pain shooting into the expansions of the nerves. It is usually unilateral, and in fact is often confined to one branch, or even to a few twigs of one branch. The point from which the pain proceeds is frequently the bony canal through which the branch issues. The ear, dura mater, and tongue are rarely attacked. The attack is not unfrequently accompanied by contractions or twitchings of the corresponding group of the facial muscles. The twitchings are either reflex, or are due to direct peripheral irritation of the fibres of the facial nerve, which are mixed with the terminal branches of the trigeminus. The reflex twitchings may be extensively distributed, involving even the muscles of the arm and trunk.

Redness or congestion of the affected part of the face is not an unfrequent symptom in neuralgia, and it may be accompanied by increased or diminished secretion from the nasal and buccal mucous membranes. This is a reflex phenomenon, the sympathetic being affected. Reflex stimulation of the vasomotor nerves frequently give rise to *disturbance of the cerebral activities*, owing to changes in the distribution of the blood in the head. Ludwig and Dittmar found that stimulation of sensory nerves caused a reflex contraction of the arterial blood vessels, and increase of the blood pressure in the cerebral vessels. Sometimes there is melancholy or hypochondriasis, and in one case of violent pain in the inferior maxillary nerve, the attack was accompanied by hallucinations of vision.

The **trophic disturbances** which sometimes accompany affections of the trigeminus are particularly interesting. They are: a brittle character of the **hair**, which frequently becomes gray, or may fall out; circumscribed areas of **inflammation of the skin**, and the appearance of a vesicular eruption upon the face [often following the distribution of certain nerves], and constituting **herpes**, which may also occur on the cornea, constituting the neuralgic **herpes corneæ** of Schmidt-Rimpler. Lastly, there is the progressive **atrophy of the face** which is usually confined to one side, but may occur on both sides (*Eulenburg*). It is caused very probably by a trophic affection of the trigeminus, although the vasomotor nerves may also be affected reflexly. Landois found that in the famous case of Romberg, a man named Schwahn, the sphygmographic tracing of the carotid pulse of the atrophied side was distinctly smaller than on the sound side.

Urbantschitsch made the remarkable observation that stimulation of the branches of the trigeminus, especially those going to the ear, caused an **increase of the sensation of light** in the person so stimulated. Blowing upon the cheeks or nasal mucous membrane, electrical stimulation, the use of snuff, smelling strong perfumes—all temporarily increase the sensation of light. The senses of taste and smell, as well as the sensibility of certain areas of the skin, can all be exalted *reflexly* by gentle stimulation of the trigeminus. In intense affections of the ear, whereby the fibres of the trigeminus are often affected sympathetically, these sensory functions may be diminished. As the ear malady begins to improve, the excitability of these sense organs also again begins to improve.

[**Complete section of the trigeminus** results in loss of sensibility in all the

parts supplied by it (Fig. 430), including one side of the face, temple, part of the ear, the fore part of the head, conjunctiva, cornea, mouth, gums, Schneiderian mucous membrane, anterior two-thirds of the tongue, and part of pharynx. In drinking from a vessel, the patient feels as if one side of it were cut away. The muscles of mastication are paralyzed on that side, food is not chewed on one side, and fur accumulates on the tongue on that side. The mucous membranes tend to ulcerate, that of the mouth being chafed by the teeth, the gums get spongy, the nasal mucous membrane tends to ulcerate, so that smelling is interfered with, and ammonia excites no reflex acts, while the eye undergoes panophthalmia.]

[Gowers is of opinion that the sensation of taste on the posterior part of the tongue, soft palate, and palatine arch depends on the fifth nerve and not on the glosso-pharyngeal nerve.]

348. **VI. NERVUS ABDUCENS.—Anatomical.**—It arises slightly in front of and partly from the nucleus of the *facial nerve* (which corresponds to the anterior horn of the spinal cord), from large celled ganglia in the deeper part of the anterior region of the fourth ventricle (emenentia teres, Fig. 427). [Its nucleus is connected with the nucleus of the third nerve of the opposite side. It appears at the posterior margin of the pons (Fig. 428, VI). This nerve has a very long course before it enters the orbit, and as it bends over the posterior margin of the pons, it is liable to be compressed there or from pressure upon the tentorium cerebelli, so that both nerves are very liable to paralysis.]

Function.—It is the voluntary nerve of the external rectus muscle. In coördinated movements of the eyeballs, however, it is involuntary.

Anastomoses.—Branches reach it from the sympathetic upon the cavernous sinus (Fig. 429). A few come from the trigeminus, and their function is analogous to similar fibres supplied to the trochlearis and oculomotorius.

Pathological.—Complete **paralysis** causes squinting inward [or *convergent squint*] and consequent diplopia. [The eye cannot be rotated outward beyond the middle line, the double images are in the same horizontal plane and vertical, the false one is to the left of the patient's eye when the left eye is affected (Fig. 426, 2). The feeling of giddiness is often severe. There is secondary deviation to the inner side, and the head is turned toward the affected side.] In dogs, section of the cervical sympathetic causes a slight deviation of the eyeball inward (*Petit*). This is explained by the fact that the abducens receives a few motor fibres from the cervical sympathetic. **Spasm** of the abducens causes external squint.

Squint.—In addition to paralysis or stimulation of certain nerves producing squint, it is to be remembered that it may also be caused by a primary affection of the muscles themselves, *e. g.*, congenital shortness, contracture, or injuries of these muscles. It may also be brought about owing to *opacities* of the transparent media of the eye; a person with, say an opacity of the cornea, rotates the affected eye involuntarily, so that the rays of light may enter the eye through a clear part of the media.

349. **VII. NERVUS FACIALIS.—Anatomical.**—This nerve consists entirely of efferent fibres, and arises from the floor of the fourth ventricle from the "**facial nucleus**" (Fig. 427, 7), which lies behind the origin of the abducens, and also by some fibres from the nucleus of the abducens [although Gowers' observations do not confirm this (§ 366)]. Other fibres arise from the cerebrum of the opposite side (§ 378, I). It consists of two roots, the smaller—**portio intermedia** of Wrisberg—forms a connection with the auditory nerve (see § 350). The original fibres of the portio intermedia are developed from the glosso-pharnygeal nucleus (*Sapolini*). It would thus appear that the sensory and gustatory fibres which are present in the chorda tympani enter it through these fibres (*Duval, Schultze, Vulpian*), so that the portia intermedia is a special part of the nerve of taste, which becomes conjoined with the facial, and runs to the tongue in the chorda. Along with the auditory nerve, it traverses the porus acusticus internus, where it passes into the facial or Fallopian canal. At first it has a transverse direction as far as the hiatus of this canal; it then bends at an acute angle at the "**knee**" (*a*) above the tympanic cavity, to descend in an osseous canal in the posterior wall of this space (Fig. 429). It emerges from the stylo-mastoid foramen, pierces the parotid gland, and is distributed in a fan-shaped manner (pes anserinus major). [The superficial origin is at the lower margin of the pons, in the depression between the olivary body and the restiform body, as indicated in Fig. 428, VII *a*.]

Its **branches** are: 1. The **motor large superficial petrosal** (*j*). It arises from the "knee" or geniculate ganglion within the Fallopian canal, in the cavity of the skull, runs upon the anterior surface of the temporal bone, traverses the foramen lacerum medium on the under surface of the base of the skull, and passes through the Vidian canal to reach the spheno-palatine ganglion (p. 645). It is

uncertain whether this nerve conveys **sensory** branches from the second division of the trigeminus to the facial.

2. Connecting branches (β) pass from the geniculate ganglion to the otic ganglion. For their course and function, see *Otic ganglion* (p. 646).

3. The **motor** branch to the **stapedius** muscle (γ).

4. The **chorda tympani** (*i i*) arises from the facial before it emerges at the stylo-mastoid foramen (δ), runs through the tympanic cavity (above the tendon of the tensor tympani, between the handle of the malleus and the long process of the incus), passes out of the skull through the petro-tympanic fissure, and then joins the lingual nerve at an acute angle (p. 646, 4). Before it unites with this nerve, it exchanges fibres with the otic ganglion (*m*). Thus, **sensory** fibres can enter the chorda from the third division of the trigeminus, which may run centripetally to the facial to be distributed along with it. In the same way, sensory fibres may pass from the lingual nerve through the chorda into the facial (*Longet*). Stimulation of the chorda—which even in man may be done in cases where the tympanic membrane is destroyed—causes a prickling feeling in the anterior margins and tip of the tongue (*Tröltsch*). O. Wolfe found that the section of the chorda in man abolished the sensibility for **tactile** and **thermal** stimuli upon the tip of the tongue; and the same was true of the sense of **taste** in this region. It is supposed by Calori, that these fibres enter the facial nerve at its periphery (especially through the auriculo-temporal into the branches of the facial), that they run in a centripetal direction in the facial, and afterward pursue a centrifugal course in the chorda. [It is possible that sensory fibres pass from the spheno-palatine ganglion of the fifth through the Vidian nerve and large superficial petrosal to enter the facial. These fibres may be those that appear in the seventh as the chorda fibres which administer to taste. Bigelow asserts that the chorda tympani is not a branch of the facial, but the continuation of the nervus intermedius of Wrisberg.] The chorda also contains **secretory** and **vaso-dilator** fibres for the sub-maxillary and sub-lingual glands (§ 145).

Gustatory Fibres.—The chorda also contains fibres administering to the sense of **taste,** for the margin and tip of the tongue (anterior two-thirds), which are conveyed to the tongue along the course of the lingual. Urbantschitsch made observations upon a man whose chorda was freely exposed, and in whom its stimulation in the tympanic cavity caused a sensation of taste (and also of touch) in the margins and tip of the tongue.

It would seem, therefore, that the **gustatory fibres of the chorda** have their origin in the glosso-pharyngeal nerve. They may reach the chorda: 1. Through the portio intermedia of Wrisberg, as already mentioned.

2. There is a channel beyond the stylo-mastoid foramen, viz., through the ramus communicans cum glosso-pharyngeo (Fig. 429), which passes from the last mentioned nerve in that branch of the facial which contains the motor fibres for the stylo-hyoid and posterior belly of the digastric muscle (Henle's N. styloideus). This nerve also supplies muscular sensibility to the stylo-hyoid and posterior belly of the digastric muscles. It is also assumed that, by means of these anastomoses, motor fibres are supplied by the facial to the glosso-pharyngeal nerve. 3. A union of the glosso-pharyngeal and facial nerves occurs in the tympanic cavity. The tympanic branch of the glosso-pharyngeal (λ) passes into this cavity, where it unites in the tympanic plexus with the small superficial petrosal nerve (β), which springs from the knee on the facial. The gustatory fibres may first pass into the otic ganglion, which is always connected with the chorda (Otic ganglion, p. 647, 3). Lastly, a connection is described through a twig (π) from the petrous ganglion of the glosso-pharyngeal, direct to the facial trunk within the Fallopian canal (*Garibaldi*).

According to some observers, the chorda contains **vaso-dilator fibres** for the anterior two-thirds of the tongue (*Vulpian*).

Pseudo-motor Action.—From one to three weeks after the section of the hypoglossal nerve, stimulation of the chorda causes movements in the tongue (*Philippeaux and Vulpian*). These movements are not so energetic as, and occur more slowly than, those caused by stimulation of the hypoglossal. *Nicotin* first excites, then paralyzes, the motor effect of the chorda. Even after cessation of the circulation, stimulation of the chorda causes movements. Heidenhain supposes

that, owing to the stimulation of the chorda, there is an increased secretion of lymph within the musculature, which acts as the cause of the muscular contraction. He called this action "*pseudo-motor*."

[If, after the union of the central end of the lingualis and the peripheral end of the hypoglossal nerve, the lingualis be stimulated, there is a genuine contraction of the musculature of the tongue, on that side. A pseudo-motor contraction is easily distinguished from a true contraction, for when a telephone is connected with the tongue, on stimulating the hypoglossal the tone of the tetanus thereby produced is heard, but on stimulating the lingual, although the pseudo-motor contractions occur, no sound is heard (*Rogowicz*).]

5. **Connection with Vagus.**—Before the chorda is given off, the trunk of the facial comes into direct relation with the auricular branch of the vagus (δ), which crosses it in the mastoid canal, and supplies it with sensory nerves (see *Vagus*).

6. **Peripheral Branches.**—After the facial issues from its canal, it supplies **motor** fibres to the stylo-hyoid and posterior belly of the digastric, occipitalis, all

FIG. 431.



Motor points of the facial nerve and the facial muscles supplied by it.

the muscles of the external ear, the muscles of expression, buccinator and platysma. The facial also contains **secretory** fibres for the face (compare § 288).

Although most of the branches of the facial are under the influence of the will, yet most men cannot voluntarily move the muscles of the nose and ear.

Anastomoses.—The branches of the seventh nerve on the face anastomose with those of the trigeminus, whereby sensory fibres are conveyed to the muscles of expression. The sensory branches of the auricular branch of the vagus, and the great auricular, enter the peripheral ends of the facial, and supply sensibility to the muscles of the ear; while the sensory fibres of the third cervical nerve similarly supply the platysma with sensibility. Section of the facial at the stylo-mastoid

foramen is painful, but it is still more so if the peripheral branches on the face are divided (*Recurrent sensibility*, § 355).

Pathological.—In all cases of **paralysis of the facial**, the most important point to determine is whether the **seat of the affection** is in the periphery, in the region of the stylo-mastoid foramen, or in the course of the long Fallopian canal, or is central (cerebral) in its origin. This point must be determined by an analysis of the symptoms. Paralysis at the stylo-mastoid foramen is very frequently **rheumatic**, and probably depends upon an exudation compressing the nerve; the exudation probably occupying the lymph space described by Rüdinger on the inner side of the Fallopian canal, between the periosteum and the nerve, and which is a continuation of the arachnoid space. Other causes are—inflammation of the parotid gland, direct injury, and pressure from the forceps during delivery. In the **course of the canal**, the causes are—fracture of the temporal bone, effusion of the blood into the canal, syphilitic effusions, and caries of the temporal bone; the last sometimes occurs in inflammation of the ear. Among **intra-cranial** causes are—affections of the membranes of the brain, and of the base of the skull in the region of the nerve, disease of the "**facial nucleus**"; lastly, affection of the cortical centre of the nerve and its connections with the nucleus. [No nerve is so liable as the seventh to be paralyzed independently.]

Symptoms of Unilateral Paralysis of the Facial [or Bell's Paralysis].—**1.** Paralysis of the **muscles of expression**: The forehead is smooth, without folds, the eyelids remain open (**lagophthalmus paralyticus**), the outer angle being slightly lower. The anterior surface of the eye rapidly becomes dry, the cornea is dull, as, owing to the paralysis of the orbicularis, the tears are not properly distributed over the conjunctiva, and, in fact, in consequence of the dryness of the eyeball, there may be temporary inflammation (**keratitis xerotica**). In order to protect the eyeball from the light, the patient turns it upward under the upper eyelid (*Bell*), relaxes the levator palpebræ, which allows the lid to fall somewhat (*Hasse*). The nose is immovable, while the naso-labial fold is obliterated. As the nostrils cannot be dilated, the sense of smell is interfered with. The impairment of the **sense of smell** depends more, however, upon the imperfect conduction of the tears, owing to paralysis of the orbicularis palpebrarum and Horner's muscle, thus causing dryness of the corresponding side of the nasal cavity. Horses, which distend the nostrils widely during respiration, after section of both facial nerves, are said by Cl. Bernard to die from interference with the respiration, or at least they suffer from severe dyspnœa (*Ellenberger*). The face is drawn toward the sound side, so that the nose, mouth, and chin are oblique. Paralysis of the buccinator interferes with the proper **formation of the bolus** of food; the food collects between the cheek and the gum, from which it is usually removed by the patient with his fingers; saliva and fluids escape from the angle of the mouth. During vigorous expiration, the cheeks are puffed outward like a sail. The **speech** may be affected owing to the difficulty of sounding the **labial consonants** (especially in double paralysis), and the vowels, u, ü (ue) ö (oe); while the speech, in paralysis of the branches to both sides of the palate, becomes nasal (§ 628). The acts of whistling, sucking, blowing, and spitting are interfered with. **In double paralysis**, many of these symptoms are greatly intensified, while others, such as the oblique position of the features, disappear. The features are completely relaxed; there is no mimetic play of the features; the patients weep and laugh, "as it were, behind a mask" (*Romberg*). **2.** In **paralysis of the palate**, when the uvula is directed toward the sound side, and the paralyzed half of the palate hangs down and cannot be raised (large superficial petrosal nerve), it is not determined to what extent this condition influences the *act of deglutition* and the *formation of the consonants*. **3. Taste** is interfered with; either it is absent on the anterior two-thirds of the tongue, or the sensation is delayed and altered. This is due to an affection of the chorda. **4. Diminution of saliva** on the affected side was first described by Arnold; still, we must determine to what extent a simultaneous affection of the sense of taste may cause a reflex interference with the secretion of saliva, or whether rapid removal of the saliva through the opened lips and angle of the mouth may cause the dryness on the affected side of the mouth. **5.** Roux pointed out that **hearing** is affected, the *sensibility to sounds* being increased (**oxyakoia, hyperakusis willisiana**). The paralysis of the stapedius muscle makes the stapes loose in the fenestra ovalis, so that all impulses from the tympanum act vigorously upon the stapes, which consequently excites considerable vibrations in the fluid of the inner ear. More rarely, in paralysis of the stapedius, it has been observed that low notes are heard at a greater distance than on the sound side (*Lucae, Mow*). **6.** As the facial in man appears to contain fibres for the **secretion of sweat**, this explains the loss of the power of sweating in the face when the nerve begins to atrophy (*Strauss, Bloch*).

Section of the facial in young animals causes atrophy of the corresponding *muscles*. The **facial bones** are also imperfectly developed; they remain smaller, and hence the bones of the sound side of the face grow toward, and ultimately across, the middle line toward the affected side (*Brown-Séquard*). The **salivary glands** also remain smaller.

Stimulation—or irritation in the area of the *facial*—causes partial or extensive, either direct or reflex, tonic or clonic spasms. The extensive forms are known as "**mimetic facial spasm.**" Among the partial forms are *tonic contraction of the eyelid* (**blepharospasm**), which is most common; and is caused reflexly by stimulation of the sensory nerves of the eye, *e.g.*, in scrofulous

ophthalmia, or from excessive sensibility of the retina (**photophobia**). More rarely, the excitement proceeds from some more distant part, *e.g.*, in one case recorded by v. Gräfe, from inflammatory stimulation of the anterior palatine arch. The centre for the reflex is the facial nucleus. The clonic form of spasm—*spasmodic winking* (**spasmus nictitans**)—is usually of reflex origin, due to irritation of the eye, the dental nerves, or even of more distant nerves. In severe cases, the affection may be bilateral, and the spasms may extend to the muscles of the neck, trunk, and upper extremities. Contraction of the muscles of the lip may be excited by emotions (rage, grief), or reflexly. Fibrillar contractions occur after section of the facial as a "degeneration phenomenon" (p. 525). [If the facial be torn out of the stylo-mastoid foramen, there is paralytic oscillation of the lip muscles (*Schiff*). If, in such an animal, the posterior root of the annulus of Vieussens be stimulated electrically, as it contains vaso-dilator fibres (*Dastre and Morat*), not only do the blood vessels of the cheek and lips dilate, but the veins pulsate and florid blood escapes from the veins, just as occurs in the sub-maxillary gland when the chorda is stimulated. On stimulating the ansa, after section of the seventh, there is a **pseudo-motor effect** on the muscles of the cheek and lips, so that there is an analogy between the chorda and the ansa (*Rogowicz*).] *Intra-cranial* stimulation of the most varied description may cause spasms. Lastly, facial spasm may be part of a general spasmodic condition, as in epilepsy, cholera, hysteria, tetanus. Aretæus (81 A.D.) made the interesting observation that the muscles of the ear contracted during tetanus. Very rarely have spasmodic elevation of the palate and increased salivation been described as the result of irritation of the facial (*Leube*). Moos observed a profuse secretion of saliva on stimulating the chorda during an operation on the tympanic cavity.

350. **VIII. NERVUS ACUSTICUS.**—Arises by *two roots* (*Stieda*); a larger anterior and a smaller posterior one. From the former proceeds the vestibular nerve, and from the latter the cochlear nerve; these are separated in the sheep and horse (*Horbaczewski*). Each root springs from a median and a lateral nucleus, so that there are four nuclei. Some fibres come from the cerebellum, and these may be connected with equilibration. The chief mass of the posterior ganglion fibres of the cochlear nerve cross and pass to the corpora quadrigemina, the internal geniculate, and finally to the temporo-sphenoidal lobe (§ 378, IV, 2). After extirpation of the temporo-sphenoidal lobe, these fibres atrophy into the internal capsule and internal geniculate body (*v. Monakow*). The striæ acusticæ form a second decussating projection system. The origins of both acoustic nerves are connected by commissures in the brain (*Flechsig*).

In the course of the internal auditory meatus, the auditory and portio intermedia of the facial exchange fibres, but the physiological significance of this is unknown.

Function.—The acusticus or auditory nerve has a **double function:** 1. It is the nerve of **hearing;** when stimulated, either at its origin, in its course, or at its peripheral terminations, it gives rise to *sensations of sound*. Every *injury*, according to its intensity and extent, causes hardness of hearing or even deafness.

2. Quite distinct from the foregoing is the other function, which depends upon the **semicircular canals**, viz., that stimulation of the peripheral expansions in the ampullæ influences the movements necessary for maintaining the **equilibrium** of the body.

Brenner's Formula.—The relation of the auditory nerve to the galvanic current is very important. In healthy persons, when there is closure at the cathode, there is the sensation of a *clang* (or tone) in the ear, which continues with variations while the current is closed. When the anode is opened, there is a feebler tone (*Brenner's Normal Acoustic Formula*). This clang coincides exactly with the resonance fundamental tone of the sound-conducting apparatus of the ear itself.

Pathological.—*Increased sensibility* of the auditory nerve in any part of its course, its centre, or peripheral expansions, causes the condition known as **hyperakusis**, which usually is a sign of greatly increased nervous excitability, as in hysteria. When excessive, it may give rise to distinctly painful impressions, which condition is known as **acoustic hyperalgia** (*Eulenburg*). **Stimulation** of the parts above named causes sensations of sound, the most common being the sensation of *singing in the ears*, or **tinnitus.** This condition is often due to changes in the amount of blood in the blood vessels of the ear—either anæmic or hyperæmic stimulation. There is well-marked tinnitus after large doses of quinine or salicin, due to the vasomotor effect of these drugs upon the vessels of the labyrinth (*Kirchner*). Not unfrequently, in cases of tinnitus, the reaction due to the galvanic current is increased. More rarely there is the so-called "*paradoxical reaction*"—*i.e.*, on applying the galvanic current to one ear, in addition to the reaction in this ear, there is the opposite result in the non-stimulated ear. In other cases of disease of the auditory nerve, noises rather than musical notes are produced by the current; *stimulation*, especially of the cortical centre of the auditory nerve, chiefly in lunatics, may cause **auditory delusions** (§ 378, IV.). According as the excitability of the auditory nerve is diminished or abolished, there is the condition of nervous hardness of hearing (**hypakusis**), or nervous deafness (**anakusis**).

The **Semicircular Canals of the Labyrinth.**—Section or injury to these canals does not interfere with hearing, but other important symptoms follow their injury, such as disturbances of equilibrium due to a feeling of giddiness, especially when the injury is bilateral (*Flourens*). This does not occur in fishes (*Kieselbach*). The **pendulum-like movement of the head**, in the direction of the plane of the injured canal, is very characteristic. If the *horizontal* canal be divided, the head (of the pigeon) is turned alternately to the right and left. The rotation takes place, especially when the animal is about to execute a movement: when it is at rest, the movement is less pronounced. The phenomenon may last for months, and injury to the *posterior vertical* canals causes a well-marked up and down movement or nodding of the head, the animal itself not unfrequently falling forward or backward. Injury to the *superior vertical* canals also causes pendulum-like vertical movements of the head, while the animal often falls forward. When *all the canals* are destroyed, various pendulum-like movements are performed, while standing is often impossible. Breuer found that electrical stimulation of the canals caused rotation of the head, while Landois, on applying a solution of salt to the canals, observed pendulum-like movements, which, however, disappeared after a time. A 25 per cent. solution of chloral dropped into the ear of a rabbit causes, after fifteen minutes, a similar destruction of the canals (*Vulpian*). Section of the acoustic nerves within the cranium has the same result (*Bechterew*).

Explanation.—Goltz regards the canals as organs of sense for ascertaining the equilibrium or position of the head in space; Mach, as an organ for ascertaining the movements of the head. According to Goltz's **statical theory**, every position of the head causes the endolymph to exert the greatest pressure upon a certain part of the canals, and thus excites in a varying degree the nerve terminations in the ampullæ. According to Breuer, when the head is rotated, currents are produced in the endolymph of the canals, which must have a fixed relation to the direction and extent of the movements of the head, and these currents, therefore, when they are perceived, afford a means of determining the movement of the head. The nervous end organs of the ampullæ are arranged for ascertaining this perception. If the semicircular canals are an apparatus—in fact, "sense organs"—for the sensation of the equilibrium, and if their function is to determine the position or movements of the head, necessarily their destruction or stimulation must alter these perceptions, and so give rise to abnormal movements of the head. Vulpian regards the rotation of the head as due to strong auditory perceptions (?) in consequence of affections of the canals. Böttcher, Tomaszewicz, and Baginsky regard the injury to the cerebellum as the cause of the phenomena. The pendulum-like movements, however, are so characteristic that they cannot be confounded with disturbances of the equilibrium which result from injury to the cerebellum.

[**Kinetic Theory.**—In 1875 Crum Brown pointed out that, if a person be rotated passively, his eyes being bandaged, he can, up to a certain point, indicate pretty accurately the amount of movement, but after a time, this cannot be done, and if the rotation, as on a potter's wheel, be stopped, the sense of rotation continues. Crum Brown suggested that currents were produced in the endolymph, while the terminal hair cells lagged behind, and were, in fact, dragged through the fluid. He pointed out that the right posterior canal is in line with the left superior, and the left posterior with the right superior, a fact which is readily observed by looking from behind at a skull, with the semicircular canals exposed (Fig. 432). He assumes that the canals are paired organs, and that each pair is connected with rotation or movement of the head in a particular direction.]

FIG. 432.



Diagram of the disposition of the semicircular canals. RS and LS, right and left superior; LP and RP, right and left posterior; LE and RE, right and left external.

Giddiness.—This feeling of false impressions as to the relations of the surroundings and consequent movements of the body, occurs especially during *acquired* changes in the normal movements of the eyes, whether due to involuntary to and fro movements of the eyeballs (**nystagmus**), or to paralysis of some eye muscle.

Active or passive movements of the head or of the body are normally accompanied by simultaneous movements of both eyeballs, which are characteristic for every position of the body. The general character of these "compensatory" bilateral movements of the eyes consists in this, that during the various changes in the position of the head

and body, the eyes strive to maintain their primary passive position. Section of the aqueduct of Sylvius at the level of the corpora quadrigemina, of the floor of the fourth ventricle, of the auditory nucleus, both acustici, as well as destruction of both membranous labyrinths, causes disappearance of these movements; while, conversely, stimulation of these parts is followed by bilateral associated movements of the eyeballs.

Compensatory movements of the eyeballs, under normal circumstances, may be caused reflexly from the membranous labyrinth. Nerve channels, capable of exciting reflex movements of both eyes, proceed from both labyrinths, and, indeed, both eyes are affected from both labyrinths. These channels pass through the auditory nerve to the *centre* (nuclei of the 3d, 4th, 6th, and 8th cranial nerves), and from the latter efferent fibres pass to the muscles of the eye (*Högyes*).

Cyon found that stimulation of the horizontal semicircular canal was followed by horizontal nystagmus; of the posterior, by vertical, and of the anterior canal, by diagonal nystagmus. Stimulation of one auditory nerve is followed by rotating nystagmus, and rotation of the body of the animal on its axis toward the stimulated side.

Poisons.—Chloroform and other poisons enfeeble the compensatory movements of the eyeballs, while nicotin and asphyxia suppress them, owing to their action on their nerve centre.

It is probable that the disturbances of equilibrium and the feeling of giddiness which follow the passage of a galvanic current through the head between the mastoid processes, are also due to an action upon the semicircular canals of the labyrinth (§ 300). Deviation of the eyeballs is produced by such a galvanic current (*Hitzig*). The same result is produced when the two electrodes are placed in the external auditory meatuses.

Pathological.—Menière's Disease.—The feeling of giddiness, not unfrequently accompanied by tinnitus, which occurs in Menière's disease, must be referred to an affection of the nerves of the ampullæ or their central organs, or of the semicircular canals themselves. By injecting fluid violently into the ear of a rabbit, giddiness, with nystagmus and rotation of the head toward the side operated on, are produced (*Baginsky*). In cases in man, where the tympanic membrane was defective, Lucæ, when employing the so-called ear air douche at 0.1 atmosphere, observed abduction of the eyeball with diplopia, giddiness, darkness in front of the eyes, while the respiration was deeper and accelerated. These phenomena must be due to stimulation or exhaustion of the vestibular branch of the auditory nerve (*Högyes*). In chronic gastric catarrh, a tendency to giddiness is an occasional symptom (Trousseau's gastric giddiness). This may, perhaps, be caused by stimulation of the gastric nerves exciting the vasomotor nerves of the labyrinth, which must affect the pressure of the endolymph. Analogous giddiness is excited from the larynx (*Charcot*), and from the urethra (*Erlenmeyer*).

[**Vertigo** or giddiness is a very common symptom in disease, and may be produced by a great many different conditions. It literally means "a turning." As Gowers points out, the most common symptom is that the patient himself has a sense of movement in one or other direction; or objects may appear to move before him; and more rarely there is actual movement "commonly in the same direction as the subjective sense of movement." It is sometimes due to a want of harmony between the impressions derived from different sense organs or "contradictoriness of sensory impressions (*Grainger Stewart*), as is sometimes felt on ascending or descending a stair, or by some persons while standing on a high tower, constituting tower or cliff giddiness. One of the most remarkable conditions is that called "**agoraphobia**" (*Benedikt, Westphal*). The person can walk quite well in a narrow lane or street, but when he attempts to cross a wide square, he experiences a feeling closely allied to giddiness. The giddiness of sea-sickness is proverbial, while some persons get giddy with waltzing or swinging. Besides occurring in Menière's disease, it sometimes occurs in locomotor ataxia, and some cerebral and cerebellar affections, including cerebral anæmia. Very distressing giddiness and headache are often produced by paralysis of some of the ocular muscles, *e.g.*, the external rectus. Defective or perverted ocular impressions, as well as similar auditory impressions, may give rise to vertigo; in the latter or labyrinthine form the vertigo may be very severe. Severe vertigo is often accompanied by vomiting. A hard plug of ear wax may press on the membrana tympani and cause severe giddiness. The forms of dyspeptic giddiness and the toxic forms due to the abuse of alcohol, tobacco, and some other drugs are familiar examples of this condition.]

[**Tinnitus Aurium**, or subjective noises in the ear, is a very common symptom in disease of the ear; the noise may be continuous or discontinuous, be buzzing, singing, or rumbling in character.]

351. **IX. NERVUS GLOSSO-PHARYNGEUS.—Anatomical.**—This nerve (Fig. 429, 9) arises from the nucleus of the same name, which consists partly of large cells (motor) and partly of small cells (belonging to the gustatory fibres). The nucleus lies in the lower half of the fourth

ventricle, deep in the medulla oblongata, near the olive (Fig. 427), and posteriorly it abuts on that of the vagus. The anterior part of the central nucleus is regarded as the root of the portio intermedia of the facial (§ 349). The nerve also receives fibres from the vagal centres. The fibres collect into two trunks, which afterward unite and leave the medulla oblongata in front of the vagus. In the fossula petrosa it has on it the **petrous ganglion**, from which, occasionally, a special part on the posterior twig is separated within the skull as the ganglion of Ehrenritter. *Communicating branches* are sent from the petrous ganglion to the trigeminus, facial (ε and π), vagus and carotid plexus. From this ganglion also the tympanic nerve (λ) ascends vertically in the tympanic cavity, where it unites with the tympanic plexus. This branch (§ 349, 4) gives *sensory* fibres to the tympanic cavity and the Eustachian tube; while, in the dog, it also carries secretory fibres for the parotid into the small superficial petrosal nerve (*Heidenhain*—§ 145).

Function.—1. It is the **nerve of taste** for the posterior third of the tongue, the lateral part of the soft palate, and the glosso-palatine arch (compare § 422). [This is denied by Gowers (p. 682, Am. Ed., 1888).]

The nerve of taste for the anterior two-thirds of the tongue is referred to under the lingual (§ 347, III, 4) and chorda tympani nerves (§ 349, 4). The glossal branches are provided with ganglia, especially where the nerve divides at the base of the circumvallate papillæ (*Remak, Kölliker, Stirling*). The nerve ends in the circumvallate papillæ (Fig. 429, U), and the end organs are represented by the taste bulbs (§ 422).

2. It is the **sensory nerve** for the posterior third of the tongue, the anterior surface of the epiglottis, the tonsils, the anterior palatine arch, the soft palate, and a part of the pharynx. From this nerve there may be discharged *reflexly*, movements of deglutition, of the palate and pharynx, which may pass into those of vomiting (§ 158). These fibres, like the gustatory fibres, can excite a reflex secretion of saliva (§ 145).

3. It is **motor** for the stylo-pharyngeus and middle constrictor of the pharynx (*Volkmann*); and, according to other observers, to the (?) glasso-palatinus (*Hein*) and the (??) levator veli palatini and azygos uvulæ (compare *Spheno-palatine ganglion*, § 347, II). It is doubtful whether the glosso-pharyngeal nerve is really a motor nerve at its origin—although Meynert and others have described a motor nucleus—or whether the motor fibres reach the nerve at the petrous ganglion, through the communicating branch from the facial.

4. A twig accompanies the lingual artery; this nerve, perhaps, is **vaso-dilator** for the lingual blood vessels.

Pathological.—There are no satisfactory observations on man of uncomplicated affections of the glosso-pharyngeal nerves.

352. X. NERVUS VAGUS.—Anatomical.—The nucleus from which the vagus arises along with the 9th and 11th nerve is in (1) the ala cinerea in the lower half of the calamus scriptorius (Fig. 427, 10) [and it is very probably the representative of the cells of the vesicular column of Clarke (§ 366)]. (2) Other fibres come from the "longitudinal bundle" or "respiratory bundle" lying outside the nucleus, and reaching down into the cervical enlargement. (3) A motor nucleus —the nucleus ambiguus—a prolongation of some of the cells of the anterior horn of the spinal cord, gives some motor fibres. It leaves the medulla oblongata by 10 to 15 threads behind the 9th nerve, between the divisions of the lateral column, and has a ganglion (**jugular**) upon it in the jugular foramen (Fig. 428, VIII). Its branches contain fibres which subserve different functions.

1. The **sensory meningeal** branch from the jugular ganglion accompanies the vasomotor fibres of the sympathetic on the middle meningeal artery, and sends fibres to the occipital and transverse sinus.

When it is irritated, as in congestion of the head and inflammation of the dura mater, it gives rise to *vomiting*.

2. The **auricular** branch (Fig. 433, *au.*) from the jugular ganglion receives a communicating branch from the petrous ganglion of the 9th nerve, traverses the canaliculus mastoideus, crossing the course of the facial, with which it exchanges fibres whose function is unknown. On its course, it gives **sensory** branches to the posterior part of the auditory meatus, and the adjoining part of the outer ear. A branch runs along with the posterior auricular branch of the facial, and confers **sensibility** on the muscles.

When this nerve is irritated, either through inflammation or by the presence of foreign bodies in the outer ear passage, it may give rise to *vomiting*. Stimulation of the deep part of the external auditory meatus in the region supplied by the auricular branch causes *coughing* reflexly [*e. g.*, from the presence of a pea in the ear]. Similarly, *contraction of the blood vessels of the ear* may be caused reflexly (*Snellen, Lovèn*).

The nerve is the remainder of a considerable branch of the vagus which exists in fishes and the larvæ of frogs, and runs under the skin along the side of the body.

3. The **connecting** branches of the vagus are: (1) A branch which directly connects the petrous ganglion of the 9th with the jugular ganglion of the 10th; its function is unknown. (2) Directly above the plexus gangliiformis vagi, the vagus is joined by the whole inner half of the *spinal accessory*. This nerve conveys to the vagus the **motor** fibres for the *larynx*, and the *cervical part of the œsophagus* (which, according to Steiner, lie in the inner part of the nerve trunk), as well as the **inhibitory** *fibres* for the *heart* (*Cl. Bernard*). (3) The plexus gangliiformis fibres, whose function is unknown, join the trunk of the vagus from the hypoglossal, superior cervical ganglion of the sympathetic, and the cervical plexus.

4. **Pharyngeal Plexus.**—The vagus sends one or two branches (Fig. 433, 2) from the upper part of the plexus gangliiformis to the *pharyngeal plexus*, where at the level of the middle constrictor of the pharynx, it is joined by the pharyngeal branches of the 9th nerve and those of the upper cervical sympathetic ganglion, near the ascending pharyngeal artery, to form the *pharyngeal plexus*. The vagal fibres in this plexus supply the *three constrictors of the pharynx* with **motor** *fibres*, while the tensor palati (*Otic ganglion*, § 347, III) and levator of the soft palate (compare *Spheno-palatine ganglion*, § 347, II) also receive motor (? sensory) fibres. **Sensory** fibres of the vagus from the pharyngeal plexus supply the pharynx from the part beneath the soft palate downward. These fibres excite the pharyngeal constrictors reflexly, during the act of swallowing (§ 156). If stimulated very strongly, they may cause *vomiting*. (The *sympathetic* fibres of the œsophageal plexus give vasomotor nerves to the œsophageal vessels; for the œsophageal branches of the 9th nerve, see above.)

5. The vagus supplies two branches to the larynx, the **superior** and **inferior laryngeal.**

(*a*) The **superior laryngeal** (Fig. 433, 3) receives **vasomotor** fibres from the superior cervical ganglion of the sympathetic. It divides into two branches, external and internal: (1) The **external** branch receives **vasomotor** fibres from the same source (they accompany the superior thyroid artery), and supply the crico-thyroid muscle with **motor** fibres, and **sensory** fibres to the lower lateral portion of the laryngeal mucous membrane. (2) The **internal** branch gives off *sensory* branches only to the glosso-epiglottidean fold, and the adjoining lateral region of the root of the tongue, the ary-epiglottidean fold, and to the whole anterior part of the larynx, except the part supplied by the external branch (*Longet*). Stimulation of any of these sensory fibres causes **coughing** reflexly. **Coughing** is produced by stimulation of the boundaries of the glottis respiratoria, but not of the vocal cords, and by stimulation of the sensory branches of the vagus to the tracheal mucous membrane, especially at the bifurcation, and also from the bronchial mucous membrane (*Kohts*). Coughing is also caused by stimulation of the auricular branch of the vagus, especially in the deep part of the external auditory meatus, of the pulmonary tissue, especially when altered pathologically; in pathological conditions (inflammation) of the pleura (? certain changes in the stomach [stomach cough]), of the liver and spleen (*Naunyn*). The **coughing centre** is said to lie on each side of the raphe, in the neighborhood of the ala cinerea (*Kohts*). Cases of violent coughing may, owing to stimulation of the pharynx, be accompanied by **vomiting** as an associated movement (§ 120).

In many individuals, coughing can be excited by stimulation of distant sensory nerves (§ 120, 1), *e. g.*, from the outer ear (auricular nerve), nasal mucous membrane, liver, spleen, stomach, intestine, uterus, mammæ, ovaries, and even from certain cutaneous areas (*Ebstein*). It is uncertain if these

FIG. 433.


I.
II.
O
au.
Oh
K
T
St
Cc
A
P
H
L
Nn
N
M
Symp.
Gyl. med.
Gyl. thor. pr
recurrens
vagus
depressor
accelerans
Symp.

conditions act directly upon the coughing centre, or first of all affect the vascularization and secretion of the respiratory organs, which in their turn affect the coughing centre.

The cough (dog, cat) caused by stimulation of the trachea and bronchi occurs at once, and lasts as long as the stimulus lasts; in stimulation of the larynx, the first effect is inhibition of the respiration accompanied by movements of deglutition, while the cough occurs after the cessation of the stimulation (*Kandarazky*).

The **superior laryngeal** contains afferent fibres which, when stimulated, cause *arrest of the respiration* and closure of the rima glottidis (*Rosenthal*)—(see *Respiratory centre*, § 368). Lastly, fibres which are efferent and serve to excite the vasomotor centre, and are in fact "*pressor fibres*"—(see *Vasomotor centre*, § 371, II).

(*b*) The **inferior laryngeal** or **recurrent** bends on the left side around the arch of the aorta, and on the right around the subclavian, and ascends in the groove between the trachea and œsophagus, giving *motor* fibres to these organs, and the lower constrictors of the pharnyx, and passes to the larynx, to supply **motor** fibres to all its muscles, except the crico-thyroid. It also has an inhibitory action upon the respiratory centre (see § 368).

A **connecting branch** runs from the superior laryngeal to the inferior (the anastomosis of Galen), which occasionally gives off *sensory* branches to the upper half of the trachea (sometimes to the larynx?); perhaps also to the œsophagus (*Longet*), and sensory fibres (?) for the muscles of the larynx supplied by the recurrent laryngeal. According to François Franck, sensory fibres pass by this anastomosis from the recurrent into the superior laryngeal. According to Waller and Burckhard, the motor fibres of both laryngeal nerves are all derived from the accessorius; while Chauveau maintains that the crico-thyroid is an exception.

Stimulation of the **superior laryngeal** is painful, and causes contraction of the crico-thyroid muscle (while the other laryngeal muscles contract *reflexly*). **Section** of both nerves, owing to paralysis of the crico-thyroids, causes slight slowing of the respirations (*Sklarek*). In dogs, the voice becomes deeper and hoarser, owing to diminished tension of the vocal cords (*Longet*). The larynx becomes insensible, so that saliva and particles of food pass into the trachea and lungs, without causing reflex contraction of the glottis or coughing. This excites "traumatic pneumonia," which results in death (*Friedländer*).

Stimulation of the recurrent nerves causes *spasm of the glottis*. **Section** of these nerves paralyzes the laryngeal muscles supplied by them, the voice becomes husky and hoarse (in the pig—*Galen*, *Riolan*, 1618) in man, dog, and cat; while rabbits retain their shrill cry. The glottis is small, with every inspiration the vocal cords approximate considerably at their anterior parts, while, during expiration they are relaxed and are separated from each other. Hence, the inspiration, especially in young individuals whose glottis respiratoria is narrow, is difficult and noisy (*Legallois*); while the expiration takes place easily. After a few days, the animal (carnivore) becomes more quiet, it respires with less effort, and the passive vibratory movements of the vocal cords become less. Even after a considerable interval, if the animal be excited, it is attacked with severe dyspnœa, which disappears only when the animal has become quiet again. Owing to paralysis of the laryngeal muscles, foreign bodies are apt to enter the trachea, while the paralysis renders difficult the first part of the process of swallowing in the œsophageal region. Broncho-pneumonia may be produced (*Arnsperger*).

FIGURE 433, p. 658.

I. *Scheme of the distribution of the vagus and accessorius.*—10, Exit of left vagus from the skull; 10_1, right vagus; 9, glosso-pharyngeal; 7, facial; 1, deep post-auricular from the facial; 2, pharyngeal branches of vagus; 6, pharyngeal branch of the glosso-pharyngeal; 3, superior laryngeal, with its anastomoses, *f*, with the sympathetic and its division, 4, into its internal, *v*, and external branches, *e*; 5, inferior or recurrent laryngeal; *au.*, auricular branch of vagus. *Cardiac nerves: g*, cardiac branches from the vagus and superior laryngeal; *i*, *h*, the three cardiac branches from the upper, *g*, middle, *x*, and lower, *y*, cervical ganglion of the sympathetic; *k*, ring of Vieusses; *l*, cardiac branch from the recurrent laryngeal; *L*, lung with the anterior and posterior pulmonary plexuses; *r*, œsophageal plexus; *oo*, gastric branches, and near them the hepatic branches, *n*; *m*, cœliac plexus; *k*, splanchnic entering former; 11, accessory nerve sending its inner branch into the gangliform plexus of the vagus—its outer branch, *ac*, supplies the sterno-mastoid, *St* and ac_1, and the trapezius, *Cc*; *O*, external auditory meatus; *Oh*, hyoid bone; *K*, thyroid cartilage; *T*, trachea; *H*, heart; *P*, pulmonary artery; *A A*, aorta; *c*, right carotid; c_1, left carotid; *s* and s_1, right and left subclavian artery; *Z Z*, diaphragm; *N*, kidney; *Nn*, suprarenal capsule; *M*, stomach; *m*, spleen; *L L*, lung and liver. II. *Scheme of the course of the depressor and accelerans in the cat.*

6. The **depressor nerve**, which in the rabbit arises by one branch from the superior laryngeal, and usually also by a second root from the trunk of the vagus itself [runs down the neck in close relation with the vagus, sympathetic, and carotid artery, enters the thorax], and joins the cardiac plexus (Fig. 434, *sc*). It is an **afferent** nerve, and when its *central* end is stimulated [provided both vagi be divided], it diminishes the energy of the vasomotor centre, and thus causes a fall of the blood pressure (hence the name given to it by Cyon and Ludwig, § 371, II). At the same time [if the vagus on the opposite side be intact], its stimulation affects the *cardio-inhibitory centre*, and thus reflexly diminishes the number of heart beats. [Its stimulation also gives rise to **pain**, so that it is the sensory nerve of the heart. If in a rabbit the vagi be divided in the middle of the neck, and the **central** end of the depressor nerve, which is the smallest of the three nerves near the carotid, be stimulated, after a short time there is no alteration of the heart beats, but there is a steady fall of the blood pressure (Fig. 106), which is due to a reflex inhibition of the vasomotor centre, resulting in a dilatation of the blood vessels of the abdomen. Of course, if the vagi be intact, there is a reflex inhibitory effect on the heart. It is doubtful if the depressor comes into action when the heart is over-distended. If it did, of course the blood pressure would be reduced by the reflex dilatation of the abdominal blood vessels.]

FIG. 434.



Scheme of the cardiac nerves in the rabbit. P, pons; M, medulla oblongata; VAG, vagus; SL, superior, IL, inferior laryngeal; *sc*, superior cardiac or depressor; *ic*, inferior cardiac or cardio-inhibitory; H, heart.

The depressor nerve is present in the cat (§ 370), hedgehog (*Aubert, Röver*), rat and mouse; in the horse and in man, fibres analogous to the depressor reënter the trunk of the vagus (*Bernhardt, Kreidmann*). Depressor fibres are also found in the rabbit, in the trunk of the vagus (*Dreschfeldt, Stelling*).

7. The **cardiac** branches (Fig. 433, *g*, *l*), as well as the cardiac plexus, have been described in § 57. These nerves contain the **inhibitory** *fibres for the heart* (Fig. 434, *ic*—**cardio-inhibitory**—*Edward Weber*, November, 1845; *Budge*, independently in May, 1846), also **sensory** fibres for the heart [in the frog (*Budge*), and partly in mammals (*Goltz*)]. Lastly, in some animals the heart receives some of the *accelerating* fibres through the trunk of the vagus. Feeble stimulation of the vagus occasionally causes acceleration of the beats of the heart (*Schiff*). [This occurs when the vagus contains accelerator fibres.] In an animal poisoned with nicotin, or atropin, which paralyzes the inhibitory fibres of the vagus, stimulation of the vagus is followed by acceleration of the heart beats (*Schiff, Schmiedeberg*) [owing to the unopposed action of any accelerated fibres that may be present in the nerve, *e. g.*, of the frog].

8. The **pulmonary** branches of the vagus join the anterior and posterior pulmonary plexuses. The *anterior* pulmonary plexus gives **sensory** and **motor** fibres to the trachea, and runs on the anterior surface of the branches of the bronchi into the lungs (*L*). The posterior plexus is formed by three to five large branches from the vagus, near the bifurcation of the trachea, together with branches from the lowest cervical ganglion of the sympathetic and fibres from the cardiac plexus. The plexuses of opposite sides exchange fibres, and branches are given off which accompany the bronchi in the lungs. **Ganglia** occur in the course of the pulmonary branches in the frog (*Arnold, W. Stirling*) [newt—*W. Stirling;* and in mammals (*Remak, Egorow, W. Stirling*)], in the larynx [*Czermak, W. Stirling*], in the trachea and bronchi [*W. Stirling, Kandarazki*]. Branches

proceed from the pulmonary plexus to the pericardium and the superior vena cava (*Luschka, Zuckerkandl*).

The **functions** of the pulmonary branches of the vagus are—(1) they supply **motor** branches to the smooth muscles of the whole bronchial system (§ 106); (2) they supply a small part of the **vasomotor** nerves of the pulmonary vessels (*Schiff*), but by far the largest number of these nerves (? all) is supplied from the connection with the sympathetic (in animals from the first dorsal ganglion)—(*Brown-Séquard, A. Fick, Badoud, Lichtheim*); (3) they supply **sensory** (cough-exciting) fibres to the whole bronchial system, and to the lungs; (4) they give **afferent** fibres, which, when stimulated, diminish the activity of the *vasomotor centre*, and thus cause a fall of the blood pressure during forced expiration; (5) similar fibres which act upon the inhibitory centre of the heart, and so influence it as to accelerate the pulse beats (§ 369, II). Simultaneous stimulation of 4 and 5 alters the pulse rhythm (*Sommerbrodt*); (6) they also contain *afferent* fibres from the pulmonary parenchyma to the medulla oblongata, which *stimulate the respiratory centre*. [These fibres are continually in action], and consequently section of both vagi is followed by diminution of the number of respirations; the respirations become at the same time deeper, while the same volume of air is changed (*Valentin*). Stimulation of the *central* end of the vagus again accelerates the respirations (*Traube, J. Rosenthal*). Thus, labored and difficult respiration is explained by the fact that the influences conveyed by these fibres which excite the respiratory centre reflexly are cut off; so it is evident, that centripetal or afferent impulses proceeding upward in the vagus are intimately concerned in maintaining normal reflex respiration; after these nerves are divided, conditions exciting the respiratory movements must originate *directly*, especially in the medulla oblongata itself (§ 368).

Pneumonia after Section of both Vagi.—The inflammation which follows section of both vagi has attracted the attention of many observers since the time of Valsalva, Morgagni (1740), and Legallois (1812). In attempting to explain this phenomenon, we must bear in mind the following considerations: (a) Section of both vagi is followed by loss of *motor* power in the muscles of the larynx, as well as the *sensibility* of the larynx, trachea, bronchi, and the lungs, provided the section be made above the origin of the superior laryngeal nerves. Hence, the glottis is not closed during swallowing, nor is it closed reflexly when foreign bodies (saliva, particles of food, irrespirable gases) enter the respiratory passages. Even the reflex act of *coughing*, which, under ordinary circumstances, would get rid of the offending bodies, is abolished. Thus, foreign bodies may readily enter the lungs, and this is favored by the fact that, owing to the simultaneous paralysis of the œsophagus, the food remains in the latter for a time, and may therefore easily enter the larynx. That this constitutes one important factor was proved by Traube, who found that the pneumonia was prevented when he caused the animals to respire by means of a tube inserted into the trachea through an aperture in the neck. If, on the contrary, only the motor recurrent nerves were divided and the œsophagus ligatured, so that in the process of attempting to swallow, food must necessarily enter the respiratory passages, "**traumatic pneumonia**" was the invariable result (*Traube, O. Frey*). (b) A second factor depends on the circumstance that, owing to the labored and difficult respiration, the *lungs become surcharged with blood*, because during the long time that the thorax is distended, the pressure of the air within the lungs is abnormally low. This condition of congestion, or abnormal filling of the pulmonary vessels with blood, is followed by *serous exudation* (pulmonary œdema), and even by exudation of blood and the formation of pus in the air vesicles (*Frey*). This same circumstance favors the entrance of fluids through the glottis (§ 352, *b*). The introduction of a tracheal cannula will prevent the entrance of fluids and the occurrence of inflammation. It is probable that a partial *paralysis* of the *pulmonary vasomotor* nerves may be concerned in the inflammation, as this conduces to an engorgement of the pulmonary capillaries. (c) Lastly, it is of consequence to determine whether *trophic* fibres are present in the vagus, which may influence the normal condition of the pulmonary tissues. According to Michaelson, the pneumonia which takes place *immediately* after section of the vagi occurs especially in the lower and middle lobes; the pneumonia which follows section of the recurrents occurs *more slowly*, and causes catarrhal inflammation, especially in the upper lobes. Rabbits, as a rule, die within twenty-four hours, with all the symptoms of pneumonia; when the above-mentioned precautions are taken, they may live for several days. Dogs may live for a long time. If the 9th, 10th, and 12th nerves be torn out on one side in a rabbit, death takes place from pneumonia (*Grünhagen*). In **birds**, bilateral section of the vagi is not followed by pneumonia (*Blainville, Billroth*), because the upper larynx remains capable of closing firmly—death takes place in eight to ten days with the symptoms of *inanition* (*Einbrodt, Zander, v. Anrep*),

while the **heart** undergoes **fatty degeneration** (*Eichhorst*), and so do the liver, stomach and muscles (*v. Anrep*). According to Wassilieff, the heart shows cloudy swelling and slight wax-like degeneration. **Frogs**, which at every respiration open the glottis, and close it during the pause, die of asphyxia. Section of the pulmonary branches has no injurious effect (*Bidder*). [Unilateral section of the vagus in **rabbits** is followed within forty-eight hours by the appearance of yellowish-white spots on the myocardium, especially near the inter-ventricular septum, on the papillary muscles, and along the furrows for the coronary arteries. The muscular fibres exhibit retrogressive changes, whereby their striæ disappear; they become swollen up and filled with albuminous granules. After eight to ten days, the interstitial tissue of these foci becomes infiltrated with small round granular cells, especially near the blood vessels. At a later stage, the interstitial connective tissue increases in amount, and the muscle atrophies. No effect is produced by section of the depressor or sympathetic, and Fantino concludes that some of the fibres of the vagus exert a trophic action on the myocardium.]

9. The **œsophageal plexus** (Fig. 434, *r*) is formed principally by branches from the vagus above the inferior laryngeal, from the pulmonary plexus, and below from the trunk itself. This plexus supplies the œsophagus with **motor** power (§ 156), the **sensibility** which is present only in the upper part, and it also supplies fibres capable of exciting *reflex* actions.

10. The **gastric plexus** (*oo*) consists of (*a*) the anterior (left) termination of the vagus, which supplies fibres to the œsophagus and courses along the small curvature, and sends a few fibres through the portal fissure into the liver; (*b*) the posterior (right) vagus, after giving off a few fibres to the œsophagus, takes part in the formation of the gastric plexus to which (*c*) *sympathetic* fibres are added at the pylorus. *Section of the vagi* is followed by hyperæmia of the gastric mucous membrane (*Panum, Pincus*), but it does not interfere with digestion (*Bidder and Schmidt*), even when it is performed at the cardia (*Kritzler, Schiff*).

11. About two-thirds of the *right* vagus on the stomach joins the **cœliac plexus**, and from it branches accompany the arteries to the liver, spleen, pancreas, duodenum, kidney, and suprarenal capsules. The vagus supplies *motor* fibres to the stomach, which belong to the root of the vagus itself and not to the accessorius (*Stilling, Bischoff*). The gastric branches also contain *afferent* fibres, which, when stimulated, cause *reflexly a secretion of saliva* (§ 145). It is undetermined whether they also cause vomiting. For the effect of the **vagus** upon the **movements of the intestine** (see § 161). According to some observers, stimulation of the vagus is followed by movement of the large as well as of the small intestine (*Stilling, Kupffer, C. Ludwig, Remak*). Stimulation of the *peripheral* end of the vagus causes contraction of the smooth muscular fibres in the capsule and trabeculæ of the *spleen* (in the rabbit and dog, § 103). Stimulation of the vagus at the cardia causes increase in the secretion of urine with dilatation of the *renal vessels*, while the blood of the renal vein becomes more arterial (*Cl. Bernard*). According to Rossbach and Quellhorst, a few *vasomotor* fibres are supplied by the vagus to the abdominal organs, while the greatest number comes from the splanchnic.

12. **Reflex Effects.**—The vagus and its branches contain fibres, some of which have been referred to already, which act *reflexly* (afferent) *upon certain nervous mechanisms.*

(*a*) On the **vasomotor centre** there act (*α*) *pressor* fibres (especially in both laryngeal nerves), whose stimulation is followed by a reflex contraction of the arterial blood channels, and thus cause a rise of the blood pressure; (*β*) *depressor* fibres (in the depressor or the vagus itself), which have exactly an opposite effect. (This subject is specially referred to under the head of the *Vasomotor nerve centre*, § 371.)

(*b*) On the **respiratory centre** there act (*α*) fibres (pulmonary branches) whose stimulation is followed by *acceleration* of the respiration; and (*β*) *inhibitory* fibres (in both laryngeals), whose stimulation is followed by slowing or arrest of the respiration. (See *Respiratory centre*, § 368.)

(*c*) On the **cardio-inhibitory system.**—[When the *central* end of one vagus is stimulated, provided the other vagus is intact, the heart may be arrested *reflexly* in the diastolic phase.] Mayer and Pribram observed that sudden distention of the stomach caused slowing and even arrest of the heart, while, at the same time, there was contraction of the arteries of the medulla oblongata and increase of the blood pressure.

(*d*) On the **vomiting centre.**—This centre may be affected by stimulation of the *central*

end of the vagus, and, as already mentioned, by stimulation of many afferent fibres in the vagus (§ 158).

(*e*) On the **pancreatic secretion.**—Stimulation of the *central* end of the vagus is followed by arrest of this secretion (§ 171).

(*f*) According to Cl. Bernard, there are fibres present in the pulmonary nerves, which, when they are stimulated, increase reflexly the **formation of sugar in the liver,** perhaps through the hepatic branches of the vagus.

Unequal Excitability.—The various branches of the vagus are not all endowed with the same degree of *excitability*. If the *peripheral* end of the vagus be stimulated, first of all with a weak stimulus, the laryngeal muscles are first affected, and afterward the heart is slowed (*Rutherford*). If the *central* end be stimulated with feeble stimuli, the "excito-respiratory" fibres are exhausted before the "inhibito-respiratory" (*Burkart*). According to Steiner, the various fibres are so arranged in the vagus that the afferent fibres lie in the outer, and the efferent in the inner, half of the trunk, in the cervical region.

Pathological.—Stimulation or paralysis in the area of the vagus must necessarily present a very different picture according as the affection is referred to the whole trunk or only to some of its branches, or whether the affection is unilateral or bilateral. **Paralysis of the pharynx and œsophagus,** which is usually of central or intracranial origin, interferes with or abolishes deglutition, so that when the œsophagus becomes filled with food there is difficulty of breathing, and the food may even pass into the nasal cavities. A peculiar sonorous gurgling is occasionally heard in the relaxed canal (deglutatio sonora). **In incomplete paralysis,** the act of deglutition is delayed and rendered more difficult, while large masses are swallowed more easily than small ones. *Increased contraction* and spasmodic stricture of the œsophagus are referred to under the phenomena of general nervous excitability (§ 186).

Spasm of the laryngeal muscles causes spasmodic closure of the glottis (*Spasmus glottidis*). This condition is most apt to occur in children, and takes place in paroxysms, with symptoms of dyspnœa and crowing inspiration; if the case be very severe, there may be muscular contractions (of the eye, jaw, digits, etc.). The symptoms are very probably due to the reflex spasms which may be discharged from the sensory nerves of several areas (teeth, intestine, skin). The impulse is conducted along the sensory nerves proceeding from these areas to the medulla oblongata, where it causes the discharge of the reflex mechanism which produces the above-mentioned results. There may be spasm of the dilators of the glottis and other laryngeal muscles (*Frāntzel*).

Stimulation of the *sensory* nerves of the larynx, as is well known, produces **coughing.** If the stimulation be very intense, as in whooping-cough, the fibres lying in the laryngeal nerves, which *inhibit* the respiratory centre, may also be stimulated; the number of respirations is diminished, and ultimately the respiration ceases, the diaphragm being relaxed; while, with the most intense stimulation, there may be spasmodic expiratory arrest of the respiration with closure of the glottis, which may last for fifteen seconds. *Paralysis of the laryngeal nerves*, which causes disturbances of *speech*, has been referred to in § 313. In *bilateral paralysis of the recurrent nerves*, in consequence of tension upon them due to dilatation of the aorta and the subclavian artery, a considerable amount of air is breathed out, owing to the futile efforts which the patient makes in trying to speak; expectoration is more difficult, while violent coughing is impossible (*v. Ziemssen*). Attacks of dyspnœa occur just as in animals, if the person make violent efforts. Some observers (*Salter, Bergson*) have referred the paroxysms of nervous **asthma,** which last for a quarter of an hour or more, and constitute *asthma bronchiale*, to stimulation of the pulmonary plexus, causing spasmodic contraction of the bronchial muscle (§ 106). Physical investigation during the paroxysms reveals nothing but the existence of some rhonchi (§ 117). If this condition is really spasmodic in its nature (? of the vessels), it must be usually of a reflex character; the afferent nerves may be those of the lung, skin, or genitals (in hysteria). Perhaps, however, it is due to a temporary paralysis of the pulmonary nerves (afferent), which excite the respiratory centre (excito-respiratory).

Stimulation of the **cardiac** branches of the vagus may cause attacks of temporary suspension of the cardiac contractions, which are accompanied by a feeling of great depression and of impending dissolution, with occasionally pain in the region of the heart. Attacks of this sort may be produced *reflexly*, *e.g.*, by stimulation or irritation of the abdominal organs (as in the experiment of Goltz of tapping the intestines). Hennoch and Silbermann observed slowing of the action of the heart in children suffering from gastric irritation. Similarly, the respiration may be affected reflexly through the vagus, a condition described by Hennoch as **asthma dyspepticum.** In cases of intermittent paralysis of the cardiac branches of the vagus, we rarely find *acceleration* of the pulse above 160 (*Riegel*), 200 (*Tuczek, L. Langer*); even 240 pulse beats per minute have been recorded (*Kuppert*), and in such cases, the beats vary much in rhythm and force, and they are very irregular. These cases require to be more minutely analyzed, as it is not clear how much is due to paralysis of the vagus and how much to the action of the accelerating mechanism of the heart. Little is known of affections of the *intra-abdominal* fibres of the vagus. It seems that the sensory branches of the stomach do not come from the vagus. If the trunk of the vagus or its centre be paralyzed, there are labored, deep, slow respirations, such as follow the section of both vagi (*Guttmann*).

353. **XI. NERVUS ACCESSORIUS WILLISII.—Anatomical.**—This nerve arises by two completely separate roots; *one* from the **accessorius** nucleus of the **medulla oblongata** (Fig. 427, 11), which is connected with the vagus nucleus; while the *other* root arises between the anterior and posterior nerve roots from the **spinal cord**, usually between the 5th and 6th cervical vertebræ. In the spinal cord, its fibres can be traced to an elongated nucleus lying on the outer side of the anterior cornu, as far downward as the 5th cervical vertebra. Near the jugular foramen both portions come together, but do not exchange fibres (*Holl*); both roots afterward separate from each other to form two distinct branches, the **anterior** (*inner*), which arises from the medulla oblongata, passing *en masse* into the plexus ganglliiformis vagi. This branch supplies the vagus with most of its *motor* fibres (compare § 352, 3), and also its *cardio-inhibitory* fibres (Fig. 433). [The upper cervical metameres or segments give origin not only to the anterior and posterior roots of the corresponding nerve roots, but *between* these roots arise the roots of the spinal accessory nerve. This nerve contains *large* medullated nerve fibres, and *fine* medullated fibres such as characterize the visceral branches of the thoracic and sacral regions (§ 356). The nerve passes by the jugular ganglion of the vagus, then divides into the external and internal branch. All the **large** fibres pass into the external branch, which, along with branches from the cervical plexus, supply the sterno-mastoid and trapezius. The internal branch, composed of **small** fibres, passes into the ganglion of the trunk of the vagus. Gaskell therefore regards the internal branch "as formed by the rami viscerales of the upper cervical and vagus nerves." These fine medullated nerve fibres probably arise from the cells of the posterior vesicular column of Clarke. The motor fibres to the trapezius and sterno-mastoid arise from the cells of the lateral horn of gray matter.]

If the accessorius be pulled out by the root in animals, the cardio-inhibitory fibres undergo degeneration. If the trunk of the vagus be stimulated in the neck four to five days after the operation, the action of the heart is no longer arrested thereby [owing to the degeneration of the cardio-inhibitory fibres] (*Waller, Schiff, Daszkiewicz, Heidenhain*); according to Heidenhain, the heart beats are accelerated immediately after pulling out the nerve.

The **external** branch arises from the spinal roots. This nerve communicates with the **sensory** branches of the posterior root of the 1st, more rarely of the 2d cervical nerve, and these fibres supply sensibility to the muscles; it then turns backward above the transverse process of the atlas, and terminates as a **motor** nerve in the sterno-mastoid and trapezius, (Fig. 433). The latter muscle usually receives motor fibres also from the cervical plexus (Fig. 429).

The external branch communicates with several cervical nerves. These fibres either participate in the innervation of the above-named muscles, or the accessorius returns part of the sensory fibres supplied by the posterior roots of the two upper cervical nerves.

Pathological.—Stimulation of the *outer* branch causes tonic or clonic spasm of the above-named muscles, usually on one side. If the branch to the sterno-mastoid be affected alone, the head is moved with each clonic spasm. If the affection be bilateral, the spasm usually takes place on opposite sides alternately, while it is rare to have it on both sides simultaneously. In **spasm of the trapezius** the head is drawn backward and to the side. *Tonic* contraction of the flexors of the head causes the characteristic position of the head known as caput obstipum (spasticum) or **wryneck.** In *paralysis* of one of these muscles, the head is drawn toward the sound side (**torticollis paralyticus**). Paralysis of the trapezius is usually only partial.

Paralysis of the whole trunk of the spinal accessory (usually caused by central conditions), besides causing paralysis of the sterno-mastoid and trapezius, also paralyzes the motor branches of the vagus already referred to (*Erb, Fränkel*).

354. **XII. NERVUS HYPOGLOSSUS.—Anatomical.**—It arises from two *large-celled* nuclei within the lowest part of the calamus scriptorius, and one adjoining *small-celled* nucleus (*Roller*), while additional fibres come from the brain (§ 378), and also perhaps from the olive (Fig. 427, 12). It springs by 10 to 15 twigs in a line with the anterior roots of the spinal nerve (Fig. 420, IX). In its development part of the hypoglossal behaves as a spinal nerve (*Froriep*).

Function.—It is **motor** to all the muscles of the **tongue**, including the genio-hyoid and thyro-hyoid.

Connections.—The trunk of the hypoglossal is connected with (1) the *superior cervical ganglion* of the *sympathetic*, which supplies it with *vasomotor* fibres for the blood vessels of the tongue. After section of the hypoglossal and lingual nerves, the corresponding half of the tongue becomes red and congested (*Schiff*). (2) There is also a branch from the plexus gangliiformis vagi, its small lingual branch, to the commencement of the hypoglossal arch. These fibres supply the hypoglossal with *sensory* fibres for the *muscles of the tongue*, for even after section of the lingual the tongue still possesses dull sensibility. It is uncertain whether fibres with a similar function are

partly derived from the cervical nerves or from the anastomosis which takes place with the lingual. (3) It is united with the *upper cervical nerves* by means of the loops known as the ansa hypoglossi. These connecting fibres run in the descendens noni to the sterno-hyoid, omo-hyoid, and sterno-thyroid. Cervical fibres do not, as a rule, enter the tongue; stimulation of the root of the hypoglossal acts upon the above-named muscles only very rarely and to a very slight extent (*Volkmann*). (Compare § 297, 3, and § 336, III.)

Bilateral section of the nerve causes complete motor paralysis of the tongue. Dogs can no longer lap, they bite the flaccid tongue. Frogs, which seize their prey with the tongue, must starve; when the tongue hangs from the mouth, it must prevent the closure of the mouth, so that these animals must die from asphyxia, as air is pumped into the lungs only when the mouth is closed.

Pathological.—Paralysis of the hypoglossal (**glossoplegia**), which is usually central in its origin, causes disturbance of *speech* (§ 319). [In unilateral palsy, the tongue lies in the mouth in its normal position, but the base is more prominent on the paralyzed side. When the tongue is protruded, it passes to the sound side by the genio-hyoglossus (§ 155).] Paralysis of the tongue also interferes with mastication, the formation of the bolus in the mouth, and deglutition in the mouth. Owing to the imperfect movements of the tongue, *taste* is imperfect, and the singing of high notes and the falsetto voice, which require certain positions of the tongue, appear to be impossible (*Bennati*).

Spasm of the tongue, which causes aphthongia (§ 318), is usually reflex in its origin, and is extremely rare. Idiopathic cases of spasm of the tongue have been described; the seat of the irritation lay either in the cortex cerebri or in the oblongata (*Berger*, *E. Remak*). For **Pseudo-motor Action**, see p. 650.

355. **THE SPINAL NERVES.—Anatomical.**—The thirty-one pairs of spinal nerves arise by means of a **posterior** [superior, gangliated] **root** (consisting of a few large rounded bundles), from the sulcus between the posterior and lateral columns of the spinal cord, and by means of an **anterior** [inferior, non-gangliated] **root** (consisting of numerous fine flat strands), from the furrow between the anterior and lateral columns, Fig. 435. The posterior roots, with the exception of the 1st cervical nerve, are the larger. Occasionally the roots on opposite sides are not symmetrical; one or other root, or even a whole nerve, may be absent from the dorsal region (*Adamkiewicz*). On the **posterior root** is the spindle-shaped **spinal ganglion** (§ 321, II, 3), which is occasionally double on the lumbar and sacral nerves. *Beyond the ganglion*, the two roots unite to form within the spinal canal the mixed trunk of a **spinal nerve**. The branches of the nerve trunk invariably contain fibres coming from both roots. The number of fibres in the nerve trunk is exactly the same as in the two roots; hence, we must conclude that the nerve cells in the spinal ganglion are intercalated in the course of the fibres (*Gaule and Birge*).

Varieties.—The spinal ganglion is sometimes double, and according to Hyrtl, isolated ganglionic cells frequently occur in the posterior root, between the ganglion and the cord. Occasionally the roots are somewhat unsymmetrical on opposite sides; in the dorsal part one or other, or both roots of a spinal nerve are sometimes absent (*Adamkiewicz*).

[**Morphology of the Spinal Nerves and Limb Plexuses.**—A typical **segmental spinal nerve** (Fig. 435), divides, after its formation, into three parts, a **dorsal** branch, or superior primary division distributed to the back, a **somatic** branch, or inferior primary division, supplying the body wall or limbs; and a **splanchnic** or **visceral** branch, or ramus communicans, connected with the sympathetic gangliated cord, and distributed to the large vessels and viscera. The somatic branch is the largest, and is generally, by human anatomists, spoken of as the "anterior primary division." In the thoracic and upper lumbar regions, the distribution of this nerve is simple. It divides into an external (or lateral) branch, and an internal (or anterior) branch, which supply respectively the lateral and anterior portions of the thoracic and abdominal walls.]

[In the region of the neck, and in relation to the limbs, the arrangement of the somatic branches becomes complicated by the formation of the plexuses. In the embryo, however, the distribution of the nerves is simpler, and a comparison can be made both with the adult arrangement, and with the typical nerve as seen in the thoracic region. In the embryo, the neck as such does not exist, and the upper limb sprouts out directly beyond the segmented visceral arches. In this state, the somatic branch is distributed as in the thoracic region; the nerve divides into an external and an internal branch, distributed to the side and front of the corresponding part of the arches in the neck, in the regions where the limbs are appearing as two flattened buds from the ventro-lateral aspect of the body. The somatic branch sweeps round into the blastema forming the limb, and divides into its two branches, external and internal, or dorsal and ventral, which are distributed to the outer (dorsal) and inner (ventral) surfaces, respectively, of the primitive limb. At this time, the cartilaginous and muscular elements of the limb have not become differentiated. While this is occurring, the dorsal and ventral parts of the somatic branches of the nerves entering the limb unite with adjacent dorsal and ventral branches, in various combinations, so as to produce the limb plexuses. The nerves resulting from these combinations are distributed to the primitive, dorsal, and ventral surfaces of the limbs. Thus, the plexuses are formed, and the peripheral distribution of the nerves has taken place

before the period of flexion and angulation of the limbs. These processes mark the conditions in the adult; but even then it is easy to make out that the nerves in the upper limb derived from the posterior (dorsal) cords of the brachial plexus supply the scapular region, extensor surface of the arm and forearm, and the back of the hand—parts which are derived from the dorsal surface of the primitive limb; while the nerves produced from the anterior (ventral) cords supply the pectoral region, front of the arm, forearm, and hand—parts representing the primitive ventral surface.]

[In the lower limb, the nerves derived from a union of the posterior branches are the external cutaneous, anterior crural, gluteal, and external popliteal. These supply the iliac surfaces, the front of the thigh, leg, and foot—belonging to the primitive dorsal surface of the limb. The nerves formed by the union of anterior branches—genito-crural, obturator, and internal popliteal, in like manner supply the parts of the limb corresponding to the ventral surface—the inner side and back of the thigh, the back of the leg, and the sole of the foot (*A. M. Paterson*).]

[**Structure of a Spinal Ganglion.**—The ganglion is invested by a thin, firmly adherent, sheath of connective tissue, which sends processes into the swelling, and is continuous with the sheaths of the nerve entering and leaving the ganglion (Fig. 436, *c*). In **mammals**, *e. g.*, rabbit, a longitudinal section of such a ganglion exhibits the cells arranged in groups, with strands of nerve fibres

FIG. 435.



Diagram of a spinal nerve; C, spinal cord; *pr*, *ar*, posterior and anterior roots; SPD, IPD, superior and inferior primary divisions; *d*, *v*, dorsal and ventral branches; *sr*, sympathetic root (*Ross*).

FIG. 436.

Longitudinal section of a spinal ganglion. *a*, nerve fibre; *b*, nerve cells; *c*, capsule.

coursing longitudinally between them (Fig. 436, *a*, *b*). The nerve cells are usually globular in form, with a distinct capsule lined with epithelium, and the cell-substance itself contains a well-defined nucleus with a nuclear envelope and a nucleolus. The capsule of the cell is continuous with the sheath of Schwann of a nerve fibre. The exact relation between the nerve fibres and the nerve cells is difficult to establish, but it is probable that each nerve cell is connected with one nerve fibre, *i. e.*, they are unipolar. In the spinal ganglia of the vertebrates above fishes, and also in the Gasserian ganglion, cells are found with a single process or fibre attached to them, the nerve fibre process not unfrequently coiling a few times within the capsule. This process, after emerging from the capsule, becomes coated with myelin, and usually soon divides at a node of Ranvier (Fig. 341, *t*). Ranvier, who first observed this arrangement, describes it as a T-shaped fibre. These nerve cells with T-shaped fibres have been observed in the spinal ganglia of all vertebrates above fishes, in the Gasserian and geniculate ganglia, as well as in the jugular and cervical ganglia of the vagus. In fishes the nerve cells of the spinal ganglia are bipolar (Fig. 368, 4). There is a rich plexus of capillaries in these ganglia, and each cell is surrounded by a meshwork of capillaries, which never penetrate the cell capsules.]

Bell's Law.—Sir Charles Bell discovered (1811) that the **anterior** roots of the spinal nerves are **motor**, the **posterior** are **sensory.**

Recurrent Sensibility.—Magendie discovered (1822) the remarkable fact that *sensory fibres* are *also present* in the anterior roots, so that their stimulation causes pain. This is due to the fact that sensory fibres pass into the anterior root after the two roots have joined, and these fibres run in the anterior root in a centripetal direction (*Schiff, Cl. Bernard*). The sensibility of the anterior root is abolished at once by section of the posterior root. This condition is called "recurrent sensibility" of the anterior root. When the sensibility of the anterior root is abolished, so is the sensibility of the surface of the spinal cord in the neighborhood of the root. A long time after section of the anterior, and when the degeneration phenomena have had time to develop (§ 325), a few non-degenerated sensory fibres are always to be found in the central stump (*Schiff, Vulpian*). Schiff found that, in cases where the motor fibres had undergone degeneration, there were always non-degenerated fibres to be found in the anterior root, which passed into the membranes of the spinal cord. The sensory fibres pass into the motor root, either at the angle of union of the roots, or in the plexus, or in the region of the peripheral terminations. Sensory fibres enter many of the branches of the motor cranial nerves at their periphery, and afterward run in a centripetal direction (p. 650). Even into the trunks of *sensory* nerves, sensory branches of other sensory nerves may enter. This explains the remarkable observation, that after section of a nerve trunk (*e. g.*, the median), its peripheral terminations still retain their sensibility (*Arloing and Tripier*). The tissue of the motor and sensory nerves, like most other tissues of the body, is provided with sensory nerves (*Nervi nervorum*, p. 580).

[It does not follow that section of a peripheral cutaneous nerve will cause anæsthesia in the part to which it is distributed; in fact, one of the principal nerve trunks of the brachial plexus may be divided without giving rise to complete anæsthesia in any part of the area of distribution of the sensory branches of the nerve, and even if there be partial or complete cutaneous anæsthesia, it is much less in extent than corresponds to the anatomical area of distribution. The anæsthetic area tends to become smaller in extent (*Ross*). Thus, there is not complete independence in the distribution of these nerves. These results are explained by the anastomosis between branches of nerves, the exchange of fibres in the terminal networks, while some sensory fibres enter the peripheral parts of a nerve and run centripetally, perhaps being distributed to the skin and conferring recurrent sensibility on the peripheral part of the nerve.]

Relative Position of Motor and Sensory Fibres.—In embryos (rabbit) the motor fibres stain more deeply with carmine than the sensory fibres, so that their position in the peripheral nerves of distribution may thereby be made out. In the *anterior branch* of a spinal nerve, the sensory fibres lie in the outer part of the branch, the motor in the inner part; while this relation is reversed in the posterior root (*L. Löwe*).

Deduction from Bell's Law.—Careful observations of the effects of section of the roots of the spinal nerves (*Magendie*, 1822), as well as the discovery of the reflex relation of the stimulation of the sensory roots to the anterior, constituting reflex movements (*Marshall Hall, Johannes Müller*, 1832), enables us to deduce the following conclusions from Bell's law: 1. At the moment of section of the **anterior root,** there is a *contraction* in the muscles supplied by this root. 2. There is at the same time a *sensation of pain* due to the "recurrent sensibility." 3. After the section, the corresponding *muscles* are *paralyzed.* 4. Stimulation of the peripheral trunk of the anterior root (immediately after the operation) causes *contraction* of the muscles, and eventually pain, owing to the recurrent sensibility. 5. Stimulation of the central end is *without effect.* 6. The sensibility of the paralyzed parts is retained completely. 7. At the moment of section of the **posterior root,** there is severe *pain.* 8. At the same time movements are discharged reflexly. 9. After the section, all parts supplied by the divided roots are devoid of sensibility. 10. Stimulation of the peripheral trunk of the divided nerve is without effect. 11. Stimulation of the central end causes *pain* and *reflex* movements. 12. The central end ultimately degenerates. 13. Movement is retained completely in the paralyzed parts, *e. g.*, in the extremities.

The **ultimate effect,** known as Wallerian degeneration, which follows section of the nerve or its roots, is referred to in § 325. Recently, Joseph has slightly modified the statements of Waller on the degeneration in the posterior roots. According to him, the spinal ganglion is the nutritive centre for by far the largest number of the fibres of this root; but individual fibres traverse the ganglion without forming connections with its cells, so that the nutritive or trophic centre for this small number of nerve fibres is in the spinal cord.

Incoördinated Movements of Insensible Limbs.—After section of the posterior roots, *e.g.*, of the nerves for the posterior extremities, the muscles retain their movements; nevertheless there are characteristic disturbances of their motor power. This is expre-sed in the awkward manner in which the animal executes its movement—it has lost to a large extent its harmony and elegance of motion. This is due to the fact that, owing to the absence of the sensibility of the muscles and skin, the animal is no longer conscious of the resistance which is opposed to its movements. Hence, the degree of muscular energy necessary for any particular effort cannot be accurately graduated. Animals which have lost the sensibility of their extremities often allow their limbs to lie in abnormal positions, such as a healthy animal would not tolerate. In man also, when the peripheral ends of the cutaneous nerves are degenerated, there are *ataxic* phenomena (§ 364, 3).

FIG. 437.



Distribution of the cutaneous nerves of the arm. A, Dorsal surface—*1 sc*, supra-clavicular; *2 ax*, axillary; *3 cps*, superior posterior cutaneous; *4 cmd*, median cutaneous; *5 cpi*, inferior posterior cutaneous; *6 cm*, median cutaneous; *7 cl*, lateral cutaneous; *8 u*, ulnar; *9 ra*, radial; *10 me*, median. B, volar surface—*1 sc*, supra-clavicular; *2 ax*, axillary; *3 cmd*, internal cutaneous; *4 cl*, lateral cutaneous; *5 cm*, cutaneous medius; *6 me*, median; *7 u*, ulnar.

FIG. 438.



Distribution of the cutaneous nerves of the leg (after *Henle*). A, Anterior surface—1, crural nerve; 2, external lateral cutaneous; 3, ilio-inguinal; 4, lumbo-inguinal; 5, external spermatic; 6, posterior cutaneous; 7, obturator; 8, great saphenous; 9, communicating peroneal; 10, superficial peroneal; 11, deep peroneal; 12, communicating tibial. B, Posterior surface—1, posterior cutaneous; 2, external femoral cutaneous; 3, obturator; 4, median posterior femoral cutaneous; 5, communicating peroneal; 6, great saphenous; 7, communicating tibial; 8, plantar cutaneous; 9, median plantar; 10, lateral plantar.

Increased Excitability.—Harless (1858), Ludwig, and Cyon (controverted by v. Bezold, Uspensky, Grünhagen, and G. Heidenhain) observed that the anterior root is more excitable as long as the posterior roots remain intact and are sensitive, and that their excitability is diminished as soon as the posterior roots are divided. In order to explain this phenomenon, we must assume that, in the intact body, a series of gentle impulses (impressions of touch, temperature, position of limbs, etc.) are continuously streaming through the posterior roots to the spinal cord, where they are transferred to the motor roots, so that a less stimulus is required to excite the anterior roots than when these reflex impulses of the posterior root, which increase the excitability, are absent. Clearly, a less stimulus will be required to excite a nerve already in a gentle state of excitement than in the case of a fibre which is not so excited. In the former case, the discharging stimulus becomes, as it were, superposed on the excitement already present. (Compare § 362.)

The anterior roots of the spinal nerves supply **efferent** fibres to—

1. All the **voluntary muscles** of the trunk and extremities.

Every muscle always receives its motor fibres from *several* anterior roots (not from a single nerve root). Hence, *every* root supplies branches to a particular group of muscles (*Preyer, P. Bert, Gad*). The experiments of Ferrier and Yeo show that stimulation of each of the anterior roots in apes (brachial and lumbo-sacral plexuses) caused a complex coördinated movement. Section of one root did not cause complete paralysis of the muscles concerned in these coördinated movements, although the force of the movement was impaired. These experiments confirm the results of clinical observation on man. The fibres for groups of muscles of different functions (*e. g.*, for flexors, extensors) arise from special limited areas of the spinal cord. The cervical and lumbar enlargements of the spinal cord are great centres for highly coördinated muscular movements.

2. The anterior roots also supply **motor fibres** for a number of organs provided with smooth muscular fibres, *e. g.*, the bladder (§ 280), ureter, uterus. [These are the viscero-motor nerves of Gaskell, and from them come also viscero-inhibitory nerves.]

3. **Motor fibres** for the smooth muscular fibres of the *blood vessels*, the *vaso-motor*, **vaso-constrictor**, or vaso-hypertonic nerves [also **accelerator** or augmentor nerves of the heart]. They run in the sympathetic for a part of their course (§ 371).

4. **Inhibitory fibres** for the blood vessels. These are but imperfectly known. They are also called **vaso-dilator** or vaso-hypotonic nerves (§ 372). [Also **inhibitory** nerves for the heart, which leave the spinal axis in the vagus.]

5. **Secretory fibres** for the sweat glands of the skin (§ 289). For a part of their course they run in the sympathetic.

6. **Trophic fibres** of the tissues (§ 342, I, *c*).

The **posterior roots** contain all the **sensory** nerves of the whole of the skin and the internal tissues, except the front part of the head, face, and the internal part of the head. They also contain the **tactile nerves** for the areas of the skin already mentioned. Stimuli which discharge *reflex movements* are conducted to the spinal cord through the posterior roots. The sensory fibres of a mixed nerve trunk supply the cutaneous area, which is moved by those muscles (or which covers those muscles) to which the same branch supplies the motor fibres. The special distribution of the motor and sensory nerves of the body belongs to anatomy (Figs. 429, 430, 437, 438).

[**Physiology of the Limb Plexuses.**—The idea that the nerve strands become rearranged in the limb plexuses so as to connect nerves derived from different parts of the spinal cord with particular groups of muscles, in order to allow of "coördination of muscular action," does not seem to be borne out by more extended observation. Herringham has shown by dissection (and the same is seen in cases of paralysis of motion and sensation) that a given muscle or part of a muscle, and a given spot of skin, are supplied by particular branches of individual spinal nerves proceeding directly from the spinal cord. The reason that the plexuses exist is, apparently, not a physiological one. Coördination cannot be effected in the plexus, where the axis cylinders of the nerves do not divide; but only in the spinal cord and central nervous system, and through the intervention of nerve cells. The existence of the plexuses is due to the fact that embryologically the limb consists of a flattened lappet, or bud, derived from certain somites, but at first presenting no signs of segmentation, with a pre-axial and a post-axial border, and outer (dorsal) and inner (ventral) surfaces of skin, covering a double layer of muscle on each surface. The dorsal and ventral branches of the nerves supply these respective surfaces; and after the nerves have grown out, the simple muscular strata become split up into individual muscles, which contain elements derived from one or more segments represented in the

primitive limb. Each nerve is segmental, and, therefore, supplies a muscle derived, for example, from the elements of two segments; the nerve of distribution must contain corresponding parts of two segmental nerves. The plexuses appear, therefore, from an embryological cause, and have no direct physiological significance (*A. M. Paterson*).]

356. THE SYMPATHETIC NERVE.—[**Anatomical.**—The sympathetic nervous system contains a large number of non-medullated or Remak's fibres, and consists of a series of **ganglia** lying on each side of the vertebral column and connected with each other by inter-ganglionic fibres. The typical distribution obtains in the thoracic region, where the **lateral** or vertebral ganglia lie close on the vertebræ. In front of this is a second series of ganglia, which do not form a double line, but are connected with the former and with each other. They are the prevertebral or **collateral** ganglia, *e. g.*, semilunar, inferior mesenteric, etc., the nerves connecting them with the former being called rami efferentes. From these, fibres proceed to connect them with ganglia lying in or about tissues or organs—the **terminal** ganglia (*Gaskell*).]

[Each spinal nerve in this region is connected with its corresponding sympathetic ganglion by the **ramus communicans**, which is formed by fibres both from the anterior and posterior roots of a spinal nerve. It corresponds to the visceral nerve of the morphologist, and is composed of two parts —a **white** and a **gray ramus.** The **white ramus** is composed entirely of **medullated** fibres, and coming from the anterior and posterior roots of a spinal nerve, passes into the lateral and collateral ganglia. These white rami occur in the dog only from the 2d thoracic to the 2d lumbar nerve (Fig. 439). Above and below this, the rami are all **gray** and composed of **non-medullated** nerve fibres (*Gaskell*).]

[In **man**, the four upper rami communicantes from the four upper cervical nerves all join the superior cervical ganglion (Fig. 428, *G g, s*), the 5th and 6th join the middle cervical, the 7th and 8th the inferior cervical ganglion. The lowest pair of ganglia are generally united by a loop on the front of the first coccygeal vertebra, and they lie in relation with the coccygeal ganglion.]

[**Cephalic Portion.**—As the sympathetic ascends to the head it forms connections with many of the cranial nerves, and there is a free exchange of fibres between these nerves. (The function and significance of these exchanges are referred to under the physiology of the cranial nerves.)]

[**Dorsal and Abdominal Portion.**—Numerous fibres pass into these parts chiefly to the *thoracic* and *abdominal cavities*, where they form large gangliated plexuses, from which functionally different fibres proceed to the different organs.]

[In the **dog**, the 2d, 3d, 4th, and 5th thoracic pass upward into the cervical sympathetic, those in the dorsal region being directed downward from the lateral ganglia to form the splanchnics (Fig. 439). The gray non-medullated nerve fibres of each gray ramus are connected with the cells of its ganglion (lateral); the fibres do not go beyond the ganglion, but really run *to* the corresponding spinal nerve to ramify in the sheaths of the nerves, the connective tissue on the vertebræ and the dura mater, and perhaps the other spinal membranes; so that, according to Gaskell, no non-medullated nerves leave the central nervous system by the spinal nerve roots. Thus, the white rami communicantes alone constitute the rami viscerales of the morphologist, and all the visceral nerves passing out from the central nervous system into the sympathetic system pass out by them alone. All the nerves in the white ramus are of small calibre (1.8 μ to 2.7 μ) and medullated, while the true motor fibres are much larger (14.4 μ to 19 μ). The small, white fibres can be traced upward as medullated fibres into the superior cervical ganglion, and in the thorax over the lateral ganglia to form the splanchnics into the collateral ganglia, beyond which they cease to be medullated. By the 2d and 3d sacral nerves some fibres of smallest calibre issue to form the **nervi erigentes**, which pass over and do not communicate with the lateral ganglia, but enter the hypogastric plexus, whence they send branches upward to the inferior mesenteric plexus and downward to the bladder, rectum, and generative organs. Gaskell proposes to call them the **pelvic splanchnic** nerves (Fig. 439).]

[In the **cervical** region, there is no white ramus, and the nerve roots contain no nerve fibres of small calibre. But in this region rises the **spinal accessory nerve**, between the anterior and posterior roots. It contains small and large nerve fibres; the former pass into the internal division of this nerve and join the ganglion of the trunk of the vagus, while the large motor fibres form its external branch and supply the sterno-mastoid and trapezius muscles.]

[All the **vasomotor nerves** arise in the central nervous system, and they leave the spinal cord as the finest medullated fibres in the anterior roots of all the spinal nerves between the 2d thoracic and 2d lumbar (dog) "along the corresponding ramus visceralis, enter the lateral or main sympathetic chain of ganglia, where they become non-medullated, and are thence distributed either directly or after communication with other ganglia" (*Gaskell*).]

[The **vaso-dilator** nerves leave the central nervous system among the fine medullated fibres, which help to form the cervico-cranial and sacral rami viscerales, and pass without altering their character into the distal ganglia (*Gaskell*).]

["The **viscero-motor** nerves upon which the peristaltic contraction of the thoracic portion of the œsophagus, stomach, and intestines depends, leave the central nervous system in the outflow of fine medullated nerves which occurs in the upper part of the cervical region, and pass by way of the rami viscerales of the accessory and vagus nerves to the ganglion trunci vagi, where they become non-medullated" (*Gaskell*).]

["The **inhibitory** nerves of the circular muscles of the alimentary canal and its appendages leave the central nervous system in the anterior roots, and pass out among the fine medullated fibres of the rami viscerales into the distal ganglia without communication with the proximal ganglia" (*Gaskell*).]

[**Structure of a Ganglion.**—The structure of the sympathetic nerve fibres and nerve cells has already been described in § 321. On making a section of a **sympathetic ganglion**, *e.g.*, the human superior cervical, we observe groups of cells with bundles of nerve fibres—chiefly non-medullated—running between them, and the whole surrounded by a laminated capsule of connective tissue, which sends septa into the ganglion. The **nerve cells** have many processes, and are, therefore, multipolar, and each cell is surrounded by a capsule with nuclei on its inner surface (Fig. 368, II). The processes pierce the capsule, and one of them certainly—and perhaps all the processes—are connected with a nerve fibre. Ranvier states that each cell has a fibrillated outer portion and a more granular inner part. Each of the processes becomes continuous with a fibre of Remak. Not unfrequently yellowish-brown pigment is found in the cell substance. Similar cells have been found in the ophthalmic, submaxillary, otic, and spheno-palatine ganglia. The number of medullated nerve fibres diminishes as the sympathetic nerves are traced toward their distribution. Ranvier states that it is possible in the rabbit to trace the conversion of a medullated fibre into a branched fibre of Remak. The **blood vessels** of the sympathetic ganglia in mammals are peculiar. The arteries are small, and after subdivision form a capillary network, each mesh of which encloses several ganglionic cells. The veins, on the contrary, are very large, tortuous, varicose, and often terminate in culs-de-sac, into which several capillaries open. The arrangement of the veins is spoken of as the **venous sinuses** of these ganglia, being compared by Ranvier to the sinuses of the dura mater and venous plexuses of the spinal canal.]



FIG. 439.

Diagram of the visceral nerves of the dog; the arrangement of the cranial visceral nerves is taken from Henle. The nerves which contain bundles of fine medullated nerve fibres are indicated thus: - - - - -; those which consist chiefly of non-medullated fibres are indicated thus: ——. The formation of the rami viscerales in the cervico-cranial, thoracic, and sacral regions, and the general distribution of the visceral nerves are shown (*Gaskell*).

Functions. — The following is merely a *general* summary:—

I. Independent Functions of the sympathetic are those of certain nerve plexuses which remain after all the nervous connections with the cerebro-spinal branches have been divided. The activities of these plexuses may be influenced—either in the direction of inhibition or stimulation—through fibres reaching them from the cerebro-spinal nerves.

To these belong:—

1. The automatic ganglia of the heart (§ 58).
2. The mesenteric plexus of the intestine (§ 161).
3. The plexuses of the uterus, Fallopian tubes, ureters (also of the blood and lymph vessels).

II. Dependent Functions.—Fibres run in the sympathetic, which (like the

peripheral nerves) are active only when their connection with the central nervous system is maintained, *e.g.*, the sensory fibres of the splanchnic. Others again convey impulses from the central nervous system to the *ganglia*, while the ganglia in turn modify the impulses which inhibit or excite the movements of the corresponding organs.

The following statement is a *résumé* of the functions of the sympathetic, according to the anatomical arrangement:—

A. Cervical Part of the Sympathetic. 1. **Pupil-dilating fibres** (compare *Ciliary ganglion*, § 347, I, and *Iris*, § 392). According to Budge, these fibres arise from the spinal cord, and run through the upper two dorsal and lowest two cervical nerves into the cervical sympathetic, which conveys them to the head. Section of the cervical sympathetic or its rami communicantes causes contraction of the pupil. (The central origin of these fibres is referred to in § 362, 1, and § 367, 8.)

2. **Motor fibres** for Müller's smooth muscle of the orbit, and *partly* for the external rectus muscle (§ 348).

3. **Vasomotor** branches for the outer ear and the side of the face (*Cl. Bernard*), tympanum (*Prussak*), conjunctiva, iris, choroid, retina (*only in part—see Ciliary ganglion*, § 347, I), for the vessels of the œsophagus, larynx, thyroid gland—fibres for the vessels of the brain and its membranes (*Donders and Callenfels*).

4. In the cervical portion are afferent fibres which excite the vasomotor centre in the medulla (*Aubert*).

5. **Secretory** (trophic) and **vasomotor** fibres for the salivary glands (§ 145).

6. **Sweat-secretory** fibres (see § 288, II).

7. According to Wolferz and Demtschenko the lachrymal glands receive sympathetic **secretory** fibres (?).

B. Thoracic and Abdominal Sympathetic.—First of all there is—

1. The sympathetic portion of the **cardiac plexus** (§ 57, 2), which receives **accelerating** or augmentor fibres for the heart from the lower cervical and 1st thoracic ganglion (*Cl. Bernard, v. Bezold, Cyon, Schmiedeberg*). The fibres arise partly from the sympathetic and partly from the plexus around the vertebral artery (*v. Bezold, Bever*). (Compare § 370.)

2. For the vasomotor fibres passing through the sympathetic to the extremities, skin of the trunk, and lungs (see § 371). For vaso-dilators (§ 472).

3. The cervical sympathetic and the splanchnic contain fibres which, when their central ends are stimulated, excite the **cardio-inhibitory system** in the medulla oblongata (*Bernstein*).

4. The functions of the **splanchnic** are referred to in §§ 164, 175, 276, and 371.

5. The functions of the **cœliac** and **mesenteric plexuses** are referred to in §§ 183 and 192. After extirpation of the cœliac ganglion, Lamansky observed temporary disturbance of digestion, undigested food being passed per anum.

6. For the **secretory** fibres for **sweating**, see § 289, II.

7. Lastly, the abdominal portion of the sympathetic contains **motor** and **vasomotor** fibres for the *spleen*, the *large intestine* (accompanying its arteries), *bladder* (§ 280), *ureters*, uterus (running in the hypogastric plexus), vas deferens, and vesiculæ seminales. *Stimulation* of all of these nerve channels causes increased movement of the organs, but it must be remembered that the diminished supply of blood thereby produced also acts as a stimulus (§ 161). *Section* of these nerves is followed by dilatation of the blood vessels, with subsequent derangement of the circulation, and ultimately of the nutrition. The relation of the **suprarenal bodies** to the sympathetic is referred to in § 103, IV. The **renal plexus** is referred to in § 276, while the **cavernous plexus** is treated of in § 436.

Pathological.—Considering the numerous connections of the sympathetic, we would naturally suppose that it offers an extensive area for pathological changes. Affections involving the vasomotor system are referred to in § 371.

The **cervical sympathetic** is most frequently paralyzed or stimulated by traumatic conditions, wounds by bullets or knives, tumors, enlarged lymph glands, aneurisms, inflammations of the apices of the lungs and the adjacent pleuræ, while exostoses of the vertebræ may stimulate it in part or paralyze it in part. The phenomena so produced have been partly analyzed in treating of the ciliary ganglion (§ 347, I). **Stimulation of the cervical sympathetic** in man causes dilatation of the pupil (**mydriasis spastica**), pallor of the face, and occasionally hyperidrosis or profuse sweating (§ 289, 2, and § 288); disturbance of vision for near objects, as the pupil cannot be contracted (see *Accommodation*), and hence the spherical aberration of the lens (§ 391) must also interfere with vision; protrusion of the eyeball with widening of the palpebral fissure. **Paralysis** or **section of the cervical sympathetic** causes increased fullness of the blood vessels of the side of the head, with occasional anidrosis; contraction of the pupil (**myosis paralytica**), which undergoes changes in its diameter during accommodation, but not as the effect of the stimulation of light—atropin dilates it slightly. The slit between the eyelids is narrowed, the eyeball retracted and sunk in the orbit, the cornea somewhat flattened, and the consistence of the eyeball diminished. Stimulation of the sympathetic is followed by an *increased secretion of saliva* (§ 145). The above-described symptoms have been occasionally accompanied by **unilateral atrophy of the face.**

[**Section of the Cervical Sympathetic.**—This experiment is easily done on a rabbit, preferably an albino one. Divide the nerve in the neck, and immediately thereafter (1) the ear and adjoining parts on that side become greatly congested with blood, blood vessels appear that were formerly not visible, and as a result of the increased quantity of blood in the ear (hyperæmia), there is (2) a rise of the temperature amounting to even 4° to 6° C. (*Cl. Bernard*). These are the *vaso-motor* changes. (3) The pupil is contracted, the cornea flattened, and there is retraction of the eyeball and consequent narrowing of the palpebral fissure. These are the *oculo-pupillary* symptoms. **Stimulation** (electrical) of the peripheral end produces the opposite results,—pallor of the ears, owing to contraction of the blood vessels, with consequent fall of the temperature; dilatation of the pupil, bulging of the cornea, protrusion of the eyeball (**exophthalmos**), and widening of the palpebral fissure. At the same time, the blood vessels to the salivary glands are contracted, and there is a secretion of *thick* saliva. The last results are due to the *vaso-constrictor and secretory* fibres. The vasomotor and oculo-pupillary fibres, although they lie in the same trunk in the neck, do not issue from the cord by the same nerve roots; the latter come out of the cord with the anterior roots of the 1st and 2d dorsal nerves (dog), while section of the cord between the 2d and 4th dorsal vertebræ produces the vasomotor changes only. The nasal mucous membrane and lachrymal gland are influenced by the sympathetic.]

[**Division** of the cervical sympathetic in young, *growing* animals results in hypertrophy of the ear and increased growth of the hair on that side (*Bidder, W. Stirling*).]

[The **vago-sympathetic nerve** (dog) in the neck contains **vaso-dilator** fibres (really in the sympathetic) for the skin and mucous membranes of that side of the head. Weak stimulation of the central end of the sympathetic causes dilatation of the blood vessels of these parts. The vaso-dilator fibres of the superior maxillary nerve probably come from the same source. The centre for these nerves is in the dorsal region of the cord between the 1st and 5th dorsal vertebræ, where the fibres pass out with the rami communicantes to enter the cervical sympathetic (*Dastre and Morat*). The vaso-dilator fibres occur in the posterior segment of the ring of Vieussens, and when they are stimulated after section of the 7th cranial nerve, there is a "**pseudo-motor**" effect on the muscles of the cheek and lip (§ 349).]

Irritation in the area of the splanchnic, as occurs occasionally in lead poisoning, is characterized by violent pain (lead colic), inhibition of the intestinal movements (hence the persistent constipation), slowing of the heart's action, brought about reflexly, just as in Goltz's "tapping" experiment (§ 369). Irritation in the area of the sensory nerves of the sympathetic may give rise to that condition which is called by Romberg neuralgia hypogastrica, a painful affection of the lower abdominal and sacral regions, hysteralgia, neuralgia testis, which are localized in the plexuses of the sympathetic. In affections of the *abdominal sympathetic*, there may be severe constipation, with diminished or increased secretion of the intestinal glands (§ 186).

357. **COMPARATIVE—HISTORICAL.—Comparative.**—Some of the **cranial nerves** may be absent, others, again, may be abortive, or exist as branches of other nerves. The facial nerve, which supplies the muscles of expression in man, and is, at the same time, the nerve for facial respiratory movements, diminishes more and more in the lower classes of the vertebrata, *pari passu* with the diminution of the facial muscle. In **birds** and **reptiles**, it supplies the muscles of the

hyoid bone, or the superficial cervical muscles of the nape of the neck. In **amphibians** (frog), the facial no longer exists as a separate nerve, the nerve which corresponds to it springing from the trigeminus. In **fishes**, the 5th and 7th nerves form a joint complex nerve. The part corresponding to the facial (also called ramus opercularis trigemini) is the chief motor nerve of the muscles of the gill cover, and is, therefore, the respiratory nerve. In the cyclostomata (lamprey) there is an independent facial. The *vagus* is present in all vertebrata; in fishes it gives off a large nerve, the *lateral nerve* of the body (N. lateralis), which runs along each side of the body close to the lateral canal. It is also present in the tadpole. Its rudimentary representative in man is the auricular branch. In the frog, the 9th, 10th, and 11th arise together from one trunk, and the 7th and 8th from another. In fishes and amphibia, the hypoglossal is the first cervical nerve. In amphioxus, the cerebral and spinal nerves are not distinct from each other. The **spinal nerves** are remarkably similar in all classes of the vertebrata. The **sympathetic** is absent in the cyclostomata, where it is represented by the vagus. Its course is along the vertebral column, where it receives the rami communicantes of the spinal nerves. In the region of the head its connections with the 5th and 10th nerves are specially developed. In frogs, and still more so in birds, the number of connections with the cranial nerves increases.

Historical.—The vagus and sympathetic were known to the Hippocratic School. According to Erasistratus, all the nerves proceed from the brain and spinal cord; Herophilus was the first to distinguish the nerves from the tendons, which Aristotle confounded with each other. Marianus (80 A. D.) recognized seven pairs of cranial nerves. Galen was in possession of a wide range of important facts in the physiology of the nervous system (§ 140); he observed that loss of voice followed ligature of the recurrent nerves; and he was acquainted with the accessorius, and the ganglia on the abdominal nerves. The cauda equina is referred to in the Talmud; Coiter (1573) described exactly the anterior and posterior spinal nerve roots. Van Helmont († 1644) states that the peripheral motor nerves also give rise to impressions of pain, and Cesalpinus (1571) remarks that interruption of the blood stream makes the parts insensible. Thomas Willis described the chief ganglia (1664). In Des Cartes there is the first indication of reflex movements; Steven Hales and Robert Whytt showed that the spinal cord was necessary for such acts. Prochaska described the reflex channels [while Marshall Hall established the doctrine of reflex, or, as he called them, "**diastaltic**" actions]. Duverney (1761) discovered the ciliary ganglion. Gall traced more carefully the course of the 3d and 6th nerves, and also the spinal nerves into the gray matter. Hitherto only nine nerves of the brain had been enumerated; Sömmerring (1791) separated the facial from the auditory nerve, Andersch (1797) the 9th, 10th, and 11th nerves.

PHYSIOLOGY OF THE NERVE CENTRES.

358. GENERAL.—[The nerve fibres and nerve cells constitute the elements out of which nerve centres are formed, being held together by connective tissue. In the process of **evolution**, groups of nerve cells with connecting fibres are arranged to constitute nervous masses, whereby there is a corresponding integration of function. Thus, with structural integration there is a functional integration. When the structure suffers so also does the function, and those parts which are most evolved, as well as those actions which have to be learned by practice, are the first to suffer during the **dissolution** of the nervous system.]

General Functions.—The central organs of the nervous system are in general characterized by the following properties :—

1. They contain **nerve cells,** which are either arranged in groups in the interior of the central organs of the nervous system, or embedded in the peripheral branches of the nerves. [Nerve cells are centres of activity, originate impulses and conduct impulses as well, while nerve fibres are chiefly conductors.]

2. The nerve centres are capable of discharging **reflexes,** *e. g.*, reflex motor, reflex secretory, and reflex inhibitory acts.

3. The centres may be the seat of **automatic excitement,** *i.e.*, they may manifest phenomena, without the application of any *apparent* external stimulus. The energy so liberated may be transferred to act upon other organs. This automatic state of excitement or stimulation may be *continuous*, *i.e.*, may be continued without interruption, when it is called tonic automatic or **tonus**; or it may be *intermittent* and occur with a certain rhythm (*rhythmical automatic*).

4. The central organs are **trophic centres** for the nerves proceeding from them ; they may also perform similar functions for the tissues innervated by them.

5. The **psychical activities** are dependent upon an intact condition of the ganglionic central organs. These various functions are distributed over different centres.

[The term "**centre**" is merely applied to an aggregation of nerve cells so related to each other as to subserve a certain function, but, inasmuch as these cells are connected to each other and with other cells in many ways, various combinations of them may result; again, we have also to take into account the greater or less resistance in some paths than in others, so that the variety of combinations which these cells may subserve is enormous. These cells give off processes which branch, and anastomose with processes from other cells. Thus, innumerable ways are opened up to nervous impulses by these combinations, so that in a certain way we may regard a cell as a junction of these conducting fibres, or a "shunt" whereby an impulse may be shunted on to one or other branch in the direction of least resistance, or in the best beaten path as it were, while there may be a "block" in other directions.]

[In connection with the histology of the central nervous system we have to study :—

A. The nervous constituents.
- (1) Nerve fibres.
- (2) Nerve cells.

B. Non-nervous constituents.
- (1) Vessels (blood and lymph).
- (2) Epithelium.
- (3) Sustentacular tissue.
  - (*a*) Connective tissue.
  - (*b*) Neuroglia.]

THE SPINAL CORD.

359. STRUCTURE OF THE SPINAL CORD.—[The key to the study of the central nervous system is to remember that it begins as an involution of the epiblast, and is originally tubular, with a central canal, dilated in the brain end into ventricles. In the spinal cord there are three concentric parts: first, the columnar ciliated epithelium, outside this the central gray tube, and covering in all, the outer white conducting fibres (*Hill*).]

Structure.—The spinal cord consists of white matter externally and gray matter internally. [It is invested by **membranes**—the **pia mater,** composed of two layers and consisting of connective tissue with blood vessels, being firmly adherent to the white matter and sending septa into

FIG. 440.



Transverse section of the spinal cord; in the centre is the butterfly form of the gray matter surrounded by white matter. *p*, posterior, and *a*, anterior, horns of the gray matter; PR, posterior roots; AR, anterior roots of a spinal nerve; A, A, the white anterior; L, L, the lateral; P, P, the posterior columns.

the substance of the cord. Both layers dip into the anterior median fissure, and only the inner one into the posterior median groove. The **arachnoid** is a more delicate membrane and non-vascular, while the **dura mater** is a tough membrane lining the vertebral canal, and forming a theca or protective coat for the cord (§ 381).] The **gray mater** has the form of two crescents)-(placed back to back [or a capital H], in which we can distinguish an **anterior** (*a*) and a **posterior horn** (*p*), a middle part, and a **gray commissure** connecting the two crescents. In the centre of this gray commissure is a canal—**central canal**—which runs from the calamus scriptorius downward; it is lined throughout by a single layer of ciliated cylindrical epithelium [in the foetus, the cilia not being visible in the adult], and the canal itself is the representative of the embryonal "medullary tube" (Figs. 440, 446). [The part of the gray commissure in front of this canal is called the *anterior*, and the part behind, the *posterior* gray commissure. In front of the gray commissure, and between it and the base of the anterior median fissure, are bundles of white nerve fibres passing in a horizontal or oblique direction from the anterior column of one side to the gray matter of

the anterior cornu of the opposite side (Fig. 440). These decussating fibres constitute the **white commissure.**]

The **white matter** surrounds the gray, and is arranged in several **columns** [**anterior, lateral,** and **posterior**—by the passage of the nerve roots to the cornua (Figs. 440, 446)]. Along the anterior surface of the cord there runs a well-marked fissure, which dips into the cord itself, but does not reach the gray matter, as a mass of white matter—the **white commissure**—runs from one side of the cord to the other. Between this fissure, known as the **anterior median fissure,** and the line of exit of the anterior roots of the spinal nerves, lies the **anterior column** (A); the white matter lying laterally between the origin of the anterior and posterior roots of the spinal nerves is the **lateral column** (L), while the white matter lying between the line of origin of the posterior roots and the so-called **posterior median fissure,** is the **posterior column** (P). [The posterior median fissure is not a real fissure, but is filled up with the inner layer of the pia mater, which dips down from the under surface of this membrane quite to the gray matter of the posterior commissure.] Each posterior column, in certain regions of the cord, may be subdivided into an inner part lying next the fissure, the **postero-median** or *Goll's column*, or the *inner root zone* (*Charcot*, Fig. 454, *c*); and an outer larger part next the posterior root, known as the **postero-external** or *Burdach's column*, or the *outer root zone* (*Charcot*, Fig. 454, *d*).

FIG. 441.

FIG. 442.

FIG. 441.—Transverse section of the white matter of the cord; × 150. *a*, peripheral layer. Besides the transverse sections of the nerve fibres, large and fine, there are three-branched connective-tissue corpuscles (*c*).

FIG. 442.—Multipolar nerve cells from the gray matter of the anterior horn of the spinal cord (ox). *a*, nerve cell; *b*, axis cylinder; *c*, gray matter; *d*, white matter of column; *e*, *e*, branches of cells.

The **white matter** consists chiefly of medullated fibres without the sheath of Schwann and Ranvier's nodes, but provided with the neuro-keratin sheaths of Kühne and Ewald (§ 321), the fibres themselves being chiefly arranged *longitudinally*. [The incisures of Schmidt exist in these fibres,

FIG. 443.

Diagram of the absolute and relative extent of the gray matter, and of the white columns in successive sectional areas of the spinal cord, as well as the sectional areas of the several entering nerve roots. NR, nerve roots; AC, LC, PC, anterior, lateral, and posterior columns; Gr, gray matter.

and can be demonstrated by the interstitial injection of osmic acid (Ranvier).] The nerve fibres of the nerve roots, as well as those that pass from the gray matter into the columns, have a transverse or oblique course. There are also decussating fibres in the anterior or white commissure. [In a

transverse section of the white matter of the spinal cord, the nerve fibres are of different sizes, and appear like small circles with a rounded dot in their centre—the axis cylinder—the latter may be stained with carmine or other dye (Fig. 441). They are smallest in the postero-median or Goll's column, and largest in the crossed and direct pyramidal tracts, which are motor. The white substance of Schwann, especially in preparations hardened in salts of chromium, often presents the appearance of concentric lines. Fine septa of connective tissue carrying blood vessels lie between groups of the nerve fibres, while here and there between the nerve fibres may be seen branched neuroglia corpuscles. Immediately underneath the pia mater there is a pretty thick layer of neuroglia, which invests the prolongations of the pia into the cord.]

[The **gray matter** differs in shape in the different regions of the cord, and so does the gray commissure (Fig. 444). The latter is thicker and shorter in the cervical than in the dorsal region, while it is very narrow in the lumbar region. The amount of gray matter undergoes a great increase opposite the origins of the large nerves, the increase being most marked opposite the cervical and lumbar enlargements. Ludwig and Woroschiloff constructed a series of curves from measurements by Stilling of the sectional areas of the gray and white matter of the cord, as well as of the several nerve roots. These curves have been arranged in the annexed convenient form by Schäfer after Woroschiloff (Fig. 443)] :—

[In the **cervical** region, the lateral white columns are large, the anterior cornu of the gray matter is wide and large, while the posterior cornu is narrow; Goll's column is marked off by a depression and a prolongation of the pia mater; the cord itself is broadest from side to side. In the **dorsal** region, the gray matter is small in animals, and both cornua are narrow and of nearly equal breadth, while the cord itself is smaller and cylindrical. In it the intermedio-lateral and posterior vesicular groups of cells are distinct. They have probably relations to viscera. The commissure lies well forward between the crescents. In the **lumbar** region, the gray matter is relatively and absolutely greatest, while the white lateral columns are small, the central canal in the commissure being nearly in the middle of the cord. In the **conus medullaris**, the gray matter makes up the great mass of it, with a few white fibres externally (Fig. 444).]

FIG. 444.



Transverse sections of the spinal cord in different regions. A, through the middle of the cervical; B, the dorsal; C, the lumbar enlargement; D, upper part of the conus medullaris; E, at the 5th sacral vertebra; F, at coccyx; A, B, C, enlarged twice; D, E, F, thrice; α, anterior, β, posterior root.

The **anterior cornu** of the gray matter is shorter and broader, and does not reach so near to the surface as the posterior; moreover, each anterior nerve root arises from it by several bundles—it contains several groups of large multipolar ganglionic cells (Fig. 442); the **posterior cornu** is more pointed, longer, and narrower, and reaches nearer to the surface, the posterior root arising by a single bundle at the postero-lateral fissure; while the cornu itself contains a few fusiform nerve cells, and is covered by the **substantia gelatinosa** of Rolando, which is in part an accumulation of neuroglia.

[The **substantia gelatinosa** on the posterior cornu is marked by striation where the posterior root fibres traverse it. It contains some connective-tissue cells and some fusiform nerve cells, especially near the margins. The substance itself stains deeply with carmine.]

[The outer margin of the gray matter near its middle is not so sharply defined from the white matter as elsewhere; and, in fact, a kind of anastomosis of the gray matter projects into the lateral column, especially in the cervical region, constituting the *processus reticularis* (Fig. 446).]

[**Arrangement of Nerve Cells**—The nerve cells are arranged in four groups, forming columns more or less continuous. There are those of the anterior and posterior horns, those of the lateral column (intermedio-lateral), and the posterior vesicular column of Clarke. The anterior and posterior groups exist as continuous columns along the entire cord. The cells in the anterior cornu are subdivided into smaller groups, which vary in the different regions of the cord. There is an *inner or median group* near the anterior angle of the cornu. It is the smallest group, and is absent in the lumbar region. Near the anterior edge is the *anterior group*, and in the external part of the cornu is the *antero-lateral group*. These two groups are often united, as in the mid-cervical region. There is usually a third large group—the *external* or *postero-lateral* in the posterior outer

angle of the anterior cornu—the cells of the anterior horn being very large (67 to 135 μ), while the fusiform cells of the posterior horn are 18 μ in diameter. Those of the lateral column are distinct, except in the lumbar and cervical enlargements, where they blend with the anterior horn. The column of Clarke (cells 40 to 90 μ) is discontinued, and is limited to (1) the thoracic region, (2) cervico-cranial region, (3) sacral region, being most conspicuous in (1), where it corresponds absolutely to the outflow of visceral nerves (*Gaskell*). In the sacral region it corresponds to the "sacral nucleus of Stilling," while in the cervical region it begins in the dog at the 2d cervical nerve, forming the cervical nucleus, being continued above into the nuclei of the vagus and glosso-pharyngeal nerves. The cells of this column give rise to small medullated nerve fibres or the **leucenteric fibres** of Gaskell.]

The multipolar ganglion cells are largest, and arranged in groups in the anterior horns of the gray matter (Fig. 446—"**motor** ganglionic cells"). [They also occur in the lateral process and in the processus reticularis. It is to be noted that the cells become more branched as we proceed upward among the vertebrata. These cells usually contain pigment granules, and, according to Pierret,

FIG. 445.

FIG. 446.



FIG. 445.—Nerve cell from Clarke's column (horse). The arrow indicates the cerebral end.
FIG. 446.—Transverse section of the spinal cord (lower dorsal). A, L, P, anterior, lateral, and posterior columns; A.M.F., P.M.F., anterior and posterior median fissures; *a*, *b*, *c*, cells of the anterior horn; *d*, posterior cornu and substantia gelatinosa; *e*, central canal; *f*, veins; *g*, anterior root bundles; *h*, posterior root bundles; *i*, white commissure; *j*, gray commissure; *l*, reticular formation.

their size has a direct relation to the length of the nerve fibre proceeding from them; so that they are largest in the lumbar enlargement, smaller in the cervical enlargement, and smallest in the dorsal region. Smaller spindle-shaped ("**sensory**") cells occur in much smaller numbers in the gray matter of the posterior horn. The cells of **Clarke's column** (Fig. 445) are smaller (30–60 μ), and are usually arranged with their long axis in the long axis of the cord. The processes are fewer, but one is generally directed toward the head, and some toward the caudal end of the body. They usually contain much pigment, which is generally disposed toward the cerebral pole of the cell.]

[In a **longitudinal section** of the cord (Fig. 447), these cells are seen to be arranged in columns, the large multipolar cells in the anterior horn (*m*); in the same section are shown, the longitudinal direction of the nerve fibres in the anterior (*a*) and posterior white columns (*c*), the horizontal direction of the fibres of the anterior and posterior nerve roots (*b* and *f*).

The **gray matter** contains an exceedingly delicate fibrous network of the finest nerve fibrils (*Gerlach*), which is produced by the repeated division of the protoplasmic processes of the multipolar

ganglionic cells. Medullated nerve fibres traverse and divide in the gray matter and become non-medullated; some of them merely pass through the gray matter of the non-medullated fibres and

FIG. 447.



FIG. 448.



FIG. 447.—Longitudinal section of the human spinal cord. *a*, anterior, *c*, posterior, *d*, lateral white columns; *b*, anterior, *e*, posterior nerve roots; *f*, horizontal (pyramidal) fibres passing to *m*, cells of anterior cornu; *u*, oblique fibres of posterior root.

FIG. 448.—Multipolar nerve cell, from the anterior horn of the spinal cord. *z*, axis-cylinder process; *y*, branched processes.

FIG. 449.



Scheme of the course of the fibres in the spinal cord. The longitudinal fibres are indicated by small circles; while the nerve cells are black.

terminate in Gerlach's network. Fibres pass from the gray matter of one side to that of the other through the commissures in front of and behind the central canal.

[By means of Weigert's method of staining medullated nerve fibres (p. 579), it has been proved that numerous, fine, medullated nerve fibres exist in the gray substance.]

Gerlach's Theory.—According to Gerlach, the connection of the fibres and cells is as follows: The fibres of the anterior root proceed directly to the ganglionic cells of the anterior horn, with which they form direct communications by means of the unbranched axial cylinder processes (Fig. 448, *z*). The gray network of protoplasmic processes, produced by the repeated branchings of the fibres of these cells, gives origin to *broad* fibres. A part of the latter (the *median* bundle) passes through the anterior white commissure to the other side, and then ascends in the anterior column of the opposite side. Other fibres (the *lateral* bundle) pass into the lateral column of the same side, and ascend in it as far as the decussation of the pyramids, where they cross in the medulla to the other side. The fibres of the *posterior root* enter the posterior horn, and, after dividing, terminate in the nervous protoplasmic network of the gray matter. By means of this network they are connected indirectly with the ganglionic cells of the posterior horn, which are said not to have an axial cylinder process. The gray network, which connects the ganglia of the anterior and posterior horns with each other, also sends fibres, which pass to the other side of the cord in front of and behind the central canal. They then take a backward course, to ascend partly in the posterior horns and partly in the lateral columns.

[The **anterior root** enters in several bundles of coarse fibres which diverge before they reach the gray matter. Most, or perhaps all, the fibres end in the large motor nerve cells in the anterior cornu or its lateral process (Fig. 449, *a*, *b*, *c*, *d*, *e*). But the fibres diverge in all directions, some of the fibres of the bundle nearest the middle line (3) end in the laterally placed cells (*e*); a part (4) crosses the anterior commissure to end in cells on the opposite side (*d'*). Some of them (6) run upward to become connected with motor cells lying further up the cord.]

[The **posterior root** enters as a single bundle, composed of finer fibres with bundles of thicker ones. The finest fibres, which are usually placed most laterally (7), or **outer radicular fibres**, curve into the longitudinal fibres, so that they are cut across in a transverse section, but they again take a horizontal course and enter the substantia gelatinosa. The remainder of the fibres split into an outer and inner part. The lateral smaller part or **central** fibres (8 to 10) passes into the substantia gelatinosa, where it divides into several strands, some of which pass into the central part of the gray matter (10), while others (8) pass upward and downward in a longitudinal direction. Some of the fibres (9) perhaps end in the nerve cells (*f*) in the posterior cornu. The median, inner or **internal radicular fasciculus** (11 to 14), sweeps through the postero-external column, and, after running a longitudinal course in the white matter, enters the gray substance of the posterior cornu. Some fibres (11) pass to the small fusiform cells (*g*); and others (13) pass to be connected with the cells of Clarke's column (*h*), when it is present. From the cells of Clarke's column, fibres seem to pass to the direct cerebellar tract (20). Some of the fibres (12) pass into the

FIG. 450.

Isolated connective-tissue corpuscle or "glia cell" from the human spinal cord; × 800.

FIG. 451.

Longitudinal section of the spinal cord. *a*, white, *b*, gray matter; *c*, crystals of mercuric chloride. Prepared by Golgi's mercuric chloride method; × 80.

posterior gray commissure, to reach the opposite side. This so far only accounts for a part of the fibres. Some of them (8 to 10) are concerned in the formation of the fine nerve plexus in the gray matter, whereby, perhaps, they become connected with the cells in the anterior cornu. It is asserted that some of the fibres (14) ultimately pass into Goll's column. Many of the fibres in the posterior root have been proved to be directly connected with nerve cells, *e. g.*, in Petromyzon by Freund, and in the Proteus by Klaussner, so that it is very doubtful if, in the higher animals, the fibres of the posterior root are directly connected with the plexus of gray fibres as suggested by Gerlach (p. 680).]

Neuroglia.—The **connective tissue** of the spinal cord arises in part from the pia mater and passes into the white matter, carrying with it blood vessels, and forming septa, which separate the nerve fibres into bundles. [The connective tissue of the central nervous system is so far peculiar, that the inter-cellular substance is reduced to a minimum. It consists of a reticulated connective tissue composed of fine fibres, which form a network. Fig. 450 shows one of the cells, "glia cells," isolated. It consists of a small, granular, nucleated body, with numerous excessively fine, slightly-branched, stiff processes. The processes form a sustentacular tissue for the nerve fibres and blood vessels. The arrangement and distribution of these cells is best seen in sections of a cord hardened by Golgi's method in corrosive sublimate solution (Fig. 451). In some situations, *e. g.*, the white matter of the cerebrum and cerebellum, the cells are smaller and more angular, and the processes are often connected with the outer coat of the blood vessels. On the whole, the connective tissue is much finer in the brain than in the cord. The central canal is surrounded with a denser layer of

this tissue, known as the "**central ependyma,**" which stains deeply with carmine, and is very like the substantia gelatinosa in its structure (p. 678). We must distinguish from this form of connective tissue that special form in the gray matter to which Virchow gave the name of **neuroglia.** It is specially adapted to fill up the spaces left by the other elements, and without interfering with the exchange of fluids serves to hold the elements together. It is an excessively finely granular ground substance in the gray matter. It is also an inter-cellular substance, but in the adult the cells to which it owes its origin are no longer to be found. It is doubtful, from its chemical nature, if it is really to be reckoned along with the connective tissues. It seems to be rather a tissue *sui generis*, belonging to the nervous system, and it is present in very small amount.] The neuroglia is also abundant on the sides and apex of the posterior horns, where it is called the **gelatinous substance of Rolando.**

[**Blood Vessels.**—The spinal cord is partly supplied with blood by arteries from the vertebrals, and partly by branches of the intercostal, lumbar, and sacral

FIG. 452.



Semi-diagrammatic arrangement of the arteries in the spinal cord. *Spa*, anterior spinal; *s*, sulcine artery; *sc*, sulco-commissural; *an*, its anastomosing branch; *cl*, to Clarke's column; *Fp*, posterior fissure; *ra*, *rp*, branches along anterior and posterior roots; *cp*, for post. cornu; *if*, inter-funicular; *la*, *lm*, *lp*, anterior, median, and posterior lateral.

FIG. 453.

Injected blood vessels of the spinal cord.

arteries, which reach it through the inter-vertebral foramina, and pass to the cord along the anterior and posterior roots.]

[**Blood Vessels.**—The **anterior median** (or anterior spinal) (Fig. 452) artery gives off branches, which dip into the fissure of the same name, pass to its base, and, after perforating the anterior commissure, divide into two branches, one for each mass of gray matter, and each branch in turn splits into three, which supply part of the anterior, median, and posterior gray matter. The arteries lying in the sulci are called **arteriæ sulci** (*s*) by Adamkiewicz. In the gray matter, there is usually a special branch to Clarke's column (*cl*). The **vaso-coronary** arteries include all those arterial branches which proceed from the periphery into the white matter; the finer branches pass only into the white matter, but the larger into the gray substance. The largest branch is the artery of the posterior fissure (*Fp*), which passes along the posterior septum and reaches almost to the commissure, giving branches in its course. There is a large artery between the column of Goll and the postero-external column, viz., the inter-funicular artery (*if*). Arteries enter along the anterior and posterior roots (*ra*, *rp*). There are also a median lateral artery (*lm*), and an anterior and posterior lateral

(*lp*, *la*), which enter the lateral column. The generel result is that the gray matter is much more vascular than the white, as is shown in Fig. 453. Some small vessels come from the pia and send branches to the white matter, and unbranched arteries to the gray matter, where they form a capillary plexus. The blood vessels are surrounded by **perivascular lymph spaces** (*His*).] [With regard to the blood vessels supplying the cord as a whole, Moxon has pointed out that, owing to the cord not being as long as the vertebral canal, the lower nerves have to run down within the vertebral canal, before they emerge from the appropriate inter-vertebral foramina. As **re-enforcing arteries** enter the cord along the course of these nerves, necessarily the branches entering along the course of the lumbar and lower dorsal nerves are long, and this, together with their small size, offers considerable resistance to the blood stream. Hence, perhaps, the reason why the lower part of the cord is so apt to be affected by various pathological conditions.]

[**Functions of the Spinal Cord.**—(1) It is a great **conducting medium**, conducting impulses upward and downward, and within itself from side to side; (2) the great **reflex centre**, or rather series of so-called centres; (3) **impulses originate** within it.]

Conducting Systems.—The whole of the longitudinal fibres of the spinal cord may be arranged systematically in special bundles, according to their function.

[**Methods.**—The course of the fibres and their division into so-called systems has been ascertained partly by **anatomical** and **embryological**, partly by **physiological** and **pathological** means. Apart from experimental methods, such as dividing one column of the cord and observing the results, we have the following methods of investigation: (1) Türck found that injury or disease of certain parts of the brain was followed by a degeneration downward, or **secondary descending degeneration** of certain of the nerve fibres connected with the seat of injury, *i. e.*, they were separated from their trophic centres and underwent degeneration. (2) P. Schieferdecker found also, after section of the cord, that above and below the level of the section, certain definite tracts of white matter underwent degeneration [thus showing that certain tracts had their trophic centre below; this constitutes **secondary ascending degeneration**]. [(3) **Gudden's Method.**—He showed, as regards the brain, that excision of a sense organ in a young growing animal was followed by atrophy of the nerve fibres and some other parts connected with it. Thus, the optic nerve and anterior corpora quadrigemina atrophy after excision of the eyeball in young rabbits.] (4) **Embryological.**—Flechsig showed that the fibres of the cord [and the brain also] during development became *covered with myelin* at different periods, those fibres becoming medullated latest which had the longest course. In this way he mapped out the following systems:—

Flechsig's Systems of Fibres.—1. In the **anterior column** lie (*a*) the uncrossed, anterior, or **direct pyramidal tract** [also called the *Column of Türck*]; and external to it is (*b*) the **anterior ground bundle**, or *anterior radicular zone* (Fig. 454). [The direct pyramidal tract varies in size, and it generally extends downward in the cord to about the middle of the dorsal region, diminishing steadily in its course; so that it would seem that this tract contains chiefly fibres for the arm. We do not know, exactly, how these fibres end, whether they cross to the opposite side, or remain on the same side, but most probably most of them pass through the anterior commissure to the gray matter of the opposite side.]

FIG. 454.



Scheme of the conducting paths in the spinal cord at the 3d dorsal nerve. The black part is the gray matter. *v*, anterior, *hw*, posterior, root; *a*, direct, and *g*, crossed, pyramidal tracts; *b*, anterior column ground bundle; *c*, Goll's column; *d*, postero-external column; *e* and *f*, mixed lateral paths; *h*, direct cerebellar tracts.

2. In the **posterior column** he distinguishes (*c*) **Goll's column**, or the *postero-median* (postero-internal) column; and (*d*) the **funiculus cuneatus**, *Burdach's column*, or the *posterior radicular zone*, or the *postero-external column*.

3. In the **lateral column** are (*e*) the **antero-lateral tract**, and (*f*) the **lateral mixed paths**, or *lateral limiting tract*, (*g*) the lateral or **crossed pyramidal tract**, and (*h*) the **direct cerebellar tract.**

[All the impulses from the central convolutions or motor areas of the cerebrum, by means of which *voluntary* movements are executed, are conducted by the **pyramidal tracts** *a* and *g* (§ 365). The fibres in these tracts descend from the central convolutions, *i. e.*, the motor areas pass through the white matter of the cerebrum, converging like the rays of a fan to the internal capsule, where they lie in the knee and anterior two-thirds of its posterior segment (the fibres for the face at the knee, and behind this in order those for the arm and leg), they then enter the middle third of the crusta (Fig. 502, *Py*), pass through the pons into the anterior pyramids of the medulla oblongata, where the great mass crosses over to the lateral column of the opposite side of the cord (**crossed pyramidal tract**), a small part descending in the cord on the same side as the antero-median tract (**direct pyramidal tract**, *a*). The crossed pyramidal tract lies external to the posterior half of the gray matter in the lateral column (Fig. 454, *g*), and it extends throughout the length of the cord. In the greater part of its course, it is separated from the surface by the direct cerebellar tract, but where the latter lies further forward, as at the third cervical segment and lower dorsal region, its posterior surface reaches the surface, while from the last dorsal segment, throughout the lumbar region, it comes quite to the surface, as the direct cerebellar tract ceases at the first lumbar vertebra. The pyramidal tract diminishes from above downward, and its fibres pass into the gray matter of the anterior cornu, and in all probability they subdivide to form fine fibrils, which become connected with the dense plexus of fine fibrils produced by the subdivision of the processes of the multipolar nerve cells. From each multipolar nerve cell, a nerve fibre proceeds and passes into the anterior root. The **direct cerebellar tract** (*h*) begins about the first lumbar nerve, and increases somewhat in thickness from below upward, but most of its fibres enter it at the first lumbar and lowest dorsal nerves. It forms a thin layer on the surface of the cord. Its fibres very probably arise in the cells of Clarke's column. As Clarke's column is connected with some of the fibres of the posterior root (for the trunk of the body), it follows that this tract connects certain parts of the posterior roots with the cerebellum. The fibres pass up through the cord and restiform body to the cerebellum. When it is divided, it degenerates upward, so that it conducts impulses in a centripetal direction.] The anterior (*e*) and lateral paths (*f*) and the anterior ground bundle (*b*) represent the channels which connect the gray matter of the spinal cord and that of the medulla oblongata; they represent the channels for reflex effects, and they also contain those fibres which are the direct continuation of the anterior spinal nerve roots, which enter the cord at different levels and penetrate into the gray matter. In *e* and *f* there are some sensory paths. Lastly, *c* unites the posterior roots with the gray nuclei of the funiculi graciles of the medulla oblongata; *d* connects some of the posterior nerve roots through the restiform body with the vermiform process of the cerebellum (*Flechsig*). The direction of conduction in the posterior columns, which are continuations of some of the fibres of the posterior roots, is upward, as part of them degenerates upward after section of the posterior root. Of the fibres of each posterior root, some pass directly into the posterior horn, another part ascends in the posterior column of the same side, and gradually as it ascends, it comes nearer the posterior median fissure. Some of these fibres enter the gray matter of the posterior horn at a higher level. The fibres of the posterior columns run upward as far as the inter-olivary layer and the decussation of the pyramids, where they seem to end, or at least form connections with the nerve cells of the funiculi graciles [clava] and cuneati [triangular nucleus]. A small part as arcuate fibres join the restiform body, and thus the cerebellum is connected with the posterior columns.

Further, the transverse **sectional area** of the direct and crossed pyramidal tracts (*a* and *g*), the lateral cerebellar tract (*h*), and Goll's column (*c*) gradually diminish from above downward; they serve to connect intra-cranial central parts with the ganglionic centres distributed along the spinal cord. The anterior root bundle (*b*), the funiculus cuneatus (*d*), and the anterior mixed lateral tracts (*e*) vary

in diameter at different parts of the cord, corresponding to the number of nerve roots. It has been concluded from this that these tracts serve to connect the gray matter at different levels in the cord with each other, and ultimately with the medulla oblongata, so that they do not pass directly to the higher parts of the brain (Fig. 443).

Nutritive Centres of the Conducting Paths.—Türck observed that the destruction of certain parts of the brain caused a **secondary degeneration** of certain parts of the cord, corresponding to the parts called *pyramidal tracts* by Flechsig (Fig. 455). P. Schieferdecker found the same effects *below* where he divided the spinal cord in a dog. Hence, it is concluded that the *nutritive* or *trophic centre* of the pyramidal tracts lies in the cerebrum. [Section of the cord, or an injury compressing the cord, besides giving rise to loss of certain functions (p. 698), results in structural changes in certain limited areas of the cord itself. Below the section after a time, the direct and crossed pyramidal tracts (Fig. 455, 1, 1′, 2, 2′) degenerate *downward, i. e.*, they undergo **descending secondary degeneration**, because they are cut off from their nutritive or trophic centres, which are situated above in the pyramidal cells of the motor areas of the brain (§ 378). The trophic centre for the fibres of the anterior root lies in the multipolar nerve cells of the anterior cornu of the gray matter of the cord. After section of the spinal cord, Goll's column and the direct cerebellar tracts degenerate *upward, i. e.*, they undergo **ascending secondary degeneration.** If the posterior columns even be divided, Goll's column degenerates upward toward the medulla oblongata, and the degeneration ends in the posterior pyramidal nucleus or clava. The same result occurs if the posterior nerve roots of the cauda equina be injured. Hence, fibres seem to pass from the posterior root into these columns, and the nerve cells in the clava must also have an important relation to these nerve fibres and the parts whence they are derived. The postero-external column remains undegenerated, so that there is a very sharp distinction between the two parts of the posterior column. As Goll's column degenerates upward, it points to its fibres conducting impulses in a centripetal direction, and to the nutritive centre for its nerve fibres being below. The trophic centre is probably in the spinal ganglion of the posterior root.]

FIG. 455.



Transverse section of the spinal cord, showing the secondary degeneration tracts. AR, anterior, TR, posterior root; 1, 1′ (CPT), region of the crossed pyramidal tract; 2, 2′ (DPT), direct pyramidal tract; PEC, postero-external column; LC, lateral column.

[If the cord be divided above the junction of the dorsal and lumbar regions, the **direct cerebellar tract** undergoes **ascending degeneration,** which extends through the restiform body to the cerebellum. Its trophic centre is probably in the cells of Clarke's column.] Those **fibres** of the spinal cord which **do not degenerate** after section of the cord, especially numerous in the lateral and anterior columns [anterior ground bundle, the anterior and lateral mixed zones of the lateral column, and the postero-external part of the posterior column], are commissural in function, connecting ganglionic cells with each other, and are, therefore, provided with a trophic centre at both ends.

Time of Development.—With regard to the time of development of the individual systems, Flechsig finds that the first formed paths are those between the periphery and the central gray matter, especially the *nerve roots*, *i. e.*, they are the first to be covered with the myelin. Then fibres which connect the gray matter at different levels are formed—the fibres which connect the gray matter of the cord with the cerebellum, and also the former with the tegmentum of the cerebral peduncle. At last the fibres which connect the ganglia of the pedunculus cerebri, and perhaps also the gray matter of the cortex cerebri with the gray matter of the cord are formed. In cases of anencephalous fœtuses, *i. e.*, where the cerebrum is absent, neither the pyramidal tracts nor the pyramids are developed. In the *brain* before birth, medullated nerve fibres are formed in the paracentral, central, and occipital convolutions, and in the island of Reil, and last of all in the frontal convolutions (*Tuczek*).

360. SPINAL REFLEXES.—By the term **reflex movement** is meant a movement caused by the stimulation of an *afferent* (sensory) nerve. The stimulus, on being applied to an **afferent nerve,** sets up a state of excitement (nervous impulse) in that nerve, which state of excitement is transmitted or conducted in a *centripetal* direction along the nerve to the *centre* (spinal cord in this case); where the nerve cells represent the **nerve centre** in the cord, the impulse is transferred to the motor, **efferent** or *centrifugal* channel. **Three factors,** therefore, are essential for a reflex motor act—a centripetal or *afferent fibre*, a *transferring centre*, a centrifugal or *efferent fibre;* these together constitute a **reflex arc** (Fig. 456). In a purely reflex act, all voluntary activity is excluded.

FIG. 456.



Scheme of a reflex arc. S, skin; M, muscle; N, nerve cell, with *af*, afferent, and *ef*, efferent fibres.

FIG. 457.



Section of a spinal segment, showing a unilateral and crossed reflex act. A, anterior, and P, posterior surface; M, muscle; S, skin; G, ganglion.

Reflex movements may be divided into the three following groups:—

I. The simple or partial reflexes, which are characterized by the fact that stimulation of a sensory area discharges movement in one muscle only, or at least in one limited group of muscles. **Examples:** A blow upon the knee causes a contraction in the quadriceps extensor cruris; contact with the conjunctiva causes closure of the eyelids. In the former case, the afferent channels arise in the tendon of the quadriceps, and the efferent channels lie in the nerve which supplies the quadriceps; in the latter case, the afferent nerve is the 5th and the efferent the 7th cranial nerve. In the former case the centre is in the lumbar region of the cord; in the latter, in the gray matter of the medulla oblongata.

II. The extensive inco-ordinate reflexes, or **reflex spasms.**—These movements occur in the form of clonic or tetanic contractions; individual groups of muscles, or all the muscles of the body may be implicated. **Causes:** A reflex spasm depends upon a double cause—(*a*) Either the gray matter or the spinal cord is in a condition of *exalted excitability*, so that the nervous impulse, after having reached the centre, is easily transferred to the neighboring centres. This excessive excitability is produced by certain poisons, more especially by *strychnin*, brucia, caffein, atropin, nicotin, carbolic acid, etc. The slightest touch applied to an animal poisoned with strychnin is sufficient to throw the animal at once into

spasms. Pathological conditions may cause a similar result; thus, there is excessive excitability in hydrophobia and tetanus. On the other hand, the central organ may be in such a condition that extensive reflexes cannot take place; thus, in the condition of apnœa, the spasms that occur in poisoning with strychnin do not take place (*J. Rosenthal and Leube*), and the same result is brought about by passive artificial respiratory movements (§ 361, 3). The performance of other passive periodic movements in various parts of the body also produces a similar condition (*Buchheim*). If the spinal cord be cooled very considerably, reflex spasms may not occur (*Kunde*). (*b*) Extensive reflex movements may also take place when the discharging *stimulus is very strong*. **Examples** of this condition occur in man, thus—intense neuralgia may be accompanied by extensive spasmodic movements.

[Fig. 458 shows the mechanism of simple and complex reflex movements. Suppose the skin to be stimulated at P, an impulse is sent to A and from it to a muscle 1 on the same side, resulting in a **unilateral** simple reflex movement—the resistance being less in this direction than in the other channels. If the impulse be stronger, or the transverse resistance in the cord diminished, the impulse may pass to B, thence to 2, resulting in a **symmetrical** reflex movement on both sides. But if a very strong impulse reach the cord, or if the excitability of the gray matter be increased, *e.g.*, by strychnin, the resistance to the diffusion of the impulse is diminished, and it passes upward to C and D, resulting in more complex movements—thus there is **irradiation**—or it may even affect the centres in the medulla oblongata, E, giving rise to general convulsive movements.]

General spasms usually manifest themselves as "**extensor tetanus,**" because the extensors overcome the flexor muscles. Nerves which arise from the medulla oblongata may be excited through the stimulation of distant afferent nerves, without general spasms being produced.

Strychnin is the most powerful reflex-producing poison we possess, and it acts upon the gray matter of the spinal cord. [An animal poisoned with strychnin exhibits tetanic spasms on the application of the slightest stimulus. All the muscles become rigid, but the extensors overcome the flexors.] If the heart of a frog be ligatured, and the poison afterward applied directly to the spinal cord, reflex spasms are produced, proving that strychnin acts upon the spinal cord. During the spasm the heart is arrested in diastole, owing to the stimulation of the vagus, while the arterial blood pressure is greatly increased, owing to stimulation of the central vasomotor centres of the medulla oblongata and spinal cord. Mammals may die from asphyxia during the attack; and, after large doses, death may occur, owing to paralysis of the spinal cord, due to the frequently recurring spasms. Fowls are unaffected by comparatively large doses. [We can prove that strychnin does not produce spasms by acting on the brain, muscle, or nerve. Destroy the brain of a frog, divide one sciatic nerve high up, and inject a small dose of strychnin into the dorsal lymph sac; in a few minutes all the muscles of the body, except those supplied by the divided nerve, will be in spasm, showing that, although the poisoned blood has circulated in the nerves and muscles of the leg, it does not act on them. Destroy the spinal cord, and the spasms cease at once.]

FIG. 458.



Scheme of mode of propagation of reflex movements. P, skin; A, B, C, D, motor cells in spinal cord; 1, 2, 3, 4, 5, muscles.

Summation of Stimuli.—By this term is meant, that a single weak stimulus, which in itself is incapable of discharging a reflex act, may, if repeated sufficiently often, produce this act. The single impulses are conducted to the spinal cord, in which the process of "summation" takes place. According to J. Rosenthal, 3 feeble stimuli per second are capable of producing this effect, although 16 stimuli per second are most effective. On increasing the number of stimuli per second, no further increase of the reflex act is possible. Other observers (*Stirling, Ward*) have found

that stimuli, such as induction shocks, are active within much wider limits, *e. g.*, from 0.05 to 0.4 second interval. W. Stirling has shown it to be extremely probable that all reflex acts are due to the repetition of impulses in the nerve centres.

[Strychnin interferes with the summation of stimuli, but the reflex excitability is so greatly exalted that a minimal stimulus is at the same time a maximal one.]

Pflüger's Law of Reflex Actions.—(1) The reflex movement occurs on *the same side* on which the sensory nerve is stimulated; while only those muscles contract whose nerves arise from the same segment of the spinal cord. (2) If the reflex occur on the *other* side, only the corresponding muscles contract. (3) If the contractions be unequal upon the two sides, then the most vigorous contractions always occur on the side which is stimulated. (4) If the reflex excitement extend to other motor nerves, those nerves are always affected which lie in the direction of the medulla oblongata. Lastly, all the muscles of the body may be thrown into contraction.

Crossed Reflexes.—There are exceptions to these rules. If the region of the eye be irritated in a frog whose cerebrum is removed, there is frequently a reflex contraction in the hind limb of the opposite side (*Luchsinger, Langendorff*). In beheaded tritons and tortoises, and in deeply narcotized dogs and cats, tickling one fore limb is frequently followed by a movement of the hind limb of the opposite side (*Luchsinger*). This phenomenon is called a "**crossed reflex**" (Fig. 457). If the spinal cord be divided along the middle line throughout its entire extent, then, of course, the reflexes are confined to *one side* only (*Schiff*).

III. Extensive co-ordinated reflexes are due to stimulation of a sensory nerve, causing the discharge of complicated reflex movements in whole groups of different muscles, the movements being "**purposive**" in character, *i. e.*, as if they were intended for a particular purpose.

Methods.—The experiments are made upon *cold-blooded animals* (decapitated or pithed frogs, tortoises, or eels) or upon *mammals*. In the latter, artificial respiration is kept up, and the four arteries going to the head are ligatured, in order to eliminate the action of the brain (*Sig. Mayer, Luchsinger*). The reflexes of the lower part of the spinal cord may be studied on animals (or men), in cases where the spinal cord is divided transversely in the upper dorsal region. In such cases, some time must elapse in order that the primary effect of the lesion (the so-called shock), which usually causes a diminution of the reflexes, may pass off. Very young mammals exhibit reflexes for a considerable time after they are beheaded.

Examples: 1. The **protective** movements of pithed or decapitated frogs. [If a drop of a dilute acid be applied to the skin of such a frog, immediately it strives to get rid of the offending body, and it generally succeeds in doing so.] Similarly, it kicks against any fixed body pushed against it. These movements are so purposive in their character, and the actions of groups of muscles are so adjusted to perform a particular act, that Pflüger regarded them as directed by, and due to "consciousness of the spinal cord." If a flame be applied to the side or part of the body of an eel, the body is moved away from the flame. The tail of a decapitated triton, tortoise, newt, eel, or snake is directed toward a gentle stimulus, but if a violent stimulus is used, it is directed away from it (*Luchsinger*).

2. **Goltz's Croaking Experiment.**—A pithed (male) frog, *i. e.*, one with its cerebral lobes alone removed (or one with its eyes or ears destroyed—*Langendorff*), croaks every time the skin of its back or flanks is gently stroked. [Some male frogs, when held up by the finger and thumb immediately behind the fore legs, croak every time gentle pressure is made on their flank.]

3. **Goltz's "Embrace Experiment."**—During the breeding season in spring, the part of the body of the male frog between the skull and the fourth vertebra, embraces every rigid object, which is brought into contact with, and gently stimulates, the skin over the sternum.

In the *intact* animal, the exciting stimulus lies in the degree of filling of the male seminal organ (*Tarchanoff*). The reflex ceases at once on gently stimulating the optic lobes (*Albertoni*).

4. In **mammals** (dogs), the following reflex acts are performed by the posterior part of the spinal cord, even after it is separated from the rest of the cord: Scratching with the hind feet a part of the skin which has been tickled (just as in intact animals); the movements necessary for emptying the bladder and for defæcation,

as well as those necessary for erection; the movements necessary for parturition (*Goltz, Freusberg and Gergens*). Coördinated movements do not, as a rule, occur simultaneously in portions of the spinal cord lying widely apart after removal of the medulla oblongata. According to Ludwig and Owsjannikow, the medulla oblongata perhaps contains a reflex organ of a higher order, which forms, as it were, a centre for combining, through the medium of the nerve fibres, the various reflex provinces in the spinal cord.

5. Coördinated reflexes may occur in man during **sleep**, and during pathological comatose conditions.

Most of the movements which we perform while we are **awake**, and which we execute **unconsciously**—or even when our psychical activities are concentrated upon some other object—really belong to the category of coördinated reflexes. Many complicated motor acts must first be learned —*e. g.*, dancing, skating, riding, walking—before unconscious harmonious coördinated reflexes can again be discharged. The coördinated reflex movements of coughing, sneezing, and vomiting depend upon the spinal cord, together with the medulla oblongata.

The following facts are also important:—

1. Reflexes are more easily and more completely discharged, when the **specific end organ** of the afferent nerve is stimulated, than when the trunk of the nerve is stimulated in its course (*Marshall Hall*, 1837). [Thus, by gently tickling the skin, it is easy to discharge a reflex act, while it requires a strong stimulus to be applied to an exposed sensory nerve in order to do so.]

2. A *stronger stimulus* is required to discharge a reflex movement than for the direct stimulation of motor nerves.

3. A movement produced reflexly is of *shorter duration* than the corresponding movement executed voluntarily. Further, the occurrence of the movement after the moment of stimulation is *distinctly delayed*. In the frog, a period nearly twelve times as long elapses before the occurrence of the contraction, than is occupied in the transmission of the impulse in the sensory and motor nerves (*Helmholtz*, 1854.) Thus, the spinal cord offers *resistance* to the transmission of impulses through it.

The term "**reflex time**" is applied to the time necessary for transferring the impulse from the afferent fibre to the nerve cells of the cord, and from them to the efferent fibre. In the frog it is equal to 0.008 to 0.015 second. The time, however, is increased by almost one-third, if the impulse pass to the *other* side of the cord, or if it pass along the cord, *e. g.*, from the sensory nerves of the anterior extremity to the motor roots of the posterior limb. Heat diminishes the reflex time and increases the reflex excitability. Lowering the temperature (winter frogs), as well as the reflex-exciting poisons already mentioned, *lengthens the reflex time*, while the reflex excitability is simultaneously increased. Conversely, the reflex time diminishes as the strength of the stimulus increases, and it may even become of minimal duration (*J. Rosenthal*). The reflex time is determined by ascertaining the moment at which the sensory nerve is stimulated, and the subsequent contraction occurs. Deduct from this the time of latent stimulation (§ 298, I), and the time necessary for the conduction of the impulse (§ 298) in the afferent and efferent nerves (*v. Helmholtz, J. Rosenthal, Exner, Wundt*).

[**Influence of Poisons.**—The latent period and reflex time are influenced by a large number of conditions. In a research as yet unpublished, W. Stirling finds that the latent period may remain nearly constant in a pithed frog for nearly two days, when tested by Türck's method. Sodic chloride does not influence the time, nor does sodic bromide or iodide. Potassic chloride, however, lengthens it enormously, or even abolishes reflex action after a very short time, and so do potassic bromide, ammonium chloride and bromide, chloral and croton-chloral. The lithia salts also lengthen the reflex time, or abolish the reflex act after a time.]

361. INHIBITION OF THE REFLEXES.—Within the body there are mechanisms which can *suppress* or *inhibit* the discharge of reflexes, and they may therefore be termed **mechanisms inhibiting the reflexes**. These are:—

1. **Voluntary Inhibition.**—Reflexes may be inhibited voluntarily, both in the region of the spinal cord and brain. **Examples**: Keeping the eyelids open when the eyeball is touched; arrest of movement when the skin is tickled. We must observe, however, that the suppression of reflexes is possible only up to a certain point. If the stimulus be strong, and repeated with sufficient frequency, the reflex impulse ultimately overcomes the voluntary effort. It is impossible to

suppress those reflex movements which cannot at any time be performed voluntarily. Thus, erection, ejaculation, parturition, and the movements of the iris, are neither direct voluntary acts, nor can they, when they are excited reflexly, be suppressed by the will.

2. **Setschenow's inhibitory centre** is another cerebral apparatus, which in the **frog** is placed in the optic lobes. If the optic lobes be separated from the rest of the brain and spinal cord, by a section made below it, the reflex excitability is increased. If the lower divided surface of the optic lobes be stimulated with a crystal of common salt or blood, the reflex movements are suppressed. The same results obtain when only *one* side is operated on. Similar organs are supposed to be present in the corpora quadrigemina and medulla oblongata of the higher vertebrates. From 1 and 2 we may explain why reflex movements occur more regularly and more readily after separation of the brain from the spinal cord.

[**Quinine** greatly diminishes the reflex excitability in the frog, but if the medulla oblongata be divided, the reflex excitability of the cord is restored. The depression is ascribed by Chaperon to the action of the quinine on Setschenow's centres.]

3. **Strong stimulation of a sensory nerve** inhibits reflex movements. The reflex does not take place if an afferent nerve be stimulated very powerfully (*Goltz, Lewisson*). **Examples:** Suppressing a sneeze by friction of the nose [compressing the skin of the nose over the exit of the nasal nerve]; suppression of the movements produced by tickling, by biting the tongue. Very violent stimulation may even suppress the coördinated reflex movements usually controlled by voluntary impulses. Violent pain of the abdominal organs (intestine, uterus, kidneys, bladder, or liver) may prevent a person from walking or even from standing. To the same category belongs the fact that persons fall down when internal organs richly supplied with nerves are injured, there being neither injury of the motor nerves nor loss of blood to account for the phenomenon. Excitement of the central organs through other centripetal channels (nerves of special sense, and those of the generative organs) diminishes the reflexes in other channels.

4. It is important to note that in the suppression of reflexes, **antagonistic muscles** are often thrown into action, whether voluntarily or by the stimulation of sensory nerves, *i. e.*, reflexly. In some cases, in order to cause suppression of the reflex, it appears to be sufficient to direct our attention to the execution of such a complicated reflex act. Thus, some persons cannot sneeze when they think intently upon this act itself (*Darwin*). The voluntary impulse rapidly reaches the reflex centre, and begins to influence it so that the normal course of the reflex stimulation, due to an impulse from the periphery, is interfered with (*Schlösser*).

5. **Poisons.**—Chloroform diminishes the reflex excitability by acting upon the centre, and a similar effect is produced by picrotoxin, morphia, narcotin, thebain, aconitin, quinine, hydrocyanic acid. [W. Stirling finds that chloral, potassic bromide and chloride, ammonium chloride, but not sodium chloride, greatly diminish the reflex excitability. Nicotin increases it in frogs (*Freusberg*).]

A constant current of electricity passed longitudinally through the cord diminishes the reflexes (*Ranke*), especially if the direction of the current is from above downward (*Legros and Onimus, Uspensky*).

[Some **drugs** affect the reflex excitability **directly** by acting on the spinal cord, *e. g.*, methylconine, but other drugs may produce the same result **indirectly** by affecting the heart and the blood supply to the cord. If the abdominal aorta of a rabbit be compressed for a few minutes to cut off the supply of blood to the cord and lower limbs, temporary paraplegia is produced.]

If frogs be asphyxiated in air deprived of all its O, the brain and spinal cord become completely unexcitable, and can no longer discharge reflex acts. The motor nerves and the muscles, however, suffer very little, and may retain their excitability for many days (*Aubert*).

[**Nature of Inhibition.**—The foregoing view assumes the existence of inhibitory centres, but it is important to point out that it has been attempted to explain this phenomenon without postulating the existence of inhibitory centres. During inhibition the function of an organ is restrained—during paralysis it is abolished, so that there is a sharp distinction between the two conditions. The analogy between inhibitory phenomena and the effects of interference of waves of light or sound has been pointed out by Bernard and Romanes, while Lauder Brunton has tried to explain the question on a

physical basis, indicating that inhibition is not dependent on the existence of special inhibitory centres, but that stimulation and inhibition are different phases of excitement, the two terms being relative conditions depending on the length of the path along which the impulse has to travel and the rate of its transmission. Brunton points out that the known facts are more consistent with an hypothesis of the interference of waves, one with another, than with the supposition that they are inhibitory centres for every so-called inhibitory act in the body. In discussing this question great regard must be had to the action of the vagus on the heart (§ 369).]

Türck's method of testing the reflex excitability of a frog is the following: A frog is pithed, and after it has recovered from the shock, its foot is dipped into *dilute sulphuric acid* [2 per 1000]. The time which elapses between the leg being dipped in and the moment it is withdrawn is noted. [The time may be estimated by means of a metronome, or the movements may be inscribed upon a recording surface. The time which elapses is known as the "period of latent stimulation."]

This time is greatly prolonged after the optic lobes have been stimulated with a crystal of common salt or blood, or after the stimulation of a sensory nerve.

Setschenow distinguished **tactile** reflexes, which are discharged by stimulation of the *nerves of touch;* and **pathic,** which are due to stimulation of *sensory* (pain-conducting) fibres. He and Paschutin suppose that the tactile reflexes are suppressed by voluntary impulses, and the pathic by the centre in the optic lobes.

Theory of Reflex Movements.—The following theory has been propounded to account for the phenomena already described: It is assumed that the *afferent* fibre within the gray matter of the spinal cord joins one or more nerve cells, and thus is placed in communication in all directions with the network of fibres in the gray substance. Any impulse reaching the gray matter of the cord has to overcome considerable **resistance.** The least resistance lies in the direction of those *efferent* fibres which emerge in the same plane and upon the same side as the entering fibre. Thus, the feeblest stimulus gives rise to a *simple reflex*, which generally is merely a simple protective movement for the part of the skin which is stimulated. Still greater resistance is opposed in the direction of other motor ganglia. If the reflex impulse is to pass to these ganglia, either the discharging *stimulus* must be considerably *increased*, or the *resistance* within the connections of the ganglia of the gray matter must be *diminished.* The latter condition is produced by the action of the above-named poisons, as well as during general increased nervous excitability (hysteria, nervousness). Thus, extensive reflex spasms may be produced either by increasing the stimulus, or by diminishing the resistance to conduction in the spinal cord. Those conditions which render the occurrence of reflexes more difficult, or abolish them altogether, must be regarded as increasing the resistance in the reflex arc in the cord. The action of the reflex inhibitory mechanism may be viewed in a similar manner.

The fibres of the reflex arc must have a connection with the reflex inhibitory paths; we must assume that equally by the reflex inhibitory stimulation resistance is introduced into the reflex arc. The explanation of *extensive coördinated movements* is accompanied with difficulties. It is assumed, that by use and also by heredity, those ganglionic cells which are the first to receive the impulse are placed in the path of least resistance in connection with those cells which transfer the impulse to the groups of muscles, whose contraction, resulting in a coördinated purposive movement, prevents the body or the limb from being affected by any injurious influences.

Pathological.—Anomalies of reflex activity afford an important field to the physician in the investigation of nervous diseases. **Enfeeblement,** or even complete **abolition** of the reflexes may occur: (1) Owing to diminished sensibility or complete insensibility of the afferent fibres; (2) in analogous affections of the central organ; (3) or, lastly, of the efferent fibres. Where there is general depression of the nervous activity (as after shocks, compression or inflammation of the central nervous organs; in asphyxia, in deep coma, and in consequence of the action of many poisons), the reflexes may be greatly diminished or even abolished.

[**Reflexes.**—The physician, by studying the condition of the reflexes, can form an idea as to the condition of practically every inch of the spinal cord. There are three groups of reflexes, (*a*) the **superficial,** (*b*) the **deep** or tendon, (*c*) the **organic reflexes.**]

[**The superficial or skin reflexes** are excited by stimulating the skin, *e. g.*, by tickling, pricking, scratching, etc. We can obtain a series of reflexes from below as far up as the lower part of the cervical region. The **plantar reflex** is obtained by tickling the soles of the feet, when the leg on that side, or, it may be, both legs are drawn up. It is always present in health, and its centre is in the lumbar enlargement of the cord. The **cremasteric** reflex is well marked in boys, and is easily produced by exciting the skin on the inner side of the thigh, when the testicle on that side is retracted. The **gluteal** reflex consists in a contraction of the gluteal

muscles, when the skin over the buttock is stimulated. The **abdominal** reflex consists in a similar contraction of the abdominal muscles, when the skin over the abdomen in the mammary line is stimulated. The **epigastric** reflex is obtained by stimulating the skin in front between the fourth and sixth ribs. The **interscapular** reflex results in a contraction of the muscles attached to the scapula, when the skin between the scapulæ is stimulated. Its centre corresponds to the lower cervical and upper dorsal region.]

[The following table, after Gowers, shows the relation of each reflex to the spinal segment or segments on which it depends:—

Cervical,	6	Interscapular.	Lumbar,	1	Cremasteric.
"	7		"	2	
"	8		"	3	*Knee Reflex.*
Dorsal,	1		"	4	Gluteal.
"	5	Epigastric.	"	5	
"	6		Sacral,	1	*Ankle Clonus.*
"	7		"	2	Plantar.
"	8	Abdominal.	"	3	Vesical.
"	9		"	4	Rectal.
"	10		"	5	Sexual.]
"	11				
"	12				

Another important diagnostic reflex is the "**abdominal reflex,**" which consists in this, that when the skin of the abdomen is stroked, *e. g.*, with the handle of a percussion hammer, the abdominal muscles contract. When this reflex is absent on both sides in a cerebral affection, it indicates a diffuse disease of the brain; its absence on one side indicates a local affection of the opposite half of the brain. The **cremasteric, conjunctival, mammillary, pupillary,** and **nasal** reflexes may also be specially investigated. In hemiplegia complicated with cerebral lesions, the reflexes on the paralyzed side are diminished, while not unfrequently the patellar reflex may be increased. In *extensive* cerebral affections accompanied by coma the reflexes are absent on both sides, including, of course, those of the anus and bladder (*O. Rosenbach*).

[Horsley finds that in the deepest **narcosis** produced by nitrous oxide gas the superficial reflexes (*e.g.*, plantar, conjunctival) are abolished, while the deep (knee jerk) remain. Anæmia of the lumbar enlargement (compression of the abdominal aorta) causes disappearances of both reflexes (*Prévost*). Chloroform and asphyxia abolish the deep as well as the superficial reflexes. Horsley regards the so-called deep reflex or knee jerk not as depending on a centre in the cord, but the contraction of the rectus femoris is due to local irritation of the muscle from sudden elongation.]

Deep or **Tendon Reflexes.**—Under pathological conditions, special attention is directed to the so-called tendon reflexes, which depend upon the fact that a blow upon a tendon (*e. g.*, the quadriceps femoris, tendo-Achilles, etc.) discharges a contraction of the corresponding muscle (*Westphal, Erb*, 1875). The patellar tendon reflex (also called "*knee phenomenon*") or simply "knee reflex," or "**knee jerk,**" is invariably absent in cases of ataxic tabes dorsalis, while in spastic spinal paralysis it is abnormally strong and extensive (*Erb*). [The "**knee jerk**" is elicited by percussing the ligamentum patellæ, and is due to a *single* spasm of the rectus. The latent period is 0.03 to 0.04 second, and it is argued by Waller and others that it is doubtful if this tendon reflex is subserved by a spinal nervous arc, while admitting the effect of the spinal cord in modifying the response of the muscle.] Section of the motor nerves abolishes the patellar phenomenon in rabbits (*Schultz*), and so does section of the cord opposite the 5th and 6th lumbar vertebræ (*Tschirjew*). Landois finds that in his own person the contraction occurs 0.048 second after the blow upon the ligamentum patellæ. According to Waller, the patellar reflex and the tendo-Achilles reflex occur 0.03 to 0.04 second, and according to Eulenburg, 0.032 second after the blow. According to Westphal, these phenomena are not simple reflex processes, but complex conditions intimately dependent

upon the muscle tonus, so that when the tonus of the quadriceps femoris is diminished, the phenomenon is abolished. In order that the phenomenon may take place, it is necessary that the outer part of the posterior column of the spinal cord remain intact (*Westphal*). [The knee jerk can be increased or reinforced by volitional acts directed to other parts of the body, *e.g.*, by exercising voluntary pressure with the hand (*Jendrássik*).] [A "**jaw jerk**" is obtained by suddenly depressing the lower jaw (*Gowers, Beevor, and De Watteville*), and the last observer finds that the latent period is 0.02 second, and if this be the case, it is an argument against these so-called "tendon reflexes" being true reflexes, and that they are direct contractions of the muscles due to sudden stimulation by extension.]

[**Method.**—The **knee jerk** is easily elicited by striking the patellar tendon with the edge of the hand or a percussion hammer when the leg is semi-flexed, as when the legs are hanging over the edge of a table or when one leg is crossed over the other. It is almost invariably present in health, but it becomes greatly exaggerated in descending degeneration of the lateral columns and lateral sclerosis.]

[**Ankle clonus** is another tendon reflex, and it is never present in health. If the leg be nearly extended, and pressure made upon the sole of the foot so as suddenly to flex the foot at the ankle, a series of (5 to 7 per second) rhythmical contractions of the muscles of the calf takes place. Gowers describes a modification elicited by tapping the muscles of the front of the leg, the "*front-tap contraction.*" Ankle clonus is excessive in sclerosis of the lateral columns and spastic paralysis.]

[In "**ankle clonus**" excited by sudden passive flexion of the foot, there is a multiple spasm of the gastrocnemius. Here also the latent period is about 0.03 to 0.04 second, and the rhythm 8 to 10 per second. This short latent period has led some observers to doubt the essentially reflex nature of this act.]

When we are about to **sleep** (§ 374), there is first of all a temporary increase of the reflexes; in the first sleep the reflexes are diminished, and the pupils are contracted. In deep sleep the abdominal, cremasteric, and patellar reflexes are absent; while tickling the soles of the feet and the nose only acts when the stimulus is of a certain intensity. In **narcosis**, *e.g.*, chloroform or morphia, the abdominal, then the conjunctival and patellar reflexes disappear; lastly, the pupils contract (*O. Rosenbach*).

Abnormal **increase** of the reflex activity usually indicates an increase of the excitability of the reflex centre, although an abnormal sensibility of the afferent nerve may be the cause. As the harmonious equilibrium of the voluntary movements is largely dependent upon and regulated by the reflexes, it is evident that in affections of the spinal cord there are frequent disturbances of the voluntary movements, *e. g.*, the characteristic disturbance of motion in attempting to walk, and in grasping movements exhibited by persons suffering from ataxic tabes dorsalis [or, as it is more generally called, *locomotor ataxia*].

[The **organic reflexes** include a consideration of the acts of micturition, erection, ejaculation, defæcation, and those connected with the motor and secretory digestive processes, respiration, and circulation.]

362. CENTRES IN THE SPINAL CORD.—Centres capable of being excited reflexly, and which can bring about the discharge of certain complicated, yet well coördinated, motor acts exist in various parts of the spinal cord. They still retain their activity after the spinal cord is separated from the medulla oblongata; further, those centres lying in the lower part of the spinal cord still retain their activity after being separated from the higher centres, but in the normal intact body, they are subjected to the control of higher reflex centres in the *medulla oblongata*. Hence, we may speak of them as subordinate spinal centres. The *cerebrum* also, partly by the production of perceptions, and partly as the organ of volition, can excite or suppress the action of certain of these subordinate spinal centres. [For the significance of the term "Centre," see p. 675.]

1. The **cilio-spinal** centre connected with the **dilatation of the pupil** lies in the lower cervical part of the cord, and extends downward to the region of the

1st to the 3d dorsal vertebra. It is excited by diminution of light; *both* pupils always react simultaneously, when *one* retina is shaded. Unilateral extirpation of this part of the spinal cord causes contraction of the pupil on the same side. The motor fibres pass out by the anterior roots of the two lower cervical and two upper dorsal nerves, into the cervical sympathetic (§ 392). Even the idea of darkness may sometimes, though rarely, cause dilatation of the pupil (*Budge*).

In goats and cats, this centre, even after being separated from the medulla oblongata, can excited directly by dyspnœic blood, and also reflexly by the stimulation of sensory nerves, *e. g.*, median, especially when the reflex excitability of the cord is increased by the action of strychnia atropin (*Luchsinger*). For the dilator centre in the medulla oblongata, see § 367, 8.

2. The **ano-spinal** centre, or centre controlling the act of **defæcation.** The afferent nerves lie in the hemorrhoidal and inferior mesenteric plexuses, the centre at the 5th (dog) or 6th to 7th (rabbit) lumbar vertebra; the efferent fibres arise from the pudendal plexus and pass to the sphincter muscles. For the relation of this centre to the cerebrum, see § 160. After section of the spinal cord [in dogs], Goltz observed that the sphincter contracted rhythmically upon the finger introduced into the anus; the coördinated activity of the centre, therefore, would seem to be possible only when the centre remains in connection with the brain.

3. The **vesico-spinal** centre for regulating micturition, or Budge's vesico-spinal centre. The centre for the *sphincter* muscle lies at the 5th (dog) or the 7th (rabbit) lumbar vertebra, and that for the muscles of the *bladder* somewhat higher. The centre acts only in a properly coördinated way in connection with the brain (§ 280).

4. The **erection** centre also lies in the lumbar region (§ 436). The afferent nerves are the sensory nerves of the penis; the efferent nerves for the deep artery of the penis are the vaso-dilator nerves, arising from the 1st to 3d sacral nerves, or Eckhard's **nervi erigentes**—while the motor nerves for the ischio-cavernosus and deep transverse perineal muscles arise from the 3d to 4th sacral nerves (§ 356). The latter may also be excited voluntarily, the former also partly by the brain, by directing the attention to the sexual activity. Eckhard observed erection to take place after stimulation of the higher regions of the spinal cord, as well as of the pons and crura cerebri.

5. The **ejaculation** centre. The afferent nerve is the dorsal of the penis, the centre (Budge's cerebro-spinal centre) lies at the 4th lumbar vertebra (rabbit); the motor fibres of the vas deferens arise from the 4th and 5th lumbar nerves, which pass into the sympathetic, and from thence to the vas deferens. The motor fibres for the bulbo-cavernosus muscle, which ejects the semen from the bulb of the urethra, lie in the 3d and 4th sacral nerves (perineal).

6. The **parturition** centre lies at the 1st and 2d lumbar vertebræ (§ 453); the afferent fibres come from the uterine plexus, to which also the motor fibres proceed (*Körner*). Goltz and Freusberg observed that a bitch became pregnant after its spinal cord was divided at the 1st lumbar vertebra.

7. **Vasomotor Centres.**—Both vasomotor and vaso-dilator centres are distributed throughout the whole spinal axis. To them belongs the centre for the *spleen*, which in the dog is opposite the 1st to 4th cervical vertebræ (*Bulgak*). They can be excited reflexly, but they are also controlled by the dominating centre in the medulla oblongata (§ 371). Psychical disturbance (cerebrum) influences them (§ 377).

[8. Perhaps there are **vaso-dilator** centres (§ 372).]

9. The **sweat** centre is perhaps distributed similarly to the vasomotor centre (§ 288).

The reflex movements discharged from these centres are orderly coördinated reflexes, and may thus be compared to the orderly reflexes of the trunk and extremities.

Muscle Tonus.—Formerly *automatic* functions were ascribed to the spinal cord, one of these being that it caused a moderate active tension of the muscles—a condition that was termed *muscle*

tone, or tonus. The existence of tonus in a striped muscle was thought to be proved by the fact that, when such a muscle was divided, its ends retracted. This is due merely to the fact that all the muscles are stretched slightly beyond their normal length (§ 301). Even paralyzed muscles, which have lost their muscular tone, show the same phenomenon. Formerly, the stronger contraction of certain muscles, after paralysis of their antagonists, and the retraction of the facial muscles to the sound side, after paralysis of the facial nerve, were also regarded as due to tonus. This result is due to the fact that, during the activity of the intact muscles, the other ones have not sufficient power to restore the parts to their normal median position. The following experiment of Auerbach and Heidenhain is against the assumption of a chronic contraction: If the muscles of the leg of a decapitated frog be stretched, it is found that they do not elongate after section of the sciatic nerve, or after it is paralyzed by touching it with ammonia or carbolic acid.

Reflex Tonus.—If, however, a decapitated frog be suspended in an *abnormal* position, we observe, after section of the sciatic nerve, or the posterior nerve roots on one side, that the leg on that side hangs limp, while the leg of the sound side is slightly retracted. The sensory nerves of the latter are slightly and continually stimulated by the weight of the limb, so that a slight reflex retraction of the leg takes place, which disappears as soon as the sensory nerves of the leg are divided. If we choose to call this slight retraction tonus, then it is a reflex tonus (*Brondgeest*). (See the experiments of *Harless, C. Ludwig, and Cyon*—§ 355.)

363. EXCITABILITY OF THE SPINAL CORD.—Even at the present time observers are by no means agreed whether the spinal cord, like peripheral nerves, is excitable, or whether it is distinguished by the remarkable peculiarity that most of its conducting paths and ganglia do not react to *direct electrical* and *mechanical* stimuli.

It is contended by some observers that if stimuli be cautiously applied either to white or gray matter, there is neither movement nor sensation (*Van Deen* (1841) *Brown-Séquard*). Care must be taken not to stimulate the roots of the spinal nerves, as these respond at once to stimuli, and thus may give rise to movements or sensations. As the spinal cord conducts to the brain impulses communicated to it from the stimulated posterior roots, but does not itself respond to stimuli which produce sensations, Schiff has applied to it the term "**æsthesodic.**" Further, as the cord can conduct both voluntary and reflex motor impulses, without, however, itself being affected by motor impulses applied to it directly, he calls it "**kinesodic.**"

Schiff's views are as follows:—

1. In the **posterior columns** the sensory root fibres of the posterior root which traverse these columns give rise to painful impressions, but the proper paths of the posterior columns themselves do not do so. The proof that stimulation of the posterior column produces sensory impressions, he finds in the fact that dilatation of the pupil occurred with every stimulation (§ 292). Removal of the posterior column produces anæsthesia (loss of tactile sensation). Algesia [or the sensation of pain] remains intact, although at first there may even be hyperalgesia.

2. The **anterior columns** are non-excitable, both for striped and non-striped muscle, as long as the stimuli are applied only to the proper paths of this column. But movements may follow, either when the anterior nerve roots are stimulated, or when, by the escape of the current, the posterior columns are affected, whereby reflex movements are produced.

According to Schiff, therefore, all the phenomena of irritation, which occur when an uninjured cord is stimulated (spasms, contracture), are caused either by simultaneous stimulation of the anterior roots, or are reflexes from the posterior columns alone, or simultaneously from the posterior columns and the posterior roots. Diseases affecting only the anterior and lateral columns alone never produce symptoms of irritation, but always of paralysis. In complete anæsthesia and apnœa, every form of stimulus is quite inactive. According to Schiff's view, all centres, both spinal and cerebral, are inexcitable by artificial means.

Direct Excitability.—Many observers, however, oppose these views, and contend that the **spinal cord is excitable to direct stimulation.** Fick observed movements to take place when he stimulated the white columns of the cord of a frog, isolated for a long distance so as to avoid the escape of the stimulating currents. Sirotinin, also, who stimulated the transverse section of the frog's cord from point to point, obtained contraction of the muscles both by mechanical and electrical stimuli. Biedermann comes to the following conclusions: The transverse section of a motor nerve is most excitable. Weak stimuli (descending opening shocks) excite the cut surface of the transversely divided spinal cord, but do not act when applied further down. Luchsinger asserts that, after dipping

the anterior part of a beheaded snake into warm water, the reflex movements of the upper part of the cord are abolished, while the direct excitability remains.

3. **Excitability of the Vasomotors.**—The **vaso-constrictor** nerves, which proceed from the vasomotor centre and run downward in the lateral columns of the cord, are excitable by all stimuli along their whole course; direct stimulation of any transverse section of the cord constricts all the blood vessels below the point of section (*C. Ludwig and Thiry*). In the same way, the fibres which ascend in the cord, and increase the action of the vasomotor centre—*pressor fibres*, are also excitable (*C. Ludwig and Dittmar*—§ 364, 10). Stimulation of these fibres, although it affects the vasomotor centre reflexly, does not cause sensation.

4. **Chemical stimuli** such as the application of common salt, or wetting the cut surface with blood, appear to excite the spinal cord.

5. The **motor centres** are directly excited by **blood heated** above 40° C., or by asphyxiated blood, or by sudden and complete anæmia of the cord produced by ligature of the aorta (*Sigm. Mayer*); and also by certain **poisons**—picrotoxin, nicotin, and compounds of barium (*Luchsinger*).

Action of Blood and Poisons.—In experiments of this kind, the spinal cord ought to be divided at the 1st lumbar vertebra, at least twenty hours before the experiment is begun. It is well to divide the posterior roots beforehand to avoid reflex movements. If, in a cat thus operated on, *dyspnœa* be produced, or its *blood overheated*, then *spasms, contraction of the vessels, and secretion of sweat* occur in the hind limbs, together with evacuation of the contents of the *bladder* and *rectum*, while there are movements of the *uterus* and *vas deferens*. Some poisons act in a similar manner. In animals with the medulla oblongata divided, rhythmical respiratory movements may be produced if the spinal cord has been previously rendered very sensitive by strychnin or overheated blood (*P. v. Rokitansky, v. Schroff*—§ 368).

The ganglion cells of the anterior cornu can be excited **mechanically** (*Birge*), and according to Biedermann the gray matter also responds to electrical stimuli.

Hyperæsthesia.—After unilateral section of the cord, or even only of the posterior or lateral columns, there is *hyperæsthesia* on the same side below the point of section (*Fodéra*, 1823, and others), so that rabbits shriek on the slightest touch. The phenomenon may last for three weeks, and then give place to normal or sub-normal excitability. On the sound side the sensibility remains permanently diminished. A similar result has been observed in cases of injury in man. An analogous phenomenon, or a tendency to contraction in the muscles below the section (**hyperkinesia**), has been observed by Brown-Séquard after section of the anterior columns.

The excitability of the cord is intimately dependent on the continuance of the circulation, for ligature of the abdominal aorta rapidly paralyzes the lower extremities (*Stenson*, 1667), due to anæmia of the cord (*Schiffer*). Later, the anterior roots of the spinal nerves, and the anæmic part of the gray matter of the cord, undergo degeneration.

364. THE CONDUCTING PATHS IN THE SPINAL CORD.—[**Posterior Root.**—(*a*) The inner part, or **internal radicular fasciculus** is supposed to convey the impressions from tendons and those for touch and locality. When the postero-external column is diseased, as in locomotor ataxia, the deep reflexes, especially the patellar tendon reflex, are enfeebled, or it may be abolished, while the implication of the fibres of the internal fasciculus gives rise to severe pain. (*b*) The **outer radicular fibres** enter the gray matter of the posterior horn, and are supposed to convey the impressions for cutaneous reflexes and temperature. (*c*) The **central fibres** pass directly into the gray matter, and are supposed to conduct painful impressions into the gray matter (Fig. 449).]

1. **Localized tactile sensations** (temperature, pressure, and the muscular

sense impressions) are conducted upward through the posterior roots to the ganglia of the posterior cornu, and lastly into the posterior column of the same side.

In **man**, the conducting path from the legs runs in Goll's column, while those for the arms run in the ground bundle (Fig. 454) (*Flechsig*). In **rabbits**, the path of localized tactile impressions lies in the lower dorsal region in the lateral columns (*Ludwig and Woroschiloff, Ott and Meade-Smith*).

Anæsthesia.—Section of individual parts of the lateral columns abolishes the sensibility for the parts of the skin connected with the part destroyed, while total section produces the same result for the whole of the opposite side of the body below the section. The condition where tactile and muscular sensibility is lost is known as *anæsthesia*.

Localized voluntary movements in man are conducted on the same side through the anterior and lateral columns (§§ 358 and 365), in the parts known as the **pyramidal tracts.** The impulses then pass into the cells of the anterior cornu, and thence to the corresponding anterior nerve roots to the muscles. The exact section experiments of Ludwig and Woroschiloff showed that, in the lower dorsal region of the **rabbit,** these paths were confined to the lateral columns. Every motor nerve fibre is connected with a nerve cell in the anterior horn of the frog's spinal cord (*Gaule and Birge*). Section of one lateral column abolishes *voluntary* movement in the corresponding individual muscles below the point of section. It is obvious, from the conduction in 1 and 2, that the lateral columns must increase in thickness and number of fibres from below upward (*Stilling, Woroschiloff*) [see Fig. 443].

3. **Tactile reflexes** (extensive and coördinated).—The fibres enter by the posterior root, and proceed to the posterior cornu. The groups of ganglionic cells, which control the coördinated reflexes, are connected together by fibres which run in the anterior tracts, the anterior ground bundle and (?) the direct cerebellar tracts (p. 684). The fibres for the muscles which are contracted pass from the motor ganglia outward through the anterior roots.

In **ataxic tabes dorsalis,** or **locomotor ataxia,** there is a degeneration of the posterior columns, characterized by a peculiar motor disturbance. The voluntary movements can be executed with full and normal vigor, but the finer harmonious adjustments are wanting or impaired, both in intensity and extent. These depend in part upon the normal existence of tactile and muscular impressions, whose channels lie in the posterior columns. After degeneration of the latter, there is not only anæsthesia, but also a disturbance in the discharge of tactile reflexes, for which the centripetal arc is interrupted. But a simultaneous lesion of the sensory nerves alone may in a similar manner materially influence the harmony of the movements, owing to the analgesia and the disappearance of the pathic reflexes (§ 355). As the fibres of the posterior root traverse the white posterior columns, we can account for the disturbances of sensation which characterize the degenerations of these parts (*Charcot and Pierret*). But even the posterior roots themselves may undergo degeneration, and this may also give rise to disturbances of sensation (p. 667). The sensory disturbances usually consist in an abnormal increase of the tactile or painful sensations, with lightning pains shooting down the limbs, and this condition may lead to one where the tactile and painful sensations are abolished. At the same time, owing to stimulation of the posterior columns, the tactile sensibility is altered, giving rise to the sensation of formication, or a feeling of constriction [**"girdle sensation"**]. The conduction of sensory impressions is often *slowed* (§ 337). The sensibility of the muscles, joints, and internal parts is altered.

The **maintenance of the equilibrium** is largely guided by the impulses which travel inward to the coördinating centres through the sensory nerves, special and general, deep and superficial. In many cases of locomotor ataxia, if the patient place his feet close together and close his eyes, he sways from side to side and may fall over, because by cutting off the guiding sensations obtained through the optic nerve, the other enfeebled impulses obtained from the skin and the deeper structures are too feeble to excite propor coördination.

4. The **inhibition** of **tactile reflexes** occurs through the anterior columns; the impulses pass from the anterior column at the corresponding level into the gray matter, where they form connections with the reflex conducting apparatus.

5. The conduction of **painful** impressions occurs through the posterior roots, and thence through the whole of the gray matter. There is a partial decussation

of these impulses in the cord, the conducting fibres passing from one side to the other. The further course of these fibres to the brain is given in § 365.

If all the gray matter be divided, except a small connecting portion, this is sufficient to conduct painful impressions. In this case, however, the conduction is *slower* (*Schiff*). Only when the gray matter is completely divided, is the conduction of painful impressions from below completely interrupted. This gives rise to the condition of **analgesia**, in which, when the posterior columns are still intact, tactile impressions are still conducted. This condition is sometimes observed in man during incomplete narcosis from chloroform and morphia (*Thiersch*). Those poisons act sooner on the nerves which administer to painful sensations than on those for tactile impressions, so that the person operated on is conscious of the contact of a knife, but not of the painful sensations caused by the knife dividing the parts. As painful impressions are conducted by the whole of the gray matter, and as the impressions are more powerful the stronger the painful impression, we may thus explain the so-called **irradiation of painful impressions.** During violent pain, the pain seems to extend to wide areas; thus, in violent toothache, proceeding from a particular tooth, the pain may be felt in the whole jaw, or it may be over one side of the head.

According to Bechterew, the paths for the conduction of painful impressions lie in the anterior part of the lateral column (dog, rabbit).

The experiments of Weiss on dogs, by dividing the lateral column at the limit of the dorsal and lumbar regions, showed that each lateral column contains sensory fibres for *both* sides. The chief mass of the motor fibres remains on the *same* side. Section of *both* lateral columns abolishes completely sensibility and motility on both sides. The anterior columns and the gray matter are not sufficient to maintain these.

The conduction of **spasmodic, involuntary, inco-ordinated** movements takes place through the gray matter, and from the latter through the anterior roots.

It occurs in epilepsy, poisoning with strychnin, uræmic poisoning, and tetanus (§ 360, II). The anæmic and dyspnœic spasms are excited in and conducted from the medulla oblongata, and communicated through the whole of the gray matter.

7. The conduction of **extensive reflex spasms** takes place from the posterior roots, perhaps to the cells of the posterior cornu and then to the cells of the anterior cornu, above and below the plane of the entering impulse (Fig. 458), and, lastly, into the anterior roots, under the conditions already referred to in § 360, II.

8. The **inhibition of pathic reflexes** occurs through the anterior columns downward, and then into the gray matter to the connecting channels of the reflex organ, into which it introduces resistance.

9. The **vasomotor** fibres run in the lateral columns (*Dittmar*), and, after they have passed into the ganglia of the gray matter at the corresponding level, they leave the spinal cord by the anterior roots. They reach the muscles of the blood vessels either through the paths of the spinal nerves, or they pass through the rami communicantes into the sympathetic, and thence into the visceral plexuses (§ 356).

Section of the spinal cord paralyzes all the vasomotor nerves below the point of section; while *stimulation* of the peripheral end of the spinal cord causes contraction of all these vessels. [Ott's experiments on cats show that the vasomotor fibres run in the lateral columns, and that they as well as the sudorific nerves decussate in the cord.]

10. **Pressor** fibres enter in the posterior roots, run upward in the lateral columns, and undergo an incomplete decussation (*Ludwig and Miescher*).

They ultimately terminate in the *dominating vasomotor centre* in the medulla oblongata, which they excite reflexly. Similarly, *depressor* fibres must pass upward in the spinal cord, but we know nothing as to their course.

11. From the **respiratory centre** in the medulla oblongata, **respiratory nerves** run downward in the lateral columns on the *same* side, and after forming connections with the ganglia of the gray matter pass through the anterior roots into the motor nerves of the respiratory muscles (*Schiff*).

Unilateral, or total destruction of the spinal cord, the higher up it is done, accordingly paralyzes more and more of the respiratory nerves, on the same or on both sides. Section of the cord above

the origin of the phrenic nerves causes death, owing to the paralysis of these nerves of the diaphragm (§ 113).

In **pathological cases**, in degeneration of, or direct injury to, the spinal cord or its individual parts, we must be careful to observe whether there may not be present simultaneously paralytic and irritative phenomena, whereby the symptoms are obscured.

[**Complete transverse section of the cord** results **immediately** in complete paralysis of motion and sensation in all the parts supplied by nerves below the seat of the injury, although the muscles below the injury retain their normal trophic and electrical conditions. There is a narrow hyperæsthetic area at the upper limit of the paralyzed area, and when this occurs in the dorsal region, it gives rise to the feeling of a belt tightly drawn round the waist, or the "girdle sensation." There is also vasomotor paralysis below the lesion, but the blood vessels soon regain their tone, owing to the subsidiary vasomotor centres in the cord. The **remote effects** come on much later, and are secondary descending degeneration in the crossed and direct pyramidal tracts and ascending degeneration in the postero-internal columns (Fig. 455). According to the seat of the lesion, the functions of the bladder and rectum may be interfered with. Injury to the upper cervical region sometimes causes hyperpyrexia.]

[**Unilateral section** results in paralysis of voluntary motion in the muscles supplied by nerves given off below the seat of the injury, although the muscles do not atrophy, but when secondary descending degeneration occurs they become rigid, and exhibit the ordinary signs of contracture. There is vasomotor paralysis on the same side, although this passes off below the injury, while the ordinary and muscular sensibility are diminished on both sides (Fig. 459). There is bilateral anæsthesia. On the opposide side there is total anæsthesia and analgesia below the lesion, but on the same side in the dorsal region there is a narrow circular anæsthetic zone (Fig. 459, *b*), corresponding to the sensory nerve fibres destroyed at the level of the section. The sensory nerves decussate shortly after they enter the cord, hence the anæsthesia on the opposite side, but they do not cross at once, but run obliquely upward before they enter the gray matter of the opposite side, so that a unilateral section will involve some fibres coming from the same side, and hence the slightly diminished sensibility in a circular area on the same side. There is a narrow hyperæsthetic area on the same side as the lesion, at the upper limit of the paralyzed cutaneous area (Fig. 459, *c*), due perhaps to stimulation of the cut ends of the sensory fibres on that side. In man there is hyperæsthesia (to touch, tickling, pain, heat, and cold) on the parts below the lesion on the same side, but the cause of this is not known. The **remote** effects are due to the usual descending and ascending degeneration which set in.]

FIG. 459.



Diagrammatic representation of a lesion of the *left* half of the spinal cord in the dorsal region. (*a*) oblique lines, motor and vasomotor paralysis; (*b*, *d*), complete anæsthesia; (*a*, *c*), hyperæsthesia of the skin.

[In **monkeys**, after hemi-section of the cord in the dorsal region, there is paralysis of voluntary motion and retention of sensibility with vasomotor paralysis of the same side, and retention of voluntary motion with anæsthesia and analgesia on the opposite side. The existence of hyperæsthesia on the side of the lesion is not certain in these animals, but there is no doubt of it in man. Ferrier also finds (in opposition to Brown-Séquard) that the muscular sense is paralyzed as well as all other forms of sensibility, on the side opposite to the lesion, but unimpaired on the side of the lesion. The muscular sense, in fact, is entirely separable from the motor innervation of muscle (*Ferrier*). The power of emptying the bladder and rectum was not affected.]

THE BRAIN.

365. GENERAL SCHEMA OF THE BRAIN.—In an organ so complicated in its structure as the brain, it is necessary to have a general view of the chief arrangements of its individual parts. Meynert gave a plan of the general arrangement of this organ, and although this plan may not be quite correct, still it is useful in the study of brain function. The weight of the brain is in man about 1358 grammes, and in woman 1220 grammes (*Bischoff*).

FIG. 460.

Dissection of the brain from above, showing the lateral, 3d, and 4th ventricles, with the basal ganglia, and surrounding parts. *a*, knee of the corpus callosum; *b*, anterior part of the right corpus striatum; *b'*, gray matter dissected off to show white fibres; *c*, points to tænia semicircularis; *d*, optic thalamus; *e*, anterior pillars of fornix, with 5th ventricle in front of them, between the two laminæ of the septum lucidum; *f*, middle or soft commissure; *g*, 3d ventricle; *h*, *i*, corpora quadrigemina; *k*, superior cerebellar peduncle; *l*, hippocampus major; *m*, posterior cornu of lateral ventricle; *n*, eminentia collateralis; *o*, 4th ventricle; *p*, medulla oblongata; *s*, cerebellum, with *r*, arbor vitæ.

[A special layer of **gray matter** of the cerebrum is placed externally and spread as a thin coating over the white matter or **centrum ovale**—which lies internally, and consists of nerve fibres or the white matter. That part lying in each hemisphere is the centrum semi-ovale. The gray matter is folded into **gyri** or **convolutions** separated from each other by **fissures** or **sulci**. Some of the latter are very marked, and serve to separate adjacent **lobes**, while the lobes themselves are further subdivided by sulci into convolutions. For a description of the lobes see § 375. Some masses of gray matter are disposed at the base of the brain, forming the **corpus striatum** (projecting into the lateral ventricles), which in reality is composed of two parts, the nucleus caudatus and lenticular nucleus (Fig. 460, *b*), the **optic thalamus** which lies behind the former, and bounds the 3d ventricle (Fig. 460, *d*), the **corpora quadrigemina** lying on the upper surface of the crura cerebri (Fig. 480, *hi*); within the tegmentum of the crura cerebri are the **red nucleus** and **locus niger** (Fig. 502). Lastly, there is the continuation of the gray matter of the cord up through the medulla, pons, and around the iter, forming the **central gray tube** and terminating anteriorly at the tuber cinereum. These various parts are connected in a variety of ways with each other, some by transverse fibres stretching between the two sides of the brain, while other longitudinal fibres bring the hinder and lower parts into relation with the fore parts.]

[Under cover of the occipital lobes, but connected with the cerebrum in front, and the spinal cord below, is the **cerebellum**, which has its gray matter externally and its white core internally. Thus we have to consider cerebro-spinal and cerebello-spinal connections.]

Meynert's Projection Systems.—The cortex of the cerebrum consists of convolutions and sulci, the "**peripheral gray matter**" (Fig. 461, C), which is recognized as a nervous structure, from the presence in it of numerous ganglionic cells (§ 358, 1). From it proceed all the motor fibres which are excited by the will, and to it proceed all the fibres coming from the organs of special sense and sensory organs, which give rise to the psychical perception of external impressions. [In

the decussation of the sensory fibres is represented as occurring near the medulla oblongata. re probable that a large number of the sensory fibres decussate shortly after they enter the is represented in Fig. 463. Some observers assert that some of the sensory fibres decussate edulla oblongata.]

Projection System.—The channels lead to and from the cortex cerebri, some of them g the **basal ganglia**, or ganglia of the cerebrum—the corpus striatum (C.*s*) (composed

FIG. 461.



e of the brain.—C, C, cortex cerebri; C.*s*, corpus striatum; N.*l*, nucleus lenticularis; T.*o*, optic thalamus; corpora quadrigemina; P, pedunculus cerebri; H, tegmentum; and *p*, crusta; 1, 1, corona radiata of the us striatum; 2, 2, of the lenticular nucleus; 3, 3, of the optic thalamus; 4, 4, of the corpora quadrigemina; yramidal fibres from the cortex cerebri (*Flechsig*); 6, 6, fibres from the corpora quadrigemina to the tegtum; *m*, further course of these fibres; 8, 8, fibres from the corpus striatum and lenticular nucleus to the ta of the pedunculus cerebri; M, further course of these; S, S, course of the sensory fibres; R, transe section of the spinal cord; *v*.W, anterior, and *h*.W, posterior roots, *a*, *a*, association system of fibres, commissural fibres. II, Transverse section through the posterior pair of the corpora quadrigemina and the nculi cerebri of man,—*p*, crusta of the peduncle; *s*, substantia nigra; *v*, corpora quadrigemina, with a ion of the aqueduct. III, The same of the dog; IV, of an ape; V, of the guinea pig. [See p. 700.]

caudate nucleus and lenticular nucleus (N.*l*),) optic thalamus (T.*o*), and corpora quadrigemina fibres form connections with cells within this central gray matter. The fibres which proceed he cortex through the corona radiata in a radiate direction constitute *Meynert's first projection*

Besides these, the white substance also contains two other systems of fibres: (*a*) **Comral fibres**, such as the corpus callosum and the anterior commissure (*c*, *c*), which are supposed

to connect the two hemispheres with each other; and (*b*) a *connecting* or **association system**, whereby two different areas of the same side are connected together (*a*, *a*). The ganglionic gray matter of the basal ganglia forms the first stage in the course of a large number of the fibres. When they enter the central gray matter, they are *interrupted* in their course. According to Meynert, the corona radiata contains bundles of fibres from the corpus striatum (1, 1), lenticular nucleus (2, 2) optic thalamus (3, 3), and corpora quadrigemina (4, 4).

The second projection system consists of longitudinal bundles of fibres, which proceed downward and reach the so-called "**central gray tube,**" which is the ganglionic gray matter reaching from the 3d ventricle through the aqueduct of Sylvius, and the medulla oblongata, to the lowest part of the gray matter of the spinal cord. It lines the inner surface of the medullary tube. It is the second stage in the course of the fibres extending from the basal ganglia to the central tubular gray matter. The fibres of this system must obviously vary greatly in length; some fibres end in the central gray matter above the medulla oblongata, *e. g.*, in the oculomotor nucleus, while others reach to the level of the last spinal nerves. In the central gray matter, not only is the course of the fibres interrupted, but there is in it an increase in the number of fibres, for far more fibres proceed peripherally from the gray matter of the medulla and spinal cord, than are sent to it from the central gray matter of the brain.

As to the arrangement of the fibres in this second system, the fibres descending from the caudate and lenticular nucleus (8, 8) are grouped into a special channel, which descends through the crusta of the cerebral peduncle, and enters the medulla oblongata, or (according to Flechsig) the pons. In the same way there proceeds from the thalamus (S) and corpora quadrigemina (6, 6) a bundle which descends through the tegmentum (H) of the cerebral peduncle. Both sets of fibres—those in the crusta and in the tegmentum—come together in the cord.

FIG. 462.



Floor of the 4th ventricle and the connections of the cerebellum. On the left side the three cerebellar peduncles are cut short; on the right the connections of the superior and inferior peduncles have been preserved, while the middle one has been cut short: 1, median groove of the 4th ventricle, with the fasciculi teretes; 2, the striæ of the auditory nerve on each side emerging from it; 3, inferior peduncle; 4, posterior pyramid and clava, with the calamus scriptorius above it; 5, superior peduncle; 6, fillet to the side of the crura cerebri; 8, corpora quadrigemina.

According to Wernicke, the lenticular nucleus and caudate nucleus are not the parts of the brain into which, from the cerebral cortex and through the corona, radiate fibres enter; but they are independent parts, analogous to the cortex, and from them fibres proceed. These fibres pass into the crusta and run along with those fibres proceeding from the thalamus and corpora quadrigemina.

According to Meynert, the fibres which pass from the thalamus and corpora quadrigemina, through the tegmentum of the cerebral peduncle, are reflex channels; so that these portions of the brain are centres for certain extensive coördinated reflexes. This is shown by the fact that, after destruction of the voluntary motor paths in animals, the technical completeness of movements, so far as these are discharged reflexly, is still intact. These channels run in the spinal cord, at first on the side (*m*), and probably ultimately cross in the spinal cord itself.

The Third Projection System.—Lastly, from the central tubular gray matter there proceeds the third system, or the **peripheral nerves**, motor and sensory. These are more numerous than the fibres of the second system.

[While there are three concentric tubes in the spinal cord (§ 359), in the part which forms the brain an extra layer of gray matter is added—the **peripheral gray tube**—constituting the cortex of the cerebral hemispheres and cerebellum, and the corpora quadrigemina. Thus, the white matter lies between two concentric masses of gray matter (*Hill*).]

Connections of the Cerebellum.—The cerebellum consists of two somewhat flattened **hemispheres** connected across the middle line by the **middle lobe** or vermiform process which is the fundamental portion of the organ, as it is best developed in lower animals, while as yet the lateral lobes are but small or absent, *e. g.*, in birds. The surface is furrowed by sulci so as to cause it to resemble a series of **folia**, leaflets or **laminæ**; larger fissures divide it into **lobes**. **Peduncles.**—The two **superior peduncles** connect it with the corpora quadrigemina and the crura cerebri. The fibres come from the lower part of the cerebellum and from its dentate nucleus, and a number of these fibres decussate in the upper part of the pons and the tegmentum, some of them becoming

connected with the red nucleus in the tegmentum of the opposite side. Some of the fibres seem to connect the cerebellum with the frontal lobes, constituting a fronto-cerebellar tract, and they are also crossed (*Gowers*). When the cerebellum is congenitally absent, these fibres are absent (*Flechsig*). By the two **inferior peduncles** or restiform bodies, it is connected with all the columns of the spinal cord, and it is to be noted that some of the fibres forming these peduncles are connected with the olivary body of the opposite side, so that they decussate. The **middle peduncle** is formed by the transverse fibres of the pons (Figs. 462, 503). It is evident that there is a cerebello-spinal, as well as a cerebro-spinal connection to be considered.

[The **gray matter** is external and the white internal, and on section the foliated branched appearance of the cerebellum constitutes the *arbor vitæ*. Within each lateral lobe is a folded mass of gray matter like that in the olivary body, called the **corpus dentatum**, and from its interior white fibres proceed. Stilling describes in the front part of the middle lobe **roof nuclei**—so called because they lie in the roof of the 4th ventricle. As is shown in Fig. 462, the **white fibres** of the superior peduncle pass to the gray matter on the inferior surface of the cerebellum, while the inferior peduncular fibres pass to the superior surface, chiefly of the median part; but both are said to form connections with the corpus dentatum; the middle peduncle is connected with the gray matter of the lateral lobes. The minute structure is described in § 380.]

The distribution of the **blood vessels** of the brain is of much practical importance. The middle cerebral artery of the Sylvian fissure supplies the motor areas of the brain in animals; in man, the paracentral lobule is supplied by the anterior cerebral artery (*Duret*). The region of the third left frontal convolution, which is the speech centre, is supplied by a special branch of the middle cerebral. According to Ferrier, that part of the brain, any injury to which causes disturbance of intelligence, is supplied by the anterior cerebral; while those regions, where injury is followed by hemi-anæsthesia, are supplied by the posterior cerebral. It is stated that anæmia of isolated parts of this area of the brain is associated with melancholia in man.

Conduction to and from cerebrum—Voluntary motor fibres.—The course of the fibres which convey impulses for voluntary motion—the **pyramidal tracts**—proceeds from the motor regions of the cerebrum (§§ 375, 378, I), passing into and through the white matter of the cerebrum through the corona radiata, and converges to the **internal capsule**, which lies between the nucleus caudatus and opticus thalamus internally and the lenticular nucleus externally (Fig. 500). [The motor fibres for the face and tongue occupy the knee of the capsule (F), those for the arm the anterior third of the posterior segment or limb (A), and those for the leg the middle third (L). They pass beneath the optic thalamus, enter the crusta of the cerebral peduncle, and occupy its middle third, or two-fifths, extending almost to the substantia nigra, the fibres for the face being next the middle line, and those for the leg most external, the fibres for the arm lying between the two. They pass into the pons on the same side, where the fibres for the face (and tongue) cross to the opposite side, to become connected with the nuclei from which the facial and hypoglossal nerves arise. The fibres for the arm, and leg (and trunk) continue their course to the medulla oblongata, where they form the anterior pyramids. In the pons, the pyramidal tracts are broken up into bundles lying between its superficial and deep transverse fibres, and surrounded by gray matter (Fig. 503); but they have no connection with the gray matter of the pons. By far the greater proportion of the fibres cross at the decussation of the pyramids to form the **crossed pyramidal tracts**, or lateral pyramidal tracts, of the lateral column of the opposite side. The small uncrossed portion is continued as the **direct pyramidal tract** on the same side. The latter fibres, perhaps, supply those muscles of the trunk (*e. g.*, respiratory, abdominal, and perineal), which always act together on both sides. According to other observers, however, they cross to the other side of the cord through the anterior white commissure, and descend in the crossed pyramidal tract or pyramidal tract of the lateral column. The fibres of the pyramidal tracts split up into fine fibrils, which form connections with the fibrils produced by the subdivision of the processes of the multipolar nerve cells. Thus, fibres form connections with the multipolar ganglionic cells of the anterior cornu of the gray matter of the spinal cord at successively lower levels, and from each multipolar cell is directed peripherally a single unbranched process, which ultimately becomes a nerve fibre. The pyramidal tracts thus end in the multipolar nerve cells of the gray matter of the spinal cord, from which the anterior roots of the spinal nerves arise.

[The course of the pyramidal tracts and the decussation of these fibres in the medulla oblongata, explain why a hemorrhage involving the cerebral motor centres, or affecting these fibres in any part of their course above the decussation, results in paralysis of the muscles supplied by the fibres so involved on the *opposite* side of the body. In their passage through the brain, the paths for direct motor impulses are not interrupted anywhere in their course by ganglion cells, not even in the corpus striatum or pons. They pass in a direct uninterrupted line, until each fibre becomes connected with a multipolar nerve cell in the anterior horn of the gray matter of the spinal cord, so that they have the longest course of any fibres in the central nervous system.]

Variation in Decussation.—There are variations as to the number of fibres which cross at the pyramids (*Flechsig*). In some cases the usual arrangement is reversed, and in some rare instances there is no decussation, so that the pyramidal tracts from the brain remain on the same side. In this way we may explain the very rare cases where paralysis of the voluntary movements takes place on the *same* side as the lesion of the cerebrum (*Morgagni*, *Pierret*). This is **direct paralysis**. [Usually about 90 per cent. of the fibres decussate.]

The **motor cranial nerves** have the centres through which they are excited voluntarily in the cortex cerebri (§ 378). The paths for such voluntary impulses also pass through the internal capsule and the crusta of the cerebral peduncle. [In the internal capsule, the fibres for the face (and tongue) lie in the knee, while they occupy the part of the middle of the crusta next the middle line. Their course is then directed across the middle line to their respective nuclei, from which fibres proceed to the muscles supplied by these nuclei.] The exact course of many of the fibres is still unknown. The hypoglossal nerve runs with the pyramidal tracts, and behaves like the anterior root of a spinal nerve (§§ 354, 357).

[**Sensory Paths.**—Our knowledge is by no means precise. Sensory impulses, passing into the cord, enter it by the posterior nerve roots, and may pass to the cerebrum or cerebellum. If to the **cerebellum**, the course, probably, is partly to the direct cerebellar tract and posterior column to the restiform body, thence to the cerebellum. If to the **cerebrum**, they *cross* the middle line in the cord not far above where they enter and pass to the lateral column, in front of the pyramidal tract. Some enter the posterior column, and others ascend in the gray matter to pass upward. As the two subdivisions of the posterior column terminate above in the nuclei of the funiculus gracilis and funiculus cuneatus, and this column contains fibres from the posterior root, it is suggested that above the clava and cuneate nucleus the fibres cross in the superior pyramidal decussation to reach the pons and tegmentum. In the medulla, it is probable that those fibres which do not decussate there do so in the pons, the impulses perhaps traveling upward in the formatio reticularis, thence into the posterior half of the pons, into the tegmentum of the crus under the corpora quadrigemina, to enter the posterior third of the posterior limb of the internal capsule (Fig. 500, S). But, of course, the sensory fibres from the face have to be connected with the sensory centres in the cerebrum, so that the sensory paths from the cord, *i. e.*, from the trunk and limbs, are joined by those from the face in the pons, and they also occupy part of the posterior third of the posterior segment of the internal capsule, so that this important part of the internal capsule conducts sensory impulses from the opposite half of the body. Some of the fibres pass into the optic thalamus, and others enter the white matter of the cerebrum, but their exact course is very uncertain. The sensory fibres derived from the organs of special sense, *e. g.*, the ear, go to the superior temporo-sphenoidal convolution, but whether directly or indirectly we do not know; perhaps some of those for vision traverse the optic thalamus. Some of the afferent fibres perhaps go to the occipital region, and Gowers asserts that some of them go to the parietal and central regions, *i. e.*, to the "motor" regions, for he holds "that disease of the motor cortex often causes impairment of the tactile sensibility."]

[Charcot has called the posterior third of the posterior segment of the internal

capsule, lying between the posterior part of the lenticular nucleus and the optic thalamus, the "carefour sensitiv" or "**sensory crossway**" (Fig. 500, S). If it be divided there is hemi-anæsthesia of the opposite side.]

Sensory Decussation in Cord.—As the greater part of the sensory fibres from the skin *decussate in the spinal cord*, and thus pass to the opposite side of the cord (Fig. 463), unilateral section of the spinal cord in man (and monkey) *Ferrier*) abolishes sensibility on the opposite side below the lesion. There is hyperæsthesia of the parts below the seat of the section on the side of the injury (§ 363). From experiments on mammals, Brown-Séquard concludes that the decussating sensory nerve fibres pass to the opposite side within the cord at different levels, the lowest being the fibres for touch, then those for tickling and pain, and, highest of all, those which administer to sensations of temperature.

All the fibres, therefore, which connect the spinal cord with the gray matter of the brain, undergo a complete decussation in their course. Hence, in man a destructive affection of one hemisphere usually causes complete motor paralysis and loss of sensibility on the *opposite* side of the body. The fibres proceeding from the nuclei of orign of the **cranial nerves** also cross within the cranium.

Not unfrequently the motor paralysis and anæsthesia occur on the *same* side of the head, in which case the lesion (due to pressure or inflammation) involves the cranial nerves lying at the base of the brain.

The **positions of decussation** are (1) in the spinal cord, (2) in the medulla oblongata, and lastly (3) in the pons. The decussation is complete in the peduncle.

Alternate Paralysis.—Gubler observed that unilateral injury to the pons caused paralysis of the facial nerve on the *same* side, but paralysis of the *opposite* half of the body. He concluded that the nerves of the trunk decussate *before* they reach the pons, while the facial fibres decussate within the pons. To these rare cases the name "*alternate hemiplegia*" is given. [When hemorrhage takes place into the *lower* part of the lateral half of the pons, there may be alternate paralysis, but when the *upper* part of the lateral half is injured, the facial is paralyzed on the same side as the body, § 379.]

The olfactory nerve is said not to decussate (?), while the optic nerve undergoes a partial decussation at the chiasma (§ 344). Some observers assert that the fibres of the trochlearis decussate at their origin.

366. THE MEDULLA OBLONGATA.—[**Structure.**—In the medulla oblongata, the fibres from the cord are rearranged, the gray matter is also much changed, while new gray matter is added. Each half of the medulla oblongata consists of the following parts, from before backward:—The **anterior pyramid, olivary body, restiform body,** and **posterior pyramid,** or funiculus gracilis (Figs. 464, 465, 466). By the divergence of the posterior pyramids and the restiform bodies, the floor of the 4th ventricle is exposed. As the central canal of the cord gradually comes nearer to the posterior surface of the medulla, it opens into the 4th ventricle. At the lower end of the medulla oblongata, on separating the anterior pyramids, we may see the **decussation of the pyramids,** where the fibres cross over to the lateral columns of the cord. The **anterior pyramid** receives the direct pyramidal tract of the anterior column of the cord from its own side, and the crossed pyramidal tract from the lateral column of the cord of the opposite side (Fig. 464). The decussating fibres (crossed pyramidal tract) of the lateral column pass across in bundles to form the decussation of the pyramids. Most of the pyramidal fibres pass through the pons directly to the cerebrum, a few fibres pass to the cerebellum, while some join fibres proceeding from the olivary body to form the olivary fasciculus or fillet.]

[Thus, only a part of the anterior column of the cord—direct pyramidal tract—is continued into the anterior pyramid, where it lies external to the fibres which pass to the lateral column of the opposite side. The remainder of the anterior column—the antero-external fibres—are continued upward, but lie deeper under cover of the anterior pyramid, where they serve to form part of the formatio reticularis (p. 709).]

[Of the fibres of the *lateral column* of the cord, some, the *direct cerebellar* tract, pass backward to join the restiform body and go to the cerebellum. These fibres lie as a thin layer on the surface of the restiform body. The *crossed pyramidal* fibres cross obliquely, at the lower end of the medulla, to the anterior pyramid of the opposite side, and in their course they traverse the gray matter of the anterior cornu (Fig. 464, *py*). These fibres form the larger and mesial portion of the anterior pyramid. The remaining fibres of the lateral columns are continued upward, and pass beneath the olivary body, where they are concealed by this structure and also by the arcuate fibres, but they appear in the floor of the medulla oblongata and are here known as the *fasciculus teres*, which goes to the cerebrum. As they pass upward, they help to form the lateral part of the formatio reticularis.]

FIG. 463.



Diagram of a spinal segment as a spinal centre and conducting medium. B, right, B', left cerebral hemisphere; M lower end of medulla oblongata; 1, motor tract from the right hemisphere, the larger part decussating at M and passing down the lateral column of the cord on the opposite side to the muscles M and M'; 2, motor tr from the left hemisphere; S, S', sensitive areas on the left side of the body; 3', 3, the main sensory tract b the left side of the body—it decussates shortly after entering the cord; S^2, S^3, sensitive areas, and 4', 4, un from the right side of the body. The arrows indicate the direction of the impulses (*Bramwell*). [Here all sensory fibres are shown as crossing in the cord.]

[The **posterior pyramid** of the oblongata is merely the upward continuation of the postero-median column, or funiculus gracilis of the cord. As it passes upward at the medulla it broadens out, forming the **clava,** which tapers away above. The clava contains a mass of gray matter—the **clavate nucleus.**]

[The **restiform body** consists chiefly of the upward continuation of the postero-external column or funiculus cuneatus of the cord. It contains a mass of gray matter, called the **cuneate** or **triangular nucleus.** Above the level of the clava, the funiculus cuneatus forms part of the lateral boundary of the 4th ventricle. Immediately outside this, *i.e.*, between it and the continuation of the posterior nerve roots, is a longitudinal prominence, which Schwalbe has called the **funiculus of Rolando.** It is formed by the head of the posterior cornu of gray matter coming nearer the surface. It also forms part of the restiform body. Some *arcuate* fibres issue from the anterior median fissure, turn transversely outward over the anterior pyramids and olivary body, and pass along with the funiculus cuneatus, the funiculus of Rolando, and the direct cerebellar fibres, to enter the corresponding lateral lobe of the cerebellum, all these structures forming its inferior peduncle. Some observers suggest that the funiculus cuneatus and funiculus of Rolando do not pass into the cerebellum.]

FIG. 464.



Section of the decussation of the pyramids. *fla*, anterior median fissure, displaced laterally by the fibres decussating at *d*; *V*, anterior column; *Ca*, anterior cornu, with its nerve cells, *a*, *b*; *cc*, central canal; *S*, lateral column; *fr*, formatio reticularis; *ce*, neck, and *g*, head of the posterior cornu; *rpCI*, posterior root of the 1st cervical nerve; *nc*, first indication of the nucleus of the funiculus cuneatus; *ng*, nucleus (clava) of the funiculus gracilis; H^1, funiculus gracilis; H^2, funiculus cuneatus; *slp*, posterior median fissure; *x*, groups of ganglionic cells in the base of the posterior cornu. × 6.

[The **olivary body** forms a well marked oval or olive-shaped body, which does not extend the whole length of the medulla (Fig. 466, *o*). Above it is separated from the pons by a groove from which the 6th nerve emerges. In the groove between it and the anterior pyramid arise the strands of the hypoglossal nerve, while in a corresponding groove along its outer surface is the line of exit of the vagus, glosso-pharyngeal, and spinal accessory nerves. It is covered on its surface by longitudinal and arcuate fibres, while in its interior it contains the **dentate nucleus.**]

[The **functions of the olivary bodies** are quite unknown, but it is important to remember that they are connected by fibres with the dentate nuclei of the cerebellum. Fibres pass into the olivary body from the posterior column of the cord of the opposite side, and it is also connected with the dentate body of the opposite side, while, as we know, the dentate body is connected with the tegmentum, so that through the left dentate body of the opposite side, the tegmentum of, say, the right crus, is connected with the right olivary body (*Gowers*).]

[**Decussation of the pyramids** is the term given to those fibres which cross obliquely in several bundles, at the lower part of the medulla, from the anterior pyramid of the medulla into the lateral

column of the cord of the opposite side (Fig. 464, *d'*) to form its lateral pyramid tracts, or crossed pyramidal tracts. The number of fibres which decussate varies, and in some cases all the fibres may cross.]

[The **gray matter** of the medulla is largely a continuation of that of the cord, although it is arranged differently. As the fibres from the lateral column of the cord pass over to form part of the anterior pyramid of the medulla on the opposite side, they traverse the gray matter, and thus cut off the tip of the anterior cornu, which is also pushed backward by the olivary body, and exists as a distinct mass, the **nucleus lateralis** (Fig. 465, *nl*). Part of the anterior gray matter also appears in the floor of the 4th ventricle as the eminence of the fasciculus teres, and from part of it springs the hypoglossal nerve (Fig. 466, *XII*). The neck joining the modified anterior and posterior cornua is much broken up by the passage of longitudinal and transverse fibres through it, so that it forms a formatio reticularis, separating the two cornua (Fig. 465, *fr*). The caput cornu posterioris comes

FIG. 465.



Section of the medulla oblongata at the so-called upper decussation of the pyramids. *fla*, anterior, *slp*, posterior median fissure; *nXI*, nucleus of the accessorius vagi; *nXII*, nucleus of the hypoglossal; *da*, the so-called superior or anterior decussation of the pyramids; *py*, anterior pyramid; *n.ar*, nucleus arciformis; O^1, median parolivary body; *O*, beginning of the nucleus of the olivary body: *nl*, nucleus of the lateral column; *Fr*, formatio reticularis; *g*, substantia gelatinosa, with (*aV*) the ascending root of the trigeminus; *nc*, nucleus of the funiculus cuneatus; nc^1, external nucleus of the funiculus cuneatus; *ng*, nucleus of the funiculus gracilis (or clava); H^1, funiculus gracilis; H^2, funiculus cuneatus; *cc*, central canal; *fa*, fa^1, fa^2, external arciform fibres. × 4.

FIG. 466.



Section of the medulla oblongata through the olivary body. *nXII*, nucleus of the hypoglossal; *nX*, *nX'*, more or less cellular parts of the nucleus of the vagus; *XII*, hypoglossal nerve; *X*, vagus; *n.am*, nucleus ambiguus; *nl*, nucleus lateralis; *o*, olivary nucleus; *oal*, external, and *oam*, internal parolivary body; *fs*, the round bundle, or funiculus solitarius; *Cr*, restiform body; *p*, anterior pyramid, surrounded by arciform fibres; *fae*, *fpol*, fibres proceeding from the olive to the raphe (pedunculus olivæ); *r*, raphe. × 4.

to be covered higher up by the ascending root of the 5th nerve (Fig. 465, *aV*), and arcuate fibres passing to the restiform body. The posterior cornu is also broken up and is thrown outward, its caput giving rise to part of the elevation seen on the surface and described as the funiculus of Rolando, while part of the base now greatly enlarged forms the gray matter in the funiculus gracilis [clavate nucleus] (Fig. 464, *ng*) and funiculus cuneatus [cuneate or triangular nucleus] (Fig. 464, *nc*). Nearer the middle line, the gray matter of the posterior gray cornu appears in the floor of the 4th ventricle, above the point where the central canal opens into it, as the nuclei of the spinal accessory, vagus, and glosso-pharyngeal nerves.]

[In the floor of the 4th ventricle near the raphe, and quite superficial, is a longitudinal mass of large multipolar nerve cells, derived from the base of the anterior cornu from which spring the several bundles forming the hypoglossal nerve; it is the **hypoglossal nucleus** (Fig. 466, *nXII*), the nerve fibres passing obliquely outward to appear between the anterior pyramid and the olivary body.

Internal to it, and next the median groove, is a small mass of cells continuous with those in the raphe, and called the nucleus of the funiculus teres (Fig. 466, *nt*). Around the central canal at the lower part of the medulla is a group of cells (Fig. 466, *nXI*), which becomes displaced laterally as it comes nearer the surface in the floor of the medulla oblongata, where it lies outside the hypoglossal nucleus, and corresponds to the prominence of the ala cinerea (Fig. 466, *nX*); and from it and its continuation upward arise from below upward part of the spinal accessory (11th), and the vagus (10th), corresponding to the position of the eminentia cinerea (Fig. 466, *X*), so that this column of cells forms the **vago-accessorius nucleus.** External to and in front of this is the nucleus for the glosso-pharyngeal nerve. Further up in the medulla, on a level with the auditory striæ and outside the previous column, is a tract of cells from which the auditory nerve (8th) in great part arises; it is the **principal auditory nucleus,** and lies just under the commencement of the inferior cerebellar peduncle (Fig. 427, 8′, 8″, 8‴). It consists of an outer and inner nucleus, which extend to the middle line. It forms connections with the cerebellum, and some fibres are said to enter the inferior cerebellar peduncle. This is an important relationship, as we know that the vestibular branch of the auditory nerve comes partly from the semicircular canals, so that in this way these organs may be connected with the cerebellum.]

[**Superadded Gray Matter.**—There is a superadded mass of gray matter not represented in the cord, that of the **olivary body,** enclosing a nucleus, the **corpus dentatum,** with its wavy strip of gray matter containing many small multipolar nerve cells embedded in neuroglia. The gray matter is covered on the surface by longitudinal and transverse fibres. It is open toward the middle line (hilum), and into it run white fibres forming its *peduncle* (Fig. 466, *p*, *o*, *l*). These fibres diverge like a fan, some of them ending in connection with the small multipolar cells of the dentate body, while others traverse the lamina of gray matter and pass backward to appear as arcuate fibres which join the restiform body; others, again, pass directly through to the surface of the olivary body, which they help to cover as the superficial arcuate fibres. The **accessory olivary nuclei** (Fig. 465, *o′*, *o″*) are two small masses of gray matter similar to the last, and looking as if they were detached from it, one lying above and external, sometimes called the **parolivary body,** and the other slightly below and internal to the olivary nucleus, the latter being separated from the dentate body by the roots of the hypoglossal nerve. The latter is sometimes called the internal parolivary body, or **nucleus of the pyramid.**]

[The **formatio reticularis** occupies the greater part of the central and lateral parts of the medulla, and is produced by the inter-crossing of bundles of fibres running longitudinally and more or less transversely in the medulla (Fig. 465, *fr*). In the more lateral portions are large multipolar nerve cells, perhaps continued upward from part of the anterior cornu, while the part next the raphe has no such cells. The longitudinal fibres consist of the upward prolongation of the antero-external columns of the cord, while some seem to arise from the clavate nuclei and olives as arcuate fibres passing upward. In the lateral portions, the longitudinal fibres are the direct continuation upward of Flechsig's antero-lateral mixed tracts of the lateral columns (p. 683). The horizontal fibres are formed by **arcuate fibres,** some of which run more or less transversely outward from the raphe. The *superficial arcuate fibres* (Fig. 466, *f*, *a*, *e*) appear in the anterior median fissure, and perhaps come through the raphe from the opposite side of the medulla, curve round the anterior pyramids, form a kind of capsule for the olives, and join the restiform body (p. 707), but they are reinforced by some of the deep arcuate fibres which traverse the olivary body (p. 707). The *deep arcuate fibres* run from the clavate and triangular nuclei horizontally inward to the raphe, and cross to the other side; others pass from the raphe to the olivary body, and through it to the restiform body. In the **raphe,** which contains nerve cells, some fibres run transversely, others longitudinally, and others from before backward.]

[**Other Nerve Nuclei—Sixth Nerve.**—Under the elevation called eminentia teres (Fig. 427) in front of the auditory striæ, close to the middle line, is a tract of large multipolar nerve cells. It was once thought to be the common nucleus of the 6th and 7th facial nerves, but Gowers has shown that "the facial ascends to this nucleus, forms a loop round it (some fibres indeed go through it), and then passes downward forward and outward, to a column of cells more deeply placed in the medulla than any other nucleus in the lower part." But the seventh has no real origin from this nucleus. **Facial Nerve.**—The nucleus lies deep in the formatio reticularis of the pons under the floor of the 4th ventricle, but outside the position of the nucleus of the 6th (Fig. 427, 7). It extends downward about as far as the auditory striæ, or a little lower. The **fifth nerve** arises from its **motor nucleus** (with large multipolar cells), which lies more superficially above and external to the 6th (Fig. 427, 5). The fibres run backward, where they are joined by fibres from the upper **sensory nucleus,** but another sensory nucleus extends down nearly to the lower end of the medulla (5″). Doubtless this extensive origin brings this nerve into intimate relation with the other cranial nerves, and accounts for the numerous reflex acts which can be discharged through the fifth nerve. Some sensory fibres are said to pass up beneath the corpora quadrigemina (*Gowers*). The **fourth nerve** arises from the valve of Vieussens, *i. e.*, the lamina of white and gray matter which stretches between the superior cerebellar peduncles. It arises, therefore, *behind* the fourth ventricle, but some of the fibres spring from nerve cells at the lower part of the nucleus of the 3d nerve. Some fibres also

descend in the pons to form a connection with the nucleus of the 6th nerve. The fibres decussate behind the aqueduct, so that in it alone, of all the cranial nerves, decussation occurs between its nucleus and its superficial origin (*Gowers*). The **third nerve** arises from a tract of cells beneath the aqueduct and near the middle line, and the fibres descend through the tegmentum to appear at the inner side of the crus cerebri. Gowers points out that, in reality, there are three distinct functional centres (1) for accommodation (ciliary muscle), (2) for the light reflex of the iris, and (3) most of the external muscles of the eyeball. It is important to notice the connection between the nuclei of the 3d, 4th, and 6th nerves, in relation to the innervation of the ocular muscles.]

Functions.—The medulla oblongata, which connects the spinal cord with the brain, has many points of resemblance with the former. [Like the cord it is concerned (1) in the **conduction** of impulses.] (2) In it, numerous **reflex centres** are present, *e. g.*, for *simple reflexes* similar to the nerve centres in the spinal cord, *e. g.*, closure of the eyelids [so that they subserve the transference of afferent into efferent impulses]. There are other centres present which seem to **dominate** or *control* similar centres placed in the cord, *e. g.*, the great vasomotor centre, the sweat-secreting, pupil-dilating centres, and the centre for combining the reflex movements of the body. Some of the centres are capable of being excited *reflexly* (§ 358, 2). (3) It is also said to contain **automatic centres** (§ 358, 3). The normal functions of the centres depend upon the **exchanges of blood gases**, effected by the circulation of the blood through the medulla. If this gaseous exchange be interrupted or interfered with, as by asphyxia, sudden anæmia, or venous congestion, these centres are first excited, and exhibit a condition of increased excitability, and at last, if they are over-stimulated, they are paralyzed. An excessive **temperature** also acts as a stimulus. All the centres, however, are not active at the same time, and they do not all exhibit the same degree of excitability. Normally, the respiratory centre and the vasomotor centre are continually in a state of rhythmical activity. In some animals, the inhibitory centre of the heart remains continually non-excited; in others, it is stimulated very slightly under normal conditions, simultaneously with the stimulation of the respiratory centre, and only during inspiration. The spasm centre is not stimulated under normal conditions; and during intra-uterine life, the respiratory centre remains quiescent. The medulla oblongata, therefore, contains a collocation of nerve centres which are essential for the maintenance of life, as well as various conducting paths of the utmost importance. We shall treat of the reflex, and afterward of the automatic centres.

367. REFLEX CENTRES OF THE MEDULLA OBLONGATA.—The medulla oblongata contains a number of reflex centres, which minister to the discharge of a large number of coördinated movements.

1. **Centre for closure of the eyelids.**—The sensory branches of the 5th cranial nerve to the cornea, conjunctiva, and the skin in the region of the eye, are the **afferent** nerves. They conduct impulses to the medulla oblongata, where they are transferred to, and excite part of, the centre of the facial nerve, whence, through branches of the facial, the **efferent** impulses are conveyed to the orbicularis palpebrarum. The centre extends from about the middle of the ala cinerea upward to the posterior margin of the pons (*Nickell*).

The reflex closure of the eyelids always occurs on *both* sides, but closure may be produced voluntarily on one side (winking). When the stimulation is *strong*, the corrugator and other groups of muscles which raise the cheek and nose toward the eye may also contract, and so form a more perfect protection and closure of the eye. Intense stimulation of the retina causes closure of the eyelids [and in this case the shortest reflex known, the latent period, is 0.05 second (*Waller*)].

2. **Sneezing centre.**—The **afferent** channels are the internal nasal branches of the trigeminus and the olfactory, the latter in the case of intense odors. The **efferent** or motor paths lie in the nerves for the muscles of expiration (§§ 120, 3, and 347, II). Sneezing cannot be performed voluntarily [but it may be inhibited by compressing the nasal nerve at its exit on the nose].

3. **Coughing centre.**—According to Kohts, it is placed a little above the inspiratory centre; the **afferent** paths are the sensory branches of the vagus (§ 352, 5, *a*). The **efferent** paths lie in the nerves of expiration and those that close the glottis (§ 120, 1).

4. **Centre for sucking and mastication.**—The **afferent** paths lie in the sensory branches of the nerves of the mouth and lips (2d and 3d branches of the trigeminus and glosso-pharyngeal). The **efferent** nerves for *sucking* are (§ 152): Facial for the lips, hypoglossal for the tongue, the inferior maxillary division of the trigeminus for the muscles which elevate and depress the jaw. For the movements of *mastication*, the same nerves are in action (§ 153); but when food passes within the dental arch, the hypoglossal is concerned in the movements of the tongue, and the facial for the buccinator.

5. **Centre for the secretion of saliva** (p. 259) lies in the floor of the 4th ventricle. Stimulation of the medulla oblongata causes a profuse secretion of saliva when the chorda tympani and glosso-pharyngeal nerves are intact, a much feebler secretion when the nerves are divided, and no secretion at all when the cervical sympathetic is extirpated at the same time (*Grützner*).

6. **Swallowing centre** lies in the floor of the 4th ventricle (§ 156).—The **afferent** paths lie in the sensory branches of the nerves of the mouth, palate, and pharynx (2d and 3d branches of the trigeminus, glosso-pharyngeal, and vagus); the **efferent** channels, in the motor branches of the pharyngeal plexus (§ 352, 4). Stimulation of the glosso-pharyngeal nerve does not cause deglutition; on the contrary, this act is inhibited (p. 273).

According to Steiner, every time we swallow there is a slight stimulation of the respiratory centre, resulting in a contraction of the diaphragm. [Kronecker has shown that if a glass of water be sipped slowly, the action of the cardio-inhibitory centre is interfered with reflexly, so that the heart beats much more rapidly, whereby the circulation is accelerated, hence probably the reason why sipping an alcoholic drink intoxicates more rapidly than when it is quickly swallowed (p. 719).]

7. **Vomiting centre** (§ 158).—The relation of certain branches of the vagus to this act are given at § 352, 2, and 12, *d*.

8. **The upper centre for the dilator pupillæ** muscle, the smooth muscles of the orbit, and the eyelids lies in the medulla oblongata. The fibres pass out partly in the trigeminus (§ 347, I, 3), partly in the lateral columns of the spinal cord as far down as the cilio-spinal region, and proceed by the two lowest cervical and the two upper dorsal nerves into the cervical sympathetic (§ 356, A, 1). The **centre** is normally excited *reflexly* by shading the retina, *i. e.*, by diminishing the amount of light admitted into the eye. It is directly excited by the circulation of dyspnœic blood in the medulla. (The centre for *contracting* the pupil is referred to at §§ 345 and 392.)

The centre may be excited reflexly by stimulation of sensory nerve, *e. g.*, the sciatic. These afferent fibres pass upward through both lateral columns to their centre (*Kowalewsky*).

9. There is a subordinate centre in the medulla oblongata, which seems to be concerned in bringing the various reflex centres of the cord into relation with each other. Owsjannikow found that, on dividing the medulla 6 mm. above the calamus scriptorius (rabbit), the *general* reflex movements of the body still occurred, and the anterior and posterior extremities participated in such general movements. If, however, the section was made 1 mm. nearer the calamus, only local partial reflex actions occurred (§ 360, III, 4); [thus, on stimulating the hind leg, the fore legs did not react—the *transference* of the reflex was interfered with]. The centre reaches upward to slightly above the lowest third of the oblongata.

The medulla in the frog also contains the general centre for movements from place to place. Section of this region abolishes the power to move from place to place; when external stimuli are applied, there remains only simple reflex movements (*Steiner*).

Pathological.—The medulla oblongata is sometimes the seat of a typical disease, known as **bulbar paralysis,** or glosso-pharyngo-labial paralysis (*Duchenne*, 1860), in which there is a progressive invasion of the different nerve nuclei (centres) of the cranial nerves which arise within the medulla, these centres being the motor portions of an important reflex apparatus. Usually, the disease begins with paralysis of the *tongue*, accompanied by fibrillar contractions, whereby speech, formation of the food into a bolus, and swallowing are interfered with (§ 354). The secretion of thick, viscid saliva points to the impossibility of secreting a thin, watery, *facial saliva* (§ 145, A), owing to paralysis of this nerve nucleus. Swallowing may be impossible, owing to paralysis of the pharynx and palate. This interferes with the formation of *consonants* [especially the linguals, *l*, *t*, *s*, *r*, and, by and by, the labial explosives, b, p] (§ 318, C); the speech becomes nasal, while fluids and solid food often pass into the nose. Then follows paralysis of the branches of the facial to the lips, and there is a characteristic expression of the mouth "as if it were frozen." All the muscles of the face may be paralyzed; sometimes the *laryngeal muscles* are paralyzed, leading to loss of voice and the entrance of food into the windpipe. The *heart beats* are often retarded, pointing to stimulation of the cardio-inhibitory fibres (arising from the accessorius). Attacks of *dyspnœa*, like those following paralysis of the recurrent nerves (§ 313, H, 1, and § 352, 5, *b*), and death may occur. Paralysis of the muscles of mastication, contraction of the pupil, and paralysis of the abducens are rare. [This disease is always bilateral, and it is important to note that it affects the nuclei of those muscles that guard the orifices of the mouth, including the tongue, the posterior nares including the soft palate, and the rima glottidis with the vocal cords.]

368. RESPIRATORY CENTRE. INNERVATION OF THE RESPIRATORY ORGANS.—The **respiratory centre** lies in the medulla oblongata (*Legallois*, 1811), behind the superficial origin of the vagi, on both sides of the posterior aspect of the apex of the calamus scriptorius, between the nuclei of the vagus and accessorius, and was named by Flourens the vital point, or **nœud vital.** The centre is double, one for each side, and it may be separated by means of a longitudinal incision (*Longet*, 1847), whereby the respiratory movements continue symmetrically on both sides. **Section of Vagi.**—If **one vagus** be divided, respiration on that side is *slowed*. If *both* vagi be divided, the respirations become much *slower* and *deeper*, but the respiratory movements are symmetrical on both sides. Stimulation of the *central* end of one vagus, both being divided, causes an arrest of the respiration only on the same side, the other side continues to breathe. The same result is obtained by stimulation of the trigeminus on one side (*Langendorff*). When the centre is divided transversely on one side, the respiratory movements on the *same* side cease (*Schiff*). Most probably the **dominating** respiratory centre lies in the medulla oblongata, and upon it depend the rhythm and symmetry of the respiratory movements; but, in addition, other and **subordinate** centres are placed in the spinal cord, and these are governed by the oblongata centre. If the spinal cord be divided in newly-born animals (dog, cat) below the medulla oblongata, respiratory movements of the thorax are sometimes observed (*Brachet*, 1835).

[If the cord be divided below the medulla, or the cranial arteries ligatured (rabbit), there may still be respiratory movements, which become more distinct if **strychnin** be previously administered, so that Langendorff assumes the existence of a spinal respiratory centre, which he finds is also influenced by reflex stimulation of sensory nerves.]

Nitschmann, by means of a vertical incision into the cervical cord, divided the spinal centre into two equal halves, each of which acted on both sides of the diaphragm after the medulla was divided just below the calamus scriptorius. The spinal centres must, therefore, be connected with each other in the cord. The spinal respiratory centre can be excited or inhibited reflexly (*Wertheimer*).

Anatomical.—Schiff locates the respiratory centre near the lateral margins of the gray matter in the floor of the 4th ventricle, but not reaching so far backward as the ala cinerea. According to Gierke, Heidenhain, and Langendorff, those parts of the medulla oblongata whose destruction causes cessation of the respiratory movements are single or double strands of nervous matter, containing gray nervous substance with small ganglion cells, and running downward in the substance of the medulla oblongata. These strands are said to arise partly from the roots of the vagus, trigeminus, spinal accessory, and glosso-pharyngeal (*Meynert*), forming connections by means of fibres with the other side, and descending as far downward as the cervical enlargement of the spinal cord (*Goll*). According to this view, this strand represents an *inter-central* band connecting the spinal cord (the place of origin of the motor respiratory nerves) with the nuclei of the above-named cranial nerves.

Cerebral Inspiratory Centre.—According to Christiani, there is a *cerebral inspiratory centre* in the optic thalamus in the floor of the 3d ventricle, which is stimulated through the optic and auditory nerves, even after extirpation of the cerebrum and corpora striata; when it is stimulated directly, it deepens and accelerates the *inspiratory* movements, and may even cause a standstill of the respiration in the inspiratory phase. This inspiratory centre may be extirpated. After this operation, an *expiratory* centre is active in the substance of the anterior pair of the corpora quadrigemina, not far from the aqueduct of Sylvius. Martin and Booker describe a second cerebral *inspiratory* centre in the posterior pair of the corpora quadrigemina. These three centres are connected with the centres in the medulla oblongata.

FIG. 467.



Scheme of the chief respiratory nerves. *ins*, inspiratory, and *exp*, expiratory centre—motor nerves are in smooth lines Expiratory motor nerves to abdominal muscles, *ab*; to muscles of back, *do*. Inspiratory motor nerves. *ph*, phrenic to diaphragm, *d*; *int*, intercostal nerves; *rl*, recurrent laryngeal; *ex*, pulmonary fibres of vagus that excite inspiratory centre; *ex'*, pulmonary fibres that excite expiratory centre; *ex''*, fibres of sup. laryngeal that excite expiratory centre; *inh*, fibres of sup. laryngeal that inhibit the inspiratory centre.

The **respiratory** centre consists of **two centres,** which are in a state of activity alternately—an **inspiratory** and an **expiratory centre** (Fig. 467), each one forming the motor central point for the acts of inspiration and expiration (§ 112). The centre is **automatic,** for, after section of all the sensory nerves which can act reflexly upon the centre, it still retains its activity. The degree of excitability and the stimulation of the centre depend upon the **state of the blood,** and chiefly upon the amount of the blood gases, the O and CO_2 (*J. Rosenthal*). According to the condition of the centre, there are several well-recognized respiratory conditions:—

1. **Apnœa.**—Complete cessation of the respiration constitutes *apnœa, i. e.*, cessation of the respiratory movements, owing to the absence of the proper stimulus, due to the blood being saturated with O and poor in CO_2. Such blood saturated with O fails to stimulate the centre, and hence the respiratory muscles are quiescent. This seems to be the condition in the fœtus during intra-uterine life. If air be vigorously and rapidly forced into the lungs of an animal by artificial respiration, the animal will cease to breathe for a time, after cessation of the artificial respiration (*Hook*, 1667), the blood being so arterialized that it no longer stimulates the respiratory centre. If a person takes a series of rapid, deep respirations his blood becomes surcharged with oxygen, and long "**apnœic pauses**" occur.

Apnœic Blood.—A. Ewald found that the arterial blood of apnœic animals was completely saturated with O, while the CO_2 was diminished; the venous blood contained less O than normal—this latter condition being due to the apnœic blood causing a considerable fall of the blood pressure and consequent slowing of the blood stream, so that the O can be more completely taken from the blood in the capillaries (*Pflüger*). The amount of O used in apnœa on the whole is not increased (§ 127). Gad remarks that during forced *artificial respiration*, the pulmonary alveoli contain a very large amount of atmospheric air; hence, they are able to arterialize the blood for a longer time, thus diminishing the necessity for respiration. According to Gad and Knoll, the excitability of the respiratory centre is reduced during apnœa, and this is caused reflexly during artificial respiration by the distention of the lungs stimulating the branches of the vagus. In quite young mammals apnœa cannot be produced (*Runge*).

[**Drugs.**—If the excitability of the respiratory centre be diminished by chloral, apnœa is readily induced, while, if the centre be excited, as by apomorphine, it is difficult to produce it.]

2. Eupnœa.—The normal stimulation of the respiratory centre, *eupnœa*, is caused by the blood, in which the amount of O and CO_2 does not exceed the normal limits (§§ 35 and 36).

3. Dyspnœa.—All conditions which diminish the O and increase the CO_2 in the blood circulating through the medulla and respiratory centre cause acceleration and deepening of the respirations, which may ultimately pass into vigorous and labored activity of all the respiratory muscles, constituting *dyspnœa*, when the difficulty of breathing is very great (§ 134). [Changes in the rhythm, § 111.]

During normal respiration, and with the commencement of the need for more air, according to Gad, the gases of the blood excite only the inspiratory centre; while the expiration follows owing to reflex stimulation of the pulmonary vagus by the distention of the lungs (p. 716). He is also of opinion that the normal respiratory movements are excited by the CO_2.

[**Muscular work**, as is well known, increases the respirations and may even cause dyspnœa. This is not due to the nervous connections of the muscles or other organs with the respiratory centre, but to changes in the blood. Geppert and Zuntz have shown, however, that the result cannot be explained by changes in the blood caused either by diminution of O or increase of CO_2. It seems to be due to the blood taking up some as yet unknown products from the contracting muscle, and carrying them to the respiratory centre, which is directly excited by them. The nature of these substances is unknown. It has been shown that the alkalinity of the blood is reduced by the formation of an acid. The substances, whatever they may be, are not excreted by the urine, and are therefore, perhaps readily oxidized (*Loewy*). C. Lehmann has proved that, in rabbits, the acidification of the blood produced by muscular exertion plays an important part in the stimulation of the respiratory centre.]

4. Asphyxia.—If blood, abnormal as regards the amount and quality of its gases, continue to circulate in the medulla, or if the condition of the blood become still more abnormal, the respiratory centre is *over-stimulated*, and ultimately *exhausted*. The respirations are diminished both in number and depth, and they become feeble and gasping in character; ultimately the movements of the respiratory muscles cease, and the heart itself soon ceases to beat. This constitutes the condition of *asphyxia*, and if it be continued, death from **suffocation** takes place. (Langendorff asserts that in asphyxiated frogs the muscles and gray nervous substance have an acid reaction.) If the conditions causing the abnormal condition of the blood be removed, the asphyxia may be prevented under favorable circumstances, especially by using **artificial respiration** (§ 134); the respiratory muscles begin to act and the heart begins to beat, so that the normal eupnœic stage is reached through the condition of dyspnœa. If the venous condition of the blood be produced slowly and very gradually, asphyxia may occur without there being any symptoms of dyspnœa, as happens when death takes place quietly and very gradually (§ 324, 5).

Causes of Dyspnœa.—(1) Direct **limitation of the activity of the respiratory organs**; diminution of the respiratory surface by inflammation, acute œdema (§ 47), or collapse of the alveoli, occlusion of the capillaries of the alveoli, compression of the lungs, entrance of air into the pleura, obstruction or compression of the windpipe. (2) **Obstruction to the entrance of the normal amount of air** by strangulation, or enclosure in an insufficient space. (3) **Enfeeblement of the circulation**, so that the medulla oblongata does not receive a sufficient amount of blood; in degeneration of the heart, valvular cardiac disease, and artificially by ligature of the carotid and vertebral arteries (*Kussmaul and Tenner*), or by preventing the free efflux of venous blood from the skull, or by the injection of a large quantity of air or indifferent particles into the right heart. (4) **Direct loss of blood**, which acts by arresting the exchange of gases in the medulla (*J. Rosenthal*). This is the cause of the "biting or snapping at the air" manifested by the decapitated heads of young animals, *e. g.*, kittens. [The phenomenon is well marked in the head of a tortoise separated from the body (*W. Stirling*).]

If we study the rapidly fatal effects of these factors on the respiratory activity, we observe that at first the respirations become quicker and deeper, then after an attack of general convulsions, ending in expiratory spasm, there follows a stage of complete cessation of respiration. Before death takes place, there are usually a few "snapping" or gasping efforts at inspiration (*Hegyes, Sigm. Mayer*—§ 111).

Condition of the Blood Gases.—As a general rule, in the production of dyspnœa, the want of O and the excess of CO_2 act simultaneously (*Pflüger and Dohmen*), but each of these alone may act as an efficient cause. According to Bernstein, blood containing a small amount of O acts chiefly

upon the inspiratory centre, and blood rich in CO_2 on the expiratory centre. (1) **Dyspnœa, from want of** O, occurs during respiration in a space of *moderate* size (§ 133), in spaces where the tension of the air is diminished, and by breathing indifferent gases or those containing no free O. When the blood is freely ventilated with N or H, the amount of CO_2 in the blood may even be diminished, and death occurs with all the signs of asphyxia (*Pflüger*). (2) **Dyspnœa, from the blood being overcharged with** CO_2, occurs by breathing air containing much CO_2 (§ 133). Air containing much CO_2 may cause dyspnœa, even when the amount of O in the blood is greater than that in the atmosphere (*Thiry*). The blood may even contain more O than normal (*Pflüger*).

Heat Dyspnœa.—An increased temperature increases the activity of the respiratory centre (§ 214, II, 3). This occurs when blood warmer than natural flows through the brain, as Fick and Goldstein observed when they placed the exposed carotids in warm tubes, so as to heat the blood passing through them. In this case the heated blood acts directly upon the brain, the medulla, and the cerebral respiratory centres (*Gad*). Direct cooling diminishes the excitability (*Frédéricq*). When the temperature is increased, vigorous artificial respiration does not produce apnœa, although the blood is highly arterialized (*Ackermann*). Emetics act in a similar manner (*Hermann and Grimm*).

Electrical stimulation of the medulla oblongata, after it is separated from the brain, discharges respiratory movements or increases those already present (*Kronecker and Marckwald*). Langendorff found that electrical, mechanical, or chemical (salts) stimulation usually caused an expiratory effect, while stimulation of the cervical spinal cord (subordinate centre) gave an inspiratory effect. According to Laborde, a superficial lesion in the region of the calamus scriptorius causes standstill of the respiration for a few minutes. If the peripheral end of the vagus be stimulated, so as to arrest the action of the heart, the respirations also cease after a few seconds. Arrest of the heart's action causes a temporary anæmia of the medulla, in consequence of which its excitability is lowered, so that the respirations cease for a time (*Langendorff*).

Action on the Centre.—The respiratory centre, besides being capable of being stimulated **directly**, may be influenced by the **will**, and also **reflexly** by stimulation of a number of afferent nerves.

1. By a **voluntary impulse** we may arrest the respiration for a short time, but only until the blood becomes so venous as to excite the centre to increased action. The number and depth of the respirations may be voluntarily increased for a long time, and we may also voluntarily change the rhythm of respiration.

2. The respiratory centre may be influenced **reflexly** both by fibres which excite it to *increased action* and by others which *inhibit* its action. (*a*) The **exciting** fibres lie in the pulmonary branches of the vagus, in the optic, auditory, and cutaneous nerves; normally their action overcomes the action of the inhibitory fibres. Thus, a cold bath deepens the respirations, and causes a moderate acceleration of the pulmonary ventilation (*Speck*).

Section of both vagi causes **slower** and **deeper** respiratory movements, owing to the cutting off of those impulses which under normal conditions pass from the lungs to excite the respiratory centre (p. 712). The **amount of air** taken in the CO_2 given off, however, is unchanged, but the inspiratory efforts are more vigorous and not so purposive (*Gad*). *Weak* tetanizing currents applied to the *central* end of the vagus, cause acceleration of the respirations, while, at the same time, the efforts of the respiratory muscles may be increased, or diminished, or remain unchanged (*Gad*). *Strong* tetanizing currents cause standstill of the respiration in the inspiratory phase (*Traube*), or especially in fatigue of the nerves, in the expiratory phase (*Budge, Burkart*). *Single* induction shocks have no effect (*Marckwald and Kronecker*).

[Marckwald, while admitting that the respiratory centre is automatically active, as well as capable of being affected reflexly, comes to the conclusion, that, when the centre is separated from all nerve channels by which afferent impulses can be conveyed to it, it is incapable of discharging rhythmical respiratory movements. He also asserts that the normal rhythmical respiration is a reflex act discharged chiefly through the vagi, and that the normal excitant of the respiratory centre is not dependent on the condition of the blood, either on the diminution of O, or the increase of CO_2. These results are opposed to the usually accepted view, and they are controverted by Loewy. Division of the medulla oblongata above the respiratory centre, so as to cut off all cerebral channels of communication, has very little effect on the respirations. If, after this, one, or both vagi be divided, there is (1) an *extraordinary slowing* of the respiration; the number of respirations may fall in the rabbit, from 20 to 2 or 4 per minute; (2) the rhythm is changed, in some cases the

inspiration may be twice or thrice as long as the expiration, but, whatever the ratio of inspiration to expiration, the respiration is rhythmical; (3) the *volume* of air respired is diminished (p. 715), but the volume for each respiration is deeper; (4) the intra-thoracic pressure is increased, during inspiration, and during expiration it is the same as before the vagotomy.]

Before Vagotomy.					After Vagotomy.						
Experiment.	Intra-thoracic Pressure.	Frequency.	Volume Resp. per Min.	Volume Resp. per Respir.	Intra-thoracic Pressure.	Frequency.	Relation of Exp. Insp.	Volume Resp. per Min.	Diminution of Vol. per Min.	Volume Resp. per Respir.	Increase of Vol. for each Resp.
	mm.		c.cm.	c.cm.				c.cm.	%		%
1	−30 to −40	20	310–350	16	−60 to −70	4	½	130–140	59	33	100
2	−22 to −24	32	530–540	16	−50 to −60	2½	½	105–120	79.5	40	150

[The above table (from Loewy) shows the result. Loewy finds that, if a centre be separated from all centripetal channels, it still discharges respiratory movements, which are rhythmical, and he has shown that these rhythmical discharges are due to the condition of the blood.]

[If one lung be made atelectic, *i. e.*, devoid of air, *e. g.*, by plugging its bronchus with a sponge tent, then the pulmonary fibres of the vagus from this lung are no longer excited during respiration, and their section has no effect on the respiration. Section of the vagus on the sound side, however, has the same consequence as double vagotomy (*Loewy*).]

Wedenski and Heidenhain find that a *temporary, weak*, electrical stimulus applied to the central end of the vagus, at the beginning of inspiration (rabbit), affects the depth of the succeeding inspirations, while a similar strong stimulus affects also the depth of the following expiration. If the stimulus be applied just at the commencement of expiration, stronger stimuli being required in this case, there is a diminution of the expiration and of the following inspiration. *Continued* tetanic stimulation of the vagus may cause decrease in the depth of the expirations, or at the same time alteration in the depth of the inspirations, without affecting the respiratory rhythm; when the stimulation is *stronger*, inspiration and expiration are diminished with or without alteration of the frequency, and with the *strongest* stimuli, respirations cease either in the inspiratory or expiratory phase.

(*b*) The **inhibitory** nerves which affect the respiratory centre run in the superior laryngeal nerve (*Rosenthal*), and also in the inferior (*Pflüger and Burkart, Hering, Breuer*), to the respiratory centre (Fig. 467, *inh*).

According to Langendorff, direct electrical, mechanical, or chemical stimulation of the centre may arrest respiration, perhaps in consequence of the stimulus affecting the central ends of the inhibitory nerves where they enter the ganglia of the respiratory centre. During the reflex inhibition of the respiration in the expiratory phase, there is a suppression of the motor impulse in the inspiratory centre (*Wegele*).

Stimulation of the superior or inferior laryngeal nerves (*b*) or their *central* ends causes slowing, and even arrest of the respiration (in expiration—*Rosenthal*). Arrest of the respiration in expiration is also caused by stimulation of the nasal (*Hering and Kratschmer*) and ophthalmic branches of the trigeminus (*Christiani*), of the olfactory, and glosso-pharyngeal (*Marckwald*). [Kratschmer found that tobacco smoke blown into a rabbit's nostrils, or puffed through a hole in the trachea into the nose, by stimulating the nasal branch of the fifth nerve, arrested the respiration in the expiratory phase; while it had no effect when blown into the lungs. Ammonia vapor applied to the nostrils arrests it in the same way. If ammonia vapor be blown into the lungs (the nasal cavity being protected from its action), the respiration may be accelerated, or deepened, or arrested occasionally in expiration, *i. e.*, according to the fibres of the vagus acted on by the vapor in the lungs (*Knoll*).] Stimulation of the pulmonary branches of the vagus by breathing irritating gases (*Knoll*) causes standstill in expiration, although some other gases cause standstill in inspiration. Chemical stimulation of the trunk of the vagus—by dilute solutions of sodic carbonate—causes expiratory inhibition of the respiration; and mechanical stimulation—rubbing with a glass rod—inspiratory inhibition

(*Knoll*). The stimulation of sensory cutaneous nerves, especially of the chest and abdomen (as occurs on taking a cold douche), and stimulation of the splanchnics, cause standstill in expiration, the first cause often giving rise to temporary clonic contractions of the respiratory muscles. The respirations are often slowed to a very great extent by pressure upon the brain [whether the pressure be due to a depressed fracture or effusion into the ventricles and subarachnoid space]. The respiration may be greatly oppressed and stertorous.

The amount of **work** done by the respiratory muscles is altered during the reflex slowing of the respiratory muscles, the work being increased during slow respiration, owing to the ineffectual inspiratory efforts (*Gad*). The **volume of the gases** which passes through the lungs during a given time remains unchanged (*Valentin*), and the gaseous exchanges are not altered at first (*Voit and Rauber*).

Automatic Regulation.—Under normal circumstances, it would seem that the pulmonary branches of the vagus act upon the two respiratory centres, so as to set in action what has been termed the *self-adjusting* mechanism; thus, the inspiratory dilatation of the lungs stimulates mechanically the fibres which reflexly excite the *expiratory* centres, while the diminution of the lungs during expiration excites the nerves which proceed to the *inspiratory* centre (*Hering and Breuer, Head*). [Thus, blowing into the lungs excites the act of expiration, and sucking air out of them excites inspiration.]

In this way we may explain the alternate play of inspiration and expiration. In deep narcosis, however, dilatation of the thorax in animals is followed first by cessation of the respiratory movements, and then by inspiration (*P. Guttmann*).

Discharge of the First Respiration.—The fœtus is in an apnœic condition until birth, when the umbilical cord is cut. During intra-uterine life, O is freely supplied to it by the activity of the placenta. All conditions which interfere with this due supply of O, as compression of the umbilical vessels and prolonged labor pains, cause a decrease of the O and an increase of the CO_2 in the blood, so that the condition of the fœtal blood is so altered as to stimulate the respiratory centre, and thus the impulse is given for the discharge of the first respiratory movement (*Schwartz*). A fœtus, still within the unopened fœtal membranes, may make respiratory movements (*Vesalius*, 1542). If the exchange of gases be interrupted to a sufficient extent, dyspnœa and ultimately death of the fœtus may occur. If, however, the venous condition of the mother's blood develops very slowly, as in cases of quiet, slow death of the mother, the medulla oblongata of the fœtus may gradually die without any respiratory movement being discharged (§ 324, 5).

According to this view, the respiratory movements are due to the direct action of the dyspnœic blood upon the medulla oblongata. [The excitability of the respiratory centre is less in the fœtus than in the newly born, and it increases from day to day after birth. Among the causes of the diminished excitability are the small amount of O in fœtal blood, and the slow velocity of the circulation. If an inspiration is discharged in the fœtus, it is at once inhibited by fluid passing into the nostrils and inhibiting the act reflexly. The chief cause of the first respiration after birth, is undoubtedly the increasing venosity of the blood, and also the disappearance of the above named reflex inhibitory process.] Death of the mother acts like compression of the umbilical cord. In the former case, the maternal venous blood robs the fœtal blood of its O, so that death of the fœtus occurs more rapidly (*Zuntz*). If the mother be *rapidly* poisoned with CO (§ 17), the fœtus may live longer, as the CO-hæmoglobin of the maternal blood cannot take any O from the fœtal blood (§ 16—*Hogyes*). In slow poisoning the CO passes into the fœtal blood (*Grèhant and Quinquand*).

In many cases, especially in cases of very prolonged labor, the excitability of the respiratory centre may be so diminished, that after birth, the dyspnœic condition of the blood alone is not sufficient to excite respiration in a normal rhythmical manner. In such cases *stimulation* of the *skin* also acts, *e. g.*, partly by the cooling produced by the evaporation of the amniotic fluid from the skin. When air has entered the lungs by the first respiratory movements, the air within the lungs also excites the pulmonary branches of the vagus (*Pflüger*), and thus the respiratory centre is stimulated reflexly to increased activity. According to v. Preuschen's observations, stimulation of the cutaneous nerves is more effective than that of the pulmonary branches of the vagus. In animals which have been rendered apnœic by free ventilation of their lungs, respiratory movements may be discharged by strong cutaneous stimuli, *e. g.*, dashing on of cold water. The mechanical stimulation of the skin by

friction or sharp blows, or the application of a cold douche, excites the respiratory centre. When the placental circulation is intact, cutaneous stimuli do not discharge respiratory movements (*Zuntz and Cohnstein*), (**Artificial respiration**, § 134).

[**Action of Drugs on the Respiratory Centre.**—Ammonia, salts of zinc and copper, strychnin, atropin, duboisin, apomorphin, emetin, the digitalis group, and heat increase the rapidity and depth of the respirations, while they become frequent and shallower after the use of alcohol, opium, chloral, chloroform, physostigmin. The excitability of the centre is first increased and then diminished by caffein, nicotin, quinine, and saponin (*Brunton*).]|

369. CENTRE FOR THE INHIBITORY NERVES OF THE HEART—(CARDIO-INHIBITORY).—The fibres of the vagus, when moderately stimulated, diminish the action of the heart; when strongly stimulated, however, they arrest its action and cause it to stand still in diastole (§ 352, 7); they are supplied to the vagus through the spinal accessory nerve, and have their centre in the medulla oblongata (§ 353).

[Gaskell has shown that stimulation of the vagus not only influences the rhythm of the heart's action, but modifies the other functions of the cardiac muscle. **Stimulation of the vagus** influences (*a*) the *automatic rhythm, i. e.*, the rate at which the heart contracts automatically; (*b*) the *force* of the contractions, more especially the auricles, although in some animals, *e. g.*, the tortoise, the ventricles are not affected; (*c*) the *power of conduction, i. e.*, the capacity for conducting the muscular contractions. According to Gaskell, the vagus acts upon the rhythmical power of the muscular fibres of the heart.]

This centre may be excited **directly** in the medulla, and also **reflexly**, by stimulating certain afferent nerves.

Many observers assume that this centre is in a state of **tonic excitement**, *i. e.*, that there is a continuous, uninterrupted, regulating, and inhibitory action of this centre upon the heart through the fibres of the vagus. According to Bernstein, this tonic excitement is caused reflexly through the abdominal and cervical sympathetic.

I. Direct Stimulation of the Centre.—This centre may be stimulated **directly**, by the same stimuli that act upon the respiratory centre. (1) *Sudden anæmia* of the oblongata, ligature of both carotids or both subclavians, or decapitating a rabbit, the vagi alone being left undivided, cause slowing and even temporary arrest of the action of the heart. (2) Sudden *venous hyperæmia* acts in a similar manner, *e. g.*, by ligaturing all the veins returning from the head. (3) *Increased venosity* of the blood, produced either by direct cessation of the respirations (rabbit), or by forcing into the lungs a quantity of air containing much CO_2 (*Traube*). As the circulation in the placenta (the respiratory organ of the fœtus) is interfered with during severe labor, this sufficiently explains the enfeeblement of the action of the heart which occurs during protracted labor; it is due to stimulation of the central end of the vagus by the dyspnœic blood (*B. S. Schultze*). (4) At the moment the respiratory centre is excited, and an *inspiration* occurs, there is a variation in the inhibitory activity of the cardiac centre (*Donders, Pflüger, Frédéricq*—§ 74, *a*, 4). (5) The centre is excited by increased *blood pressure* within the cerebral arteries.

II. The centre may be excited **reflexly** by—(1) Stimulation of sensory nerves (*Lovén*). (2) Stimulation of the central end of one vagus, provided the other vagus is intact. (3) Stimulation of the sensory nerves of the intestines, by tapping upon the belly (Goltz's **tapping experiment**), whereby the action of the heart is arrested. Stimulation of the splanchnic directly (*Asp and Ludwig*), or of the abdominal or cervical sympathetic, produces the same result. Very strong stimulation of sensory nerves, however, arrests the above-named reflex effects upon the vagus (§ 361, 3).

Tapping Experiment.—Goltz's experiment succeeds at once, by tapping the intestines of a frog directly, say, with the handle of a scalpel, especially if the intestine has been exposed to the air for a short time, so as to become inflamed (*Tarchanoff*). Stimulation of the stomach of the dog causes slowing of the heart beat (*Sig. Mayer and Pribram*). [M'William finds that the action of the

heart of the **eel** may be arrested reflexly with very great facility. The reflex inhibition is obtained by slight stimulation of the gills (through the branchial nerves), the skin of the head and tail, and parietal peritoneum, by severe injury of almost any part of the animal, except the abdominal organs.]

[**Effect of Swallowing Fluids.**—Kronecker has shown that the act of swallowing interferes with or abolishes temporarily the cardio-inhibitory action of the vagus, so that the pulse rate is greatly accelerated. Merely sipping a wineglassful of water may raise the rate 30 per cent. Hence, sipping cold water acts as a powerful cardiac stimulant.]

According to Hering, the excitability of the cardio-inhibitory centre is diminished by vigorous artificial ventilation of the lungs with atmospheric air. At the same time, there is a considerable fall of the blood pressure (§ 352, 8, 4). In man, a vigorous expiration, owing to the increased intra-pulmonary pressure, causes an acceleration of the heart beat, which Sommerbrodt ascribes to a diminution of the activity of the vagi. At the same time the activity of the vasomotor centre is diminished (§ 60, 2).

Stimulation of the trunk of the vagus from the centre downward, along its whole course, and also of certain of its cardiac branches [inferior cardiac], causes the heart either to beat more slowly, or arrests its action in diastole. The result depends upon the strength of the stimulus employed; feeble stimuli slow the action of the heart, while strong stimuli **arrest it in diastole.** The frog's heart may be arrested by stimulating the fibres of the vagus upon the sinus venosus [or by stimulating the vagus in its course as in Fig. 468]. If *strong* stimuli be applied, either to the centre or to the course of the nerve, for a *long time*, the part stimulated becomes *fatigued* and the heart beats more rapidly in spite of the continued stimulation. If a part of the nerve lying nearer the heart be stimulated, inhibition of the heart's action is brought about, as the stimulus acts upon a fresh portion of nerve.

FIG. 468.



Beating of a frog's heart taken by means of a lever resting on the heart. The lowest curve shows when the vagus was stimulated and the consequent arrest of the heart beat (*Stirling*).

The following points have also been ascertained regarding the **stimulation of the inhibitory fibres**:—

1. The experiments of Lõwit on the frog's heart, confirmed by Heidenhain, showed that electrical and chemical stimulation of the vagus produce different results, as regards the extent of the ventricular systole, as well as the number of heart beats; the contractions either become smaller, or less frequent, or they become smaller and less frequent simultaneously. Strong stimuli cause, in addition, well-marked relaxation of the heart muscle during diastole.

2. In order to cause inhibition of the heart, a *continuous* stimulus is not necessary. A *rhythmically interrupted* moderate stimulus suffices (*v. Bezold*); 18 to 20 stimuli per second are required for mammals, and 2 to 3 per second for cold-blooded animals.

3. Donders, with Prahl and Nüel, observed that arrest of the heart's action did not take place immediately the stimulus was applied to the vagus; but about 1/6 of a second—**period of latent stimulation**—elapsed before the effect was produced on the heart.

4. If the heart be arrested by stimulation of the vagus, it can still contract, if it be excited *directly*, *e.g.*, by pricking it with a needle, when it executes a *single* contraction. [This holds good only for some animals, *e.g.*, frog, tortoise, birds and mammals. In fishes, only the ventricle responds to stimulation during marked inhibition; in the newt, only the bulbus arteriosus. In the newt's heart, the sinus, auricles, and ventricle are all inexcitable to direct stimulation during strong inhibition.]

5. According to A. B. Meyer, inhibitory fibres are present only in the *right* vagus in the **turtle.** It is usually stated that the *right* vagus is more effective than the left in other animals, *e, g.*, rabbit (*Masoin*); but this is subject to many exceptions (*Landois and Langendorff*). [In the **newt,** the right vagus acts more readily on the ventricle than on the other parts of the heart; *slight* stimulation of the right vagus can arrest the ventricle, while the sinus and auricles go on beating.]

6. The vagus has been compressed by the finger in the neck of man (*Czermak, Concato*); but this experiment is accompanied by danger, and ought not to be undertaken. The electrotonic condition of the vagus is stated in § 335, III.

7. Schiff found that stimulation of the vagus of the frog caused acceleration of the heart beat, when he displaced the blood of the heart with saline solution. If blood serum be supplied to the heart, the vagus retains its inhibitory action.

8. Many **soda salts** in a proper concentration arrest the inhibitory action of the vagus, while **potash salts** restore the inhibitory function of the vagi suspended by the soda salts. If, however, the soda or potash salts act too long upon the heart, they produce a condition in which, after the inhibitory function of the vagi is abolished, it is not again restored. The heart's action in this condition is usually arhythmical (*Löwit*).

9. If the **intracardial pressure** be greatly increased, so as to accelerate greatly the cardiac pulsations, the activity of the vagus is correspondingly diminished (*J. M. Ludwig and Luchsinger*).

[**Differences in Animals.**—Perhaps the most remarkable fact in connection with the influence of the vagus on the eel's heart and that of all other **fishes** examined, is, that vagus stimulation causes the sinus and auricle to be entirely inexcitable to direct stimulation during strong inhibition. Nerve stimulation has in this case the very peculiar effect of rendering the muscular tissue temporarily incapable of responding to even the strongest direct stimuli, *e.g.*, powerful induction shocks. This would appear to be decisive evidence that the vagus acts on **muscle** directly, and not simply on automatic motor ganglia, as was held according to the old view (*M' William*).]

Poisons.—*Muscarin* stimulates the terminations of the vagus in the heart, and causes the heart to stand still in diastole (*Schmiedeberg and Koppe*). [See p. 127 for Gaskell's views.] If *atropin* be applied in solution to the heart, this action is set aside, and the heart begins to beat again. [Atropin abolishes completely the inhibitory action of the vagus on the heart. If it be injected into the jugular vein of a rabbit, the pulse beats are increased 27 per cent., in the dog, they may be trebled, and in a man under its full influence the pulse beats may rise from 70 to 150 or more. After atropin, it is impossible to arrest the action of the heart by stimulation of the vagus, and in the frog this cannot be done even by stimulation of the inhibitory centre in the heart itself, so that atropin must be regarded as paralyzing the *intra-cardiac terminations* of the vagus.] *Digitalin* diminishes the number of heart beats by stimulating the cardio-inhibitory centre (vagus) in the medulla. Large doses diminish the excitability of the vagus centre, and increase at the same time the accelerating cardiac ganglia, so that the heart beats are thereby increased. In small doses, digitalin raises the blood pressure by stimulating the vasomotor centre and the elements of the vascular wall (*Klug*). *Nicotin* first excites the vagus, then rapidly paralyzes it. *Hydrocyanic acid* has the same effect (*Preyer*). *Atropin* (*v. Bezold*) and *curara* (large dose—*Cl. Bernard and Kölliker*) paralyze the vagi, and so does a very low temperature or high fever.

370. CENTRE FOR THE ACCELERATING CARDIAC NERVES.—Nervus Accelerans.—It is more than probable that a centre exists in the medulla oblongata, which sends *accelerating fibres* to the heart. These fibres pass from the medulla oblongata—but from which part thereof has not been exactly ascertained—through the spinal cord, and leave the cord through the rami communicantes of the lower cervical and upper six dorsal nerves (*Stricker*), to pass into the sympathetic nerve. Some of these fibres, issuing from the spinal cord, pass through the first thoracic sympathetic ganglion and the ring of Vieussens, to join the cardiac plexus (Figs. 469, 470). [These fibres, proceeding from the spinal cord, frequently accompany the nerve running along the vertebral artery], and they constitute the *Nervus accelerans cordis*. [Fig. 470 shows the accelerator fibres passing through the ganglion stellatum of the cat to join the cardiac plexus.] If the vagi of an animal be divided, stimulation of the medulla oblongata, of the lower end of the divided cervical spinal cord, even of the lower cervical ganglion, or of the upper dorsal ganglion of the sympathetic (*Gang. stellatum*), causes acceleration of the heart beats in the dog and rabbit, without the blood pressure undergoing any change (*Cl. Bernard, v. Bezold, Cyon*).

On stimulating the medulla oblongata, or the cervical portion of the spinal cord, the *vasomotor nerves* are, of course, simultaneously excited. The consequence is that the blood vessels, supplied by vasomotor nerves from the spot which is stimulated, contract, and the blood pressure is greatly increased. Again, a simple increase of the blood pressure accelerates the action of the heart; this experiment does not prove directly the existence of accelerating fibres lying in the upper part of the spinal cord. If, however, the splanchnic nerves be divided beforehand (when, as they supply the largest vasomotor area in the body, the result of their division is to cause a great fall of the blood pressure), then on stimulating the above-named parts, after this operation, the heart beats are still increased in number, so that this increase cannot be due to the increased blood pressure. Indirectly it may be shown, by dividing or extirpating all the nerves of the cardiac plexus, or at least all the nerves going to the heart, that stimulation of the medulla oblongata, or cervical part of the spinal cord, no longer causes an increased frequency of the heart's action to the same extent as before division of these nerves. The slightly increased frequency in this case is due to the increased blood pressure.

The accelerating centre is certainly not continually in a state of *tonic* excitement, as section of the accelerans nerve does not cause slowing of the action of the heart; the same is true of destruction of the medulla oblongata or of the cervical spinal cord. In the latter case, the splanchnic nerves must be divided beforehand, to avoid the slowing effect on the action of the heart produced by the great fall of the blood pressure consequent upon destruction of the cord, otherwise we might be apt to ascribe the result to the action of the accelerating centre, when it is in reality due to the diminished blood pressure (*Cyon*).

According to the results of the older observers (*v. Bezold and others*), some accelerating fibres run in the *cervical sympathetic*. A few fibres pass through the

FIG. 469.



FIG. 470.



FIG. 469.—Scheme of the course of the accelerans fibres. P, pons; MO, medulla oblongata; C, spinal cord; V, inhibitory centre for heart; A, accelerans centre; VAG., vagus; SL, superior; IL, inferior laryngeal; SC, superior, IC, inferior cardiac; H, heart; C, cerebral impulse; S, cervical sympathetic; *a*, *a*, accelerans fibres.

FIG. 470.—Cardiac plexus, and ganglion stellatum of the cat. R, right, L, left × 1½; 1, vagus; 2′, cervical sympathetic, and in the annulus of Vieussens; 2, communicating branches from the middle cervical ganglion and the ganglion stellatum; 2′, thoracic sympathetic; 3, recurrent laryngeal; 4, depressor nerve; 5, middle cervical ganglion; 5′, communication between 5 and the vagus; 6, ganglion stellatum (1st thoracic ganglion); 7, communicating branches with the vagus; 8, nervus accelerans, 8, 8′, 8″, roots of accelerans; 9, branch of the ganglion stellatum.

vagus to reach the heart (§ 352, 7), and when they are stimulated, either the heart beat is accelerated or the cardiac contractions strengthened (*Heidenhain and Lõwit*), or the latter alone occurs (*Pawlow*). The inhibitory fibres of the vagus lose their excitability more readily than the accelerating fibres, but the vagus fibres are more excitable than those of the accelerans.

Tarchanoff has described some very rare cases of individuals who, by a merely *voluntary effort*, and while at rest, the respirations remaining unaffected, could nearly double the number of their pulse beats.

Modifying Conditions.—When the peripheral end of the *nervus accelerans* is stimulated, a considerable time elapses before the effect upon the frequency of the heart takes place, *i.e.*, it has a

long latent period. Further, the acceleration thus produced disappears gradually. If the **vagus** and **accelerans** fibres be stimulated **simultaneously**, only the inhibitory action of the vagus is manifested. If, *while the accelerans* is being stimulated, the vagus be suddenly excited, there is a prompt diminution in the number of the heart beats; and if the stimulation of the vagus is stopped, the accelerating effect of the accelerans is again rapidly manifested (*C. Ludwig with Schmiedeberg, Bowditch, Baxt*). According to the experiments of Stricker and Wagner on dogs, with both vagi divided, a diminution of the number of the heart beats occurred when both accelerantes were divided. This would indicate a tonic innervation of the latter nerves.

[**Accelerans in the Frog.**—Gaskell showed that stimulation of the vagus might produce two opposing effects; the one of the nature of inhibition, the other of augmentation. In the **crocodile,** the accelerans fibres leave the sympathetic chain at the large ganglion corresponding to the ganglion stellatum of the dog, and run along the vertebral artery up to the superior vena cava, and, after anastomosing with branches of the vagus, pass to the heart. "Stimulation of these fibres increases the *rate* of the cardiac rhythm, and augments the *force* of auricular contractions; while stimulation of the vagus slows the rhythm, and diminishes the strength of the auricular contractions." The *strength* of the *ventricular* contraction, both in the tortoise and crocodile, does not seem to be influenced by stimulation of the vagus, and probably also it is unaffected by the sympathetic. The so-called vagus of the frog, in reality, consists of pure vagus fibres and sympathetic fibres, and is in fact a vago-sympathetic. Gaskell finds that *stimulation of the sympathetic,* before it joins the combined ganglion of the sympathetic and vagus, produces *purely augmentor* or accelerating effects; while *stimulation of the vagus,* before it enters the ganglion, produces purely *inhibitory* effects. The two sets of fibres are quite distinct, so that in the **frog,** the sympathetic is a purely augmentor (accelerator), and the vagus a purely inhibitory nerve. Acceleration is merely one of the effects produced by stimulation of these nerves; hence, Gaskell suggests that they ought to be called "**augmentor,**" or simply cardiac sympathetic nerves.]

[In his more recent researches Gaskell asserts that vagus stimulation produces *first* an inhibitory or depressing effect, but that it ultimately improves the condition of the heart as regards force, rate, or regularity—one or all of these. He regards it as a true **anabolic nerve** (§ 342, **d**).]

371. VASOMOTOR CENTRE AND VASOMOTOR NERVES.—Vasomotor Centre.—The chief dominating or **general centre,** which supplies all the **non-striped muscles** of the arterial system with *motor* nerves (**vasomotor,** vaso-constrictor, vaso-hypertonic nerves), lies in the medulla oblongata, at a point which contains many ganglionic cells (*Ludwig and Thiry*). Those nerves which pass to the blood vessels are known as **vasomotor nerves.** The centre (which is 3 millimetres long and 1½ millimetre broad in the rabbit) reaches from the region of the upper part of the floor of the medulla oblongata to within 4 to 5 mm. of the calamus scriptorius. Each half of the body has its own centre, placed 2½ millimetres from the middle line on its own side, in that part of the medulla oblongata which represents the upward continuation of the lateral columns of the spinal cord; according to Ludwig, Owsjannikow, and Dittmar, in the lower part of the superior olives. **Stimulation** of this central area causes contraction of all the arteries, and, in consequence, there is great increase of the arterial blood pressure, resulting in swelling of the veins and heart. **Paralysis** of this centre causes relaxation and dilatation of all the arteries, and consequently there is an enormous fall of the blood pressere. Under ordinary circumstances, the vasomotor centre is in a condition of *moderate tonic* excitement (§ 366). Just as in the case of the cardiac and respiratory centres, the vasomotor centre may be excited directly and reflexly.

[**Position—How ascertained.**—As stimulation of the *central* end of a sensory nerve, *e.g.*, the sciatic, in an animal under the influence of **curara,** causes a rise in the blood pressure, even after removal of the cerebrum, it is evident that

the centre is not in the cerebrum itself. For the effect of **chloral**, under the same conditions, see p. 724. By making a series of sections from above downward, it is found that this reflex effect is not affected until a short distance above the medulla oblongata is reached. If more and more of the medulla oblongata be removed from above downward, then the reflex rise of the blood pressure becomes less and less until, when the section is made 4 to 5 mm. above the calamus scriptorius, the effect ceases altogether. This is taken to be the lower limit of the *general* vasomotor centre. The bilateral centre corresponds to some large multipolar nerve cells, described by Clarke as the antero-lateral nucleus.]

I. Direct Stimulation of the Centre.—The *amount* and *quality* of the **gases** contained in the blood flowing through the medulla are of primary importance. In the condition of apnœa (§ 368, 1), the centre seems to be very slightly excited, as the blood pressure undergoes a considerable decrease. When the mixture of blood gases is such as exists under normal circumstances, the centre is in a state of moderate excitement, and running parallel with the respiratory movements are variations in the excitement of the centre (Traube-Hering curves—§ 85), these variations being indicated by the rise of the blood pressure. When the blood is highly venous, produced either by asphyxia or by the inspiration of air containing a large amount of CO_2, the centre is strongly excited, so that all the arteries of the body contract, while the venous system and the heart become distended with blood (*Thiry*). At the same time, the velocity of the blood stream is increased (*Heidenhain*). The same result is produced by ligature of both the carotid and subclavian arteries, thus causing sudden anæmia of the medulla oblongata; and, no doubt, also by the sudden stagnation of the blood in venous hyperæmia.

Emptiness of the Arteries after Death.—The venosity of the blood which occurs after death always produces an energetic stimulation of the vasomotor centre, in consequence of which the arteries are firmly contracted. The blood is thereby forced toward the capillaries and veins, and thus is explained the "emptiness of the arteries after death."

Effect on Hemorrhage.—Blood flows much more freely from large wounds, when the vasomotor centre is intact, than if it be destroyed (frog). As psychical excitement undoubtedly influences the vasomotor centre, we may thus explain the influence of psychical excitement (speaking, etc.) upon the cessation of hemorrhage. If the hemorrhage be severe, stimulation of the medulla oblongata, due to the anæmia, may ultimately cause constriction of the small arteries, and thus arrest the bleeding. Thus, surgeons are acquainted with the fact that dangerous hemorrhage is often arrested as soon as unconsciousness, due to cerebral anæmia, occurs. If the heart be ligatured in a frog, all the blood is ultimately forced into the veins, and this result is also due to the anæmic stimulation of the oblongata (*Goltz*). In *mammals*, when the heart is ligatured, the equilibration of the blood pressure between the arterial and venous systems takes place more slowly when the medulla oblongata is destroyed than when it is intact (*v. Bezold, Gscheidlen*).

[**Effect of Destruction of the Vasomotor Centre.**—If two frogs be pithed and their hearts exposed, and both be suspended, then the hearts of both will be found to beat rhythmically and fill with blood. Destroy the medulla oblongata and spinal cord of one of them, then immediately in this case, the heart, although continuing to beat with an altered rhythm, ceases to be filled with blood; it appears collapsed, pale, and bloodless. There is a great accumulation of the blood in the abdominal organs and veins, and it is not returned to the heart, so that the arteries are empty. This experiment of Goltz is held to show the existence of *venous tonus* depending on a cerebro-spinal centre. If a limb of this frog be amputated, there is little or no hemorrhage, while in the other frog the hemorrhage is severe. The bearing of this experiment on conditions of "shock" is evident.]

Action of Poisons.—*Strychnin* stimulates the centre directly, even in curarized dogs, and so do *nicotin* and *Calabar bean*.

Direct Electrical Stimulation.—On stimulating the centre directly in animals, it is found that single induction shocks only become effective when they succeed each other at the rate of 2 to 3 shocks per second. Thus there is a "**summation**" of the single shocks. The maximum contraction of the arteries, as expressed by the maximum blood pressure, is reached when 10 to 12 *strong*, or 20 to 25 *moderately* strong shocks per second are applied (*Kronecker and Nicolaides*).

Course of the Vasomotor Nerves.—From the vasomotor centre fibres proceed directly through some of the cranial nerves to their area of distribution; through the trigeminus partly to

the interior of the **eye** (§ 347, I, 2), through the lingual and hypoglossal to the **tongue** (§ 347, III, 4), through the vagus to a limited extent to the **lungs** (§ 352, 8, 2), and to the **intestines** (§ 352, 11).

All the other vasomotor nerves descend into the lateral columns of the spinal cord (§ 364, 9); hence, stimulation of the lower cut end of the spinal cord causes contraction of the blood vessels supplied by the nerves below the point of section (*Pflüger*). In their course through the cord, these fibres form connections with the *subordinate vasomotor centres in the gray matter of the cord* (§ 362, 7), and then leave the cord either directly through the *anterior* roots of the spinal nerves to their areas of distribution, or pass through the rami communicantes into the sympathetic, and from them reach the blood vessels to which they are distributed (§ 356) [see Fig. 439].

The following is the arrangement of these nerves in the region of the **head**: The *cervical portion of the sympathetic* supplies the great majority of the blood vessels of the head (see *Sympathetic*, § 356, A, 3). In some animals, the *great auricular nerve* supplies a few vasomotor fibres to its own area of distribution (*Schiff, Lovèn, Moreau*). The vasomotor nerves to the **upper extremities** pass through the anterior roots of the middle dorsal nerves into the thoracic sympathetic, and upward to the 1st thoracic ganglion, and from thence through the rami communicantes to the brachial plexus (*Schiff, Cyon*). The skin of the **trunk** receives its vasomotor nerves through the dorsal and lumbar nerves. The vasomotor nerves to the **lower extremities** pass through the nerves of the lumbar and sacral plexuses into the sympathetic, and from thence to the lower limbs (*Pflüger, Schiff, Cl. Bernard*). The **lungs**, in addition to a few fibres through the vagus, are supplied from the cervical spinal cord through the 1st thoracic ganglion (*Brown-Séquard, Fick and Badoud, Lichtheim*). The **splanchnic** is the greatest vasomotor nerve in the body, and supplies the **abdominal viscera** (§ 356, B—*v. Bezold, Ludwig and Cyon*). The vasomotor nerves of the **liver** (§ 173, 6), **kidney** (§ 276), and **spleen** (§ 103) have been referred to already. According to Stricker, most of the vasomotor nerves leave the spinal cord between the 5th cervical and the 1st dorsal vertebræ. [Gaskell finds that in the dog (Fig. 439) they begin to leave the cord at the 2d dorsal nerve (§ 366).]

As a general rule, the blood vessels for the **skin** of the trunk and extremities are innervated from those nerves which give other fibres (*e. g.*, sensory) to those regions. The different vascular areas behave differently with regard to the intensity of the action of the vasomotor nerves. The most powerful vasomotor nerves are those that act upon the blood vessels of peripheral parts, *e. g.*, the toes, the fingers, and ears; while those that act upon central parts seem to be less active (*Lewaschew*), *e. g.*, on the pulmonic circulation (§ 88).

II. Reflex Stimulation of the Centre.—There are fibres contained in the different afferent nerves, whose stimulation affects the vasomotor centre. There are nerve fibres whose stimulation *excites* the vasomotor centre, thus causing a stronger contraction of the arteries, and consequently an increase of the arterial blood pressure. These are called "**pressor**" fibres. Conversely, there are other fibres whose stimulation reflexly diminishes the excitability of the vasomotor centre. These act as reflex inhibitory nerves on the centre, and are known as "**depressor**" fibres.

Pressor, or excito-vasomotor nerves, have already been referred to in connection with the superior and inferior laryngeal nerves (§ 352, 12, *a*,), in the trigeminus, which, when stimulated directly (§ 347), causes a pressor action, as well as when stimulating vapors are blown into the nostrils (*Hering and Kratschmer*). [The rise of the blood pressure in this case, however, is accompanied by a change in the character of the heart's beat and in the respirations. Rutherford has shown that in the rabbit the vapor of chloroform, ether, amyl nitrite, acetic acid, or ammonia held before the nose of a rabbit, greatly retards or even arrests the heart's action, and the same is true if the nostrils be closed by the hand. This arrest does not occur if the trachea be opened, and Rutherford regards the result as due not to the stimulation of the sensory fibres of the trigeminus, but to the *state of the blood* acting on the cardio-inhibitory nerve apparatus.] Hubert and Roever found pressor fibres in the cervical sympathetic; S. Mayer and Pribram found that mechanical stimulation of the stomach, especially of its serosa, caused pressor effects (§ 352, 12, *c*). According to Lovèn, the *first* effect of stimulating every sensory nerve is a pressor action.

[If a dog be poisoned with **curara**, and the *central* end of one sciatic nerve be stimulated, there is a great and steady rise of the blood pressure, chiefly owing to the contraction of the abdominal blood vessels, and at the same time there is no change in the heart beat. If, however, the animal be poisoned with **chloral**, there is a fall of the blood pressure resembling a depressor effect.]

O. Naumann found that **weak**, electrical stimulation of the skin caused at first contraction of the blood vessels, especially of the mesentery, lungs, and the web, with simultaneous excitement of the cardiac activity and acceleration of the circulation (frog). **Strong** stimuli, however, had an opposite effect, *i. e.*, a depressor effect, with simultaneous decrease of the cardiac activity. Grützner and Heidenhain found that **contact with the skin** caused a pressor effect, while painful impressions produced no effect. The application of **heat** and **cold** to the skin produces reflexly a change in the lumen of the blood vessels and in the cardiac activity (*Röhrig, Winternitz*). Pinching the skin causes contraction of the vessels of the pia mater of the rabbit (*Schüller*), and the same result was produced by a warm bath, while cold dilated the vessels. These results are due partly to pressor and partly to depressor effects, but the chief cause of the dilatation of the blood vessels is the increased blood pressure due to the cold constricting the cutaneous vessels. Heat, of course, has the opposite effect. In **man**, most stimuli applied to sensory nerves produce an effect: feeble cutaneous stimuli, tickling (even unpleasant odors, bitter or acid tastes, optical and acoustic stimuli) at the parts where they are applied, cause a fall of the cutaneous temperature, and diminution of the volume of the corresponding limb, sometimes increase of the general blood pressure and change of the heart beat. The opposite effects are produced by painful stimulation, the action of heat (and even by pleasant odors and sweet tastes). The former cause simultaneously dilatation of the cerebral vessels and increase the vascular contents of the skull—the latter cause the opposite results (*Istominow and Tarchanoff*).

Depressor fibres, *i, e.*, fibres whose stimulation diminishes the activity of the vasomotor centre, are present in many nerves. They are specially numerous in the *superior cardiac* branch of the vagus, which is known as the *depressor nerve* (§ 352, 6). The trunk of the vagus below the latter also contains depressor fibres (*v. Bezold*), as well as the pulmonary fibres (dog). The latter also act as depressors, during expiratory efforts (§ 74); while Hering found that inflating the lungs (to 50 mm. Hg pressure) caused a fall of the blood pressure (and also accelerated the heart beats—§ 369, II). Stimulation of the central end of sensory nerves, especially when it is intense and long continued, causes dilatation of the blood vessels in the area supplied by them (*Lovèn*). According to Latschenberger and Deahna, all sensory nerves contain both pressor and depressor fibres.

[If a rabbit be poisoned with curara, and the *central* end of the **great auricular nerve** be stimulated, there is a double effect—one local and the other general; the blood vessels throughout the body, but especially in the splanchnic area, contract, so that there is a general rise of the blood pressure, while the blood vessels of the ear are dilated. If the central end of the **tibial nerve** be stimulated, there is a rise of the general blood pressure, but a local dilatation of the saphena artery in the limb of that side (*Lovèn*). Again, the temperature of one hand and the condition of its blood vessels influence that of the other. If one hand be dipped in cold water, the temperature of the other hand falls. Thus, pressor and depressor effects may be obtained from the same nerve. The vasomotor centre, therefore, primarily regulates the condition of the blood vessels, but through them it obtains its importance by regulating and controlling the *blood supply* according to the needs of an organ.]

The central artery of a rabbit's ear contracts regularly and rhythmically 3 to 5 times per minute. Schiff observed that stimulation of sensory nerves caused a dilatation of the artery, which was preceded by a slight temporary constriction.

Depressor effects are produced in the area of an artery on which direct pressure is made, as occurs, for example, when the sphygmograph is applied for a long time—the pulse curves become larger, and there are signs of diminished arterial tension (§ 75).

Rhythmical Contraction of Arteries.—In the intact body slow alternating contraction and dilatation, without a uniform rhythm, have been observed in the arteries of the ear of the rabbit, the membrane of a bat's wing, and the web of a frog's foot. This arrangement, observed by Schiff, supplies more or less blood to the parts according to the action of external conditions. It has been called a "**periodic regulatory vascular movement.**" This movement may be useful when a vessel is occluded, as after ligature, and may help to establish more rapidly the collateral circulation. Stefani has shown that this occurs with more difficulty after section of the nerves.

Direct local applications may influence the lumen of the blood vessels; **cold** and **moderate electrical stimuli** cause **contraction**; while, conversely, **heat** and **strong mechanical** or **electrical stimuli** cause **dilatation**, although with the last two there is usually a preliminary constriction.

Poisons.—Almost all the digitalis group of substances cause constriction; quinine and salicin constrict the splenic vessels. The other febrifuges dilate the vessels (*Thomson*). See p. 138.

Effect on Temperature.—The vasomotor nerves influence the temperature, not only of individual parts, but of the whole body.

1. **Local Effects.—Section** of a peripheral vasomotor nerve, *e. g.*, the **cervical sympathetic,** is followed by dilatation of the blood vessels of the parts supplied by it (such as the ear of the rabbit), the intra-arterial pressure dilating the paralyzed walls of the vessels. Much arterial blood, therefore, passes into and causes *congestion* and redness of the parts, or hyperæmia, while, at the same time, the *temperature* is increased. There is also increased transudation through the dilated capillaries within the dilated areas; the velocity of the blood stream is of course diminished, and the blood pressure increased. The pulse is also felt more easily, because the blood vessels are dilated. Owing to the increase of the blood stream, the blood may flow from the veins almost arterial (bright red) in its characters, and the pulse may even be propagated into the veins, so that the blood spouts from them (*Cl. Bernard*). **Stimulation** of the peripheral end of a vasomotor nerve causes the opposite results—pallor, owing to contraction of the vessels, diminished transudation, and fall of the temperature on the surface. The smaller arteries may contract so much that their lumen is almost obliterated. Continued stimulation ultimately exhausts the nerve, and causes at the same time the phenomena of paralysis of the vascular wall.

Secondary Results.—The immediate results of paralysis of the vasomotor nerves lead to other effects; the paralysis of the muscles of the blood vessels must lead to congestion of the blood in the part; the blood moves more slowly, so that the parts in contact with the air cool more easily, and hence the first stage of *increase* of the temperature may be followed by a *fall* of the temperature. The ear of a rabbit with the sympathetic divided, after several weeks becomes cooler than the ear on the sound one. If in man the motor muscular nerves, as well as the vasomotor fibres, are paralyzed, then the paralyzed limb becomes cooler, because the paralyzed muscles no longer contract to aid in the production of heat (§ 338), and also because the dilatation of the muscular arteries, which accompanies a muscular contraction, is absent. Should atrophy of the paralyzed muscles set in, the blood vessels also become smaller. Hence, paralyzed limbs in man generally become cooler as time goes on. The *primary* effect, however, in a limb, *e. g.*, after section of the sciatic or lesion of the brachial plexus, is an increase of the temperature.

If, at the same time, the vasomotor nerves of a large area of the skin be paralyzed, *e. g.*, the lower half of the body after section of the spinal cord, then so much heat is given off from the dilated blood vessels that, either the warming of the skin lasts for a very short time and to a slight degree, or there may be cooling at once. Some observers (*Tschetschichin, Naunyn, Quincke*) observed a rise of the temperature after section of the cervical spinal cord, but Riegel did not observe this increase.

2. **Effect on the Temperature of the Body.**—Stimulation or paralysis of the vasomotor nerves of a *small* area has practically no effect on the general temperature of the body. If, however, the vasomotor nerves of a *considerable area* of the skin be suddenly paralyzed, then the temperature of the entire body falls, because more heat is given off from the dilated vessels than under normal circumstances. This occurs when the spinal cord is divided high up in the neck. The inhalation of a few drops of amyl nitrite, which dilates the blood vessels of the skin, causes a fall of the temperature (*Sassetki and Manassein*). Conversely, stimulation of the vasomotor nerves of a large area increases the temperature, because the constricted vessels give off less heat. The temperature in fever may be partly explained in this way (§ 220, 4).

The **activity of the heart,** *i. e.*, the number and energy of the cardiac contractions, is influenced by the condition of the vasomotor nerves. When a large vasomotor area is paralyzed, the blood channels are dilated, so that the blood does not flow to the heart at the usual rate and in the usual amount, as the pressure is considerably diminished. Hence, the heart executes extremely small and feeble contractions. Stricker observed that the heart of a dog ceased to beat on extirpating the spinal cord from the 1st cervical to the 8th dorsal vertebra. Conversely,

we know that stimulation of a large vasomotor area, by constricting the blood vessels, raises the arterial blood pressure considerably. As the arterial pressure affects the pressure within the left ventricle, it may act as a mechanical stimulus to the cardiac wall, and increase the cardiac contractions both in number and strength. Hence, the circulation is accelerated (*Heidenhain, Slavjansky*).

Splanchnic.—By far the largest vasomotor area in the body is that controlled by the splanchnic nerves, as they supply the blood vessels of the abdomen (§ 161); hence, stimulation of their peripheral ends is followed by a great rise of the blood pressure. When they are divided, there is such a fall of the blood pressure that other parts of the body become more or less anæmic, and the animal may even die from "being bled into its own belly," *i. e.*, from what has been called "**intra-vascular hemorrhage.**" Animals whose portal vein is ligatured die for the same reason (*C. Ludwig and Thiry*) [see § 87]. The capacity of the vascular system, depending as it does in part upon the condition of the vasomotor nerves, influences the *body weight*. Stimulation of certain vascular areas may cause the rapid excretion of water, and we may thus account in part for the diminution of the body weight, which has been sometimes observed after an epileptic attack terminating with polyuria.

Trophic disturbances sometimes occur after affections of the vasomotor nerves (§ 342, I, *c*). Paralysis of the vasomotor nerves not only causes dilatation of the blood vessels and local increase of the blood pressure, but it may also cause increased transudation through the capillaries [§ 203]. When the active contraction of the muscles is abolished, the blood stream at the same time becomes slower, and in some cases, the skin becomes livid, owing to the venous congestion. There is a diminution of the normal transpiration, and the epidermis may be dry and peel off in scales. The growth of the hair and nails may be affected by the congestion of blood, and other tissues may also suffer.

Vasomotor Centres in the Spinal Cord.—Besides the dominating centre in the medulla oblongata, the blood vessels are acted upon by *local* or *subordinate vasomotor centres in the gray matter of the spinal cord*, as is proved by the following observations: If the spinal cord of an animal be divided, then all the blood vessels supplied by vasomotor nerves below the point of section are paralyzed, as the vasomotor fibres proceed from the medulla oblongata. If the animal lives, the blood vessels regain their tone and their former calibre, while the rhythmical movements of their muscular walls are ascribed to the subordinate centres in the lower part of the spinal cord (*Lister, Goltz*—§ 362, 7).

The **subordinate spinal centres** may, further, be stimulated **directly** by dyspnœic blood, and also **reflexly**, in the rabbit and frog (*Ustimowitsch*). After destruction of the medulla oblongata, the arteries of the frog's web still contract reflexly when the sensory nerves of the hind leg are stimulated (*Putnam, Nussbaum, Vulpian*). In the dog, opposite the 3d to 6th dorsal nerve is a spinal vasomotor centre (origin of the splanchnic), which can be excited reflexly (*Smirnow*), and there is a similar one in the lower part of the spinal cord (*Vulpian*).

If the lower divided part of the cord be *crushed*, the blood vessels again dilate, owing to the destruction of the subordinate centres. In animals which survive this operation, the vessels of the paralyzed parts gradually recover their normal diameter and rhythmical movements. This effect is ascribed to *ganglia* which are supposed to exist along the course of the vessels. [It is to be recollected that the existence of these peripheral nervous mechanisms has not been proved.] These ganglia [or peripheral nervous mechanisms] might be compared to the ganglia of the heart, and seem by themselves capable of sustaining the movements of the vascular wall. Even the blood vessels of an excised kidney exhibit periodic variations of their calibre (*C. Ludwig and Mosso*). It is important to observe that the walls of the blood vessels contract as soon as the blood becomes highly *venous*. Hence, the blood vessels offer a greater resistance to the passage of venous than of arterial blood (*C. Ludwig*). Nevertheless, the blood vessels, although they recover part of their tone and mobility, never do so *completely*.

The effects of direct mechanical, chemical, and electrical stimuli on blood vessels may be due to their action on these peripheral nervous mechanisms. The arteries may contract so much as almost to disappear, but sometimes dilatation follows the primary stimulus.

Lewaschew found that limbs in which the vasomotor fibres had undergone degeneration reacted like intact limbs to variations of temperature; heat relaxed the vessels, and cold contracted them. It is, however, doubtful if the variations of the vascular lumen depend upon the stimulation of the peripheral nervous mechanisms. Amyl nitrite and digitalis are supposed to act on those hypothetical mechanisms.

The *pulsating veins* in the bat's wing still continue to beat after section of all their nerves, which is in favor of the existence of local nervous mechanisms (*Luchsinger, Schiff*).

Influence of the Cerebrum.—The cerebrum influences the vasomotor centre, as is proved by the sudden pallor that accompanies some psychical conditions, such as fright or terror. There is a centre in the gray matter of the cerebrum where stimulation causes cooling of the opposite side of the body.

Although there is one general vasomotor centre in the medulla oblongata, which influences *all* the blood vessels of the body, it is really a *complex composite* centre, consisting of a *number* of closely aggregated centres, each of which presides over a particular vascular area. We know something, *e. g.*, of the *hepatic* (§ 175) and *renal* centres (§ 276).

Many **poisons** *excite* the vasomotor nerves, such as ergotin, tannic acid, copaiba, and cubebs; others *first excite*, and then *paralyze*, *e. g.*, chloral hydrate, morphia, laudanosin, veratrin, nicotin, Calabar bean, alcohol; others rapidly *paralyze* them, *e. g.*, amyl nitrite, CO (§ 17), atropin, muscarin. The paralytic action of the poison is proved by the fact that, after section of the vagi and accelerantes, neither the pressor nor the depressor nerves, when stimulated, produce any effect. Many pathological infective agents affect the vasomotor nerves.

The **veins** are also influenced by vasomotor nerves, and so are the **lymphatics**, but we know very little about this condition.

Pathological.—The **angio-neuroses**, or nervous affections of blood vessels, form a most important group of diseases. The parts primarily affected may be either the peripheral nervous mechanisms, the subordinate centres in the cord, the dominating centre in the medulla, or the gray matter of the cerebrum. The effect may be direct or reflex. The dilatation of the vessels may also be due to stimulation of vaso-dilator nerves, and the physician must be careful to distinguish whether the result is due to paralysis of the vaso-constrictor nerves or stimulation of the vaso-dilator fibres.

Angio-neuroses of the skin occur in affections of the vasomotor nerves, either as a **diffuse** redness or pallor; or there may be **circumscribed** affections. Sometimes, owing to the stimulation of individual vasomotor nerves, there are local cutaneous arterio-spasms (*Nothnagel*). In certain acute febrile attacks—after previous initial violent stimulation of the vasomotor nerves, especially during the cold stage of fever—there may be different forms of paralytic phenomena of the cutaneous vessels. In some cases of epilepsy in man, Trousseau observed irregular, red, angio-paralytic patches (**ataches cérébrales**). Continued strong stimulation may lead to interruption of the circulation, which may result in gangrene of the skin and deeper-seated parts (*Weiss*).

Hemicrania, due to unilateral spasm of the branches of the carotid on the head, is accompanied by severe headache (*Du Bois-Reymond*). The cervical sympathetic nerve is intensely stimulated—a pale, collapsed, and cool side of the face, contraction of the temporal artery like a firm whipcord, dilatation of the pupil, secretion of thick saliva, are sure signs of this affection. This form may be followed by the opposite condition of paralysis of the cervical sympathetic, where the effects are reversed. Sometimes the two conditions may alternate.

Basedow's disease is a remarkable condition, in which the vasomotor nerves are concerned; the heart beats very rapidly (90 to 129–200 beats per minute), causing palpitation; there is swelling of the thyroid gland (**struma**), and projection of the eyeballs (**exophthalmos**), with imperfectly coördinated movements of the upper eyelid, whereby the plane of vision is raised or lowered. Perhaps in this disease we have to deal with a simultaneous stimulation of the accelerans cordis (§ 370), the motor fibres of Müller's muscles of the orbit and eyelids (§ 347, I), as well as of the vaso-dilators of the thyroid gland. The disease may be due to direct stimulation of the sympathetic channels or their spinal origins, or it may be referred to some reflex cause. It has also been explained, however, thus, that the exophthalmos and struma are the consequence of vasomotor paralysis, which results in enlargement of the blood vessels, while the increased cardiac action is a sign of the diminished or arrested inhibitory action of the vagus. All these phenomena may be caused, according to Filehne, by injury to the upper part of both restiform bodies in rabbits.

Visceral Angio-neuroses.—The occurrence of sudden hyperæmia, with transudations and ecchymoses in some thoracic or abdominal organs may have a neurotic basis. As already mentioned, injury to the pons, corpus striatum, and optic thalamus may give rise to hyperæmia, and

ecchymoses in the lungs, pleuræ, intestines and kidneys. According to Brown-Séquard, compression or section of one-half of the pons causes ecchymoses, especially in the lung of the opposite side; he also observed ecchymoses in the renal capsule after injury of the lumbar portion of the spinal cord (§ 379).

The dependence of **diabetes mellitus** upon injury to the vasomotor nerves is referred to in § 175; the action of the vasomotor nerves on the **secretion of urine** in § 276; and **fever** in § 220.

372. **VASO-DILATOR CENTRE AND NERVES.**—Although a **vaso-dilator centre** has not been definitely proved to exist in the medulla, still its existence there has been surmised. Its action is opposite to that of the vasomotor centre. The centre is certainly not in a continuous or tonic state of excitement. The vaso-dilator nerves behave in their functions similarly to the cardiac branches of the vagus; both, when stimulated, cause relaxation and rest (*Schiff, Cl. Bernard*). Hence, these nerves have been called *vaso-inhibitory*, vaso-hypotonic, or **vaso-dilator nerves.** Dyspnœic blood stimulates this centre as well as the vasomotor centre, so that the cutaneous vessels are dilated, while simultaneously the vessels of the internal organs are contracted and the organs anæmic, owing to the stimulation of their vasomotor centre (*Dastre and Morat*). Nicotin is a powerful excitant of the vaso-dilator nerves (*Ostroumoff*): it raises the temperature of the foot (dog), and increases the formation of lymph (*Rogowicz*).

[The **existence of vaso-dilator nerves** is assumed in accordance with such facts as the following: If the **chorda tympani** be divided, there is no change in the blood vessels of the submaxillary gland; but if its *peripheral* end be stimulated, in addition to other results, (§ 145), there is dilatation of the blood vessels of the submaxillary gland, so that its veins discharge bright florid blood, while they spout like an artery. Similarly, if the **nervi erigentes** be divided, there is no effect on the blood vessels of the penis (§ 362, 4); but if their *peripheral* ends be stimulated with Faradic electricity, the sinuses of the corpora cavernosa dilate, become filled with blood, and erection takes place (§ 436). Other examples in **muscle** and elsewhere are referred to below.]

Course of the Vaso-dilator Nerves.—To some organs they pass as special nerves—to other parts of the body, however, they proceed along with the vasomotor and other nerves. According to Dastre and Morat, the vaso-dilator nerves for the **bucco-labial region** (dog) pass out from the cord by the 1st to the 3d dorsal nerves, and go through the rami communicantes into the sympathetic, then to the superior cervical ganglion, and lastly through the carotid and inter-carotid plexus into the trigeminus. [The fibres occur in the posterior segment of the ring of Vieussens, and if they be stimulated there is dilatation of the vessels in the lip and cheek on that side (p. 673).] The maxillary branch of the trigeminus, however, also contains vaso-dilator fibres proper to itself (*Laffont*). In the gray matter of the cord, there is a special subordinate centre for the vaso-dilator fibres of the bucco-labial region. This centre may be acted on reflexly by stimulation of the vagus, especially its pulmonary branches, and even by stimulating the sciatic nerve. The **ear** receives its nerves from the 1st dorsal and lowest cervical ganglion, the **upper limb** from the thoracic portion, and the **lower limb** from the abdominal portion of the sympathetic. The vaso-dilator fibres run to the **submaxillary and sublingual glands** in the **chorda tympani** (§ 349, 4), while those for the posterior part of the **tongue** run in the glosso-pharyngeal nerve (§ 351, 4—*Vulpian*). Perhaps the vagus contains those for the **kidneys** (§ 276). *Stimulation* of the **nervi erigentes** proceeding from the sacral plexus causes dilatation of the arteries of the **penis**, together with congestion of the corpora cavernosa (§ 436) (*Eckhard, Lovèn*). Eckhard found that erection of the penis can be produced by stimulation of the spinal cord and of the pons as far as the peduncles, which may explain the phenomenon of priapism in connection with pathological irritations in these regions. The **muscles** receive the vaso-dilator fibres for their vessels through the trunks of the motor nerves. *Stimulation of a motor* nerve or the spinal cord causes not only contraction of the corresponding muscles, but also dilatation of their blood vessels (§ 294, II—*C. Ludwig and Sczelkow, Hafiz, Gaskell*)—the dilatation of the vessels taking place even when the muscle is prevented from shortening. [Gaskell observed under the microscope the dilatation produced by stimulation of the nerve to the mylo-hyoid muscle of the frog.] The vaso-dilators remain medullated up to their terminal ganglion (*Gaskell*).

The **vaso-dilators** (like the vasomotors, p. 727) also have **subordinate centres** in the **spinal cord**; *e. g.*, the fibres of the labio-buccal region at the

1st to 3d dorsal vertebræ. This centre may be influenced reflexly through the pulmonary fibres of the vagus, and also through the sciatic (*Laffont, Smirnow*). According to Holtz, a similar centre lies in the lowest part of the cord.

Goltz showed that, in the **nerves to the limbs** (*e.g.*, in the sciatic nerve), the vasomotor and vaso-dilator fibres lie side by side in the same nerve. If the peripheral end of this nerve be stimulated immediately after it is divided, the action of the vaso-constrictor fibres overcomes that of the dilators. If the peripheral end be stimulated 4 to 6 days after the section, when the vaso-constrictors have lost their excitability, the blood vessels dilate under the action of the vaso-dilator fibres. *Stimuli which are applied at long intervals to the nerve act especially on the vaso-dilator fibres; while tetanizing stimuli act on the vasomotors. The latent period of the vaso-dilators is longer, and they are more easily exhausted than the vasomotors* (*Bowditch and Warren*). The sciatic nerve receives both kinds of fibres from the sympathetic. It is assumed that the peripheral nervous mechanisms in connection with the blood vessels are influenced by both kinds of vascular nerves; the vasomotors (constrictors) increase, while the vaso-dilators diminish the activity of these mechanisms or ganglia. [It is, however, possible to explain their effects by supposing that they act directly upon the muscular fibres of the blood vessels without the intervention of any nervous ganglionic structures.]

[Section of the spinal cord high up in the neck causes, of course, a great fall of the blood pressure, owing to the division of the vasomotor nerves. In the dog the pressure may fall to 30–40 mm. Hg. After isolation of the cord, in rabbits alone, stimulation of the central end of a sensory nerve causes a rise of the blood pressure; in dogs, however, under the same conditions, the blood pressure *falls*. Dyspnœic blood also causes a rise of the blood pressure, which is preceded by a fall (*Ustimowitch*). This reflex fall of the blood pressure takes place after section of the splanchnics, and the nerves to the extremities, but it does not take place if the spinal cord be divided at the lumbar or lower dorsal region. If the cord be divided in the lower dorsal region, stimulation of the brachial plexus has no effect, while the fall occurs after stimulation of the central end of the sciatic. These experiments indicate that the vaso-dilator nerves which cause the fall of the blood pressure arise in the lower part of the spinal cord (lumbar), and that they are probably contained in the visceral nerves and not in those for the extremities (*Thayer and Pal*).]

In the muscles of the face, paralyzed by extirpation of the facial nerve, stimulation of the ring of Vieussens causes **pseudo-motor** contractions of these muscles, just as stimulation of the chorda tympani causes such contractions in the paralyzed tongue (§ 349, 4), after section of the hypoglossal nerve (*Rogowicz*).

In analyzing the vascular phenomena resulting from experiments on these nerves, we must be very careful to determine whether the dilatation is the result of *stimulation of the vaso-dilators*, or a consequence of paralysis of the vaso-constrictors. *Psychical* conditions act upon the vaso-dilator nerves—the blush of shame, which is not confined to the face, but may even extend over the whole skin, is probably due to stimulation of the vaso-dilator centre.

Influence on Temperature.—The vaso-dilator nerves obviously have a considerable influence on the *temperature* of the body and on the heat of the individual parts of the body. *Both* vascular centres must act as important regulatory mechanisms for the radiation of heat through the cutaneous vessels (§ 214, II). Probably they are kept in activity reflexly by sensory nerves. Disturbances in their function may lead to an abnormal accumulation of heat, as in fever (§ 220), or to abnormal cooling (§ 213, 7). Some observers, however, assume the existence of an intra-cranial "**heat-regulating centre**" (*Tschetschichin, Naunyn, Quincke*). According to Wood, separation of the medulla oblongata from the pons causes an increased radiation and a diminished production of heat, due to the cutting off of the influences from the heat-regulating centre (§ 377).

373. **SPASM CENTRE—SWEAT CENTRE.—Spasm Centre.**—In the medulla oblongata, just where it joins the pons, there is a centre, whose stimulation causes *general spasms*. The centre may be excited by suddenly producing a highly venous condition of the blood ("asphyxia spasms"), in cases of drowning in mammals (but not in frogs), sudden anæmia of the medulla oblongata, either in consequence of hemorrhage or ligature of both carotids and subclavians (*Kussmaul and Tenner*), and lastly, by sudden venous stagnation caused by compressing the veins coming from the head. In all these cases, the stimulation of the centre is due to the sudden *interruption of the normal exchange of the gases*. When these factors act quite gradually, death may take place without convulsions. Direct stimulation by means of *chemical* substances (ammonia carbonate,

potash, and soda salts, etc.), applied to the medulla, quickly causes general convulsions (*Papellier*). Intense direct *mechanical* stimulation of the medulla, as by its sudden destruction, causes general convulsions.

Position.—Nothnagel attempted by direct stimulation to map out the position of the spasm centre in rabbits; it extends from the area above the ala cinerea upward to the corpora quadrigemina. It is limited externally by the locus cœruleus and the tuberculum acusticum. In the frog. it lies in the lower half of the 4th ventricle (*Heubel*). The centre is affected in extensive reflex spasms (§ 364, 6), *e. g.*, in poisoning with strychnin and in hydrophobia.

Poisons.—Many inorganic and organic poisons, most cardiac poisons, nicotin, picrotoxin, ammonia (§ 277), and the compounds of barium cause death after producing convulsions, by acting on the spasm centre (*Röber, Heubel, Böhm*).

If the arteries going to the brain be ligatured so as to paralyze the medulla oblongata, then, on ligaturing the abdominal aorta, spasms of the lower limbs occur, owing to the anæmic stimulation of the motor ganglia of the spinal cord (*Sigm. Mayer*).

Pathological—Epilepsy.—Schroeder van der Kolk found the blood vessels of the oblongata dilated and increased in cases of epilepsy. Brown-Séquard observed that injury to the central or peripheral nervous system (spinal cord, oblongata, peduncle, corpora quadrigemina, sciatic nerve) of guinea pigs produced epilepsy, and this condition even became *hereditary*. Stimulation of the cheek or of the face "**epileptic zone**," on the same side as the injury (spinal cord), caused at once an attack of epilepsy; but when the peduncle was injured, the opposite side must be stimulated. Westphal made guinea pigs epileptic by repeated light blows on the skull, and this condition also became hereditary. In these cases, there was effusion of blood in the medulla oblongata and upper part of the spinal cord (§§ 375 and 378, 1). Direct stimulation of the cerebrum also produces epileptic convulsions. Strong electrical stimulation of the motor areas of the cortex cerebri is often followed by an epileptic attack (§ 375). [It is no unfrequent occurrence, while one is stimulating the motor areas of the cortex cerebri of a dog, to find the animal exhibiting symptoms of local or general epilepsy.]

Sweat Centre.—A **dominating centre** for the secretion of the sweat of the entire surface of the body (§ 289, II)—with subordinate spinal centres (§ 362, 8)—occurs in the medulla oblongata (*Adamkiewicz, Marmé, Nawrocki*). It is double, and in rare cases the excitability is unequal on the two sides, as is manifested by unilateral perspiration (§ 289, 2).

Poisons.—Calabar bean, nicotin, picrotoxin, camphor, and ammonium acetate, cause a secretion of sweat by acting directly on the sweat-centre. Muscarin causes local stimulation of the peripheral sweat fibres—it causes sweating of the hind limbs after section of the sciatic nerves. Atropin arrests the action of muscarin (*Ott, Wood, Field, Nawrocki*).

[**Regeneration of the Spinal Cord.**—In some animals, true nervous matter is reproduced after part of the spinal cord has been destroyed, at least this is so in tritons and lizards (*H. Müller*). In these animals, when the tail is removed, it is reproduced, and Müller found that a part of the spinal cord corresponding to the new part of the tail is reproduced. Morphologically, the elements were the same, but the spinal nerves were not reproduced, while physiologically, the new nerve substance was not functionally active; it corresponds, as it were, to a lower stage of development. According to Masius and Vanlair, an excised portion of the spinal cord of a frog is reproduced after six months; while Brown-Séquard maintains that reunion of the divided surfaces of the cord takes place in pigeons after six to fifteen months. A partial reunion is asserted to occur in dogs by Dentan, Naunyn and Eichhorst, although Schieferdecker obtained only negative results, the divided ends being united only by connective tissue (*Schwalbe*).]

374. **PSYCHICAL FUNCTIONS OF THE BRAIN.**—The hemispheres of the cerebrum are usually said to be the *seat of all the psychical activities*. Only when they are intact are the processes of thinking, feeling and willing possible. After they are destroyed, the organism comes to be like a complicated machine, and its whole activity is only the expression of the external and internal stimuli which act upon it. The psychical activities appear to be located in both hemispheres, so that after destruction of a considerable part of one of them, the other seems to act in place of the part destroyed. [Objection has been taken to the term the "seat of" the will and intelligence, and undoubtedly it is more consistent with what we know, or rather do *not* know, to say, that the existence of volition and intelligence is dependent on the connection of the cerebral cortex with the rest of the brain.]

[That a certain condition of the cerebral hemispheres is necessary for the manifestation of the intellectual faculties, is admitted on all hands; for, compression of the brain, *e. g.*, by a depressed fracture of the skull, and sudden cessation of the supply of blood to the brain, abolish consciousness. The intellectual faculties are affected by inflammation of the meninges involving the surface of the brain, the action of drugs affects the intellectual and other faculties; but while all this is admitted we cannot say precisely upon what parts of the brain ideation depends. The **pre-frontal area**, or the convolutions in front of the ascending frontal supplied by the anterior cerebral artery, are sometimes regarded as the anatomical substratum of certain mental acts. At any rate, electrical stimulation of these parts is not followed by muscular motion, and, according to Ferrier, if this region be extirpated in the monkey, there is no motor or sensory disturbance in this animal; it still exhibits emotional feeling, all its special senses remain, and the power of voluntary motion is retained; but, nevertheless, there is a decided alteration in the animal's character and behavior, so that it exhibits considerable psychological alterations, and, according to Ferrier, "it has lost to all appearance the faculty of attention and intelligent observation."]

Observations on Man.—Cases in which considerable *unilateral* lesions or destruction of one hemisphere have taken place, without the psychical activities *appearing* to suffer, sometimes occur. The following is a case communicated by Longet: A boy, 16 years of age, had his parietal bone fractured by a stone falling on it, so that part of the protruding brain matter had to be removed. On reapplying the bandages, more brain matter had to be removed. After 18 days he fell out of bed, and more brain matter protruded, which was removed. On the 35th day he got intoxicated, tore off the bandages, and with them a part of the brain matter. After his recovery, the boy still retained his intelligence, but he was hemiplegic. Even when *both* hemispheres are *moderately* destroyed, the intelligence *appears* to be intact; thus, Trousseau describes the case of an officer whose fore-brain was pierced transversely by a bullet. There was *scarcely* any appearance of his mental or bodily faculties being affected. In other cases, destruction of parts of the brain peculiarly alters the character. We must be extremely careful, however, in forming conclusions in all such cases [In the celebrated "**American crow-bar case**" recorded by Bigelow, a young man was hit by a bar of iron 1¼ inch in diameter, which traversed the anterior part of the left hemisphere, going clean out at the top of his head. This man lived for thirteen years without any permanent alterations of motor or sensory functions; but "the man's disposition and character were observed to have undergone a serious change. There were, however, some changes which might be referable to injury to the frontal region." In all cases it is most important to know both the exact *site* and the *extent* of the lesion. Ross points out that the characteristic features of lesions in the pre-frontal cortical region are affected by "psychical disturbances, consisting of dementia, apathy and somnolency."]

Imperfect development of the cerebrum.—**Microcephalia** and hydrocephalus yield every result between diminution of the psychical activities and idiocy. Extensive inflammation, degeneration, pressure, anæmia of the blood vessels and the actions of many poisons produce the same effect.

Flourens' Doctrine.—Flourens assumed that the **whole of the cerebrum** is concerned in *every* psychical process. From his experiments on pigeons, he concluded that, if a small part of the hemispheres remained intact, it was sufficient for the manifestation of the mental functions; just in proportion as the gray matter of the hemispheres is removed, *all* the functions of the cerebrum are enfeebled, and when all the gray matter is removed, all the functions are abolished. According to this view, neither the different faculties nor the different perceptions are localized in special areas. Goltz holds a somewhat similar view to that of Flourens. He assumes that if an uninjured part of the cerebrum remain it can to a certain extent perform the functions of the parts that have been removed. This Vulpian has called the law of "**functional substitution**" (loi de suppléance).

The **Phrenological doctrine** of Gall († 1828) and Spurzheim assumes that the different mental faculties are located in different parts of the brain, and it is assumed that a large development of a particular organ may be detected by examining the external configuration of the head (**Cranioscopy**).

Removal of the Cerebrum.—After the removal of both cerebral hemispheres, in most animals, every voluntary movement and all conscious impression and sensory perception entirely ceases. On the other hand, the whole mechanical movements and the maintenance of the equilibrium of the movements are retained. The **maintenance of the equilibrium** depends upon the mid-brain, and is regulated by important reflex channels (§ 379).

Sudden cessation of the circulation in the brain, *e.g.*, by decapitation, is followed at once by cessation of the mental faculties. When Hayem and Barrier perfused the blood of a horse through the carotids of a decapitated dog's head, the head showed signs of consciousness and will for 10 seconds, but not longer.

The **mid-brain** (corpora quadrigemina) is connected not only with the gray matter of the spinal cord and medulla oblongata, the seat of extensive reflex

mechanisms (§ 367), but it also receives fibres coming from the higher organs of sense, which also excite movements reflexly. The corpora quadrigemina are also supposed to contain a reflex inhibitory apparatus (§ 361, 2). The joint action of all these parts makes the corpora quadrigemina one of the most important organs for the harmonious execution of movements, and this even in a higher degree than the medulla oblongata itself (*Goltz*). Animals with their corpora quadrigemina intact retain the equilibrium of their bodies under the most varied conditions, but they lose this power as soon as the mid-brain is destroyed (*Goltz*). Christiani locates the coördinating centre for the change of place and the maintenance of the equilibrium, in mammals, in front of the inspiratory centre in the 3d ventricle (§ 368).

That **impressions from the skin and sense organs** are concerned in the **maintenance of the equilibrium**, is proved by the following facts: A frog without its cerebrum at once loses its power of balancing itself as soon as the skin is removed from its hind limbs. The action of impressions communicated through the eyes is proved by the difficulty or impossibility of maintaining the equilibrium in nystagmus (§ 350), and by the vertigo which often accompanies paralysis of the external ocular muscles. In persons whose cutaneous sensibility is diminished, the eyes are the chief organs for the maintenance of the equilibrium; they fall over when the eyes are closed. [This is well illustrated in cases of locomotor ataxia (p. 697).]

Frog.—A frog with its cerebrum removed retains its power of maintaining its equilibrium. It can sit, spring, or execute complicated coördinated movements when appropriate stimuli are applied; when placed on its back, it immediately turns into its normal position on its belly; if stimulated it gives one or two springs, and then comes to rest; when thrown into water, it swims to the margin of the vessel, and it may crawl up the side, and sit passive upon the edge of the vessel. When incited to move, it exhibits the most complete harmony and unity in all its movements. Unless it is stimulated, it never makes independent, voluntary, purposive movements. It sits in the same place continually as if in sleep, it takes no food, it has no feelings of hunger and thirst, it shows no symptoms of fear, and ultimately, if left alone, it becomes desiccated like a mummy on the spot where it sits. [If the flanks of such a frog be stroked, it croaks with the utmost regularity according to the number of times it is stroked. Langendorff has shown that a frog croaks under the same circumstances, when both optic nerves are divided. It seems to be influenced by light; for, if an object be placed in front of it so as to throw a strong shadow, then on stimulating the frog it will spring not against the object, *a*, but in the direction, *b* (Fig. 471). Steiner finds that if a glass plate be substituted for an opaque object like a book, the frog always jumps against this obstacle. Its **balancing** movements on a board are quite remarkable and acrobatic in character. If it be placed on a board, and the board gently inclined (Fig. 472), it does not fall off, as a frog with only its spinal cord will do, but as the board is inclined, so as to alter the animal's centre of gravity, it slowly crawls up the board until its equilibrium is restored. If the board be sloped as in Fig. 472, it will crawl up until it sits on the edge, and if the board be still further tilted, the frog will move as indicated in the figure. It only does so, however, when the board is inclined, and it rests as soon as its centre of gravity is restored. It responds to every stimulus, just like a complex machine, answering each stimulus with an appropriate action.]

FIG. 471.

Frog without its cerebrum avoiding an object placed in its path.

FIG. 472.

Frog without its cerebrum moving on an inclined board (*Goltz*).

A **pigeon** without its cerebral hemispheres behaves in a similar manner (Fig. 473). When undisturbed it sits continuously, *as if in sleep*, but when stimulated, it shows complete harmony of all its movements; it can walk, fly, perch, and balance its body. The sensory nerves and those of special sensation conduct impulses to the brain; they only discharge reflex movements, but they do not excite conscious impressions. Hence, the bird starts when a pistol is fired close to its ear; it closes its eyes when it is brought near a flame, and the pupils contract; it turns away its head when the vapor of ammonia is applied to its nostrils. All these impressions are not perceived as conscious perceptions. The perceptive faculties—the will and memory—are abolished; the animal never takes food or drinks spontaneously. But if food be placed at the back part of its throat it is swallowed [reflex act], and in this way the animal may be maintained alive for months (*Flourens*).

FIG. 473.

Pigeon with its cerebral hemispheres removed.

Fish appear to behave differently. A carp with its cerebrum removed (Fig. 483, VI, 1) can see and may even select its food, and seems to execute its movements voluntarily (*Steiner*, *Vulpian*).

Mammals (rabbit), owing to the great loss of blood consequent on removal of the cerebrum, are not well suited for experiments of this kind. Immediately after the operation they show great signs of muscular weakness. When they recover, they present the same general phenomena; only when they are stimulated they run, as it were, blindfolded against an obstacle. Vulpian observed a peculiar shriek or cry which such a rabbit makes under the circumstances. Sometimes even in man a peculiar cry is emitted in some cases of pressure or inflammation rendering the cerebral hemispheres inactive.

Observations on **somnambulists** show that in man, also, complete harmony of all movements may be retained, without the assistance of the will or conscious impressions and perceptions. As a matter of fact, many of our ordinary movements are accomplished without our being conscious of them. They take place under the guidance of the basal ganglia.

The degree of intelligence in the animal kingdom is in relation to the size of the cerebral hemispheres, in proportion to the mass of the other parts of the central nervous system. Taking the brain alone into consideration, we observe that those animals have the highest intelligence in which the cerebral hemispheres greatly exceed the mid-brain in weight. The mid-brain is represented by the optic lobes in the lower vertebrates, and by the corpora quadrigemina in the higher vertebrates. In Fig. 483, VI, represents the brain of a carp; V, of a frog; and IV, of a pigeon. In all these cases 1 indicates the cerebral hemispheres; 2, the optic lobes; 3, the cerebellum; and 4 the medulla oblongata. In the carp, the cerebral hemispheres are smaller than the optic lobes; in the frog, they exceed the latter in size. In the pigeon the cerebrum begins to project backward over the cerebellum. The degree of intelligence increases in these animals in this proportion. In the dog's brain (Fig. 483, II) the hemispheres completely cover the corpora quadrigemina, but the cerebellum still lies behind the cerebrum. In man the occipital lobes of the cerebrum completely overlap the cerebellum (Fig. 479). [The projection of the occipital lobes over the cerebellum is due to the development of the frontal lobes pushing backward the convolutions that lie behind them, and not entirely to increased development of the occipital lobes.]

Meynert's Theory.—According to Meynert, we may represent this relation in another way. As is known, fibres proceed downward from the cerebral hemispheres, through the crusta or basis of the cerebral peduncle. These fibres are separated from the upper fibres or tegmentum of the peduncle by the locus niger, the tegmentum being connected with the corpora quadrigemina and the optic thalamus. The larger, therefore, the cerebral hemispheres, the more numerous will be the fibres proceeding from it. In Fig. 461, II, is a transverse section of the posterior corpora quadrigemina, with the aqeduct of Sylvius and both cerebral peduncles of an adult man; *p*, *p*, is the crusta of each

peduncle, and above it lies the locus niger, *s*. Fig. 461, IV, shows the same parts in a monkey; III, in a dog; and V, in a guinea-pig. The crusta diminishes in the above series. There is a corresponding diminution of the cerebral hemispheres, and, at the same time, in the intelligence of the corresponding animals.

Sulci and Gyri.—The degree of intelligence also depends upon the number and depth of the convolutions. In the lowest vertebrates (fish, frog, bird) the furrows or sulci are absent (Fig. 461, IV, V, VI); in the rabbit there are two shallow furrows on each side (III). The dog has a completely furrowed cerebrum (I, II). Most remarkable is the complexity of the sulci and convolutions of the cerebrum of the elephant, one of the most intelligent of animals. Nevertheless, some very stupid animals, as the ox, have very complex convolutions.

The **absolute weight** of the brain cannot be taken as a guide to intelligence. The elephant has *absolutely* the heaviest brain, but man has *relatively* the heaviest brain. [We ought also to take into account the complexity of the convolutions and the depth of the gray matter, its vascularity, and the extent of anastomoses between its nerve cells.]

Time an Element in all Psychical Processes.—Every psychical process requires a certain time for its occurrence—a certain time always elapses between the application of the stimulus and the conscious reaction.

Nature of Stimulus.	Reaction Time.	Name of Observer.
Shock on left hand,	.12	Exner.
Shock on forehead,	.13	do.
Shock on toe of left foot,	.17	do.
Sudden noise,	.13	do.
Visual impressions of electric spark,	.15	do.
Hearing a sound,	.16	Donders.
Currrent to tongue causing taste,	.16	v. Vintschgau and Hönigschmied.
Saline taste,	.15	do.
Taste of sugar,	.16	do.
" acids,	.16	do.
" quinine,	.23	do.

Reaction Time.—This time is known as "*reaction time*," and is distinctly longer than the simple reflex time required for a reflex act. It can be measured by causing the person experimented on to indicate by means of an electrical signal the moment when the stimulus is applied. The reaction time consis's of the following events: (1) The *duration of perception, i. e.*, when we become conscious of the impression; (2) the duration of the time required to direct the *attention* to the impression, *i. e.*, the *duration of apperception;* and (3) the *duration of the voluntary impulse*, together with (4) the time required for conducting the impulse in the afferent nerves to the centre, and (5) the time for the impulse to travel outward in the motor nerves. If the signal be made with the hand, then the reaction time for the impression of *sound* is 0.136 to 0.167 second; for taste, 0.15 to 0.23; touch, 0.133 to 0.201 second (*Horsch, v. Vintschgau and Hönigschmied*); for olfactory impressions, which, of course, depend upon many conditions (the phase of respiration, current of air), 0.2 to 0.5 second. Intense stimulation, increased attention, practice, expectation, and knowledge of the kind of stimulants to be applied, all diminish the time. Tactile impressions are most rapidly perceived when they are applied to the most sensitive parts (*v. Vintschgau*). The time is increased with very strong stimuli, and when objects difficult to be distinguished are applied (*v. Helmholtz and Baxt*). The time required to direct the **attention** to a number consisting of 1 to 3 figures, Tigerstedt and Bergquist found to be 0.015 to 0.035 second. Alcohol and the anæsthetics alter the time; according to their degree of action they shorten or lengthen it (*Kraplin*). In order that two shocks applied after each other be distinguished as two distinct impressions, a certain interval must elapse between the two shocks—for the ear, 0·002 to 0·0075 second; for the eye, 0.044 to 0.47 second; for the finger, 0.277 second.

[**The Dilemma.**—When a person is experimented on, and he is not told whether the right or left side is to be stimulated, or what colored disc may be presented to the eye, then the time to respond correctly is longer.]

[**Drugs** and other conditions affect the reaction time. Ether and chloroform lengthen it, while alcohol does the same, but the person imagines he really reacts quicker. Noises also lengthen it.]

In **sleep** and **waking**, we observe the periodicity of the active and passive conditions of the brain. During sleep, there is diminished excitability of the whole nervous system, which is only partly due to the fatigue of afferent nerves, but is largely due to the condition of the central nervous system. During sleep, we require to apply strong stimuli to produce reflex acts. In the deepest sleep the

psychical or mental processes seem to be completely in abeyance, so that a person asleep might be compared to an animal with its cerebral hemispheres removed. Toward the approach of the period when a person is about to waken, psychical activity may manifest itself in the form of dreams, which differ, however, from normal mental processes. They consist either of impressions, where there is no objective cause (hallucinations), or of voluntary impulses which are not executed, or trains of thought where the reasoning and judging powers are disturbed. Often, especially near the time of waking, the actual stimuli may so act as to give rise to impressions which become mixed with the thoughts of a dream. The diminished activity of the heart (§ 70, 3, *c*), the respiration (§ 127, 4), the gastric and intestinal movements (§ 213, 4), the formation of heat (§ 216, 4), and the secretions point to a diminished excitability of the corresponding nerve centres, and the diminished reflex excitability to a corresponding condition of the spinal cord. The pupils are contracted during sleep, the deeper the latter is; so that in the deepest sleep they do not become contracted on the application of light. The pupils dilate when sensory or auditory stimuli are applied, and the lighter the sleep, the more is this the case; they are widest at the moments of awaking (*Plotke*). [Hughlings Jackson finds that the retina is more anæmic than in the waking state.] During sleep, there seems to be a condition of increased action of certain sphincter muscles—those for contracting the pupil and closing the eyelids (*Rosenbach*). The soundness of the sleep may be determined by the intensity of the sound required to waken a person. Kohlschütter found that at first sleep deepens very quickly, then more slowly, and the maximum is reached after one hour (according to Mönninghoff and Preisbergen after 1¼ hour); it then rapidly lightens, until several hours before waking it is very light. External or internal stimuli may suddenly diminish the depth of the sleep, but this may be followed again by deep sleep. The deeper the sleep, the longer it lasts. [Durham asserts that the brain is anæmic, that the arteries and veins of the pia mater are contracted during sleep and the brain smaller; but is this cause or effect?]

The **cause of sleep** is the using up of the potential energy, especially in the central nervous system, which renders a restitution of energy necessary. Perhaps the accumulation of the decomposition products of the nervous activity may also act as producers of sleep (? lactates—*Preyer*.) Sleep cannot be kept up for above a certain time, nor can it be interrupted voluntarily. Many narcotics rapidly produce sleep. [The "diastolic phase of cerebral activity," as sleep has been called, is largely dependent on the absence of stimuli. We must suppose that there are two factors, one central, represented by the excitability of the cerebrum, which will vary under different conditions, and the other external, represented by the impulses reaching the cerebrum through the different sense organs. We know that a tendency to sleep is favored by removal of external stimuli, by shutting the eyes, retiring to a quiet place, etc. The external sensory impressions, indeed, influence the whole metabolism. Strumpell describes the case of a boy whose sensory inlets were all paralyzed except one eye and one ear, and when these inlets were closed the boy fell asleep, showing how intimately the waking condition is bound up with sensory afferent impulses reaching the cerebral centres.]

[**Hypnotics**, such as opium, morphia, KBr, chloral, are drugs which induce sleep.]

Hypnotism, or Animal Magnetism.—[Most important observations on this subject were made by Braid of Manchester, whose results are confirmed by many of the recent re-discoveries of Weinhold, Heidenhain, and others.] Heidenhain assumes that the cause of this condition is due to an inhibition of the ganglionic cells of the cerebrum, produced by continuous feeble stimulation of the face (slightly stroking the skin or electrical applications), or of the optic nerve (as by gazing steadily at a small brilliant object), or of the auditory nerve (by uniform sounds); while sudden and strong stimulation of the same nerves, especially blowing upon the face, abolishes the condition. Berger attributes great importance [as did Carpenter and Braid long ago] to the psychological factor, whereby the attention was directed to a particular part of the body. The facility with which different persons become hypnotic varies very greatly. When the hypnotic condition has been produced a number of times, its subsequent occurrence is facilitated, *e. g.*, by merely pressing upon the brow, by placing the body passively in a certain position, or by stroking the skin. In some people the mere idea of the condition suffices. A hypnotized person is no longer able to open his eyelids when they are pressed together. This is followed by spasm of the apparatus for accommodation in the eye, the range of accommodation is diminished, and there may be deviation of the position of the eyeballs; then follow phenomena of stimulation of the sympathetic in the oblongata; dilatation of the fissure of the eyelids and the pupil, exophthalmos, and increase of the respiration and pulse. At a certain stage, there may be a great increase in the sensitiveness of the functions of the sense-organs, and also of the muscular sensibility. Afterward there may be analgesia of the part stroked, and loss of taste; the sense of temperature is lost less rapidly, and still later that of sight, of smell, and of hearing. Owing to the abolition or suspension of consciousness, stimuli applied to the sense organs do not produce conscious impressions or perceptions. But stimuli applied to the sense organs of a hypnotized person cause movements, which, however, are unconscious, although they stimulate voluntary acts. In persons with greatly increased reflex excitability, voluntary movements may excite reflex spasms; the person may be unable to coördinate his organs for speech.

Types.—According to Grützner, there are several forms of hypnotism: (1) *Passive sleep*, where words are still understood, which occurs especially in girls; (2) owing to the increased reflex excita-

bility of the striped muscles, certain *groups of muscles* may be contracted—a condition which may last for days, especially in strong people; at the same time ataxia may occur, and the muscles may fail to perform their functions (**artificial katalepsy**). During the stage of lethargy in hysterical persons, the tendon reflexes are absent often (*Charcot and Richer*); (3) *autonomy at call, i. e.*, the hypnotized person—in most cases the consciousness is still retained—obeys a command, in his condition of light sleep. When the hand is grasped or the head stroked, he executes involuntary movements—runs about, dances, rides on a stool, and the like; (4) *hallucinations* occur only in some individuals when they waken from a deep sleep, the hallucinations (usually consisting of the sensation of sparks of fire or odors) being very strong and well pronounced; (5) imitation is rare, ordinary movements, such as walking, are easily imitated, the finer movements occur rarely. The "**echo speech**" is produced by pressure upon the neck, speaking into the throat, or against the abdomen. Pressure over the right eyebrow often ushers in the speech. Color sensation is suspended by placing the warm hand on the eye, or by stroking the opposite side of the head (*Cohn*). Stroking the limbs in the reverse direction gradually removes the rigidity of the limbs and causes the person to waken. Blowing on a part does so at once. Insane persons can be hypnotized. Disagreeable results follow only when the condition is induced too often and too continuously.

Hypnotism in Animals.—A hen remains in a fixed position when an object is suddenly placed before its eyes, or when a straw is placed over its beak, or when the head of the animal is pressed on the ground and a chalk line made before its beak (Kircher's experimentum mirabile, 1644). [Langley has hypnotized a crocodile.] Birds, rabbits and frogs remain passive for a time after they have been gently stroked on the back. Crayfish stand on their head and claws (*Czermak*).

375. **STRUCTURE OF THE CEREBRUM—MOTOR CORTICAL CENTRES.**—[**Cerebral Convolution.**—A vertical section of a cerebral convolution consists of a thin layer of gray matter externally enclosing a white core (Fig. 478). The cortex consists of cells and fibres embedded in a matrix, and to the nerve cells nerve fibres proceed from the white matter. The nerve cells of the cortex vary in size, form and distribution in the different layers and also in different convolutions. Taking such a convolution as the ascending frontal or **motor area type**, we get the appearances shown in Fig. 474. It is covered on its surface by the pia mater. (1) The most *superficial* layer is narrow, and consists of much neuroglia, a network of branched nerve fibrils, a few scattered small multipolar nerve cells, and a layer of very small medullated nerve fibres; (2) a layer of close-set, *small, angular*, or *short, pyramidal nerve cells;* (3) the thickest layer or formation of the cornu ammonis, consisting of many layers of *larger pyramidal cells*, which are larger in the deeper than in the more superficial layers. They are not so closely packed together, as many granules lie between them. At the lowest part of this layer the cells are larger than elsewhere, presenting some resemblance to the cells of the anterior cornu of the gray matter of the spinal cord. By some it is described as a special layer, and termed the *ganglion-cell layer.* This layer is specially well marked in those convolutions which are described as containing motor centres. Among the large cells are a few small angular-looking cells, which become more numerous lower down, and from (4) a narrow layer of numerous small, branched, irregular, ganglionic cells—the "*granular formation*" of Meynert. In the motor areas mixed with these are large pyramidal cells, disposed in groups called "cell clusters." (5) A layer of spindle-shaped *fusiform* branched cells—the *claustral formation* of Meynert—lying for the most part parallel to the surface of the convolution. No layer is composed exclusively of one form of cell. The above represents the *motor* type. Then follows the *white* matter (*m*), consisting of medullated nerve fibres, which run in groups into the gray matter, where they lose their myelin. The fibres are somewhat smaller than in the other parts of the nervous system (diameter $\frac{1}{1000}$ inch), and between them lie a few nuclear elements.]

[In the **sensory type**, as in the occipital lobe (Fig. 475), the first and second layers are not unlike the corresponding layers in the motor type, and the fusiform cells in the seventh layer also resemble the latter. The layer of pyramidal cells (3) is not so large, while its deeper part, sometimes called the "ganglion-cell-layer," contains no large cells. (5) Between the two is (4) a layer with numerous angular granule-like bodies or cells, called the "granule layer."]

[**The hippocampus major** contains, besides a layer of neurolgia and some white matter on the surface, a regular series of pyramidal cells, which give it a characteristic appearance. This is the part which varies most. It is to be remembered that the transition from one type to the other takes place gradually.]

[**Pyramidal Cells of the Cortex.**—Each cell is more or less pyramidal in shape, giving off several processes—(*a*) an **apical process**, which is often very long, and runs toward the surface of the cerebrum, where it is said to terminate in an ovoid corpuscle, closely resembling those in which the ultimate branches of Purkinje's cells of the cerebellum end; (*b*) the unbranched **median basilar process**, which is an axial cylinder process, and becomes continuous with the axial cylinder of a nerve fibre of the white matter. It ultimately becomes invested by myelin. (*c*) The **lateral processes** are given off chiefly near the base of the cell, and they soon branch to form part of the ground plexus of fibrils which everywhere pervades the gray matter.]

Each cell is surrounded by a **lymph space**, and so are the blood vessels, in the latter case forming a perivascular space, which communicates with the pericellular lymph space, as in Fig. 476.

FIG. 474.

Cortex of motor area of brain of monkey (× 150). 1, superficial layer; 2, small angular cells; 3, pyramidal cells; 4, ganglionic cells and cell clusters; 5, fusiform cells (*Ferrier*, after *Bevan Lewis*).

FIG. 475.

Cortex of occipital lobe. 1, superficial layer; 2, small angular cells; 3, 5, pyramidal cells; 4, granule layer; 6, granules and ganglionic layer; 7, spindle cells. (*Ferrier*, after *Bevan Lewis*.)

FIG. 476.

Perivascular and pericellular lymph spaces. *a*, capillary with a lymph space communicating with the pericellular lymph space *b*, round the cell a lymph space *c*, containing two lymph corpuscles. × 250.

FIG. 477.

Vertical section of a frontal convolution (Weigert's method) × 50. P, pia mater; 1–3, five layers of Meynert; *a*, superficial layer of connective tissue; *b*, *i*, successive layers of medullated nerve fibres; *k*, white matter.

[**Nerve Fibres in the Cortex.**—The ordinary methods of hardening the brain do not enable us to detect the enormous number of **medullated nerve fibres** in the gray matter. By using Exner's osmic acid method, or Weigert's or Pal's method, we obtain such a result as is shown in Fig. 477. Under the pia (P) is a layer of connective tissue (*a*) devoid of nerve fibres. Beneath it is a layer (*b*) occupying about the half of the outer layer, which is almost entirely taken up by medullated nerve fibres; most of these are fine, but a few of them are coarse, and run parallel to the surface and tangential to the arc of the outer contour of the convolution. Internal to this is a layer of medullated fibres (*c*), which cross each other in various directions; while a similar network (*d*) occurs in the small-celled layer. (2) In the layer of large pyramidal cells (3) there are bundles of medullated fibres, running radially (*e*); but at the lower part of this layer there is a very dense network (*f*), forming (in a Weigert's preparation) a dense, dark band, corresponding to the outer layer of Baillanger. In the layers marked (*g* and *h*), which are partly in the third and partly in the fourth cortical layer, the radial arrangement is more marked and more compact, and the thick fibres are more numerous. In the middle is (*h*) a narrow, dense network corresponding to Baillanger's inner layer. The lower part of the fourth layer, and the whole of the fifth, are occupied by *i*. It is to be remembered that all the convolutions do not present exactly the same structure and arrangement (*Obersteiner*).]

[**Variations.**—The gray matter differs in different parts of the brain. In the gray matter of the cornu ammonis, the large pyramidal cells of (3) make up the chief mass; in the claustrum (4) is most abundant. In the **central convolutions** (ascending frontal and parietal), according to Betz, Mierzejewski, and Bevan Lewis, very large pyramidal cells are found in the lower part of the third layer. Similar cells have been found in the posterior extremities of the frontal convolutions in some animals—the posterior parietal lobule, and para-central lobule, all of which have motor functions. In those convolutions which are regarded as subserving **sensory** functions, a somewhat different type prevails, *e.g.*, the occipital gyri or annectant convolution (*B. Lewis*). The very large pyramidal cells are absent, while the granule layer exists as a well-marked layer between the layer of large pyramidal cells and the ganglion cell layer (Fig. 475).]

[Fuchs finds that there are no medullated fibres either in the cortex or medulla until the end of the first month of life. The medullated fibres appear in the uppermost layer at the fifth month, and in the second at the end of the first year, the radial bundles in the deeper layers at the second month. The medullated fibres increase until the seventh or eighth year, when they have the same arrangement as in the adult.]

FIG. 478.



1, 1, medullary arteries; and 1′, 1″, in groups between the convolutions; 2, 2, arteries of the cortex cerebri; *a*, large-meshed plexus in first layer; *b*, closer plexus in middle layer; *c*, opener plexus in the gray matter next the white substance, with its vessels (*d*).

[**Blood Vessels.**—The adventitia of the small cerebral vessels contains pigment and granular cells, filled with oil granules. In the newborn child the blood vessels of the brain are beset with cells, filled with fatty granules. Perhaps the granules supply part of the material for the formation of the myelin sheath on the nerve fibres. About the fifth year the fat is replaced by a yellow pigment. In adults, yellow or brown glancing pigment granules are found in the adventitia of the arteries. In the adventitia of the veins there is no pigment, but generally some fat. The gray matter is much more vascular than the white, and when injected, a section of a convolution presents the appearance shown in Fig. 478. The **nutritive** arteries consist of (*a*) the long **medullary arteries** (1) which pass from the pia mater through the gray matter into the central white matter or centrum ovale. They are **terminal** arteries, and do not communicate with each other in their course; thus, they supply independent vascular areas; nor do they anastomose with any of the arteries derived from the ganglionic system of blood vessels; 12 to 15 of them are seen in a section of a convolution. (*b*) The short **cortical nutritive** articles (2) are smaller and shorter than the foregoing. Although some of them enter the white matter, they chiefly supply the cortex, where

they form an open-meshed plexus in the first layer (*a*), while in the next layer (*b*) the plexus of capillaries is dense, the plexus again being wider in the inner layers (*c*).]

[**Central or Ganglionic Arteries.**—From the trunks constituting the circle of Willis (Fig. in § 381), branches are given off, which pass upward and enter the brain to supply the basal ganglia with blood. They are arranged in several groups, but they are all **terminal**, each one supplying its own area, nor do they anastomose with the arteries of the cortex.]

Cerebral Arteries.—From a practical point of view, the distribution of the blood vessels of the brain is important. The artery of the Sylvian fissure supplies the *motor* areas of the brain in animals; in man, the precentral lobule is supplied by a branch of the anterior cerebral artery (*Duret*). The region of the third left frontal convolution, which is connected with the function of speech, is supplied by a special branch of the Sylvian artery. Those areas of the frontal lobes whose injury results in disturbance of the intelligence, are supplied by the anterior cerebral artery. Those regions of the cortex cerebri, whose injury, according to Ferrier, causes hemianæsthesia, are supplied by the posterior cerebral artery.

FIG. 479.

Left side of the human brain (diagrammatic). F, frontal; P, parietal; O, occipital; T, temporo-sphenoidal lobe; S, fissure of Sylvius; S', horizontal, S'', ascending ramus of S; *c*, sulcus centralis, or fissure of Rolando; A, ascending frontal, and B, ascending parietal convolution; F_1, superior, F_2, middle, and F_3, inferior frontal convolutions; f_1, superior, and f_2, inferior frontal fissures; f_3, sulcus præcentralis; P, superior parietal lobule; P_2, inferior parietal lobule, consisting of P_2, supra-marginal gyrus, and P_2', angular gyrus; *ip*, sulcus interparietalis; *cm*, termination of calloso-marginal fissure; O_1, first, O_2, second, O_3, third occipital convolutions; *po*, parieto-occipital fissure; *o*, transverse occipital fissure; o_2, inferior longitudinal occipital fissure; T_1, first, T_2, second, T_3, third temporo-sphenoidal convolutions; t_1, first, t_2, second temporo-sphenoidal fissures.

[In connection with the localization of the centres in the cortex, it is important to be thoroughly acquainted with the arrangement of the **cerebral convolutions.** Each half of the outer cerebral surface is divided by certain **fissures** into five **lobes—frontal, parietal, occipital, temporo-sphenoidal,** and **central,** or **island of Reil** (Fig. 481). The **frontal lobe** (Fig. 479) consists of three convolutions, with numerous secondary folds running nearly horizontal, named superior (F_1), middle (F_2), and inferior (F_3) frontal convolutions. Behind these is a large convolution, the ascending frontal (A), which ascends almost vertically, immediately behind these—separated from them, however, by the precentral fissure (f_3), and mapped off behind by the fissure of Rolando, or the central sulcus (*c*).]

[The **parietal lobe** (Fig. 479, P) is limited in front by the fissure of Rolando, below in part by the Sylvian fissure, and behind by the parieto-occipital fissure. It consists of the ascending parietal (posterior central) convolution (Fig. 479, B), which ascends just behind the fissure of Rolando, and parallel to the ascending frontal, with which it is continuous below; above, it becomes continuous

with the superior parietal lobule (P_1), while the latter is separated from the inferior parietal lobule (*"pli courbe"*) by the inter-parietal sulcus. The inferior parietal lobule consists of (*a*) a part arching over the upper end of the Sylvian fissure, the supra-marginal convolution (P_2), which is continuous with the superior temporo-sphenoidal convolution. Behind is (*b*) the angular gyrus (P_2'), which arches round the posterior end of the parallel fissure, and becomes connected with the middle temporo-sphenoidal convolution.]

[The **temporo-sphenoidal** or **temporal lobe** (Fig. 479, T) consists of three horizontal convolutions—superior, middle, and inferior—the two former being separated by the parallel sulcus, while the whole lobe is mapped off from the frontal by the Sylvian fissure (S).]

[The **occipital lobe** (Fig. 479, O) is small, forms the rounded posterior end of the cerebrum, and is separated from the parietal lobe by the parieto-occipital fissure, which fissure is bridged over at the lower part by the four annectant gyri (*plis de passage* of Gratiolet). It has three convolutions—superior (O_1), middle (O_2), and inferior (O_3)—on its outer surface.]

[The **central lobe** or **island of Reil**, consists of five or six short, straight convolutions (gyri operti—Fig. 481), radiating outward and backward from near the anterior perforated spot, and can only be seen when the margins of the Sylvian fissure are pulled asunder. The **operculum**, consisting of the extremities of the inferior frontal, ascending parietal, and frontal convolutions, lie outside it, cover it, and conceal it from view.]

FIG. 480.



Median aspect of the right hemisphere. CC, corpus callosum divided longitudinally; Gf, gyrus fornicatus; H, gyrus hippocampi; *h*, sulcus hippocampi; U, uncinate gyrus; *cm*, calloso-marginal fissure; F, first frontal convolution; *c*, terminal portion of fissure of Rolando; A, ascending frontal; B, ascending parietal convolution and paracentral lobule; P_1', præcuneus or quadrate lobule; Oz, cuneus; Po, parieto-occipital fissure; o_1, transverse occipital fissure; *oc*, calcarine fissure; *oc'*, superior, *oc''*, inferior ramus of the same; D, gyrus descendens; T_4, gyrus occipito-temporalis lateralis (lobulus fusiformis); T_5, gyrus occipito-temporalis medialis (lobulus lingualis).

[On the **inner** or **mesial** surface of the cerebrum are—the **gyrus fornicatus** (Fig. 480, Gf), or convolution of the corpus callosum, which runs parallel to and bends round the anterior and posterior extremities of the corpus callosum, terminating posteriorly in the gyrus uncinatus or gyrus hippocampi (Fig. 480, H), and ending anteriorly in a crooked extremity, the subiculum cornu ammonis (Fig. 480, U). Above it is the calloso-marginal fissure (Fig. 480, *cm*), and running parallel to it is the **marginal convolution** (Fig. 480), which lies between the latter fissure and the margin of the longitudinal fissure; it is, however, merely the mesial aspect of the frontal and parietal convolutions. The **quadrate lobule** or **præcuneus** lies (Fig. 480, Pi), between the posterior extremity of the calloso-marginal fissure and the parieto-occipital fissure; it is merely the mesial aspect of the ascending parietal convolution. The parieto-occipital fissure terminates below in the **calcarine fissure** (Fig. 480, *oc*), and the latter runs backward in the occipital lobe dividing it into two branches, *oc'*, *oc''*. Between the parieto-occipital and calcarine fissures lies the wedge-shaped lobule termed the **cuneus** (Fig. 480, Oz). The calcarine fissure indicates on the surface the position of the *calcar avis* or **hippocampus minor**, in the posterior cornu of the lateral ventricle. The **dentate fissure** or *sulcus hippocampi* (Fig. 480, *h*) marks the position of the elevation of the hippocampus major, or cornu ammonis, in the lateral ventricle. The **temporo-sphenoidal lobe** terminates anteriorly in the **uncinate gyrus**, while, running along the former and the occipital lobes, is the **collateral fissure** (occipito-temporal sulcus), which marks the position of the eminentia collateralis in the

descending cornu of the lateral ventricle, while it also separates the *superior* from the *inferior* temporo-occipital convolutions (T_4 and T_5).]

Motor Centres.—In 1870 Fritsch and Hitzig discovered a series of circumscribed regions on the surface of the cerebral convolutions, whose stimulation by means of electricity causes coördinated *movements* in quite distinct groups of muscles of the *opposite* side of the body (Fig. 483, I, II).

Methods—Stimulation.—The surface of the cerebrum is exposed in an animal (dog, monkey) by removing a part of the skull covering the so-called motor convolutions and dividing the dura mater. When the convolutions are fully exposed, a pair of blunt non-polarizable (§ 328) needle electrodes are applied, near each other, to various parts of the cerebral surface. We may employ the closing or opening shock of a **constant** current, or the constant current may be rapidly interrupted, the current being of such a strength as to be distinctly perceived when it is applied to the tip of the tongue (*Fritsch and Hitzig*). Or, the **induced** current may be used, also of such a strength that it is readily felt when applied to the tip of the tongue (*Ferrier*, 1873). The cerebrum is completely *insensible to severe operations made upon it.*

The areas of the cerebral cortex whose stimulation discharges the characteristic movements, are regarded by some as *actual centres*, because the reaction time after stimulation of the centres and the duration of the muscular contraction are longer than when the sub-cortical fibres which lead toward the deeper parts of the brain are stimulated. Another circumstance favoring this view is, that the excitability of these areas is influenced by the stimulation of afferent nerves (*Bubnoff and Heidenhain*). It may be that these centres are acted upon by voluntary impulses in the execution of voluntary movements. Hence, they have been called "*psychomotor centres.*" [At any rate, these areas have a definite relation to certain motor acts, and perhaps it is well to speak of them as "areas of representation" of the function to which they are related.]

FIG. 481.

Orbital surface of the left frontal lobe and the island of Reil, the tip of the temporo-sphenoidal lobe removed to show the latter. 17, convolution of the margin of the longitudinal fissure; O, olfactory fissure, with the olfactory lobe removed; TR, tri-radiate fissure; 1'' and 1''', convolutions on the orbital surface; 1, 1, 1, 1, under surface of the infero-frontal convolution; 4, under surface of the ascending frontal, and, 5, of the ascending parietal convolutions; C, central lobe or island.

The motor areas of the cerebrum (dog, cat, sheep) are characterized by the presence of specially large pyramidal cells (*Betz, Merzejewsky, Bevan Lewis*); while similar cells were found by Obersteiner in the areas marked 4 and 8 (Fig. 483), and Betz found them in the ascending frontal convolution of man, in the third frontal convolution, and in the island of Reil. O. Soltmann found that stimulation of the motor areas in **newly-born** animals is without result, while only the deeper fibres of the corona radiata are excitable.

Modifying Conditions.—In the condition of deep narcosis produced by chloroform, ether, chloral, morphia, or in apnœa, the excitability of the centres is abolished (*Schiff*), while the sub-cortical conducting paths still retain their excitability (*Bubnoff and Heidenhain*). Small doses of these poisons and also of atropin at first increase the excitability of the centres. Moderate loss of blood excites them, while a great loss of blood diminishes and then abolishes the excitability (*Munk and Orschansky*). Slight inflammation increases, while cooling diminishes, the excitability. If the cortex cerebri be removed in animals, the excitability of the fibres of the corona radiata is completely abolished about the fourth day, just as in the case of a peripheral nerve separated from its centre (*Albertoni, Dupuy, Franck and Pitres*).

Stimulation of Sub-cortical Parts.—As the fibres of the corona radiata converge toward the centre of the hemisphere, it is evident that, after removal of the cortex, stimulation of these fibres in the deeper parts of the hemisphere is followed by the same motor results (*Gudden and Eckhard*). The stimulus is applied merely to a

deeper part of the motor path. If the stimulus be applied to parts situated still more deeply, as for example to the *internal capsule*, general contraction of the muscles on the opposite side is the result.

Time Relations of the Stimulation.—According to Franck and Pitres, the time which elapses between the moment of stimulation of the cortex and the resulting movement, after deducting the period of latent stimulation for the muscles, and the time necessary for the conduction of the impulse through the cord and nerves of the extremities, is 0.045 second. Heidenhain and Bubnoff found that, during moderate morphia narcosis, when the stimulating current was increased in strength, the muscular contraction and the reaction time became shorter. After removal of the cortex, the occurrence of the muscular contraction from the moment of stimulation of the white matter is diminished ¼ to ⅓. The form of the muscular contraction is longer and more extended when the cortex, than when the sub-cortical paths, are stimulated. If the animal (dog) be in a state of high reflex excitability, these differences disappear; in both cases the contraction follows very rapidly (*Bubnoff and Heidenhain*). If the stimulus be very strong the muscles of the *same* side

FIG. 482.



View of the brain from above (semi-diagrammatic). S_1, end of ramus of the Sylvian fissure. The other letters refer to the same parts as in Fig. 479.

may contract, but somewhat *later* than those of the opposite side. If the motor areas for the fore and hind limbs be stimulated simultaneously, the latter contract somewhat after the former.

Number of Stimuli.—If 40 stimuli per second be applied to a motor area, then the corresponding muscles yield 40 single contractions; while with 46 single stimuli per second there results a continued complete contraction (*Franck and Pitres*). In one and the same animal, the *same number of stimuli* is required to produce a continuous contraction, whether the cortical centre, the motor nerve, or even the muscle itself be stimulated. With very feeble stimuli, **summation of stimuli** takes place, for the muscular contraction only begins after several ineffective stimuli have been applied. [It is generally held that the rhythm of a contracting muscle is the same as the rhythm of the stimuli applied to its motor nerve, but Schäfer and Horsley contend that this holds good for rates of stimuli to about 10 or 12 per second. They find that the same is true for the cortex cerebri, corona radiata, and medulla spinalis, viz., that the muscular response does not vary with the rhythm

(*i. e.*, number of stimuli per sec.), but that the rhythm is constant—about 10 per sec.—and independent of the number of stimuli per sec., provided they are above 10 per sec. applied to these parts. Indeed, all voluntary contractions show a similar rate of undulation in the muscle curve. Perhaps the rhythm of the efferent impulses is modified in the motor nerve cells of the spinal cord.

[The matter, as regards electrical stimulation of the cortex cerebri, resolves itself into this, that stimulation of certain cortical areas always causes contraction in definite muscles or groups of muscles, resulting in definite coördinated movements on the *opposite* side of the body; the areas have been called "**motor areas.**" They have been mapped out and ascertained in a large number of animals, and the question comes to be, Are there similar areas in man?]

Primary Fissures and Convolutions of the Dog's Brain.—The *position* of the motor centres in the dog's brain is indicated in Fig. 483, I and II. The dog's brain is marked by two "primary fissures," viz., the **sulcus cruciatus** (S), which intersects the longitudinal fissure at a right angle at the junction of its anterior with its middle third. This fissure has been called the sulcus frontalis, or the fissura coronalis. The second primary fissure is the **fossa Sylvii** (F). Four "**primary convolutions,**" in addition, are arranged with reference to these primary fissures. The first primary convolution (I), in the form of a sharply curved knee, embraces the fossa Sylvii (F). The second convolution (II) runs nearly parallel to the first. The fourth primary convolution (IV) bounds the longitudinal fissure, and is separated from its fellow of the opposite side by the falx cerebri; anteriorly it embraces the sulcus cruciatus (S), so that it is divided into two parts, by this sulcus, a part, the gyrus præcruciatus or præfrontalis, lying in front of the sulcus, and the gyrus postcruciatus (postfrontalis) lying behind it. The third primary convolution (III) runs parallel to the fourth. Some authors count the convolutions from the longitudinal fissure outward. In Fig. 483, I and II, the *motor areas* or *centres* are indicated by dots on the individual primary convolutions. We must remember, however, that the centres are not mere points, but that they vary in size from that of a pea upward, according to the size of the animal. Motor areas have been mapped out in the brain of the monkey, rabbit, rat, bird, and frog.

Position of the Motor Centres (Dog).—Fritsch and Hitzig, in 1870, mapped out the following motor areas, whose position may be readily found on referring to Fig. 483: 1, is the centre for the *muscles of the neck;* 2, for the extensors and adductors of the *fore limb;* 3, for the flexion and rotation of the fore leg; 4, for the movements of the *hind limb*, which Luciani and Tamburini resolved into two antagonistic centres; 5, for the *muscles of the face*, or the facial centre. In 1873 Ferrier discovered the following additional centres: 6, for the lateral switching movements of the *tail;* 7, for the retraction and abduction of the fore limb; 8, for the elevation of the shoulder and extension of the fore limb, as in walking; the area marked 9, 9, 9, controls the movements of the orbicularis palpebrarum, and of the zygomaticus (closure of the eyelids), together with the upward movement of the eyeball and narrowing of the pupil. Stimulation of the areas *a, a* (Fig. II) is followed by retraction and elevation of the angle of the mouth, with partial opening of the mouth; at *b*, Ferrier observed opening of the mouth with protrusion and retraction of the tongue, while the dog not unfrequently howled. He called this centre the "*oral centre.*" Stimulation of *c c* causes retraction of the angle of the mouth, owing to the action of the platysma, while *c'* causes elevation of the angle of the mouth and of one-half of the face, until the eye may be closed, just as in 9. Stimulation of *d* is followed by opening of the eye and dilatation of the pupil, while the eyes and head are turned toward the other side. According to H. Munk, the prefrontal region has an influence upon the attitude of the body (?). The perineal muscles contract when the gyrus postcruciatus is stimulated. Stimulation of the gyrus præcruciatus on its anterior and sloping aspect causes movements in the pharynx and larynx.

The position of the individual motor areas may vary somewhat, and they may be slightly different on the two sides (*Luciani and Tamburini*).

Strong Stimuli.—If the stimulation be very strong, not only the muscles on the opposite side, but those on the same side, may contract. These latter movements belong to the class of associated movements, and are due to conduction through commissural fibres. Those muscles, which usually (muscles of mastication) or always (muscles of eye, larynx, and face) act together, appear to have a centre not only in the opposite but also in the hemisphere of the same side (*Exner*). [All observers have found that stimulation of the facial centre causes identical (associated) movements on *both* sides of the face, so that both sides of the face seem to be represented in each hemisphere. Schäfer and Horsley's experiments make it very probable that some other muscles, *e.g.*, some of the trunk muscles, pectorals, and recti abdominis, are represented bilaterally in the hemispheres.

This is an important point in relation to recovery after the supposed destruction of a centre, and has an intimate bearing on the question of "Substitution," in reference to the restoration of nerve function (p. 732).]

FIG. 483.



I, Cerebrum of the dog from above; II, from the side; I, II, III, IV, the four primary convolutions.—S, sulcus cruciatus; F, Sylvian fossa; *o*, olfactory lobe; *p*, optic nerve; 1, motor area for the muscles of the neck; 2, extensors and abductors of the fore limb; 3, flexors and rotators of the fore limb; 4, the muscles of the hind limb; 5, the facial muscles; 6, lateral switching movements of the tail; 7, retraction and abduction of the fore limb; 8, elevation of the shoulder and extension of fore limb (movements as in walking); 9, 9, orbicularis palpebrarum, zygomaticus, closure of the eyelids. II, *a*, *a*, retraction and elevation of the angle of the mouth; *b*, opening of the mouth and movements of the oral centre; *c*, *c*, platysma; *d*, opening of the eye; I, *t*, thermic centre, according to Eulenburg and Landois. III, cerebrum of the rabbit from above; IV, cerebrum of the pigeon from above; V, cerebrum of the frog from above; VI, cerebrum of the carp from above (in all these *o* is the olfactory lobe; 1, cerebrum; 2, optic lobe; 3, cerebellum; 4, medulla oblongata).

Mechanical stimulation, *e.g.*, scraping the motor areas for the limbs, produces movements in these parts (*Luciani*).

Cerebral Epilepsy.—It is of great practical diagnostic importance to ascertain if stimulation of the motor areas in man, due to local diseases (inflammation,

tumors, softening, degenerative irritation), causes movements. [Hughlings-Jackson has shown that local diseases of the cortex may cause spasmodic contractions in certain groups of muscles, a condition known as "**Jacksonian Epilepsy**," and he explains in this way the occurrence of unilateral local epileptiform spasms, which were observed by Ferrier and Landois to occur after inflammatory irritation.] Luciani observed these spasms in dogs, and sometimes they were so violent and general as to constitute an attack of epilepsy. This condition became hereditary, and the animals ultimately died from epilepsy (§ 373). According to Eckhard, epileptic attacks are never produced by stimulation of the surface of the posterior convolutions.

Strong stimulation of the motor regions may give rise in dogs to a complete general convulsive **epileptic attack**, which usually begins with contractions of the groups of muscles specially related to the stimulated centre (*Ferrier, Eulenburg and Landois, Albertoni, Luciani and Tamburini*); then often passes to the corresponding limb of the opposite side (associated movements); and lastly, all the muscles of the body are thrown into tonic and then into clonic spasms. The opposite side of the body has been observed to pass into spasm from below upward, after the contractions were developed in the other side. The spasmodic excitement passes from centre to centre, an intermediate motor region never being passed over. After this condition has once been produced, the slightest stimulation may suffice to bring on a new epileptic attack (§ 373). During the attack, the cerebral circulation is accelerated. According to Eckhard and Danillo, epileptic attacks cannot be discharged from the posterior part of the cerebrum by means of weak currents. Stimulation of the **sub-cortical** white matter causes epilepsy, which, however, begins in the muscles of the *same* side (*Bubnoff and Heidenhain*). These contractions are due to an escape of the electrical current, which thus reaches the medulla oblongata (§ 373).

If certain motor areas are **extirpated**, the epileptic attack is absent from the muscles controlled by these areas (*Luciani*). Separation of the motor cortical area by means of a horizontal section *during* an attack cuts short the latter (*Munk*). During an epileptic attack it is possible to excise the motor area of one extremity, and thus exclude this limb from the attack while the rest of the body is convulsed.

Drugs.—The continued use of *potassium bromide* prevents the production of epilepsy on stimulating the cortical areas.

Chemical Stimulation.—Substances such as occur in urine, *e.g.*, kreatinin, kreatin, acid potassic phosphate, and sediment of urates, when sprinkled on the motor areas of the dog, cause pronounced eclampsic, *clonic convulsions*, which recur spontaneously, and are followed by deep coma. These symptoms are like those of uræmic poisoning. The sensory centres, especially that for vision, seem also to be affected by chemical stimulation (*Landois*).

[**Motor Centres in the Monkey.**—Ferrier has mapped out a large number of centres on the outer surface of the brain in the monkey, and to each centre he has given a number. These numbers have been transferred to corresponding convolutions on the human brain, numbered accordingly. These areas are specially distributed on the convolutions around the fissure of Rolando, including in the monkey, the posterior extremities of the posterior and middle frontal convolutions, the ascending frontal, ascending parietal, and part of the parietal lobule.]

[Fig. 484 represents these areas transferred to the corresponding areas in **man**. (1) On the superior parietal lobule (advance of the opposite hind limb, as in walking). (2), (3), (4) Around the upper extremity of the fissure of Rolando (complex movements of the opposite leg and arm, and of the trunk, as in swimming). (*a*), (*b*), (*c*), (*d*) On the ascending parietal or posterior central convolution (individual and combined movements of the fingers and wrist of the opposite hand or prehensile movements). (5) Posterior end of the superior frontal convolution (extension forward of the opposite arm and hand). (6) Upper part of the ascending frontal or anterior central convolution (supination and flexion of the opposite forearm). (7) Middle of the same convolution (retraction and elevation of the opposite angle of the mouth). (8) At the lower end of the same convolution (elevation of the ali nasi and upper lip, and depression of the lower lip on the opposite side). (9), (10) Broca's convolution (opening of the mouth with protrusion and retraction of the tongue—aphasic region). (11) Between 10 and the lower end of the ascending parietal convolution (retraction of the opposite angle of the mouth, the head turns toward one side). (12) Posterior part of the superior and middle frontal convolutions (the eyes open widely, the pupils dilate, and the head and eyes turn toward the opposite side). (13), (13′) Supra-marginal and angular gyrus (the eyes move toward the opposite side, and upward or downward—centre of vision). (14) Superior tem-

poro-sphenoidal convolution (pricking of the opposite ear, pupils dilate, and the head and eyes turn to the opposite side—hearing centre).]

[**Experiments on Monkeys.**—Electrical stimulation of the anterior part of the frontal lobes yields negative results; but behind the anterior end of the sagittal limb of the precentral sulcus, there are lateral movements of the head and eyes. If the anterior third or fourth be removed, Schäfer and Horsley observed no motor paralysis nor any deficiency of general or special sensibility. Excitation of the **external surface** (*motor area*) led Ferrier to map out the areas named on p. 744. Schäfer and Horsley's experiments agree with Ferrier's, and they map out the

FIG. 484.



The brain with the chief convolutions (after *Ecker*). See also Figs. 498, 499 in their relation to the skull. The numbers 1 to 14, and the letters *a* to *d*, indicate cortical areas (p. 746). S, Sylvian fissure; C, central sulcus, or fissure of Rolando; A, anterior, and B, posterior central convolutions; F_1, upper, F_2, middle, and F_3, lowest frontal convolutions; f_1, superior, and f_2, inferior frontal fissure; f_3, sulcus præcentralis; P_1, superior, P_2, inferior parietal lobe, with P_2, gyrus supra-marginalis; P_2^1, gyrus angularis; *ip*, sulcus interparietalis; *cm*, end of calloso-marginal fissure; O_1, O_2, O_3, occipital convolutions; *po*, parieto-occipital fissure; T_1, T_2, T_3, temporo-sphenoidal convolutions; K_1, K_2, K_3, points in the coronal suture; 4_1, 4_2, in the lambdoidal suture.

motor area into a number of main areas, each of which is particularly concerned with the movement of a particular part or limb, and in some of which, centres concerned with more specialized movements may be marked out. The **arm area** is roughly triangular (Fig. 485), and "occupies most of the upper half of the ascending parietal and ascending frontal gyri, from a little beneath the level of the sagittal part of the precentral fissure below, nearly to the margin of the hemisphere above, together with the adjacent part of the frontal lobe below the small antero-posterior sulcus." It bends round and is continuous with a part of the marginal gyrus. The special movements of the arm are indicated in Fig. 485.]

[The **face area** gives rise not only to movements of the facial muscles, but also of the whole of the upper end of the alimentary tube. It comprises the whole of the surrounding parietal and frontal convolutions below the arm area, down to the fissure of Sylvius, and including the external surface of the operculum.]

[The **head area**, or area for visual direction, comprises part of the frontal lobe from the margin of the hemisphere to the face area. In front it is bounded by the non-excitable part of the frontal lobe. Its stimulation gives the results obtained by Ferrier on stimulating his No. 12 centre. The **leg area** is partly situate on the mesial surface, but it extends over to the external surface from the parieto-occipital fissure nearly to the level of the anterior end of the small sulcus marked *x*. The **trunk area** scarcely extends over the margin to reach the external surface.]

[Schäfer and Horsley have extended Ferrier's researches, and shown that motor centres exist in the **marginal convolution** (Fig. 486), which is excitable only in that portion corresponding in extent (antero-posteriorly) to the excitable portion of the outer surface of the hemisphere. Anteriorly it reaches forward to a line which is opposite the junction of the posterior and middle thirds of the

FIG. 485.

Diagram of the motor areas on the outer surface of a monkey's brain (*Horsley and Schäfer*).

FIG. 486.

Diagram of the motor areas on the marginal convolution of a monkey's brain (*Horsley and Schäfer*).

superior frontal convolution (centre 12), while posteriorly it extends backward opposite to the parietal lobule, including the paracentral lobule, which contains large multipolar pyramidal motor cells. The rest of the mesial surface is excitable. They find that the centres are arranged from before backward in the following order: (1) Movements of the head—this area is very small, and belongs to the large head area on the external surface; (2) of the forearm and hand; (3) of the arm at the shoulder; (4) of the upper dorsal part of the trunk; (6) of the leg at the hip; (7) of the lower leg at the knee; (8) of the foot and toes.]

Excitation of the Area AS produces movements of the arm (Fig. 489). These vary according to the spot stimulated, but toward the anterior part of the area, movements of the wrist and forearm, toward the posterior part movements of the arm and shoulder, are more frequently the result of the excitation. Excitation of **Tr** produces movements of the trunk, generally arching and rotation. Those movements which are called forth by stimulating the anterior part of the area are usually confined to the upper part of the trunk (thoracic region), and are often associated with movements of the shoulder and arm; those called forth by stimulating the posterior parts are movements of the abdominal and pelvic regions and of the tail, and are often associated with movements of the hip and leg. Excitation of the area **L** produces movements in the lower limb. These vary according to the part stimulated, extension of the hip being especially associated with excitation of the anterior part of the area, and contraction of the hamstrings with excitation of the middle part.]

[**Do similar Centres exist in Man?**—The results of clinical and pathological investigations show, that similar although not absolutely identical areas exist in man. The motor areas, or those which have a special relation to voluntary motion in man, exist in part on the convolutions bounding the fissure of Rolando, and occupy the "**central**" convolutions, *i. e.*, the ascending frontal and ascending parietal convolutions along with the superior parietal lobule, and along the mesial surface of the hemisphere, the paracentral lobule and precuneus (Fig. 488). In this region, the upper third of the ascending frontal and parietal convolutions along with the superior parietal are the **leg** area (Fig. 488, *leg*), the middle third of the ascending parietal and ascending frontal for the **arm**, and the upper part of the lowest third of these convolutions for the **face**, while the very lowest part of the ascending frontal convolution is the area for the movements of the **lips** (L) and **tongue** (T). (Compare Figs. 485, 490.) The last area, with the posterior extremity of the third left frontal convolution, is the centre for voluntary **speech.** We cannot say whether these "centres" are sharply mapped off from each other. In any case a very strong stimulation of one centre may involve an adjacent area. So far as is yet known, centres Nos. 5 and 12, as represented on the monkey's brain—those on the posterior extremity of the superior and middle frontal convolutions,—(5) for extension forward of the arm and hand, and (12) for opening the eyes and turning the head toward the opposite side (as in surprise), are not represented in the human brain. So accurately have certain of these areas been located, that surgeons, in suitable cases, have been able to excise a tumor causing certain symptoms, with relief of those symptoms.]

[We may, therefore, assert as a general proposition that the muscles of one lateral half of the body are regulated by certain areas in the opposite cerebral hemispheres.]

[Gowers maintains that the motor region is not exclusively motor, but that destruction of this area also leads to some loss of sensation. Starr also asserts that perceptions occur in the gray matter of the cortex of the "central" region and parietal convolutions, and that the various sensory areas for the various parts of the body lie about, and coincide to some extent with, the motor various areas for similar parts, but the sensory area is more extensive than the motor area, extending into the parietal behind the motor area, which is confined to the ascending frontal and parietal convolutions.]

II. Method of Destruction or **Ablation of Parts of the Cortex.**—Much confusion in this matter has arisen from comparing the results obtained on animals of different species. [It seems quite certain that the results obtained in the dog are quite different from those in the monkey. The motor areas may be simply excised with a knife, or the surface of the brain may be washed away with a stream of water, as was done by Goltz in dogs.]

[In the **dog**, the areas which are described as motor may be removed either by the knife (*Hermann*) or by means of a stream of water so directed as to wash away the gray matter (*Goltz*). In both cases, although there was some paralysis on the opposite side of the body, this was but temporary, for the paralysis disappeared within a few days, the animals having very decided control over their muscles, although Goltz admits that certain acts, especially those which the dogs had been trained to execute, *e.g.*, giving a paw, were executed "clumsily," indicating some failure of complete control, which Goltz ascribed to loss of tactile sensibility. Goltz thinks that the *extent* of the injury has more to do with the result than the locality. The restoration of motion was not due to the action of the corresponding centre of the opposite side, as destruction of this centre, although it produced the usual symptoms on the side which it governed, had no effect on the previous result (*Carville and Duret*).]

[In the **monkey**, there can be no doubt, from the experiments of Ferrier, that destruction of a motor centre, *e.g.*, that for the arm, results in *permanent* paralysis of the arm of the opposite side, and if the centres for the arm and leg are destroyed, there is permanent hemiplegia of the opposite side. "In order that the hemiplegia or paraplegia produced by cortical ablation shall be complete, it is necessary to include the part of the marginal gyrus corresponding in longitudinal extent to the excitable areas of the external surface." The amount of paralysis produced by ablation of the marginal gyri alone is as great as that caused by removal of the much more extensive external areas; but the

complexity of the muscular movements which are governed from these areas is much greater than in those governed from the marginal gyrus (*Schäfer and Horsley*).]

[In **man**, records of destructive lesions of the motor areas in whole or part have now accumulated to such an extent as to leave no doubt, that if there be, say, a destructive lesion of the middle third of the cortex of the ascending frontal and ascending parietal convolutions, there will be paralysis of the arm of the opposite side; and the same is true for the other centres.]

[In **extirpation or ablation of the motor centres**, again, much confusion has arisen from comparing the results obtained on different animals. In the dog, there is no permanent motor paralysis, in the monkey and man there is. The difference is this, that in the dog the lower centres, perhaps the basal ganglia, are able to subserve the execution of those coördinated movements required for standing, progression, etc. As we proceed higher in the animal scale, the motor cortical centres assume more and more of the functions subserved by the basal ganglia in lower animals. There is, as it were, a gradual displacement of motor centres to the cortical region, as we ascend in the zoölogical scale.]

Differences in Animals.—The higher the development of the intelligence of animals, the more have their movements been learned, and the more have they gradually come to be controlled by the will; in them the disturbance of the motor phenomena becomes more pronounced and persistent after destruction of the cortical psychomotor centres. While in the lower vertebrates, including the **birds**, extirpation of the whole hemispheres does not materially interfere with movements, the coördinated reflex movements being sufficient—in **dogs** occasionally, but exceptionally, extirpation of several motor areas produces visible permanent disturbance of motor acts—and in **monkeys** and **man** (§ 378), the paralytic phenomena may be intense and persistent.

Acquired Movements.—Among the movements performed by men are many which have been acquired after much practice, and have been subjected to voluntary control, *e.g.*, the movements of the hands for many manual occupations. After a lesion of certain motor areas, such movements are reacquired only very slowly and incompletely, or it may be not at all. [The interference with these finer acquired movements sometimes becomes very marked in lesions of the motor areas produced by hemorrhage, and in some cases of hemiplegia.] Those movements, however, which are, as it were, innate [or as they are sometimes termed **fundamental** in opposition to acquired], and are under control of the will without much practice—such as the associated movements of the eyes, face, some of those of the limbs—are either rapidly restored after the lesion, or they appear to suffer but slightly after a lesion of the cerebral cortex; the facial muscles are never so completely paralyzed as from a lesion of the trunk of the facial nerve; usually the eye can be closed in the former case. The movements necessary for sucking have been performed by hemicephalic infants.

Theoretical.—Hitzig ascribes the disturbance of movement, after the removal of the motor centres, to the loss of the "*muscular sensibility*." Schiff refers it to the loss of *tactile sensibility*. According to Ferrier, the tactile and sensory impressions are not appreciably diminished or altered. The descending degeneration of the pyramidal tracts in the lateral columns, according to Schiff, occurs after section of the posterior half of the cervical spinal cord, or even after section of the posterior part of the lateral columns. After dividing the latter, and allowing secondary degeneration to take place, it is not possible to discharge movements by stimulating the cortex cerebri. [Schiff divided the posterior column of the cord, and found that stimulation of the opposite motor cortex failed to excite movements in the opposite fore limbs. He supposed that this result was due to ascending degeneration. Horsley finds, however, that Schiff's results are due to transverse aseptic myelitis at the seat of operation, thus causing a "block" there in the motor tract.] The posterior columns, and their continuation upward to the brain, are supposed to carry the impulses upward to the cerebrum (ascending the limb of the reflex arc), where, after being modified in the centres, they are carried outward by the pyramidal tracts (descending limb of the reflex arc). [Some hold that the posterior columns are directly connected with the cortical motor area, while others think that a sensory perceptive centre is interposed between the afferent and efferent impulses.] Between, but deeper in the brain, lie the centres for tactile sensibility. Landois and Eulenburg observed in a dog, from which the motor centres for the extremities had been removed on *both* sides, that the movements became completely *ataxic*, *i.e.*, the animal could not execute such coördinated movements as walking, standing, etc. Goltz regards the disturbances of movement after injury of the cortex as due to inhibition. Schiff maintains that when the cortex cerebi is stimulated we do not stimulate a cortical centre, but only the sensory channels of a reflex arc, the continuation of the posterior columns, so that on this supposition the movements resulting from stimulation of the motor points would be reflex movements. The centres lie deeper in the brain. This view is not generally entertained.

Modifying Conditions.—The excitability of the motor centres is capable of being considerably modified. Stimulation of sensory nerves diminishes it; thus, the curve of contraction of the muscles becomes lower and longer, while the reaction-time is lengthened simultaneously. Only when, owing to strong stimulation, the reflex muscular contractions are vigorous, the excitability of the cortical centres appears to be increased. Specially noteworthy is the fact that, in a certain stage of **morphia narcosis**, a stimulus which is too feeble to discharge a contraction becomes effective at once, if immediately before the stimulus is applied to the cortical centre, the skin of certain cutaneous areas be subjected to gentle tactile stimulation. When *strong* pressure is applied to the foot, the contractions become tonic in their nature, so that all stimuli, which under normal conditions produce only temporary stimulation, now stimulate these centres continuously. If, during the tonic contraction, one gently strokes the back of the foot, blows on the face, gently taps the nose, or stimulates the sciatic nerve, suddenly relaxation of the muscles again occurs. The phenomena call to mind the analogous observations in hypnotized animals (§ 374). Another very remarkable observation is, that when either owing to a reflex effect, or to *strong* electrical stimulation of a cortical centre, contraction of the corresponding muscles is produced, then *feeble* stimulation of the same centre, but also of other centres, suppresses the movement. Thus, we have the remarkable fact that, according to the strength of the stimulus applied to the motor apparatus, we can either produce movement or suppress a movement already in progress (*Bubnoff and Heidenhain*).

[**Excision of the Thyroid** affects the nerve centres. After thyroidectomy (twenty-four hours) the tetanus obtained by stimulating the cortex is greatly changed. It ceases when the stimulating current is shut off, as suddenly as that observed on stimulating the corona radiata. In more advanced cases, the tetanus is soon exhausted, and is often followed by clonic epileptoid spasms. In the latter stages, after thyroidectomy, there may be only a feeble tetanus, or none at all, on stimulating the motor areas, so great is the state of depression of function of these centres (*Horsley*).]

[Warner has directed attention to **visible muscular movements** apart from those studied in epilepsy, chorea, athetosis—and including attitude, gait, movements of the eyeballs, position of the hand, and posture in general, etc.—as **expressive of states of the brain** and nerve centres.]

376. **SENSORY CORTICAL CENTRES.**—[There must be some connection between the surface of the brain and the afferent channels through which **sensory impulses** pass inward, and although the channels for sensory impulses are, perhaps, not so definitely localized as those for voluntary motion, still we know that sensory impulses for the opposite half of the body travel upward through the posterior third of the posterior limb of the internal capsule (Fig. 500, S), to radiate in all probability into the occipital and temporo-sphenoidal lobes. Parts of these convolutions are sometimes spoken of as "**sensory centres**" or "psycho-sensorial" areas.]

[The same **methods** have been applied to the investigation of these centres, viz., stimulation and extirpation. **Stimulation.**—Ferrier found that electrical stimulation of the angular gyrus (monkey) caused movements of the eyeballs toward the side, with sometimes associated movements of the head, but he regarded these as reflex movements, so that for this and other reasons he, in his earliest contributions, considered the angular gyrus and adjacent parts as the "centre for vision." On stimulating the first temporo sphenoidal convolution, the monkey pricked the opposite ear, the pupils dilated, while the head and ears turned to the opposite side, it exhibited movements similar to those caused by a loud sound; these movements are also reflex phenomena, so that he located the "auditory centre" in this region, and on somewhat similar grounds. As the result of inferences from the stimulation and extirpation of other parts, he referred the centres for smell and taste to the tip of the temporo-sphenoidal lobe, and for touch to the hippocampus major, but all these statements have not been confirmed.]

[Goltz experimented on dogs by **washing away** the cortex cerebri, and found that when a sufficient amount of the gray matter is removed, and after recovery from the immediate effects of the operation, there is a peculiar defect of vision and other sensory defects, but so far Goltz has not found that there is any difference in this respect between removal of the anterior and posterior lobes of the dog's brain. The dog is not blind, as it can see and use its eyes to avoid obstacles, but it seemed as

if the animal failed to recognize food or flesh *as such*, when placed before it; while exhibitions which before the operation greatly excited the dog, ceased to do so. Goltz caused his servant to dress himself in a mummer's red colored garb, which previously had greatly excited the dog, but after the operation the dog, although it was not blind, was no longer excited thereby. Nor was it afterward cowed by the appearance of a whip. After a time there was recovery to a certain extent if the animal was trained, whether by the deposition of new impressions, or by opening up new channels, or by the partial recovery of some parts of the gray matter not removed, it is impossible to say.]

[Munk has mapped out the surface of the brain into a series of "sensory" or psycho-sensorial centres, but he distinguishes between complete and total extirpation of these centres and the phenomena which follow these operations.]

When these *centres* are *partially* disorganized, the mechanism of the sensory activity may remain intact, but "the conscious link is wanting." A dog with its centres thus destroyed, sees, hears, or smells, but it no longer knows what it sees, hears, or smells. These centres are in a certain sense the seat of experience that has been acquired through the organs of sense. **Stimulation** of these centres may give rise to movements, such as occur when sudden intense sensory impressions are produced. These movements, therefore, are to be regarded as reflex, partly as extensive coördinated reflex movements, and are in no way to be confounded with the movements which result from direct stimulation of the motor cortical centres. To this belongs dilatation of the pupil and the fissure of the eyelids, as well as lateral movements of the eyeball.

1. **The "visual area,"** according to Munk, embraces the outer convex part of the occipital lobe of the dog's brain. [This area and its connections are represented in Fig. 487. It is, therefore, in the area supplied by the posterior cerebral artery.] If the occipital lobes be completely destroyed, the dog remains permanently blind (**"cortical** or **absolute blindness"**). If, however, only the central circular area be destroyed, there is loss of the conscious visual sensation, which may be called **"psychical blindness"** (*Munk*) [a condition of visual defect like that observed by Goltz in the dog, in which the dog saw an object, *e. g.*, its food, but failed to recognize it as such. There is a certain amount of recovery if the whole visual area be not removed. According to Schäfer, the visual area of the cerebral cortex in the monkey comprises the whole of the occipital lobe, and perhaps a part of the angular gyrus. He finds, with Munk, that removal of one occipital lobe is followed by **hemianopia**, *i. e.*, blindness in the lateral half of each retina corresponding to the side operated on. The blindness passes off. Removal of both occipital lobes is said to produce total and permanent blindness, whereas destruction of the cortex of both angular gyri is not followed by any appreciable permanent defect of vision. Ferrier, however, does not accept these statements.]

FIG. 487.

Course of the psycho-optic fibres (after *Munk*).

[Ferrier and Yeo find that after operations conducted antiseptically, removal of both occipital lobes (monkeys) does not cause any recognizable disturbance of vision, or other bodily or mental derangement, provided the lesion does not extend beyond the parieto-occipital fissure. Nor does destruction of both angular gyri cause permanent loss of vision; such loss of vision lasts only three days, so that in Ferrier's original experiments, the animals lived for too short a time after the operation, to enable a just conclusion to be arrived at. Destruction of both angular gyri and occipital lobes causes total and permanent blindness in both eyes in monkeys, without any impairment of the other senses or motor power. This region Ferrier calls the "occipito-angular region."

[**Stimulation** of the *angular gyrus* causes movements of the eyes to the opposite side, with closure of the eyelids and contraction of the pupil. The eyeballs were directed upward or downward according as the electrodes were applied to the anterior or posterior limb of the angular gyrus (*Ferrier*). Stimulation of the whole of the cortex of the occipital lobe, including its mesial and under surfaces, causes conjugate deviation of the eyes to the opposite side, the direction of movement varying with the position of the electrodes.]

Mauthner denies the existence of cortical blindness, and believes that, after destruction of the middle of the visual centre, the reason why the dog does not recognize the object with the opposite eye is because, owing to there being only indirect vision, there is no distinct impression on the retina. The position of the visual centre has been variously stated by different observers. According to Ferrier, in the dog it lies in the occipital part of the III primary convolution, near the spot marked *e, e, e*, in Fig. 483; according to his newer researches, in the occipital lobe and gyrus angularis.

Connection with the Retina.—Munk asserts that in dogs *both* retinæ are connected with each visual cortical centre, and in such a manner that the greatest part of each retina is connected with the *opposite* cortical centre, and only by its most external lateral marginal part with the centre of the *same* side (Fig. 487). If we imagine the surface of *one* retina to be projected upon the centres, then the most external margin of the first is connected with the centre of the *same* side, the inner margin of the retina with the inner area of the *opposite* centre, the upper margin with the anterior area, and the lower marginal part of the retina with the posterior area of the opposite side. The (shaded) middle of the centre corresponds to the position of direct vision of the retina of the *opposite* side (compare § 344).

Stimulation of the visual centre in dogs causes movements of the eyes toward the other side, sometimes with similar movements of the head and contraction of the pupils. If one eye be excised from newborn dogs the opposite visual centre after several months is less developed (*Munk*). After **extirpation** of the visual centre in young dogs, the channels which connect it with the optic nerve undergo degeneration (*Monakow*) (§ 344).

In monkeys, the centre occupies the occipital lobe. Unilateral destruction causes temporary blindness of the halves of *both* retinæ, *i. e.*, hemianopia on the side of the injury. The visual centre in pigeons (Fig. 483, IV, where 1 is placed) lies somewhat behind and internal to the highest curvature of the hemispheres (*M'Kendrick, Ferrier, Musehold*). The visual centre in the frog lies in the optic lobe (*Blaschko*).

[The **visual path** is along the optic nerve to the chiasma, where the fibres from the nasal half of each retina cross to the optic tract, some of the fibres perhaps becoming connected with the external corpora geniculata, and some with the pulvinar of the optic thalamus and corpora quadrigemina, while the great mass sweeps backward to the occipital lobes as the optic expansion of Gratiolet. Destruction of this path behind the chiasma causes **hemiopia** or **hemianopia**, and certain diseases of the occipital cortex cause a similar result. Perhaps, however, there is another centre in the angular gyrus (and supra-marginal lobe), for in cases of word blindness disease has been found in these regions. Sometimes flashes of light or the appearance of a ball of fire form the aura in epilepsy, and Hughlings-Jackson thinks that discharging lesions of the right occipital lobe cause colored vision more frequently than on the left.]

2. **The centre for hearing**, or "**auditory area**," lies in the **dog**, according to Ferrier, in the region of the second primary convolution at *f, f, f* (Fig. 483, II), while in the **monkey** and **man** it is in the first temporal or temporo-sphenoidal gyrus (Ferrier's centre, No. 14). Munk locates it in the same region. According to Munk, destruction of the entire region causes deafness of the *opposite* ear, while destruction of the middle shaded part alone causes "**psychical deafness**" ("*Seelentaubheit*"). Electrical irritation of the upper two-thirds of the superior temporal convolution is followed by a reaction which closely resembles that produced by a sudden fright, or that produced by a sudden unexpected noise. [There is a quick retraction of the opposite ear, *i. e.*, "pricking" of the ear as if toward the supposed origin of the sound, combined generally with turning of the head and eyes to that side, and dilatation of the pupil.] Ferrier locates the centre for hearing in the monkey in the *superior temporo-sphenoidal convolution*, and he finds that when the centres on both sides are *extirpated*, the animal is absolutely deaf; it takes no cognizance of a pistol fired in its neighborhood. [From his experi-

ments on monkeys, Schäfer denies absolutely the conclusions of the above-named experiments. Schäfer points out that it is not difficult to substantiate hearing in monkeys; it is difficult to substantiate deafness, for quite normal monkeys will often fail to pay the least attention to loud sounds. In six monkeys, Schäfer asserts that after more or less complete destruction of the superior temporal gyrus on both sides, hearing was not perceptibly affected. In one case, both temporal lobes were completely removed without any permanent diminution in the acuteness of hearing. These results are opposed to the ordinary clinical teaching on this subject.] In **man,** injuries to the first and second temporo-sphenoidal convolutions on one side do not appear to cause complete deafness of one ear, as it seems that the sense of hearing for each ear is perhaps represented on both sides. Bilateral lesions of these convolutions in man cause complete deafness. Disease of these two convolutions is associated with **word deafness** (p. 763). Wernicke cites the case of a person first affected with word deafness, who afterward became completely deaf; and after death, a bilateral lesion was found in the first temporo-sphenoidal convolution. These convolutions are supplied with blood by the middle cerebral or Sylvian artery.

[The **auditory paths** are from the auditory nuclei in the medulla oblongata through the pons, where they perhaps cross into the tegmentum, thence into the "sensory crossway," and onward to the auditory centre.]

[**Auditory Auræ.**—Equally important with these effects of disease are the sensory impressions, or "**auræ,**" which sometimes usher in an attack of epilepsy; sometimes these auræ consist of sounds or noises, and in these cases the seat of the disease is often in the first temporo-sphenoidal convolution.]

[3. **The olfactory centre** has not been so definitely settled as some of the others. There is strong presumptive evidence that it is situated in the hippocampal region of the temporal lobe, at its lower extremity. This view is strengthened by the anatomical relations of this region to the olfactory tract and anterior commissure (*Ferrier*). M'Lane Hamilton has recorded a case of epilepsy ushered in by an aura of a disagreeable odor, in which there was atrophy of the gray matter of the right uncinate gyrus.]

[**Olfactory Path.**—Although the outer root of the olfactory tract runs direct to the uncinate gyrus, in *hemianæsthesia* resulting from injury to the "sensory crossway," smell is lost on the opposite side, while it is lost on the same side when the uncinate gyrus is involved. It may be that the impulses go first to their own side, and cross afterward.]

[4. We do not know the **centre for taste,** and even the course of the nerve of taste is disputed. Ferrier places it close to that of smell.]

On stimulating the subiculum in monkeys, dogs, cats, and rabbits, he observed peculiar movements of the lips and partial closure of the nostrils on the same side (§ 365). In man, subjective olfactory and gustatory perceptions are regarded as irritative phenomena, while loss of these sensory activities, often complicated with other cerebral phenomena, is regarded as a symptom of their paralysis.

[The **gustatory path** crosses in the posterior part of the posterior segment of the internal capsule. While Gowers admits that the chorda tympani is the nerve of taste for the anterior two-thirds of the tongue, he thinks that it reaches the facial nerve from the spheno-palatine ganglion through the Vidian nerve. He denies that the glosso-pharyngeal is concerned in taste, and "he believes that taste impressions reach the brain solely by the roots of the 5th nerve." He admits that the nerves of taste to the back part of the tongue may be *distributed* with the glosso-pharyngeal, reaching them through the otic ganglion by the small superficial petrosal and tympanic plexus.]

[5. Ferrier places the centre for **tactile** sensation in the **hippocampal region** close to the distribution of part of the posterior cerebral artery; so far this has not been confirmed. The centre for the sensation of **pain** has not been defined; probably it is very diffuse. **The limbic lobe,** according to Broca, includes the **hippocampal convolution** and the **gyrus fornicatus.** Ferrier found that removal of the hippocampal region resulted in a diminution of the sensibility of the opposite side of the body. Horsley and Schäfer observed only a temporary

hemianæsthesia, but they found that an extensive lesion of the **gyrus fornicatus** was followed by hemianæsthesia, more or less marked and persistent. From their experiments, these observers conclude that the limbic lobe "is largely, if not exclusively, concerned in the appreciation of sensations, painful and tactile."]

6. Munk is of opinion that the surface of the cerebrum in the region of the motor centres acts at the same time as "**sensory areas**" ("*Fühlsphäre*"), *i. e.*, they serve as centres for the *tactile* and *muscular* sensations and those of the innervation of the opposite side. He asserts that after injury to these regions the corresponding functions are affected.

According to Bechterew, the centres for the perception of tactile impressions, those of innervation, of the muscular sense, and painful impressions are placed in the neighborhood of the motor areas (dog); the first immediately behind and external to the motor areas, the others in the region close to the origin of the Sylvian fissure. [So far this agrees with the views of Starr (p. 749).]

Goltz, who first accurately described the disturbances of vision following upon injuries to the cortex in dogs, is opposed to the view of sensory localization. He believes that each eye is connected with both hemispheres. He asserts that the disturbance of vision, after injury to the brain, consists merely in a diminished color and space sense. The recovery of the visual perception of one eye after injury of one side of the cortex cerebri, he explains by supposing that this injury merely causes a temporary inhibition of the visual activity in the opposite eye, which disappears at a later period. Instead of psychical blindness and deafness he speaks of a "cerebro-optical and "cerebro-acoustical weakness."

377. **THERMAL CORTICAL CENTRES.**—Eulenberg and Landois discovered an area on the cortex cerebri, whose stimulation produced an undoubted effect upon the temperature and condition of the blood vessels of the opposite extremities. This region (Fig. 483, I, *t*) generally embraces the area in which, at the same time, the motor centres for the flexors and rotators of the fore limb (3), and for the muscles of the hind limb (4) are placed. The areas for the anterior and posterior limbs are placed apart; that for the anterior limb lies somewhat more anteriorly, close to the lateral end of the crucial sulcus. **Destruction** of this region causes increase of the temperature of the opposite extremities; the temperature may vary considerably (1.5° to 2°, and even rising to 13° C.). This result has been confirmed by Hitzig, Bechterew, Wood, and others. This rise of the temperature is usually present for a considerable time after the injury, although it may undergo variations. Sometimes it may last three months, in other cases it gradually reaches the normal in two or three days. In well-marked cases, there is a diminution of the resistance of the wall of the femoral artery to pressure, and the pulse curve is not so high (*Reinke*). Local electrical **stimulation** of the area causes a slight temporary cooling of the opposite extremities, which may be detected by the thermo-electric method. Stimulation by means of common salt acts in the same way, but in this case the phenomena of destruction of the centre soon appear. As yet, it has not been proved that there is a similar area for each half of the head. The cerebro-epileptic attacks (§ 375) increase the bodily temperature, partly owing to the increased production of heat by the muscles (§ 302), partly owing to diminished radiation of heat through the cutaneous vessels, in consequence of stimulation of the thermal cortical nerves. The experiments led to no definite results when performed on rabbits. According to Wood, destruction of these centres occasions an increased production of heat that can be measured by calorimetric methods, while stimulation causes the opposite result.

These experiments explain how psychical stimulation of the cerebrum may have an effect upon the diameter of the blood vessels and on the temperature, as evidenced by sudden paleness and congestion (§ 378, III).

[**Heat Production.**—Injury to the fore-brain has no effect on the temperature. * If the brain of a rabbit be punctured through the large fontanelle, and the stylet be forced through the gray matter on the surface, white matter and the median portion of the corpus striatum right to the base of the brain, there is a rapid rise of the temperature which may last several days. Injury to the gray cortex does not affect the temperature. After puncture of the corpus striatum, the highest temperature is reached only after twenty-four to seventy hours, but when the puncture reaches the base of the brain this result occurs in two to four hours. Electrical stimulation of these areas causes the same effect on the temperature. Direct injury to certain parts of the brain is followed by a rise of the temperature—or fever. See also, p. 376, for further evidence of the existence of thermal centres. There is at the same time an increase of the O taken in, the CO_2 given off and a decided increase of the N given off, indicating an increase in the proteid metabolism, which points to an increased production of heat (*Aronsohn and Sachs, Richet, Wood*).]

General and Theoretical.—Goltz's View.—Goltz uses a different method to remove the cortex cerebri—he makes an opening in the skull of a dog, and by means of a **stream of water** washes away the desired amount of brain matter. He describes, first of all, **inhibitory phenomena**, which are temporary and due to a temporary suppression of the activity of the nervous apparatus, which, however, is not injured anatomically; this may be explained in the same way as the suppression of reflexes by strong stimulation of sensory nerves (§ 361, 3). In addition, there are the **permanent**

phenomena, due to the disappearance of the activity of the nervous apparatus, which is removed by the operation. A dog, with a large mass of its cerebral cortex removed, may be compared to an eating, complex, reflex machine. It behaves like an intensely stupid dog, walks slowly, with its head hanging down; its cutaneous sensibility is diminished in all its qualities—it is less sensitive to pressure on the skin; it takes less cognizance of variations of temperature, and does not comprehend how to feel; it can with difficulty accommodate itself to the outer world, especially with regard to seeking out and taking its food. On the other hand, there is no paralysis of its muscles. The dog still sees, but it does not understand what it does see; it looks like a somnambulist, who avoids obstacles without obtaining a clear perception of their nature. It hears, as it can be wakened from sleep by a call, but it hears like a person just wakened from a deep sleep by a voice—such a person does not at once obtain a distinct perception of the sound. The same is the case with the other senses. It howls from hunger, and eats until its stomach is filled; it manifests no symptoms of sexual excitement.

Goltz supposes that every part of the brain is concerned in the functions of willing, feeling, perception, and thinking. Every section is, independently of the others, connected by conducting paths with all the voluntary muscles, and, on the other hand, with all the sensory nerves of the body. He regards it as possible that the individual lobes have different functions.

After removal of the anterior or **frontal convolutions** and the motor areas, there is at first unilateral motor and sensory paralysis and affection of vision. After some months, there remains only the loss of the muscular sense. If the operation be bilateral, the phenomena are more marked; there are innumerable purposeless associated movements, and the dogs become vicious. Marked and permanent disturbance in the capacity to utilize the impressions from the sense organs is not a necessary consequence of removal of the frontal convolutions.

Removal of the **occipital lobes** interferes most with vision. Bilateral removal makes the animal almost blind. The dog remains obedient and lively. There is no disturbance of motion or of the muscular sense.

Inhibitory Phenomena.—Injury to the brain also causes inhibitory phenomena, such as the disturbances of motion, the complete hemiplegia which is frequently observed after large unilateral injuries of the cortex cerebri; these are regarded by Goltz as inhibitory phenomena, due to the injury acting on lower infra-cortical centres, whose action inhibits movement, but these movements are recovered as soon as the inhibitory action ceases.

378. TOPOGRAPHY OF THE CORTEX CEREBRI.—A short *résumé* of the arrangement of convolutions, according to Ecker, is given in § 375.

I. The cortical **motor areas** for the face and the limbs are grouped around

FIG. 488.

Motor areas in man shaded—outer surface of the left side of human brain. Dotted area, the aphasic region (modified from Gowers).

FIG. 489.

Inner surface of right hemisphere. *AS*, area governing the movements of the arm and shoulder; *Tr*, of the trunk; *leg*, those of the leg; *Gf*, gyrus fornicatus; *CC*, corpus callosum; *U*, uncinate gyrus; *O*, occipital lobe.

the fissure of Rolando, including the ascending frontal, ascending parietal, and part of the parietal lobule (Fig. 488). The centre for the **face** occupies the lowest third of the ascending frontal convolution, and reaches also to the lowest fifth of the ascending parietal. The **arm** centre occupies the middle third of the ascending frontal and middle three-fifths of the ascending parietal convolutions, while the leg centre lies at the upper end of the sulcus and extends backward into the parietal lobule (and perhaps on to the superior frontal convolution) (Fig. 488).

The **leg** centre is continued over on to the paracentral lobule, opposite the upper end of the fissure of Rolando, in the marginal convolution on the mesial aspect of the hemisphere (Fig. 490), where the centres for the muscles of the trunk also exist (p. 748). The centre for **speech** is in the posterior part of the third left frontal convolution (Fig. 488).

Blood Supply.—These convolutions are supplied with blood from four to five branches of the Sylvian artery, which may sometimes be plugged with an embolon. When a clot lodges in this artery, the branches to the basal ganglia may remain pervious, while the cortical branches may be plugged (*Duret, Heubner*) (§ 381).

[**Hemiplegia** consists of motor paralysis of one-half of the body, although, as a rule, all the muscles are not paralyzed to the same extent; in some there may be complete paralysis, *i. e.*, they are entirely removed from voluntary control, while in others, there is merely impaired voluntary control. It may be caused by affections of the cortical areas or by lesion of the motor tracts above the medulla, and the paralysis is always on the side opposite to the lesion, owing to the decussation of the motor paths in the medulla. If the case be a severe one, we have what Charcot terms *hémiplégie centrale vulgaire*, or "complete hemiplegia," due to lesion of the cortical centres for the face, arm, and leg. While the arm and leg are completely paralyzed, the lower part of the face is more affected than the upper half, which is usually not much affected. All those movements under voluntary control, and

FIG. 490.

Transverse section of a cerebral hemisphere. CC*a*, corpus callosum; NC, caudate nucleus; NL, lenticular nucleus; IC, internal capsule; CA, internal carotid artery; *a*SL, lenticulostriate artery; ("Artery of hemorrhage"); F, A, L, T, position of motor areas governing the movements of the face, arm, leg, and trunk muscles of the opposite side (*Horsley*).

FIG. 491.



Scheme of the innervation of bilaterally associated muscles (*Ross*).

especially those that have been learned, are abolished, while the associated and bilateral movements, which even animals can execute immediately after birth, remain more or less unaffected. Hence, the hand is more paralyzed than the arm; this, again, than the leg; the lower facial branches more than the upper; the nerves of the trunk scarcely at all (*Ferrier*). When an extraordinary effort is made, it will be found that there is some impairment of the power of the muscles of mastication and respiration, although the muscles on opposite sides act together (*Gowers*). The trunk muscles, as a rule, are but slightly affected, or not all, as their centre is elsewhere. There may be alterations of sensibility and of the reflexes.]

[Conduction through the whole of the pyramidal fibres coming from one hemisphere may be interrupted, and yet all the muscles on the opposite side of the body are not paralyzed. The muscles which are comparatively unaffected are those associated in their action with the muscles of the opposite side, *e.g.*, the respiratory muscles. Broadbent assumes that such muscles have a bilateral representation in the motor areas. Suppose in Fig. 491, B, B′, to represent the cerebral cortex; M, M, motor centres in it; N, N′, nerve nuclei in the spinal cord or medulla oblongata; P, P′, the pyramidal tracts passing to spinal nuclei N, N′; *m*, *m′*, nerves proceeding from the last. 1, 2, 3, 4, 5, represent different lesions. In the case of muscles on opposite sides of the body, which act independently, *e.g.*, those of the hand, this is all the mechanism, but in bilaterally associated muscles there is another mechanism, viz., commissural fibres between the nerve nuclei, the one *c* conducting from right to left, and *c′* from left to right. When there is an injury at 1 or 3, impulses can still pass from the uninjured side M to N′ and through *c′* to the muscles *m*, *m′*. In this way, both muscles receive motor impulses from one hemisphere (*Ross*).]

Conjugate deviation of the eyes, with rotation of the head, is frequently present in the early period of hemiplegia, although it usually disappears. When a person turns his head to one side, there is an associated movement of certain of the ocular muscles with those of the neck. The head and eyes are usually turned to the side of the lesion; this is termed "conjugate deviation," so that the power of voluntarily moving the eyes and head to the paralyzed side is temporarily lost. The unopposed muscles rotate the head and eyes to the sound side. If the lesion be in the posterior part of the pons, the deviation is to the paralyzed side (*Prévost*).

[**Subsequent Effects.**—If there be a hemorrhage, say into these motor regions, or from the lenticulo-striate artery, so as to compress the pyramidal fibres in the knee and anterior two-thirds of the posterior segment of the internal capsule, then there is usually tonic or persistent contraction of the muscles affected. These tonic spasms may accompany the hemorrhage, or come on a few days after it, and set up the condition of **early rigidity.** The contraction or spasm—if any—accompanying the hemorrhage, is due to direct irritation of the pyramidal fibres, while that which comes on a few days later, and usually lasts a few weeks, is also due to irritation of these fibres, probably produced by inflammatory action in and around the seat of the lesion. The affected limb is stiff and resists passive movement. After a few weeks, **late rigidity** sets in and is persistent, and it is characterized by structural changes in the pyramidal paths which lead to other results. There is **secondary descending degeneration** in the pyramidal tracts, which causes "**contracture**" in the paralyzed limbs, while at the same time, the deep or tendinous and periosteal reflexes (ankle clonus, rectus clonus, and the deep reflexes of the arm tendons, are exaggerated). The spastic rigidity is usually more marked in the arm than in the leg, and it generally affects the flexors more than the extensors, so that the upper arm is drawn close to the trunk, the elbow, arm, and fingers flexed; in the leg, the extensors of the leg overcome the peronei. Hitzig has pointed out that the contracture is less during sleep, and after rest. The muscles at first can be stretched by sustained pressure, but after months or years, structural changes occur in the muscles, ligaments, and tendons, and the limbs assume a permanent and characteristic attitude.]

In hemiplegic persons, the power of the unparalyzed side is sometimes diminished, which is not sufficiently explained by the fact that some bundles of the pyramidal tracts remain on the *same* side (*Brown-Séquard, Charcot*).

Acquired Movements.—Some movements performed by man are learned only after much practice, and are only completely brought under the influence of the will after a time, such as the movements of the hand in learning a trade. Such movements are re-acquired only very slowly, or not at all, after injury to the motor areas in which they are represented. Those movements, however, which the body performs without previous training, such as the associated movements of the eyeballs, the face, and some of those of the legs, are rapidly recovered after such an injury, or they suffer but little, if at all. Thus, the facial muscles seem never to be so completely paralyzed after a lesion of the facial cortical centre, as in affections of the trunk of the facial nerve; the eye especially can be closed. Sucking movements have been observed in hemicephalous fœtuses.

Degeneration of the Pyramidal Tracts.—After destruction of the cortical motor areas, descending degeneration of the cortico-motor paths, or "*pyramidal tracts*," takes place (§ 365). Degenerative changes have been found to occur within the white matter under the cortex in the anterior two-thirds of the posterior segment of the internal capsule, [in the middle third of the crusta (Figs. 492, *, 493, L], pons, in the anterior pyramids of the medulla oblongata (Fig. 492), and thence they have been traced into the pyramidal paths (direct and crossed) of the spinal cord (*Charcot, Singer*). It is evident that lesions of these tracts at any part of their course must have the same result, viz., to produce hemiplegia. (For the subsequent effects, see p. 699.) In a case of congenital absence of the left forearm, Edinger found that the right central convolutions were less developed.

It is doubtful if the **muscular sense** is represented in the motor areas; Nothnagel supposes it to be located in the temporal parietal lobes. It is to be noted, however, that in man there may be general loss of the muscular sense or of motor representations, and, on the other hand, a pure motor paralysis without loss of the former.

Ataxic motor conditions, similar to those that occur in animals (p. 750), take place in man, and are known as *cerebral ataxia*.

The **position of the centres** is given at p. 746.

[But we may have **localized lesions** affecting one or more of the cortical motor areas; these are called **monoplegiæ**. Cases in man are now sufficiently numerous to permit of accurate diagnosis.] **Crural monoplegia** [rare lesions recorded in the convolutions at the upper end of the fissure of Rolando, and the continuation of this area on to the paracentral lobule of the marginal convolution],—**brachio-crural**, more common, in the upper and middle thirds of the

FIG. 492.



Secondary descending degeneration in middle third of right crus and medulla, after destruction of the cortical motor centres on the right side.

FIG. 493.



Horizontal section of the cerebral peduncle in secondary degeneration of the pyramidal tracts, where the lesion was limited to the middle third of the posterior segment of the internal capsule. F, healthy crusta; L, locus niger; P, internal third of the crusta on the diseased side; D, secondary degeneration in the middle third of the crusta; CQ, corpora quadrigemina with the iter below them.

ascending frontal and ascending parietal convolutions—**brachial, brachio-facial —facial,** the last in the lowest part of the central convolutions.

Paralysis of the muscles of the neck and throat indicates a lesion of the central convolutions, and so does paralysis of the muscles of the eye. Lesions of the cortex always cause simultaneous movements of the head and eyeballs.

Irritation of the Motor Centres.—If the motor centres are irritated by pathological processes, such as hyperæmia, or inflammation in a syphilitic diathesis —more rarely by tumors, tubercle, cysts, cicatrices, fragments of bone—there arise spasmodic movements in the corresponding muscle groups. This condition of a sudden discharge of the gray matter resulting in local spasms is called "**Jacksonian cerebral epilepsy.**"

[Convulsions and spasms may be discharged from motor cortical lesions, and

these, whether they affect the general or localized areas, give rise to unilateral convolutions and **monospasm** respectively.]

Monospasm.—According to the seat of the spasm, it is called *facial*, *brachial*, *crural monospasm*, etc. Of course these spasms may affect several groups of muscles. Bartholow and Sciamanna have stimulated the exposed human brain successfully with electricity.

Cerebral Epilepsy.—Very powerful stimulation of *one* side may give rise to *bilateral* spasms, with loss of consciousness. In this case, impulses are conducted to the other hemisphere by commissural fibres (§ 379).

Movements of the Eye.—Nothing definite is known regarding the centre in the cortex for voluntary *combined movements* of the eyeballs in man. In paralytic affections of the cortex and of the paths proceeding from it, we occasionally find both eyes with a lateral deviation. If the paralytic affection lies in one cerebral hemisphere, the **conjugate deviation** of the eyeballs is toward the sound side (p. 638). If it is situated in the conducting paths, after these have decussated, viz., in the pons, the eyes are turned toward the paralyzed side (*Prévost*).

If the part be irritated so as to produce spasms in the opposite side of the body, of course the eyes are turned in the direction opposite to that in pure paralysis. Instead of the lateral deviation of the eyeballs already described, there is occasionally in cerebral paralysis merely a *weakening* of the lateral recti muscles, so that during rest the eyes are not yet turned toward the sound side, but they cannot be turned strongly toward the affected side (*Leichtenstern*, *Hunnius*). The centre for the levator palpebræ superioris appears to be placed in the angular gyrus (*Grasset*, *Landouzy*).

II. The Centre for Speech.—The investigations of Bouilland [1825], Dax [1836], Broca [1861], Kussmaul, Broadbent and others have shown that the **third left frontal convolution** of the cerebrum (Figs. 484, F3, and 488) is of essential importance for speech, while probably the island of Reil is also concerned. The island is deeply placed, and is seen on lifting up the overhanging part of the brain called the operculum, lying between the two branches of the Sylvian fissure (S). The motor centres for the organs of speech (lips, tongue) lie in this region, and here, also, the psychical processes in the act of speech are completed. In the great majority of mankind, the centre for speech is located in the *left* hemisphere. The fact that most men are *right-handed* also points to a finer construction of the motor apparatus for the upper extremity, which must also be located in the left hemisphere. Men, therefore, with pronounced *right-handedness* ("droiters") are evidently *left-brained* ("gauchers du cerveau"—*Broca*). By far the greater number of mankind are "*left-brained speakers*" (*Kussmaul*); still there are exceptions. As a matter of fact, cases have been observed of *left-handed* persons who lost their power of speech after a lesion of the *right* hemisphere (*Ogle*). Investigations on the brains of remarkable men have shown that in them the third frontal convolution is more extensive and more complex than in men of lower mental calibre. In deaf mutes it is very simple; microcephales and monkeys possess only a rudimentary third frontal (*Rüdinger*).

The **motor tract for speech** passes along the upper edge of the island of Reil, then into the substance of the hemispheres internal to the posterior edge of the knee of the internal capsule; from thence, through the crusta of the left cerebral peduncle into the left half of the pons, where it crosses then into the medulla oblongata, which is the place where all the motor nerves (trigeminus, facial, hypoglossal, vagus and the respiratory nerves) concerned in speech arise. Total destruction of these paths, therefore, cause total aphasia; while partial destruction causes a greater or less disturbance of the mechanism of articulation, which has been called "**anarthria**" by Leyden and Wernicke.

Conditions.—Three activities are required for speech—(1) the normal movement of the vocal apparatus (tongue, lips, mouth and respiratory apparatus); (2) a knowledge of the signs for objects and ideas (oral, written and imitative or mimetic signs); (3) the correct union of both.

Aphasia (*ἀ* priv. and *φάσις* speech)—Injury of the speech centre causes either a loss or more or less considerable disturbance of the power of speech. The loss of the power of speech is called "*aphasia.*" [Aphasia, as usually understood,

means the partial or complete loss of the power of articulate speech from cerebral causes.]

The following **forms** of aphasia may be distinguished:—

1. **Ataxic aphasia** (or the oro-lingual hemiparesis of Ferrier), *i. e.*, the loss of speech owing to inability to execute the various movements of the mouth necessary for speech. Whenever such a person attempts to speak, he merely executes incoördinated grimaces and utters inarticulate sounds. [The muscles concerned in articulation, however, are not paralyzed, but there is an absence of coördination of these muscles due to disease of the cortical centre.] Hence, the patient cannot repeat what is said to him. Nevertheless, the *psychical* processes necessary for speech are completely retained, and all words are remembered; and hence, these persons can still give expression to their thoughts graphically or by *writing*. If, however, the finely adjusted movements necessary for writing are lost, owing to an affection of the centre for the hand, then there arises at the same time the condition of **agraphia**, or inability to execute those movements necessary for writing. Such a person, when he desires to express his ideas in writing, only succeeds in making a few unintelligible scrawls on the paper. Occasionally such patients suffer from loss of the power of imitation or the execution of particular movements of the limbs and body constituting *pantomime* speech or **amimia** (*Kussmaul*).

2. **Amnesic Aphasia,** or Loss of the Memory of Words.—Should the patient, however, hear the word, its significance recurs to him. The movements necessary for speech remain intact; hence, such a patient can at once repeat or write down what is said to him. Sometimes only certain kinds of words are forgotten, or it may be even only parts of certain words, so that only part of these words is spoken. [Nouns and proper names usually go first.] Cases of amnesic aphasia, or the mixed ataxic-amnesic form of disturbance of speech, point to a lesion of the third frontal convolution and of the island of Reil on the *left* side. Another form of amnesic aphasia consists in this that the words remain in one's memory but do not come when they are wanted, *i. e.*, the association between the idea and the proper word to give expression to it is inhibited (*Kussmaul*). It is common for old persons to forget the names of persons or proper names; indeed, such a phenomenon is common within physiological limits, and it may ultimately pass into the pathological condition of **amnesia senilis.** Among the disturbances of speech of *cerebral* origin, Kussmaul reckons the following:—

3. **Paraphasia,** or the inability to connect rightly the ideas with the proper words to express these ideas, so that, instead of giving expression to the proper ideas, the sense may be inverted, or the form of words may be unintelligible. It is as if the person were continually making a "slip of the tongue."

4. **Agrammatism** and **ataxaphasia,** or the inability to form the words grammatically and to arrange them synthetically into sentences. Besides these, there is—

5. A pathological slow way of speaking (**bradyphasia**), or a pathological and stuttering way of reading (**tumultus sermonis**), both conditions being due to derangement of the cortex (*Kussmaul*). The disturbances of speech depending essentially upon affections of the *peripheral* nerves, or of the muscles of the organs of the voice and speech, are already referred to in §§ 319, 349, and 354.

[In **word blindness,** the person cannot name a letter or a word, so that he cannot understand symbols, such as printed or written words, or it may be any familiar object, although he can see quite well, while he can speak fluently and write correctly.]

[In **word deafness,** the person hears other sounds and is not deaf, but he does not hear words.]

Fig. 494. Fig. 495.



Schemes of aphasia. A, centre for auditory images; M, for motor images; B, perception centre; Oc, eye; E, reading centre; 1 to 7, lesions (*Lichtheim*).

[The study of aphasia in its various forms is simplified by a study of the mode of **acquisition of language** by a child. The child hears spoken words and obtains auditory memories or impressions of these sounds (called by Lichtheim "**auditory word representations**"), and this must form the starting-point of language, and by and by it begins to coördinate its muscles to produce

sounds imitative of these. Thus we have two centres, one for "**auditory images**" (Fig. 494, A), and the other for "**motor images**" (Fig. 494, M), and these two must be connected, thus establishing a reflex arc. There is a receptive and an emissive department as represented in the scheme. We must assume the existence of a higher centre (B), "in which concepts are elaborated," where these sounds become intelligible. Volitional language requires a connection between B and M, as well as between A and M. But we have also **reading** and **writing**. Suppose O to represent a centre for visual impressions (printed words or writing): these we can understand through the connection between such visual impressions and auditory impressions, whereby a path is established through OA (Fig. 495). In reading aloud, however, the oro-lingual muscles must be coördinated, so we have the path OAM opened up. In writing, or copying written characters, the movements of the hand are special, and perhaps require a special centre, or at least a special arrangement of the channels for impulses in the centre; the movements are learned under the guidance of ocular impressions, so we connect O and E, E being the centre guiding the movements in writing. As to volitional writing, the impulse passes through M—but does it pass directly to E, or indirectly through A? Lichtheim assumes that it goes direct from M to E. It is evident that there are seven channels which may be interrupted, each one giving rise to a different form of aphasia (1 to 7).]

[Looked at from another point of view, either the ingoing (*a*) or outgoing (*m*) channels or centres, or the commissural fibres between both, may be affected. If the motor centre is affected, we have Wernicke's "**motor aphasia**;" if the sensory, his "**sensory aphasia.**"]

[In the most common form, or **ataxic aphasia** (*Kussmaul*), which was that described by Broca, or the "motor aphasia" of Wernicke, the lesion is in Fig. 494, in M., *i. e.*, in the motor, or what Ross calls the emissive department. In such a case, it is obvious that there will be **loss of** (1) volitional speech, (2) repetition of words, (3) reading aloud, (4) volitional writing, and (5) writing to dictation; while there will **exist** (*a*) understanding of spoken words, (*b*) also of written words, (*c*) and the faculty of copying. If the lesion be in A, we have the "sensorial aphasia" of Wernicke, *i. e.*, in the acoustic word centre; we find **loss of** (1) understanding of spoken language, (2) also of written language, (3) faculty of repeating words, (4) and of writing to dictation, (5) and of reading aloud; there will **exist** (*a*) the faculty of writing, (*b*) of copying words, and (*c*) of volitional speech, but the volitional speech is imperfect, the wrong word being often used, so that there is the condition of "**paraphasia.**" If the connection between A and M be destroyed, other results will follow, and such cases of "commissural" aphasia have been described by Wernicke. If the interruption be between B and M, we have a not uncommon variety of motor aphasia (4), when there is **loss of** (1) volitional speech, and (2) volitional writing, and there **exist** (*a*) understanding of spoken language, (*b*) of written language, (*c*) and the faculty of copying; but it differs from Broca's aphasia in that there also exists the faculty (*d*) of repeating words, (*e*) of writing to dictation, (*f*) and of reading aloud. If the lesion is in Mm (5), the symptoms will be those of Broca's aphasia, but there will exist (1) the faculty of volitional writing, and (2) of writing to dictation. Many examples of this occur where patients have lost the faculty of speaking, but can express their thoughts in writing. In lesions of the path A B (6), there will be **loss of** (1) understanding of spoken language, and (2) of written language, and there will **exist** (*a*) volitional speech (but it will be paraphasic), (*b*) volitional writing (but it will have the characters of paragraphia), (*c*) the faculty of repeating words, (*d*) reading aloud, (*e*) writing to dictation, and (*f*) power of copying words. The person will be quite unable to understand what he repeats, reads aloud, or copies.]

FIG. 496.



[Fig. 496 shows diagrammatically the conditions in motor and sensory aphasia. From the eye and ear centripetal fibres (v and a) ascend to terminate in the visual (V) and auditory centres (A), in the cortex, while afferent fibres (s, s′, s″), indicated by dotted lines, also pass from the articulations, muscles of the hand, and orbit to the cerebrum. The dotted lines on the surface of the cortex represent the association system of fibres which connects the centres with each other. The centres for vocal (V) and written expression (W) are connected by centrifugal fibres, m and m′, with the hand and larynx respectively (*Ross*).]

III. **The thermal centre** for the extremities is associated with the motor areas (§ 377). Injury or degeneration of these areas causes inequality of the temperature on both sides (*Bechterew*).

IV. The sensory regions are those areas in which conscious perceptions of the sensory impressions are accomplished. Perhaps they are the substratum of sensory perceptions, and of the memory of sensory impressions.

1. **The visual centre,** according to Munk, includes the occipital lobes (Fig. 484, o^1, o^2, o^3), while, according to Ferrier, it also includes the angular gyrus. Huguenin observed, in a case of long-standing blindness, consecutive disappearance of the occipital convolutions on both sides of the parieto-occipital fissure, while Giovanardi, in a case of congenital absence of the eyes, observed atrophy of the occipital lobes, which were separated by a deep furrow from the rest of the brain. Stimulation of the centre gives rise to the phenomena of light and color. Injury causes disturbance of vision, especially hemiopia of the same side (§ 344—*Westphal*). When *one* centre is the seat of irritation, there is photopsia of the same halves of both eyes (*Charcot*). Stimulation of both centres causes the occurrence of the phenomena of light or color, or visual hallucinations in the entire field of vision. Cases of injury to the brain, where the sensations of light and space are quite intact, and where the color sense alone is abolished, seem to indicate that the color sense centre must be specially localized in the visual centre (*Samelsohn*). After injury of certain parts, especially of the lower parietal lobe, "*psychical blindness*" may occur. A special form of this condition is known as "**word blindness**" or **alexia** (Coecitas verbalis), which consists in this, that the patient is no longer able to recognize ordinary written or printed characters (p. 761).

Charcot records an interesting case of psychical blindness. After a violent paroxysm of rage, an intelligent man suddenly lost the memory of visual impressions; all objects (persons, streets, houses) which were well known to him appeared to be quite strange, so that he did not even recognize himself in a mirror. Visual perceptions were entirely absent from his dreams.

Clinical observations on **hemianopia** (§ 344) show that the field of vision of each eye is divided into a larger outer and a smaller inner portion, separated from each other by a vertical line passing through the macula lutea. Each right or left half of both visual fields is related to *one* hemisphere; both left halves are projected upon the left occipital lobes, and both right upon the right occipital lobes (Fig. 487). Thus, in binocular vision, every picture (when not too small) must be seen in two halves; the left half by the left, the right half by the right hemisphere (*Wernicke*).

As a result of pathological stimulation of the visual centre, especially in the insane, visual spectres may be produced. Pick observed a case where the hallucinations were confined to the right eye. Celebrated examples of ocular spectra occurred in Cardanus, Swedenborg, Nicolai, J. Kerner, and Hölderlin.

After degeneration of the cortical centre, the fibres which connect the occipital lobes with the external geniculate body, the anterior corpora quadrigemina, pulvinar, these structures themselves, and the origin of the optic tract undergo degeneration (*v. Monakow*).

2. The **auditory centre** lies on both sides (crossed) in the temporo-sphenoidal lobes [according to Ferrier in the superior temporal convolution]; when it is completely removed, deafness results, while partial (left side) injury causes psychical deafness. [See p. 754 for contradictory results.] Among the phenomena caused by partial injury is *surditas verbalis* (**word deafness**), which may occur alone or in conjunction with coecitas verbalis. Wernicke found in all cases of word deafness softening of the first left temporo-sphenoidal convolution (p. 754). In left-handed persons, the centre lies perhaps in the right temporo-sphenoidal lobes (*Westphal*).

Clinical.—We may refer word blindness and word deafness to the aphataxic group of diseases, in so far as they resemble the amnesic form. A person word blind or word deaf resembles one who in early youth has learned a foreign tongue, which he has completely forgotten at a later period. He hears or reads the words and written characters; he can even repeat or write the words, but he has completely lost the significance of the signs. While an amnesic-aphasic person has only lost the key to open his vocal treasure, in a person who is word blind or word deaf even this is gone. From a case of recovery it is known that to the patient the words sound like a confused noise. Huguenin found atrophy of the temporo-sphenoidal lobes after long-continued deafness.

3. **Gustatory and Olfactory Centre.**—In the uncinate gyrus on the *inner* side of the temporo-sphenoidal lobe (especially on the inner side of that marked

U in Fig. 480), Ferrier locates the joint centres for smell and taste. These two centres do not seem to be distinct, locally, from each other.

4. **Tactile Areas.**—According to Tripier and others, all the *tactile* cerebral fields from different parts of the body coincide with the motor cortical centres for these parts [compare p. 755].

Occasionally, in epileptics, strong stimulation of the sensory centres, as expressed in the excessive subjective sensations, accompanies the spasmodic attacks (compare § 393, 12). Such epileptiform hallucinations, however, occur without spasms, and are accompanied only by disturbances of consciousness of very short duration (*Berger*).

Course of the Sensory Paths.—The nerve fibres which conduct impulses from the sensory organs to the sensory cortical centres pass through the *posterior third* of the *posterior limb of the internal capsule* between the optic thalamus and the lenticular nucleus (Fig. 500, S). Hence, section of this part of the internal capsule causes **hemianæsthesia** of the opposite half of the body (*Charcot*). In such a case, sensory functions are abolished—only the viscera retaining their sensibility. There may also be loss of hearing, smell, and taste,—and hemiopia (*Bechterew*).

Pathological.—In cases where there is more or less injury or degeneration of these paths, there is a corresponding greater or less pronounced loss of the pressure and temperature sense, of the cutaneous and muscular sensibility, of taste, smell, and hearing. The eye is rarely quite blind, but the sharpness of vision is interfered with, the field of vision is narrowed, while the color sense may be partially or completely lost. The eye on the same side may suffer to a slight extent.

V. Numerous cases of injury of the **anterior frontal region**, without interference with motor or sensory functions have been collected by Charcot, Ferrier, and others. On the other hand, enfeeblement of the intelligence and idiocy are often observed in acquired or congenital defects of the prefrontal region. In highly intellectual men, Rüdinger found in addition a considerable development of the temporo-sphenoidal lobe. According to Flechsig, there is no doubt that the frontal lobes and the temporo-occipital zone are related to intellectual processes, more especially the "higher" of these.

FIG. 497.



Relation of the fissures and convolutions to the surface of the scalp. +, most prominent part of the parietal eminence; *a*, convex line bounding parietal lobe below; *b*, convex line bounding the temporo-sphenoidal lobe behind (*R. W. Reid*).

Topography of the Brain.—The relations of the chief fissures and convolutions of the brain to the surface of the skull are given in Fig. 484, the brain being represented after Ecker. [Turner and others have given minute directions for finding the position of the different convolutions by reference to the sutures and other prominent parts of the skull. The annexed diagram by R. W. Reid shows the relations of the convolutions to certain fixed lines (Fig. 497).]

[The position of the **fissure of Rolando**, where its upper end joins the great longitudinal fissure, is obtained by measuring on the scalp, K, in the middle line, the distance between the glabella and the external occipital protuberance, or the inion, which, in ordinary heads, varies from 11 to 13 inches

(Fig. 499). Measured from before backward, along this line, the distance from the glabella to the top of the fissure is 55.7 per cent. of the length of the whole line. The direction of the fissure is downward and forward, and the long axis of the fissure forms, with the average mesial line, an angle of 67°, the angle opening forward. Its average length is 3⅜ inches.]

[The **fissure of Sylvius** is found by drawing a line from the external angular process of the frontal bone backward to the occipital protuberance, taking the nearest route between these two points. A point 1⅛ inch backward from the angular process along this line, marks the origin of the fissure; while a straight line drawn to the centre of the parietal eminence marks the course of its posterior limb. The parieto-occipital fissure will be two inches behind the upper end of the Rolandic fissure (*A. W. Hare*).]

[**Corpus Callosum.**—It is usually stated that the corpus callosum connects the convolutions of one side of the brain with those on the other, *i. e.*, that it is an inter-hemispherical commissure. D. J. Hamilton, however, is of opinion that it is not an inter-hemispheric commissure, but is due to cortical fibres coming from the cortex cerebri to be connected with the basal ganglia of the opposite side. On this view, the "corona radiata," as usually understood, consists only of the fibres which pass from the cerebral peduncle directly up to the cortex on the same side, and are contained in the posterior division and knee of the internal capsule. They correspond to the motor pyramidal tracts. Hamilton maintains that all the other fibres of the internal capsule pass into the **crossed callosal** tract, and instead of running directly up to the cortex on the same side, cross in the corpus callosum to the cortex of the opposite side. Beevor, relying on the examination of the brain of monkeys, by Weigert's method, denies that any fibres of the corpus callosum pass into the external or internal capsules, and he supports the old view that the corpus callosum is a commissure between the two hemispheres.]

Erb observed a case of its almost complete destruction without any considerable effect on motility, coördination, sensibility, reflexes, senses, speech, or any marked impairment of intelligence.

379. BASAL GANGLIA — MID-BRAIN. — [The **corpus striatum** consists of two parts, an intra-ventricular portion projecting into the lateral ventricle, the **caudate**

FIG. 498.

The fissures of Rolando and Sylvius are marked as broad dark lines. The shaded circles mark approximately the motor areas. 1, lower extremity; 2, 3, 4, 5, 6, and *a*, *b*, *c*, *d*, upper extremity; 7, 8, 9, 10, 11, oro-lingual muscles (*A. W. Hare*).

FIG. 499.



Head, skull, and cerebral fissures. OPr, occipital protuberance; EAP, external angular process; SF, Sylvian fissure; A, its ascending limb; FR, fissure of Rolando; PE, parietal eminence; MMA, middle meningeal artery; TS, tip of temporo-sphenoidal lobe; B, Broca's convolution; IF, inferior frontal sulcus; POF, parieto-occipital fissure; IPF, intra-parietal sulcus (*A. W. Hare*).

nucleus, and an extra-ventricular portion, the **lenticular nucleus**. Between the head of the caudate nucleus internally, and the lenticular nucleus externally, lies the anterior division of the internal capsule. The fibres which pass between these ganglia do not seem to form connections with them. The expanded head of the caudate nucleus is in front, and lies inside and around the front, of the lenticular nucleus, with which and the anterior perforated space it is continuous; it sweeps backward into a tailed extremity, which nearly surrounds the lenticular nucleus like a loop. The **lenticular nucleus** is biconvex in a horizontal section, but triangular and subdivided into three divisions when seen in a vertical section (Fig. 501). The older observations on the corpora striata in man may be dismissed, as a distinction was not drawn between injury to its two parts on the one hand and the internal capsule on the other.

[The **caudate nucleus and lenticular nucleus** in their development are coördinate with the development of the cortex cerebri. **Electrical stimulation** of these ganglia causes general muscular contractions in the opposite half of the body, which are due to simultaneous stimulation of the neighboring cortico-muscular paths. The same result is obtained as if all the motor cortical centres were stimulated simultaneously.]

Gilky did not observe movements on stimulating the corpus striatum in rabbits; it would seem that, in these animals the motor paths do not traverse these ganglia, but merely pass alongside of them.

[**Lesions** of the lenticular nucleus or of the caudate nucleus do not seem to give rise to any permanent symptoms, provided the internal capsule be not injured.] Destruction of the internal capsule, however, causes paralysis of motion or sensibility, or both, on the opposite side of the body, according to the part of it which is injured. The corpus striatum is quite insensible to painful stimulation (*Longet*).

Pathological.—In man, a lesion, not too small, destroying the anterior part of the corpus striatum is followed by permanent paralysis of the opposite side, provided the internal capsule is injured, but the paralysis gradually disappears, if the lenticular and caudate nucleus only are affected (compare § 365). Sometimes there is dilatation of the blood vessels in consequence of vasomotor paralysis (§ 377) if the posterior part is injured (*Nothnagel*); redness and a slightly increased temperature of the paralyzed extremities, at least for a certain time; swelling or œdema of the extremities; sweating; anomalies of the pulse detectable by the sphygmograph; decubitus acutus on the paralyzed side; abnormalities of the nails, hair, skin; acute inflammation of joints, especially of the shoulder. Later, **contracture** or permanent contraction of the paralyzed muscles takes place (*Huguenin, Charcot*). In some cases there is cutaneous anæsthesia, and occasionally enfeeblement of the sense organs of the paralyzed side, and both when the posterior third or sensory crossway of the posterior section of the internal capsule is affected. Usually, however, *hemiplegia* and *hemianæsthesia* occur together.

Optic Thalamus.—Ferrier did not observe any movements on stimulating the optic thalami with electricity. As the pulvinar, or posterior extremity of the optic thalamus, is in part the origin of the optic nerve, and is also connected by fibres with the cortex cerebri, it is probably related to the sense of sight. Injury to its posterior third in man, results in disturbance of vision (*Nothnagel*). Ferrier surmises that the sensory fibres pass through the optic thalami on their way to the cortex, so that when they are destroyed, insensibility of the opposite half of the body is produced. Removal of the optic thalamus, or destruction of the part in the neighborhood of the inspiratory centre in the wall of the third ventricle, influences the coördinated movements in the rabbit (*Christiani*).

We know very little definitely as to the functions of these organs. After injury to one thalamus, there has been observed enfeeblement or paralysis of the muscles of the opposite side, together with mouvements de manège; and sometimes hemianæsthesia of the opposite side, with or without affections of the motor areas, have been recorded. Extirpation of certain cortical areas (rabbit) is followed by atrophy of certain parts of the thalamus (*v. Monakow*).

[**Internal Capsule.**—In connection with the functions of the basal ganglia it is most important to remember their relation to the internal capsule. The corpus

striatum consists of an intra-ventricular part, the *caudate nucleus*; and an extra-ventricular part, the *lenticular nucleus*. The lenticular nucleus consists of three parts, best seen in a vertical section (501, 1, 2, 3), with white matter between them, the **striæ medullares.** The anterior limb of the internal capsule sweeps

FIG. 500.



Human brain, with the hemispheres removed by a horizontal incision on the right side. 4, trochlear; 8, acoustic nerve; 6, origin of the abducens; F, A, L, position of the pyramidal (motor) fibres for the face, arm, and leg; S, sensory fibres.

between the caudate and lenticular nucleus, while the posterior segment lies between the optic thalamus and the lenticular nucleus (Fig. 500). External to the first division of the lenticular nucleus is the **external capsule** (Figs. 500, 501), whose function is unknown. External to this is the **claustrum**, whose function is also

unknown. It is evident that hemorrhage into or about the basal ganglia is apt to involve the fibres of the internal capsule.] When the lenticulo-striate artery, or as it is called the "artery of hemorrhage," ruptures (Fig. 490, *a*SL), it may not only destroy the lenticular nucleus, but the internal capsule will be compressed; and the same is the case with the lenticulo-optic artery—the external capsule will tend to force the blood inward. We know that, in the **posterior segment** of the capsule, the volitional or pyramidal fibres lie in the following order from before backward—those for the face (and tongue) in the knee, in the anterior third those for the arm and hand, and in the middle third for the leg, and perhaps behind these those for the trunk (Fig. 500, F, A, L), so that a very small lesion in this region will affect a large number of these fibres, converging as they do like the rays of a fan from the motor cortical areas, where the arrangement of these centres is a supero-inferior one (Fig. 488), to become an antero-posterior one in the knee and posterior limb of the internal capsule (Fig. 500). The posterior third of this limb is sensory and is the "sensory crossway."

FIG. 501.



Frontal section through the right cerebral hemisphere in front of the soft commissure (posterior surface of the section).

[Horsley points out that hemorrhage from the lenticulo-striate artery affects in order the muscles of the face, arm, leg and trunk, while recovery is in the inverse order.]

[The **crura cerebri** Fig. 461, P), or cerebral peduncles, are two thick strands as they emerge above the pons, and as they are much larger than the pyramidal tracts, they must receive many fibres within the pons. A transverse section (Fig. 502) shows that, on them posteriorly and connecting them, are the corpora quadrigemina. (CQ). The crus proper is divided by the substantia nigra (SN) into a lower part, the **crusta** or basis, and an upper part, or **tegmentum.** The crusta is composed of ascending and descending nerve fibres; but the tegmentum, in addition to many nerve fibres, contains much gray matter with nerve cells. Near the middle is the "**red nucleus**" or "tegmental nucleus" (RN). Outside this is the fillet (F), a well-defined bundle of nerve fibres running upward from the pons. Above the nucleus, near the middle line, is the "posterior longitudinal bundle" (p. l. b), which is triangular in section. Above the tegmentum lie many nerve cells, the origin of the third nerve (III), and arranged around the iter is much gray matter.]

Injury to **one cerebral peduncle** causes, in the first place, violent pain and spasm of the opposite side, while the blood vessels on that side contract, and the salivary glands secrete. These phenomena of irritation are followed by paralytic symptoms of the *opposite* side, viz., anæsthesia (§ 365) and paresis, or incomplete voluntary control over the muscles, as well as paralysis of the vasomotor nerves. In affections of the cerebral peduncle in man, we must remember the relation of the oculomotorius to it, as the lattér is often paralyzed on the *same* side [while the

extremities, tongue, and half the face are paralyzed on the opposite side from the lesion].

The **middle third** of the **crusta** of the cerebral peduncle (Fig. 502) includes the direct pyramidal tracts (§§ 365, 378). The fibres of the **inner third** connect the frontal lobes with the cerebellum through the superior cerebellar peduncles. In the **outer third** are fibres which connect the pons with the temporal and occipital cerebral lobes (*Flechsig*). The fibres which pass from the tegmentum into the corona radiata conduct sensory impulses (*Flechsig*).

FIG. 502.



Scheme of transverse section of the cerebral peduncles. CQ, corpora quadrigemina; Aq, aqueduct; p.l.b., posterior longitudinal bundle; F, fillet or lemniscus; RN, red nucleus; SN, substantia nigra; III, third nerve; Py, pyramidal tracts; FC, fronto-cerebellar; and TOC, temporo-occipital fibres of the crusta; CC, caudate-cerebellar fibres in upper part of crusta (after *Wernicke and Gowers*).

[The **pons varolii** contain ascending and descending fibres, as well as transverse ones, and, in addition, the continuation upward of gray matter from the medulla, special masses of gray matter, and the nuclei of certain cranial nerves. Its appearance in section necessarily varies with the region where the section is made. Fig. 503 is a transverse section through part of the seventh nerve. The lower part shows the superficial (s.t.f.) and deep (d.t.f.) transverse fibres, with the pyramidal fibres (Py) between them.]

Stimulation or section of the pons causes pain and spasms; after the section, there may be sensory, motor, and vasomotor paralysis, together with forced movements. For diagnostic purposes in man, it is important to observe if alternate hemiplegia be present.

[In lesions situated in the **lower half** of one side of the pons, there is facial paralysis on the same side as the lesion and paralysis (motor and sensory, and more or less complete) on the opposite side

FIG. 503.



Transverse section of the pons through part of the seventh nerve. × 2. F.R., formatio reticularis; VII, seventh nerve; Va, ascending root, and Vm, motor root of the fifth nerve; F, fillet; s.o., superior olive; s.l.b., superior longitudinal bundle; Py, pyramidal fibres; R, restiform body; M.P., middle peduncles ot cerebellum; d.t.f. and s.t.f., deep and transverse superficial fibres of the pons (after *Wernicke*).

FIG. 504.



Scheme of the fibres in the pons. PT, pyramidal tracts; F, facial fibres; *u*, upper; *l*, lower lesion; MO, medulla oblongata; DP, decussation of pyramids.

of the body—this is called **alternate paralysis**; while, if the lesion be in the **upper half** of one side of the pons, the facial paralysis is on the same side as the paralysis of the body. But the parts supplied by the 5th and 6th nerves may also be involved. This is explained by Fig. 504, where the upper facial fibres cross in the pons. Sudden and extensive lesions of the pons are frequently asso-

ciated with hyperpyrexia, the temperature often rising rapidly within an hour, perhaps from the gray matter in the floor of the 4th ventricle being affected; but whether it is due to some effect on a heat-regulating or heat-producing centre is uncertain. **Tumors** of considerable size may press on the pons without producing very marked symptoms, as tumors tend to push aside tissues, unless they be infiltrating in their character. Lesions of the transverse superficial fibres (**middle cerebellar peduncles**) often give rise to involuntary forced movements, there being a tendency to move to one side or the other.]

The Corpora Quadrigemina.—Destruction of these bodies *on one side* in mammals (or their homologues, the optic lobes in birds, amphibians, and fishes) causes actual *blindness*, which may be on the same or the opposite side, according to the relation of the fibres crossing at the optic chiasma (§ 344). *Total* destruction causes blindness of both eyes. At the same time, the reflex contraction of the pupil, due to stimulation of the retina with light, no longer takes place (*Flourens*), where the optic is the afferent and the oculomotorius the efferent nerve (§ 345). If the cerebral hemispheres alone be removed, the pupil still contracts to light, as well as after mechanical stimulation of the optic nerve (*H. Mayo*). Destruction of the corporo quadrigemina interferes with the complete harmony of the motor acts; disturbance of equilibrium and incoördination of movements occur (*Serres*). In **frogs**, Goltz observed not only awkward, clumsy movements, but at the same time the animals have to a large extent lost the power of completely balancing the body (p. 733). A similar result was observed in pigeons (*M'Kendrick*) and rabbits (*Ferrier*). Extirpation of the eyeball is followed by atrophy of the opposite anterior corpus quadrigeminum (*Gudden*).

According to Bechterew, the fibres of one optic tract pass through the anterior brachium (Fig. 500) into the anterior pair (nates) of the corpora quadrigemina; while those fibres which cross in the chiasma (Fig. 425) pass into the posterior pair (testes). According to this arrangement we have partial blindness, according as one or other pair of these bodies is destroyed.

[In **man**, very little is known regarding the effects of disease of the corpora quadrigemina, interference with the ocular muscles being the most marked symptom; but the incoördination of movement which has been observed may be due to pressure upon the superior cerebellar peduncle, while it is by no means certain that the defects of vision are directly due to lesions of these bodies.]

Stimulation of the Corpora Quadrigemina.—The corpora quadrigemina react to electrical, chemical, and mechanical stimuli. The results of stimulation are very variously stated. According to some observers, there is dilatation of the pupil on the same side; according to Ferrier, it may be the pupil on the opposite or on the same side. The stimulation may be conducted from the corpora quadrigemina to the medulla oblongata, and to the origin of the sympathetic, for, after section of the sympathetic nerve in the neck, dilatation of the pupil no longer takes place. According to Knoll, the contraction of the pupil observed by the older experimenters occurs only when the adjoining optic tract is stimulated. Stimulation of the right anterior corpus quadrigeminum causes deviation of *both* eyes to the left (and conversely); on continuing the stimulation, the head is turned to this side. On dividing the corpora quadrigemina by a vertical median incision, stimulation of one side causes the result to take place only on one side (*Adamük*). Ferrier observed signs of pain on stimulating these organs in mammals. Carville and Duret conclude from their experiments, that these organs are centres for the extensor movements of the trunk. Ferrier found, on stimulating one optic lobe in a pigeon, dilatation of the opposite pupil, turning of the head toward the other side and backward, movement of the opposite wing and leg; strong stimulation caused flapping movements of both wings. Danilewsky, Ferrier, and Lauder Brunton observed a rise of the blood pressure and slowing of the heart beat, together with deeper inspiration and expiration.

Bechterew ascribes all the phenomena, except those of vision itself, which accompany injury or stimulation of these bodies, to affections of deeper-seated parts. He asserts that the corpora quadrigemina contain neither the centre for the movements of the pupils nor that for the combined movements of the eyeballs; not even the centre for maintaining the equilibrium of the body. Stimulation of these bodies causes the animals to perform marked movements. Reflex phenomena, nystagmus, forced movements, and unsteadiness of the gait only occur, however, when the deeper parts are injured.

Pathological.—Lesions of the anterior pair in man, according to the extent of the lesion, cause disturbance of vision, failure of the pupil to contract to light, and even blindness; there may be paralysis of the oculomotorii on both sides. Disease of the posterior pair may be associated with disturbances of coördination (*Nothnagel*).

Forced Movements.—It is evident from what has been said regarding the importance of the corpora quadrigemina for the harmonious execution of move-

ments, that *unilateral* injury of such parts as are connected with them by conducting channels, must give rise to peculiar unilateral disturbance of the equilibrium, causing variations from the symmetrical movements of both sides of the body. These movements are called *forced movements*. To this class belong the "**mouvements de manège**," where the animal, instead of moving in a straight line, runs round in a circle; **index movements**, where the anterior part of the body is moved round the posterior part, which remains in its place, just like the movements of an index round its axis; and **rolling movements**, when the animal rolls on its long axis. All these forms of movement may pass into each other, and they are, in fact, merely different varieties of the same kind of movement. The parts of the nervous system whose injury produces these movements are the corpus striatum, optic thalamus, cerebral peduncle, pons, middle cerebellar peduncles, and certain parts of the medulla oblongata. Eulenburg observed index movements in the rabbit, after injury to the surface of the brain, and Bechterew observed the same in dogs. Forced movements, together with nystagmus and rotation of the eyeballs, are caused by injury to the olives (*Bechterew*). The statements of observers vary as to the direction and kind of movement produced by injuring individual parts. The following observations have been made: Section of the **anterior part of the pons**, and of the crura cerebelli causes index, or, it may be, rolling movements toward the other side; section of the **posterior** part of the same regions causes rolling movements toward the *same* side, while the same result is caused by a deeper puncture into the tuberculum acusticum, or into the restiform body. Section of one cerebral peduncle causes mouvements de manège, while the body is curved with the convexity toward the same side. The nearer to the pons the section is made, the smaller is the circle described; ultimately index movements occur. Injury to one optic thalamus produces results similar to puncture of the anterior part of the cerebral peduncle, because the latter is injured along with it at the same time. Injury to the anterior part of one optic thalamus causes the opposite kind of forced movement, viz., with the concavity of the body toward the injured side. Injury to the spinal portion of the medulla oblongata is followed by bending of the head and vertebral column, with the convexity toward the injured side, along with movements in a circle. When the anterior end of the calamus and the part above it are injured, the movements are toward the sound side.

Strabismus and **Nystagmus.**—Among the forced movements may be reckoned deviation of the eyeballs, strabismus or squinting, and involuntary oscillation of the eyeballs, constituting *nystagmus*. The latter condition occurs after superficial lesions of the restiform body, as well as of the floor of the 4th ventricle. A unilateral, deep, transverse injury, from the apex of the calamus upward as far as the tuberculum acusticum, causes the eye of the same side to squint downward and forward, that of the other side backward and upward. Section of both sides causes this condition to disappear (*Schwahn*). Hence, Eckhard assumes that the medulla oblongata is the seat of an apparatus controlling the movements of the eyes (*Eckhard*), which can be excited by sudden anæmia, *e. g.*, ligature of the cephalic arteries in a rabbit.

In pathological degeneration of the olivary body of the medulla oblongata in man, Meschede observed intense rotatory movements toward the *same* side.

Theory.—In order to explain the occurrence of forced movements, it is suggested that there is unilateral incomplete paralysis (*Lafarque*), so that the animal in its efforts to move onward leaves the paralytic side slightly behind the other, and hence there is a variation from the symmetry of the movements. Brown-Séquard regards the matter in exactly an opposite light, viz., as due to stimulation from injury, causing an excessive activity of one-half of the body. Henle ascribes the movements to *vertigo*, or a feeling of giddiness caused by the injury. In all operations on the central nervous system, where the equilibrium is deeply affected, there is a considerable increase in the number and depth of the respirations (*Landois*).

Other Effects.—Some observers noticed variations of the **blood pressure** and a change in the

number of heart beats after stimulation of the cortex cerebri, *e. g.*, after electrical stimulation of the motor areas for the extremities (*Bochefontaine*). Balogh observed acceleration of the **pulse**, on stimulating several points on the cortex cerebri of a dog, and from one point slowing of the pulse. Eckhard stimulated the surface of the brain in rabbits, and, as a rule, he observed that, as long as single crossed movements occurred in the anterior extremities, there was no effect upon the heart, but that the heart became affected as soon as other movements occurred. This consists in slow strong pulse beats, with occasional weaker beats, while at the same time the blood pressure is slightly increased (*Bochefontaine*). If the vagi be divided beforehand, the effect upon the pulse disappears, while the increase of the blood pressure remains. That psychical processes affect the action of the heart was known to Homer and Chrysipp. Bochefontaine and Lépine, on stimulating several points, especially in the neighborhood of the sulcus cruciatus in the dog, observed increased secretion of **saliva**, slowing of the movements of the stomach, peristalsis of the intestine, contraction of the spleen, of the uterus, of the bladder, and increased respirations. Bufalini, on stimulating those parts of the cortex which cause movements of the jaw, observed secretion of gastric juice with increase of the temperature of the stomach. Schiff, Brown-Séquard, Ebstein, Klosterhalfen, and others have observed that injury to the pons, corpus striatum, thalamus, cerebral peduncle, and medulla oblongata often causes hyperæmia and **hemorrhage** into the lung (according to Brown-Séquard, especially after injury to one side of the pons, which affects the opposite lung), under the pleura, in the stomach, intestine, and kidneys. Gastric hemorrhage is common after injury to the pons just where the cerebral peduncles join it. Similar phenomena have been observed in man after apoplexy or cerebral hemorrhage.

Specially interesting is the cerebral *unilateral* **decubitus acutus** or bedsore, described by Charcot, which always occurs on the paralyzed side of the body, *i. e.*, on the side opposite to the cerebral injury. It begins on the second or third day, rapidly causes enormous destruction and sloughing of the tissues on the back and lower extremities, and death soon takes place. The decubitus which occurs after spinal injuries, usually begins in the middle line of the buttocks, and extends symmetrically on *both* sides. In cases of unilateral injury to the spinal cord, the decubitus occurs on the *corresponding* side of the sacral region (p. 632).

FIG. 505.



Longitudinal section of an adult human brain. *Aq*, aqueduct of Sylvius; *B*, corpus callosum; *Ca*, anterior commissure; *Cm*, middle commissure; *Col*, lamina terminalis; *Cp*, posterior commissure; *FM*, foramen of Munro; *G*, fornix; *H*, pituitary body; *HH*, cerebellum; *MH*, corpora quadrigemina; *MH*, medulla oblongata; *P*, pons Varolii; *R*, spinal cord; *Sp*, septum lucidum; *I*, infundibulum; *Tch*, tela choroidea; *To*, optic thalamus; *VH*, cerebrum; *Z*, pineal gland; *I*, olfactory lobe and nerve; *II*, optic nerve.

[The **Pineal Gland** or **epiphysis cerebri** lies on the back of, and is connected with, the third ventricle (Fig. 505, *Z*). It projects backward between the corpora quadrigemina. It is originally developed as a hollow outgrowth from that part of the embryonic brain which becomes the third ventricle. The hollow centre usually disappears, while the distal portion becomes enlarged and is often lobulated. Its distal portion may terminate outside the skull; and in some animals there is developed in the median line of the skull an eye—**pineal eye**—arranged on the invertebrate plan, as in Anguis, Hatteria, etc. (*De Graaf, Spencer*) (§ 405).]

[The **pituitary body** or **hypophysis cerebri** consists of two lobes, different in origin and structure (Fig. 505, *H*). The *posterior lobe* is developed as a hollow outgrowth from the part of the embryonic brain connected with the third ventricle. It loses its cavity and its nervous tissue; is permeated by connective tissue and blood vessels; and is connected with the floor of the third ventricle by the infundibulum. The *anterior lobe* is developed as a tubular invagination of the stomodæum, *i. e*, from the ectoderm of the buccal cavity; but it soon loses its connection with this cavity as the upper end enlarges, and the stalk atrophies. In mammalia, the upper expanded end unites with the anterior lobe to form the pituitary body. For the effects of its removal, see § 103, V.]

380. STRUCTURE AND FUNCTIONS OF THE CEREBELLUM.—[**Structure.**—On examining a vertical section of a cerebral leaflet, we observe the following microscopic appearances: Externally is the pia mater with its blood vessels (Fig. 506, *a*), which penetrate into the gray matter; within is the medulla, composed of white fibres. The **gray matter** consists of *b*, a broad **outer** or **molecular** layer, largely composed of branched fibrils; and internal to it is *d*, the

"**granular,**" nuclear, or rust-colored layer. On the boundary line between these two, is the layer of Purkinje's cells, *c*. The **cells of Purkinje** form a single layer of large multipolar flask-shaped nerve cells, which have been compared to the branched antlers of a stag (Fig. 507). From their outer surface is given off a process which rapidly divides, and gives rise to a large number of smaller processes running outward in the outer gray layer. Some of these processes form part of the ground plexus of fibrils in this layer. An unbranched axial cylinder process is sent inward to the granular layers, where it becomes continuous with a nerve fibre—every cell of Purkinje being continuous with a straight unbranched medullated nerve fibre. The *unbranched* fibres run straight from the medulla through the granular layer, forming no connection with its granules. A second set of *branched* or anastomosing, often varicose, nerve fibres, finer than the foregoing, pass from the medulla into the granular layer, where they form a network which is continued

FIG. 506.



Vertical section of the cerebellum. *a*, pia mater; *b*, external layer; *c*, layer of Purkinje's cells; *d*, inner layer; *e*, medullary white matter.

FIG. 507.

Purkinje's cell, sublimate preparation. × 120.

into the molecular layer. The **granular layer** is composed of closely packed granules of two kinds; one is stained by hæmatoxylin, and the other with eosin (*Denissenko*). The hæmatoxylin stained cells are most numerous; they consist of a nucleus surrounded by protoplasm, and are what were formerly called granules. The eosin-stained cells, which are also stained by nigrosin (*Beevor*), are interposed in the course of medullated nerve fibres. The hæmatoxylin cells, called glia cells by Beevor, have processes, and form a network throughout the granular layer, which also extends into the molecular layer. This network is regarded as the continuation of the modified myelin of the nerve fibres, and it forms a capsule for the cells of Purkinje. The **molecular layer** consists of a ground substance, composed of a spongy network of fine fibrils, which seem to be of the nature of neuro-keratin, strengthened here and there by stronger fibres. In the meshes lies a homogeneous substance. Some of this substance is more condensed to form a *limitans externa* on the surface of the cerebellum, while on the boundary line next the granular layer the branches of the glia cells form a *limitans interna*, and between the two stretches the neuro-keratin network. Some small variocose nerve fibres exist in this layer continuous with those in the granular layer. The branched process of the **cells of Purkinje** is fibrillated, and the finer processes are composed also of fibrils, which are gradually distributed until they become isolated. It is suggested by Beevor that these fibrils bend at a right angle in a plane parallel to the surface, and rearrange themselves as fibres

surrounded by a medullated sheath, and that these fibres run inward through the molecular and granular layers—as the branched fibres—to the medulla.]

Function.—Injuries of the cerebellum cause disturbances in the harmony of the movements of the body. Most probably, the cerebellum is a great and important central organ for the finer coördination and integration of movements. The fact that it is connected with all the columns of the spinal cord and with all the central ganglionic masses, renders this very probable. The direct cerebellar tracts from the lateral column of the cord conduct sensory impressions to the cerebellum, and thus indicate the posture of the trunk. The cerebellum may affect the motor nerves of the cord through fibres which pass downward in the lateral columns of the cord from the restiform bodies (*Flechsig*). Injury of the cerebellum neither produces disturbance of the psychical activities, nor does it interfere with the will or consciousness. Injuries to the cerebellum itself do not give rise to pain.

According to Schiff, the cerebellum does not actually regulate the coördination of movements. According to him, there is a mechanism on both sides of the middle line, which increases all the complicated muscular movements—not only those for powerful contractions, but also the peculiar fine movements which fix the limbs and joints. Luciani asserts that destruction of the cerebellum produces a condition of incomplete tonus, there being a want of energy to control the voluntary muscles. Each half of the organ acts on both halves of the body.

Injury or Removal of Cerebellum.—The immediate results produced by injury to or removal of the cerebellum have been admirably described by Flourens (Fig. 508). On removing the most superficial layers in a **pigeon**, the animal merely showed signs of weakness and interference with the uniformity of its movements. On removing more of the cerebellum, the animal became greatly excited, and made violent irregular movements, which did not partake of the character of convulsions. The sensorium was unaffected, while vision and hearing were intact. Coördinated movements, such as walking, flying, springing, and turning, could be executed but imperfectly. After removal of the deepest layers, the power of executing the above-named movements was completely abolished. On placing the pigeon on its back, it could not get on its legs; at the same time it made continually the greatest exertions in its movements, but these were always incoördinated, and therefore without any satisfactory result. The will, intelligence, and perception remained intact; the animal could see and hear, and sought to avoid obstacles placed in its way. It gradually exhausted itself in fruitless efforts to get on its legs, and ultimately remained in its abnormal position, quite exhausted. Flourens concluded from these experiments that the cerebellum is the centre for coördinating voluntary movements. Lussana and Morganti regard the cerebellum as the seat of the muscular sense.

FIG. 508.

Pigeon with its cerebellum removed.

[**Extirpation in Mammals.**—The dangers attending this operation are so great, that but few animals survive. Luciani, however, by using antiseptic and other precautions, has been able to operate so that complete cicatrization was obtained, the animal (young bitch) being restored to health for a few months. The cerebellum alone was removed, but not its peduncles. As in all other similar operations, we must distinguish sharply the phenomenon manifested during recovery from those after complete recovery. During the *first period* of six weeks, from the time of the operation until complete recovery, the symptoms are those of injury and irritation of the divided peduncles, along with those resulting from the removal of the organ. They are clonic contractions of the

muscles of the fore limb, neck, and back, passing into tonic contractions when the animal attempts to move, and also weakness of the hind legs, so that all the normal voluntary movements are interfered with, *i. e.*, incoördinated, although these symptoms may be explained by the injury to adjoining parts. There was no sensory disturbance or loss of the muscular sense, although closing the eyes rendered standing impossible. As recovery takes place, these symptoms disappear, and the animal enters on the *second period*, where the symptoms depending on the actual loss of the organ are pronounced. The contracture and pseudo-paralytic weakness disappear, while there are alterations in the tone of the individual muscles, producing a sort of "**cerebellar ataxy.**" The dog could swim in quite a normal manner, its power of equilibration was not interfered with, but acts requiring a greater development of muscular energy could not be properly executed. This period lasted four to five months. After this time its health gave way, there was otitis, conjunctivitis, articular and cutaneous inflammations, while a peculiar form of marasmus set in, the animal dying after eight months. In **fishes**, also, the removal of the cerebellum does not affect their power of locomotion (*Bandelot*).]

Duration of the Phenomena.—After superficial lesions, or after a deep incision, the disturbances of coördination soon pass away (*Flourens*). If the injury affects the lowest third of the cerebellum, the motor disturbances remain permanently. Symmetrical lesions do not disturb coördination (*Schiff*). After removing the greater portion of the cerebellum in birds, Weir Mitchell has observed that the original disturbances gradually disappear; and *after months* only slight weakness and a condition of rapid fatigue remain.

After ablation of the cerebellum, **secondary degeneration** occurs in the part of the pons around the pyramids, the lower olives, all the cerebellar peduncles and the direct cerebellar tract, usually on the same side (*Flechsig*). It is found also in individual fibres in all the cranial nerves and the anterior roots of the spinal nerves (*Marchi*).

In the **dog**, superficial injuries of the vermiform process, or of one-half of the organ, produce merely temporary disturbances; while deep injuries to the vermiform process, or removal of one hemisphere and a part of the vermiform process, cause permanent rigidity of the legs and shaking of the head; if the worm and both halves are destroyed, there follows permanent pronounced disturbance of coördination (*v. Mering*). According to Baginsky, destruction of a large part of the vermiform process alone causes in mammals permanent disturbance of coördination. Ferrier found that a vertical section of the cerebellum in **monkeys** produced only inconsiderable disturbances of the equilibrium; after injury of the anterior part of the middle lobe, the animal often tumbles forward; while, when the posterior part is injured, it falls backward. After injury of the lateral lobe, the animal is drawn toward the affected side (*Schiff, Vulpian, Ferrier, Hitzig*). If the middle commissure be injured, the animal rolls violently on its long axis toward the injured side (*Magendie*). Paralysis never occurs after injuries of the cerebellum, nor is there ever disturbance of sensation or of the sense of touch. Luciani found that, in animals with the cerebellum extirpated, marasmus ultimately set in. In **frogs**, an important organ concerned with motion lies at the junction of the oblongata with the cerebellum (*Eckhard*). After it is removed the animal can no longer execute coördinated jumping movements, nor can it crawl (*Goltz*).

[In **man**, the cerebellum is connected with the maintenance of the equilibrium. There may be a lesion of the hemispheres without any marked symptoms; but if the middle lobe be injured or pressed on by a tumor, there is usually a **reeling** or staggering gait, like that of a drunken man. Ross points out that, if the tumor affect the upper part of this lobe, the tendency is to fall backward, and if in the lower part, to fall forward or to revolve round a horizontal axis. Vomiting is frequently persistent and well marked, while there may be nystagmus and tonic retraction of the head.]

After injuries of the cerebellum, involuntary oscillations of the eyeballs or **nystagmus**, as well as squinting (*Magendie, Hertwig*), have been observed; while Ferrier observed movements of the eyeballs after electrical stimulation. According to Curschmann, Eckhard and Schwann, this occurs only when the medulla oblongata is involved (§ 379).

Effects of Electricity and Vertigo.—If an electrical current be passed through the head, by placing the electrodes in the mastoid fossæ behind both ears, with the + pole behind the right and the — pole behind the left ear, then on closing the current, there is severe *vertigo*, and the head and body lean to the + pole, while the objects around seem to be displaced to the left. If the eyes be closed, while the current is passing, the movements appear to be transferred to the person himself, so that he has a feeling of rotation to the left (*Purkinje*). At the moment the head leans toward the anode, the eyes turn in that direction, and often exhibit nystagmus. The electrical current probably stimulates the nerves of the ampullæ, as we know that affections of these bodies cause vertigo (§ 350). The cerebellum has no relation to the sexual activities, as was maintained by Gall. The contractions of the uterus observed by Valentin, Budge, and Spiegelberg, after stimulation of the cerebellum, are as yet unexplained.

Pathological.—Lesions of one hemisphere may give rise to no symptoms; but if the middle lobe is involved, there is incoördination of movement, especially a tendency to fall, unsteady gait and pronounced vertigo. Irritative lesions of the middle peduncle cause complete gyrating movements of the body around its axis, together with rotation of the eyes and head (*Nothnagel*).

381. PROTECTIVE APPARATUS OF THE BRAIN.—The Membranes.—The **dura mater cerebralis** is intimately united to the periosteum of the cavity of the skull, while the spinal dura mater forms around the spinal cord a freely suspended long sac, fixed only on its anterior surface. It is a fibrous membrane, consisting of firm bundles of connective tissue intermixed with numerous elastic fibres, and provided with flattened connective-tissue corpuscles and Waldeyer's plasma cells. The smooth, inner surface is covered with a layer of endothelium. It is but slightly supplied with blood vessels, although they are more numerous in the outer layers; the lymphatics are numerous, while nerves whose terminations are unknown give to the dura its exquisite sensibility to painful operations on it. Pacinian corpuscles have been found in the dura over the temporal bone. The lymphatic **subdural space** (*Key and Retzius*) lies between the dura and the arachnoid, and between the pia and arachnoid is the **subarachnoid space** (Fig. 509). These two spaces do not communicate directly. The delicate arachnoid, thin and partially perforated, poor in blood vessels and without nerves, is covered on both surfaces with squamous endothelium. Only on the spinal cord is it separated from the pia, so that between the two lies the lymphatic subarachnoid space; over the brain, the two membranes are for the most part united together, except the parts bridging over the sulci between adjacent convolutions. The arachnoid passes from convolution to convolution without dipping into the sulci, while the pia dips into each sulcus (Fig. 509, *a*). The **ventricles** of the brain communicate freely with the lymphatic subarachnoid space, but not with the subdural space. The pia consists of delicate bundles of connective tissue without any admixture of elastic fibres; it is richly supplied with blood vessels and lymphatics, and carries nerves which accompany the blood vessels into the substance of the brain. The lymphatics open into the subarachnoid space (§ 196).

FIG. 509.

Vertical section of the cortex cerebri and its membranes; × 2½. *co*, cortex cerebri; *p*, intima piæ dipping into the sulci; *a*, arachnoid, connected with *p* by means of the loose subarachnoid trabeculæ in the subarachnoid space, *sa*; *v*, *v*, blood vessels; *d*, dura; *sd*, subdural space.

[**Subarachnoid Fluid,** or **cerebro-spinal fluid,** lies in the subarachnoid space, which is traversed by trabeculæ of connective tissue. Within the brain are a series of cavities called **ventricles,** which communicate one with another in a definite way. The fourth ventricle is lined by a layer of columnar epithelium, and covered in dorsally by a membrane and continuation of the pia mater, from the middle of which there hangs into the roof of the fourth ventricle two vascular processes composed of capillaries—the choroid plexuses of the fourth ventricle, which are comparable to the larger plexuses of the lateral ventricles. In this membrane is the **foramen of Magendie** and two other smaller foramina, whereby the fluid in the subarachnoid space communicates with that in the fourth ventricle; but the lymphatics of the nerve sheaths can be injected from the subarachnoid space, so that there is direct continuity of the fluid in the ventricles of the brain with that in the subarachnoid space, perivascular spaces of the cerebral substance, and the perineural lymphatics of nerves. The average **quantity** is about 2 ounces, and if it be suddenly withdrawn, epilepsy or convulsions may be produced; or, if it be rapidly increased in amount, coma may be produced. The middle and posterior parts of the brain and the medulla oblongata do not rest directly on bone, but are separated by a distinct interval from their osseous case, an interval occupied by the cerebro-spinal fluid and traversed by trabeculæ, so that, as Hilton expresses it, this fluid forms a perfect water bed for those parts, being sustained by the venous circulation and the elasticity of the dura. It has important mechanical functions, protecting delicate parts of the brain from injury; by distributing vibratory impulses it insulates the nerve roots, and has important relations to the quantity of blood in the brain and the cerebral circulation (Chemical Composition, § 198).]

[**Spina bifida.**—Sometimes the laminæ of the vertebræ in the lumbar or other region of the spinal column are imperfectly developed, in which case the membranes project through as a tumor distended by cerebro-spinal fluid and covered by skin. The effects of rapid tapping or compressing the sac are readily studied in such cases.]

The **Pacchionian bodies**, or granulations, are connective-tissue villi, which serve for the outflow of lymph from the subdural and subarachnoid spaces into the sinuses of the dura mater, especially the longitudinal sinus. The subarachnoid space also communicates with the spaces in the spongy bone of the skull, and with the veins of the skull and surface of the face (*Kollmann*). The subdural space also communicates with the lymphatic spaces in the dura, while the latter communicate directly with the veins of the dura. Both the subdural and subarachnoid lymphatic spaces communicate with the lymphatics of the nasal mucous membrane. The space outside the dura of the spinal cord is called the **epidural space**, and may be regarded as lymphatic in its nature; the pleural and peritoneal cavities may be filled from it; but it does not communicate with the cavity of the skull. The plexuses of blood vessels are surrounded by undeveloped connective tissue. The telæ choroideæ in the newborn are still covered with ciliated epithelium.

Movements of the Brain.—The pulsations of the large basal cerebral vessels communicate their **pulsatile** movements (§ 79, 6) to the brain—the **respiratory** movements also affect it, so that the brain rises during expiration and sinks during inspiration. Lastly, there are slight alternating *vascular* elevations and depressions, occurring 2 to 6 times per minute, due to the periodic dilatation and contraction of the blood vessels (§ 371). Psychical excitement influences these, and they are most regular during sleep. The movements are best seen especially where the membranes of the brain offer little resistance, *e.g.*, over the fontanelles in children, and where the membranes have been exposed by trephining. The presence of the cerebro-spinal fluid is most important for the occurrence of these movements, as it propagates the pressure uniformly, so that every systolic and expiratory dilatation of the blood vessels is concentrated upon those parts of the cerebral membrane which do not offer any resistance (*Donders*). When the fluid escapes, the movements may almost disappear.

Mental excitement increases the pulsations of the brain. At the moment of awaking, the amount of blood in the brain diminishes; sensory stimuli applied during sleep, so that the sleeper does not awake, increase the amount of blood. As the arteries within the rigid skull case change their volume with each pulse beat, the veins (sinuses) exhibit at every beat a pulsatile variation in volume, the opposite of that occurring in the arteries (*Mosso*).

The Cerebral Blood Vessels.—The blood vessels of the pia, of course, are regulated by the vasomotor nerves (§ 356, A 3), and their calibre may also be influenced by the stimulation of more distant parts of the body (§ 347). Donders trephined the skull so as to make a round hole, and filled it with a piece of glass, so that with a microscope he could observe changes in the calibre of the blood vessels. Paralysis of the vasomotor nerves and narcotics dilate the blood vessels; they become greatly contracted at death (§ 373, I). The blood vessels are dilated during cerebral activity (§ 100, A), as well as during sleep. Increased pressure within the skull causes great derangement of the cerebral activity—labored respiration (§ 368, B), unconsciousness even to coma, and paralytic phenomena—all of which may in part be referable to disturbances of the circulation. If all the cranial arteries be ligatured suddenly, there is immediate loss of consciousness, together with strong stimulation of the medulla oblongata and its centres, and death takes place rapidly with convulsions (compare § 373).

By the **free anastomosis** which takes place at the base of the brain, forming the **circle of Willis** (Fig. 510), the individual parts of the brain are preserved from want of blood, when one or other blood vessels is compressed or ligatured. *Within* the brain, the arteries are distributed as "**terminal**" arteries, *i.e.*, the terminal branches of any one artery end in their own area, and do not anastomose with those of adjoining areas (*Cohnheim*). On the other hand, the peripheral arteries (arteries of the corpus callosum, Sylvian fissure, and deep cerebral) which run externally on the brain, form free anastomoses (*Tschomirow*).

[The **nutrient** or **ganglionic arteries** for the central ganglia arise in groups from the circle of Willis, or from the first two centimetres of its trunks. The **antero-median** group (1) supplies the anterior part of the head of the caudate nucleus. The **postero-median** (2) enter the posterior perforated space and supply the internal surface of the optic thalami and the walls of the third ventricle. The **antero-lateral** groups (3, 3) from the middle cerebral enter the anterior perforated space, supply the corpora striata, the anterior part of the optic thalamus, and the internal capsule. These branches are apt to rupture. The **postero-lateral** (4, 4) supply a large part of the optic thalami (*Charcot*). A line drawn at a distance of two centimetres outside the circle of Willis, encloses the **ganglionic area**. The cerebral convolutions are supplied by the large branches of the circle of Willis. The **anterior cerebral** curves round the corpus callosum, and supplies the gyrus rectus and the supra-orbital, the first and second frontal convolutions, the upper part of the ascending frontal, and the inner surface of the hemisphere as far as the quadrate lobule (Fig. 510, I). The **posterior**

cerebral goes to the region of the occipital lobe and the inferior aspect of the temporal lobe; the **middle cerebral** or **Sylvian** artery divides into four branches, which go to the posterior part of the frontal lobe, ascending frontal, and to all the parietal lobes, *i.e.*, chiefly to the motor areas (III), the angular gyrus, and to the first temporo-sphenoidal lobule. The terminal branches of these ganglionic arteries do not anastomose with the cortical system. Fig. 511 shows the ganglionic arteries piercing the basal ganglia. Obviously, when hemorrhage of the lenticulo-striate artery or "**artery of hemorrhage**" (4, 4) occurs, it will compress the lenticular nucleus, or tear it up, and may even injure the parts outside, such as the external capsule, claustrum (T), and island of Reil (R), or those inside, *e.g.*, the internal capsule.]

FIG. 510.



Arteries of the base of the brain, or circle of Willis. C, C, internal carotids; CA, anterior cerebral; S, S, Sylvian arteries; V, V, vertebrals; B, basilar; CP, posterior cerebrals; 1, 2, 3, 3, 4, 4, groups of nutrient arteries. The dotted line shows the limit of the ganglionic area.

[Thus, the **anterior cerebral** supplies the prefrontal area and a small part of the motor area, that for the leg centre in the para central lobule and upper end of the ascending frontal (and perhaps that for the trunk). The **posterior cerebral** supplies the centre for vision, and that connected with the course of the posterior part of the optic expansion, and also the sensory part of the internal capsule. The **middle cerebral** supplies the motor areas of the cortex, except part of the leg centre and the basal ganglia, the auditory centre, and that for speech.]

[The **cerebral circulation** has many peculiarities. The curves on the arteries serve to modify the effect of the cardiac shock, the circle of Willis permits within limits a free circulation; but, in as far as the skull is largely a rigid box, it was at one time taught that, as the brain substance and its fluids were practically incompressible, it was impossible to alter the amount of blood in the brain. This is a mistake. The amount of blood undergoes an alteration in this way, that when more blood passes in, some cerebro-spinal fluid moves out, and *vice versâ*, so that there is an intimate relation between these fluids. In the developing skull, the cerebro-spinal fluid may accumulate in large amount within the ventricles, and greatly distend both them and the yielding skull case from internal pressure, as in **acute hydrocephalus**. The peculiarities and independence of the cortical and ganglionic arteries have already been referred to. Plugging by means of a clot, vegetation or wart, carried from the heart, is common in the left middle cerebral artery. Why? When the plug is washed away by the blood stream, owing to the left carotid springing from the aorta nearly in line with the blood current, the plug readily passes into the carotid and so into the left middle cerebral which is in line with the internal carotid. In such a case, the convolutions and parts supplied by it are suddenly deprived of blood with immediate and serious results.]

[The **venous circulation** is peculiar. The sinuses are really spaces between the layers of the tough dura mater, and partly bounded by bone. The blood moves in the longitudinal sinus from before backward, but most of the cortical veins open into it in a forward direction, so that their stream is opposed to that in the sinus. Thus, the blood which enters the brain by ascending arteries reaches the sinuses by ascending veins, the reverse of what obtains elsewhere, in parts where ascending veins convey blood from descending arteries, whereby the hydrostatic pressure and gravity aid the circulation, but here gravitation is opposed to the flow of blood in the cerebral veins. This will help to explain the occurrence of thrombosis in these vessels. Some of the veins on the surface communicate with intra-cranial veins, *e.g.*, those of the nose, the facial through the ophthalmic, mastoid veins, and veins of the diploë. Hence, morbid processes affecting the scalp (erysipelas), ear (caries), or face (carbuncle) may readily affect intra-cranial structures (*Gowers*).]

If a person who has been in bed for a long time, and whose blood is small in amount, be suddenly raised into the erect position, cerebral anæmia is not unfrequently produced, owing to hydrostatic causes. At the same time, there may be loss of consciousness and impairment of the senses. Liebermeister regards the *thyroid gland* as a collateral blood reservoir which empties its blood toward the head during such changes of the position of the body. Perhaps this may explain the swelling of the thyroid as a compensatory act, when the heart beats violently, and the brain is surcharged with blood (§§ 103, III, and 371). Very violent muscular exertion, as well as marked activity of other organs, causes a very considerable fall of the blood pressure in the carotid.

Pressure on the Brain.—The brain and the fluid surrounding it are constantly subjected to a certain mean *pressure*, which must ultimately depend upon the blood pressure within the vascular system. The investigations of Naunyn and Schreiber on the *cerebral pressure* (or cerebro-spinal pressure) showed that the pressure must be slightly less than the pressure within the carotid, before the symptoms proper to pressure on the brain occur. These are, sudden attacks of headache, with vertigo, or it may be loss of consciousness, vomiting, slowing of the pulse, slow and shallow respiration, convulsions—while the pressure of the cerebro-spinal fluid is increased. The cause of these phenomena lies in the anæmia of the brain. If the pressure is moderate, the above named symptoms may remain latent; nevertheless, disturbances of the nutrition of the brain occur, with consecutive phenomena, such as persistent slight headache, feeling of vertigo, muscular weakness and disturbances of vision (owing to neuro-retinitis with choked disk). Increase of the blood pressure

FIG. 511.

Transverse section of the cerebrum behind the optic chiasma. Arteries of the corpus striatum. C *h*, optic chiasma; B, section of optic tract; L, lenticular nucleus; I, internal capsule, C, caudate nucleus; E, external capsule; T, claustrum; R, convolutions of the island of Reil; V, V, section of the lateral ventricles; P, P, pillars of the fornix; O, gray substance of the third ventricle. Vascular areas—I, anterior cerebral artery; II, Sylvian artery; III, posterior cerebral artery; 1, internal carotid; 2, Sylvian; 3, anterior cerebral artery; 4, 4, lenticulostriate arteries; 5, 5, lenticular arteries.

diminishes the symptoms, while diminution of the blood pressure causes more pronounced phenomena of cerebro-spinal pressure. In the dog, *pain* begins with a pressure of 70 to 80 mm. Hg. *Consciousness is abolished* when the pressure is higher, and at 80 to 100 mm. *spasms* take place. A pressure of 100 to 120 mm. causes *slowing of the pulse*, owing to stimulation of the vagus at its origin; the respirations are temporarily accelerated and then diminish. Long-continued severe compression always, sooner or later, ends fatally. The blood pressure at first is increased, owing to reflex stimulation of the vasomotor centre from the pressure stimulating the sensory nerves; ultimately, the blood pressure falls, and the pulse becomes very slow. Irregular variations in the blood pressure point to a direct central stimulation of the vasomotor centre by pressure. The application of continued slowly increasing pressure compresses the brain (*Adamkiewicz*).

382. COMPARATIVE—HISTORICAL.—Comparative.—Nerves are absent in the **protozoa.** Neuro-muscular cells occur in the **cœlenterata**, in the hydroida and medusæ, and they are the first indications of a nervous apparatus (§ 296). The umbrella of the medusa is covered with a plexus of nerve fibrils, which at various parts along its margin is provided with small cellular thickenings corresponding to ganglia, and from these, nerve fibres proceed to the sense organs. Many of the **worms** possess a nervous ring in the cephalic portion, and in those provided with an intestine a single or double nervous cord, in the form of a ring, surrounds the pharynx. Branches (often two) pass from this into the elongated body, and usually these carry ganglia corresponding to each ring of the body of the animal. In the leech, only one gangliated cord is present.

In the **echinodermata**, a large nerve ring surrounds the mouth; and from it large nerves proceed, corresponding to the chief trunks of the water vascular system. At the points where the nerves are given off, the nervous ring is provided with the so-called "ambulacral brains." The **arthropoda** are provided with a large cephalic ganglion placed above the pharynx, from which nerves pass to the sense organs. Another ganglion lies on the under surface of the pharynx, and is connected with the former by commissures. The pharynx is thus embraced by a gangliated ring, and from it proceeds the abdominal gangliated double chain along the ventral surface of the body, through the thorax and abdomen. Sometimes several ganglia unite to form a large compound ganglion, while, in other cases, each segment of the body contains its own ganglia. In the **mollusca** the œsophageal nervous ring is present, although the ganglionic masses vary much in position within it. A number of compound ganglia lie scattered in different parts of the body, and are united by nerves to the former. They represent the sympathetic system. In **cephalopoda**, the œsophageal ring has almost no commissure, and a part of the ganglionic matter is enclosed in a cartilaginous capsule, and is often spoken of as a "brain." Additional ganglia are found in the mantle, heart and stomach. In **vertebrates**, the nervous system invariably lies on the dorsal aspect of the body. In the amphioxus, there is no separation into brain and spinal cord. (See §§ 374 and 375.)

Historical.—Alkmäon (580 B. C.) placed the seat of consciousness in the brain; Galen (131–203 A. D.) regarded it as the seat of the impulses for voluntary movements. Aristotle (384 B. C.) ascribed the relatively largest brain to man; he stated that it was inexcitable to stimuli (insensible). One of the functions he ascribed to the brain was to cool the heat ascending from the heart. Herophilus (300 B. C.) gave the name calamus scriptorius; and he regarded the 4th ventricle as the most important organ for the maintenance of life. Even in Homer there are repeated references to the dangers of injuries of the neck. Aretæus and Cassius Felix (97 A. D.) were aware of the fact that lesion of one cerebral hemisphere caused paralysis on the opposite side of the body. Galen was acquainted with the path in the spinal cord connected with movement and sensation. Vesalius (1540) described the five ventricles of the brain. R. Colombo (1559) observed the movements of the brain isochronous with the action of the heart. A more careful description of these movements was given by Riolan (1618). Coiter (1573) discovered that an animal can live after removal of its cerebrum. About the middle of the 17th century, Wepfer discovered the hemorrhagic nature of apoplexy. Schneider (1660) estimated the weight of the brain in different animals. Mistichelli (1709) and Petit (1710) described the decussation of the fibres of the spinal cord below the pons. Gall discovered the partial origin of the optic nerve from the anterior pair of the corpora quadrigemina, and by dissecting the brain from below, he attempted to trace the course of the nerve fibres to the convolutions (1810). Rolando described more accurately the form of the gray matter of the spinal cord. Carus (1814) discovered the central canal. The most compendious work on the brain was written by Burdach (1819–1826). The most recent observations are referred to in the text.

PHYSIOLOGY OF THE SENSE ORGANS.

383. INTRODUCTORY OBSERVATIONS. — Requisite Conditions.—The **sense organs** have the function of transferring to the sensorium impressions of the various phenomena of the external world; they are, in fact, the intermediate instruments of *sensory perceptions*. In order that this may occur, the following conditions must be fulfilled: (1) The sense organ, provided with its specific **end organ**, must be anatomically perfect, and capable of acting physiologically. (2) A "**specific stimulus**" must be present, which under normal conditions acts upon the end organ. (3) The sense organ must be connected with the cerebrum by means of a nerve, and the conduction through this path must be uninterrupted. (4) During the act of stimulation, the psychical activity (attention) must be directed to the process, and then the **sensation** results, *e. g.*, of light or sound, through the sense organ. (5) Lastly, when, by a psychical act, the sensation is referred to the external cause, then there is a conscious sensory perception. Often, however, this relation is completed as an unconscious conclusion, as it is essentially a deduction from previous experience.

Stimuli.—With regard to the stimuli which are applied to the sensory apparatus, we distinguish: (1) **Adequate** or **homologous** stimuli, *i. e.*, stimuli for whose action the sense organs are specially adapted, such as the rods and cones of the retina for the vibrations of the ether. Thus, each sense organ has a specific form of stimulus best adapted to act upon it. This is what Johannes Müller called the "**law of specific energy.**" (2) There are many other forms of stimuli (mechanical, thermal, chemical, electrical, internal somatic) which act upon the sense organs, producing the flash of light beheld when the eye is struck; singing in the ears when there is congestion of the head. These **heterologous** stimuli act upon the nervous elements of the sensory apparatus along their *entire* course, from the end organ to the cortex cerebri. The homologous stimuli, on the other hand, act only on the end organ, *i. e.*, light has no effect whatever upon the trunk of the exposed optic nerve.

Strength and Liminal Intensity.—Homologous stimuli act upon the sensory organs only within certain limits as to *strength*. Very feeble stimuli at first produce no effect. That strength of stimulus which is just sufficient to cause the first trace of a sensation is called by Fechner the "**liminal intensity**" of the sensation. As the strength of the stimulus increases, so also do the sensations, but the sensations increase equally when the strength of the stimulus increases in relative proportions. Thus, we have the same sensation of equal increase of light when, instead of 10 candles, 11, or instead of 100 candles, 110 are lighted—the proportion of increase in both cases is equal to one-tenth. As the logarithm of the numbers increases in an equal degree, when the numbers increase in the same relative proportion, the law may be expressed thus: "The sensations do not increase with the absolute strength of the stimuli, but nearly as the logarithm of the strength of the stimulus." This is *Fechner's* "**psycho-physical law,**" but its accuracy has recently been challenged by E. Hering. [It holds good only with regard to stimuli of medium strength.] If the specific stimulus be too intense, it gives rise to peculiar painful sensations, *e. g.*, a feeling of blindness or deafness, as the case may be. The sense organs respond to adequate stimuli, but only within certain *limits* of the stimulus, *e. g.*, the ear responds only to vibrating bodies emitting a certain range of vibrations per second; the retina responds only to the vibrations

of the ether between red and violet, but not to the so-called heat vibrations or to the chemically active vibrations.

[It was Weber who worked out the relation between the intensity of stimuli and the changes in the quantity of the resulting sensations. He used the method of "least observable differences," as applied to sensations of pressure and the measurements of lines by the eye. Hence, it is called **Weber's Law**; but Fechner expanded it and assumed that all just observable differences are equally great, and so the law is sometimes called by his name.]

[**Fechner's Law.**—Expressed in another way, the result depends on (1) the strength of the stimulus, and (2) the degree of excitability. Supposing the latter to be constant, while the former is varied, it is found that if the stimulus be doubled, tripled, or quadrupled, the sensation increases only as the *logarithm of the stimulus*. Suppose the stimulus to be increased 10, 100, or 1000 times, then the sensation increases only as 1, 2, or 3. Just as there is a *lower limit of excitation liminal intensity* (or *threshold*), so there is an upper limit or *maximum of excitation* or *height* of sensibility, when any further increase produces no appreciable increase in the sensation. Thus, we do not notice any difference between the central and peripheral portion of the sun's disk, though the difference of light intensity is enormous (*Sully*). Between these two is the *range of sensibility* (*Wundt*). There is always a constant ratio between the strength of the stimulus and the intensity of the sensation. The stronger the stimulus already applied, the stronger must be the increase of the stimulus in order to cause a perceptible increase of the sensation (**Weber's Law**). The necessary increment is proportional to the intensity of the stimulus, and it varies for each sense organ. If a weight of 10 grammes be placed in the hand, it is found that 3.3 grammes must be added or removed before a difference in the sensation is perceptible; if 100 grammes are held, 33.3 grammes must be added or removed to obtain a perceptible difference in the sensation. The magnitude of the fraction indicating the increment of stimulus necessary to obtain a perceptible difference of the sensation, is spoken of as the *constant proportion* or the *discriminative* sensibility. In the above case it is 1 : 3. The following table gives approximately the constant proportion for each sense:—

Tactile Sensation, ...	1 : 3. $\frac{1}{3}$	Muscular Sensation, . . .	6 : 100. $\frac{6}{100}$
Thermal "	1 : 3. $\frac{1}{3}$	Visual " . . .	1 : 100. $\frac{1}{100}$.]
Auditory "	1 : 3. $\frac{1}{3}$		

[The application of the law to temperature sensations is beset with great difficulties, while for taste and smell we do not know that it is really applicable. From an experimental point of view, it cannot be said to be proved, and its application is obviously somewhat restricted to certain sensations, and to these only within a certain range. It certainly does not hold good for sensations of pressure, and muscular sense, near the lower limits for these senses. At best it is only an approximately correct statement of what holds true of the relative intensity of certain sensations of light and hearing, and less exactly of pressure and the muscular sense, when these sensations are of moderate strength" (*Ladd*).]

The term **after-sensation** is applied to the following phenomenon, viz., that, as a rule, the sensation lasts longer than the stimulus producing it; thus, there is an after-sensation, after pressure is applied to the skin. **Subjective sensations** occur when stimuli due to internal somatic causes excite the nervous apparatus of the sense organ. The highest degrees of these, depending mostly upon pathological stimulation of the sensory cortical centres, are characterized as **hallucinations**, *e. g.*, when a delirious person imagines he sees figures or hears sounds which have no objective reality. In opposition to this condition, the term **illusion** is applied to modifications by the sensorium of sensations actually caused by external objects, *e. g.*, when the rolling of a wagon is mistaken for thunder.

In a **newborn child**, the sense of touch is strongly developed, that of pain slightly, muscular sensations are undoubtedly present, while smell and taste are frequently confounded. Auditory stimuli are heard from the second day onward, the stimulus of light immediately after birth, but a peripheral field of vision does not yet exist (*Cuignet*). Toward the fourth to fifth week, the movements of convergence and accommodation are noticeable, while after four months, colors are distinguished. The various stimuli are not perceived simultaneously—a reflex inhibitory centre is not yet developed (*Genzmer*).

THE VISUAL APPARATUS—THE EYE.

384. HISTOLOGICAL OBSERVATIONS.—In the following remarks it is assumed that the student is familiar with the anatomical structure of the eye:—

The Cornea, for the sake of simplicity, is regarded as uniformly spherical, although, properly speaking, it differs slightly from this form. It is more like a *vertical* section of a somewhat oblique ellipsoid, which we must suppose to be formed by rotating an ellipse around its long axis (*Brücke*). It is nearly of uniform thickness throughout, only in the infant it is slightly thicker in the centre, and in the adult slightly thinner. The cornea consists of the **following layers**:—

[1. Anterior stratified epithelium.
2. Anterior elastic lamina.
3. Substantia propria.
4. Posterior elastic lamina.
5. Single layer of epithelium.]

1. The **anterior epithelium**, stratified and nucleated, consists of many layers of cells (Fig. 514, *a*). The deeper cells are more or less columnar, are arranged side by side, and are called supporting cells. The cells of the middle layers are more arched, and dip with finger-shaped processes into corresponding spaces between their neighbors. The most superficial cells are flat, perfectly smooth, hard, keratin, containing, squamous epithelium. 2. The epithelial layer rests upon the **anterior**

FIG. 512.



Cornea of the frog treated with chloride of gold, showing the corneal corpuscles stained, and a few nerve fibrils.

FIG. 513.

Cornea of the frog treated with silver nitrate; the ground substance is stained, while the spaces for the corneal corpuscles are left unstained.

elastic membrane (Bowman's elastic lamina), a structureless, clear, basement-like membrane (*b*), whose existence is denied by Brücke. 3. The **substantia propria** of the cornea consists of (chondrin-yielding) fibres composed of delicate fibrils of connective tissue. The fibres are arranged in mat-like thin lamellæ (*l*), more or less united together, and are placed in layers over each other. Toward the anterior elastic lamina, the fibres bend round and perforate the superficial lamellæ, thus serving as supporting fibres. [These perforating fibres are comparable to Sharpey's fibres in bone.]

Between the lamellæ are a series of inter-communicating spaces lined by endothelium. These spaces are really **lymph spaces**, and they communicate with the lymphatics of the conjunctiva. The fixed **corneal corpuscles** lie in these spaces (*c*), and are provided with numerous processes, which anastomose with the processes of corpuscles lying between the lamellæ above and below, and on either side of them. Kühne observed that stimulation of the corneal nerves was followed by contraction of these cells (§ 201, 7), while Kühne and Waldeyer maintain that they are connected with the corneal nerve fibrils.

[The **corneal corpuscles** are looked upon as branched connective-tissue corpuscles lying in and not quite filling the branched spaces between the lamellæ. The processes anastomose freely with similar cells in the same plane, and to a less extent with the processes of cells in planes immediately

FIG. 514.



Antero-posterior section at the junction of the cornea with the sclerotic. *a*, anterior corneal epithelium; *b*, Bowman's lamina; *c*, corneal corpuscles; *l*, corneal lamellæ (the whole thickness lying between *b* and *d* is the substantia propria corneæ); *d*, Descemet's membrane; *e*, its epithelium; *f*, junction of cornea with the sclerotic; *g*, limbus conjunctivæ; *h*, conjunctiva; *i*, canal of Schlemm; *k*, Leber's venous plexus (is regarded by Leber as belonging to *i*); *m*, *m*, meshes in the tissues of the lig. iridis pectinatum; *n*, attachment of the iris; *o*, longitudinal, *p*, circular (divided transversely) bundles of fibres of the sclerotic; *q*, perichoroidal space; *s*, meridional [radiating], *t*, equatorial (circular) bundles of the ciliary muscle; *u*, transverse section of a ciliary artery; *v*, epithelium of the iris (a continuation of that on the posterior surface of the cornea); *w*, substance of the iris; *x*, pigment of the iris; *z*, a ciliary process.

above and below them. In a section stained with gold chloride, they present the appearance seen in Fig. 512. In a vertical section of the cornea, they appear fusiform and parallel to the free surface of the cornea (Fig. 514). If the cornea of a frog be penciled with silver nitrate, the cement substance between the lamellæ is blackened, and the branched cell spaces remain clear, as in Fig. 513. The one figure represents, as it were, the positive, and the other the negative image.]

Leucocytes also pass into these lymph spaces or juice canals. The importance of these leucocytes in inflammation is referred to in § 200. 4. The transparent, structureless, **posterior elastic membrane** (*d*), the membrane of Descemet or Demours, is in many animals fibrillated, and shows evidence of stratification, while toward the margin of the cornea there are occasionally slight conical

elevations. This membrane is very tough and very resistant (of great importance in inflammation). If it be removed, it rolls up toward the convex side. At its periphery it becomes continuous with the fibro-elastic reticulated ligamentum pectinatum iridis, whose trabeculæ are covered by epithelium. 5. The posterior **single layer of epithelium** consists of flat, delicate, nucleated cells (*e*), which are continued from the margin of the cornea on to the anterior surface of the iris (*v*). Fine juice canals exist in the spaces between the individual cells (*v. Recklinghausen*). These spaces communicate with a system of fine tubes under the epithelium, perforate Descemet's membrane, and thus communicate with the corneal spaces.

[**Bowman's tubes** are artificial productions, formed by forcing air or a colored fluid between the lamellæ, when it passes between the bundles of fibrils, forming a series of tubes with dilatations on them and running at right angles to one another between the lamellæ.]

The **nerves** of the cornea, which are derived from the long and short ciliary nerves (§ 347), are partly **sensory** in function. They enter the cornea at its margin as medullated fibres, but the myelin soon disappears, while the axial cylinders split up into fibrils. [The axial cylinders branch and form a plexus between the lamellæ, especially near the anterior surface, the **fundamental** or **ground plexus** (Fig. 515, *n*). There are triangular nuclei at the nodal points, but they probably belong to the sheath of flattened cells which cover the larger branches. There is a finer and denser plexus of fibrils immediately under the anterior epithelium, **sub-epithelial plexus**, which is derived from the former, the fibrils arising in pencils or groups (Fig. 516). Some fibrils perforate the anterior elastic lamina, **rami perforantes**, and pass between the anterior epithelial cells to form the **intra-epithelial network** (Fig. 515, *b*, *p*). Some observers suppose that they terminate in free, pointed, or bulbous ends. There is also a fine plexus of fibrils in the posterior layers of the cornea, near Descemet's membrane. It gives off numerous fine fibrils which come into intimate, if not direct, anatomical relation with the corneal corpuscles. The *trophic* fibres of the cornea (§ 347) are, perhaps, those deeper branches which are connected with the corneal corpuscles.]

FIG. 515.



Vertical section of the cornea stained with gold chloride. *n*, nerve fibrils; *a*, perforated branch; *r*, nucleus; *p*, *b*, inter-epithelial termination of fibrils; *s*, anterior elastic lamina.

[**Method.**—These fibrils are best revealed by staining a cornea with chloride of gold, which tinges them of a purplish line after exposure to light (*Cohnheim*).]

Blood vessels occur only in the outer margin of the cornea (Fig. 518, *v*), and extend 2 mm. over the cornea above, 1.5 mm. below, and 1 mm. laterally—the most external capillaries form arched loops, and thus turn on themselves. The cornea is nourished from the blood vessels in its margin. Opacities of the cornea give rise to many forms of visual defects.

The sclerotic is a thick fibrous membrane, composed of, *p*, circular (equatorial) and, *v*, longitudinal (meridional) bundles of connective tissue woven together (Fig. 514). The spaces between the bundles contain colorless and pigmented connective-tissue corpuscles and also leucocytes. It is thickest posteriorly, thinner at the equator, while in front of this it again becomes thicker, owing to the insertion of the tendons of the straight muscles of the eyeball. It contains few blood vessels, which form a wide-meshed capillary plexus, immediately under its deep surface. Other vessels form an arterial ring around the entrance of the optic nerve. It rarely is quite spherical; it rather resembles an ellipsoid, which we might imagine to be formed by the rotation of an ellipse around its short axis (short eyes) or around its long axis (long eyes). Above and below, the sclerotic overlaps like a fold the clear margin of the cornea; hence, when the cornea is viewed from before, it appears transversely elliptical, when seen from behind, it appears circular. Following the margin of the cornea, but lying still within the substance of the sclerotic, is the circular **canal of Schlemm** (*i*), which communicates with other anastomosing veins, the venous plexus of Leber (*k*). Schwalbe and Waldeyer regard Schlemm's canal as a lymphatic. Posteriorly, the sclerotic becomes continuous with the fibrous covering of the optic nerve derived from the dura mater. The sclerotic is provided with nerves, which are said to terminate in the cells of the scleral substance (*Helfreich*).

The **tunica uvea**, or the uveal tract, is composed of the choroid, the ciliary part of the choroid, and the iris.

The **choroid** is composed of the following layers (Fig. 517): (1) Most internally is the trans-

parent **limiting membrane**, 0.7 μ in thickness, but it is slightly thicker anteriorly. (2) The very vascular capillary network of the **chorio-capillaris**, or membrane of Ruysch, embedded in a homogeneous layer. Then follows (3) a layer of a thick **elastic network**, covered on both surfaces by endothelium (*Sattler*). (4) The **choroid proper** consists of a layer with pigmented connective-tissue corpuscles, together with a thick elastic network, containing the numerous venous vessels as well as the arteries. The pigmented layers are known as the **supra-choroidea**, or lamina fusca, which surrounds the large lymphatic space lined with endothelium and called the **perichoroidal space**, *g*. In newborn infants, which according to Aristotle have the iris dark blue, the uveal tissue is devoid of pigment; in brunettes it is developed later, and in blondes not at all.

In the **ciliary part** of the choroid, the pigmented connective-tissue corpuscles are not so numerous. The **ciliary muscle** (tensor choroideæ, or muscle of accommodation) is placed in this region. It arises (*s*), by means of a branched, reticulated, connective-tissue origin, from the inner side of the junction of the cornea and the sclerotic, near the canal of Schlemm, and passes backward to be inserted into the choroid. This constitutes the **radiating** fibres. Other fibres lying internal to these are arranged **circularly**, *t*, in bundles in the ciliary margin. These circular fibres are sometimes called Heinrich Müller's muscle. The muscle consists of smooth muscular fibres, and is supplied by the oculomotorius (§ 345, 3).

FIG. 516.

Nerve plexus in the cornea after gold chloride. *n*, nerve; *a*, fibrils.

FIG. 517.

Vertical section of the choroid and a part of the sclerotic. (1) sclerotic; (2) lamina supra-choroidea; (3) layer of large vessels; (4) limiting layer; (5) chorio-capillaris; (6) hyaline membrane; (7) pigment epithelium; (*g*) large blood vessels; (*f*) pigment cells; (*c*) sections of capillaries.

The **iris** consists of the following parts from before backward: a layer of epithelial cells (*v*) continuous with those covering the posterior surface of the cornea, a layer of reticulated connective tissue, the layer of blood vessels, and lastly a posterior limiting membrane, which contains the pigmentary epithelium (*x*) (*Michel*). In brunettes, the texture of the iris contains pigmented connective tissue corpuscles. The iris in some animals is described as containing two muscles composed of smooth muscular fibres—one set constituting the **sphincter pupillæ** (circular—Fig. 533), which surrounds the pupil, and lies nearer the posterior than the anterior surface of the iris (§ 392). Its nerve of supply is derived from the oculomotorius (§ 345, 2). The other fibres constitute the **dilator pupillæ** (radiating), which consists of a thinner layer of fibres arranged in a radiate manner. Some of the fibres reach to the margin of the pupil, while others bend into the sphincter. [The existence of a dilator pupillæ in man is denied (§ 392).] At the outer margin of the iris, the radial bundles are arranged in anastomosing arches, and form a circular muscular layer (*Merkel*). The chief nerve of supply for the dilator fibres is the sympathetic (§ 347, 3). Ganglia occur in the ciliary nerves in the choroid [and they are found also in the iris]. Gerlach has recently applied the term *ligamentum annulare bulbi* to that complex fibrous arrangement which surrounds the iris, and at the same time

forms the point of union of the ciliary body, iris, ciliary muscle, sinus venosus iridis, and the line of junction of the cornea and sclerotic.

The **choroidal vessels** are of great importance in connection with the nutrition of the eye. According to Leber, they are arranged as follows:

The **arteries** are—1. The **short posterior ciliary**, which are about twenty in number and perforate the sclerotic near the optic nerve (Fig. 518, *a*, *a*). They terminate in the vascular network of the chorio-capillaris (*m*), which reaches as far as the ora serrata. 2. The **long posterior ciliary**; one of these lies on the nasal and the other on the temporal side, and they run (*b*) to the ciliary part of the choroid, where they divide dichotomously, and penetrate into the iris, where they help to form the circulus arteriosus iridis major (*p*). 3. The **anterior ciliary** (*c*), which arise from the muscular branches, perforate the sclerotic anteriorly, and give branches to the ciliary part of the choroid and to the iris. About twelve branches run backward (*o*) from them to the chorio-capillaris.

Veins.—1. The **anterior ciliary** veins (*c*) receive the blood from the anterior part of the uvea and carry it outward. These branches are connected with Schlemm's canal and Leber's venous plexus. They do not receive any blood from the iris. 2. The **venous plexus** of the ciliary processes (*r*) receives the blood from the iris (*q*), and passes backward to the choroidal veins. 3. The large **vasa vorticosa** Stenosis (*h*) perforate the sclerotic behind the equator of the bulb.

The inner margin of the iris rests upon the anterior surface of the lens; the posterior chamber is small in adults, and in the newborn child it may be said scarcely to exist—it is so small. When Berlin blue is injected into the anterior chamber of the eye, it generally passes into the anterior ciliary veins (*Schwalbe*). Even in living animals, carmin also behaves in a similar manner (*Heisrath*); hence, these observers conclude that there is a *direct* communication between the veins and the aqueous chamber, as these substances do not diffuse through membranes.

Internal to the choroid lies the single layer of **hexagonal cells** (0.0135 to 0.02 mm. in breadth) filled with crystalline pigment. This layer really belongs to the retina. It consists of a single layer of cells as far as the ora serrata—it is continued on to the ciliary processes and the posterior surface of the iris, where it forms several layers (Fig. 514, *x*). In albinos it is devoid of pigment; on the other hand, the uppermost cells, which lie on the ridges of the ciliary processes, are always devoid of pigment. [The processes of these cells vary in length with the nature and kind of light acting on the retina (§ 398).]

FIG. 518.



Diagram of the blood vessels of the eye (horizontal view, veins black, arteries light, with a double contour). *a*, *a*, short posterior ciliary; *b*, long posterior ciliary; *c*, *c'*, anterior ciliary artery and vein; *d*, *d'*, artery and vein of the conjunctiva; *e*, *e'*, central artery and vein of retina; *f*, blood vessels of the inner, and *g*, of the outer optic sheath; *h*, vorticose vein; *i*, posterior short ciliary vein confined to the sclerotic; *k*, branch of the posterior short ciliary artery to the optic nerve; *l*, anastomosis of the choroidal vessels with those of the optic; *m*, chorio-capillaris; *n*, episcleral branches; *o*, recurrent choroidal artery; *p*, great circular artery of iris (transverse section); *q*, blood vessels of the iris; *r*, ciliary process; *s*, branch of a vorticose vein from the ciliary muscle; *t*, branch of the anterior ciliary vein to the ciliary muscle; *u*, circular vein; *v*, marginal loops of vessels on the cornea; *w*, anterior artery and vein of the conjunctiva.

The **retina** externally is in contact with the layer of hexagonal pigment cells (*Pi*), which in its development and functions really belongs to the retina. The cells are not flat, but they send pigmented processes into the space between the ends of the rods. In some animals (rabbit) the cells contain fatty granules and other substances. The cells are larger and darker at the ora serrata (*Kühne*). The retina is composed of the following **layers**, proceeding from without inward:—

[1. Layer of pigment cells.
2. Rods and cones.
3. *External limiting membrane.*
4. Outer nuclear layer.
5. Outer molecular (granular or internuclear) layer.
6. Inner nuclear layer.
7. Inner molecular (granular) layer.
8. Layer of nerve cells (ganglionic layer).
9. Layer of nerve fibres.
10. *Internal limiting membrane.*]

1. The **hexagonal pigment cells** already described. 2. The layer of **rods and cones** (*St*) or *neuro-epithelium* of Schwalbe [*bacillary layer*, or the *visual cells*, or *visual epithelium* of Kühne] (Fig. 520). These lie externally next the choroid, but they are absent at the entrance of the optic nerve. Then follows the **external limiting membrane** (*Le*), which is perforated by the bases of the rods and cones. 3. The **external nuclear layer** (*äu.K*); this and all the succeeding layers are called "brain layers" by Schwalbe. 4. The **external granular** (*äu.gr*), or internuclear layer, which is perforated by the fibres which proceed inward from the nuclei of 3 to reach 5, the nuclei of the **internal nuclear layer** (*inK*). The nuclei of this layer, which are connected by fibres with the

FIG. 519.



Vertical section of human retina. *a*, rods and cones; *b*, ext., and *g*, int. limit. memb.; *c*, ext., and *f*, int. nucl. layers; *e*, ext., and *g*, int. gran. layers; *h*, blood vessel and nerve cells; *i*, nerve fibres.

FIG. 520.

Layers of the retina. *Pi*, hexagonal pigment cells; *St*, rods and cones; *Le*, ext. limiting membrane; *äu.K*, ext. nuclear layer; *äu.gr*, ext. granular layer; *inK*, int. nuclear; *in.gr*, int. granular; *Ggl*, ganglionic nerve cells; *o*, fibres of optic nerve; *Li*, int. limit. membrane; *Rk*, fibres of Müller; *K*, nuclei; *Sy*, spaces for the nervous elements.

rods and cones, are marked by transverse lines in the macula lutea (*Krause, Denissenko*). 6. The finely granular **internal granular** layer (*in.gr*), through which the fibres proceeding from the inner nuclear layer cannot be traced. It would seem as if these fibres break up into the finest fibrils, into which also the branched processes of the ganglionic cells of 7, the **ganglionic layer**, extend. According to v. Vintschgau, the processes of the ganglionic cells are connected with the fibres. 8. The next, or fibrous layer, consists of the **fibres of the optic nerve** (*o*), and most internally is the **internal limiting membrane** (*Li*). According to W. Krause, there are 400,000 broad, and as many narrow, optic fibres, so that for every fibre there are 7 cones, about 100 rods, and 7 pigment cells. The optic

fibres are absent from the macula lutea, where, however, there are numerous ganglionic cells. Between the two homogeneous limiting membranes (*Le* and *Li*) lies the **connective-tissue substance** of the retina. It contains the perforating fibres, or **Müller's fibres**, which run in a radiate manner between the two membranes, and hold the various layers of the retina together. They begin by a wing-shaped expansion at the internal limiting membrane (*Rk*), and in their course outward contain nuclei (*k*). They are absent at the yellow spot. The supporting tissue forms a network in all the layers, holes being left for the nervous portions (*Sg*). The inner segments of the rods and cones are also surrounded by a sustentacular substance. As the retina passes forward to the ora serrata, it becomes thinner and thinner, gradually becoming richer in connective-tissue elements and poorer in nerve elements, until, in the ciliary part, only the cylindrical cells remain (Fig. 519).

[**Macula Lutea and Fovea Centralis.**—There are no rods in the fovea, while the cones are longer and narrower than in the other parts of the retina (Fig. 521). The other layers also are thinner, especially at the macula lutea, but they become thicker toward the margins of the fovea, where the ganglionic layer consists of several rows of bipolar cells. The yellow tint is due to pigment lying between the layers composing the yellow spot.]

The **blood vessels** of the retina lie in the *inner* layers near the inner granular layer. Only near the entrance of the optic nerve are they connected by fine branches with the choroidal vessels; they are surrounded by perivascular lymph spaces. The greatest number of capillaries runs in the layers external to the inner granular layer (*Hesse*). The fovea centralis is devoid of blood vessels (*Nettleship, Becker*). Except in mammals, the eel (*Denissenko*), and some tortoises (*H. Müller*), the retina receives no blood vessels. Destruction of the retina is followed by blindness.

FIG. 521.



Section of the fovea centralis. *a*, cones; *b* and *g*, int. and ext. limit. memb.; *c*, ext., and *e*, nuclear layer; *d*, fibres; *f*, nerve cells.

[**Retinal Epithelium.**—The single layer of pigmentary cells containing granules of melanin sends processes downward, like the hairs of a brush, between the rods and cones (§ 398). Kühne has shown that the nature and amount of light influence the condition of these processes (Fig. 563). The protoplasm of these cells in a frog kept for several hours in the dark, is retracted, and the pigment granules lie chiefly in the body of the cell and in the processes near the cell. In a frog kept in bright daylight, the processes loaded with pigment penetrate downward between the rods and cones as far as the external limiting membrane.]

Each **rod** and **cone** consists of an **outer** and an **inner segment**. During life, the outer segment contains a reddish pigment or the visual purple (*Boll*).

Visual purple [or **rhodopsin**] may be preserved by keeping the eye in darkness; but it is soon bleached by daylight, while it is again restored when the eye is placed in darkness. It can be extracted from the retina by means of a 2.5 per cent. solution of the bile acids, especially from eyes that have been kept in 10 per cent. solution of common salt (*Ayres*). The rods are 0.04 to 0.06 mm. high and 0.0016 to 0.0018 mm. broad, and exhibit longitudinal striation, produced by the presence of fine grooves; a fine fibril runs in their interior (*Ritter*). The external segment occasionally cleaves transversely into a number of fine transparent disks. [It is a very resistant structure, and in this respect resembles neuro-keratin.] Krause found an ellipsoidal body, the "rod ellipsoid," at the junction of the inner and outer segments of the rods. The cones are devoid of visual purple, but their outer segment is striated longitudinally, and it also readily breaks across into thin disks. Only cones are present in the macula lutea. In the neighborhood of the yellow spot, each cone is surrounded by a ring of rods. The cones become less numerous toward the periphery of the retina. In nocturnal animals, such as the owl and bat, there are either no cones or imperfect ones. The

retinæ of birds contain many cones, that of the tortoise only cones. The rods and cones rest on the sieve-like perforated external limiting membrane (*Le*). Both send processes through the membrane, the cones to the larger and higher-placed nuclei, the rods to the nuclei, with transverse markings in the external nuclear layer. [The cones are particularly large in some fishes, *e. g.*, the cod, while the skate has no cones, but only rods. The same is the case in the shark and sturgeon, hedgehog, bat, and mole.]

[**Distribution and Regeneration of Rhodopsin.**—Keep a rabbit in the dark for some time, kill it, remove its eyeball, and examine its retina by the aid of monochromatic (sodium) light. The retina will be purple red in color, all except the macula lutea and a small part at the ora serrata. The pigment is confined to the *outer segments of the rods*. It is absent in pigeons, hens, and one bat, although the last has only rods. It is found both in nocturnal and diurnal animals. Its color is quickly bleached by light, and it fades rapidly at a temperature of 50° to 76° C., while trypsin, alum, and ammonia do not affect it It is restored in the retina by the action of the retinal epithelium. If the retinal epithelium or choroid be lifted off from an excised eye exposed to light, the purple is destroyed; but if the eye be placed in darkness and the retinal epithelium replaced, the color is restored.]

Chemistry of the Retina.—The reaction of the retina, when quite fresh, is acid, and becomes alkaline in darkness. The rods and cones contain albumin, neuro-keratin, nuclein, and in the cones are the pigmented oil globules, the so-called "**chromophanes.**" The other layers contain the constituents of the gray matter of the brain.

[**Cones.**—There is no coloring matter in the outer segment of the cones, but in fishes, reptiles, and birds the inner segment contains a globular-colored body, often red and yellow, the pigment being held in solution by a fatty body. Kühne has separated a green (**chlorophane**), a yellow (**xanthophane**), and a red (**rhodophane**) pigment. They all give a blue with iodine, and are bleached by light (*Schwalbe*).]

The crystalline lens is enclosed in a transparent capsule, thicker anteriorly than posteriorly, and it is covered on the inner surface of the anterior wall by a layer of low epithelium. Toward the margin of the lens, these cells elongate into nucleated fibres, which all bend round the margin of the lens, and on both sides of the lens abut with their ends against each of the triradiate figures. The lens fibres contain globulin enclosed in a kind of membrane. Owing to mutual pressure, they are hexagonal when seen in transverse section (Fig. 522, 2), while in many animals, especially fishes, their margins are serrated [the teeth dovetail into each other]. For the sake of simplicity, we may regard the lens as a biconvex body with spherical surfaces, the posterior surface being more curved. As a matter of fact, the anterior part is part of an ellipsoid formed by rotation on a short axis. The posterior surface resembles the section of a paraboloid, *i. e.*, we might regard it as formed by the rotation of a parabola on its axis (*Brücke*). The outer layers of the lens have less refractive power than the more internal layers. The central part of the lens or nucleus is, at the same time, firmer, and more convex than the entire lens. The margin of the lens is always separated from the ciliary processes by an intermediate space.

FIG. 522.



1, Fibres of the lens; 2, transverse section of the lens fibres.

[**Chemistry.**—The lens contains about two-thirds of its weight of water, while its chief solid is a globulin, called by Berzelius **crystallin** (24.6 per cent.), with a little serum albumin, salts, cholesterin, and fats.]

[**Cataract.**—Sometimes the lens becomes more or less opaque, the opacity beginning either in the middle or outer parts of the lens. This is generally due to fatty degeneration of the fibres, cholesterin being deposited. An opaque, cataractous condition of the lens may be produced in frogs, by injecting a solution of some salts or sugar in the lymph sacs; the result is that these salts absorb the water from the lens, and thus make it opaque. The cataract of diabetes is probably produced from the presence of grape sugar in the blood.]

The **zonule of Zinn**, at the ora serrata, is applied as a folded membrane to the ciliary part of the uvea, so that the ciliary processes are pressed into its folds, and are united to it. It passes to the margins of the lens, where it is inserted by a series of folds into the anterior part of the capsule of the lens. Behind the zonule of Zinn, and reaching as far as the vitreous humor, is the **canal of Petit.** The zonule is a fibrous perforated membrane. According to Merkel, the canal of Petit is enclosed by very fine fibres, so that it is really not a canal, but a complex communicating system of spaces (*Gerlach*). Nevertheless, the zonule represents a stretched membrane, holding the lens in position, and may therefore be regarded as the **suspensory ligament** of the lens.

Opacity or cloudiness of the lens (gray cataract) hinders the passage of light into the eye.

Aphakia, or the absence of the lens (as after operation for cataract) may be remedied by a pair of strong convex spectacles. Of course, such an eye does not possess the power of accommodation.

The **vitreous humor,** as far as the ora serrata, is bounded by the internal limiting membrane of the retina (*Henle, Iwanoff*). From here forward, lying between both, are the meridional fibres of the zonule, which are united with the surface of the vitreous and the ciliary processes. A part of the fibrous layer bends into the saucer-shaped depression, and bounds it. A canal, 2 mm. in diameter, runs from the optic papilla to the posterior surface of the capsule of the lens; it is called the **hyaloid canal,** and was formerly traversed by blood vessels. The peripheral part of the vitreous humor is laminated like an onion, the middle is homogeneous; in the former, especially in the fœtus, are round fusiform or branched cells of mucous tissue of the vitreous, while in the centre there are disintegrated remains of these cells (*Iwanoff*). The vitreous humor contains a very small percentage of solids, 1.5 per cent. of **mucin** [and, according to Picard, there is 0.5 per cent. of urea, and about .75 of sodic chloride].

[**Structure.**—The vitreous humor consists essentially of **mucous tissue,** in whose meshes lie a very watery fluid, containing the organic and inorganic bodies in solution. According to Younan, the vitreous contains two types of cells—(1) **amœboid cells** of various shapes and sizes. They lie on

FIG. 523.



Horizontal section of the entrance of the optic nerve and the coats of the eye. *a*, inner, *b*, outer layers of the retina; *c*, choroid; *d*, sclerotic; *e*, physiological cup; *f*, central artery of retina in axial canal; *g*, its point of bifurcation; *h*, lamina cribrosa; *i*, outer (dural) sheath; *m*, outer (subdural) space; *n*, inner (subarachnoid) space; *r*, middle (arachnoid) sheath; *p*, inner (pial) sheath; *i*, bundles of nerve fibres; *k*, longitudinal septa of connective tissue.

the inner surface of the lining hyaloid membrane and the other membranes in the cortex of the vitreous; (2) large **branching** multipolar **cells.** The vitreous is permeated by a large number of transparent, clear, homogeneous **hyaloid membranes,** which are so disposed as to give rise to a concentric lamination. The **canal of Stilling** represents in the adult the situation of the hyaloid artery of the fœtus. It can readily be injected by a colored fluid.]

The **lymphatics** of the eye consist of an anterior and a posterior set. The **anterior** consist of the anterior and posterior chambers of the eye (aqueous) which communicate with the lymphatics of the iris, ciliary processes, cornea, and conjunctiva. The **posterior** consist of the perichoroidal space between the sclerotic and the choroid (*Schwalbe*). This space is connected by means of the perivascular lymphatics around the trunks of the vasa vorticosa, with the large lymph space of Tenon, which lies between the sclerotic and Tenon's capsule. Posteriorly, this is continued into a lymph channel, which invests the surface of the optic nerve; while anteriorly it communicates directly with the sub-conjunctival lymph spaces of the eyeball. The optic nerve has **three sheaths**—(1) the **dural**; (2) the **arachnoid**; and (3) the **pial** sheath, derived from the corresponding membranes of the brain. **Two lymph spaces** lie between these three sheaths—the **subdural space** between 1 and 2, and the **subarachnoid space** between 2 and 3 (Fig. 509). Both spaces are lined by endo-

thelium; and the fine trabeculæ passing from one wall to the other are similarly covered. According to Axel Key and Retzius, these lymph spaces communicate anteriorly with the perichoroidal space.

The aqueous humor closely resembles the cerebro-spinal fluid, and contains albumin and sugar; the former is increased, and the latter disappears after death. The same occurs in the vitreous. The albumin increases when the difference between the blood pressure and the intraocular pressure rises. Such variations of pressure, and also intense stimuli applied to the eye, cause the production of fibrin in the anterior chamber (*Jesner and Grünhagen*).

Intraocular Pressure.—The cavity of the bulb is practically filled with watery fluids, which, during life, are constantly subjected to a certain pressure, the "intraocular pressure." Ultimately, this depends upon the blood pressure within the arteries of the retina and uvea, and must rise and fall with it. The pressure is determined by pressing upon the eyeball, and ascertaining whether it is tense, or soft and compressible. Just as in the case of the arterial pressure, the intraocular pressure is influenced by many circumstances; it is increased at every pulse beat and at every expiration, while it is decreased during inspiration. The elastic tension of the sclerotic and cornea regulates the increase of the arterial pressure by acting like the air chamber in a fire engine; thus, when more arterial blood is pumped into the eyeball, more venous blood is also expelled. The constancy of the intraocular pressure is also influenced by the fact that, just as the aqueous humor is removed, it is secreted, or rather formed, as rapidly as it is absorbed (§ 392). [Fick has invented an instrument for the direct measurement of the intraocular pressure, a small plate of known size is pressed against the eyeball, and the pressure exerted is registered by means of a spring and index.]

The secretion of the aqueous humor occurs pretty rapidly, as may be surmised from the fact, that hæmoglobin is found in the aqueous humor half an hour after dissolved blood (lamb's) is injected into the blood vessels of a dog. It is rapidly reformed, after evacuation, through a wound in the cornea. According to Knies, the watery fluid within the eyeball is secreted, especially from the chorio-capillaris, and reaches the supra-choroidal space, in the lymph sheaths of the optic nerve, and partly through the network of the sclerotic. It saturates the retina, vitreous, lens, and for the most part passes through the zonula ciliaris into the posterior chamber, and through the pupil into the anterior chamber. The movements of the fluid within the eyeball have been recently studied by Ehrlich, who used **fluorescin**, an indifferent substance, which, on being introduced into the body, passes into the fluids of the eyeball, and in a very dilute solution may be recognized by its green fluorescence in reflected light. From observations on the entrance of this substance into the eye, Schöler and Uhthoff regard the posterior surface of the iris and the ciliary body as the secretory organs for the aqueous humor. It passes through the pupil into the anterior chamber; some passes into the lens, and along the canal of Petit into the vitreous humor (*Pflüger*). Section of the cervical sympathetic, and still more of the trigeminus, accelerates the secretion of the aqueous, but its amount is diminished. If the substance is dropped into the conjunctival sac, it percolates toward the centre of the cornea, and through the latter into the anterior chamber (*Pflüger*).

A current passes forward from the vitreous humor around the lens, and there is an outflow along the central artery of the retina backward through the optic nerve to the cavity of the skull (*Gifford*). The current in the spaces between the sheaths flows from the brain to the eye (*Quincke*).

The **outflow** of the aqueous humor, according to Leber and Heisrath, takes place chiefly between the meshes of the ligamentum pectinatum iridis (Fig. 514, *m*, *m*), and the canal of Schlemm (*i*, *i*), into the anterior circular veins (p. 787). A small part of the aqueous humor diffuses into the posterior layers of the cornea to nourish it (*Leber*). None of the water is conducted from the eyeball by any special efferent lymphatics (*Leber*). Under normal circumstances, the pressure is nearly the same in the vitreous and aqueous chambers, but atropin seems to diminish the pressure in the former and to increase it in the latter, while Calabar bean has an opposite action (*Ad. Weber*). Arrest of the outflow of the venous blood often increases the pressure in the vitreous, and diminishes that in the aqueous chamber. Compression of the bulb from without causes more fluid to pass out of the eye temporarily than enters it. The diminution of the intraocular pressure is well marked after section of the trigeminus, while it rises when this nerve is stimulated. The statements of observers regarding the effect of the sympathetic nerve upon the pressure vary. Interruption to the venous outflow increases the pressure, while an imperfect supply of blood, the outflow being normal, diminishes the pressure. The innervation of the blood vessels of the eye is referred to at § 347.

385. **DIOPTRIC OBSERVATIONS.**—**The eye as an optical instrument** is comparable to a **camera obscura**; in both, an **inverted diminished image** of the objects of the external world is formed upon a background, the field of projection. Instead of the single lens of the camera, however, the eye has **several refractive media** placed behind each other—**cornea, aqueous humor, lens** (whose individual parts—capsule, cortical layers, and nucleus, all possess different refractive indices), and **vitreous humor.** Every two of these adjacent media are bounded by a **"refractive surface,"** which may be regarded as spherical. The field of projection of the eye is the retina, which is colored with the visual purple (*Boll, Kühne*). As this substance is bleached chemically by the direct action of light, so that the pictures may be temporarily fixed upon the retina, the comparison of the eye with the camera of the photographer becomes more striking. In order that the passage of the rays of light through the media of the eye may be rightly understood, we must know the following factors: (1) the refractive indices of all the media; (2) the form of the

refractive surfaces; (3) the distance of the various media from each other and from the field of projection or retina.

Action of a Converging Lens.—We must know how a convex lens acts upon light. In a convex lens we distinguish the centre of curvature, *i. e.*, the centre of both spherical surfaces (Fig. 524, I, m, m_1). The line connecting both is called the **chief axis**; the centre of this line is the **optical centre** of the lens (o). All rays which pass through the optical centre of the lens pass through unbent, or without being refracted; they are called the chief or principal rays (n, n_1). The following are the laws regulating the action of a convex lens upon rays of light:—

1. Rays which fall upon the lens, **parallel** with the principal axis (II, f, a), are so refracted that they are collected on the other side of the lens, at a point called the focus or **principal focus** (f). The distance of this point from the central point (o) of the lens, is called the **focal distance** of the lens (f, o). The converse of this condition is evident, viz., rays which diverge from a focus and reach the lens, pass through it to the other side, parallel with the principal axis, without again coming together.

2. Rays of light proceeding from a source of light (IV, l) in the prolonged principal axis, but *beyond* the focal point (f), again converge to a point on the other side of the lens. The following cases may occur: (a) When the distance of the light from the lens is equal to twice the focal distance,

FIG. 524.



Figures illustrating the action of lenses upon rays of light passing through them.

the focus or point of convergence lies at the same distance on the other side of the lens, *i. e.*, twice the focal distance. (b) If the luminous point be moved nearer to the focus, then the focal point is moved further away. (c) If the light is still further from the lens than twice the focal distance, then the focal point comes correspondingly near to the lens.

3. Rays proceeding from a point of the chief axis (III, b) within the focal distance, pass out at the other side less divergent, but do not come to a focus again. Conversely, rays which are convergent, and pass through a collecting lens, have their focal point within the focal distance.

4. If the luminous point (V, a) is placed in the secondary ray (a, b), the same laws obtain, provided the angle formed by the secondary ray with the principal axis is small.

Formation of images by convex lenses.—After what has been stated, regarding the position of the point of convergence of rays proceeding from a luminous point, the construction of the image of any object by a convex lens is easily accomplished. This is done simply by projecting images of the various parts of the object. Thus, evidently (in V), b is the focal point of the object, a, while v is the focal point of the object, l. The picture is **inverted.** *Collecting lenses form an inverted and real image* (*i. e.*, upon a screen) *only of such objects as are placed beyond the focal point of the lens.*

With regard to the **size** and **distance** of the image from the lens, there are the following cases: (a) If the object be placed at twice the focal distance from the lens, the image of the same is just the

same size and at the same distance from the lens as the object is. (*b*) If the object be nearer than the focus, the image recedes and at the same time becomes larger. (*c*) If the object be further removed from the lens than twice the focal distance, then the image is nearer to the lens and at the same time becomes smaller.

Position of the Focal Point.—The distance of the focal point from the lens is readily calculated according to the following formula: Where l = the distance of the luminous point, b = the distance of the image, and f = the focal distance of the lens: $\frac{1}{l}+\frac{1}{b}=\frac{1}{f}$, or $\frac{1}{b}=\frac{1}{f}-\frac{1}{l}$.

Example.—Let $l = 24$ centimetres, $f = 6$ cm. Then $\frac{1}{b}=\frac{1}{6}-\frac{1}{24}=\frac{1}{8}$; so that $b = 8$ cm., *i. e.*, the image is formed 8 cm. behind the lens. Further, let $l = 10$ cm., $f = 5$ cm. (*i. e.*, $l = 2f$). Then $\frac{1}{b}=\frac{1}{5}-\frac{1}{10}=\frac{1}{10}$; so that $b = 10$, *i. e.*, the image is placed at twice the focal distance of the lens. Lastly, let $l = \infty$. Then $\frac{1}{b}=\frac{1}{f}-\frac{1}{\infty}$; so that $b = f$, *i. e.*, the image of parallel rays coming from infinity lies in the focal point of the lens.

Refractive Indices.—A ray of light, which passes in a perpendicular direction from one medium into another medium of *different* density, passes through the latter without changing its course or being refracted. In Fig. 525, if G D is ⊥ A B, then so is D D, ⊥ A B; for a plane surface A B is the horizontal, and G D the vertical line. If the surface be spherical, then the vertical line is the

FIG. 525.



FIG. 526.



prolonged radius of this sphere. If, however, the ray of light fall *obliquely* upon the surface, it is "**refracted,**" *i. e.*, it is bent out of its original course. The incident and the refracted ray nevertheless lie in *one plane*. When the oblique incident ray passes from a *less dense* medium (*e. g.*, air) into one *more dense* (*e. g.*, water), the refracted or excident ray is bent *toward* the perpendicular. If, conversely, it pass from a more dense to a less dense medium, it is bent *away* from the perpendicular. The angle (*i*, G D S) which the incident ray (S D) forms with the perpendicular (G D) is called the **angle of incidence,** the angle formed by the refracted ray (D S_1) with the prolonged perpendicular (D D) is called the **angle of refraction,** D D S_1 (*r*). The refractive power is expressed as the **refractive index.** The term **refractive index** (*n*) means, that number which shows for a certain substance, how many times the sine of the angle of incidence is greater than the sine of the angle of refraction, when a ray of light passes from the air into that substance. Thus, n = sin. i : sin. $r = ab, : cd$. On comparing the refractive indices of two media, we always assume that the ray passes from *air* into the medium. On passing from the air into water, the ray of light is so refracted that the sine of the angle of incidence is to the sine of the angle of refraction, as 4 : 3; the refractive index $= \frac{4}{3}$ (or more exactly = 1.336). With glass the proportion is = 3 : 2 (= 1.535—*Snellius*, 1620; *Descartes*). The sine of the incident and refractive angles are related as the velocity of light with both media.

The construction of the refracted ray, the refractive index being given, is simple: **Example.**—Suppose in Fig. 526, L = the air, G = a dense medium (glass) with a spherical surface, *xy*, and with its centre at *m*; *p o* = the oblique incident ray the *m Z* is the perpendicular <) = *i* the angle

of incidence. The refractive index given is $\frac{3}{2}$; the object is to find the direction of the refracted way. From o as centre describe a circle with a radius of any length; from a draw a perpendicular, $a\ b$ to $m\ Z$; then $a\ b$ is the sine of the angle of incidence, i. Divide the line $a\ b$ into three equal parts, and prolong it to the extent of two of these parts, viz., to p. Draw the line p parallel to $m\ Z$. The line joining o to n is the direction of the refracted ray. On making a line, $n\ s$, perpendicular to $m\ Z$, $n\ s = b\ p$. Further, $n\ s$ = sine $<) = r$. So that $a\ b : s\ n$ or : $b\ p) = 3 : 2$ or sin. i : sin. $r = \frac{3}{2}$.

Optical cardinal point of a simple collecting system.—Two refractive media (Fig. 527, L and G), which are separated from each other by a spherical surface (a, b), form a simple collecting system. It is easy to estimate the construction of an incident ray coming from the first medium (L) and falling obliquely upon the surface (a, b) separating the two media, as well as to ascertain its direction in the second medium, G, and also from the position of a luminous point in the first medium, to estimate the position of the corresponding focal point in the second medium. The factors required to be known are the following: L (Fig. 527) is the first, and G the second medium, a, b = the spherical surface whose centre is m. Of course, all the radii drawn from m to $a\ b$ ($m\ x$, $m\ n$) are perpendiculars, so that all rays falling in the direction of the radii must pass unrefracted through m. All rays of this sort are called rays or **lines of direction**; m, as the point of intersection of all these, is called the **nodal point.** The line which connects m with the vertex of the spherical surface, x, and which is prolonged in both directions, is called the **optic axis,** O Q. A plane (E, F) in x, perpendicular to O Q, is called the **principal plane,** and in it x is the **principal point.** The following facts have been ascertained: (1) All rays (a to a_5), which in the first medium are parallel with each other and with the optic axis, and fall upon $a\ b$, are so refracted in the second medium that they are all again united in one point (p_1) of the second medium. This is called the *second principal focus.* A plane in this point perpendicular to O Q is called the *second focal plane* (C D). (2) All rays (c to c_2), which in the first medium are parallel to each other, but not parallel to O Q, reunite in a point of the second focal plane (r), where the non-refracted directive ray (c_1, $m\ r$) meets this. (In this case, the angle formed by the rays c to c_2 with C Q must be very small.) The propositions 1 and 2 of course may be reversed; the divergent rays proceeding from p toward $a\ b$ pass into the first medium parallel to each other, and also with the axis C Q (a to a_5); and the rays proceeding from r pass into the first medium parallel to each other, but not parallel to the axis O Q (as c to c_2). (3) All rays, which in the second medium are parallel to each other (b to b_5) and with the axis O Q, reunite in a point in the first medium (p), called the *first focal point;* of course, the converse of this is true. A plane in this point perpendicular to O Q is called the *first focal plane* (A, B). The radius of the refractive surface (m, x) is equal to the difference of the distance of both focal points (p and p_1) from the principal focus (x); thus $m\ x = p_1\ x - p\ x$. From these comparatively simple propositions it is easy to determine the following points:—

FIG. 527.



1. **The construction of the refracted ray.**—Let A be the first (Fig. 528); B, the second medium; $c\ d$, the spherical surface separating the two; $a\ b$, the optical axis; k, the nodal point; p, the first and p_1 the second principal focus; C, D, the second focal plane. Suppose $x\ y$ to represent the direction of the incident ray, what is the construction of the refracted ray in the second medium? Prolong the refracted ray, P, k, Q parallel to x, y, then y, Q is the direction of the refracted ray (according to 2).

2. **Construction of the image for a given object.**—In Fig. 529, B, c, d, a, b, k, p, and p_1, C, D are as before. Suppose a luminous point (o) in the first medium, what is the position of the image in the second medium? Prolong the unrefracted ray (o, k, P), and draw the ray (o, x) parallel to the axis (a, b). The parallel rays (a, e and o, x) reunite in p (according to proposition 1) Prolong x, p_1 until it intersects the ray (o, P), then the image of o is at P, the rays of light (o x and o k) proceeding from the luminous point (o) reunite in P.

FIG. 528.



Construction of the refracted ray and the image in several refractive media.—If several refractive media be placed behind each other, we must proceed from medium to medium with the same methods as above described. This would be very tedious, especially when dealing with small objects. Gauss (1840) calculated that in such cases the method of construction is very simple. If the several media are "**centred**," *i. e.*, if all have the same optic axis, then the refractive indices of

FIG. 529.



such a centred system may be represented by two equal, strong, refractive surfaces at a certain distance. The rays falling upon the first surface are not refracted by it, but are essentially projected forward parallel with themselves to the second surface. Refraction takes place first at the second surface, just as if only *one* refractive surface was present. In order to make the calculation, we must know the refractive indices of the media, the radii of the refractive surfaces, and the distance of the refractive surfaces from each other.

Construction of the refracted ray is accomplished as follows: Let a b represent the optical axis (Fig. 530, I); H, the first focal point determined by calculation; h h, the principal plane; H_1, the second focal point; h_1, h_1, the second principal plane; k, the first, and k_1 the second nodal point; F, the second focal point; and F_1, F_1, the second focal plane. Make the ray of direction p k_1 parallel to m_1, n_1. According to proposition 2, p, k_1 and m_1, n_1 must meet in a point of the plane F_1 F_1. As p k_1 passes through unrefracted, the ray from n_1 must fall at r; n_1 r is, therefore, the direction of the refracted ray.

Construction of the focal point.—Let o be a luminous point (Fig. 530, II), what is the position of its image in the last medium? Prolong from o the ray of direction o k, and make o, x parallel to a b. Both rays are prolonged in a parallel direction to the second focal plane. The ray parallel to a b goes through F; m, k_1 as the ray of direction passes through unrefracted. O, where n, F, and m k_1 intersect each other, is the position of the image of o.

386. DIOPTRICS—RETINAL IMAGE—OPHTHALMOMETER.

—**Position of the cardinal points.**—The eye surrounded with air on the anterior surface of the cornea, represents a concentric system of refractive media with spherical separating surfaces. In order to ascertain the course of the rays through the various media of the eye, we must know the position of both principal foci of both nodal points as well as the two principal focal points. Gauss, Listing, and v. Helmholtz have calculated the position of these points. In order to make this calculation, we require to know the refractive indices of the media of the eye, the radii of the refractive surfaces, and the distance of the latter from each other. These will be referred to afterward. (1) The *first principal point* is 2.1746 mm.

and (2) the *second principal point* is 2.5724 mm. behind the anterior surface of the cornea. (3) The *first nodal point*, 0.7580 mm. ; and (4) the *second nodal point*, 0.3602 mm. in front of the posterior surface of the lens. (5) The *second principal focus*, 14.6470 mm. behind the posterior surface of the lens; and (6) the *first principal focus*, 12.8326 in front of the anterior surface of the cornea.

FIG. 530.



Listing's reduced eye.—The distance between the two principal points, or the two nodal points, is so small (only 0.4 mm.), that, practically, without introducing any great error in the construction, we may assume *one* mean nodal or principal point lying between the two nodal or principal points. By this simple procedure

FIG. 531.



we gain *one* refractive surface for all the media of the eye, and only *one* nodal point, through which all the rays of direction from without must pass without being refracted. This schematic simplified eye is called "**the reduced eye**" of Listing.

Formation of the retinal image.—Thus, the construction of the image on the retina becomes very simple. In distinct vision, the **inverted image** is formed on the retina. Let A B represent an object placed vertically in front of the eye (Fig. 531). A pencil of rays passes from A into the eye; the ray of direction, A *d*, passes without refraction through the nodal point, *k*. Further, as the focal point for the luminous point, A, is upon the retina, all the rays proceeding from A must reunite in *d*. The same is true of the rays proceeding from B, and, of course, for rays sent out from an intermediate point of the body, A B. The retinal image is, as it were, a mosaic, composed of innumerable foci of the object. As all the rays of direction must pass through the common nodal point, *k*, this is also called the "*point of intersection of the visual rays.*"

The inverted image on the retina is easily seen in the excised eye of an albino rabbit, by holding up any object in front of the cornea and observing the inverted image through the transparent coats of the eyeball.

The size of the retinal image may also be calculated, provided we know the size of the object, and its distance from the cornea. As the two triangles, A B *k* and *c d k* are similar, A B : *c d* = *f k* : *k g*, so that *c d* = (A B, *k g*) : *f k*. All these values are known, viz., *k g* = 15.16 mm.; further, *f k* = *a k* × *a*, *f*, where *a f* is measured directly, and *a k* = 7.44 mm. The size of A B is measured directly.

The angle, A *k* B, is called the **visual angle**, and of course it is equal to the angle *c k d*. It is evident that the nearer objects, *x y*, and *r s*, must have the same visual angle. Hence, all the three objects, A B, *x y*, and *r s*, give a retinal image of the same size. Such objects, whose ends when united with the nodal point form a visual angle of the same size, and consequently form retinal images of the same size, have the same "**apparent size.**"

In order to determine the optical cardinal points by calculation, after the method of Gauss, we must know the following factors:—

1. **The refractive indices**: for the cornea, 1.377; aqueous humor, 1.377; lens, 1.454 (as the mean value of all the layers); vitreous humor, 1.336; air being taken as 1, and water 1.335.

2. **The radii of the spherical refractive surfaces**: of the cornea, 7.7 mm.; of the anterior surface of the lens, 10.3; of the posterior, 6.1 mm.

3. **The distance of the refractive surfaces**: from the vertex of the cornea to the anterior surface of the lens, 3.4 mm.; from the latter to the posterior surface of the lens (axis of the lens), 4 mm.; diameter of the vitreous humor, 14.6 mm. The total length of the optic axis is 22,0 mm.

[**Kühne's Artificial Eye.**—The formation of an inverted image, and the other points in the dioptrics of the eye can be studied most effectively on Kühne's artificial eye, the course of the rays of light being visible in water tinged with eosine.]

Ophthalmometer.—This is an instrument to enable us to measure the radii of the refractive media of the eye. As the normal curvature cannot be accurately measured on the dead eye, owing to the rapid collapse of the ocular tunics, we have recourse to the process of Kohlrausch, for calcu-

FIG. 532.



Scheme of the ophthalmometer of Helmholtz.

lating the radii of the refractive surfaces from the size of the reflected images in the living eye. *The size of a luminous body is to the size of its reflected image, as the distance of both to half the radius of the convex mirror.* Hence, it is necessary to measure the size of the reflected image. This is

done by means of the ophthalmometer of Helmholtz (Fig. 532). The apparatus is constructed on the following principle: If we observe an object through a glass plate placed obliquely, the object appears to be displaced laterally; the displacement becomes greater, the more obliquely the plate is moved. Suppose the observer, A, to look through the telescope, F, which has the plate, G, placed obliquely in front of the *upper* half of its objective, he sees the corneal reflected image, *a b*, of the eye, B, and the image appears to be displaced laterally, viz., to *a′ b′*. If a second plate, G, be placed in front of the *lower* half of the telescope, but placed in the opposite direction, so that both plates, corresponding to the middle line of the objective, intersect at an angle, then the observer sees the reflected image, *a b*, displaced laterally to *a″ b″*. As both glass plates rotate round their point of intersection, the position of both is so selected, that both reflected images just touch each other with their inner margins (so that *b′* abuts closely upon *a″*). The size of the reflected image can be determined from the size of the angle formed by both plates, but we must take into calculation the thickness of the glass plates and their refractive indices. The size of the corneal image, and also that in the lens, may be ascertained in the passive eye, and also in the eye accommodated for a near object, and the length of the radius of the curved surface may be calculated therefrom (*Helmholtz and others*).

Fluorescence.—All the media of the eye, even the retina, are slightly fluorescent; the lens most, the vitreous humor least (*v. Helmholtz*).

Erect Vision.—As the **retinal image is inverted,** we must explain how we see objects *upright*. By a *psychical* act, the impulses from any point of the retina are again referred to the exterior, in the direction through the nodal point; thus the stimulation of the point *d* is referred to A, that of *c* to B (Fig. 531). The reference of the image to the external world happens thus, that all points appear to lie in a surface floating in front of the eye, which is called the **field of vision.** The field of vision is the inverted surface of the retina projected externally; hence, the field of vision appears erect again, as the inverted retinal image is again projected internally but inverted (Fig. 531).

That the stimulation of any point is again projected in an inverse direction through the nodal point, is proved by the simple experiment, that pressure upon the *outer* aspect of the eyeball is projected or referred to the *inner* aspect of the field of vision. The entoptical phenomena of the retina are similarly projected externally and inverted; so that, *e.g.*, the entrance of the optic nerve is referred externally to the yellow spot (see § 393). All sensations from the retina are projected externally.

387. **ACCOMMODATION OF THE EYE.**—According to No. 2 (p. 793), the rays of light proceeding from a luminous point, *e.g.*, a flame, and acted upon by a collecting (convex) lens, are brought to a focus or focal point, which has always a definite relation to the luminous object. If a projection surface or screen be placed at this distance from the lens, a real and inverted image of the object is obtained upon the screen. If the screen be placed nearer to the lens (Fig. 524, IV, *a, b*), or further away from it (*c, d*), no distinct image of the object is formed, but **diffusion circles** are obtained; because, in the former case, the rays have not united, and in the latter, because the rays, after uniting, have crossed each other and become divergent. If the luminous point be brought nearer to, or removed further from the lens, in order to obtain a distinct image, in every case, the screen must be brought nearer, or removed from the lens, to keep the same distance between the lens and the screen. If, however, the screen be fixed permanently, while the distance between the luminous point and the lens varies, a distinct image can only be obtained upon the screen, provided the lens, as the luminous point approaches it, becomes more convex, *i. e.*, refracts the rays of light more strongly—conversely, when the distance between the luminous point and the lens becomes greater, the lens must become less curved, *i. e.*, refract less strongly.

In the eye, the projection surface or screen is represented by the retina, which is permanently fixed at a certain distance; but the eye has the power of forming distinct images of near and distant objects upon the retina, so that the refractive power, *i. e.*, the form of the crystalline lens in the eye, must undergo a change in curvature corresponding in every case to the distance of the object. [It is important to remember, that we cannot see a near object and a distant one with equal distinctness *at the same time*, and hence arises the necessity for accommodation.]

Accommodation.—By the term "accommodation of the eye," is understood that property of the eye, whereby it forms distinct images of distant as well as near objects upon the retina. This power depends upon the fact, that the **crystalline lens alters its curvature,** becoming more convex (thicker), or less curved (flatter), according to the distance of the object. When the lens is absent from the eyeball, accommodation is impossible (*Th. Young*, in *Donders*, "Accommodation and Refraction of the Eye)."

During **rest** [or **negative accommodation**], or when the eye is passive, it is

accommodated for the *greatest distance, i. e.*, images of objects placed at an infinite distance (*e. g.*, the moon) are found upon the retina. In this case, rays coming from such a distance are practically *parallel*, and when they enter the eye, are in the *passive normal* eye (**emmetropic**) brought to a focus on the retina. When looking at a distant object, a distinct image is formed on the retina without the aid of any muscular action.

That distant objects are seen without the aid of any muscular action is shown by the following considerations: (1) With the normal, or emmetropic eye, we can see distant objects clearly and distinctly, without experiencing any feeling of effort. On opening the eyelids after a long period of rest, the objects at a distance are at once distinctly visible in the field of vision. (2) If, in consequence of paralysis of the mechanism of accommodation (*e.g.*, through paralysis of the oculomotor nerve—§ 345, 7), the eye is unable to focus images of objects placed at different distances, still distinct images are obtained

FIG. 533.



Anterior quadrant of a horizontal section of the eyeball, cornea, and lens. *a*, substantia propria of the cornea; *b*, Bowman's elastic membrane; *c*, anterior corneal epithelium; *d*, Descemet's membrane; *e*, its epithelium; *f*, conjunctiva; *g*, sclerotic; *h*, iris; *i*, sphincter iridis; *j*, ligamentum pectinatum iridis, with the adjoining vacuolated tissue; *k*, canal of Schlemm; *l*, longitudinal; *m*, circular muscular fibres of the ciliary muscle; *n*, ciliary process; *o*, ciliary part of the retina; *q*, canal of Petit, with Z, zonule of Zinn in front of it; and *p*, the posterior layer of the hyaloid membrane; *r*, anterior, *s*, posterior part of the capsule of the lens; *t*, choroid; *u*, perichoroidal space; T, pigment epithelium of the iris; *x*, margin of the lens.

of distant objects. Thus, paralysis of the mechanism of accommodation is always accompanied by inability to focus a near object, never a distant object. A temporary paralysis occurs with the same results when a solution of atropin or duboisin is dropped into the eye, and also in poisoning with these drugs (§ 392).

When the eye is accommodated for a **near object** [**positive accommodation**], the lens is thicker, its anterior surface is more curved (**convex**), and projects further into the anterior chamber of the eye (*Cramer*, 1851, *v. Helmholtz*, 1853). The mechanism producing this result is the following: During **rest**, the lens is kept somewhat flattened against the vitreous humor lying behind it, by the tension of the stretched zonule of Zinn, which is attached round the margin of the lens (Fig. 533, Z). When the muscle of accommodation, the ciliary muscle (*l*, *m*), contracts, it pulls forward the margin of the choroid, so that the zonule of Zinn in

intimate relation with it is **relaxed**. [When we accommodate for a **near** object, the **ciliary muscle contracts**, pulls forward the choroid, relaxes the zonule of Zinn, and this in turn diminishes the tension of the anterior part of the capsule of the lens.] The lens assumes a more curved form, in virtue of its **elasticity**, so that it becomes more convex as soon as the tension of the zonule of Zinn, which keeps it flattened, is diminished (Fig. 534). As the posterior surface of the lens lies in the saucer-shaped unyielding depression of the vitreous humor, the **anterior surface** of the lens in becoming more **convex** must necessarily protrude more forward.

Nerves.—According to Hensen and Völckers, the origin of the nerves of accommodation lies in the most anterior root bundles of the oculomotorius. Stimulation of the posterior part of the floor of the third ventricle causes accommodation; if a part lying slightly posterior to this be stimulated, contraction of the pupil occurs. On stimulating the limit between the third ventricle and the aqueduct, there results

FIG. 534.



Scheme of accommodation for near and distant objects. The right side of the figure represents the condition of the lens during accommodation for a near object, and the left side when the eye is at rest. The letters indicate the same parts on both sides; those on the right side are marked thus ′; *A*, left, *B*, right half of the lens; *C*, cornea; *S*, sclerotic; *C.S.*, canal of Schlemm; *V.K.*, anterior chamber; *J*, iris; *P*, margin of the pupil; *V*, anterior surface; *H*, posterior surface of the lens; *R*, margin of the lens; *F*, margin of the ciliary processes; *a* and *b*, space between the two former; the line *Z*, *X*, indicates the thickness of the lens during accommodation for a near object; *Z*, *V*, the thickness of the lens when the eye is passive.

contraction of the internal rectus muscle, while stimulation of the other parts around the *iter* causes contraction of the superior rectus, levator palpebræ, rectus inferior, and inferior oblique muscles.

Proofs.—That the lens undergoes an alteration in its curvature, during accommodation, is proved by the following facts:—

1. **Purkinje-Sanson's Images.**—If a lighted candle be held at one side of the eye, or if light be allowed to fall on the eye through two triangular holes, placed above each other and cut in a piece of cardboard, in the latter case the observer will see three pairs of reflected images [in the former, three images]. The brightest and most distinct image (or pair of images) is **erect** and is produced by the anterior surface of the **cornea** (Fig. 535, *a*). The second image (or pair of images) is also **erect**. It is the largest, but it is not so bright (*b*), and it is reflected by the **anterior surface** of the **lens**. (The size of a reflected image from a convex mirror is greater, the longer the radius of curvature of the reflecting surface.) The latter image lies 8 mm. *behind* the plane of the pupil. The third image (or pair of images) is of medium size and medium brightness—it is **inverted** and lies nearly in the plane of the pupil (*c*). The posterior capsule of the lens, which reflects the last image, acts like a concave mirror. If a luminous object be placed at a distance from a concave mirror, its inverted, diminished, *real* image lies close to the focus toward the side of the object. If the images be studied when the observed eye is passive, *i. e.*, in the phase of negative accommodation, on asking the person experi-

FIG. 535.



Sanson-Purkinje's images. *a*, *b*, *c*, during negative, and *a*,, *b*,, *c*,, positive accommodation.

mented upon to accommodate his eye for a near object, at once a change in the relative position and size of some of the images is apparent. The middle pair of images reflected by the anterior surface of the lens diminish in size and approach each other (b), which depends upon the fact that the anterior surface of the lens has become more convex. At the same time, the image (or pair of images) comes nearer to the image formed by the cornea (a, and c,) as the anterior surface of the lens lies nearer to the cornea. The other images (or pair of images) neither change their size nor position. Helmholtz, with the aid of the ophthalmometer, has measured the diminution of the radius of curvature of the anterior surface of the lens during accommodation for a near object.

FIG. 536.

Phakoscope of Helmholtz.

[**Phakoscope.**—These images may be readily shown by means of the phakoscope of v. Helmholtz (Fig. 536). It consists of a triangular box with its angles cut off and blackened inside. The observer's eye is placed at a, while on the opposite side of the box are two prisms, b, b^1; the observed eye is placed at the side of the box opposite to C. When a candle is held in front of the prisms, b and b^1, three pairs of images are seen in the observed eye. Ask the person to accommodate for a distant object, and note the position of the images. On pushing up the slide C with a pin attached to it, and asking him to accommodate for the pin, *i. e.*, for a near object, the position and size of the middle images chiefly will be seen to alter as described above.]

2. In consequence of the increased curvature of the lens during accommodation for a near object, the refractive indices within the eye must undergo a change. According to v. Helmholtz, the annexed measurements obtain in negative and positive accommodation respectively.

3. **Lateral View of the Pupil.**—If the passive eye be looked at from the side, we observe only a small black strip of the pupil, which becomes broader as soon as the person experimented on accommodates for a near object, as the whole pupil is pushed more forward.

4. **Focal Line.**—If light be admitted through the cornea into the anterior chamber, the "focal line" formed by the concave surface of the cornea falls upon the iris. If the experiment be made upon a person whose eye is accommodated for a distant object, so that the line lies near the margin of the pupil, it gradually recedes

Accommodation.	Negative—Mm.	Positive—Mm.
Radius of the cornea,	8	8
Radius of anterior surface of lens,	10	6
Radius of posterior surface of lens,	6	5.5
Position of the vertex of the outer surface of the lens behind the vertex of the cornea,	3.6	3.2
Position of the posterior vertex of the lens,	7.2	7.2
Position of the anterior focal point,	12.9	11.24
Position of the first principal point,	1.94	2.03
Position of the second principal point,	6.96	6.51
Position of the posterior focal point behind the anterior vertex of the cornea,	22.23	20.25

toward the scleral margin of the iris, as soon as the person accommodates for a near object, because the iris becomes more oblique as its inner margin is pushed forward.

5. **Change in Size of Pupil.**—On accommodating for a **near** object, the **pupil contracts**, while in accommodation for a **distant** object, it **dilates** (*Descartes*, 1637). The contraction takes place slightly after the accommodation (*Donders*). This phenomenon may be regarded as an associated movement, as both the ciliary muscle and the sphincter pupillæ are supplied by the oculomotorius (§ 345, 2, 3). A reference to Fig. 533 shows that the latter also directly supports the ciliary muscle; as the inner margin of the iris passes inward (toward r), its tension tends to be propagated to the ciliary margin of the choroid, which also must pass inward. The ciliary processes are made tense, chiefly by the ciliary muscle (tensor choroidæ). Accommodation can still be performed, even though the iris be absent or cleft.

6. **Internal Rotation of the Eye.**—On rotating the eyeball inward, accommodation for a near object is performed involuntarily. As rotation of both eyeballs inward takes place when the axes of

vision are directed to a *near* object, it is evident that this must be accompanied involuntarily by an accommodation of the eye for a near object.

7. **Time for Accommodation.**—A person can accommodate from a near to a distant object (which depends upon relaxation of the ciliary muscle) much more rapidly than conversely, from a distant to a near object (*Vierordt, Aeby*). The process of accommodation requires a longer time, the nearer the object is brought to the eye (*Vierordt, Völckers and Hensen*). The time necessary for the image reflected from the anterior surface of the lens to change its place during accommodation is less than that required for subjective accommodation (*Aubert and Angelucci*).

8. **Line of Accommodation.**—When the eye is placed in a certain position during accommodation, we may see not *one* point alone distinctly, but a whole series of points behind each other. Czermak called the line in which these points lie the *line of accommodation*. The more the eye is accommodated for a distant object, the longer does this line become. All objects placed at a greater distance from the eye than 60 to 70 metres appear equally distinct to the eye. The line becomes shorter the more we accommodate for a near object—*i. e.*, when we accommodate as much as possible for a near object, a second point can only be seen indistinctly at a *short* distance behind the object looked at.

9. The **nerves** concerned in the mechanism of accommodation are referred to under *Oculomotorius* (§ 345, and again in § 704).

Scheiner's Experiment.—The experiment which bears the name of Scheiner (1619) serves to illustrate the refractive action of the lens during accommodation for a near object, as well as for a distant object. Make two small pin holes (S, *d*) in a piece of cardboard (Fig. 537, K, K_1), the holes being nearer to each other than the diameter of the pupil. On looking through these holes, S, *d*, at two needles (*p* and *r*) placed behind each other, then on accommodating for the *near* needle (*p*) the far needle (*r*) becomes double and inverted. On accommodating for the **near** needle (*p*), of course the rays proceeding from it fall upon the retina at the focus (p_1); while the rays coming from the far needle (*r*) have *already* united and crossed in the vitreous humor, whence they diverge more and more and form two pictures ($r_{'}$,$r_{''}$) on the retina. If the *right* hole in the cardboard (*d*) be closed, the *left* picture on the retina ($r_{''}$) of the double images of the far needle disappears. An analogous result is obtained on accommodating for the **far** needle (R). The near needle (P) gives a double image ($P_{'}$, $P_{''}$), because the rays from it have not yet come to a focus. On closing the *right* hole ($d_{'}$), the *right* double image ($P_{'}$) disappears (*Porterfield*). When the eye of the observer is accommodated for the *near* needle, on closing one aperture the double image of the distant point disappears on that side; but if the eye is accommodated for the *distant* needle, on closing one hole the crossed image of the near needle disappears.

FIG. 537.



Scheiner's Experiment.

388. REFRACTIVE POWER OF THE EYE—ANOMALIES OF REFRACTION.—The limits of distinct vision vary very greatly in different eyes. We distinguish the **far point [p. r., punctum remotum]** and the **near point [p. p., punctum proximum]**; the former indicates the distance to which an object may be removed from the eye, and may still be seen distinctly; the latter, the distance to which any object may be brought to the eye, and may still be seen distinctly. The distance between these two points is called the **range of accommodation**. The types of eyeball are characterized as follows:—

1. **The normal** or **emmetropic eye** is so arranged when at *rest* that parallel rays (Fig. 538, *r*, *r*) coming from the most distant objects can be focused on the retina (r_1). The *far* point, therefore, is $= \infty$ (infinity). When accommodating as much as possible for a near object, whereby the convexity of the lens is increased (Fig. 538, *a*) rays from a luminous point placed at a distance of 5 inches are still focused on the retina, *i. e.*, the *near point* is = 5 inches (1 inch = 27 mm.). The range of accommodation, or ["*the range of distinct vision*"], therefore, is from 5 inches (10-12 cm.) to ∞.

FIG. 538.



Condition of refraction in the normal *passive* eye and during *accommodation*.

2. **The short-sighted, myopic eye** (or long eye) cannot, *when at rest*, bring parallel rays from infinity to a focus on the retina (Fig. 539). These rays decussate within the vitreous humor (at O), and after crossing form diffusion circles upon the retina. The object must be removed from the *passive* eye to a distance of 60 to 120 inches (to *f*), in order that the rays may be focused on the retina. The passive myopic eye, therefore, can only focus *divergent* rays upon the retina. The *far point*, therefore, lies abnormally near. With an intense effort at accommodation, objects at a distance of 4 to 2 inches, or even less, from the eye may be seen distinctly. The *near point*, therefore, lies abnormally near; the *range of accommodation* is diminished.

FIG. 539.



Myopic Eye.

Short-sightedness, or myopia, usually depends upon congenital, and frequently hereditary, elongation of the eyeball. This anomaly of the refractive media is easily corrected by using a **diverging lens (concave)**, which makes parallel rays divergent, so that they can be brought to a focus on the retina. It is remarkable that most children are myopic when they are born. This myopia, however, depends upon a too-curved condition of the cornea and lens, and on the lens being too near the cornea. As the eye grows, this short-sightedness disappears. The **cause** of myopia in children is ascribed to the continued activity of the ciliary muscle in reading, writing, etc., or the continued convergence of the eyeballs, whereby the external pressure upon the eyeball is increased.

FIG. 540.



Hypermetropic Eye.

3. **The long-sighted, hypermetropic eye,** hyperoptic (flat eye) when at *rest*, can only cause convergent rays to come to a focus on the retina (Fig. 540). Distinct images can only be formed when the rays proceeding from objects are rendered convergent by means of a convex lens, as parallel rays would come to a focus behind the retina (at *f*). All rays proceeding from natural objects are either divergent, or at most nearly

parallel, never convergent. Hence, a long-sighted person, when the eye is *passive*, *i. e.*, is *negatively* accommodated, cannot see distinctly without a convex lens. When the ciliary muscle contracts, slightly convergent, parallel, and even slightly divergent rays may be focused, according to the increasing degree of the accommodation. The *far point* of the eye is negative, the *near point* abnormally distant (over 8 to 80 inches), while the *range of accommodation* is infinitely great.

The **cause** of hypermetropia is abnormal shortness of the eye, which is generally due to imperfect development in all directions. It is **corrected** by using a **convex** lens.

[**Defective Accommodation.**—In the **presbyopic eye**, or long-sighted eye of old people, the near point is further away than normal, but the far point is still unaffected. In such cases, the person cannot see a near object distinctly, unless it be held at a considerable distance from the eye. It is due to a defect in the mechanism of accommodation, the lens becoming somewhat flatter, less elastic, and denser with old age, while the ciliary muscle becomes weaker. In hypermetropia, on the contrary, the mechanism of accommodation may be perfect, yet from the shape of the eye the person cannot focus on his retina the rays of light from a near object. In presbyopia the range of distinct vision is diminished. The defect is remedied by weak **convex** glasses. The defect usually begins about forty-five years of age.]

Estimation of the Far Point—Snellen's Types.—In order to determine the *far point* of an eye, gradually bring nearer to the eye objects which form a visual angle of 5 minutes (*e. g.*, Snellen's small-type letters, or the *medium* type, 4 to 8, of Jaeger), until they can be seen distinctly. The distance from the eye indicates the far point. In order to determine the far point of a *myopic* person, place at 20 inches distant from the eye the same objects which give a visual angle of 5 minutes, and ascertain the *concave lens* which will enable the person to see the objects distinctly. To estimate the *near point*, bring small objects (*e. g.*, the finest print) nearer and nearer to the eye, until it finally becomes indistinct. The distance at which one can still see distinctly indicates the far point.

Optometer.—The optometer may also be used to determine the *near* and *far points*. A small object, *e. g.*, a needle, is so arranged as to be movable along a scale, along which the eye to be investigated can look as a person looks along the sight of a rifle. The needle is moved as near as possible, and then removed as far as possible, in each case as long as it is seen distinctly. The distance of the near and far point and the range of accommodation can be read off directly upon the scale (*Gräefe*).

389. FORCE OF ACCOMMODATION.—Force.—The range of accommodation, which is easily determined experimentally, does not by itself determine the proper *power* or *force* of accommodation. The measure of the latter depends upon the *mechanical work* done by the muscle of accommodation, or the ciliary muscle. Of course this cannot be directly determined in the eye itself. Hence, this force is measured by the *optical effect*, which results in consequence of the change in the shape of the lens, brought about by the energy of the contracting muscle.

In the **normal eye**, during the passive condition, the rays coming from infinity, and therefore parallel (which are dotted in Fig. 541), are focused upon the retina at *f*. If rays coming from a distance of 5 inches (p. 806) are to be focused, the whole available energy of the ciliary muscle must be brought into play to allow the lens to become more convex, so that the rays may be brought to a focus at *f*. The energy of accommodation, therefore, produces an *optical effect* in as far as it increases the convexity of the anterior surface of the passive lens (A), by the amount indicated by B. Practically, we may regard the matter as if a new convex lens (B) were added to the existing convex lens (A). What, therefore, must be the focal distance of the lens (B), in order that rays coming from the near point (5 inches) may be focused upon the retina at *f*? Evidently, the lens B must make the diverging rays coming from *p*, parallel, and then A can focus them at *f*. Convex lenses cause those rays proceeding from their *focal points* to pass out at the other side as parallel rays (§ 385, I). Hence, in our case, the lens must have a focal distance of 5 inches. The normal eye, therefore, with

FIG. 541.



the far point $= \infty$, and the near point $= 5$ inches, has a power of accommodation equal to a lens of 5 inches focal distance. When the lens by the energy of accommodation is rendered more powerfully refractive, the increase (B) can readily be eliminated by placing before the eye a *concave lens* which possesses exactly the opposite optical effect of the increase of accommodation (B). Hence, it is possible to indicate the power (force) of accommodation of the eye by a lens of a definite focal distance, *i. e.*, by the optical effect produced by the latter. Therefore, according to Donders, the measure of the force of accommodation of the eye is the reciprocal value of the focal distance of a concave lens, which, when placed before the accommodated eye, so refracts the rays of light coming from the near point (p) as if they came from the far point.

Example.—We may calculate the force of the accommodation according to the following formula: $\frac{1}{x} = \frac{1}{p} - \frac{1}{r}$, *i. e.*, the force of accommodation, expressed as the dioptric value of a lens (of x inch focal distance), is equal to the difference of the reciprocal values of the distances of the near point (p) and of the far point (r) of the eye. In the *emmetropic* eye, as already mentioned, $p = 5$, $r = \infty$. Its force of accommodation is therefore $\frac{1}{x} = \frac{1}{p} - \frac{1}{8}$, so that $x = 5$, *i. e.*, it is equal to a lens of 5 inches focal distance. In a *myopic* eye, $p = 4$, $r = 12$, so that $\frac{1}{x} = \frac{1}{4} - \frac{1}{12}$, *i. e.*, $x = 6$. In another myopic eye, with $p = 4$ and $r = 20$, then $x = 5$, which is a normal force of accommodation. Hence, it is evident that two different eyes, possessing a very different *range* of accommodation, may nevertheless have the same *force* of accommodation. **Example.**—The one eye has $p = 4$, $r = \infty$, the other, $p = 2$, $r = 4$. In both cases, $\frac{1}{x} = \frac{1}{4}$, so that the force of accommodation of both eyes is equal to the dioptric value of a lens of 4 inches focal distance. Conversely, two eyes may have the same range of accommodation, and yet their force of accommodation be very unequal. **Example.**—The one eye has $p = 3$, $r = 6$; the other $p = 6$, $r = 9$. Both, therefore, have a range of accommodation of 3 inches. For these, the force of accommodation, $\frac{1}{x} = \frac{1}{3} - \frac{1}{6}$, $x = 6$; and $\frac{1}{x} = \frac{1}{6} - \frac{1}{9}$, $x = 18$.

Relation of range to force of accommodation.—The *general law* is, that, the *ranges* of accommodation of two eyes being equally great, then their *forces* of accommodation are equal, provided that their near points are the same. If the *ranges* of accommodation for both eyes are equally great, but their near points unequal, then the *forces* of accommodation are also unequal—the latter being greater in the eyes with the smallest near point. This is due to the fact that every difference of distance *near* a lens has a much greater effect upon the image as compared with differences in the distance *far* from a lens. The emmetropic eye can see distinctly objects at 60 to 70 metres, and even to infinity, without accommodation.

While p and r may be directly estimated in the emmetropic and myopic eyes, this is impossible with the hypermetropic (long-sighted) eye. The far point in the latter is negative; indeed, in very pronounced hypermetropia even the near point may be negative. The far point may be estimated by making the hypermetropic eye practically a normal eye by using suitable convex lenses. The *relative* near point may then be determined by means of the lens.

Even from the 15th year onward, the power of accommodation is generally diminished for near objects—perhaps this is due to a diminution of the elasticity of the lens (*Donders*).

390. **SPECTACLES.**—The focal distance of concave (diverging), as well as convex (converging), spectacles, depends upon the refractive index of the glass (usually 3 : 2), and on the length of the radius of curvature. If the curvature of both sides of the lens is the same (biconcave or biconvex), then, with the ordinary refractive index of glass, the focal distance is the same as the radius of curvature. If one surface of the lens is plane, then the focal distance is twice as great as the radius of the spherical surface. Spectacles are arranged according to their *focal distance in inches*, but a lens of shorter focal distance than 1 inch is generally not used. They may also be arranged according to their *refractive power*. In this case, the refractive power of a lens of 1 inch focus is taken as the unit. A lens of 2 inches focus refracts light only half as much as the unit measure of 1 inch focus; a lens of 3 inches focus refracts ⅓ as strongly, etc. This is the case both with convex and concave lenses, the latter, of course, having a negative focal distance; thus, "concave—⅛," indicates that a concave lens diverges the rays of light one-eighth as strongly as the concave lens of 1 inch (negative) focal distance.

Choice of Spectacles.—Having determined the *near* point in a **myopic** eye, of course we require to render parallel the divergent rays coming from the far point, just as if they came from infinity. This is done by selecting a **concave** lens of the focal distance of the far point. The greatest distance is the far point of the emmetropic eye. Suppose a myopic eye with a far point of 6 inches, then such a person requires a *concave* lens of 6 inches focus to enable him to see distinctly at the greatest distance. Thus, in a myopic eye, the distance of the far point from the eye is directly equal to the focus of the (weakest) concave lens, which enables one to see distinctly objects at the greatest distance. These lenses generally have the same number as the spectacles required to correct the

defect. **Example.**—A myopic eye with a far point of 8 inches requires a *concave* lens of 8 inches focus, *i. e.*, the concave spectacles No. 8. For the **hypermetropic** (long-sighted) eye, the focal distance of the strongest **convex** lens, which enables the hypermetropic eye to see the most distant objects distinctly, is at the same time the distance of the far point from the eye. **Example.**—A hypermetropic eye which can see the most distant objects with the aid of a *convex* lens of 12 inches focus has a far point of 12; the proper spectacles are convex No. 12.

[**Diopter** or **Dioptric.**—The focal length of a lens used to be expressed in inches; and as the unit was taken as 1 inch, necessarily all weaker lenses were expressed in fractions of an inch. In the method advocated by Donders, the standard is a lens of a focal distance of 1 metre (39.370 English inches, about 40 inches), and this unit is called a *dioptric*. Thus, the standard is a weak lens, so that the stronger lenses are multiples of this. Hence, a lens of 2 dioptrics = one of about 20 inches focus; 10 dioptrics = 4 inches focus; and so on. The lenses are numbered from No. 1, *i. e.*, 1 dioptric onward. It is convenient to use signs instead of the words convex and concave. For convex the sign *plus* + is used, and for concave the sign *minus* —. Thus a + 4.0 means a convex lens of 4 dioptrics, and a —4.0 = a concave lens of 4 dioptrics.]

In all cases of myopia or hypermetropia, the person ought to wear the proper spectacles. In a **myopic eye**, when the far point is still more than 5 inches, the patient ought always to wear spectacles; but generally the working distance, *e. g.*, for reading, writing and for handicrafts, is about 12 inches from the eye. If the person desires to do finer work (etching, drawing), requiring the object to be brought nearer to the eye, so as to obtain a larger image upon the retina, then he should either remove the spectacles altogether or use a weaker pair.

The **hypermetropic person** ought to wear his convex spectacles when looking at a near object, and especially when the illumination is feeble, because then, owing to the dilatation of the pupil, the diffusion circles of the eye tend to become very pronounced. It is advisable to wear at first convex spectacles, which are slightly too strong. **Cylindrical lenses** are referred to under *Astigmatism*. Spectacles provided with dull colored or blue glasses are used to protect the retina when the light is too intense. **Stenopaic spectacles** are narrow diaphragms placed in front of the eye, which cause it to move in a definite direction in order to see through the opening of the diaphragm.

391. CHROMATIC AND SPHERICAL ABERRATION, ASTIGMATISM.—Chromatic Aberration.—All the rays of *white* light which undergo refraction are at the same time broken up by dispersion into a bundle of rays which, when they are received on a screen, form a spectrum. This is due to the fact that the different colors of the spectrum possess different degrees of refrangibility. The violet rays are refracted most strongly; the red rays least.

A white point on a black ground does not form a sharp simple image on the retina, but many colored points appear after each other. If the eye is accommodated so strongly as to focus the violet rays to a sharp image, then all the other colors must form concentric diffusion circles, which become larger toward the red. In the centre of all the circles, where all the colors of the spectrum are superposed, a white point is produced by their mixture, while around it are placed the colored circles. The distance of the focus of the red rays from that of the violet in the eye = 0.58 to 0.62 mm. The focal distance for red is, according to v. Helmholtz, for the reduced eye, 20.524 mm.; for violet, 20.140 mm. Thus, the near and far points for violet light are nearer each other than in the case of red light; white objects, therefore, appear reddish when beyond the far point, but when nearer than the near point they are violet. Hence the eye must accommodate more strongly for red rays than for violet, so that we judge red objects to be nearer us than violet objects placed at an equal distance (*Brücke*).

Monochromatic, or Spherical Aberration.—Apart from the decomposition or dispersion of white light into its components—the rays of white light, proceeding from a point if transmitted through refractive spherical surfaces—we find that, before the rays are again brought to a focus the *marginal* rays are more strongly refracted than those passing through the central parts of the lens. Hence, there is not *one* focus, but many. In the eye this defect is naturally **corrected** by the *iris*, which, acting as a diaphragm, cuts off the marginal rays (Fig. 531), especially when the lens is most convex, when the pupil also is most contracted. In addition, the margin of the lens has less refractive power than the central substance; lastly, the margins of the refractive spherical surfaces of the eye are less curved toward their margins than the parts lying nearer to the optical axis. Compare the form of the cornea (p. 783) and the lens (p. 790).

Imperfect Centring of the Refractive Surfaces.—The sharp projection of an image is somewhat interfered with by the fact that the refractive surfaces are not exactly centred (*Brücke*). Thus, the vertex of the cornea is not exactly in the termination of the optic axis; the vertices of both surfaces of the lens, and even the different layers of the lens itself, are not exactly in the optic axis. The variations, however, and the disturbances produced thereby are very small indeed.

Regular Astigmatism.—When the curvature of the refractive surfaces of the eye is unequally great in its different meridians, of course the rays of light cannot be united or focused in one point. Generally, in such cases, the cornea is more curved in its vertical meridian and least in the horizontal

(as is shown by ophthalmometric measurements, p. 798). The rays passing through the vertical meridian come to a focus, *first*, in a horizontal focal line; while the rays entering horizontally unite afterward in a vertical line. There is thus no common focus for the light rays in the eye; hence the name "astigmatism." The lens also is unequally curved in its meridians, but it is the reverse of the cornea; consequently, a part of the inequality of the curvature of the cornea is thereby compensated, and only a part of it affects the rays of light. The emmetropic eye has a *very slight* degree of this inequality (normal astigmatism). If two very fine lines of equal thickness be drawn on white paper, so as to intersect each other at right angles, it will be found that, in order to see the horizontal line quite sharply, the paper must be brought slightly nearer to the eye than when we focus the vertical line. When the inequality of curvature of the meridian is considerable, of course exact vision is no longer possible.

[Fig. 542 shows the effect of an astigmatic surface on the rays of light. Let *a b c d* be such a surface, and suppose diverging rays to proceed from *f*. The rays passing through *c d* come to a

FIG. 542.



Action of an astigmatic surface on a cone of light (*Frost*).

focus at f_1, while those passing through the vertical meridian are focused at f_2. The outline of the cone of rays between *a b c d* and f_2 varies, as shown in the figure. At a certain part it is oval, with its axis vertical, at another the long axis of the oval is horizontal, while at other places it is circular, or the rays are focused in a horizontal or vertical line.]

Correction.—This condition is corrected by a **cylindrical lens**, *i. e.*, a lens so cut as to be without curvature in one direction, while in the other direction (vertical to the former) it is curved. The lens is placed in front of the eye, so that the direction of its curvature coincides with the direction of least curvature of the eye (*v. Helmholtz, Knapp, Donders*). The section C *a b c d* of the cylindrical lens (Fig. 543) represents a plano-convex, the section C $a\ \beta\ \gamma\ \delta$, a concavo-convex lens.

FIG. 543.



Cylindrical glasses for astigmatism.

[**Test.**—Draw two lines of equal thickness at right angles to each other. An astigmatic person cannot see both lines with equal distinctness at the same time, one line will appear thicker than the other. Or, a series of lines radiating from a centre may be used (**astigmatic clock**) when that line which is parallel to the astigmatic meridian will be seen most distinctly; while, with the vertical meridian most curved, it would be the vertical line.]

Irregular Astigmatism.—Owing to the radiate arrangement of the fibres in the interior of the crystalline lens, and in consequence of the unequal course of the fibres within the different parts of one and *the same meridian* of the lens, the rays of light passing through one meridian of the lens cannot all be brought to one focus. Hence, we do not obtain a distinct sharp image of distant luminous points, such as stars or street lamps, but we see a radiate jagged figure provided with rays. The same obtains on holding a piece of cardboard with a small hole in it toward the light, at a distance from the eye slightly greater than the far point. Slight degrees of this irregular astigmatism are normal, but when it is highly developed it greatly interferes with vision, by forming *several* foci of an object instead of one (**Polyopia monocularis**). Of course this condition cannot obtain in an eye devoid of a lens.

392. IRIS.—Functions.—1. The iris acts like a **diaphragm** in an optical apparatus by cutting off the marginal rays, which, if they entered the eye, would cause *spherical aberration*, and thus produce indistinct vision (Fig. 531).

2. As the pupil contracts strongly in a bright light, and dilates when the light is feeble, it **regulates** the amount of **light** entering the eye; thus, fewer rays enter the eye when the light is strong than when it is feeble.

3. To a certain extent it supports the action of the ciliary muscle.

Muscles and Nerves.—The iris is usually described as being provided with **two** *sets of muscular fibres*—the **sphincter**, which immediately surrounds the pupil and is supplied by the oculomotorius (§ 345, 2), and the **dilator pupillæ** (p. 786), supplied chiefly by the cervical sympathetic (§ 356, A, 1), and the trigeminus (§ 347, 3). Both muscles stand in an *antagonistic* relation to each other (§ 345), the pupil dilates moderately after section or paralysis of the oculomotorius, owing to the contraction of the dilator fibres which are supplied by the cervical sympathetic; conversely, the pupil contracts when the sympathetic is divided or extirpated (*Petit*, 1727). When both nerves are stimulated simultaneously, the pupil contracts, so that the excitability of the oculomotorius overcomes the sympathetic.

[The **existence of a dilator pupillæ muscle** is not universally recognized, and in fact some observers doubt its existence. The muscular nature of the radial fibres in the posterior limiting membrane of the iris is denied by Grünhagen, while Koganei regards these as in no case muscular, and the dilating fibres as represented by fibres radiating from the iris. These fibres are well developed in birds and the otter, exist in traces in the rabbit, and are absent in man. Gaskell points out that in this case the size of the pupil must in part depend on the elasticity of the radial fibres of the iris, while the dilator nerve fibres must act on the sphincter fibres, causing them to relax. Gaskell groups the sphincter of the iris with those muscles "supplied by two nerves of opposite character, the one motor, the other inhibitory." The dilatation of the pupil caused by stimulation of the cervical sympathetic is usually explained by the hypothesis that this nerve contains motor fibres, which act on the dilator fibres. Grünhagen thought that it might be due chiefly to the constriction of the blood vessels of the iris; Gaskell suggests that the nerve acts on the sphincter muscle, and is the inhibitory nerve of that muscle, dilatation taking place because the sphincter is normally in a condition of tonic contraction, and also because the posterior limiting membrane is elastic.]

Nerves.—Arnstein and A. Meyer have studied the mode of termination of the nerve fibres in the iris. All the medullated nerve fibres lose their white sheaths after a time; most of the fibres (*motor*) in the region of the sphincter consist of naked bundles of fibrils. A network of very delicate *sensory* nerves lies under the anterior epithelium. Numerous fibrils pass to the capillaries and arteries as *vasomotor nerves*. [Many ganglionic cells are intercalated in the course of the fibres.]

Movements of the iris occur under the following conditions:—

1. **Action of light on the retina** causes (according to its intensity and amount) a corresponding **contraction of the pupil**; the same effect is produced by *stimulation of the optic nerve itself* (*Herbert Mayo*, † 1852). This movement is a reflex act [the *afferent* nerve being the optic and the *efferent* the oculomotorius; the impulse is transferred from the former to the latter in a centre situated somewhere below the corpora quadrigemina (Fig. 544, C)]. The older observers locate the centre in the corpora quadrigemina, the recent observers in the medulla oblongata (p. 711). *Both* pupils always react, although only one retina be stimulated; generally under normal circumstances both contract to the same extent (*Donders*), owing to intercentral communication [coupling] of the two pupillo-constricting centres. [This is called consensual contraction of the pupil.] After section of the optic nerve the pupil dilates, and subsequent section of the oculomotorius no longer produces any further dilatation (*Knoll*).

2. **The centre for the dilator fibres of the pupil** (pupillo-dilating centre) is excited by *dyspnœic blood* (§ 367, 8). If the dyspnœa ultimately passes into asphyxia, the dilatation of the pupil diminishes. Of course, if the peripheral dilating fibres (§ 247, 3) [*e.g.*, the sympathetic nerve in the neck] be previously divided, this effect cannot take place, as the dyspnœic blood acts on the *centre* and not on the nerve fibres.

3. The **centre**, as well as the subordinate "**cilio-spinal region**" of the spinal cord (§ 362, 1), is also capable of being excited **reflexly**; painful stimulation of sensory nerves, in addition to causing protrusion of the eyeballs (§ 347), a fact proved in the case of persons subjected to torture, produces dilatation of the pupils (*Arndt, Bernard, Westphal, Luchsinger*); while a similar effect is caused by labor pains, a loud call in the ear, stimulation of the nerves of the sexual organs, and even by slight tactile impressions (*Foà and Schiff*). According to Bechterew, the foregoing results are due to inhibition of the light reflex in the sense expressed in § 361, 3.

4. The **condition of the blood vessels** of the iris influences the size of the pupil; all conditions causing injection or congestion of these vessels contract the pupil, all conditions diminishing them dilate it. The pupil, therefore, is **contracted** by *forced expiration*, which prevents the return of venous blood from the head, momentarily by every *pulse-beat*, owing to the diastolic filling of the arteries; *diminution of the intraocular pressure, e.g.*, after puncture of the anterior chamber, because, owing to the diminished intraocular pressure, there is less resistance to the passage of blood into the blood vessels of the iris (*Hensen and Völckers*); paralysis of the vasomotor fibres of the iris (§ 347, 2). Conversely, the pupil is **dilated** by conditions the reverse of those already mentioned, and also by *strong muscular exertion*, whereby blood flows freely into the dilated muscular blood vessels; also, when

death takes place. The condition of the filling of the blood vessels also explains the fact that the pupil dilated with atropin becomes smaller when a part of the sympathetic in the upper cervical ganglion, carrying the vasomotor fibres of the iris, is excised; also, that after extirpation of this ganglion, atropin always causes a less diminution of the pupil on this side. The fact that when the pupil is already dilated by stimulation of the sympathetic, it is further dilated by atropin, is due to a diminished injection of the blood vessels of the iris. If an animal with its pupils dilated with atropin be rapidly bled, the pupils contract, owing to the anæmic stimulation of the origin of the oculomotorius (*Moriggia*). The dilatation of the pupils observed in cases of neuralgia of the trigeminus, is partly due to the stimulation of the dilating fibres, partly to the stimulation of the vasomotor fibres of the iris (§ 347, 2).

5. **Contraction of the pupil** occurs as an **associated movement**, during *accommodation* for a near object (p. 802, 5), and when the *eyeballs are rotated inward*, which is the case during *sleep* (p. 735). Conversely, intense movements of the iris, caused by variations in the brightness of dazzling illumination, *e. g.*, of the electric light, are followed by disturbing associated movements of the ciliary muscle (*Ljubinsky*). In certain movements discharged from the medulla oblongata (forced respiration, chewing, swallowing, vomiting), dilatation of the pupil occurs, as a kind of *associated movement*.

[**Argyll Robertson Pupil.**—In this condition the pupil does not contract to light, although it contracts when the eye is accommodated for a near object, vision usually being normal. The lesion is situated in those structures connecting the afferent and efferent fibres at their central ends (at Δ in Fig. 544), *i. e.*, the connection between the corpora quadrigemina and the oculomotorius. It is most frequently found in locomotor ataxia, although it also occurs in progressive paralysis of the insane.]

FIG. 544.



Scheme of the nerves of the iris. B, centrum optici; C, oculomotor centre; D, dilator centre (spinal); E, iris; G, optic nerve; H, oculomotor (sphincter) roots; I, sympathetic (dilator); K, L, anterior roots; M, N, O, posterior roots; Δ, seat of lesion, causing pupillary immobility; * probable seat of lesion, causing myosis.

Direct stimulation at the margin of the cornea causes dilatation of the pupil (*E. H. Weber*); in fact, direct stimulation of circumscribed areas of the margin of the iris causes partial contraction of the dilator fibres (*Bernstein and Dogiel*). Stimulation near the centre of the cornea contracts the pupil (*E. H. Weber*). In addition, we must assume that the iris itself contains elements that influence the diameter of the pupil (*Sig. Mayer and Pribram*).

Our knowledge of the **action of poisons** on the iris is still very obscure. Those substances which dilate the pupil are called **mydriatics**, *e. g.*, **atropin**, homatropin, duboisin, daturin, and hyoscyamin. They act chiefly by paralyzing the oculomotorius. But, in addition, there must be also an effect upon the dilating fibres, for after complete paralysis (section) of the oculomotorius, the *moderate* dilatation of the pupil thereby produced (§ 345, 5) is still further increased by atropin. *Minimal doses* of atropin contract the pupil, owing to stimulation of the pupillo-constrictor fibres; *enormous* doses cause moderate dilatation of the pupil in consequence of paralysis of the dilating as well as of the constricting nerve fibres. Atropin acts after destruction of the ciliary [ophthalmic] ganglion (*Hensen and Völckers*) [and division of all the nerves except the optic], and in the excised eye (*De Ruyter*), (so that atropin is a **local mydriatic**. In moderate doses it paralyzes the nervous terminations of the 3d nerve (but not in birds whose iris contains striped muscle), and in larger doses it also paralyzes the muscular fibres]. [**Cocaine**, or cucaine, is obtained from the leaves of Erythroxylon coca. When applied locally it acts as a powerful local anæsthetic, and hence it is very useful for operations about the muco-cutaneous orifices. A 4 per cent. solution dropped into the eye produces complete insensibility of the cornea in a few minutes. It causes dilatation of the pupils, though they react to light and to the movements of accommodation. It also causes temporary paralysis of accommodation, a sensation of heaviness and coldness of the eyeball, enlargement of the palpebral fissure, constriction of the small peripheral vessels, and slight lachrymation.

Myotics are those substances which **contract** the pupil: **Physostigmin** (= Eserin, the alkaloid of Calabar bean), nicotin, pilocarpin, muscarin, morphia, according to some observers (*Grünhagen*) cause stimulation of the oculomotorius, while others say they paralyze the sympathetic. As these substances cause spasm of the ciliary muscle, it is supposed that the first of these has an analogous action on the sphincter. It is *probable* that they paralyze the dilator fibres and stimulate the oculo-

motor fibres. [Among **local myotics**, *i. e.*, those which act on the eye, some act on the muscular fibres of the iris, *e. g.*, physostigmin or eserin, while others act on the peripheral terminations of the 3d nerve, *e. g.*, pilocarpin, muscarin. Muscarin causes very great contraction of the pupil from spasm of the circular fibres, due to its action on the 3d nerve; eserin, on the other hand, although contracting the pupil, also affects the dilator fibres. The contraction of the pupil due to opium is central in its cause.]

If the one pupil be contracted or dilated by these substances, the other pupil, conversely, is dilated or contracted, owing to the change in the amount of light admitted into the eye into which the poison has been introduced. The **anæsthetics** (ether, chloroform, alcohol, etc.), when they begin to cause stupor, contract the pupil, and when their action is intense they dilate it (*Dogiel*). Chloroform during the stage when it causes excitement (preceding the narcosis), stimulates the centre for the dilatation of the pupil; after a time this centre is paralyzed, so that the pupil no longer dilates on the application of external stimuli. Thereafter the pupillo-constrictor centre is stimulated, whereby the pupil may be contracted to the size of a pin's head; ultimately this centre is paralyzed, and the pupil becomes dilated.

Time for Movements of Iris.—The reflex dilatation of the pupil occurs slightly later than the reflex contraction, the time in the two cases being 0.5 and 0.3 second respectively, after stimulation by light (*v. Vintschgau*). A certain *time* always elapses, until the iris, corresponding to the strength of the stimulus of light exciting the retina, "adapts" itself to produce a suitable size of the pupil (*Aubert*). Contraction of the pupil occurs very rapidly after stimulation of the oculomotorius in birds; in rabbits 0.89 second elapses after stimulation of the sympathetic, until the dilatation begins (*Arlt*).

Excised Eye.—Light causes contraction of the pupil in the *excised* eye of amphibians and fishes (*Arnola*). Even the iris of the eel, when cut out and placed in normal saline solution, contracts to

FIG. 545.

FIG. 546.

Gorham's pupil photometer. Fig. 545 shows the disk with a slot and two holes. Fig. 546 gives a side view with the diameter of the pupil marked on it. The upper end is closed by the disk, while the lower end is open.

light (*Arnold*), the green and blue rays being most active. *Increase of the temperature* causes mydriasis in the excised eye of the frog or eel, while cooling causes myosis (*H. Müller*).

[**Size of the Pupil.**—Jonathan Hutchinson recommends a **pupilometer**, consisting of a metal plate perforated with a series of holes of different sizes. The smallest hole measures about ¼ of a line, and the largest is 4½ lines. The plate is placed just below the patient's eye, and the hole is selected which corresponds with the size of the pupil.]

[**Gorham's Pupil Photometer.**—This ingenious instrument may be used as a **pupilometer**, and also as a **photometer**. It consists of a piece of bronzed tubing 1.9 in. long and 1.5 in. diameter (Figs. 545 and 546). One end is closed by a disk or cap, which is pierced in its radii by a series of holes at distances varying from .05 in. to .28 in. There is a slot in the cap which allows one pair of holes to be visible at a time, while on the cylinder is engraved the linear distance of each pair of holes. In using the instrument as a **pupilometer**, look through the open end of the tube (the bottom in Fig. 546), with both eyes open, toward a sheet of white paper or the sky, when two disks of light will be seen. Then revolve the lid or cap slowly until the two white disks *just touch one another at their edges*. The decimal fraction opposite the two apertures seen on the scale outside indicates the diameter of the pupil in 100ths of an inch. When using it as a *photometer*, it is assumed that the size of the pupil gives an index of the intensity of the amount of light which influences the diameter of the pupil.]

Intraocular Pressure.—The movements of the iris are always accompanied by variations of the intraocular pressure. The muscles of the iris affect the intraocular pressure, in that the dilatation of the pupil increases it, while contraction of the pupil diminishes it. The increased or diminished tension can be felt when two fingers are pressed on the eyeball. Stimulation of the sympathetic increases, while its section diminishes the pressure. **Action of Drugs.**—Atropin dropped into the

eye, after producing a short temporary diminution of the tension, increases it; eserin, after a primary increase, causes a diminution of the pressure (*Graser and Hölzke*).

393. ENTOPTICAL PHENOMENA.—Entoptical phenomena depend upon the perception of objects present within the eyeball itself.

1. **Shadows** are formed upon the retina by different opaque bodies. In order to see them in one's own eye, proceed thus: By means of a strong convex lens project a small image of a flame upon a paper screen, prick a small opening through the image of the flame, and place one eye at the other side of the screen, so that the illuminated puncture lies in the anterior focus of the eye, *i. e.*, about 13 mm. in front of the cornea. As the rays proceeding from this point pass parallel through the media of the eye, a diffuse bright field of vision, surrounded by the black margins of the iris, is obtained. All dark bodies which lie in the course of the rays of light throw a shadow upon the retina, and appear as specks. There are various forms of these shadows (Fig. 547):—

(a) The **spectrum mucro-lacrimale**, especially upon the margin of the eyelids, depending upon particles of mucus, fat globules from the Meibomian glands, dust mixed with tears, causing cloudy or drop-like retinal shadows, which are removed by winking.

(b) **Folds in the cornea.**—If the cornea be pressed laterally with the finger, wrinkled shadows, due to temporary wrinkles in the cornea, are produced.

(c) **Lens shadows.**—Bead-like or dark specks, bright and star-like figures, the former due to deposits on and in the lens, the latter to the radiate structure of the lens.

(d) **Muscæ volitantes** (*Dechales*, 1690), like strings of beads, circles, groups of balls or pale stripes, depend upon opaque particles (cells, disintegrating cells, granular fibres) in the **vitreous humor.** They move about when the eye is moved rapidly. Listing (1845) showed that one may determine pretty accurately the position of these objects. While making the observation upon one's own eyes, raise or depress the source of light; those shadows which are caused by bodies on a level

FIG. 547.

Entoptical shadows.

with the pupil retain their relative positions in the bright fields of vision. Shadows which appear to move in the same direction as the source of light are caused by bodies which lie in *front* of the plane of the pupil—those, however, which appear to move in the opposite direction depend upon objects behind the plane of the pupil.

2. **Purkinje's figure** (1819) depends upon the **blood vessels within the retina,** which cast a shadow upon the most external layer of the retina, viz., upon the rods and cones, these being the parts acted upon by light. In ordinary vision we do not observe these shadows. According to v. Helmholtz, this is due to the fact that the sensibility of the shaded parts of the retina is greater, and their excitability is less exhausted, than all the other parts of the retina. As soon, however, as we change the position of the shadow of the blood vessels, instead of being directly behind, so that the blood vessels come to lie more *laterally* and behind them, *i. e.*, upon places which do not receive shadows from the blood vessels when the rays of light pass through the eye in the ordinary way, then the figure of the blood vessels becomes apparent at once. All that is necessary is to cause the light to enter the eyeball obliquely. **Method.**—(1) This may be done by passing an intense light through the sclerotic, *e. g.*, by throwing upon the sclerotic a small, bright, luminous image from a source of light. On moving the source of light, the figure of the blood vessels moves in the same direction. (2) Look directly upward to the sky, wink with the upper eyelid drooping, so that for a moment, corresponding to the act of winking, rays of light enter obliquely the lowest part of the pupils. (3) Look through a small aperture toward a bright sky, and move the aperture rapidly to and fro, so that from both sides of the blood vessels shadows fall rapidly upon the nearest series of rods and cones. (4) In a darkened room look straight ahead, and move a light to and fro close under the eyes. Occasionally, while performing this experiment, one may see the macula lutea as a non-vascular shaded depression, and, owing to the inversion of the objects, it lies on the *inner* side of the entrance of the optic nerve.

3. **Movements of the blood corpuscles in the retinal capillaries.**—On looking, without accommodating the eye, toward a large bright surface, or through a dark blue glass toward the sun, we see bright spots, like points, forming longer or shorter chains, moving in tortuous paths. The phenomenon is, perhaps, caused by the red blood corpuscles (in the capillaries posterior to the external granular layer) acting as small light collecting concave disks, concentrating the light falling upon them from bright surfaces, and throwing it upon the rods of the retina. Each corpuscle must be in a special position; should it rotate, the phenomenon disappears. Vierordt, who projected the movement upon a screen, calculated, from the velocity of their motion, the velocity of the blood stream in the retinal capillaries as equal to 0.5 to 0.75 mm. in a second, which corresponds very closely with the results obtained directly in other capillaries by E. H. Weber and Volkmann (§ 90, 4). When the carotids are compressed, the movement is slower on freeing them from the compression; during short forced expirations the movement is accelerated (*Landois*).

4. The **entoptical pulse** (§ 79, 2) depends upon the pulsating arteries irritating mechanically the rods lying outside them.

5. **Pressure Phosphenes.**—Pressure applied to the eye causes a series of phenomena: (*a*) Partial pressure upon the eyeball causes the so-called illuminated "pressure picture" or *phosphene*, which was known to Aristotle. As the impression upon the retina is referred to something outside the eye, the phosphene is always perceived on the side of the field of vision *opposite* to where the pressure affects the retina, *e. g.*, pressure upon the *outer* surface of the eyeball causes the flash of light to appear on the *inner* side. If the retina is not well lighted, the phosphene appears luminous; if the retina is well lighted, it appears as a dark speck, within which the visual perception is momentarily abolished. (*b*) If a uniform pressure be applied to the eyeball continuously from before backward, as Purkinje pointed out, after some time there appear in the field of vision very sparkling variable figures, which perform a wonderful fantastic play, and often resemble the sparkling effects obtained in a kaleidoscope (*v. Helmholtz*), and are probably comparable to the feeling of formication produced by pressure upon sensory nerves ("sleeping of the limbs"). (*c*) By applying equable and continued pressure, Steinbach and Purkinje observed a network with moving contents of a bluish-silvery color, which seemed to correspond to the retinal veins. Vierordt and Laiblin observed the branching of the blood vessels of the *choroid* as a red network upon a black ground. (*d*) According to Houdin, we may detect the position of the yellow spot by pressure upon the eyeball.

6. **The entrance of the optic nerve** may be detected on moving the eye rapidly backward, and especially inward, as a fiery ring or semicircle about the size of a pea. Probably, owing to the movement of the retina, the entrance of the optic nerve is stimulated mechanically by the rapid bending. Purkinje and others observed that the ring remained persistent on turning the eye strongly inward. If the retina be brightly illuminated, the ring appears dark, and when the field of vision is colored, the ring has a different tint. If Purkinje's figure be produced at the same time, one may observe that the vascular trunk proceeds from this ring—a proof that the ring corresponds to the entrance of the optic nerve (*Landois*).

7. **Accommodation Spot.**—On accommodating the eye strongly toward a white surface, there appears in the middle a small, bright, trembling shimmer, and in its centre a coarse brown speck, about the size of a pea, is seen (*Purkinje*). If pressure be applied externally to the eyeball, this speck becomes more distinct. After having once observed the phenomenon, occasionally on pressing laterally upon the opened eye we may see it as a bright speck in the field of vision—another proof that the intraocular pressure is increased during accommodation.

8. **Mechanical Optical Stimulation.**—On dividing the optic nerve in man, as in extirpation of the eyeball, a flash of light is observed at the moment of section by the person operated on. The section of the nerve fibres themselves is painless, but section of the sheaths is painful.

9. The **accommodation phosphene** is the occurrence of a fiery ring at the periphery of the field of vision, seen on suddenly bringing the eyes to rest after accommodating for a long time in the dark (*Purkinje*). The sudden tension of the zonule of Zinn resulting from the relaxation causes a mechanical stretching of the outermost part of the margin of the retina, or it may be of a part of the retina behind this. Purkinje observed the phenomenon after suddenly relaxing the pressure on the eye.

10. **Electrical Phenomena.**—Electrical currents, when applied to the eye, cause a strong flash of light over the whole field of vision. One pole of the battery may be placed on the under eyelid and the other on the neck. The flash at closing [making] the current is strongest with an ascending current, that with opening [breaking] the current with a descending current. If a uniform continuous *ascending* current be transmitted through the closed eyes, the dark disk of the elevation at the entrance of the optic nerve appears in a whitish-*violet* field of vision; with a *descending* current, the field of vision is *reddish* and dark, in which the position of the optic nerve appears light blue (*v. Helmholtz*). If external colors are looked at simultaneously, these colors blend to form a violet or yellow with the colors looked at (*Schelske*). During the passage of the ascending current we see external objects indistinctly and *smaller* when the eyes are open; while with the descending current they are *larger* and more distinct (*Ritter*). Sometimes the position of the macula lutea appears dark on a bright ground, or the reverse, according to the direction of the current. If the current be opened [broken] the phenomena are reversed (§ 335), and the eye soon returns to rest.

11. The **yellow spot** appears sometimes as a dark circle when there is a uniform blue illumination. In a strong light the position of the yellow spot is surrounded by a bright area, twice or thrice as large, called "**Löwe's ring.**" [**Clerk Maxwell's Experiment.**—On looking through a solution of chrome alum in a bottle or vessel with parallel glass sides, we observe an oval purplish spot in the greenish color of the alum. This is due to the pigment of the yellow spot.]

Haidinger's Brushes.—On directing the eye toward a source of polarized light, "Haidinger's polarized brushes" appear at the point of fixation. They are seen on looking through a Nicol's prism at a bright cloud (*v. Helmholtz*). They are bright and bluish on a surface, bounded by two neighboring hyperbola on a white field; the dark bundle separating them is smallest in the centre and yellow. Of the various colors of homogeneous light, blue alone shows the brushes (*Stokes*). According to v. Helmholtz, the seat of the phenomenon is the yellow spot, and is due to the yellow-colored elements of the yellow spot being slightly doubly refractive, while at one part they absorb more, at another less, of the rays entering the eye.

12. Lastly, there are the visual sensations depending on **internal causes**, *e. g.*, increased bounding of the blood through the retina, as during violent coughing, increased intraocular pressure. Stimulation of the *visual areas* (§ 378, IV) may produce spectra, which Cardanus (1550), Goethe, Nicolai, and Johannes Müller could produce voluntarily.

394. ILLUMINATION OF THE EYE.—OPHTHALMOSCOPE.—The light which enters the eye is partly absorbed by the black uveal pigment, and partly again reflected from the eye, and always in the same direction in which the rays entered the eye. By placing one's self in front of the eye of another person, of course, the head, being an opaque body, cuts off a large number of rays. Owing to the position of the head, no rays of light can enter the eye; and of course none can be reflected back to the eye of the observer. Hence, the eye of the person being examined always appears black, because those rays which alone

FIG. 548.



Arrangement for examining the eye of B. A, eye of observer; *x*, source of light; S, S, plate of glass directed obliquely, reflecting light into B.

could be reflected in the direction of the eye of the observer are cut off. As soon, however, as we succeed in causing rays of light to enter the eye at the same time and in the *same* direction in which we observe the eye of another person, the fundus of the eye appears brightly illuminated.

The following simple arrangement is sufficient for the purposes (Fig. 548): Let B be the eye of the patient, A that of the observer, and let a flame be placed at *x*. The rays of light proceeding from *x* impinge upon the obliquely placed *plate of glass* (S, S), and are reflected in the direction of the dotted lines into the eye (B). The fundus of the eye appears in this position to be brightly illuminated in diffusion circles around *b*. As the observer (A) can see through the obliquely placed glass plate (S, S), and in the same direction as the reflected rays (*x*, *y*), he sees the retina around *b* brightly illuminated.

In order that this method be made available for practical purposes, we must, of course, be able to distinguish the details, such as the blood vessels of the fundus of the eye, the macula lutea, the entrance of the optic nerve, abnormalities of the retina, and the choroidal pigment, etc. The following considerations show us how to proceed in order to accomplish this. As already mentioned, and

FIG. 549.



as Fig. 531 shows, a small inverted image is formed on the retina (c, d) when we look at an object (A, B); conversely, according to the same dioptric law, an enlarged inverted real image of a small distinct area of the retina (c, d—depending on the distance for which the eye was accommodated) must be formed outside the eye (A, B).

FIG. 550.



If the fundus of this eye be sufficiently illuminated, this aerial image will be correspondingly bright.

In order to see the individual parts of the retinal picture more distinctly, the observer must accommodate his own eye for the position of this image. In such circumstances the eye of the observer would be too near the observed eye. His eye when so accommodated is removed from the eye of

FIG. 551.



the patient by his own visual distance, and by the visual distance of the patient. As this distance is considerable, the individual small details of the fundus cannot be seen distinctly. Further, owing to the contraction of the pupil of the patient, only a small area of the fundus can be seen, and this only under a small visual angle, quite apart from the fact that it is often impossible to accommodate for the real image of the fundus of the patient.

Hence, the eye of the observer must be brought nearer to the eye of the patient. This may be done in two ways: (1) Either by placing in front of the eye of the patient a strong *convex lens* (of 1 to 3 inches focus—Fig. 549, C). This causes the retinal image to be nearer to the eye (at B), owing to the strong lens refracting the rays of light. The observer (M) can come nearer to the eye, and can still accommodate for the image of the fundus of the eye. (2) Or a *concave lens* is placed immediately in front of the eye of the patient (Fig. 550, *o*). The rays of light emerging from the eye of the patient (P) are either made parallel by the concave lens (*o*), and are brought to a focus on the retina of the emmetropic observer (A); or, if the lens causes the rays to diverge (Fig. 551), an erect, virtual image is formed at a distance behind the eye of the patient (at R). In these cases, also, the observer can go much nearer to the eye of the patient.

The **ophthalmoscope** invented by v. Helmholtz enables us to examine the whole of the fundus of the eye.

[**Direct Method.**—Use a concave mirror of 20 centimetres focal distance, with a central opening. Reflect a beam of light into the patient's eye, where the rays cross in the vitreous and illuminate the fundus of the eye. These rays again pass out of the eye and reach the observer's eye through the central hole in the mirror. If the observer be emmetropic they come to a focus on his retina. In this way all the parts of the retina are seen in their normal position, but enlarged. Hence, it is some-

FIG. 552.



The entrance of the optic nerve with the adjacent parts of the fundus of the normal eye. *a*, ring of connective tissue; *b*, choroidal ring; *c*, arteries; *d*, veins; *g*, division of the central artery; *h*, division of the central vein; L, lamina cribrosa; *t*, temporal (outer) side; *n*, nasal (inner) side.

FIG. 553.

Morton's Ophthalmoscope.

times called the examination of the **upright image.** The eye of the patient and observer must be at rest, *i. e.*, be negatively accommodated, while the mirror must be brought as near as possible to the eye of the patient.]

[**Indirect Method**, by which a more general view of the fundus is obtained. Throw the light into the patient's eye by an ophthalmoscopic mirror as above, but held at a distance of about 50 cm. (10 inches) from the patient's eye. Hold a biconvex lens of 14 dioptrics focal length vertically between the mirror and the patient's eye (Fig. 549), the observer looking through the hole of the mirror. What he does see is an **inverted aerial image** at B. Only a small part of the fundus oculi can be seen at one time.]

[The ophthalmoscope, besides being used for examining the interior of the eyeball, is of the utmost use in determining the existence and amount of **anomalies of refraction** in the refractive media. For this purpose an ophthalmoscope requires to be provided with *plus* and *minus* lenses, which can be readily brought before the eye of the observer. This is readily done by an ingenious mechanism devised by Couper, and made use of in the handy students' ophthalmoscope of Morton (Fig. 553). The lenses are moved by a driving wheel on the left figure, while at the same time is indicated at a certain aperture the lens presented at the sight hole. The instrument is also provided with a mov-

able arrangement carrying a concave mirror at either end. One of these mirrors is 10 inches in focus, and is used for indirect examination and retinoscopy, while the other is of 3 inches focus for direct examination, and is fixed at an angle of 25°.]

[**Retinoscopy.**—The ophthalmoscope is used also for this purpose. A beam of light is reflected into the eye by the ophthalmoscopic mirror, and the play of light and shade on the fundus oculi observed. A study of this is important in determining anomalies of refraction. For the method the student is referred to a text-book on "Diseases of the Eye."]

[**Artificial Eye.**—The student may practice the use of the ophthalmoscope on an artificial eye, such as that of Frost (Fig. 554) or Perrin.]

Illumination.—In order to illuminate the interior of the eye, v. Helmholtz used several plates of glass, placed behind each other, in the position of S, S, in Fig. 548. Afterward he used a plane or concave mirror of 7 inches focus (Fig. 549), with a hole in the centre. Fig. 552 shows the appearance of the fundus of the eye, as seen with the ophthalmoscope. In albinos the fundus of the eye appears red, because light passes into the eye through the sclerotic and uvea, which are devoid of

FIG. 554.

Frost's Artificial Eye.

FIG. 555.



Action of the Orthoscope.

pigment. If a diaphragm be placed over the eye, so that the pupil alone is free, the eye appears black (*Donders*).

Tapetum.—In many animals the eyes have a bright green lustre. These eyes have a special layer, the tapetum, or the membrane versicolor of Fielding; in carnivora it consists of cells, in herbivora of fibres, placed between the capillaries of the choroid and the stroma of the uvea. These structures exhibit interference colors and reflect much light, so that the colored lustre appears in the eye.

Oblique illumination is used with advantage for investigating the anterior chamber. A bright beam of light, condensed by a convex lens, is thrown *laterally* upon the cornea into the eye, and so directed upon the point to be investigated as to illuminate it. A point so illuminated, *e. g.*, a part of the iris, may be examined from a distance by means of a lens, or even by a microscope (*Liebreich*).

The **Orthoscope.**—Czermak constructed this instrument, in which the eye is placed under water (Fig. 555). It consists of a small glass trough with one of its walls removed. The margins of the open side are pressed firmly against the region of the eye. The eye and its surroundings form, as it were, the sixth side of the trough, which is filled with water, so that the cornea is bathed therewith. As the refractive index of water is almost the same as the refractive index of the media of the eye, the

rays of light pass into the eye in a straight direction without being refracted. Hence, objects in the anterior chamber can be seen directly, as if they were not within the eye at all. Another advantage is that the objects can be brought nearer to the eye of the observer. The rays of light emerging from the point (*a*) of the fundus, if the eye were surrounded by air, would leave the eye as the parallel lines, *b*, *c*, *b*, *c*. Under water, these rays, *a*, *b*, continue in the direction *a*, *b*, as far as *b*, *d*, where they emerge from the water, and are bent from the perpendicular to *d*, *e*, *d*, *e*. The eye of the observer, looking in the direction *e*, *d*, sees the point, *a*, *nearer*, viz., in the direction *e*, *d*, *a'*, lying at *a*.

395. ACTIVITY OF THE RETINA IN VISION.—I. Blind Spot.—The **rods and cones** alone are the parts of the retina **sensitive to light**, they alone are excited by the vibrations of the ether. This is confirmed by Mariotte's experiment (1688), which proves that the entrance of the optic nerve, where rods and cones are absent, is devoid of visual sensibility. Hence it is spoken of as the "*blind spot*."

[**Mariotte's Experiment.**—Make two marks, about three inches apart, upon paper (Fig. 556). Look at the cross with the right eye, keeping the left eye closed, and hold the paper about a foot from the eye, when both the cross and the circle will be seen. Gradually approximate the paper to the eye, keeping the open eye steadily fixed on the cross; at a certain moment the circle will disappear, and on bringing the paper nearer to the eye it will reappear. The moment when the circle disappears is when its image falls upon the entrance of the optic nerve.]

Position and Size.—The entrance of the optic nerve lies about 3.5 mm. internal to the visual axis of the eyeball in the retina. Its diameter is 1.8 mm. The apparent diameter of the blind spot in the field of vision is in a horizontal direction 6° 56′—this lies 12° 35′ to 18° 55′ horizontally from

FIG. 556.



the fixed point. Eleven full moons placed side by side would disappear on the surface, and so would a human face at a distance of over 2 metres.

Proofs.—The following facts prove that the entrance of the **optic nerve is insensible to light**: (1) Donders projected, by means of a mirror, the small image of a flame upon the entrance of the optic nerve of another person, and the person had no sensation of light. But a sensation of light was experienced, when the image of the flame was projected upon the neighboring parts of the retina. (2) On combining with Mariotte's experiment the experiment which causes entoptical phenomena at the entrance of the optic nerve, this coincides with the blind spot (§ 393, 6 and 7).

Form of Blind Spot.—In order to determine the *form and apparent size of the blind spot* in one's own eye, fix the head at about 25 centimetres from a surface of white paper; select a small point on the latter and keep the eye directed toward it; then, starting from the position of the blind spot, move a white feather in all directions over the paper; whenever the tip of the feather becomes visible, make a mark at this spot. The blind spot may be mapped out in this way. It has an irregular, elliptical form from which processes proceed, due to the equally non-sensitive origins of the large blood vessels of the retina (*Hueck*). (Mariotte concluded from his experiment that the choroid, which is perforated by the optic nerve, is the membrane sensitive to light, as the nerves are nowhere absent from the retina.)

The blind spot causes no appreciable gap in the field of vision.—As this area is not excited by light, a black spot cannot appear in the field of vision, for the sensation of black implies the presence of retinal elements, which, however, are absent from the blind spot. The circumstance, however, that in spite of the existence of an inexcitable spot during vision, no part of the field of vision appears to be *unoccupied*, is due to a psychical action. The unoccupied area of the field of vision, corresponding to the blind spot, is filled in, according to probability, by a psychical process (*E. H. Weber*). Hence, when a white point disappears from a black surface, the whole surface appears to us black; a white surface, from which a black point falls on the blind spot, appears quite white; a page of print, gray throughout, etc. According to the probabilities, certain parts are supplied—parts of a circle, the middle parts of a long line, the central part of a cross. Such images, however, as

cannot be constructed according to the probabilities, are not perfected, *e. g.*, the end of a line or a human face. In other cases the condition known as "*contraction*" of the field of vision tends to fill up the gap. This will be evident on looking at the nine adjoining letters, so that *e* disappears; we no longer see the three letters on each side of it in straight lines, but *b*, *f*, *h*, *d* are turned in toward *e*. The adjoining parts of the field of vision seem to extend over and around the blind spot, and thus help to compensate for the blind spot.

a b c
d (e) f
g h i

II. Optic Fibres Inexcitable to Light.—The layer of the *fibres of the optic nerve* in the retina is *not sensitive to light*. This is proved by the fact that, in the fovea centralis, which is the area of most acute vision, there are no nerve fibres. Further, Purkinje's figure proves that as the arteries of the retina lie behind the optic fibres, the latter cannot be concerned in the perception of the former.

III. Rods and Cones.—The outer segments of the rods and cones have rounded outlines, and are packed close together; but natural spaces must exist between them, corresponding to the spaces that must exist between groups of bodies with a circular outline. These parts are insensible to light, so that a retinal image is composed like a mosaic of round stones. The diameter of a cone in the yellow spot is 2 to 2.5 μ (*M. Schultze*). If two images of two small points, placed very near each other, fall upon the retina, they will still be distinguished as distinct images, provided that both images fall upon two different cones. The two images on the retina need only be 3–4–5.4 μ apart, in order that each may be seen separately, for then the images still fall upon *two* adjoining cones. If the distance be diminished so very much that both images fall upon *one* cone, or one upon one cone and the other upon the intermediate or cement substance, then only *one* image is perceived. The images must be further apart in the peripheral portion of the retina in order that they may be separately distinguished.

As the rounded end surfaces of the cones do not lie exactly under each other, but are so arranged that one series of circles is adapted to the interstices of the following series, this explains why fine dark lines lying near each other appear to have alternating twists upon them, as the images of these must fall upon the cones, at one time to the right, at another to the left.

IV. The **fovea centralis** is the region of **most acute vision**, where only cones are present, and where they are very numerous and closely packed (Fig. 521). The cones are less numerous in the peripheral areas of the retina, and consequently vision is much less acute in these regions. We may therefore conclude that the cones are more important for vision than the rods. When we wish to see an object distinctly, we involuntarily turn our eyes so that the retinal image falls upon the fovea centralis. In doing this we are said to "*fix*" our eyes upon an object. The line drawn from the fovea to the object is called the **axis of vision** (Fig. 557, *S r*). It forms an angle of only 3.5–7° with the "*optical axis*" (*O A*), which unites the centres of the spherical surfaces of the **refractive media** of the eye. The point of intersection, of course, lies in the nodal point (*Kn*) of the lens (p. 820). The term "**direct vision**" is applied to vision when the direction of the axis of vision is in line with the object [*i.e.*, when the image of the object falls directly on the fovea centralis].

"**Indirect vision**" occurs when the rays of light from an object fall upon the **peripheral parts** of the retina. Indirect vision is much less acute than the direct.

To test the acuity of direct vision, draw two fine parallel lines close to each other, and gradually remove them more and more from the eye, until both appear *almost* to unite and form one line. The size of the retinal image may be ascertained by determining the distance of the two lines from each other, and the distance of the lines from the eye, or, from the corresponding visual angle, which is generally from 60 to 90 seconds.

Perimetry.—In order to test **indirect vision**, we may use the *perimeter* of Aubert and Förster. The eye is placed opposite a fixed point, from which a semicircle proceeds, so that the eye lies in the centre of it. As the semicircle rotates round the fixed point, on rotating the former we can circumscribe the surface of a hemisphere, in the centre of which the eye is placed. Proceeding from the fixed point, objects are placed upon semicircles, and are gradually pushed more and more toward the

periphery of the field of vision, until the object becomes indistinct, and finally disappears. The process of testing is continued by placing the arc successively in the different meridians of the field of vision.

[**M'Hardy's perimeter** is a very convenient form (Fig. 558). It consists of two uprights (C and D), which are fixed to the opposite ends of a flat basal plate (A). C carries an arrangement for supporting the patient's head, while D carries the automatic arrangement for the perimetric record. Both of these can be raised or depressed by the screws (G and *b*). The patient's chin rests on the chin-rest (E), while in the mouth is placed Landolt's biting fixation (L), which is detachable. The position of the head can be altered by sliding F on L, which can be fixed in any position by the screw

FIG. 557.



Horizontal section of the right eye. *a*, cornea; *b*, conjunctiva; *c*, sclerotic; *d*, anterior chamber containing the aqueous humor; *e*, iris; *ff'*, pupil; *g*, posterior chamber; *l*, Petit's canal; *j*, ciliary muscle; *k*, corneo-scleral limit; *i*, canal of Schlemm; *m*, choroid; *n*, retina; *o*, vitreous humor; *No*, optic nerve; *q*, nerve sheaths; *p*, nerve-fibres; *lc*, lamina cribrosa. The line *O A* indicates the optic axis; *S r*, the axis of vision; *r*, the position of the fovea centralis.

(O). The porcelain button (I) just below the patient's eye (*l*) is connected with the adjustment of the "fixation point." The automatic recording apparatus consists of a revolving quadrant (*k*, *k*,), which describes a hemisphere round a horizontal axis passing through the centre of the hollow male axle, turning in the female end of *a*, which is supported by D. The quadrant can be fixed at any point by *g*. On the front concave surface of the quadrant is fixed a circular white piece of ivory, representing the "fixation point," from which a needle projects, and which is the zero of the instrument. A carriage (*i*), in which the test objects are placed, can be moved in the concave face of the quadrant by means of the milled head (*j*), which moves the carriage by means of a tooth and pinion wheel.]

FIG. 558.

M'Hardy's perimeter. I, porcelain button; M, bit; E, for fixing the head; *g*, *k*, quadrant; *o*, fixation point; *p*, pointer for piercing the record chart held in the frame (*e*) which moves on *c*; D, upright supporting the quadrant and the automatic arrangement of slides (*k* and *l*), which are moved by *j*.

[When the milled head (*j*) is turned, it moves the carriage and two slides (*k* and *l*), the two slides moving in the ratio of 2 to 1. The rate of the carriage is so adjusted that it travels ten times faster than *l*, and five times faster than *k*. The pointer (*p*) is connected with these slides, so that it moves when they move, and records its movements by piercing the record chart, which is fixed in the double-faced frame (*e*). The frame for the record chart is hinged near *c* to the upright (D). The frame, when upright, comes so near the pointer that the latter can pierce a chart placed in the frame. The patient is directed to look at the "fixation point," which is merely a small ivory button placed in the imaginary axis of the hemisphere on the front of the centre of the concave surface of the quadrant; the projecting needle point (*o*) indicates its position. This is the zero of the quadrant, and on each side of it the quadrant is divided into 90°.]

[In testing the field of vision, place the carriage so as to cover zero, adjust the eye for the fixation point, and look steadily at it, when, if all is right, the pointer (*p*) ought to pierce the centre of the chart. Move the carriage along the quadrant by *j* until it disappears from the field of vision, and when it does so the pointer is made to pierce the chart. Make another observation in another direction by altering the position of the quadrant, and go on doing so until a complete record is obtained

FIG. 559.

Priestley Smith's Perimeter.

of the field of vision. Test the other eye in the same way. The color field may be tested by using colored papers in the carriage.]

[**Priestley Smith's Perimeter** (Fig. 559).—The wooden knob on the left of the figure is placed under the eye of the patient, who stares at the fixed point in the axis of the quadrant, which can be moved in any meridian. The test object is a square piece of white paper, which is moved along the quadrant. The chart is placed on the posterior surface of the hand wheel and moves with it, so that the meridians of the chart move with the quadrant. There is a scale behind the hand wheel corresponding with the circles on the chart, so that the observer can prick off his observations directly.]

[**Scotoma** is the term applied to dimness or blindness in certain parts of the field of vision, which may be **central, marginal,** or in **patches.**]

The capacity for **distinguishing colors** diminishes more rapidly at the periphery of the retina, than that for distinguishing differences in the brightness or intensity of light. In fact, the periphery of the retina is slightly red blind. The diminution is greater in the vertical meridian of the eye than in the horizontal, and it diminishes with the distance from the fixation point (*Aubert and*

FIG. 560.

Perimetric chart of a healthy and a diseased eye.

Förster). These observers also state that, during accommodation for a distant object, the diminution of the capacity to distinguish brightness and color toward the periphery of the lens, occurs more rapidly than with near vision. The excitability of the retina for colors and brightness is greater at a point equally distant from the fovea centralis on the temporal than on the nasal side of the eye (*Schön*).

Perimetric Chart.—If the arc of the perimeter (Fig. 559) be divided into 90 degrees, beginning at the fixation point (central point), and proceeding to L and M (Fig. 560); and if a series of concentric circles be inscribed on this, with the point of fixation as their centre, we can construct a **topographical chart** of the visual capacity of the normal or healthy eye from the data obtained by the examination of the retina.

Fig. 560 is an example; the *thick* lines indicate a diseased eye, the corresponding *thin* lines a healthy eye. The continuous line indicates the limits for the perception of white; the interrupted line that for blue; the punctuated and interrupted line that for red; *m* is the blind spot. In the normal eye the limits for the perception of colors are as follows:—

	White.	Blue.	Red.	Green.
Externally,	70°–88°	65°	60°	40°
Internally,	50°–60°	60°	50°	40°
Upward,	45°–55°	45°	40°	30°–35°
Downward,	65°–70°	60°	50°	35°

V. Specific Energy.—The rods and cones alone are endowed with what Johannes Müller called "*specific energy*," *i. e.*, they alone are set into activity by the ethereal vibrations, to produce those impulses which result in vision. *Mechanical* and *electrical* stimuli, however, when applied to any part of the course of the nervous apparatus, produce visual phenomena. Mechanical stimuli are more intense stimuli than light rays, as is shown by performing the dark-pressure figure with the eyes open (§ 393, 5, *a*), whereby the circulation in the retina is interfered with; in the region of pressure, we cannot see external objects which affect the retina uniformly and continuously.

VI. The **duration** of the retinal **stimulation** must be exceedingly short, as the electrical spark lasts only 0.000000868 second; still, as a general rule, a shorter time is required, the larger and brighter the object looked at. Alternate stimulation with light 17 to 18 times per minute, is perceived most intensely (*Brücke*). Further, an increase or diminution of 0.01 part of the intensity of the light is perceptible (§ 383). A shorter time is required to perceive yellow than is required for violet and red (*Vierordt*). The retina becomes more sensitive to light, after a person has been kept in the dark for a long time, and also after repose during the night. If light be allowed to act on the eyes for a long time, and especially if it be intense, it causes **fatigue** of the retina, which begins sooner in the centre than in the periphery of the organ (*Aubert*). At first the fatigue comes on rapidly and afterward develops more slowly—it is most marked in the morning (*A. Fick*). The periphery of the retina is specially characterized by its capacity for distinguishing movements (*Exner*).

VII. Visual Purple.—The mode of the action of light upon the end organs of the retina has already been referred to (p. 789) in connection with the "*visual purple*" or **rhodopsin** (*Boll, Kühne*). Kühne showed that, by illuminating the retina, actual pictures (*e. g.* the image of a window) could be produced on the retina, but they gradually disappeared. From this point of view we might regard the retina as comparable, to a certain extent, to the sensitive plate of a photographic apparatus.

Optogram.—The visual purple is formed by the pigment epithelium of the retina. Perhaps we might compare the process to a kind of secretion. The visual purple may be restored in a retina by laying the latter upon living choroidal epithelium. The pigment disappears from the mammalian retina by the action of light 60 times more rapidly than from the retina of the frog. In a rabbit's eye, whose pupil was dilated with atropin, Ewald and Kühne obtained a sharp picture or optogram of a bright object placed at a distance of 24 cm. from the eye—the image was "fixed" by a 4 per cent. solution of alum. Visual purple withstands all the oxidizing reagents; zinc chloride, acetic acid, and corrosive sublimate change it into a yellow substance—it becomes *white* only through the action of light; the dark heat rays are without effect, while it is decomposed above a temperature of 52° C. [As visual purple is absent from the cones, and cones only are present in the fovea centralis, we cannot explain vision by optograms formed by the visual purple.]

VIII. Destruction of the **rods and cones** of the retina causes corresponding dark spots in the field of vision.

396. PERCEPTION OF COLORS.—**Physical.**—The vibrations of the light ether are perceived by the retina only within distinct limits. If a beam of white light, *e. g.*, from the sun, be transmitted through a prism, the light rays are refracted and dispersed, and a "**prismatic spectrum**" is obtained (Fig. 17). White light contains rays of very different wave lengths or periods of vibration. The dark **heat rays**, whose wave length is 0.00194 mm., are refracted least (*Fizeau*). They do not

act upon the retina, and are therefore invisible. They act, however, upon sensory nerves. Accn. 90 per cent. of these rays is absorbed by the media of the eye (*Brücke and Knoblauch*). From Frauenhofer's line, A, onward, the oscillations of the light ether excite the retina in the following order: *Red* with 481 billions of vibrations per second, *orange* with 532, *yellow* with 563, *green* with 607, *blue* with 653, *indigo* with 676, and *violet* with 764 billion vibrations per second. The **sensation of color** therefore depends on the **number of vibrations of the light ether**, just as the pitch of a note depends on the number of vibrations of the sounding body (*Newton*, 1704; *Hartley*, 1772). Beyond the violet lie the **chemically-active** [actinic] rays of the spectrum. After cutting out all the spectrum, including the violet rays, v. Helmholtz succeeded in seeing the ultra-violet rays, which had a feeble grayish-blue color. The heat rays in the colored part of the spectrum are transmitted by the media of the eye in the same way as through water. The existence of the ultra-violet rays is best ascertained by the phenomenon of **fluorescence.** Von Helmholtz, on illuminating a solution of sulphate of quinine with the ultra-violet rays, saw a bluish-white light proceeding from all parts of the solution which were acted on by the ultra-violet rays. As the media of the eye themselves exhibit fluorescence (*v. Helmholtz*), they must increase the power of the retina to distinguish these rays. The ultra-violet rays are not largely absorbed by the media of the eye (*Brücke*).

In order that a color be perceived, it is essential that a certain amount of light fall upon the retina. Blue, when at the lowest degree of brightness, gives a color sensation with an amount of light which is sixteen times less than that required for red (*Dobrowlosky*).

Intensity of the Impression of Light.—While light of different periods of vibration applied to the eye excites the different sensations of color, the **amplitude** of the vibrations (height of the waves) determines the **intensity of the impression** of light; just as the loudness of a note depends on the amplitude of the vibrations of the sounding body. The sun's light contains all the rays which excite the sensation of color in us, and when all these rays fall simultaneously upon the retina we experience the sensation of white. If the colors of the spectrum obtained by means of a prism be reunited, white light is again obtained. If no vibrations of the light-ether reach the retina, every sensation of light and color is absent, but we can scarcely apply the term **black** to this condition. It is rather the **absence of sensation,** such as, for example, is the case when a beam of light falls on the skin of the back. This does not give the sensation of black, but rather that of no sensation of light.

Simple and Mixed Colors.—We distinguish **simple** colors, *e. g.*, those of the spectrum. In order to perceive these, the retina must be excited (set into vibration) by a distinct number of oscillations (see above). Further, we distinguish "**mixed colors**," whose sensations are produced when the retina is excited by two or more simple colors, simultaneously or rapidly alternating. The most complex mixed color is **white**, which is composed of a mixture of **all the simple** colors of the spectrum.

The "**complementary colors**" are important. Any two colors which together give the sensation of white are complementary to each other. The "**contrast colors**" are mentioned here merely to complete the list. They are closely related to the complementary colors. Any two colors which, when mixed, supplement the generally prevailing tone of the light, are contrast colors. When the sky is blue, the two contrast colors must be bluish-white: with bright gaslight they must be yellowish-white, and in pure white light of course all the complementary are the same as the contrast colors (*Brücke*).

Methods of Mixing Colors.—1. Two solar spectra are projected upon a screen, and the spectra are so arranged as to cause any one part of one spectrum to cover any part of the other.

2. Look obliquely through a vertically arranged glass plate at a color placed behind it. Another color is placed in *front* of the glass plate, so that its image is also reflected into the eye of the observer; thus, the light of one color transmitted through the glass plate and the reflected light from the other color reach the eye simultaneously. [**Lambert's Method.**—This is easily done by Lambert's method. Use colored wafers and a slip of glass; place a red wafer on a sheet of black paper, and about 3 inches behind it another blue one. Hold the plate of glass midway and vertically between them, and so incline the glass that, while looking through it at the red wafer, a reflected image of the blue one will be projected into the eye in the same direction as that of the red image, when we have the sensation of purple].

3. A rotatory disk, with sectors of various colors, is rapidly rotated in front of the eyes. On rapidly rotating the colored disk, the impressions produced by the individual colors are united to produce a mixed color. If the rotating disk, which yields, let us suppose, white, on mixing the colors of the spectrum, be reflected in a rapidly rotating mirror, then the individual components of the white reappear.

4. Place in front of each of the small holes in the cardboard used for Scheiner's experiment

(Fig. 537) two differently colored pieces of glass; the colored rays of light passing through the holes unite on the retina, and produce a mixed color (*Czermak*).

Complementary Colors.—Investigation shows that the following colors of the spectrum are complementary, *i. e.*, every pair gives rise to white:—

Red and greenish-blue, Orange and Cyan blue,
Yellow and indigo blue, Greenish-yellow and violet,

while green has the compound complementary color, purple (*v. Helmholtz*).

The **mixed colors** may be determined from the following table. At the top of the vertical and horizontal columns are placed the simple colors; the mixed colors occur where they intersect the corresponding vertical and horizontal columns (Dk. = dark; wh. = whitish):—

	Violet.	Indigo.	Cyan blue.	Bluish-green.	Green.	Greenish-yellow.	Yellow.
Red	Purple	Dk. rose	Wh. rose	White	Wh.-yellow	Gold-yellow	Orange
Orange	Dk. rose	Wh. rose	White	Wh.-yellow	Yellow	Yellow	...
Yellow	Wh. rose	White	Wh.-green	Wh.-yellow	Gr.-yellow	...	...
Gr.-yellow	White	Wh.-green	Wh.-green	Green	...	...	...
Green	White-blue	Water blue	Bl.-green.	...	...	...	...
Bluish-green	Water blue	Water blue	...	...	...	...	...
Cyan blue	Indigo	...	...	...	...	...	...

The following **results** have been obtained from observations on the mixture of colors:—

1. If two simple, but non-complementary, spectral colors be mixed with each other, they give rise to a color sensation, which may be represented by a color lying in the spectrum between both, and mixed with a certain quantity of white. Hence we may produce every impression of mixed colors by a color of the spectrum + white (*Grassman*).

2. The less white the colors contain, the more "**saturated**" they are said to be; the more white they contain, the more unsaturated do they appear. The saturation of a color diminishes with the intensity of the illumination.

Geometrical Color Table.—Since the time of Newton, attempts have been made to construct a so-called "geometrical color table," which will enable any mixed color to be readily found. Fig. 561 shows such a color table; white is placed in the middle, and from it to every point in the curve—which is marked with the names of the colors—suppose each color to be so placed that, proceeding from white, the colors are arranged, beginning with the brightest tone, always followed by the most saturated tone, until the pure saturated spectral color lies in the point of the curve marked with the name of the color. The mixed color, purple, is placed between violet and red. In order to determine from this table the mixed color of any two spectral colors, unite the points of these colors by a straight line. Suppose weights corresponding to the units of intensity of these colors, to be placed on both points of the curve indicating colors, then the position of the centre of gravity of both in the line connecting the colors indicates the position of the mixed color in the table. The mixed color of two spectral colors always lies in the color table in the straight line connecting the two color points. Further, the impression of the mixed color corresponds to an intermediate spectral color mixed with white. The complementary color of any spectral color is found at once by making a line from the point of this color through white, until it intersects the opposite margin of the color table; the point of intersection indicates the complementary color. If pure white be produced by mixing two complementary co'ors, the color lying nearest white on the connecting line must be specially strong, as then only would the centre of gravity of the lines uniting both colors lie in the point marked white.

FIG. 561.



Geometrical color cone or table.

By means of the color table we may ascertain the *mixed color of three or more colors*. For example, it is required to find the mixed color resulting from the union of the point, *a* (pale yellow), *b* (fairly saturated bluish-green), and *c* (fairly saturated blue). On the three points place weights corresponding to their intensities, and ascertain the centre of gravity of the weight, *a*, *b*, *c*; it will lie at *p*. It is obvious, however, that the impression of this mixed color, whitish green-blue, can be produced by green-blue + white, so that *p* may be also the centre of gravity of two weights, which lie in the line connecting white and green-blue.

We may describe a triangle, V, Gr, R, about the color table so as to enclose it completely. The **three fundamental** or **primary colors** lie in the angles of this triangle, red, green, violet. It is evident that each of the colored impressions, *i. e.*, any point of the color table, may be determined by placing weights corresponding to the intensity of the *primary colors* at the angles of the triangle, so that the point of the color table, or what is the same thing, the desired mixed color, is the centre of gravity of the triangle with its angles weighted as above. The intensity of the three primary colors, in order to produce the mixed color, must be represented in the same proportion as the weights.

Theories.—Various theories have been proposed to account for color sensation.

1. According to one theory, color sensation is produced by *one* kind of element present in the retina, being excited in *different ways* by light of different colors (oscillations of the light ether of different wave lengths, number of vibrations, and refractive indices).

2. Young-Helmholtz Theory.—The theory of Thomas Young (1807) and v. Helmholtz (1852) assumes that **three** different kinds of **nerve elements**, corresponding to the three primary colors, are present in the retina. Stimulation of the first kind causes the sensation of **red**, of the second **green**, and of the third **violet**.

The elements sensitive to red are most strongly excited by light with the longest wave length, the red rays; those for green by medium wave lengths, green rays; those for violet by the rays of shortest wave length, violet rays. Further, it is assumed, in order to explain a number of phenomena, that *every color of the spectrum excites all the kinds of fibres, some of them feebly, others strongly.*

FIG. 562.



Suppose in Fig. 562 the colors of the spectrum are arranged in their natural order from red to violet horizontally, then the three curves raised upon the abscissa might indicate the strength of the stimulation of the three kinds of retinal elements. The continuous curve corresponds to the rays producing the sensation of red, the dotted line that of green, and the broken line that of violet. Pure *red* light, as indicated by the height of the ordinates in R, strongly excites the elements sensitive to red, and feebly the other two kinds of terminations, resulting in the sensation of *red*. Simple yellow excites moderately the elements for red and green, and feebly those for violet = sensation of *yellow*. Simple green excites strongly the elements for green, but much more feebly the two other kinds = sensation of *green*. Simple blue excites to a moderate extent the elements for green and violet; more feebly those for red = sensation of *blue*. Simple violet excites strongly the corresponding elements, feebly the others = sensation of *violet*. Stimulation of any two elements excites the impression of a mixed color; while, if all of them be excited in a nearly equal degree, the sensation of white is produced. As a matter of fact, the Young-Helmholtz theory gives a simple explanation of the phenomena of the physiological doctrine of color. It has been attempted to make the results obtained by examination of the structure of the retina accord with this view. According to Max Schultze, the **cones** alone are end organs connected with the perception of color. The presence of longitudinal striation in their outer segments is regarded as constituting them multiple terminal end organs. Our power of color sensation, so far as it depends on the retina, would, on this view of the matter, bear a relation to the number of cones. The degree of color sensation is most developed in the macula lutea, which contains only cones, and diminishes as the distance from the point increases, while it is absent in the peripheral parts of the retina. The **rods** of the retina are said to be concerned only with the capacity to distinguish between quantitative sensations of light.

3. **Hering's Theory.**—Ew. Hering, in order to explain the sensation of light, proceeds from the axiom stated under 1, p. 825. What we are conscious of, and call a visual sensation, is the physical expression for the **metabolism in the visual substance** ("*Sehsubstanz*"), *i. e.*, in those nerve masses which are excited in the process of vision. Like every other corporeal matter this substance during the activity of the metabolic process undergoes decomposition or "**disassimilation**"; while during rest it must be again renewed, or "**assimilate**" new material. Hering assumes that for the perception of **white** and **black**, two different qualities of the chemical processes take place in the visual substance, so that the sensation of **white** corresponds to the **disassimilation** (decomposition), and that of **black** to the **assimilation** (restitution) of the visual substance. According to this view, the different degrees of distinctness or intensity with which these two sensations appear, occur in the several transitions between pure white and deep black; or the proportions in which they appear to be mixed (gray), correspond to the intensity of these two psycho-physical processes. Thus, the consumption and restitution of matter in the visual substance are the primary processes in the sensation of white and black. In the production of the sensation of white, the consumption of the visual substance is caused by the vibrating ethereal waves acting as the discharging force or stimulus, while the degree of the sensation of whiteness is proportional to the quantity of the matter consumed. The process of restitution discharges the sensation of black; the more rapidly it occurs the stronger is the sensation of black. *The consumption of the visual substance at one place causes a greater restitution in the adjoining parts.* Both processes influence each other simultaneously and conjointly. [In the production of a visual sensation, it is important to remember that the condition of one part of the retina influences contemporaneously the condition of adjoining parts of the retina, *i. e.*, "the sensation which arises through the stimulation of any given point of the retina, is also a function of the state of other immediately contiguous points."] This explains physiologically the phenomenon of **contrast** of which the old view could give only a psychical interpretation (p. 832).

Similarly, **color sensation** is regarded as a sensation of decomposition (disassimilation) and of restitution (assimilation); in addition to **white, red** and **yellow** are the expression of **decomposition**; while **green** and **blue** represent the sensation of **restitution**. Thus, the visual substance is subject to three different ways of chemical change or metabolism. We may explain in this way the *colored* phenomena of contrast and the complimentary after images. The sensation of black-white may occur simultaneously with all colors; hence, every color sensation is accompanied by that of dark or bright, so that we cannot have an absolutely pure color. There are three different constituents of the visual substance; that connected with the sensation of black-white (colorless), that with blue-yellow, and that with red-green. All the rays of the visible spectrum act in disassimilating the black-white substance, but the different rays act in different degrees. The blue-yellow or the red-green substances, on the other hand, are disassimilated only by certain rays, some rays causing assimilation, while others are inactive. Mixed light appears colorless when it causes an equally strong disassimilation and assimilation in the blue-yellow and in the red-green substance, so that the two processes mutually antagonize each other, and the action on the black-white substance appears pure. Two objective kinds of light, which together yield white, are not to be regarded as complementary, but as antagonistic, kinds of light, as they do not supplement each other to produce white, but only allow this to appear pure, because, being antagonistic, they mutually prevent each other's action.

The imperfection of the Young-Helmholtz theory of color sensation is that it recognizes only one kind of excitability, excitement and fatigue (corresponding to Hering's disassimilation), and that it ignores the antagonistic relation of certain light rays to the eye. It does not regard white as consisting of complementary light rays, which neutralize each other by their action on the colored visual substance, but as uniting to form white (*Hering*).

[While it suffices to explain a great many of the phenomena of light and color, *e.g.*, the mixing of colors and complementary colors, it does not satisfactorily explain contrast or color blindness. Fick admits that it does not explain the following important fact: Every ray of light, while exciting a color sensation if it falls on a sufficient area of the posterior polar part of the eyeball, provided it acts on an extremely limited part of the retina, even if it be colored light, produces a whitish impression. This is exactly the opposite of what we should expect, viz., the smaller the area of retina acted on, the more readily should the particular nerve ending be excited and a pure color sensation result.]

In **applying this theory to color blindness** (§ 397), we must assume that those who are **red-blind** want the red-green visual substance; there are but two partial spectra in their solar spectrum, the black-white and the yellow-blue. The position of green appears to such an one to be colorless; the rays of the red part of the spectrum are visible, so far as the sensation of yellow and white produced by these rays is strong enough to excite the retina. Hering divides his spectrum into a yellow and a blue half. A **violet-blind** person wants the yellow-blue visual substance; in his spectrum there are only two partial spectra, the black-white and the red-green. In cases of **complete color blindness**, the yellow-blue and

red-green substances are absent. Hence, such a person has only the sensation of bright and dark. The sensibility to light and the length of the spectrum are retained; the brightest part in this case, as in the normal eye, is in the yellow (*Hering*).

397. COLOR BLINDNESS AND ITS PRACTICAL IMPORTANCE.—Causes.—By the term **color blindness** (**dyschromatopsy**) is meant a pathological condition in which some individuals are unable to distinguish certain colors. Huddart (1777) was acquainted with the condition, but it was first accurately described by Dalton (1794), who himself was red blind. The term color blindness was given to it by Brewster.

The supporters of the Young-Helmholtz theory assume that, corresponding to the paralysis of the three color perceiving elements of the retina, there are the following kinds of color blindness:—

1. Red blindness. 2. Green blindness. 3. Violet blindness.

The highest degree being termed **complete color blindness.**

The supporters of E. Hering's theory of color sensation distinguish the following kinds:—

1. **Complete Color Blindness** (**Achromatopsy**).—The spectrum appears achromatic; the position of the greenish-yellow is the brightest, while it is darker on both sides of it. A colored picture appears like a photograph or an engraving. Occasionally the different degrees of light intensity are perceived in one shade of color, *e. g.*, yellow, which cannot be compared with any other color. O. Becker and v. Hippel observed cases of *unilateral* congenital complete color blindness, while the other eye was normal for color perception.

2. **Blue-yellow blindness.**—The spectrum is dichromatic, and consists only of red and green. The blue-violet end of the spectrum is usually greatly shortened. In pure cases only the red and green are correctly distinguished (Mauthner's **erythrochloropy**), but not the other colors. Unilateral cases have been observed.

3. **Red-green Blindness.**—The spectrum is also dichromatic. Yellow and blue are correctly distinguished; violet and blue are both taken for blue. The sensations for red and green are absent altogether. There are several forms of this—(*a*) **Green blindness**, or the red-green blindness, with undiminished spectrum (Mauthner's **xanthokyanopy**), in which bright green and dark red are confounded. In the spectrum yellow abuts directly on blue, or between the two, at most there is a strip of gray. The maximum of brightness is in the yellow. It is often unilateral and often hereditary. (*b*) **Red blindness** (or the red-green blindness with undiminished spectrum, also called **Daltonism**), in which bright red and dark green are confounded. The spectrum consists of yellow and blue, but the yellow lies in the orange. The red end of the spectrum is uncolored, or even dark. The greatest brightness, as well as the limit between yellow and blue, lies more toward the right.

4. **Incomplete color blindness,** or a diminished color sense, indicates the condition in which the acuteness of color perception is diminished, so that the colors can be detected only in large objects, or only when they are near, and when they are mixed with white they no longer appear as such. A certain degree of this form is frequent, in as far as many persons are unable to distinguish greenish-blue from bluish-green.

Acquired color blindness occurs in diseases of the retina and atrophy of the optic nerve in commencing tabes, in some forms of cerebral disease (p. 763), and intoxications. At first green-blindness occurs, which is soon followed by red blindness. The peripheral zone of the retina suffers sooner than the central area. In hysterical persons there may be intermittent attacks of color-blindness (*Charcot*); and the same occurs in hypnotized persons (p. 736).

H. Cohn found that, on **heating the eyeball** of some color-blind persons, the color blindness disappeared temporarily. Occasionally in persons without a lens red vision is present, and is due to unknown causes. **Percentage.**—Holmgren found that 2.7 per cent. of persons were color blind, most being *red* and *green* blind, and very few violet blind.

Limits of Normal Color Blindness.—The investigations on the power of color perception in the *normal* retina are best carried out by means of Aubert-Förster's perimeter, or that of M'Hardy (§ 395). It is found that *our color perception is complete only in the middle of the field of vision.* Around this is a middle zone, in which only blue and yellow are perceived, in which, therefore, there is red blindness. Outside this zone, there is a peripheral girdle, where there is complete color blindness (§ 395). Hence a red-blind person is distinguished from a person with normal vision, in that the central area of the normal field of vision is absent in the former, this being rather included in the middle zone. The field of vision of a green-blind person differs from that of a person with normal vision, in that his peripheral zone corresponds to the intermediate and peripheral zones of the normal eye. The violet-blind person is distinguished by the complete absence of the normal peripheral zone. The incomplete color blindness of these two kinds is characterized by a uniformly diminished central field. [When very intense colors are used, such as those of the solar spectrum, the retina can distinguish them quite up to its margin (*Landolt*).]

In poisoning with **santonin**, violet blindness (yellow vision) occurs in consequence of the paralysis of the violet perceptive retinal elements, which not unfrequently is preceded by stimulation of these elements, resulting in violet vision, *i. e.*, objects seem to be colored violet (*Hüfner*). Such is the explanation of this phenomenon given by Holmgren. Max Schultze, however, referred the yellow vision, *i. e.*, seeing objects yellow, to an increase of the yellow pigment in the macula lutea.

When colored objects are very small, and illuminated only for a short time, the normal eye first fails to perceive red (*Aubert*); hence, it appears that a stronger stimulus is required to excite the sensation of red. Brücke found that very rapidly intermittent white light is perceived as green, because the short duration of the stimulation fails to excite the elements of the retina connected with the sensation of red.

[The **practical importance** of color blindness was pointed out by George Wilson, and again more recently by Holmgren.] No person should be employed in the marine or railway service until he has been properly certified as able to distinguish red from green.

Methods of Testing Color Blindness.—Following Seebeck, Holmgren used small **skeins of colored wools** as the simplest material, in red, orange, yellow, greenish-yellow, green, greenish-blue, blue, violet, purple, rose, brown, gray. There are five finely graduated shades of each of the above colors. When testing a person, select only one skein—*e. g.*, a bright red or rose—from the mass of colored wools placed in front of him, and place it aside, asking him to seek out those skeins which he supposes are nearest to it in color.

Macé and Nacati have measured the acuteness of vision by illuminating a small object with different parts of the spectrum. They compared the observations on red- and green-blind persons with their own results, and found that a red-blind person perceives green light as much brighter than it appears to a normal person. The green-blind had an excessive sensibility for red and violet. It appears that what the color blind lose in perceptive power for one color they gain for another. They have also a keen sense for variations in brightness.

398. **STIMULATION OF THE RETINA.**—As with every other nervous apparatus, a certain but determinable time elapses after the rays of light fall upon the eye before the action of the light takes place, whether the light acts so as to produce a conscious impression, or produces merely a reflex effect upon the pupil. The *strength* of the impression produced depends partly and chiefly upon the excitability of the retina and the other nervous structures. If the light acts for a long time with equal intensity, the excitation, after having reached its culminating point, rapidly diminishes again, at first more rapidly, and afterward more and more slowly.

[When the **retina is stimulated by light**, there is (1) an effect on the rhodopsin (p. 790). (2) The electro-motive force is diminished (§ 332).. (3) The processes of the hexagonal pigment cells of the retina dipping between the rods and cones are affected; thus they are retracted in darkness, and protruded in the light (Fig. 563). (4) Engelmann has shown that the length and shape of the cones vary with the action of light. The cones are retracted in darkness and protruded under the influence of light (Fig. 563). This alteration in the shape of the cones takes place even if the light acts on the skin, and not on the eyeball at all.]

1. FIG. 563. 2.

The cones of the retina and pigment cells (of the frog) as affected by light and darkness; 1 after two days in darkness; 2. after ten minutes in daylight.

After-Images.—If the light acts on the eye for some time so as to excite the retina, and if it be suddenly withheld, the retina still remains for some time in an excited condition, which is more intense and lasts longer, the stronger and the longer the light may have been applied, and the more excitable the condition of the retina. Thus, after every visual perception, especially if it is very distinct and bright, there remains a so-called "*after-image*." We distinguish a "**positive after-image**," which is an image of similar brightness, and a similar color.

"That the impression of any picture remains for some time upon the eye is a physiological phenomenon; when such an impression can be seen for a long time, it becomes pathological. The weaker the eye is, the longer the image remains upon it. The retina does not recover itself so quickly, and we may regard the action as a kind of paralysis. This is not to be wondered at in the case of dazzling pictures. After looking at the sun, the image may remain on the retina for several days. A similar result sometimes occurs with pictures which are not dazzling. Busch records that the impression of an engraving, with all its details, remained on his eye for 17 minutes" (*Goethe*).

Experiments and Apparatus for Positive After-Images.—1. When a burning stick is rapidly rotated, it appears as a fiery circle.

2. The **phanakistoscope** (*Plateau*) or the **stroboscopic disks** (*Stampfer*). Upon a disk or cylinder, a series of objects is so depicted that successive drawings represent individual factors of one continuous movement. On looking through an opening at such a disk rotated rapidly, we see pictures of the different phases moving so quickly that each rapidly follows the one in front of it. As the impression of the one picture remains until the following one takes its place, it has the appearance as if the successive phases of the movement were continuous, and one and the same figure. The apparatus under the name of **zoetrope**, which is extensively used as a toy, is generally stated to have been invented in 1832. It was described by Cardanus in 1550. It may be used to represent certain movements, *e. g.*, of the spermatozoa and ciliary motion, the movements of the heart and those of locomotion.

3. The **color top** contains on the sectors of its disk the colors which are to be mixed. As the color of each sector leaves a condition of excitation for the whole duration of a revolution, all the colors must be perceived simultaneously, *i. e.*, as a mixed color.

[**Illusions of Motion.**—Silvanus P. Thompson points out that if a series of concentric circles in black and white be made on paper, and the sheet on which the circles are drawn be moved with a motion, as if one were rinsing out a pail, but with a very minute radius, then all the circles appear to rotate with the same angular velocity as that imparted. Professor Thompson has contrived other forms of this illusion, in the form of **strobic disks.**]

Negative After-Images.—Occasionally, when the stimulation of the retina is strong and very intense, a "negative," instead of a positive after-image, appears. In a negative after-image, the *bright* parts of the object appear *dark*, and the *colored* parts in corresponding **contrast colors** (p. 824).

Examples of Negative After-Images.—After looking for a long time at a dazzlingly illuminated white window, on closing the eyes we have the impression of a bright cross, or crosses, as the case may be, with dark panes.

Negative colored after-images are beautifully shown by Nörrenberg's apparatus. Look steadily at a colored surface, *e. g.*, a yellow board with a small blue square attached to the centre of its surface. A white screen is allowed to fall suddenly in front of the board—the white surface now has a bluish appearance, with a yellow square in its centre.

The usual **explanation** of dark negative after-images is that the retinal elements are fatigued by the light, so that for some time they become less excitable, and consequently light is but feebly perceived in the corresponding areas of the retina; hence, darkness prevails.

Hering explains the dark after-images as due to a process of assimilation in the black-white visual substance. In explaining *colored* after-images, the Young-Helmholtz theory assumes that, under the action of the light waves, *e. g.*, red, the retinal elements connected with the perception of this color are paralyzed. On now looking suddenly on a white surface, the mixture of all the colors appears as white *minus* red, *i. e.*, the white appears *green*. In bright daylight the contrast color lies very near the complementary color. According to Hering, the contrast after-image is explained by the assimilation of the corresponding colored visual substance, in this case, of the "red-green" (§ 397). From the commencement of a momentary illumination until the appearance of an after-image, 0.344 sec. elapses (*v. Vintschgau and Lustig*).

Not unfrequently, after intense stimulation of the retina, positive and negative after-images *alternate* with each other until they gradually fuse. After looking at the dark-red setting sun we see alternate disks of red and green.

The phenomena of contrast undergo some modification in the peripheral areas of the retina, owing to the partial color blindness which occurs in these areas (*Adamück and Woinow*).

Irradiation is the term applied to certain phenomena where we form a false estimate of visual impressions, owing to *inexact accommodation*. If, from inexact accommodation, the margins of the object are projected upon the retina in diffusion circles, the mind tends to add the undefined margin to those parts of the visual image which are most prominent in the image itself. What is *bright* appears larger

and overcomes what is dark, while an object, without reference to brightness or color, has the same relation to its background (Fig. 564). When the accommodation is quite accurate, the phenomenon of irradiation is not present. [On looking at Fig. 565 from a distance, the white squares appear larger and as if they were united by a white band.]

"A dark object appears smaller than a bright one of the same size. On looking at the same time from a certain distance at two circles of the same size, a white one on a black background, and a black on a white background, we estimate the latter to be about one-fifth less than the former (Fig. 564). On making the black circle one-fifth larger they will appear equal. Tycho de Brahe remarks that the moon, when in conjunction (dark), appears to be one-fifth smaller than in opposition (full, bright). The first lunar crescent appears to belong to a larger disk than the dark one adjoining it, which can occasionally be distinguished at the time of the new light. Black clothes make persons appear to be much smaller than light clothes. A light seen behind a margin gives the appearance of a cut in the margin. A ruler, behind which is placed a lighted candle, appears to the observer to have a notch in it. The sun, when rising and setting, appears to make a depression in the horizon" (*Goethe*).

[**Contrast.**—The fundamental phenomena are such as these, that a bright object looks brighter surrounded by objects darker than itself; and darker with surroundings brighter than itself. There may be contrasts either with bright or dark objects or with colored ones.]

FIG. 564.

For Irradiation.

FIG. 565.

For Irradiation.

Simultaneous Contrast.—By this term is meant a phenomenon like the following: When *bright* and *dark* parts are present in a picture at the same time, the bright (white) parts always appear to be more intensely bright the less white there is near them, or, what is the same thing, the darker the surroundings, and, conversely, they appear less bright the more white tints that are present near them. A similar phenomenon occurs with *colored* pictures. A color in a picture appears to us to be more intense the less of this color there is in the adjoining parts, that is, the more the surroundings resemble the tints of the contrast color. Simultaneous contrast arises from simultaneous impressions occurring in two adjoining and different parts of the retina.

Examples of Contrast for Bright and Dark.—1. Look at a white network on a black ground; the parts where the white lines intersect appear darker, because there is least black near them.

2. Look at a point of a small strip of dark gray paper in front of a dark black background. Push a large piece of white paper between the strip and the background; the strip on the white ground now appears to be much darker than before. On again removing the white paper, the strip at once again appears bright (*Hering*).

3. Look with both eyes toward a grayish-white surface, *e. g.*, the ceiling of a room. After gazing for some time, place in front of the eye a paper tube eight inches long, and an inch to an inch and a quarter in diameter, blackened in the inside. The part of the ceiling seen through the tube appears as a round white spot (*Landois*).

Examples for Colors.—1. Place a piece of gray paper on a red, yellow, or blue ground; the contrast colors appear at once, viz., green, blue, or yellow. The phenomenon is made still more distinct by covering the whole with transparent tracing paper (*Herm. Meyer*). Under similar circumstances, printed matter on a colored ground appears in its complementary color (*W. v. Bezold*).

2. An air bubble in the strongly tinged field of vision of a thick microscopical preparation appears with an intense contrast color (*Landois*).

3. Paste four green sectors upon a rotatory white disk, leave a ring round the centre of the disk uncovered by green, and cover it with a black strip. On rotating such a disk the black part appears red and not gray (*Brücke*).

4. Look with both eyes toward a grayish-white surface, and place in front of one eye a tube about the length and breadth of a finger, composed of transparent oiled paper, gummed together to such thickness as will permit light to pass through its walls. The part of the surface seen through the tube appears in its contrast color. The experiment also shows the contrast in the intensity of the illumination (*Landois*). A white piece of paper, with a round black spot in its centre, when looked at through a blue glass appears blue with a black spot. If a white spot of the same size on a black ground be placed in front, so that it is reflected in the glass plate and just covers the black spot, it shows the contrast color yellow (*Ragona Scina*).

5. The **colored shadows** also belong to the group of simultaneous contrasts. "Two conditions are necessary for the production of colored shadows—firstly, that the light gives some kind of a color to the white surface; second, that the shadow is illuminated, to a certain extent, by another light. During the twilight, place a short lighted candle on a white surface, between it and the fading daylight hold a pencil vertically, so that the shadow thrown by the candle is illuminated, but not abolished by the feeble daylight; the shadow appears of a beautiful *blue*. The blue shadow is easily seen, but it requires a little attention to observe that the white paper acts like a reddish-yellow surface, whereby the blue color apparent to the eye is improved. One of the most beautiful cases of colored shadows is seen in connection with the full moon. The light of the candle and that of the moon can be completely equalized. Both shadows can be obtained of equal strength and distinctness, so that both colors are completely balanced. Place the plate opposite the light of the moon, the lighted candle a little to one side at a suitable distance. In front of the plate hold an opaque body, when a double shadow appears, the one thrown by the moon and lighted by the candle being bright reddish-yellow; and, conversely, the one thrown by the candle and lighted by the moon appears of a beautiful blue. Where the two shadows come together and unite is black" (*Goethe*).

6. "Take a plate of green glass of considerable thickness and hold it so as to get the bars of a window reflected in it, the bars will be seen double, the image formed by the under surface of the glass being *green*, while the image coming from the under surface of the glass, and which ought really to be colorless, appears to be purple. The experiment may be performed with a vessel filled with water, with a mirror at its base. With pure water colorless images are obtained, while by coloring the water colored images are produced" (*Goethe*).

Explanation of Contrast.—Some of these phenomena may be explained as due to an error of judgment. During the simultaneous action of several impressions, the judgment errs, so that when an effect occurs at one place, this acts to the slightest extent in the neighboring parts. When, therefore, brightness acts upon a part of the retina, the judgment ascribes the smallest possible action of the brightness to the adjoining parts of the retina. It is the same with colors. It is far more probable that the phenomena are to be referred to actual physiological processes (*Hering*). Partial *stimulation with light affects not only the part so acted on, but also the surrounding area of the retina* (p. 827); the part directly excited undergoing increased *disassimilation*, the (indirectly stimulated) adjoining area undergoing increased *assimilation;* the increase of the latter is greatest in the immediate neighborhood of the illuminated portion, and rapidly diminishes as the distance from it increases. By the increase of the assimilation in those parts not acted on by the image of the object, this is prevented, so that the diffused light is perceived. The increase of the assimilation in the immediate neighborhood of the illuminated spot is greatest, so that the perception of this relatively stronger different light is largely rendered impossible (*Hering*).

[Helmholtz thus ascribed the phenomena of contrast to psychical conditions, *i. e.*, errors of judgment, but this explanation is certainly not complete. A far more satisfactory solution of the problem is that of Hering, that stimulation of one part of the retina affects the condition of adjoining parts. If a white disk on a black background be looked at for a time, and then the eyes be closed, a negative after-image of the disk appears, but it is darker and blacker than the visual area, and it has a light area around, brightest close to the disk, *i. e.*, the adjacent part of the retina is affected. This Hering has called **successive light induction.**]

Successive Contrast.—Look for a long time at a dark or bright object, or at a colored (*e. g.*, red) one, and then allow the effect of the contrast to occur on the retina, *i. e.*, with reference to the above, bright and dark, or the contrast color green, then these become very intense. This phenomenon has also been called "*successive contrast.*" In this case the negative after-image obviously plays a part.

[Some **drugs** cause subjective visual sensations, but these do so by acting on the brain, *e. g.*, alcohol, as in delirium tremens, cannabis indica, sodic salicylate, and large doses of digitalis (*Brunton*).]

399. MOVEMENTS OF THE EYEBALLS—EYE MUSCLES.—

The globular eyeball is capable of extensive and free movement on the correspondingly excavated fatty pad of the orbit, just like the head of a long bone in the corresponding socket of a freely movable arthrodial joint. The movements of the eyeball, however, are limited by certain conditions, by the mode in which the eye muscles are attached to it. Thus, when one muscle contracts, its antagonistic muscle acts like a bridle, and so limits the movement; the movements are also limited by the insertion of the optic nerve. The soft elastic pad of the orbit on which the eyeball rests is itself subject to be moved forward or backward, so that the eyeball also must participate in these movements.

Protrusion of the eyeball takes place—1. By congestion of the blood vessels, especially of the veins in the orbit, such as occurs when the overflow of the venous blood from the head is interfered with, as in cases of hanging. 2. By contraction of the smooth muscular fibres in Tenon's capsule, in the spheno-maxillary fissure, and in the eyelids (§ 404), which are innervated by the cervical sympathetic nerve. 3. By voluntary forced opening of the palpebral fissure, whereby the pressure of the eyelids acting on the eyeball is diminished. 4. By the action of the oblique muscles, which act by pulling the eyeball inward and forward. If the superior oblique be contracted when the eyelids are forcibly opened, the eyeball may be protruded about 1 mm. When protrusion of the eyeball occurs pathologically (as in 1 and 2), the condition is called **exophthalmos.**

Retraction of the eyeball is the opposite condition, and is caused—1. By closing the eyelids forcibly. 2. By an empty condition of the retro-bulbar blood vessels, diminished succulence, or disappearance of the tissue of the orbit. 3. Section of the cervical sympathetic in dogs causes the eyeball to sink somewhat in the orbit. The smooth muscular fibres of Tenon's capsule are perhaps antagonistic in their action to the four recti when acting together, and thus prevent the eyeball from being drawn too far backward. Many animals have a special *retractor bulbi* muscle, *e.g.*, amphibians, reptiles, and many mammals; the ruminants have four.

The movements of the eyes are almost always accompanied by similar movements of the head, chiefly on looking upward, less so on looking laterally, and least of all when looking downward.

The difficult investigations on the movements of the eyeballs have been carried out, especially by Listing, Meissner, Helmholtz, Donders, A. Fick, and E. Hering.

Axes.—All the movements of the eyeball take place round its **point of rotation** (Fig. 566, O), which lies 1.77 mm. behind the centre of the visual axis, or 10.957 mm. from the vertex of the cornea (*Donders*). In order to determine more carefully the movements of the eyeball, it is necessary to have certain definite data: 1. The **visual axis** (S, S_1), or the antero-posterior axis of the eyeball, unites the point of rotation with the fovea centralis, and is continued straight forward to the vertex of the cornea. 2. The **transverse, or horizontal axis** (Q, Q_1), is the straight line connecting the points of rotation of both eyes and its extension outward. Of course, it is at right angles to 1. 3. The **vertical axis** passes vertically through the point of rotation at right angles to 1 and 2. These three axes form a coördinate system. We must imagine that in the orbit there is a fixed determinate axial system, whose point of intersection corresponds with the point of rotation of the eyeball. When the eye is at rest (primary position), the three axes of the eyeball completely coincide with the three axes of the coördinate system in the orbit. When the eyeball, however, is moved, two or more axes are displaced from this, so that they must form angles with the fixed orbital system.

Planes of Separation.—In order to be more exact, and also partly for further estimations, let us suppose three *planes* passing through the eyeball, and that their position is secured by any two axes. 1. The **horizontal** plane of separation divides the eyeball into an upper and lower half; it is determined by the visual transverse axis. In its course through the retina it forms the **horizontal line of separation** of the latter; the coats of the eyeball itself cut it in their horizontal meridian. 2. The **vertical** plane divides the eyeball into an inner and outer half; it is determined by the visual and vertical axes. It cuts the retina in the **vertical line of separation** of the latter and the periphery of the bulb in the vertical meridian of the eyeball. 3. The **equatorial** plane divides the eyeball into an anterior and posterior half; its position is determined by the vertical and transverse axes, and it cuts the sclerotic in the equator of the eyeball. The horizontal and vertical lines of separation of the retina, which intersect in the fovea centralis, divide the retina into four quadrants.

In order to define more precisely the movements of the eyeball, v. Helmholtz has introduced the following terms: He calls the straight line which connects the point of rotation of the eye with the fixed point in the outer world, the **visual line** ("Blicklinie"), while a plane passing through these lines in both eyes he called the *visual plane;* the *ground line* of this plane is the line uniting the two points of rotation, viz., the transverse axis of the eyeball. Suppose a sagittal section (antero-posterior) to be made through the head, so as to divide the latter into a right and left half, then this

plane would halve the ground line of the visual plane, and when prolonged forward would intersect the visual plane in the median line. The visual point of the eye can be (1) raised or lowered—the field which it traverses being called the visual field ("Blickfeld"); it is part of a spherical surface with the point of rotation of the eye in its centre. Proceeding from the primary position of both eyes, which is characterized by both visual lines being parallel with each other and horizontal, then the elevation of the visual plane can be determined by the angle which this forms with the plane of the primary position. This angle is called the *angle of elevation*—it is positive when the visual plane is raised (to the forehead), and negative when it is lowered (chinward). (2) From the primary position, the visual line can be turned laterally in the visual plane. The extent of this lateral deviation is measured by the **angle of lateral rotation**, *i. e.*, by the angle which the visual line forms with the median line of the visual plane; it is said to be positive when the posterior part of the visual line is turned to the right, negative when to the left. The following are the positions of the eyeball:—

1. **Primary position** [or "position of rest"], in which both the lines of vision are parallel with each other, and the visual planes are horizontal. The three axes of the eyeball coincide with the three fixed axes of the coördinate system in the orbit.

2. **Secondary positions** are due to movements of the eye from the primary position. There are two different varieties—(*a*) where the visual lines are parallel, but are directed *upward* or *downward*. The transverse axis of both eyes remains the same as in the primary position; the deviations of the other two axes expressed by the amount of the angle of elevation of the line of vision. (*b*) The second variety of the secondary position is produced by the *convergence* or *divergence* of the lines of vision. In this variety the vertical axis, round which the lateral rotation takes place, remains as in the primary position; the other axes form angles; the amount of the deviation is expressed by the "angle of lateral rotation." The eye, when in the primary position, can be rotated from this position 42° outward, 45° inward, 34° upward, and 57° downward (*Schuurmann*).

3. **Tertiary position** is the position brought about by the movements of the eye, in which the lines of vision are *convergent*, and are at the same time *inclined* upward or downward.

[**Listing's Law** is that which expresses the movements of the eyeball. When the eyeball moves from the primary position, or position of rest, the angle of rotation of the eye in the second position is the same as if the eye were turned about a fixed axis perpendicular to both the first and the second positions of the visual line (*Helmholtz*).]

All the three axes of the eye are no longer coincident with the axes in the primary position. The exact direction of the visual lines is determined by the amount of the angle of lateral rotation and the angle of elevation. There is still another important point. The eyeball is always rotated at the same time round the line of vision and round its axis (*Volkmann, Hering*). As the iris rotates round the visual line like a wheel round its axis, this rotation is called "**circular rotation**" ("*Raddrehung*") of the eye, which is always connected with the tertiary positions. Even oblique movements may be regarded as composed of—(1) a rotation round the vertical axis, and (2) round the transverse axis; or it may be referred to rotation round a single constant axis placed between the above-named axes, passing through the point of rotation of the eyeball, and at right angles to the secondary and primary direction of the visual axis (line of vision)—(*Listing*). The amount of circular rotation is measured by the angle which the horizontal separation line of the retina forms with the horizontal separation of the retina of the eye in the primary position. This angle is said to be positive, when the eye itself rotates in the same direction as the hand of a watch observed by the same eye, *i. e.*, when the upper end of the vertical line of separation of the retina is turned to the right.

According to Donders, the angle of rotation increases with the angle of elevation and the angle of lateral rotation—it may exceed 10°. With equally great elevation or depression of the visual plane, the rotation is greater, the greater the elevation or depression of the line of vision.

On looking *upward* in the tertiary position, the upper ends of the vertical lines of separation of the retina *diverge;* on looking downward they converge. If the visual plane be raised, the eye, when it deviates laterally to the right, makes a circular rotation to the left. When the visual plane is depressed, on deviating the eye to the right or left, there is a corresponding circular rotation to the right or left. Or we may express the result thus: When the angle of elevation and the angle of deviation have the same sign (+ or —), then the rotation of the eyeball is negative; when, however, the signs are unequal, the rotation is positive. In order to make the circular rotation visible in one's own eye accommodate one eye for a surface divided by vertical and horizontal lines until a positive after-image is produced, and then rapidly rotate the eye into the third position. The lines of the after-image then form angles with the lines of the background. As the position of the vertical meridian of the eye is important from a practical point of view, it is necessary to note that, in the primary and secondary positions of the eyes, the vertical meridian retains its vertical position. On looking to

FIG. 566.



Scheme of the action of the ocular muscles.

the left and upward, or to the right and downward, the vertical meridians of both eyes are turned to the left; conversely, they are turned to the right on looking to the left and downward, or to the right and upward.

In the secondary positions of the eye, rotation of the axis of the eye never occurs (*Listing*). Very slight rolling of the eyes occurs, however, when the head is inclined toward the shoulder, and in the direction opposite to that of the head, it is about 1° for every 10° of inclination of the head (*Skrebitzk*).

Ocular Muscles.—The movements of the eyeball are accomplished by means of the **four straight** and **two oblique** ocular muscles. In order to understand the action of each of these muscles, we must know the plane of traction of the muscles and the axis of rotation of the eyeball. The **plane of traction** is found by the plane lying in the middle of the origin and insertion of the muscle and

the point of rotation of the eyeball. The **axis of rotation** is always at right angles to the plane of traction in the point of rotation of the eyeball.

1. The **rectus internus** (I) and **externus** (E) rotate the eye almost exactly inward and outward (Fig. 566). The plane of traction lies in the plane of the paper; Q, E, is the direction of the traction of the external rectus, Q_1, I, that of the internal. The axis of rotation is in the point of rotation, O, at right angles to the plane of the paper, so that it coincides with the vertical axis of the eyeball. 2. The axis of rotation of the **R. superior and inferior** (the dotted line, R. sup., R. inf.), lies in the horizontal plane of separation of the eye, but it forms an angle of about 20° with the transverse axis (Q, Q_1); the direction of the traction for both muscles is indicated by the line *s*, *i*. By the action of these muscles, the cornea is turned upward and slightly inward, or downward and slightly inward. 3. The axis of rotation of both oblique muscles (the dotted lines, Obl. sup. and Obl. inf.) also lies in the horizontal plane of separation of the eyeball, and it forms an angle of 60° with the transverse axis. The direction of the traction of the *inferior* oblique gives the line, *a*, *b*; that of the *superior*, the line, *c*, *d*. The action of these muscles, therefore, is in the one case to rotate the cornea outward and upward, and in the other outward and downward. These actions, of course, only obtain when the eyes are in the primary position; in every other position the axis of rotation of each muscle changes.

When the eyes are at rest, the muscles are in equilibrium. Owing to the power of the internal recti, the visual axes converge and would meet, if prolonged 40 centimetres in front of the eye. In the movements of the eyeball, one, two, or three muscles may be concerned. *One* muscle acts only when the eye is moved directly outward or inward, especially the internal and external rectus. *Two* muscles act when the eyeball is moved directly upward (superior rectus and inferior oblique) or downward (inferior rectus and superior oblique). *Three* muscles are in action when the eyeballs take a diagonal direction, especially for *inward* and *upward*, by the internal and the superior rectus and inferior oblique; for *inward* and *downward*, the internal and inferior rectus and superior oblique; for *outward* and *downward*, the external and inferior rectus and superior oblique; for *outward* and *upward*, the external and superior rectus and inferior oblique.

[The following table shows the action of the muscles of the eyeball:—

Inward,	Rectus internus.	*Inward and downward*,	Rectus internus. Rectus inferior. Obliquus superior.
Outward,	Rectus externus.		
Upward,	Rectus superior. Obliquus inferior.	*Outward and upward*,	Rectus externus. Rectus superior. Obliquus inferior.
Downward,	Rectus inferior. Obliquus superior.		
Inward and upward,	Rectus internus. Rectus superior. Obliquus inferior.	*Outward and downward*,	Rectus externus. Rectus inferior. Obliquus superior.]

Ruete imitated the movements of the eyeballs by means of a model, which he called the **ophthalmotrope**.

The size of the eyeball and its length diminish with age. The mobility is less in the vertical than in the lateral direction, and less upward than downward. The normal and myopic eye can be moved more outward, and the long-sighted eye more inward; the external and internal recti act most when the eye is moved outward, the obliqui when it is rotated inward. An eye can be turned inward to a greater extent when the other eye at the same time is turned outward than when the other is turned inward. During near vision, the right eye can be turned less to the right, and the left to the left, than during distant vision (*Hering*).

Simultaneous Ocular Movements.—Both eyes are always moved simultaneously. Even when one eye is quite blind, the ocular muscles move when the whole eyeball is excited. When the head is straight, the movements always take place so that both visual planes (visual axes) lie in the same plane. In front both visual axes can diverge only to a trifling extent, while they can converge consider-

ably. If individual ocular muscles are paralyzed, the position of the visual axis in the same place is disturbed, and *squinting* results, so that the patient no longer can direct both visual axes simultaneously to the same point, but he directs the one eye after the other. Even nystagmus (p. 771) occurs in both eyes simultaneously, and in the same direction. The innate simultaneous movement of both eyes is spoken of as an **associated movement** (*Joh. Müller*). E. Hering showed that in all ocular movements there is a *uniformity of the innervation* as well. Even during such movements, in which one eye apparently is at rest, there is a movement, due to the action of two antagonistic forces, the movements resulting in a slight to and fro motion of the eyeball.

The **motor nerves** of the ocular muscles are the oculomotorius (§ 345), the trochlearis (§ 346), and the abducens (§ 348). The **centre** lies in the corpora quadrigemina, and below it (§ 379), and partly in the medulla oblongata (§ 379).

400. **BINOCULAR VISION.—Advantages.**—Vision with both eyes affords the following advantages: (1) The *field of vision* of both eyes is considerably larger than that of one eye. (2) The perception of *depth* is rendered easier, as the retinal images are obtained from two different points. (3) A more exact estimate of the *distance* and *size* of an object can be formed, in consequence of the perception of the degree of convergence of both eyes. (4) The *correction of certain errors* in the one eye is rendered possible by the other.

When the position of the head is *fixed*, we can easily form a conception as to the *form of the entire field of vision* if we close one eye and direct the open eye inward. We observe that it is pear-shaped, broad above and smaller below; the silhouette, or profile of the nose causes the depression between the upper and lower part of the field.

401. **IDENTICAL POINTS—HOROPTER.—Identical Points.**—If we imagine the retinæ of both eyes to be a pair of hollow saucers placed one within the other, so that the yellow spots of both eyes coincide, and also the similar quadrants of the retinæ, then all those points of both retinæ which coincide or cover each other are called "**identical**" or "**corresponding points**" of the retina. The two meridians which separate the quadrants coinciding with each other are called the "**lines of separation.**" Physiologically, the identical points are characterized by the fact that, when they are both simultaneously excited by light, the excitement proceeding from them is, by a psychical act, referred to one and the same point of the field of vision, lying, of course, in a direction through the nodal point of each eye. Stimulation of *both* identical points causes only *one* image in the field of vision. Hence all those objects of the external world, whose rays of light pass through the nodal points to fall upon identical points of the retina, are seen *singly*, because their images from both eyes are referred to the same point of the field of vision, so that they cover each other. All other objects whose images do not fall upon identical points of the retina cause **double vision**, or **diplopia.**

Proofs.—If we look at a linear object with the points 1, 2, 3, then the corresponding retinal images are 1, 2, 3 and 1, 2, 3, which are obviously identical points of the retinæ (Fig. 567). If, while looking at this line, there be a point, A, nearer the eyes, or B, further from them, then, on focusing for 1, 2, 3, neither the rays (A, *a*, A, *a*) coming from A, nor those (B, *b*, B, *b*) from **B**, fall upon identical points; hence A and B appear double.

Make a point (*e.g.*, 2) with ink on paper; of course the image will fall upon both foveæ centrales of the retinæ (2, 2), which of course are identical points. Now press laterally upon one eye, so as to displace it slightly, then two points at once appear, because the image of the point no longer falls upon the fovea centralis of the displaced eye, but on an adjoining non-identical part of the retina. When we squint voluntarily all objects appear double.

The vertical surfaces of separation of the retina do not exactly coincide with the *vertical meridians*. There is a certain amount of divergence (0.5°–3°), less above, which varies in different individuals, and it may be in the same individual at different times (*Hering*). The horizontal lines of separation, however, coincide. Images which fall upon the vertical lines of separation appear to be vertical to

those on the horizontal lines, although they are not actually so. Hence, the vertical lines of separation are the *apparent* vertical meridians. Some observers regard the identical points of the retina as an *acquired* arrangement; others regard it as normally *innate*. Persons who have had a squint from their birth see singly; in these cases, the identical points must be differently disposed.

The **horopter** represents all those points of the outer world from which rays of light passing into both eyes fall upon identical points of the retina, the eyes being in a certain position. It varies with the different positions of the eyes.

1. In the **primary position** of both eyes with the visual axes parallel, the rays of direction proceeding from two identical points of the two retinæ are parallel and intersect only at infinity. Hence for the primary position the horopter is a plane in infinity.

2. In the **secondary position** of the eyes with converging visual axes, the horopter for the transverse lines of separation is a circle which passes through the nodal points of both eyes (Fig. 568, K, K), and through the fixed points I, II, III. The horopter of the vertical lines of separation is in this position vertical to the plane of vision.

3. In the symmetrical **tertiary position**, in which the horizontal and vertical lines of separation form an angle, the horopter of the vertical lines of separation is a straight line inclined toward the

FIG. 567.



Scheme of identical and non-identical points of the retina.

FIG. 568.



Horopter for the secondary position, with convergence of the visual axes.

horizon. There is no horopter for the identical points of the horizontal lines of separation, as the lines of direction prolonged from the identical points of these points do not intersect.

4. In the unsymmetrical tertiary position (with rolling) of the eyes, in which the fixed point lies at unequal distances from both nodal points, the horopter is a curve of a complex form.

All objects, the rays proceeding from which fall upon **non-identical** points of the retinæ, appear **double**. We can distinguish *direct* or *crossed* double images, according as the rays prolonged from the non-identical points of the retina intersect *in front* of or *behind* the fixed point.

Experiment.—Hold two fingers—the one behind the other—before both eyes. Accommodate for the far one and then the near one appears double, and when we accommodate for the near one the far one appears double. If, when accommodating for the near one, the right eye be closed, the left (crossed) image of the far finger disappears. On accommodating for the far finger and closing the right eye, the right (direct) double image of the near finger disappears.

Double images are referred to the proper distance from the eyes, just as single images are.

Neglect of Double Images.—Notwithstanding the very large number of double images which must be formed during vision, they do not disturb vision. As a general rule they are "neglected," so that the attention must, as a rule, be directed to them before they are perceived. This condition is favored thus:—

1. The attention is always directed to the point of the field of vision which is accommodated for at the time. The image of this part is projected on to both yellow spots, which are identical points of the retina.
2. The form and color of objects on the lateral parts of the retina are not perceived so sharply.
3. The eyes are always accommodated for those points which are looked at. Hence, indistinct images with diffusion circles are always formed by those objects which yield double images, so that they can be more readily neglected.
4. Many double images lie so close together that the greater part of them, when the images are large, covers the other.
5. By practice images which do not exactly coincide may be united.

402. STEREOSCOPIC VISION.—On looking at an object, both eyes do not yield exactly similar images of that object—the images are slightly different, because the two eyes look at the object from two different points of view. With the right eye we can see more of the side of the body directed toward it, and the same is the case with the left eye. Notwithstanding this inequality, the two images are united. How two different images are combined is best understood by analyzing the stereoscopic images.

FIG. 569.



Two Stereoscopic Drawings.

Let, in Fig. 569, L and R represent two such images as are obtained with the left and right eyes. These images, when seen with a stereoscope, look like a truncated pyramid, which projects toward the eye of the observer, as the points indicated by the same signs cover each other. On measuring the distance of the points, which coincide or cover each other in both figures, we find that the distances A, *a*, B, *b*, C, *c*, D, *d* are equally great, and at the same time are the *widest* of all the points of both figures; the distances E, *e*, F, *f*, G, *g*, H, *h* are also equal, but are *smaller* than the former. On looking at the coinciding lines (A, E, *a*, *e*, and B, F, *b*, *f*), we observe that all the points of this line which lie nearer to A *a* and B *b* are further apart than those lying nearer E *e* and F *f*.

Comparing these results with the stereoscopic image, we have the following laws for **stereoscopic vision**: **1.** All those points of two stereoscopic images, and of course of two retinal images of an object, which in both images are equally distant from each other, appear on the same plane. **2.** All points which are nearer to each other, compared with the distance of other points, appear to be nearer to the observer. **3.** Conversely, all points which lie further apart from each other appear perspectively in the background.

The **cause** of this phenomenon lies in the fact that, "in vision with both eyes we constantly refer the position of the individual images in the direction of the visual axis to where they both intersect."

Proofs.—The following stereoscopic experiment proves this (Fig. 570): Take both images of two pairs of points (*a*, *b*, and *a*, *β*), which are at unequal distances from each other on the surface of the paper. By means of small stereoscopic prisms cause them to coincide, then the combined point, A of *a*, and *a* appears at a distance on the plane of the paper, while the other point, B, produced by the superposition of *b* and *β*, floats in the air before the observer. Fig. 570 shows how this occurs. The following experiment shows the same result: Draw two figures, which are to be superposed similar to the lines B, A, A, E, *b*, *a*, and *a*, *e*, in Fig. 569. In the lines B, A, and *b*, *a*, all the points which are to be superposed lie equally distant from each other, while, on the contrary, all the points in A, E, and *a*, *e*, which lie nearer E and *e*, are constantly nearer to each other. When looked at with a stereoscope, the superposed verticals, A, *e*, and B, *b*, lie in the plane of the paper, while the superposed lines, A, *a*, and E, *e*, project obliquely toward the observer from the plane of the paper. From these two fundamental experiments we may analyze all pairs of stereoscopic pictures. Thus, in Fig. 569, if we exchange the two pictures, so that R lies in the place of L, then we must obtain the impression of a truncated hollow pyramid.

Two stereoscopic pictures, which are so constructed that the one contains the body from the front and above, and the other contains it from the front and below (suppose in Fig. 569 the lines A B, and *a b*, were the ground lines), can never be superposed by means of the stereoscope.

This process has been explained in another way. Of the two figures, R and L (Fig. 569), only A B C D, and *a b c d*, fall upon identical points of the retina, hence these alone can be superposed; or, when there is a different convergence of the visual axis, only E F G H, and *e f g h*, can be superposed, for the same reason. Suppose the square ground surfaces of the figures are first superposed, in order to explain the stereoscopic impression, it is further assumed that both eyes, after superposition of the ground squares, are rapidly moved toward the apex of the pyramid. As the axis of the eyes must thereby converge more and more, the apex of the pyramid appears to project; as all points which require the convergence of the eyes for their vision appear to us to be nearer (see below). Thus, all corresponding parts of both figures would be brought, one after the other, upon identical points of the retina by the movements of the eyes (*Brücke*).

FIG. 570.



Wheatstone's Stereoscope.

FIG. 571.



Scheme of Brewster's Stereoscope.

It has been urged against this view that the duration of an electrical spark suffices for stereoscopic vision (*Dove*)—a time which is quite insufficient for the movements of the eyes. Although this may be true for many figures, yet in the correct combination of complex or extraordinary figures, these movements of the visual axes are not excluded, and in many individuals they are distinctly advantageous. Not only the actual movements necessary for this act, but the sensations derived from the muscles are also concerned.

When two figures are *momentarily* combined to form a stereoscopic picture, there being no movement of the eyes, clearly many points in the stereoscopic pictures are superposed which, *strictly* speaking, do not fall upon identical points of the retina. Hence we cannot characterize the identical points of the retina as coinciding mathematically; but from a physiological point of view we must regard such points as identical, which, *as a rule*, by simultaneous stimulation, give rise to a single image. The mind obviously plays a part in this combination of images. There is a certain psychical tendency to fuse the double images on the retinæ into one

image, in accordance with the fact that we, from experience, recognize the existence of a single object. If the differences between two stereoscopic pictures be too great, so that parts of the retina too wide apart are excited thereby, or when new lines are present in a picture, and do not admit of a stereoscopic effect, or disturb the combination, then the stereoscopic effect ceases.

The **stereoscope** is an instrument by means of which two somewhat similar pictures drawn in perspective may be superposed so that they appear single. Wheatstone (1838) obtained this result by means of two mirrors placed at an angle (Fig. 570); Brewster (1843) by two prisms (Fig. 571). The construction and mode of action are obvious from the illustrations.

Some pairs of two such pictures may be combined, without a stereoscope, by directing the visual axis of each eye to the picture held opposite to it.

Two completely identical pictures, *i. e.*, in which all corresponding points have exactly the same relation to each other as the same sides of two copies of a book, appear quite flat under the stereoscope; as soon, however, as in one of them one or more points alters its relation to the corresponding points, this point either projects or recedes from the plane.

Telestereoscope.—When objects, placed at a great distance, are looked at, *e. g.*, the most distant part of a landscape, they appear to us to be flat, as in a picture, and do not stand out, because the slight differences of position of our eyes in the head are not to be compared with the great distance. In order to obtain a stereoscopic view of such objects, v. Helmholtz constructed the **telestereoscope** (Fig. 572), an apparatus which by means of two parallel mirrors, places, as it were, the point of view of both eyes wider apart. Of the mirrors, L and R each projects its image of the landscape upon *l* and *r*, to which both eyes, O, *o*, are directed. According to the distance between L and R the eyes O, *o*, as it were, are displaced to O_1, o_1. The distant landscape appears like a stereoscopic view. In order to see distant parts more clearly and nearer, a double telescope or opera glass may be placed in front of the eyes.

Take two corresponding stereoscopic pictures, with the surfaces black in one case and light in the other. Draw two truncated pyramids like

FIG. 572.



Telestereoscope of v. Helmholtz.

FIG. 573.



Wheatstone's Pseudoscope.

Fig. 569, make one figure exactly like L, *i. e.*, with a white surface and black lines, and the other with white lines and a black surface, then under the stereoscope such objects **glance**. The cause of the glancing condition is that the glancing body at a certain distance reflects bright light into one eye and not into the other, because a ray reflected at an angle cannot enter both eyes simultaneously (*Dove*).

Wheatstone's Pseudoscope consists of two right-angled prisms (Fig. 573, A and B) enclosed in a tube, through which we can look in a direction parallel with the surfaces of the hypothenuses. If a spherical surface be looked at with this instrument, the image formed in each eye is inverted laterally. The right eye sees the view usually obtained by the left eye, and conversely; the shadow which the body in the light throws upon a light ground is reversed. Hence the ball appears hollow.

Struggle of the Fields of Vision.—The stereoscope is also useful for the following purpose: In vision with both eyes, both eyes are almost never active simultaneously and to the same extent; both undergo variations, so that first the impression on the one retina and then that on the other is stronger. If two different surfaces be placed in a stereoscope, then, especially when they are luminous, these two alternate in the general field of vision, according as one or other eye is active (*Panum*). Take two surfaces with lines ruled on them, so that when the surfaces are superposed the lines will cross each other, then either the one or the other system of lines is more prominent (*Panum*). The same is true with colored stereoscopic figures, so that there is a contest or struggle of the colored fields of vision.

403. ESTIMATION OF SIZE AND DISTANCE.—Size.—We estimate the size of an object—apart from all other factors—from the **size of the**

retinal image; thus the moon is estimated to be larger than the stars. If, while looking at a distant landscape, a fly should suddenly pass across our field of vision, near to our eye, then the image of the fly, owing to the relatively great size of the retinal image, may give one the impression of an object as large as a bird. If, owing to defective accommodation, the image gives rise to diffusion circles, the size may appear to be even greater. But objects of very unequal size give equally large retinal images, especially if they are placed at such a distance that they form the same **visual angle** (Fig. 531); so that in estimating the **actual size** of an object, as opposed to the **apparent size** determined by the visual angle, the *estimate of distance* is of the greatest importance.

As to the **distance** of an object, we obtain some information from the **feeling of accommodation**, as a greater effort of the muscle of accommodation is required for exact vision of a near object than for seeing a distant one. But, as with two objects at unequal distances giving retinal images of the *same size*, we know from experience that that object is smaller which is near, then that object is estimated to be the smaller for which, during vision, we must accommodate more strongly.

In this way we explain the following: A person beginning to use a microscope always observes with his eyes accommodated for a near object, while one used to the microscope looks through it without accommodating. Hence beginners always estimate microscopic objects as too small, and on making a drawing of them it is too small. If we produce an after-image in one eye, it at once appears smaller on accommodating for a near object, and again becomes larger during negative accommodation. If we look with one eye at a small body placed as near as possible to the eye, then a body lying behind it, but seen only indirectly, appears smaller.

Angle of Convergence of Visual Axes.—In estimating the **size** of an object, and taking into account our estimate of its distance, we also obtain much more important information from the degree of **convergence of the visual axes**. We refer the position of an object, viewed with both eyes, to the point where both visual axes intersect. The angle formed by the two visual axes at this point is called the "angle of convergence of the visual axes" ("*Gesichtswinkel*"). The larger, therefore, the visual angle, the size of the retinal image remaining the same—we judge the object to be nearer. The nearer the object is, it may be the smaller, in order to form a "**visual angle**" of the same size, such as a distant large object would give. Hence, we conclude that with the same apparent size (equally large visual angle, or retinal images of the same size) we judge that object to be smallest which gives the greatest convergence of the visual axes during binocular vision. As to the muscular exertion necessary for this purpose, we obtain information from the **muscular sense** of the ocular muscles.

FIG. 574.



Rollett's glass plate apparatus.

Experiments and Proofs.—The chess-board phenomenon of H. Meyer. 1. If we look at a uniform chess-board-like pattern (tapestry or carpet), then, when the visual axes are directed directly forward, the spaces on the pattern appear of a certain size. If, now, we look at a nearer object, we may cause the visual axes to cross, when the pattern apparently moves toward the plane of the fixed point, so that the crossed double images are superposed, and the pattern at once appears smaller.

2. Rollett looks at an object through two thick prisms of glass placed at an angle. The plates are at one time so placed that the apex of the angle is directed toward the observer (Fig. 574, II), at another in the reverse position (I). If both eyes, *f* and *i*, are to see the object *a*, in I, then as the glass plates so displace the rays, *a*, *c*, and *a*, *g*, as to make them parallel with the direction of these rays, viz., *e*, *f*, and *h*, *i*, then the eyes must *converge* more than when they are turned directly toward *a*. Hence the object appears nearer and smaller, as at *a*. In II, the rays, b_1 *k*, and b_1 *o*, from the nearer object b_1, fall upon

the glass plates. In order to see b_1, the eyes (n and q) must *diverge* more, so that b appears more distant and larger.

3. In looking through *Wheatstone's reflecting stereoscope* (Fig. 571), it is obvious that the more the two images approach the observer, the more must the observer converge his visual axes, because the angles of incidence and reflexion are greater. Hence the compound picture now appears to him to be *smaller*. If the centre of the image, R, recedes to R_1, then of course the angle, S_{11}, $r\ \rho$, is equal to S_1, $r\ R_1$, and the same on the left side.

4. In using the *telestereoscope*, the two eyes are, as it were, separated from each other, then of course in looking at objects at a certain distance the convergence of the visual axes must be greater than in normal vision. Hence, objects in a landscape appear as in a small model. But as we are accustomed to infer that such small objects are at a great distance, hence the objects themselves appear to recede in the distance.

Estimation of Distance.—When the retinal images are of the same size, we estimate the distance to be greater the less the **effort of accommodation**, and conversely. In binocular vision, when the retinal images are of the same size, we infer that that object is most distant for which the optic axes are least converged, and conversely. Thus, the estimation of size and distance go hand in hand, in great part at least, and the correct estimation of the distance also gives us a correct estimate of the size of objects (*Descartes*). A further aid to the estimation of distance is the observation of the *apparent displacement* of objects, on moving our head or body. In the latter, especially, lateral objects appear to change their position toward the background, the nearer they are to us. Hence, when traveling in a train, in which case the change of position of the objects occurs very rapidly, the objects themselves are regarded as nearer, and also smaller (*Dove*). Lastly, those objects appear to us to be *nearest* which are most *distinct* in the field of vision.

Example.—A light in a dark landscape, and a dazzling crown of snow on a hill, appear to be near to us; looked at from the top of a high mountain, the silver glancing curved course of a river not unfrequently appears as if it were raised from the plane.

False Estimates of Size and Direction.—1. A line divided by intermediate points appears longer than one not so divided. Hence the heavens do not appear to us as a hollow sphere, but as curved like an ellipse; and for the last reason the disk of the setting sun is estimated to be larger than the sun when it is in the zenith. 2. If we move a circle slowly to and fro behind a slit, it appears as a horizontal ellipse; if we move it rapidly, it appears as a vertical ellipse. 3. If a very fine line be drawn obliquely across a vertical thick black line, then the direction of the fine line beyond the thick one appears to be different from its original direction. 4. **Zöllner's Lines.**—Draw three parallel horizontal lines 1 centimetre apart, and through the upper and lower ones draw short oblique parallel lines in the direction from above and the left to below and the right; through the middle line draw similar oblique lines, but in the opposite direction, then the three horizontal lines no longer appear to be parallel. [Fig. 575 shows a modification of this. The lines are actually parallel, although some of them appear to converge and others diverge.] If we look in a dark room at a bright vertical line and then bend the head toward the shoulder, the line appears to be bent in the opposite direction (*Aubert*).

FIG. 575.

Zöllner's Lines.

404. **PROTECTIVE ORGANS OF THE EYE.—I.** The **eyelids** are represented in sections in Fig. 576. The tarsus is in reality not cartilage, but merely a rigid plate of connective tissue, in which the **Meibomian glands** are imbedded; acinous sebaceous glands moisten the edges of the eyelids with fatty matter. At the basal margin of the tarsus, especially of the upper one, close to the reflection of the conjunctiva, open the acino-tubular glands of Krause. The conjunctiva covers the anterior surface of the bulb as far as the margin of the cornea, over which the epithelium alone is continued. On the posterior surface of the eyelid, the conjunctiva is partly provided with papillæ. It is covered by stratified prismatic epithelium. Coiled **glands** occur in ruminants just outside the margin of the cornea, while outside this, toward the outer angle of the eye in the pig, there are simple glandular sacs. Waldeyer describes modified sweat glands in the tarsal margins in man. Small lymphatic sacs in the conjunctiva are called trachoma glands. Krause found **end bulbs** in the conjunctiva (§ 424). The blood vessels in the conjunctiva communicate

with the juice canals in the cornea and sclerotic (p. 787). The secretion of the conjunctiva, besides some mucus, consists of tears, which may be as abundant as that formed in the lachrymal glands.

Closure of the eyelids is effected by the orbicularis palpebrarum (*facial nerve*, § 349), whereby the upper lid falls in virtue of its own weight. This muscle contracts—(1) voluntarily; (2) involuntarily (single contractions); (3) reflexly by stimulation of all the sensory fibres of the trigeminus distributed to the bulb and its immediate neighborhood (§ 347), also by intense stimulation of the retina by light; (4) continued involuntary closure occurs during sleep.

FIG. 576.



Vertical section through the upper eyelid. *A*, cutis; 1, epidermis; 2, chorium; *B*, and 3, subcutaneous connective tissue; *C* and 7, orbicularis muscle; *D*, loose sub-muscular connective tissue; *E*, insertion of H. Müller's muscle; *F*, tarsus; *G*, conjunctiva; *J*, inner, *K*, outer edge of the lid; 4, pigment cells; 5, sweat glands; 6, hair follicles; 8 and 23, sections of nerves; 9, arteries; 10, veins; 11, cilia; 12, modified sweat glands; 13, circular muscle of Riolan; 14, Meibomian gland; 15, section of an acinus of the same; 16, posterior tarsal glands; 18 and 19, tissue of the tarsus; 20, pre-tarsal or sub-muscular connective tissue; 21 and 22, conjunctivæ, with its epithelium; 24, fat; 25, loosely woven posterior end of the tarsus; 26, section of a palpebral artery.

Opening of the eyelids is brought about by the passive descent of the lower one, and the active elevation of the upper eyelid by the levator palpebræ superioris (§ 345). The smooth muscular fibres of the eyelids also aid (p. 643). In looking downward, the lower eyelid is pulled downward by bands of connective tissue which run from the inferior rectus to the inferior tarsal cartilage (*Schwalbe*).

II. The **lachrymal apparatus** consists of the **lachrymal glands**, which in structure closely resemble the parotid, their acini being lined by low cylindrical granular epithelium. Four to five larger, and eight to ten smaller **excretory ducts** conduct the tears above the outer angle of the lid into the fornix conjunctivæ. The **tear ducts**, beginning at the puncta lachrymalis, are composed of connective and elastic tissue, and are lined by stratified squamous epithelium. Striped muscle accompanies the duct, and by its contraction keeps the duct open. Toldt found no sphincter surrounding the puncta lachrymalia, while Gerlach found an incomplete circular musculature. The connective-tissue covering of the tear sac and canal is united with the adjoining periosteum. The thin mucous membrane, which contains much adenoid tissue and lymph cells, is lined by a single layer of ciliated cylindrical epithelium, which below passes into the stratified form. The opening of the duct is often provided with a valve-like fold (Hasner's valve).

The **conduction of the tears** occurs between the lids and the bulb by means of *capillarity*, the closure of the eyelids aiding the process. The Meibomian secretion prevents the overflow of the tears [just as greasing the edge of a glass vessel prevents the water in it from overflowing]. The tears are conducted from the puncta through the duct, chiefly by a

siphon action. Horner's muscle (also known to Duvernoy, 1678) likewise aids, as every time the eyelids are closed it pulls upon the posterior wall of the sac, and thus dilates the latter, so that it aspirates tears into it (*Henke*).

E. H. Weber and Hasner ascribe the aspiration of the tears to the diminution of the amount of air in the nasal cavities during inspiration. Arlt asserts that the tear sac is compressed by the contraction of the orbicularis muscle, so that the tears must be forced toward the nose. Lastly, Stellwag supposes that when the eyelids are closed the tears are simply pressed into the puncta, while Gad denies that there is any kind of pumping mechanism in the nasal canal. Landois points out that the tear ducts are surrounded by a plexus of veins, which according to their state of distention may influence the size of these tubes.

The **secretion of tears** takes place only by *direct* stimulation of the lachrymal nerve (§ 347, I, 2), subcutaneous malar (§ 347, II, 2), and cervical sympathetic (§ 356, A, 6), which have been called **secretory nerves.** Secretion may also be excited *reflexly* (p. 641) by stimulation of the nasal mucous membrane only on the same side (*Herzenstein*). The ordinary secretion in the waking condition is really a reflex secretion produced by the stimulation of the anterior surface of the bulb by the air, or by the evaporation of tears. A very **bright light** also causes a reflex secretion of tears, the optic being the afferent nerve. The **centre** in the rabbit does not extend forward beyond the origin of the fifth nerve, but it extends downward to the fifth vertebra (*Eckhard*). During sleep all these factors are absent, and there is no secretion. **Histological changes.**—Reichel found that in the **active gland** (after injection of pilocarpin) the secretory cells became granular, turbid, and smaller, while the outlines of the cells became less distinct, and the nuclei spheroidal. In the **resting gland**, the cells are bright and slightly granular, with irregular nuclei. Intense stimulation by *light* acting on the optic nerve causes a reflex secretion of tears. The flow of tears accompanying certain violent emotions, and even hearty laughing, is still unexplained. During coughing and vomiting the secretion of tears is increased partly reflexly, and partly by the outflow being prevented by the expiratory pressure.

Function.—The tears moisten the bulb, protect it from drying, and float away small particles, being aided in this by the closure of the eyelids. Atropin diminishes the tears (*Mogaard*).

Composition.—The tears are alkaline, saline to taste, and represent a "serous" secretion. Water 98.1 to 99; 1.46 organic substances (0.1 albumin and mucin, 0.1 epithelium); 0.4 to 0.8 salts (especially NaCl).

[**Action of Drugs.**—Essential volatile oils and eserin increase the secretion of tears, atropin arrests it, while eserin antagonizes the effect of atropin and causes an increased secretion.]

405. **COMPARATIVE—HISTORICAL.—Comparative.**—The **simplest form** of visual apparatus is represented by aggregations of pigment cells in the outer coverings of the body, which are in connection with the termination of afferent nerves. The pigment absorbs the rays of light, and in virtue of the light ether discharges kinetic energy, which excites the terminations of the nervous apparatus. Collections of pigment cells, with nerve fibres attached, and provided with a clear refractive body, occur on the margin of the bell of the higher medusæ, while the lower forms have only aggregations of pigment on the bases of their tentacles. Also, in many lower worms there are pigment spots near the brain. In others, the pigment lies as a covering round the terminations of the nerves, which occur as "crystalline rods" or "crystalline spheres." In parasitic worms, the visual apparatus is absent. In **star-fishes**, the eyes are at the tips of the arms, and consist of a spherical crystal organ surrounded with pigment, with a nerve going to it. In all other echinodermata there are only accumulations of pigment. Among the **annulosa** there are several grades of visual apparatus. (1) **Without a cornea**, there may be only one crystal sphere (nervous end organ) near the brain, as in the young of the crab; or there may be several crystal spheres forming a compound eye, as in the lower crabs. (2) **With a cornea**, consisting of a lenticular body formed from the chitin of the outer integument, the eye itself may be simple, merely consisting of one crystal rod, or it may be compound. The compound eye consists of only one large lenticular cornea, common to all the crystal rods, as in the spiders; or each crystal rod has a special lenticular cornea for itself. The numerous rods surrounded by pigment are closely packed together, and are arranged upon a curved surface, so that their free ends also form a part of a sphere. The chitinous investment of the head is faceted, and forms a small corneal lens on the free end of each rod. According

to one view, each facette, with the lens and crystal sphere, is a special eye, and just as man has two eyes so insects have several hundred. Each eye sees the picture of the outer world *in toto*. This view is supported by the following experiment of van Leeuwenhoek: If the cornea be sliced off, each facette thereof gives a special image of an object. If a cross be made on the mirror of a microscope, while a piece of the facetted cornea is placed as an object upon the stage, then we see an image of the cross in each facette of the cornea. Thus for each rod (crystal sphere) there would be a special image. Each corneal facette, however, forms only a part of the image of the outer world, so that we must regard the image as composed like a mosaic. Among **mollusca**, the fixed brachiopoda have two pigment spots near the brain, but only in their larval condition; while the mussel has, under similar conditions, pigment spots with a refractive body. The adult mussel, however, has pigment spots (ocelli) only in the margin of the mantel, but some mollusks have stalked and highly developed eyes. Some of the lower snails have no eyes, some have pigment spots on the head, while the garden snail has stalked eyes provided with a cornea, an optic nerve with retina and pigment, and even a lens and vitreous body. Among **cephalopoda**, the nautilus has no cornea or lens, so that the sea water flows freely into the orbits. Others have a lens and no cornea, while some have an opening in the cornea (Loligo, Sepia, Octopus). All the other parts of the eye are well developed. Among **vertebrata**, Amphioxus has no eyes. They exist in a degenerated condition in Proteus and the mammal Spalax. In many fishes, amphibians, and reptiles, the eye is covered by a piece of transparent skin. [**Pineal or Epiphysial Eye.**—Some lizards, *e.g.*, Hatteria, have a rudimentary median eye in the median line of the head, and lodged in the parietal foramen. It is developed from the pineal body, and its lens is formed from the optic cup, so that light falls upon the retina without penetrating the fibres of the optic nerve. Thus, it is an invertebrate type of eye, where the retina and lens are developed from epidermal structures, while in the vertebrate eye, the retina is developed from the cerebrum.] Some hag-fishes, the crocodile, and birds have eyelids, and a **nictitating membrane** at the inner angle of the eye. Connected with it is the **Harderian gland.** In mammals the nictitating membrane is represented only by the plica semilunaris. There is no lachrymal apparatus in fishes. The tears of snakes remain under the watch-glass-like cutis with which the eyes are covered. The sclerotic often contains cartilage which may ossify. A vascular organ, the **processus falciformis**, passes from the middle of the choroid into the interior of the vitreous body in osseous fishes, its anterior extremity being termed the campanula Halleri. Similarly, there is the **pecten** in birds, but it is provided with muscular fibres. In birds the cornea is surrounded by a bony ring. The whale has an enormously thick sclerotic. In **aquatic animals**, the lens is nearly spherical. The **muscles** of the iris and choroid are transversely striped in birds and reptiles. The retinal rods in all vertebrates are directed from before backward, while the analogous elements (crystal rods and spheres) in invertebrata are directed from behind forward.

Historical.—The Hippocratic School were acquainted with the optic nerve and lens. Aristotle (384 B.C.) mentions that section of the optic nerve causes blindness—he was acquainted with after-images, short and long sight. Herophilus (307 B.C.) discovered the retina, and the ciliary processes received their name in his school. Galen (131–203 A.D.) described the six muscles of the eyeball, the puncta lachrymalia, and tear duct. Aerengar (1521) was aware of the fatty matter at the edge of the eyelids. Stephanus (1545) and Casseri (1609) described the Meibomian glands, which were afterward redescribed by Meibom (1666). Fallopius described the vitreous membrane and the ciliary ligament. Plater (1583) mentions that the posterior surface of the lens is more curved. Aldrovandi observed the remainder of the pupillary membrane (1599). Observations were made at the time of Vesalius (1540) on the refractive action of the lens. Leonardo da Vinci compared the eye to a camera obscura. Maurolykos compared the action of the lens to that of a lens of glass, but it was Kepler (1611) who first showed the true refractive index of the lens and the formation of the retinal image, but he thought that during accommodation the retina moved forward and backward. The Jesuit, Scheiner (†1650), mentions, however, that the lens becomes more convex by the ciliary processes, and he assumed the existence of muscular fibres in the uvea. He referred long and short sight to the curvature of the lens, and he first showed the retinal image in an excised eye. With regard to the use of **spectacles** there is a reference in Pliny. It is said that at the beginning of the 14th century the Florentine, Salvino d'Armato degli Armati di Fir (†1317), and the monk, Alessandro de Spina (†1313), invented spectacles. Kepler (1611) and Descartes (1637) described their action. Mayo (†1852) described the 3d nerve as the constrictor nerve of the pupil. Zinn contributed considerably to our knowledge of the structure of the eye. Ruysch described muscular fibres in the iris, and Monro described the sphincter of the pupil (1794) Jacob described the bacillary layer of the retina—Sœmmering (1791) the yellow spot. Brewster and Chossat (1819) tested the refractive indices of the optical media. Purkinje (1819) studied subjective vision.

HEARING.

406. THE ORGAN OF HEARING.—Stimulation of the Auditory Nerve.—The normal manner in which the auditory nerve is excited, is by means of **sonorous vibrations,** which set in motion the end organs of the acoustic nerve, which lie in the endolymph of the labyrinth of the inner ear, on membranous expansions of the cochlea and semicircular canals. Hence, the sonorous vibrations are first transmitted to the fluid in the labyrinth, and this, in turn, is thrown into waves, which set the end organs into vibration. Thus, the excitement of the auditory nerves is brought about by the *mechanical stimulation of the wave motion of the lymph of the labyrinth.*

FIG. 577.



Scheme of the organ of hearing. AG, external auditory meatus; T, tympanic membrane; K, malleus with its head (*h*), short process (*kf*), and handle (*m*); *a*, incus, its short process (*x*), and its long process united to the stapes (*s*) by means of the Sylvian ossicle (*z*); P, middle ear; *o*, fenestra ovalis; *r*, fenestra rotunda; *x*, beginning of the lamina spiralis of the cochlea; *pt*, scala tympani, and *vt*, scala vestibuli; V, vestibuli; S, sacule; U, utricle; H, semicircular canals; TE, Eustachian tube. The long arrow indicates the line of traction of the tensor tympani; the short curved one, that of the stapedius.

The fluid or lymph of the labyrinth is surrounded by the exceedingly hard osseous mass of the temporal bone (Fig. 577). Only at one small roundish and slightly triangular area, the **fenestra rotunda** (*r*), the fluid is bounded by a delicate yielding membrane, which is in contact with the air in the middle ear or tympanum (P). Not far from the fenestra rotunda is the **fenestra ovalis** (*o*), in which the base of the stapes (*s*) is fixed by means of a yielding membranous ring. The outer surface of this also is in contact with the air in the middle ear. As the perilymph of the inner ear is in contact at these two places with a yielding boundary, it is clear that the lymph itself may exhibit oscillatory movements, as it must follow the movements of the yielding boundaries.

The sonorous vibrations may set the perilymph in vibration in *three* different ways:—

1. **Conduction through the Bones of the Head.**—This occurs especially when the vibrating solid body is applied directly to some part of the head, *e. g.*, a tuning fork placed on the head, the sound being propagated most intensely in the direction of the prolongation of the handle of the instrument—also when the sound is conducted to the head by means of fluid, as when the head is ducked

under water. Vibrations of the air, however, are practically not transferred directly to the bones of the head, as is shown by the fact that we are deaf when the ears are stopped.

The soft parts of the head, which lie immediately upon bone, conduct sound best, and of the projecting part, the best conductor is the cartilaginous portion of the external ear. But even under the most favorable circumstance, conduction through the bones of the head is far less effective than the conduction of the sound waves through the external auditory meatus. If a tuning fork be made to vibrate between the teeth until we no longer hear it, its tone may still be heard on bringing it near the ear (*Rinne*). The conduction through the bones is favored when the oscillations are not transferred from the bones to the tympanic membrane, and are thus transferred to the air, in the outer ear. Hence, we hear the sound of a tuning fork applied to the head better when the ears are stopped, as this prevents the propagation of the sound waves through the air in the outer ear. If, in a *deaf* person, the conduction is still normal through the cranial bones, then the cause of the deafness is not in the nervous part of the ear, but in the external sound-conducting part of the apparatus.

2. **Normal hearing** takes place through the **external auditory meatus.** The enormous vibrations of the air first set the tympanic membrane in vibration (Fig. 577, T); this moves the malleus (*h*), whose long process is inserted into it; the malleus moves the incus (*a*), and this the stapes (*s*), which transfers the movements of its plate to the perilymph of the labyrinth.

3. **Direct Conduction to the Fenestra.**—In man, in consequence of occasional disease of the middle ear, whereby the tympanic membrane and auditory ossicles may be destroyed, the auditory apparatus may be excited, although only in a very feeble manner, by the vibrations of the air being directly transferred to the membrane of the fenestra rotunda (*r*), and the parts closing the fenestra ovalis (*o*). The membrane of the fenestra rotunda may vibrate alone, even when the oval window is closed with a rigid body (*Weber-Liel*).

407. **PHYSICAL INTRODUCTION.**—**Sound** is produced by the vibration of elastic bodies capable of vibration. Alternate **condensation and rarefaction** of the surrounding air are thus produced; or, in other words, **sound waves** in which the particles vibrate longitudinally or in the direction of the propagation of the sound are excited. Around the point of origin of the sound, these condensations and rarefactions occur in equal concentric circles, which conduct the sound vibrations to our outer ear. The vibrations of the sounding body are so called "stationary vibrations," *i. e.*, all the particles of the vibrating body are always in the same phase of movement, in that they pass into movement simultaneously, they reach the maximum of movement simultaneously, *e. g.*, in the particles of a sounding vibrating metal rod. Sound is **produced** by the stationary vibrations of elastic bodies; it is **propagated** by progressive wave motion of elastic media, generally the air. The wave length of a tone, *i. e.*, the distance of one maximum of condensation to the next one in the air, is proportional to the duration of the vibration of the body, whose vibrations produce the sound waves.

If λ is the wave length of a tone, t in second the durations of a vibration of the body producing the wave, then $\lambda = a\,t$, where $a = 340.88$ metres, which is the rate per second of propagation of sound waves in the air. The rapidity of the transmission of sound waves in water = 1435 metres per second, *i. e.*, nearly four times as rapid as in air; while, in solids capable of vibration, it is propagated from seven to eighteen times faster than in the air. Sound waves are conducted best through the same medium; when they have to pass through several media they are always weakened.

Reflection of the sound waves occurs when they impinge upon a solid obstacle, in which case the angle of reflection is always equal to the angle of incidence.

Wave Movements.—We distinguish—I. **Progressive wave movements** which occur in two forms—(1) As *longitudinal* waves, in which the individual particles of the vibrating body vibrate around their centre of gravity in the direction of the propagation of the wave; examples are the waves in water and air. This movement causes an accumulation of the particles at certain places, *e. g.*, on the crests of the waves in water waves, while at other places they are diminished. This kind of wave is called a wave of **condensation and rarefaction.** (2) If, however, each particle in the progressive wave moves vertically up and down, *i. e.*, transversely to the direction of the propagation of the wave, then we have the simple *transverse* wave, or progressive waves, in which there is no condensation or rarefaction in the direction of propagation, as each particle is merely displaced laterally. An example of this is the *progressive* waves in a rope.

II. **Stationary Flexion Waves.**—When all the particles of an elastic vibrating body so oscillate that all of them are always in the same phase of movement as the limbs of a vibrating tuning fork or a plucked string, then this kind of movement is described as stationary flexion waves. As bodies, whose expansion in the direction of oscillation is very slight, vibrate to and fro in the stationary flexion wave, so we see that the small parts of the auditory apparatus (tympanic membrane, ossicles, lymph of the labyrinth) oscillate in stationary flexion waves.

408. EAR MUSCLES—EXTERNAL AUDITORY MEATUS.—When the **external ear** is absent, little or no impairment of the hearing is observed; hence, the physiological functions of these organs are but slight. Boerhaave thought that the elevations and depressions of the outer ear might be connected with the reflection of the sound waves. Numerous sound waves, however, must be again reflected outward; and those waves which reach the deep part of the concha are said to be reflected toward the tragus, to be reflected by it into the external auditory meatus. According to Schneider, when the depressions in the ear are filled up with wax, hearing is impaired; other observers, however, have found the hearing to be unaffected. Mach points out that the dimensions of the external ear are proportionally too small to act as reflecting organs for the wave lengths of noises.

Muscles of the External Ear.—(1) The whole ear is moved by the retrahentes, attrahens, and attollens. (2) The *form* of the ear may be altered by the tragicus, antitragicus, helicis major and minor *internally;* and by the transversus and obliquus auriculæ *externally*. Persons who can move their ears do not find that the hearing is influenced during the movement. The Mm. helicis major and minor are regarded as elevators of the helix; the transversus and obliquus auriculæ as dilators of the concha; the tragicus and antitragicus as constrictors of the meatus. In animals, the external ear and the action of its muscles have a marked effect upon hearing. The muscles point the ear in the direction of the sound, while other muscles contract or dilate the space within the external ear. In many diving animals, the meatus can be closed by a kind of valve.

The **external meatus** is 3 to 3.25 cm. long [1⅛ to 1¼ inch], 8 to 9 mm. high, and 6 to 8 mm. broad at its outer opening (Fig. 578). It is the conductor of the sound waves to the tympanic membrane, so that almost all the sound waves first impinge upon its wall, and are then reflected toward the tympanic membrane. To see well down into the meatus, we must pull the auricle upward and backward. Occlusion of the meatus, especially by a plug of inspissated wax (§ 287), of course interferes with the hearing [and when it presses on the membrana tympani may give rise to severe vertigo].

FIG. 578.

The external auditory meatus and the tympanic cavity. M, osseous spaces in the temporal bone; Pc, cartilaginous part of the meatus; L, membranous union between both; F, auricular surface for the condyle of the lower jaw.

409. TYMPANIC MEMBRANE.—The **tympanic membrane**, which is tolerably laxly fixed in a special osseous cleft, with a thickened margin, is an elastic, unyielding, and almost non-extensible membrane of about 0.1 mm. in thickness, and with a superficial area of 50 square millimetres (Fig. 581). It is elliptical in form, its greater diameter being 9.5 to 10 mm., and its lesser 8 mm., and it is fixed in the floor of the external meatus obliquely, at an angle of 40°, being directed from above and outward, downward and inward. Both tympanic membranes converge anteriorly, so that if both were prolonged they would meet to form an angle of 130° to 135°. The oblique position enables a larger surface to be presented than would be obtained if it were stretched vertically, so that more sound waves can fall vertically upon it. The membrane is not stretched flat, but a little under its centre (umbilicus) it is drawn slightly inward by the handle of the malleus, which is attached to it; while the short process of the malleus slightly bulges out the membrane near its upper margin (Figs. 577, 584).

Structure.—The tympanic membrane consists of **three layers**: (1) The **membrana propria** is a fibrous membrane with **radial** fibres on its outer surface, and **circularly** arranged fibres on its inner aspect. (2) The surface directed toward the meatus is covered with a thin and semi-transparent part of the **cutis**. (3) The side toward the tympanum is covered with a delicate mucous membrane, with simple **squamous epithelium**. Numerous nerves and lymph vessels, as well as inner and outer blood vessels, occur in the membrane.

[The middle layer, or substantia propria, is fixed to a ring of bone, which is deficient above. It is filled up by a layer composed of the mucous and cutaneous layers, called the *membrana flaccida*, or Shrapnell's membrane.]

[**Examination.**—When examining the outer ear and membrana tympani, pull the auricle upward and backward. The membrana tympani is examined by means of an ear speculum (Fig. 582). The speculum is placed in the ear, and light is reflected into it by means of a concave mirror, perforated in the centre, and having a focal distance of four or five inches. It is convenient to have the mirror fixed to a band placed round the head, as in the case of the laryngoscopic reflector (Fig. 359). It is important to remember that the membrane is placed obliquely, so that the posterior and upper parts are nearer the surface. The membrane in health is grayish in color and transparent, so that the handle of the malleus is seen running from above downward and backward, while at the anterior and inferior part there is a cone of light with its apex directed inward.]

FIG. 579.

Tympanic membrane with the auditory ossicles (left) seen from within. *Ci*, incus; *Cm*, malleus; *Ch*, chorda tympani; *T*, pouch-like depression (after *Urbantschitsch*).

FIG. 581.

Tympanic membrane of a newborn child, seen from without, with the handle of the malleus visible on it. *At*, tympanic ring, with its anterior (*v*) and posterior (*h*) ends.

FIG. 580.



Tympanic membrane and the auditory ossicles (left) seen from within, *i. e.*, from the tympanic cavity. M, manubrium or handle of the malleus; T, insertion of the tensor tympani; *h*, head; *lF*, long process of the malleus; *a*, incus, with the short (K) and the long (*l*) process; S, plate of the stapes; A*x*, A*x*, is the common axis of rotation of the auditory ossicles; S, the pinion-wheel arrangement between the malleus and incus.

FIG. 582.

Ear specula, of various sizes.

Function.—The tympanic membrane catches up the sound waves which penetrate into the external meatus, and is set into vibration by them, the vibrations corresponding in number and amplitude to the vibrating movements of the air. Politzer connected the auditory ossicles fixed to the tympanic membrane of a duck with a recording apparatus, and could thus register the vibrations produced by sounding any particular tone. Owing to its small dimensions, the tympanic membrane can vibrate *in toto*, to and fro in the direction of the sound waves corresponding to the condensations and rarefactions of the vibrating air, and therefore executes *transverse vibrations*, for which it is specially adapted, owing to the relatively slight resistance.

Fundamental Note.—Stretched strings and membranes are generally only thrown into actual and considerable sympathetic vibration when they are affected by tones which correspond with their own fundamental tone, or whose number of vibrations is some multiple of the number of vibrations of the same, as the octave. When other tones act on them, they exhibit only inconsiderable sympathetic vibration. If a membrane be stretched over a funnel or cylinder, and if a nodule of sealing wax attached to a silk thread be made just to touch the centre of the membrane, then the sealing wax remains nearly at rest when tones or sounds

are made in the neighborhood; as soon, however, as the fundamental or proper tone of this arrangement is sounded, the nodule is propelled by the strong vibrations of the membrane.

If we apply this to the tympanic membrane, then it also should exhibit very great vibrations when its own fundamental note is sounded, but only slight vibrations when other tones are produced. This, however, would produce great inequality in the audible sounds. There is an arrangement of the membrane whereby this is prevented. (1) Great resistance is offered to the vibrations of the tympanic membrane, owing to its union with the auditory ossicles. These act as a **damping apparatus**, which provides, as in damped membranes generally, that the tympanic membrane shall not exhibit excessive sympathetic vibrations for its own fundamental note. But the damping also makes the sympathetic vibrations less for all the other tones. In this way, *all* vibrations of the tympanic membrane are modified; especially, however, is the excessive vibration diminished during the sounding of its fundamental tone. The membrane is at the same time rendered more capable of responding to the vibrations of different wave lengths. The damping also *prevents after vibrations*. (2) Corresponding to the small *mass* of the tympanic membrane, its sympathetic vibrations must also be small. Nevertheless, these slight elongations are quite sufficient to convey the sonorous movements to the most delicate end organs of the auditory nerve; in fact, there are arrangements in the tympanum which still further diminish the vibrations of the tympanic membrane.

As v. Helmholtz has shown, the strong sympathetic vibrations of the tympanic membrane are not completely set aside by this damping arrangement. The painful sensations produced by some tones are, perhaps, due to the sympathetic vibration of the membrana tympani. According to Kessel, certain parts of the membrane vibrate to certain tones; the shortest radial fibres at the upper part of the anterior and upper segment vibrate with the highest tones, the longest fibres at the posterior segment with the deepest tones. At the upper part of the posterior segment noises are transmitted.

According to Fick, the tympanic membrane, besides possessing the property of taking up all vibrations with nearly equal intensity, has also the properties of a resonance apparatus; *i. e.*, it causes a summation of the energy of successive vibrations. This is due to the funnel shape of the membrane, and to the radial, rigid insertion of the handle of the malleus.

Pathological.—Thickenings or inequalities of the tympanic membrane interfere with the acuteness of hearing, owing to the diminished capacity for vibration thereby produced. Holes in and loss of its substance act similarly. In extensive destruction, an artificial tympanum is placed in the external meatus, and its vibrations, to a certain extent, replace those of the lost membrane (*Toynbee*). [Fig. 583 shows an artificial tympanic membrane.]

410. AUDITORY OSSICLES AND THEIR MUSCLES.—The auditory ossicles have a **double function.**—(1) By means of the "chain" which they form, they transfer the vibrations of the tympanic membrane to the perilymph of the labyrinth. (2) They also afford points of attachment for the muscles of the middle ear, which can alter the *tension* of the membrana tympani, and the *pressure* on the lymph of the labyrinth.

FIG. 583.

Toynbee's artificial membrana tympani.

FIG. 584.



The auditory ossicles (right). *C.m*, head; *C*, neck; *Pbr*, short process; *Prl*, long process; *M*, handle of the malleus; *Ci*, body; *G*, articular surface; *h*, short, and *v*, long process of the incus; *O.S*, so-called lenticular ossicle; *C.s*, head; *a*, anterior, and *p*, posterior limb; *P*, plate of the stapes.

Mechanism.—The *form* and *position* of the ossicles are given in Figures 584 and 585. They form a jointed *chain* which connects the tympanic membrane, M, by means of the malleus, *h*, incus, *a*, and stapes, S, with the perilymph of the labyrinth.

The **mode of movement** of the ossicles is of special importance. The handle of the malleus is firmly united to the fibres of the tympanic membrane (Fig. 585, *n*). Besides this, the malleus is fixed by *ligaments* which prescribe the direction of its movements. Two ligaments—the lig. mallei anticum (passing from the processus Folianus) and the posticum (from a small crest on the neck)—together form a common axial band (*v. Helmholtz*), which acts in the direction from behind forward, *i. e.*, parallel to the surface of the tympanic membrane. The neck of the malleus lies between the insertions of both ligaments. The united ligament determines the "**axis of rotation**" of the movement of the malleus.

FIG. 585.

Tympanum and auditory ossicles (left) magnified. A.G., external meatus; M, membrana tympani, which is attached to the handle of the malleus, *n*, and near it the short process, *p*; *k*, head of the malleus; *a*, incus; *k*, its short process with its ligament; *l*, long process; *s*, Sylvian ossicle; S, stapes; A*x*, A*x*, is the axis of rotation of the ossicles, it is shown in perspective, and must be imagined to penetrate the plane of the paper; *t*, line of traction of the tensor tympani. The other arrows indicate the movement of the ossicles when the tensor contracts.

When the handle of the malleus is drawn *inward*, of course its head moves in the opposite direction, or outward. The *incus*, *a*, is only partially fixed by a ligament, which attaches its short process to the wall of the tympanic cavity, in front of the entrance to the mastoid cells, *k*. The not very tense articulation joining it to the head of the malleus, *k*, which lies with its saddle-shaped articular surface in the hollow of the incus, is important. The lower margin of the incus (Fig. 584, S) acts like a tooth of a cog wheel. Thus, when the handle of the malleus moves inward to the tympanic cavity, the incus, and its long process, *b*, which is parallel to the handle of the malleus, also pass inward. The incus forms almost a right angle with the stapes, S, through the intervention of the Sylvian ossicle, *s*. If, however, as by condensation of the air in the tympanum, the membrana tympani and the handle of the malleus move *outward*, the long process of the incus does not make a similar movement, as the malleus moves away from this margin of the incus. Hence, the stapes is not liable to be torn from its socket. The malleus and incus form an **angular lever**, which moves round a common axis (Fig. 581 and Fig. 585, A*x*, A*x*). In the *inward* movement, the malleus follows the incus, as if both formed one piece. The *common axis* (Fig. 580) is not, however, the axial ligament of the malleus, but it is formed *anteriorly* by the processus Folianus, *lF*, directed forward, and *posteriorly* by the short process of the incus directed backward. The rotation of both ossicles around this axis occurs in a plane vertical to the plane of the membrana tympani. During the rotation, of course the parts above this axis (head of the malleus and upper part of the body of the incus) take a direction opposite to the parts lying below it (the handle of the malleus and the long process of the incus), as is indicated in Fig. 585 by the direction of the arrows. The movement of the handle of the malleus must follow that of the membrana tympani, and *vice versâ*, while the movement of the stapes is connected with the movement of the long process of the incus. As the long process of the incus is only two-thirds of the length of the

handle of the malleus (Figs. 577, 581, 585), of course the *excursion* of the tip of the former, and with it of the stapes, must be correspondingly *less* than the movement of the tip of the handle of the malleus; while, on the other hand, the *force* of the movement of the tip of the handle of the malleus, corresponding to the diminution of the excursion, will be *increased*.

Mode of Vibration.—Thus, the movement of the membrana tympani inward causes a less extensive but a *more powerful* movement of the foot of the stapes against the perilymph of the labyrinth. v. Helmholtz and Politzer calculated the extent of the movement to be 0.07 mm. The mode in which the vibrations of the membrana tympani are conveyed to the lymph of the labyrinth, through the chain of ossicles, is quite analogous to the mechanism of these parts already described. Long delicate glass threads have been fixed to these ossicles, and their movements were thus graphically recorded on a smoked surface (*Politzer, Hensen*). Or, strongly refractive particles are fixed to the ossicles, while the beam of light reflected from them can be examined by means of a microscope (*Buck, v. Helmholtz*). All the experiments showed that the transference of the sound waves is accomplished by means of the mechanism of the **angular lever**, composed of the auditory ossicles already described. As the vibrations of the membrana tympani are conveyed to the handle of the malleus, they are weakened to about one-fourth of their original strength (*Politzer*). [The membrana tympani is many times (30) larger than the fenestra ovalis, and the relation in size might be represented by a funnel. The arm of the malleal end of the lever where the power acts is 9½ mm. long, while the short or stapedial arm is 6½ mm., so that the latter moves less than the former, but what is lost in extent is gained in force.]

[**Methods.**—Politzer attached small, very light levers to each of the ossicles, and inscribed their movements on a revolving cylinder. An organ pipe was sounded, and when the levers were of the same length, the malleus made the greatest excursion and the stapes the least. Buck attached starch grains to the ossicles, illuminated them, and observed the movements of the refractive starch granules by means of a microscope provided with a micrometer.]

[The **ossicles** move *en masse*, and not in the way of propagating molecular vibrations.] As the excursions of the ossicles during sonorous vibrations are, however, only nominal, there is practically no change in the position of the joints with each vibration. The latter will only occur when extensive movements take place by means of the muscles.

FIG. 586.

Tensor tympani—the Eustachian tube (left).

The **muscles** of the auditory ossicles alter the position and tension of the membrana tympani, as well as the pressure of the lymph of the labyrinth. The **tensor tympani**, which lies in an osseous groove above the Eustachian tube, has its tendon deflected round an osseous projection [processus cochleariformis], which lies external to it, almost at right angles to the groove above it, and is inserted immediately above the axes of rotation of the malleus (Fig. 580, M). When the muscle contracts in the direction of the arrow, *t*, then the handle of the malleus (*n*) pulls the membrana tympani (M) inward and tightens it (Fig. 585). This also causes a movement of the incus and stapes (S) which must be pressed more deeply into the fenestra ovalis as already described. When the muscle relaxes, then, owing to the *elasticity* of the rotated axial ligament and the tense membrana tympani itself, the position of equilibrium is again restored. The **motor nerve** of this muscle arises from the trigeminus, and passes through the *otic ganglion* (p. 647). C. Ludwig and Politzer observed that stimulation of the fifth nerve within the cranium [dog] caused the above mentioned movement.

Use of the Tension.—The tension of the membrana tympani caused by the tensor tympani has a double function (*Joh. Müller*)—1. The tense membrane offers very great resistance to sympathetic vibrations when the sound waves are very intense, as it is a physical fact that stretched membranes are more difficult to throw into sympathetic vibrations the tenser they are. Thus, the tension so far protects the auditory organ, as it prevents too intense vibrations applied to the membrana tympani from reaching the terminations of the nerves. 2. The tension of the membrana tympani must vary according to the degree of contraction of the tensor. Thus, the membrana for the time being has a different fundamental tone, and is thereby capable of vibrating to the correspondingly higher tone, it, as it were, being in a certain sense accommodated for.

Comparison with Iris.—The membrana tympani has been compared with the iris. Both membranes prevent by contraction—narrowing of the pupil and tension of the membrana tympani—the too intense action of the specific stimulus from causing too great stimulation, and both *adapt* the sensory apparatus for the action of moderate or weak stimuli. This movement in both membranes is brought about *reflexly*, in the ear through the N. acusticus, which causes a reflex stimulation of the motor fibres for the tensor tympani.

Effect of Tension.—That increased tension of the membrana tympani renders it less sensitive to sound waves is easily proved, thus: Close the mouth and nose, and make either a forced expiration, so that the air is forced into the Eustachian tube, which bulges out the membrana tympani, or inspire forcibly, whereby the air in the tympanum is diminished, so that the membrana bulges inward. In both cases hearing is interfered with as long as the increased tension lasts. If a funnel with a small lateral opening, and whose wide end is covered by a membrane, be placed in the external meatus, hearing becomes less distinct when the membrane is stretched (*Joh. Müller*). If air be blown into the external auditory meatus, both tensores tympani contract, and in consequence of this the hearing of the other ear is temporarily affected (*Gellé*).

Normally, the tensor tympani is excited *reflexly*. The muscle is not directly and by itself subject to the control of the will. According to L. Fick, the following phenomenon is due to an "associated movement" of the tensor: When he pressed his jaws firmly against each other, he heard in his ear a piping, singing tone, while a capillary tube, which was fixed air-tight into the meatus, had a drop of water which was in it rapidly drawn inward. During this experiment, a person with normal hearing hears all musical tones as if they were louder, while all the highest non-musical tones are enfeebled (*Lucae*). When *yawning*, v. Helmholtz and Politzer found that hearing was enfeebled for certain tones.

Contraction of the Tensor.—Hensen showed that the contraction of the tensor tympani during hearing is not a continued contraction, but what might be termed a "twitch." A twitch takes place at the beginning of the act of hearing, which favors the perception of the sound, as the membrana tympani thus set in motion vibrates more readily to higher tones than when it is at rest. On exposing the tympanum in cats and dogs, it was found that this contraction or twitch occurs only at the beginning of the sound, and that it soon ceases, although the sound may continue.

FIG. ~~578~~ 587

Right stapedius muscle.

Action of the Stapedius.—The muscle arises within the eminentia pyramidalis, and is inserted into the head of the stapes and Sylvian ossicle (Fig. 585); when it draws upon the head of the stapes, as indicated in Fig. 577, by the small curved arrow, it must place the bone obliquely, whereby the posterior end of the plate of the stapes is pressed somewhat deeper *inward* into the fenestra ovalis, while the anterior is, as it were, displaced somewhat *outward*. The stapes is thereby more fixed, as the fibrous mass [annular ligament] which surrounds the fenestra ovalis and keeps the stapes in its place becomes more tense. The activity of this muscle, therefore, prevents too intense shocks, which may be communicated from the incus to the stapes, from being conveyed to the perilymph. It is supplied by the **facial nerve** (§ 349, 3).

The stapedius in many persons executes an *associated* movement, when the eyelids are forcibly closed (§ 349). Some persons can cause it to contract *reflexly* by scratching the skin in front of the meatus, or by gently stroking the outer margin of the orbit (*Henle*). It seems to be excited reflexly in many diseases of the ear when the tympanum is being syringed.

Other Views.—According to Lucae, when the stapes is displaced obliquely, its head forces the

long process of the incus, and also the membrana tympani, *outward*, so that it is regarded as an *antagonist* of the tensor tympani. Politzer observed that the pressure within the labyrinth fell when he stimulated the muscle. According to Toynbee, the stapedius acts as a lever and moves the stapes slightly out of the fenestra ovalis, thus making it more free to move, so that it is more capable of vibrating. Henle supposes that the stapedius is more concerned in *fixing* than in moving the stapes, and that it comes into action when there is danger of too great movement being communicated to the stapes from the incus. Landois agrees with this opinion, and compares the stapedius with the orbicularis palpebrarum, both being protective muscles.

Pathological.—Immobility of the auditory ossicles, either by adhesions or anchyloses, causing diminished vibrations, interferes with hearing; while the same result occurs when the stapes is firmly anchylosed into the fenestra ovalis. The tendon of the tensor tympani has been divided in cases of contracture of the muscles. For paralysis of the tensor, see p. 648, and for the stapedius, p. 652.

411. **EUSTACHIAN TUBE—TYMPANUM.**—The **Eustachian tube** [4 centimetres in length, 1⅝ in.] is the **ventilating tube** of the tympanic cavity. It keeps the tension of the air within the tympanum the same as that within the pharynx and outer air (Figs. 577, 586). Only when the tension of the air is the same outside and inside the tympanum, is the normal vibration of the membrana tympani possible. The tube is generally *closed*, as the surfaces of the mucous membrane lining it come into apposition. During **swallowing**, however, the tube is opened, owing to the traction of the fibres of the tensor veli palatini [spheno-salpingo-staphylinus sive abductor tubae (*v. Tröltsch*), sive dilator tubae (*Rüdinger*)] inserted into the membrano-cartilaginous part of the tube (*Toynbee, Politzer*). (Compare § 139, 2.) When the tube is closed, the vibrations of the membrana tympani are transferred in a more undiminished condition to the auditory ossicles than when it is open, whereby part of the vibrating air is forced through the tube (*Mach and Kessel*). If, however, the tympanic cavity is closed *permanently*, the air within it becomes so rarefied (§ 139) that the membrana tympani, owing to the abnormally low tension, becomes drawn inward, thus causing difficulty of hearing. As the tube is lined by ciliated epithelium it carries outward to the pharynx the secretions of the tympanum (p. 501).

Noise in the Tube.—A sharp hissing noise is heard in the tube during swallowing, when we swallow slowly and at the same time contract the tensor tympani, due to the separation of the adhesive surfaces of its lining membrane. Another person may hear this noise by using a stethoscope or his ear.

In Valsalva's experiment (§ 60), as soon as the pressure of the air reaches 10 to 40 mm. Hg, air enters the tube. The sound is heard first, and then we feel the increased tension of the tympanic membrane, owing to the entrance of air into the tympanum. During forced inspiration, when the nose and mouth are closed, air is sucked out, while the tympanum is ultimately drawn inward.

The M. levator veli palatini, as it passes under the base of the opening of the tube into the pharynx, forms the *levator eminence* or cushion (Fig. 354, W). Hence, when this muscle contracts and its belly thickens, as at the commencement of the act of deglutition and during phonation, the lower wall of the pharyngeal opening is raised, and the opening thereby narrowed (*Lucae*). The *contraction* of the tensor, occurring during the latter part of the act of deglutition, dilates the tube.

Other Views.—According to Rüdinger, the tube is always open, although only by a very narrow passage in the upper part of the canal, while the canal is dilated during swallowing. According to Cleland, the tube is generally open, and is closed during swallowing.

[**Practical Importance.**—The tympanic cavity forms an osseous box, and therefore a protective organ for the auditory ossicles and their muscles, while the increased air space obtained by its communication with the mastoid cells permits free vibration of the membrana tympani. The six sides of the tympanum have important practical relations. It is about half an inch in height, and one or two lines in breadth, *i. e.*, from without inward. Its *roof* is separated from the cavity of the brain by a very thin piece of bone, which is sometimes defective, so that encephalitis may follow an abscess of the middle ear. The *outer* wall is formed by the membrana tympani, while on the *inner* wall are the fenestra ovalis and rotunda, the ridge of the aqueductus Fallopii, the promontory, and the pyramid. The *floor* consists of a thin plate of bone, which roofs in the jugular fossa and separates it from the jugular vein. Fractures of the base of the skull may rupture the carotid artery or internal jugular vein; hence, hemorrhage from the ears is a bad symptom

in these cases. Caries of the ear may extend to other organs. The *anterior* wall is in close relation with the carotid artery, while the *posterior* communicates with the mastoid cells, so that fluids from the middle ear sometimes escape through the mastoid cells.]

That the air in the tympanum can communicate its vibrations to the membrane of the fenestra rotunda is true (p. 848, 3), but *normally* this is so slight, when compared with the conduction through the auditory ossicles, that it scarcely need be taken into account.

Structure.—The tube and tympanum are lined by common mucous membrane, covered by ciliated epithelium, while the membrana is lined by a layer of squamous epithelium. Mucous glands were found by Tröltsch and Wendt in the mucous membrane. [The epithelium covering the ossicles and tensor tympani is not ciliated.]

FIG. 588.

Eustachian Catheter.

Pathological.—The tube is often occluded, owing to chronic catarrh and narrowing from cicatrices, hypertrophy of the mucous membrane, or the presence of tumors. The deafness thereby produced may often be cured by *catheterizing* the tube from the nose (Fig. 588). Effusions into or suppuration within the tympanum of course paralyze the sound-conducting mechanism, while inflammation often causes subsequent affections of the plexus tympanicus. If the temporal bone be destroyed by progressive caries within the tympanum, inflammation of the neighboring cerebral structures may occur and cause death.

FIG. 589.

Politzer's Ear Bag.

[**Methods.**—Not unfrequently the aurist is called upon to dilate the Eustachian tube, which in certain cases requires the use of a **Eustachian catheter** introduced into the tube along the floor of the nose (Fig. 588). At other times he requires to fill the tympanic cavity with air, which is easily done by means of a **Politzer's bag** (Fig. 589). The nozzle is introduced into one nostril, while the other nostril is closed, and the patient is directed to swallow, while at the same moment the surgeon compresses the bag, and the patient's mouth being closed, air is forced through the open Eustachian tube into the middle ear. Sometimes a small curved narrow manometer, containing a drop of colored water, is placed in the outer ear (*Politzer*). Normally, when the patient swallows, the fluid ought to move in the tube.]

412. CONDUCTION OF SOUND IN THE LABYRINTH.—The vibrations of the foot of the stapes in the fenestra ovalis give rise to waves in the perilymph within the inner ear or labyrinth. These waves are so-called "*flexion waves*," *i. e.*, the perilymph moves in mass before the impulse of the base of the stapes. This is only possible from the existence of a *yielding* membrane—that filling the fenestra rotunda, and sometimes called the *membrana secundaria*, which during rest bulges inward to the scala tympani, and can be bulged outward toward the tympanic cavity by the impulse communicated to it by the movement of the perilymph (Fig. 577, *r*). The flexion waves must correspond in number and intensity to the vibrations of the auditory ossicles, and must also excite the free terminations of the auditory nerve, which float free in the endolymph.

FIG. 590.

External appearance of the labyrinth, fenestra ovalis, cochlea to the left and (*f*) the upper, (*h*) horizontal, and (*s*) posterior semicircular canal (left).

As the endolymph of the saccule and utricle lying in the vestibule receives the first impulse, and as these communicate anteriorly with the cochlea, and posteriorly with the semicircular canals, consequently the motion of the perilymph must be propagated through these canals. To **reach the cochlea**, the movement passes

from the *sacculo* (lying in the fovea hemispherica) along the scala vestibuli to the helicotrema, where it passes into the scala tympani, where it reaches the membrane of the fenestra rotunda, and causes it to bulge outward. From the *utricle* (lying in the fovea hemielliptica), in a similar manner the movement is propagated through the *semicircular canals*. Politzer observed that the endolymph in the superior semicircular canal rose when he caused contraction of the tensor tympani by stimulating the trigeminus, just as the base of the stapes must be forced against the perilymph with every vibration of the membrana tympani.

[**Practical.**—It is well to view the organ of hearing as consisting of two mechanisms:—

1. The sound-conducting apparatus.
2. The sound-perceiving apparatus.

The **former** includes the *outer* ear, with its auricle and external meatus; the *middle* ear and the parts which bound it, or open into it. The **latter** consists of the *inner* ear with the expansion of the auditory nerve in the labyrinth, the nerve itself, and the sound-perceiving and interpreting centre or centres in the brain (p. 753).]

[**Testing the Sound conduction.**—In any case of deafness, it is essential to estimate the degree of deafness by the methods stated at p. 848, and it is well to do so both for such sounds as those of a watch and conversation. We have next to determine whether the *sound-conducting* or the *sound-perceiving* apparatus is affected. If a person is deaf to sounds transmitted through the air, on applying a sounding tuning fork to the middle line of the head or teeth, if it be heard distinctly, then the sound-perceiving apparatus is intact, and we have to look for the cause of deafness in the outer or middle ear. In a healthy person, the sound of the tuning fork is heard of equal intensity in both ears. In this case the sound is conducted directly to the labyrinth by the cranial bones. In cases of disease of the sound-conducting mechanism, the sound of the tuning fork is heard loudest in the *deafer* ear. Ed. Weber pointed out that, if one ear be stopped and a vibrating tuning fork placed on the head, the sound is referred to the plugged ear, where it is heard loudest. It is assumed that when the ear is plugged, the sound-waves transmitted by the cranial bones are prevented from escaping (*Mach*). If, on the contrary, the sound be heard loudest in the good ear, then in all probability there is some affection of the sound-perceiving apparatus or labyrinth, although there are exceptions to this statement, especially in elderly people. Another plan is to connect two telephones with an induction machine, provided with a vibrating Neef's hammer. The sounds of the vibrations of the latter are reproduced in the telephones, and if they be placed to the ears, then the healthy ears hear only *one* sound, which is referred to the middle line, and usually to the back of the head. In diseased conditions this is altered—it is referred to one side or the other.]

413. LABYRINTH AND AUDITORY NERVE.—Scheme.—The **vestibule** (Fig. 591, III) contains two separate sacs; one of them, the **saccule,** *s* (round sac or S. hemisphæricus), communicates with the **ductus cochlearis,** C*c*, of the cochlea: the other, the **utricle,** U (elliptical sac, or sacculus hemiellipticus), communicates with the semicircular canals, C*s*, C*s*.

The **cochlea** consists of 2½ turns of a tube disposed round a central column or **modiolus.** The tube is divided into two compartments by a horizontal septum, partly osseous and partly membranous, the **lamina spiralis ossea** and **membranacea** (Fig. 595; Fig. 591, I). The **lower compartment** is the **scala tympani,** and is separated from the cavity of the tympanum by the membrane of the fenestra rotunda.

The **upper compartment** is the **scala vestibuli,** which communicates with the vestibule of the labyrinth (Fig. 591, I). These two compartments communicate directly by a small opening at the apex of the cochlea, a sickle-shaped edge ["hamulus"] of the lamina spiralis bounding the **helicotrema** (Fig. 577). The scala vestibuli is divided by **Reissner's membrane** (Fig. 591, I), which arises near the outer part of the lamina spiralis ossea, and runs obliquely outward to the wall of the cochlea so as to cut off a small triangular canal, the **ductus** or **canalis cochlearis,** or **scala media,** C*c*, whose floor is formed for the most part by the lamina spiralis membranacea, and on which the end organ of the auditory nerve—**Corti's organ**—is placed. The lower end of the canalis cochlearis

is blind, III, and divided toward the saccule, with which it communicates by means of the small **canalis reuniens**, *Cr* (*Hensen*). The **utricle** (Fig. 591, III, U) communicates with the three semicircular canals, *Cs*, *Cs*—each by means of an ampulla, within which lie the terminations of the ampullary nerves, but as the posterior and the superior canals unite, there is only one common ampulla for them. The membranous semicircular canals lie within the osseous canals, perilymph

FIG. 591.



I, transverse section of a turn of the cochlea; II, A, ampulla of a semicircular canal with the crista acustica; *a*, *p*, auditory cells; *p*, provided with a fine hair; T, otoliths; III, scheme of the human labyrinth; IV, scheme of a bird's labyrinth; V, scheme of a fish's labyrinth.

lying between the two. **Perilymph** also fills the scala vestibuli and tympani, so that all the spaces within the labyrinth are filled by fluid, while the spaces themselves are lined by short cylindrical epithelium.

The system of spaces, filled by **endolymph**, is the only part containing the nervous end organs for hearing. All these spaces communicate with each other; the semicircular canals directly with

FIG. 592.

FIG. 593.



The interior of the right labyrinth with its membranous canals and nerves.

In Fig. 592, the outer wall of the bony labyrinth is removed to show the membranous parts within—1, commencement of the spiral tube of the cochlea; 2, posterior semicircular canal, partly opened; 3, horizontal; 4, superior canal; 5, utricle; 6, saccule; 7, lamina spiralis; 7', scala tympani; 8, ampulla of the superior membranous canal; 9, of the horizontal; 10, of the posterior canal.

Fig. 593 shows the membranous labyrinth and nerves detached—1, facial nerve in the internal auditory meatus; 2, anterior division of the auditory nerve giving branches to 5, 8, and 9, the utricle and the ampullæ of the superior and horizontal canals; 3, posterior division of the auditory nerve, giving branches to the saccule, 6, and posterior ampulla, 10, and cochlea, 4; 7, united part of the posterior and superior canals; 11, posterior extremity of the horizontal canal.

the utricle, the ductus cochlearis with the saccule through the canalis reuniens; and lastly, the saccule and utricle through the "**saccus endolymphaticus**," which springs by an isolated limb from each sac; the limbs then unite, as in the letter **Y**, and pass through the osseous aqueductus vestibuli to end blindly in the dura mater of the brain (Fig. III, R—*Böttcher*, *Retzius*). The aqueductus cochleæ is another narrow passage, which begins in the scala tympani, immediately in front of the fenestra

rotunda, and opens close to the fossa jugularis. It forms a direct means of communication between the perilymph of the cochlea and the subarachnoid space.

Semicircular Canals and Vestibular Sacs.—The membranous semicircular canals do not fill the corresponding osseous canals completely, but are separated from them by a pretty wide space, which is filled with perilymph (Fig. 592). At the concave margin they are fixed by connective tissue to the osseous walls. The ampullæ, however, completely fill the corresponding osseous dilatations. The canals and ampullæ consist externally of an outer, vascular, connective-tissue layer, on which there rests a well-marked hyaline layer, bearing a single layer of flattened epithelium.

Crista Acustica.—The vestibular branch of the auditory nerve sends a branch to each ampulla and to the saccule and utricle (Fig. 593). In the **ampullæ** (Fig. 591, II, A), the nerve (*c*) terminates in connection with the **crista acustica**, which is a yellow elevation projecting into the equator of the ampulla. The medullated nerve fibres, *n*, form a plexus in the connective-tissue layer, lose their myelin as they pass to the hyaline basement membrane, and each ends in a cell provided with a rigid hair (*o*, *p*) 90 μ in length, so that the crista is largely covered with these **hair cells**, but between them are **supporting cells** like cylindrical epithelium (*a*), and not unfrequently containing granules of yellow pigment. The hairs or "**auditory hairs**" (*M. Schultze*) are composed of many fine fibres (*Retzius*). An excessively fine membrane (**membrana tectoria**) covers the hairs (*Pritchard*, *Lang*).

FIG. 594.

Vertical section of the macula acustica of a rabbit.

Maculæ Acusticæ.—The nerve terminations in the maculæ acusticæ of the **saccule** and **utricle** are exactly the same as in the ampullæ, only the free surface of their membrana tectoria is sprinkled with small white chalk-like crystals or **otoliths** (II, T), composed of calcic carbonate, which are sometimes amorphous and partly in the form of arragonite, lying fixed in the viscid endolymph. The non-medullated axis cylinders of the saccular nerves enter directly into the substance of the hair cells. The terminations of the nerves have been investigated, chiefly in fishes, in the rays.

[Fig. 594 is a vertical section of a macula acustica of the rabbit. The medullated nerves (*n*) lose their myelin at the external limiting membrane, become non-medullated, pierce this membrane, and form a basal plexus (*pb*) between (*i*) the epithelial cells, and finally terminate in the sensory ciliated cells (*r*). The epithelium itself consists of basal cells (*cb*), fusiform or supporting cells (*f*), and the ciliated neuro-epithelium (*r*), each cell being provided with a cilium, which perforates the external limiting membrane (*a*). There is thus a remarkable likeness to the olfactory epithelium.]

Cochlea.—The terminations of the cochlear branch of the auditory nerve lie in connection with **Corti's organ**, which is placed in the canalis or ductus cochlearis (Fig. 591, I, *Cc*, and III, *Cc*, and Fig. 595), the small triangular chamber [or scala media,] cut off from the scala vestibuli by the membrane of Reissner. Corti's organ is placed on the lamina spiralis membranacea, and consists of a *supporting apparatus* composed of the so-called **Corti's arches**, each of which consists of two **Corti's rods** (*z*, *y*), which lie upon each other like the beams of a house. But every two rods do not form an arch, as there are always three inner to two outer rods (*Claudius*). There are about 4500 outer rods (*Waldeyer*).

The ductus cochlearis becomes larger toward the apex of the cochlea, and the rods also become longer; the **inner** ones are 30 μ long in the first turn, and 34 μ in the upper, the **outer** rods 47 μ and 69 μ respectively. The span of the arches also increases (*Hensen*). [The arches leave a triangular tunnel beneath them.] The proper end organs of the cochlear nerve are the cylindrical "**hair cells**" (*Kölliker*) previously observed by Corti, which are from 16,400 to 20,000 in number (*Hensen*, *Waldeyer*). There is *one* row of **inner cells** (*i*) which rests on a layer of small granular cells (K) (*Böttcher*, *Waldeyer*); the **outer cells** (*a*, *a*) number 12,000 in man (*Retzius*), and rest upon the basement membrane, being disposed in three or even four rows. Between the outer hair cells there are other cellular structures, which are either regarded as special cells (**Deiter's cells**), or are regarded merely as processes of the hair cells (*Lavdowsky*). [The cochlear branch of the auditory nerve enters the modiolus, and runs upward in the osseous channels there provided for it, and as it does so gives branches to the lamina spiralis, where they run between the osseous plates which form the lamina.] The fibres (N) come out of the lamina spiralis after traversing the **ganglionic cells** in their course (Figs. 591, 595, I, G), and end by fine varicose fibrils in the hair cells (Fig. 595) (*Waldeyer*, *Gottstein*, *Lavdowsky*, *Retzius*).

Membrana Reticularis.—Corti's rods and the hair cells are covered by a special membrane (*o*), the **membrana reticularis** of Kölliker. The upper ends of the hair cells, however, project through holes in this membrane, which consists of a kind of cement substance holding these parts together (*Lavdowsky*). [Springing from the outer end of the lamina spiralis, or crista spiralis, is the **membrana tectoria**, sometimes called the membrane of Corti. It is a well-defined structure, often

fibrillated in appearance, and extends outward over the organ of Corti.] Waldeyer regards it as a damping apparatus for this organ (Fig. 595, Mb. Corti).

[**Basilar Membrane.**—Its breadth increases from the base to the apex of the cochlea. This fact is important in connection with the theory of the perception of tone. It is supposed that high notes are appreciated by structures in connection with the former, and low notes by the upper parts of the basilar membrane. In one case, recorded by Moos and Steinbrugge, a patient heard low notes only in the right ear, and after death it was found that the auditory nerve in the first turn of the cochlea was atrophied.]

Intra-Labyrinthine Pressure.—The lymph within the labyrinth is under a certain pressure. Every diminution of the pressure of the air in the tympanum is accompanied by a corresponding diminution of the intra-labyrinthine pressure, while conversely every increase of pressure is accompanied by an increase of the lymph pressure (*F. Bezold*).

The **perilymph** of the inner ear flows away chiefly through the aqueductus cochleæ, in the circumference of the foramen jugulare, into the peripheral lymphatic system, which also takes up the cerebro-spinal fluid of the subarachnoid space,

FIG. 595.



Scheme of the ductus cochlearis and the organ of Corti. N, cochlear nerve: K, inner, and P, outer hair cells: *n*, nerve fibrils terminating in P; *a*, *a*, supporting cells; *d*, cells in the sulcus spiralis; *z*, inner rod of Corti; Mb, Corti, membrane of Corti, or the membrana tectoria; *o*, the membrana reticularis; H, G, cells filling up the space near the outer wall.

while a small part drains away to the sub-dural space through the internal auditory meatus. The **endolymph** flows through the arachnoid sheath of the N. acusticus into the subarachnoid space (*C. Hasse*).

414. AUDITORY PERCEPTIONS.—Every normal ear is able to distinguish **musical tones** and **noises.** Physical experiments prove that **tones** are produced when a vibrating elastic body executes **periodic** movements, *i. e.*, when the sounding body executes the same movement in equal intervals of time, as the vibrations of a string which has been plucked. A **noise** is produced by **non-periodic** movements, *i. e.*, when the sounding body executes unequal movements in equal intervals of time. [The non-periodic movements clash together on the ear, and produce dissonance, as when we strike the keyboard of a piano at random.] This is readily proved by means of the *siren*. Suppose that there are forty holes in the rotatory disk of this instrument, placed at exactly the same distance from each other, on rotating the disk and directing a current of air against it, obviously with

every rotation the air will be rarefied and condensed exactly forty times. Every two condensations and rarefactions are separated from each other by an *equal* interval of time. This arrangement yields a characteristic *musical tone* or note. If a similar disk with holes perforated in it at *unequal* distances be used, on air being forced against it, a whirring non-musical *noise* is produced, because the movements of the sounding body (the condensations and rarefactions of the air) are *non-periodic*. [The double siren of v. Helmholtz is an improved instrument for showing the same facts.]

The **normal ear** also distinguishes in **every tone three distinct factors**:—[(1) Intensity or force; (2) Pitch; (3) Quality, *timbre* or "*klang*."]

1. The **intensity** of a tone depends upon the greater or lesser **amplitude** of the vibrations of the sounding body. It is well known that a vibrating string emits a feebler sound when its excursions are smaller. (The intensity of a sound corresponds to the *degree of illumination or brightness* in the case of the eye.)

2. The **pitch** depends upon the **number** of vibrations which occur in a given time [or the length of time occupied by a single vibration]. This is proved by means of the siren. If the rotating disk have a series of forty holes at equal intervals, and another series of eighty equidistant from each other, on blowing a stream of air against the rotating disk we hear two sounds of unequal pitch, one being the octave of the other. (The perception of pitch corresponds to the *sensation of color* in the case of the eye.)

3. The **quality** or **timbre** ("*Klangfarbe*") is peculiar to different sonorous bodies. [It is the peculiarity of a musical tone by which we are enabled to distinguish it as coming from a particular instrument, or from the human voice. Thus, the same note struck on a piano and sounded on a violin differ in quality or *timbre*.] It depends upon the *peculiar form of the vibration*, or the form of the wave of the sonorous body. (There is no analogous sensation in the case of light.)

I. Perception of Pitch.—By means of the organ of hearing, we can determine that different tones have a different pitch. In the so-called musical scale, or gamut, this difference is very marked to a normal ear. But in the scale there are again four tones, which, when they are sounded together, cause in a normal ear the sensation of an agreeable sound, which once heard can readily be reproduced. This is the tone of the so-called **accord**, Triad, or Common Chord, consisting of the 1st, 3d, and 5th tones of the scale, to which the 8th tone or octave is added. We have next to determine the pitch of the tones of the chord, and then that of the other tones of the scale. The siren is used for the fundamental experiment, from which the others can easily be calculated. Four concentric circles are drawn upon the rotatory disk of the siren; the inner circle contains 40 holes, the second 50, the third 60, and the outer 80—all the holes being at equal distances from each other. If the disk be rotated, and air forced against each series of holes *in turn*, we distinguish successively the four tones of the *accord* (major chord with its octave); when all the four series are blown upon *simultaneously*, we hear in complete purity the major chord itself. The *relative number of the holes* in the four series indicates in the simplest manner the relative pitch of the tones of the major chord. While one revolution of the disk is necessary to produce the *fundamental ground tone* (key note or tonic) with 40 condensations and rarefactions of the air—in order to produce the **octave**, we must have double the number of condensations and rarefactions during one revolution in the same time. Thus, the relation of the number of vibrations of the Ground tone or Tonic to the Octave next above it, is 1 : 2. In the second series we have 50 holes, which causes the pitch of the **third**; hence, the relation of the Ground tone to the Third in this case is 40 : 50, or $1 : 1\frac{1}{4} = \frac{5}{4}$, *i. e.*, for every vibration of the Ground tone there are $\frac{5}{4}$ vibrations in the Third. In the third series are 60 holes, which, when blown upon, yield the **fifth**; hence, the ratio of the Ground tone to the Fifth in our disk is 40 : 60, or $1 : 1\frac{1}{2} = \frac{3}{2}$. In the same way we can estimate the pitch of the Fourth tone, and we find that the number of vibrations of the First, Third, Fifth, and Octave are to each other as $1 : \frac{5}{4} : \frac{3}{2} : 2$.

The **minor chord** is quite as characteristic to a normal ear as the major. It is distinguished essentially from the latter by its Third being half a tone lower. We can easily imitate it by the siren, as the *Minor Third* consists of a number of vibrations which stand to the Ground tone as 6 : 5, *i. e.*, if 5 vibrations occur in a given time in the Ground tone, then 6 occur in the Minor Third; its vibration number, therefore, is $\frac{6}{5}$.

From these relations of the Major and Minor common chords, we may calculate the relative tones in the scale, and we must remember that the Octave of a tone always yields the fullest and most complete harmony. It is evident that as the Major Third, and Minor Third, and the Fifth harmonize

with the fundamental Ground tone or key note, they must also harmonize with the Octave of the key note. We obtain from the Major Third with the number of vibrations $\frac{5}{4}$, the Minor Sixth $\frac{8}{5}$, from the Minor Third with $\frac{6}{5}$, the Major Sixth $= (\frac{6}{10} =)\ \frac{3}{5}$; from the Fifth with $\frac{3}{2}$, the Fourth $= \frac{4}{3}$. These relations are known as the "Inversions of the intervals." These relations of the tones are, collectively, the consonant intervals of the scale. The dissonant stages, or discords, of the scale can be obtained as follows: Suppose that we have the Ground tone or key note C, with the number of vibrations $= 1$, the Third E $= \frac{5}{4}$, the Fifth G $= \frac{3}{2}$, and the Octave $= 2$, we then derive from the Fifth or Dominant G a Major chord; this is G, B, D'. The relative number of vibrations of these 3 tones is the same as in the Major chord of C, C, E, G. Hence, the number of vibrations of G : B is as C : E. When we substitute the values we obtain $\frac{3}{2} : B = 1 : \frac{5}{4}$, *i. e.*, $B = \frac{15}{8}$. But D' : B = G : E; so that D : $\frac{15}{8} = \frac{3}{2} : \frac{5}{4}$, *i. e.*, D' $= \frac{15}{8}$, or an octave lower, we have D $= \frac{9}{8}$. Deduce from F (subdominant) a Major chord, F, A, C'. The relation of A : C' = E : G, or A : 2 $= \frac{5}{4} : \frac{3}{2}$, *i. e.*, A $= \frac{5}{3}$. Lastly, F : A = C : E, or F : $\frac{5}{3} = 1 : \frac{5}{4}$, *i. e.*, F $= \frac{4}{3}$. So that all the tones of the scale have the following number of vibrations: I, C $= 1$; II, D $= \frac{9}{8}$; III, E $= \frac{5}{4}$; IV, F $= \frac{4}{3}$; V, G $= \frac{3}{2}$; VI, A $= \frac{5}{3}$; VII, B $= \frac{15}{8}$; VIII, C $= 2$.

Conventional Estimate of Pitch.—Conventionally, the pitch or concert pitch of the note, *a*, is taken at 440 vibrations in the second (*Scheibler*, 1834), although in France it is taken at 435 vibrations per second. From this we can estimate the absolute number of vibrations for the tones of the scale: C = 33, D = 37.125, E = 41.25, F = 44, G = 49.5, A = 55, B = 61.875 vibrations. The number of vibrations of the next highest octave is found at once by multiplying these numbers by 2.

Musical Notes.—The **lowest notes** used in music are the double bass, E, with 41.25 vibrations, pianoforte C with 33, grand piano A, with 27.5 and organ C with 16.5. The **highest** notes in music are the pianoforte c^v with 4224, and d^v on the piccolo flute, with 4752 vibrations per second.

FIG. 596.

Galton's Whistle.

Limits of Auditory Perception.—According to Preyer, the limit of the perception of the lowest audible tone lies between 16 and 23 vibrations per second, and e^{viii} with 40,960 vibrations as the highest audible tone; so that this embraces about 11½ octaves.

[**Audibility of Shrill Notes.**—This varies very greatly in different persons (*Wollaston*). There is a remarkable falling off of the power as age advances (*Galton*). For testing this Galton uses a small whistle made of a brass tube, with a diameter of less than $\frac{1}{10}$ of an inch (Fig. 596). A plug is fitted at the lower end to lengthen or shorten the tube, whereby the pitch of the note is altered. Among animals Galton finds none superior to cats in the power of hearing shrill sounds, and he attributes this "to differentiation by natural selection among these animals until they have the power of hearing all the high notes made by mice and other little creatures they have to catch."]

Variations in Auditory Perception.—It is rare to find that tones produced by more than 35,000 vibrations per second are heard. When the tensor tympani is contracted, the perception may be increased for tones 3000 to 5000 vibrations higher, but rarely more. **Pathologically**, the perception for high notes may be abnormally acute—(1) When the tension of the sound-conducting apparatus generally is increased. (2) By elimination of the sound-conducting apparatus of the middle ear, which offers greater or less resistance to the propagation of very high notes, as perforation of the membrana tympani, or loss of the incus and malleus. In these cases, the stapes is directly set in vibration by the sound waves, when tones up to 80,000 vibrations have been perceived. Diminished tension of the sound-conducting apparatus causes diminution of the perception for high tones (*Blake*).

A smaller number of vibrations than 16 per second (as in the organ) are no longer heard as a tone, but as single dull impulses. The tones that are produced beyond the highest audible note, as by stroking small tuning-forks with a violin bow, are also no longer heard as tones, but they cause a painful cutting kind of impression in the ear. In the musical scale the range is, approximately, from C of the first octave with 16.5 vibrations to e, the eighth octave.

Comparison of Ear and Eye.—In comparing the perception of the eye with that of the ear, we see at once that the range of accommodation of the ear is much greater. Red has 456 billions of vibrations per second, while the visible violet has but 667, so that the eye only takes cognizance of vibrations which do not form even one octave.

Lowest Audible Tone.—As to the *smallest* number of successive vibrations which the ear can perceive as a sensation of tone, Savart and Pfaundler considered that two would suffice. If, however, we exclude in our experiments the possibility of the occurrence of overtones, 4 to 8 (*Mach*) or even 16 to 20 vibrations (*F. Auerbach, Kohlrausch*) are necessary to produce a characteristic tone.

When tones succeed each other rapidly, they are still perceived as distinct, when

at least 0.1 second intervenes between two successive tones (*v. Helmholtz*); if they follow each other more rapidly, they fuse with each other, although a short-time interval is sufficient for many musical tones.

By the term, "*fineness of the ear*," or, as we say, a "good ear," is meant the capacity of distinguishing from each other, as different, two tones of nearly the same number of vibrations. This power can be greatly increased by practice, so that musicians can distinguish tones that differ in pitch by only $\frac{1}{500}$, or even $\frac{1}{1200}$, of their vibrations.

With regard to the **time sense**, it is found that beats are more precisely perceived by the ear than by the other sense organs (*Höring, Mach*).

Pathological.—According to Lucae, there are some ears that are better adapted for hearing *low* notes and others for *high* notes. Both conditions are disadvantageous for hearing speech. Those who hear low notes best hear the highest consonants imperfectly. The low notes are heard abnormally loud in rheumatic facial paralysis, while the high tones are heard abnormally loud in cases of loss of the membrana tympani, incus, and malleus. The stapedius is in full action, whereby the highest tones are heard louder at the expense of the lower notes. Many persons with normal hearing hear a tone higher with one ear than with the other. This condition is called **diplacusis binauralis**. In rare cases, sudden loss of the perception of certain tones has been observed, *e. g.*, the **bass deafness** of Moos. In a case described by Magnus, the tones d, b, were not heard (§ 316).

II. Perception of the Intensity of Tone.—The *intensity* of a tone depends upon the *amplitude of the vibrations* of the sounding body. The intensity of the tone is proportional to the square of the amplitude of vibration of the sounding body, *i. e.*, with 2, 3, or 4 times the amplitude the intensity of the tone is 4, 9, 16 times as strong. As sonorous vibrations are communicated to our ears by the wave movements of the air, it is evident that the tones must become less and less intense the further we are from the source of the sound. The intensity of the sound is inversely proportional to the square of the distance of the source of the sound from the ear.

Tests.—1. Place a watch horizontally near the ear, and test how close it may be brought to the ear, and also how far it may be removed, and still its sounds be heard. Measure the distance. 2. Itard uses a small hammer suspended like a pendulum, and allowed to fall upon a hard surface. 3. Balls of different weights are allowed to fall from varying heights upon a plate. In this case the intensity of the sound is proportional to the product of the weight of the ball into the height it falls.

As to the **limits** of the perception of the intensity of tone, it is found that a spherule weighing 1 milligram, and falling from a height of 1 mm. upon a glass plate, is heard at a distance of 5 centimetres (*Schafhäult*).

415. PERCEPTION OF QUALITY—VOWELS.—By the term **quality** ("Klangfarbe"), *musical color* or **timbre**, is understood a peculiar character of the tone, by which it can be distinguished apart from its pitch and intensity. Thus, a flute, horn, violin, and the human voice may all sound the same note with equal intensity, and yet all the four are distinguished at once by their specific quality. Wherein lies the essence ("Wesen") of tone-color? The investigations of v. Helmholtz have proved that, among mechanisms which produce tones, only those that produce pendulum-like vibrations, *i. e.*, the to-and-fro vibrations of a metallic rod with one end fixed, and tuning forks, execute simple pendulum-like vibrations. This can be shown by making a tuning fork write off its vibrations on a recording surface, when a completely uniform wave line, with equal elevations and depressions, is noted. The term "**tone**" is restricted to those sounds, hardly ever occurring in nature, which are due to simple pendulum-like vibrations.

Other investigations have shown that the tones of musical instruments and of the human voice, all of which have a characteristic quality of their own, are composed of many single simple tones. Among these *one* is characterized by its intensity, and at the same time it determines the pitch of the whole compound musical "tone picture." This is called the **fundamental tone** or keynote. The other weaker tones which, as it were, spring from and are mingled with this, vary in different instruments both in intensity and number. They are "**upper tones**," and their vibrations are always some multiple—2, 3, 4, 5 .... times—of the fundamental tone or keynote. In general, we say that all those outbursts of sound which embrace numerous strong upper tones, especially of high pitch, in addition to the fundamental tone, are characterized by a sharp, piercing, and rough quality, such as emanates from a trumpet or clarionet, and that conversely the quality is characterized by mildness and softness when the overtones are few, feeble, and low, *e.g.*, such as are produced by the flute. It requires a well-trained musical ear to distinguish, in an instrumental burst, the overtones apart from the fundamental tone. But this is very easily done with the aid of **resonators** (Fig. 600). These consist of spherical or funnel-shaped hollow bodies, made of brass or some other substance, which, by means of a short tube, can be placed in the outer ear. If a resonator be placed in the ear, we can hear the feeblest overtone of the same number of vibrations as the fundamental tone. Thus, musical instruments are distinguished by the number, intensity, and pitch of the overtones which they produce. A vibrating metallic

rod and a tuning fork have no overtones; they only give the fundamental tone. As already mentioned, the term *simple* tone is applied to sounds due to simple pendulum-like vibrations, while a sound composed of a fundamental tone and overtones is called a "klang" or *compound* musical tone.

FIG. 597.



Curves of a musical tone obtained by compounding the curve of a fundamental tone with that of its overtones.

Vibration Curve of a Musical Tone.—When we remember that a musical tone or clang consists of a fundamental tone, and a number of overtones of a certain intensity, which determine its quality, then we ought to be able to construct geometrically the vibration curve of the musical tone. Let A represent the vibration curve of the fundamental tone, and B that of the first moderately weak overtone (Fig. 597). The combination of these two curves is obtained simply by computing the height of the ordinates, whereby the ordinates of the overtone curve, lying above the abscissa or horizontal line, are added to the fundamental tone curve, while those of the ordinates below the line are subtracted from it. Thus we obtain the curve C, which is not a simple pendulum-like curve, but one which corresponds to an *unsteady* movement. A new curve of the second overtone may be added to C, and so on. The result of all these combinations is that the vibration curves corresponding to the compound musical tones are *unsteady* periodic curves. All these curves must, of course, vary with the number and pitch of the compound overtone curves.

Displacement of the Phases.—The form of the vibration of one and the same musical tone may vary very greatly if, in compounding the curves A and B, the curve B is only slightly displaced laterally. If B is displaced so that the hollow of the wave *r* falls under A, the addition of both curves yields the curve *r*, *r*, *r*, with small elevations and broad valleys. If B be displaced still further, until the elevation of the wave, *h*, coincides with A, we obtain still another form, so that by displacement of the *phases* of the wave motions of the compounded simple pendulum-like vibrations, we obtain numerous different forms of the same musical tone. The displacement of the phases, however, has no effect on the ear.

The general result of these observations, and those of Fourier, is that the quality of a musical tone depends upon the characteristic form of the vibratory movement.

Analysis of Vowels.—The human voice represents a reed instrument with vibrating elastic membranes, the vocal cords (§ 312). In uttering the various vowels the mouth assumes a characteristic form, so that its cavity has a certain fundamental tone peculiar to itself. Thus, to the fundamental tone of a certain pitch produced within the larynx, there are added certain overtones, which communicate to the laryngeal tone the vocal or vowel quality. Hence, a vowel is the timbre or quality of a musical tone which is produced in the larynx. The quality depends upon the number, intensity, and pitch of the overtones, and the latter, again, depend on the configuration of the "vocal cavity" in uttering the different vowels (§ 317).

Suppose a person to sing the vowels one after the other on a special note, *e. g.*, b ♭, we can, with the aid of resonators, determine the overtones, and in what intensity they are mixed with the fundamental tone, b ♭, to give the characteristic quality. According to v. Helmholtz, when we sound the vowels on b ♭, for each of the three vowels, *one* overtone is specially characteristic for A–b^{II} ♭; for O–b^{I} ♭; for U–f. The other vowels and the diphthongs have each *two* specially characteristic overtones, because in these cases the mouth is so shaped that the posterior larger cavity, and also the anterior narrower part, each yields a special tone, (§ 316, I and E). These two overtones are for E–B^{III} ♭ and f^{I}; for I–d^{IV} and f; for A–g^{III} and d^{II}; Ö–c^{III} ♯ and f^{I}; for U–g^{III} and f. These, however, are only the special upper tones. There are many more upper tones, but they are not so prominent.

Artificial Vowels.—Just as it is possible to analyze a vowel into its fundamental tone and its upper tones, it is possible to compound tones to produce the vowels by simultaneously sounding the fundamental tone and the corresponding upper tones. (1) A vowel is produced simply by singing loudly a vowel, *e. g.*, A, upon a certain note against the free strings of an open piano, while by the pedal the damper is kept raised. As soon as we stop singing, the characteristic vowel is sounded by the strings of the piano. The voice sets into sympathetic vibration all those strings whose overtones (in addition to the fundamental tone) occur in the vocal compound tone, so that they vibrate for a time after the voice ceases (*v. Helmholtz*). (2) The vowel apparatus devised by v. Helmholtz consists of numerous tuning forks, which are kept vibrating by means of electro-magnets. The lowest tuning fork gives the fundamental tone, B ♭, and the others the overtones. A resonator is placed in front of each tuning fork, and the distance between the two can be varied at pleasure. The

onators can be opened and closed by a lid passing in front of their openings. When the resonator closed, we cannot hear the tone emitted by the tuning-fork placed in front of it; but when one or re resonators are opened the tone is heard distinctly, and it is louder the more the resonator is

FIG. 598.



Koenig's manometric capsule (A) and mirror (M)—(*Koenig*).

FIG. 599.



Flame pictures of the vowels OU, O, and A (*Koenig*).

opened. By means of a series of keys, like the keys of a pianoforte, we can rapidly open and close the resonators at will, and thus combine various overtones with the fundamental tone so as to produce vowels with different qualities. v. Helmholtz makes the following compositions: U = B♭ with b♭ weak and f′; O = damped B♭ with b♭ strong and weaker b♭, f′, d″; A = b♭ (fundamental tone) with moderately strong b♭ and f″, and strong b″♭ and d‴; A = b♭ (fundamental tone) with b♭ and f″ somewhat stronger than for A, d strong, b″♭ weaker, d‴ and f‴ as strong as possible; E = b♭ (as fundamental tone) moderately strong, with b♭ and f′ moderate also, and f‴, a♭‴, and b‴♭ as strong as possible; I could not be produced.

In **Appunn's apparatus**, the fundamental tone and the overtones are produced by means of organ pipes, whose tones can be combined to produce the vowels, but it is not so good as the tuning forks, since the organ pipes do not yield simple tones, but nevertheless some of the vowels can be admirably reproduced with this apparatus.

Edison's Phonograph.—If we utter the vowels against a delicate membrane stretched over the

Fig. 600.



Koenig's apparatus for analyzing a compound tone with the fundamental tone ut_2.

end of a hollow cylinder, and if a writing style be fixed to the centre of the membrane, and the style be so arranged that it can write or record its movements on a piece of soft tinfoil arranged on a revolving apparatus, then the vowel curve is stamped as it were upon the tinfoil. If the style now be made to touch the tinfoil while the latter is moved, then the style is moved—it moves the membrane, and we hear distinctly by resonance the vowel sound reproduced.

[**Koenig's Manometric Flames.**—By means of this apparatus the quality of the vowel sounds is easily shown. It consists of a small wooden capsule, A, divided into two compartments by a piece of thin sheet india-rubber. Ordinary gas passes into the chamber on one side of the membrane, through the stop-cock, and it is lighted at a small burner. To the other compartment is attached a wider tube with a mouthpiece. The whole is fixed on a stand, and near it is placed a four-sided rotating mirror, M, as suggested by Wheatstone (Fig. 598). On speaking or singing a vowel into the mouthpiece, and rotating the mirror, a toothed or zigzag flame picture is obtained in the mirror. The form of the flame picture is characteristic for each vowel, and varies, of course, with the pitch].

[Fig. 599 shows the form of the flame picture obtained in the rotating mirror when the vowels, OU, O, A, are sung at a pitch of ut_1, sol_1, and ut_2. This series shows how they differ in quality.]

[Koenig has also invented the apparatus for **analyzing any compound tone** whose fundamental tone is UT_2 (Fig. 600). It consists of a series of resonators, from UT_2 to UT_5, fixed in an iron frame. Each resonator is connected with its special flame, which is pictured in a long, narrow, square, rotating mirror. If a tuning fork UT_2 be sounded, only the flame UT_2 is affected, and so on with each tuning fork of the harmonic series. Suppose a compound note containing the fundamental tone UT_2, and its harmonics be sounded, then the flame of UT_2, and those of the other harmonics in the note are also affected, so that the tone can be analyzed optically. The same may be done with the vowels.]

416. **LABYRINTH DURING HEARING.**—If we ask what rôle the ear plays in the perception of the **quality** of sounds, then we must assume that, just as with the help of resonators a musical note can be resolved into its fundamental tone and overtones, so the ear is capable of performing such an analysis. The ear resolves the complicated wave forms of musical tones into their components. These components it perceives as tones harmonious with each other; with marked attention each is perceived singly, so that the ear distinguishes as different tone colors only different combinations of these simple tone sensations. The resolution of complex vibrations, due to quality, into simple pendulum-like vibrations is a characteristic function of the ear. What apparatus in the ear is capable of doing this? If we sing vigorously, *e. g.*, the musical vowel A on a definite note, say b ♭—against the strings of an open pianoforte while the damper is raised, then we cause all those strings, and *only* those, to vibrate sympathetically, which are contained in the vowel so sung. We must, therefore, assume that an analogous sympathetic apparatus occurs in the ear, which is tuned, as it were, for different pitches, and which will vibrate sympathetically like the strings of a pianoforte. "If we could so connect every string of a piano with a nerve fibre that the nerve fibre would be excited and perceived as often as the string vibrated, then, as is actually the case in the ear, every musical note which affected the instrument would excite a series of sensations exactly corresponding to the pendulum-like vibrations into which the original movements of the air can be resolved; and thus the existence of each individual overtone would be exactly perceived, as is actually the case with the ear. The perception of tones of different pitch would, under these circumstances, depend upon different nerve fibres, and hence would occur quite independently of each other. Microscopic investigation shows that there are somewhat similar structures in the ear. The free ends of all the nerve fibres are connected with small elastic particles which we must assume are set into sympathetic vibration by the sound waves" (*v. Helmholtz*).

Resolution by the Cochlea.—Formerly v. Helmholtz considered the rods of Corti to be the apparatus that vibrated and stimulated the terminations of the nerves. But, as **birds** and **amphibians**, which certainly can distinguish musical notes, have *no* rods (*Hasse*), the *stretched radial fibres of the membrana basilaris*, on which the organ of Corti is placed, and which are shortest in the first turn of the cochlea, becoming longer toward the apex of the cochlea, are now regarded as the vibrating threads (*Hensen*). Thus, a string-like fibre of the membrana basilaris, which is capable of vibrating, corresponds to every possible simple tone. According to Hensen, the hairs of the labyrinth, which are of unequal length, may serve this purpose. Destruction of the apex of the cochlea causes deafness to deeper tones (*Baginsky*).

[**Hensen's Experiments.**—That the hairs in connection with the hair cells vibrate to a particular note is also rendered probable by the experiments of Hensen on the crustacean *Mysis*. He found that certain of the minute hairs (auditory hairs) in the auditory organ of this animal, situate at the base of the antennæ, vibrated when certain tones were sounded on a keyed horn. The movements of the hairs were observed by a low-power microscope. In mammals, however, there is a difficulty, as the hairs attached to the cells appear to be all about the same length. We must not forget that the perception of sound is a mental act.]

This assumption also explains the perception of *noises*.

Of **noises** in the strictly physical sense, it is assumed that they, like single impulses, are perceived by the aid of the saccules and the ampullæ.

It is assumed that the **saccules** and the **ampullæ** are concerned in the general perception of hearing, *i. e.*, of shocks communicated to the auditory nerve (by impulses and noises); while by the **cochlea** we estimate the pitch and depth of the vibrations, and musical character of the vibrations produced by tones.

The relation of the **semicircular canals** to the equilibrium of the body is referred to in § 350.

417. SIMULTANEOUS ACTION OF TWO TONES—HARMONY—BEATS—DISCORDS—DIFFERENTIAL TONES.—When *two* tones of different pitch fall upon the ear simultaneously, they cause different sensations according to the difference in pitch.

1. Consonance.—If the number of vibrations of the two tones is in the ratio of simple multiples, as 1 : 2 : 3 : 4, so that when the low notes make one vibration the higher one makes 2 : 3 or 4 . . . . then we experience a sensation of complete harmony or concord.

2. Interference.—If, however, the two tones do not stand to each other in the relation of simple multiples, then when both tones are sounded simultaneously *interference* takes place. The hollows of the one sound wave can no longer coincide with the hollows of the other, and the crests with the crests, but, corresponding to the difference of number of vibrations of both curves, sometimes a wave crest must coincide with a wave hollow. Hence, when wave crest meets wave crest, there must be an *increase* in the strength of the tone, and when a hollow coincides with a crest, the sound must be weakened. Thus we obtain the impression of those variations in tone intensity which have been called "**beats.**"

The number of vibrations is of course always equal to the difference of the number of vibrations of both tones. The beats are perceived most distinctly when two organ tones of low pitch are sounded together in unison, but slightly out of tune. Suppose we take two organ pipes with 33 vibrations per second, and so alter one pipe that it gives 34 vibrations per second, then *one* distinct beat will be heard every second. The beats are heard more frequently the greater the difference between the number of vibrations of the two tones.

Successive Beats.—The beats, however, produce very different impressions upon the ear according to the rapidity with which they succeed each other.

1. Isolated Beats.—When they occur at long intervals, we may perceive them as completely isolated, but single intensifications of the sound with subsequent enfeeblement, so that they give rise to the impression of *isolated beats*.

2. Dissonance.—When the beats occur more rapidly they cause a continuous disagreeable whirring impression, which is spoken of as *dissonance*, or an unharmonious sensation. The greatest degree of unpleasant painful dissonance occurs when there are 33 beats per second.

3. Harmony.—If the beats take place more rapidly than 33 times per second, the sensation of dissonance gradually diminishes, and it does so the more rapidly the beats occur. The sensation passes gradually from moderately inharmonious relations (which in music have to be resolved by certain laws) toward consonance or harmony. The tone relations are successively the Second, Seventh, Minor Third, Minor Sixth, Major Third, Major Sixth, Fourth and Fifth.

4. Action of the Musical Tones ("*Klänge*").—Two musical "klangs," or compound tones, falling on the ear simultaneously, produce a result similar to that of two simple tones; but in this case we have to deal not only with the two fundamental tones; but also with the overtones. Hence the degree of dissonance of two musical tones is the more pronounced the more the fundamental tones and the overtones (and the "differential" tones) produce beats which number about 33 per second.

5. Differential Tones.—Lastly, two "klangs," or two simple musical tones

sounding simultaneously, may give rise to *new tones* when they are uniformly and simultaneously sounding in corresponding intensity. We can hear, if we listen attentively, a third new tone, whose number of vibrations corresponds to the difference between the two primary tones, and hence it is called a "*differential tone.*"

Summational Tones.—It was formerly supposed that new tones could arise from the summation or *addition* of their number of vibrations, but it has been shown that these tones are in reality differential tones of a high order (*Appunn*, *Preyer*).

418. PERCEPTION OF SOUND—OBJECTIVE AND SUBJECTIVE AUDITION—AFTER-SENSATION.—Objective and Auditory Perceptions.—When the stimulation of the terminations of the nerves of the labyrinth is referred to the outer world, then we have *objective auditory perceptions*. Such stimulations are only referred to the outer world as are conveyed to the membrana tympani by vibrations of the air, as is shown by the fact that if the head be immersed in water, and the auditory meatuses be filled thereby, we hear all the vibrations as if they occurred within our head itself (*Ed. Weber*), and the same is the case with our own voices, as well as with the sound waves conducted through the bones of the head, when both ears are firmly plugged.

Perception of Direction.—As to the perception of the direction whence sound comes, we obtain some information from the relation of both meatuses to the source of the sound, especially if we turn the head in the supposed direction of the sound. We distinguish more easily the direction from which noise mixed with musical tones come than that of tones (*Rayleigh*). When both ears are stimulated equally, we refer the source of the sound to the middle line anteriorly, but when one ear is stimulated more strongly than the other, we refer the source of the sound more to one side (*Kessel*). The position of the ear muscles, which perhaps act like an ear funnel, is important. According to Ed. Weber, it is more difficult to determine the direction of sound when the ears are firmly fixed to the side of the head. Further, if we place the hollow of both hands in front of the ear, so as to form an open cavity behind them, we are apt to suppose that a sounding body placed in front is behind us. The semicircular canals are said also to be concerned, as sound coming from a certain direction must always excite one canal more than the others. Thus, the left horizontal canal is most stimulated by horizontal sound waves coming from the left (*Preyer*). Other observers assert that the membrana tympani localizes the sound, as only certain parts of it are affected by the sound waves.

The **distance** of a sound is judged of partly by the *intensity* or *loudness* of the sound, such as we have learned to estimate from sound at a known distance. But still we are subject to many misconceptions in this respect.

Among **subjective auditory sensations** are the *after vibrations*, especially of intense and continued musical tones; the **tinnitus aurium** (p. 655), which often accompanies abnormal movements of the blood in the ear, may be due to a mechanical stimulation of the auditory fibres, perhaps by the blood stream (*Brenner*).

[**Drugs.**—Cannabis indica seems to act on the hearing centre, giving rise to subjective sounds; the hearing is rendered more acute by strychnin; while quinine and sodic salicylate in large doses cause ringing in the ears (*Brunton*).]

Entotical perceptions, which are due to causes within the ear itself, are such as hearing the *pulse beats* in the surrounding arteries, and the rushing sound of the blood, which is especially strong when there is increased resonance of the ear (as when the meatus or tympanum is closed, or when fluid accumulates in the latter), during increased cardiac action, or in hyperæsthesia of the auditory nerve (*Brenner*). Sometimes there is a cracking noise in the maxillary articulation, the noise produced by traction of the muscles on the Eustachian tube (§ 411), and when air is forced into the latter, or when the membrana tympani is forced outward or inward (§ 350).

Fatigue.—The ear after a time becomes fatigued, either for one tone or for a series of tones which have acted on it, while the perceptive activity is not affected for other tones. Complete recovery, however, takes place in a few seconds (*Urbantschitsch*).

VIDE PAGE 683

Auditory After-Sensations.—(1) Those that correspond to *positive* after-sensations, where the after-sensation is so closely connected with the original tone that both appear to be continuous. (2) There are some after-sensations, where a pause intervenes between the end of the objective and the beginning of the subjective tone (*Urbantschitsch*). (3) There seems also to be a form corresponding to *negative* after-images.

In some persons, the perception of a tone is accompanied by the occurrence of subjective colors, or the sensation of light, *e.g.*, the sound of a trumpet, accompanied by the sensation of yellow. More seldom visual sensations of this kind are observed when the nerves of taste, smell, or touch are excited (*Nussbaumer, Lehmann and Bleuler*). It is more common to find that an intense sharp sound is accompanied by an associated sensation of the sensory nerves. Thus many people experience a cold shudder when a slate pencil is drawn in a peculiar manner across a slate.

[**Color Associations.**—Color is in some persons instantaneously associated with sound, and Galton remarks that it is rather common in children, although in an ill-developed degree, and the tendency seems to be very hereditary. Sometimes a particular color is associated with a particular letter, vowel sounds particularly evoking colors. Galton has given colored representations of these color associations, and he points out their relation to what he calls **number forms**, or the association of certain forms with certain numbers.]

An auditory impulse communicated to *one* ear at the same time often causes an increase in the auditory function of the *other* ear, in consequence of the stimulation of the auditory centres of *both* sides (*Urbantschitsch, Eitelberg*).

Other Stimuli.—The auditory apparatus, besides being excited by sound waves, is also affected by heterologous stimuli. It is stimulated *mechanically* by a sudden blow on the ear. The effects of *electricity* and pathological conditions are referred to in § 350.

419. COMPARATIVE—HISTORICAL.—The lowest **fishes**, the cyclostomata (Petromyzon), have a saccule provided with auditory hairs containing otoliths, and communicating with two semicircular canals, while the myxinoids have only one semicircular canal. Most of the other fishes, however, have a utricle communicating with three semicircular canals. In the carp, prolongations of the labyrinth communicate with the swimming bladder. In **amphibia**, the structure of the labyrinth is somewhat like that in fishes, but the cochlea is not typically developed. Most amphibia, except the frog, are devoid of a membrana tympani. Only the fenestra ovalis (not the rotunda) exists, and it is connected in the frog by three ossicles with the freely-exposed membrana tympani. Among **reptiles** the appendix to the saccule, corresponding to the cochlea, begins to be prominent. In the tortoise it is saccular, but in the crocodile it is longer, and somewhat curved and dilated at the end. In all reptiles the fenestra rotunda is developed, whereby the cochlea is connected with the labyrinth. In crocodiles and **birds**, the cochlea is divided into a scala vestibuli and S. tympani. Snakes are devoid of a tympanic cavity. In birds both saccules (Fig. 591, IV, U S′) are united (*Hasse*), the canal of the cochlea (U C), which is connected by means of a fine tube (C) with the saccule, is larger, and shows indications of a spiral arrangement, and has a flask-like blind end, the lagena (L). The auditory ossicles in reptiles and birds are reduced to *one* column-like rod, corresponding to the stapes, and called the **columella**. The lowest **mammals** (Echidna) have structures very like those of birds, while the higher mammals have the same type as in man (Fig. 591, III). The Eustachian tube is always open in the whale.

Among **invertebrata**, the auditory organ is very simple in medusæ and molluscs. It is merely a bladder filled with fluid, with the auditory nerves provided with the ganglia in its walls. Hair cells occur in the interior, provided with one or more otoliths. Hensen observed that in some of the annulosa, when sound was conducted into the water, some of the auditory bristles vibrated, being adapted for special tones. In cephalopoda, we distinguish the first differentiation into a membranous and cartilaginous labyrinth.

Historical.—Empedocles (473 B. C.) referred auditory impressions to the cochlea. The Hippocratic School was acquainted with the tympanum, and Aristotle (384 B. C.) with the Eustachian tube. Vesalius (1561) described the tensor tympani; Cardanus (1560) the conduction through the bones of the head; while Fallopius (1561) described the vestibule, the semicircular canals, chorda tympani, the two fenestræ, the cochlea, and the aqueduct. Eustachius († 1570) described the malleolus, the lamina spiralis of the cochlea, the Eustachian tube, as well as the muscles of the ear; Plater the ampullæ (1583); Casseri (1600) the lamina spiralis membranacea. Sylvius (1667) discovered the ossicle called by his name; Vesling (1641) the stapedius. Mersenne (1618) was acquainted with overtones; Gassendus (1658) experimented on the conduction of sound. Acoustics were greatly advanced by the work of Chladni (1802). The most recent and largest work on the ear in vertebrates is by G. Retzius (1881–84).

THE SENSE OF SMELL.

420. STRUCTURE OF THE ORGAN OF SMELL.—Regio Olfactoria.—The area of the distribution of the olfactory nerve is the **regio olfactoria**, which embraces the upper part of the septum, the upper, and part of the middle (*Cm*) turbinated bone (Fig. 601, *Cs*). All the remainder of the nasal cavity is called the **regio respiratoria**. These two regions are distinguished as follows: (1) The regio olfactoria has a thicker mucous membrane. (2) It is covered by a single layer of cylindrical epithelium, the cells being often branched at their lower ends, and contain a yellow or brownish-red pigment (Figs. 602, 603, E). (3) It is colored by this pigment, and is thereby distinguished from the uncolored regio respiratoria, which is covered by ciliated epithelium. (4) It

FIG. 601.



Nasal and pharyngo-nasal cavities. *L.*, levator elevation; *P.s.p.*, plica salpingo-palatina; *Cs*, *Cm*, *Ci*, the three turbinated bones (*Urbantschitsch*).

FIG. 602.



Vertical section of the olfactory region (rabbit), × 560. *s*, disk; *zo*, zone of oval, and *zr* of spherical nuclei; *b*, basal cells; *dr*, part of a Bowman's gland; *n*, branch of the olfactory nerve.

contains peculiar tubular glands (**Bowman's glands**), described as "mixed glands" by Paulsen (§ 142), while the rest of the mucous membrane contains numerous acinous *serous* glands (*Heidenhain*); but in man the latter are said to be mixed glands (*Stöhr*) (Fig. 602). Lymph follicles lie in the mucous membrane, and from them numerous leucocytes pass out on to free surface (*Stöhr*). (5) Lastly, the regio olfactoria embraces the end organs of the olfactory nerve. The long, narrow **olfactory cells** (Fig. 603, N) are distributed between the ordinary cylindrical epithelium (E) covering the regio olfactoria. The body of the cell is spindle-shaped, with a large nucleus containing nucleoli, and it sends upward between the cylindrical cells a narrow (0.9 to 1.8 μ) smooth rod, quite up to the free surface of the mucous membrane. In the frog (*n*) the free end carries delicate projecting hairs or bristles. In the deeper part of the mucous membrane, the olfactory cells pass into, and become continuous with, varicose fine nerve fibres, which pass into the olfactory nerve (§ 321, I, 1). According to C. K. Hoffmann and Exner, after section of the olfactory nerve, the specific olfactory end organs become changed into cylindrical epithelium (frog), and in warm-blooded animals they undergo

fatty degeneration, even on the 15th day. v. Brunn found a homogeneous limiting membrane, which had holes in it for transmitting the processes of the olfactory cells only.

[The **respiratory part** of the nasal mucous membrane is lined by **ciliated** epithelium stratified like that in the trachea and resting on a basement membrane. Below this there are many lymph corpuscles and aggregations of adenoid tissue.]

[The **organ of Jacobson** is present in all mammals, and consists of two narrow tubes protected by cartilage, and placed in the lower and anterior part of the nasal septum. Each tube terminates blindly behind, but anteriorly it opens into the nasal furrow or into the naso-palatine canal (dog). The wall next the middle line is covered by olfactory epithelium, and receives olfactory nerves (rabbit, guinea-pig), and it contains glands similar to those of the olfactory region; the outer wall is covered by columnar epithelium ciliated in some animals (*Klein*).]

FIG. 603.

N, olfactory cells (human); *n*, from the frog; E, epithelium of the regio olfactoria.

421. OLFACTORY SENSATIONS.—Olfactory sensations are produced by the action of gaseous, odorous substances, being brought into **direct contact** with the olfactory cells, during the act of *breathing*. The current of air is divided by the anterior projection of the lowest turbinated bone, so that a part above the latter is conducted to the regio olfactoria. Odorous bodies taken into the mouth and then expired through the posterior nares are said not to be smelt (*Bidder*). [This is certainly not true, as has been proved by Aronsohn.]

[It is usually stated that only odorous particles suspended in air excite the sensation of smell. This is certainly not the whole truth—otherwise, how do aquatic animals, like fish, smell? Moreover, the mucous membrane is always moist, and in some cases where there is a profuse secretion from the olfactory mucous membrane, there is no impairment of the sense of smell.]

During inspiration, the air streams along close to the septum, while little of it passes through the nasal passages, especially the superior (*Paulsen and Exner*). [The expired air takes almost the same course as the inspired air.]

The *first* moment of contact between the odorous body and the olfactory mucous membrane appears to be the time when the sensation takes place, as, when we wish to obtain a more exact perception, we *sniff* several times, *i. e.*, a series of rapid inspirations are taken, the mouth being kept closed. During **sniffing**, the air within the nasal cavities is rarefied, and as air rushes in to equilibrate the pressure, the air, laden with odorous particles, streams over the olfactory region. Odorous fluids are said not to give rise to the sensation of smell when they are brought into direct contact with the olfactory mucous membrane, as by pouring eau de Cologne into the nostrils (*Tourtual*, 1827; *E. H. Weber*, 1847). [Aronsohn has, however, shown that these experiments are not accurate, for one can smell eau de Cologne, clove oil, etc., when a mixture of these bodies with .73 per cent. NaCl is applied to the olfactory mucous membrane; the most suitable medium is .73 per cent. NaCl and its temperature 40–43° C.] Even water alone temporarily affects the cells. We know practically nothing about the nature of the action of odorous bodies, but many odorous vapors have a considerable power of absorbing heat (*Tyndall*). [Odorous bodies diminish the number of respirations (*Gourewitsch*).]

The **intensity of the sensation** depends on—1. The size of the olfactory surface, as animals with a very keen sense of smell are found to have complex turbinated bones covered by the olfactory mucous membrane. 2. The concentration of the odorous mixture of the air. Still, some substances may be attenuated enormously (*e. g.*, musk to the two-millionth of a milligramme), and still be smelt. 3. The frequency of the conduction of the vapor to the olfactory cells (sniffing).

[The **acuteness** of the sense of smell is greatly improved by practice. A boy named James Mitchell, who was deaf, dumb, and blind, used his sense of smell, like a dog, to distinguish persons and things.]

[As in the case of sight and hearing, it has been sought to connect the *quality* of taste and smell with the *kind* of vibrating stimulus. Ramsay showed that many facts pointed to the dependence of smell upon the vibratory motion of odorous particles; thus, many gases and vapors of low specific gravity—*i. e.*, with a very rapid vibration of their molecules—are perfectly odorless, while such substances as the alcohols and fatty acids, alike in chemical and physical properties, can excite generic smells, the higher members of the group being more powerful in this respect than the lower ones. Taking the elements as arranged in a "Natural Classification" by Mendelejeff, Haycraft has shown that elements in the same group are capable of producing similar or related tastes, and the same seems to be true for smell (*Haycraft*).]

We can smell the following substances in the following proportions: Bromine $\frac{1}{20000}$, sulphuretted hydrogen $\frac{1}{5000000}$ milligramme in 1 c.cm. of air (*Valentin*; also $\frac{1}{40000000}$ of a milligramme of chlorphenol, and $\frac{1}{40000000000}$ of a milligramme of mercaptan (*E. Fischer and Penzoldt*).

Electrical stimuli give rise to olfactory sensations. [Althaus found that **electrical stimulation** of the olfactory mucous membrane gave rise to the sensation of the smell of phosphorus, and Aronsohn found that he smelt on making the current when the cathode—and on breaking the current when the anode—was in the nose.

The **variations** are referred to in § 343. If the two nostrils are filled with different odorous substances there is no mixture of the odors, but we smell sometimes the one and sometimes the other (*Valentin*). [Some substances appear to affect some regions of the olfactory membrane, while others affect other parts.] The sense of smell, however, is very soon blunted, or even paralyzed. [It can be blunted or fatigued in a few minutes; but after it is completely fatigued it can recover in a minute.] Morphia, when mixed with a little sugar and taken as snuff, paralyzes the olfactory apparatus, while strychnin makes it more sensitive (*Lichtenfels and Fröhlich*).

The **sensory** nerves of the nasal mucous membrane (§ 347, II) [*i. e.*, those supplied from the fifth cranial nerve] are stimulated by irritating vapors, and may even cause pain, *e. g.*, ammonia and acetic acid. In a very diluted condition they may even act on the olfactory nerves. The nose is useful as a sentinel for guarding against the introduction of disagreeable odors and foods. The sense of smell is aided by the sense of taste, and conversely.

[**Flavor** depends on the sense of smell, and, to test it, use substances, solid or fluid, with an *aroma* or *bouquet*, such as wine or roast beef.]

[**Method of Testing**.—In doing so, avoid the use of pungent substances like ammonia, which excite the fifth nerve. Use some of the essential volatile oils, such as cloves, bergamot, and the fetid gum resins, or musk and camphor. Electrical stimuli are not available. **Action of Drugs**, § 343.]

Comparative.—In the lowest **vertebrata**, pits, or depressions provided with an olfactory nerve, represent the simplest olfactory organ. Amphioxus and the cyclostomata have only *one* olfactory pit; all other vertebrates have two. In some animals (frog) the nose communicates with the mouth by ducts. The olfactory nerve is absent in the whale.

Historical.—Rufus Ephesius (97 A.D.) described the passage of the olfactory nerve through the ethmoid bone. Rudius (1600) dissected the body of a man with congenital anosmia, in whom the olfactory nerves were absent. Magendie originally supposed that the nasal branch of the fifth was the nerve of smell, a view successfully combated by Eschricht.

THE SENSE OF TASTE.

all

422. STRUCTURE OF THE GUSTATORY ORGANS.—Gustatory Region.—There is considerable difference of opinion as to what regions of the mouth are endowed with taste: (1) The root of the tongue in the neighborhood of the circumvallate papillæ, the area of distribution of the glosso-pharyngeal nerve, is undoubtedly endowed with taste (§ 351). (2) The tip and margins of the tongue are gustatory, but there are very considerable variations. (3) The lateral part of the soft palate and the glosso-palatine arch are endowed with taste from the glosso-pharyngeal nerve. (4) It is uncertain whether the hard palate and the entrance to the larynx are endowed with taste (*Drielsma*). The middle of the tongue is not gustatory.

[**Tongue—Mucous Membrane.**—The structure of the tongue, as a muscular organ covered with mucous membrane, has already been described (§ 155). The dorsal surface of the tongue, in front of the blind foramen, is beset with elevations of the mucous membrane, which extend to its tip and borders. These elevations, or **papillæ**, are of three kinds; **filiform, fungiform,** and **circumvallate.** They consist of elevations of the mucous membrane, visible to the naked eye, and covered by stratified squamous epithelium, while the central core of connective tissue contains blood and lymph vessels and nerves. The **filiform papillæ** occur over the whole tongue, and are smallest and most numerous. They are conical eminences covered by stratified squamous epithelium,

FIG. 604.

FIG. 605.

FIG. 604.—Longitudinal section of the dorsum of the human tongue. 1, section of two filiform papillæ, with secondary papillæ (2); 3, double, 4, single process of epithelium with loose epithelial scales. × 30.
FIG. 605.—Longitudinal section of the human tongue. 1, secondary papillæ on 2, the fungiform papillæ; 3, base of 2; 4, small filiform papilla. × 30.

and often beset with secondary papillæ (Fig. 604). The **fungiform papillæ** occur chiefly over the middle and front part of the tongue, and are not so numerous as the last. They are club-shaped, with a narrow base, and broad, expanded, rounded head. They also have secondary papillæ. They are generally brighter red than the others (Fig. 605). The **circumvallate papillæ,** 8 to 12 in number, diverge from the foramen cæcum at the back part of the tongue in two rows in the form of a wide V, the open angle of the V being directed forward. They are large, with a broad, expanded top, and are lodged in a depression of the mucous membrane, being surrounded by a wall of mucous

membrane, and separated from it by a circular trench, into the base of which gland ducts often open. They have numerous secondary papillæ, and in them are taste bulbs, Fig. 606, I.]

Taste bulbs.—The **end organs** of the gustatory nerves are the taste bulbs or taste buds dis-

FIG. 606.



I, Transverse section of a circumvallate papilla; W, the papilla; v_1, v_3, the wall in section; R, R, the circular slit or fossa; K, K, the taste bulbs in position; N, N, the nerves. II, Isolated taste bulb; D, supporting or protective cells; K, under end; E, free end, open, with the projecting apices of the taste cells. III, Isolated protective cell (*d*) with a taste cell (*e*).

covered by Schwalbe and Lovèn (1867). They occur on the lateral surfaces of the circumvallate papillæ (Fig. 606, I), and upon the opposite side K, of the fossa or capillary slit, R, R, which surrounds the central eminence or papilla; they occur more rarely on the surface. They also occur on the fungiform papillæ, in the papillæ of the soft palate and uvula (*A. Hoffmann*), on the under surface of the epiglottis, the upper part of the posterior surface of the epiglottis, and the inner side of the arytenoid cartilages (*Verson, Davis*), and on the vocal cords (*Simanowsky*). Many buds or bulbs disappear in old age.

[In the rabbit and some other animals, there is a folded laminated organ on each side of the posterior part of the tongue, called the **papilla foliata**; the folds have on each side of them numerous taste buds (Fig. 607).]

FIG. 607.



Vertical section of two septa of the papilla foliata (rabbit). × 80. Each septum, *l*, has secondary septa, *l'*; *g*, taste buds; *n*, medullated nerve; *d*, serous gland, and part of its duct, *a*; *M*, muscular fibres of the tongue.

Structure of the taste bulbs.—They are 81 μ high and 33 μ thick, barrel-shaped, and embedded in the thick stratified squamous epithelium of the tongue. Each bulb consists of a series of lancet-shaped, bent, nucleated, outer **supporting or protective cells**, arranged like the staves of a barrel (Fig. 606, II, D, insolated in III, *a*). They are so arranged as to leave a small opening, or the "**gustatory pore**," at the free end of the bulb. Surrounded by these cells, and lying in the axis of the bud, are 1 to 10 **gustatory cells** (II, E), some of which are provided with a delicate process (III, *e*) at their free ends, while their lower fixed ends send out basal processes, which become continuous with the terminations of the nerves of taste, which have become non-medullated. After section of the glosso-pharyngeal, the taste buds degenerate, while the protective cells become changed into ordinary epithelial cells within four months (*v. Vintschgau and Hönigschmied*). Very

similar structures were found by Leydig in the skin of fresh-water fishes. The *glands* of the tongue and their secretory fibres from the 9th cranial nerve are referred to in § 141 (*Drasch*).

423. **GUSTATORY SENSATIONS.—Varieties.**—There are *four* different gustatory qualities, the sensations of **1. Sweet; 2. Bitter; 3. Acid; 4. Saline.** Acid and saline substances at the same time also stimulate the sensory nerves of the tongue, but when greatly diluted, they only excite the end organs of the specific nerves of taste. Perhaps there are special nerve fibres for each different gustatory quality (*v. Vintschgau*).

Conditions.—Sapid substances, in order that they may be tasted, require the following conditions: They must be **dissolved** in the fluid of the mouth, especially substances that are solid or gaseous. The **intensity** of the gustatory sensation depends on: **1.** The *size of the surface* acted on. Sensation is favored by rubbing in the substance between the papillæ, in fact, this is illustrated in the rubbing movements of the tongue during mastication (§ 354). **2.** The *concentration* of the sapid substance is of great importance. Valentin found that the following series of substances ceased to be tasted in the order here stated, as they were gradually diluted—syrup, sugar, common salt, aloes, quinine, sulphuric acid. Quinine can be diluted 20 times more than common salt and still be tasted (*Camerer*). **3.** The *time* which elapses between the application of the sapid substance and the production of the sensation varies with different substances. Saline substances are tasted most rapidly (after 0.17 second, according to *v. Vintschgau*), then sweet, acid and bitter (quinine after 0.258 second, *v. Vintschgau*). This even occurs with a mixture of these substances (*Schirmer*). The last-named substances produce the most persistent "**after-taste.**" **4.** The *delicacy* of the sense of taste is partly congenital, but it can be greatly improved by practice. If a person continues to taste the same sapid substance, or a nearly related one, or even any very intensely sapid substance, the gustatory sense is soon affected, and it becomes impossible to give a correct judgment as to the taste of the sapid body. **5.** Taste is greatly aided by the sense of **smell,** and in fact we often confound taste with smell; thus, ether, chloroform, musk, and assafœtida only affect the organ of smell. [The combined action of taste and smell in some cases gives rise to **flavor** (p. 873).] The eye even may aid the determination, as in the experiment where in rapidly tasting red and white wine one after the other, when the eyes are covered, we soon become unable to distinguish between the one and the other. **6.** The most advantageous *temperature* for taste is between 10° to 35° C.; hot and cold water temporarily paralyze taste.

Ice placed on the tongue suppresses, sometimes entirely, the whole gustatory apparatus; cocain alone, bitter tastes, and water containing 2 per cent. of H_2SO_4, excite afterward a sweet taste (*Aducco and Mosso*).

Electrical Current.—The **constant current,** when applied to the tongue, excites, both during its passage and when it is opened or closed, a sensation of acidity at the + pole, and at the — pole an alkaline taste, or, more correctly, a harsh, burning sensation (*Sulzer*, 1752). This is not due to the action of the electrolytes of the fluid in the mouth, for even when the tongue is moistened with an acid fluid the alkaline sensation is experienced at the — pole (*Volta*). We cannot, however, set aside the supposition that perhaps electrolytes, or decomposition products, may be formed in the deeper parts and excite the gustatory fibres. Rapidly **interrupted currents** do not excite taste (*Grünhagen*). v. Vintschgau, who has only incomplete taste on the tip of the tongue, finds that when the *tip* of the tongue is traversed by an electrical current, there is never a gustatory sensation, but always a distinct tactile one. In experiments on Hönigschmied, who is possessed of normal taste in the tip of the tongue, there was often a metallic or acid taste at the + pole on the tip of the tongue, while at the — pole taste was often absent, and when it was present it was almost always alkaline, and acid only exceptionally. After interrupting the current there was a **metallic after-taste** with both directions of the current.

[**Testing Taste.**—Direct the person to put out his tongue and close his eyes, and after drying the tongue apply the sapid substance by means of a glass rod or a small brush. Try to confine the stimulus as much as possible to one place, and after each experiment rinse the mouth with water. A wine-taster chews an olive

to "clean the palate," as he says. For testing *bitter* taste use a solution of quinine or quassia; for *sweet*, sugar [or the intensely sweet substance "saccharine" obtained from coal tar]; *saline*, common salt; and *acid*, dilute citric or acetic acid. The galvanic current may also be used.]

Pathological.—Diseases of the tongue, as well as dryness of the mouth caused by interference with the salivary secretion, interfere with the sense of taste. **Subjective gustatory** impressions are common among the insane, and are due to some central cause, perhaps to irritation of the centre for taste (§ 378, IV, 3). After poisoning with santonin, a bitter taste is experienced, while after the subcutaneous injection of morphia, there is a bitter and acid taste. The terms **hypergeusia, hypogeusia,** and **ageusia** are applied to the increase, diminution, and abolition of the sense of taste. Many tactile impressions on the tongue are frequently confounded with gustatory sensations, *e.g.*, the so-called biting, cooling, prickling, sandy, mealy, astringent, and harsh tastes.

Comparative.—About 1760 taste bulbs occur on the circumvallate papillæ of the ox. The term **papilla foliata** is applied to a large folded gustatory organ placed laterally on the side of the tongue (Fig. 607), especially of the rabbit (*Rapp*, 1832), which in man is represented by analogous organs, composed of longitudinal folds, lying in the fimbriæ linguæ on each side of the posterior part of the tongue (*Krause, v. Wyss*). Taste bulbs are absent in reptiles and birds. They are numerous in the gill slits of the tadpole (*F. E. Schultze*), while the tongue of the frog is covered with epithelium resembling gustatory cells (*Billroth, Axel Key*). The goblet-shaped organs in the skin of fishes and tadpoles have a structure similar to the taste bulbs, and may perhaps have the same function. There are taste bulbs in the mouth of the carp and ray.

Historical.—Bellini regarded the papillæ as the organs of taste (1711). Richerand, Mayo, and Fodera thought that the lingual was the only nerve of taste, but Magendie proved that, after it was divided, the posterior part of the tongue was still endowed with taste. Panizza (1834) described the glosso-pharyngeal as the nerve of taste, the gustatory as the nerve of touch, and the hypoglossal as the motor nerve of the tongue.

THE SENSE OF TOUCH.

424. TERMINATIONS OF SENSORY NERVES.—1. The **touch corpuscles of Wagner and Meissner** lie in the **papillæ** of the cutis vera (§ 283), and are most numerous in the palm of the hand and the sole of the foot, especially in the fingers and toes, there being about 21 to every square millimetre of skin, or 108 to 400 of the papillæ containing blood vessels. They are less abundant on the back of the hand and foot, mamma, lips, and tip of the tongue, rare on the glans clitoridis, and occur singly and scattered on the volar side of the forearm, even in the anthropoid apes. They are oval or elliptical bodies, 40–200 μ long [$\frac{1}{300}$ in.], and 60–70 μ broad [$\frac{1}{300}$ to $\frac{1}{300}$ in.], and are covered externally by layers of connective tissue arranged transversely in layers, and within is a granular mass with elongated striped nuclei (Figs. 608, 609, *e*). One to three medullated nerve fibres pass to the lower end of each corpuscle, and surround it in a spiral manner two or three

FIG. 608.



Vertical section of the skin of the palm of the hand. *a*, blood vessels; *b*, papilla of the cutis vera; *c*, capillary; *d*, nerve fibre passing to a touch corpuscle; *f*, nerve fibre divided transversely; *e*, Wagner's touch corpuscle; *g*, cells of the Malpighian layer of the skin.

FIG. 609.

Wagner's touch corpuscle from the palm, treated with gold chloride; *n*, nerve fibres; *a*, *a*, groups of glomeruli.

times; the fibres then lose their myelin, and, after dividing into 4 to 6 fibrils, branch within the corpuscle. The exact mode of termination of the fibrils is not known. Some observers suppose that the transverse fibrillation is due to the coils or windings of the nerve fibrils; while according to others, the inner part consists of numerous flattened cells lying one over the other, between which the pale terminal fibres end either in swellings or with disk-like expansions, such as occur in Merkel's corpuscles.

[These do not contain a soft core such as exists in Pacini's corpuscles. The corpuscles appear to consist of connective tissue with imperfect septa passing into the interior from the fibrous capsule. After the nerve fibre enters it loses its myelin, and then branches, while the branches anastomose

and follow a spiral course within the corpuscle, finally to terminate in slight enlargements. According to Thin, there are simple and compound corpuscles, depending on the number of nerve fibres entering them.]

Kollmann describes three special tactile areas in the hand: (1) The tips of the fingers with 24 touch corpuscles in a length of 10 mm.; (2) the three eminences lying on the palm behind the slits between the fingers, with 5.4–2.7 touch corpuscles in the same length; and (3) the ball of the thumb and little finger with 3.1–3.5 touch corpuscles. The first two areas also contain many of the corpuscles of Vater or Pacini, while in the latter these corpuscles are fewer and scattered. In the other parts of the hand the nervous end organs are much less developed.

2. **Vater's** (1741) or **Pacini's corpuscles** are oval bodies (Fig. 610), 1–2 mm. long, lying in the subcutaneous tissue on the nerves of the fingers and toes (600–1400), in the neighborhood of

FIG. 610.



Vater's or Pacini's corpuscle. *a*, stalk; *b*, nerve fibre entering it; *c*, *d*, connective-tissue envelope; *e*, axis cylinder, with its end divided at *f*.

FIG. 611.



End bulb from human conjunctiva. *a*, nucleated capsule; *b*, core; *c*, fibre entering and branching, terminating in core at *d*.

FIG. 612.

Tactile corpuscles, clitoris of rabbit.

joints and muscles, the sympathetic abdominal plexuses, near the aorta and coccygeal gland on the dorsum of the penis and clitoris, and in the mesocolon [and mesentery] of the cat. [They also occur in the course of the intercostal and periosteal nerves, and Stirling has seen them in the capsule of lymphatic glands. They are attached to the nerves of the hand and feet, and are so large as to be visible to the naked eye, both in these regions and between the layers of the mesentery of the cat. They are whitish or somewhat transparent, with a white line in the centre (cat); in man they are $\frac{1}{15}$ to $\frac{1}{10}$ inch long, and $\frac{1}{15}$ to $\frac{1}{16}$ inch broad, and are attached by a stalk or pedicle (Fig. 610, *a*) to the nerve.] They consist of numerous nucleated connective-tissue capsules or **lamellæ** lined by endothelium, separated from each other by fluid, and lying one within the other like the coats of an onion, while in the axis is a **central core.** A medullated nerve fibre passes to each, where its sheath of

Schwann unites with the capsule. It loses its myelin, and passes into the interior as an axial cylinder (Fig. 610 *e*), where it either ends in a small knob or may divide dichotomously (Fig. 610, *f*), each branch terminating in a small pear-shaped *enlargement.* [Each large corpuscle is covered by 40–50 **lamellæ**, or tunics, which are thinner and closer to each other (Fig. 610, *d'*) internally than in the outer part, where they are thicker and wider apart. The lamellæ are like the laminæ in the lamellated sheath of a nerve, and are composed of an elastic basis mixed with white fibres of connective tissue, while the inner surface of each lamella is lined by a single continuous layer of endothelium continuous with that of the perineurium. It is easily stained with silver nitrate. The **efferent nerve fibre** is covered with a thick sheath of lamellated connective tissue (sheath of Henle), which becomes blended with the outer lamellæ of the corpuscle. The medullated nerve is sometimes accompanied by a blood vessel, and pierces the various tunics, retaining its myelin until it reaches the core, where it terminates as already described.]

3. **Krause's end bulbs** very probably occur as a regular mode of nerve termination in the cutis and mucous membranes of all mammals (Fig. 611). They are elongated, oval or round bodies, 0.075 to 0.14 mm. long, and have been found in the deeper layers of the conjunctiva bulbi, floor of the mouth, margins of the lips, nasal mucous membrane, epiglottis, fungiform and circumvallate papillæ, glans penis and clitoris, volar surface of the toes of the guinea pig, ear and body of the mouse, and in the wing of the bat. [In the calf, the "**cylindrical end bulbs**" are oval, with a nerve fibre terminating within them. The sheath of Henle becomes continuous with the nucleated capsule, while the axial cylinder, devoid of its myelin, is continued into the soft core. In man the end bulbs are "spheroidal," and consist of a nucleated connective-tissue capsule continuous with Henle's sheath of the nerve, and enclosing many cells, among which the axis cylinder which enters

FIG. 613.

Tactile corpuscles from the duck's tongue. A, composed of three cells with two interposed disks, with axis cylinder, *n*, passing into them. B, two tactile cells and one disk.

FIG. 614.

Bouchon epidermique from the groin of a guinea-pig, after the action of gold chloride. *n*, nerve fibre; *a*, tactile cells; *m*, tactile disks; *c*, epithelial cells.

the bulb branches and terminates.] The spheroidal end bulbs occur in man, in the nasal mucous membrane, conjunctiva, mouth, epiglottis, and the mucous folds of the rectum. According to Waldeyer and Longworth, the nerve fibrils terminate in the cells within the capsule. These cells are said to be comparable to Merkel's tactile cells (*Waldeyer*).

The **genital corpuscles** of Krause, which occur in the skin and mucous membrane of the glans penis, clitoris, and vagina, appear to be end bulbs more or less fused together (Fig. 612).

The **articulation nerve corpuscles** occur in the synovial mucous membrane of the joints of the fingers. They are larger than the end bulbs, and have numerous oval nuclei externally, while one to four nerve fibres enter them.

4. **Tactile or touch corpuscles of Merkel**, sometimes also called the **corpuscles of Grandry**, occur in the beak and tongue of the duck and goose, in the epidermis of man and mammals, and in the outer root sheath of tactile hairs or feelers (Fig. 613). They are small bodies composed of a capsule enclosing two, three, or more large, granular, somewhat flattened nucleated and nucleolated cells, piled one on the other in a vertical row like a row of cheeses. Each corpuscle receives at one side a medullated nerve fibre which loses its myelin, and branches, to terminate, according to some observers (*Merkel*), in the cells themselves, and according to others (*Ranvier, Izquierdo, Hesse*) in the protoplasmic transparent substance or disk lying between the cells. [This intercellular disk is the "**disk tactil**" of Ranvier, or the "*Tastplatte*" of Hesse.] When there is a great aggregation of these cells, large structures are formed which appear to form a kind of transition between these and touch corpuscles. [According to Klein, the terminal fibrils end neither in the touch cells nor tactile disk, but in minute swellings in the interstitial substance between the touch cells, in a manner very similar to that occurring in the end bulbs.]

[According to Merkel, tactile cells, either isolated or in groups, but in the latter case never forming an independent end organ, occur in the deeper layers of the epidermis of man and mammals and also in the papillæ. They consist of round or flask-shaped cells, with the lower pointed neck of the flask continuous with the axis-cylinder of a nerve fibre. They are regarded by Merkel as the simplest form of a tactile end organ, but their existence is doubted by some observers.]

Among animals there are many other forms of sensory end organs. [**Herbst's corpuscles** occur in the mucous membrane of the tongue of the duck, and resemble small Vater's corpuscles, but their lamellæ are thinner and nearer each other, while the axis cylinder within the central core is bordered on each side by a row of nuclei.] In the nose of the mole there is a peculiar end organ (*Eimer*), while there are "*end capsules*" in the penis of the hedgehog and the tongue of the elephant, and "*nerve rings*" in the ears of the mouse.

5. [**Other Modes of Ending of Sensory Nerves.**—Some sensory nerves terminate not by means of special end organs, but their axis cylinder splits up into fibrils to form a nervous network, from which fine fibrils are given off to terminate in the tissue in which the nerve ends. These fibrils, as in the cornea (§ 384), terminate by means of free ends between the epithelium on the anterior surface of the cornea, and some observers state that the free ends are provided with small enlargements ("*boutons terminals*") (Fig. 614, *a*). These enlargements or "**tactile cells**" occur in the groin of the guinea-pig and mole. A similar mode of termination occurs between the cells of the epidermis in man and mammals (Fig. 293).]

6. **Tendons**, especially at their junction with muscles, have special end organs (*Sachs*, *Rollett*, *Golgi*), which assume various forms; it may be a network of primitive nerve fibrils, or flattened end flakes or plates in the sterno-radial muscle of the frog, or elongated oval end bulbs, not unlike the end bulbs of the conjunctiva, or small simple Pacinian corpuscles.

Prus found ganglion cells more frequently in the subcutaneous tissue than in the corium, and they appeared to have some relation to the blood vessels and sweat glands.

425. SENSORY AND TACTILE SENSATIONS.—In the sensory nerve trunks there are two functionally different kinds of nerve fibres: (1) Those which administer to *painful* impressions, which are sensory nerves in the narrower sense of the word; and (2) those which administer to tactile impressions and may therefore be called *tactile* nerves. The sensations of **temperature** and **pressure** are also reckoned as belonging to the tactile group. It is extremely probable that the sensory and tactile nerves have different end organs and fibres, and that they have also special perceptive nerve centres in the brain, although this is not definitely proved. This view, however, is supported by the following facts:—

1. That sensory and tactile impressions cannot be discharged at the same time from all the parts which are endowed with sensibility. Tactile sensations, including pressure and temperature, are only discharged from the coverings of the skin, the mouth, the entrance to and floor of the nose, the pharynx, the lower end of the rectum and genito-urinary orifices; feeble indistinct sensations of temperature are felt in the œsophagus. Tactile sensations are absent from all internal viscera, as has been proved in man in cases of gastric, intestinal, and urinary fistulæ. Pain alone can be discharged from these organs. 2. The conduction channels of the tactile and sensory nerves lie in different parts of the spinal cord (§ 364, 1 and 5). This renders probable the assumption that their central and peripheral ends also are different. 3. Very probably the reflex acts discharged by both kinds of nerve fibres—the tactile and pathic—are controlled, or even inhibited, by special central nerve organs (§ 361—?). 4. Under pathological conditions, and under the action of narcotics, the one sensation may be suppressed while the other is retained (§ 364, 5).

Sensory Stimuli.—In order to discharge a painful impression from sensory nerves, *relatively strong* stimuli are required. The stimuli may be mechanical, chemical, electrical, thermal, and somatic, the last being due to inflammation or anomalies of nutrition and the like.

Peripheral Reference of the Sensations.—These nerves are excitable along their entire course, and so is their central termination, so that pain may be produced by stimulating them in any part of their course, but this pain, according to the "law of peripheral perception," is always referred to the periphery.

The tactile nerves can only discharge a tactile impression or sensation of contact when moderately strong mechanical pressure is exerted, while thermal stimuli are

required to produce a temperature sensation, and in both cases, the results are obtained only when the appropriate stimuli are applied to the end organs. If pressure or cold be applied to the *course* of a nerve trunk, *e.g.*, to the ulna at the inner surface of the elbow joint, we are conscious of painful sensations, but never of those of temperature, referable to the *peripheral* terminations of the nerves in the inner fingers. All strong stimuli disturb normal tactile sensations by over-stimulation, and hence cause pain.

The law of the specific energy of nerves leads us to assume that the cutaneous nerves contain different kinds of nerve fibres with different kinds of end organs, which subserve different kinds of impressions, *e.g.*, pressure, temperature, and pain. Blix and Goldscheider have found such differences. Electrical stimulation causes different sensations according to the part of the skin where it is applied; at one spot, pain only is produced, at another a sensation of cold, at a third a sensation of heat, and at a fourth, a sensation of pressure. At every temperature point or spot, there is insensibility for pain or pressure. The "**pressure points**" or pressure spots lie much closer together, and are more numerous than the temperature points. There are special "**pain spots**" and even "tickling spots." These spots are arranged in a linear chain, which usually radiates from the hair follicles. The "tickling spots" coincide with the pressure and pain spots. The feeling of tickling corresponds to the feeblest stimulation of a nerve fibre, and pain to the strongest. The pain spots can be isolated by means of a needle, or electrically, especially in the cutaneous furrows, in which the pressure sense is absent.

Goldscheider removed from his own body small pieces of skin, in which he had previously ascertained the presence of these "spots," and then investigated the excised skin microscopically. At each such spot he found a rich supply of nerves; at the pressure spots, there were no touch corpuscles.

[By means of the skin, impressions are supplied also to the brain, whereby we become conscious of the amount and direction of a body moved in contact with the skin. Indeed, the discriminative sensibility is more acute for motion than for touch; but the liability to error in judging of the distance and direction is great (*Hall*).]

[Very complex sensations are obtained by means of the combined action of the skin and muscles, *e. g.*, those known as "**feelings of double contact.**" These sensations are of the greatest advantage in acquiring the use of instruments and tools. If we touch an object with a rod, we seem to feel the object at the point of the rod, and not in the hand where the cutaneous nerves are actually stimulated. With a walking stick, we feel the ground at the end of the stick. Touch the tips of the hair, or a tooth, and the sensation is referred to the tips of the hair in the one case, and the crown of the tooth in the other](*Ladd*).]

FIG. 615.

Æsthesiometer.

426. SENSE OF LOCALITY.—We are not only able to distinguish differences of pressure or temperature by our sensory nerves, but we are able to distinguish the part which has been touched. This capacity is spoken of as the sense of space or **locality.**

Methods of Testing.—1. Place the two blunted points of a pair of compasses (Fig. 615) upon the part of the skin to be investigated, and determine the smallest distance at which the two points are felt only as *one* impression. Sieveking's **æsthesiometer** may be used instead (Fig. 616); one of the points is movable along a graduated rod, while the other is fixed. 2. The distance between the points of the instrument being kept the same, touch several parts of the skin, and ask if the person feels the impression of the points coming nearer to or going wider apart. 3. Touch a part of the skin with a blunt instrument, and observe if the point touched is correctly indicated by the patient. 4. Separate the points of two pairs of compasses unequally, and place their points upon different parts of the skin, and ask the person to state when the points of both appear to be equally far apart. A distance of 4 lines on the forehead appears to be equal to a distance of 2.4 lines on the upper lip. This is Fechner's "**methods of equivalents.**"

The following results have been obtained. The sense of locality of a part of the skin is more acute under the following conditions:—

1. The greater the *number of tactile nerves* in the corresponding part of the skin.

2. The greater the *mobility of the part*, so that it increases in the extremities toward the fingers and toes. The sense of locality is always very acute in parts of the body that are very rapidly moved (*Vierordt*).

3. The sensibility of the limbs is finer in the *transverse axis* than in the long axis of the limb, to the extent of ⅛ on the flexor surface of the upper limb, and ¼ on the extensor surface.

4. The *mode of application* of the points of the æsthesiometer: (*a*) According as they are applied one after the other, instead of simultaneously, or as they are considerably warmer or colder than the skin (*Klug*), a person may distinguish a less distance between the points. (*b*) If we begin with the points wide apart and approximate them, then we can distinguish a less distance than when we proceed from imperceptible distances to larger ones. (*c*) If the one point is warm and the other cold, on exceeding the next distance we feel two impressions, but we cannot rightly judge of their relative positions (*Czermak*).

5. *Exercise* greatly improves the sense of locality; hence the extraordinary acuteness of this sense in the blind, and the improvement always occurs on both sides of the body (*Volkmann*).

[Fr. Galton finds that the reputed increased acuteness of the other senses in the case of the blind is not so great as is generally alleged. He tested a large number of boys at an educational blind asylum, with the result that the performances of the blind boys were by no means superior to those of other boys. He points out, however, that "the guidance of the blind depends mainly on the multitude of collateral indications, to which they give much heed, and not in their superiority in any of them."]

FIG. 616.



Æsthesiometer of Sieveking.

6. *Moistening* the skin with indifferent fluids increases the acuteness. If, however, the skin between two points, which are still felt as two distinct objects, be slightly tickled, or be traversed by an imperceptible electrical current, the impressions become fused (*Suslowa*). The sense of locality is rendered more acute at the cathode when a constant current is used (*Suslowa*), and when the skin is congested by stimulation (*Klinkenberg*), and also by slight stretching of the skin (*Schmey*); further, by baths of carbonic acid (*v. Basch and v. Dietl*), or warm common salt, and temporarily by the use of caffein (*Rumpf*).

7. *Anæmia*, produced by elevating the limbs, or *venous hyperæmia* (by compressing the veins), blunts the sense, and so does too frequent testing of the sense of locality, by producing fatigue. The sense is also blunted by cold applied to the skin, the influence of the anode, strong stretching of the skin, as over the abdomen during pregnancy, previous exertions of the muscles under the part of the skin tested, and some poisons, *e. g.*, atropin, daturin, morphin, strychnin, alcohol, potassium bromide, cannabin, and chloral hydrate.

Smallest Appreciable Distance.—The following statement gives the smallest distance, in *millimetres*, at which two points of a pair of compasses can still be distinguished as double by an adult. The corresponding numbers for a boy twelve years of age are given within brackets.

	Millimetres.
Tip of tongue,	1.1 [1.1]
Third phalanx of finger, volar surface,	2. –2.3 [1.7]
Red part of the lip,	4.5 [3.9]
Second phalanx of finger, volar surface,	4. –4.5 [3.9]
First phalanx of finger, volar surface,	5. –5.5
Third phalanx of finger, dorsal surface,	6.8 [4.5]
Tip of nose,	6.8 [4.5]
Head of metacarpal bone, volar,	5. –6.8 [4.5]
Ball of thumb,	6.5–7.
Ball of little finger,	5.5–6.
Centre of palm,	8. –9.
Dorsum and side of tongue, white of the lips, metacarpal part of the thumb,	9. [6.8]
Third phalanx of the great toe, plantar surface,	11.3 [6.8]
Second phalanx of the fingers, dorsal surface.	11.3 [9.]
Back,	11.3 [9.]

	Millimetres.
Eyelid,	11.3 [9.]
Centre of hard palate,	13.5 [11.3]
Lower third of the forearm, volar surface,	15.
In front of the zygoma,	15.8 [11.3]
Plantar surface of the great toe,	15.8 [9.]
Inner surface of the lip,	20.3 [13.5]
Behind the zygoma,	22.6 [15.8]
Forehead,	22.6 [18.]
Occiput,	27.1 [22.6]
Back of the hand,	31.6 [22.6]
Under the chin,	33.8 [22.6]
Vertex,	33.8 [22.6]
Knee,	36.1 [31.6]
Sacrum, gluteal region,	44.6 [33.8]
Forearm and leg,	45.1 [33.8]
Neck,	54.1 [36.1]
Back, at the fifth dorsal vertebra, lower dorsal and lumbar region,	54.1
Middle of the neck,	67.7
Upper arm, thigh, and centre of the back,	67.7 [31.6–40.6]

Illusions of the sense of locality occur very frequently; the most marked are: (1) A uniform movement over a cutaneous surface appears to be quicker in those places which have the finest sense of locality. (2) If we merely *touch* the skin with the two points of an æsthesiometer, then they feel as if they were wider apart than when the two points are *moved along* the skin (*Fechner*). (3) A sphere, when touched with short rods, feels larger than when long rods are used (*Tourtual*). (4) When the fingers of one hand are crossed, a small pebble or sphere placed between them feels double (**Aristotle's experiment**). [When a pebble is rolled between the crossed index and middle finger (Fig. 617, B), it feels as if two balls were present, but with the fingers uncrossed single.] (5) When pieces of skin are transplanted, *e.g.*, from the forehead, to form a nose, the person operated on feels, often for a long time, the new nasal part as if it were his forehead.

FIG. 617.

A. B.

Aristotle's Experiment.

Theoretical.—Numerous experiments were made by E. H. Weber, Lotze, Meissner, Czermak, and others, to explain the phenomena of the sense of space. **Weber's theory** goes upon the assumption, that one and the same nerve fibre proceeding from the brain to the skin can only take up one kind of impression, and administer thereto. He called the part of the skin to which each single nerve fibre is distributed a "**circle of sensation.**" When two stimuli act simultaneously upon the tactile end organ, then a double sensation is felt, when one or more circles of sensation lie between the two points stimulated. This explanation, based upon anatomical considerations, does not explain how it is that, with practice, the circles of sensation become smaller, and also how it is that only *one* sensation occurs, when both points of the instruments are so applied that both points, although further apart than the diameter of a circle of sensation, at one time lie upon two adjoining circles, at another between two others with another circle intercalated between them.

Wundt's Theory.—In accordance with the conclusions of Lotze, Wundt proceeds from a psycho-physiological basis, that every part of the skin with tactile sensibility always conveys to the brain the *locality* of the sensation. Every cutaneous area, therefore, gives to the tactile sensation a

"*local color*" or quality, which is spoken of as the **local sign**. He assumes that this local color diminishes from point to point of the skin. This gradation is very sudden in those parts of the skin where the sense of space is very acute, but occurs very gradually where the sense of space is more obtuse. Separate impressions unite into a common one, as soon as the gradation of the local color becomes imperceptible. By practice and attention differences of sensation are experienced, which ordinarily are not observed, so that he explains the diminution of the circles of sensation by practice. The circle of sensation is an area of the skin, within which the local color of the sensation changes so little that two separate impressions fuse into *one*.

427. PRESSURE SENSE.—By the sense of pressure we obtain a knowledge of the amount of weight or pressure which is being exercised at the time on the different parts of the skin.

A specific end apparatus arranged in a punctated manner is connected with the pressure sense (Fig. 618). These points or spots are called "**pressure spots**" or "**pressure points**" (*Blix*), and are endowed with varying degrees of sensibility; at some places (back, thigh) they are distinguished by a markedly pronounced after-sensation. The arrangement of the pressure spots follows the type of the arrangement of the temperature spots. The pressure spots have usually another direction than that of hot and cold spots; as a rule, they are denser. The minimal distance at which two pressure spots, when simultaneously stimulated, are felt as double, is—on the back, 4 to 6 mm.; breast, 0.8; abdomen, 1.5 to 2; cheek, 0.4 to 0.6; upper arm, 0.6 to 0.8; forearm, 0.5; back of the hand, 0.3 to 0.6; palm, 0.1 to 0.5; leg, 0.8 to 2; back of foot, 0.8 to 1; sole of foot, 0.8 to 1 mm.

FIG. 618.

Pressure spots. *a*, middle of the sole of the foot; *b*, skin of zygoma; *c*, skin of the back.

Methods.—1. Place, on the part of the skin to be investigated, different **weights**, one after the other, and ascertain what perceptions they give rise to, and the sense of the difference of pressure to which they give rise. We must be careful to exclude differences of temperature and prevent the displacement of the weights—the weights must always be placed on the same spot, and the skin should be covered beforehand with a disk, while the muscular sense must be eliminated (§ 430). [This is done by supporting the hand or part of the skin which is being tested, so that the action of all the muscles is excluded.] 2. A process is attached to a balance and made to touch the skin, while by placing weights in the scale pan or removing them, we test what differences in weight the person experimented on is able to distinguish (*Dohrn*). 3. In order to avoid the necessity of changing the weights, A. Eulenburg invented his **baræsthesiometer**, which is constructed on the same principle as a spiral spring paper clip or balance. There is a small button which rests on the skin and is depressed by the spring. An index shows at once the pressure in grammes, and the instrument is so arranged that the pressure can be very easily varied. 4. Goltz uses a **pulsating elastic tube**, in which he can produce waves of different height. He tested how high the latter must be before they are experienced as pulse waves, when the tube is placed upon the skin. 5. Landois uses a **mercurial balance** (Fig. 619). The beam of a balance (W) moves upon two knife edges (O, O), and is carried on the horizontal arm (*b*) of a heavy support (T). One arm of the beam is provided with a screw (*m*) on which an equilibrating weight (S) can be moved. The other arm (*d*) passes into a vertical calibrated tube (R). Below this is the pressure pad (P) which can be loaded as desired by a weight (G), and which can be placed upon the part of the skin to be tested (H). From an adjoining burette (B) held in a clamp (A), mercury can pass through a tube in the direction of the arrows, to one part of the balance and into the tube (R). On the stop-cock (*h*) being closed, whenever pressure is exerted on the tube (D, D), the mercury rises through *d* into R, and increases the pressure on P. We measure the weight of the mercury corresponding to each division of the tube (R). This instrument enables rapid variations of the weight to be made without giving rise to any shock. In estimating both the pressure sense and temperature sense, it is best to proceed on the principle of "**the least perceptible difference**," *i. e.*, the different pressures or temperatures are graduated, either beginning with *great* differences, or proceeding from the *smallest* difference, and determining the limit at which the person can distinguish a difference in the sensation.

Results.—1. The *smallest perceptible pressure*, when applied to different parts of the skin, varies very greatly according to the locality. The greatest acuteness of sensibility is on the forehead, temples and the back of the head and forearm, which perceive a pressure of 0.002 grm.; the fingers first feel with a weight of

0.005 to 0.015 grm.; the chin, abdomen and nose with 0.04 to 0.05 grm.; the finger nail 1 grm. (*Kammler and Aubert*).

The greater the sensibility of the skin, the more rapidly can stimuli succeed each other, and still be perceived as single impressions; 52 stimuli per second may be applied to the volar side of the upper arm, 61 on the back of the hand, 70 to the tips of the fingers, and still be felt singly (*Bloch*).

2. Intermittent variations of pressure, as in Goltz's tube, are felt more acutely by the tips of the fingers than with the forehead.

3. Differences between two weights are perceived by the tips of the fingers when the ratio is 29 : 30 (in the forearm as 18.2 : 20), provided the weights are not too light or too heavy. In passing from the use of very light to heavy weights, the acuteness or fineness of the perception of difference increases at once, but with

FIG. 619.



Landois' Mercurial Balance for Testing the Pressure Sense.

heavier weights, the power of distinguishing differences rapidly diminishes again (*E. Hering, Biedermann*). This observation is at variance with the psycho-physical law of Fechner (§ 383).

4. A. Eulenburg found the following gradations in the fineness of the pressure sense: The forehead, lips, dorsum of the cheeks and temples appreciate differences of $\frac{1}{40}$ to $\frac{1}{30}$ (200 : 205 to 300 : 310 grm.). The dorsal surface of the last phalanx of the fingers, the forearm, hand, 1st and 2d phalanx, the volar surface of the hand, forearm and upper arm, distinguish differences of $\frac{1}{10}$ to $\frac{1}{20}$ (200 : 220 to 220 : 210 grm.). The anterior surface of the leg and thigh are similar to the forearm. Then follow the dorsum of the foot and toes, the sole of the foot, and the posterior surface of the leg and thigh. Dohrn determined the smallest additional

weight, which, when added to 1 grm. already resting on the skin, was appreciated as a difference, and he found that for the 3d phalanx of the finger it was 0.499 grm.; back of the foot, 0.5 grm.; 2d phalanx, 0.771 grm.; 1st phalanx, 0.02 grm.; leg, 1 grm.; back of the hand, 1.156 grm.; palm, 1.018 grm.; patella, 1.5 grm.; forearm, 1.99 grm.; umbilicus, 3.5 grms.; and the back, 3.8 grms.

5. Too long time must not elapse between the application of two successive weights, but 100 seconds may elapse when the difference between the weights is 4 : 5 (*E. H. Weber*).

6. The sensation of an **after pressure** is very marked, especially if the weight is considerable and has been applied for a length of time. But even light weights, when applied, must be separated by an interval of at least $\frac{1}{480}$ to $\frac{1}{610}$ second, in order to be perceived. When they are applied at shorter intervals the sensations become fused. When Valentin pressed the tips of his fingers against a wheel provided with blunt teeth he felt the impression of a *smooth* margin, when the teeth were applied to the skin at the intervals above mentioned; when the wheel was rotated more slowly, each tooth gave rise to a distinct impression. Vibrations of strings are distinguished as such when the number of vibrations is 1506 to 1552 per second (*v. Wittich and Grünhagen*).

7. It is remarkable that pressure produced by the uniform compression of a part of the body, *e. g.*, by dipping a finger or arm in mercury, is not felt as such; the sensation is felt only at *the limit of the fluid*, on the volar surface of the finger, at the limit of the surface of the mercury.

428. TEMPERATURE SENSE.—The temperature sense makes us acquainted with the variations of the heat of the skin.

A specific end apparatus arranged in a punctated manner is connected with the temperature sense.

These "**temperature spots**" are arranged in a linear manner or in chains, which are usually slightly curved (Figs. 620, 621). They generally radiate from certain points of the skin, usually the hair roots. The chain of the "**cold spots**" usually does not coincide with those of the "**hot spots,**" although the point

FIG. 620.



A, cold spots, B, hot spots, from the volar surface of the terminal phalanx of the index finger to the margins of the nail.

FIG. 621.

C, cold spots, and D, warm spots of the radial half of the dorsal surface of the wrist. The arrow indicates the direction in which the hair points.

from which they radiate may be the same. Frequently, these punctated lines are not complete, but they may be indicated by scattered points, between which, not unfrequently points or spots for other qualities of sensation may be intercalated. Near the hairs there are almost always temperature spots. In parts of the skin, where the temperature sensibility is slight, the temperature points are present only near the hairs.

The sensation of cold occurs at once, while the sensation of heat develops gradually. Mechanical and electrical stimulation also excite the sensation of

temperature. A gentle touch of the temperature spots is not perceived; these points seem to be anæsthetic toward pressure and pain. As a general rule, the cold spots are more abundant over the whole body—there are more of them in a given area—while the hot spots may be quite absent. The hot spots are, as a rule, perceived as double at a greater distance apart than the cold spots. The minimal distance on the forehead is 0.8 mm. for the cold spots, and 4 to 5 mm. for the warm spots; on the breast the corresponding numbers are 2 and 4 to 5; back, 1.5 to 2 and 4 to 6; back of hand 2 to 3 and 3 to 4; palm, 0.8 to 2; thigh and leg, 2 to 3 and 3 to 4 mm.

Method.—To test the hot and cold spots, use a hot or cold metallic rod; at the cold spots, when they are lightly touched, only the sensation of cold will be felt, and a corresponding effect with a hot rod at the hot spots. Both spots are insensible to objects of the same temperature as the skin.

According to E. Hering, what determines the sensation of temperature is the temperature of the thermic end apparatus itself, *i. e.*, its zero temperature. As often as the temperature of a cutaneous area is *above* its **zero temperature**, we feel it as *warm;* in the opposite case, *cold.* The one or the other sensation is more marked, the more the one or other temperature varies from the zero temperature. The zero temperature can undergo changes within considerable limits, owing to external conditions.

Methods.—To the surface of the skin objects of the same size and with the same thermal conductivity are applied successively at different temperatures: 1. Nothnagel uses small wooden cups with a metallic base, and filled with warm and cold water, the temperature being registered by a thermometer placed in the cups. [2. Clinically, two test-tubes filled with cold and warm water, or two spoons, the one hot and the other cold, may be used.]

Results.—1. As a general rule, the feeling of cold is produced when a body applied to the skin robs it of heat; and, conversely, we have a sensation of warmth when heat is communicated to the skin.

2. The greater the thermal conductivity of the substance touching the skin, the more intense is the feeling of heat or cold (§ 218).

3. At a temperature of 15.5°–35° C., we distinguish distinctly differences of temperature of 0.2°–0.16° R. with the tips of the fingers (*E. H. Weber*). Temperatures just below that of the blood (33°–27° C.—*Nothnagel*) are distinguished most distinctly by the most sensitive parts, even to differences of 0.05° C. (*Lindermann*). Differences of temperature are less easily made out when dealing with temperatures of 33°–39° C., as well as between 14°–27° C. A temperature of 55° C., and also one a few degrees above zero (2.8° C.), cause distinct pain in addition to the sensation of temperature.

4. The sensibility for cold is generally greater than for warmth,—that of the left hand is greater than the right (*Goldscheider*). The different parts of the skin also vary in the acuteness of their thermal sense, and in the following order: Tip of the tongue, eyelids, cheeks, lips, neck and body. The perceptible minimum Nothnagel found to be 0.4° on the breast; 0.9° on the back; 0.3°, back of the hand; 0.4°, palm; 0.2, arm; 0.4°, back of the foot; 0.5°, thigh; 0.6°, leg; 0.4°–0.2°, cheek; 0.4°–0.3° C., temple. The thermal sense is less acute in the middle line, *e.g.*, the nose, than on each side of it (*E. H. Weber*). Fig. 622 shows that in one and the same portion of skin, the cold and hot spots are differently located, *i.e.*, their different topography.

If the mucous membrane of the mouth be penciled with a 10 per cent. solution of cocain, the sensibility for heat is abolished; the cooling sensation of menthol depends upon its stimulation of the cold nerves; CO_2 applied to the skin excites the heat nerves (*Goldscheider*).

5. Differences of temperature are most easily perceived when the same part of the skin is affected successively by objects of different temperature. If, however, two different temperatures act simultaneously and side by side, the impressions are apt to become fused, especially when the two areas are very near each other.

6. Practice improves the temperature sense; congestion of venous blood in the skin diminishes it; diminution of the amount of blood in the skin improves it (*M. Alsberg*). When *large* areas of the skin are touched, the perception of differences is more acute than with small areas. Rapid variations of the temperature produce more intense sensations than gradual changes of temperature. Fatigue occurs soon.

Illusions are very common: 1. The sensations of heat and cold sometimes alternate in a paradoxical manner. When the skin is dipped first into water at 10° C. we feel cold, and if it be then dipped at once into water at 16° C., we have at first a feeling of warmth, but soon again of cold. 2. The same temperature applied to a large surface of the skin is estimated to be greater than when it is applied to a small area, *e.g.*, the whole hand when placed in water at 29 5° C. feels warmer than when a finger is dipped into water at 32° C. 3. Cold weights are judged to be heavier than warm ones.

Pathological.—Tactile sensibility is only seldom *increased* (**hyperpselaphesia**), but great sensibility to differences of temperature is manifested by areas of the skin whose epidermis is partly removed or altered by vesicants or herpes zoster, and the same occurs in some cases of locomotor ataxia; while the sense of locality is rendered more acute in the two former cases and in erysipelas.

FIG. 622.



Cold and hot spots from the same part of the anterior surface of the forearm. *a*, cold spots; *b*, hot spots. The dark parts are the most sensitive, the hatched the medium, the dotted the feebly, and the vacant spaces the non-sensitive.

An abnormal condition of the sense of locality was described by Brown-Séquard, where three points were felt when only two were applied, and two when one was applied to the skin. Landois finds that in himself pricking the skin of the sternum over the angle of Ludovicus is always accompanied by a sensation in the knee. [Some persons, when cold water is applied to the scalp, have a sensation referable to the skin of the loins (*Stirling*).] A remarkable variation of the sense of locality occurs in moderate poisoning with morphia, where the person feels himself abnormally large or greatly diminished. In degeneration of the posterior columns of the cord, Obersteiner observed that the patient was unable to say whether his right or left side was touched ("**allochiria**"). Ferrier observed a case where a stimulus applied to the right side was referred to the left, and *vice versâ*.

Diminution and paralysis of the tactile sense (**Hypopselaphesia and Apselaphesia**) occur either in conjunction with simultaneous injury to the sensory nerves, or alone. It is rare to find that one of the qualities of the tactile sense is lost, *e.g.*, either the tactile sense or the sense of temperature—a condition which has been called "*partial tactile paralysis.*" Limbs which are "*sleeping*" feel heat and not cold (*Herzen*).

429. COMMON SENSATION—PAIN.—By the term **common sensation** we understand pleasant or unpleasant sensations in those parts of our bodies

which are endowed with sensibility, and which are not referable to external objects, and whose characters are difficult to describe, and cannot be compared with other sensations. Each sensation is, as it were, a peculiar one. To this belong pain, hunger, thirst, malaise, fatigue, horror, vertigo, tickling, well-being, illness, the respiratory feeling of free or impeded breathing.

Pain may occur wherever sensory nerves are distributed, and it is invariably caused by a stronger stimulus than normal being applied to sensory nerves. Every kind of stimulation, mechanical, thermal, chemical, electrical, as well as somatic (inflammation or disturbances of nutrition), may excite pain. The last appears to be especially active, as many tissues become extremely painful during inflammation (*e.g.*, muscles and bones), while they are comparatively insensible to cutting. Pain may be produced by stimulating a sensory nerve in any part of its course, from its centre to the periphery, but the sensation is invariably referred to the peripheral end of the nerve. This is the **law of the peripheral reference of sensations.** Hence, stimulation of a nerve, as in the scar of an amputated limb, may give rise to a sensation of pain which is referred to the parts already removed. Too violent stimulation of a sensory nerve in its course may render it incapable of conducting impressions, so that peripheral impressions are no longer perceived. If a sufficient stimulus to produce pain be then applied to the central part of the nerve, such an impression is still referred to the peripheral end of the nerve. Thus we explain the paradoxical **anæsthesia dolorosa.** In connection with painful impressions, the patient is often unable to localize them exactly. This is most easily done when a small injury (prick of a needle) is made on a peripheral part. When, however, the stimulation occurs in the course of the nerve, or in the centre, or in nerves whose peripheral ends are not accessible, as in the intestines, pain (as belly-ache), which cannot easily be localized, is the result.

Irradiation.—During violent pain there is not unfrequently irradiation of the pain (§ 364, 5), whereby localization is impossible. It is rare for pain to remain continuous and uniform; more generally there are exacerbations and diminutions of the intensity, and sometimes *periodic* intensification, as in some neuralgias.

The **intensity** of the pain depends especially upon the excitability of the sensory nerves. There are considerable individual variations in this respect, some nerves, *e. g.*, the trigeminus and splanchnic, being very sensitive. The larger the number of fibres affected the more severe the pain. The duration is also of importance, in as far as the same stimulation, when long continued, may become unbearable. We speak of piercing, cutting, boring, burning, throbbing, pressing, gnawing, dull, and other kinds of pain, but we are quite unacquainted with the conditions on which such different sensations depend. Painful impressions are abolished by **anæsthetics** and **narcotics**, such as ether, chloroform, morphia, etc. (§ 364, 5).

Methods of Testing.—To test the cutaneous sensibility, we usually employ the constant or induced electrical current. Determine first the *minimum sensibility*, *i. e.*, the strength of the current which excites the first trace of sensation, and also the *minimum of pain*, *i. e.*, the feeblest strength of the current which first causes distinct impressions of pain. The electrodes consist of thin metallic needles, and are placed 1 to 2 cm. apart.

Pathological.—When the excitability of the nerves which administer to painful sensations is increased, a slight touch of the skin, nay, even a breath of cold air, may excite the most violent pain, constituting **cutaneous hyperalgia**, especially in inflammatory or exanthematic conditions of the skin. The term **cutaneous paralgia** is applied to certain anomalous, disagreeable, or painful sensations which are frequently referred to the skin—itching, creeping, formication, cold, and burning. In cerebro-spinal meningitis, sometimes a prick in the sole of the foot produces a double sensation of pain and a double reflex contraction. Perhaps this condition may be explained by supposing that in a part of the nerve the condition is delayed (§ 337, 2). In **neuralgia** there is severe pain, occurring in paroxysms, with violent exacerbations and pain shooting into other parts (p. 648). Very frequently excessive pain is produced by pressure on the nerve where it makes its exit from a foramen or traverses a fascia.

Valleix's Points Douloureux (1841).—The skin itself to which the sensory nerve runs, especially at first, may be very sensitive; and when the neuralgia is of long duration the sensibility may

be diminished even to the condition of analgesia (*Türck*); in the latter case there may be pronounced anæsthesia dolorosa (p. 890).

Diminution or **paralysis** of the sense of pain (**hypalgia** and **analgia**) may be due to affections of the ends of the nerves, or of their course, or central terminations.

Metalloscopy.—In hysterical patients suffering from hemianæsthesia, it is found that the feeling of the paralyzed side is restored, when small metallic plates or larger pieces of different metals are applied to the affected parts (*Burcq, Charcot*). At the same time that the affected part recovers its sensibility the opposite limb or side becomes anæsthetic. This condition has been spoken of as transference of sensibility. The phenomenon is not due to galvanic currents developed by the metals; but it may be, perhaps, explained by the fact that, under physiological conditions, and in a healthy person, every increase of the sensibility on one side of the body, produced by the application of warm metallic plates or bandages, is followed by a diminution of the sensibility of the opposite side. Conversely, it is found that when one side of the body is rendered less sensitive by the application of cold plates, the homologous part of the other side becomes more sensitive (*Rumpf*).

430. MUSCULAR SENSE.—Muscular Sensibility.—The sensory nerves of the muscles (§ 292) always convey to us impressions as to the activity or non-activity of these organs, and in the former case, these impressions enable us to judge of the degree of contraction. It also informs us of the amount of the contraction to be employed to overcome resistance. Obviously, the muscular sense must be largely supported and aided by the sense of pressure, and conversely. E. H. Weber showed, however, that the muscle sense is finer than the pressure sense, as by it we can distinguish weights in the ratio of 39 : 40, while the pressure sense only enables us to distinguish those in the ratio of 29 : 30. In some cases there has been observed total cutaneous insensibility, while the muscular sense was retained completely. A frog deprived of its skin can spring without any apparent disturbance. The muscular sense is also greatly aided by the sensibility of the joints, bones, and fasciæ. Many muscles, *e. g.*, those of respiration, have only slight muscular sensibility, while it seems to be absent normally in the heart and non-striped muscle.

[The muscular sense stands midway between special and common sensations, and by it we obtain a knowledge of the condition of our muscles, and to what extent they are contracted; also the position of the various parts of our bodies and the resistance offered by external objects. Thus, sensations accompanying muscular movement are twofold—(*a*) the movements in the unopposed muscles, as the movements of the limbs in space; and (*b*) those of resistance where there is opposition to the movement, as in lifting a weight. In the latter case the sensations due to innervation are important, and of course in such cases we have also to take into account the sensations obtained from mere pressure upon the skin. Our sensations derived from muscular movements depend on the *direction and duration* of the movements. On the sensations thus conveyed to the sensorium, we form judgments as to the direction of a point in space, as well as of the distance between two points in space. This is very marked in the case of the ocular muscles. It is also evident that the muscular sense is intimately related to, and often combined with, the exercise of the sensation of touch and sight (*Sully*).]

Methods of Testing.—Weights are wrapped in a towel and suspended to the part to be tested. The patient estimates the weight by raising and lowering it. The *electro-muscular sensibility* also may be proved thus: cause the muscles to contract by means of induction shocks, and observe the sensation thereby produced. [Direct the patient to place his feet together while standing, and then close his eyes. A healthy person can stand quite steady, but in one with the muscular sense impaired, as in locomotor ataxia, the patient may move to and fro, or even fall (p. 697). Again, a person with his muscular sense impaired may not be able to touch accurately and at once some part of his body, when his eyes are closed.]

A healthy person perceives a weight of 1 gramme applied to his upper arm; when a weight of 15 grms. is applied, he perceives an addition of 1 grm. If the original weight be 50 grms., he will detect the addition of 2 grms.; if the original weight be 100 grms., he will detect 3 grms. The weight detectable by the individual finger varies. With the leg, when the weight is applied at the knee, the individual may detect 30 to 40 grms.; but sometimes only a greater weight. Often one can detect a difference of 10 to 20, or 30 to 70 grms.

Section of a sensory nerve causes disturbance of the fine graduation of movement (p. 668). Meynert supposes that the cerebral **centre** for muscular sensibility lies in the motor cortical centres, the muscles being connected by motor and sensory paths with the ganglionic cells in these centres.

Too severe muscular exercise causes the sensation of **fatigue**, *oppression*, and *weight* in the limbs (§ 304).

Pathological.—Abnormal increase of the muscular sense is rare (*muscular hyperalgia and hyperæsthesia*), as in *anxietas tibiarum*, a painful condition of unrest which leads to a continual change in the position of the limbs. In **cramp** there is intense pain, due to stimulation of the sensory nerves of the muscle, and the same is the case in inflammation. *Diminution* of the muscular sensibility occurs in some choreic and ataxic persons (§ 364, 5). In locomotor ataxia the muscular sense of the upper extremities may be normal or weakened, while it is usually considerably diminished in the legs. [The muscular sense is said to be increased in the hypnotic condition, and in somnambulists.]

REPRODUCTION AND DEVELOPMENT

431. FORMS OF REPRODUCTION.—I. Abiogenesis (Generatio æquivoca, sive spontanea, **spontaneous generation**).—It was formely assumed that, under certain circumstances, non-living matter derived from the decomposition of organic materials became changed spontaneously into living beings. While Aristotle ascribed this mode of origin to insects, the recent observers who advocate this form of generation restrict its action solely to the lowest organisms. Experimental evidence is distinctly against spontaneous generation. If organized matter be heated to a very high temperature in sealed tubes, and be thus deprived of all living organisms or their spores, there is no generation of any organism. Hence, the dictum, "Omne vivum ex ovo" (*Harvey*, or, ex vivo). Some highly organized invertebrate animals (Gordius, Anguillula, Tardigrada, and Rotatoria) may be dried, and even heated to 140° C., and yet regain their vital activities on being moistened (**Anabiosis**).

II. Division or **fission** occurs in many protozoa (amœba, infusoria). The organism, just as is the case with cells, divides, the nucleus when present taking an active part in the process, so that two nuclei and two masses of protoplasm forming two organisms are produced. The Ophidiasters among the echinoderms divide spontaneously, and they are said to throw off an arm which may develop into a complete animal. According to Trembley (1744), the hydra may be divided into pieces, and each piece gives rise to a new individual [although under normal circumstances the hydra gives off buds, and is provided with generative organs].

[**Division of Cells.**—Although a **cell** is defined as a "nucleated mass of living protoplasm," recent researches have shown that, from a histological as well as from a chemical point of view, a cell is really a very complex structure. The apparently homogeneous cell substance is traversed by a fine **plexus of fibrils**, with a homogeneous substance in its meshes, while a similar network of fibrils exists within the nucleus itself (Fig. 623).]

FIG. 623.

FIG. 624.



FIG. 623.—Changes in a cell nucleus during karyokinesis.

FIG. 624.—Typical nucleated cell of the intestinal epithelium of a flesh maggot. *mc*, membrane of cell; *mn*, membrane of nucleus; *pc*, cellular protoplasm, with the radiating *reticulum*, and the *enchylema* enclosed in its meshes; *pn*, plasma of nucleus; *bn*, nuclear filament showing numerous twists.

[The **nucleus** of a typical cell is a spherical vesicle, consisting of a **membrane** containing what is called "**achromatin**," because it is not readily stained by staining reagents. Flemming has also called it *nuclear fluid*, or intermediate substance. The achromatin substance is permeated by a delicate **reticular network**, or plexus of fibrils, which has been called "**chromatin**," "**nucleoplasm**," "**karyoplasma**," and "**karyomiton**." The network stains readily with pigments, hence the name "chromatin" given to it by Flemming. The nodal points of the network give a dotted or granular appearance to the nucleus, especially when it is examined with a low power. The nuclear

membrane also consists of chromatin (Fig. 624). In the meshes of the network lie **nucleoli**, which seem to differ in constitution, and perhaps in function. According to Flemming, there are principal and accessory nucleoli in some nuclei. In Carnoy's nomenclature the several parts are spoken of as a fine *reticulum* of fibrils, enclosing in its meshes a fluid—the *enchylema*—which contains various particles in suspension.]

[**Direct Cell Division.**—A cell may **divide directly**, as it were, by simple cleavage, and in the process the nucleus usually divides before the cell protoplasm. The nucleus becomes constricted in the centre, has an hour-glass shape, and soon divides into two.]

[**Indirect Cell Division.**—Recent observations, confirmed by a great number of investigators, conclusively prove that the process of division in cells is a very complicated one, the changes in the nucleus being very remarkable. The terms **karyokinesis, mitosis,** or **indirect division** have been applied to this process. Figs. 623, 625 show the changes that take place in the nucleus. The chromatin or **intranuclear network** (*a*, B) passes into a **convolution** of fibrils, while the nuclear envelope becomes less distinct, the fibrils at the same time becoming thicker and forming loops, which gradually arrange themselves around a centre (*c* and *d*) in the form of a **wreath, rosette,** or **spirem** (C). The fibres curve round both at the periphery and the centre and form loops; but when their peripheral connections are severed or dissolved, we obtain a star-shaped form or **aster** (D), composed of single loops radiating from the centre (*e*). The loops divide in the direction of their length; their number is doubled, but they are thinner. By this further subdivision, the whole is composed of fine radiating fibrils (*f*), which gradually arrange themselves around two poles, or new centres, to form the **barrel-form** or **pithode** (E); the two groups of loops then separate still further, and arrange themselves so as form a **diaster**, or double star (*g*), the two groups being sepa-

FIG. 625.

Mitosis. A, nuclear reticulum, resting state; B, preparing for division; C, wreath stage; D, monaster stage; E, barrel stage; F, diaster stage; G, daughter wreath stage; H, daughter cells, passing to resting stage.

rated by a substance called the **equatorial plate**. Each of the groups of fibrils becomes more elongated, and forms a nuclear spindle, which indicates the position of a new nucleus. The protoplasm separates into two parts. In each of these parts the chromatin rearranges itself into an irregular coil, and the whole is called **dispirem** (G), and when division is complete, the chromatin filaments assume the form seen in a resting nucleus. This whole complex process may be accomplished in 1 to 4 hours. The separate groups of fibrils again become convoluted, each group gets a nuclear membrane, while the cell protoplasm divides, and two **daughter nuclei** are obtained from the original cell.]

The following scheme represents some of the more important changes:—

Mother nucleus.	*Daughter nuclei.*
1. Network.	8. Network.
2. Convolution.	7. Convolution.
3. Wreath or Spirem.	6. Dispirem.
4. Aster.	5. Disaster.

Equatorial grouping of chromatin.

III. **Budding** or **gemmation** occurs in a well-marked form among the polyps and in some infusorians (Vorticella). A bud is given off by the parent, and gradually comes more and more to resemble the latter. The bud either remains permanently attached to the parent, so that a complex organism is produced, in which the digestive organs communicate with each other directly, or in some cases there may be a "colony" with a common nervous system, such as the polyzoa. In some composite animals (siphonophora) the different polyps perform different functions. Some have a digestive, others a motor, and a third a generative function, so that there is a physiological division of labor. Buds which are given off from the parent are formed internally in the rhizopoda. In some

animals (polyps, infusoria), which can reproduce themselves by buds or division, there is also the formation of male and female elements of generation, so that they have a sexual and a non-sexual mode of reproduction.

IV. Conjugation is a form of reproduction which leads up to the sexual form. It occurs in the unicellular Gregarinæ. The anterior end of one such organism unites with the posterior end of another; both become encysted, and form *one* passive spherical body. The conjoined structures form an amorphous mass, from which numerous globular bodies are formed, and in each of which numerous oblong structures—the pseudo navicelli—are developed. Those bodies become, or give rise to an amœboid structure, which forms a nucleus and an envelope, and becomes transformed into a gregarina.

Sexual reproduction requires the formation of the embryo from the conjunction of the male and female reproductive elements, the **sperm cell** and the **germ cell**. These products may be formed either in *one* individual (hermaphroditism, as in the flat worms and gasteropods), or in *two* separate organisms (male or female). Sexual reproduction embraces the following varieties:—

V. Metamorphosis is that form of sexual reproduction in which the embryo from an early period undergoes a series of marked changes of external form, *e. g.*, the chrysalis stage, and the pupa stage, and in none of these stages is reproduction possible. Lastly, the final sexually developed form (the imago stage in butterflies) is produced, which forms the sexual products whose union gives rise to organisms which repeat the same cycle of changes. Metamorphosis occurs extensively among the insects; some of them have several stages (holo-metabolic), and others have few stages (hemi-metabolic). It also occurs in some arthropoda, and worms, *e. g.*, trichina; the sexual form of the animal occurs in the intestine, the numerous *larvæ* wander into the muscles, where they become encysted, and form undeveloped sexual organs, constituting the pupa stage of the muscular trichina. When the encysted form is eaten by another animal, the sexual organs come into activity, a new brood is formed, and the cycle is repeated. Metamorphosis also occurs in the frog and in petromyzon. [This is really a condition in which the embryo undergoes marked changes of form before it becomes sexually mature.]

FIG. 626.

A ripe egg taken from the uterus of Tænia solium. *a*, Albuminous envelope; *b*, remains of the yelk; *c*, covering of the embryo; *d*, embryo with embryonal hooklets.

FIG. 627.



Encapsuled cysticercus from Tænia solium embedded in a human sartorius. Natural size.

VI. Alternation of Generations (*Steenstrup*).—In this variety some of the members of the cycle can produce new beings non-sexually, while in the final stage reproduction is always sexual. From a medical point of view, the life history of the **tapeworm** or **Tænia** is most important. The segments of the tapeworm are called **proglottides** (Fig. 631), and each segment is hermaphrodite, with testes, vas deferens, penis, ovary, etc., and numerous ova. The segments are evacuated with the fæces. The eggs are fertilized after they are shed (Fig. 626), and from them is developed an elliptical **embryo**, provided with six hooklets, which is swallowed by another animal, the host. These embryos bore their way into the tissues of the host, where they undergo development, forming the encysted stage (Cysticercus (Fig. 627), Coenurus, or Echinococcus (Fig. 630). The encysted capsule may contain one (cysticercus) or many (coenurus) sessile heads of the tænia. In order to undergo further development, the cysticercus must be eaten alive by another animal, when the head or **scolex** fixes itself by the hooklets and suckers to the intestine of its new host (Fig. 629), where it begins to bud and produce a series of new segments between the head and the last formed segment, and thus the cycle is repeated.

The most important flat worms are: **Tænia solium**, in man; the Cysticercus cellulosæ (Fig. 628), in the pig, when it constitutes the *measle* in pork; **Tænia mediocanellata** (Fig. 631), the encysted

stage, in the ox; **Tænia coenurus,** in the dog's intestine; the encysted stage, or Coenurus cerebralis, in the brain of the sheep, where it gives rise to the condition of "staggers"; **Tænia echinococcus,** in the dog's intestine: the embryos or scolices occur in the liver of man as "**hydatids.**"

The medusæ also exhibit alternation of generations, and so do some insects, especially the plant lice or aphides.

VII. Parthenogenesis (*Owen, v. Siebold*).—In this variety, in addition to sexual reproduction, new individuals may be produced without sexual union. The non-sexually produced brood is always

FIG. 628.

Cysticerci from Tænia solium removed from their capsule. 1, natural size; 2, magnified. *a*, embryo sac: *b*, cavity produced by budding of the embryo sac; *c*, suctorial disks and hooklets.

FIG. 629.

Cysticercus of Tænia solium, with its head and segments protruded. *a*, caudal sac; *b*, head of the tapeworm, with disks and hooklets (scolex); *c*, neck.

FIG. 630.

Part of an Echinococcus capsule, with developing buds. *a*, sheath; *b*, parenchymatous layer; *c*, germinating capsule filled with scolices.

of one sex, as in the bees. A bee hive contains a queen, the workers, and the drones or males. During the nuptial flight, the queen is impregnated by the males, and the seminal fluid is stored up in the receptaculum seminis of the queen, and it appears that the queen may voluntarily permit the contact of this fluid with the ova or withhold it. All fertilized eggs give rise to female, and all unfertilized ones to male bees.

VIII. Sexual reproduction without any intermediate stages occurs in, besides man, mammals, birds, reptiles, and most fishes.

432. TESTIS—SEMINAL FLUID.—[**Testis.**—In the testis or male reproductive organ, the seminal fluid which contains the male element or spermatozoa is formed. The **framework** of the gland consists of a thick, strong, white, fibrous covering, the **tunica albuginea,** composed chiefly of white, interlacing, fibrous tissue. Externally, this layer is covered by the visceral layer

FIG. 631.

Tænia Mediocanellata. Natural size.

of the serous membrane, or the **tunica vaginalis,** which invests the testis and epididymis. The tunica albuginea is prolonged for some distance as a vertical septum into the posterior part of the testis, to form the **mediastinum testis** or **corpus Highmori. Septa** or trabeculæ—more or less complete—stretch from the under surface of the T. albuginea toward the mediastinum, so that the

organ is subdivided thereby into a number of **compartments** or **lobules**, with their bases directed outward and their apices toward the mediastinum. From these, finer sustentacular fibres pass into the compartments to support the structures lying in these compartments.]

[**Arrangement of Tubules.**—Each compartment contains several **seminal tubules**, long convoluted tubules ($\frac{1}{100}$ in. in diam.) which rarely branch except at their outer end; they are about 2 feet in length and exceed 800 in number. These tubules run toward the mediastinum, those in one compartment uniting at an acute angle with each other, to form a smaller number of narrower straight tubules—**tubuli recti** (Fig. 632). These straight tubules open into a network of tubules in the mediastinum to form the **rete testis**, a dense network of tubules of irregular diameter (Fig. 632). From this network there proceed 12 to 15 wider ducts,—the **vasa efferentia**—which after emerging from the testis are at first straight, but soon become convoluted—and form a series of conical eminences—the **coni vasculosi**—which together form the head of the **epididymis**. These tubes gradually unite with each other and form the body and globus minor of the **epididymis**, which, when unraveled, is a tube about 20 feet long, terminating in the **vas deferens** (2 feet long), which is the excretory duct of the testis.]

FIG. 632.



Transverse section of the testis (low-power view).

[**Structure of a Tubule.**—The **seminal tubules** consist of a thick, well-marked basement membrane, composed of flattened nucleated cells arranged like membranes (Fig. 637). These tubes are lined by several layers of more or less cubical cells; there is an **outer** row of such cells next the basement membrane, and often showing a dividing large nucleus. Internal to these are several layers of **inner** large clear cells, with nuclei often dividing, so that they form many daughter cells which lie internal to them and next the lumen. From these daughter cells are formed the spermatozoa, and they constitute the **spermatoblasts**. These several layers of cells leave a distinct lumen. The **tubuli recti** are narrow in diameter, and lined by a single layer of squamous or flattened epithelium (Fig. 633). The **rete testis** consists merely of channels in the fibrous stroma without a distinct membrana propria, but lined by flattened epithelium. The **vasa efferentia** and **coni vasculosi** have circular smooth muscular fibres in their walls, and are lined by a layer of columnar ciliated epithelium with striated protoplasm. At the bases of these cells in some parts is a layer of smaller granular cells. These tubules form the **epididymis**, whose tubules have the same structure (Fig. 634). In sheep, pigment cells are often found in the basement membrane. The **vas deferens** is lined by several layers of columnar epithelium resting on a dense layer of fibrous tissue—the **mucosa**. Outside this is the **muscular coat**, a thick layer of non-striped muscle composed of a thick inner *circular*, and thick outer *longitudinal* layer, a thin submucous coat connecting the muscular and mucous coats together; outside all is the fibrous **adventitia**.]

[The **interstitial tissue** (Fig. 632), supporting the seminal tubules, is laminated and covered by endothelial plates, with slits or spaces between the lamellæ, which form the origin of the **lymphatics**. These lymph spaces are easily injected by the puncture method. In fact, if Berlin blue

be forced into the testis, the lymphatics of the testis and spermatic cord are readily filled with the injection. In some animals (boar), and to a less extent in man, dog, there are also fairly large polyhedral **interstitial cells**, often with a large nucleus and sometimes pigmented. They represent the residue of the epithelial cells of the Wolffian bodies (*Klein*), or, according to Waldeyer, they are plasma cells. The **blood vessels** are numerous, and form a dense plexus outside the basement membrane of the seminal tubules.]

Chemical Composition.—The **seminal fluid**, as discharged from the urethra, is mixed with the secretion of the glands of the vas deferens, Cowper's glands, and those of the prostate, and with the fluid of the vesiculæ seminales. Its *reaction* is neutral or alkaline, and it contains 82 per cent. of water, serum albumin, alkali albuminate, nuclein, lecithin, cholesterin, fats (protamin ?), phosphorized fat, salts (2 per cent.), especially phosphates of the alkalies and earths, together with sulphates, carbonates, and chlorides. The odorous body, whose nature is unknown, was called "*spermatin*" by Vauquelin.

Seminal Fluid.—The sticky, whitish-yellow seminal fluid, largely composed of a mixture of the secretions of the above-named glands, when exposed to the air, becomes more fluid, and on adding

FIG. 633.



Convoluted seminal tubule opening into a narrow straight tube.

FIG. 634.



Transverse section of the tubules of the epididymis.

water it becomes gelatinous, and from it separate whitish transparent flakes. When long exposed, it forms rhomboidal crystals, which, according to Schreiner, consist of phosphatic salts with an organic base (C_7H_9N). These **crystals** (Fig. 635) are said to be derived from the prostatic fluid, and are identical with the so-called Charcot's crystals (Fig. 149, *c*, and § 138). The **prostatic fluid** is thin, milky, amphoteric, or of slightly acid reaction, and is possessed of the seminal odor. The phosphoric acid necessary for the formation of the crystals is obtained from the seminal fluid. A somewhat similar odor occurs in the albumin of eggs not quite fresh. The non-poisonous ptomain, cadaverin (pentamethyldiamin of *Landenburg*), isolated by Brieger from dead bodies, has a similar odor. The secretion of the vesiculæ seminales of the guinea-pig contains much fibrinogen (p. 424).

The **spermatozoa** are 50 μ long, and consist of a flattened pear-shaped **head** (Fig. 636, 1 and 2, *k*), which is followed by a rod-shaped **middle piece**, *m* (*Schweigger-Seidel*), and a long tail-like prolongation or **cilium**, *f*. The spermatozoon is propelled forward by the to-and-fro movements of the tail, at the rate of 0.05 to 0.5 mm. per second; the movement is most rapid immediately after the fluid is shed, but it gradually becomes feebler.

Finer Structure.—The observations of Jensen have shown that the middle piece and head are still more complex, although this is not the case in human spermatozoa and those of the bull (*G. Retzius*). These consist of a flattened, long, narrow, transparent, protoplasmic mass, with a fibre composed of many delicate threads in both margins. At the tip of the tail both fibres unite into one. The fibre of the one margin is generally straight, the other is thrown into wave-like folds, or winds in a spiral manner round the other (*W. Krause, Gibbes*). G. Retzius describes a special terminal filament (Fig. 636, *e*). An axial thread surrounded by an envelope of protoplasm, traverses the middle piece and the tail (*Eimer, v. Braun*). [Leydig showed that in the salamander there is a delicate membrane attached to the tail, and Gibbes has described a spiral thread attached to the head (newt) and connected with the middle piece by a hyaline membrane.]

Motion of the Spermatozoa.—[After the discharge of the seminal fluid, the spermatozoa exhibit spontaneous movements for many hours or days.] The movements are due to the lashing movements of the tail, which moves in a circle or rotates on its long axis, the impulse to movement proceeding from the protoplasm of the middle piece and the tail, which seem to be capable of moving when they are detached (*Eimer*). These movements are comparable to those that occur in cilia (§ 292), and there are transition forms between ciliary and amœboid movements, as in the Monera. **Reagents.**—Within the testis they do not exhibit movement, as the fluid is not sufficiently dilute to permit them to move. Their movements are specially lively in the normal secretion of the female sexual organs (*Bischoff*), and they move pretty freely, and for a long time, in all normal animal secretions except saliva. Their movements are paralyzed by water, alcohol, ether, chloroform, creosote, gum, dextrin, vegetable mucin, syrup of grape sugar, or very alkaline or acid uterine or vaginal mucus (*Donné*), acids and metallic salts, and a too high or too low temperature. The narcotics, as long as they are chemically indifferent, behave as indifferent fluids, and so do medium solutions of urea, sugar, albumin, common salt, glycerin, amygdalin, etc.; but if these be too dilute or too concentrated, they alter the amount of water in the spermatozoa and paralyze them. The quiescence produced by water may be set aside by dilute alkalies (*Virchow*), as with cilia (p. 501). Engelmann finds that minute traces of acids, alcohol, and ether excite movements. The spermatozoa of the frog may be frozen four times in succession without killing them. They bear a heat of 43.75° C., and they will live for 70 days when placed in the abdominal cavity of another frog (*Mantegazza*).

Resistance.—Owing to the large amounts of earthy salts which they contain, when dried upon a microscopical slide, they still retain their form (*Valentin*). Their form is not destroyed by nitric, sulphuric, hydrochloric, or boiling acetic acid, or by caustic alkalies; solutions of NaCl and saltpetre (10 to 15 per cent.) change them into amorphous masses. Their organic basis resembles the semi-solid albumin of epithelium.

Seminal fluid, besides spermatozoa, also contains **seminal cells**, a few epithelial cells from the seminal passages, numerous lecithin granules, stratified amyloid bodies (inconstant), granular yellow pigment, especially in old age, leucocytes, and **sperma crystals** (*Fürbinger*).

FIG. 635.

Crystals from spermatic fluid.

Development of Spermatozoa.—The walls of the seminal tubules, *n*, which are made up of spindle-shaped cells, are lined by a nucleated, protoplasmic layer (Fig. 637, I, *b*, and IV, *h*), from which there project into the lumen of the tube long (0.053 mm.), column-like prolongations (I, *c*, and II, III, IV), which break up at their free end into several round or oval lobules (II)—the **spermatoblasts** (*v. Ebner*); these consist of soft, finely granular protoplasm, and usually have an oval nucleus in their lower part. During development, each lobule of the spermatoblast elongates into a tail (IV, *r*), while the deeper part forms the head and middle pieces of the future spermatozoon (IV, *k*). At this stage the spermatoblast is like a greatly enlarged, irregular, cylindrical, epithelial cell. When development is complete, the head and middle piece are detached (III, *t*), and ultimately the remaining part of the spermatoblast undergoes fatty degeneration. Not unfrequently in spermatozoa we may observe a small mass of protoplasm adhering to

the tail and the middle piece (III, *t*). Between the spermatoblasts are numerous round amœboid cells devoid of an envelope, and connected to each other by pro-

FIG. 636.



Spermatozoa. 1, human (× 600), the head seen from the side; 2, on edge; *k*, head; *m*, middle piece; *f*, tail; terminal filament; 3, from the mouse; 4, bothriocephalus latus; 5, deer; 6, mole; 7, green woodpecker; 8, black swan; 9, from a cross between a goldfinch (M) and a canary (F); 10, from cobitis.

ces es. They seem to secrete the *fluid* part of the semen, and they may therefore be called **seminal cells** (I, *s*, II, III, IV, *p*). A spermatozoon, therefore, is a detached, independently mobile cilium of an enlarged epithelial cell. Some ob-

FIG. 637.

Semi-diagrammatic spermatogenesis: I, Transverse section of a seminal tubule—*a*, membrane; *b*, protoplasmic lining; *c*, spermatoblast; *s*, seminal cells. II, Unripe spermatoblast—*f*, rounded ciliate lobules; *p*, seminal cells. IV, Spermatoblast, with ripe spermatozoa (*k*) not yet detached; tail, *r*; *n*, wall of the seminal tubule; *h*, its protoplasmic layer. III, Spermatoblast with a spermatozoon free, *t*.

servers adhere to the view that the spermatozoa are, in part at least, formed within round cells, by a process of endogenous development.

According to Benda and v. Ebner, the spermatoblasts are formed by the coalescence (copulation) of a group of seminal cells with the lower part of the foot plate and stalk of the spermatoblasts. Each seminal cell forms from its nucleus the head, and from its protoplasm the tail of a spermatozoon. For the complete formation of these parts, there must be a coalescence of the seminal cells with the spermatoblasts.

Shape.—The spermatozoa of most animals are like cilia with larger or smaller heads. The head is elliptical (mammals), or pear-shaped (mammals), or cylindrical (birds, amphibians, fish), or corkscrew (singing birds, paludina), or merely like hairs (insects—Fig. 636). Immobile seminal cells, quite different from the ordinary forms, occur in myriapoda and the oyster.

FIG. 638.

Section of a cat's ovary. The place of attachment or hilum is below. On the left is a corpus luteum.

433. THE OVARY — OVUM — UTERUS.—[Structure of the Ovary.—The ovary consists of a connective-tissue **framework**, with blood vessels, nerves, lymphatics and numerous non-striped muscular fibres. The **ova** are embedded in this matrix (Fig. 638). The surface of the ovary is covered with a layer of columnar epithelium (Fig. 639, *e*), the remains of the **germ epithelium**. The most superficial layer is called the **albuginea**; it does not contain any ova. Below it is the **cortical layer** of Schrön, which contains the smallest Graafian follicles ($\frac{1}{150}$ inch—Fig. 638), while deeper down are the larger follicles ($\frac{1}{30}$ to $\frac{1}{100}$ inch). There are 40,000 to 70,000 follicles in the ovary of a female infant. Each ovum lies within its follicle or **Graafian vesicle.**]

FIG. 639.

Section of an ovary. *e*, germ epithelium; 1, large sized follicles; 2, 2, middle sized, and 3, 3, smaller sized follicles; *o*, ovum within a Graafian follicle; *v*, *v*, blood vessels of the stroma; *g*, cells of the membrana granulosa.

Structure of an Ovum.—The human ovum (*C. E. v. Bear*, 1827) is 0.18 to 0.2 mm. [$\frac{1}{120}$ in.] in diameter, and is a spherical cellular body with a thick, solid, elastic envelope, the **zona pellucida**, with radiating striæ (Fig. 640). The zona pellucida encloses the cell contents represented by the protoplasmic, granular, contractile **vitellus** or **yelk**, which in turn contains the eccentrically placed spherical nucleus or **germinal vesicle** (40–50 μ—*Purkinje*, 1825; *Coste*, 1834). The germinal vesicle contains the nucleolus or **germinal spot** (5–7 μ—*R. Wagner*, 1835). The *chemical composition* is given in § 232.

[Ovum.			Cell
Zona pellucida	corresponds	to the	Cell wall.
Vitellus	"	"	Cell contents.
Germinal vesicle	"	"	Nucleus.
Germinal spot	"	"	Nucleolus.]

[This arrangement shows the corresponding parts in a cell and the ovum, and in fact the ovum represents a **typical cell.**]

The **zona pellucida** (Figs. 640, 641, V, Z), to which cells the Graafian follicles are often adherent, is a cuticular membrane formed secondarily by the follicle (*Pflüger*). According to Van

Beneden, it is lined by a thin membrane next the vitellus, and he regards the thin membrane as the original cell membrane of the ovum. The fine radiating striæ in the zona are said to be due to the existence of numerous canals (*Kölliker, v. Sehlen*). It is still undecided whether there is a special *micropyle* or hole for the entrance of the spermatozoa.

A **micropyle** has been observed in some ova (holothurians, many fishes, mussels). The ova of some animals (many insects, *e. g.*, the flea) have porous canals in some part of their zona, and these serve both for the entrance of the spermatozoa and for the respiratory exchanges in the ovum.

FIG. 640.



Ripe ovum of rabbit.

The development of the ova takes place in the following manner: The surface of the ovary is covered with a layer of cylindrical epithelium—the so-called "**germ epithelium**"—and between these cells lie somewhat spherical "**primordial ova**" (Fig. 641, I, *a*, *a*). The epithelium covering the surface dips into the ovary at various places to form "**ovarian tubes**" (Fig. 683). These tubes, from and in which the ova are developed (*Waldeyer*), become deeper and deeper, and they contain, in their interior, large, single spherical cells with a nucleus and a nucleolus, and other smaller and more numerous cells lining the tube. The large cells are the cells (**primordial ova**) that are to develop into ova, while the smaller cells are the epithelium of the tube, and are direct continuations of the cylindrical epithelium on the surface of the ovary. The upper extremities of the tubes become closed, while the tube itself is divided into a number of rounded compartments—snared off, as it were, by the ingrowth of the ovarian stroma (I, *c*). Each compartment so snared off usually contains one, or at most two, ova (IV, *o*, *o*), and becomes developed into a Graafian follicle. The embryonic follicle enlarges, and fluid appears within it; while its lateral small cells become changed into the epithelium lining the Graafian follicle itself, or those of the membrana granulosa. The cells of the membrana granulosa form an elevation at one part—the **discus proligerus**—by which the ovum is attached to the membrana granulosa. The follicles are at first only 0.03 mm. in diameter, but they become larger, especially at puberty. [The smaller ova are near the surface of the ovary, the larger ones deeper in its substance (Fig. 639).] When a Graafian follicle with its ovum is about to **ripen** (IV), it sinks or passes downward into the substance of the ovary, and enlarges at the same time by the accumulation of fluid—the **liquor folliculi**—between the tunica and membrana granulosa. It is covered by a vascular outer membrane—the **theca folliculi**—which is lined by the epithelium constituting the **membrana granulosa** (IV, *g*). When a **Graafian follicle** is about to **burst**, it again rises to the surface of the ovary, and attains a diameter of 1.0 to 1.5 mm., and is now ready to burst and discharge its ovum. [The tissue between the enlarged Graafian follicle and the surface of the ovary gradually becomes thinner and thinner and less vascular, and at last gives way, when the ovum is discharged and caught by the fimbriated extremity of the Fallopian tube embracing the ovary, so that the ovum is shed into the Fallopian tube itself.] Only a small number of the Graafian

follicles undergo development normally, by far the greatest number atrophy and never ripen. (The study of the development of the ova and the ovary was advanced particularly by Martin Barry, Pflüger, Billroth, Schrön, His, Waldeyer, Kölliker, Koster, Lindgren, Schulin, Foulis, Balfour and others.)

According to Waldeyer, the mammalian ovum is not a simple cell, but a compound structure. The original primitive ovum is, according to him, formed only of the germinal vesicle and germinal spot, with the surrounding membranous clear part of the vitellus (Fig. 641, III). The remainder of the vitellus is developed by the transformation of granulosa cells, which also form the zona pellucida.

Holoblastic and Meroblastic Ova.—The ova of frogs and cyclostomata have the same type as mammalian ova; they are called **holoblastic ova**, because all their contents go to form cells which take part in the formation of the embryo. In contrast with these, the birds, the monotremes alone among the mammals (*Caldwell*), the reptiles and the other fishes have **meroblastic ova** (*Reichert*).

FIG. 641.



I, An ovarian tube in process of development (newborn girl). *a*, *a*, young ova between the epithelial cells on the surface of the ovary; *b*, the ovarian tube with ova and epithelial cells; *c*, a small follicle cut off and enclosing an ovum. II, Open ovarian tube from a bitch. III, Isolated primordial ovum (human). IV, Older follicle with two ova (*o*, *o*) and the tunica granulosa (*g*) of a bitch. V, Part of the surface of a ripe ovum of a rabbit—*z*, zona pellucida; *d*, vitellus; *e*, adherent cells of the membrana granulosa. VI, First polar globule formed. VII, Formation of the second polar globule (*Fol*).

The latter, in addition to the white or formative yelk, which corresponds to the yelk of the holoblastic eggs, and gives rise to the embryonic cells, contains the food-yelk (yellow in birds), which during development is a reserve store of food for the developing embryo.

Hen's Egg.—The small, white, round, finely granular speck, the **cicatricula, blastoderm, or tread,** which is 2.5–3.5 mm. broad and 0.28–0.37 thick, lying upon the surface of the yellow yelk, corresponds to the contents of the mammalian ovum, and is, therefore, the formative yelk. In the cicatricula lie the germinal vesicle and spot (Fig. 642). From the tread in which lie the characteristic white yelk elements, processes pass into the yellow yelk. A part passes as an exceedingly thin layer round the yelk, or cortical protoplasm. [The cicatricula in an unincubated egg is always uppermost whatever the position of the egg, provided the contents can rotate freely, and this is due to the lighter specific gravity of that part of the yelk in connection with the cicatricula. In a fecundated egg the cicatricula has a white margin (the **area opaca**), surrounding a clear transparent area, the beginning of the **area pellucida**, containing an opaque spot in its centre. If an egg be boiled very hard and a section made of the yelk, it will be found to consist of alternating layers of

white and yellow yelk. The outermost layer is a thin layer of white yelk, which is slightly thicker at the margin of the cicatricula. Within the centre of the yelk is a flask-shaped mass of white yelk, the neck of the flask being connected with the white yelk outside. This flask shaped mass does not become so hard on being boiled, and its upper expanded end is known as the "**nucleus of Pander.**" The great mass of the yelk is made up, however, of yellow yelk.] **Microscopically,** the **yellow yelk** consists of soft yellow spheres, of from 23–100 μ in diameter, and they are often polyhedral from mutual pressure (Fig. 643, *b*). [They are very delicate and non-nucleated, but filled with fine granules, which are, perhaps, proteid in their nature, as they are insoluble in ether and alcohol. They are developed by the proliferation of the granulosa cells of the Graafian follicle, which also seem ultimately to form the granulo-fibrous double envelope or the **vitelline membrane** (*Eimer*). The whole yelk of the hen's egg is regarded by some observers as equivalent to the mammalian ovum *plus* the corpus luteum. Microscopically, the **white yelk** consists of small vesicles (5–75 μ) containing a refractive substance and larger spheres containing several smaller spherules (Fig. 643, *a*). The whole yelk is enveloped by the **vitelline membrane,** which is transparent, but possesses a fine fibrous structure, and it seems to be allied to elastic tissue.]

When the yelk is fully developed within the Graafian follicles of the hen's ovarium, the follicle bursts and discharges the yelk, which passes into the oviduct, where in its passage it rotates, owing to the direction of the folds of the mucous membrane of the oviduct. The numerous glands of the oviduct secrete the **albumin,** or white of the egg, which is deposited in layers around the yelk in its passage along the duct, and forms at the anterior and posterior **chalazae.** [The **chalazae** are two twisted cords composed of twisted layers of the outer denser part of the albumin. They extend

FIG. 642.



Scheme of a meroblastic egg.

FIG. 643.

a, White; *b*, yellow yelk granules.

from the poles of the yelk not quite to the outer part of the albumin.] [The albumin is invested by the **membrana testacea,** or **shell membrane,** which is composed of two layers—an outer thicker and an inner thinner one (Fig. 644). Over the greater part of the albumin these two layers are united, but at the broad end of the hen's egg they tend to separate, and air passing through the porous shell separates them more and more as the fluid of the egg evaporates. This air space is not found in fresh-laid eggs.] The layers consist of spontaneously coagulated keratin-like fibres arranged in a spiral manner around the albumin (*Lindvall and Hamarsten*). [External to this is the **test,** or **shell,** which consists of an organic matrix impregnated with lime salts.] The shell consists of albumin impregnated with lime salts, which form a very porous mortar. [The shell is porous, and its inner layer is perforated by vertical canals, through which the respiratory exchange of the gases can take place.] In the eggs of some birds there is an outer, structureless, porous, slimy, or fatty cuticula. The shell is secreted in the lower part of the oviduct. The shell is partly used up for the development of the bones of the chick (*Prout, Gruwe,* although this is denied by *Polt and Preyer*). The pigment which often occurs in many layers of the surface of the eggs of some birds appears to be a derivative of hæmoglobin and biliverdin.

Chemical Composition.—The **yellow yelk** is alkaline, and colored yellow owing to the presence of **lutein,** which contains iron. It contains several proteids [including a globulin body called **vitellin** (p. 424)], a body resembling nuclein, lecithin, vitellin, glycerin-phosphoric acid, cholesterin, olein, palmitin, dextrose, potassic chloride, iron, earthy phosphates, fluoric and silicic acids. The presence of cerebrin, glycogen, and starch is uncertain. [Dareste states that starch is present.]

[The **albumin of egg** contains—water, 86 per cent.; proteids, 12; fat and extractives, 1.5; saline matter, including sodic and potassic chlorides, phosphates, and sulphates, .5 per cent.]

[The **uterus**, a thick, hollow muscular organ, is covered externally by a **serous coat**, and lined

FIG. 644.



Fowl's egg after thirty hours' incubation. *a*, shell; *b*, shell membrane; *b'*, air chamber; *c*, boundary between outer and middle portion of albumin; *d*, more fluid albumin; *e*, chalazae; *v*, yelk; *av*, area opaca; *ao*, area vasculosa, and in its centre is the embryo.

FIG. 645.

Vertical section of the mucous membrane of the human uterus, *e*, columnar epithelium, the cilia absent; *gg*, utricular glands; *ct*, intra-glandular connective tissue; *vv*, blood vessels; *mm*, muscularis mucosæ.

FIG. 646.



Left broad ligament, Fallopian tube, ovary, and parovarium. *a*, uterus; *b*, isthmus of Fallopian tube; *c*, ampulla; *g*, fimbriated end of the tube, with the parovarium to its right; *e*, ovary; *f*, ovarian ligament.

internally by a **mucous membrane**, while between the two is the thick **muscular coat** composed of smooth muscular fibres arranged in a great number of layers and in different directions.

The mucous membrane of the body of the uterus in the unimpregnated condition has no folds, while the muscularis mucosæ is very well developed, and forms a great part of the uterine muscular wall. The mucous membrane is lined by a single layer of columnar ciliated epithelium. A vertical section shows the mucous membrane to contain numerous tubular glands (Fig. 645)—the **uterine glands**—which branch toward their lower ends. They have a membrana propria, and are lined by a single layer of ciliated epithelium, a small lumen being left in the centre. The utricular glands are not formed during intra-uterine life (*Turner*), nor are there any glands in the human uterus at birth (*G. J. Engelmann*). There are numerous slit-like *lymphatic* spaces in the mucous

FIG. 647.



Transverse section of the Fallopian tube.

membrane (*Leopold*), which communicate with well-marked lymphatic vessels existing in this and the other layers of the organ. In the **cervix**, the mucous membrane is folded, presenting in the virgin the appearance known as the arbor vitæ. The external surface of the vaginal part of the neck is covered by stratified squamous epithelium, like the vagina.]

[The **Fallopian tubes** are really the ducts of the ovaries (Fig. 646). They consist of a serous, muscular (an external longitudinal, and an internal circular) layer of non-striped muscle, and a mucous layer thrown into many folds and lined by a single layer of ciliated columnar epithelium, but no glands (Fig. 647).]

434. PUBERTY.—The term **puberty** is applied to the period at which a human being becomes capable of procreating, which occurs from the 13th to 15th years in the female, and the 14th to 16th in the male. In warm climates, puberty may occur in girls even at 8 years of age. Toward the 40th to 50th year, the procreative faculty ceases in the female with the cessation of the menses; this constitutes the **menopause** or **grand climacteric**, while in man the formation of seminal fluid has been observed up to old age. From the period of puberty onward, the sexual appetite occurs, and the ripe ova are discharged from the ovary. [But ova are discharged even before puberty or menstruation has occurred.] At puberty, the internal and external generative organs and their annexes become more vascular and undergo development; the pelvis of the female assumes the characteristic female shape. For the changes in the mammæ see § 230. At the same time hair is developed on the pubes and axilla, and in the male on the face, while the sebaceous glands become larger and more active.

Other changes occur, especially in the **larynx**. In the boy the larynx elongates in its antero-posterior diameter, the thyroid, or Adam's apple, becomes more prominent, while the vocal cords lengthen, so that the voice is hoarse, or husky, or "breaks," the voice being lowered at least an octave. In the female the larynx becomes longer, while the compass of the voice is increased. The vital capacity (§ 108), corresponding to the increase in the size of the chest, undergoes a considerable increase; the whole form and expression assume the characteristic sexual appearance, while the psychical energies also receive an impulse.

435. MENSTRUATION.—External Signs.—At regular intervals of time, of 27⅓–28 days in a mature female, there is a rupture of one or more ripe Graafian follicles, while at the same time there is a discharge of blood from the external genitals. This is known as the process of *menstruation* (or menses, catamenia, or periods). Most women menstruate during the first quarter of the moon, and only a few at new and full moon (*Strohl*). In mammals, the analogous condition is spoken of as the period of heat [or the "rut" in deer]. There is a slightly bloody discharge from the external genitals in carnivora, the mare and cow (*Aristotle*), while apes in their wild condition have a well-marked menstrual discharge (*Neubert*). [Observations on cases where abdominal section has been performed have shown that the Graafian follicles mature and burst at any time (*Lawson Tait, Leopold*).]

The **onset** of menstruation is usually heralded by constitutional and local phenomena—there is an increased feeling of congestion in the internal generative organs, pain in the back and loins, tension in the region of the uterus and ovaries, which are sensitive to pressure, fatigue in the limbs, alternate feeling of heat and cold, and even a slight increase of the temperature of the skin (*Kersch*). There may be retardation of the process of digestion and variations in the evacuation of the fæces and urine, and in the secretion of sweat. The discharge is *slimy* at first, and then becomes *bloody*, lasting three to four days; the blood is venous, and shows little tendency to coagulate, provided it is mixed with much alkaline mucus from the genital passages; but, if the hemorrhage be free, the blood may be clotted. The **quantity** of blood is 100 to 200 grms. [The blood contains many white blood corpuscles and epithelial cells.] After cessation of the discharge of blood there is a moderate amount of mucus given off.

FIG. 648. FIG. 649.

Diagram of the uterus just before menstruation. The shaded portion represents the mucous membrane.

Uterus when menstruation has just ceased, showing the cavity of the body deprived of mucous membrane (*J. Williams*).

The characteristic internal phenomena which accompany menstruation are: (1) The changes in the uterine mucous membrane; and (2) the rupture of the Graafian follicle.

1. Changes in the uterine mucous membrane.—The uterine mucous membrane is the chief source of the blood. The ciliated epithelium of the congested, swollen, and folded, soft, thick (3 to 6 mm.) mucous membrane is shed. The orifices of the numerous mucous glands of the mucous membrane are distinct, the glands enlarge, and the cells undergo *fatty degeneration*, and so do the tissue and the blood vessels lying between the glands. The tissue contains more leucocytes than normal. This fatty degeneration and the excretion of the degenerated tissue occur, however, only in the superficial layers of the mucosa, whose blood vessels, when torn across, yield the blood. The deeper layers remain intact, and from them, after menstruation is over, the new mucous membrane is developed (*Kundrat and G. J. Engelmann*). [Leopold denies the existence of this fatty degeneration. According to Williams, the entire mucous membrane is removed at each menstrual period, and it is regenerated from the muscular coat (Fig. 649). The mucous membrane of the cervix remains free from these changes.]

2. Ovulation.—The second important internal phenomenon is *ovulation*, in which process the ovary becomes more vascular—the ripe follicle is turgid with fluid, and in part projects above the surface of the ovary. The follicle ultimately

bursts, its membranes and the epithelium covering of the ovary are torn or give way under the pressure, the bursting being accompanied by the discharge of a small amount of blood. At the same time, the congested, turgid, and erected fimbriated extremity of the Fallopian tube is applied to the ovary, so that the discharged ovum, with its adherent granulosa cells, and the liquor folliculi, are caught by the funnel-shaped extremity of the tube (Fig. 646). The ovum, when discharged, is carried toward the uterus by the ciliated epithelium (§ 433) of the tube, and perhaps also partly by the contraction of its muscular coat. Ducalliez and Küss found that, by fully injecting the blood vessels, they could imitate the erection of the Fallopian tube. Rouget points out that the non-striped muscle of the broad ligaments may cause constriction of the vessels, and thus secure the necessary injection of the blood vessels of the Fallopian tube.

Pflüger's Theory.—There are two theories as to the connection between ovulation or the discharge of an ovum and the escape of blood from the uterine mucous membrane. Pflüger regards the bloody discharge from the superficial layers of the uterine mucous membrane as a physiological preparation or "freshening" of the tissue (in the surgical sense), by which it will be prepared to receive the ovum when the latter reaches the uterus, so that union can take place between the ovum and the freshly-exposed surface of the mucous membrane, and thus the ovum will receive nourishment from a new surface.

Reichert's Theory.—This view is opposed to that of Reichert, Engelmann, Williams, and others. According to Reichert's theory, before an ovum is discharged at all there is a sympathetic change in the uterine mucous membrane, whereby it becomes more vascular, more spongy, and swollen up. The mucous membrane so altered is spoken of as the *membrana decidua menstrualis*, and from its nature it is in a proper condition to receive, retain, and nourish a fertilized ovum which may come into contact with it. If the ovum, however, be not fertilized, and escape from the genital passages, then the uterine mucous membrane degenerates, and blood is shed as above described. According to this view, the hemorrhage from the uterine mucous membrane is a sign of the non-occurrence of pregnancy; the mucous membrane degenerates because it is not required for this occasion; the menstrual blood is an external sign that the ovum has not been impregnated. So that pregnancy, *i. e.*, the development of the embryo in utero, is to be calculated, not from the last menstruation, but from some time between the last menstruation and the period which does not occur.

FIG. 650.

Stroma of ovary.
Outer layer of follicle.
Vessels between outer layer and tunica propria.
Folded and thickened tunica propria.

Fresh corpus luteum.

FIG. 651.

Corpus luteum of cow (× 1½).

FIG. 652.

Lutein cells from the corpus luteum of cow.

In some cases the ovulation and the formation of the decidua menstrualis occur separately, so that there may be menstruation without ovulation, and ovulation without menstruation.

Corpus Luteum.—When a Graafian follicle bursts, it discharges its contents and collapses; in the interior are the remains of the membrana granulosa and a small effusion of blood, which soon coagulates. The small rupture soon heals, after the serum is absorbed. The vascular wall of the follicle swells up. Villous prolongations or granulations of young connective tissue, rich in capillaries and cells, grow into the interior of the follicle (Fig. 651). Colorless blood corpuscles also wander into the interior. At the same time the cells of the granulosa proliferate, and form several layers of cells, which ultimately, after the disappearance of a number of blood-vessels, undergo fatty degeneration, **lutein**, and *fatty* matter being formed, and it is this mass which gives the corpus luteum its yellow color (Fig. 652). The capsule becomes more and more fused with the ovarian stroma. If pregnancy does not take place after the menstruation, then the fatty matter is rapidly absorbed, and the effused blood is changed into hæmatoidin (§ 20) and other derivatives of hæmoglobin, while there is a gradual shriveling of the whole mass, which is complete in about four weeks, only a very small remainder being left. Such a corpus luteum *i.e.*, one not accompanied by pregnancy, is called a **false corpus luteum.** If, however, pregnancy occurs, then the corpus luteum, instead of shriveling, grows and becomes a large body, especially at the third and fourth month, the walls are thicker, the color deeper, so that the corpus luteum at the period of delivery may be 6 to 10 mm. in diameter, and its remains may be found in the ovary for a very long time thereafter (Fig. 651). This form is sometimes spoken of as a **true corpus luteum.** [We cannot draw a sharp distinction between these two forms.] Only a very small number of the ova in the ovary undergo development and are discharged; by far the greater number degenerate (*Slavjansky*).

436. PENIS—ERECTION.—Penis.—[The penis is composed of the two long cylindrical **corpora cavernosa,** the **corpus spongiosum,** which lies between and below them, and surrounds the urethra; these are held together by fibrous and muscular sheaths, and are composed of **erectile tissue.**] Our knowledge of the distribution of the blood within the penis is chiefly due to C. Langer's researches. The albuginea of the corpus spongiosum consists of tendinous connective tissue, containing thickly-woven elastic tissue and smooth muscular fibres, which together form a solid fibrous envelope, from which numerous interlacing trabeculæ pass into the interior, so that the corpus spongiosum comes to resemble a sponge. The anastomosing spaces bounded by these trabeculæ form a series of inter-communicating venous spaces or sinuses filled with blood and lined by a layer of endothelium constituting erectile tissue (Fig. 653). The largest sinuses lie in the lower and external part of the corpus cavernosum, while they are less numerous and smaller in the upper part. The small **arteries** arise from the A. profunda penis, which runs along the septum, and pass to the trabeculæ after following a very sinuous course. At the outer part of the corpus spongiosum, some of the small arteries become directly continuous with the larger venous sinuses; some of them, however, terminate in capillaries, both in the outer part and within the corpus spongiosum, the *capillaries* ultimately terminating in the venous sinuses. The helicine arteries of the penis described by Joh. Müller are merely much twisted arteries. The *deep veins* of the penis arise by fine veinlets within the body of the organ, while the veins proceeding from the cavernous spaces pass to the dorsum of the penis to form the *vena dorsalis penis*. As these vessels have to traverse the meshes of the vascular network in the cortex of the corpora cavernosa penis, it is evident that, when the network is congested by being filled with blood, it must compress the outgoing venous trunks. The corpus cavernosum urethræ consists for the most part of an external layer of closely packed anastomosing veins, which surround the longitudinally directed blood vessels of the urethra.

FIG. 653.

Erectile tissue. *a*, trabeculæ of connective tissue with elastic fibres and smooth muscle (*c*); *b*, venous spaces.

In the dog, all the arteries of the penis run at first toward the surface, where they divide into penicilli. The veins arise from the capillary loops in the papillæ, and they empty their blood into

the cavernous spaces. Only a small part of the blood passes to the cavernous spaces through the internal capillaries and veins, but arterial blood never flows directly into these spaces (*M. v. Frey*).

Mechanism of Erection.—Erection is due to the overfilling of the blood vessels of the penis with blood, whereby the volume of the organ is increased four or five times, while, at the same time, there are also a higher temperature, increased blood pressure (to $\frac{1}{6}$ of that in the carotid—*Eckhard*), with at first a pulsatile movement, increased consistence, and erection of the organ.

Regner de Graaf obtained complete erection of the penis by forcibly injecting its blood vessels (1668).

The **preliminary phenomena** consist in a considerable increase of the arterial blood supply, the arteries being dilated and pulsating strongly. The arteries are controlled by the nervi erigentes. The **nervi erigentes** [called by Gaskell the pelvic splanchnics (Fig. 439)] arise chiefly from the second (more rarely the third) sacral nerves (dog), and have ganglionic cells in their course (*Lovèn, Nikolsky*). These nerves contain **vaso-dilator fibres**, which can be excited in part reflexly from the sensory nerves of the penis, the transference centre being in the centre for erection in the spinal cord (§ 372, 4). Sensory impressions produced by voluntary movements of the genital apparatus (by the ischio- and bulbo-cavernosi and cremaster muscles) can also discharge this reflex; while the thought of sexual impulses, referable to the penis, tends to induce erection. The nervi erigentes also supply the longitudinal fibres of the rectum (*Fellner*).

FIG. 654.



Anterior wall of the pelvis with the uro-genital septum seen from the front. The corpus cavernosum (4) with the urethra (3) is cut across below its exit from the pelvis. 1, symphysis pubis; 2, dorsal vein of the penis; 5, part of the bulbo-cavernosus; *t*, deep transversus perinei with its fascia (*f*); 6, vena profunda penis; 7, artery and vein of the bulbo-cavernosus.

The **centre for erection** in the spinal cord (§ 362, 2) is, however, controlled by the dominating vaso-dilator centre in the medulla oblongata (§ 372), and the two centres are connected by fibres within the cord; hence stimulation of the upper part of the cord, as by asphyxiated blood (§ 362, 5) or muscarin, may also be followed by erection (*Nikolsky*). [The seminal fluid is frequently found discharged in persons who have been hanged.]

The *psychical activity of the cerebrum* has a decided influence on the genital vaso-dilator nerves. Just as the psychical disturbance which accompanies anger or shame is followed by dilatation of the blood vessels of the head, owing to stimulation of the vaso-dilator fibres, so when the attention is directed to the sexual centres there is an action upon the nervi erigentes. This action of the brain is more comprehensible, since we know that the diameter of the blood vessels is affected by the cortex cerebri (§ 377). The fibres probably pass from the cerebrum through the peduncles of the cerebrum and the pons; as a matter of fact, if these parts be stimulated erection may take place (§ 362, 4) (*Eckhard*).

When the impulse to erection is obtained by the increased supply of arterial blood, the *full completion* of the act is brought about by the activity of the following

transversely striped **muscles**: (1) The *ischio-cavernosus* arises from the coccyx, and by its tendinous union surrounds the root of the penis (Fig. 172). When it contracts, it compresses the root of the penis from above and laterally, so that the outflow of blood from the penis is hindered. It has no action on the dorsal vein of the penis, as this vessel lies in a groove on the dorsum of the penis, and is therefore protected from compression by the tendon. (2) The *deep transversus perinei* is perforated by the venæ profundæ penis, which come from the corpora cavernosa, so that when it contracts it must compress these veins between the tense horizontal fibres (Fig. 654, 6). The deep veins of the penis join the common pudendal vein and the plexus Santorini. (3) Lastly, the *bulbo-cavernosus* is concerned in the hardening of the urethral corpus spongiosum, as it compresses the bulb of the urethra (Figs. 654, 5, 172). All these muscles are partly under the control of the will, whereby the erection may be increased. Normally, however, their contraction is excited **reflexly** by stimulation of the sensory nerves of the penis (§ 362, 4).

The congestion of blood is not complete, else, in pathological cases, continuous erection, as in satyriasis, would give rise to gangrene. The accumulation of the blood in the penis is favored by the fact that the origins of the veins of the penis lie in the corpus cavernosum, which, when it enlarges, must compress them. There are also trabecular, smooth, muscular fibres, which compress the large venous plexus of Santorini.

That erection is a complex motor act depending on the nervous system, is proved by an experiment of Hausmann, who found that section of the nerves of the penis prevented erection in a stallion. The imperfect erection which occurs in the female is confined to the corpora cavernosa clitoridis and the bulbi vestibuli. During erection, the passage from the urethra to the bladder is closed, partly by the swelling of the caput gallinaginis, and partly by the action of the sphincter urethræ, which is connected with the deep transversus perinei.

437. EJACULATION—RECEPTION OF THE SEMEN.—In connection with the **ejaculation** of the seminal fluid, we must distinguish two different factors—(1) its passage from the testicles to the vesiculæ seminales; (2) the act of ejaculation itself. The former is caused by the newly-secreted fluid forcing on that in front of it, by the action of the ciliated epithelium (which lines the epididymis to the beginning of the vas deferens), and also by the peristaltic movements of the smooth muscular fibres of the vas deferens. Ejaculation, however, requires strong peristaltic contractions of the vasa deferentia and the vesiculæ seminales, which are brought about by the reflex stimulation of the ejaculation centre in the spinal cord (§ 362, 5). As soon as the seminal fluid reaches the urethra, there is a rhythmical contraction of the bulbo-cavernosus muscle (produced by the mechanical dilatation of the urethra), whereby the fluid is forcibly ejected from the urethra. Both vasa deferentia and vesiculæ do not always eject their contents into the urethra simultaneously. With moderate excitement the contents of only one may be discharged. The ischio-cavernosus and deep transversus perinei contract at the same time as the bulbo-cavernosus, although the former have no effect on the act of ejaculation. In the female also, under normal circumstances, at the height of the sexual excitement there is a reflex movement corresponding to ejaculation. It consists of a movement analogous to that in man. At first there is a reflex peristaltic movement of the Fallopian tube and uterus, proceeding from the end of the tube toward the vagina, and produced reflexly by the stimulation of the genital nerves. Dembo observed that stimulation of the anterior upper wall of the vagina in animals caused a gradual contraction of the uterus. By this movement, corresponding to that of the vasa deferentia in man, a certain amount of the mucus normally lining the uterus is forced into the vagina.

This is followed by the rhythmical contraction of the sphincter cunni (analogous to the bulbo-cavernosus), also of the ischio-cavernosus, and deep transversus perinei. The uterus is erected by the powerful contraction of its muscular fibres and round ligaments, while at the same time it descends toward the vagina, its cavity is more and more diminished, and its mucous contents are forced out. When

the uterus relaxes after the stage of excitement, it aspirates into its cavity the seminal fluid injected into the vestibule (*Aristotle, Bischoff*).

But the suction of the greatly excited uterus is not necessary for the reception of the semen (*Aristotle*). The spermatozoa may wriggle by their own movements from the vagina into the orifice of the uterus (*Kristeller*). The cases of pregnancy where, from some pathological causes (partial closure of the vagina or vulva), the penis has not passed into the vagina during coition, prove that the spermatozoa can traverse the whole length of the vagina, and pass into the uterus.

438. FERTILIZATION OF THE OVUM.—The **ovum** is fertilized by one **spermatozoon** passing into it.

Swammerdam († 1685) proved that contact of the semen with the ovum was necessary for fertilization. Spallanzani (1768) proved that the fertilizing agent was the spermatozoa, and not the clear filtered fluid part of the semen, and that the spermatozoa, even after being enormously diluted, were still capable of action. Martin Barry (1850) was the first to observe the entrance of a spermatozoon into the ovum of the rabbit. This occurs pretty rapidly, by a boring movement through the vitelline membrane (*Leuckhart*). The entrance is effected either through the porous canals or the micropyle (*Keber*, p. 902).

Theories.—As to the manner in which the spermatozoon affects the ovum, there are great differences of opinion. Aristotle compared it to an action like that of rennet on milk; Bischoff, to that of yeast on a fermentable mass, *i. e.*, to a catalytic action. These theories, however, are quite unsatisfactory, as we know that the unfertilized ova of the hen, rabbit (*Hensen*), pig (*Bischoff*), salpa (*Kuppfer*) (but not the frog—*Pflüger*) can undergo the initial stages of development as far as the stage of cleavage, and the star fishes even as far as the larval form (*Greef*.)

Place of Fertilization.—The place where fertilization occurs is either the *ovary*, as indicated by the occurrence of abdominal pregnancy, or the *Fallopian tube*, and the numerous recesses in the latter afford a good temporary nidus for the spermatozoa. This view is supported by the occurrence of tubal pregnancy. Thus, the spermatozoa must be able to pass through the Fallopian tube to the ovary, which is probably brought about chiefly by the movements proper to the spermatozoa themselves. It is uncertain whether the peristaltic movements of the uterus and Fallopian tube are concerned in this process; certainly ciliary movement is not concerned, as the cilia of the Fallopian tube act from above downward. When once the ovum has passed unfertilized into the uterus, it is not fertilized in the uterus. It is assumed that the ovum reaches the uterus within 2 to 3 weeks (in the bitch, 8 to 14 days).

Twins occur in 1 in 87 pregnancies, but oftener in warm climates; triplets, 1 : 7600; four at a birth, 1 : 330,000. More than six at a time have not been observed. The average number of pregnancies in a woman is 4½.

Superfecundation.—By this term is understood the fertilization of two ova at the *same menstruation*, by two different acts of coition. Thus, a mare may throw a foal and a mule, after being covered first by a stallion and then by an ass. A white and a black child have been born as twins by a woman.

Superfœtation is when a second impregnation takes place at a *later* period of pregnancy, as in the second or third month. This, however, is only possible in a double uterus, or when menstruation persists until the time of the second impregnation. It is said to occur frequently in the hare.

Hybrids are produced when there is a cross between *different species* (horse, ass, zebra—dog, jackal, wolf—goat, ibex—goat, sheep—species of llama—camel, dromedary—tiger, lion—species of pheasant—goose, swan—carp, crucian—species of butterflies). Most hybrids are sterile, especially as regards the formation of properly formed spermatozoa; while the hybrid females are for the most part fertile with the male of both parents, *e. g.*, the mule; but the characters of the offspring tend to return to those of the species of the parents. Very few hybrids are fertile when crossed by hybrids. In many species of frogs the absence of hybrids is accounted for by the mechanical obstacles to fertilization of the ova.

Tubal Migration of the Ovum.—Under exceptional circumstances, the ovum discharged from a ruptured Graafian follicle passes into the Fallopian tube of the *other* side, as is proved by the occurrence of tubal pregnancy and pregnancy of an abnormal rudimentary horn of the uterus, in which case the true corpus luteum is found on the *other side* of the ovary. This is spoken of as "**external migration**" (*Kussmaul, Leopold*). This observation coincides with experiment, as granular fluids, *e.g.*, China-ink, when injected into the peritoneal cavity, pass

into both Fallopian tubes, and are carried by the ciliated epithelium to the uterus (*Pinner*). In animals with a double uterus with two orifices, the ova may migrate through the os of the one into the other uterus, a condition which is spoken of as "**internal migration.**"

439. **IMPREGNATION—CLEAVAGE—LAYERS OF THE EMBRYO.—Maturation of the Ovum.**—In birds and mammals, important changes occur in the ovum **before impregnation.** The germinal vesicle comes to the surface and disappears from view, while the germinal spot also disappears. In place of the germinal vesicle, a spindle-shaped body appears. The granular elements of the protoplasmic vitellus arrange themselves around each of the two poles of the spindle, in the form of a star, the double star, or diaster of Fol—**nuclear spindle** (Figs. 655, 656). When this takes place, the *peripheral pole* of the nucleus or altered germinal vesicle, along with some of the cellular substance of the ovum, protrudes upon the surface of the vitellus, where they are nipped off from the ovum in the form of small corpuscles just like an excretory product (Fig. 657). These bodies, which are not made use of in the further development and growth of the ovum, are called **polar** or **directing globules** (*Fol, Bütschli, O. Hertwig*), although the elimination of small bodies from the yelk was known to

FIG. 655.

Formation of polar globules in a star-fish (Asterias glacialis). A, ripe ovum with eccentric germinal vesicle and spot; B–E, gradual metamorphosis of germinal vesicle and spot, as seen in the *living egg*, into two asters; F, formation of first polar globule, and withdrawal of the remaining part of the nuclear spindle within the ovum; G, surface view of living ovum with view of first polar globule; H, formation of second polar globule; I, a later stage, showing the remaining internal part of the spindle in the form of two clear vesicles; K, ovum with two polar globules and radial striæ around the female pronucleus; L, extrusion of polar globule. (*Geddes:* A–K, after *Fol;* L, after *O. Hertwig.*)

FIG. 656.



Egg of Scorpæna scrofa. The germinal vesicle is extruding a polar globule, and withdrawing toward the centre of the ovum. Near it is the male pronucleus.

Dumortier [1837], Bischoff, P. J. van Beneden, Fritz Müller [1848], Rathke, and others. The remaining part of the germinal vesicle stays within the vitellus and travels back toward the centre of the ovum, to form the **female pronucleus** (*O. Hertwig, Fol, Selenka, E. van Beneden*). [Before, however, the altered germinal vesicle travels downward again into the substance of the ovum, it divides again as before, and from it is given off the second polar globule, and then the remainder of the germinal vesicle forms the female pronucleus (Fig. 655). At the same time the vitellus shrinks somewhat within the vitelline membrane.]

Impregnation.—As a rule, only one spermatozoon penetrates the ovum, and as it does so, it moves toward the female pronucleus, while its head becomes surrounded with a star; it then loses its head and cilium, or tail, the latter only serving as a motor organ, while the remaining middle piece swells up to form a second new nucleus, the **male pronucleus** (*Fol, Selenka*). According to Flemming, it is the anterior part of the head, and according to Rein and Eberth, it is the head which is so changed. Thereafter, the male and female pronucleus unite, undergoing amœboid movements at the same time, to form the **new nucleus** of the *fertilized ovum.* The female pronucleus receives the male pronucleus in a little depression on its surface. Thereafter the yelk assumes a radiate appearance

(*Rein*). [The union of the representatives of the male and female elements forms the *first embryonic segmentation sphere* or **blastosphere**, which divides into two cells, and these again into four, and so on (Fig. 658).]

FIG. 657.



Egg of a Star-fish (Asteracanthion) with two extruded polar globules. Male and female pronuclei near each other.

In Echinoderms, O. Hertwig and Fol observed that several embryos were formed when, under abnormal conditions, several spermatozoa penetrated an ovum. The male pronuclei, formed from the several spermatozoa, then fused each with a fragment of the female pronucleus. Under similar circumstances, Born observed in amphibians abnormal cleavage, but no further development.

Cleavage of the Yelk.—In an ovum so fertilized the yelk contracts somewhat around the newly-formed nucleus, so that it becomes slightly separated from the vitelline membrane, and for the first time the nucleus and the yelk divides into two nucleated spheres. This process is spoken of as a **complete cleavage** or *fission* (Fig. 658). Each of these two cells again divides into two, and the process is repeated, so that

FIG. 658.



Segmentation of a rabbit's ovum. *a*, two-celled stage; *b*, four-celled stage; *c*, eight-celled stage; *d*, *e*, many blastomeres showing the more rapid division of the outer-layer cells, and the gradual enclosure of the inner-layer cells; *ect*, outer-layer cells; *ent*, inner-layer cells; *pgl*, polar globules; *zp*, zona pellucida.

4, 8, 16, 32, and so on, spheres are formed (Fig. 659). This constitutes the cleavage of the yelk, and the process goes on until the whole yelk is subdivided into numerous small, nucleated spheres, the "**mulberry mass**" or "**segmentation spheres**" or "**morula**," or the protoplasmic primordial spheres (20 to 25 μ) which are devoid of an envelope. [Each cell divides by a process of karyokinesis. According to Van Beneden, the segmentation begins in 1–2 hours after the union of the pronuclei, and the process is complete in about 75 hours. These primitive cells, from which all the tissues of the future embryo are formed, are called **blastomeres**.]

FIG. 659.

Cleavage of the yelk of the egg of Anchylostomum duodenale.

Variation of Lines of Cleavage.—According to the observations of Pflüger, the ova of the frog can be made to undergo cleavage in very different directions, according to the angle between the axis of the egg and the line of gravitation. This, of course, we can alter as we please, by placing the eggs at any angle to the line of gravitation. By the axis of the ovum is meant a line connecting the centre of the black surface and the middle of the white part, which, in the fertilized ovum, is always vertical. In such cases of abnormal cleavage the deposition of the organs takes place from other constituents of the egg than those from which they are formed under normal conditions. Under normal circumstances, according to Roux, the first line of cleavage in the frog is in the same direction as the central nervous system. The second intersects the first at a right angle, so as to divide the mass of ovum into two *unequal* parts, the larger of which forms the anterior part of the embryo.

Blastoderm.—During this time the ovum is enlarging by absorption of fluid into its interior. All the cells, from mutual pressure against each other, become polyhedral, and are so arranged as to form a cellular envelope or bladder, the **blastoderm** or **germinal membrane**, which lies on the internal surface of the vitelline membrane (*De Graaf, v. Baer, Bischoff, Coste*). A small part of the cells not used in the formation of the blastoderm is found on some part of the latter. [In the ovum of the **bird**, where there is only **partial segmentation**, the blastoderm is a small, round body resting on the surface of the yelk, under the vitelline membrane, so that it does not completely surround the yelk, or a hollow cavity, as in mammals. In mammals, this cavity is called the **segmentation cavity.**]

FIG. 660.



Blastodermic vesicle of a rabbit. *ect*, ectoderm, or outer layer of cells; *ent*, inner layer of cells.

FIG. 661.



Pr, primitive streak; *R*, medullary groove; *U*, first proto-vertebra.

The hollow sphere, composed of cells, is called the **blastodermic vesicle** by Reichert (Fig. 660), and in the human embryo it is formed at the 10th to 12th day, in the rabbit at the 4th, the guinea-pig at the 3½, the cat 7th, dog 11th, fox 14th, ruminantia at the 10th to 12th day, and the deer at the 60th day.

When the blastoderm grows to 2 mm. (rabbit), whereby the vitelline membrane is distended to a very thin, delicate membrane, then at one part of it there appears the **germinal area**, the area germinativa, or the embryonal shield (*Coste, Kölliker*), as a round white spot, in which the blastoderm, owing to the proliferation of its cells, becomes *double*. The upper layer is called the **ectoderm** or **epiblast**, and in some animals it consists of several layers of cells, while the lower layer is the **endoderm** or **hypoblast**. The hypoblast continues to grow at its edges, so that it ultimately forms a completely closed sac, on which the epiblast is applied concentrically. The embryonal area soon becomes more pear-shaped, and afterward biscuit-shaped. At the same time the surface of the zona pellucida develops numerous small, hollow, structureless villi, and is called the **primitive chorion.**

At the posterior part, or narrow end, of the embryonic shield, the **primitive streak** (Fig. 661, I, *Pr*) appears at first as an elongated opaque circular thickening, and later as a longer streak or groove, the **primitive groove**. [The opacity

is due to the fact that there are several layers of cells in this region (Fig. 662). In a transverse section through the primitive streak, three layers of cells are seen. They form part of the middle layer or mesoblast, and are originally derived from the hypoblast. These cells fuse with those of the epiblast. The remainder of the hypoblastic cells retain their stellate character.] At the same time a new layer of

FIG. 662.



Transverse section of the primitive streak of a fowl's blastoderm. *ep*, epiblast; *hy*, hypoblast; *m*, mesoblast; *pr*, primitive groove; *yk*, yoke of germinal wall.

cells is developed between the epiblast and hypoblast, the **mesoderm** or **mesoblast** (Fig. 662, I), which soon extends over the embryonal area, and into the blastoderm. [There has been much discussion as to the origin of the mesoblast, but in vertebrates it seems to be originally developed from the hypoblast. Fig. 663 shows a portion of the hypoblast in its axial part, in process of forming the notochord, which is described as mesoblastic.] Blood vessels are formed within the mesoblast, and are distributed over the blastoderm to form the area vasculosa.

FIG. 663.



Transverse section of an embryo newt. *a*, mesenteron; *a.x. hy*, axial hypoblast, forming the notochord; *bc*, cœlom or body cavity; *ep*, epiblast; *hy*, digestive hypoblast; *som*, somatic mesoblast; *spm*, splanchnic mesoblast; *np*, neural plate.

Medullary Groove. — A longitudinal groove, the medullary groove, is formed at the anterior part of the embryonal shield, but it gradually extends posteriorly, embracing the anterior part of the primitive streak with its divided posterior end, while the primitive streak itself gradually becomes relatively and absolutely smaller and less distinct, until it disappears altogether (Fig. 661, I, and II, *Pr*).

The position of the embryo is indicated by the central part becoming more transparent,—the **area pellucida**,—which is surrounded by a more opaque part—the **area opaca**. [The area opaca rests directly upon the white yelk in the fowl, and it takes no share in the formation of the embryo, but gives rise to structures which are temporary, and are connected with the nutrition of the embryo. The embryo is formed in the area pellucida alone.]

From the **epiblast** [*neuro-epidermal layer*] are developed the central nervous system and epidermal tissues, including the epithelium of the sense organs.

From the **mesoblast** are formed most of the organs of the body [including the vascular, muscular, and skeletal systems, and, according to some, the connective tissue. It also gives rise to the generative glands and excretory organs].

From the **hypoblast** *epithelio-glandular layer* [which is the secretory layer], arise the intestinal epithelium, and that of the glands which open into intestine. The notochord is also formed from its axial portion. [The mouth and anus being formed by an inpushing of the epiblast, are lined by epiblast, and are sometimes called the **stomodæum** and **proctodæum** respectively.]

[**Structure of the Blastoderm** (Fig. 664).—Originally it is composed of only two layers, and in a vertical section of it the **epiblast** consists of a single row of nucleated granular cells, arranged side by side, with their long axes placed vertically. The **hypoblast** consists of larger cells than the foregoing, although they vary in size. They are spherical and very granular, so that no nucleus is visible in them. The cells form a kind of network, and occur in more than one layer, especially at the periphery. It rests on white yelk, and under it are large spherical refractive cells, spoken of as **formative cells** (*c*).]

FIG. 664.

Vertical section of part of the unincubated blastoderm of a hen. *a*, epiblast; *b*, hypoblast; *c*, formative cells resting on white yelk; *f*, archenteron.

The cells of the epiblast, and especially those of the hypoblast, nourish themselves by the direct absorption and incorporation of the constituents of the yelk into themselves. The amœboid movements of these cells play a part in the process of absorption. The absorbed particles are changed, or, as it were, digested within the cells, and the product used in the processes of growth and development (*Kollmann*).

440. STRUCTURES FORMED FROM THE EPIBLAST.—Laminæ Dorsales.—The medullary groove upon the epiblast (also called outer, serous, sensorial, corneal, or animal layer) becomes deeper (Fig. 665, II). The two longitudinal elevations or **laminæ dorsales** consist of a thickening of the epiblast, and grow up over the medullary groove, to meet each other and coalesce by their free edges in the middle line posteriorly. Thus, the open groove is changed into a closed tube—the **medullary or neural tube** (III). The cells next the lumen of the tube ultimately become the ciliated epithelium lining the central canal of the spinal cord, while the other cells of the nipped-off portion of the epiblast form the ganglionic part of the central nervous system and its processes.

Primary Cerebral Vesicles.—[The laminæ dorsales unite first in the region of the neck of the embryo, and soon this is followed by the union of those over the future head.] The medullary tube is not of uniform diameter, for at the anterior end it becomes dilated and mapped out by constrictions into the primary vesicles of the brain, which at first are arranged one behind the other, in the following order, each one being smaller than the one in front of it: the **fore-brain** (representing the structures from which the cerebral hemispheres are developed); the **mid-brain** (corpora quadrigemina); the **hind-brain** (cerebellum); and the **after-brain** (medulla oblongata), which is gradually continued into the spinal cord (IV and V). The posterior part of the medullary tube has a dilatation at the lumbar enlargement. In birds, the medullary groove remains open in this situation to form a lozenge-shaped dilatation, the sinus rhomboidalis.

Cranial Flexures.—The anterior part of the medullary tube curves on itself, especially at the junction of the spinal cord and oblongata, between the mid-brain and hind brain, and again almost at right angles between the fore-brain and

FIG. 665.



I, The three layers of the blastoderm of a mammalian ovum—Z, zona pellucida; E, epiblast; *m*, mesoblast; *e*, hypoblast. II, Section of an embryo, with six protovertebræ at the 1st day—M, medullary groove; *h*, somatopleure; U, protovertebræ; *c*, chorda dorsalis; S, the lateral plates divided into two; *e*, hypoblast. III, Section of an embryo chick at the 2d day in the region behind the heart—M, medullary groove; *h*, outer part of somatopleure; *u*, protovertebra; *c*, chorda; *w*, Wolffian duct; K, cœlom; *x*, inner part of somatopleure; *y*, inner part of splanchnopleure; A, amniotic fold; *a*, aorta; *e*, hypoblast. IV, Scheme of a longitudinal section of an early embryo. V, Scheme of the formation of the head and tail folds—*r*, head fold; D, anterior extremity of the future intestinal tract; S, tail fold, first rudiment of the cavity of the rectum. VI, Scheme of a longitudinal section through an embryo after the formation of the head and tail folds—A *o*, omphalo-mesenteric arteries; V *o*, omphalo-mesenteric veins; *a*, position of the allantois; A, amniotic fold. VII, Scheme of a longitudinal section through a human ovum—Z, zona pellucida; S, serous cavity; *r*, union of the amniotic folds; A, cavity of the amnion; *a*, allantois; N, umbilical vesicle; *m*, mesoblast; *h*, heart; U, primitive intestine. VIII, Schematic transverse section of the pregnant uterus during the formation of the placenta; U, muscular wall of the uterus; *p*, uterine mucous membrane, or decidua vera; *b*, maternal part of the placenta, or decidua serotina; *r*, decidua reflexa; *ch*, chorion; A, amnion; *n*, umbilical cord; *a*, allantois, with the urachus; N, umbilical vesicle, with D, the omphalo-mesenteric duct; *t t*, openings of the Fallopian tubes; G, canal of the cervix uteri. IX, Scheme of a human embryo, with the visceral arches still persistent—A, amnion; V, fore-brain; M, mid-brain; H, hind-brain; N, after-brain; U, primitive vertebræ; *a*, eye; *p*, nasal pits; S, frontal process; *y*, internal nasal process; *n*, external nasal process; *r*, superior maxillary process of the 1st visceral arch; 1, 2, 3, and 4, the four visceral arches, with the visceral clefts between them; *v*, auditory vesicle; *h*, heart, with *e*, primitive aorta, which divides into five aortic arches; *f*, descending aorta; *om*, omphalo-mesenteric artery; *b*, the omphalo-mesenteric arteries on the umbilical vesicle; *c*, omphalo-mesenteric vein; L, liver, with venæ advehentes and revehentes; D, intestine; *i*, inferior cava; T, coccyx; *all*, allantois, with *z*, one umbilical artery, and *x*, an umbilical vein.

mid-brain. [Thus, a displacement of the primary vesicles is produced, and the head of the future embryo is mapped off.] At first all the cerebral vesicles are devoid of convolutions and sulci. On each side of the fore-brain there grows out a stalked hollow vesicle (VI), the **primary optic vesicle**. The remainder of the epiblast forms the epidermal covering of the body. At an early period we can distinguish the stratum corneum and the Malpighian layer of the skin (§ 283); from the former are developed the hairs, nails, feathers, etc.

Partial Cleavage.—Only a partial cleavage takes place in the eggs of birds and in meroblastic ova, *i. e.*, only the *white yelk* in the neighborhood of the cicatricula divides into numerous segmentation spheres (*Coste*, 1848). The cells arrange themselves in two layers lying one over the other. The upper layer or *epiblast* is the larger, and contains small pale cells; the lower layer, or *hypoblast*, which at first is not a continuous layer, ultimately forms a continuous layer, but its periphery is smaller than the upper layer, while its cells are larger and more granular.

Between the epiblast and hypoblast there is formed, from the primitive streak as a product of cell-proliferation, the **mesoblast**, which is said by Kölliker to be due to the division of the cells of the epiblast. It gradually extends in a peripheral direction between the two other layers. All the three layers grow at their periphery. In the mesoblast blood vessels are developed. All the three layers, as they grow, come ultimately to enclose the yelk, so that their margins come together at the opposite pole of the yelk.

FIG. 666.



Embryo fowl of the 2d day, × 50. *Ao*, area opaca; *Ap*, area pellucida; *Hh*, hind-brain; *Mh*, mid-brain; *Vh*, fore-brain; *om*, omphalo-mesenteric veins; *omr*, point where the closure of the neural groove is traveling backward with the protovertebræ; *Vw*, muscle plates; *Rf*, posterior part of widely-open neural groove; *Rw*, neural ridge; *vAf*, anterior amniotic fold.

441. STRUCTURES FORMED FROM THE MESOBLAST AND HYPOBLAST. — The **mesoblast** (vascular layer or middle layer) forms immediately under the medullary groove, a cylindrical cellular cord, the **chorda dorsalis**, or **notochord**, which is thicker at the tail than at the cephalic end (Fig. 665, II, III, *c*). It is present in all vertebrata, and also in the larval form of the ascidians, but in the latter it disappears in the adult form (*Kowalewsky*). In man it is relatively small. It forms the basis of the bodies of the vertebræ, and around it, as a central core, the substance of the bodies of the vertebræ is deposited, so that they are strung on it, as it were, like beads on a string. After it is formed, it becomes surrounded by a double sheath-like covering (*Gegenbaur, Kölliker*).

The recent observations of L. Gerlach and Strahl show that the chorda dorsalis is derived from the hypoblast (Fig. 663). It does not contain chondrin or glutin, but albumin (*Retzius*).

Protovertebræ.—The cells of the mesoblast, on each side of the chorda, arrange themselves into cubical masses, always disposed in pairs behind each other,

the **protovertebræ** (Fig. 665, U and *u*). The first pair correspond to the atlas. At a later period each protovertebra shows a marginal cellular area and a nuclear area (Fig. 665). Only part of it goes to form a future vertebra. The part of the mesoblast lying external to the protovertebræ, the **lateral plates** (Fig. 665, II, *s*), splits into two layers, an upper one and a lower one, which, however, are united by a **median plate** at the protovertebræ. The space between the two layers of the mesoblast is called the **pleuro-peritoneal cavity**, or the **cœlom** of Haeckel (III, K). The upper layer of the lateral plate becomes united to the epiblast, and forms the cutaneo-muscular plate of German authors, or the **somatopleure** (Fig. 665, III, *x*; Fig. 667, *so*), while the inner one unites with the hypoblast to form the intestinal plate of German authors, or the **splanchnopleure** (Fig. 665, III, *y*; Fig. 667, *sp*). On the surfaces of these plates, which are directed toward each other, the endothelium lining the pleuro-peritoneal cavity is developed. On the surface of the median plate, directed toward the cœlom, some cylindrical cells,

FIG. 667.



Transverse section of an embryo duck. *am*, amnion; *ao*, aorta; *ca.v*, cardinal vein; *ch*, notochord; *hy*, hypoblast; *ms*, muscle plate; *so*, somatopleure; *sp*, splanchnopleure; *sp.c*, spinal cord; *sp.g*, spinal ganglion; *st*, segmental tube; *wd*, Wolffian (segmental) duct.

the "**germ epithelium**" of Waldeyer, remain, which form the ovarian tubes and the ova (§ 438).

According to Remak, the skin, the muscles of the trunk, and the blood vessels, and according to His, only the musculature of the trunk, are derived from the somatopleure. Both observers agree that the splanchnopleure furnishes the musculature of the intestinal tract.

Parablastic and Archiblastic Cells.—According to His, the blood vessels, blood, and connective tissue are not developed from true mesoblastic cells, but he asserts that for this purpose certain cells wander in from the margins of the blastoderm between the epiblast and hypoblast, these cells being derived from outside the position of the embryo, from the elements of the white yelk. His calls these structures *parablastic*, in opposition to the *archiblastic*, which belong to the three layers of the embryo. Waldeyer also adheres to the parablastic structure of blood and connective tissue, but he assumes that the material from which the latter is formed is continuous protoplasm, and of equal value with the elements of the blastoderm.

The **hypoblast** does not undergo any change at this time; it applies itself to the inner layer of the mesoblast, as a single layer of cells, to form the splanchnopleure.

442. FORMATION OF EMBRYO, HEART, PRIMITIVE CIRCULATION.—Head and Tail Folds.—Up to this time the embryo lies with its three layers in the plane of the layers themselves. The cephalic end of the future embryo is first raised above the level of this plane (Fig. 665, V). In front of, and under the head, there is an inflection or tucking-in of the layers, which is spoken of as the **head-fold** (V, *r*). [It gradually travels backward, so that the embryo is raised above the level of its surroundings.] The raised cephalic end is hollow, and it communicates with the space in the interior of the umbilical vesicle. The cavity in the head is spoken of as the **head-gut** or **fore-gut** (V, D.). The formation of the fore-gut, by the elevation of the head from the plane of the three layers, occurs on the second day in the chick, and in the dog on the 22d day. The **tail-fold** is formed in precisely the same way, in the chick on the 3d day, and in the dog on the 22d day. The tail-fold, S, also is hollow, and the space within it is the **hind-gut**, *d*. Thus, the body of the embryo is supported or rests on a hollow stalk, which at first is wide, and communicates with the cavity of the umbilical vesicle. This duct or communication is called the **omphalo-mesenteric duct**, or the **vitello-intestinal** or **vitelline duct**. The saccular vesicle attached to it in mammals is called the **umbilical vesicle** (VII, N), while the analogous much larger sac in birds, which contains the yellow nutritive yelk, is called the **yelk sac**. The omphalo-mesenteric or vitelline duct in course of time becomes narrower, and is ultimately obliterated in the chick on the 5th day. The point where it is continuous with the abdominal wall is the abdominal umbilicus, and where it is inserted into the primitive intestine, the intestinal umbilicus.

[Sometimes part of the vitelline duct remains attached to the intestine, and may prove dangerous by becoming so displaced as to constrict a loop of intestine, and thus cause strangulation of the gut.]

Heart.—Before this process of constriction is complete, some cells are mapped off from that part of the splanchnopleure which lies immediately under the head-gut; this indicates the *position of the heart*, which appears in the chick at the end of the first day, as a small, bright red, rhythmically contracting point, the *punctum saliens*, or the στίγμη κινουμένη of Aristotle. In mammals it appears much later.

The **heart**, VI, begins first as a mass of cells, some of which in the centre disappear to form a central cavity, so that the whole looks like a pale hollow bud (originally a pair) of the splanchnopleure. The central cavity soon dilates; it grows, and becomes suspended in the cœlom by a duplicature like a mesentery (mesocardium), while the space which it occupies is spoken of as the *fovea cardica*. The heart now assunes an elongated tubular form, with its aortic portion directed forward, and its venous end backward; it then undergoes a slight *f*-shaped curve (Fig. 675, 1). From the middle of the 2d day, the heart begins to beat in the chick, at the rate of about 40 beats per minute. [It is very important to note that at first, although the heart beats rhythmically, it does not contain any nerve cells.]

From the anterior end of the heart, there proceeds from the bulbus aortæ, the aorta which passes forward and divides into two **primitive aortæ**, which then curve and pass backward under the cerebral vesicles, and run in front of the protovertebræ. Opposite the omphalo-mesenteric duct, each primitive aorta in the chick sends off one, in mammals several (dog 4 to 5), omphalo-mesenteric arteries (VI, A, *o*), which spread out to form a vascular network within the mesoblast of the umbilical vesicle. From this network, there arise the omphalo-mesenteric veins, which run backward on the vitelline duct, and end by two trunks in the venous end of the tubular heart. In the chick, these veins arise from the sinus terminalis of the future vena terminalis of the area vasculosa. Thus, the **first** or **primitive circulation** is a closed system, and functionally it is concerned in

carrying nutriment and oxygen to the embryo. In the bird, the latter is supplied through the porous shell, and the former is supplied up to the end of incubation by the yelk. In mammals, both are supplied by the blood vessels of the uterine mucous membrane to the ovum. In birds, owing to the absorption of the contents of the yelk sac, the vascular area steadily diminishes, until ultimately, toward the end of the period of incubation, the shriveled yelk sac slips into the abdominal cavity. In mammals, the circulation on the umbilical vesicle *i. e.*, through the omphalo-mesenteric vessels, soon diminishes, while the umbilical vesicle itself shrivels to a small appendix, and the **second circulation** is formed to replace the omphalo-mesenteric system. The first blood vessels are formed in the chick, in the **area vasculosa**, outside the position of the embryo, at the last quarter of the first day, before any part of the heart is visible. The blood vessels begin in vaso-formative cells [constituting the "**blood islands**" of Pander]. At first they are solid, but they soon become hollow (§ 7, A).

A narrow-meshed plexus of *lymphatics* is formed in the area vasculosa of the chick (*His*), and it communicates with the amniotic cavity (*A. Budge*).

443. **FORMATION OF THE BODY.—Body-Wall.**—(1) The **cœlom**, or **pleuro-peritoneal cavity**, becomes larger and larger, while at the same time the difference between the body-wall and the wall of the intestine becomes more pronounced. The latter becomes more separated from the protovertebræ, as the middle plate begins to be elongated to form a mesentery. The body-wall, or somatopleure, composed of the epiblast and the outer layer of the cleft mesoblast, becomes thickened by the ingrowth into it of the muscular layer from the muscle-plate, and the position of the bones and the spinal nerves from the protovertebræ. These grow between the epiblast and the outer layer of the mesoblast (*Remak*). [The somatopleure, or parietal lamina, from each side grows forward and toward the middle line, where they meet to form the body-wall, while at the same time, the splanchnopleure, or visceral lamina, on each side also grow and meet in the middle line, and when they do so, they enclose the intestine. Thus, there is one tube within the other, and the space between is the pleuro-peritoneal cavity.]

(2) **Vertebral Column.**—A dorsally placed structure, called the **muscle plate** (Fig. 667, *ms.*), is differentiated from each of the protovertebræ; the remainder of the protovertebræ, the protovertebra proper, coalesces with that on the other side, so that both completely surround the chorda, to form the **membrana reuniens inferior**, in the chick on the 3d, and in the rabbit on the 10th day, while, at the same time, they close over the medullary tube dorsally, in the chick at the 4th day, to form the **membrana reuniens superior** (*Reichert*). Thus, there is a union of the masses of the protovertebræ in *front* of the medullary tube, which encloses the chorda, and represents the basis of the *bodies* of all the vertebræ, while the membrana reuniens superior, pushed between the muscle plates and the epiblast on the one hand and the medullary tube on the other, represents the position of the entire vertebral *laminæ* as well as the intervertebral ligaments between them. In some rare cases the membrana reuniens superior is not developed, so that the medullary tube is covered only by the epiblast (epidermis), either throughout its entire extent, or at certain parts. This constitutes the condition of **spina bifida**, or, when it occurs in the head, hemicephalia. The vertebral column at this membranous stage is in the same condition as the vertebral column of the cyclostomata (Petromyzon). The membranes of the spinal cord, the spinal ganglia, and spinal nerves are formed from the membrana reuniens superior.

Lastly, parts of the somatopleures also grow toward the middle line of the back, and insinuate themselves between the muscle plate and the epiblast; thus, the dorsal skin is formed (*Remak*).

In the membranous vertebral column, there are formed the several *cartilaginous* vertebræ, the one behind the other, in man at the 6th to 7th week, although at first they do not form closed vertebral arches; the latter are closed in man about the 4th month. Each cartilaginous vertebra, however, is not formed from a pair of protovertebræ, *i.e.*, the 6th cervical vertebra from the 6th pair of protovertebræ, but there is a new subdivision of the vertebral column, so that the lower half of the preceding protovertebra and the upper half of the succeeding protovertebra unite to form the final vertebra. While the bodies are becoming cartilaginous the chorda becomes smaller, but it still remains larger in the intervertebral disks. The body of the first vertebra or atlas unites with that of the axis to form its odontoid process, and in addition it forms the arcus anterior atlantis and the transverse ligament (*Hasse*). The chorda can be followed upward through the ligamentum suspensorium dentis as far as the posterior part of the sphenoid bone.

The **histogenetic formation of cartilage** from the indifferent formative cells takes place by division and growth of the cells, until they ultimately form clear nucleated sacs. The cement substance is probably formed by the outer parts of the cells (parietal substance) uniting and secreting the intercellular substance. It is supposed by some that the latter contains fine canals, which connect the protoplasm of the adjoining cells.

Visceral Clefts and Arches.—Each side of the cervical region contains four slit-like openings—the *visceral clefts* or *branchial openings* (*Rathke*); in the chick, the upper three are formed at the 3d, and the fourth on the 4th day. Above the slits are thickenings of the lateral wall, which constitute the **visceral or branchial arches** (Fig. 671). The clefts are formed by a perforation from the fore gut, but this, perhaps, does not always occur in the chick, mammal, and man (*His*), and they are lined by the cells of the hypoblast. On each side in each visceral arch, *i.e.*, above and below each cleft, there runs an aortic arch, five on each side (Fig. 665, IX). These aortic arches persist in fishes. In man, all the slits close, except the uppermost one, from which the auditory meatus, the tympanic cavity, and the Eustachian tube are developed. The four visceral arches are for the most part made use of later for other formations (p. 931).

Primitive Mouth and Anus.—Immediately under the fore-brain, in the middle line, is a thin spot, where there is at first a small depression, and ultimately a rupture, forming the **primitive oral aperture**, which represents both the mouth and the nose. Similarly, there is a depression at the caudal end, and the depression ultimately deepens, thus communicating with the hind gut to form the anus. When the latter part of the process is incomplete, there is **atresia ani**, or imperforate anus. Several processes are given off from the primitive intestine, including the hypoblast and its muscular layers, to form the lungs, the liver, the pancreas, the cæcum (in birds), and the allantois.

The **extremities** appear at the sides of the body as short unjointed stumps or projections at the 3d or 4th week in the human embryo.

444. AMNION AND ALLANTOIS.—Amnion.—During the elevation of the embryo from its surroundings, immediately in front of the head (at the end of the 2d day in the chick), there rises up a fold consisting of the epiblast and the outer layer of the mesoblast, which gradually extends to form a sort of hood over the cephalic head of the embryo (Fig. 665, VI, A). In the same way, but somewhat later, a fold rises at the caudal end, and between both along the lateral borders similar elevations occur, the lateral folds (Fig. 665, III, A). All these folds grow over the back of the embryo to meet over the middle line posteriorly, where they unite at the 3d day, in the chick, to form the **amniotic sac.** Thus, a *cavity* which becomes filled with fluid—the **amniotic fluid**—is developed around the embryo [so that the embryo really floats in the fluid of the amniotic sac]. In mammals, also, the amnion is developed very early, just as in birds (Fig. 665, VII, A). From the middle of pregnancy onward, the amnion is applied directly to the

chorion, and united to it by a gelatinous layer of tissue, the tunica media of Bischoff.

Amniotic Fluid.—The amnion, and the allantois as well, are formed only in mammals, birds, and reptiles, which have hence been called **amniota**, while the lower vertebrates, which are devoid of an amnion, are called **anamnia**. **Composition.**—The **amniotic fluid** is a clear, serous, alkaline fluid, specific gravity 1007 to 1011, containing, besides epithelium, lanugo hairs, ½ to 2 per cent. of fixed solids. Among the latter are albumin ($\frac{1}{10}$ to $\frac{1}{3}$ per cent.), mucin, globulin, a vitelline-like body, some grape sugar, urea, ammonium carbonate, very probably derived from the decomposition of urea, sometimes lactic acid and kreatinin, calcic sulphate and phosphate, and common salt. About the middle of pregnancy, it amounts to about 1–1.5 kilo. [2.2–3.3 lbs.], and at the end about 0.5 kilo. The amniotic fluid is of fœtal origin, as is shown by its occurrence in birds, and is, perhaps, a transudation through the fœtal membranes. In mammals, the urine of the fœtus forms part of it during the second half of pregnancy (*Gusserow*). In the pathological condition of **hydramnion**, the blood vessels of the uterine mucous membrane secrete a watery fluid. The fluid preserves the fœtus and also the vessels of the fœtal membranes from mechanical injuries; it permits the limbs to move freely, and protects them from growing together; and, lastly, it is important for dilating the os uteri during labor. The amnion is capable of contraction at the 7th day in the chick; and this is due to the smooth muscular fibres which are developed in the cutaneous plate in its mesoblastic portion, but nerves have not been found.

Allantois.—From the anterior surface of the caudal end of the embryo, there grows out a small double projection, which becomes hollowed out to form a sac projecting into the cavity of the cœlom or pleuro-peritoneal cavity (Fig. 665); it constitutes the *allantois*, and is formed in the chick before the 5th day, and in man, during the 2d week. Being a true projection from the hind gut, the allantois has two layers, one from the hypoblast, and the other from the muscular layer, so that it is an offshoot from the splanchnopleure. From both sides, there pass on to the allantois the **umbilical arteries** from the hypogastric arteries, and they ramify on the surface of the sac. The allantois grows, like a urinary bladder gradually being distended, in front of the hind gut in the pleuro-peritoneal cavity toward the umbilicus; and lastly, it grows out of the umbilicus, and projects beyond it alongside the omphalo-mesenteric or vitelline duct, its vessels growing with it (Fig. 665, VII, *a*); but, after this stage, it behaves differently in birds and mammals.

In **birds**, after the allantois passes out of the umbilicus, it undergoes great development, so that within a short time it lines the whole of the interior of the shell as a highly vascular and saccular membrane. Its arteries are at first branches of the primitive aortæ, but with the development of the posterior extremities they appear as branches of the hypogastric arteries. Two allantoidal or *umbilical veins* proceed from the numerous capillaries of the allantois. They pass backward through the umbilicus, and at first unite with the omphalo-mesenteric veins to join the venous end of the heart. In birds this circulation on the allantois, or *second circulation*, is **respiratory** in function, as its vessels serve for the exchange of gases through the porous shell. The circulation gradually assumes the respiratory functions of the umbilical vesicle, as the latter gradually becomes smaller and smaller, and ceases to be a sufficient respiratory organ. Toward the end of the period of incubation the chick may breathe and cry within the shell (*Aristotle*)—a proof that the respiratory function of the allantois is partly taken over by the lungs. The allantois is also the **excretory** organ of the urinary constituents. Into its cavity in mammals the ducts of the *primitive kidneys*, or the *Wolffian ducts*, open, but in birds and reptiles, which possess a cloaca, these open into the posterior wall of the cloaca. The primitive kidneys, or Wolffian bodies, consist of many glomeruli, and empty their secretion through the Wolffian ducts into the allantois (in birds into the cloaca), and the secretion passes through the allantois, per the umbilicus, into the peripheral part of the urinary sac. Remak found ammonium and sodium urate, allantoin, grape sugar, and salts in the contents of the allantois. From the 8th day onward, the allantois of the chick is contractile (*Vulpian*), owing to the presence of smooth fibres derived from the splanchnopleure. Lymphatics accompany the branches of the arteries (*A. Budge*).

Allantois in Mammals.—In mammals and man, the relation of the allantois is somewhat different. The first part or its origin forms the **urinary bladder**, and from the vertex of the latter there proceeds through the umbilicus a tube, the **urachus**, which is open at first (Fig. 665, VIII, *a*). The blind part of the sac of the allantois outside the abdomen is in some animals filled with a fluid like urine. In man, however, this sac disappears during the 2d month, so that there remains only the vessels which lie in the muscular part of the allantois. In some animals,

however, the allantois grows larger, does not shrivel, but obtains through the urachus from the bladder an alkaline turbid fluid, which contains some albumin, sugar, urea, and allantoin. The relations of the umbilical vessels will be described in connection with the fœtal membranes.

445. FŒTAL MEMBRANES, PLACENTA, FŒTAL CIRCULATION.—Decidua.—When a fecundated ovum reaches the uterus, it becomes surrounded by a special covering, which William Hunter (1775) described as the **membrana decidua**, because it was shed at birth. We distinguish the **decidua vera** (Fig. 665, VIII, *p*), which is merely the thickened, very vascular, softened, more spongy, and somewhat altered mucous membrane of the uterus. [Sometimes in a diseased condition, as in dysmenorrhœa, the superficial layer of the uterine mucous membrane is thrown off nearly *en masse* in a triangular form (Fig. 668). This serves to show the shape of the decidua, which is that of the uterus.] When the ovum reaches the uterus, it is caught in a crypt or fold of the decidua, and from the latter there grow up elevations around the ovum; but these elevations are thin, and soon meet over the back of the ovum to form the **decidua reflexa** (Fig. 665, VIII, *r*). At the 2d to 3d month, there is still a space in the uterus outside the reflexa; in the 4th month, the whole cavity is filled by the ovum. At one part the ovum lies directly upon the d. vera [and that part is spoken of as the **decidua serotina**], but by far the greatest part of the surface of the ovum is in contact with the reflexa. In the region of the d. serotina the **placenta** is ultimately formed.

FIG. 668.

A dysmenorrhœal membrane laid open.

Structure of the Decidua Vera.—The d. vera at the 3d month is 4 to 7 mm. thick, and at the 4th only 1 to 3 mm., and it no longer has any epithelium; but it is very vascular, and is possessed of lymphatics around the glands and blood vessels (*Leopold*), and in its loose substance are large round cells (decidua cells—*Kölliker*), which in the deeper parts become changed into fibre cells—there are also lymphoid cells. The uterine glands, which become greatly developed at the commencement of pregnancy, at the 3d to the 4th month form non-cellular, wide, bulging tubes, which become indistinct in the later months, and in which the epithelium disappears more and more. The **d. reflexa**, much thinner than the vera from the middle of pregnancy, is devoid of epithelium, and is without vessels and glands. Toward the end of pregnancy both deciduæ unite.

The ovum, covered at first with small hollow **villi**, is surrounded by the decidua. From the formation of the amnion it follows that, after it is closed, a completely closed sac passes away from the embryo to lie next the **primitive chorion**. This membrane is the "serous covering" of v. Baer (Fig. 665, VII, *s*), or the **false amnion**. It becomes closely applied to the inner surface of the chorion, and extends even into its villi. The allantois proceeding from the umbilicus comes to lie directly in contact with the fœtal membrane; its sac disappears about the 2d month in man, but its vascular layer grows rapidly and lines the whole of the inner surface of the chorion, where it is found on the 18th day (*Coste*). From the 4th week the blood vessels, along with a covering of connective tissue, branch and

penetrate into the hollow cavities of the villi, and completely fill them. At this time the primitive chorion disappears. Thus, we have a stage of general vascularization of the chorion. In the place of the derivative of the zona pellucida we have the vascular villi of the allantois, which are covered by the epiblastic cells derived from the false amnion. This stage lasts only until the 3d month, when the chorionic villi disappear all over that part of the surface of the ovum which is in contact with the decidua reflexa. On the other hand, the villi of the chorion, where they lie in direct contact with the decidua serotina, become larger and more branched. Thus, there is distinguished the **chorion laeve** and **c. frondosum.**

The chorion laeve, which consists of a connective-tissue matrix covered externally by several layers of cells, has a few isolated villi at wide intervals. Between the chorion and the amnion is a gelatinous substance (membrana intermedia) or undeveloped connective tissue.

Placenta.—The large villi of the chorion frondosum penetrate into the tissue of the decidua serotina of the uterine mucous membrane. [It was formerly supposed that the chorionic villi entered the mouths of the uterine glands, but the researches of Ercolani and Turner have shown that, although the uterine glands enlarge during the early months of utero-gestation, the villi do not enter the glands. The villi enter the crypts of the uterine mucous membrane. The glands of the inner layer of the decidua serotina soon disappear.] As the villi grow into the decidua serotina, they push against the walls of the large blood vessels, which are similar to capillaries in structure, so that the villi come to be bathed by the blood of the mother in the uterine sinuses, or they float in the colossal decidual capillaries (Fig. 665, VII, *b*). The villi do not float naked in the maternal blood, but they are covered by a layer of cells derived from the decidua. Some villi, with bulbous ends, unite firmly with the tissue of the uterine part of the placenta to form a firm bond of connection. [The placenta is formed by the mutual intergrowth of the chorionic villi and the decidua serotina.] Thus, it consists of a **fœtal part,** including all the villi, and a **maternal or uterine part,** which is the very vascular decidua serotina. At the time of birth, both parts are so firmly united that they cannot be separated. Around the margin of the placenta is a large venous vessel, the *marginal sinus* of the placenta. [Friedländer found the uterine sinuses below the placental site blocked by giant cells after the 8th month of pregnancy. Leopold confirms this, and found the same in the serotinal veins.] **Functions.**—The placenta is the **nutritive, excretory,** and **respiratory** organ of the fœtus (§ 368); the latter receives its necessary pabulum by endosmosis from the maternal sinuses through the coverings and vascular wall of the villi in which the fœtal blood circulates. [The placenta also contains *glycogen.*]

FIG. 669.



Human placental villi. Blood vessels black.

[**Structure.**—A piece of fresh placenta teased in normal saline solution, shows the villi provided with lateral offshoots, and consisting of a connective-tissue framework, containing a capillary network with arteries and veins, while the villi themselves are covered by a layer of somewhat cubical epithelium (Fig. 669).]

Uterine Milk.—Between the villi of the placenta there is a clear fluid, which contains numerous small, albuminous globules, and this fluid, which is abundant in the cow, is spoken of as the uterine milk. It seems to be formed by the breaking up of the decidual cells. It has been supposed to be nutritive in function. [The maternal placenta, therefore, seems to be a secreting structure, while the fœtal part has an absorbing function. The uterine milk has been analyzed by Gamgee, who found that it contained fatty, albuminous, and saline constituents, while sugar and casein were absent.]

The investigations of Walter show, that after poisoning pregnant animals with strychnin, morphia, veratrin, curara, and ergotin, these substances are not found in the fœtus, although many other chemical substances pass into it.

[Savory found that strychnin injected into a fœtus in utero caused tetanic convulsions in the mother (bitch), while syphilis may be communicated from the father to the mother through the medium of the fœtus (*Hutchinson*). A. Harvey's record of observations on the crossing of breeds of animals—chiefly of horses and allied species—show that materials can pass from the fœtus to the mother.]

On looking at a placenta, it is seen that its villi are distributed on large areas separated from each other by depressions. This complex arrangement might be compared with the cotyledons of some animals.

The **position of the placenta** is, as a rule, on the anterior or posterior wall of the uterus, more rarely on the fundus uteri, or laterally from the opening of the Fallopian tube, or over the internal orifice of the cervix, the last constituting the condition of **placenta praevia**, which is a very dangerous form of placental insertion, as the placenta has to be ruptured before birth can take place, so that the mother often dies from hemorrhage. The umbilical cord may be inserted in the centre of the placenta (*insertio centralis*), or more toward the margin (*ins. marginalis*), or the chord may be fixed to the chorion laeve. Sometimes, though rarely, there are small subsidiary placentæ (*pl. succenturiata*), in addition to the large one. When the placenta consists of two halves, it is called duplex or bipartite, a condition said by Hyrtl to be constant in the apes of the old world.

Structure of the Cord.—The umbilical cord (48 to 60 cm. [20 to 24 inches] long, 11 to 13 mm. thick) is covered by a sheath from the amnion. The blood vessels make about forty **spiral turns**, and they begin to appear about the second month. [The cause of the twisting is not well understood, but Virchow has shown that capillaries pass from the skin for a short distance on the cord, and they do so unequally, and it may be that this may aid in the production of the torsion.] It contains two strongly muscular and contractile arteries, and one umbilical vein. The two arteries anastomose in the placenta (*Hyrtl*). In addition, the cord contains the continuation of the urachus, the hypoblastic portion of the allantois (Fig. 665, VIII, *a*), which remains until the second month, but afterward is much shriveled. The omphalo-mesenteric duct of the umbilical vesicle (N) is reduced to a thread-like stalk (Fig. 665, VIII, D). **Wharton's jelly** surrounds the umbilical blood vessels. Wharton's jelly is a gelatinous-like connective tissue, consisting of branched corpuscles, lymphoid cells, some connective-tissue fibrils, and even elastic fibres. It yields **mucin.** It is traversed by numerous juice canals lined by endothelial cells, but other blood and lymphatic vessels are absent. Nerves occur 3–8–11 cm. from the umbilicus (*Schott, Valentin*).

The **fœtal circulation,** which is established after the development of the allantois, has the following course (Fig. 670): The blood of the fœtus passes from the hypogastric arteries through the two umbilical arteries, through the umbilical cord to the placenta, where the arteries split up into capillaries. The blood is returned from the placenta by the umbilical vein, although the color of the blood cannot be distinguished from the venous or impure blood in the umbilical arteries. The

umbilical vein (Fig. 673, 3, *u*) returns to the umbilicus, passes upward under the margin of the liver, gives a branch to the vena portæ (*a*), and runs as the **ductus venosus** into the inferior vena cava, which carries the blood into the right auricle. Directed by the Eustachian valve and the tubercle of Lower (Fig. 675, 6, *tL*), the great mass of the blood passes through the **foramen ovale** into the left auricle, owing to the presence of the valve of the foramen ovale. From the left auricle it passes into the left ventricle, aorta, and hypogastric arteries, to the umbilical arteries. The blood of the superior vena cava of the fœtus passes from the right auricle into the right ventricle (Fig. 675, 6, *Cs*). From the right ventricle it passes into the pulmonary artery (Fig. 675, 7, *P*), and through the **ductus arteriosus** of Botalli (*B*) into the aorta. There are, therefore, two streams of blood in the right auricle which cross each other, the descending one from the head through the superior vena cava, passing in front of the transverse one from the inferior vena cava to the foramen ovale.] Only a small amount of the blood passes through the as yet small branches of the pulmonary artery to the lungs (Fig. 675, 7, *1*, *2*). The course of the blood makes it evident that the head and upper limbs of the fœtus are nourished by purer blood than the remainder of the trunk, which is supplied with blood mixed with the blood of the superior vena cava.

FIG. 670.

Course of the fœtal circulation (*Cleland*).

After birth, the umbilical arteries are obliterated, and become the lateral ligaments of the bladder, while their lower parts remain as the superior vesical arteries. The umbilical vein is obliterated, and remains as the ligamentum teres, or round ligament of the liver, and so is the ductus venosus Arantii. Lastly, the foramen ovule is closed, and the ductus arteriosus is obliterated, the latter forming the lig. arteriosus.

The **condition of the membranes** where there are more fœtuses than one: (1) With twins there are two completely separated ova, with two placentæ and two deciduæ reflexæ. (2) Two completely separated ova may have only one reflexa, whereby the placentæ grow together, while their blood vessels remain distinct. The chorion is actually double, but cannot be separated into two lamellæ at the point of union. (3) One reflexa, one chorion, one placenta, two umbilical cords, and two amnia. The vessels anastomose in the placenta. In this case there is one ovum with a double yelk, or with two germinal vesicles in one yelk. (4) As in (3), but only one amnion, caused by the formation of two embryos in the same blastoderm of the same germinal vesicle.

Formation of the fœtal membranes.—The oldest mammals have no placenta or umbilical vessels; these are the **Mammalia implacentalia**, including the monetremata and marsupials. The second group includes the **Mammalia placentalia**. Among these (a) the **non-deciduata** possess only chorionic villi supplied by the umbilical vessels, which project into the depressions of the uterine mucous membrane, and from which they are pulled out at birth (Pl. diffusa, *e.g.*, pachydermata, cetacea, solidungula, camelidæ). In the *ruminants*, the villi are arranged in groups or **cotyledons**, which grow into the uterine mucous membrane, from which they are pulled out at birth.

(b) In the **deciduata,** there is such a firm union between the chorionic villi with the uterine mucous membrane, that the uterine part of the placenta comes away with the fœtal part at birth. In this case the placenta is either **zonary** (carnivora, pinnipedia, elephant) or **discoid** (apex, insectivora, edentata, rodentia).

446. CHRONOLOGY OF HUMAN DEVELOPMENT.—Development during the 1st Month.—At the 12th–13th day the ovum is saccular (5.5 mm. and 3 mm. in diameter); there is simply the blastodermic vesicle, with the blastoderm at one part, consisting of two layers; the zona pellucida beset with small villi (*Reichert*). At the 15th–16th day the ovum (5–6 mm.) is covered with simple cylindrical villi. The zona pellucida consists of embryonic connective tissue covered with a layer of flattened epithelium. The primitive groove and the laminæ dorsales appear. Then follows the stage when the allantois is first formed. At the 15th–18th day Coste investigated an ovum. It was 13.2 mm. long, with small branched villi; the embryo itself was 2.2 mm. long, of a curved form, and with a moderately enlarged cephalic end. The amnion, umbilical vesicle with a wide vitelline duct, and the allantois were developed, the last already united to the false amnion. The S-shaped heart lies in the cardiac cavity, shows a cavity and a bulbous aortæ, but neither auricles nor ventricles. The visceral arches and clefts are indicated, but they are not perforated. The omphalo-mesenteric vessels forming the first circulation on the umbilical vesicle are developed, the duct (vitelline) is still quite open, and two primitive aortæ run in front of the protovertebræ. The allantois attached to the fœtal membranes is provided with blood vessels. The two omphalo-mesenteric veins unite with the two umbilical veins, and pass to the venous end of the heart. The mouth is in process of formation. The limbs and sense organs absent; the Wolffian bodies probably present.

At the 20th day all the visceral arches are formed, and the clefts are perforated. The mid-brain forms the highest part of the brain, while the two auricles appear in the heart. The connection with the umbilical vesicle is still moderately wide. The embyro is 2.6–3.3–4 mm. long, while the head is turned to one side (*His*). At a slightly later period the temporal and cervical flexures take place, and the hemispheres appear more prominently; the vitelline duct is narrowed, the position of the liver is indicated, while the limbs are still absent (*His*).

At the 21st day the ovum is 13 mm. long and the embryo 4–4.5 mm.; the umbilical vesicle 2.2 mm., and the intestine almost closed. Three branchial clefts, Wolffian bodies laid down, and the *first appearance of the limbs*, three cerebral vesicles, auditory capsules present (*R. Wagner*). Coste also observed, in addition, the nasal pits, eye, the opening for the mouth, with the frontal and superior maxillary processes, the heart with two ventricles and two auricles.

End of the 1st Month.—The embryos of 25–28 days are characterized by the distinctly stalked condition of the umbilical vesicle and the distinct presence of limbs. Size of the ovum, 17.6 mm.; embryo, 13 mm.; umbilical vesicle, 5 5 mm., with blood vessels.

2d Month.—The embryos of 28–35 days are more elongated, and all the branchial clefts are closed except the first. The allantois has now only three vessels, as the right umbilical vein is obliterated. At the 5th week the nasal pits are united with the angle of the mouth by furrows, which close to form canals at the 6th week (*Toldt*). At 35–42 days the nasal and oral orifices are separated, the face is flat, the limbs show three divisions, the toes are not so sharply defined as the fingers. The outer ear appears as a low projection at the 7th week. The Wolffian bodies are much reduced in size. Length of body at 7th to 8th week, 1.6–4.1 cm.

End of the 2d Month.—Ovum, 6½ cm.; villi, 1.3 mm. long; the circulation on the umbilical vesicle has disappeared; embryo, 26 mm. long, and weighs 4 grammes. Eyelids and nose present, umbilical cord 8 mm. long, abdominal cavity closed, ossification beginning in the lower jaw, clavicle, ribs, bodies of the vertebræ; sex indistinct, kidneys laid down.

3d Month.—Ovum as large as a goose's egg, beginning of the placenta, embryo 7–9 cm., weighing 20 grammes, and is now spoken of as a **fœtus.** External ear well formed, umbilical cord 7 cm. long. Beginning of the difference between the sexes in the external genitals, umbilicus in the lower fourth of the linea alba.

4th Month.—Fœtus, 17 cm. long, weighing 120 grammes; sex distinct, hair and nails beginning to be formed, placenta weighs 80 grammes, umbilical cord 19 cm. long, umbilicus above the lowest fourth of the linea alba, contractions or movements of the limbs, meconium in the intestine, skin with blood vessels shining through it, eyelids closed.

5th Month.—Fœtus, length of body, 9.7–14.7 cm., total length 18 to 28 cm., weighing 284 grammes; hair on the head and lanugo distinct; skin still somewhat red and thin, and covered with vernix caseosa (§ 287, 2), is less transparent; weight of placenta, 178 grammes; umbilical cord, 31 cm. long.

6th Month.—Fœtus, length of body, 15–18.7, total length, 29–37 cm., weighing 634 grammes; lanugo more abundant; vernix more abundant; testicles in the abdomen; pupillary membrane and eyelashes present; meconium in the large intestine.

7th Month.—Fœtus, length of body, 18–22.8, total length, 35–38 cm., weighing 1218 grammes; the descent of the testicles begins—*one* testicle in the inguinal canal, the eyes open, the pupillary membrane often absorbed at its centre in the 28th week. In the brain other fissures are formed besides the primary ones. The fœtus is capable of living independently. At the beginning of this month there is a centre of ossification in the os calcis.

8th Month.—Fœtus, length of body, 24–27.8, total length 42 cm., weighing 1.5 to 2 kilos. (3.3 to 4.4 lbs.); hair of the head abundant, 1 3 cm. long, nails with a small margin, umbilicus below the middle of the linea alba, one testicle in the scrotum.

9th Month.—Fœtus, length of body, 30–37, total length, 47–67 cm., weighing 2234 grammes, and is not distinguishable from the child at the full period.

Fœtus at the Full Period.—Length of body, 51 cm. [20 inches], weight, 3¼ kilos. [7 lbs.], lanugo present only on the shoulders, skin white. The nails of the fingers project beyond the tips of the fingers, umbilicus slightly below the middle of the linea alba. The centre of ossification in the lower epiphysis of the femur is 4 to 8 mm. broad.

Period of Gestation or Incubation (*Schenk*).

	Days.		Days.		Weeks.		Weeks.
Coluber,	12	Rabbit,	32	Dog,	9	Sheep,	21
Hen,	21	Hare,	32	Fox,	9	Goat,	22
Duck,	21		Weeks.	Foumart,	9	Roe,	24
Goose,	29	Rat,	5	Badger,	10	Bear,	39
Stork,	42	Guinea-pig,	7	Wolf,	10	Small apes,	39
Cassowary,	65	Cat,	8	Lion,	14	Deer,	36–40
Mouse,	24	Marten,	8	Pig,	17	Woman,	40

Horse, Camel, 13 months; Rhinoceros, 18 months; and the Elephant, 24 months.

Limitation of the supply of O to eggs during incubation, leads to the formation of dwarf chicks.

447. FORMATION OF THE OSSEOUS SYSTEM.—Vertebral Column.—The ossification of the **vertebræ** begins at the 8th to the 9th week, and first of all there is a centre in each vertebral arch, then a centre is formed in the body behind the chorda, which, however, is composed of two closely apposed centres. At the 5th month the osseous matter has reached the surface, the chorda within the body of the vertebra is compressed; the three parts unite in the 1st year. The atlas has one centre in the anterior arch and two in the posterior; they unite at the 3d year. The epistropheus has a centre at the 1st year. The three points of the sacral vertebræ unite or anchylose between the 2d and the 6th year, and all the vertebræ (sacral) become united to form one body between the 18th and 25th years. Each of the four coccygeal vertebræ has a centre from the 1st to 10th year. The vertebræ in later years produce 1 to 2 centres in each process; 1 to 2 centres in each transverse process; 1 in the mamillary process of the lumbar vertebræ; and 1 in each articular process (8 to 15 years). Of the upper and under surfaces of the body of a vertebra each forms an epiphyseal thin osseous plate, which may still be visible at the 20th year. Groups of the cells of the chorda are still to be found within the intervertebral disks. As long as the coccygeal vertebræ, the odontoid process, and the base of the skull are cartilaginous, they still contain the remains of the chorda (*H. Müller*). The coccygeal vertebræ form the tail, and they originally project in man like a tail (Fig. 665, IX, T), which is ultimately covered over by the growth of the soft parts (*His*).

The **ribs** bud out from the protovertebræ, and are represented on each vertebra. The thoracic ribs become cartilaginous in the 2d month and grow forward into the wall of the chest, whereby the seven upper ones are united by a median portion (*Rathke*), which represents the position of one-half of the sternum, and when the two halves meet in the middle line the sternum is formed. When this does not occur we have the condition of the **cleft sternum.** At the 6th month there is a centre of ossification in the manubrium, then 4 to 13 in pairs in the body, and 1 in the ensiform process. Each rib has a centre of ossification in its body at the 2d month, and at the 8th to 14th one in the tubercle and another in the head. These anchylose at the 14th to 25th year. Sometimes cervical ribs are present in man, and they are largely developed in birds.

The **skull.**—The chorda extends forward into the axial part of the base to the sphenoid bone. The skull at first is **membranous,** or the **primordial cranium;** at the 2d month the basal portion becomes **cartilaginous,** including the occipital bone, except the upper half, the anterior and posterior part and wings of the sphenoid bone, the petrous part and mastoid process of the temporal bone, the ethmoid with the nasal septum, and the cartilaginous part of the nose. The other parts of the skull remain **membranous,** so that there is a cartilaginous and membranous primordial cranium.

I. The **occipital bone** has a centre of ossification in the basilar part at the 3d month, and one in the condyloid part and another in the fossa cerebelli, while there are two centres in the membranous cerebral fossæ. The four centres of the body unite during intra-uterine life. All the other parts unite at the 1st to 2d year.

II. The **post-sphenoid.**—From the 3d month it has two centres in the sella turcica, two in the sulcus caroticus, two in both great wings, which also form the lamina externa of the pterygoid process, while the non-cartilaginous and previously formed inner lamina arises from the superior maxillary process of the first branchial arch. During the first half of fœtal life these centres unite as far as the great wings; the dorsum sellæ and the clinoid process, as far as the synchondrosis spheno-occipitalis, are still cartilaginous, but they ossify at the 13th year.

III. The **pre-sphenoid** at the 8th month has two centres in the small wings and two in the body. At the 6th month they unite, but cartilage is still found within them even at the 13th year.

IV. The **ethmoid** has a centre in the labyrinth at the 5th month, then in the 1st year a centre in the central lamina. They unite about the 5th or 6th year.

V. Among the **membranous bones** are the inner lamina of the pterygoid process (one centre), the upper half of the tabular plate of the occipital (two points), the parietal bone (one centre in the parietal eminence), the frontal bone (one double centre in the frontal eminence), three small centres in the nasal spine, spina trochlearis and zygomatic process, nasal (one centre), the edges of the parietal bones (one centre), the tympanic ring (one centre), the lachrymal, vomer, and intermaxillary bone.

The **facial bones** are intimately related to the transformations of the *branchial arches* and *branchial clefts* (Fig. 671). The median end of the **first branchial arch** projects inward from each side toward the large oral aperture. It has two processes, the **superior maxillary process** which grows more laterally toward the side of the mouth, and the **inferior maxillary process**, which surrounds the lower margin of the mouth (Fig. 665, IX). From above downward there grows as an elongation of the basis cranii the **frontal process** (*s*), a broad process with a point (*y*) at its lower and outer angle, the inner nasal process. The frontal and the superior maxillary processes (*r*) unite with each other in such a way that the former projects between the two latter. At the same time there is anchylosed with the superior maxillary process the small **external nasal process** (*n*), a prolongation of the lateral part of the skull, and lying above the superior maxillary process. Between the latter and the outer nasal process is a slit leading to the eye (*a*). Thus the mouth is cut off from the nasal apertures which lie above it. But the separation is continued also within the mouth; the superior maxillary process produces the upper jaw, the nasal process, and the intermaxillary process (*Goethe*)—the latter is present in man, but is united to the upper jaw. The **intermaxillary bone**, which in many animals remains as a separate bone (os incisivum), carries the incisor teeth. At the 9th week the hard palate is closed, and on it rests the septum of the nose, descending vertically from the frontal process. The lower jaw is formed from the inferior maxillary process. At the circumference of the oral aperture the lips and the alveolar walls are formed. The tongue is formed behind the point of the union of the second and third branchial arches (*His*); while, according to Born, it is formed by an intermediate part between the inferior maxillary processes.

FIG. 671.



Head of embryo rabbit of 10 days (× 12). *a*, eye; *at*, atrium or primitive auricle of heart; *b*, aortic bulb; *k'*, *k''*, *k'''*, first (mandibular), second (hyoid), third (1st branchial) visceral arch; *m*, mouth; *s*, superior, and *u*, inferior maxillary process; *s*, mid-brain; *v*, part of head and fore-brain; *v*, ventricle of heart.

These transformations may be interrupted. If the frontal process remains separate from the superior maxillary processes, then the mouth is not separated from the nose. This separation may occur only in the soft parts, constituting **hare-lip** (Fig. 672); or it may involve the hard palate, constituting **cleft palate**. Both conditions may occur on one or both sides. From the posterior part of the

FIG. 672.

FIG. 673.



FIG. 672.—Hare-lip on the left side.
FIG. 673.—Inner view of the lower jaw of an embryo pig 3 inches long (× 3½). *mk*, Meckel's cartilage; *d*, dentary bone; *cr*, coronoid process; *ar*, articular process (condyle); *ag*, angular process; *ml*, malleus; *mb*, manubrium.

first branchial arch are formed the *malleus* (ossified at the 4th month), and **Meckel's cartilage** (Fig. 673), which proceeds from the latter behind the tympanic ring as a long cartilaginous process, extending along the inner side of the lower jaw, almost to its middle. It disappears after the 6th month; still its posterior part forms the internal lateral ligament of the maxillary articulation. Near where it leaves the malleus is the processus Folii (*Baumüller*). A part of its median end ossifies,

and unites with the lower jaw. The lower jaw is laid down in membrane from the first branchial arch, while the angle and condyle are formed from a cartilaginous process. The union of both bones to form the chin occurs at the 1st year. From the superior maxillary process are formed the inner lamella of the pterygoid process, the palatine process of the upper jaw, and the palatine bone at the end of the 2d month, and lastly the malar bone.

The **second arch** [*hyoid*], arising from the temporal bone, and running parallel with the first arch, gives rise to the stapes (although according to Salensky, this is derived from the first arch), the eminentia pyramidalis, with the stapedius muscle, the incus, the styloid process of the temporal bone, the (formerly cartilaginous) stylo-hyoid ligament, the smaller cornu of the hyoid bone, and lastly the glosso-palatine arch (*His*).

The **third arch** (*thyro-hyoid*) forms the greater cornu and body of the hyoid bone and the pharyngo-palatine arch (*His*).

The **fourth arch** gives rise to the thyroid cartilage (*His*).

Branchial Clefts.—The *first* branchial or visceral is represented by the external auditory meatus, the tympanic cavity, and the Eustachian tube; all the other clefts close. Should one or other of the clefts remain open, a condition that is sometimes hereditary in some families, a **cervical fistula** results, and it may be formed either from without or within. Sometimes only a blind diverticulum remains. Branchiogenic tumors and cysts depend upon the branchial arches (*R. Volkmann*).

[**Relation of Branchial Clefts to Nerves.**—It is important to note that the clefts in front of the mouth (**pre-oral**), and those behind it (**post-oral**), have a relation to certain nerves. The *lachrymal* slit between the frontal and nasal processes is supplied by the *first division of the trigeminus*. The *nasal slit* between the superior maxillary process and the nasal process is supplied by the bifurcation of the *third nerve*. The *oval cleft*, between the superior maxillary processes and the mandibular arch, is supplied by the *second and third divisions of the trigeminus*. The first post-oral or tympanic-Eustachian cleft, between the mandibular arch (1st) and the hyoid arch, is supplied by the *portio dura*. The next cleft is supplied by the *glosso-pharyngeal*, and the succeeding clefts by branches of the *vagus*.]

The **thymus** and **thyroid glands** are formed as paired diverticula from the epithelium covering the branchial arches. The epithelium of the last two clefts does not disappear (pig), but proliferates and pushes inward cylindrical processes, which develop into two epithelial vesicles, the paired commencement of the thyroid glands. These vesicles have at first a central slit, which communicates with the pharynx (*Wölfler*). According to His, the thyroid gland appears as an epithelial vesicle in the region of the 2d pair of visceral arches in front of the tongue—in man at the 4th week. Solid buds, which ultimately become hollow, are given off from the cavity in the centre of the embryonic thyroid gland. The two glands ultimately unite together. The only epithelial part of the *thymus* which remains is the so-called concentric corpuscles (p. 198). According to Born, this gland is a diverticulum from the 3d cleft, while His ascribes its origin to the 4th and 5th aortic arches in man at the 4th week. The **carotid gland** is of epithelial origin, being a variety of the thyroid (*Stieda*).

The Extremities.—The origin and course of the nerves of the brachial plexus (p. 666) show that the *upper extremity* was originally placed much nearer to the cranium, while the position of the *posterior* pair corresponds to the last lumbar and the 3d or 4th sacral vertebræ (*His*).

The clavicle, according to Bruch, is not a membrane bone, but is formed in cartilage like the furculum of birds (*Gegenbauer*). At the 2d month it is four times as large as the upper limb; it is the first bone to ossify at the 7th week. At puberty a sternal epiphysis is formed. Episternal bones must be referred to the clavicles (*Götte*). Ruge regards pieces of cartilages existing between the clavicle and the sternum as the analogues of the episternum of animals. The clavicle is absent in many mammals (carnivora); it is very large in flying animals, and in the rabbit is half membranous. The furculum of birds represents the united clavicles.

The scapula at first is united with the clavicle (*Rathke, Götte*), and at the end of the 2d month it has a median centre of ossification, which rapidly extends. Morphologically, the accessory centre in the coracoid process is interesting; the latter also forms the upper part of the articular surface. In birds the corresponding structure forms the **coracoid bone**, and is united with the sternum; while in man only a membranous band stretches from the tip of the coracoid process to the sternum. The long, basal, osseous strip corresponds to the *supra-scapular bone* of many animals. The other centres of ossification are—one in the lower angle, two or three in the acromion, one in the articular surface, and an inconstant one in the spine. Complete consolidation occurs at puberty.

The humerus ossifies at the 8th to the 9th week in its shaft. The other centres are—one in the upper epiphysis, and one in the capitellum (1st year); one in the great tuberosity and one in the small tuberosity (2d year); two in the condyles (5th to 10th year); one in the trochlea (12th year). The epiphyses unite with the shaft at the 16th to 20th year.

The radius ossifies in the shaft at the 3d month. The other centres are—one in the lower epiphysis (5th year), one in the upper (6th year), and an inconstant one in the tuberosity, and one in the styloid process. They unite at puberty.

The ulna also ossifies in the shaft at the 3d month. There is a centre in the lower end (6th

year), two in the olecranon (11th to 14th year), and an inconstant one in the coronoid process, and one in the styloid process. They consolidate at puberty.

The carpus is arranged in mammals in two rows. The **first row** contains three bones—the radial, intermediate, and ulnar bones. In man these are represented by the scaphoid, semi-lunar, and cuneiform bones; the pisiform is only a sesamoid bone in the tendon of the flexor carpi ulnaris. The **second row** really consists of as many bones as there are digits (*e. g.*, salamander). In man the common position of the 4th and 5th fingers is represented by the unciform bone. Morphologically, it is interesting to observe that an **os centrale**, corresponding to the os carpale centrale of reptiles, amphibians, and some mammals, is formed at first, but disappears at the 3d month, or unites with the scaphoid. Only in very rare cases is it persistent. All the carpal bones are cartilaginous at birth. They ossify as follows: Os magnum, unciform (1st year), cuneiform (3d year), trapezium, semilunar (5th year), scaphoid (6th year), trapezoid (7th year), and pisiform (12th year).

The metacarpal bones have a centre in their diaphyses at the end of the 3d month, and so have the **phalanges.** All the phalanges and the first bone of the thumb have their cartilaginous epiphyses at the central end, and the other metacarpal bones at the peripheral end, so that the first bone of the thumb is to be regarded as a phalanx. The epiphyses of the metacarpal bones ossify at the 2d, and those of the phalanges at the 3d year. They consolidate at puberty.

The innominate bone, when cartilaginous, consists of two parts—the pubis and the ischium (*Rosenberg*). Ossification begins with three centres—one in the ilium (3d to 4th month), one in the descending ramus of the ischium (4th to 5th month), one in the horizontal ramus of the pubis (5th to 7th month). Between the 6th to the 14th year, three centres are formed where the bodies of the three bones meet in the acetabulum, another in the superficies auricularis, and one in the symphysis. Other accessory centres are: One in the anterior inferior spine, the crests of the ilium, the tuberosity and the spine of the ischium, the tuberculum pubis, eminentia iliopectinea, and floor of the acetabulum. At first the descending ramus of the pubis and the ascending ramus of the ischium unite at the 7th to 8th year; the Y-shaped suture in the acetabulum remains until puberty (Fig. 674).

FIG. 674.



Centres of ossification of the innominate bone.

The femur has its middle centre at the end of the 2d month. At birth, there is a centre in the lower epiphyses; slightly later in the head. In addition, there is one in the great trochanter (3d to 11th year), one in the lesser trochanter (13th to 14th year), two in the condyles (4th to 8th year); all unite about the time of puberty. The **patella** is a sesamoid bone in the tendon of the quadriceps femoris. It is cartilaginous at the 2d month, and ossifies from the 1st to the 3d year.

The tarsus generally resembles the carpus. The os calcis ossifies at the beginning of the 7th month, the astragalus at the beginning of the 8th month, the cuboid at the end of the 10th, the scaphoid (1st to 5th year), the I and II cuneiform (3d year), and the III cuneiform (4th year). An accessory centre is formed in the heel of the calcaneum at the 5th to 10th year, which consolidates at puberty.

The metatarsal bones are formed like the metacarpals, only later.

[**Histogenesis of Bone.**—The great majority of our bones are laid down in cartilage, or are preceded by a cartilaginous stage, including the bones of the limbs, backbone, base of the skull, sternum, and ribs. These consist of solid masses of hyaline cartilage covered by a membrane, which is identical with and ultimately becomes the periosteum. The formation of bone, when preceded by cartilage, is called **endochondral bone.** Some bones, such as the tabular bones of the vault of the cranium, the facial bones, and part of the lower jaw, are not preceded by cartilage. In the latter there is merely a membrane present, while from and in it the future bone is formed. It becomes the future periosteum as well. This is called the **intra-membranous** or **periosteal** mode of formation.]

[**Endochondral Formation.—(1)** The cartilage has the shape of the future bone only in miniature, and it is covered with periosteum. In the cartilage an opaque spot or centre of ossification appears, due to the deposition of lime salts in its matrix. The cartilage cells proliferate in this area,

but the first bone is formed under the periosteum in the shaft, so that an osseous case like a muff surrounds the cartilage. This bone is formed by the sub-periosteal **osteoblasts.** (2) Blood vessels, accompanied by osteoblasts and connective tissue, grow into the cartilage from the osteogenic layer of the periosteum (*periosteal processes* of Virchow), so that the cartilage becomes channeled and *vascular*. As these channels extend they open into the already enlarged cartilage lacunæ, absorption of the matrix taking place, while other parts of the cartilaginous matrix become calcified. Thus a series of cavities, bounded by calcified cartilage—the **primary medullary cavities**—are formed. They contain the *primary* or *cartilage marrow*, consisting of blood vessels, osteoblasts, and osteoclasts, carried in from the osteogenic layer of the periosteum, and of course the cartilage cells that have been liberated from their lacunæ. (3) The osteoblasts are now in the interior of the cartilage, where they dispose themselves on the calcified cartilage, and secrete or form around them an osseous matrix, thus enclosing the calcified cartilage, while the osteoblasts themselves become embedded in the products of their own activity and remain as **bone corpuscles.** Bone therefore is at first spongy bone, and as the primary medullary spaces gradually become filled up by new osseous matter it becomes denser, while the calcified cartilage is gradually absorbed. It is to be remembered that, *pari passu* with the deposition of the new bone, bone and cartilage are being absorbed by the **osteoclasts.**]

Chemical Composition of Bone.—Dry bone contains ⅓ of organic matter or **ossein,** from which gelatin can be extracted by prolonged boiling; and about ⅔ mineral matter, which consists of neutral calcic phosphate, 57 per cent.; calcic carbonate, 7 per cent.; magnesic phosphate, 1 to 2 per cent.; calcic fluoride, 1 per cent., with traces of chlorine; and water, about 23 per cent. The **marrow** contains fluid fat, albumin, hypoxanthin, cholesterin, and extractives. The *red* marrow contains more iron, corresponding to its larger proportion of hæmoglobin (*Nasse*).

[The **medullary cavity** of a long bone is occupied by *yellow* marrow, which contains about 96 per cent. of fat. The *red* marrow occurs in the ends of long bones, in the flat bones of the skull, and in some short bones. It contains very little fat, and is really lymphoid in its characters, being, in fact, a *blood-forming tissue* (p. 53).]

Growth of Bones.—Long bones grow in **thickness** by the deposition of new bone from the periosteum, the osteoblasts becoming embedded in the osseous matrix to form the *bone corpuscles*. Some of the fibres of the connective tissue, which are caught up, as it were, in the process, remain as **Sharpey's fibres,** which are calcified fibres of white fibrous tissue, bolting together the peripheric lamellæ. [Müller and Schäfer have shown that there are also fibres in the peripheric lamellæ, comparable to yellow elastic fibres; they branch, stain deeply with magenta, and are best developed in the bones of birds.]

[At the same time that bone is being deposited on the surface, it is being absorbed in the marrow cavity by the action of the **osteoclasts,** so that a metallic ring placed round a bone in a young animal ultimately comes to lie in the medullary cavity (*Duhamel*). The **growth in length** takes place by the continual growth and ossification of the epiphyseal cartilage. The cartilage is gradually absorbed from below, but it proliferates at the same time, so that what is lost in one direction is more than made up in the other (*J. Hunter*).]

When the growth of bone is at an end, the epiphysis becomes united to the diaphysis, the epiphyseal cartilage itself becoming ossified. It is not definitely proved whether there is an interstitial expansion or growth of the true osseous substance itself, as maintained by Wolff (§ 244, 9).

[**Howship's Lacunæ.**—The **osteoclasts** or myeloplaxes are large multinuclear giant cells, which erode bone. They can be seen in great numbers lying in small depressions corresponding to them—Howship's lacunæ—on the fang of a temporary tooth, when it is being absorbed. They are readily seen in a microscopical section of spongy bones with the soft parts preserved.]

The **form** of a bone is influenced by external conditions. The bones are stronger the greater the activity of the muscles acting on them. If pressure acting normally upon a bone be removed, the bone develops in the direction of least resistance, and becomes thicker in that direction. Bone develops more slowly on the side of the greatest external pressure, and it is curved by unilateral pressure (*Lesshaft*).

448. **DEVELOPMENT OF THE VASCULAR SYSTEM. — Heart.** — [The heart appears as a solid mass of cells in the splanchnopleure, at the front end of the embryo, immediately under the "foregut." Very soon a cavity appears in this mass of cells; some of the latter float free in the fluid, while the cellular wall begins to pulsate rhythmically. This hollow cellular structure elongates into a tube, which very soon assumes a shape somewhat like an S (Fig. 675, 1)], and there are indications of its being subdivided into (*a*) an upper aortic part with the **bulbus arteriosus**; (*b*) a middle or **ventricular part**; and (*v*) a lower venous or **auricular part.** The heart then curves on itself in the form of a horseshoe (2), so that the venous end (*A*) comes to lie above and slightly behind the arterial end. On the right and left side, respectively, of the venous part is a blind hollow outgrowth, which forms the large auricle on each side (3, *o*, o_1). The flexure of the body of the heart corresponding to the great curvature (2, *V*) is divided into two large compartments (3), the division being indicated by a slight depression on the surface. The large truncus venosus (4, *v*), which joins with the middle of the posterior wall of the auricular part, is composed of the superior and inferior venæ cavæ. This common trunk is absorbed at a later period into the

enlarging auricle, and thus arise the separate terminations of the superior and inferior venæ cavæ. In man, the heart soon comes to lie in a special cavity, which in part is bounded by a portion of the diaphragm (*His*). At the 4th to 5th week, the heart begins to be divided into a right and a left half. Corresponding to the position of the vertical ventricular furrow, a septum grows upward vertically in the interior of the heart, and divides the ventricular part into a right and left ventricle (5, *R*, *L*). There is a constriction in the heart, between the auricular and ventricular portions, forming the **canalis auricularis.** It contains a communication between the auricle and both ventricles, lying between an anterior and posterior projecting lip of endothelium, from which the auriculo-ventricular valves are formed (*F. Schmidt*). The ventricular septum grows upward toward the canalis auricularis, and is complete at the 8th week. Thus, the large undivided auricle communicates by a right and left auriculo-ventricular opening with the corresponding ventricle (5). At the same time two septa (4, *p a*) appear in the interior of the **truncus arteriosus** (4, *p*), which ultimately meet, and thus divide this tube into two tubes (5, *a p*), the latter forming the aorta and

FIG. 675.



Development of the heart. 1, Early appearance of the heart—*a*, aortic part, with the bulbus, *b*; *v*, venous end. 2, Horseshoe-shaped curving of the heart—*a*, aortic end, with the bulbus, *b*; *V*, ventricle; *A*, auricular part. 3, Formation of the auricular appendages, *o*, o_1, and the external furrow in the ventricle. 4, Commencing division of the aorta, *p*, into two tubes, *a*. 5, View from behind of the opened auricle, *v*, *v*, into the *L*, and *R*, ventricles, and between the two latter the projecting ventricular septum, while the aorta (*a*) and pulmonary artery (*p*) open into their respective ventricles. 6, Relation of the orifices of the superior (*Cs*) and inferior vena cava (*Ci*) to the auricle (schematic view from above)—*x*, direction of the blood of the superior vena cava into the right auricle; *y*, that of the inferior cava to the left auricle; *tL*, tubercle of Lower. 7, Heart of the ripe fœtus—*R*, right, *L*, left ventricle; *a*, aorta, with the innominate, *c*, *c*, carotid, *c*, and left subclavian artery, *s*; *B*, ductus arteriosus; *p*, pulmonary artery, with the small branches *1* and *2*, to the lungs.

pulmonary artery, and are disposed toward each other like the tubes in a double-barreled gun. The septum grows downward until it meets the ventricular septum (5), so that the right ventricle comes to be connected with the pulmonary artery, and the left with the aorta. The division of the truncus arteriosus, however, takes place only in the first part of its course. The division does not take place above, so that the pulmonary artery and aorta unite in one common trunk above. This communication between the pulmonary artery and the aorta is the **ductus arteriosus Bŏtalli** (7, *B*).

In the **auricle** a septum grows from the front and behind, ending internally with a concave margin. The vena cava superior (6, *Cs*) terminates to the right of this fold, so that its blood will tend to go toward the right ventricle, in the direction of the arrow in 6, *x*. The cava inferior, on the other hand (6, *Ci*), opens directly opposite the fold. On the left of its orifice the valve of the foramen ovale is formed by a fold growing toward the auricular fold, so that the blood current from the inferior vena cava goes only to the *left*, in the direction of the arrow, *y*; on the right of the orifice

of the cava, and opposite the fold, is the Eustachian valve, which, in conjunction with the tubercle of Lower (*tL*), directs the stream from the inferior vena cava to the left auricle, through the pervious **foramen ovale.** Compare the fœtal circulation (p. 928). **After birth,** the valve of the foramen ovale closes that aperture, while the ductus arteriosus also becomes impervious, so that the blood of the pulmonary artery is forced to go through the pulmonary branches proceeding to the expanding lungs. Sometimes the foramen ovale remains pervious, giving rise to serious symptoms after a time, and constituting **morbus ceruleus.**

FIG. 676.



The aortic arches. 1. The first position of the 1, 2, and 3 arches. 2. 5 aortic arches; *ta*, common aortic trunk; *ad*, descending aorta. 3. Disappearance of the upper two arches on each side—*S*, subclavian artery; *v*, vertebral artery; *ax*, axillary artery. 4. Transition to the final stage—*P*, pulmonary artery; *A*, aorta; *dB*, ductus arteriosus (*Botalli*); *S*, right subclavian, united with the right common carotid, which divides into the internal (*Ci*) and external carotid (*Ce*); *ax*, axillary; *v*, vertebral artery.

Arteries.—With the formation of the branchial arches and clefts, the number of aortic arches on each side becomes increased to 5 (Fig. 676), which run above and below each branchial cleft, in a branchial arch, and then all reunite behind in a common descending trunk (2, *ad*) (*Rathke*). These blood vessels remain only in animals that breathe by gills. In man, the upper two arches disappear completely (3). When the truncus arteriosus divides into the pulmonary artery and the aorta (4, *P*, *A*), the lowest arch on the left side, with its origin, forms the pulmonary artery (4), and it springs from the right side of the heart. Of these the *left* lowest arch forms the **ductus arteriosus** (*dB*), and from the commencement of the latter proceed the pulmonary branches of the pulmonary artery. Of the remaining arches which are united with the aorta, the left middle one (*i. e.*, the fourth left) forms the permanent aortic arch into which the ductus arteriosus opens, while the right one (fourth) forms the subclavian artery; the third arch forms on each side the origin of the carotids (*Ci*, *Ce*). The arteries of the first and second circulations have been referred to already (p. 922). When the umbilical vesicle, with its primary circulation, diminishes, only *one* omphalo-mesenteric artery is present, which gives a branch to the intestine. At a later period, the omphalo-mesenteric arteries atrophy, while the artery to the intestine—the superior mesenteric—becomes the largest of all, it being originally derived from one of the omphalo-mesenteric arteries.

FIG. 677.



I, First appearance of the veins of the embryo. II, Their transformations to form the final arrangement.

Veins of the Body.—The veins first formed in the **body of the embryo** itself are the two **cardinal veins**; on each side an anterior (Fig. 677, I, *cs*), and a posterior (*ci*), which proceed toward the heart and unite on each side to form a large trunk, the **duct of Cuvier** (*DC*), which passes into the venous part of the heart. The anterior cardinal veins give off the **subclavian veins** (*bb*)

and the common jugular veins, which divide into the external (*Je*) and internal (*Ji*) jugular veins. In addition, there is a *transverse anastomosing branch* passing obliquely from the left (where it divides) to the right, which joins their trunk lower down. In the final arrangement (II) this anastomosis (*As*) becomes very large to form the *left innominate vein*, while with the growth of the arms the subclavian veins increase (*bb*); and lastly, the calibre of the jugular vein changes, the internal jugular (*Ji*) becoming very large, and the external jugular (*Je*) smaller. In some animals, *e.g.*, the dog and rabbit, the large embryonic size is retained. The part of the left superior cardinal vein, from the anastomosis downward to the left duct of Cuvier, disappears. The *posterior cardinal veins* divide in the pelvis into the hypogastric (I, *h*) and external iliac (*f*, *f*). The inferior cava at first is very small (I, *Ve*), divides at the entrance to the pelvis, and on each side goes into the point of division of the cardinal veins. There is also a transverse ascending anastomosis between the right and left cardinal veins. For the final arrangement, the cava inferior (II, *Ci*) dilates, and with it the hypogastric and external iliac vein on each side. The right cardinal vein remains very small (*Vena azygos*, *Az*,) and also the lower part from the left one to the transverse anastomosis. The latter itself also remains very small (*Vena hemiazygos*, *Hz*). On the other hand, the upper part above the anastomosis to the duct of Cuvier disappears. Lastly, the common large venous trunk is so absorbed into the wall of the auricle (*V*) that both venæ cavæ have each a separate orifice (p. 928). The embryonic condition of the veins persists in fishes.

Veins of the First and Second Circulation, and Portal System.—The two omphalo-mesenteric veins (*om*, om_1) open into the posterior or venous end of the tubular heart (Fig.

FIG. 678.



Development of the veins and portal system. *H*, heart; *R*, *L*, right and left side of the body; *om*, right omphalo-mesenteric vein; om_1, left; *u*, right umbilical vein; u_1, left; *Ci*, vena cava inferior; *a*, venæ advehentes; *r*, venæ revehentes; *D*, intestine; *m*, mesenteric vein; 4, *l*, splenic vein; 2, *l*, liver.

678, 1, *H*). The right vein, however, disappears very soon. As soon as the allantois is formed, the two umbilical veins join the truncus venosus(1, *u*, u_1). At first the omphalo-mesenteric veins are larger than the umbilical veins; at a later period this is reversed, and the right umbilical vein disappears. As soon as veins are formed within the body proper of the embryo, the inferior cava also opens into the truncus venosus (2, *Ci*). Gradually the umbilical vein (2, u_1) becomes the chief trunk, while the small omphalo-mesenteric (2, om_1) carries little blood.

Portal System.—The umbilical and omphalo-mesenteric veins pass in part directly under the liver to reach the heart. They send branches—carrying arterial blood—to the liver, and the latter grows round these vessels. These branches are the **venæ advehentes** (2 and 3, *a*). The blood circulating through the liver from the venæ advehentes is returned by other veins, the **venæ revehentes** (2 and 3, *r*), which reunite at the blunt margin of the liver with the chief trunk of the umbilical vein. The umbilical vein (3, u_1) and the omphalo-mesenteric vein (3, om_1) anastomose in the liver. When the intestine develops (3, *D*), the mesenteric vein (*m*) opens into the omphalo-mesenteric vein, and the splenic vein as well (4, *l*). when the spleen is formed. At a later period, when the omphalo-mesenteric vein (4, om_1) disappears, the vein from the intestine now becomes the common trunk of the previously united vessels. It unites in the liver with the umbilical vein to form the trunk of the vena portæ. When, after birth, the umbilical vein disappears (4, u_1), the mesenteric alone remains as the **portal vein**. As the **ductus venosus** is obliterated, the portal vein must send its blood through the liver, and thus the portal circulation is completed.

449. FORMATION OF THE INTESTINAL CANAL.—The **primitive intestine**, or gut, consists of a straight tube proceeding from the head to the tail. The vitelline duct is inserted at that point, which at a later period corresponds to the lower part of the ileum. At the 4th week the tube makes a slight bend toward the umbilicus (Fig. 679, I). As already mentioned, the vitel-

FIG. 679.



Development of the intestine. *v*, stomach; *o*, insertion of the vitelline duct; *t*, small intestine; *c*, colon; *r*, rectum.

FIG. 680.



Formation of the lungs. A, Diverticula of the lungs as double sacs—*k*, mesoblastic layer; *l*, hypoblastic layer; *m*, stomach; *s*, œsophagus. B, Further branching of the lungs—*t*, trachea; *b*, *e*, bronchi; *f*, projecting vesicles.

line duct is obliterated, remaining only for a time as a thread attached to the intestine, being still visible at the 3d month. Sometimes it remains as a short blind tube communicating with the intestine. This is the so-called "*true intestinal diverticulum*;" occasionally a cord—the obliterated omphalo-mesenteric vessels—passes from it to the umbilicus. In very rare cases, the duct may

FIG. 681.



Formation of the omentum. I and II—*hg*, gastro-hepatic ligament; *m*, great, *n*, lesser curvature of the stomach; *s*, posterior, and *i*, anterior fold or plate of the omentum; *mc*, mesocolon; *c*, colon. III—*L*, liver; *t*, small intestine; *b*, mesentery; *p*, pancreas; *d*, duodenum; *r*, rectum; *N*, great omentum.

remain open as far as the umbilicus, forming a congenital fistula of the ileum, or it may give rise to cystic formations (*M. Roth*). In a human fœtus at the 4th week, His distinguished the cavity of the mouth, pharynx, œsophagus, stomach, duodenum, mesenterial intestine, and the hind gut, with the cloaca. The intestine then forms the *first coil* (Fig. 679, II) by rotating on itself at the intes-

tinal umbilicus, so that the lower part of the intestine lying next the knee-like bend comes to lie above, while the upper part lies below. From the lower part of this loop, there proceed the coils of the **small intestine** (III, *i*), which gradually grow longer. From the upper limb of the loop, which also elongates, the **large intestine** is formed; first the descending colon, then by elongation the transverse colon, and lastly the ascending colon.

Glands.—By **diverticula,** or protrusions from the intestine, the various glands are formed. The cells of the hypoblast proliferate and take part in the process, as they form the secretory cells of the glands, while the mesoblastic part of the splanchnopleure forms the membranes of the glands, giving them their shape. The diverticula are as follows:—

1. The **salivary glands,** which grow out from the oral cavity at first as simple solid buds, but afterward become hollow and branched. [The salivary glands are developed from the epiblast lining the mouth (stomodæum).]

2. The **lungs,** which arise as two separate hollow buds (Fig. 680, A, 2), and ultimately have only one common duct, are protrusions from the œsophagus. The upper part of the united tracheal tube forms the larynx. The epiglottis and the thyroid cartilage originate from the part which forms the tongue (*Ganghofner*). The two hollow spheres grow and ramify like branched tubular glands with hollow processes (B, *f*). In the first period of development, there is no essential difference between the epithelium of the bronchi and that of the primitive air vesicles (*Stieda*). The **spleen**

FIG. 682.



Development of the internal generative organs. I, Undifferentiated condition—D, reproductive gland, lying on the tubules of the Wolffian body; W, Wolffian duct; M, Müllerian duct; S, uro-genital sinus. II, Transformations in the female—F, fimbria, with the hydatid, h^1; T, Fallopian tube; U, uterus; S, uro-genital sinus; O, ovary; P, parovarium. III, Transformations in the male—H, testis; E, epididymis, with the hydatid, *h*; *a*, vas aberrans; V, vas deferens; S, uro-genital sinus; *u*, male uterus. 4, *d*, hind gut; *a*, allantois; *u*, urachus; K, cloaca. 5, M, rectum; *m*, perineum; *b*, position of the bladder; S, uro-genital sinus.

and **suprarenal capsules,** however, are not developed in this way. The former arises in a fold of the mesogastrium at the 2d month (*His*); the latter are originally larger than the kidneys.

3. The **pancreas** arises in the same way as the salivary glands, but is not visible at the 4th week (*His*).

4. The **liver** begins very early, and appears as a diverticulum, with two hollow *primitive hepatic ducts,* which branch and form bile ducts. At their periphery they penetrate between the solid masses of cells—the liver cells—which are derived from the hypoblast. At the 2d month the liver is a large organ, and secretes at the 3d month (§ 182).

5. In birds two small blind sacs are formed from the hind gut.

6. The fœtal respiratory organ, the **allantois,** is treated of specially (§ 444).

Peritoneum and Mesentery.—The inner surface of the *cœlom,* or body cavity, the surface of the intestine, and its mesentery are covered by a serous coat—the *peritoneum.* At first the simple intestine is contained in a fold, or duplicature of the peritoneum; on the stomach, which is merely at first a spindle-shaped dilatation of the tube placed vertically, it is called mesogastrium. Afterward, the stomach turns on its side, so that the left surface is directed forward and the right backward. Thus, the insertion of the mesogastrium, which originally was directed backward (to the vertebral column), is directed to the left; the line of insertion forming the region of the great curvature, which becomes still more curved. From the great curvature, the mesogastrium becomes elongated like a pouch (Fig. 681, I and II, *s*, *i*), constituting the omental sac, which extends so far downward

as to pass over the transverse colon and the loops of the small intestine (III, *N*). As the mesogastrium originally consists of two plates, of course the omentum must consist of four plates. At the 4th month, the posterior surface of the omental sac unites with the surface of the transverse colon (*Joh. Müller*).

450. **URINARY AND GENERATIVE ORGANS.—Urinary apparatus.**—The first indication of this apparatus occurs in the chick at the 2d day and in the rabbit at the 9th, as the ducts of the **primitive kidneys** or **Wolffian ducts** (Fig. 682, I, W), which are formed from some cells mapped off from the lateral plate above and to the side of the protovertebræ, and extending from the fifth to the last vertebra. The ducts are solid at first, but soon become hollow, and from their cavities there extend laterally a series of small tubes, which in the chick communicate freely with the peritoneal cavity (*Kölliker*). Into one end of each of these tubes grows a tuft of blood vessels forming a structure resembling the glomeruli of the kidney. The tubes elongate, form convolutions, and increase in number. The upper end of the Wolffian duct is closed at first, its lower end, which lies in a projecting fold—the plica urogenitalis of Waldeyer—in the peritoneal cavity, opens into the uro-genital sinus. Close above the orifice of the Wolffian duct appears the ureter as the duct of the kidney. The duct elongates, and branches at its upper end. Each canal at its end is like a stalked caoutchouc sac (*Toldt*), and into it there grow the already formed glomeruli. The duct of the kidney opens independently into the uro-genital sinus, and forms the **ureter.** The part where the branching of the duct stops forms the pelvis of the kidney, and the branches themselves the renal tubules. Toldt found Malpighian corpuscles in the human kidney at the 2d month, and Henle's loops at the 4th. The first appearance of the **urinary bladder** is at the 4th week (*His*), and is more distinct at the 2d month, as the dilated first part of the allantois (Fig. 682). The upper part of the allantois remains as the obliterated **urachus**, in the middle vesicle ligament.

FIG. 683.

Section of mammalian ovary showing development of ova and their follicles. *Ei*, Ripe ovum; *G*, follicular cells of germinal epithelium; *g*, blood vessels; *K*, germinal vesicle and spot; *KE*, germinal epithelium; *Lf*, liquor folliculi; *Mg*, membrana granulosa; *Mp*, zona pellucida; *PS*, ingrowths from germinal epithelium, ovarian tubes, by means of which some of the nests retain their connection with the epithelium; *S*, cavity which appears within the Graafian follicle; *So*, stroma of ovary; *Tf*, Theca folliculi or ovi-capsule; *U*, primitive ova.

Internal Reproductive Organs.—In front of and internal to the Wolffian bodies, there arises in the mesoblast the elongated reproductive gland, **germ-ridge**, or mass of **germ epithelium** (Fig. 682, I, D), which in both sexes is originally alike (Fig. 683, K, E). In addition, there is formed a canal or duct parallel to the Wolffian duct (W), which also opens into the uro-genital sinus; this is **Müller's duct** (M). The elevation of the future reproductive gland is covered originally by germ epithelium (*Waldeyer*). The upper end of the Müllerian duct opens free into the abdominal cavity, while the lower ends of both ducts unite for a distance. Some of the germinal cells covering the surface of the future ovary enlarge to form ova, and sink into the stroma to form ova embedded in their Graafian follicles (§ 433) (Fig. 683). In the **female**, the Müllerian ducts form the Fallopian tube (II, T), and the lower united ends the uterus.

In the **male**, the germ epithelium is not so full. According to Waldeyer, there are two kinds of tubes in the Wolffian bodies, and some of these penetrate the position of the reproductive gland. These tubes, which are connected with the Wolffian ducts, become the seminiferous tubules (*v. Wittich*), and the Wolffian duct itself becomes the vas deferens, with the vesiculæ seminales. According to some other observers, however, tubes which become the seminiferous tubules, are developed within the reproductive gland itself, and these tubes lined with their germ epithelium ultimately form a connection with the Wolffian ducts.

The **Müllerian ducts**, which are really the ducts of the reproductive glands, disappear in man, all except the lowest part, which becomes the male uterus or vesicula prostatica (III, *u*),—the homologue of the uterus. The upper tubules of the Wolffian body unite at the 3d month with the reproductive gland (which has now become the body of the testis), and become the coni vasculosi of the epididymis, which are lined by ciliated epithelium (E); the remainder of the Wolffian body disappears. Some detached tubules form the vasa aberrantia (*a*) of the testicle (*Kobelt*). The hydatid of Morgagni (*h*), at the head of the epididymis, according to Luschka and others, is a part of the

epididymis—Fleischl regards it as the rudiment of the male ovary. The organ of the Giraldès is part of the Wolffian body. The Wolffian duct itself becomes the vas deferens (V) from which the vesiculæ seminales are developed. The two Wolffian and two Müllerian ducts, as they enter the pelvis, unite to form a common cord—the **genital cord.**

In the **female**, the tubes of the Wolffian bodies disappear, all except a few tubules, lined with ciliated epithelium, constituting the **parovarium**, or organ of Rosenmüller (Fig. 646), and a part analogous to the organ of Giraldès in the broad ligament of the uterus (*Waldeyer*) (Fig. 682, P). The same is the case with the Wolffian ducts. In some animals (ruminants, pig, cat and fox) they remain permanently as the **ducts of Gaertner.**

The Müllerian duct is frayed out at its upper end to form the fimbriæ of the Fallopian tube, and it is often provided with a hydatid (h^1). That part of the uro-genital sinus into which the four ducts open grows above into a hollow sphere, which forms the vagina (*Rathke*). According to Thiersch and Leuckart, however, the two Müllerian ducts unite at their lower ends to form the united uterus (U) and vagina, while their free upper ends form the Fallopian tubes (T). The Müllerian ducts at first open into the posterior part of the urinary bladder below the ureters (uro-genital sinus, S), while ultimately this part of the bladder becomes so elongated posteriorly that the vagina (the united Müllerian ducts) and the urethra are united below and deeply within the vestibule of the vagina. At the 3d to the 4th month, the uterus and vagina are not separate from each other, but at the 5th to the 6th month the uterus is defined from the vagina.

The **testicles** lie originally in the lumbar region of the abdominal cavity (Fig. 684, V, *t*), and are carried by a fold of the peritoneum—the mesorchium (*m*). From the hilum of the testicle a cord, the **gubernaculum testis**, runs through the inguinal canal into the base of the scrotum. At the same time a septum-like process is developed independently from the peritoneum to the base of the scrotum (*pv*). The testicle passes through the inguinal canal into the scrotum, but the mechanism and the cause of the descent are not accurately ascertained.—[Descent of testis, § 446.]

The **ovaries** also descend somewhat. The round ligament of the uterus corresponds to the gubernaculum testis. A process of the peritoneum passes in the female into the inguinal canal as Nuck's canal. It is rare to find the ovaries descending into the labia majora.

[The origin of the urinary and generative organs is undoubtedly associated with the development of the Wolffian bodies. The researches of Semper and Balfour on elasmobranch fishes show that the process is a very complex one. There is a mass of cells on each side of the vertebral column, which is divided into three parts, the first called the **pronephros**, or head kidney of Balfour and Sedgwick, the middle one, the **mesonephros** or Wolffian body, and the posterior one or **metanephros**, which is formed after the other two, gives origin to the permanent kidney in the amniota. The Müllerian duct is connected with the pronephros, the Wolffian duct with the mesonephros, and the ureter with the metanephros.]

[The following table, modified from Quain, shows the destiny of these structures:—

Female.	*Male.*
Müllerian Ducts (Ducts of the Pronephros).	
Fallopian tubes.	Hydatid of Morgagni.
Hydatid.	Male uterus.
Uterus and vagina.	
Wolffian Bodies (Mesonephros).	
Parovarium.	Vasa efferentia, Coni vasculosi.
Paroöphoron.	Organ of Giraldès, Vasa aberrantia.
Round ligament of the uterus.	Gubernaculum testis.
Wolffian Ducts.	
Chief tube of parovarium.	Convoluted tube of epididymis.
Ducts of Gaertner.	Vas deferens and vesiculæ seminales.
Metanephros.	
Kidney.	Ureter.]

The external genitals are at first not distinguishable in the two sexes (Fig. 684, *I*). At the 4th week, there is merely an orifice at the posterior extremity of the trunk, representing both the anus and the opening of the urachus, and forming a **cloaca** (Fig. 682, 4, K). In front of this an elevation—the **genital eminence**—appears about the 6th week, and on each side of the orifice a large cutaneous elevation (*II*, *w*). At the end of the 2d month, there is a groove on the under surface of the genital eminence, leading back to the cloaca, and with distinct walls bounding it (*II*, *r*). At the middle of the 3d month, the cloacal opening is divided by the growth of the perineum, between the urachus (now become the urinary bladder) (Fig. 682, 5, *b*) and the rectum (M).

In the **male**, the genital eminence enlarges, its groove deepens from the opening of the bladder onward to the apex of the elevation at the 10th week. The two edges unite to enclose the groove which becomes the urethra. When this does not take place, **hypospadias** occurs. At the 4th·

month the glans, and at the 6th the prepuce, are formed. The large cutaneous folds meet in the middle line or raphe to form the scrotum.

In the **female**, the undifferentiated condition remains to a certain extent permanent. The small genital eminence remains as the **clitoris**, the margins of its furrow become the **nymphæ**, the cutaneous elevations remain separate to form the **labia majora**. The uro-genital sinus remains short as the vestibule of the vagina, while in man, by the closing of the genital groove, it has a long additional tube, the urethra. [The accompanying illustrations, after Schroeder, show the changes of the external organs of generation in the female. In the early period (6th week), the

FIG. 684.



Development of the external genitals. *I.* and *II.*—Genital eminence; *r*, genital groove; *s*, coccyx; *w*, cutaneous elevations. *IV*—*P*, penis; *R*, raphe penis; *S*, scrotum. *III.*—*c*, clitoris; *l*, labia minora; *L*, labia majora; *a*, anus. *V.* and *VI.*—Descent of the testicle; *t*, testis; *m*, mesorchium; *pv*, processus vaginalis of the peritoneum; *M*, abdominal wall; *S*, scrotum.

hind gut (Fig. 685, R), allantois (ALL), and the Müllerian ducts (M) communicate, but not with the exterior. About the 10th week a depression or inflection of the skin takes place, **genital cleft**, until it meets the hind gut and allantois, whereby the cloaca (Fig. 686, CL) is formed. The cloaca is then divided into an interior part, the **uro-genital sinus**, into which the Müllerian ducts open, and a posterior part, the anus. There is a downward growth of the tissue between the hind gut and the allantois to form the perineum (Fig. 687). The uro-genital sinus then contracts at its upper

FIG. 685.

R, rectum continuous with the allantois (ALL—bladder); M, duct of Müller (vagina); A, depression of skin below genital eminence, growing inward to form the vulva.

FIG. 686.

The depression has become continuous with the rectum and allantois to form the cloaca (CL).

FIG. 687.



The cloaca is becoming divided into uro-genital sinus (SU) and anus by the downward growth of the perineal septum. The ducts of Müller are united to form the vagina (V).

FIG. 688.

Perineum completely formed.

part to form the short urethra, its lower part remaining as the vestibule (Fig. 688, SV), while the vagina has been formed by the union of the lower parts of the two Müllerian ducts. The bladder (B) is the expanded lower end of the stalk of the allantois.]

The causes of the difference of sex are by no means well known. From a statistical analysis of 80,000 cases, the influence of the age of the parents has been shown by Hofacker and Sadler. If the husband is younger than the wife there are as many boys as girls; if both are of the same age, there are 1029 boys to 1000 girls; if the husband is older, 1057 boys to 1000 girls. In insects, food has a most important influence. Pflüger's investigations on frogs show that all external con-

ditions during development are without effect on the determination of the sex, so that the latter would seem to be determined before impregnation.

451. FORMATION OF THE CENTRAL NERVOUS SYSTEM.—Fore brain.—At each side of the fore brain, or anterior cerebral vesicle, which is covered externally by epiblast and internally by the ependyma, there grows out a large stalked hollow vesicle, the rudiment of the **cerebral hemispheres.** The relatively wide opening in the stalk, or communication, ultimately becomes very small, and is the foramen of Monro. The middle part between the two cerebral vesicles remains small, and is the **'tween or interbrain** with the third ventricle in its interior. It elongates at the second month toward the base of the brain as a funnel-shaped projection, to form the tuber cinereum with the infundibulum. The thalami optici, projecting and enlarging from the sides of the third ventricle, narrow the foramen of Monro to a semilunar slit. At the base of the brain are formed, in the second month, the corpora albicantia, at the third the chiasma; while within the third ventricle the commissures are formed. The **hypophysis,** belonging to the mid brain, is a diverticulum of the nasal mucous membrane, extending through the base of the skull toward the hollow infundibulum, which grows to meet it (Fig. 505, *T*). There is, as it were, a tendency to the union of the cavity of the fore gut with the medullary tube. In the amphioxus (*Kowalewsky*), goose (*Gasser*), and lizard (*Strahl*) the medullary tube communicated originally with the hind gut by the canalis myeloentericus. The choroid plexus, which grows into the ventricles of the hemispheres through the foramen of Monro, is a vascular development of the ependyma. At the fourth month, the **conarium** (pineal gland) is formed, and at this time the corpora quadrigemina cover the hemispheres. The **corpora striata** begin to be developed in the cerebral (lateral) ventricle at the second month, while the cornu ammonis is formed at the fourth month. [The external walls and floor of the primitively simple central hemipheres become much thickened, the thickenings in the floor constitute the corpora striata, which protrude into the lateral ventricles, their position being indicated on the surface of the brain by the Sylvian fissure. As they extend backward, they become connected with the optic thalami (Fig. 689, *st*, *th*). The corpora striata are connected together by the anterior commissure. From the inner wall of each hemisphere, there grow into each lateral ventricle two projections; the upper one forms the **hippocampus major** or cornu ammonis (Fig. 689, *h*), while the lower one becomes folded, remains thin, receives numerous blood vessels from the falx cerebri, and forms the **choroid plexus** (Fig. 689, *pl*).] At the third month the Sylvian fissure is formed, and the basis of the island of Reil. The permanent cerebral convolutions are formed from the seventh month onward.

FIG. 689.



Transverse section of the brain of an embryo sheep 2.7 cm. long; × 10. *a*, cartilage of orbito-sphenoid; *c*, peduncular fibres; *ch*, optic chiasm; *f*, median cerebral fissure; *h*, cerebral hemispheres, with a convolution upon their inner wall, projecting into the lateral ventricle, *l*; *m*, foramen of Monro; *o*, optic nerve; *p*, pharynx; *pl*, lateral plexus; *s*, termination of the median fissure, which forms the roof of the third ventricle; *sa*, body of the anterior sphenoid; *st*, corpus striatum; *t*, third ventricle; *th*, anterior deep portion of the optic thalamus (*Kölliker*).

The **mid brain,** or middle cerebral vesicle, is gradually covered over by the backward growth of the hemispheres; its cavity forms the **aqueduct of Sylvius** (Fig. 690). Depressions appear on the surface of the vesicle to divide it into four, the **corpora quadrigemina,** in birds into two, the corpora bigemina (Fig. 690, *bg*), the longitudinal depression being formed at the third, and the transverse one at the seventh month. The **cerebral peduncle** is formed by a thickening in the base of this vesicle.

In the **hind brain** are found the cerebellar hemispheres, which grow backward to meet in the middle line. The vermis is formed at the seventh month. The cerebellum covers in the part of the medullary tube lying below it, which is not closed, as far as the calamus. The **pons** arises in the floor of the hind brain at the third month.

The spindle-shaped narrow **after brain** forms the **medulla oblongata,** with the opening of the medullary tube in its upper part.

[The following table, from Quain, shows the destiny of each cerebral vesicle:—

I. Anterior Primary Vesicle, ...	1. *Prosencephalon*, ... (fore brain)	Cerebral hemispheres, corpora striata, corpus callosum, fornix, lateral ventricles, olfactory bulb.
	2. *Thalamencephalon*, . . (inter or 'tween brain)	Thalami optici, pineal gland, pituitary body, crura cerebri, aqueduct of Sylvius, optic nerve.
II. Middle Primary Vesicle, ...	3. *Mesencephalon*, ... (mid brain)	Corpora quadrigemina, cruri cerebri, aqueduct of Sylvius, optic nerve (secondarily).
III. Posterior Primary Vesicle, . .	4. *Epencephalon*, ... (hind brain)	Cerebellum, pons, anterior part of the fourth ventricle.
	5. *Metencephalon*, ... (after brain)	Medulla oblongata, fourth ventricle, auditory nerve.

Spinal Cord.—The spinal cord is developed from the medullary tube behind the medulla oblongata, first the gray matter around the canal, while the white matter is added afterward outside this. The ganglionic cells increase by division in amphibians (*Lominsky*). At first the spinal cord reaches to the coccyx. In the adult, the spinal cord reaches only to the first or second lumbar vertebræ, so that it does not elongate so much as the vertebræ can. It is a question how far this want of harmony in the development of these two structures may lead to disturbances of sensibility or paralysis of the lower limbs in children. The first **muscles** are formed in the back at the second month; at the fourth month they are red. The **spinal ganglia** are formed from a special strip of epiblastic cells. They are seen at the 4th week, and so are the anterior spinal roots and some of the trunks of the spinal nerves, while the posterior roots are still absent. At this period the ganglia of the fifth, seventh, eighth, ninth, and tenth nerves and part of their origins are present, while the first, second, third, and twelfth nerves and the sympathetic are not yet far differentiated (*His*). The **peripheral nerves** grow out from the ganglia of the spinal cord (first the motor and afterward the sensory nerves), and penetrate into the other parts of the body (*His*). At first they are devoid of myelin.

FIG. 690.

Diagram of an embryonic fowl's brain. *ac*, anterior commissure; *amv*, anterior medullary velum, and below it the aqueduct of Sylvius and the cerebral peduncles; *ba*, basilar artery; *bg*, corpora bigemina; *cai*, internal carotid artery; *cbl*, cerebellum; *ch*³, *ch*⁴, choroid plexuses of the third and fourth ventricles; *h*, cerebral hemispheres; *inf*, infundibulum; *lt*, lamina terminalis; *li*, lateral ventricle; *obl*, medulla oblongata; *olf*, olfactory lobe and nerve; *opc*, optic commissure; *pin*, pineal gland, *pit*, pituitary body; *ps*, pons Varolii; *r*, floor of fourth ventricle; *st*, corpus striatum; *v*³, third ventricle; *v*⁴, fourth ventricle (*Quain, after Mihalkovics*).

452. THE SENSE ORGANS.—Eye.—The **primary optic vesicle** grows out from the fore brain toward the outer covering of the head or epiblast, and soon becomes folded in on itself (fourth week), so that the stalked optic vesicle is shaped like an egg cup (Fig. 691, I). The cavity in the interior of this cup is called the **secondary optic vesicle.** The inflected part becomes the retina (IV, *r*), while the posterior part becomes the choroidal epithelium (IV, *p*). The stalk becomes the optic nerve. At the under surface of the depression there is a slit—the **choroidal fissure**—which permits some of the mesoblast to gain access to the interior of the eye. This slit forms the **coloboma** (II); it is prolonged backward on the stalk, and contains the central artery of the retina. The margins of the coloboma afterward unite completely with each other, but in some rare conditions this does not take place, in which case we have to deal with a coloboma of the choroid or retina, as the case may be. In the bird the embryonic coloboma slit does not close up, but a vascular process of the mesoblast dips into it, and passes into the eye to form the **pecten** (p. 846). The same is the case in fishes, where there is a large vascular process of the meso- and epiblast forming the *processus falciformis* (p. 846).

The depression or inflection of the optic vesicle is due to the downgrowth into it of a thickening of the epiblast (I, L). It is hollow, and as it grows inward ultimately becomes spherical and separated from the epiblast to form the **crystalline lens,** so that the lens is epiblastic in its origin, while the capsule of the lens is a cuticular structure formed from the epiblast. That part of the epiblast which covers the vesicle in front of the lens ultimately becomes the stratified epithelium of the cornea. The layer of pigment of the invaginated optic vesicle is applied to the ciliary body, and the posterior surface of the iris, when the latter is formed. The cornea is formed at the sixth week. The substance

of the choroid, sclerotic, and cornea is formed around the position of the eye from the mesoblast (*m*). The capsule of the lens is at first completely surrounded by a vascular membrane—the **membrana capsulo-pupillaris.** Afterward, the lens passes more posteriorly into the eye—the anterior part of the capsulo-pupillary membrane, however, remains in the anterior part of the eye, while toward it grows the margin of the iris (seventh week), so that the pupil is closed by this part of the vascular capsule, membrana pupillaris. The blood vessels of the iris are continuous with those of the pupillary membrane; those of the posterior capsule of the lens give off the hyaloid artery, a continuation of the

FIG. 691.



Development of the eye. I, Inflexion of the sac of the lens (L) into the primary optic vesicle (P)—*e*, epidermis; *m*, mesoblast. II, The inflexion seen from below—*n*, optic nerve; *e*, the outer; *i*, the inner layer of the inflected vesicle; L, lens. III, Longitudinal section of II. IV, Further development—*e*, corneal epithelium; *c*, cornea; *m*, membrana capsulo-pupillaris; L, lens; *a*, central artery of the retina; *s*, sclerotic; *ch*, choroid; *p*, pigment layer of the retina; *r*, retina. V, Persistent remains of the pupillary membrane.

central artery of the retina; its veins pass into those of the iris and choroid. The vitreous humor at the fourth week is represented by a cellular mass between the lens and the retina. The pupillary membrane disappears at the seventh month. It may remain throughout life (V).

Organ of Smell.—On the under surface and lateral limit of the fore-brain, the epiblast forms a groove or pit with thickened epithelium, which forms a depression toward the brain, but always remains as a pit or depression; this is the **olfactory** or **nasal pit,** to which the olfactory nerve afterward sends its branches. For the formation of the nose, see p. 931.

FIG. 692.



Early stages in the development of the vertebrate ear. A–D, Early stages in the chick (*Reissner*). E, Transverse section through the auditory pit of a 50 hours' chick (*Marshall*). F, Transverse section through the hind brain of a fœtal sheep. *acv*, anterior cardinal (jugular) vein; *am*, amnion; *ao*, aortic arch; *ce*, cochlea; *rv*, recessus (aqueductus) vestibuli; *v*, vestibulum; *vc*, vertical semicircular canal; *viii*, auditory nerve.

Organ of Hearing.—On both sides of the after-brain or posterior brain vesicle, above the first visceral or hyoid arch, there is a depression or pit formed in the epiblast, which gradually extends deeper toward the brain—this is the **labyrinth pit** or **auditory sac,** which soon becomes flask-shaped (Fig. 692, A, B).

[The stalk, which originally connected the cavity of the sac with the surface, persists as the aqueductus vestibuli; and its blind swollen distal extremity as the **saccus endolymphaticus,** or recessus vestibuli (*Haddon*, Fig. 692, *r*, *v*).] The pit is ultimately completely cut off from the

epiblast, just like the lens, and is now called the **vesicle of the labyrinth** or **primary auditory vesicle.** Its related portion forms the utricle, from which, at the 2d month, the **semicircular canals** and the **cochlea** are developed (Fig. 692, D). The union with the brain occurs later, along with the development of the auditory nerve. The first visceral cleft remains as an irregular passage from the Eustachian tube to the external auditory meatus. The *outer ear* appears at the 7th week.

Organ of Taste.—The gustatory papillæ are developed in the later period of intra-uterine life, and several days before birth the taste-buds appear (*Fr. Hermann*).

453. **BIRTH.**—With the growth of the ovum, the uterus becomes more distended, its walls more muscular and more vascular, although the uterine walls are not thicker at the end of pregnancy. Toward the end of gestation the cervical canal is intact until labor begins, or at any rate it is but slightly opened up at its upper part. After a period of 280 days of gestation, "labor" begins, whereby the contents of the uterus are discharged. The labor pains occur rhythmically and periodically, being separated from each other by intervals free from pain. Each pain begins gradually, reaches a maximum, and then slowly declines. With each pain the heat of the uterus increases (§ 303), while the heart-beat of the fœtus becomes slower and feebler, which is due to stimulation of the vagus in the medulla oblongata (§ 369, 3).

[At the full time the membranes and placenta line the uterus. The membranes consist, from within outward, of amnion, chorion, decidua reflexa, and decidua vera. The fundi of the uterine glands persist in the deep part of the decidua vera, and thus form a spongy layer, the part above this being the compact layer in the deep part of the placenta, *e. g.*, near the uterine wall; we have also the fundi of the uterine gland persisting in the decidua serotina. When the placenta and membranes are expelled after birth, the **line of separation** takes place in the part of the membranes and placenta where the fundi of the glands persist. After labor is completely finished, the uterus is lined by the remains of the spongy layer of the decidua vera and serotina, *e. g.*, is lined by a layer which contains the fundi of the uterine glands. The new mucous membrane is **regenerated** by the growth of the epithelium and connective tissue in this part. The **membranes expelled** are made up of amnion, chorion, deciduæ reflexæ, and the compact layer of the decidua vera.]

The uterine movements during labor proceed in a peristaltic manner from the Fallopian tube to the cervix, and occupy 20 to 30 seconds. In the curve registered by these movements there is usually a more steep ascent than descent.

[**Power in Ordinary Labor.**—Sometimes the ovum is expelled whole, the membranes containing the liquor amnii remaining unruptured. Poppel has pointed out that the force which ruptures the bag of membranes is sufficient to complete delivery, so that, as Matthews Duncan remarks, the strength of the membranes gives us a means of ascertaining the power of labor in the easiest class of natural labors. Matthews Duncan, from experiments on the pressure required to rupture the membranes, concludes that the great majority of labors are completed by a propelling force not exceeding 40 lbs.]

Polaillon estimates the pressure exerted by the uterus upon the fœtus at each pain to be 154 kilos. [338.8 lbs.], so that, according to this calculation, the uterus at each pain performs 8820 kilogram-metres of work (§ 301). [This estimate is certainly far too high.]

After-Birth.—After the fœtus is expelled, the placenta remains behind; but it is soon expelled by the contractions of the uterus. During the contraction of the uterus to expel the placenta, a not inconsiderable amount of the placental blood is forced into the child (§ 40). [It is more probable that the child aspirates the blood from the fœtus portion of the placenta. This can be seen in late ligature of the cord. The child may thus gain two ounces of blood.] After a time the placenta, the membranes and the decidua—constituting the *after-birth*—are expelled.

Influence of Nerves on the Uterus.—1. Stimulation of the hypogastric plexus causes contraction of the uterus. The fibres arise from the spinal cord, from the last dorsal, and upper three or four lumbar nerves, run into the sympathetic, and then reach the hypogastric plexus (*Frankenhäuser*). 2. Stimulation of the nervi erigentes, which are derived from the sacral plexus, causes movement (*v. Basch and Hofmann*). 3. Stimulation of the lumbar and sacral parts of the cord causes powerful movements (*Spiegelberg*). There is a *centre for the act of parturition* in the lumbar region of the cord (§ 362, 6). The uterus, like the intestine, probably contains *independent* or *parenchymatous nerve centres* (*Körner*), which can be excited by suspension of the respiration, and

by anæmia (by compressing the aorta, or rapid hemorrhage). Decrease of the bodily temperature diminishes, while an increase of the temperature increases the movement, which, however, ceases during high fever (*Fromme*). The experiments made by Rein upon bitches show that, if all the nerves going to the uterus be divided, practically all the functions connected with conception, pregnancy, and parturition can take place, even although the uterus is separated from all its cerebro-spinal connections. Hence, we must look to the presence of some **automatic ganglia** in the uterus itself. According to Dembo, there is a centre in the anterior wall of the vagina of the rabbit. According to Jastreboff, the vagina of the rabbit contracts rhythmically. Sclerotic acid greatly excites the uterine contractions (*v. Swiecicki*), so does anæmia (*Kronecker and Jastreboff*). 4. The uterus contracts **reflexly** on stimulating the central end of the sciatic nerve (*v. Basch and Hofmann*), the central end of the brachial plexus (*Schlesinger*), and the nipple (*Scanzoni*). 5. The uterus is supplied by *vasomotor nerves* (hypogastric plexus), which come from the splanchnic; and also by *vaso-dilator fibres*, the latter through the nervi erigentes. The vasomotor nerves are affected reflexly by stimulation of the sciatic nerve (*v. Basch and Hofmann*).

[In the rabbit the vagina and uterine cornua exhibit regular movements of a "peristaltic" nature. These exist apart from any extraneous stimulus, and are probably a vital property of the tissue. They can be demonstrated in animals a few weeks old, and have been recorded continuously for many hours. Frequently they are more vigorous six hours after than at the beginning, showing that they are not due to the irritation of the operation necessary to demonstrate them.

Their rate and extent vary. In young animals they are frequent (1 to 4 per minute), but irregular in character. In nulliparous adults they are less frequent and somewhat more regular. During pregnancy they increase greatly in extent, and their rate becomes 1 in 120 to 130 seconds. These characters are retained after pregnancy for many months at least. They are diminished or abolished by chloroform narcosis, are scarcely affected by ether. Water at 100° to 120° F. produces a persistent contraction accompanied by blanching of the tissue. Similar effects are produced by dilute acetic acid (*Milne Murray*).]

Lochia.—After birth the whole mucous membrane (decidua) is shed; its inner surface, therefore, represents a large wounded surface, on which a new mucous membrane is developed. The discharge given off after birth constitutes the lochia.

Involution of the Uterus.—After birth the thick muscular mass decreases in size, some of its fibres undergoing fatty degeneration. Within the lumen of the blood vessels of the uterus itself, there begins in the interna of these vessels a proliferation of the connective-tissue elements, whereby within a few months the blood vessels so affected become completely occluded. The smooth muscular fibres of the middle coat of the arteries undergo fatty degeneration. The relatively large vascular spaces in the region of the placenta are filled by blood clots, which are ultimately traversed by outgrowths of the connective tissue of the vascular walls.

Milk Fever.—After birth, there is a peculiar action on the vasomotor system, constituting milk fever, while at the 2d to 3d day there is a more copious supply of blood to the mammary gland for the secretion of milk (§ 231). [After birth the pulse becomes slow and remains so in a normal puerperium. The so-called milk fever is not found in cases where strict cleanliness is observed during the labor and puerperium.] For the cause of the first respiration in the child, see p. 717.

454. **COMPARATIVE—HISTORICAL.**—A sketch of the development of man must necessarily have some reference to the general scheme of development in the Animal Kingdom. The question as to how the numerous forms of animal life at present existing on the globe have arisen has been answered in several ways. It has been asserted that each species has retained its characters unchanged from the beginning, so that we speak of the "constancy of species." This view, developed by Linnæus, Cuvier, Agassiz, and others, is opposed by that supported by Lamarck, 1809, or the doctrine of the "Unity of the Animal Kingdom," corresponding to the ancient view of Empedocles, that all species of animals were derived by variations from a few fundamental forms; that at first there were only a few lower forms from which the numerous species were developed—a view supported by Geoffrey St. Hilaire and Goethe. After a long period this view was restated and elucidated in the most brilliant and most fruitful manner by Charles Darwin in his "Origin of Species" (1859) and other works. He attempted to show how modifications may be brought about by uniform and varying conditions acting for a long time. Among created beings each one struggles with its neighbor, so that there is a real "**struggle for existence.**" Many qualities, such as vigor, rapidity, color, reproductive activity, etc., are hereditary, so that in this way by "**natural selection**" there may be a gradual improvement, and therewith a gradual change of the species. In addition, organ-

isms can, within certain limits, accommodate themselves to their surroundings or environment. Thus certain useful organs or parts may undergo development, while inactive or useless parts may undergo retrogression, and form "**rudimentary organs.**" This process of "natural selection," causing gradual changes in the form of organisms, finds its counterpart in "**artificial selection**" among plants and animals. Breeders of animals, for example, by selecting the proper crosses, can within a relatively short time produce very material alterations in the form and characters of the animals which they breed, the changes being more pronounced than many of those that separate well-defined species. But, just as with artificial selection, there is sometimes a sudden "**reversion**" to a former type, so in the development of species by natural selection there is sometimes a condition of **atavism.** Obviously, a wide distribution of one species in different climates must increase the liability to change, as very different conditions of environment come into play. Thus, the migration of organisms may gradually lead to a change of species.

Biological Law.—Without discussing the development of different organisms, we may refer to the "*fundamental biological law*" of Haeckel, viz., "that the ontogeny is a short repetition of the phylogeny," [**ontogeny** being the history of the development of *single* beings, or of the individual from the ovum onward, while **phylogeny** is the history of the development of a *whole stock* of organisms, from the lowest forms of the series upward] (p. 33). When applied to man, this law asserts that the individual stages in the course of the development of the human embryo, *e. g.*, its existence as a unicellular ovum, as a group of cells after complete cleavage, as a blastodermic vesicle, as an organism without a body cavity, etc.; that these stages of development indicate or represent so many animal forms, through which the human species in the course of untold ages has been gradually evolved. The individual stages which the human race has passed in this process of evolution are rapidly rehearsed in its embryonic development. This conception has not passed without challenge. In any case, the comparison of the human development and its individual organs with the corresponding perfect organs of lower vertebrates is of great importance. Thus, a mammal during the development of its organs is originally possessed of the tubular heart, the branchial clefts, the undeveloped brain, the cartilaginous chorda dorsalis, and many arrangements of the vascular system, etc.), which are permanent throughout the life of the lowest vertebrates. These incomplete stages are perfected in the ascending classes of vertebrates. Still, there are many difficulties to contend with in establishing both the evolution hypothesis of Darwin and the biological law of Haeckel.

Historical.—Although the impetus to the study of the history of development has been most stimulated in recent times, the ancient philosophers held distinct but very varied views on the question of development. Passing over the views of Pythagoras (550 B. C.) and Anaxagoras (500 B. C.), Empedocles (473 B. C.) taught that the embryo was nourished through the umbilicus; while he named the chorion and amnion. Hippocrates observed incubated eggs from day to day, noticed that the allantois protruded through the umbilicus, and observed that the chick escaped from the egg on the 20th day. He taught that a 7 months' foetus was viable, and explained the possibility of superfœtation from the horns of the uterus. The writings of Aristotle (born 384 B. C.) contain many references to development, and many of them are already referred to in the text. He taught that the embryo receives its vascular supply through the umbilical vessels, and that the placenta sucked the blood from the vascular uterus like the rootlets of a tree absorbing moisture. He distinguished the polycotyledonary from the diffuse placenta; and he referred the former to animals without a complete row of teeth in both jaws In the incubated egg of the chick he distinguished the blood vessels of the umbilical vesicle, which carried food from the cavity of the latter, and also the allantois. He also observed that the head of the chick lay on its right leg, and that the umbilical sac was ultimately absorbed into the body. The formation of double monsters he ascribed to the union of two germs or two embryos lying near each other. During generation the female produces the matter, the male the principle which gives it form and motion. There are also numerous references to reproduction in the lower animals. Erasistratus (304 B. C.) described the embryo as arising by new formations in the ovum—Epigenesis,—while his contemporary, Herophilus, found that the pregnant uterus was closed. He was aware of the glandular nature of the prostate, and named the vesiculæ seminalis and the epididymis. Galen (131–203 A. D.) was acquainted with the existence of the foramen ovale, and the course of the blood in the fœtus through it, and through the ductus arteriosus. He was also aware of the physiological relation between the breast and the blood vessels of the uterus, and he described how the uterus contracted on pressure being applied to it. In the Talmud it is stated that an animal with its uterus extirpated may live, that the pubes separates during birth, and there is a record of a case of Cæsarean section, the child being saved. Sylvius described the value of the foramen ovale; Vesalius (1540) the ovarian follicles; Eustachius († 1570) the ductus arteriosus (Botalli) and the branches of the umbilical vein to the liver. Arantius investigated the duct which bears his name, and he asserted that the umbilical arteries do not anastomose with the maternal vessels in the placenta. In Libavius (1597) it is stated that the child may cry *in utero*. Riolan (1618) was aware of the existence of the corpus Highmorianum testis. Pavius (1657) investigated the position of the testes in the lumbar region of the fœtus. Harvey (1633) stated the fundamental axiom, "*Omne vivum ex ovo*." Fabricius ab Aquapendente (1600) collected the materials known for the history of the development of the chick. Regner de Graaf described more carefully

the follicles which bear his name, and he found a mammalian ovum in the Fallopian tube. Swammerdam († 1685) discovered metamorphosis, and he dissected a butterfly from the chrysalis before the Grand Duke of Tuscany. He described the cleavage of the frog's egg. Malpighi († 1694) gave a good description of the development of the chick with illustrations. Hartsoecker (1730) asserted that the spermatozoa pass into the ovum. The first half of the 18th century was occupied with a discussion as to whether the ovum or the sperm was the more important for the new formation (the Ovulists and Spermatists); and also as to whether the fœtus was formed or developed within the ovum (Epigenesis), or if it merely increased in growth. The question of spontaneous generation has been frequently investigated since the time of Needham in 1745.

New Epoch.—A new epoch began with Caspar Fried. Wolff (1759), who was the first to teach that the embryo was formed from layers, and that the tissues were composed of smaller parts (corresponding to the cells of the present period). He observed exactly the formation of the intestine. William Hunter (1775) described the membranes of the pregnant uterus. Sœmmering (1799) described the formation of the external human configuration, and Oken and Kieser that of the intestines. Oken and Goethe taught that the skull was composed of vertebræ. Tiedemann described the formation of the brain, and Meckel that of monsters. The basis for the study of the development of an animal from the layers of the embryo was laid by the researches of Pander (1817), Carl Ernst v. Baer (1828–1834), Remak, and many other observers; and Schwann was the first to trace the development of all the tissues from the ovum. [Schleiden enunciated the cell theory with reference to the minute structure of vegetable tissues, while Schwann applied the theory to the structure of animal tissues. Among those whose names are most prominent in connection with the evolution of this theory are Martin Barry, von Mohl, Leydig, Remak, Goodsir, Virchow, Beale, Max Schultze Brücke, and a host of recent observers.]

APPENDIX A.

GENERAL BIBLIOGRAPHY.

SYSTEMATIC WORKS AND TEXT-BOOKS.—**A. v. Haller,** Elementa physiologiæ corporis humani, 1757–1766, 8 vols., Auctarium, 1780.—**F. Magendie,** Précis élémentaire de physiologie, 1816, 2d ed., 1825.—**Johannes Müller,** Handbuch der Physiologie des Menschen, 2d ed., 1858–1861 (translated by W. Baly).—**Donders,** Phys. d. Mensch., pt. i, Leip., 1856.—**C. Ludwig,** Lehrbuch der Physiologie des Menschen, 2d ed., 1858–1861.—**Otto Funke,** Lehrbuch der Physiologie, 7th ed., by A. Grünhagen, 1884.—**G. Valentin,** Lehrbuch der Physiologie, 1844 (translated by Brinton, 1853).—**Moleschott,** Phys. d. Nahrungsmittel, 2d ed., Giessen, 1859.—**F. A. Longet,** Traité de physiologie, 2d ed., 1860–1861.—**Joh. Ranke,** Grundzüge der Physiologie, 4th ed., 1881.—**E. Brücke,** Vorlesungen über Physiologie, 3d ed., 1885.—**L. Hermann,** Grundriss der Physiologie, 8th ed., 1885 (translated and enlarged by **A. Gamgee,** 2d English ed., 1878).—**W. Wundt,** Lehrbuch der Physiologie, 4th ed., 1878, and Grundzüge d. physiol. Psycholog., 3d ed., Leip., 1887.—**M. Foster,** Text-book of Physiology, 4th ed., 1883.—**H. Milne-Edwards,** Leçons sur la physiologie et l'anatomie comparée, 14 vols., 1857–1880.—**G. Colin,** Traité de Physiologie comparée des animaux, Paris, 1871–1873.—**Bernard,** Leç. de Pathol. expér., Paris, 1872.—**Marshall,** Phys. (Diagrams and Text), 1875.—**Stricker,** Vorles. ü. allg. u. exp. Path., Wien, 1878.—**Munk,** Physiologie d. Menschen u. d. Säugethiere, Berlin, 2d ed., 1888.—**Schmidt-Mulheim,** Grundriss d. spec. Physiologie d. Haus-säugethiere, Leipzig, 1879.—**Vierordt,** Grundriss d. Physiologie d. Menschen, 5th ed., Tübingen, 1857.—**Todd and Bowman's** Cyclopædia of Anat. and Phys.—**Hermann,** Expt. Toxicologie, 1874.—**W. Rutherford,** A Text-book of Physiology, pt. i, Edinburgh, 1880.—**W. B. Carpenter,** Princip. of Phys., 8th ed., edited by Power, London, 1876.—**J. Beclard,** Traité élém. de Phys., Paris, 1880.—**Cohnheim,** Vorlesungen ü. allgem. Pathologie, Berlin, 1880.—**Huxley's** Elements, 1885.—**H. Beaunis,** Nouveaux éléments de Physiologie humaine, 2d ed., 1881.—**Flint,** Text-book, New York, 1876; and Phys. of Man, 1866–1873.—**Kirkes,** Handbook of Physiology, 11th ed., 1884.—**Dalton,** Text-book, 1882.—**J. G. M'Kendrick,** Text-book of Physiology, Glasgow, 1888.—**Samuel,** Handb. d. allg. Path., Stutt., 1879.—The works of **Herbert Spencer** and **G. H. Lewes.**—**E. D. Mapother,** Manual of Physiology, 3d ed., rewritten by J. F. Knott, Dublin, 1882.—**A. Fick,** Compendium d. Phys., 1882.—**Steiner,** Physiologie, 4th ed., Leipzig, 1888.—**Nuel** and **Frédéricq,** Elém. de Phys., Gand, 1883.—**Preyer,** Elemente der allgemeinen Physiologie, 1883.—**T. Lauder-Brunton,** Pharmacology, Therapeutics, and Materia Medica, 1887.—**H. Power,** Elements of Physiol., London, 1884.—**Wundt,** Phys. méd., 1878.—**Daniell,** Text-book of the Principles of Physics, 1884.—**Fick,** Med. Physik., 2d ed., 1884.—**M'Gregor Robertson,** Physiological Physics, London, 1885.—**Draper,** Med. Physics, 1885.—**Yeo,** Manual of Physiology, 2d ed., London, 1887.—**L. v. Thanhoffer,** Grundzüge d. vergl. Physiologie u. Histologie, Stuttgart, 1885.—**Ziegler,** Text-book of Path. Anat. (trans. by D. Macalister), 1883–1884.—**P. H. Pye-Smith,** Syllabus of Lectures on Physiology, London, 1885.—**Chapman,** Treatise on Human Phys., Philad., 1887.—**Klein,** Microörganisms and Disease, 1884.—**Magnin** and **Steinberg,** Bacteria, 1884.—**Woodhead** and **Hare,** Mycology, 1885.—**Crookshank,** Bacteriology, 1886.—**Davis,** Text-book of Biol., London, 1888.—**Vines,** Physiology of Plants.—**Albertoni** and **Stefani,** Manuale di Fisiol. umana, 1888.—**Ellenberger,** Lehrb. d. vergleich. Histol. u. Physiol. d. Hausthiere, Berlin, 1887.—**Landois** and **Stirling,** Text-book, 3d ed., 1888.

YEARLY REPORTS, BIBLIOGRAPHICAL WORKS.—1834–1837: "Jahresberichte über die Fortschritte der Physiologie," by **Joh. Müller,** in his Archiv.—1838–1846: by **Th. L. Bischoff,** *ebenda.*—1836–1843: in "Repertorium für Anatomie und Physiologie," by **G. Valentin,** 8 vols.—1856–1871: in "Zeitschrift für rationelle Medicin," by **G. Meissner,** and continued since 1872 under the title—"Jahresberichte über die Fortschritte der Anatomie und Physiologie," by **F. Hofmann,** and **G. Schwalbe,** Leipzig.—1841–1865: Jahresbericht über die Fortschritte der gesammten

Medicin, by **Canstatt**, continued by **Virchow** and **Hirsch**.—1822–1849: **Froriep's** Notizen, 101 vols. (References and Bibliography).—Centralblatt für die medicinischen Wissenschaften, Berlin; yearly since 1863.—Biologisches Centralblatt, Erlangen, since 1881.—1817–1818: Isis, by **Oken**.—Catalogue of Scientific Papers compiled and published by the Royal Society of London, 1800–1873, 8 vols.—**Engelmann**, 1700–1846: Bibliotheca historico-naturalis (Titles of Books on Comparative Physiology).—Jahrbuch der gesammten Medicin, by **Schmidt**, since 1826.—Bibliotheca anatomica qua scripta ad anatomen et physiologiam facientia a rerum initus recensentur auctore **Alberto von Haller**, 2 vols. (important for the older literature up to 1776).—Yearly Reports on Physiology, in Journal of Anat. and Phys., by **Rutherford, Gamgee**, and **Stirling**; also Monthly Reports in London Med. Record, since its commencement in 1873.—Index medicus.—Neurologisches Centralblatt.—Med. Bibliographie by **A. Würzburg**, since 1886.—Fortschritt d. Med.

HISTORICAL.—**Kurt Sprengel**, Versuch einer pragmatischen Geschichte der Arzneykunde, 3d ed., 1821.—**W. Hamilton**, Hist. of Med. Surg. and Anat., 1831.—**Bostock's** Syst. of Phys., 3d ed., 1836.—**J. C. Poggendorf**, Geschichte der exacten Wissenschaft, 1863.—**J. Goodsir**, Titles of Papers on Anat. and Phys., 1849–1852, Edin., 1853.—**Meyer**, Gesch. d. Botanik, Königs., 1854–1857.—**H. Haeser**, Lehrbuch der Geschichte der Medicin, Jena, 1875.—**Julius Sachs**, Geschichte der Botanik seit 16. Jahrh. bis 1860; 1875.—**Bouchut**, Hist. de la méd., Paris, 1873.—**Fournié**, Applic. de la scien. a la méd., Paris, 1873.—**Willis's** William Harvey, 1878; and his Servetus and Calvin, London, 1877. Biographisches Lexikon, Vienna, 1884.

ENCYCLOPÆDIAS.—**R. Wagner**, Handwörterbuch der Physiologie, 4 vols., 1842–1853.—**R. B. Todd**, The Cyclopædia of Anatomy and Physiology, 1836–1852.—**Pierer** and **N. Choulant**, Anatomisch-physiologisches Realwörterbuch, 8 vols., 1816–1829.—**L. Hermann**, Handbuch der Physiologie, 1879–1884. Real-Encyclop. d. gesam. Med., edited by **Eulenberg**, Wien, 1888.

PRACTICAL WORK IN THE LABORATORY.—**R. Gscheidlen**, Physiologische Methodik, 1876 (not yet completed).—**E. Cyon**, Methodik der physiologischen Experimente u. Vivisektionen, with Atlas, 1876 (only one part issued). **Ott**, The Actions of Medicines, Phil., 1878.—**Claude Bernard** and **Huette** Précis iconographique de médecine operatoire et d'anatomie chirurgicale, with 113 plates, 1873; also Leçons de physiologie operatoire (edited by Duval), Paris, 1879.—**Sanderson, Foster, Klein**, and **Brunton**, Handbook for the Physiological Laboratory (Text and Atlas). The French edition contains additional matter.—**Rutherford**, Outlines of Pract. Hist., 1876.—**Meade-Smith**, Trans. of Hermann's Toxicol.—**J. Burdon Sanderson**, Practical Exercises in Physiology, London, 1882.—**Foster** and **Langley**, Pract. Phys., London. 1884.—**B. Stewart** and **Gee**, Pract. Physics.—**Vierordt**, Anat. Physiol. u. Physik. Daten u. Tabellen, Jena, 1888.—**Müller-Pouillet**, Lehrb. d. Physik., 8th ed., Braunschweig.—**Wüllner**, Lehrb. d. exp. Physik.—**Livon**, Manuel de Vivisect., Paris, 1882.—**Harris** and **Power**, Manual for the Phys. Lab., 5th ed., 1888.—**Straus-Durckheim**, Anat. descrip. comp. du. chat, Paris, 1845.—**W. Krause**, Die Anatomie des Kaninchens, Leipzig, 2d ed., 1883.—**A. Ecker**, Die Anatomie des Frosches, 1864–1882, 2d ed., pt. i, 1888.—Biolog. Memoirs, edited by **Burdon-Sanderson**.—**Stirling**, Outlines of Pract. Physiol., Lond., 1888.

SPECIAL LABORATORY REPORTS.—**Ludwig** and his pupils, Arbeiten aus der physiologischen Anstalt zu Leipzig, since 1866.—**Burdon-Sanderson** and **Schäfer**, Collected papers from the Physiological Laboratory of University College, London, 1876–1885.—**Gamgee**, Studies from the Physiological Laboratory of Owens College, Manchester, 1877–78.—**Traube**, Beitr. z. Path. u. Phys., Berlin, 1871.—**J. Czermak**, Gesammelte Schriften, 1879.—**Marey**, Physiologie expérimentale, Travaux du laboratoire, Paris, 1875.—**L. Ranvier**, Laboratoire d'histologie du Collège de France, Paris, since 1875.—**Loven**, Physiol. Mittheil., Stockholm, 1882–84.—**W. Kühne**, Untersuchungen des physiologischen Instituts der Universität, Heidelberg, since 1877.—**R. Heidenhain**, Studien des physiologischen Instituts zu Breslau, 1861–68.—**Stricker**, Studien aus dem Institute für experimentelle Pathologie, Vienna.—**John Reid**, Physiological and Anatomical Researches, Edinburgh, 1848.—**Rollett's** Untersuch. a. d Inst. zu Gratz, since 1870.—**Schenk**, Mitth. a. d. embryol. Inst. z. Wien, 1877–.—**Preyer**, Sammlung phys. Abhandl., Jena, 1877.—**Von Wittich**, Mitth. a. d. Königsb. Phys. Lab., 1878.—**Rossbach**, Pharmacol. Unters. Würzb., 1873.—**Fick**, Arb. a. d. Würzburger Hochschule, Würzburg, 1872.—**Hoppe-Seyler**, Med.-chem. Unters., 1866–71.—**Laborde**, Travaux de Lab. de Phys. de la Faculté de Méd., Paris, 1885. Studies from the Biol. Lab. of Owens College, pt. i, 1886.—**Tigerstedt**, Mitth. v. d. phys. Lab. in Stockholm, 1888.

JOURNALS, PERIODICALS.—Archiv für die Physiologie, by **J. C. Reil** and **Autenreith**, 12 vols., Halle, 1796–1815. *Continued as*—Deutsches Archiv für die Physiologie, by **J. F. Meckel**, 8 vols., Halle, 1815–1823. *Continued as*—Archiv für Anatomie und Physiologie, by **J. F. Meckel**, 6 vols., Leipzig, 1826–1832. *Continued as*—Archiv für Anatomie und wissenschaftliche Medicin, by **Johannes Müller**, 25 vols., Berlin, 1834–1858. *Continued under the same title* by—**C. B. Reichert** and **E. du Bois-Reymond**, 1859–1876. *When it was divided into*—Zeitschrift für Anatomie und Entwickelungsgeschichte, by **W. His** and **Braune**, and Archiv für Physiologie, by

E. du Bois-Reymond, until 1877. *Is continued as*—Archiv für Anatomie und Physiologie by **W. His, W. Braune**, and **E. du Bois-Reymond**.—Archiv für die gesammte Physiologie des Menschen und der Thiere, by **E. F. W. Pflüger**, Bonn, since 1868.—Zeitschrift für Biologie, edited from 1865 by **Buhl, Pettenkofer, Voit**, and **Radlkofer**; from 1875 by the first three, and since 1880 by **Pettenkofer** and **Voit**, presently by **Voit** and **Kühne**.—Journal de Physiologie experimentale et pathologique, by **F. Magendie**, 11 vols., Paris, 1821–1831.—Zeitschrift für die organische Physik, by **C. F. Heusinger**, 4 vols., Eisenach, 1827–1828—Zeitschrift für Physiologie, by **F. Tiedemann** and **Treviranus**, 5 vols., 1824–1833.—Journal de l'anatomie et de la physiologie normales et pathologiques de l'homme et des animaux, by **Ch. Robin** and **Pouchet**, since 1864.—Archives de physiologie normale et pathologique, by **Brown-Séquard, Charcot, Vulpian**, Paris, since 1868.—Journal of Anatomy and Physiology, edited by **Humphry, Turner**, and **M'Kendrick**, since 1867.—Journal of Physiology, edited by **M. Foster**, since 1878.—Archives Italiennes de Biologie, by **C. Emery** and **A. Mosso**, since 1881.—Annales de sciences naturelles, Paris, since 1824.—Archives de Zoologie expérimentale et générale by **Lacaze-Duthiers**, Paris, since 1872.—Archives de Biologie, by **Ed. van Beneden**, and **Ch. van Bambeke**, since 1880.—Physiolog. Centralblatt, by **Exner** and **Gad**, since 1887.—Zeitschrift für wissenschaftliche Zoologie, by **C. T. von Siebold** and **A. von Kölliker**, Leipzig, since 1849.—Archiv für pathologische Anatomie und Physiologie und für klinische Medicin, by **R. Virchow**, Berlin, since 1847.—Zeit. f. wissensch. Mikroscop., **Behrens**, Braunschweig.—Archiv für Naturgeschichte, by **Wiegmann**; *continued by* **Erichsen** and **Troschel**, Berlin, since 1835.—Untersuchungen zur Naturlehre des Menschen und der Thiere, by **Jac. Moleschott**, since 1857.—Zeitschrift für rationelle Medicin, **Henle, Pfeufer**, and **Meissner**.—Sitzungsberichte der Akademie der Wissenschaften (Math. Nat.-Wiss. Classe), Vienna.—Philosophical Transactions, London.—Proceedings of the Royal Society, London.—Transactions of the Royal Society, Edinburgh.—Proceedings of the Royal Society, Edinburgh.—Quarterly Microscopical Journal, London.—Monthly Microscopical Journal, London.—Journal of the Royal Microscopical Society, London.—Comptes rendus, Paris.—Anatomischer Anzeiger.—Index Medicus.—**Cohn**, Beiträge zur Physiologie der Pflanzen, Breslau, 1872.—The Philosophical Magazine, Edinburgh, London, and Cambridge.—Boston Medical and Surgical Journal.—Verhandlungen der physikal.-medicinischen Gesellschaft zu Würzburg.—Archives of Medicine, edited by **L. Beale**, London, 1856.—Annals and Magazine of Natural History.—Annales (Mémoires) Archives du Muséum d'histoire naturelle, Paris.—Jenaische Zeitschrift für Naturwissenschaft.—Mémoires de l'Academie des Sciences de l'Institut de France, Paris.—Morphologisches Jahrbuch, by **C. Gegenbaur**, since 1876.—Nova Acta Academiæ Leopoldino-Carolinæ.—Zoologischer Anzeiger, by **V. Carus**, since 1878.—Abhandlungen and Monatsberichte der k. preussischen Akademie der Wissenschaft zu Berlin.—Archiv für experimentelle Pathologie und Pharmakologie, by **Naunyn** and **Schreiber**, Leipzig, since 1873.—Deutsches Archiv für klin. Medicin, by **v. Ziemssen** and **Zenker**, Leipzig.—Journal de Pharmacie et de Chimie, Paris.—Archiv für Psychiatrie und Nervenkrankheiten, by **Gudden** and others, Berlin, since 1868.—Archiv für wissenschaftliche und praktische Thierheilkunde, by **Roloff**, Berlin, 1874.—Archives générales de médecine, Paris.—Brain, since 1879, edited by **de Watteville**.—Archives de Neurologie, by **Charcot**, Paris, 1875.—Zeit. f. Hygiene, by **Koch** and **Flügge**.—The various Medical Journals, including the Lancet and British Medical Journal, Edinburgh Medical Journal, London Medical Record, New York Med. Record, Practitioner, Medical Chronicle.—Arch. for Otology, N. Y.—Arch. for Ophthal., N. Y.—Internat. Jour. of Med. Sciences, Edin.—Revue de Med., Paris.—Zeit. f. Klin. Med., Berlin.—Intern. Monatssch. f. Anat. u. Physiol.—Asclepiad.—Nature.

HISTOLOGY.—**Henle**, Handbuch der systematischen Anatomie des Menschen, 3d ed., 1866–1883.—**Rutherford**, Outlines of Pract. Histol., 1876.—**W. Krause**, Allgemeine und Mikroskopische Anatomie, Hannover, 1876.—**F. Leydig**, Lehrbuch der Histologie des Menschen und der Thiere, Hamm, 1857; and his Untersuchungen, 1883; and his Zell u. Gewebe, Bonn, 1885.—**V. Mihalkovics**, General Anatomy (Hungarian), 1881.—**L. Ranvier**, Traité technique d'histologie, Paris, 1875–1888.—**G. Schwalbe**, Lehrbuch der Neurologie, Erlangen, 1881; Lehrb. d. Anat. d. Sinnesorgane.—**S. Stricker**, Handbook of Histology (translated by the New Sydenham Society), 1871–1873.—Archiv für mikroskopische Anatomie, Bonn; edited formerly by **Max Schultze**, and presently by **Waldeyer** and **La Valette**.—Quarterly Microscopical Journal, London.—Monthly Microscopical Journal, London.—Journal of the Royal Microscopical Society, London.—**Schwann**, Mikrosk. Untersuch., 1838 (translated by the Sydenham Society, 1847).—**W. Kühne**, Das Protoplasma, Leipzig, 1864.—**Max Schultze**, Das Protoplasma, Leipzig, 1863.—**R. Virchow**, Die Cellular Pathologie (translated by **Chance**), 1860.—**L. Beale**, The Structure of the Elementary Tissues, London, 1881.—**A. Kölliker**, A Manual of Human Microscopic Anatomy, London, 1860; and his Icones Histolog., Leip., 1864.—**J. Goodsir**, Anatomical and Pathological Observations, edited by **W. Turner**, Edinburgh.—Quain's Anatomy, 9th ed., edited by **A. Thomson, Schäfer**, and **Thane**, London, 1882.—**Rindfleisch**, A Manual of Pathological Anatomy (translated by **R. Baxter**), London, 1873.—**C. Toldt**, Lehrbuch der Gewebelehre, Stuttgart, 3d ed., 1888.—**E. Klein** and **E. Noble-Smith**, Atlas of Histology, London, 1872.—**H. Frey**, Handbuch der Histologie und Histochemie des Menschen, Leipzig, 1876, Grundzüge, 1885, and Das Mikroskop., 8th ed., 1886.—**Fol**, Lehr. d. vergleich. mikros. Anatomie, Leip., 1885.—**Behrens**, Tabellen z.

Gebrauch b. mik. Arbeiten, Braunschweig, 1887.—**Fearnley**, Pract. Histol., 1887.—**Brass**, Kurzes Lehrb. d. Histol., Leip., 1888.—**Beale**, How to Work with the Micros., Lond., 1880.—**W. Stirling**, Histological Memoranda, Aberdeen, 1880.— **E. A. Schäfer**, Practical Histol., 1877; and Essentials of Histol., 1887.—**W. Stirling**, Text-book of Practical Histology, London, 1881.—**Heitzmann**, Microsc. Morphology, 1882.—**Purser**, Man. of Hist., Dublin.—**E. Klein**, Elements of Hist., London, 1883.—**W. Flemming**, Zellsubst. u. Zelltheil., Leipzig, 1882.—**Cadiat**, Traité d'anat. gén., Paris, 1879.—**Bizzozero**, Hand. d. klin. Mikroskop., Erlang., 2d ed., 1888.—**Carnoy**, Gilson and Denys. Biol. Cellul., Louvain, 1884–88.—**Friedländer**, Mik. Technik., 3d ed., Berlin, 1888.—**Gierke**, Farberei z. mik. Zwecken., Braun., 1885.—**Frommann**, Unters. u. thier. u. pflanz. Zellen, Jena. 1884.—**Wiedersheim**, Lehrb. d. vergl. Anat., Jena, 1888.—**S. L. Schenk**, Grundriss der Histologie d. Menschen, Vienna, 1885.—**Orth**, Cursus d. norm. Histol., 4th ed., 1886.—**S. Mayer**, Histolog. Taschenbuch, Prag., 1887.—**Stöhr**, Lehrb. d. Histol., Jena, 1888.—**Lee** and **Henneguy**, Traité de meth. de l'Anat., Paris, 1888.

PHYSIOLOGICAL CHEMISTRY.—**Hoppe-Seyler**, Physiologische Chemie, Berlin, 1877–1879.—**Lehmann**, Lehrb. d. phys. Chem., 3d ed., Leipzig, 1853; and Handbuch, 1859.—**J. König**, Chemie der menschlichen Nahrung und Genussmittel, 2d ed., Berlin, 1883.—**Leo. Liebermann**, Grundzüge der Chemie des Menschen, Stuttgart, 1880.—**Robin** and **Verdeil**, Traité de chim, anat. et phys. (with Atlas), Paris, 1853.—**J. Moleschott**, Physiologie der Nahrungsmittel, 2d ed., Giessen, 1859.—**E. Smith**, Foods, 1873.—**A. Wynter Blyth**, Foods, 1887.—**Gorup-Besanez**, Anleitung zur Zoochemischen Analyse. 1871.—**Gautier**, Chimie appliqué à la Physiologie, 1874.—**Lehmann's** Phys. Chem. (translated by Cavendish Soc., 1851–54), with Atlas of O. Funke's plates.—**Kingzett**, Animal Chem., 1878.—**Thudichum**, Ann. of Chem. Med., 1879.—**A. Gamgee**, Physiological Chemistry of the Animal Body, vol. i, 1880.—**Hoppe-Seyler**, Medicinische Chemische Untersuchungen, Berlin.—Zeitschrift für physiologische Chemie, by Hoppe-Seyler, Strassburg, since 1877.—**Watts'** Dictionary of Chemistry, second supplement, London, 1875.—**Ralfe**, Clinical Chemistry, London, 1880; and Clinical Chem., 1883.—**Wurtz**, Traité de chim. biol., Paris, 1880.—**T. C. Charles**, Physiological and Pathological Chemistry, London, 1884.—**Parkes'** Hygiene, 7th ed.—**Flügge**, Lehrb. d. hygien. Untersuchung., Leip., 1881.—**Maly's** Jahresb. ü. Thierchemie since 1870.—**Landolt**, Das opt. Drehungsvermog. org. Subst. Braun., 1879.—Articles in **Hermann's** Handbuch d. Physiologie, 1879–1884, and the various Text-books on Organic Chemistry.—**Roscoe** and **Schorlemmer**, (Organic) Chem., 1884.—**Nowak**, Lehrbuch d. Hygiene, Wien.—**Beilstein**, Handb. d. org. Chem., Hamb. and Leip., 2d ed., 1825 —**Ladenburg**, Handb. d. Chemie, Breslau, 1883.—**Rosenthal**, Vorles. ü. öffent. u. priv. Gesundheitspflege, Erlangen, 1887.—**Kossel**, Leitfaden f. med.-chem. Curse, 2d ed., Berlin, 1888.

APPENDIX B.

COMPARISON OF THE METRICAL WITH THE COMMON MEASURES.

By Dr. Warren De la Rue.

MEASURES OF LENGTH.

	In English Inches.	In English Feet = 12 Inches.	In English Yards = 3 Feet.
Millimetre	0.03937	0.0032809	0.0010936
Centimetre	0.39371	0.0328090	0.0109363
Decimetre	3.93708	0.3280899	0.1093633
Metre	39.37079	3.2808992	1.0936331
Decametre	393.70790	32.8089920	10.9363310
Hectometre	3937.07900	328.0899200	109.3633100
Kilometre	39370.79000	3280.8992000	1093.6331000
Myriometre	393707.90000	32808.9920000	10936.3310000

1 Inch = 2.539954 Centimetres. | 1 Foot = 3.0479449 Decimetres. | 1 Yard = 0.91438348 Metre.

MEASURES OF CAPACITY.

	In Cubic Inches.	In Cubic Feet = 1728 Cubic Inches.	In Pints = 34.65923 Cubic Inches.
Millilitre or cubic centimetre	0.061027	0.0000353	0.001761
Centilitre or 10 cubic centimetres	0.610271	0.0003532	0.017608
Decilitre or 100 cubic centimetres	6.102705	0.0035317	0.176077
Litre or Cubic decimetre	61.027052	0.0353166	1.760773
Decalitre or centistere	610.270515	0.3531658	17.607734
Hectolitre or decistere	6102.705152	3.5316581	176.077341
Kilolitre or stere, or cubic metre	61027.051519	35.3165807	1760.773414
Myriolitre or decastere	610270.515194	353.1658074	17607.734140

1 Cubic Inch = 16.3861759 Cubic Centimetres. | 1 Cubic Foot = 28.3153119 Cubic Decimetres.

The UNIT OF VOLUME is 1 Cubic Centimetre.

MEASURES OF WEIGHT.

	In English Grains.	In Troy Ounces = 480 Grains.	In Avoirdupois Lbs. = 7000 Grains.
Milligramme	0.015432	0.000032	0.0000022
Centigramme	0.154323	0.000322	0.0000220
Decigramme	1.543235	0.003215	0.0002205
Gramme	15.432349	0.032151	0.0022046
Decagramme	154.323488	0.321507	0.0220462
Hectogramme	1543.234880	3.215073	0.2204621
Kilogramme	15432.348800	32.150727	2.2046213
Myriogramme	154323.488000	321.507267	22.0462126

The UNIT OF MASS in the metrical system is 1 Gramme, which is the mass or weight of 1 Cubic Centimetre (1 c.c.) of water at 4° C., *i.e.*, at its temperature of maximum density.

CORRESPONDING DEGREES IN THE FAHRENHEIT AND CENTIGRADE SCALES

Fahr.	Cent.	Fahr.	Cent.	Fahr.	Cent.	Cent.	Fahr.	Cent.	Fahr.	Cent.	Fahr.
500°	260°.0	140°	60°.0	40°	4°.4	100°	212°.0	60°	140°.0	20°	68°.0
450°	232°.2	135°	57°.2	35°	1°.7	98°	208°.4	58°	136°.4	18°	64°.4
400°	204°.4	130°	54°.4	32°	0°.0	96°	204°.8	56°	132°.8	16°	60°.8
350°	176°.7	125°	51°.7	30°	— 1°.1	94°	201°.2	54°	129°.2	14°	57°.2
300°	148°.9	120°	48°.9	25°	— 3°.9	92°	197°.6	52°	125°.6	12°	53°.6
212°	100°.0	115°	46°.1	20°	— 6°.7	90°	194°.0	50°	122°.0	10°	50°.0
210°	98°.9	110°	43°.3	15°	— 9°.4	88°	190°.4	48°	118°.4	8°	46°.4
205°	96°.1	105°	40°.5	10°	—12°.2	86°	186°.8	46°	114°.8	6°	42°.8
200°	93°.3	100°	37°.8	5°	—15°.0	84°	183°.2	44°	111°.2	4°	39°.2
195°	90°.5	95°	35°.0	0°	—17°.8	82°	179°.6	42°	107°.6	2°	35°.6
190°	87°.8	90°	32°.2	— 5°	—20°.5	80°	176°.0	40°	104°.0	0°	32°.0
185°	85°.0	85°	29°.4	—10°	—23°.3	78°	172°.4	38°	100°.4	— 2°	28°.4
180°	82°.2	80°	26°.7	—15°	—26°.1	76°	168°.8	36°	96°.8	— 4°	24°.8
175°	79°.4	75°	23°.9	—20°	—28°.9	74°	165°.2	34°	93°.2	— 6°	21°.2
170°	76°.7	70°	21°.1	—25°	—31°.7	72°	161°.6	32°	89°.6	— 8°	17°.6
165°	73°.9	65°	18°.3	—30°	—34°.4	70°	158°.0	30°	86°.0	—10°	14°.0
160°	71°.1	60°	15°.5	—35°	—37°.2	68°	154°.4	28°	82°.4	—12°	10°.4
155°	68°.3	55°	12°.8	—40°	—40°.0	66°	150°.8	26°	78°.8	—14°	6°.8
150°	65°.5	50°	10°.0	—45°	—42°.8	64°	147°.2	24°	75°.2	—16°	3°.2
145°	62°.8	45°	7°.2	—50°	—45°.6	62°	143°.6	22°	71°.6	—18°	—0°.4
										—20°	—4°.0

To turn C° into F°, multiply by 9, divide by 5, and add 32°.
To turn F° into C°, deduct 32, multiply by 5, and divide by 9.

INDEX.

Abdominal muscles in respiration, 217
Abdominal reflex, 692
Abducens, 649
Aberration, chromatic, 807
spherical, 807
Abiogenesis, 893
Absolute blindness, 752
Absorption by fluids, 80
by solids, 80
forces of, 342
influence of nerves on, 347
organs of, 336
Absorption of—
Carbohydrates, 344
Coloring matter, 346
Digested food, 342
Effusions, 359
Fat soaps, 345
Grape sugar, 344
Inorganic substances, 344
Nutrient enemata, 347
Oxygen, 232, 236
Peptones, 345
Small particles, 346
Solutions, 344
Sugars, 344
Unchanged proteids, 345
Absorption spectra, 62
Accelerans nerve, 720
in frog, 722
Accommodation of eye, 799
defective, 805
force of, 805
line of, 803
nerves of, 803
phosphene, 813
range of, 806
spot, 813
time for, 803
Accord, 861
Acetic acid, 429
Aceton, 454, 464
Acetylene, 66
Achromatin, 893
Achromatopsy, 828
Achroödextrin, 262
Acid albumin, 425
Acid hæmatin, 66
Acids, free, 422
Acoustic nerve, 653
tetanus, 600
Acquired movements, 758
Acrylic acid series, 429
Action currents, 605
Active insufficiency, 552
Addison's disease, 200, 498
Adelomorphous cells, 285
Adenin, 433
Adenoid tissue, 351
Adipocere, 412
Adventitia, 137
Ægophony, 225
Aërobes, 325
Æsthesiometer, 882
Æsthesodic substance, 695
Afferent nerves, 633
After-birth, 946
After-images, 829
After-sensation, 782
Ageusia, 877
Agoraphobia, 655
Agrammatism, 761
Agraphia, 761
Ague, 197
Air, changes in respiration, 231
collection of, 228
composition of, 230
diffusion of, 234
expired, 231
impurities in, 244
quantity exchanged, 232
Air cells, 205
Albumimeter, 459
Albuminoids, 426
Albumin of egg, 905
Albumins, 423
Albuminuria, 457
Albumoses, animal, 425
vegetable, 425
Alcohol, 400
Alcohols, 430
Alcoholic drinks, 400
Alcool au tiers, 50
Aleurone grains, 425
Alexia, 763
Alkali albumin, 425
Alkali hæmatin, 66
Alkaline fermentation, 457
Alkaloids, 400
Allantoin, 402, 452
Allantois, 924
Allochiria, 889
Allorhythmia, 150
Alloxan, 449
Almén's test, 461
Alternate hemiplegia, 705
Alternate paralysis, 705, 769
Alternation of generations, 895
Amaurosis, 637
Amblyopia, 637
American crow-bar case, 731
Amido acids, 432
Amido acetic acid, 312, 432
Amido-caproic acid, 300
Amimia, 761
Amines, 432
Ammoniæmia, 479
Amnesia, 761
Amnion, 923
Amniota, 924
Amniotic fluid, 924
Amœboid movement, 55, 500
Ampère's rule, 593
Amphiarthroses, 549
Ampho peptone, 292
Amphoric breathing, 224
Amygdalin, 359
Amyloid substance, 425
Amylopsin, 299
Amylum, 431
Anabiosis, 893
Anacrotism, 151
Anæmia, 58, 89
metabolism in, 89
pernicious, 58
Anærobes, 325
Anæsthesia dolorosa, 890
Anæsthetic leprosy, 632
Anæsthetics, 890
Anabolic nerves, 633
Anabolism, 388
Anakusis, 653
Analgesia, 698
Analgia, 891
Anamnia, 924
Anarthria, 760
Anasarca, 359
Anelectrotonus, 616
Aneurism, 157, 158
Angiograph, 143
Angiometer, 151
Angioneuroses, 728
Anidrosis, 497
Animals, characters of, 39
Animal foods, 405
magnetism, 736
Anions, 594
Anisotropous substance, 504
Ankle clonus, 693
Anode, 584

Aperistalsis, 281
Apex beat, 102, 110
Aphakia, 791
Aphasia, 760
Aphonia, 573
Apnœa, 713
Appunn's apparatus, 866
Apselaphesia, 859
Aqueous humor, 792
Arachnoid mater, 776
Archiblastic cells, 920
Area opaca, 916
  pellucida, 916
  vasculosa, 922
Argyll Robertson pupil, 810
Arhythmia cordis, 98
Aristotle's experiment, 884
Aromatic acids, 430
  oxyacids, 433
Arrector pili muscle, 490
Arterial tension, 147
Arteries, 137
  blood pressure in, 165
  central, 740
  development of, 936
  emptiness of, 723
  rhythmical contraction of, 725
  sounds in, 184
  structure of, 135
  tension in, 165
  termination in veins, 181
Arteriogram, 143
Arthroidal joints, 549
Articular cartilage, 548
Articulation nerve corpuscles, 880
Artificial cold-blooded condition, 386
Artificial eye, 798
  digestion, 295
  gastric juice, 291
  pancreatic juice, 300
  respiration, 241
Asphyxia, 233
Astigmatism, 795
Ataxia, 668, 750, 759
Ataxic tabes, 697
Atelectasis, 226, 243
Atmospheric pressure, 247
  diminution of, 248
  increase of, 248
Atresia ani, 923
Atrophy, 554
  of the face, 648
Atropin, 524
  in eye, 638, 810
Attention, time for, 735
Audible tone, lowest, 862
Auditory after-sensations, 870
  area, 753
  axis, 754
  centre, 753
  delusions, 653
  meatus, 849
  nerve, 847
  ossicles, 851
  paths, 754
  perceptions, 860
  sac, 945
Auerbach's plexus, 281, 341
Augmentor nerves, 722
Auricles of heart, 91, 93
  development of, 935
Auscultation of heart, 117
  of lungs, 223
Automatic excitement, 675
Autonomy, 737
Auxocardia, 128
Avidity, 290
Axis of vision, 819

Bacillus, 324
  acidi lactici, 325
  anthracis, 90
  [illegible]
Atavism, 948
Ataxaphasia, 761
Leclanché's, 5
Sweet's, 595
Bears, 868
  isolated, 868
  successive, 868
Bed-sores, 632
Beef tea, 397
Beer, 401
Bell's law, 667
  deductions from, 6
Bell's paralysis, 652
Benzoic acid, 451
Bert's experiment, 624
Bidder's ganglion, 119
Bile, 312
  acids, 312
  composition of, 31
  crystallized, 312
  ducts, 306
    ligature of,
  effects of drugs on,
  excretion of, 316
  fate of, 320
  functions of, 319
  gases of, 314
  passage of drugs i
  pigments, 313
  pressure, 317
  reabsorption of, 31
  secretion of, 315
  spectrum of, 314
  test for, 313, 314
Biliary fistula, 316
Bilicyanin, 314
Bilifascin, 314
Biliprasin, 314
Bilirubin, 313
Biliverdin, 313
Binocular vision, 537
Biological law, 948
Biology, 33
Biot's respiration, 216
Birth, [illegible]

Blood, arterial, 86
carbon dioxide in, 85
clot, 70
coagulation, 72
color, 33
coloring matter, 59
composition of, 61
defibrinated, 70
distribution of, 187
electrical condition of, 629
extractives, 80
fats in, 79
fibrin in, 58, 71
gases in, 80
granules of, 58
islands, 51, 922
lake-colored, 49
loss of, 89
microscopic examination of, 44
nitrogen in, 86
odor, 43
organisms in, 90
oxygen in, 83
ozone in, 84
plasma, 70
plates, 57
portal vein, 86
proteids of, 78
quantity, 86
reaction, 33
salts in, 80
serum, 70
specific gravity of, 43
taste, 43
temperature, 44
transfusion of, 87
variations in, 87
venous, 86
water in, 80
Blood channels, intercellular, 137
Blood corpuscles—stroma, 49
abnormal changes, 58
action of reagents on, 47, 49, 56
amœboid movements, 55
change of form, 47
chemical composition, 59
circulation, 180
color, 47
colorless, 53
conservation of, 49
crenation, 47
decay, 53
diapedesis, 56, 182
effect of drugs, 56
effect of reagents, 47
form, 44, 50
Gower's method, 46
histology of, 46
human, red, 44
white, 53, 69
intracellular origin, 52
Malassez's method, 45
Blood corpuscles, nucleated, 58
number, 44, 58
of newt, 54
origin, 51
parasites of, 59
pathological changes, 58
proteids of, 69
rouleaux of, 47
size, 44, 50, 58
staining of, 48
stroma, 46
transfusion of, 87
weight, 44
white, 53
Blood current, 180
in capillaries, 181
velocity of, 177
Blood gases, 80
estimation of, O, CO_2, and N, 83
extraction, 81
gas-pumps for, 81
quantity, 82
Blood glands, 192
Blood islands, 51, 922
Blood plasma, 70
Blood pressure, 161
arterial, 165
capillary, 171
estimation of, 161
in pulmonary artery, 173
in veins, 171
relation to pulse, 170
variations of, 165, 170
Blood vessels, 134
action of drugs on, 138
cohesion of, 139
elasticity of, 138
lymphatics, 137
pathology of, 139
properties of, 137, 138
structure of, 134
Blue pus, 498
sweat, 498
Body, vibrations of, 158
Body-wall, formation of, 922
Bone, chemical composition of, 934
callus of, 418
development of, 933
effect of madder on, 418
fracture of, 418
growth of, 934
histogenesis of, 933
red marrow, 53
Bones, mechanism of, 547
Böttger's test, 264
Boutons terminals, 881
Bowman's tubes, 785
glands, 871
Box pulse-measurer, 140
Bradyphasia, 761
Brain, 700
arteries of, 777, 778
blood vessels of, 777
general scheme of, 700
Brain impulses, course of, 683
in invertebrata, 780
membranes of, 776
motor centres of, 742
movements of, 777
of dog, 744
pressure on, 779
protective apparatus of, 776
psychical functions of, 731
pulse in, 158
pyramidal tracts of, 703, 758
topography of, 756, 764
weight of, 700
Branchial arches, 923
clefts, 923, 932
Brandy, 401
Bread, 398
Brenner's formula, 653
Broca's convolution, 760
Bromidrosis, 498
Bronchial breathing, 223, 224
fremitus, 224
Bronchiole, 205
Bronchophony, 225
Bronchus, extra-pulmonary, 204
intra-pulmonary, 204, 205
small, 205
Bronzed skin, 200
Brownian movement, 261
Bruit, 184
de diable, 185
Brunner's glands, 321, 339
Buchanan's experiments, 74
Bulbar paralysis, 712
Bulbus arteriosus, 934
Butter, 393
Butyric acid, 325, 429

Cachexia, 198
Caffein, 400
Calabar bean on eye, 638
Calcic phosphate, 421
Calculi, biliary, 314, 332
salivary, 260, 331
urinary, 468
Callus, 418
Calorimeter, 362
Canal of cochlea, 857
hyaloid, 791
Nuck, 941
of spinal cord, 676
of Stilling, 791
Petit, 790
Schlemm, 785
semicircular, 859
Canalis cochlearis, 857
reuniens, 858
Capillaries, 136
action of silver nitrate on, 136
blood current in, 181

Capillaries, circulation, 181
contractility of, 139
development of, 53
form and arrangement of, 180
pressure in, 171
stigmata of, 136
velocity of blood in, 178
Capillary electrometer, 603
Capsule, external, 767
Glisson's, 304
internal, 766
of Tenon, 791
Carbohydrates, 436
fermentation of, 325
Carbolic acid urine, 453
Carbon dioxide, conditions affecting, 232
estimation of, 229
excretion of, 232, 236
in air, 230
in blood, 85
in expired air, 231
where formed, 238
Carbonic oxide hæmoglobin, 65
oxide, 65
poisoning by, 65
Cardiac cycle, 98
dullness, 117
ganglia, 118
hypertrophy, 110
impulse, 102, 110
movements, 107
murmurs, 114
nerves, 118
nutritive fluids, 120
plexus, 118
poisons, 127
revolution, 98
sounds, 112
Cardinal points, 796
Cardiogram, 102
Cardiograph, 102
Cardio-inhibitory centre, 168, 718
nerves, 718
Cardio-pneumatic movement, 128
Caricin, 301
Carnin, 396
Carotid gland, 118, 137, 200, 201
Cartilage, 548, 923
Casein, 393, 425
Catacrotic pulse, 145
Cataphoric action, 598
Cataract, 790
Cathartics, 284
Cathelectrotonus, 615
Cathode, 594
Caudate nucleus, 765, 766
Cavernous formations, 137
Cells, division of, 893
Cellulose, 262
Cement, 268
Cement, action of silver nitrate on, 136
substance, 136
Centre, accelerans, 720
ano-spinal, 694
auditory, 763
cardio-inhibitory, 718
cilio-spinal, 693
closure of eyelids, 710
coughing, 711
dilator of pupil, 693, 711
ejaculation, 694
erection, 694, 910
for coughing, 711
for defæcation, 694
for mastication and sucking, 711
for saliva, 711
gustatory, 763
heat regulating, 730
micturition, 694
olfactory, 763
parturition, 694
pupil, 711
respiratory, 712
sensory, 751
sneezing, 710
spasm, 730
speech, 760
swallowing, 711
sweat, 694, 730
vaso-dilator, 694, 729
vasomotor, 694, 722
vesico-spinal, 694
visual, 763
vomiting, 711
Centre of gravity, 554
Centrifugal nerves, 631
Centripetal nerves, 633
Centro-acinar cells, 297
Cereals, 398
Cerebellum, 772
Action of electricity on, 775
Connections of, 702
Function of, 774
Pathology of, 776
Removal of, 774
Structure of, 772
Cerebral arteries, 740, 777, 778
epilepsy, 745, 759
fissures, dog, 744
inspiratory centre, 713
motor centres, 756
sensory centres, 763
vesicles, 918
Cerebrin, 428, 581
Cerebro-spinal fluid, 354
Cerebrum, 700
blood vessels of, 739, 740, 777
convolutions of, 740
epilepsy of, 745
excision of centres, 750
Flourens' doctrine, 732
Cerebrum, functions of, 731
Goltz's theory of, 755
imperfect development of, 732
lobes of, 740
motor regions of, 744
movements of, 777
removal of, 732
sensory centres, 751
structure of, 737
sulci and gyri of, 740, 741
thermal centres of, 755
weight of, 700
Cerumen, 494
Cervical sympathetic, section of, 673
Chalazæ, 904
Charcot's crystals, 247
disease, 632
Cheese, 395
Chemical affinity, 37.
Chess-board phenomenon, 842
Chest, dimensions of, 220
Cheyne-Stokes' phenomenon, 216
Chiasma, 635
Chitin, 428
Chloasma, 495
Chloral, 724
Chlorophane, 790
Chlorosis, 58
Chocolate, 400
Cholæmia, 317
Cholalic acid, 312, 430
Cholesteræmia, 319
Cholesterin, 69, 314, 320, 582
Choletelin, 314
Cholin, 581
Choloidinic acid, 313
Choluria, 462
Chondrin, 427
Chondrogen, 427
Chorda dorsalis, 919
Chorda tympani, 650, 729
Chordæ tendineæ, 100
Chorion læve, 926
frondosum, 926
primitive, 925
Choroid, 785
Choroidal fissure, 944
Christison's formula, 440
Chromatic aberration, 807
Chromatin, 893
Chromatophores, 499
Chromatopsia, 637
Chromidrosis, 498
Chromophanes, 790
Chronograph, 530
Chyle, 353
movement of, 356
vessels, 348
Chylous urine, 467

Chyme, 292
Cicatricula, 903
Cilia, 500
conditions for movement, 501
effect of reagents on, 501
functions of, 501
Ciliary ganglion, 641
motion, 500
force of, 501
muscle, 786, 801
nerves, 641
Ciliated epithelium, 500
Cilio-spinal region, 693
Circle of Willis, 778
Circulating albumin, 403
Circulation, capillary, 181
duration of, 179
first, 921
fœtal, 927
portal, 91
pulmonary, 91
schemata of, 161
second, 922
systemic, 91
Circumpolarization, 265
Circumvallate papillæ, 874
Claustrum, 767
Cleft sternum, 109
palate, 931
Clerk-Maxwell's experiment, 814
Cleavage of yelk, 914
lines of, 915
partial, 917
Climacteric, 906
Clitoris, 942
Closing, continued contraction, 619
Closing shock, 599
Clothing, 379
Coagulable fluids, 78
Coagulated proteids, 425
Coagulation experiments, 76
Coagulation of blood, 71, 72, 74
theories of, 74, 77
Cocaine, 810
Coccygeal gland, 137, 200
Cochlea, 857
Cocoa, 400
Coecitas verbalis, 763
Cœlom, 920
Coffee, 400
Cold-blooded animals, 365
Cold on the body, 385
uses of, 387
Cold spots, 887
Collagen, 426
Colloids, 343
Coloboma, 944
Colostrum, 394
Color associations, 870
Color blindness, 828
acquired, 828
testing, 829
Color sensation, 824
Color, Hering's theory, 827
Young-Helmholtz theory, 826
Colored shadows, 832
Colorless corpuscles, 53
Color top, 830
Colors, complementary, 824
contrast, 830
geometrical table, 825
methods of mixing, 824
mixed, 825
simple, 824.
Columella, 870
Columns of the cord, 677
Coma, diabetic, 311
Comedo, 498
Common sensation, 889
Comparative—
Circulation, 201
Digestion, 334
Hearing, 870
Heat, 387
Kidney and urine, 486
Metabolism, 433
Motor organs, 558
Nerve centres, 779, 780
Nerves and electro-physiology, 629
Peripheral nerves, 674
Reproduction and development, 947
Respiration, 249
Sight, 845
Skin, 499
Smell, 873
Taste, 877
Voice and Speech, 574
Compensation, 604
Complemental air, 210
Complementary colors, 824
Compound eye, 845
Concretions, 330
Condensed milk, 395
Condiments, 400
Conduction in the cord, 683, 696
Conductivity, 623
Conglutin, 425
Congo red, 288
Conjugate deviation, 638, 758
Conjugation, 895
Connective-tissue spaces, 348
Consonance, 868
Consonants, 572
Constant current, action of, 532
Constant elements—
Bunsen's, 595
Daniell's, 595
Grennet, 595
Grove's, 595
Leclanché's, 596
Smee's, 595
Constipation, 332
Contraction, cardiac, 127
fibrillar, 526
initial, 537
Contraction, muscular (see *Myogram*)
of blood vessels, 137
remainder, 530
rhythmical, 523
secondary, 609
without metals, 606
Contracture, 529
Contrast, 830
colors, 824, 830
Convergent lens, action of, 793
Cornea, 783, 784
Coronary vessels, 97
effects of ligature of, 97
Corpora quadrigemina, 700, 702, 770
Corpulence, 413
Corpus callosum, 765
luteum, 909
spongiosum, 909
striatum, 700, 765
Corresponding points, 837
Cortical blindness, 752
Corti's organ, 857
Cotyledons, 928
Coughing, 226
centre for, 711
Cracked-pot sound, 223
Cramp, 892
Cranial flexures, 918
nerves, 634
Cranioscopy, 732
Creatinometer, 394
Cremasteric reflex, 691
Crepitation, 224
Crescents of Gianuzzi, 253
Crista acustica, 859
Crossed reflexes, 688
Crura cerebri, 768
Crusta, 769
petrosa, 268
phlogistica, 71
Crying, 227
Crystallin, 424, 790
Crystalline lens, 790
spheres, 845
Crystallized bile, 312
Crystalloids, 343
Cubic space, 245
Curara, action of, 520, 523, 724
Cutaneous respiration, 238
trophic affections, 631
Cuticular membrane, 268
Cyanogen, 66
Cylindrical lenses, 807
Cynuric acid, 452
Cyrtometer, 220
Cysticercus, 895
Cystin, 464
Cytozoon, 48

Daltonism, 827, 828. 3-4.
Damping apparatus, 851
Darby's fluid meat, 294

Deiter's cells, 859
Delomorphous cells, 285
Demarcation current, 604
Demodex folliculorum, 494
Denis's plasmine, 74
Dentine, 268
Dentition, 270
Depressor fibres, 660, 662, 725
nerve, 167, 660
Deutero-albumose, 293
Development, chronology of, 929
Dextrin, 431
Dextrose, 431
Diabetes mellitus, 310
Diabetic coma, 311
Dialysis, 343
Diapedesis, 182
Diaphanometer, 394
Diaphoretics, 496
Diaphragm, 217
Diarrhœa, 333
Diastatic action, 262, 299, 323, 428
Diastole, 98
Dichroism, 59
Dicrotic pulse, 148
wave, 145
Diet, adequate, 406
effect of age on, 407
effect of work on, 407
flesh, 409
flesh and fat, 411
of carbohydrates, 410
quality of, 403
quantity, 403
Difference theory, 613
Differential rheotom, 610
tones, 868
Diffusion, 342
circles, 799
of gases, 80
Digestion during fever, 332
in plants, 334
Digestion, 664
Diuretics, 471
Division of cells, 893
Double conduction in nerve, 623
Double contact, feeling of, 882
Double images, neglect of, 839
Dreams, 736
Drepanidium, 48
Dromograph, 177
Dropsy, 359
Duct of Cuvier, 936
Gaertner, 941
Ductus arteriosus, 928
venosus, 928
Dura mater, 776
Dust particles, 244
Dys-albumose, 293
Dyschromatopsy, 828
Dyslysin, 313
Dysperistalsis, 281
Dyspnœa, 215, 241, 714

Ear, 847
conduction in, 887
development of, 945
external, 849
fatigue of, 869
fineness of, 862
labyrinth of, 946
meatus of, 849
ossicles of, 851
speculum, 849
tympanum of, 849
Earthy phosphates, 455
Eccentric hypertrophy, 101
Echo speech, 737
Ectoderm, 915
Ectopia cordis, 109
Efferent nerves, 631
Effusions, 359
Egg albumin, 424, 459
Eggs, 395
Skin, 611
Electricity, therapeutical 624
Electrodes, non-polarizat
other forms,
Electrolysis, 594
Electrometer, 603
Electro-motive force, 591
Electro physiology, 591
Electro-therapeutics, 624
Electrotonus, 611, 612
currents in,
in conducto
in inhib
nerves, 6
in motor
611, 615
in muscle,
in sensory
617
Eleidin, 487
Elementary granules of bl
Embryo, formation of, 9
Emetics, 276
Emmetropic eye, 800, 80
Emotions, expression of,
Emulsification, 301
Emulsin, 359
Emulsion, 301
Emydin, 425
Enamel, 269
Enamel organ, 270
Enchylema, 894
End arteries, 192
bulbs, 880
organs, 631
plate, 507
Endocardial pressure, 10
Endocardium, 95
Endoderm, 915
Endolymph, 858
Endomysium, 502
Endoneurium, 580

Enzym, 427
Epiblast, 915
Epicardium, 92
Epidermal appendages, 416
Epididymis, 897
Epidural space, 777
Epigenesis, 949
Epiglottis, 273
injury to, 273
Epilepsy, 731, 745
Epineurium, 579
Epiphysis cerebri, 772
Epithelium, ciliated, 203, 500
Eponychium, 490
Equator, 612
Equilibrium, 653, 697, 732
Erectile tissue, 909
Erection, centre for, 909
of penis, 909
Erect vision, 799
Errhines, 227
Erythrochlorophy, 828
Erythro-dextrin, 262
-granulose, 431
Esbach's method, 459
Eserine, 810
Ether, 34
Eudiometer, 81
Eukalyn, 432
Euperistalsis, 281
Eupnœa, 714
Eustachian catheter, 856
tube, 855
Excitability, action of poisons on, 696
Excitable points of a nerve, 591
Excito-motor nerves, 633
Excretin, 328
Excretion of fæcal matter, 278
Exophthalmos, 833
Expectorants, 247
Experimentum mirabile, 737
Expiration, 213
Expiratory muscles, 217
Explosives, 572
Extensor tetanus, 687
External capsule, 767
genitals, 941, 942
Extra current, 599
Extrapolar region, 615
Extremities, development of, 923
Exudation, 360
Eye, 783
accommodation of, 799
artificial, 778
astigmatism, 807
chromatic aberration of, 807
compound, 843
development of, 944
effect of electrical currents, 813
emmetropic, 800
entoptical phenomena, 812
epiphyseal, 846
excised, 811
Eye, fundus of, 816
hypermetropic, 804
illumination of, 814
movements of, 833
muscles of, 833
myopic, 804
pineal, 846
presbyopic, 805
protective organs of, 843
refractive power of, 803
structure of, 783
Eyeballs, axis of, 833
movements of, 835
muscles of, 835
planes of, 833
positions of, 834
protrusion of, 833
retraction of, 833
simultaneous movements of, 830
Eye currents, 611
Eyelids, 843

Facial nerve, 649
Fæcal matter, 328
excretion of, 278
Fainting, 102
Fallopian tubes, 905
Fall-rhetom, 614
Falsetto voice, 568
Faradic current, 599
Faradization in paralysis, 627
Far point, 803
Fascia, lymphatics of, 357
Fatigue of muscle, 545
stuffs, 545
Fats, 429
decomposition of, 301
metabolism of, 410
origin of, 411
Fat-splitting ferment, 301
Fatty acids, 429
degeneration, 414
Febrifuges, 384
Fechner's law, 782
Fehling's solution, 264, 463
Fermentation, 401
in intestine, 324
test, 265
Ferments, 428
fate of, 324
organized, 428
unorganized, 427
Fertilization of ovum, 912
Fever, 383
after transfusion, 189
Fibres of Tomes, 268
Fibrillar contraction, 525
Fibrin, 58, 71
Fibrin factors, 75
Fibrin-ferment, 76
Fibrinogen, 75, 424
Fibrinoplastin, 75
Fibroin, 426
Field of vision, 799
Field of vision, contest of, 841
Filaria sanguinis, 467
Filiform papillæ, 874
Filtration, 344
First respiration, discharge of, 717
effects of, on thorax, 226
Fish extract, 397
Fission, 893
Fistula, biliary, 316
gastric, 291
intestinal, 322
pancreatic, 298
pyloric, 289
Thiry's, 322
Vella's, 322
Flame spectra, 62
Flavor, 873
Fleischl's law of contraction, 618
hæmometer, 61
Flesh, 396
Flight, 559
Floor space, 245
Flourens' doctrine, 732
Fluid vein, 184
Fluids, flow of, 132
introduction of, 267
Fluorescence, 824
of eye, 799
Fluorescin, 792
Focal distance, 793
line, 802
point, 794
Fœtal circulation, 927
membranes, 925
Follicles, solitary, 339
Fontana's markings, 582
Fontanelle, pulse in, 158
Foods, isodynamic, 363
plastic, 403
quantity, 403, 406
respiratory, 403
utilization of, 399
vegetable, 397
Foramen ovale, 928
of Magendie, 776
Force of accommodation, 805
Forced movements, 770
Forces, 35
Fore-gut, 921
Formatio reticularis, 709
Formative cells, 918
Fovea cardica, 921
centralis, 789, 819
Fractional heat coagulation, 70
Free acid, formation of, 290
Fremitus, 224
Friction sounds, 224
Frog current, 607
Fromann's lines, 579
Fruits, 399
Fundamental note, 863
Fundus glands, 285
Fungi, 324
Fungiform papillæ, 874

Gaertner, ducts of, 941
Galactorrhœa, 392
Galactose, 431
Gallop, 558
Gall stones, 332
Galton's whistle, 862
Galvanic battery, 594
  excitability, 628
Galvano-cautery, 629
Galvanometer, 594
  reflecting, 597
Galvano-puncture, 629
  tonus, 586
Gamgee's method, 76
Ganglionic arteries, 740
Gangrene, 632
Gargling, 227
Gaseous exchanges, 232
Gases, absorption of, 80
  diffusion of, 80
  extraction of, 81
  in blood, 80
  indifferent, 244
  in lymph, 239
  in stomach, 297
  irrespirable, 244
  poisonous, 244
  respired, 232
Gaskell's clamp, 122
Gas-pump, 81
Gasserian ganglion, 641, 642
Gas sphygmoscope, 144
Gastric digestion, 292
  conditions affecting, 294
  fistula, 291
  pathological variations, 331
Gastric giddiness, 655
Gastric juice, 287
  action of drugs on, 291
  action on tissues, 296
  actions of, 292
  artificial, 291
Gaule's experiment, 48
Gelatin, 296, 410, 426
Gelatin *v.* albumin, 410
Gemmation, 894
Genital cord, 941
  corpuscles, 880
  eminence, 941
Genu valgum, 553
  varum, 553
Geometrical color table, 825
Gerlach's theory, 680
Germ epithelium, 901, 920
Germinal area, 915
  membrane, 915
Germinating cells, 350
Germs, 244
Gestation, period of, 930
Giddiness, 654, 655
Ginglymus, 548
Giraldès, organ of, 941
Girdle sensation, 699
Gizzard, 275
Glance, 841
Glands, albuminous, 250
  Bowman's, 871
  Brunner's, 321, 339
  buccal, 250
  carotid, 118, 137, 200, 201
  ceruminous, 494
  changes in, 253
  coccygeal, 137, 200
  Ebner's, 251
  fundus, 285
  Harderian, 846
  lachrymal, 844
  Lieberkühn's, 322, 339
  lingual, 250
  lymph, 351
  mammary, 390
  Meibomian, 843
  mixed, 253
  Moll's, 492
  mucous, 250
  Nuhn's, 251
  parotid, 258
  peptic, 285
  Peyer's, 339
  pyloric, 286
  salivary, 250
  sebaceous, 492
  serous, 250
  solitary, 339
  sublingual, 258
  submaxillary, 253
  sweat, 492
  uterine, 906
  Weber's, 250
Glaucoma, 644
Gliadin, 426
Glisson's capsule, 304
Globin, 425
Globulins, 424
Globuloses, 293
Glomerulus, 435
Glosso-pharyngeal nerve, 655
Glossoplegia, 665
Glossy skin, 632
Glottis, 561, 562
Glucose, 310, 431, 462
  tests for, 264, 265, 462
Glucosides, 428
Glutamic acid, 433
Gluteal reflex, 691
Gluten, 426
Glycerin, 429, 430
  method, 263
Glycerin-phosphoric acid, 430
Glycin, 432
Glycocholic acid, 312
Glycogen, 308, 431
Glycolic acid, 430
Glycosuria, 310, 462
Gmelin-Heintz' reaction, 314
Goblet cells, 337
Goitre, 198
Goll's column, 683
Goltz's balancing experiments, 733
Goltz's croaking experiment, 688
  embrace experiment, 688
  œsophagus experiments, 274
Gorham's pupil photometer, 811
Gout, 89
Graafian follicle, 901
Gracilis experiment, 624
Grandry's corpuscles, 880
Granules, elementary, 58
Granulose, 262
Grape-sugar, 431, 462
  absorption of, 344
  estimation of, 265
  injection of, 309
  in urine, 462
  tests for, 264
  volumetric analysis, 463
Gravitation, 35
Great auricular nerve, 725
Green blindness, 828
Green vegetables, 399
Growth, 420
Guanidin, 532
Guanin, 489, 502
Guarana, 400
Gubernaculum testis, 941
Gum, 431
Gustatory centre, 754, 763
  fibres, 650
  region, 874
  sensations, 876
Gymnastics, 553
Gymnotus, 629
Gyri, 700

Hay's reaction, 313, 462
Hæmacytometer, 46
Hæmadromometer, 175
Hæmadynamometer, 161
Hæmatin, 66, 67
Hæmatoblasts, 57
Hæmatohidrosis, 498
Hæmatoidin, 68
Hæmatoma aurium, 632
Hæmatoporphyrin, 67
Hæmaturia, 460
Hæmautography, 144
Hæmin and its tests, 67, 461
Hæmochromogen, 66
Hæmocyanin, 79
Hæmocytolysis, 48
Hæmocytometer, 46
Hæmocytotrypsis, 48
Hæmodynamometer, 161
Hæmoglobin, 59
  amount of, 61
  analysis, 59
  carbonic oxide, 65
  compounds of, 62
  crystals, 59
  decomposition of, 66

Hæmoglobin, estimation of, 60
nitric oxide, 66
pathological, 61
preparation, 59
proteids of, 68
reduced, 63
spectrum, 62
Hæmoglobinometer, 60
Hæmoglobinuria, 460
Hæmometer, 61
Hæmophilia, 72
Hemorrhage, death by, 89
effect on, 723
Hemorrhagic diathesis, 72
Hæmotachometer, 176
Haidinger's brushes, 814
Hair, 490
cells, 859
follicle, 490
Halisterisis, 553
Hallucinations, 782
Hammarsten, 75
on blood, 75
Harderian gland, 846
Hare-lip, 931
Harmony, 868
Harrison's groove, 215
Hassall's corpuscles, 198
Hawking, 227
Hay's test, 313
Head-fold, 921
Head-gut, 921
Hearing, 847
Heart, 92
accelerated action, 108
action of fluids on, 123
action of gases, 127
action of poisons on, 124, 127
apex, 124
apex beat, 102
arrangement of fibres, 92
aspiration of, 172
auricular systole, 98
automatic centres, 121
automatic regulation, 96 97
blood vessels of, 97
changes in shape, 106
chordæ tendineæ, 100
cutting experiments, 109
development of, 921, 934
diastole, 98
duration of movements, 116
endocardium, 95
examination of, 117
frog's, 118
ganglia of, 118
hypertrophy of, 101
impulse of, 102
innervation of, 117
movements of, 98
muscular fibres, 94
myocardium, 92
nerves, 118
Heart nutritive fluids, 120
palpitation of, 101
pause of, 100, 107
pericardium, 95
Purkinje's fibres, 96
regulation of, 96, 97
section of, 122
sounds of, 112
staircase beats of, 122, 126
systole, 98
valves of, 95
weight, 96
work of, 180
Heat, 37
balance of, 379
calorimeter, 371
centres, 377, 755
conductivity, 373
dyspnœa, 215, 715
employment of, 384
estimation of, 371
excretion of, 377
income and expenditure, 380
in inflamed parts, 387
in muscle, 543
latent, 362
production, 364
regulating centre, 376
relation to work, 381
sources of, 362
specific, 371
stiffening, 517
storage of, 382
units, 37, 363
variations in production, 380
Helicotrema, 857
Heller's test, 265, 458
blood test, 461
Helmholtz's modification, 599
Hemeralopia, 637
Hemialbumin, 293
Hemialbumose, 292, 293
Hemianæsthesia, 744
Hemianopsia, 636
Hemicrania, 728
Hemiopia, 636
Hemipeptone, 292
Hemiplegia, 757
Hemisystole, 112
Henle's loop, 435
sheath, 580
Hen's egg, 903
Hensen's experiments, 867
Hepatic cells, 305
chemical composition of, 307
zones, 305
Hepatogenic icterus, 317
Herbst's corpuscles, 881
Hermann's theory of tissue currents, 613
Herpes, 632
Hetero-albumose, 293
Hetero-xanthin, 450
Heterologous stimuli, 781
Hewson's experiments, 74
Hibernation, 386
Hiccough, 227
Hippocampus, 738
Hippuric acid, 451
Hippus, 638
Histo-hæmatin, 200
Historical—
Absorption, 361
Circulation, 202
Digestion, 334
Hearing, 870
Heat, 387
Kidney and urine, 486
Metabolism, 433
Nerves and electro-physiology, 629
Nerve centres, 780
Peripheral nerves, 674
Reproduction and development, 948
Respiration, 249
Sight, 845
Skin, 499
Smell, 873
Taste, 877
Voice and speech, 573
Hoarseness, 573
Holoblastic ova, 903
Homoiothermal animals, 365
Homologous stimuli, 781
Horopter, 838
Hot spots, 887
Howship's lacunæ, 934
Humor, aqueous, 792
Hunger and starvation, 408
Hyaloid canal, 791
Hybrids, 912
Hydatids, 896
Hydræmia, 89
Hydramnion, 924
Hydrobilirubin, 314
Hydrocele, 75
Hydrocephalus, 778
Hydrochinon, 453
Hydrochloric acid, 288
Hydrocyanic acid, 66
Hydrogen in body, 421
Hydrolytic ferments, 427
Hydronephrosis, 485
Hydrostatic test, 209
Hydroxylbenzol, 453
Hyo-cholalic acid, 313
Hypakusis, 653
Hypalgia, 891
Hyperæsthesia, 696
Hyperakusis, 653
Hyperalgia, 653
Hyperdicrotism, 149
Hypergeusia, 877
Hyperglobulie, 88
Hyperidrosis, 498
Hyperkinesia, 696
Hypermetropia, 804

Hyperoptic, 804
Hyperosmia, 634
Hyperpselaphesia, 889
Hypertrophy of heart, 101, 111
of muscle, 554
Hypnotism, 736
Hypoblast, 915
Hypogeusia, 877
Hypoglossal nerve, 664
Hypophysis cerebri, 200, 772
Hypopselaphesia, 889
Hyposmia, 634
Hypospadias, 941
Hypoxanthin, 433

Ichthidin, 425
Icterus, 318
Identical points, 837
Ileo-colic valve, 277
Ileus, 278
Illumination of eye, 814
Illusion, 782
Images, formation of, 798
Imbibition currents, 615
Impregnation, 913
Impulse, cardiac, 102
Impulses in brain, course of, 704
Inanition, 233
Incisures, 578
Income, 406
Indican, 452
Indifferent point, 615
Indigo blue, 453
Indigo carmine test, 463
Indigogen, 453
Indirect vision, 819
Indol, 300, 327
Induction, 599
Inductorium, 601
Inferior maxillary nerve, 645
Inhibition, nature of, 690
Inhibition of reflexes, 689
Inhibitory action of brain, 756
nerves, 633
for heart, 718
for intestine, 282
for respiration, 716
Inion, 764
Initial contraction, 537
Inosinic acid, 433
Inosit, 432
Insectivorous plants, 334
Inspiration, 213
centre for, 713
muscles of, 216
ordinary, 216
Intelligence, degree of, 734
Intercellular blood channels, 137
Intercentral nerves, 633
Intercostal muscles, 218
Interference, 868
Interglobular spaces, 268
Interlobular vein, 304
Internal capsule, 766
Internal reproductive organs, 940
respiration, 203, 238
Intestinal fistula, 322
gases, 324
juice, 323
actions of, 323
paresis, 282
Intestine, 278
artificial circulation, 283
development of, 938
effect of drugs on, 283
fermentation processes in, 324
large, 328, 342
movements of, 278
small, 336
Intra-labyrinthine pressure, 860
Intra-lobular vein, 304
Intra-ocular pressure, 644, 792, 811
Intra-thoracic pressure, 225
Intra-vascular hemorrhage, 727
Inulin, 432
Inunction, 498
Invertin, 326
Invert sugar, 326
Inverted image, 798
Ions, 594
Iris, 786
action of poisons on, 810
blood vessels of, 787
functions of, 808
movements of, 809
muscles of, 809
nerves of, 809
Irradiation, 830
of pain, 698, 890
Ischuria, 486
Island of Reil, 741
Isodynamic foods, 363
Isolated beats, 868
Isometrical act, 537
Isotropous, 511

Jacksonian epilepsy, 746, 759
Jacobson's organ, 872
Jaeger's types, 805
Jaundice, 317
Jaw jerk, 693
Joints, 548
arthrodial, 549
ball and socket, 549
ginglymus, 548
mechanism of, 547
rigid, 549
screw-hinge, 548
Juice canals, 348

Karyokinesis, 894
Karyomiton, 893
Karyoplasma, 893
Katabolic metabolism, 388
nerves, 633
Katalepsy, 737
Kations, 594
Keratin, 426
Keratitis, 652
Keys—
Capillary contact, 603
Friction, 602
Plug, 602
Kidney, 434
blood of, 475
chemistry of, 475
conditions affecting, 476
reabsorption in, 473
structure of, 434
volume of, 477
Kinæsodic substance, 695
Kinetic energy, 362
theory, 654
Klang, 864
Knee phenomenon, 693
jerk, 693
reflex, 693
Kœnig's monometric flames, 866
Koumiss, 395
Krause's end bulbs, 880
Kreatin, 433
Kreatinin, 433, 449
properties, 449
quantity, 449
test, 449
Kresol, 433
Kryptophanic acid, 454
Kühne's artificial eye, 798
experiments, 606, 623
pancreas powder, 301
Kymograph, 162
Fick's, 165
Hering's, 164
Ludwig's, 162
Kyphosis, 553

Labials, 572
Labor, power of, 946
Labyrinth, 856
Lachrymal apparatus, 844
Lacteals, 336, 348
Lactic acid, 288, 393, 430
ferment, 296
Lactometer, 394
Lactoprotein, 393
Lactoscope, 394
Lactose, 431
Lævulose, 326, 431
Lagophthalmus, 638
Lambert's method, 824
Laminæ dorsales, 918
Lamina spiralis, 857
Language, 761
Lanoline, 494
Lanugo, 491
Lapping, 267
Lardacein, 425
Large intestine, 328, 342
absorption in, 328

Laryngoscope, 566
Larynx, cartilages of, 560
during respiration, 567
experiments on, 568
illumination of, 565
mucous membrane of, 564
muscles of, 561
view of, 566
vocal cords, 560
Latent heat, 362
period, 528
Lateral plates, 920
Laughing, 227
Law of conservation of energy, 38
contraction, 618
isolated conduction, 623
peripheral perception, 881
specific energy, 781
Leaping, 557
Lecithin, 69, 429, 518
Legumin, 398
Lens, chemistry of, 790
crystalline, 790
development of, 945
Lenticular nucleus, 766
Leptothrix epidermalis, 498
buccalis, 261
Leucic acid, 430
Leucin, 300
Leucocytes, 54
Leucoderma, 632
Leucomaines, 294
Leukæmia, 59
Levers, 551
Lichenin, 432
Lieben's test, 454
Lieberkühn's glands, 321
jelly, 425
Liebermann's reaction, 424
Liebig's extract, 397
Life, 38
Limbic lobe, 754
Limb plexus, 669
Liminal intensity, 781
Line of accommodation, 803
Ling's system, 553
Lingual nerve, 646
Lipæmia, 88
Liquor sanguinis, 70
Listing's reduced eye, 797
law, 834
Liver, 303
action of drugs on cells, 306
chemical composition, 307
cirrhosis of, 307
development of, 939
fat in, 309
functions of, 311
glycogen in, 308
influence on metabolism, 316
Liver, pathology of, 307
pulse in, 186
regeneration of, 307
structure of, 303
Lobes of brain, 740
Locality, sense of, 882
illusions of, 884
Lochia, 947
Locomotor ataxia, 697
Lordosis, 553
Loss by skin, 238
Loss of weight, 409
Löwe's ring, 814
Lungs, 203
chemical composition of, 209
development of, 939
elastic tension of, 129, 173, 210
examination of, 220
excision of, 209
limits of, 221
physical properties, 209
structure of, 205
tonus, 208
Lunule, 489
Lutein, 909
Luxus consumption, 403
Lymph, 353
movement of, 356
gases of, 239, 354
Lymphatics, 348
of eye, 791
origin of, 348
Lymph corpuscles, 352
origin and decay of, 355, 356
follicles, 351
glands, 351
hearts, 358

Macropia, 638
Macula lutea, 789
Maculæ acusticæ, 859
Madder, feeding with, 418
Magnetization, 599
Magneto-induction, 600
Major chord, 861
Malapterurus, 629
Malt, 401
Maltose, 262, 431
Mammary glands, 390
changes in, 390
development of, 391
structure of, 390
Manometer, 161
frog, 123
maximum, 100
minimum, 100
Manometric flames, 866
Marey's tambour, 109
Margarin, 489
Marginal convolutions, 741
Mariotte's experiment, 818
Massage, 553
Mastication, 267
Mastication, muscles of, 267
nerves of, 267
Matè, 400
Matter, 34
Maturation of ovum, 913
Meat soup, 397
Meckel's cartilage, 931
ganglion, 645
Meconium, 320
Medulla oblongata, 705
Functions of, 710
Gray matter of, 708
Reflex centres in, 710
Structure of, 705
Medullary groove, 916
tube, 918
Meibomian glands, 843
Meiocardia, 128
Meissner's plexus, 275, 281, 342
Melanæmia, 59
Melanin, 429
Melitose, 431
Mellitæmia, 88
Mellituria, 88
Membrana decidua menstrualis, 925
flaccida, 849
reticularis, 860
reuniens, 922
secundaria, 856
tectoria, 859
tympani, 849
Membranes of brain, 776
Menière's disease, 655
Menopause, 906
Menstruation, 907
Mercurial balance, 885
Merkel's cells, 880
Meroblastic ova, 903
Mesentery, development of, 939
Mesoblast, 916
Mesonephros, 941
Metabolic equilibrium, 402
phenomena, 388
Metabolism, 388
in anæmia, 89
on flesh and other diets, 409
Metakresol, 453
Metalbumin, 424
Metallic tinkling, 224
Metalloscopy, 891
Metamorphosis, 895
Metanephros, 941
Meteorism, 282
Methæmoglobin, 64
Methylamine, 432
Meynert's projection systems, 700
theory, 734
Micrococci, 457
Micrococcus ureæ, 457
Microcytes, 58
Micropyle, 902
Microscope, 180
Microörganisms, 330

Micro-spectroscope, 62
Micturition, 483
centre for, 694
Migration of ovum, 912
Milk, 392
action of drugs on, 392
coagulation of, 393
colostrum, 390
composition of, 391
curdling ferment, 288, 393
digestion of, 295
fever, 392, 947
globules of, 392
peptonized, 303
plasma, 392
preparations of, 395
substitutes for, 394
sugar, 393
tests for, 394
Millon's reagent, 423
Mimetic spasm, 652
Mimicry, 574
Minor chord, 861
Mitosis, 894
Mixed colors, 825
Modiolus, 857
Molecular basis of chyle, 353
Molecules, 34
Molisch's test, 265
Monoplegia, 759
Monospasm, 760
Moore's test, 265
Moreau's experiment, 323
Mormyrus, 629
Morphology, 33
Morula, 914
Motion, illusions of, 830
Motor areas, 756
Motor centres, dog, 742, 744
excision of, 749
in man, 749
in monkey, 746
nerves, 631
paths, 703
points on the surface, 624, 625
Mouth, 250
glands of, 250
Mouvements de manège, 771
Movements of the eye, 833
acquired, 750
forced, 770
incoördinated, 668
Mucedin, 426
Mucigen, 337
Mucin, 312, 426
Mucous membrane currents, 611
tissue, 791
Mucus, effect of drugs on, 247
formation of, 245, 312
Mulberry mass, 914
Mulder's test, 265
Müller's ducts, 940
experiment, 129, 154
fibres, 789
valve, 228
Multiplicator, 593
Murexide test, 449
Murmurs, cardiac, 115
venous, 185
Muscæ volitantes, 812
Muscarin, 720
Muscle, 502
action of two stimuli on, 533
action of veratrin, 532
active changes in, 524
arrangement of, 549
atrophic proliferation of, 554
blood vessels of, 506
cardiac, 92, 509
changes during contraction, 524
chemical composition, 511
current, 597
curve of, 528
degenerations of, 554
development of, 509
effect of acids on, 518
effect of cold on, 518
effect of distilled water on, 518
effect of exercise on, 553
effect of heat on, 517
elasticity of, 541
electric currents of, 604
excitability of, 519
extractives of, 514
fatigue of, 545
ferments, 512
fibrillæ, 504
formation of heat in, 543
gases in, 513
glycogen in, 512, 514
hypertrophy, 554
involuntary, 502
lymphatics of, 507
metabolism of, 513
myosin of, 572
nerves of, 507
nutrition of, 553
of heart, 92, 509
perimysium of, 502
physical characters, 511
plasma of, 511
plate, 922
polarized light on, 511
reaction, 511
recovery of, 547
red and pale, 509
relation to tendons, 506
rhythmical contraction, 523
rigor mortis of, 515
rods, 505
sensibility, 508, 543
serum of, 512
smooth, 502, 509
sound of, 545
Muscle, spectrum of, 509
staircase of, 535
stimuli of, 522
structure of striped, 502
tetanus, 534
tonus, 543, 694
uses of, 549
volume of, 524
voluntary, 502
work of, 538
Muscle current, 603
theories, 613
Muscular contraction (see *Myogram*), rate of, 537
Muscular energy, 515
exercise, 233
sense, 891
work, 514
laws of, 538
Mutes, 572
Mydriasis, 638
Mydriatics, 810
Myelin forms, 577
Myocardium, 92
Myogram, 528
effect of constant current on, 532
effect of fatigue on, 531
effect of poisons on, 532
effect of veratrin on, 532
effect of weights on, 531
method of studying, 526
stages of, 529
Myograph, Helmholtz's, 526
pendulum, 526
Pflüger's, 528
simple, 528
spring, 528
Myohæmatin, 429, 509
Myopia, 804
Myoryctes Weismanni, 511
Myosin, 424, 512
ferment, 512
Myosis, 639
Myotics, 811
Myxœdema, 199, 632

Nails, 489
Narcotics, 890
Nasal breathing, 226
timbre, 571
Nasmyth's membrane, 268
Native albumins, 424
Natural selection, 947
Near point, 803
Neef's hammer, 601
Negative accommodation, 800
after images, 830
pressure, 344
variation, 607, 609

Nephrozymose, 454
Nerve cells, 575, 580
bipolar, 580
multipolar, 580, 679
of cerebrum, 737
Purkinje's, 773
with a spiral fibre, 581
Nerve centres, general functions, 675
Nerve current, 603
Nerve fibres, 575
action of nitrate of silver on, 579
chemical properties of, 581
classification of, 631
death of, 591
degeneration of, 587
development of, 580
division of, 579
effect of a constant current on, 585
electrical current of, 603
electrical stimuli, 585
excitability of, 583
fatigue of, 587
incisures of, 578
mechanical properties of, 582
medullated, 575
metabolism of, 582
nutrition of, 588
Ranvier's nodes, 578
reaction of, 582
recovery of, 587
regeneration of, 587, 589
sheaths of, 579
stimuli of, 583
structure of, 575
suture of, 590
terminations of, 878
to glands, 256
traumatic degeneration of, 589
trophic centres of, 589
unequal excitability of, 586
union of, 590
unipolar stimulation of, 587
Nerve impulse, rate of, 620
method of measuring, 621
modifying conditions of, 620
Nerve motion, 623
Nerve-muscle preparation, 606
Nerves, 631
afferent, 633
anabolic, 633
centrifugal, 631
centripetal, 633
cranial, 634
electrical, 623
intercentral, 633
katabolic, 633
Nerves, motor, 631
secretory, 631
sensory, 633
special sense, 633
spinal, 665
trophic, 631
union of, 590
vaso-dilator, 729
vasomotor, 722
visceral, 633
Nerve stretching, 583
Nervi nervorum, 580
Nervous system, 575
development, 943
Nervus abducens, 649
accelerans, 720
accessorius, 664
acusticus, 653
depressor, 660
erigens, 693, 729, 910
facialis, 649
glossopharyngeus, 655
hypoglossus, 664
oculomotorius, 637
olfactorius, 634
opticus, 634
sympathicus, 670
trigeminus, 640
trochlearis, 639
vagus, 657
Neubauer's test, 265
Neuralgia, 648
Neuroglia, 681, 682
Neural tube, 918
Neurasthenia gastrica, 331
Neurin, 581
Neuro-epithelium, 788
Neuro-keratin, 578
Neuro-muscular cells, 522
New-born child, digestion of, 291
pulse, 149
size, 419
temperature, 374
urine of, 440
weight, 419
Nictitating membrane, 846
Nitrites, 64
on pulse, 147
Nitrogen in air, 230
in blood, 85
in body, 421
given off, 402
Nœud vital, 712
Noises, 860
Nose, development of, 931
structure, 871
Notochord, 919
Nuclear spindle, 861
Nuclein, 426
Nucleus of Pander, 904
Number forms, 870
Nussbaum's experiments, 472
Nutrient enemata, 347
Nyctalopia, 637
Nystagmus, 654, 771
Oatmeal, 398
Octave, 861
Oculomotorius, 637
Odontoblasts, 268
Œdema, 359
cachectic, 360
pulmonary, 226
Œsophagus, 274, 275
Ohm's law, 592
Oleic acid, 429
Oligæmia, 89
Olivary body, 707
Olfactory centre, 754, 763
nerve, 634
sensations, 872
Omphalo-mesenteric duct, 921
vessels, 922
Onamatopoesy, 574
Oncograph, 195, 477
Oncometer, 477
Ontogeny, 948
Opening shock, 599
Ophthalmia neuro-paralytica, 644
intermittens, 644
sympathetic, 644
Ophthalmic nerve, 641
Ophthalmometer, 798
Ophthalmoscope, 814
Optic nerve, 634, 813
radiation, 635
thalamus, 766
tract, 634
vesicle, 919
Optical cardinal points, 795
Optogram, 823
Optometer, 805
Ordinates, 164
Organic albumin, 403
compounds, 423
reflexes, 693
Ortho-kresol, 453
Orthopnœa, 215
Orthoscope, 817
Osmasome, 397
Ossein, 427
Osseous system, formation of, 930
Osteoblasts, 934
Osteoclasts, 934
Osteomalacia, 553
Otic ganglion, 646
Ovarian tubes, 902
Ovary, 901
Overcrowding, 245
Ovulation, 907
theories of, 908
Ovum, 901
development of, 902
discharge of, 908
fertilization of, 912
impregnation of, 913
maturation of, 913
migration of, 912
structure of, 901
Oxalic acid, 430, 450

Pacchionian bodies, 777
Pacini's corpuscles, 879
Pain, 889
irradiation of, 890
points, 882
Painful impressions, conduction of, 697
Palmitic acid, 429
Palpitation, 101
Pancreas, 297
changes in, 298
development of, 939
fistula of, 298
juice of, 299
paralytic secretion, 303
powder, 301
salt, 302
Pancreatic secretion, 298
actions of, 299
artificial juice, 300
action of nerves on, 302
action of poisons on, 303
composition, 298, 299
extracts, 302
Panophthalmia, 643
Pansphygmograph, 102
Papain, 301
Papilla foliata, 875
Papillæ of tongue, 874
Parablastic cells, 920
Paradoxical contraction, 612
Paraglobulin, 78
Parakresol, 433, 453
Paralbumin, 423
Paralgia, 890
Paralytic secretion of saliva, 258
pancreatic juice, 303
Paramylum, 432
Para peptone, 292
Paraphasia, 761
Peptogenic substances, 291
Peptone, 292, 294
absorption of, 345
forming ferment, 288
injection of, 73, 345
metabolism of, 410
tests for, 294
Peptonized foods, 303
Peptonuria, 459
Percussion of heart, 117
lungs, 222
sounds, 222
wave, 145
Perforating ulcer of the foot, 632
Pericardium, 95
fluid of, 354
Perilymph, 858
Perimeter, Aubert and Forster, 819
M'Hardy's, 820
Priestley Smith's, 822
Perimetric chart, 820
Perimetry, 819
Perimysium, 92, 502
Perineurium, 580
Periodontal membrane, 268
Peristaltic movement 277
action of blood on, 281
action of nerves on, 283
Peritoneum, development of, 939
Perivascular spaces, 738
Pernicious anæmia, 58
Pettenkofer's test, 313
apparatus, 229
Peyer's glands, 339
Pflüger's law, 617
law of reflexes, 688
Phagocytes, 56
Phakoscope, 802
Phänakistoscope, 830
Phases, displacement of, 864
Phenol, 327, 453
Phenylsulphonic acid, 453
Pitch, 861
Pituitary body, 772
Placenta, 926
Placental bruit, 184
Plantar reflex, 691
Plants, characters of, 39
digestion by, 334
electrical currents
Plasma cells, 776
of blood, 70, 78
of invertebrates,
of lymph, 353
of milk, 392
of muscle, 511
Plasmine, 74
Plethora, 88
Plethysmography, 187
Pleura, 206
Pleuro-peritoneal cavity,
Pleximeter, 221
Pneumatic cabinet, 155
Pneumatogram, 214
Pneumatometer, 226
Pneumograph, 128, 213
Pneumonia after section
661
Pneumothorax, 210
Poikilothermal animals,
Poiseuille's space, 181
Poisons, heart, 127
Polar globules, 913
Polarization, galvanic, 59
internal, 598
Polarizing after-currents,
Politzer's ear bag, 856
Polyæmia, 87
apocoptica, 87
aquosa, 87
hyperalbumino
polycythæmica
serosa, 87
Polyopia monocularis, 80
Pons Varolii, 769
Porret's phenomenon, 50

Potatoes, 398
Presbyopia, 805
Pressor fibres, 724
Pressure, arterial, 165
atmospheric, 247
intra-labyrinthine, 860
of blood, 161
phosphenes, 813
points, 882, 885
respiratory, 225
sense of, 885
Presystolic sound, 115
Prickle cells, 487
Primitive anus, 923
aorta, 921
chorion, 915, 925
circulation, 921
groove, 915
kidneys, 940
mouth, 923
streak, 915
Primordial cranium, 930
ova, 902
Principal focus, 793
Proctodæum, 918
Proglottis, 895
Progressive muscular atrophy, 554
Pronephros, 941
Pronucleus, male, 913
female, 913
Propepsin, 289
Propeptone, 292
Protagon, 428
Proteids, 423
coagulated, 425
gastric digestion of, 292
fermentation of, 327
metabolism of, 409
pancreatic digestion of, 300
reactions of, 423
vegetable, 425
Proteolytic ferments, 427
Proteoses, 292
Protistæ, 33, 41
Proto-albumose, 293
Protovertebræ, 919
Pseudo-hypertropic paralysis, 554
Pseudo-motor action, 650, 653
Pseudoscope, 841
Pseudo-stomata, 206
Psychical activities, 731
blindness, 752
deafness, 753
processes, time of, 735
Psycho-physical law, 781
Ptomaines, 294
Ptosis, 638
Ptyalin, 263, 264
Ptyalism, 259
Puberty, 906
Pulmonary artery, pressure in, 173
vessels, 206
Pulmonary œdema, 226
Pulp of tooth, 269
of spleen, 192
Pulse, 139
anacrotic, 153
capillary, 161
catacrotic, 145
characters of, 144
conditions affecting, 149
curve, 144
dicrotic, 148
entoptical, 157
hyperdicrotic, 149
in animals, 150
in jugular vein, 186
in liver, 186
influence of pressure on, 155
influence of respiration on, 153
instruments for investigating, 140
monocrotic, 148
of various arteries, 151
paradoxical, 155
pathological, 158
rate, 149, 170
recurrent, 152
tracing, 144
trigeminal, 150
variations in, 150
venous, 185
wave, 156
Pulses, 398
Pulsus alternans, 150
bigeminus, 150
caprizans, 149
dicrotus, 149
intercurrens, 150
myurus, 150
Pumping mechanisms, 357
Pupil, 802
action of poisons on, 810
Argyll Robertson, 810
functions of, 808
movements of, 809
photometer, 811
size of, 811
Pupilometer, 811
Purgatives, 283
Purkinje, cells of, 773
fibres of, 96, 509
figure, 812
Sanson's images, 801
Pus corpuscles, 182
Putrefaction, pancreatic, 300
Putrefactive processes, 328
Pyloric glands, 286
changes in, 289, 290
fistula, 289
Pyramidal cells, 739
tracts, 684
degeneration of, 758
Pyrokatechin, 430, 453
Pyuria, 465
Quality of a note, 861, 863
Quantity of blood, 86
of food, 405
of gases, 232
Râles, dry, 224
moist, 224
Rami communicantes, 670
Range of accommodation, 806
Ranvier's nodes, 578
Raynaud's disease, 632
Reaction impulse, 105
Reaction of degeneration, 627
Reaction time, 624, 735
Recoil wave, 145
Rectum, 283
Recurrent pulse, 152
sensibility, 667
Red blindness, 828
Reduced eye of Listing, 797
Reducing agents, 84
Reductions in intestine, 328
Reflex acts, examples of, 687
inhibition of, 689
law of, 688
movements, 686
Reflex movements, theory of, 691
nerves, 633
organic, 693
spasms, 686
tactile, 697
time, 689
tonus, 695
Reflexes, crossed, 688
deep, 692
spinal, 686
organic, 694
Refracted ray, 794
Refractive indices, 794
Regeneration of tissues, 416
of nerve, 589
Regio olfactoria, 871
respiratoria, 871
Regnault's apparatus, 228
Reissner's membrane, 857
Relative proportions of diet, 405
Remak's ganglion, 119
Renal plexus, 476
Rennet, 295, 393
Reproduction, forms of, 893
Requisites in a proper diet, 405
Reserve air, 210
Residual air, 210
Resistance, 132
Resonance organs, 560
Resonants, 572
Resonators, 867
Resorcin, 453
Respiration, 203
amphoric, 224
artificial, 243
Biot's, 216
bronchial, 224
centre for, 712
chemistry of, 227

Respiration, cog-wheel, 224
cutaneous, 238
first, 717
forced, 216
foreign gases, 244
in a closed space, 240
in animals, 212
internal, 238
mechanism of, 209
muscles of, 216
nasal, 226
number of, 211
pathological, 215
periodic, 216
pressure during, 225
pressure on heart, 128
sounds of, 223
time of, 212
type, 214
variations of, 211
vesicular, 223
Respiratory apparatus, 203
Andral and Gavarret, 228
centre, 712
mechanism of, 209
v. Pettenkofer, 229
quotient, 231
Regnault and Reiset, 229
Scharling, 229
undulations, 167
Restiform bodies, 705
Rete mirabile, 91
Retina, 787
activity in vision, 818
blood vessels of, 789
capillaries, movements in, 813
chemistry of, 790
epithelium of, 789
rods and cones of, 788, 819
stimulation of, 829
structure of, 787
visual purple of, 789
Retinal image, formation of, 798
size of, 798
Retinoscopy, 817
Reversion, 948
Rheocord, 592
Rheometer, 176
Rheophores, 625
Rheoscopic limb, 606
Rheostat, 593
Rheotom, 610
Rhinoscopy, 568
Rhodophane, 790
Rhodopsin, 789
Ribs, 218
Ricket's, 553
Rigor mortis, 515
Ritter's opening tetanus, 618
tetanus, 618
Ritter-Valli law, 591
Rods and cones, 788, 819
Rods of Corti, 859
Rosenthal's modification, 521
Rotatory disk for colors, 824
Rudimentary organs, 948
Rumination, 333
Running, 555

Saccharomycetes, 401
Saccharose, 431
Saccule, 857
Saftcanälchen, 348
Saline cathartics, 284
Saliva, action of nerves on, 256
action of poisons on, 257
action on starch, 262
chorda, 256
composition of, 261
facial, 256
functions of, 263
mixed, 261
new-born child, 262
paralytic secretion, 258
parotid, 260
pathological, 331
ptyalin, 260, 263
reflex secretion of, 258
sublingual, 261
submaxillary, 260
sympathetic, 256
theory of secretion, 260
Salivary corpuscles, 261
Salivary glands, 252
changes in, 253
development of, 939
extirpation of, 258
nerves of, 255
Salts, 421
Sanson-Purkinje's images, 801
Saponification, 301
Sarcina ventriculi, 332
Sarcoglia, 508
Sarcolactic acid, 512
Sarcolemma, 503
Sarcolytes, 509
Sarcoplasts, 509
Sarcous elements, 504
Sarkin, 450
Sarkosin, 433
Saviotti's canals, 298
Scheiner's experiment, 803
Schiff's test, 449
Schizomycetes, 90, 324
Schmidt's researches, 74
Schreger's lines, 268
Schwann's sheath, 578
Sclerotic, 785
Scoliosis, 553
Scotoma, 822
Screw-hinge joint, 548
Scrotum, formation of, 941
Scurvy, 58
Scyllit, 432
Sebaceous glands, 492
secretion, 493
Seborrhœa, 498
Secondary circulation, 922
contraction, 609
decompositions, 595
degeneration, 683
tetanus, 609
Secretion currents, 611
Secretory nerves, 631
Sectional area, 178
Segmentation sphere, 914
Self-stimulation of muscle, 606
Semen, composition of, 898
ejaculation of, 911
reception of, 911
Semicircular canals, 654, 859
Sensation, 781
Sense organs, 781
development of, 944
Sensory areas, 751
crossway, 705, 768
paths, 704
sensations, 881
Serin, 433
Serous cavities, 350
Serum of blood, 71
Serum albumin, 78, 424
Serum globulin, 78, 424
Setschenow's centres, 690
Sex, difference of, 942
Shadows, lens, 812
colored, 832
Sharpey's fibres, 934
Short-sightedness, 804
Shunt, 598
Sialogogues, 259
Sighing, 227
Silver lines, 136
Simple colors, 824
Simultaneous contrast, 830
Sinuses, 137
Sitting, 555
Size, 419, 420
estimation of, 841
increase in, 419
false estimate of, 843
Skatol, 300, 327, 454
Skin, absorption by, 498
chorium of, 487
currents of, 607
epidermis, 487
functions of 487
galvanic conduction of, 499
glands of, 492
historical, 499
pigments, 495
protective covering, 493
respiratory organ, 238, 493
structure of, 487
varnishing the, 493
Skin currents, 611
Sleep, 735
Small intestine, 336

Small intestine, absorption by, 344
structure of, 336
Smegma, 494
Smell, sense of, 871
Sneezing, 227
Snellen's types, 805
Sniffing, 872
Snoring, 227
Sodic chloride, 421
salts, 421
Solitary follicles, 339, 342
Somatopleure, 920
Somnambulism, 734
Sorbin, 432
Sound, 848
cardiac, 109
conduction to ear, 848, 857
direction of, 869
distance of, 869
perception of, 869
reflection of, 848
Sounds, cardiac, 112
cracked pot, 223
respiratory, 223
tympanitic, 223
vesicular, 223
Spasm centre, 730
Spasmus nictitans, 653
Specific energy, 781, 823
Spectacles, 806
Spectra, absorption, 62
flame, 62
ocular, 814
Spectroscope, 61
Spectrum mucro-lacrimale, 812
of bile, 314
of blood, 62
of muscle, 509
Speech, 569
centre for, 760
pathological variations, 573
Spermatin, 898
Spermatozoa, 898
Spermatoblasts, 899
Spheno-palatine ganglion, 645
Spherical aberration, 807
Sphincters, 552
Sphincter ani, 279
pupillæ, 786
urethræ, 483
Sphygmogram, 144
Sphygmograph, 140
Dudgeon's, 142
Ludwig's, 142
Marey's, 141
Sphygmometer, 140
Sphygmomanometer, 165
Sphygmoscope, 144
Sphygmotonometer, 139
Spina bifida, 776, 922
Spinal accessory nerve, 664
Spinal cord, 676
action of blood and poisons on, 696
Spinal cord, blood vessels of, 682
centres, 693
conducting paths in, 683
conducting system of, 683, 696
degeneration of, 685
development of, 944
excitability of, 695
Flechsig's systems, 683
functions of, 683
ganglion, 666
Gerlach's theory, 680
nerves, 665
neuroglia of, 681
nutritive centres in, 685
reflexes, 686
regeneration of, 731
secondary degeneration of, 685
segment of, 685
structure of, 676
time of development, 686
transverse section of, 699
unilateral section of, 699
vasomotor centres in, 727
Spinal cord, Woroschiloff's observations, 697
Spinal nerves, 665
anterior roots of, 669
posterior roots of, 669
Spiral joints, 549
Spirillum, 90, 324
Spirochæta, 90, 324
Spirometer, 211
Splanchnic nerve, 282
Splanchnopleure, 920
Spleen, 192
action of drugs on, 197
chemical composition, 194
contraction of, 195
extirpation of, 194
functions of, 194
influence of nerves on, 196
oncograph, 195
regeneration of, 194
structure, 192
tumors of, 197
Spongin, 426
Spontaneous generation, 893
Spores, 326
Spring kymograph, 164
Spring myograph, 529
Springing, 555
Sputum, abnormal coloration, 248
normal, 247
Squint, 638
Staircase, 535
Stammering, 573
Standing, 554
Stannius's experiment, 121
Stapedius, 854
Starch, 431
Starvation, 408
Stasis, 183
Statical theory of Goltz, 654
Stationary vibrations, 848
Steapsin, 301
Stenopaic spectacles, 807
Stenosis, 112
Stenson's experiment, 517
Stercobilin, 314, 329
Stercorin, 329
Stereoscope, 841
Stereoscopic vision, 839
Sternutatories, 227
Stethograph, 213
Stigmata, 136
Stilling, canal of, 791
Stimuli, 519
adequate, 781
heterologous, 781
homologous, 781
muscular, 522
Stoffwechsel, 41
Stomach, 284
cancer of, 331
catarrh of, 331
changes in glands, 288
gases in, 297
glands of, 285, 286
movements of, 275
structure of, 284
Stomata, 182, 350
Stomodæum, 918
Storage albumin, 403
Strabismus, 771
Strangury, 486
Strassburg's test, 462
Striæ medullares, 767
Strobic disks, 830
Stroboscopic disks, 830
Stroma-fibrin and plasma-fibrin, 78
Stromuhr, 176
Struggle for existence, 947
Struma, 728
Strychnin, action of, 687
Stuttering, 573
Subarachnoid space, 776
fluid, 776
Subdural space, 776
Subjective sensations, 782
Sublingual gland, 258
Submaxillary ganglion, 647
atropin on, 257
gland, 253
saliva, 260
Substantia gelatinosa, 678
Successive beats, 868
contrast, 832
light-induction, 832
Succinic acid, 454
Succus entericus, 323
action of drugs on, 323
Suction, 267
Sudorifics, 495
Sugars, 435
estimation of, 265
tests for, 264

Sulphindigotate of soda, 472
Summation of stimuli, 534, 687
Summational tones, 869
Superfecundation, 912
Superficial reflexes, 691
Superfœtation, 912
Superior maxillary nerve, 644
Supplemental air, 210
Supra-renal capsules, 200
Surditas verbalis, 763
Suture, secondary, 590
Sutures, 549
Swallowing fluids, 719
Sweat, 494
  chemical composition, 494
  conditions influencing secretion, 495
  excretion of substances by, 495
  glands, 492
  insensible, 494
  nerves, 496
  pathological variations of, 497
Sweat centre, 496, 497, 731
  spinal, 730
Swimming, 559
Sympathetic ganglion, 671
  nerve, 670
  section of, 673, 726
  stimulation of, 673, 726
Symphyses, 549
Synchondroses, 549
Syncope, 102
Synergetic muscles, 552
Synovia, 548
Syntonin, 292, 425
Systole, cardiac, 98

Tabes, 697
Taches cerebrales. 728
Tactile areas, 764
  corpuscles, 880
  sensations, 881
  sensations, conduction of, 696
Tænia, 895
Tail-fold, 921
Talipes calcaneus, 553
  equinus, 553
  varus, 553
Tambour, Marey's, 142
Tapetum, 817
Tapping experiment, 718
Taste, centre for, 754
  organ of, 874
  testing, 876
Taste bulbs, 875
Taurin, 433
Taurocholic acid, 433
Tea, 400
  effects of, 264
Tears, 844
Tegmentum, 768
Telestereoscope, 841
Telolemma, 508
Temperature of animals, 366
  accommodation for, 381
  artificial increase of, 384
  estimation of, 366
  febrile, 383
  how influenced, 370
  lowering of, 386
  post-mortem, 385
  regulation of, 376
  topography of, 369
  variations of, 373
Temperature sense, 887
  illusions of, 889
Tendon, 506
  nerves of, 511, 881
  reflexes, 692
Tensor choroideæ, 801
  tympani, 853
Terminal arteries, 181
Testicle, descent of, 941
Testis, 896
Tetanomotor, 584
Tetanus, 534, 536, 586
  secondary, 609
Tetronerythrin, 79
Theobromin, 400
Thermal centre, 376
  nerves, 376
Thermo-electric methods, 367
  needles, 368
Thermogenesis, 364
Thermometer, 366
  clinical, 366
  maximal and minimal, 366
  metastatic, 368
  outflow, 367
Thermometry, 366
Thirst, 403
Thiry's fistula, 322
Thomsen's disease, 533
Thoracometer, 220
Thrombosis, 74
Thymus, 197
  development of, 932
Thyroid, 198
  development of, 932
Tidal air, 210
  wave, 145
Timbre, 569, 571, 861
Time in psychical processes, 735
Time sense, 863
Tinnitus, 655
Tissue formers, 403
  metabolism of, 405
  regeneration of, 406
Tizzoni's reaction, 309
Tobin's tubes, 245
Tomes, fibres of, 268
Tone inductorium, 537
Tones, 863
Tongue, glands of, 250
  movements of, 271
  nerves of, 272
  taste bulbs of, 875
Tonometer, 123
Tonsils, 251
Tonus, 694
Tooth, 268
  action of drugs on, 271
  chemistry of, 269
  development of, 270
  eruption of, 270, 271
  permanent, 271
  pulp of, 268
  structure of, 268
  temporary, 270
Topography, cerebral, 756, 764
Toricelli's theorem, 132
Torpedo, 629
Torticollis, 664
Touch corpuscles, 878
Touch, sense of, 878
Trachea, 203
Transfusion, 189
  of blood, 189
  of other fluids, 191
Transitional epithelium, 480
Transplantation of tissues, 419
Transudations, 360
Trapezius, spasm of, 664
Traube-Hering curves, 168
Traumatic degeneration of nerves, 589
Trehalose, 431
Trichina, 895
Trigeminus, 640
  ganglia of, 641, 645, 646, 647
  inferior maxillary branch, 645
  neuralgia of, 648
  ophthalmic branch, 641
  paralysis of, 649
  pathological, 648
  section of, 643, 648
  superior maxillary branch, 644
  trophic functions of, 643
Triple phosphate, 457
Trismus, 648
Trochlearis, 639
Trommer's test, 264
Tropæolin, 288
Trophic centres, 589
  fibres, 589
  nerves, 589, 632
Trophoneuroses, 632
Trotting, 558
Trypsin, 300
Trypsinogen, 300

Tryptone, 299
Tube casts, 466
Tubes, capillary, 134
division of, 134
elastic, 134
movements of fluids in, 134
rigid, 134
Tumultus sermonis, 761
Tunicin, 432
Turacin, 429
Türck's method, 691
Twins, 912
Twitch, 528
Tympanic membrane, 849
artificial, 851
Tyrosin, 300, 433, 465

Ulcer of foot, perforating, 632
Umbilical arteries, 924
cord, 927
veins, 924
vesicle, 921
Unipolar induction, 600
stimulation, 587
Upper tones, 863
Urachus, 924
Uræmia, 479
Urates, 448
Urea, 443
antecedents of, 445
compounds of, 445
decomposition of, 444
effect of exercise on, 444
ferment, 457
formation of, 445, 473, 474
nitrate of, 445
occurrence of, 445
oxalate of, 446
pathological, 445
phosphate of, 446
preparation of, 445
properties of, 443
qualitative estimation of, 446
quantitative estimation of, 446
quantity of, 444
relation of, to muscular work, 444
Ureameter, 446
Ureter, ligature of, 474
pressure in, 471
structure and functions of, 480
Uric acid, 447
diathesis, 480
formation of, 474
occurrence, 448
properties of, 447
qualitative estimation, 449
quantitative estimation of, 449
acid, quantity, 447
Uric acid, solubility, 448
tests for, 449
Urinary bladder, 481
calculi, 468
closure of, 483
deposits, 465
development of, 925
organs, 434
pressure in, 485
Urine, 440
accumulation of, 483
aceton in, 464
acid fermentation, 456
acidity, 443
albumin in, 457
alkaline fermentation, 457
alkaloids, 480
amount of solids, 441
bile in, 462
blood in, 460
calculi, 468
changes of in bladder, 485
characters of, 440
color, 441
coloring matters of, 452
consistence, 442
cystin in, 465
deposits in, 465
dextrin in, 464
effect of blood pressure on, 470
egg albumin in, 459
electrical condition of, 629
excretion of pigments by, 473
fermentations of, 456
ferments in, 454
fluorescence, 442
fungi in, 466
gases in, 456
globulin in, 459
hemi-albumose, 459
incontinence of, 486
influence of nerves on, 476
inorganic constituents, 454
inosit in, 464
leucin in, 465
milk-sugar in, 464
movement of, 481
mucin in, 442, 460
mucus in, 442, 460
organisms in, 465
passage of substances into, 475
peptone in, 459
phosphoric acid in, 455
physical characters of, 440
pigments of, 452
propeptone in, 459.
quantity, 440
Urine, reaction, 442
retention of, 486
secretion of, 469
silicic acid in, 456
sodic chloride in, 454
solids of, 441
specific gravity, 440
spontaneous changes in, 456
sugar in, 462
sulphuric acid in, 455
taste of, 442
taste for albumin in, 458
tube casts in, 466
tyrosin in, 465
Urinometer, 440
Urobilin, 67, 452
Urochrome, 452
Uroerythrin, 452
Uro-genital sinus, 942
Uromelanin, 452
Urorubin, 452
Urostealith, 468
Uterine milk, 927
Uterus, 905
development of, 940
involution of, 947
nerves of, 946
Utricle, 858
Uvea, 785

Vagotomy, 716
Vagus, 656
cardiac branches, 660
depressor nerve of, 167, 660
effect of section, 661
on heart, 169
pathological, 663
pneumonia after section, 661
reflex effects of, 662
stimulation of, 169, 719
unequal excitability of, 663
Valleix's points douloureux, 890
Valsalva's experiment, 129, 154
Valve, ileo-colic, 277
pyloric, 275
Valves of heart, 95
disease of, 111
injury to, 101
of veins, 136
sounds of, 185
Valvulæ conniventes, 336
Varicose fibres, 575
Varix, 172
Varnishing the skin, 387
Vas deferens, 897
Vasa vasorum, 137
Vascular system, development of, 934
Vaso dilator centre, 729
nerves, 729
Vaso-formative cells, 52

Vasomotor centre, 422
destruction of, 723
nerves, 722
spinal, 727
Vasomotor nerves, course of, 723
Vater's corpuscles, 879
Vegetable albumin, 425
casein, 425
foods, 397
preserved, 399
proteids, 425
Veins, 136
cardinal, 936
development of, 936
movement of blood in, 183
murmurs in, 185
pressure in, 171
pulse in, 185
structure of, 137
tonus of, 723
valves in, 137, 185
valvular sounds in, 185
varicose, 172
velocity of blood in, 183
Vella's fistula, 322
Velocity of blood stream, 132
Venous blood, 86
Ventilation, 245
Ventricles, 94, 108
aspiration, 99
brain, 776
capacity of, 161, 179
fibres of, 94
impulse of, 104
negative pressure in, 100
systole of, 100, 108
Veratrin, 532
Vernix caseosa, 494
Vertebræ, mobility of, 554
Vertebral column, 922
Vertigo, 655
Vestibular sacs, 859
Vibrations of body, 158
Vibratives, 572
Vibrio, 90
Villus, intestinal, 337
absorption by, 346
chorionic, 925
Villus, contractility of, 339
placental, 926
Violet-blindness, 828
Visceral arches, 923
clefts, 923
Vision, binocular, 837
stereoscopic, 839
Visual angle, 798
apparatus, 783
centre, 752, 763
purple, 789, 823
Vital capacity, 210
Vitellin, 424
Vitelline duct, 921
Vitreous humor, 791
Vocal cords, 559
conditions influencing the, 568
Voice, 509
falsetto, 568
in animals, 574
pathological variations of, 573
physics of, 560
pitch of, 560
production of, 569
range of, 569
Volume pulse, 188
Volumetric method, 447
Vomiting, 276
centre for, 276, 711
Vowels, 570
analysis of, 570, 864
artificial, 864
formation of, 570
Kœnig's apparatus for, 867

Wagner's corpuscles, 878
Waking, 735
Walking, 555
Wallerian law of degeneration, 589
Wandering cells, 349
Warm-blooded animals, 365
Washed blood clot, 74
Water, 388, 421
absorbed by skin, 498
absorption of, 344
exhaled by skin, 238, 492
Water, exhaled from lungs, 232
hardness of, 389
impurities, 388
in urine, 440
vapor of, in air, 231
Wave pulse, 145
propagation of, 154
Wave motion, 134
Wave movements, 848
Waves, in elastic tubes, 156
Weber's paradox, 543
law, 782
Weigert's method, 579
Weight, 419
Weyl's test, 449
Wharton's jelly, 927
Whispering, 570
White of egg, 423
Wine, 401
Wolffian bodies, 940
ducts, 940
Word blindness, 761
Word deafness, 754, 761
Work, 539
unit of, 36

Xanthin, 450
Xanthokyanopy, 828
Xanthophane, 990
Xanthoproteic reaction, 423
Xerosis, 644

Yawning, 227
Yeast, 428
Yelk, 904
cleavage of, 914
sac, 921
Yellow spot, 814
Young-Helmholtz theory, 826

Zero temperature, 888
Zimmermann, blood particles of, 58
Zinn, zonule of, 790
Zoetrope, 830
Zöllner's lines, 843
Zona pellucida, 901
Zooglœa, 325
Zymogen, 300

CLASSIFIED LIST, WITH PRICES,

OF ALL BOOKS PUBLISHED BY

P. BLAKISTON, SON & CO., PHILADELPHIA.

When the price is not given below, the book is out of print or about to be published.
Cloth binding, unless otherwise specified. For full descriptions of each book, see following Catalogue.

ANÆSTHETICS.

Buxton. Anæsthetics. - $1.25
Sansom. Chloroform. - 1.25
Turnbull. 3d Ed. - 3.00

ANATOMY.

Ballou. Veterinary Anat. 1.00
Heath. Practical. 7th Ed. 5.00
Holden. Dissector. Oil-cloth, 4.50
—— Osteology. - - 6.00
—— Landmarks. 4th Ed. 1.25
Macalister's Text-Book. 816 Illus. Clo. 7.50; Sh. 8.50
Potter. Compend of. 4th Ed. 117 Illustrations. - 1.00
Sutton. Ligaments. - 1.25

ATLASES AND DIAGRAMS.

Bentley & Trimens. - 90.00
Flower. Of Nerves. - 3.50
Heath. Operative Surgery. 12.00
Marshall's Phys. and Anat. Diagrams. $40.00 and 60.00
Savage. Pelvic Organs. 12.00

BRAIN AND INSANITY.

Bucknill and Tuke. Psychological Medicine. - - 8.00
Gowers. Diagnosis of Diseases of the Brain. New Ed. 2.00
Lewis, (Bevan). Mental Diseases. - - - 6.00
Mann's Psychological Med. 5.00
Wood. Brain and Overwork. .50

CHEMISTRY.

See Technological Books.

Allen. Commercial Organic Analysis. 2d Ed. Volume I. 4.50
—— Volume II. - - 5.00
—— Volume III. Part I. 4.50
Bartley. Medical. - 2.50
Bloxam's Text-Book. 7th Ed. 4.50
Bowman's Practical. - 2.00
Groves and Thorp. Chemical Technology. Vol. I. Fuels 7.50
Holland's Urine, Poisons and Milk - - - - 1.00
Leffmann's New Compend. 1.00
Müter. Pract. and Anal. 2.00
Richter's Inorganic. 3d Ed. 2.00
—— Organic. - - 3.00
Smith. Electro-Chem. Anal. ——
Stammer. Problems. - .75
Sutton. Volumetric Anal. 5.00
Symonds. Manual of. 2.00
Tidy. Modern Chem. 2d Ed. 5.50
Trimble. Analytical. - 1.50
Valentin. Qualt. Anal. 7th Ed. 3.00
Watts. (Fowne's) Inorg. 2.25
—— (Fowne's) Organ. 2.25
Wolff. Applied Medical. 1.00
Woody. Essentials of.

CHILDREN.

Chavasse. Mental Culture of. 1.00
Day. Diseases of. - - 3.00
Dillnberger. Women and. 1.50
Goodhart and Starr. 3.00; Sh. 3.50
Hale. Care of. - .75
Hatfield. Compend of. 1.00
Hillier. Diseases of. - 1.25
Meigs. Infant Feeding and Milk Analysis. - 1.00
Meigs and Pepper's Treatise. 5.00
Money. Treatment of. - 3.00
Osler. Cerebral Palsies of. 2.00
Smith. Wasting Diseases of. 3.00
—— Clinical Studies. - 2.50
Starr. Digestive Organs of. 2.50
—— Hygiene of the Nursery. 1.00

CLINICAL CHARTS.

Davis. Obstetrical. Pads, $ .50
Griffiths. Graphic. " .50
Temperature Charts. " .50

COMPENDS

And The Quiz-Compends.

Ballou. Veterinary Anat. 1.00
Brubaker's Physiol. 5th Ed. 1.00
Fox and Gould. The Eye. 1.00
Hatfield. Children. - 1.00
Horwitz. Surgery. 3d Ed. 1.00
Hughes. Practice. 2 Pts. Ea. 1.00
Landis. Obstetrics. 4th Ed. 1.00
Leffmann's Chemistry. 3d Ed. 1.00
Mason. Electricity. - 1.00
Morris. Gynæcology. - 1.00
Potter's Anatomy. 4th Ed. 1.00
—— Materia Medica. 5th Ed. 1.00
Roberts. Mat. Med. and Phar. 2.00
Stewart, Pharmacy. 2d Ed. 1.00
Warren. Dentistry. - 1.00

DEFORMITIES.

Churchill. Face and Foot. 3.50
Coles. Of Mouth. - 4.50
Prince. Orthopædics. - 4.50
Reeves. " - 2.25
Roberts. Club-foot. - .50
——Noses. - .50

DENTISTRY.

Barrett. Dental Surg. - 1.25
Blodgett. Dental Pathology. 1.75
Flagg. Plastic Filling. - 4.00
Fillebrown. Op. Dent. Illus. 2.50
Gorgas. Dental Medicine. 3.50
Harris. Principles and Prac. 7.00
—— Dictionary of. - 6.50
Heath. Dis. of Jaws. - 4.50
—— Lectures on Jaws. Bds. 1.00
Leber and Rottenstein. Caries. Paper 75; Cloth 1.25
Richardson. Mech. Dent. 4.50
Sewell. Dental Surg. - ——
Stocken. Materia Medica. 2.50
Taft. Operative Dentistry. 4.25
——, Index of Dental Lit. 2.00
Talbot. Irregularity of Teeth. 3.00
Tomes. Dental Surgery. 5.00
—— Dental Anatomy. 4.00
Warren's Compend of. - 1.00
White. Mouth and Teeth. .50

DICTIONARIES.

Cleveland's Pocket Medical. .75
Gould's New Medl. ½ Lea., 3.25; ½ M. Thumb Index 4.25
Harris' Dental. Clo. 6.50; Shp. 7.50
Longley's Pronouncing - 1.00
Maxwell. Terminologia Medica Polyglotta. - - 4.00
Treves. German English. 3.75

DIRECTORY.

Medical, of Philadelphia, 2.50

EAR.

Burnett. Hearing, etc. .50
Jones. Aural Surgery. - 2.75
Pritchard. Diseases of. 1.50

ELECTRICITY.

Althaus' Text Book. - 6.00
Mason's Compend. - 1.00

EYE.

Arlt. Diseases of. - - 2.50
Fox and Gould. Compend. 1.00
Gower's Ophthalmoscopy. ——
Harlan. Eyesight. - .50
Hartridge. Refraction. 3d Ed. 2.00
Higgins. Practical Manual. 1.75
—— Handbook, .50
Liebreich. Atlas of Ophth. 15.00
Macnamara. Diseases of. $4.00
Meyer and Fergus. Complete Text-Book, with Colored Plates. 270 Illus. Clo. 4.50; Sh. 5.50
Morton. Refraction. 3d Ed. 1.00
Ophthalmic Review. Monthly. - 3.00

FEVERS.

Collie, On Fevers. - 1.50
Welch. Enteric Fever. 2.00

HEADACHES.

Day. Their Treatment, etc. 1.25

HEALTH AND DOMESTIC MEDICINE.

Bulkley. The Skin. - .50
Burnett. Hearing. - .50
Cohen. Throat and Voice. .50
Dulles. Emergencies. 3d Ed. .75
Harlan. Eyesight. - .50
Hartshorne. Our Homes. .50
Hufeland. Long Life. - 1.00
Lincoln. Hygiene. - .50
Osgood. Dangers of Winter. .50
Packard. Sea Air, etc. .50
Richardson's Long Life. .50
Tanner. On Poisons. - .75
White. Mouth and Teeth. .50
Wilson. Summer and its Dis. .50
Wilson's Domestic Hygiene. 1.00
Wood. Brain Work. - .50

HEART.

Fothergill. Diseases of. 3.50
Sansom. Diseases of. - 1.25

HISTOLOGY.

See Microscope and Pathology.

HYGIENE.

Frankland. Water Analysis. 1.00
Fox. Water, Air, Food. 4.00
Lincoln. School Hygiene. .50
Parke's (E.) Hygiene. 7th Ed. 4.50
—— (L. C.), Manual. 2.50
Starr. Hygiene of the Nursery. 1.00
Wilson's Handbook of. - 2.75
—— Domestic. - - 1.00

JOURNALS, ETC.

Archives of Surgery. 4 Nos. 3.00
Jl. of Laryngology. 12 " 3.00
Jl. of Dermatology. " " 3.00
Ophthalmic Review. " " 3.00
New Sydenham Society's Publications - - - 3.00

KIDNEY DISEASES.

Beale. Renal and Urin. 1.75
Edwards. How to Live with Bright's Disease. - - .50
Greenhow. Addison's Dis. 3.00
Ralfe. Dis. of Kidney, etc. 2.75
Tyson. Bright's Disease and Diabetes, Illus. - 3.50

LIVER.

Habershon. Diseases of. 1.50
Harley. Diseases of. - 3.00

LUNGS AND CHEST.

See Phy. Diagnosis and Throat.

Hare. Mediastinal Disease. 2.00
Harris. On the Chest. - 2.50
Williams. Consumption. 5.00

MATERIA MEDICA.

Biddle. 11th Ed. Clo. 4.25; Sheep, - - - - 5.00
Gorgas. Dental. 3d Ed. 3.50
Merrell's Digest. - 4.00
Potter's Compend of. 5th Ed. 1.00
—— Handbook of. Second Ed. Clo. 4.00; Sheep, - 5.00
Roberts' Compend of. 1.00

MEDICAL JURISPRUDENCE.

Reese. Medical Jurisprudence & Toxicology, 2d Ed 3.00; Sh 3.50
Woodman and Tidy's Treatise, including Toxicology. 7.50

MICROSCOPE.

Beale. How to Work with. 7.50
—— In Medicine. - 7.50
Carpenter. The Microscope. ——
Lee Vade Mecum of. 2d Ed. 4.00
MacDonald. Examination of Water by. - - - 2.75
Wythe. The Microscopist. 3.00

MISCELLANEOUS.

Burdett. Hospitals. - 2.25
Beale. Life Theories, etc. 2.00
—— Slight Ailments. 1.25
—— Bioplasm. - - 2.25
—— Life and Vital Action. 2.00
Black. Micro-organisms. 1.50
Crookshank. Vaccination. 8.50
Davis. Text-book of Biology. 4.00
Duckworth. On Gout. - 7.00
Edwards. Vaccination. .50
Garrod. Rheumatism, etc. 6.00
Gross. Life of John Hunter. 1.25
Haddon. Embryology. - 6.00
Henry. Anæmia. - .75
Holden. The Sphygmograph. 2.00
Keating. Life Insurance. *Net*, 2.00
MacMunn. The Spectroscope 3.00
Madden. Health Resorts. 2.50
Smythe. Med'l Heresies. 1.25

MASSAGE.

Murrell. Massage. 5th Ed. 1.50
Ostrom. Massage. Illus. .75

NERVOUS DISEASES, Etc.

Flower. Atlas of Nerves. 3.50
Bowlby. Injuries of. - 4.50
Gowers. Manual of. 1 vol. 341 Illustrations. - 6.50
—— Dis. of Spinal Cord. ——
—— Diseases of Brain. 2.00
—— Syphilis and the Nervous System. - - ——
Obersteiner. Central Nervous System. - - - - - ——
Osler. Cerebral Palsies. 2.00
Page. Injuries of Spine. ——
Radcliffe. Epilepsy, Pain, etc. 1.25
Thorburn. Surgery of the Spinal Cord - - - 4.50
Watson. Concussions. 1.00

NURSING.

Cullingworth. Manual of. 1.00
—— Monthly Nursing. .50
Domville's Manual. 6th Ed. .75
Fullerton. Obst. Nursing. 1.25
Humphrey. Manual of 1.25
Luckes. Hospital Sisters. 1.00
Parvin. Obstetric Nursing. .75
Starr. Hygiene of the Nursery. 1.00
Temperature Charts. - .50

OBSTETRICS.

Bar. Antiseptic Obstet. 1.75
Barnes. Obstetric Operations. 3.75
Cazeaux and Tarnier. Students' Ed. Colored Plates. 5.00
Davis. Obstetrcial Chart. .50
Galabin's Manual of. 3.00
Glisan's Text-book. 2d Ed. 4.00
Landis. Compend 4th Ed. 1.00
Meadows. Manual. - 2.00
Rigby. Obstetric Mem. .50
Strahan. Extra-Uterine Preg. 1.50
Tyler Smith's Treatise. 4.00
Swayne's Aphorisms 9th Ed. 1.25
Winckel's Text-book. 6.00

PATHOLOGY & HISTOLOGY.

Blodgett. Dental Pathology 1.75
Bowlby. Surgical Path. 2.00
Gibbes. Practical. - 1.75
Gilliam. Essentials of. - 2.00
Stirling's Practical. - 4.00
Virchow. Post-mortems. 1.00
—— Cellular Pathology. 4.00
Wynter & Withered. Path. 4.00

PHARMACY.

Beasley's Druggists' Rec'ts. $2.25
—— Formulary. - - 2.25
Flückiger. Cinchona Barks. 1.50
Kirby. Pharm. of Remedies. 2.25
Mackenzie. Phar. of Throat. 1.25
Merrell's Digest. - - 4.00
Proctor. Practical Pharm. 4.50
Robinson. Latin Grammar of. ——
Stewart's Compend. 2d Ed. 1.00
Tuson. Veterinary Pharm. 2.50

PHYSIOLOGY.

Beale's Bioplasm. - - 2.25
Brubaker's Compend. Illustrated. 4th Ed. - - 1.00
Kirkes' 12th Ed. (Author's Ed.) Cloth, 4.00; Sheep, 5.00
Landois' Text-book. 583 Illustrations. 2d Ed. - - 6.50
Sanderson's Laboratory B'k. 5.00
Sterling. Practical Phys. 2.25
Tyson's Cell Doctrine. - 2.00
Yeo's Manual. 321 Illustrations 3d Ed. Cloth, 3.00; Sheep, 3.50

POISONS.

Aitken. The Ptomaines, etc. 1.25
Black. Formation of. - 1.50
Reese. Toxicology. 2d Ed. 3.00
Tanner. Memoranda of. .75

PRACTICE.

Beale. Slight Ailments. 1.25
Fagge's Practice. 2 Vols. 8.00
Fenwick's Outlines of. - 1.25
Fowler's Dictionary of.
Hughes. Compend of. 2 Pts. 2.00
—— Physicians' Edition. 1 Vol. Morocco, Gilt edge. 2.50
Roberts. Text-book. 7th Ed. 5.50
Tanner's Index of Diseases. 3.00
Taylor's Manual of. - 4.00
Warner's Case Taking. 1.75

PRESCRIPTION BOOKS.

Beasley's 3000 Prescriptions. 2.25
—— Receipt Book. - 2.25
—— Formulary. - - 2.25
Pereira's Pocket-book. 1.00
Wythe's Dose and Symptom Book. 17th Ed. - - 1.00

SKIN AND HAIR.

Anderson's Text-Book. 4.50
Bulkley. The Skin. - .50
Crocker. Dis. of Skin. Illus. 5.50
Van Harlingen. Diagnosis and Treatment of Skin Dis. Col. Plates & Engravings. 2.50

STIMULANTS & NARCOTICS.

Lizars. On Tobacco. - .50
Miller. On Alcohol .50
Parrish. Inebriety. - 1.25

SURGERY AND SURGICAL DISEASES.

Caird and Cathcart. Surgical Handbook. Leather, 2.50
Dulles. Emergencies. - .75
Gamgee. Wounds. - 3.50
Heath's Operative. - 12.00
—— Minor. 9th Ed. - 2.00
—— Diseases of Jaws. 4.50
—— Lectures on Jaws. 1.00
Horwitz. Compend. 3d Ed. 1.00
Jacobson. Operations of. - 5.00
Porter's Surgeon's Pocket-book. - - Leather. 2.25
Roberts. (A. S.) Club-Foot. .50
—— (A. S.) Bow-Legs. .50
Smith. Abdominal Surg. 7.00
Swain. Surg. Emergencies. 1.50
Walsham. Practical Surg. 3.00
Watson's Amputations. 5.50

TECHNOLOGICAL BOOKS.

See also Chemistry.

Cameron. Oils & Varnishes. 2.50
—— Soap and Candles. 2.25
Gardner. Brewing, etc. 1.75
Gardner. Acetic Acid, etc. 1.75
—— Bleaching & Dyeing. 1.75
Groves and Thorp. Chemical Technology. Vol. I. Mills on Fuels. Cl. 7.50; ½M. 9.00
Overman. Mineralogy. $1.00
Piggott. On Copper. - 1.00

THERAPEUTICS.

Biddle. 11th Ed. Cl. 4.25; Sh. 5.00
Cohen. Inhalations. - 1.25
Field. Cathartics and Emetics. 1.75
Headland. Action of Med. 3.00
Kirby. Selected Remedies. 2.25
Mays. Therap. Forces. 1.25
—— Theine - - - 50
Ott. Action of Medicines. 2.00
Potter's Compend. 5th Ed. 1.00
——, Handbook of. 4.00; Sh. 5.00
Starr, Walker and Powell. Phys. Action of Medicines. .75
Waring's Practical. 4th Ed. 3.00

THROAT AND NOSE.

Cohen. Throat and Voice. .50
—— Inhalations. - 1.25
Greenhow. Bronchitis. 1.25
James. Sore Throat - - 1.25
Journal of Laryngology. 3.00
Mackenzie. The Œsophagus, Naso-Pharynx, etc. - 3.00
—— Pharmacopœia. - 1.25
Murrell. Bronchitis. - 1.50
Potter. Stammering, etc. 1.00
Woakes. Post-Nasal Catarrh. 1.50
—— Nasal Polypus, etc. 1.25
—— Deafness, Giddiness, etc. ——

TRANSACTIONS AND REPORTS.

Penna. Hospital Reports. 1.25
Power and Holmes' Reports. 1.25
Trans. College of Physicians. 3.50
—— Amer. Surg. Assoc. 3.00
—— **Assoc. Amer. Phys.** 3.50

URINE & URINARY ORGANS.

Acton. Repro. Organs. 2.00
Beale. Urin. & Renal Dis. 1.75
—— Urin. Deposits. Plates. 2.00
Holland. The Urine and Common Poisons. 3d Ed. - 1.00
Legg. On Urine. - - .75
MacMunn. Chem. of Urine, 3.00
Marshall and Smith. Urine. 1.00
Ralfe. Kidney and Uri. Org. 2.75
Schnée. Diabetes. - 2.00
Thompson. Urinary Organs. 3.50
—— Surg. of Urin. Organs. 1.25
—— Calculous Dis. 3d. Ed. 1.00
—— Lithotomy. - - 3.50
—— Prostate. 6th Ed. 2.00
Thornton. Surg. of Kidney. 1.75
Tyson. Exam. of Urine. 1.50
Van Nüys. Urine Analysis. 2.00

VENEREAL DISEASES.

Cooper. Syphilis. - - 3.50
Durkee. Gonorrhœa. - 3.50
Hill and Cooper's Manual. 1.00
Lewin. Syphilis. Pa 75; Clo. 1.25

VISITING LISTS.

Lindsay and Blakiston's Regular Edition. *Send for Circular.* - - 1.00 to 3.00
—— Perpetual Edition. 1.25
—— Monthly Ed. Plain, .75; Tucks, 1.00

WATER.

Fox. Water, Air, Food. 4.00
Frankland. Analysis of. 1.00
Leffmann & Beam. Exam. of. 1.25
MacDonald. Analysis of. 2.75

WOMEN, DISEASES OF.

Byford's Text-book. 4th Ed. 5.00
—— Uterus. - - - 1.25
Dillnberger. and Children. 1.50
Doran. Gynæc. Operations. 4.50
Hodge. Tumors. Note Book .50
Lewers. Dis. of Women. 2.25
Morris. Compend. - 1.00
Scanzoni. Sexual Organs of. 4.00
Tilt. Change of Life. - 1.25
Winckel, by Parvin. Manual of. Illus. Clo., 3.00; Sh. 3.50

FROM PROF. J. M. DACOSTA.
"I find it an excellent work, doing credit to the learning and discrimination of the author."

A NEW MEDICAL DICTIONARY.

Small 8vo, Half Morocco, as above, with Thumb Index, ... $4.25
Plain Dark Leather, without Thumb Index, 3.25

A compact, concise Vocabulary, including all the Words and Phrases used in medicine, with their proper Pronunciation and Definitions.

BASED ON RECENT MEDICAL LITERATURE.

BY

GEORGE M. GOULD, A.B., M.D.,

Ophthalmic Surgeon to the Philadelphia Hospital, Clinical Chief Ophthalmological Dept. German Hospital, Philadelphia.

It is not a mere compilation from other dictionaries. The definitions have been made by the aid of the most recent standard text-books in the various branches of medicine. It includes

SEVERAL THOUSAND NEW WORDS NOT CONTAINED IN ANY SIMILAR WORK.

IT CONTAINS TABLES of the **ABBREVIATIONS** used in Medicine, of the **ARTERIES**, of the **BACILLI**, giving the Name, Habitat, Characteristics, etc.; of **GANGLIA, LEUCOMAÏNES, MICROCOCCI, MUSCLES, NERVES, PLEXUSES, PTOMAÏNES**, with the Name, Formula, Physiological Action, etc.; and the **COMPARISON OF THERMOMETERS**, of all the most used **WEIGHTS AND MEASURES** of the world, of the **MINERAL SPRINGS OF THE U. S., VITAL STATISTICS**, etc. Much of the material thus classified is not obtainable by English readers in any other work.

OPINIONS OF PROMINENT MEDICAL TEACHERS.

"The compact size of this dictionary, its clear type, and its accuracy are unfailing pointers to its coming popularity."—*John B. Hamilton, Supervising Surgeon-General U. S. Marine Hospital Service, Washington.*

"It is certainly as convenient and as useful a volume as can be found, regarding contents as well as arrangement."—*Julius Pohlman, Prof. of Physiology, Medical Dept., Univ. of Buffalo.*

"I have examined it with considerable care, and am very much pleased with it. It is a handy book for reference, and so far as I have examined it, it is accurate in every particular."—*E. H. Bartley, Prof. of Chemistry, Long Island College Hospital, Brooklyn.*

"I consider this *the* dictionary of all others for the medical student, and shall see that it is placed on our list of text-books."—*A. R. Thomas, M.D., Dean Hahnemann Medl. Col., Philadelphia.*

"It will be recommended among our text-books in our new catalogue."—*S. E. Chaillé, M.D., Dean Medl. Dept., Tulane Univ., New Orleans.*

"Compact, exact, up to date, and the tables are most excellent and instructive. I prefer it to the larger and older books."—*Prof. C. B. Parker, Medl. Dept., Western Reserve Univ., Cleveland.*

"I have given your 'New Medical Dictionary' a critical examination. Its size has made it convenient to the study table and handy for frequent use. At the same time it is comprehensive as to the number of words, including those of the latest coinage, and concise in its definitions. The etymology and accentuation materially enhance its value, and help to make it worthy a place with the classical books of reference for medical students."—*J. W. Holland, M.D., Dean Jefferson Medl. Col., Phila.*

☞ May be obtained through all Booksellers. Sample pages free.

P. BLAKISTON, SON & CO.'S

Medical and Scientific Publications,

No. 1012 WALNUT ST., PHILADELPHIA.

ACTON. The Functions and Disorders of the Reproductive Organs in Childhood, Youth, Adult Age and Advanced Life, considered in their Physiological, Social and Moral Relations. By WM. ACTON, M.D., M.R.C.S. 7th Edition. Cloth, $2.00

AITKEN. Animal Alkaloids, the Ptomaines, Leucomaines and Extractives in their Pathological Relations. A short summary of recent researches as to the origin of some diseases by or through the physiological processes going on during life. By WILLIAM AITKEN, M.D., F.R.S., Professor of Pathology in the Army Medical School, Netley, England. 2nd Ed. Enlarged. Cloth, $1.25

ALLEN. Commercial Organic Analysis. A Treatise on the Modes of Assaying the Various Organic Chemicals and Products employed in the Arts, Manufactures, Medicine, etc., with Concise Methods for the Detection of Impurities, Adulterations, etc. Second Edition. Revised and Enlarged. By ALFRED ALLEN, F.C.S.

Vol. I. Alcohols, Ethers, Vegetable Acids, Starch and its Isomers. etc. *Out of Print.*

Vol. II. Fixed Oils and Fats, Hydrocarbons and Mineral Oils, Phenols and their Derivatives, Coloring Matters, etc. *Out of Print.*

Vol. III.—Part I. Acid Derivatives of Phenols, Aromatic Acids, Tannins, Dyes, and Coloring Matters. 8vo. Cloth, $4.50

ANDERSON. A Treatise on Skin Diseases. With special reference to Diagnosis and Treatment, and including an Analysis of 11,000 consecutive cases. By T. MCCALL ANDERSON, M.D., Professor of Clinical Medicine, University of Glasgow. With several Full-page Plates, two of which are Colored Lithographs, and numerous Wood Engravings. Octavo. 650 pages. Cloth, $4.50; Leather, $5.50

ARCHIVES OF SURGERY. Edited by JONATHAN HUTCHINSON, F.R.S. Colored Illustrations. Published Quarterly. Per Vol., $3.00

ARLT. Diseases of the Eye. Clinical Studies on Diseases of the Eye. Including the Conjunctiva, Cornea and Sclerotic, Iris and Ciliary Body. By Dr. FERD. RITTER VON ARLT, University of Vienna. Authorized Translation by LYMAN WARE, M.D., Surgeon to the Illinois Charitable Eye and Ear Infirmary, Chicago. Illustrated. 8vo. Cloth, $2.50

BALLOU. Veterinary Anatomy and Physiology. By WM. R. BALLOU, M.D., Prof. of Equine Anatomy, New York College of Veterinary Surgeons, Physician to Bellevue Dispensary, and Lecturer on Genito-Urinary Surgery, New York Polyclinic, etc. With 29 Graphic Illustrations. 12mo. *No. 12 ? Quiz-Compend Series. ?* Cloth, $1.00. Interleaved, for the addition of notes, $1.25

BAR. Antiseptic Midwifery. The Principles of Antiseptic Methods Applied to Obstetric Practice. By Dr. PAUL BAR, Obstetrician to, formerly Interne in, the Maternity Hospital, Paris. Authorized Translation by HENRY D. FRY, M.D. with an Appendix by the author. Octavo. Cloth, 1.75

BARNES. Lectures on Obstetric Operations, including the Treatment of Hemorrhage, and forming a Guide to Difficult Labor. By ROBERT BARNES, M.D., F.R.C.P. Fourth Edition. Illustrated. 8vo. Cloth, $3.75

BARRETT. Dental Surgery for General Practitioners and Students of Medicine and Dentistry. Extraction of Teeth, etc. By A. W. BARRETT, M.D. Second Edition. Illustrated *Practical Series.* [*See page 19.*] Cloth, $1.25

BARTLEY. Medical Chemistry. Second Edition. A Text-book for Medical and Pharmaceutical Students. By E. H. BARTLEY, M.D., Professor of Chemistry and Toxicology at the Long Island College Hospital; President of the American Society of Public Analysts; Chief Chemist, Board of Health, of Brooklyn, N.Y. Revised and enlarged. With 62 Illustrations. Glossary and Complete Index. 423 pages. 12mo. Cloth, $2.50

BEALE. On Slight Ailments; their Nature and Treatment. By LIONEL S. BEALE, M.D., F.R.S., Professor of Practice, King's Medical College, London. Second Edition. Enlarged and Illustrated. 8vo. Cloth, $1.25

Urinary and Renal Diseases and Calculous Disorders. Hints on Diagnosis and Treatment. Demi-8vo. 356 pages. Cloth, $1.75

The Use of the Microscope in Practical Medicine. For Students and Practitioners, with full directions for examining the various secretions, etc., in the Microscope. Fourth Edition. 500 Illustrations. 8vo. Cloth, $7.50

How to Work with the Microscope. A Complete Manual of Microscopical Manipulation, containing a full description of many new processes of investigation, with directions for examining objects under the highest powers, and for taking photographs of microscopic objects. Fifth Edition. Containing over 400 Illustrations, many of them colored. 8vo. Cloth, $7.50

Bioplasm. A Contribution to the Physiology of Life, or an Introduction to the Study of Physiology and Medicine, for Students. Illus. Cloth, $2.25

Life Theories and Religious Thought. Six Colored Plates. Cloth, $2.00

On Life and Vital Action in Health and Disease. 12mo. Cloth, $2.00

One Hundred Urinary Deposits, on eight sheets, for the Hospital, Laboratory, or Surgery. New Edition. 4to. Paper, $2.00

BEASLEY'S Book of Prescriptions. Containing over 3100 Prescriptions, collected from the Practice of the most Eminent Physicians and Surgeons—English, French and American; a Compendious History of the Materia Medica, Lists of the Doses of all Officinal and Established Preparations, and an Index of Diseases and their Remedies. By HENRY BEASLEY. Sixth Edition. Cloth, $2.25

Druggists' General Receipt Book. Comprising a copious Veterinary Formulary; Recipes in Patent and Proprietary Medicines, Druggists' Nostrums, etc.; Perfumery and Cosmetics; Beverages, Dietetic Articles and Condiments; Trade Chemicals, Scientific Processes, and an Appendix of Useful Tables. Ninth Edition. Revised. Cloth, $2.25

Pocket Formulary and Synopsis of the British and Foreign Pharmacopœias. Comprising Standard and Approved Formulæ for the Preparations and Compounds Employed in Medical Practice. Eleventh Edition. Cloth, $2.25

BIDDLE'S Materia Medica and Therapeutics. Eleventh Edition. For the Use of Students and Physicians. By Prof. JOHN B. BIDDLE, M.D., Professor of Materia Medica in Jefferson Medical College, Philadelphia. The Eleventh Edition, thoroughly revised, and in many parts rewritten, by his son, CLEMENT BIDDLE, M.D., Assistant Surgeon, U. S. Navy, and HENRY MORRIS, M.D., Demonstrator of Obstetrics in Jefferson Medical College, Fellow of the College of Physicians, of Philadelphia, etc. Cloth, $4.25; Sheep, $5.00

BLACK. Micro-Organisms. The Formation of Poisons by Micro-Organisms. A Biological study of the Germ Theory of Disease. By G. V. BLACK, M.D., D.D.S. Cloth, $1.50

BLODGETT'S Dental Pathology. By ALBERT N. BLODGETT, M.D., Late Professor of Pathology and Therapeutics, Boston Dental College. 33 Illustrations. 12mo. Cloth, $1.75

BLOXAM. Chemistry, Inorganic and Organic. With Experiments. By CHARLES L. BLOXAM. Edited by J. M. THOMPSON, Professor of Chemistry in King's College, London, and A. G. BLOXAM, Dem. of Chem., Royal Agricultural College, Cirencester. Seventh Edition. Revised and Enlarged. With 330 Engravings. 8vo. Cloth, $4.50; Leather, $5.50

BOWLBY. Injuries and Diseases of the Nerves, and their surgical treatment. By ANTHONY A. BOWLBY, F.R.C.S., Surgical Registrar and Demonstrator of Practical Surgery at St. Bartholomew's Hospital. Illustrated by 4 Colored and 20 other full-page plates. 8vo. Cloth, $4.50

Surgical Pathology and Morbid Anatomy. 135 Illustrations. Cloth, $2.00

BOWMAN. Practical Chemistry, including analysis, with about 100 Illustrations. By Prof. JOHN E. BOWMAN. Eighth English Edition. Revised by Prof. BLOXAM, Professor of Chemistry, King's College, London. Cloth, $2.00

BRUBAKER. Physiology. A Compend of Physiology, specially adapted for the use of Students and Physicians. By A. P. BRUBAKER, M.D., Demonstrator of Physiology at Jefferson Medical College, Prof. of Physiology, Penn'a College of Dental Surgery, Philadelphia. Fifth Edition. Revised, Enlarged and Illustrated. *No. 4, ? Quiz-Compend Series ?* 12mo. Cloth, $1.00
Interleaved for the addition of notes, $1.25

BUCKNILL AND TUKE'S Manual of Psychological Medicine: containing the Lunacy Laws, the Nosology, Ætiology, Statistics, Description, Diagnosis, Pathology (including morbid Histology) and Treatment of Insanity. By JOHN CHARLES BUCKNILL, M.D., F.R.S., and DANIEL HACK TUKE, M.D., F.R.C.P. Fourth Edition. Numerous illustrations. 8vo. Cloth, $8.00

BULKLEY. The Skin in Health and Disease. By L. DUNCAN BULKLEY, M.D., Attending Physician at the New York Hospital. Illustrated. Cloth, .50

BUXTON. On Anæsthetics. A Manual. By DUDLEY WILMOT BUXTON, M.R.C.S., M.R.C.P., Asst. to Prof. of Med., and Administrator of Anæsthetics, University College Hospital, London. *Practical Series.* [*See page 19.*] Cloth, $1.25

BURNETT. Hearing, and How to Keep It. By CHAS. H. BURNETT, M.D., Prof. of Diseases of the Ear, at the Philadelphia Polyclinic. Illustrated. Cloth, .50

BYFORD. Diseases of Women. The Practice of Medicine and Surgery, as applied to the Diseases and Accidents Incident to Women. By W. H. BYFORD, A.M., M.D., Professor of Gynæcology in Rush Medical College and of Obstetrics in the Woman's Medical College; Surgeon to the Woman's Hospital; Ex-President American Gynæcological Society, etc., and HENRY T. BYFORD, M.D., Surgeon to the Woman's Hospital of Chicago; Gynæcologist to St. Luke's Hospital; President Chicago Gynæcological Society, etc. Fourth Edition. Revised, Rewritten and Enlarged. With 306 Illustrations, over 100 of which are original. Octavo. 832 pages. Cloth, $5.00; Leather, $6.00

On the Uterus. Chronic Inflammation and Displacement. Cloth, $1.25

CAIRD and CATHCART. Surgical Handbook for the use of Practitioners and Students. By F. MITCHELL CAIRD, M.B., F.R.C.S., and C. WALKER CATHCART, M.B., F.R.C.S., Asst. Surgeons Royal Infirmary. With over 200 Illustrations. 32mo. 400 pages. Pocket size. Leather covers, $2.50

CAMERON. Oils and Varnishes. A Practical Handbook, by JAMES CAMERON, F.I.C. With Illustrations, Formulæ, Tables, etc. 12mo. Cloth, $2.50

Soap and Candles. A New Handbook for Manufacturers, Chemists, Analysts, etc. Compiled from all reliable and recent sources. 54 Illustrations. 12mo. Cloth, 2.25

CARPENTER. The Microscope and Its Revelations. By W. B. CARPENTER, M.D., F.R.S. Seventh Edition. Revised and Enlarged, with over 500 Illustrations and Lithographs. *New Edition in Press.*

CAZEAUX and TARNIER'S Midwifery. With Appendix, by Mundé. Eighth Revised and Enlarged Edition. With Colored Plates and numerous other Illustrations. The Theory and Practice of Obstetrics; including the Diseases of Pregnancy and Parturition, Obstetrical Operations, etc. By P. CAZEAUX, Member of the Imperial Academy of Medicine, Adjunct Professor in the Faculty of Medicine in Paris. Remodeled and rearranged, with revisions and additions, by S. TARNIER, M.D., Professor of Obstetrics and Diseases of Women and Children in the Faculty of Medicine of Paris. Eighth American, from the Eighth French and First Italian Edition. Edited and Enlarged by ROBERT J. HESS, M.D., Physician to the Northern Dispensary, Phila., etc., with an Appendix by PAUL F. MUNDÉ, M.D., Professor of Gynæcology at the New York Polyclinic, and at Dartmouth College; Vice-President American Gynæcological Society, etc. Illustrated by Chromo-Lithographs, Lithographs, and other Full-page Plates, seven of which are beautifully colored, and numerous Wood Engravings. *Students' Edition.* One Vol., 8vo. Cloth, $5.00; Full Leather, $6.00

CHAVASSE. The Mental Culture and Training of Children. Cloth, $1.00

CHURCHILL. Face and Foot Deformities. By FRED. CHURCHILL, M.D., Ass't Surgeon to the Victoria Hospital for Sick Children, London. Six Plain and Two Colored Lithographs. 8vo. Cloth, $3.50

CLEVELAND'S Pocket Dictionary. A Pronouncing Medical Lexicon, containing correct Pronunciation and Definition of terms used in medicine and the collateral sciences, abbreviations used in prescriptions, list of poisons, their antidotes, etc. By C. H. CLEVELAND, M.D. Thirty-third Edition. Very small pocket size. Cloth, .75; Tucks with Pocket, $1.00

COHEN on Inhalation, its Therapeutics and Practice, including a Description of the Apparatus Employed, etc. By J. SOLIS-COHEN, M.D. Cl., $1.25

The Throat and Voice. Illustrated. 12mo. Cloth, .50

COLLIE, On Fevers. A Practical Treatise on Fevers, Their History, Etiology, Diagnosis, Prognosis and Treatment. By ALEXANDER COLLIE, M.D., M.R.C.P., Lond. With Colored Plates. *Practical Series. See Page 19.* Cloth, $2.50

COOPER on Syphilis and Pseudo-Syphilis. By ALFRED COOPER, F.R.C.S., Surgeon to West London Hospital. Octavo. Cloth, $3.50

CROOKSHANK. History and Pathology of Vaccination. In two volumes. Vol. I, a Critical Inquiry. Vol. II (Edited), Selected Essays. By EDGAR M. CROOKSHANK, M.B., Professor of Comparative Pathology and Bacteriology in King's College, London; Author of a "Manual of Bacteriology," etc. With 22 Colored Plates, Fac-simile Letters, etc., and other Illustrations. Royal 8vo. Over 1100 pages. Handsome Cloth, Gilt Top, $8.50

CROCKER. Diseases of the Skin. Their Description, Pathology, Diagnosis and Treatment. By H. RADCLIFFE CROCKER, M.D., Physician to the Dept. of Skin Dis. University College Hospital, London. With Illustrations. Cloth, $5.50

CULLINGWORTH. A Manual of Nursing, Medical and Surgical. By CHARLES J. CULLINGWORTH, M.D., Physician to St. Thomas' Hospital, London. Third Revised Edition. With 18 Illustrations. 12mo. Cloth, $1.00

A Manual for Monthly Nurses. Third Edition. 32mo. Cloth, .50

DAVIS. Biology. An Elementary Treatise. By J. R. AINSWORTH DAVIS, of University College, Aberystwyth, Wales. Thoroughly Illustrated. 12mo. $4.00

DAVIS. Obstetrical Chart. Designed by ED. P. DAVIS, M.D., and J. P. CROZER GRIFFITH, M.D. Sample copies free. Put up in loose packages of 50, $ .50 Price to Hospitals, 500 copies, $4.00; 1000 copies, $7.50. With name of Hospital printed on, 50 cents extra.

DAY. Diseases of Children. A Practical and Systematic Treatise for Practitioners and Students. By WM. H. DAY, M.D. Second Edition. Rewritten and very much Enlarged. 8vo. 752 pp. Price reduced. Cloth, $3.00; Sheep, $4.00

On Headaches. The Nature, Causes and Treatment of Headaches. Fourth Edition. Illustrated. 8vo. Paper, .75; Cloth, $1.25

DERMATOLOGY, Journal of. Edited by MALCOLM MORRIS, M.R.C.S. London, and D. G. BROOKE, M.R.C.S. Manchester, Eng. Monthly. Per Annum, $3.00

DILLNBERGER. On Women and Children. The Treatment of the Diseases Peculiar to Women and Children. By Dr. EMIL DILLNBERGER. 12mo. Cloth, $1.50

DOMVILLE. Manual for Nurses and others engaged in attending to the sick. By ED. J. DOMVILLE, M.D. Sixth Ed. With Recipes for Sick-room Cookery, etc. Cloth, .75

DORAN. Gynæcological Operations. A Handbook. By ALBAN DORAN, F.R.C.S., Asst. Surg. to the Samaritan Free Hospital for Women and Children, London. 166 Illustrations. 8vo. Cloth, $4.50

DUCKWORTH. On Gout. Illustrated. A treatise on Gout. By SIR DYCE DUCKWORTH, M.D. (Edin.), F.R.C.P., Physician to, and Lecturer on Clinical Medicine at, St. Bartholomew's Hospital, London. With Chromo-lithographs and Engravings. Octavo. Cloth, $7.00

DULLES. What to Do First, In Accidents and Poisoning. By C. W. DULLES, M.D. Third Edition, Enlarged, with new Illustrations. Cloth, .75

DURKEE, On Gonorrhœa and Syphilis. By SILAS DURKEE, M.D. Sixth Edition. Revised and Enlarged, with Portrait and Eight Colored Illustrations. Cloth, $3.50

EDWARDS. Bright's Disease. How a Person Affected with Bright's Disease Ought to Live. By JOS. F. EDWARDS, M.D. 2d Ed. Reduced to Cloth, .50

Vaccination and Smallpox. Showing the Reasons in favor of Vaccination, and the Fallacy of the Arguments advanced against it, with Hints on the Management and Care of Smallpox patients. Cloth, .50

FAGGE. The Principles and Practice of Medicine. By C. HILTON FAGGE, M.D., F.R.C.P., F R.M.C.S., Examiner in Medicine, University of London; Physician to, and Lecturer on Pathology in, Guy's Hospital; Senior Physician to Evelina Hospital for Sick Children, etc. Arranged for the press by PHILIP H. PYE SMITH, M.D., Lect. on Medicine in Guy's Hospital. Including a section on Cutaneous Affections, by the Editor; Chapter on Cardiac Diseases, by SAMUEL WILKES, M.D., F.R.S., and Complete Indexes by ROBERT EDMUND CARRINGTON. 2 vols. Royal 8vo. Cloth, $8.00; Leather, $10.00; Half Russia, $12.00.

FENWICK'S Outlines of Practice of Medicine. With Formulæ and Illustrations. By SAMUEL FENWICK, M.D. 12mo. Cloth, $1.25

FIELD. Evacuant Medication—Cathartics and Emetics. By HENRY M. FIELD, M.D., Professor of Therapeutics, Dartmouth Medical College, Corporate Member Gynæcological Society of Boston, etc. 12mo. 288 pp. Cloth, $1.75

FILLEBROWN. A Text-Book of Operative Dentistry. Written by invitation of the National Association of Dental Faculties. By THOMAS FILLEBROWN, M.D., D.M.D., Professor of Operative Dentistry in the Dental School of Harvard University; Member of the American Dental Assoc., etc. Illus. 8vo. Clo., $2.50

FLAGG. Plastics and Plastic Fillings, as pertaining to the filling of all Cavities of Decay in Teeth below medium in structure, and to difficult and inaccessible cavities in teeth of all grades of structure. By J. FOSTER FLAGG, D.D.S., Professor of Dental Pathology in Philadelphia Dental College. Third Revised Edition. With many Illustrations. 8vo. Cloth, $4.00

FLOWER'S Diagrams of the Nerves of the Human Body. Exhibiting their Origin, Divisions and Connections, with their Distribution to the various Regions of the Cutaneous Surface and to all the Muscles. By WILLIAM H. FLOWER, F.R.C.S., F.R.S., Hunterian Professor of Comparative Anatomy, and Conservator of the Museum of the Royal College of Surgeons. Third Edition, thoroughly revised. With six Large Folio Maps or Diagrams. 4to. Cloth, $3.50

FLÜCKIGER. The Cinchona Barks Pharmacognostically Considered. By Professor FRIEDRICH FLÜCKIGER, of Strasburg. Translated by FREDERICK B. POWER, PH.D. With 8 Lithographic Plates. Royal octavo. Cloth, $1.50

FOTHERGILL. On the Heart and Its Diseases. With Their Treatment. Including the Gouty Heart. By J. MILNER FOTHERGILL, M.D., Member of the Royal College of Physicians of London. 2d Ed. Rewritten. 8vo. Cloth, $3.50

FOWLER'S Dictionary of Practical Medicine. *By Various Writers.* An Encyclopedia of Medicine. Edited by JAMES KINGSTON FOWLER, M.A., M.D., F.R.C.P., Senior Asst. Physician to the Middlesex Hospital and the Hospital for Consumption, Brompton, London. 8vo. *Just Ready.* Cloth, ; Half Morocco,

FOX. Water, Air and Food. Sanitary Examinations of Water, Air and Food. By CORNELIUS B. FOX, M.D. 110 Engravings. 2d Ed., Revised. Cloth, $4.00

FOX AND GOULD. Compend on Diseases of the Eye and Refraction, including Treatment and Surgery. By L. WEBSTER FOX, M.D., Chief Clinical Assistant, Ophthalmological Department, Jefferson Medical College Hospital; Ophthalmic Surgeon, Germantown Hospital, Philadelphia; late Clinical Assistant at Moorfields, London, England, etc., and GEO. M. GOULD, M.D. Second Edition. Enlarged. 71 Illustrations and 39 Formulæ. *Being No. 8, ? Quiz-Compend ? Series.* Cloth, $1.00. Interleaved for the addition of notes, $1.25

FRANKLAND'S Water Analysis. For Sanitary Purposes, with Hints for the Interpretation of Results. By E. FRANKLAND, M.D., F.R.S. Illustrated. 12mo. Cloth, $1.00

FULLERTON. Obstetrical Nursing. A Handbook for Nurses, Students and Mothers. By ANNA M. FULLERTON, M.D., Demonstrator of Obstetrics in the Woman's Medical College; Physician in charge of, and Obstetrician and Gynæcologist to, the Woman's Hospital, Philadelphia, etc. 34 Illustrations, several of which are original. 12mo. 212 pages. Cloth, $1.25

GALABIN'S Midwifery. A Manual for Students and Practitioners. By A. LEWIS GALABIN, M.D., F.R.C.P., Professor of Midwifery at and Obstetric Physician to, Guy's Hospital, London. 227 Illustrations. Cloth, $3.00; Leather, $3.50

GAMGEE. Wounds and Fractures, and their Treatment. By SAMPSON GAMGEE, F.R.S.E., etc. Second Edition. 44 Illustrations. 8vo. Cloth, $3.50

GARDNER. The Brewer, Distiller and Wine Manufacturer. A Handbook for all Interested in the Manufacture and Trade of Alcohol and Its Compounds. Edited by JOHN GARDNER, F.C.S. Illustrated. Cloth, $1.75

Bleaching, Dyeing, and Calico Printing. With Formulæ. Illustrated. $1.75

Acetic Acid, Vinegar, Ammonia and Alum. Illustrated. Cloth, $1.75

GARROD. On Rheumatism. A Treatise on Rheumatism and Rheumatic Arthritis. By ARCHIBALD EDWARD GARROD, M.A. Oxon., M.D., M.R.C.S. Eng., Asst. Physician, West London Hospital. Illustrated. Octavo. Cloth, $6.00

GIBBES'S Practical Histology and Pathology. By HENEAGE GIBBES, M.B. 12mo. Third Edition. Cloth, $1.75

GILLIAM'S Pathology. The Essentials of Pathology; a Handbook for Students. By D. TOD GILLIAM, M.D., Professor of Physiology, Starling Medical College, Columbus, O. With 47 Illustrations. 12mo. Cloth, $2.00

GLISAN'S Modern Midwifery. A Text-book. By RODNEY GLISAN, M.D., Emeritus Professor of Midwifery and Diseases of Women and Children in Willamette Univ., Portland, Oregon. 129 Illus. 8vo. 2d Edition. Cloth, $3.00

GOODHART and STARR'S Diseases of Children. The Student's Guide to the Diseases of Children. By J. F. GOODHART, M.D., F.R.C.P., Physician to Evelina Hospital for Children; Demonstrator of Morbid Anatomy at Guy's Hospital. Second American from the Third English Edition. Rearranged and Edited, with notes and additions, by LOUIS STARR, M.D., Clinical Professor of Diseases of Children in the University of Pennsylvania; Physician to the Children's Hospital. With many new prescriptions. Cloth, $3.00; Leather, $3.50

GORGAS'S Dental Medicine. A Manual of Materia Medica and Therapeutics. By FERDINAND J. S. GORGAS, M.D., D.D.S., Professor of the Principles of Dental Science, Dental Surgery and Dental Mechanism in the Dental Department of the University of Maryland. Third Edition. Enlarged. 8vo. Cloth, $3.50

GOULD'S New Medical Dictionary. Including all the Words and Phrases used in Medicine, with their proper Pronunciation and Definitions, based on Recent Medical Literature. By GEORGE M. GOULD, B.A., M.D., Ophthalmic Surgeon to the Philadelphia Hospital, etc., With Tables of the Bacilli, Micrococci, Leucomaïnes, Ptomaïnes, etc., of the Arteries, Muscles, Nerves, Ganglia and Plexuses; Mineral Springs of U. S., Vital Statistics, etc. Small octavo, 520 pages. Half Dark Leather, $3.25; Half Morocco, Thumb Index, $4.25

GOWERS, Manual of Diseases of the Nervous System. A Complete Text-book. By WILLIAM R. GOWERS, M.D., Prof. Clinical Medicine, University College, London. Physician to National Hospital for the Paralyzed and Epileptic. 341 Illustrations and 1360 pages. Octavo. Cloth, $6.50; Leather, $7.50

This work is published in two volumes in London. By special arrangement with the author, we have reprinted it in one, using the original illustrations.

GOWERS, Diagnosis of Diseases of the Brain. 8vo. Second Edition. Illustrated. Cloth, $2.00

Diagnosis of Diseases of the Spinal Cord. 4th Edition. *Preparing.*

Medical Ophthalmoscopy. A Manual and Atlas, with Colored Autotype and Lithograph Plates of Original Drawings, Wood Cuts, etc. 3d Edition, revised by DR. W. S. COLMAN. Octavo. *In Press.*

Syphilis and the Nervous System. Being the Lettsomian Lectures for 1889. 8vo. *In Press.*

GROSS'S Biography of John Hunter. John Hunter and His Pupils. By Professor S. D. GROSS, M.D. With a Portrait. 8vo. Paper, .75; Cloth, $1.25

GREENHOW. Addison's Disease. Illustrated by Plates and Reports of Cases. By E. HEADLAM GREENHOW, M.D. 8vo. Cloth, $3.00

Chronic Bronchitis, especially as connected with Gout, Emphysema, and Diseases of the Heart. 12mo. Paper, .75; Cloth, $1.25

GRIFFITH'S Graphic Clinical Chart. Designed by J. P. CROZER GRIFFITH, M.D., Instructor in Clinical Medicine in the University of Pennsylvania. *Printed in three colors.* Sample copies free. Put up in loose packages of 50, $ .50 Price to Hospitals, 500 copies, $4.00; 1000 copies, $7.50. With name of Hospital printed on, 50 cents extra.

GROVES AND THORP. Chemical Technology. A new and Complete Work. The Application of Chemistry to the Arts and Manufactures. Edited by CHARLES E. GROVES, F.R.S., and WM. THORP, B.Sc., F.I.C. In about eight volumes, with numerous illustrations. *Each volume sold separately.*

Vol. I. FUEL. By Dr. E. J. MILLS, F.R.S., Professor of Chemistry, Anderson College, Glasgow; and Mr. F. J. ROWAN, assisted by an American expert. 607 Illustrations and 4 plates. Octavo. Cloth, 7.50; Half Morocco, $9.00

HABERSHON. On Some Diseases of the Liver. By S. O. HABERSHON, M.D., F.R.C.P., late Senior Physician to Guy's Hospital. A New Edition. Cloth, $1.50

HADDON'S Embryology. An Introduction to the Study of Embryology. For the Use of Students. By A. C. HADDON, M.A., Prof. of Zoölogy, Royal College of Science, Dublin. 190 Illustrations. Cloth, 6.00

HALE. On the Management of Children in Health and Disease. A Book for Mothers. By AMIE M. HALE, M.D. New Enlarged Edition. 12mo. Cloth, .75

HARE. Mediastinal Disease. The Pathology, Clinical History and Diagnosis of Affections of the Mediastinum other than those of the Heart and Aorta, with tables giving the Clinical History of 520 cases. The essay to which was awarded the Fothergillian Medal of the Medical Society of London, 1888. By H. A. HARE, M.D. (Univ. of Pa.), Demonstrator of Therapeutics and Instructor in Physical Diagnosis in the Medical Department, and Instructor in Physiology in the Biological Department, Univ of Pa. 8vo. Illustrated by Six Plates. Cloth, $2.00

HARLAN. Eyesight, and How to Care for It. By GEORGE C. HARLAN, M.D., Prof. of Diseases of the Eye, Philadelphia Polyclinic. Illustrated. Cloth, .50

HARLEY. Diseases of the Liver, With or Without Jaundice. Diagnosis and Treatment. By GEORGE HARLEY, M.D. With Colored Plates and Numerous Illustrations. 8vo. Price reduced. Cloth, $3.00; Leather, $4.00

HARRIS. On the Chest. Including the Principal Affections of the Pleuræ, Lungs, Pericardium, Heart and Aorta. By VINCENT D. HARRIS, F.R.C.P., Physician to the Victoria Park Hospital for Diseases of the Chest, London. With 55 Illustrations. Cloth, $2.50

HARRIS'S Principles and Practice of Dentistry. Including Anatomy, Physiology, Pathology, Therapeutics, Dental Surgery and Mechanism. By CHAPIN A. HARRIS, M.D., D.D.S., late President of the Baltimore Dental College, author of "Dictionary of Medical Terminology and Dental Surgery." Twelfth Edition. Revised and Edited by FERDINAND J. S. GORGAS, A.M., M.D., D.D.S., author of "Dental Medicine;" Professor of the Principles of Dental Science, Dental Surgery and Dental Mechanism in the University of Maryland. Two Full-page Plates and 1086 Illustrations. 1225 pages. 8vo. Cloth, $7.00; Leather, $8.00

Medical and Dental Dictionary. A Dictionary of Medical Terminology, Dental Surgery, and the Collateral Sciences. Fourth Edition, carefully Revised and Enlarged. By FERDINAND J. S. GORGAS, M.D., D.D.S., Prof. of Dental Surgery in the Baltimore College. 8vo. Cloth, $6.50; Leather, $7 50

HARTRIDGE. Refraction. The Refraction of the Eye. A Manual for Students. By GUSTAVUS HARTRIDGE, F.R.C.S., Consulting Ophthalmic Surgeon to St. Bartholomew's Hospital; Ass't Surgeon to the Royal Westminster Ophthalmic Hospital, etc. 96 Illustrations and Test Types. Fourth Edition. Cloth, $2.00

HARTSHORNE. Our Homes. Their Situation, Construction, Drainage, etc. By HENRY HARTSHORNE, M.D. Illustrated. Cloth, .50

HATFIELD. Diseases of Children. By MARCUS P. HATFIELD, Professor of Diseases of Children, Chicago Medical College. *Being No. 14, ? Quiz-Compend ? Series.* 12mo. Cloth, $1.00

Interleaved for the addition of notes, 1.25

HEADLAND'S Action of Medicines. On the Action of Medicines in the System. By F. W. HEADLAND, M.D. Ninth American Edition. 8vo. Cloth, $3.00

HEATH'S Operative Surgery. A Course of Operative Surgery, consisting of a Series of Plates, Drawn from Nature by M. Léveillé, of Paris. With Descriptive Text of Each Operation. By CHRISTOPHER HEATH, F.R.C.S., Holme Professor of Clinical Surgery in University College, London. Quarto. Second Edition. Revised. *Sold by Subscription.* Cloth, $12.00

Minor Surgery and Bandaging. Ninth Edition. Revised and Enlarged. With 142 Illustrations. 12mo. Cloth, $2.00

Practical Anatomy. A Manual of Dissections. Seventh London Edition. 24 Colored Plates, and nearly 300 other Illustrations. Cloth, $5.00

Injuries and Diseases of the Jaws. Third Edition. Revised, with over 150 Illustrations. 8vo. Cloth, $4.50

Lectures on Certain Diseases of the Jaws, delivered at the Royal College of Surgeons of England, 1887. 64 Illustrations. 8vo. Boards, $1.00

HENRY. Anæmia. A Practical Treatise. By FRED'K P. HENRY, M.D., Prof. Clinical Med. Phila. Polyclinic, Physician to Episcopal and Phila. Hospitals, to Home for Consumptives, etc. 12mo. Half Cloth, .75

HIGGENS' Ophthalmic Practice. A Manual for Students and Practitioners. By CHARLES HIGGENS, F.R.C.S. Ophthalmic Surgeon at Guy's Hospital. *Practical Series.* *See Page 19.* Cloth, $1.75

Ophthalmic Practice. A Handbook. Second Edition. 32mo. Cloth, .50

HILL AND COOPER. Venereal Diseases. The Student's Manual of Venereal Diseases, being a concise description of those Affections and their Treatment. By BERKELEY HILL, M.D., Professor of Clinical Surgery, University College, and ARTHUR COOPER, M.D., Late House Surgeon to the Lock Hospital, London. 4th Edition. 12mo. Cloth, $1.00

HILLIER. Diseases of Children. A Clinical Treatise. By THOMAS HILLIER, M.D. 8vo. Cloth, $1.25

HOLDEN'S Anatomy. A Manual of the Dissections of the Human Body. By LUTHER HOLDEN, F.R.C.S. Fifth Edition. Carefully Revised and Enlarged. Specially concerning the Anatomy of the Nervous System, Organs of Special Sense, etc. By JOHN LANGTON, F.R.C.S., Surgeon to, and Lecturer on Anatomy at, St. Bartholomew's Hospital. 208 Illustrations. 8vo.
Oilcloth Covers, for the Dissecting Room, $4.50; Cloth, $5.00; Leather, $6.00

Human Osteology. Comprising a Description of the Bones, with Colored Delineations of the Attachments of the Muscles. The General and Microscopical Structure of Bone and its Development. Carefully Revised. By the Author and Prof. STEWART, of the Royal College of Surgeons' Museum. With Lithographic Plates and Numerous Illustrations. 7th Ed. Cloth, $6.00

Landmarks. Medical and Surgical. 4th Edition. 8vo. Cloth, $1.25

HOLDEN. The Sphygmograph. Its Physiological and Pathological Indications By EDGAR HOLDEN, M.D. Illustrated. 8vo. Cloth, $2.00

HOLLAND. The Urine, the Common Poisons and the Milk. Memoranda, Chemical and Microscopical, for Laboratory Use. By J. W. HOLLAND, M.D., Professor of Medical Chemistry and Toxicology in Jefferson Medical College, of Philadelphia. Third Edition, Revised and Enlarged. Illustrated and Interleaved. 12mo. Cloth, $1.00

HORWITZ'S Compend of Surgery, including Minor Surgery, Amputations, Fractures, Dislocations, Surgical Diseases, and the Latest Antiseptic Rules, etc., with Differential Diagnosis and Treatment. By ORVILLE HORWITZ, B.S., M.D., Demonstrator of Anatomy, Jefferson Medical College; Chief, Out-Patient Surgical Department, Jefferson Medical College Hospital. Third Edition. Very much Enlarged and Rearranged. 91 Illustrations and 77 Formulæ. 12mo. *No. 9 ? Quiz-Compend ? Series.* Cloth, $1.00. Interleaved for the addition of notes, $1.25

HUFELAND. Long Life. Art of Prolonging Life. By C. W. HUFELAND. Edited by ERASMUS WILSON, M.D. 12mo. Cloth, $1.00

HUGHES. Compend of the Practice of Medicine. Fourth Edition. Revised and Enlarged. By DANIEL E. HUGHES, M.D., Demonstrator of Clinical Medicine at Jefferson Medical College, Philadelphia. In two parts. *Being Nos. 2 and 3, ? Quiz-Compend ? Series.*

PART I.—Continued, Eruptive and Periodical Fevers, Diseases of the Stomach, Intestines, Peritoneum, Biliary Passages, Liver, Kidneys, etc., and General Diseases, etc.

PART II.—Diseases of the Respiratory System, Circulatory System and Nervous System; Diseases of the Blood, etc.
Price of each Part, in Cloth, $1.00; interleaved for the addition of Notes, $1.25

Physicians' Edition.—In one volume, including the above two parts, a section on Skin Diseases, and an index. *Fourth revised, enlarged Edition. 462 pages.* Full Morocco, Gilt Edge, $2.50

HUMPHREY. A Manual for Nurses. Including general Anatomy and Physiology, management of the sick room, etc. By LAURENCE HUMPHREY, M.A., M.B., M.R.C.S., Assistant Physician to, and Lecturer at, Addenbrook's Hospital, Cambridge, England. 12mo. Illustrated. 242 pages. Cloth, $1.25

JACOBSON. Operations of Surgery. By W. H. A. JACOBSON, B.A. OXON., F.R C.S., Eng.; Ass't Surgeon, Guy's Hospital; Surgeon at Royal Hospital for Children and Women, etc. With over 200 Illust. Cloth, $5.00; Leather, $6.00

JAMES on Sore Throat. Its Nature, Varieties and Treatment, including its Connection with other Diseases. By PROSSER JAMES, M.D. Fourth Edition, Revised and Enlarged. Colored Plates and Wood-cuts. Paper .75; Cloth, $1.25

JONES' Aural Surgery. A Practical Handbook on Aural Surgery. By H. MACNAUGHTON JONES, M.D., Surgeon to the Cork Ophthalmic and Aural Hospital. Illustrated. Second Edition, with new Wood Engravings. 12mo. Cloth, $2.75

JOURNAL of Laryngology and Rhinology. A Monthly Analytical Record, devoted to Diseases of the Throat and Nose. Edited by MORELL MACKENZIE, M.D. *Sample Nos., 25 cents.* Subscription per annum, $3.00

KEATING. How to Examine for Life Insurance. A Practical Handbook. By JOHN M. KEATING, President of the Association of Life-Insurance Medical Directors. With 3 Full-page Plates and other Illustrations. 8vo. Cloth, *net*, $2.00

KIRKES' Physiology. (*Authorized Edition.*) A Handbook of Physiology. Twelfth London Edition, Revised and Enlarged. By W. MORRANT BAKER, M.D. 460 Illustrations. 12mo. Cloth, $4.00; Leather, $5.00

LANDIS' Compend of Obstetrics; especially adapted to the Use of Students and Physicians. By HENRY G. LANDIS, M.D., Professor of Obstetrics and Diseases of Women, in Starling Medical College, Columbus, Ohio. Fourth Edition. Enlarged. With Many Illustrations. *No. 5 ? Quiz-Compend ? Series.* Cloth, $1.00; interleaved for the addition of Notes, $1.25

LANDOIS. A Text-Book of Human Physiology; including Histology and Microscopical Anatomy, with special reference to the requirements of Practical Medicine. By DR. L. LANDOIS, Professor of Physiology and Director of the Physiological Institute in the University of Greifswald. Third American, translated from the Sixth German Edition, with additions, by WM. STIRLING, M.D., D.Sc., Brackenbury Professor of Physiology and Histology in Owen's College, Manchester; Examiner in Physiology in University of Oxford, England. With 692 Illustrations. 8vo. Cloth, $6.50; Leather, $7.50

LEBER AND ROTTENSTEIN. Dental Caries and Its Causes. An Investigation into the Influence of Fungi in the Destruction of the Teeth. By Drs. LEBER and ROTTENSTEIN. Illustrated. Paper, .75; Cloth, $1.25

LEE. The Microtomist's Vade Mecum. Second Edition. A Handbook of Methods of Microscopical Anatomy. By ARTHUR BOLLES LEE, Asst. in the Russian Laboratory of Zoölogy, at Villefranche-sur-Mer (Nice). 660 Formulæ, etc. Enlarged and Revised. Cloth, $4.00

LEFFMANN'S Compend of Chemistry, Inorganic and Organic. Including Urine Analysis. By HENRY LEFFMANN, M.D., Prof. of Chemistry and Metallurgy in the Penna. College of Dental Surgery, and in the Wagner Free Institute of Science, Philadelphia. *No. 10 ? Quiz-Compend ? Series.* Third Edition. Rewritten and Adapted for Students of Medicine and Dentistry. 12mo. Cloth, $1.00. Interleaved for the addition of Notes, $1.25

LEFFMANN & BEAM. Examination of Water for Sanitary and Technical Purposes. By HENRY LEFFMANN, M.D., Professor of Chemistry and Metallurgy, Penna. College of Dental Surgery, Hygienist and Food Inspector Penna. State Board of Agriculture, etc.; and WILLIAM BEAM, A.M., formerly Chief Chemist B. & O. R. R. Illustrated. 12mo. Cloth, $1.25

LEGG on the Urine. Practical Guide to the Examination of the Urine, for Practitioner and Student. By J. WICKHAM LEGG, M.D. Sixth Edition, Enlarged. Illustrated. 12mo. Cloth, .75

LEWERS. On the Diseases of Women. Second Edition. With over 120 Engravings. *Practical Series. See Page 19.* 12mo. Cloth, $2.50

LEWIN on Syphilis. The Treatment of Syphilis. By Dr. GEORGE LEWIN, of Berlin. Translated by CARL PROEGLER, M.D., and E. H. GALE, M.D., Surgeons U. S. Army. Illustrated. 12mo. Paper, .75; Cloth, $1.25

LEWIS, (BEVAN). Mental Diseases. A text-book having special reference to the Pathological aspects of Insanity. By BEVAN LEWIS, L.R.C.P., M.R.C.S., Medical Director, West Riding Asylum, Wakefield, England. 18 Lithographic plates and other Illustrations. 8vo. Cloth, $6.00

LIEBREICH'S Atlas of Ophthalmoscopy, composed of 12 Chromo-Lithographic Plates (containing 59 Figures), with Text. Translated by H. R. SWANZY, M.B. Third Edition. 4to. Boards, $15.00

LINCOLN. School and Industrial Hygiene. By D. F. LINCOLN, M.D. Cloth, .50

LIZARS, (JOHN). On Tobacco. The Use and Abuse of Tobacco. Cloth, .50

LONGLEY'S Pocket Medical Dictionary for Students and Physicians. Giving the Correct Definition and Pronunciation of all Words and Terms in General Use in Medicine and the Collateral Sciences, with an Appendix, containing Poisons and their Antidotes, Abbreviations Used in Prescriptions, and a Metric Scale of Doses. By ELIAS LONGLEY. Cloth, $1.00; Tucks and Pocket, $1.25

LÜCKES. Hospital Sisters and their Duties. By EVA C. E. LÜCKES, Matron to the London Hospital; Author of "Lectures on Nursing." 12mo. Cloth, $1.00

MAC MUNN. Chemistry of Urine. Illustrated. Outlines of the Clinical Chemistry of Urine. By C. A. MAC MUNN, M.A., M.D., Dublin. Sixty-four Wood-cuts and Plate of Spectra. Octavo. $3.00

On the Spectroscope in Medicine. With 3 Chromo-lithographic Plates of Physiological and Pathological Spectra, and 13 Wood Cuts. Cloth, $3.00

MACNAMARA. On the Eye. A Manual of the Diseases of the Eye. By C. MACNAMARA, M.D. Fourth Edition, Carefully Revised; with Additions and Numerous Colored Plates, Diagrams of Eye, Wood-cuts, and Test Types. Demi 8vo. Cloth, $4.00

MACALISTER'S Human Anatomy. 800 Illustrations. A New Text-book for Students and Practitioners. Systematic and Topographical, including the Embryology, Histology and Morphology of Man. With special reference to the requirements of Practical Surgery and Medicine. By ALEX. MACALISTER, M.D., F.R.S., Professor of Anatomy in the University of Cambridge, England; Examiner in Zoölogy and Comparative Anatomy, University of London; formerly Professor of Anatomy and Surgery, University of Dublin. With 816 Illustrations, 400 of which are original. Octavo. Cloth, $7.50; Leather, $8.50

MACDONALD'S Microscopical Examinations of Water and Air. A Guide to the Microscopical Examination of Drinking Water, with an Appendix on the Microscopical Examination of Air. By J. D. MACDONALD, M.D. With 25 Lithographic Plates, Reference Tables, etc. Second Ed., Revised. 8vo. Cloth, $2.75

MACKENZIE. The Œsophagus, Nose, Naso-Pharynx, etc. By SIR MORELL MACKENZIE, M.D., Senior Physician to the Hospital for Diseases of the Chest and Throat, London. Illus. Being Vol. II of the First Edition of his Treatise on the Throat and Nose. Complete in itself. Cloth, $3.00; Leather, $4.00

The Pharmacopœia of the Hospital for Diseases of the Throat and Nose. Fourth Edition, Enlarged, Containing 250 Formulæ, with Directions for their Preparation and Use. 16mo. Cloth, $1.25

MANN'S Manual of Psychological Medicine and Allied Nervous Diseases. Their Diagnosis, Pathology, Prognosis and Treatment, including their Medico-Legal Aspects; with chapter on Expert Testimony, and an abstract of the laws relating to the Insane in all the States of the Union. By EDWARD C. MANN, M.D., member of the New York County Medical Society. With Illustrations of Typical Faces of the Insane, Handwriting of the Insane, and Micro-photographic Sections of the Brain and Spinal Cord. Octavo. Cloth, $5.00; Leather $6.00

MARSHALL'S Physiological Diagrams, Life Size, Colored. Eleven Life-size Diagrams (each 7 feet by 3 feet 7 inches). Designed for Demonstration before the Class. By JOHN MARSHALL, F.R.S., F.R.C.S., Professor of Anatomy to the Royal Academy; Professor of Surgery, University College, London, etc.

In Sheets Unmounted, $40.00

Backed with Muslin and Mounted on Rollers, $60.00

Ditto, Spring Rollers, in Handsome Walnut Wall Map Case (Send for Special Circular), ... $100.00

Single Plates, Sheets, $5.00; Mounted, $7.50; Explanatory Key, 50 cents.

No. 1—The Skeleton and Ligaments. No. 2—The Muscles and Joints, with Animal Mechanics. No. 3—The Viscera in Position. The Structure of the Lungs. No. 4—The Heart and Principal Blood-vessels. No. 5—The Lymphatics or Absorbents. No. 6—The Digestive Organs. No. 7—The Brain and Nerves. Nos. 8 and 9—The Organs of the Senses. Nos. 10 and 11—The Microscopic Structure of the Textures and Organs.

MARSHALL & SMITH. On the Urine. The Chemical Analysis of the Urine. By JOHN MARSHALL, M.D., and Prof. EDGAR F. SMITH, of the Chemical Laboratories, University of Pennsylvania. Phototype Plates. 12mo. Cloth, $1.00

MASON'S Compend of Electricity, and its Medical and Surgical Uses. By CHARLES F. MASON, M.D., Assistant Surgeon U. S. Army. With an Introduction by CHARLES H. MAY, M.D., Instructor in the New York Polyclinic. Numerous Illustrations. 12mo. Cloth, $1.00

MAXWELL. Terminologia Medica Polyglotta. By Dr. THEODORE MAXWELL, assisted by others in various countries. 8vo. Cloth, $4.00

The object of this work is to assist the medical men of any nationality in reading medical literature written in a language not their own. Each term is usually given in seven languages, viz.: English, French, German, Italian, Spanish, Russian and Latin.

MAYS' Therapeutic Forces; or, The Action of Medicine in the Light of the Doctrine of Conservation of Force. By THOMAS J. MAYS, M.D. Cloth, $1.25

Theine in the Treatment of Neuralgia. Being a Contribution to the Therapeutics of Pain. 16mo. ½ bound, .50

MEADOWS' Obstetrics. A Text-Book of Midwifery. Including the Signs and Symptoms of Pregnancy, Obstetric Operations, Diseases of the Puerperal State, etc. By ALFRED MEADOWS, M.D. Third American, from Fourth London Edition. Revised and Enlarged. With 145 Illustrations. 8vo. Cloth, $2.00

MEDICAL Directory of Philadelphia and Camden, 1889. Containing lists of Physicians *of all Schools of Practice*, Dentists, Veterinarians, Druggists and Chemists, with information concerning Medical Societies, Colleges and Associations, Hospitals, Asylums, Charities, etc. Morocco, Gilt edges, $2.50

MEIGS. Milk Analysis and Infant Feeding. A Practical Treatise on the Examination of Human and Cows' Milk, Cream, Condensed Milk, etc., and Directions as to the Diet of Young Infants. By ARTHUR V. MEIGS, M.D., Physician to the Pennsylvania Hospital, Philadelphia. 12mo. Cloth, $1.00

MEIGS and PEPPER on Children. A Practical Treatise on the Diseases of Children. By J. FORSYTH MEIGS, M.D., Fellow of the College of Physicians of Philadelphia, etc., etc., and WILLIAM PEPPER, M.D., Professor of the Principles and Practice of Medicine in the Medical Department, University of Pennsylvania. Seventh Edition. Cloth, $5.00; Leather, $6.00

MERRELL'S Digest of Materia Medica. Forming a Complete Pharmacopœia for the use of Physicians, Pharmacists and Students. By ALBERT MERRELL, M.D. Octavo. Half dark Calf, $4.00

MEYER. Ophthalmology. A Manual of Diseases of the Eye. By DR. EDOUARD MEYER, Prof. à L'École de la Faculté de Médicine de Paris, Chev. of the Legion of Honor, etc. Translated from the Third French Edition, with the assistance of the author, by A. FREEDLAND FERGUS, M.B., Assistant Surgeon Glasgow Eye Infirmary. With 270 Illustrations, and two Colored Plates prepared under the direction of DR. RICHARD LIEBREICH, M.R.C.S., Author of the "Atlas of Ophthalmoscopy." 8vo. Cloth, $4.50; Leather, $5.50

MILLER and LIZAR'S Alcohol and Tobacco. Alcohol. Its Place and Power. By JAMES MILLER, F.R.C.S.; and, Tobacco, Its Use and Abuse. By JOHN LIZARS, M.D. The two essays in one volume. Cloth, $1.00; Separate, each .50

MILLS. Fuel and Its Applications. By E. J. MILLS, D.Sc., F.R.S., and E. J. ROWAN, C.E. (See Groves and Thorp Technology.) 8vo. Clo., $7.50; Half Mor. $9.00

MONEY. On Children. Treatment of Disease in Children, including the Outlines of Diagnosis and the Chief Pathological Differences between Children and Adults. By ANGEL MONEY, M.D., M.R.C.P., Asst. Physician to the Hospital for Sick Children, Great Ormond St., and to the Victoria Park Chest Hospital, London. *Practical Series.* *See Page 19.* 12mo. 560 pages. Cloth, $3.00

MORRIS. Compend of Gynæcology. By HENRY MORRIS, M.D., Demonstrator of Obstetrics, Jefferson Medical College, Phila., etc. *Being ? Quiz-Compend ? No. 7.* *Nearly Ready.*

MORTON on Refraction of the Eye. Its Diagnosis and the Correction of its Errors. With Chapter on Keratoscopy, and Test Types. By A. MORTON, M.B. Third Edition, Revised and Enlarged. Cloth, $1.00

MURRELL. Massotherapeutics. Massage as a Mode of Treatment. By WM. MURRELL, M.D., F.R.C.P., Lecturer on Pharmacology and Therapeutics at Westminster Hospital. 5th Edition. Revised. 12mo. Cloth, $1.50

Chronic Bronchitis and its Treatment. A Clinical Study. 12mo. 176 pages. Cloth, $1 50

MÜTER. Practical and Analytical Chemistry. By JOHN MÜTER, F.R.S., F.C.S., etc. Third Edition. Revised and Illustrated. Cloth, $2.00

NEW SYDENHAM SOCIETY Publications. Three to Six Volumes published each year, *List of Volumes upon application.* Per annum, $9.00

OBERSTEINER, The Central Nervous System. A Guide to the study of their structure in Health and Disease. By Professor H. OBERSTEINER, of the University of Vienna. Translated, with annotations and additions, by Alex. Hill, M.A., M.D., Master of Downing College, Cambridge. 198 Illustrations. Cloth, $6.00

OPHTHALMIC REVIEW. A Monthly Record of Ophthalmic Science. Published in London. *Sample Numbers, 25 cents.* Per annum, $3.00

OSGOOD. The Winter and Its Dangers. By HAMILTON OSGOOD, M.D. Cloth, .50

OSLER. Cerebral Palsies of Children. A Clinical Study from the Infirmary for Nervous Diseases, Philadelphia. By WILLIAM OSLER, M.D., F.R.C.P., London, etc. 8vo. Cloth, $2.00

OSTROM. Massage and the Original Swedish Movements. Their Application to Various Diseases of the Body. A Manual for Students, Nurses and Physicians. By KURRE W. OSTROM, from the Royal University of Upsala, Sweden; Instructor in Massage and Swedish Movements in the Hospital of the University of Pennsylvania, and in the Philadelphia Polyclinic and College for Graduates in Medicine, etc. Illustrated by Wood Engravings, drawn especially for this purpose. 12mo. Cloth, .75

OVERMAN'S Practical Mineralogy, Assaying and Mining, with a Description of the Useful Minerals, etc. By FREDERICK OVERMAN, Mining Engineer. Eleventh Edition. 12mo. Cloth, $1.00

PACKARD'S Sea Air and Sea Bathing. By JOHN H. PACKARD, one of the Physicians to the Pennsylvania Hospital, Philadelphia. Cloth, .50

PAGE'S Injuries of the Spine and Spinal Cord, without apparent Lesion and Nervous Shock. In their Surgical and Medico-Legal Aspects. By HERBERT W. PAGE, M.D., F.R.C.S. Third Edition, Revised. Octavo. *Preparing.*

PARKES' Practical Hygiene. By EDWARD A. PARKES, M.D. The Seventh Revised and Enlarged Edition. With Many Illustrations. 8vo. Cloth, $4.50

PARKES. Hygiene and Public Health. A Practical Manual. By LOUIS C. PARKES, M.D., D.P.H. London Hospital; Assistant Professor of Hygiene and Public Health, at University College, etc. 12mo. Second Edition. Cloth, $2.50

PARRISH'S Alcoholic Inebriety. From a Medical Standpoint, with Illustrative Cases from the Clinical Records of the Author. By JOSEPH PARRISH, M.D., President of the Amer. Assoc. for Cure of Inebriates. Paper, .75; Cloth, $1.25

PARVIN'S Winckel's Diseases of Women. (See Winckel, page 24).

PARVIN. Lectures on Obstetric Nursing. Delivered at the Training School for Nurses of the Philadelphia Hospital. By THEOPHILUS PARVIN, M.D., Professor of Obstetrics and Diseases of Women and Children, at Jefferson Medical College; Obstetrician to Philadelphia Hospital. 12mo. Cloth, .75

PENNSYLVANIA Hospital Reports. Edited by a Committee of the Hospital Staff: J. M. DACOSTA, M.D., and WILLIAM HUNT. Containing Original Articles by the Staff. With many other Illustrations. Paper, .75; Cloth, $1.25

PHYSICIAN'S VISITING LIST. Published Annually. Thirty-ninth Year of its Publication.

REGULAR EDITION.

For 25 Patients weekly.			Tucks, pocket and pencil,		Gilt Edges,	.	.	$1.00
50	"	"	"	"	"	"	"	.	.	1.25
75	"	"	"	"	"	"	"	.	.	1.50
100	"	"	"	"	"	"	"	.	.	2.00
50	"	" 2 vols.	Jan. to June / July to Dec.		"	"	"	.	.	2.50
100	"	" 2 vols.	Jan. to June / July to Dec.		"	"	"	.	.	3.00

INTERLEAVED EDITION.

For 25 Patients weekly, interleaved, tucks, pocket, etc.,					"	"	.	.	1.25
50	"	"	"	"	"	"	.	.	1.50
50	"	" 2 vols.	Jan. to June / July to Dec.	"	"	"	"	.	.	3.00

Perpetual Edition, without Dates and with Special Memorandum Pages.

For 25 Patients, interleaved, tucks, pocket and pencil,							.	.	$1.25
50	"	"	"	"	"	"	.	.	1.50

Monthly Edition, without Dates. Can be commenced at any time and used until full. Requires only one writing of patient's name for the whole month.
Plain binding, without flap or Pencil, .75
Leather cover, Pocket and Pencil, $1.00

EXTRA Pencils will be sent, postpaid, for 25 cents per half dozen.

☞ This List combines the several essential qualities of strength, compactness, durability and convenience. It is made in all sizes and styles to meet the wants of all physicians. It is not an elaborate, complicated system of keeping accounts, but a plain, simple record, that may be kept with the least expenditure of time and trouble—hence its popularity. A special circular, descriptive of contents and improvements, will be sent upon application.

PEREIRA'S Prescription Book. Containing Lists of Terms, Phrases, Contractions and Abbreviations used in Prescriptions, Explanatory Notes, Grammatical Construction of Prescriptions, Rules for the Pronunciation of Pharmaceutical Terms. By JONATHAN PEREIRA, M.D. Sixteenth Edition. Cloth, $1.00; Tucks $1.25

PIGGOTT Copper Mining and Copper Ore. 12mo. Cloth, $1.00

PORTER'S Surgeon's Pocket-Book. By SURGEON-MAJOR J. H. PORTER, late Professor of Military Surgery in the Army Medical School, Netley, England. Revised, and partly Rewritten, by SURGEON-MAJOR C. H. GODWIN, of the Army Medical School (Netley, England). Third Edition. Small 12mo. Leather Covers, $2.25

POWER, HOLMES, ANSTIE and BARNES (Drs.). Reports on the Progress of Medicine, Surgery, Physiology, Midwifery, Diseases of Women and Children, Materia Medica, Medical Jurisprudence, Ophthalmology, etc. Reported for the New Sydenham Society. 8vo. Paper, .75; Cloth, $1.25

POTTER. A Handbook of Materia Medica, Pharmacy and Therapeutics, including the Action of Medicines, Special Therapeutics, Pharmacology, etc. Including over 600 Prescriptions and Formulæ. By SAMUEL O. L. POTTER, M.A., M.D., Professor of the Practice of Medicine, Cooper Medical College, San Francisco; late A. A. Surgeon U. S. Army. Second Edition, Revised and Enlarged. 8vo. *With Thumb Index in each copy.* Cloth, $4.00; Leather, $5.00

Speech and Its Defects. Considered Physiologically, Pathologically and Remedially; being the Lea Prize Thesis of Jefferson Medical College, 1882. Revised and Corrected. 12mo. Cloth, $1.00

THE PRACTICAL SERIES.

THREE NEW VOLUMES.

PARKES. Hygiene and Public Health. A Practical Manual. By LOUIS C. PARKES, M.D., D.P.H., London Hospital; Fellow of the Sanitary Institute; Assistant Professor of Hygiene and Public Health, at University College, etc. 12mo. Second Edition. Cloth, $2.50

LEWERS. On the Diseases of Women. A Practical Treatise. By Dr. A. H. N. LEWERS, Assistant Obstetric Physician to the London Hospital; and Physician to Out-patients, Queen Charlotte's Lying-in Hospital; Examiner in Midwifery and Diseases of Women to the Society of Apothecaries of London. With 139 Engravings. Second Edition, Revised. Cloth, $2.50

BUXTON. On Anæsthetics. A Manual of their Uses and Administration. By DUDLEY WILMOT BUXTON, M.D., B.S., Ass't to Prof. of Med., and Administrator of Anæsthetics, University College Hospital, London. Illustrated.

Second Edition in Press.

MONEY. On Children. Treatment of Disease in Children, including the Outlines of Diagnosis and the Chief Pathological Differences between Children and Adults. By ANGEL MONEY, M.D., M.R.C.P., Ass't Physician to the Hospital for Sick Children, Great Ormond St., and to the Victoria Park Chest Hospital, London. 12mo. 560 pages. Cloth, $3.00

PRITCHARD. On the Ear. Handbook of Diseases of the Ear. By URBAN PRITCHARD, M.D., F.R.C.S., Professor of Aural Surgery, King's College, London, Aural Surgeon to King's College Hospital, Senior Surgeon to the Royal Ear Hospital, etc. 12mo. Cloth, $1.50

BARRETT. Dental Surgery for General Practitioners and Students of Medicine and Dentistry. Extraction of Teeth, etc. By A. W. BARRETT, M.D. 2d Edition, Revised and Enlarged. 80 Illustrations. Cloth, $1.25

COLLIE On Fevers. A Practical Treatise on Fevers, Their History, Etiology. Diagnosis, Prognosis and Treatment. By ALEXANDER COLLIE, M.D., M.R.C.P., Lond. Medical Officer of the Homerton, and of the London Fever Hospitals. Colored Plates. Cloth, $2.50

RALFE. Diseases of the Kidney and Urinary Derangements. By C. H. RALFE, M.D., F.R.C.P., Ass't Physician to the London Hospital. Illustrated. 12mo. Cloth, $2.75

REEVES. Bodily Deformities and their Treatment. A Handbook of Practical Orthopædics. By H. A. REEVES, M.D., Senior Ass't Surgeon to the London Hospital, Surgeon to the Royal Orthopædic Hospital. 228 Illus. Cloth, $2.25

HIGGENS. Ophthalmic Practice. A Manual for Students and Practitioners. By CHARLES HIGGINS, F.R.C.P., Opthalmic Surgeon to Guy's Hospital. Illustrated. 274 pages. Cloth, $1.75

*** The volumes of this series, written by well-known physicians and surgeons of large private and hospital experience, embrace the various branches of medicine and surgery. They are of a thoroughly practical character, calculated to meet the requirements of the practitioner, and present the most recent methods and information in a compact shape and at a low price.

Bound Uniformly, in a Handsome and Distinctive Cloth Binding, and mailed to any address, on receipt of the price.

POTTER. Compend of Anatomy, including **Visceral Anatomy.** Formerly published separately. *Based upon Gray.* Fourth Edition, Revised, and greatly Enlarged. With an Index and 117 Illustrations. *Being No. 1 ? Quiz-Compend ? Series.* Cloth, $1.00; Interleaved for taking Notes, $1.25

Compend of Materia Medica, Therapeutics and Prescription Writing, arranged in accordance with the last Revision U. S. Pharmacopœia, with special reference to the Physiological Action of Drugs. Fifth Revised and Improved Edition, with Index. *Being No. 6 ? Quiz-Compend ? Series.* Cloth, $1.00. Interleaved for taking Notes, $1.25

PRITCHARD on the Ear. Handbook of Diseases of the Ear. By URBAN PRITCHARD, M.D., F.R.C.S., Professor of Aural Surgery, King's College, London, Aural Surgeon to King's College Hospital, Senior Surgeon to the Royal Ear Hospital, etc. 12mo. *Practical Series. See Page 19.* Cloth, $1.50

PROCTER'S Practical Pharmacy. Lectures on Practical Pharmacy. With 43 Engravings and 32 Lithographic Fac-simile Prescriptions. By BARNARD S. PROCTER. Second Edition. Cloth, $4.50

RADCLIFFE on Epilepsy, Pain, Paralysis, and other Disorders of the Nervous System. By CHARLES BLAND RADCLIFFE, M.D. Illus. Paper, .75; Cloth, $1.25

RALFE. Diseases of the Kidney and Urinary Derangements. By C. H. RALFE. Illustrated. 12mo. *Practical Series. See Page 19.* Cloth, $2.75

REESE'S Medical Jurisprudence and Toxicology. A Text-book for Medical and Legal Practitioners and Students. By JOHN J. REESE, M.D., Editor of Taylor's Jurisprudence, Professor of the Principles and Practice of Medical Jurisprudence, including Toxicology, in the University of Pennsylvania Medical Department. 2d. Ed. Enlarged. Crown Octavo. Cloth, $3.00; Leather, $3.50

REEVES. Bodily Deformities and their Treatment. A Handbook of Practical Orthopædics. By H. A. REEVES, M.D. *Practical Series. See Page 19.* Cl., $2.25

RICHARDSON. Long Life, and How to Reach It. By J. G. RICHARDSON, Prof. of Hygiene, University of Penna. Cloth, .50

RICHARDSON'S Mechanical Dentistry. A Practical Treatise on Mechanical Dentistry. By JOSEPH RICHARDSON, D.D.S. Fifth Edition. Thoroughly Revised. With 569 Illustrations. 8vo. Cloth, $4.50; Leather, $5.50

RIGBY'S Obstetric Memoranda. 4th Ed. By MEADOWS. 32mo. Cloth, .50

RICHTER'S Inorganic Chemistry. A Text-book for Students. By Prof. VICTOR VON RICHTER, University of Breslau. Third American, from Fifth German Edition. Authorized Translation by EDGAR F. SMITH, M.A., PH.D., Prof. of Chemistry, University of Pennsylvania, Member of the Chemical Societies of Berlin and Paris. 89 Illustrations and a Colored Plate. 12mo. Cloth, $2.00

Organic Chemistry. A Text-book for Students. Translated from the Fourth German Ed., by Prof. Edgar F. Smith. Illus. Cloth, $3.00; Leather, $3.50

ROBERTS. Bow-Legs. Clinical Lectures on Orthopædic Surgery. By A. SYDNEY ROBERTS, M.D., Instructor in Orthopædic Surg. in the Univ. of Penn'a, Surg. to the Univ. Hospital. Illustrated. 12mo. Cloth, .50; Boards, .50

ROBERTS. Practice of Medicine. The Theory and Practice of Medicine. By FREDERICK ROBERTS, M.D., Professor of Therapeutics at University College, London. Seventh Edition, with Illustrations. 8vo. Cloth, $5.50; Leather, $6.50

Materia Medica and Pharmacy. A Compend for Students. Cloth, $2.00

ROBERTS (John B.). Crooked and Deformed Noses. 8vo. Cloth, .75; Paper, .50

ROBINSON. Latin Grammar of Pharmacy and Medicine. By H. D. ROBINSON, PH.D., Professor of Latin Language and Literature, University of Kansas, Lawrence. With an Introduction by L. E. SAYRE, PH.G., Professor of Pharmacy in, and Dean of the Dept. of Pharmacy, University of Kansas. 12mo. *Nearly Ready.*

SANDERSON'S Physiological Laboratory. A Handbook of the Physiological Laboratory. Being Practical Exercises for Students in Physiology and Histology. By J. BURDON SANDERSON, M.D., E. KLEIN, M.D., MICHAEL FOSTER, M.D., F.R.S., and T. LAUDER BRUNTON, M.D. With over 350 Illustrations and Appropriate Letter-press Explanations and References. One Volume. Cloth, $5.00

SANSOM'S Diseases of the Heart. Valvular Disease of the Heart. By ARTHUR ERNEST SANSOM, M.D. Illustrated. 12mo. Cloth, $1.25

On Chloroform. Its Action and Administration. Paper, .75; Cloth, $1.25

SCANZONI. Sexual Organs of Women. A Practical Treatise on the Diseases of the Sexual Organs of Women. By F. W. VON SCANZONI, Prof. of Midwifery and Diseases of Females, University of Würzburg, etc. Edited by A. K. GARDNER, A.M., M.D. 60 Illustrations. Fourth Edition. Octavo. Cloth, $4.00

SCHNÉE. Diabetes, its Cause and Permanent Cure. From the standpoint of experience and Scientific Investigation. By EMIL SCHNÉE, Consulting Physician at Carlsbad. Translated from the German by R. L. TAFEL, A.M., PH.D. Revised and Enlarged by the author. Octavo. Cloth, $2.00

SEWELL. Dental Surgery, including Special Anatomy and Surgery. By HENRY SEWELL, M.R.C.S., L.D.S., President Odontological Society of Great Britain. 3d Edition, greatly enlarged, with about 200 Illustrations. *Nearly Ready.*

SMITH'S Wasting Diseases of Infants and Children. By EUSTACE SMITH, M.D., F.R.C.P., Physician to the East London Children's Hospital. Fifth London Edition, Enlarged. 8vo. Cloth, $3.00

Clinical Studies of Diseases in Children. Second Edition. Cloth, $2.50

SMITH. Abdominal Surgery. Being a Systematic Description of all the Principal Operations. By J. GREIG SMITH, M.A., F.R.S.E., Surg. to British Royal Infirmary. Illustrated. Third Edition. Cloth, $7.00

SMITH. Electro-Chemical Analysis. By EDGAR F. SMITH, Prof. of Analytical Chemistry, University of Penna. 26 Illustrations. 12mo. Cloth, $

SMITH (TYLER). Lectures on Obstetrics. Delivered at St. Mary's Hospital. With an Introductory Lecture on the History and Art of Midwifery, and Copious Annotations. By A. K. GARDNER, A.M., M.D. 233 Illus. 3d Ed. 8vo. Cloth, $4.00

SMYTHE (G. C.). Medical Heresies. Historically Considered. 12mo. Cloth, $1.25

STAMMER. Chemical Problems, with Explanations and Answers. By KARL STAMMER. Translated from the 2d German Edition, by Prof. W. S. HOSKINSON, A.M., Wittenberg College, Springfield, Ohio. 12mo. Cloth. .75

STARR and WALKER. Physiological Action of Medicines. Prepared for the use of Students of the Medical Department, University of Penna. By LOUIS STARR, M.D., J. B. WALKER, M.D. and W. M. POWELL, M.D. Third Edition. Enlarged. 32mo. Cloth, .75

STARR. The Digestive Organs in Childhood. The Diseases of the Digestive Organs in Infancy and Childhood. With Chapters on the Investigation of Disease and the Management of Children. By LOUIS STARR, M.D., Clinical Prof. of Diseases of Children in the Hospital of the University of Penn'a; Physician to the Children's Hospital, Phila. 8vo. Cut or uncut edges. Cloth, $2.50

The Hygiene of the Nursery, including the General Regimen and Feeding of Infants and Children, and the Domestic Management of the Ordinary Emergencies of Early Life. Second Edition. Enlarged. 24 Illustrations. 12mo. 280 pages, Cloth, $1.00

See also Goodhart and Starr. *Page 10.*

STEWART'S Compend of Pharmacy. Based upon "Remington's Text-Book of Pharmacy." By F. E. STEWART, M.D., PH.G., Quiz Master in Chem. and Theoretical Pharmacy, Phila. College of Pharmacy; Demonstrator and Lect. in Pharmacology, Medico-Chirurgical College, and in Woman's Medical College. 2d. Ed. *? Quiz-Compend ? Series.* Cloth, $1.00; Interleaved for the addition of notes, $1.25

STIRLING. Outlines of Practical Physiology. Including Chemical and Experimental Physiology, with Special Reference to Practical Medicine. By W. STIRLING, M.D., Sc.D., Prof. of Phys., Owens College, Victoria University, Manchester. Examiner in Honors School of Science, Oxford, England. 142 Illustrations. 309 pages. Cloth, $2.25

Outlines of Practical Histology. A Manual for Students. With 344 Illustrations. 12mo. Cloth, $4.00

STOCKEN'S Dental Materia Medica. Dental Materia Medica and Therapeutics, with Pharmacopœia. By JAMES STOCKEN, D.D.S. Third Edition. Cloth, $2.50

STRAHAN. Extra-Uterine Pregnancy. The Diagnosis and Treatment of Extra-Uterine Pregnancy. Being the Jenks Prize Essay of the College of Physicians of Philadelphia. By JOHN STRAHAN, M.D. (Univ. of Ireland), late Res. Surgeon Belfast Union Infirmary and Fever Hospital. Octavo. Cloth, $1.50

SUTTON'S Volumetric Analysis. A Systematic Handbook for the Quantitative Estimation of Chemical Substances by Measure, Applied to Liquids, Solids and Gases. By FRANCIS SUTTON, F.C.S. Fifth Edition, Revised and Enlarged, with Illustrations. 8vo. Cloth, $4.50

SUTTON. Ligaments. Their Nature and Morphology. By JOHN BLAND SUTTON, F.R.C.S., Lecturer on Pathology, Royal College of Surgeons; Assistant Surgeon and Demonstrator of Anatomy, Middlesex Hospital, London. Illustrated. 12mo. Cloth, 1.25

SWAIN. Surgical Emergencies, together with the Emergencies Attendant on Parturition and the Treatment of Poisoning. A Manual for the Use of General Practitioners. By W. F. SWAIN, F.R.C.S. Fourth Edition. Illustrated. 1.50

SWAYNE'S Obstetric Aphorisms, for the Use of Students commencing Midwifery Practice. By JOSEPH G. SWAYNE, M.D. Ninth Edition. Illus. Cloth, $1.25

SYMONDS. Manual of Chemistry, for the special use of Medical Students. By BRANDRETH SYMONDS, A.M., M.D., Asst. Physician Roosevelt Hospital, Out-Patient Department; Attending Physician Northwestern Dispensary, New York. 12mo. Cloth, $2.00; Interleaved for Notes, $2.40

TAFT'S Operative Dentistry. A Practical Treatise on Operative Dentistry. By JONATHAN TAFT, D.D.S. Fourth Revised and Enlarged Edition. Over 100 Illustrations. 8vo. Cloth, $4.25; Leather, $5.00

Index of Dental Periodical Literature. 8vo. Cloth, $2.00

TALBOT. Irregularities of the Teeth, and Their Treatment. By EUGENE S. TALBOT, M.D., Professor of Dental Surgery Woman's Medical College, and Lecturer on Dental Pathology in Rush Medical College, Chicago. Second Edition, Revised and Enlarged by about 100 pages. Octavo. 234 Illustrations. (169 of which are original). 261 pages. Cloth, $3.00

TANNER'S Index of Diseases and their Treatment. By THOS. HAWKES TANNER, M.D., F.R.C.P. Second Edition, Revised and Enlarged. By W. H. BROADBENT, M.D. With Additions. Appendix of Formulæ, etc. 8vo. Cloth, $3.00

Memoranda of Poisons and their Antidotes and Tests. Sixth American, from the Last London Edition. Revised by HENRY LEFFMANN, M.D., Professor of Chemistry in Pennsylvania College of Dental Surgery and in the Philadelphia Polyclinic. 12mo. Cloth, .75

TAYLOR. Practice of Medicine. A Manual. By FREDERICK TAYLOR, M.D., Physician to, and Lecturer on Medicine at Guy's Hospital, London; Physician to Evelina Hospital for Sick Children, and Examiner in Materia Medica and Pharmaceutical Chemistry, University of London. Cloth, $4.00

TEMPERATURE Charts for Recording Temperature, Respiration, Pulse, Day of Disease, Date, Age, Sex, Occupation, Name, etc. Put up in pads; each .50

THOMPSON. Lithotomy and Lithotrity. Practical Lithotomy and Lithotrity; or an Inquiry into the best Modes of Removing Stone from the Bladder. By Sir HENRY THOMPSON, F.R.C.S., Emeritus Professor of Clinical Surgery in University College. Third Edition. With 87 Engravings. 8vo. Cloth, $3.50

Urinary Organs. Diseases of the Urinary Organs. Containing 32 Lectures. Eighth London Ed. Octavo. 470 pages. Cloth, $3.50

On the Prostate. Diseases of the Prostate. Their Pathology and Treatment. Sixth London Edition. 8vo. Illustrated. Cloth, $2.00

Calculous Diseases. The Preventive Treatment of Calculous Disease, and the Use of Solvent Remedies. Third Edition. 16mo. Cloth, $1.00

Surgery of the Urinary Organs. Some Important Points connected with the Surgery of the Urinary Organs. Illus. Paper, .75; Cloth, $1.25

THORBURN. Surgery of the Spinal Cord. A Contribution to the study of. By WILLIAM THORBURN, B.S., B.Sc., M.D., Lond., F.R.C.S., Eng. With Illustrations. Octavo. Cloth, $4.50

THORNTON. The Surgery of the Kidney. By JOHN KNOWSLEY THORNTON, M.B. Edin. With 19 Illustrations. Cloth, $1.75

TIDY. Modern Chemistry, Inorganic and Organic. A Handbook for the Use of Students. By CHAS. MEYMOTT TIDY, F.R.C., Prof. of Chemistry and Medical Jurisprudence and Public Health at London Hospital; Medical Officer of Health and Public Analyst of the City of London. 8vo. 2d Edition. Cloth, $5.50

TILT'S Change of Life in Women, in Health and Disease. A Practical Treatise on the Diseases incidental to Women at the Decline of Life. By EDWARD JOHN TILT, M.D. Fourth London Edition. 8vo. Paper cover, .75; Cloth, $1.25

TOMES' Dental Anatomy. A Manual of Dental Anatomy, Human and Comparative. By C. S. TOMES, D.D.S. 212 Illustrations. 3d Ed. 12mo. Cloth, $4.00

Dental Surgery. A System of Dental Surgery. By JOHN TOMES, F.R.S. Third Edition, Revised and Enlarged. By C. S. TOMES, D.D.S. With 292 Illustrations. 12mo. 772 pages. Cloth, $5.00

TRANSACTIONS of the College of Physicians of Philadelphia. Third Series. Vols. I, II, III, IV, V, Cloth, each, $2.50. VI, VII, Cloth, each, $3.50. Vol. VIII, 1886, Cloth, $3.75. Vol. IX, Cloth, $2.50.

TRANSACTIONS American Surgical Association. Illustrated. Royal 8vo. Price of Vol. I, II, III, IV, V, each, Cloth, $3.00. Vol. VI, Cloth, $4.50. Vol. VII, Cloth, $3.00.

TRANSACTIONS of the Association of American Physicians. Vols. I and II, Cloth, $2.50 each; Vol. III, Cloth, $3.50. Vol. IV, Cloth, $3.00.

TREVES. German-English Medical Dictionary. By FREDERICK TREVES, F.R.C.S., assisted by DR. HUGO LANG, B.A., (Munich). 12mo. ½ Russian, $3.75

TRIMBLE. Practical and Analytical Chemistry. Being a complete course in Chemical Analysis. By HENRY TRIMBLE, PH.G., Professor of Analytical Chemistry in the Philadelphia College of Pharmacy. Second Edition. Enlarged. Illustrated. 8vo. Cloth, $1.50

TURNBULL'S Artificial Anæsthesia. The Advantages and Accidents of Artificial Anæsthesia; Its Employment in the Treatment of Disease; Modes of Administration; Considering their Relative Risks; Tests of Purity; Treatment of Asphyxia; Spasms of the Glottis; Syncope, etc. By LAURENCE TURNBULL, M.D., PH. G., Aural Surgeon to Jefferson College Hospital, etc. Third Edition, Revised and Enlarged. 40 Illustrations. 12mo. Cloth, $3.00

TUSON. Veterinary Pharmacopœia. Including the Outlines of Materia Medica and Therapeutics. For the Use of Students and Practitioners of Veterinary Medicine. By RICHARD V. TUSON, F.C.S. Third Edition. 12mo. Cloth, $2.50

TYSON. Bright's Disease and Diabetes. With Especial Reference to Pathology and Therapeutics. By JAMES TYSON, M.D., Professor of Pathology and Morbid Anatomy in the University of Pennsylvania. Including a Section on Retinitis in Bright's Disease. By WM. F. NORRIS, M.D., Clin. Prof. of Ophthalmology, in Univ. of Penna. With Colored Plates and many Wood Engravings. 8vo. Cloth, $3.50

Guide to the Examination of Urine. Sixth Edition. For the Use of Physicians and Students. With Colored Plates and Numerous Illustrations Engraved on Wood. Sixth Edition. Revised. 12mo. 250 pages. Cloth, $1.50

Cell Doctrine. Its History and Present State. With a Copious Bibliography of the subject. Illustrated. Second Edition. 8vo. Cloth, $2.00

VALENTIN'S Qualitative Analysis. A Course of Qualitative Chemical Analysis. By WM. G. VALENTIN, F.C.S. Seventh Edition. Illustrated. Octavo. Cloth, $3.00

VAN HARLINGEN on Skin Diseases. A Practical Manual of Diagnosis and Treatment. By ARTHUR VAN HARLINGEN, M.D., Professor of Diseases of the Skin in the Philadelphia Polyclinic; Clinical Lecturer on Dermatology at Jefferson Medical College. Second Edition. Revised and Enlarged. With Formulæ. Eight Colored and other full page plates, and New Illustrations. Cloth, 2.50

VAN NÜYS on The Urine. Chemical Analysis of Healthy and Diseased Urine, Qualitative and Quantitative. By T. C. VAN NÜYS, Professor of Chemistry Indiana University. 39 Illustrations. Octavo. Cloth, $2.00

VIRCHOW'S Post-mortem Examinations. A Description and Explanation of the Method of Performing them in the Dead House of the Berlin Charité Hospital, with especial reference to Medico-legal Practice. By Prof. VIRCHOW. Translated by Dr. T. P. SMITH. Third Edition, with Additions. Cloth, $1.00

Cellular Pathology, as based upon Physiological and Pathological Histology. 20 Lectures delivered at the Pathological Institute of Berlin. Translated from the 2d Ed. by F. CHANCE, M.D. 134 Illus. 8th Am. Ed. Cloth, $4.00

WALSHAM. Manual of Practical Surgery. For Students and Physicians. By WM. J. WALSHAM, M.D., F.R.C.S., Asst. Surg. to, and Dem. of Practical Surg. in, St. Bartholomew's Hospital, Surg. to Metropolitan Free Hospital, London. With 236 Engravings. *New Series of Manuals.* Cloth, $3.00; Leather, $3.50

WARING. Practical Therapeutics. A Manual for Physicians and Students. By Edward J. Waring, M.D. Fourth Edition. Revised, Rewritten and Rearranged by DUDLEY W. BUXTON, M.D., Assistant to the Professor of Medicine, University College, London. Crown Octavo. Cloth, $3.00; Leather, $3.50

WARNER. Case Taking. A Manual of Clinical Medicine and Case Taking. By FRANCIS WARNER, M.D. Second Edition. Cloth, $1.75

WARREN. Compend Dental Pathology and Dental Medicine. Containing all the most noteworthy points of interest to the Dental student. By GEO. W. WARREN, D.D.S., Clinical Chief, Penn'a College of Dental Surgery, Phila. Illus. *Being No. 13 ? Quiz-Compend ? Series.* 12mo. Cloth, $1.00
Interleaved for the addition of notes, 1.25

WATSON on Amputations of the Extremities and Their Complications. By B. A. WATSON, A.M., M.D., Surgeon to the Jersey City Charity Hospital and to Christ's Hospital, Jersey City, N. J.; Member of the American Surgical Association. 250 Wood Engravings and two Full-page Colored Plates. Cloth, $5.50

Concussions. An Experimental Study of Lesions arising from Severe Concussions. 8vo. Paper cover, $1.00

WATTS' Inorganic Chemistry. A Manual of Chemistry, Physical and Inorganic. (Being the 13th Edition of FOWNE'S PHYSICAL AND INORGANIC CHEMISTRY.) By HENRY WATTS, B.A., F.R.S., Editor of the Journal of the Chemical Society; Author of "A Dictionary of Chemistry," etc. With Colored Plate of Spectra and other Illustrations. 12mo. 595 pages. Cloth, $2.25

Organic Chemistry. Second Edition. By WM. A. TILDEN, D.Sc., F.R.S. (Being the 13th Edition of FOWNE'S ORGANIC CHEMISTRY.) Illustrated. 12mo. Cloth, $2.25

WELCH'S Enteric Fever. Its Prevalence and Modifications; Ætiology, Pathology and Treatment. By FRANCIS H. WELCH, F.R.C.S. 8vo. Cloth, $2.00

WHITE. The Mouth and Teeth. By J. W. WHITE, M.D., D.D.S. Editor of the Dental Cosmos. Illustrated. Cloth, .50

WILLIAMS. Pulmonary Consumption. Its Etiology, Pathology and Treatment, with an Analysis of 1000 Cases to Exemplify its Duration and Modes of Arrest. By C. J. B. WILLIAMS, M.D. Second Edition. Enlarged and Rewritten. By C. THEODORE WILLIAMS, M.D. With 4 Colored Plates and other Illustrations. Octavo. Cloth, 5.00

WILSON'S Text-Book of Domestic Hygiene and Sanitary Information. A Guide to Personal and Domestic Hygiene. By GEORGE WILSON, M.D., Medical Officer of Health. Edited by JOS. G. RICHARDSON, M.D., Professor of Hygiene at the University of Pennsylvania. Cloth, $1.00

WILSON. Handbook of Hygiene and Sanitary Science. With Illustrations. Sixth Edition, Revised and Enlarged. 8vo. Cloth, $2.75

WILSON. The Summer and Its Diseases. By JAMES C. WILSON, M.D. Cloth, .50

WINCKEL. Diseases of Women. Second Edition. Including the Diseases of the Bladder and Urethra. By Dr. F. WINCKEL, Professor of Gynæcology, and Director of the Royal University Clinic for Women, in Munich. Translated by special authority of Author and Publisher, by Dr. J. H. WILLIAMSON, Resident Physician of Allegheny General Hospital, Allegheny, Pa., under the supervision of, and with an Introduction by, THEOPHILUS PARVIN, M.D., Professor of Obstetrics and Diseases of Women and Children in Jefferson Medical College, Philadelphia. With 150 Engravings on Wood, most of which are original 2d Edition, Revised and Enlarged. Cloth, $3.00; Leather, $3.50

Text-Book of Obstetrics; Including the Pathology and Therapeutics of the Puerperal State. Authorized Translation by J. CLIFTON EDGAR, A.M., M.D., Adjunct Professor to the Chair of Obstetrics, Medical Department, University, City of New York. With nearly 200 Handsome Illus., the majority of which are original with this work. Octavo. Cloth, $6.00; Leather, $7.00

WOAKES. Post-Nasal Catarrh and Diseases of the Nose, causing Deafness. By EDWARD WOAKES, M.D., Senior Aural Surgeon to the London Hospital for Diseases of the Throat and Chest. 26 Illustrations. Cloth, $1.50

Nasal Polypus, with Neuralgia, Hay Fever and Asthma in Relation to Ethmoiditis. 12mo. Cloth, $1.25

On Deafness, Giddiness and Noises in the Head, or the Naso-Pharyngeal aspect of Ear Disease. Third Edition. Illustrated. *In Press.*

WOLFF. Manual of Applied Medical Chemistry for Students and Practitioners of Medicine. By LAWRENCE WOLFF, M.D., Demonstrator of Chemistry in Jefferson Medical College, Philadelphia. Cloth, $1.00

WOOD. Brain Work and Overwork. By Prof. H. C. WOOD, Clinical Professor of Nervous Diseases, University of Pennsylvania. 12mo. Cloth, .50

WOODY. Essentials of Chemistry and Urinalysis. By SAM E. WOODY, A.M., M.D., Professor of Chemistry and Public Hygiene, and Clinical Lecturer on Diseases of Children, in the Kentucky School of Medicine. Third Edition. Illustrated. 12mo. Cloth,

WOODMAN and TIDY. Medical Jurisprudence. Forensic Medicine and Toxicology. By W. BATHURST WOODMAN, M.D., Physician to the London Hospital, and CHARLES MEYMOTT TIDY, F.C.S., Professor of Chemistry and Medical Jurisprudence at the London Hospital. With Chromo-lithographic Plates, and 116 other Illustrations. Octavo. Leather, $8.50

WYNTER and WETHERED. Clinical and Practical Pathology. A Manual of Clinical and Practical Pathology. By W. ESSEX WYNTER, M.D., Medical Registrar and late Demonstrator of Anatomy and Chemistry at the Middlesex Hospital, and FRANK J. WETHERED, M.D., Asst. Physician to the City of London Hospital for Diseases of the Chest. With 4 Colored Plates and 67 other Illustrations. 8vo. Cloth, $4.00

WYTHE on the Microscope. A Manual of Microscopy and Compendium of the Microscopic Sciences, Micro-mineralogy, Biology, Histology and Practical Medicine, with Index and Glossary and the genera of microscopic plants. By JOSEPH H. WYTHE, A.M., M.D. Fourth Edition. 252 Illus. Cloth, $3.00

Dose and Symptom Book. The Physician's Pocket Dose and Symptom Book. Containing the Doses and Uses of all the Principal Articles of the Materia Medica, and Officinal Preparations. 17th Edition, Revised and Rewritten. Cloth, $1.00; Leather, with Tucks and Pocket, $1.25

YEO'S Manual of Physiology. Fourth Edition. A Text-book for Students of Medicine. By GERALD F. YEO., M.D. F.R.C.S., Professor of Physiology in King's College, London. Fourth Edition; revised and enlarged by the author. With New Illustrations. 321 carefully printed Wood Engravings. A Glossary and Complete Index. Crown Octavo. *Being No. 4, New Series of Manuals.* Cloth, $3.00; Leather, $3.50

geon to Metropolitan Free Hospital, London, etc. 230 Illust. 650 pp.
Cloth, $3.0

From the Polyclinic.

"While evidently intended to be a text-book for students, and therefore small in size and compactly less full enough for the use of those practitioners who desire a short account of the various surgical pri involved in the treatment of the ordinary run of surgical cases. The author seems to be a conservative with advanced ideas."

PARVIN'S–WINCKEL'S DISEASES OF WOMEN. Second Edition. A T
eases of Women. Including the Diseases of the Bladder and Urethra. By DR. F. W
of Gynæcology and Director of the Royal University Clinic for Women, in Munich. E
by THEOPHILUS PARVIN, M.D., Professor of Obstetrics and Diseases of Women and
son Medical College. Illustrated by 150 fine Engravings on Wood, most of which
Cloth, $3.0

GALABIN'S MIDWIFERY. A Manual of Widwifery. By ALFRED LEWIS GA
Obstetric Physician and Lecturer on Midwifery and the Diseases of Women at Guy's
Examiner in Midwifery to the Conjoint Examining Board of England. 227 Illustra
Cloth, $3.0

From the Archives of Gynæcology, New York.

"The illustrations are mostly NEW and WELL EXECUTED, and we heartily commend this book as far s
upon this subject."

YEO'S MANUAL OF PHYSIOLOGY. Fourth Edition. A New Text-book
GERALD F. YEO, M.D., F.R.C.S., Professor of Physiology in King's College, Lond
tions and a Glossary. 758 pages. Cloth, $3.0

RICHTER'S ORGANIC CHEMISTRY. By PROF. VICTOR VON RICHTER, Un
Authorized translation. First American, from the Fourth German Edition. By EDGA
PH.D., Translator of Richter's Inorganic Chemistry; Prof. of Chemistry in Wittenber
field, Ohio; formerly in the Laboratories of the University of Pennsylvania; Membe
Societies of Berlin and Paris, of the Academy of Natural Sciences of Philadelphia
710 pages. Cloth, $3.0

GOODHART AND STARR, DISEASES OF CHILDREN. Second Edition. E
M.D., Physician to the Evelina Hospital for Children; Assistant Physician to Guy's
Second American from third English Edition. Revised and Edited by LOUIS STA
Professor of Diseases of Children in the Hospital of the University of Pennsylvania, an
Children's Hospital, Phila. With many new Prescriptions and Directions for making
Milk, for the Artificial Digestion of Milk, etc. 760 pages. Cloth, $3.0

From The New York Medical Record.

"As it is said of some men, so it might be said of some books, that they are 'born to greatness.'
we believe, a mission, particularly in the hands of the young members of the profession. In these days o
literature, it is refreshing to meet with an author who knows both what to say and when he has said it."

WARING'S PRACTICAL THERAPEUTICS. Fourth Edition. A Manual o
peutics, considered with reference to Articles of the Materia Medica. Containing,
Diseases, with a list of Medicines applicable as Remedies, and a full Index of t
Preparations noticed in the work. By EDWARD JOHN WARING, M.D., F.R.C.P.,
Edition. Rewritten and Revised. Edited by DUDLEY W. BUXTON, M.D., Asst. to the
at University College Hospital; Member of the Royal College of Physicians of Lond
Cloth, $3.0

From The Kansas City Medical Record.

"As a work of reference it excels, on account of the several complete indexes added to this edition

JUST PUBLISHED. THIRD EDITION.

HUMAN PHYSIOLOGY.

BY LANDOIS AND STIRLING.

With 692 Illustrations.

THIRD AMERICAN, FROM THE SIXTH GERMAN EDITION.

A Text-Book of Human Physiology, including Histology and Microscopical Anatomy, **with special reference to the requirements of Practical Medicine.** By Dr. L. LANDOIS, Professor of Physiology and Director of the Physiological Institute, University of Greifswald. Translated from the Fifth German Edition, with additions by WM. STIRLING, M.D., Sc.D., Brackenbury, Professor of Physiology and Histology in Owen's College and Victoria University, Manchester; Examiner in the Honors' School of Science, University of Oxford, England. Third Edition, revised and enlarged. 692 Illustrations.

"A BRIDGE BETWEEN PHYSIOLOGY AND PRACTICAL MEDICINE."

One Volume. Royal Octavo. Cloth, $6.50; Leather, $7.50.

From the Prefaces to the English Edition.

The fact that Prof. Landois' book has passed through four large editions in the original since 1880, and that in barely six months' time a second edition of the English has been called for, shows that in some special way it has met a want. The characteristic which has thus commended the work will be found mainly to lie in its eminent practicability; and it is this consideration which has induced me to undertake the task of putting it into English. Landois' work, in fact, forms a *Bridge* between Physiology and the Practice of Medicine. It never loses sight of the fact that the student of to-day is the practicing physician of to-morrow. In the same way, the work offers to the busy physician in practice a ready means of refreshing his memory on the theoretical aspects of Medicine. He can pass backward from the examination of pathological phenomena to the normal processes, and, in the study of these, find new indications and new lights for the appreciation and treatment of the cases under consideration. With this object in view, all the methods of investigation which may, to advantage, be used by the practitioner, are carefully and fully described. Many additions, and about one hundred illustrations, have been introduced into this second English edition, and the whole work carefully revised.

PRESS NOTICES.

"**Most effectively aids the busy physician** to trace from morbid phenomena back the course of divergence from healthy physical operations, and to gather in this way new lights and novel indications for the COMPREHENSION AND TREATMENT of the maladies with which he is called upon to cope."—*American Journal of Medical Sciences.*

"I know of no book which is its equal in the applications to the needs of clinical medicine."—*Prof. Harrison Allen, late Professor of Physiology, University of Pennsylvania.*

"We have no hesitation in saying that THIS IS THE WORK to which the PRACTITIONER will turn whenever he desires light thrown upon the phenomena of a COMPLICATED OR IMPORTANT CASE."—*Edinburgh Medical Journal.*

"So great are the advantages offered by Prof. LANDOIS' TEXT-BOOK, from the EXHAUSTIVE and EMINENTLY PRACTICAL manner in which the subject is treated, that it has passed through FOUR large editions in the same number of years. . . . Dr. STIRLING'S annotations have materially added to the value of the work. Admirably adapted for the PRACTITIONER. . . . With this Text-book at command, NO STUDENT COULD FAIL IN HIS EXAMINATION."—*The Lancet.*

"One of the MOST PRACTICAL WORKS on Physiology ever written, forming a 'bridge' between Physiology and Practical Medicine. . . . Its chief merits are its completeness and conciseness. . . . The additions by the Editor are able and judicious. . . . EXCELLENTLY CLEAR, ATTRACTIVE and SUCCINCT."—*British Medical Journal.*

"The great subjects dealt with are treated in an admirably clear, terse, and happily illustrated manner."—*Practitioner.*

"Unquestionably the most admirable exposition of the relations of Human Physiology to Practical Medicine ever laid before English readers"—*Students' Journal.*

"As a work of reference, LANDOIS and STIRLING'S Treatise OUGHT TO TAKE THE FOREMOST PLACE among the text-books in the English language. The wood-cuts are noticeable for their number and beauty."—*Glasgow Medical Journal.*

"**Landois' Physiology is, without question, the best text-book on the subject that has ever been written.**"—*New York Medical Record.*

"The chapter on the Brain and Spinal Cord will be a most valuable one for the general reader, the translator's notes adding not a little to its importance. The sections on Sight and Hearing are exhaustive. . . . The Chemistry of the Urine is thoroughly considered. . . . In its present form, the value of the original has been greatly increased. . . . The text is smooth, accurate, and unusually free from Germanisms; in fact, it is good English."—*New York Medical Journal.*

"It is not for the physiological student alone that Prof. Landois' book possesses great value, for IT HAS BEEN ADDRESSED TO THE PRACTITIONER OF MEDICINE as well, who will find here a direct application of physiological to pathological processes." *Medical Bulletin.*

P. BLAKISTON, SON & CO., Publishers, 1012 Walnut St., Philadelphia.

Glasgow, etc.

WITH COLORED PLATES AND NUMEROUS WOOD

Octavo. 650 Pages. Cloth, $4.50; Leather, $5.5

A treatise on Diseases of the Skin, **with reference to Diagnos** including an Analysis of 11,000 Consecutive Cases. Thoroughly il handsome wood engravings, and several colored and steel plates direction of the author, from special drawings by Dr. John Wilson.

PARTICULARLY STRONG IN TREA

☞ Special attention is given to the Differential Diagnosis of Ski treatment. There are over 150 prescriptions, which will serve as in dealing with obstinate and chronic cases.

There has been no complete treatise on Dermatology issued for se Anderson has, therefore, chosen an opportune time to publish his b

ILLUSTRATING ONE OF THE DISEASES OF THE HAIR (*See Fig. b, page*

For nearly twenty-five years Professor Anderson has been a gener hospital physician, with unusual opportunities for the study of this cl not a "specialist," as the term is understood. His experience value, and the physician will feel that, in consulting this work, he riences of a man situated as himself—with the same difficulties of dia and who has surmounted them successfully. We believe this to be the book that will be recognized at once; for it is undoubtedly a the present contains much practical information and many hints where. **Professor Anderson is particularly happy in illust tant relations subsisting between the general economy an his ideas of pathology and therapeutics,** including a considera and local manifestations of the common diseases of the economy upon the surface, will find many appreciative readers.

NEW AND REVISED EDITIONS.

? QUIZ-COMPENDS. ?

A SERIES OF PRACTICAL MANUALS FOR THE PHYSICIAN AND STUDENT.

Compiled in accordance with the latest teachings of prominent lecturers and the most popular Text-books.

Bound in Cloth, each $1.00. Interleaved, for the Addition of Notes, $1.25.

They form a most complete, practical and exhaustive set of manuals, containing information nowhere else collected in such a practical shape. Thoroughly up to the times in every respect, containing many new prescriptions and formulæ, and over 300 illustrations, many of which have been drawn and engraved specially for this series. The authors have had large experience as quiz-masters and attachés of colleges, with exceptional opportunities for noting the most recent advances and methods. The arrangement of the subjects, illustrations, types, etc., are all of the most approved form. They are constantly being revised, so as to include the latest and best teachings, and can be used by students of any college of medicine, dentistry and pharmacy.

No. 1. Human Anatomy. Fourth Edition, including Visceral Anatomy, formerly published separately. Over 100 Illustrations. By SAMUEL O. L. POTTER, M.A., M.D., late A. A. Surgeon, U. S. Army. Professor of Practice, Cooper Med. College, San Francisco.

Nos. 2 and 3. Practice of Medicine. Fourth Edition, Enlarged. By DANIEL E. HUGHES, M.D., late Demonstrator of Clinical Medicine in Jefferson Med. College, Phila.; Physician-in Chief, Philadelphia Hospital. In two parts.

PART I.—Continued, Eruptive and Periodical Fevers, Diseases of the Stomach, Intestines, Peritoneum, Biliary Passages, Liver, Kidneys, etc. (including Tests for Urine), General Diseases, etc.

PART II.—Diseases of the Respiratory System (including Physical Diagnosis), Circulatory System and Nervous System; Diseases of the Blood, etc.

*** These little books can be regarded as a full set of notes upon the Practice of Medicine, containing the Synonyms, Definitions, Causes, Symptoms, Prognosis, Diagnosis, Treatment, etc., of each disease, and including a number of prescriptions hitherto unpublished.

No. 4. Physiology, including Embryology. Fifth Edition. By ALBERT P. BRUBAKER, M.D., Prof. of Physiology, Penn'a College of Dental Surgery; Demonstrator of Physiology in Jefferson Med. College, Phila. Revised, Enlarged and Illustrated.

No. 5. Obstetrics. Illustrated. Fourth Edition. For Physicians and Students. By HENRY G. LANDIS, M.D., Prof. of Obstetrics and Diseases of Women, in Starling Medical College, Columbus. Revised Edition. New Illustrations.

No. 6. Materia Medica, Therapeutics and Prescription Writing. Fifth Revised Edition. With especial Reference to the Physiological Action of Drugs, and a complete article on Prescription Writing. Based on the Last Revision (Sixth) of the U. S. Pharmacopœia, and including many unofficinal remedies. By SAMUEL O. L. POTTER, M.A., M.D., late A. A. Surg. U. S. Army; Prof. of Practice, Cooper Med. College, San Francisco. 5th Edition. Improved and Enlarged.

No. 7. Gynæcology. A Compend of Diseases of Women. By HENRY MORRIS, M.D., Demonstrator of Obstetrics, Jefferson Medical College, Philadelphia. *In Press.*

No. 8. Diseases of the Eye and Refraction, including Treatment and Surgery. By L. WEBSTER FOX, M.D., Chief Clinical Assistant Opthalmological Dept., Jefferson Medical College, etc., and GEO. M. GOULD, A.B. 71 Illustrations, 39 Formulæ. 2d Edition.

No. 9. Surgery. Illustrated. Third Edition. Including Fractures, Wounds, Dislocations, Sprains, Amputations and other operations; Inflammation, Suppuration, Ulcers, Syphilis, Tumors, Shock, etc. Diseases of the Spine, Ear, Bladder, Testicles, Anus, and other Surgical Diseases. By ORVILLE HORWITZ, A.M., M.D., Demonstrator of Surgery, Jefferson Medical College. Third Edition. Revised 77 Formulæ and 91 Illustrations.

No. 10. Medical Chemistry. Third Edition. Inorganic and Organic, including Urine Analysis. For Medical and Dental Students. By HENRY LEFFMANN, M.D., Prof. of Chemistry in Penn'a College of Dental Surgery, Phila. Third Edition. Revised and Enlarged.

No. 11. Pharmacy. Based upon "Remington's Text-Book of Pharmacy." By F. E. STEWART, M.D., PH.G., Professor of Pharmacy, Powers College of Pharmacy; late Quiz-Master at Philadelphia College of Pharmacy. Second Edition. Revised.

No. 12. Veterinary Anatomy and Physiology. Illustrated. By WM. R. BALLOU, M.D., Prof. of Equine Anatomy, New York College of Veterinary Surgeons, etc. 29 Illustrations.

No. 13. Warren. Dental Pathology and Dental Medicine. Containing all the most noteworthy points of interest to the Dental student. By GEO. W. WARREN, D.D.S., Clinical Chief, Penn'a College of Dental Surgery, Philadelphia. Illus.

No. 14. Hatfield. Diseases of Children. By MARCUS P. HATFIELD, Professor of Diseases of Children, Chicago Medical College.

☞ *These books are constantly revised to keep up with the latest teachings and discoveries.*

"IT STANDS WITHOUT AN EQUAL AS THE MOST COMPLETE WORK ON PRACTICE IN THE ENGLISH LANGUAGE."—*New York Medical Journal.*

FAGGE'S PRACTICE OF MEDICINE.

Two Large Royal Octavo Volumes. Containing over 1900 Pages.

PRICE, HANDSOMELY BOUND IN CLOTH, $8.00.

The Principles and Practice of Medicine.

BY CHARLES HILTON FAGGE, M.D., F.R.C.P., F.R.M.C.S.,

Examiner in Medicine, University of London; Physician to, and Lecturer on Pathology in, Guy's Hospital; Senior Physician to Evelina Hospital for Sick Children, etc.

EDITED AND ARRANGED FOR THE PRESS

BY P. H. PYE-SMITH, M.D., F.R.C.P.,

Lecturer on Medicine in Guy's Hospital, London, etc.,

WITH A SECTION ON CUTANEOUS AFFECTIONS, BY THE EDITOR, A CHAPTER ON CARDIAC DISEASES, BY SAMUEL WILKES, M.D., F.R.S., AND TWO INDEXES, ONE OF AUTHORS AND ONE OF SUBJECTS, BY ROBERT EDMUND CARRINGTON.

Two Volumes. Royal Octavo. 1900 Pages.

Price in Cloth, $8.00. Full Leather, $10.00. Half Morocco, $12.00. Half Russia, $12.00.

It is based on laborious researches into the pathological and clinical records of Guy's Hospital, London, during the twenty years in which the author has held office there as Medical Registrar, as Pathologist, and as Physician. Familiar beyond most, if not all, of his contemporaries, with modern medical literature, a diligent reader of French and German periodicals, Dr. Fagge, with his remarkably retentive memory and methodical habits, was able to bring to his work of collection and criticism almost unequaled opportunities of extensive experience in the wards and dead house. The result is that which will probably be admitted to be a fuller, more original, and more elaborate text-book on medicine than has yet appeared. It is the first of importance emanating from Guy's Hospital, and the only two-volume work on the Practice of Medicine that has been issued for a number of years. Several subjects, such as Syphilis, that are usually omitted or but slightly spoken of in a general work of this character, receive full attention.

Dr. Walter Moxon, one of Dr. Fagge's contemporaries, and a great personal friend, writes of him, in a recent number of the *London Lancet*:—

"Fagge was, to my mind, the type of true medical greatness. I believe he was capable of any kind of excellence. His greatness as a physician became evident to observers of character very soon after his brilliant student career had placed him on the staff of Guy's Hospital; he did not merely group already known facts, but he found new facts. Former volumes of Guy's Hospital Reports contain ample and most valuable proof of his greatness as a physician. His power of observation was sustained by immense memory, and brought into action by vivid and constant suggestiveness of intelligence. He was a physician by grace of nature, and being gifted with a quickness of perception, a genius for clinical facts and a patience in observation, he was at once recognized as a successful practitioner and a leading figure in the hospital and among the profession.

PUBLISHED ANNUALLY. 1890.

NOW READY. 39TH YEAR.

THE PHYSICIAN'S VISITING LIST.

(LINDSAY & BLAKISTON'S.)

CONTENTS.

ALMANAC for 1890 and 1891.
TABLE OF SIGNS to be used in keeping accounts.
MARSHALL HALL'S READY METHOD IN ASPHYXIA.
POISONS AND ANTIDOTES, revised for 1890.
THE METRIC OR FRENCH DECIMAL SYSTEM OF WEIGHTS AND MEASURES.
DOSE TABLE, revised and rewritten for 1890, by HOBART AMORY HARE, M D, Demonstrator of Therapeutics, University of Pennsylvania.
LIST OF NEW REMEDIES for 1890, by same author.
AIDS TO DIAGNOSIS AND TREATMENT OF DISEASES OF THE EYE, DR. L. WEBSTER FOX, Clinical Asst. Eye Dept., Jefferson Medical College Hospital, and G. M. GOULD, M.D.
DIAGRAM SHOWING ERUPTION OF MILK TEETH, DR. LOUIS STARR, Prof. of Diseases of Children, University Hospital, Philadelphia.
POSOLOGICAL TABLE, MEADOWS.
DISINFECTANTS AND DISINFECTING.
EXAMINATION OF URINE, DR. J. DALAND, *based upon Tyson's* "Practical Examination of Urine." 6th Edition.
INCOMPATIBILITY, DR. S. O. L. POTTER.
A NEW COMPLETE TABLE FOR CALCULATING THE PERIOD OF UTERO-GESTATION.
SYLVESTER'S METHOD FOR ARTIFICIAL RESPIRATION. Illustrated.
DIAGRAM OF THE CHEST.
BLANK LEAVES, suitably ruled, for Visiting Lists, Monthly Memoranda, Addresses of Patients and others; Addresses of Nurses, their references, etc.; Accounts asked for; Memoranda of Wants; Obstetric and Vaccination Engagements; Record of Births and Deaths; Cash Account, etc.

REGULAR EDITION.

For 25 Patients weekly.					Tucks, pockets and Pencil,		$1.00
50	"	"			"	"	1.25
75	"	"			"	"	1.50
100	"	"			"	"	2.00
50	"	"	2 Vols.	Jan. to June / July to Dec.	"	"	2.50
100	"	"	2 Vols.	Jan. to June / July to Dec.	"	"	3.00

INTERLEAVED EDITION.

For 25 Patients weekly.					Interleaved, tucks and Pencil,		1.25
50	"	"			"	"	1.50
50	"	"	2 Vols.	Jan. to June / July to Dec.	"	"	3.00

PERPETUAL EDITION, without Dates.

No. 1. Containing space for over 1300 names, with blank page opposite each Visiting List page. Bound in Red Leather cover, with pocket and Pencil, $1.25

No. 2. Containing space for 2600 names, with blank page opposite each Visiting List page. Bound like No. 1, with Pocket and Pencil, ... 1.50

MONTHLY EDITION, without Dates.

No. 1. Bound without Flap or Pencil, ...75

No. 2. " with Tucks, Pencil, etc., ... 1.00

These lists, without dates, can be commenced at any time, and used until full, and are particularly useful to young physicians unable to estimate the number of patients they may have during the first years of Practice, and to physicians in localities where epidemics occur frequently. In the Monthly Edition the patient's name has to be entered but once each month.

"For completeness, compactness, and simplicity of arrangement it is excelled by none in the market."—*N. Y. Medical Record.*

"The book is convenient in form, not too bulky, and in every respect the very best Visiting List published."—*Canada Medical and Surgical Journal.*

"After all the trials made, there are none superior to it."—*Gaillard's Medical Journal.*

"The most popular Visiting List extant."—*Buffalo Medical and Surgical Journal.*

"We have used it for years, and do not hesitate to pronounce it equal, if not superior, to any."—*Southern Clinic.*

This is not a complicated system of keeping accounts, but a plain, systematic record which, with the least expenditure of time and trouble, keeps an accurate and concise list of daily visits, engagements, etc.

NEW TEXT-BOOKS.

Macalister's Human Anatomy. 816 Illustrations (400 of which are Original). Just Ready.

A NEW TEXT-BOOK for Students and Practitioners, Systematic and Topographical, including the Embryology, Histology and Morphology of Man. With special reference to **the requirements of Practical Surgery and Medicine.** By ALEX. MACALISTER, M.D., F.R.S., F.S.A., Professor of Anatomy in the University of Cambridge, England; Examiner in Zoölogy and Comparative Anatomy, University of London; formerly Professor of Anatomy and Surgery, University of Dublin. With 816 Illustrations, 400 of which are original. Octavo.

Cloth, $7.50; Leather, $8.50

*** Professor Macalister's reputation as an Anatomist and Zoölogist is such that nothing need be said of the scientific value of this book. Regarding the illustrations, printing and binding we may say, however, that the workmanship is of the best character in every respect. No expense has been spared to make a handsome volume, the 400 original illustrations adding greatly to its appearance as well as to its practical value as a working book for students and physicians.

Potter's Materia Medica, Pharmacy and Therapeutics. Second Edition. Revised and Enlarged.

A HANDBOOK OF MATERIA MEDICA, PHARMACY AND THERAPEUTICS—including the Physiological Action of Drugs, Special Therapeutics of Diseases, Official and Extemporaneous Pharmacy, etc. By SAM'L O. L. POTTER, M.A., M.D., Professor of the Practice of Medicine in Cooper Medical College, San Francisco; Late A. A. Surgeon, U. S. Army, Author of "Speech and its Defects," and the "Quiz-Compends" of Anatomy and Materia Medica, etc. Revised, Enlarged and Improved. Octavo. *With Thumb Index in each copy.*

Cloth, $4.00; Leather, $5.00

"The author has aimed to embrace in a single volume the essentials of practical materia medica and therapeutics, and has produced a book small enough for easy carriage and easy reference, large enough to contain a carefully digested, but full, clear and well-arranged mass of information. He has not adhered to any pharmacopœia, as is the case of certain recent manuals, thereby limiting his work, and in this day of new remedies causing constant disappointment, but has brought it up to date in the most satisfactory way. No new remedy of any acknowledged value is omitted from this list. Under each the section on physiological action and therapeutics has been written with care. . . . In the enumeration of drugs suited to different disorders a very successful effort at discrimination has been made, both in the stage of disease and in the cases peculiarly suited to the remedy. It is no mere list of diseases followed by a catalogue of drugs, but is a digest of modern therapeutics, and as such will prove of immense use to its possessor."—*The Therapeutic Gazette.*

Winckel's Obstetrics. Original Illustrations.

A TEXT-BOOK OF OBSTETRICS, INCLUDING THE PATHOLOGY AND THERAPEUTICS OF THE PUERPERAL STATE. By DR. F. WINCKEL, Professor of Gynæcology, and Director of the Royal University Clinic for Women, in Munich. Authorized Translation, by J. CLIFTON EDGAR, M.D., Adjunct Professor to the Chair of Obstetrics, Medical Dept., University, of the City of New York, with nearly 200 handsome illustrations, the majority of which are original with this work. Octavo.

Cloth, $6.00; Leather, $7.00



LANE MEDICAL LIBRARY

To avoid fine, this book should be returned on or before the date last stamped below.

Visual perceptive events of.

1st Photo chemical development of image on the retina

2d Stimulation of visual centre

3d Psychical activity in the centre of brain

Color sensation depends on,

1st Size of visual
yellow
blue

2d Degree of illu
violet
red

3d Background
Contrast-d
round

F34 Landois, L. i. e. C.C.A.I
L25s A text-book of human
1889 physiology. 54790
NAME DATE DUE